



Solutions that meet
your demands for:

speed
accuracy
productivity

Our measure is your success.

Excellent choices for
environmental applications






Table of Contents

The table of contents on the right has been linked to the individual sections in this compendium. Click on the text to jump to a specific section.

If you prefer to search for words or phrases used in any of the enclosed applications notes, click on the Search button below to open Acrobat's Search window.

Search

Solution Segments

Emerging Contaminants

PPCPs
PFOA/PFOS
PBDEs
Other

Water

Volatiles
Semi-volatiles
Pesticides and Residues
Inorganics
Other

Soil & Sediment

Volatiles
Semi-volatiles
Pesticides and Residues
Inorganics
Other

Air

Applications

Material Analysis

Applications

Productivity Tools

Applications


Index



Emerging Contaminants

PPCPs Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)



Determination of Pharmaceuticals in Water by SPE and LC/MS/MS in Both Positive and Negative Ion Modes

Application Note

Environmental

Author

Chin-Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Using solid phase extraction (SPE) and liquid chromatography/tandem mass spectrometry (LC/MS/MS), 19 pharmaceuticals in positive ion mode and 11 pharmaceuticals in negative ion mode were analyzed at low picogram level on column without any derivatization. Good linearity was observed for analytes from 1 pg to 1 ng on column.

Repeatability from six injections of analytes at 5 pg on column showed RSDs below 15%, for all target compounds except for fluoxetine at 23%.



Agilent Technologies

Introduction

Many articles in leading medical journals and newspapers reported sexual development and reproductive problems in animals and humans, for example, low sperm counts, genital deformities, male fish making eggs, and others. Scientists suggested that man-made chemicals (for example, pesticides and pharmaceuticals) are disrupting the endocrine system.

Compounds like antibiotics, over-the-counter medicines, and caffeine drain through the sewage system largely unaltered into rivers and streams, and even get into the drinking water supply in very small amounts. In order to monitor the trace pharmaceuticals in surface and ground water, an effective sample preparation and analysis method is required.

In 1999, the U.S. Geological Survey National Water Quality Laboratory (NWQL) developed and implemented an Oasis HLB, solid-phase extraction (SPE), and a high-performance liquid chromatography (HPLC)-mass spectrometry (MS) method to analyze pharmaceuticals.

Instrumentation

Positive Ion Mode

LC:	1200 LC	
Column:	ZORBAX Extend-C-18, RRHT, 2.1 mm × 100 mm, 1.8 µm	
Column temperature:	40 °C	
Mobile phases:	A: 0.1% formic acid in water, add NH ₄ OH buffer to pH 5.5 B: Acetonitrile (ACN)	
Flow rate:	0.3 mL/min	
Gradient:	Time	%B
	0	0
	15	100
	20	100
	21.5	0
Injection volume:	1.0 µL	
MS:	G6410A QQQ	
Ionization:	ESI-(+)	
Mass range:	125 to 800 amu	
Scan time:	300 ms	
Capillary:	3500 V	
Nebulizer P:	40 psi	
Drying gas:	9 L/min	
Gas temperature:	350 °C	
Skimmer:	35 V	

Using the Multiple Reaction Monitoring (MRM) technique, any interference and matrix signal from organic matters in the water can be minimized from the target compound signals for better confirmation and quantitation. In this application note, SPE and LC/MS/MS methods are described to analyze 19 pharmaceuticals in positive ion mode and 11 pharmaceuticals in negative ion mode.

Experimental

Sample Preparation Procedure

See Reference 1 for more information.

1. Filter water samples in the field or laboratory using 0.7-µm glass fiber filters.
2. Pump 1 L of the filtered water sample, at a flow rate of 10 mL/min, through an Oasis HLB (SPE) cartridge containing 0.5 g of sorbent.
3. Elute the HLB column with 6 mL of methanol followed by 4 mL of 0.1% trifluoroacetic acid (TFA) in methanol.

Negative Ion Mode

LC:	1200 LC	
Column:	ZORBAX Extend-C-18, RRHT, 2.1 mm × 100 mm, 1.8 µm	
Column temperature:	60 °C	
Mobile phases:	A: 0.04% Glacial acetic acid in water B: Acetonitrile (ACN)	
Flow rate:	0.3 mL/min	
Gradient:	Time	%B
	0	0
	1	40
	2	52
	3	70
	6	100
	13	100
	14	0
Injection volume:	1.0 µL	
MS:	G6410A QQQ	
Ionization:	ESI (-)	
Mass range:	120–800 amu	
Scan time:	300 ms	
Capillary:	3500 V	
Nebulizer P:	40 psi	
Drying gas:	9 L/min	
Gas temperature:	200 °C	
Skimmer:	35 V	

The MRM parameters for positive ion mode and negative ion mode are listed in Tables 1 and 2, respectively.

Table 1. Positive Ion Mode MRM Method Parameters

Name	RT	MW	Precursor	Quant ion	Collision V	Dwell	Segment
Metformin HCl	0.856	129	130.4	71.5	15	300	1
Acetaminophen	4.591	151	152.3	110.3	18	30	2
Salbutamol	4.717	239	240.4	148.4	15	30	2
Cimetidine	4.815	252	253.4	94.9	17	30	2
1,7,-Dimethylxanthine	4.89	180	181.3	123.9	20	30	2
Cotinine	5.24	176	177.3	118.3	29	30	2
Codeine	5.321	299	300.4	164.9	30	30	2
Caffeine	5.493	194	195.3	137.9	22	30	2
Trimethoprim	5.935	290	291.4	122.8	25	30	2
Thiabendazole	7.194	201	202.3	131.3	35	100	3
Sulfamethoxazole	7.309	253	254.3	156.0	15	100	3
Azithromycin	7.326	749	375.5	157.9	16	100	3
Diphenhydramine	8.446	255	256.5	167.1	5	100	4
Diltiazem HCl	8.693	414	415.4	177.6	18	100	4
Carbamazepine	8.912	236	237.4	194.0	20	100	4
Fluoxetine HCl	9.71	309	310.4	148.5	0	100	5
Dehydronifedipine	10.635	344	345.4	283.9	27	100	5
Warfarin	11.152	308	309.4	163.3	15	100	5
Miconazole nitrate salt	12.865	416	417.2	159.3	30	300	6

Table 2. Negative Ion Mode MRM Method Parameters

Name	RT	MW	Precursor	Quant ion	Frag. V	Collision V	Dwell	Segment
Hydrochlorothiazide	3.42	297	296	269	140	20	70	1
Aspirin	3.49	180	179	122	120	15	70	1
Enalaprilat	3.71	348	347	114	120	10	70	1
Furosemide	4.51	330	329	285	140	15	70	1
Ketoprofen	5.17	254	253	209	80	5	70	2
Clofibric acid	5.20	214	213	127	80	10	70	2
Napoxen	5.20	230	229	170	80	10	70	2
Diclofenac sodium salt	5.84	294	294	250	100	10	100	3
Ibuprofen	6.03	206	205	161	80	0	100	3
Ibuprofen-d3	6.03	209	208	164	80	0	100	3
Gemfibrozil	6.49	250	249	121	120	25	150	4
Triclocarban	6.66	314	313	160	140	15	150	4

Results and Discussion

The total ion chromatogram (TIC) in negative ion mode is shown in Figure 1. The analysis time in negative ion mode is less than 7 minutes for the 11 analytes. Their peak widths are about 0.1 minute, using a 1.8- μm particle size column. The narrower peak width gives a higher signal-to-noise (s/n) ratio compared to a 3.5- μm or larger particle size column.




Figure 1. Negative ion mode TIC of 11 pharmaceuticals.

A few compounds, for example, ketoprofen (Figure 2), are sensitive to heat from the drying gas. Higher drying gas temperature (350 °C) lowers the intensity of the precursor ions. Therefore, in the negative ion mode, the drying gas temperature was set to 200 °C.




Figure 2. Higher drying gas temperature lowers precursor intensity for certain compounds.

In Figure 3, it was interesting to see that the fragment ion actually had a higher m/z value than the precursor ion. For azithromycin, the doubly charged ion showed higher intensity than the singly charged ion and was chosen as the precursor. Therefore, depending on the precursor chosen, it is

sometimes necessary to set the upper mass of the product ion scan to be higher than the precursor ion.

Figure 4 shows the overlaid chromatograms of 19 pharmaceuticals, each at 5 pg on column, from the positive ion mode MRM analysis.




Figure 3. Doubly charged precursor results in a fragment at higher m/z .




Figure 4. Overlaid MRM chromatograms of the 19 pharmaceuticals in positive ion mode.

Figure 5 shows the overlaid chromatograms of 10 pharmaceuticals, each at 10 pg on column, from the negative ion mode MRM analysis. In both Figures 4 and 5, the analysis times were relatively short and s/n ratios were high.




Figure 5. Overlay of MRM results from the 10 pharmaceuticals in negative ion mode.

Table 3 shows the linearity results of all 19 pharmaceuticals (ESI+) over the range of 1, 5, 10, 20, 40, 100, 200, 400, and 1,000 pg on column. Two calibration models were used: a linear model and a quadratic model that both included origin with no weighting. Some of the compounds showed significant fitting improvement from the linear model to the quadratic model. This is the nature of these compounds.

Table 3. Linearity: 1, 5, 10, 20, 40, 100, 200, 400, and 1,000 pg on Column (ESI+), Origin Included, No Weighting

Compound	R ² (linear fit)	R ² (quadratic fit)
Metformin HCl	0.9975	0.9999
1,7,-Dimethylxanthine	0.9998	0.9998
Acetaminophen	0.9852	0.9999
Caffeine	0.9992	0.9997
Cimetidine	0.9968	0.9998
Codeine	0.9989	0.9997
Cotinine	0.9971	0.9998
Salbutamol	0.9850	0.9994
Trimethoprim	0.9980	0.9999
Azithromycin	0.9633	0.9998
Sulfamethoxazole	0.9998	0.9999
Thiabendazole	0.9997	0.9998
Carbamazepine	0.9926	0.9999
Diltiazem HCl	0.9997	0.9997
Diphenhydramine	0.9975	0.9998
Dehydronifedipine	0.9985	0.9993
Fluoxetine HCl	0.9984	0.9997
Warfarin	0.9989	0.9997
Miconazole nitrate salt	0.9989	0.9995

Table 4 shows the repeatability results from six injections of 5 pg of each analyte on column. In general, the RSDs are below 15%, except for fluoxetine, which was at 23%.

Table 4. Repeatability from Six Injections at 5 pg/μL (5 pg on column), ESI(+)

Compound	%RSD
Metformin HCl	12.4
1,7,-Dimethylxanthine	8.6
Acetaminophen	6.1
Caffeine	5.7
Cimetidine	4.1
Codeine	16.2
Cotinine	10.5
Salbutamol	3.7
Trimethoprim	3.6
Azithromycin	9.4
Sulfamethoxazole	10.7
Thiabendazole	5.3
Carbamazepine	2.8
Diltiazem HCl	4.7
Diphenhydramine	3.7
Dehydronifedipine	5.4
Fluoxetine HCl	23.4
Warfarin	4.4
Miconazole nitrate salt	2.9

Table 5 shows the linearity results of all 11 pharmaceuticals (ESI-) over the range of 10, 20, 40, 80, 400, and 800 pg on column. All the R² values were above 0.99, except triclocarban, which was about 0.97.

Table 5. Linearity: 10, 20, 40, 80, 400, and 800 pg on Column (ESI-), Origin Included, No Weighting

Compound	R ² (linear fit)
Hydrochlorothiazide	0.9999
Aspirin	0.9977
Enalaprilat	0.9981
Furosemide	0.9997
Ketoprofen	0.9988
Clofibric acid	0.9997
Naproxen	0.9994
Diclofenac Na salt	0.9993
Ibuprofen	0.9997
Ibuprofen-d3	0.9998
Gemfibrozil	0.9993
Triclocarban	0.9655

Once the method is established, one can screen and quantify target analytes in water. Figures 6, 7, and 8 are MRM analyses of actual water sample extracts in positive and negative ion modes.




Figure 6. Pharmaceuticals screening in positive ion mode.




Figure 7. Pharmaceuticals screening in negative ion mode.




Figure 8. Pharmaceuticals screening in negative ion mode.

Figure 6 shows several of the pharmaceuticals, for example, diphenhydramine and acetaminophen, that were common to several of the water samples. Some of the antibiotics were also found in the samples. Interestingly enough, in Figures 7 and 8, the most common pharmaceuticals in the water samples were related to high blood pressure and cholesterol medications.

Conclusions

Using SPE and LC/MS/MS, 19 pharmaceuticals in positive ion mode and 11 pharmaceuticals in negative ion mode were analyzed at low picogram level on column without any derivatization. Good linearity was observed for analytes from 1 pg to 1 ng on column.

Repeatability study from six injections of target analytes at 5 pg on column showed RSDs below 15%, except for fluoxetine at 23%.

This method was applied to water sample extracts, finding that several target pharmaceutical drugs were commonly found among the analyzed samples.

Reference

1. USGS SOP: Instrumental Analysis for Determination of Human Health Pharmaceuticals in Water by Chemically Modified Styrene-Divinylbenzene Resin-Based Solid-Phase Extraction and High-Performance Liquid Chromatography/Mass Spectrometry, by Steve Werner, 2006.

Acknowledgments

The author gratefully acknowledges the assistance of Stephen Werner and Ed Furlong of the National Water Quality Lab – United States Geological Survey (Lakewood, CO) for providing the sample preparation procedures and extracts used in this work.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Published in the USA
September 17, 2008
5989-5319EN



Agilent Technologies

The Use of Accurate Mass, Isotope Ratios, and MS/MS for the PPCPs in Water



Application

Environmental

Authors

Michael Zumwalt
Agilent Technologies, Inc.
9780 S Meridian Blvd.
Englewood, CO 80112-5910
USA

David Weil
Agilent Technologies, Inc.
10 N. Martingale Road, Suite 550
Schaumburg, IL 60173-2292
USA

Chin-Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

An Agilent 6510 Quadrupole Time-of-Flight Mass Spectrometer (QTOF) is used to analyze several surface water samples for the presence of pharmaceutical compounds. A simple gradient elution is carried out on a Rapid Resolution High Throughput Extend C18 column (particle size 1.8 μm). Of 54 potential compounds, as many as 11 are identified in one of the samples using an algorithm known as the Agilent Molecular Feature Extractor (MFE). To make comparisons among several samples, another algorithm, known as Mass Profiler, is applied to the data processed by the MFE. Since the MFE may generate thousands of potential compounds known as features, Mass Profiler makes statistical comparisons of the features between two different samples to determine what is unique and what is common. All of this work is done with the full-scan mass spectral data. When compounds of interest are determined, accurate mass full-scan MS/MS

can be invoked for structural elucidation. The results of full-scan MS/MS applied to caffeine are included as an example and are relevant because many medications include caffeine as an ingredient.

Introduction

During the three decades prior to the year 2000, the study of chemical pollution was confined primarily to pesticides. Following a seminal article by C. Daughton [1], this focus began to shift to the emerging environmental concern for pharmaceuticals and personal care products (PPCPs). Many of these pharmaceuticals, including estrogen, have been known as endocrine disruptors, or chemicals that disrupt the physiological function of hormones in organisms. In 2004 a report from the United States Geological Survey [2] was made as a result of discovering a high preponderance of intersex (male fish exhibiting female characteristics) in smallmouth bass of the Potomac River.

The USGS has found pesticides, flame retardants, and personal-care products containing known or suspected endocrine-disrupting compounds in the Potomac River. Many of these compounds continue to be known as emerging contaminants because they are still being discovered and don't exist on any currently regulated target lists. As such, it is important to use adequate techniques to help identify these compounds and possible metabolites.

Using accurate mass in full-scan (mass range) mass spectrometry (MS), compound empirical formulas can be determined for purposes of identification. Furthermore, the high degree of spectral resolution allows for selective identification among co-eluting compounds. Isotope ratios are an additional tool because they help identify com-



Agilent Technologies

pounds with high carbon numbers as well as those that contain elements like chlorine and sulfur. Although these tools do a lot to confirm chemical formula, it may still be left to the user to decide which of the possible structures of isobaric compounds apply.

To assist in the analytical need for structural elucidation, selective MS/MS by using the quadrupole time-of-flight mass spectrometer (QTOF) is implemented. Because the Agilent QTOF also has very accurate mass at the MS/MS level, it is easier to determine the structures of the product ions, which correspond as substructures of the precursor ion and thereby reduce the number of possible structures pertaining to the derived empirical formulas from several to one.

The list of pharmaceuticals to look for in the environment is ever-increasing and many of them are metabolites with unknown structures. Identifying these compounds requires the technology of the QTOF. Furthermore, the fast scanning capability is necessary for identifying 10s to 100s of these compounds in samples with relatively short run times. The Agilent QTOF is capable of acquiring full-scan MS data at the rate of 20 spectra/sec. The resulting large amount of data representing a possibly large number of compounds needs to be converted into useful information. The Agilent Molecular Feature Extractor (MFE), which is a standard part of the MassHunter Qualitative Analysis software, carries out the following steps:

- Persistent chemical background removed

- Co-eluting interferences resolved
- Isotopic clusters recognized and grouped
- 2D/3D data visualization
- Chemical identification (accurate mass, isotope matching)
- Database searching (NIST, ChemIDPlus)

In addition to applying the algorithm Mass Feature Extractor to pull out the features from the chromatographic data, which could be compounds, another algorithm, known as Mass Profiler, is applied to the list of features among different samples to determine differences and commonalities. Each sample is injected three times, or multiple samples from the same source could be used to determine what is statistically consistent in terms of the features derived for the sample by MFE. The result is called a group. Two groups representing two different sample sources can then be compared to see what features differ, are unique, or are common, and, if common, whether they differ in abundance.

A batch of water samples is filtered and extracted using solid-phase extraction, which resulted in an approximate 1,000-fold increase in concentration. Samples analyzed in this work are believed to contain compounds at the 10 to 100 ppb level, which corresponds to the 10 to 100 ppt range in the original water sample. The compounds that may be in these samples are included with their exact neutral masses in Table 1.

Table 1. List of Compounds with Corresponding Neutral Masses That May Be in a Given Sample

Compound	Neut. mass	Compound	Neut. mass	Compound	Neut. mass
Acetaminophen	151.06333	Diphenhydramine	255.16231	Paroxetine	329.14272
Albuterol	239.15214	Duloxetine	297.11873	Ranitidine	314.14126
Aspirin	180.04226	Enalaprilat	348.16852	Sertraline	305.07380
Bupropion	239.10769	Erythromycin	573.51210	Simvastatin	418.27192
Caffeine	194.08038	Fluoxetine	309.13405	Sulfachloropyridazine	284.01347
Carbamazepine	236.09496	Fluvoxamine	318.15551	Sulfadimethoxine	310.07358
Cimetidine	252.11572	Furosemide	330.00772	Sulfamethazine	278.08375
Clofibric acid	214.03967	Gemifrozil	250.15698	Sulfamethizole	270.02452
Citalopram	324.16379	HCTZ	296.96447	Sulfamethoxazole	253.05211
Codeine	299.15215	Ketoprofen	254.09429	Thiabendazole	201.03607
Cotinine	176.09496	Miconazole	413.98602	Triclocarban	313.97805
Dehydronifedipine	344.10084	Naproxen	230.09429	Triclosan	287.95116
Diclofenac	295.01668	Norfluoxetine	295.11840	Trimethoprim	274.14298
Diltiazem	414.16133	Norserttraline	293.05000	Venlafaxine	267.12593
		1,7-dimethylxanthine	180.06473	Warfarin	308.10486

Experimental

Sample Preparation

Prepared samples are provided by the United States Geological Service National Water Quality Laboratory (USGS/NWQL) in Denver, Colorado. The details of the procedure used are not included in this application, but are available upon request. Pharmaceuticals are typically extracted from surface water by using disposable polypropylene syringe cartridges that contain 0.5 g of polymeric sorbent. One liter of sample is pumped through the solid-phase extraction (SPE) cartridge. The analyte material is later eluted into 1 mL of methanol, resulting in a concentration increase of three orders of magnitude.

LC/MS Method Details

LC Conditions

Agilent 1100 Series binary pump, degasser, wellplate sampler, and thermostatted column compartment

Column	Agilent ZORBAX RRHT Extend C18 2.1 mm × 50 mm, 1.8 μm Agilent p/n: 727700-902		
Column temperature	40 °C		
Mobile phases	A = 0.1% formic acid in water B = 0.1% formic acid in acetonitrile		
Flow rate	0.3 mL/min		
Injection volume	5 μL		
Gradient			
	Time (min)	%B	
	0.0	0	
	10.0	67	Stop time: 15 min
	11.0	100	Post run: 10 min

MS Conditions

Mode	Positive electrospray ionization using the Agilent G3251A Dual ESI source
Nebulizer pressure	40 psig
Drying gas flow	9 L/min
Drying gas temp.	350 °C
V _{cap}	3500 V
Scan range	<i>m/z</i> 50–1000
Scan speed	1 scan/sec

MS/MS Conditions

Collision energy	30 V
Scan range	<i>m/z</i> 50–1000
Scan speed	1 scan/sec

Results and Discussion

Of the several samples analyzed, results for Samples 4 and 10 will be considered here. To get an idea of the task at hand, an overlay of the total ion and base peak chromatograms for the first injection of Sample 4 is shown in Figure 1. The base peak chromatogram is generated to help the analyst identify peaks in the chromatogram corresponding to real compounds. Figure 2 shows the spectrum at the apex of one such peak. Note the complexity of this spectrum and the difficulty involved in not only determining which spectral peaks are of value, as they may pertain to co-eluting compounds, but then having to apply this reasoning to several peaks in the chromatogram.

Applying the algorithm of the Molecular Feature Extractor program to this data file results in the display of the processed chromatogram and the corresponding contour plot shown in Figure 3. The upper left-hand chromatogram is the unprocessed TIC, same as shown in Figure 1. On the right is the processed chromatogram after applying the steps listed in the Introduction. Random background noise has been removed. Below each of these chromatograms are shown the corresponding contour plots, which are the presentations of spectral data points in an *m/z* versus chromatographic retention time plots. The contour plot at the lower left-hand corner of the display shows a very dense distribution of data points, most of which correspond to random noise.

The contour plot at the lower right-hand corner is the result of processing the data so that a significant amount of molecular features are derived for closer examination. In fact, using the following settings for filtering the data, some 5,431 features are derived for this sample in the first injection:

- Spectral S/N > 2
- Mass range: *m/z* 150 to 800
- [M + Na]⁺ and [M + NH₄]⁺ adducts considered
- Relative intensity in the spectrum > 0.1%
- Each feature must contain at least 2 ions




Figure 1. Overlay of total ion chromatogram (TIC) and base peak chromatogram (BPC) for Sample 4.

If we now investigate some of the features that have been found we can begin with the peak apex spectrum examined in Figure 2. The retention time is 6.445 minutes and MFE has derived features at 6.448 minutes as shown in Figure 4. The unprocessed spectrum at the top of the figure matches

that of Figure 2. However, removing random noise and using the filtering rules above a processed spectrum containing 12 features is derived and shown at the bottom. A subset of the list of features is shown at right.




Figure 2. Spectrum at apex of base peak with retention time of 6.445 minute.




Figure 3. Both unprocessed and processed data of Sample 4 using MFE.




Figure 4. Twelve features shown at derived retention time of 6.448 minutes.

If we want to filter the data to only show compounds corresponding to the list at the beginning of this article, we can place the neutral masses into an inclusion list of MFE as shown in Figure 5. We also assume that the compounds of interest do not elute until after 4 minutes and the mass range of interest is 150 to 600, which corresponds to the compounds of Table 1.

After applying the filtering of data with the compound list shown in Figure 5, eight features appear to be found in Sample 4 as shown in Figure 6. The corresponding chromatogram containing these eight features is also shown.

Before looking more closely at any one of these compounds, the data of Sample 4 is now going to be compared with data from another sample, Sample 10. The comparison will be carried out using an algorithm known as Mass Profiler. In

order to use Mass Profiler, at least three injections of each sample must be made to determine what is consistently there and what is random and should be disregarded. In this work each sample is injected three times. The data is first processed by MFE to generate features. Mass Profiler filters out features that are inconsistent among the three injections for each sample. The resulting data is called a Group. Therefore, in comparing Samples 4 and 10 Mass Profiler will be referring to them as Group 4 and Group 10.

In Figure 7, Mass Profiler shows a plot of features common to both Groups 4 and 10 and displays them as mass versus retention time. By clicking on any one of the feature points in the display, one can see the common feature for both Groups along with possible empirical formulas for the derived neutral mass.

Display Filters

Feature Position

☐ Use all the available data

RT Min: 4.0 Max: 15.0 min.

Mass: 150 600 Da

Special Masses

☐ Exclude ☒ Limit to these Tolerance: 0.0050 Da

284.0135	287.9512	293.0500	295.0167	295.1184
296.9645	297.1187	299.1521	305.0738	308.1049
309.1341	310.0736	313.9781	314.1413	318.1555
324.1638	329.1427	330.0077	344.1008	348.1685
413.9880	414.1613	418.2719	573.5121	

Masses from Table 1

Isotope Pattern

Formula Custom

formula

normalized height error: 0.15

Mass Defect

☐ Peptide Like

target defect = 0.00 (Da) + 0.00000 x mass

deviation allowed: 0.50 Da

Features of Unknown Mass

☒ included ☐ excluded ☐ limited to these

Number of Ions

☒ >= 2 ☐ <

Abundance

Relative Absolute Top

Min Relative Abundance: 0.100 %

Neutral Losses

Tolerance: 0.0050 Da

OK Cancel

Figure 5. Display filter settings for finding features that match compound list of Table 1.

Export features:8 / groups:8													
	Group	RT	mass	mass SD	abund.	satur.	height	#ions	minZ	maxZ	#z	width	#features
1	1	9.629	236.0961		915731		267469	2	1	1	1	0.045	1
2	2	5.678	299.1536		431858		91085	2	1	1	1	0.083	1
3	3	8.095	236.0961		382835		96590	2	1	1	1	0.052	1
4	4	8.671	299.1527		229538		23883	3	1	1	1	0.121	1
5	5	6.064	299.1525		146722		26146	2	1	1	1	0.076	1
6	6	11.598	250.1607		134252		19366	2	1	1	1	0.128	1
7	7	8.262	252.1204		63528		12743	2	1	1	1	0.058	1
8	8	5.307	296.9660	0.0019	28147		3522	4	1	1	1	0.072	1




Figure 6. Eight features found corresponding to the neutral masses of Table 1. Corresponding processed chromatogram also shown.




Figure 7. Features present in both Groups 4 and 10 total 346.

For example, in comparing features between the two sample groups a differential analysis plot can be generated as shown in Figure 8. In this plot, the features of Group 10 that are more or less abundant than the corresponding features in Group 4 are represented. More specifically, at a retention time of 8.495 minutes there is a data point in Figure 8 that corresponds to a feature in Group 10 that is approximately 4× intensity over the corresponding feature in Group 4, which corresponds to

a log 2 ratio of 2. By clicking on this data point in the display of Figure 8 one can see that this feature is identified as diphenhydramine, with a chemical formula of $C_{17}H_{21}NO$ and accurate mass of 0.7 ppm. See Figure 9.

With Mass Profiler it is also possible to compare two samples in terms of what features are in one sample that are not in the other. In Figure 10 we see such a comparison.




Figure 8. Features common to Groups 4 and 10 but differing in magnitude.




Figure 9. Feature at 8.495 minutes retention time corresponds to diphenhydramine.




Figure 10. Features only in Group 4 (highlighted with boxes) or in Group 10.

Mass Profiler has determined that there are 33 features only in Group 4 or in Group 10 and are not common to the two samples. Since the display in Mass Profiler is in color the features exclusive to Group 4 are blue and the features exclusive to Group 10 are red. Since Agilent applications are normally published in black and white, boxes have been placed around the blue features for Group 4 for viewing convenience.

So far, all of the data have been collected in full-scan MS mode. Once features are identified as compounds needing more structural information, or it is of interest to perform some quantitation, a targeted MS/MS analysis can be performed in which the ion mass of the feature is considered as precursor ion and fragmented to form accurate mass product ions. The accurate mass of these product ions can determine their chemical formula and possible structures. Because the QTOF also has a high degree of spectral resolution in MS/MS mode, very narrow extracted ion chromatograms may be generated for each ion and then summed together for quantitation signal.

In Figure 11 we see the accurate mass MS/MS fragmentation of caffeine using the MS/MS settings noted in the LC/MS Method Details. Caffeine is of environmental interest because many medications contain it as an ingredient. Chemical formulas for each product ion is derived based on the possible arrangements of C, H, N, and O. Knowing the structure of caffeine, structures of the fragment ions can be proposed using their corresponding chemi-


cal formula. The fragment structures are generated using ACD/MS Fragmentor (ACD Labs Release v. 10, Advanced Chemistry Development, Inc., Toronto, ON, Canada).

Conclusions

The QTOF is an excellent instrument for identifying compounds using accurate mass in full-scan MS and MS/MS. Accurate mass leads to chemical formula, which can also give structural information when forming product ions in MS/MS. As a lot of data is acquired by this type of instrument to look at samples that may contain large amounts of known and unknown compounds, it is important to have algorithms like Molecular Feature Extractor that can filter usable features out of the chemical background. These features are generated from spectra as a result of removing random background signal and finding clusters of isotopes that make sense.

While this analysis is useful for one sample it may also be important to make comparisons among multiple samples as well. Another algorithm known as Mass Profiler makes such comparisons. More specifically, comparisons such as what is common to two samples and how they differ in amount. Or, what features are in one sample that aren't in the other. Once the feature is considered for more investigation, targeted MS/MS may be carried out on that feature to get structural information based on the generation of product ions.

Calculate chemical formula given accurate mass measurement and using elements C, H, N, and O



Proposed Structures

Figure 11. Targeted MS/MS mode for caffeine-producing product ions that may be used for structural elucidation as well as quantitation.

References

1. C. G. Daughton and T. A. Ternes, "Pharmaceuticals and Personal Care Products in the Environment: Agents of Subtle Change?," *Environmental Health Perspectives*, 107, Suppl. 6, Dec 1999.
2. D. B. Chambers and T. J. Leiker, "A Reconnaissance for Emerging Contaminants in the South Branch Potomac River, Cacapon River, and Williams River Basins, West Virginia, April–October 2004," Open File Report 2006-1393, United States Geological Survey, <http://pubs.usgs.gov/of/2006/1393/>.

Acknowledgments

The authors gratefully acknowledge the assistance of Stephen Werner and Ed Furlong of the National Water Quality Lab – United States Geological Survey (Lakewood, CO) for providing the samples analyzed in this work.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

For more details concerning this application, please contact Michael Zumwalt at Agilent Technologies, Inc.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
October 12, 2007
5989-7339EN



Agilent Technologies



EPA Method 1694: Agilent's 6410A LC/MS/MS Solution for Pharmaceuticals and Personal Care Products in Water, Soil, Sediment, and Biosolids by HPLC/MS/MS

Application Note

Environmental

Authors

Imma Ferrer and E. Michael Thurman
Center for Environmental Mass
Spectrometry
University of Colorado
Civil, Environmental, and Architectural
Engineering
ECOT 441, 428 UCB
Boulder, CO 80309
USA

Jerry Zweigenbaum
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

An analytical methodology for screening and confirming the presence of 65 pharmaceuticals in water samples was developed using the Agilent G6410A Triple Quadrupole mass spectrometer (QQQ). The method was developed following the guidelines in EPA Method 1694. Four distinct chromatographic gradients and LC conditions were used according to the polarity and extraction of the different pharmaceuticals. Positive and negative ion electrospray were used with two multi-reaction monitoring (MRM) transitions (a quantifier and a qualifier ion for each compound), which adds extra confirmation in this methodology compared with the EPA method. Linearity of response of three orders of magnitude was demonstrated ($r^2 > 0.99$) for all the pharmaceuticals studied. The analytical performance of the method was evaluated for one wastewater sample collected from Boulder Creek, Colorado; positive identifications for carbamazepine and diphenhydramine were found for this sample using the methodology developed in this work.



Agilent Technologies

Introduction

The analytical challenge of measuring emerging contaminants in the environment has been a major research focus of scientists for the last 20 years. Pharmaceuticals and personal care products (PPCPs) are an important group of contaminants that have been targeted, especially in the last decade. In the area of PPCPs there are several methods addressing the analysis of these analytes, including EPA Method 1694 [1], which was recently published (December 2007). This EPA protocol uses solid-phase extraction (SPE) for water sample preparation [1]. The extracts are then analyzed directly by a

tandem mass spectrometer using a single transition for each compound. This application note describes the Agilent solution to this method, which is demonstrated with the Agilent model 6410A LC/MS QQQ. The Agilent initial implementation for EPA Method 1694 consists of 65 analytes (of 75 total analytes) and 17 labeled internal standards (of 20 total), which are a mixture of PPCPs that are analyzed each by a single MRM transition. (Note that the other compounds and internal standards could not be obtained at this time.) The method also uses Agilent C-18 and Hydrophilic Interaction Chromatography (HILIC) columns for all analytes. To provide additional confirmation, a second MRM transition was added for 60 of the 65 analytes analyzed. This gives an even greater assurance of correct identification than prescribed by the EPA. Table 1 shows the list of pharmaceuticals studied here.

Table 1. Analytes Studied in This Work

List of Group 1 Compounds EPA 1694: 46 Analytes

Acetaminophen	Codeine	Flumequine	Penicillin V	Sulfanilamide
Ampicillin	Cotinine	Fluoxetine	Roxithromycin	Thiabendazole
Azithromycin	Dehydronifedipine	Lincomycin	Sarafloxacin	Trimethoprim
Caffeine	Digoxigenin	Lomefloxacin	Sulfachloropyridazine	Tylosin
Carbadox	Diltiazem	Miconazole	Sulfadiazine	Virginiamycin
Carbamazepine	1,7-Dimethylxanthine	Norfloxacin	Sulfadimethoxine	Digoxin*
Cefotaxime	Diphenhydramine	Ofloxacin	Sulfamerazine	
Ciprofloxacin	Enrofloxacin	Oxacillin	Sulfamethazine	
Clarithromycin	Erythromycin	Oxolinic acid	Sulfamethizole	
Cloxacillin	Erythromycin anhydrate	Penicillin G	Sulfamethoxazole	

*Compound formed intractable Na adduct with current conditions.

List of Group 2, 3, and 4 Compounds: EPA 1694: 19 Analytes

Anhydrotetracycline (2)	Doxycycline (2)	Minocycline (2)	Triclocarban (3)
			Triclosan (3)
			Warfarin (3)
Chlorotetracycline (2)	4-Epianhydrotetracycline (2)	Tetracycline(2)	Albuterol (4)
		Meclocycline (2)	Cimetidine (4)
			Metformin (4)
Demeclocycline(2)	4-Epitetracycline(2)	Gemfibrozil (3)	Ranitidine (4)
		Ibuprofen (3)	
		Naproxen (3)	

List of Labeled Internal Standards

$^{13}\text{C}_2$ - ^{15}N -Acetaminophen	$^{13}\text{C}_2$ -Erythromycin	$^{13}\text{C}_6$ -Sulfamethazine	$^{13}\text{C}_3$ -Trimethoprim
$^{13}\text{C}_3$ -Atrazine	Fluoxetine- d_6	$^{13}\text{C}_6$ -Sulfamethoxazole	Warfarin- d_5
$^{13}\text{C}_3$ -Caffeine	Gemfibrozil- d_6	$^{13}\text{C}_6$ -2,4,5-Trichloro-phenoxycetic acid	Carbamazepine- d_{10} (Extra compound, not EPA list)
$^{13}\text{C}_3$ - ^{15}N -Ciprofloxacin	$^{13}\text{C}_3$ -Ibuprofen	$^{13}\text{C}_6$ -Triclocarban	
Cotinine- d_3	^{13}C -Naproxen- d_3	$^{13}\text{C}_{12}$ -Triclosan	

Experimental

Sample Preparation

Pharmaceutical analytical standards were purchased from Sigma, (St. Louis, MO). All stable isotope labeled compounds used as internal standards were obtained from Cambridge Isotope Laboratories (Andover, MA). Individual pharmaceutical stock solutions (approximately 1,000 µg/mL) were prepared in pure acetonitrile or methanol, depending on the solubility of each individual compound, and stored at -18 °C. From these solutions, working standard solutions were prepared by dilution with acetonitrile and water.

Water samples were collected from the wastewater treatment plant at the Boulder Creek outfall (Boulder, CO) and extracted as per the EPA method. Agilent has introduced a polymeric SPE sorbent with hydrophilic/lipophilic properties that may also be appropriate for this application. "Blank" wastewater extracts were used to prepare the matrix-matched standards for validation purposes. The wastewater extracts were spiked with the mix of pharmaceuticals at different concentrations (ranging from 0.1 to 500 ng/mL or ppb) and subsequently analyzed by LC/MS/MS.

LC/MS/MS Instrumentation

The analytes were subdivided in groups (according to EPA protocol for sample extraction) and LC conditions for the chromatographic separation of each group are as follows.

LC Conditions for Group 1-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	10% ACN and 90% H ₂ O with 0.1% HCOOH
Flow rate	0.2–0.3 mL/min
Gradient	t ₀ = 10% ACN, 0.2 mL/min t ₅ = 10% ACN, 0.2 mL/min t ₈ = 10% ACN, 0.3 mL/min t ₂₄ = 60% ACN, 0.3 mL/min t ₃₀ = 100% ACN
Injection volumes	15 µL

LC conditions for Group 2-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	10% ACN and 90% H ₂ O with 0.1% HCOOH
Flow rate	0.2 mL/min
Gradient	t ₀ = 10% ACN t ₁₀ = 10% ACN t ₃₀ = 100% ACN
Injection volumes	15 µL

LC conditions for Group 3-acidic extraction, negative electrospray ionization (ESI-) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	40% MeOH and 60% H ₂ O with 5 mM ammonium acetate, pH 5.5
Flow rate	0.2 mL/min
Gradient	t _{0.5} = 40% MeOH t ₇ = 100% MeOH
Injection volumes	15 µL

LC conditions for Group 4-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX HILIC Plus 2.1 × 100 mm, 3.5 µm (p/n 959793-901 custom order until November 1, 2008)
Column temperature	25 °C
Mobile phase	98% ACN and 2% H ₂ O with 10 mM ammonium acetate, pH 6.7
Flow rate	0.25 mL/min
Gradient	t ₀ = 98% ACN t ₅ = 70% ACN t ₁₂ = 70% ACN
Injection volumes	15 µL

The mass spectrometer conditions were general to all groups and are as follows.

MS Conditions

Mode	Positive and negative (depending on group) ESI using the Agilent G6410A Triple Quadrupole mass spectrometer
Nebulizer	40 psig
Drying gas flow	9 L/min
V capillary	4000 V
Drying gas temperature	300 °C
Fragmentor voltage	70–130 V
Collision energy	5–35 V
MRM	2 transitions for every compound as shown in Table 1
Dwell time	10 msec

Results and Discussion

Optimization of LC/MS/MS Conditions

The initial study consisted of two parts. First was to optimize the fragmentor voltage for each of the pharmaceuticals studied in order to produce the largest signal for the precursor ion. Typically the protonated molecule was used for the precursor ion. Each compound was analyzed separately using an automated procedure (MassHunter Optimizer software, Agilent Technologies, Santa Clara, CA) to check the fragmentor at each voltage. The data was then selected for optimal fragmentor signal and each compound was optimized again to determine automatically the collision energies for both the quantifying and qualifying ions. Optimal collision energies varied between 5 and 35 V. The MRM transitions and optimized energies used for this study are shown in Tables 2A to 2D.

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1 (The labeled standards are bold.)

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Acetaminophen	90	152 → 110 152 → 65	15 35
¹³C₂-¹⁵N-Acetaminophen	90	155 → 111 155 → 93	15 25
Ampicillin	70	350 → 160 350 → 106	10 15
¹³C₃-Atrazine	120	219 → 177 219 → 98	15 25
Azithromycin	130	749.5 → 591.4 749.5 → 158	30 35
Caffeine	110	195 → 138 195 → 110	15 25
¹³C₃-Caffeine	110	198 → 140 198 → 112	15 25
Carbadox	80	263 → 231 263 → 130	5 35
Carbamazepine	110	237 → 194 237 → 179	15 35
Carbamazepine-d₁₀	110	247 → 204 247 → 202	15 35
Cefotaxime	90	456 → 396 456 → 324	5 5
Ciprofloxacin	110	332 → 314 332 → 231	20 35
¹³C₃-¹⁵N-Ciprofloxacin	110	336 → 318 336 → 235	15 35

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1
(The labeled standards are bold.) continued

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Clarithromycin	110	748.5 → 158 748.5 → 590	25 15
Cloxacillin	90	436 → 160 436 → 277	15 15
Codeine	130	300 → 215 300 → 165	25 35
Cotinine	90	177 → 98 177 → 80	25 25
Cotinine-d₃	90	180 → 80 180 → 101	25 25
Dehydronifedipine	130	345 → 284 345 → 268	25 25
Digoxigenin	90	391 → 355 391 → 337	15 15
Digoxin	No response, Na adduct		
Diltiazem	130	415 → 178 415 → 150	25 25
1,7-Dimethylxanthine	90	181 → 124 181 → 99	15 15
Diphenhydramine	70	256 → 167 256 → 152	15 35
Enrofloxacin	130	360 → 316 360 → 342	15 15
Erythromycin	90	734.5 → 158 734.5 → 576	35 15
¹³C₂-Erythromycin	90	736.5 → 160 736.5 → 578	25 15
Erythromycin anhydrate	90	716.5 → 158 716.5 → 116	25 25
Flumequine	90	262 → 174 262 → 244	35 15
Fluoxetine	90	310 → 148	5
Fluoxetine-d₆	90	316 → 154	5
Lincomycin	110	407 → 126 407 → 359	25 15
Lomefloxacin	130	352 → 308 352 → 265	15 25
Miconazole	90	415 → 159 415 → 69	35 25
Norfloxacin	70	320 → 302 320 → 276	15 15
Ofloxacin	110	362 → 318 362 → 261	15 25

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1 (The labeled standards are bold.) continued

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Oxacillin	70	402 → 160 402 → 243	15 5
Oxolinic acid	90	262 → 244 262 → 216	15 25
Penicillin G	90	335 → 160 335 → 176	5 5
Penicillin V	70	351 → 160 351 → 114	5 25
Roxithromycin	130	837.5 → 679 837.5 → 158	15 35
Sarafloxacin	130	386 → 299 386 → 368	25 25
Sulfachloropyridazine	90	285 → 156 285 → 92	10 25
Sulfadiazine	110	251 → 156 251 → 92	15 25
Sulfadimethoxine	80	311 → 156 311 → 92	20 35
Sulfamerazine	110	265 → 156 265 → 92	15 25
Sulfamethazine	90	279 → 156 279 → 186	15 15
¹³C₆-Sulfamethazine	90	285 → 186 285 → 162	25 25
Sulfamethizole	80	271 → 156 271 → 92	10 25
Sulfamethoxazole	110	254 → 156 254 → 92	15 25
¹³C₆-Sulfamethoxazole	110	260 → 162 260 → 98	15 25
Sulfanilamide	70	173 → 156 173 → 92	5 15
Thiabendazole	130	202 → 175 202 → 131	25 35
¹³C₆-2,4,5-Trichlorophenoxyacetic acid	110	259 → 201 259 → 165	5 25
Trimethoprim	110	291 → 230 291 → 261	25 25
¹³C₃-Trimethoprim	110	294 → 233 294 → 264	25 25
Tylosin	110	916.5 → 174 916.5 → 772	35 35
Virginiamycin	110	526 → 508 526 → 355	5 15

Table 2B. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 2

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Anhydrotetracycline	90	427 → 410 427 → 154	15 25
Chlorotetracycline	110	479 → 462 479 → 197	15 35
Demeclocycline	130	465 → 430 465 → 448	25 15
Doxycycline	110	445 → 428 445 → 154	15 25
4-Epianhydrotetracycline (EATC)	90	427 → 410 427 → 105	15 35
4-Epitetracycline (ETC)	110	445 → 410 445 → 427	15 5
Minocycline	90	458 → 441	15
Tetracycline (TC)	110	445 → 410 445 → 427	15 5

Table 2C. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 3

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Gemfibrozil	100	249 → 121	5
Gemfibrozil-d₆	100	255 → 121	5
Ibuprofen	75	205 → 161	5
¹³C₃-Ibuprofen	75	208 → 163	5
Naproxen	75	229 → 169 229 → 170	25 5
¹³C-Naproxen-d₃	75	233 → 169 233 → 170	25 5
Triclocarban	100	313 → 160 313 → 126	10 25
¹³C₆-Triclocarban	90	319 → 160 319 → 132	5 25
Triclosan	75	287 → 35	5
¹³C₁₂-Triclosan	75	299 → 35	5
Warfarin	125	307 → 117 307 → 161	35 15
Warfarin-d₅	90	312 → 161 312 → 255	15 25

Table 2D. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 4

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Albuterol (Salbutamol)	90	240 → 148	15
		240 → 166	5
Cimetidine	100	253 → 159	10
		253 → 95	25
Metformin	80	130 → 60	10
		130 → 71	25
Ranitidine	110	315 → 176	15
		315 → 130	25

Chromatographic separation was done independently for each group and a dwell time of 10 msec was used for every MRM transition. Figures 1A to 1D show the chromatograms corresponding to 100 ppb standard on column for all the pharmaceuticals studied. Extracted ion chromatograms are overlaid for each one of the target analytes according to their respective protonated molecule and product-ion MRM transitions.




Figure 1A. MRM extracted chromatogram for pharmaceuticals in Group 1. Three time segments were used in this chromatographic separation.




Figure 1B. MRM extracted chromatogram for pharmaceuticals in Group 2. Only one transition shown. See Table 2B for compound identification.




Figure 1C. MRM extracted chromatogram for pharmaceuticals in Group 3. Only one transition shown. See Table 2C for compound identification.




Figure 1D. MRM extracted chromatogram for pharmaceuticals in Group 4.

Application to Wastewater Samples

To confirm the suitability of the method for analysis of real samples, matrix-matched standards were analyzed in a wastewater matrix from an effluent site, at eight concentrations (0.1, 0.5, 1, 5, 10, 50, 100, and 500 ng/mL or ppb concentrations). Figure 2 shows an example standard curve for acetaminophen in the wastewater matrix. In general, all compounds gave linear results with excellent sensitivity over three orders of magnitude, with r^2 values of 0.99 or greater.




Figure 2. Calibration curve for acetaminophen in a wastewater matrix using a seven-point curve from 0.1 to 100 ng/mL (ppb) using a linear fit with no origin treatment.

Finally, a “blank” wastewater sample was analyzed and the presence of two pharmaceuticals, carbamazepine and diphenhydramine, could be confirmed with two MRM transitions. Figure 3 shows the ion ratios qualifying for these two compounds in a wastewater extract. As shown in Figure 3 in the two ion profiles, both pharmaceuticals were easily identified in this complex matrix due to the selectivity of the MRM transitions and instrument sensitivity.




Figure 3. MRM chromatograms of a wastewater sample for carbamazepine and diphenhydramine using two transitions.

Conclusions

The results of this study show that the Agilent 6410A Triple Quadrupole is a robust, sensitive, and reliable instrument for the study of pharmaceuticals in water samples, using high throughput methods. The Agilent 6410A Triple Quadrupole has been shown to be a successful instrument for the implementation of EPA Method 1694.

References

1. EPA Method 1694: Pharmaceuticals and personal care products in water, soil, sediment, and biosolids by HPLC/MS/MS, December 2007, EPA-821-R-08-002.

www.agilent.com/chem

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Printed in the USA
September 19, 2008
5989-9665EN



Agilent Technologies




Emerging Contaminants

PFOA/PFOS Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)

Quantitative Analysis of Perfluorooctanoic Acid by LC/MS/MS



Application Brief

Environmental

Authors

Sheher Mohsin
Agilent Technologies, Inc.
10 N. Martingale Rd., Suite 550
Schaumburg, IL 60173-2292
USA

Michael Zumwalt
Agilent Technologies, Inc.
9780 S Meridian Blvd., MS 1-1E
Englewood, CO 80112-5910
USA

Abstract

An Agilent 6410 Triple Quadrupole Mass Spectrometer (QQQ) is used to analyze perfluorooctanoic acid (PFOA). A simple isocratic elution is carried out on a Rapid Resolution High Throughput C18 column (particle size 1.8 μ m) with only water and methanol solvents containing 10 mM ammonium acetate. Elution time for standard dilutions of PFOA is only 2.3 minutes. Good linearity over more than 4 orders of magnitude, from 9 fg/ μ L to 150 pg/ μ L, is demonstrated with excellent peak area reproducibility of 5.5 % RSD at the 9 fg/ μ L level. The average peak-to-peak signal-to-noise (S/N) ratio at this level is 7.2. Sensitivity of surface water extracts is expected to be similar.


Introduction

Perfluorooctanoic acid (PFOA) is a synthetic chemical that does not occur naturally in the environment.

Companies use PFOA to make fluoropolymers, which are substances with valuable properties for applications such as fire resistance and oil, stain, and grease repellence. Toxicological studies have shown that exposure to PFOA can result in developmental/reproductive toxicity, liver damage, and possibly cancer. PFOA is highly persistent in the environment and has been found at very low levels in both the environment and in the blood of the general U.S. population. Recent studies by the EPA have indicated the need for additional testing and monitoring. Detection at levels < 100 ppt in drinking water is required by the European Union.

In this work, dilutions of the PFOA standard are run at levels ranging from 9 fg/ μ L to 150 pg/ μ L, with a correlation coefficient of linearity of $R^2 > 0.997$. Nonlinearity is seen with the 1,500 pg/ μ L level. During the worklist the 9 fg/ μ L level is injected six times in a row to determine reproducibility. Based on peak areas the reproducibility at this lowest level of investigation is 5.5% RSD. Since the injection volume is 10 μ L, the on-column injection amount at this lowest level is only 90 fg.

The structure of PFOA is shown below.



This molecule is a carboxylic acid, which is expected to show good sensitivity in negative ion mode using electrospray ionization (ESI).



Agilent Technologies

Experimental

Sample Preparation

The PFOA standard is obtained at a concentration of 1,500 ng/ μ L. Dilutions in methanol are made up at 0.009, 0.015, 0.15, 0.45, 0.75, 1.5, 15.0, 150, and 1,500 pg/ μ L concentrations.

LC/MS Method Details

LC Conditions

Agilent 1100 Series binary pump, degasser, wellplate sampler, and thermostatted column compartment

Column: Agilent ZORBAX Eclipse Plus RRHT C18,
2.1 mm $\times$ 100 mm, 1.8 μ m (p/n 959764-902)

Column temperature: 40 $^{\circ}$ C

Mobile phase: A = 10 mM ammonium acetate in water
B = 10 mM ammonium acetate in
80:20 methanol/water

Flow rate: 0.3 mL/min

Injection volume: 10 μ L

Isocratic: 85% B

Stop time: 3 minutes

Needle wash: 75:25 methanol/water; flush port
10 seconds

MS Conditions

Mode: Negative ESI using the Agilent G1948B
ionization source

Nebulizer: 35 psig

Drying gas flow: 10 L/min

Drying gas temp: 300 $^{\circ}$ C

V_{cap} : 4,000 V

Resolution (FWHM): Q1 = 0.7 amu; Q2 = 0.7 amu

MRM transition: m/z 413.0 > 369.0

Fragmentor: 67 V

Collision energy: 3 V

Dwell time: 200 msec

Results and Discussion

The calibration curve for this work is shown in Figure 1. At the lowest level of investigation (9 fg/ μ L) nine replicate injections are made. Nine replicate injections are also made at the 15 fg/ μ L level. As seen in Figure 2, the peak area reproducibility is 5.5% RSD. The average S/N ratio at this level is 7.2. Noise is calculated from the 1–1.5-minute region.




Figure 1. Calibration curve for PFOA. Lowest three levels consist of nine replicate injections at 9 fg/ μ L and 15 fg/ μ L each, and one injection at 150 fg/ μ L.




Figure 2. Excellent sensitivity and reproducibility at the lowest level investigated.

If an additional dilution level of 1,500 pg/μL is added to the calibration curve, then we see the result shown in Figure 3, in which a quadratic curve fit of the data is required. However, note the excellent correlation coefficient of $R^2 > 0.99999$.

Conclusions

The perfluorooctanoic acid compound is very sensitive to negative electrospray ionization mode. Very good linearity is demonstrated with the standard at dilutions ranging from 9 fg/uL to 150 pg/μL, which corresponds to an on-column injection amount ranging from 90 fg to 1.5 ng. Peak area reproducibility at the lowest level investigated of 9 fg/μL is excellent at 5.5% RSD, and the average signal-to-noise ratio of the replicate injections at this level is 7.2. Signal saturation is seen at 1,500 pg/μL, or 15 ng on-column. As drinking water is a relatively clean matrix, it is expected that similar sensitivity will be achievable with extracted samples.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

For more details concerning this application brief, please contact Michael Zumwalt at Agilent Technologies, Inc




Figure 3. Saturation seen with addition of 1500 pg/μL level, or 15 ng on-column.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
 April 3, 2007
 5989-6577EN



Agilent Technologies



Addressing the Challenges of Analyzing Trace Perfluorooctanoic Acid (PFOA) and Perfluorooctane Sulfonate (PFOS) Using LC/QQQ

Application

Food, Environmental

Authors

Robert D. Voyksner
LCMS Limited
PO Box 27228
Raleigh, NC 27611-7228
USA

Chin-Kai Meng
Agilent Technologies
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

An approach to the difficult task of quantifying trace quantities of perfluorooctanoic acid (PFOA) and perfluorooctane sulfonate (PFOS) in complex matrix was developed using liquid chromatography and tandem mass spectrometry (LC/MS/MS). The technique uses isotopically labeled analytes for accurate quantitation (0.4 to 400 pg on column). It is important to recognize that if using the linear chain sample as standard for calibration, the quantitation results of real-world samples (branched and linear isomers mixed) will be off by as much as 40%.

Introduction

Perfluorooctanoic acid (PFOA) is an industrial surfactant and a necessary processing aid in the manufacture of fluoropolymers [1]. Fluoropolymers have many valuable properties, including fire resistance and the ability to repel oil, stains, grease

and water. One of the most common uses of PFOA is for processing polytetrafluoroethylene (PTFE), most widely known as Teflon®. PFOA is also a by-product from direct and indirect contact with food packaging (for example, microwave-popcorn bags, bags for muffins or french fries, pizza box liners, boxes for hamburgers, and sandwich wrappers), and in the fabrication of water- and stain-resistant clothes.

Perfluorooctanesulfonic acid (PFOS) is usually used as the sodium or potassium salt and is referred to as perfluorooctane sulfonate. See Figure 1.





Figure 1. Chemical structures for PFOA and PFOS. Note that both have C8 chains.



Agilent Technologies

Quantitative Analysis of Perfluorooctanoic Acid by LC/MS/MS



Application Brief

Environmental

Authors

Sheher Mohsin
Agilent Technologies, Inc.
10 N. Martingale Rd., Suite 550
Schaumburg, IL 60173-2292
USA

Michael Zumwalt
Agilent Technologies, Inc.
9780 S Meridian Blvd., MS 1-1E
Englewood, CO 80112-5910
USA

Abstract

An Agilent 6410 Triple Quadrupole Mass Spectrometer (QQQ) is used to analyze perfluorooctanoic acid (PFOA). A simple isocratic elution is carried out on a Rapid Resolution High Throughput C18 column (particle size 1.8 μ m) with only water and methanol solvents containing 10 mM ammonium acetate. Elution time for standard dilutions of PFOA is only 2.3 minutes. Good linearity over more than 4 orders of magnitude, from 9 fg/ μ L to 150 pg/ μ L, is demonstrated with excellent peak area reproducibility of 5.5 % RSD at the 9 fg/ μ L level. The average peak-to-peak signal-to-noise (S/N) ratio at this level is 7.2. Sensitivity of surface water extracts is expected to be similar.


Introduction

Perfluorooctanoic acid (PFOA) is a synthetic chemical that does not occur naturally in the environment.

Companies use PFOA to make fluoropolymers, which are substances with valuable properties for applications such as fire resistance and oil, stain, and grease repellence. Toxicological studies have shown that exposure to PFOA can result in developmental/reproductive toxicity, liver damage, and possibly cancer. PFOA is highly persistent in the environment and has been found at very low levels in both the environment and in the blood of the general U.S. population. Recent studies by the EPA have indicated the need for additional testing and monitoring. Detection at levels < 100 ppt in drinking water is required by the European Union.

In this work, dilutions of the PFOA standard are run at levels ranging from 9 fg/ μ L to 150 pg/ μ L, with a correlation coefficient of linearity of $R^2 > 0.997$. Nonlinearity is seen with the 1,500 pg/ μ L level. During the worklist the 9 fg/ μ L level is injected six times in a row to determine reproducibility. Based on peak areas the reproducibility at this lowest level of investigation is 5.5% RSD. Since the injection volume is 10 μ L, the on-column injection amount at this lowest level is only 90 fg.

The structure of PFOA is shown below.



This molecule is a carboxylic acid, which is expected to show good sensitivity in negative ion mode using electrospray ionization (ESI).



Agilent Technologies

Experimental

Sample Preparation

The PFOA standard is obtained at a concentration of 1,500 ng/ μ L. Dilutions in methanol are made up at 0.009, 0.015, 0.15, 0.45, 0.75, 1.5, 15.0, 150, and 1,500 pg/ μ L concentrations.

LC/MS Method Details

LC Conditions

Agilent 1100 Series binary pump, degasser, wellplate sampler, and thermostatted column compartment

Column: Agilent ZORBAX Eclipse Plus RRHT C18,
2.1 mm $\times$ 100 mm, 1.8 μ m (p/n 959764-902)

Column temperature: 40 $^{\circ}$ C

Mobile phase: A = 10 mM ammonium acetate in water
B = 10 mM ammonium acetate in
80:20 methanol/water

Flow rate: 0.3 mL/min

Injection volume: 10 μ L

Isocratic: 85% B

Stop time: 3 minutes

Needle wash: 75:25 methanol/water; flush port
10 seconds

MS Conditions

Mode: Negative ESI using the Agilent G1948B
ionization source

Nebulizer: 35 psig

Drying gas flow: 10 L/min

Drying gas temp: 300 $^{\circ}$ C

V_{cap} : 4,000 V

Resolution (FWHM): Q1 = 0.7 amu; Q2 = 0.7 amu

MRM transition: m/z 413.0 > 369.0

Fragmentor: 67 V

Collision energy: 3 V

Dwell time: 200 msec

Results and Discussion

The calibration curve for this work is shown in Figure 1. At the lowest level of investigation (9 fg/ μ L) nine replicate injections are made. Nine replicate injections are also made at the 15 fg/ μ L level. As seen in Figure 2, the peak area reproducibility is 5.5% RSD. The average S/N ratio at this level is 7.2. Noise is calculated from the 1–1.5-minute region.




Figure 1. Calibration curve for PFOA. Lowest three levels consist of nine replicate injections at 9 fg/ μ L and 15 fg/ μ L each, and one injection at 150 fg/ μ L.




Figure 2. Excellent sensitivity and reproducibility at the lowest level investigated.

If an additional dilution level of 1,500 pg/μL is added to the calibration curve, then we see the result shown in Figure 3, in which a quadratic curve fit of the data is required. However, note the excellent correlation coefficient of $R^2 > 0.99999$.

Conclusions

The perfluorooctanoic acid compound is very sensitive to negative electrospray ionization mode. Very good linearity is demonstrated with the standard at dilutions ranging from 9 fg/μL to 150 pg/μL, which corresponds to an on-column injection amount ranging from 90 fg to 1.5 ng. Peak area reproducibility at the lowest level investigated of 9 fg/μL is excellent at 5.5% RSD, and the average signal-to-noise ratio of the replicate injections at this level is 7.2. Signal saturation is seen at 1,500 pg/μL, or 15 ng on-column. As drinking water is a relatively clean matrix, it is expected that similar sensitivity will be achievable with extracted samples.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

For more details concerning this application brief, please contact Michael Zumwalt at Agilent Technologies, Inc




Figure 3. Saturation seen with addition of 1500 pg/μL level, or 15 ng on-column.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
 April 3, 2007
 5989-6577EN



Agilent Technologies

Analytical Methodology for PFOA/PFOS

- LC/MS/MS is the preferred detection methodology due to its high sensitivity and specificity in complex matrices.
- Multiple reaction monitoring (MRM) is used to quantitate, using two or more product ions for confirmation.
- The detection limit is typically in the range 1 to 100 pg/mL (ppt), requiring high-sensitivity detection.
- On-column or off-line solid-phase extraction (SPE) and concentration are needed to achieve low-level detection (1 pg/mL).

Measuring PFOS and PFOA

Issue 1: *What transitions should be used to give the best accuracy when quantifying with a linear standard?*

Quantification of PFOS and PFOA is usually based on a linear standard, but actual samples show a series of branched isomers together with the linear isomer. The ratio of these isomers varies based upon biodegradation and industrial processes in their formation; therefore, it is unlikely that a standard can be formulated to mimic the actual sample. The relative intensities of the MRM transitions will vary based upon branching, making some transitions better than others. Branching impacts ionization efficiency and CID energy; therefore, it affects the accuracy of analytical measurement [2].

Issue 2: *Can isotopically labeled standards in matrix be used to measure nonlabeled PFOS and PFOA?*

Most biological and environmental matrices have background levels of PFOS and PFOA; although matrix-matched calibrations are providing good results, the accuracy can be enhanced. The method of standard additions is a protocol to address this issue, but it adds several additional injections to the analysis. Matrix may have varying amount of background. Standard addition is not practical in analyzing many different matrices. Solvent calibrations do not correct for matrix effects.

Experimental

Sample Prep

- All solvent standards were prepared in methanol.

- Plasma extracts were prepared by acetonitrile precipitation and centrifuging, with the upper layer taken and spiked with known concentrations of PFOA or PFOS.

LC

- Agilent 1200 Rapid Resolution LC system
- ZORBAX Eclipse Plus C18 Rapid Resolution HT column 2.1 cm × 50 mm, 1.8-μm particles (P/N 959741-902)
- 20-μL injection, 0.4 mL/min column flow
- 0 to 100% B in 10 min, A = water with 2 mM ammonium acetate; B = MeOH

MS/MS

- Agilent QQQ
- Negative-ion detection
- 3500 V_{cap}, drying gas 9.5 L/min at 350 °C, nebulizer 45 psi
- Fragmentor voltages, collision energy (CE), and ion transitions are experimentally determined

Multiple Reaction Monitoring (MRM)

Figure 2 displays a cross-section of the Agilent 6410 QQQ above a hypothetical sequence of spectra characteristic of ion transitions within the instrument.

The ions are generated in the source shown at the far left of the figure. The precursor ion of interest is then selected from this mixture and isolated through the Q1 quadrupole, which acts as a mass filter. This is similar to selected ion monitoring (SIM). After Q1, characteristic fragments that are specific to the structure of the precursor ion are generated in the collision cell (Q2, although not a quadrupole). By using the Q3 quadrupole, these fragments are then selected for measurement at the detector. This is a selective form of collision-induced dissociation (CID), known as tandem MS/MS. By setting Q3 to a specific fragment ion existing in the collision cell, the chemical or background noise is almost totally eliminated from the analyte signal, therefore, significantly increasing the signal-to-noise ratio. Ion 210 is called the precursor ion and ions 158 and 191 are product ions. Each transition (210→191 or 210→158) is a reaction for a particular target. Typically, the QQQ is used to monitor multiple analytes or mass transitions, therefore, the term MRM. The 158 could be considered the quantitation ion, because it is the




Figure 2. A cross-section of the Agilent 6410 QQQ above a sequence of spectra characteristic of ion transitions within the instrument for a hypothetical sample (*not* PFOA or PFOS). Note that the final spectrum is very clean, containing only the desired target ions. (HED = high-energy dynode electron multiplier)

most intense, and 191 could be used for confirmation by using the area ratio of the 191 qualifier to the 158 quantifier ion as a criterion for confirmation. With MRM, most chemical noise is eliminated in Q1, and again in Q3, allowing us to get ppt detection.

The fragmentor is the voltage at the exit end of the glass capillary where the pressure is about 1 mTorr. Fragmentor and collision energies need to be optimized. A fragmentor that is too small won't have enough force to push ions through the gas. A fragmentor that is too high can cause CID of precursor ions in the vacuum prior to mass analysis, thereby reducing sensitivity. The actual voltage used is compound-, mass-, and charge-dependent, and therefore needs to be optimized to get the best sensitivity. The CE in the collision cell needs to be optimized in order to generate the most intense product ions representative of each target compound. Collision cell voltage will depend on the bond strength, the molecular weight of the compound, and the path by which the ion is formed (directly from the precursor ion or through a series of sequential intermediates). Typically each product ion will exhibit a preferential collision energy that results in the best signal abundance.

The experimental operations required to arrive at optimal conditions are exemplified by the series of experiments shown in Figures 3 to 5.

Optimization of the fragmentor voltages for the $[M-H]^-$ ions of PFOA (m/z 413) and PFOS (m/z 499) are shown in Figure 3.

Note that there is little signal detected for PFOA at the optimal fragmentor voltage for PFOS (200 V). Ions 413 and 499 are called precursor ions. PFOA is relatively fragile; its precursor signal drops off at 160 V. PFOS shows that it is harder than PFOA to break apart; the best fragmentor voltage for PFOS is 200 V.

The appropriate collision energies for product ions m/z 369 $[M-CO_2H]^-$ and m/z 169 $[C_3F_7]^-$ are experimentally determined and used to quantify PFOA. See Figure 4.

In each case the collision energy producing the most intense peak for each ion is chosen for the analysis. PFOA takes little collision energy to break into ion m/z 369 (6 V for highest intensity).




Figure 3. Determination of optimal fragmentor voltage using sequential plots of signal intensity versus applied voltage.

To maximize the intensity of the ion at m/z 169, the collision energy needs to go to 16 V.

The QQQ software can switch collision energies very rapidly. So in a method, the optimal collision voltage can be selected for each ion transition.

In the same manner, the appropriate collision energies for PFOS product ions at m/z 169, 99, and 80 are experimentally determined and used for its quantitation. The optimal collision energies for the three ion transitions are 45, 50, and 70 V. See Figure 5.




Figure 4. Signal intensity as a function of collision energy for PFOA product ions m/z 369 $[M-CO_2H]^-$ and m/z 169 $[C_3F_7]^+$.

Notice the big difference in collision energy between PFOA (6 to 16 V) and PFOS (45 to 70 V). We have seen from fragmentor optimization that PFOA is relatively fragile compared to PFOS, in which the optimum fragmentor voltages are 120 and 200 V for PFOA and PFOS, respectively. The CE reinforces that aspect.

Example calibration curves for the specified product ions used to quantitate PFOA and PFOS are shown in Figure 6. The analyst can also sum the intensities of these MRM transitions to get a calibration curve.

These five ion transitions exhibit linear correlation coefficients > 0.998 , and are good for quantitation over three orders of magnitude. Notice that the lowest amount on column is 0.4 pg.

Regarding issue 1: *What transitions should be used to give the best accuracy when quantifying with a linear standard?*

This is addressed using Figures 7 to 9.

Figure 7 exhibits chromatograms from these representative transitions for PFOA and PFOS for the linear standard and samples containing branches (10-min gradient).






Figure 5. Signal intensity as a function of collision energy for PFOS product ions at m/z 169, 99, and 80.

PFOA



PFOS



Concentration range 0.02 to 20 ng/mL (0.4 to 400 pg injected on column)

Figure 6. Calibration curves for the product ions used to measure PFOA and PFOS.

Real-world samples have been detected with branched isomers due to manufacturing processes, metabolism, and degradation processes. The top chromatogram of Figure 7 shows only linear chain compounds from a standard. The bottom chromatogram is an actual sample from the environment. It shows additional peaks (shoulders) in the chromatogram resulting from branched isomers.

We examine those peaks in greater detail in Figure 8.




Figure 7. MRM chromatograms for PFOA and PFOS for both linear and branched samples.

The relative abundances for each MRM transition are dependent on the branching locations and the specific mass transitions. Figure 8 shows a 10-minute run. The chromatography can separate the linear from the branched isomers. The branched sample is typically a C7 chain with a methyl side group (isooctyl isomer). The most interesting part of the analysis is that the ion ratios for the branched compounds are very different from the linear chain compounds [3, 4, 5]. For

linear PFOA, the ion at m/z 169 is about 30 to 40% of ion 369. The branched isomer shows that the ratio changed to 90 to 100%. For linear PFOS, the ion at m/z 99 is about 50% of ion 80 and is 500% of ion 169. The branched isomer shows that ion 99 is only 20 to 30% of ion 80, and 100% of ion 169. This is a cause of concern in terms of quantitation accuracy. This shows that CID stability is very different when the analyte is branched.




Figure 8. MRM chromatograms for PFOA and PFOS for both linear and branched samples.

Another variable in the analysis is the gradient time. Figure 9 compares the effect of a 3-min versus 10-min gradient.

In the fast gradient case (on the right), the branched isomers (dashed lines) are not resolved from the linear isomers (solid lines), resulting in a significant error in the measured value (most noticeable for PFOS).

The two chromatograms on the left are the same two that are shown in Figure 8. They are used here for comparison against the unresolved analytes shown on the right (3-min run). Although we would like to cut down on the analysis time, the branched and linear isomers need to be resolved in order to get accurate quantitation results.

Two samples of the same concentration. One sample is the pure linear isomer; the other sample has a mixture of branched isomers. If their MRM responses (ion ratios) are the same, they would show the same results as when the isomers are not resolved. This example shows that the responses are not the same when the isomers are not resolved. If you add the responses of the side chain analyte and the linear chain analyte of the same sample, the area of each ion transition is different from the pure linear chain analyte ion transition, as seen in the two chromatograms on the right, most apparent is for PFOS. If using the linear chain sample as standard for calibration, the results of real-world samples (branched and linear isomers mixed) will be off by as much as 40% (see Table 1). The quantitation falls apart.




Figure 9. Comparison of PFOA and PFOS MRM chromatograms produced using both 10- and 3-minute gradients. The 3-minute gradient chromatograms are on the right.

The effect of measurement accuracy (*not* ion ratios) of total PFOA and PFOS in branched samples against a linear standard for each MRM transition is shown in Table 1.

Table 1. Measurement Accuracy (Target Is 100%) as Function of Compound, Transition, and Run Time

Compound	MRM transition	Percent response (n = 8)	
		10-min run	3-min run
PFOA	413→369	105.9	108.2
	413→169	96.4	89.4
PFOS	499→169	102.5	112.2
	499→99	75.0	73.3
	499→80	59.3	61.1

The best MRM ions are in bold type. The best results for PFOA can be obtained by averaging the results for the two MRM ions together.

Ion ratios can cause quantitation failure. For PFOA, it does not matter if it's a 3-min run or a 10-min run: the ion 369 transition response is always higher and the ion 169 transition response is always lower. The errors are larger for the 3-min run. The variations are greater for PFOS. In literature, PFOS analysis monitors the ion 80 transition, but it exhibits a large variation. It can be as low as 60%, as seen in Table 1. 499 → 169 is a good transition for quantitation. It is much more accurate, but it is less sensitive compared to 499 → 80 transition.

Regarding issue 2: Can isotopically labeled standards in matrix be used to measure non-labeled PFOS and PFOA?

This is addressed using Figures 10 to 12.

Observations regarding the effect of different matrices on signal responses are shown in Figure 10. The taller trace represents the response of PFOA in methanol. The response is lower as the same amount of PFOA is added into a plasma extract.

The matrix effect (common using electrospray ionization) can lead to signal suppression or enhancement; therefore, matrix-matched calibrations are required for accurate quantitation. Due to varying background levels of PFOS and PFOA in matrix, it may not be feasible to use matrix-matched calibrations for quantitating PFOS or PFOA concentrations in study samples. Also, the method of standard additions is not a practical alternative for many matrices with varying levels of target analytes.

As a practical alternative, measuring PFOA using isotopically labeled matrix-matched standards was examined. Results are shown in Figures 11 and 12.

Figure 11 shows that isotopically labeled standards can provide a good linear calibration curve over the quantitation range of 0.02 to 20 ng/mL (0.4 to 400 pg on column). Excellent linear correlation coefficients (≥ 0.9994) were obtained.





Figure 10. PFOA responses in MeOH and plasma extract at the same concentrations.



Calibration in plasma from 0.02 to 20 ng/mL

Figure 11. Linear correlations for PFOA using two different isotopically labeled calibration standards.




Figure 12. Both isotopically labeled PFOA compounds show good correlation to the unlabeled PFOA. The same transitions for the labeled and native forms of the PFOA were used.

Table 2. Comparison of Different Matrix-Matched Calibrations for Measuring PFOA in Plasma

	Calibration standard	Matrix for calibration	Plasma sample response (Std Dev)
1	PFOA	MeOH	71 (± 33 %)
2	PFOA [1,2- ¹³ C]	Plasma	100.4 (± 3.1 %)
3	PFOA [1,2,3,4- ¹³ C]	Plasma	97.3 (± 5.1 %)

Matrix-matched calibrations using isotopically labeled PFOA work well.

For row 1, the calibration standard used MeOH as the solvent, and the plasma sample exhibited a 71% response due to matrix suppression. Therefore, we cannot use a calibration standard in MeOH to quantitate samples in matrix; the variation can be as large as 30%. Rows 2 and 3 show that if the calibration is done using an isotopically labeled compound in matrix, the actual plasma sample yields accurate results: 100 and 97%.

Conclusions

- The Agilent LC/QQQ is an excellent instrument for quantifying trace target compounds in complex mixtures.
- The best ion transitions for analysis need to be determined experimentally.
- Fragmentor voltages and collision energies require experimental determination and optimization.
- Using MRM in the QQQ helps achieve the lowest detection limits in complex matrices.
- Branched PFOA/PFOS can affect quantitation accuracy as much as 40% unless it is corrected.
- Matrix suppression can cause the quantitation to be off by as much as 30%. Isotopically labeled analytes work well for accurate quantitation in spite of varying background levels of PFOA/PFOS in matrices.

References

1. Perfluorooctanoic Acid (PFOA), USEPA, <http://www.epa.gov/oppt/pfoa/>
2. T. J. Wallington, M. D. Hurley, J. Xia, D. J. Wuebbles, S. Sillman, A. Ito, J. E. Penner, D. A. Ellis, J. Martin, S. A. Mabury, O. J. Nielsen, and M. P. Sulbaek Andersen, "Formation of C₇F₁₅COOH (PFOA) and Other Perfluorocarboxylic Acids

During the Atmospheric Oxidation of 8:2 Fluorotelomer Alcohol," *Environ. Sci. Technol.*, 40 (3), 924–930, 2006

3. Jonathan P. Benskin, Mahmoud Bataineh, and Jonathan W. Martin, "Simultaneous Characterization of Perfluoroalkyl Carboxylate, Sulfonate, and Sulfonamide Isomers by Liquid Chromatography-Tandem Mass Spectrometry," *Anal. Chem.*, 79 (17), 6455–6464, 2007
4. I. Langlois and M. Oehme, "Structural identification of isomers present in technical perfluorooctane sulfonate by tandem mass spectrometry," *Rapid Commun. Mass Spectrom.* 20, 844–850, 2006
5. Amila O. De Silva and Scott A. Mabury, "Isomer Distribution of Perfluorocarboxylates in Human Blood: Potential Correlation to Source," *Environ. Sci. Technol.* 40, 2903–2909, 2006

Acknowledgement

Partial support and the standards for this study were provided by the Environmental Lab of the 3M Company (St Paul, MN).

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
April 23, 2008
5989-7790EN



Agilent Technologies



Analyzing Compounds of Environmental Interest Using an LC/Q-TOF

Part 2: Fluorotelomer Unsaturated Acids

Application

Environmental

Authors

Jim Lau, Chin-Kai Meng, and Jennifer Gushue
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Robert J. Letcher and Shaogang Chu
Wildlife and Landscape Science Directorate
Science and Technology Branch
Environment Canada
National Wildlife Research Centre
Carleton University
Ottawa, Ontario, K1A 0H3
Canada

Abstract

Perfluoroalkyl substances (PFASs) have been widely used in a variety of products due to their chemical inertness, resistance to heat, and ability to repel water and oils. PFASs exhibit a high propensity for persistence and bioaccumulation in wildlife, which is causing concern. Due to different manufacturing and degradation processes, different chain lengths and functional groups of PFAS exist in the environment. An LC/Q-TOF is best suited to screen, identify, and quantify many perfluoroalkyl compounds in different matrices.

This LC/Q-TOF application shows good mass accuracy (well below 3 ppm) and good resolution (> 13,500). Excellent quantification results for selected PFASs were obtained from extracts derived from blind liver samples.

Introduction

Environment Canada is tasked with risk assessment and the evaluation of impact of a variety of compounds in environmental matrices, including wildlife tissues, water, sediment, and air [1, 2]. A number of compounds classified as perfluoroalkyl substances (PFASs) have been widely used in a variety of products due to their chemical inertness, resistance to heat, and ability to repel water and oils. Some of the commercial PFAS products include lubricants, adhesives, stain and soil repellents, paper coatings, and fire-fighting foams. Due to their unique chemical and biological stability, some PFASs exhibit a high propensity for persistence and bioaccumulation in wildlife. In recent years, particular environmental concern has arisen as a number of PFASs have been reported in tissues of marine mammal, seabird, and fish species inhabiting various regions of the Arctic. More specifically, some PFASs, such as perfluorooctane sulfonate (PFOS) [$\text{CF}_3(\text{CF}_2)_7\text{SO}_3\text{H}$] and C8 to C15 chain length perfluorinated carboxylates (PFCAs), have been reported present at similar or higher concentrations than persistent organochlorines (OCs) in polar bears [3–5].

Many of the PFASs originate from the two manufacturing processes of electrochemical fluorination (perfluoroalkyl sulfonamido alcohols degrade to PFOS) and telomerization (fluorotelomer alcohols [FTOHs] are transformed to PFOA). The degradation pathway for telomers is:



Agilent Technologies

From 8:2 fluorotelomer alcohol (8:2 FTOH) to:

- Major products: 8:2 fluorotelomer aldehyde (8:2 FTAL), 8:2 fluorotelomer carboxylate (8:2 FTCA), and perfluorooctanoic acid (PFOA) [CF₃(CF₂)₆CO₂H]
- Minor products: 8:2 fluorotelomer unsaturated carboxylate (8:2 FTUCA, CF₃(CF₂)₆CF=COOH) and perfluorononanoic acid (PFNA)

Then from 8:2 FTCA and 8:2 FTUCA (degradation products from above) to:

- Major product: PFOA
- Minor product: PFNA

This application uses fluorotelomer unsaturated carboxylates (FTUCAs – metabolites of telomer alcohols) to demonstrate the mass accuracy, resolution, and the quantification capability of the LC/Q-TOF.

Experimental

Samples

This study analyzed three standard solutions of the following three target compounds at 1, 100, and 250 ppb. Three internal standards (ISTDs) at 50 ppb each were also added to each of the three solutions. A fourth sample was a blind liver extract with an undisclosed concentration of the three target compounds.

Target Compounds:

FHUEA (C8, 6:2 FTUCA)	2H-Perfluoro-2-octenoic acid CF ₃ (CF ₂) ₄ CF=CH-COOH
FOUEA (C10, 8:2 FTUCA)	2H-Perfluoro-2-decenoic acid CF ₃ (CF ₂) ₆ CF=CH-COOH
FDUEA (C12, 10:2 FTUCA)	2H-Perfluoro-2-dodecenoic acid CF ₃ (CF ₂) ₈ CF=CH-COOH

ISTDs:

MFHUEA	2H-Perfluoro-[1,2- ¹³ C ₂]-2-octenoic acid CF ₃ (CF ₂) ₄ CF=C ¹³ H-C ¹³ OOH
MFOUEA	2H-Perfluoro-[1,2- ¹³ C ₂]-2-decenoic acid CF ₃ (CF ₂) ₆ CF=C ¹³ H-C ¹³ OOH
MFDUEA	2H-Perfluoro-[1,2- ¹³ C ₂]-2-dodecenoic acid CF ₃ (CF ₂) ₈ CF=C ¹³ H-C ¹³ OOH

Instrument Parameters

All sample analyses were performed on an Agilent 1200 SL Rapid Resolution LC coupled to an Agilent 6520 Q-TOF.

All sample analyses were performed under LC/Q-TOF autotune conditions. Mass accuracy, sensitivity, and resolution for all samples were measured without any changes to 6520 Q-TOF instrument parameters, except ion source conditions appropriate for the spray chamber type, LC flow, and sample thermal stability.

Mobile A	3 mM NH ₄ OAc
Mobile B	MeOH
LC column	ZORBAX XDB 2.1 mm × 50 mm, C-18, 3.5-μm particle size
Flow rate	0.5 mL/min
Injection volume	10 μL
MS	Scanned at 2.5 scans/sec, 50 to 1,100 <i>m/z</i>
Negative ref. ions	<i>m/z</i> 113, 1034
Q-TOF parameters	Set by autotune
Drying gas	12 L/min N ₂ at 300 °C
Nebulizer pressure	50 psi
ESI (–)	3 KV
Fragmentor	275 V

Results and Discussion

Table 1 shows the mass accuracy and resolution of the six compounds analyzed in this study. The accuracy for each compound was under 3 ppm and the resolution was > 13,500. Table 2 shows the quantitation ions and results. The quantitation ion was not the molecular ion but a fragment ion from the collision-induced dissociation (CID). The fragment ion is a lost fragment of “FCOOH” ([M–H][–] – 64) from the deprotonated molecular ion. The calibration range was 1 to 250 ppb (that is, 10 pg to 2.5 ng on column). Good signal-to-noise ratios (un-smoothed signal) were observed for the three FTUCA standards at 1 ppb (see Figure 1).

A blind mixture of the three standards in liver extract was quantified by Q-TOF. Excellent quantification results were obtained for all three targets:

Compound	Measured	Actual
FOUEA	4.0 ppb	5 ppb
FHUEA	2.7 ppb	5 ppb
FDUEA	6.7 ppb	5 ppb

By comparing the ISTD responses, ion suppression (matrix effect) was observed in analyzing the liver extract. It has been shown using an LC/QQQ system with atmospheric pressure photoionization (APPI) is a more effective technique than electrospray ionization (ESI) to analyze FTOHs and perfluorinated sulfonamides [6].

Table 1. Mass Accuracy and Resolution of the Six FTUCA Analyzed in This Study

	Formula	Mass accuracy (ppm)	Resolution
FHUEA	C ₈ H ₂ F ₁₂ O ₂	-0.98	13692
MFHUEA	[¹³ C] ₂ C ₆ H ₂ F ₁₂ O ₂	-0.39	13789
FOUEA	C ₁₀ H ₂ F ₁₆ O ₂	-0.19	14018
MFOUEA	[¹³ C] ₂ C ₈ H ₂ F ₁₆ O ₂	-2.08	13564
FDUEA	C ₁₂ H ₂ F ₂₀ O ₂	-0.62	15399
MFDUEA	[¹³ C] ₂ C ₁₀ H ₂ F ₂₀ O ₂	-1.33	14322

Table 2. Quantification Ions and Linearity of the FTUCA
(The quantitation ion is a lost fragment of "FCOOH" from the molecular ion.)

	Formula	[M-H] ⁻	Quant Ion ([M-H] ⁻ - 64)	R ² (1-250 ppb)
FHUEA	C ₈ H ₂ F ₁₂ O ₂	357	293	0.9992
MFHUEA	[¹³ C] ₂ C ₆ H ₂ F ₁₂ O ₂	359	294	—
FOUEA	C ₁₀ H ₂ F ₁₆ O ₂	457	393	0.9998
MFOUEA	[¹³ C] ₂ C ₈ H ₂ F ₁₆ O ₂	459	394	—
FDUEA	C ₁₂ H ₂ F ₂₀ O ₂	557	493	0.9972
MFDUEA	[¹³ C] ₂ C ₁₀ H ₂ F ₂₀ O ₂	559	494	—




Figure 1. Expansion of EICs for quant ions of 1 ppb FTUCA standards (S/N > 5, unsmoothed signal).

Conclusions

Some of the most impressive aspects about the LC/Q-TOF were the mass accuracy, the linear dynamic range, and the signal-to-noise ratios. For environmental applications, using Q-TOF can greatly reduce interference from complex matrices and improve the accuracy of the results. This application of Q-TOF shows good mass accuracy (well below 3 ppm) and good resolution (> 13,500). Excellent quantification results were obtained from a blind liver extract.

References

1. Jim Lau, Chin-Kai Meng, Jennifer Gushue, Mehran Alaei, and Vimal Balakrishnan, "Analyzing Compounds of Environmental Interest Using an LC/Q-TOF – Part 1: Dyes and Pigments," Agilent Technologies publication 5989-9336EN, August 2008.
2. Jim Lau, Chin-Kai Meng, Jennifer Gushue, Mark Hewitt, and Suzanne Batchelor, "Analyzing Compounds of Environmental Interest Using an LC/Q-TOF – Part 3: Imidacloprid and Manool," Agilent Technologies publication 5989-9129EN, August 2008.
3. J. W. Martin, M. M. Smithwick, B. M. Braune, P. F. Hoekstra, D. C. G. Muir, and S. A. Mabury, "Identification of Long-Chain Perfluorinated Acids in Biota from the Canadian Arctic," *Environ. Sci. Technol.*, 2004, 38, 373–380.

4. M. M. Smithwick, D. C. G. Muir, S. A. Mabury, K. R. Solomon, J. W. Martin, C. Sonne, E. W. Born, R. J. Letcher, and R. Dietz, "Perfluoroalkyl Contaminants in Liver Tissue from East Greenland Polar Bears (*Ursus maritimus*)," *Environ. Toxicol. Chem.*, 2005, 24, 981–986.
5. M. M. Smithwick, S. A. Mabury, K. R. Solomon, C. Sonne, J. W. Martin, E. W. Born, R. Dietz, A. E. Derocher, R. J. Letcher, T. J. Evans, G. W. Gabrielsen, J. Nagy, I. Stirling, M. K. Taylor, and D. C. G. Muir, "Circumpolar Study of Perfluoroalkyl Contaminants in Polar Bears (*Ursus maritimus*)," *Environ. Sci. Technol.*, 2005, 39, 5517–5523.
6. S. G. Chu and R. J. Letcher, "Methodological Comparison of the Determination of Fluorotelomer Alcohols and Perfluorinated Sulfonamides in Biotic Samples by Liquid Chromatography-Atmospheric Pressure Photoionization and -Electrospray Mass Spectrometry," in preparation.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
August 11, 2008
5989-9132EN




Agilent Technologies



Emerging Contaminants

PBDEs Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)



GC Analysis of Polybrominated Flame Retardants

Application

Environmental

Authors

Eberhardt Kuhn, Jason Ellis
Agilent Technologies, Inc.
91 Blue Ravine Rd,
Folsom, CA 95630
USA

Steve Wilbur
Agilent Technologies, Inc.
3380 146th Place SE
Suite 300
Bellevue, WA 98007
USA

Abstract

Polybrominated diphenyl ethers (PBDE) are used as flame retardants in such diverse products as textiles, circuit boards, and computer covers. Through the disposal of those products in landfills, PBDEs have found their way into the environment. Studies have shown that PBDEs have detrimental health effects.

Detection and quantitation of these compounds is complicated by their intrinsic properties: high boiling points and low thermal stability. This application note describes

development of suitable gas chromatography/mass spectrometry, gas chromatography micro electron capture detection, and gas chromatography inductively coupled plasma mass spectrometry methods to analyze PBDEs. The Agilent DB-XLB is the column of choice for this demanding analysis. The detection limit with micro electron capture detector was 100 ppt for most congeners.

Introduction

The presence of polybrominated diphenyl ethers (PBDE) throughout the environment has attracted the attention of scientists around the world. PBDEs are used as flame retardants in many commercial products, such as textiles and furniture, and in circuit boards in consumer electronics, such as TVs and computers. As more and more of these abundant consumer products find their way into landfills, PBDEs have been found in our drinking water supplies [1]. One alarming study predicts that the levels found in human breast milk of North American women appear to double every 2 to 5 years [2]. Exposure of personnel working with computers is also a concern [3]. While the toxicology of PBDE is still under investigation, research has established that it is persistent, bioaccumulative, and toxic. There is evidence that



Agilent Technologies

PBDE can cause neurotoxic effects similar to the now-banned polychlorinated biphenyls (PCB). As a result, California has just signed legislation banning the use of PBDEs [4]. Like PCBs, there are 209 PBDE congeners (Figure 1), and they are named in analogy to PCBs [5]. However, only seven congeners comprise about 95% of all detected peaks [6]. These major congeners are (by IUPAC number): 28, 47, 99, 100, 153, 154, and 209.




Figure 1. Structure of PBDE.

Until recently, the lack of available standards and individual congeners has made accurate quantitation difficult [7]. Now, practically all individual congeners are commercially available. For analysis by GC, several different stationary phases have been used. However, analysis times are generally quite long, and often not all critical congeners are sufficiently resolved. This study investigates two different columns and three detection modes. DB-XLB (Agilent Technologies, Folsom CA), a proprietary low-polarity stationary phase and DB-35ms (Agilent Technologies, Folsom CA), a mid-polarity phase, are both columns that have very low bleed and high thermal stability. DB-XLB has shown to be an excellent choice for detailed, high-resolution analysis of PCB congeners by GC/MS [8]. The structural similarities between PCBs and PBDEs suggest that DB-XLB should be an excellent choice for separation of PBDEs as well. DB-35ms has shown to be a suitable confirmatory column to DB-XLB [9]. The detection modes evaluated were mass selective detector (MSD), micro electron capture detector (μ ECD), and inductively coupled plasma mass spectrometry (ICP-MS). Method optimization efforts for speed, sensitivity, and resolution included different column dimensions, inlet conditions, detector settings, and temperature programs.

Results and Discussion

Baseline separation of all 14 critical congeners (Table 1) in a standard mixture including decabromodiphenylether (BDE-209) could be accomplished by DB-XLB in about 20 minutes with excellent peak shape and response of the decabromodiphenylether [10].

Table 1. PBDE Congeners in Test Mix EO-5103 Elution Order on DB-XLB

Peak	Congener (2.5 mg/mL)
1	2,2',4-TriBDE (BDE-17)
2	2,4,4'-TriBDE (BDE-28)
3	2,3',4',6-TetraBDE (BDE-71)
4	2,2',4,4'-TetraBDE (BDE-47)
5	2,3',4,4'-TetraBDE (BDE-66)
6	2,2',4,4',6-PentaBDE (BDE-100)
7	2,2',4,4',5-PentaBDE (BDE-99)
8	2,2',3,4,4'-PentaBDE (BDE-85)
9	2,2',4,4',5,6'-HexaBDE (BDE-154)
10	2,2',4,4',5,5'-HexaBDE (BDE-153)
11	2,2',3,4,4',5'-HexaBDE (BDE-138)
12	2,2',3,4,4',5',6-HeptaBDE (BDE-183)
13	2,3,3',4,4',5,6-HeptaBDE (BDE-190)
14	DecaBDE (BDE-209) (12.5 mg/mL)

A more demanding mixture (Table 2a,b) containing 39 of the most common and important congeners at very low concentration could be separated by DB-XLB in about 14 minutes (Figure 2a, b). This is much faster than analysis times typically reported with other columns. Although two of the tetra isomers are very close with this column, they were baseline resolved with DB-35ms. By contrast, there were two co-elutions with the DB-35ms, which were both baseline resolved on DB-XLB. This demonstrates that these two stationary phases are an excellent choice as a pair of confirmation columns. For baseline resolution of all congeners on a single column, as well as for separation of more complex mixtures, a column with more theoretical plates and/or a higher phase ratio may be necessary. Using


a DB-XLB, 30 m × 0.18 mm × 0.18 µm gave complete baseline separation of the tetra isomers, as did a DB-5ms, 60 m × 0.25 mm × 0.25 µm. However, the higher substituted isomers, in particular BDE-209, showed relatively low response. The lower phase ratio results in longer retention times for all congeners. This longer residence time on the column at high temperature may lead to on-column break down of these thermally labile compounds.

Table 2a. PBDE Congeners in Test Mix EO-5113 Elution Order on DB-XLB

2-MonoBDE (#1)	2',3,4-TriBDE (#33)	2,3,4,5,6-PentaBDE (#116)
3-MonoBDE (#2)	2,4,4'-TriBDE (#28)	2,3',4,4',5-PentaBDE (#118)
4-MonoBDE (#3)	3,3',4-TriBDE (#35)	
	3,4,4'-TriBDE (#37)	2,2',4,4',6,6'-HexaBDE(#155)
2,6-DiBDE (#10)		
2,4-DiBDE (#7)	2,4,4',6-TetraBDE (#75)	2,2',3,4,4'-PentaBDE (#85)
3,3'-DiBDE (#11)	2,2',4,5'-TetraBDE (#49)	3,3',4,4',5-PentaBDE (#126)
2,4'-DiBDE (#8)	2,3',4',6-TetraBDE (#71)	
3,4-DiBDE (#12)	2,2',4,4'-TetraBDE (#47)	2,2',4,4',5,6'-HexaBDE(#154)
3,4'-DiBDE (#13)	2,3',4,4'-TetraBDE (#66)	2,2',4,4',5,5'-HexaBDE(#153)
4,4'-DiBDE (#15)	3,3',4,4'-TetraBDE (#77)	2,2',3,4,4',5'-HexaBDE(#138)
		2,3,4,4',5,6-HexaBDE (#166)
2,4',6-TriBDE (#32)	2,2',4,4',6-PentaBDE (#100)	2,2',3,4,4',5',6-HeptaBDE (#183)
2,4,6-TriBDE (#30)	2,3',4,4',6-PentaBDE (#119)	2,2',3,4,4',5,6-HeptaBDE(#181)
2,2',4-TriBDE (#17)	2,2',4,4',5-PentaBDE (#99)	2,3,3',4,4',5,6-HeptaBDE (#190)
2,3',4-TriBDE (#25)		

Table 2b. PBDE Congeners in Test Mix EO-5113 Elution Order on DB-35ms

3-MonoBDE (#2)	2,4,4'-TriBDE (#28)	2,3',4,4',5-PentaBDE (#118)
2-MonoBDE (#1)	2',3,4-TriBDE (#33)	2,3,4,5,6-PentaBDE (#116)
4-MonoBDE (#3)	3,3',4-TriBDE (#35)	
	3,4,4'-TriBDE (#37)	2,2',4,4',6,6'-HexaBDE(#155)
2,6-DiBDE (#10)		
2,4-DiBDE (#7)	2,2',4,5'-TetraBDE (#49)	3,3',4,4',5-PentaBDE (#126)
3,3'-DiBDE (#11)	2,4,4',6-TetraBDE (#75)	2,2',3,4,4'-PentaBDE (#85)
2,4'-DiBDE (#8)	2,3',4',6-TetraBDE (#71)	
3,4-DiBDE (#12)	2,2',4,4'-TetraBDE (#47)	2,2',4,4',5,6'-HexaBDE(#154)
3,4'-DiBDE (#13)	2,3',4,4'-TetraBDE (#66)	2,2',4,4',5,5'-HexaBDE(#153)
4,4'-DiBDE (#15)	3,3',4,4'-TetraBDE (#77)	2,2',3,4,4',5'-HexaBDE(#138)
		2,3,4,4',5,6-HexaBDE (#166)
2,4',6-TriBDE (#32)	2,2',4,4',6-PentaBDE (#100)	2,2',3,4,4',5',6-HeptaBDE (#183)
2,4,6-TriBDE (#30)	2,3',4,4',6-PentaBDE (#119)	2,2',3,4,4',5,6-HeptaBDE(#181)
2,3',4-TriBDE (#25)	2,2',4,4',5-PentaBDE (#99)	2,3,3',4,4',5,6-HeptaBDE (#190)
2,2',4-TriBDE (#17)		




Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m $\times$ 0.25 mm id $\times$ 0.1 μ m (Agilent Technologies, part number 122-1231)
 Carrier gas: Helium at 38 cm/s at 100 $^{\circ}$ C (1.2 mL/min), constant flow mode
 Oven: 100 $^{\circ}$ C for 1 min; 100 $^{\circ}$ C to 340 $^{\circ}$ C at 20 $^{\circ}$ C/min, 340 $^{\circ}$ C for 12 min
 Injector: Cool-on-column, oven-track mode, 0.5 μ L
 Detector: Agilent 5973 MSD; transfer line at 325 $^{\circ}$ C, EI
 SIM: (Ions monitored: 231.8, 248.0, 327.9, 398.6, 400.5, 405.8, 845.7, 563.6, 643.5, 721.4, 799.3)

Note:

Mono-through octa-substituted homologs detected using selected ion monitoring (SIM) at the most intense of the M^{+} , $(M+2)^{+}$, $(M+4)^{+}$, $(M+6)^{+}$, or $(M+8)^{+}$ masses, with a data acquisition rate of approximately 3 cycles/second. Monitoring the molecular ion was not possible above octa-substituted PBDEs due to the limitations of the mass range of the Agilent 5973 instrument (maximum of m/z 800). Decabromodiphenylether was detected by monitoring significant fragments of high abundance: m/z 231.8, 398.6, 400.5, and 799.3.

Figure 2a. Gas chromatography/mass spectrometry (GC/MS) of PBDE congener mixture (E0-5113).




Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m $\times$ 0.25 mm id $\times$ 0.1 μ m (Agilent Technologies, part number 122-1231)
 Carrier gas: Helium at 38 cm/s at 100 $^{\circ}$ C (1.2 mL/min), constant flow mode
 Oven: 100 $^{\circ}$ C for 1 min; 100 $^{\circ}$ C to 340 $^{\circ}$ C at 20 $^{\circ}$ C/min, 340 $^{\circ}$ C for 12 min
 Injector: Cool-on-column, oven-track mode, 0.5 μ L
 Detector: Agilent 5973 MSD; transfer line at 325 $^{\circ}$ C, EI
 SIM: (Ions monitored: 231.8, 248.0, 327.9, 398.6, 400.5, 405.8, 845.7, 563.6, 643.5, 721.4, 799.3)

Note:

Mono-through octa-substituted homologs detected using SIM at the most intense of the M^+ , $(M+2)^+$, $(M+4)^+$, $(M+6)^+$, or $(M+8)^+$ masses, with a data acquisition rate of approximately 3 cycles/second. Monitoring the molecular ion was not possible above octa-substituted PBDEs due to the limitations of the mass range of the 5973 instrument (maximum of m/z 800). Decabromodiphenylether was detected by monitoring significant fragments of high abundance: m/z 231.8, 398.6, 400.5, and 799.3.

Figure 2b. GC/MS of PBDE congener mixture (EO-5113).

Figure 3 shows a chromatogram of a commercial flame retardant mixture. While commercial samples are typically classified as “penta”, “octa”, or “deca”, they contain other congeners as well. Again, the congeners in this mixture are well resolved, and the run time is very short (13 minutes).




Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
Column: DB-XLB, 30 m $\times$ 0.25 mm id $\times$ 0.1 μ m (Agilent Technologies, part number 122-1231)
Carrier gas: Helium at 38 cm/s at 100 $^{\circ}$ C (1.2 mL/min), constant flow mode
Oven: 100 $^{\circ}$ C for 1 min; 100 $^{\circ}$ C to 340 $^{\circ}$ C at 20 $^{\circ}$ C/min, 34 $^{\circ}$ C for 12 min
Injector: Cool-on-column, oven-track mode, 0.5 μ L
Detector: Agilent 5973 MSD; transfer line at 325 $^{\circ}$ C, EI
SIM: (Ions monitored: 231.8, 248.0, 327.9, 398.6, 400.5, 405.8, 845.7, 563.6, 643.5, 721.4, 799.3)

Figure 3. Commercial flame retardant penta DE71-R.


Analysis times could be reduced even further by using hydrogen carrier gas and an Electron Capture Detector (ECD). This combination allows for faster flow rates, while improving sensitivity and lowering the detection limit. With the same column dimensions as above, run times of around 15 minutes are possible. With a custom-made column (DB-XLB, 15 m $\times$ 0.18 mm id $\times$ 0.07 μ m) the run time was less than 12 minutes (Figure 4), with no signs of degradation of the 209 congener. Break down of the higher congeners was, however, dependent on the run conditions. An inlet

temperature of 250 °C worked best, while the μ ECD gave best results at 300 °C. At higher detector temperature, degradation was noticeable, while lower ECD temperatures resulted in tailing peaks (likely due to cold trapping). As expected, sensitivity for PBDEs with a μ ECD is excellent (Figure 5). In the splitless injection mode, the detection limit under those run conditions for the tri and higher substituted PBDEs was around 100 ppt, with a signal-to-noise ratio of >20. The calibration curve for 2,2',4,4',6-PentaBDE (BDE-100) was linear from 1 ppm to 100 ppt.



Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 15 m $\times$ 0.18 mm id $\times$ 0.07 μ m (Agilent Technologies, custom column)
 Carrier gas: Hydrogen at 72 cm/s at 100 °C (4.0 mL/min), constant flow mode
 Oven: 100 °C for 0.5 min; 100 °C to 300 °C at 30 °C/min, 300 °C for 5 min
 Injector: 250 °C, split 20:1, 1 μ L
 Detector: ECD at 300 °C


Figure 4. GC- μ ECD of PBDE congener mixture (E0-5103).



Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m × 0.25 mm id × 0.1 μm (Agilent Technologies, part number 122-1231)
 Carrier gas: Hydrogen at 72 cm/s at 100 °C (4.0 mL/min), constant flow mode
 Oven: 100 °C for 1 min; 100 °C to 300 °C at 25 °C/min, 300 °C for 10 min
 Injector: 300 °C, splitless, 1 μL
 Detector: ECD at 300 °C

Figure 5. GC-μECD of PBDE mixture EO-5103 at 500 ppt.

The same sensitivity could be achieved with GC-ICP-MS. Figure 6 shows congener mixture EO-5103 diluted to 10 ppb. Calibration curves of individual congeners from 1 ppm to 1 ppb were linear ($R^2 = 1.000$), and the lower detection limit is calculated at 150 ppt. The system setup conditions for the ICP-MS, such as torch position, may not be fully optimized yet, so detection limits may be even lower.



Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m × 0.25 mm id × 0.1 μm (Agilent Technologies, part number 122-1231)
 Carrier Gas: Helium at 36 cm/s at 100 °C (1.5 mL/min), constant flow mode
 Oven: 100 °C for 1 min; 100 °C to 300 °C at 20 °C/min, 320 °C for 13 min
 Injector: 320 °C, splitless, 1 μL
 Detector: Agilent 7500cs ICP-MS, monitoring Br at $m/z = 81$

Figure 6. GC-ICP-MS of PBDE mixture EO-5103 at 10 ppb.

Conclusions

DB-XLB is the column of choice for GC analysis of PBDEs. The high upper temperature limit and very low bleed characteristics of this column make it ideal for this class of large molecules. While the high upper temperature limit allows for fast run times - complete analyses, including BDE-209, can be run in about 20 minutes, the extremely low bleed at those temperatures increases sensitivity, thus providing lower detection limits. The DB-35ms is an excellent secondary column that has the same outstanding bleed and thermal properties as DB-XLB, yet a different selectivity required for a confirmation column. In general, short columns with a high phase ratio (thin film) yield better response for the higher congeners, since the shorter residence times on the column reduce the exposure to high temperatures, therefore reducing on-column break down.

Due to the high bromine content of PBDEs, sensitivity on an ECD is very high. With splitless injection, the lower detection limit that we achieved is approximately 100 ppt. This limit might be pushed even lower with a programmable temperature vaporization (PTV) inlet, where larger injection volumes are possible. However, in real samples, for example, marine wildlife, other halogenated compounds, like PCBs, may be present. Since an ECD cannot distinguish between halogens, it is impossible to determine if a PCB co-elutes with a PBDE, thus quantitation may not be accurate. GC/MS offers secondary confirmation of the identity of the eluted peak, but sensitivity is not as great. In SIM mode, the detection limit for PBDEs is estimated at about 10 ppb. GC-ICP-MS offers both - high sensitivity and ion selectivity. It can be tuned for Cl or Br. Thus, by monitoring for example m/z 81, only PBDE would be detected, and PCB would not interfere with quantitation.

Acknowledgements

Individual PBDE congeners were a generous gift from AccuStandard (New Haven, CT). Special thanks to Mehran Alaei and Ivy D'Sa of the Aquatic Ecosystem Protection Research Branch, National Water Research Institute, Burlington, Canada, for helpful discussions, sharing of data, and providing samples of industrial brominated flame retardants. Thanks also to Harry Prest and Emmett Soffey of Agilent Technologies and Robert Trengrove of Murdoch University for helpful discussions and providing data.

References

1. October 13, 2001, *Science News*, Vol. **160**, No. 15.
2. December 8, 2001, *Science News*, Vol. **160**, No. 22.
3. Andreas Sjödin et al, (1999) *Environmental Health Perspectives*, **107**:643-648.
4. August 4, 2003, *Chemical and Engineering News*, Vol. **81**, No. 31.
5. Karlheinz Ballschmitter et al, (1992) *J. High Res Chrom.*, **15**, 260-270.
6. Mehran Alaei of Environment Canada, personal communication
7. Andreas Sjödin et al, (1998) *Journal of Chromatography A*, **822**, 83-89.
8. J. W. Cochran and G. M. Frame, (1999) *Journal of Chromatography A*, **843**, 323-368.
9. Cameron George, (2001), *Separation Times* Vol. **14**, No. 1.
10. Eberhardt Kuhn et al, Pittcon 2003, 310-14P.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2003

Printed in the USA
September 11, 2003
5989-0094EN



Agilent Technologies



Determination of Polybrominated Diphenylethers (PBDE) in Sediment and Sewage Sludge

Application

Environmental

Authors

Sonia Wanner
Centre d'Analyse et de Recherche (CAR)
76 route du Rhin
F-67441 Illkirch
France

Isabelle Chanel
Agilent Technologies France
Parc Club du Moulin à Vent
33 rue du Docteur Levy
F-69693 Venissieux
France

Abstract

Generally used as flame retardants, polybrominated diphenylethers (PBDE) have become chemicals of significant environmental concern. While little toxicological information is available, PBDEs have been determined to be persistent and bio-accumulative substances, similar to well-known environmental contaminants such as polychlorinated biphenyls (PCBs). Therefore, environmental laboratories are asked to analyze polybrominated diphenylethers (flame retardants) in sediment and sewage sludge. This application note describes the successful separation of all PBDEs, including the most difficult, decabrominated diphenylether. Examples include standards as well as real samples of sewage sludge with quantitative data.

Introduction

With increasing frequency, environmental laboratories are asked to analyze PBDEs (flame retardants) in sediment and sewage sludge. See Figure 1.




Figure 1. Structure of PBDEs.

Brominated flame retardants (BFRs) are a group of chemicals added to many products, including computers, TVs, and household textiles, in order to reduce fire risk. Two substances, decabromodiphenyl ether (DecaBDE) and tetrabromobisphenol A (TBBP-A), account for about 50% of world use of brominated flame retardants. Two other polybrominated diphenyl ethers (PolyBDE) - octabromodiphenyl ether (OctaBDE) and pentabromodiphenyl ether (PentaBDE) - are used commercially, but in much smaller quantities than DecaBDE.

Heating (for example, during manufacture of plastics) and burning of materials containing PBDEs and other BFRs can produce polybrominated



Agilent Technologies

dibenzo-p-dioxins and dibenzofurans, which have similar toxicological effects to chlorinated dioxins. Research has shown that low-level exposure of young mice to PBDEs causes permanent disturbances in behavior, memory, and learning (Eriksson et al., 1998) [1]. PBDEs have also been shown to disrupt the thyroid hormone system in rats and mice; these systems are a crucial part of the development of the brain and body (Darnerud and Thuvander, 1998 [2]; Hallgren and Darnerud, 1998) [3].

The release of these organic pollutants can be revealed by analyses of sewage sludge produced by municipal waste-water treatment plants. Therefore, the European community has given a directive (2000/60/CE) [4] for water to analyze four PBDEs (BDE-99, BDE-100, BDE-205, BDE-209) and is now working on an ISO norm ISO/CD 22032 to analyze eight PBDEs (BDE-47, BDE-99, BDE-100, BDE-153, BDE-154, BDE-183, BDE-205, BDE-209).

This analysis starts with an extraction of brominated diphenyl ethers (BDEs) from the dried sample of sediment or sewage sludge by a solvent (for example, hexane or other solvents suitable to get high extraction rates). The extract is cleaned, with silica, for example, if necessary. After concentration, the BDEs are separated by capillary gas chromatography (GC) and detected with a suitable system. A calibration over the total procedure using an internal standard (ISTD) mix is used to calculate the concentration in the sample.

When analyzing PBDE with GC, a number of problems arise: [5]

- Adsorption to glass surfaces
- Discrimination of high molecular weight compounds

- Degradation of the heavier congeners
- Irreproducible results
- Disappearing peaks

This application note gives analysts the necessary tools to attempt low-level detection of PBDE by gas chromatography/mass spectrometry (GC/MS).

Materials and Methods

Samples

All sewage sludge and sediment samples were provided by municipal waste-water treatment plants. Ten grams of sediment or 1 g of sewage sludge is liquid extracted. The extract is cleaned on silica and the clean extract is concentrated in 1-mL hexane prior to GC analysis.

Standards and ISTDs

The project for the European norm 22032 (2000/60/CE) is requesting analysis of four PBDE (BDE-99, BDE-100, BDE-205 and BDE-209) and recommends TetraBDE (BDE-77) as ISTD. (See Table 1.) These standards were purchased commercially and were of the highest grade available. A test mixture of pentaBDE (BDE-99, BDE-100), octaBDE (BDE-205), and decaBDE (BDE-209) was used for the evaluation in order to obtain a GC analysis with little or no discrimination. BDE-77 was used as ISTD. Standard solutions containing 0.01; 0.05; 0.1; 0.2; 0.25; 0.5 ng/μL of pentaBDE, 0.5; 1; 2; 3; 4; ng/μL of decaBDE and octaBDE, and 0.2 ng/μL of ISTD were prepared in hexane.

Table 1. Selected BDEs

Name	Formula	Abbreviation	Molar mass g/mol
3,3',4,4'-tetraBDE	C ₁₂ H ₆ Br ₄ O	BDE-77	481.715
2,2',4,4',5-pentaBDE	C ₁₂ H ₅ Br ₅ O	BDE-99	564.6911
2,2',4,4',6-pentaBDE	C ₁₂ H ₅ Br ₅ O	BDE-100	564.6911
2,3,3',4,4',5,5',6-octaBDE	C ₁₂ H ₂ Br ₈ O	BDE-205	801.3804
DecaBDE	C ₁₂ Br ₁₀ O	BDE-209	959.1714

GC Conditions

The selection of column and injection parameters is of great importance for the GC analysis of PBDE, especially for the high molecular weight congeners. See Table 2.

The temperature of the GC is of great importance since some congeners decompose at temperatures just above 300 °C. Thermal degradation is a function of temperature and time; thus, by choosing a column with as little retention for the BDE congeners as possible and shortening the column to the minimum length required for the separation, thermal degradation can be minimized. In addition, pulsed injection allows shorter injection time and also helps to minimize risk of thermal degradation.

A pulsed splitless injection and a DB-1 30 m, 0.32 mm, thin film, 0.1 µm, really minimizes the time each PDBE stays in both the injector and in the column and avoids degradation.

Table 2. Optimized Run Conditions

Column:	DB-1
Part number:	123-1031
Length:	30 m
Diameter:	0.32 mm
Film thickness:	0.1 µm
Carrier:	Helium at 58 cm/s Flow rate 2.5 mL/min
Injector:	2 µL Pulsed splitless at 250 °C
Oven:	60 °C for 2 minutes 60 °C–200 °C at 10 °C/min 200 °C for 2 minutes 200 °C–300 °C at 20 °C/min 300 °C for 25 minutes
Detector	MS
Agilent 5973 inert MSD	
SIM mode	Group 1 / 3 min / <i>m/z</i> 486; 484; 326 Group 2 / 20 min / <i>m/z</i> 406; 564; 566 Group 3 / 24 min / <i>m/z</i> 642; 644; 562 Group 4 / 28 min / <i>m/z</i> 799; 797
Quad temperature	150 °C
Source temperature	230 °C
Transfer line temperature	300 °C

Results and Discussion

The chromatograms (Figures 2 and 3) show very good peak shapes for each PBDE and a high response for the most critical decaBDE (BDE-209) (see Figure 4) using the optimized run conditions listed in Table 2.




Figure 2. Total Ion Chromatogram (TIC) of a standard mixture at 2–20 ng/μL
1–2: pentaBDE
3–9: octaBDE
10: decaBDE




Figure 3. Selected Extracted Ion Chromatograms (EICs) of a standard mixture at 0.5–5 ng/μL.




Figure 4. EIC of BDE-209 in a standard mixture at 5 ng/μL.

In order to have a precise quantitation, five point calibration curves from 0.01 to 0.25 ng/μL for pentaBDE and from 0.5 to 4 ng/μL of octa and decaBDE were achieved with ISTD BDE-77 at 0.2 ng/μL. (See Figure 5.) For all components, the R^2 values range from 0.996 to 1, meeting the AFNOR requirements for valid quantitation (See Table 3).

Table 3. Calibration Curve Summary Using Optimized Analysis Conditions with GC/MS

Compound	Calibration range (ng/μL)	Target ion m/z	Qualifier ion m/z	R^2 value
BDE-77	<i>ISTD-0.2</i>	486.0	326.0	ISTD
BDE-99	<i>0.01-0.25</i>	405.8	563.6	1
BDE-100	<i>0.01-0.25</i>	405.8	563.6	1
BDE-205	<i>0.5-4</i>	641.6	643.6	0.990
BDE-209	<i>0.5-4</i>	799.4	797.4	0.996




Figure 5. Calibration curve for decaBDE (BDE-209) by GC/MS.

Concerning the limit of detection (LOD), the lower level at 1 µg/kg (10 µg/kg for sewage sludge\) for pentaBDE and 50 µg/kg (500 µg/kg for sewage sludge) for octaBDE and decaBDE in sediment, which is 10 pg/µL of pentaBDE or 0.5 ng/µL of octa and decaBDE in solution, is easily achieved. This is the case even for decaBDE because a very good signal-to-noise ratio was achieved, as shown in Figure 6.




Figure 6. EIC of BDE-209 in a standard mixture at 0.5 ng/µL, which is the required LOD 50 µg/kg of sediment.

Real sewage sludge samples were analyzed using the run conditions listed in Table 2. Figure 7 shows one example. The EICs of the different PDBE show that only one pentaBDE and the decaBDE are present in this sample, and they were quantified in a quantitation report showed on Table 4.




Figure 7. Overlaid EICs for BDE-77, 99, and 209 from sewage sludge.

Table 4. Quantitation Report of Real Sewage Sludge

ISTDs	RT	QIon	Response	Conc units	Dev(min)
BDE 77	19.43	486	823207	0.20 ng/μL	0.02
Target compounds					Qvalue
BDE 100	20.14	406	22687	0.0072 ng/μL	11
BDE 99	20.48	406	107372	0.0405 ng/μL	87
BDE 205	23.91	642	17336	0.3417 ng/μL	57
BDE 209	28.31	799	64526	5.2530 ng/μL	90

Summary

By combining the highly inert thin film DB-1 with the Agilent 6890 gas chromatograph and the Agilent 5973 inert MSD, laboratories can achieve accurate quantitation of PBDE in sediments and sewage sludge.

References

1. P. Eriksson, E. Jakobsson, and A. Fredriksson, Developmental neurotoxicity of brominated flame retardants, polybrominated diphenyl ethers and tetrabromo-bis-phenol A. (1998) *Organohalogen Compounds*, **35**: 375-377.
2. S. Hallgren and P.O. Darnerud, Effects of polybrominated diphenyl ethers (PBDEs), polychlorinated biphenyls, (PCBs) and chlorinated paraffins (CPs) on thyroid hormone levels and enzyme activities in rats. (1998) *Organohalogen Compounds*, **35**: 391-394.
3. P.O. Darnerud and A. Thuvander, Studies on immunological effects of polybrominated diphenyl ether (PBDE) and polychlorinated biphenyl (PCB) exposure in rats and mice. (1998) *Organohalogen Compounds*, **35**: 415-418.
4. European framework directive on water policy N° (2000/60/CE)
5. E. Kuhn, J. Ellis, and S. Wilbur, GC Analysis of Polybrominated Flame Retardants, Agilent Technologies publication 5989-0094EN www.agilent.com/chem

Acknowledgements

Dominique Eisenblaetter (CAR, Illkirch) and Bruno Schnepf (CARSO, Lyon) are acknowledged for supporting the partnership with Agilent Technologies France. Jean-Paul Chauve (Agilent Technologies France) and Eberhardt Kuhn (Agilent Technologies USA) are acknowledged for their technical support.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
June 4, 2004
5989-1110EN



Agilent Technologies



Determination of Polybrominated Diphenyl Ethers in Polymeric Materials Using the 6890 GC/5973N inert MSD with Electron Impact Ionization

Application

Environmental, Component Testing

Authors

Chuanhong Tu
Agilent Technologies, PuDong
Shanghai CHINA

Harry F. Prest
Agilent Technologies, Inc.
Santa Clara, CA
USA

Abstract

Due to their ubiquitous appearance in the ecosphere, various polybrominated diphenyl ether formulations have been banned. A major application of PBDEs is to impart fire retardancy to plastics used in electronics and electrical applications. This application note details an approach to determining the PBDEs present in the technical formulations in polymers. The instrumental analysis uses GC/MS with selected-ion monitoring (SIM) to determine tri-BDEs through the decaBDE in 15 minutes. Full scan spectra are presented for the PBDEs with interpretation and to provide an explanation of the choices in SIM ions. To insure correct identification of the PBDE isomers and allow rapid and convenient implementation in the laboratory, Retention Time Locking is applied to an internal standard. A sample preparation scheme referenced in this document provides two flexible and simple approaches to processing polymeric materials for this instrumental technique. PentaBDE, OctaBDE and DecaBDE technical formulations are characterized under the method and results for a typical high-impact polystyrene sample are also presented.

Introduction

Polybrominated diphenyl ethers (PBDEs) are a major issue in discussions of persistent organic contaminants. The detection of PBDEs in essentially all compartments of the ecosystem, including human serum and breast milk, has resulted in a ban of the manufacture and use of certain PBDE formulations by the European Union (EU). Some companies have made it a policy not to allow these compounds in their components and have insisted their suppliers comply. Because the PBDEs are added at percent concentrations (as w/w), the usage of these formulations has been prodigious. Global consumption in 2001 was estimated at 7500, 3790, 56100 metric tons, for the PentaBDE, OctaBDE and DecaBDE technical formulations, respectively.

PBDE analysis even at these relatively high concentrations is challenging in several respects. The PBDEs are a complicated class of compounds and their utility in suppressing combustion also makes them relatively fragile and subject to degradation in GC analysis. This was demonstrated by using shorter GC columns to improve PBDE responses, the most significant improvement being for the deca-BDE (BDE 209) [1]. The loss in congener resolution is less important in this application because the technical mixtures most frequently applied in polymers predominantly consist of isomers extending from the tri-BDEs to the deca-BDE and far less than the 209 possible congeners. Distinguishing congeners on the basis of their electron impact (EI) mass spectrum may be possible since there appears to be some differences in their spectra, however the most reliable index remains retention time (RT). For this reason, compound



Agilent Technologies

Retention Time Locking (RTL) is used to simplify identification and reproduction of the method in the user's laboratory.

Another complication is in sample preparation. There are several methods for extracting PBDEs from polymers each with advantages and disadvantages [2]. Of the many methods, the two approaches applied in processing samples for this application note are relatively inexpensive, simple, universal in application and in their acceptance, and allow for high sample throughput with minimal polymeric interferences. They are polymer dissolution and soxhlet extraction.

Experimental

Polymer samples were obtained from Agilent customers in the electrical and electronic component industries. Specific details of the polymer dissolution and soxhlet extraction methods are presented elsewhere [3]. In summary, the methods extract PBDEs from the sample via solvent, a dilution is made into toluene and PCB 209 is added to follow the dilution factor. Prior to injection, PCB 207 is added as an internal (injection) standard. Standards were made taking into account the potential percent concentration range of the PBDEs in polymeric samples and dilution factors used in the method.

PBDE standards were acquired from Cambridge Isotope Laboratories (Andover, MA) and AccuStandard (New Haven, CT). PCBs 209 and 207 were acquired from AccuStandard (New Haven, CT). Solutions were made in toluene of Burdick & Jackson solvent (VWR Scientific, San Francisco, CA).

Instrumental Configuration and Conditions

The 6890 GC and 5793N-inert MSD (mass selective detector) system configuration and conditions are given in Table 1. The GC is operated under constant flow conditions developed by applying RTL to lock the PCB 209 internal standard RT at 9.350 minutes. The 5793N inert MSD was equipped with the new Performance Electronics upgrade and allowed a single SIM group containing 24 ions to be used. The SIM ions are listed in Table 1 and were acquired with a dwell of 10-ms. This single SIM group method can be used to develop a preliminary method that can be further refined into multiple SIM groups by applying the AUTOSIM utility if the user wishes [4]. This is recommended for 5793-MSDs using standard electronics and targeting only congeners known to predominate in the particular technical mixture.

Table 1. GC and MSD Configuration and Parameters

Injection parameters

Injection mode	Pulsed splitless		
Injection volume	1 μ L		
Injection port temperature	320 °C		
Pulse pressure and time	15.8 psi	1.80 min	
Purge flow and time	50.0 mL/min	2.00 min	
Gas saver flow and time	20.0 mL/min	3.00 min	

DB-5ms Column and oven parameters

GC column	DB-5ms (15 m $\times$ 0.25 mm id, 0.1 μ m film) (p/n: 122-5511)		
Flow and mode	1.8 mL/min	Constant flow	
RTL parameters	9.350 min	RTL compound PCB 209	
Detector and outlet pressure	MSD	Vacuum	
Oven temperature	90 °C	1.00 min	
program	20 °C/min	340 °C	2.00 min
Oven equilibrium time	1.0 min		
Total program time	15.5 min		
MSD transfer line temp	320 °C		

Mass spectrometer parameters

Tune parameters	Autotune		
Electron multiplier voltage	Autotune + 400V		
Solvent delay	6.5 min		
Quadrupole temperature	150 °C		
Inert source temperature	300 °C		

Mass spectrometer SIM ions for single group

405.8	246.0	123.0
485.7	325.9	162.9
563.6	403.8	201.9
643.5	483.7	241.9
721.5	561.6	320.8
799.4	641.5	360.7
719.4	461.7	399.7
463.7	497.7	499.7

*Optional addition of m/z 280.8

Miscellaneous parts

Septa	5182-0739	BTO septa (400 °C)
Liner	5181-3315	Deactivated 4-mm id double taper
GC column ferrule	5181-3323	250 μ m Vespel/Graphite
MSD interface ferrule	5062-3508	0.4-mm id preconditioned vespel/graphite

Results

Chromatography

After evaluating a series of columns the DB-5ms phase seems the best choice overall, which is consistent with the literature [1]. The literature shows that the shorter columns and thinner films are of benefit to improving the PBDE responses, especially deca-BDE (PBDE-209) [1] and this approach is applied here. The benefit appears in both response and also in shorter analysis times; elution of deca-BDE occurs in less than 15 minutes. The separation on the DB-5ms phase seems sufficient for characterizing PBDE additives in polymers since the desire is not so much the complete separation as it is the overall composition and contribution of the various isomers [5]. Nonetheless, the short analysis time makes RT reproducibility and accuracy more critical for correct assignments of the various PBDE isomers and this is greatly enhanced by applying RTL. A list of the Retention Time Locked elutions of the most prominent PBDEs is presented in Table 2. For reference, Figures 1, 2 and 3 present chromatograms of PentaBDE, OctaBDE, and DecaBDE technical mixtures with approximate elution windows of the various isomers.

Table 2. Prominent PBDE Congeners and their Locked RTs

Compound name	RTL RT (min)
PCB 207	8.69
PCB 209 (locking compound)	9.350
PBDE 17 (tri Br)	6.89
PBDE 28 (tri Br)	7.08
PBDE 71 (tetra Br)	7.97
PBDE 47 (tetra Br)	8.09
PBDE 66 (tetra Br)	8.25
PBDE 100 (penta Br)	8.82
PBDE 99 (penta Br)	9.06
PBDE 85 (penta Br)	9.43
PBDE 154 (hexa Br)	9.62
PBDE 153 (hexa Br)	9.93
PBDE 138 (hexa Br)	10.31
PBDE 183 (hepta Br)	10.73
? hepta PBDE	11.07
PBDE 190 (hepta Br)	11.23
PBDE 204 (octa)	11.62
PBDE 203 (octa)	11.78
? PBDE 196 (octa)	11.84
PBDE 205 (octa)	12.00
PBDE 208 (nona)	12.56
PBDE 207 (nona)	12.64
PBDE 209 (deca Br)	13.60

Note - tentative identification of PBDE 196 was based on reference [1]




Figure 1 Reconstructed ion chromatogram (RIC) for the GC/MS EI-SIM acquisition of a PentaBDE technical mixture (Cambridge Isotope Laboratories).




Figure 2 RIC for the GC/MS EI-SIM acquisition of a OctaBDE technical mixture (Cambridge Isotope Laboratories)




Figure 3 RIC for the GC/MS EI-SIM acquisition of a DecaBDE technical mixture (Cambridge Isotope Laboratories).

PBDE Spectral Interpretation

The EI ionization mass spectra of the PBDE congeners are rich in details and partially described in the literature [7]. Among the isomers the spectra are expected to be approximately identical in pattern and fragmentation pathway. Figure 4 presents a full scan spectrum of a hexabrominated-DE, PBDE-138, obtained at a source temperature of 300 °C. The spectrum shows the isotope cluster due to the molecular ion (643 m/z) and an intense cluster (484 m/z) consistent with the loss of Br₂. The mass assignment of the m/z 484 cluster is consistent with the result of $[M-Br_2]^+$, that is, $[C_{12}H_4OBr_4]^+$, and shows the tetrabrominated pattern (18 : 69 : 100 : 65 : 16). The next highest abundance isotope cluster appears around 242 m/z . Figure 4 shows this cluster and the cluster at m/z 484, $[M-Br_2]^+$. The isotope cluster patterns are similar, which suggests the same degree of

bromination, but the fragment mass assignments are half those of the 484 cluster and mass spacing is not 2 but 1 m/z unit. While it is possible this is due to overlapping fragments, the close correspondence in patterns lead the authors to propose that this isotope cluster is due to double-charged fragments; that is, $[M-Br_2]^{+2}$. Recently, this assignment was confirmed by high-resolution MS and the results will be published elsewhere [8]. This $[M-Br_2]^{+2}$ fragment is common among the PBDEs congeners and grows in relative abundance as the degree of bromination increases: approximately in 10% tetraBDEs; 15% in pentaBDEs; 20%–25% in hexaBDEs and heptaBDEs; 45% in octaBDEs; 60% in nonaBDEs; and > 80% in decaBDE. Figures 5, 6, 7, 8 and 9 show spectra for several PBDEs. We have also observed the same phenomena for the polybrominated biphenyls (PBBs). We also find the ratios vary within an isomeric series more than in PCBs.




Figure 4 Normalized EI mass spectrum of a hexabrominated-DE, PBDE-138, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 5 Sections of the normalized EI mass spectrum of the hexabrominated-DE, PBDE-138, for the $[M-Br_2]^+$ and proposed $[M-Br_2]^{+2}$ clusters.




Figure 6 Normalized EI mass spectrum of a pentabrominated-DE obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 7 Normalized EI mass spectrum of a heptabrominated-DE obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 8 Normalized EI mass spectrum of an octabrominated-DE, PDBE-203, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 9 Normalized EI mass spectrum of a nonabrominated-DE, PDBE-208, obtained in scan from 150–800 m/z at a source temperature of 300 °C.

In considering the EI spectrum of the decabromodiphenyl ether, PBDE-209, the same observations apply, Figure 10. Although the cluster of the molecular ion at 959 u, eludes the mass range limitation of the 5973N-MSD, the loss of Br₂ forms an intense isotope cluster at m/z 799, [M-Br₂]⁺ and the doubly charged fragment(s) for the [M-Br₂]⁺² at m/z 400 (399.6) as shown in Figure 11. Other data has shown that the intensity of the molecular ion cluster (959 u) is far less than that of the fragments at m/z 799 as is the trend for the PBDEs.




Figure 10 Normalized EI mass spectrum of the decabrominated-DE, PBDE-209, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 11 Normalized EI mass spectrum of the decabrominated-DE, PBDE-209, obtained in scan from 150–800 m/z at a source temperature of 300 °C.

Therefore these ions (that is, $[M-Br_2]^+$, $[M-Br_2]^{+2}$ and $[M]^+$ where available), and compound RTs, identify and allow determination of the deca-BDE and other PBDEs to the ability of the 15-m column to separate the isomers, which appears quite effective and sufficient for characterizing additives. The monitored ions are given in Table 3 with the ions for the internal standards used in this analysis. Obviously, the bromines provide other ions displaced in mass by two units (except for the doubly-charged ions) that offer other additional ions for quantitation or confirmation.

Using the ions listed in Table 3 to identify the PBDE isomers, the regions in the chromatograms presented in Figures 1, 2 and 3 were labeled with the isomer elution windows. These ions and their ratios were also used to characterize PBDEs not available in the standards but found to occur within the samples and technical mixtures (for example, PBDE 196).

Results for Polymeric Samples

Extracting PBDEs from polymers requires that the entrained PBDEs permeate the polymer into the extracting medium. Apparently “melting” the polymer closes the transport corridors in the polymer and impedes extraction. However, “swelling” the polymer with a proper solvent, greatly improves the kinetics of extraction. Beyond deciding the proper solvent, the optimal time of the extraction must be experimentally determined for each plastic based on its consistency and response to the solvent. For the polymer dissolution and soxhlet extraction methods used here, solvent contact

times or the number of soxhlet cycles for near complete extraction was determined by serial extraction. Other concerns are described in the sample preparation protocols [3].

Figure 12 shows the chromatogram for an extracted HIPS (high-impact polystyrene) polymer sample supplied by an Agilent customer and Table 4 shows the results for replicate extractions and analysis. Note the chromatogram and its major components closely resembles the chromatogram for the OctaBDE technical mixture (Figure 2) and indicates the specificity of the selected ions and most importantly, the lack of polymeric interferences. The reproducibility of the component compositions is a testament to the reproducibility of the total method. A good portion of the variance is introduced by the high dilution factors used in the method to bring the polymer extract concentrations with the scale of the PBDE standards and therefore discriminates against the lower abundance components producing a higher degree of variation and absolute detection. A series of 25 replicate injections of an extracted sample showed negligible degradation in response or chromatography. The robust performance is largely due to the high MSD ion source and quadrupole operating temperatures of 300 °C and 150 °C, respectively. These high temperatures mitigate the effect of co-extracted polymeric residues on the ion source optics to render robust performance. The high operating temperature of the quadrupole provides a very long lifetime without cleaning or maintenance even when analyzing very dirty matrices such as these.

Table 3. Quantitation and Confirmation Ions for the PB_nDEs (n>2)

PBDE bromination	$[M]^+$	$[M-Br_2]^+$	$[M-Br_2]^{+2}$	Confirmation ion
3	405.8	246.0	123.0	403.8
4	485.7	325.9	162.9	483.7
5	563.6	403.8	201.9	561.6
6	643.5	483.7	241.9	641.5
7	721.5	561.6	(280.8 **)	563.6/719.4
8	799.4	641.5	320.8	643.5
9	—	719.4	360.7	721.5
10	—	799.4	399.7	—
PCB 207	463.7	461.7	—	—
PCB 209	497.7	499.7	—	—

**The 280.8 and 281.8 m/z ions can be compromised by column bleed interferences so these were not used in acquisition although they provide a useful diagnostic for column degradation.




Figure 12 RIC of the GC/MS SIM acquisition of an extracted HIPS polymer sample.

Table 4. Extraction Results for Replicate Analysis of a Polymer Sample for PBDE Composition Using the Two Extraction and Sample Preparation Protocols [3]

Soxhlet polymer extraction protocol results						
Sums	Replicate 1 (%)	Replicate 2 (%)	Replicate 3 (%)	Replicate 4 (%)	Replicate 5 (%)	SD
HexaBDEs	9.1	9.5	8.9	8.7	9.1	0.3
HeptaBDEs	53.3	52.5	51.7	53.1	53.1	0.7
OctaBDEs	29.5	29.5	30.7	29.5	29.8	0.5
NonaBDEs	8.0	8.4	8.6	8.7	8.1	0.3

Polymer Dissolution Extraction Protocol Results*				
Sums	Replicate 1 (%)	Replicate 2 (%)	Replicate 3 (%)	SD
HexaBDEs	9.9	10.0	9.7	0.2
HeptaBDEs	55.3	56.2	55.9	0.5
OctaBDEs	34.8	33.8	34.4	0.5

SD standard deviation

No tri-BDEs, tetraBDEs, pentaBDEs, or decaBDE were detected.

*A difference in analyte lists used to quantitate the soxhlet extracts slightly skews the results, specifically the addition of the nona-BDE analytes. Removing this group, the results agree within 3%.

Remarks

Figure 13 presents two overlaid reconstructed ion chromatograms of the SIM acquisitions of two splits of a single PBDE standard. One of the splits was contained in a clear vial and was exposed to laboratory light for about a week and the other split was stored in amber vial and in a freezer as a reference. The most impressive feature is the dramatic loss of the decaBDE and the possible appearance of another intense nonaBDE (around 11.8 minutes). Note the nonaBDEs in the standard showed no degradation while the octaBDEs and heptaBDEs showed varying degrees of loss in concentration. A number of small peaks appear in the baseline that suggest, on the basis of their fragments, ion ratios, and proximity to existing PBDEs in the standard, the presence of other BDE isomers. Assigning any identification in SIM without a standard reference compound to confirm RT and fragment ratios, or a full scan acquisition, must be considered highly speculative. However, the data does indicate a degradation of the decaBDE and some other PBDEs, and suggests possible isomerization of the some PBDEs under the influence of typical laboratory fluorescent lights. Time and resources do not allow us to pursue this matter,

but we provide these observations since there are implications in sample handling and standard preparation and storage.

Conclusions

The 5973N inert MSD equipped with performance electronics allows a single SIM group to survey for PBDE isomers important to characterizing the technical formulations of the PBDEs. Using a single group has the advantages of allowing many formulations to be studied without regard to the particular elution of the congeners (which would require careful maintenance of SIM windows), simplified setup and very rapid analysis. Implementing RTL allows specific congeners to be characterized and quantitated with high confidence. The intense fragmentation of the PBDEs and their universal propensity to form $[M-Br_2]^+$ and $[M-Br_2]^{+2}$ ions provides a unique fingerprint for each degree of bromination. The 15-m column used here provides rapid analysis and sufficient class separation. The method is universally applicable regardless of the sample preparation scheme as demonstrated here by replicate polymer analysis by two techniques, soxhlet extraction and polymer dissolution.




Figure 13. PBDE standard unexposed (green) and exposed to laboratory light. Delta (Δ) indicates change in response as Exposed-Unexposed (with negative signs indicating loss in response and positive an increased response).

References:

1. J. Bjorklund, et al., "Influence of the injection technique and the column system on gas chromatographic determination of polybrominated diphenyl ethers", (2004) *Journal of Chromatography A*, **1041**(1-2): p. 201-210.
2. A. M. Altwaiq, M. Wolf, and R. van Eldik, "Extraction of brominated flame retardants from polymeric waste material using different solvents and supercritical carbon dioxide", (2003) *Analytica Chimica Acta*, **491**(1): p. 111-123.
3. H. Prest. and C. Tu, "Sample Preparation Protocols for Polybrominated Diphenyl Ethers in Polymeric Materials for GC-MS analysis", (2005), available to Agilent customers by request through their Agilent sales agents. www.agilent.com/chem
4. H. Prest and D.W. Peterson, "New approaches to the development of GC-MS selected ion monitoring acquisition and quantitation methods", (2001), Agilent Technologies, publication 5988-4188EN www.agilent.com/chem
5. P. Korytar, et al., "Retention-time database of 126 polybrominated diphenyl ether congeners and two Bromkal technical mixtures on seven capillary gas chromatographic columns", (2005) *Journal of Chromatography A*, **1065**(2): p. 239-249.
6. V. Giarrocco, B. Quimby, and M. Klee, "Retention Time Locking: Concepts and Applications", (1998), Agilent Technologies, publication 5966-2469EN www.agilent.com/chem
7. S. Huber, and K. Ballschmiter, "Characterisation of five technical mixtures of brominated flame retardants", (2001) *Fresenius Journal of Analytical Chemistry*, **371**(6): p. 882-890.
8. Q. Zhang, et al., Rapid Communications in Mass Spectrometry, in preparation.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
April 5, 2005
5989-2850EN



Agilent Technologies



Applying the 5975 inert MSD to the Higher Molecular Weight Polybrominated Diphenyl Ethers (PBDEs)

Application

Environmental, Component Testing

Author

Harry F. Prest
Agilent Technologies, Inc.
Santa Clara, CA
USA

This note presents the full scan spectra obtained for the PBDEs over the extended mass range of the 5975 inert MSD. The polymeric sample preparation and extraction protocols are cited elsewhere and supply two approaches to PBDE determinations [1].

Abstract

A previous application note presented results for analysis of the polybrominated diphenyl ethers (PBDEs) in polymers using the 5973N inert MSD [1]. Mass spectra were presented and interpreted for all of the important PBDEs. The new 5975 inert MSD provides many new features and improvements with expanded mass range to 1050 u being but one. This note presents the full spectra of the octa-, nona and decabrominated biphenyls ethers including ions that appear beyond the mass range of the previous 5973 MSD platform.

Introduction

PBDEs have become the “new PCBs” due to their widespread detection throughout the ecosystem. They have some structural and consequently mass spectral features in common with the polychlorinated biphenyls (PCBs) as well. The series of fragments formed by loss of chlorines ($M-nCl_2$) generates a number of intense ions useful in their determination. The PCBs also show relatively intense molecular ion clusters that assist in distinguishing the congeners. Similar attributes are expected and hoped for the PBDEs which show much more analytical difficulty than the PCBs.

Experimental

PBDE standards were acquired from Cambridge Isotope Laboratories (Andover, MA) and AccuStandard (New Haven, CT).

Instrumental Configuration and Conditions

The 6890 GC configuration and conditions are given in the previous application note [1]. The 5975 inert MSD system was operated in scan mode for acquisition of the PBDE spectra. The MSD scan operating parameters are cited in Table 1.

Table 1. 5975 inert MSD Configuration and Parameters

Mass spectrometer parameters	
Ionization mode	Electron impact
Ionization energy	70 eV
Tune parameters	Autotune
Electron multiplier voltage	Autotune + 400V
Scan mode	200–1000 u
Quadrupole temperature	150 °C
Inert source temperature	300 °C

Full conditions and parameters, as appropriate to the polymer analysis cited in reference 1, are available in the eMethod for this analysis (www.agilent.com/chem/emethods).



Agilent Technologies

Results

EI Spectra of the Higher Molecular Weight PBDEs

Figures 1, 2, and 3 present the full-scan spectra of an octa-, nona- and the decabromodiphenyl ether. Note that most intense ions in all cases are the $[M-Br_2]^+$ and the corresponding to $[M-Br_2]^{+2}$ ions. The relative abundance of the molecular ion clusters $[M]^+$ are under 30%. Figure 4 compares the

theoretical isotopic pattern to that experimentally obtained by the 5975 inert MSD. Agreement is good in both the abundance of the isotopes and the mass accuracy using the standard system Autotune. Mass accuracy agrees to within 0.2 m/z of the theoretical and experimental values. Table 2 presents the important ions for the PBDEs greater than the dibromodE. These ions are those most important to characterizing the technical mixtures used as additives to polymers.




Figure 1. Electron impact ionization spectrum of an octabromodiphenyl ether (PBDE-203) from 200 to 810 m/z .




Figure 2. Electron impact ionization spectrum of a nonabromodiphenyl ether (PBDE-208) from 200 to 890 m/z .




Figure 3. Electron impact ionization spectrum of the decabromodiphenyl ether (PBDE-209) from 200 to 1000 m/z .




Figure 4. Experimental spectrum of the decabromodiphenyl ether (PBDE-209) molecular ion cluster $[M]^+$ versus theory.

Table 2. Important Ions for the PB_nDEs ($n > 2$)

PBDE bromination	$[M]^+$	$[M-Br_2]^+$	$[M-Br_2]^{+2}$
3	405.8	246.0	123.0
4	485.7	325.9	162.9
5	563.6	403.8	201.9
6	643.5	483.7	241.9
7	721.5	561.6	(280.8 **)
8	801.4	641.5	320.8
9	879.3	719.4	359.7
10	959.2	799.3	399.7

**The 280.8 and 281.8 m/z ions can be compromised by column bleed interferences so these have not been used in acquisition although they provide a useful diagnostic for column degradation.

The user should note the ion source and quadrupole temperature settings in Table 1. Figure 5 presents SIM acquisitions of several higher molecular weight PBDEs at source temperatures of 300 °C and 230 °C. Notice the signal height roughly doubles on average for the PBDEs at the higher ion source temperature. The insert in the figure shows the improvement in the peak shape for the hexabrominated diphenyl ether. This peak sharpening accounts for the increase in signal height. Since these compounds elute at higher temperatures

among other high boiling components that belong to the matrix, heating the quadrupole is important for robust and low maintenance operation in samples.




Figure 5. Overlaid RIC SIM acquisitions of five PBDEs at ion source temperatures of 230 °C and 300 °C. Insert is expanded view of hexa-BDE overlays near baseline.

Conclusions

The new 5975 inert MSD has an expanded set of features including mass range. High mass accuracy under standard autotuning is obtained even at the high masses typical of the brominated diphenyl ethers. As users survey higher mass compounds, the heated quadrupole and high temperature capabilities of the 5975 inert MSD will become even more important to rugged and robust analyses in complicated samples.

More details on the other relevant instrumental parameters are available in the eMethod (www.agilent.com/chem/emethods).

Reference

1. C. Tu, and H. Prest, Determination of polybrominated diphenyl ethers in polymeric materials using the 6890 GC/5973N Inert MSD

with electron impact ionization. Agilent Technologies, publication 5989-2850EN, www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2005

Printed in the USA
June 13, 2005
5989-3142EN



Agilent Technologies

Polybrominated Diphenyl Ether (PBDE) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column



Application

Environmental

Authors

Ken Lynam and Doris Smith
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Trace and ultra trace-level polybrominated diphenyl ether (PBDE) analyses are important tools for understanding food supply and environmental quality worldwide. In this application, trace-level PBDE analysis is demonstrated using electron impact single quadrupole scanning mass spectrometry. For these challenging separations, knowing that each GC column has been thoroughly tested for column inertness gives the analyst higher confidence in the accuracy of the results.

Agilent Technologies Inc. has implemented new testing procedures to more effectively evaluate GC column inertness performance. This new testing procedure employs deliberately aggressive probes to thoroughly investigate column inertness and quality. These extremely active probes, including 1-propionic acid, 4-picoline, and trimethyl phosphate, are used to verify each column's inertness performance.


Introduction

Polybrominated diphenyl ethers (PBDEs) are both persistent and increasingly common in the environment. These chemicals are typically used as flame retardants in textiles and electronic products such as televisions and computer equipment. There are

209 possible PBDE congeners that vary in the degree of bromination from mono to fully brominated decabromodiphenyl ether. Each of the individual congeners is assigned both an IUPAC name and bromodiphenyl ether (BDE) number, by convention. For example, fully brominated decabromodiphenyl ether is assigned the number BDE-209.

PBDEs as a class of molecules tend to undergo degradation on exposure to heat and light. BDE-209's long retention and susceptibility to thermal breakdown make it a particularly challenging analyte.

BDE-209 Structure



Unfortunately, these chemicals continue to find their way into food supplies and common house dust. [1–5] Similarities between PBDEs and polychlorinated biphenyl (PCBs) compounds include their tendency to persist in the environment and to bioaccumulate in adipose tissues.

The chief routes of human exposure to PBDEs appear to be ingestion of contaminated foods and inhalation of contaminated house dust. Measurable levels of PBDEs have been found in fish, meats,



Agilent Technologies

dairy products, eggs, and vegetables. Higher levels of PBDEs are found more often in fish than in other food sources. House dust studies in the U.S., Belgium, and Singapore have all shown appreciable levels of PBDEs. The need for reliable, sensitive, and robust analytical methods for the analysis of PBDEs is of global concern.

Long-term human toxicities for PBDEs are not well understood, even though a number of studies have found appreciable levels in breast milk and human adipose tissue. These studies suggest a link between long-term exposure of the mother to specific BDEs and neurological effects in the growing fetus. Human health concerns led to a ban on the use of penta-BDE and octa-BDE within the European Union in 2004.

This application highlights the value of using a 15-m Agilent J&W DB-5ms Ultra Inert capillary GC column for challenging PBDE analysis. Agilent Technologies Inc. has implemented new testing procedures to more effectively evaluate GC column inertness performance. This new testing procedure employs deliberately aggressive probes to thoroughly investigate column inertness and quality. These extremely active probes, including 1-propionic acid, 4-picoline, and trimethyl phosphate, are

used to verify each column's inertness performance. Capillary GC column activity as a potential source of result uncertainty has been all but eliminated with the Ultra Inert series of columns.

Experimental

An Agilent 6890N GC/5975B MSD equipped with a 7683B autosampler was used for this series of experiments. Table 1 lists the chromatographic conditions used for these analyses. Table 2 lists flow-path consumable supplies used in these experiments.

Sample Preparation

A seven-level eight-component BDE calibration curve set was purchased from AccuStandard (New Haven, CT). These solutions were transferred directly to amber glass autosampler vials and used as supplied. Concentration ranges were 0.5 to 250 ng/mL for BDEs -47, -100, -99, -154, -153, -183, and -205. BDE-209 concentration ranged from 2.5 to 1,000 ng/mL. The isooctane used was Burdick and Jackson Ultra Resi Grade purchased through VWR International (West Chester, PA, USA). Isooctane was used as a reagent blank and syringe wash solvent.

Table 1. Chromatographic Conditions

GC	Agilent 6890N/5973B MSD					
Sampler	Agilent 7683B, 5.0-μL syringe (Agilent p/n 5188-5246), 1.0-μL splitless injection, 5 ng each component on column					
Carrier	Helium 72 cm/s, constant flow					
Inlet	Pulsed splitless; 325 °C, 20 psi until 1.5 min, purge flow 50 mL/min at 2.0 min					
Inlet liner	Deactivated dual taper direct connect (Agilent p/n G1544-80700)					
Column	Agilent J&W DB-5ms Ultra Inert 15 m × 0.25 mm × 0.25 μm (Agilent p/n 122-5512UI)					
Oven	150 to 325 °C (17 °C/min), hold 5 min					
Detection	MSD source at 300 °C, quadrupole at 150 °C, transfer line at 300 °C, scan range 200–1000 amu					
SIM program						
	Time (min)	Group	PBDE bromination	[M]⁺	SIM ions [M–Br₂]⁺ [M–Br₂]⁺²	Confirmation ion
	3.00	1	3	405.8	246	247.9
			4	485.7	325.8	162.9
	5.75	2	5	536.6	403.8	565.7
			6	643.6	483.7	241.8
	8.00	3	7	721.5	561.6	563.6
	9.25	4	8	801.5	641.5	320.8
	11.50	5	10	959.3	799.4	399.7
						797

Table 2. Flow Path Supplies

Vials	Amber glass vials (Agilent p/n 5182-0716)
Vial caps	Blue screw cap (Agilent p/n 5282-0723)
Vial inserts	100 μ L glass/polymer feet (Agilent p/n 5181-1270)
Syringe	5 μ L (Agilent p/n 5181-1273)
Septum	Advanced Green (Agilent p/n 5183-4759)
Inlet liners	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Ferrules	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323)
20x magnifier	20x magnifier loupe (Agilent p/n 430-1020)

Results and Discussion

Baseline Inertness Profile for Ultra Inert Columns

The basic approach for inertness verification for the Agilent J&W Ultra Inert series of capillary GC columns is testing with highly active probes at low concentration and low temperature. [6] This is a new rigorous approach that establishes consistent baseline inertness profiles for each column in the Agilent J&W Ultra Inert GC column series. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species that tend to adsorb onto the column's active sites, particularly at trace levels, like the BDEs in this application example. A detailed

description of the test mix and additional application examples are available in references 7 through 9.

PBDE Analyses

PBDE-209 is a particularly challenging analyte due to its long retention and tendency to degrade with high-temperature exposure. High-temperature thermal stability is an issue for this class of compounds, but is more pronounced for BDE-209, as it is highly brominated and well retained. One key to successful BDE analysis is to limit the time that these compounds are exposed to high temperatures. A 15-m long column, as opposed to a typical 30-m long column was used in this case to limit residence time for BDE-209. [10,11] Fortunately, the BDEs resolve well, with symmetrical peak shapes, when using Agilent J&W DB-5ms phase, enabling successful separation on the shorter column. Figure 1 shows a total ion chromatogram of the eight BDEs investigated in this study.

In this application a seven-level eight-component BDE calibration curve set was evaluated over the concentration range of 0.5 to 250 ng/mL for BDEs -47, -100, -99, -154, -153, -183, and -205 and the range of 2.5 to 1,000 ng/mL BDE 209 on an Agilent J&W Ultra Inert DB-5ms 15 m $\times$ 0.25 mm $\times$ 0.25 μ m (p/n 122-5512UI) column. Sensitivity was excellent, even for the more challenging BDE-209 with a 0.025 ng on-column loading, yielding a 3.28 signal-to-noise level. The exploded view of the BDE-209 peak in Figure 2 illustrates the sensitivity observed for a 0.025-ng on-column loading of BDE-209.




Figure 1. Total ion chromatogram (SIM mode) of a 0.005-ng (BDEs -47, -100, -99, -154, -153, -183, -205, and -209) and 0.025-ng (BDE-209) on-column loading on an Agilent J&W DB-5ms Ultra Inert 15 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 122-5512UI).




Figure 2. Enlarged section of the total ion chromatogram (SIM mode) of a 0.025-ng BDE-209 on-column loading. The large peak in the figure is BDE-209, a particularly challenging BDE due to its long retention and thermal instability.

Linearity was excellent across the range studied, giving R^2 values of 0.997 or greater in all cases. Figure 3 indicates the correlation coefficients for each of the individual analytes and shows an example linear regression plot for BDE-209.




Figure 3. Correlation coefficients for the eight components over the 0.5 ng/mL to 1,000 ng/mL concentration range (BDE-209 2.5 to 1,000 ng/mL) used in this study. An example linear regression plot of particularly challenging BDE-209 is also shown.

Conclusions

This application successfully demonstrates the use of a 15-m Agilent J&W DB-5ms Ultra Inert capillary GC column for trace-level BDEs in a 15-minute analysis. Linearity was excellent for all eight BDEs studied, yielding 0.997 or greater R^2 values down to a 0.005 ng (0.025 ng for BDE-209) on-column loading of each component. One of the reasons for the excellent linearity and high R^2 values is the highly inert surface of the column. The lack of chemically active sites makes these columns an excellent choice for trace-level applications.

The Agilent 6890/5975B GC/MSD (SIM mode) equipped with an inert electron impact source had excellent sensitivity with even the most challenging BDE in this set, PBD-209. The signal-to-noise ratio for a 0.025-ng on-column loading of BDE-209 was greater than three to one with this system. This result shows clearly the power of using an Agilent J&W DB-5ms Ultra Inert column for trace-level BDE analysis. Lower limits of quantification are expected when using one of Agilent's latest GC/MS offerings, such as the 7890/5975C GC/MSD Triple-Axis Detector coupled with an Agilent J&W DB-5ms Ultra Inert GC capillary column.

References

1. Nerissa Wu, Thomas Herrmann, Olaf Paepke, Joel Tickner, Robert Hale, Ellen Harvey, Mark La Guardia, Michael D. McClean, and Thomas Webster, "Human Exposure to PBDEs: Associations of PBDE Body Burdens with Food Consumption and House Dust," *Environmental Science & Technology*, Volume 41, Number 5, 2007, pages 1584–1589
2. Stefan Voorspoels, Adrian Covaci, Hugo Neels, and Paul Schepens, "Dietary PBDE Intake: A Market-Basket Study in Belgium," *Environmental International*, Volume 33, Issue 1, January 2007, pages 93–97
3. Jing Tan, Si Min Cheng, Annamalai Loganath, Yap Seng Chong, and Jeffery Philip Obbard, "Polybrominated Diphenyl Ethers in House Dust in Singapore," *Chemosphere*, Volume 66, Issue 6, January 2007, pages 985–992
4. Souichi Ohta, Diasule Ishizuka, Hajime Nishinura, Teruyuki Nakoa, Osamu Azoasa, Yoshiko Shimaduzu, Fumie Ochiai, Takafumi Kida, Masatoshi Nishi, and Hideaki Miyata, "Comparison of Polybrominated Diphenyl Ethers in Fish, Vegetables, and Meats and Levels in Human Milk of Nursing Women in Japan," *Chemosphere*, Volume 46, Issue 5, February 2002, pages 689–696
5. Thomas A. McDonald, "Polybrominated Diphenylether Levels Among United States Residents: Daily Intake and Risk of Harm to the Developing Brain and Reproductive Organs," *Integrated Environmental Assessment and Management*, Volume 1, Number 4, 2005, pages 343–354
6. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenyltrimethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
7. "Agilent J&W Ultra Inert GC Columns: A New Tool to Battle Challenging Active Analytes," Agilent Technologies publication 5989-8665EN, June 2, 2008
8. Kenneth Lynam, "Semivolatiles Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column," Agilent Technologies publication 5989-8616EN, May 19, 2008
9. Kenneth Lynam and Doris Smith, "Polycyclic Aromatic Hydrocarbon (PAH) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9181EN, July 24, 2008
10. Jonas Björklund, Petter Tollbäck, Christian Hiärne, Eva Dyremark, and Conny Östman, "Influence of the Injection Technique and the Column System on Gas Chromatographic Determination of Polybrominated Diphenyl Ethers," *Journal of Chromatography A*, 1041 (2004) 201–210
11. Chuanhong Tu and Harry Prest, "Determination of Polybrominated Diphenyl Ethers in Polymeric Materials Using the 6890 GC/5793N Inert MSD with Electron Impact Ionization," Agilent Technologies publication 5989-2850EN, April 5, 2005

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
August 27, 2008
5989-9571EN



Agilent Technologies




Emerging Contaminants

Other Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)

Analyzing Compounds of Environmental Interest Using an LC/Q-TOF

Part 3: Imidacloprid and Manool



Application

Environmental

Authors

Jim Lau, Chin-Kai Meng, and Jennifer Gushue
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

L. Mark Hewitt and Suzanne Batchelor
Aquatic Ecosystem Protection Research Division
Water Science and Technology Directorate
Environment Canada
867 Lakeshore Road
Burlington, ON, L7R 4A6
Canada

Abstract

Effluent discharges from pulp mill, sewage, or pesticide run-off are released into aquatic environments as complex mixtures. This study uses two types of discharge compounds (an insecticide and a pulp mill condensate) to illustrate the LC/Q-TOF sensitivity, linear range, quantitative, and qualitative analysis functionalities.

Introduction

Environment Canada is tasked with risk assessment and the evaluation of environmental impact of a variety of compounds [1, 2]. Effluent discharges from pulp mill, sewage, or pesticide run-off are released into aquatic environments as complex mixtures. Solid-phase extraction (SPE) or gel permeation chromatography (GPC) and GC/MS are

typically used to characterize substances from the discharge. LC/MS has been used to identify difficult-to-analyze polar compounds. However, the potential for LC/MS to identify unknown polar compounds has yet to be fully realized.

This study uses two types of discharge compounds to illustrate the LC/Q-TOF sensitivity, linear range, quantitative, and qualitative analysis functionalities. Imidacloprid (an insecticide) is tricky to analyze by GC/MS. It has been used in Atlantic Canada (run-off from potato fields) and there appear to be some nontargeted toxicological effects by this insecticide. Accurate mass and quantitation capability from a Q-TOF are critical for the routine analysis of target compounds.

The other sample is a pulp mill condensate. Pulp mills are the largest users of fresh water in Canada. Bleached kraft pulp and paper mill final effluents are known sources of compounds that affect reproductive endocrine homeostasis in fish [3, 4]. Environment Canada is working closely with a pulp mill that has developed a reverse osmosis process to help meet its effluent regulatory requirements for toxicity. Manool, a terpenoid present in trees, is one of the compounds removed by reverse osmosis and is related to compounds suspected of causing the reproductive problems in fish. An analysis is needed to confirm its presence in the condensates treated by reverse osmosis. A Q-TOF is capable of screening and identifying impurities and degradation products.



Agilent Technologies

Experimental

Samples

Figures 1 and 2 show the two compounds used in this study. Calibration solutions (10, 20, 50, 100, and 200 ppb) of imidacloprid were made from a 10.11 ppm stock solution in methanol. An additional sample was a blind with an undisclosed concentration of imidacloprid to evaluate the quantitation ability of the Q-TOF.

Samples of manool included a standard solution in methanol and a pulp extract treated with reverse osmosis process.




Figure 1. Imidacloprid.




Figure 2. Manool.

Instrument Parameters

All sample analyses were performed on an Agilent 1200 SL Rapid Resolution LC coupled to an Agilent 6520 Q-TOF.

All sample analyses were performed under Q-TOF autotune conditions. Mass accuracy, sensitivity, and resolution for all samples were measured without any changes to 6520 Q-TOF instrument parameters, except ion source conditions appropriate for the spray chamber type, LC flow, and sample thermal stability.

Mobile A	5 mM NH ₄ OAc, pH 4
Mobile B	MeOH
LC column	ZORBAX XDB 2.1 × 50 mm, C-18, 3.5-μm particle size
Flow rate	0.5 mL/min
Injection volume	5 μL
MS	Scanned at 2 scans/sec, 50 to 1,100 <i>m/z</i>
Positive reference ions	<i>m/z</i> 121, 922
AutoMS/MS	2 scans/sec MS and 2 scans/sec MS/MS
Q-TOF parameters	Set by autotune
Drying gas	12 L/min N ₂
Drying gas temperature	300 °C (imidacloprid), 150 °C (manool)
Nebulizer pressure	50 psi
ESI (+)	3 KV
Fragmentor	120 V

Results and Discussion

Imidacloprid

Figure 3 is a “Batch-at-a-Glance” screen from the MassHunter software. All the samples analyzed are listed on the top half of the screen. The calibration curve and the corresponding quantitation ion for each sample are displayed on the bottom half of the screen. All calibration standards (10, 20, 50, 100, and 200 ppb) and samples were analyzed in triplicate during the batch to check precision and accuracy.




Figure 3. "Batch-at-a-Glance" screen from the Mass Hunter software showing the quantitation and calibration results of imidacloprid.

The R^2 for the calibration curve was 0.9984 and the accuracy for each standard was between 94 and 113%. The quantitation results (triplicate) of a sample with unknown concentration of imidacloprid were 305, 287, and 296 pg/ μ L. The results were very close to the actual amount of 303.3 pg/ μ L. The largest difference from the actual was less than 6% (287 versus 303.3). Table 1 shows the precision results for each calibration standard (three injections each). This demonstrates the good precision and accuracy of the LC/Q-TOF system.

Table 1. Instrument Precision for Each Calibration Standard and the Unknown Sample (three injections for each level).

Level	%RSD
10	5.5
20	1.3
50	2.0
100	0.7
200	3.2
(303.3)	3.1

Table 2 shows that the mass accuracy for the 10-ppb imidacloprid standard was 1.76 ppm and 1.03 ppm for the 200-ppb standard. This illustrates that there is no trade-off between mass accuracy and dynamic range under the same autotune settings.

Manool

A standard solution of manool in methanol was analyzed by LC/Q-TOF. Multiple peaks were observed as shown in Figure 4. Several peaks are manool-related impurities (diterpenes). It is interesting to note that MH^+ of manool was not observed in the Q-TOF spectrum (Figure 5). The most significant ion was $MH^+ - H_2O$. Other ions included $MNH_4^+ - H_2O$, MNH_4^+ , and MNa^+ . The thermal neutral loss ions were confirmed by MS/MS analyses. Figures 6 and 7 show the MS1 and MS/MS spectra of ion m/z 308 and 290, respectively. The MS/MS spectra of both ions are very similar, suggesting similar precursor ions that differ by a loss of H_2O (m/z 18).

Table 2. Mass Accuracy of Measuring Different Concentrations of Imidacloprid ($C_9H_{10}ClN_5O_2$)

	Exact mass	Calculated MH^+	Measured MH^+	Accuracy
10 ppb	255.052299	256.05958	256.06003	1.76 ppm
200 ppb	255.052299	256.05958	256.05984	1.03 ppm

A pulp mill condensate extract was also analyzed by LC/Q-TOF. Figure 8 is the overlay of the TIC and the largest 15 compounds (within m/z 200 to 600) found by molecular feature extractor. The major compounds were identified as:

- $C_{20}H_{30}O_4$ (dihexyl phthalate)
- $C_{20}H_{34}O$ (Manool)
- $C_{22}H_{34}O_4$ (diheptyl phthalate)
- $C_{24}H_{38}O_4$ (dioctyl phthalate)

There were also unknowns with molecular formulae $C_{20}H_{30}O$, $C_{20}H_{30}O_3$, and $C_{20}H_{34}O_2$ that are C_{20} suspected diterpene analogues of manool. These data show that the reverse osmosis system removes these natural products from the condensates.




Figure 4. Characterization of manool and impurities.




Figure 5. Characteristic ions of manool. This spectrum shows all of the different possibilities (for example, loss of water, adducts).




Figure 6. MS/MS of pulp sample confirming origin of thermal neutral loss ions in MS spectrum for m/z 308 (manool + NH_4)⁺.




Figure 7. MS/MS of pulp sample confirming origin of thermal neutral loss ions in MS spectrum for m/z 290 (manool - H_2O + NH_4)⁺.




Figure 8. Molecular feature extractor extraction of the 15 largest m/z 200 to 600 compounds in a pulp extract.

Conclusions

Excellent mass accuracy (< 2 ppm), instrument precision (%RSD < 6%), and quantitation results (quant accuracy < 6%) were obtained from the imidacloprid analysis.

Many manool-related compounds (terpenes) were identified by Q-TOF using formula search or molecular feature extractor followed by exact mass database search. The lower sprayer temperature and adding NH_4OAc in mobile phase were critical to get molecular ions and MS/MS ions.

References

1. Jim Lau, Chin-Kai Meng, Jennifer Gushue, Mehran Alaei, and Vimal Balakrishnan, "Analyzing Compounds of Environmental Interest Using an LC/Q-TOF – Part 1: Dyes and Pigments," Agilent Technologies publication 5989-9336EN, August 2008.
2. Jim Lau, Chin-Kai Meng, Jennifer Gushue, Robert J. Letcher, and Shaogang Chu, "Analyzing Compounds of Environmental Interest Using an LC/Q-TOF – Part 2: Fluorotelomer Unsaturated Acids," Agilent Technologies publication 5989-9132EN, August 2008.
3. L. Mark Hewitt et al., "Isolation of Compounds from Bleached Kraft Mill Recovery Condensates Associated with Reduced Levels of Testosterone in Mummichog (*Fundulus heteroclitus*)," *Environmental Toxicology and Chemistry*, Vol. 21, No. 7, pp. 1359–1367, 2002.
4. L. Mark Hewitt et al., "Altered Reproduction in Fish Exposed to Pulp and Paper Mill Effluents: Roles of Individual Compounds and Mill Operating Conditions," *Environmental Toxicology and Chemistry*, Vol. 27, No. 3, pp. 682–697, 2008.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008


Printed in the USA
August 11, 2008
5989-9129EN



Agilent Technologies

Analyzing Compounds of Environmental Interest Using an LC/Q-TOF

Part 1: Dyes and Pigments



Application

Environmental

Authors

Jim Lau, Chin-Kai Meng, and Jennifer Gushue
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Vimal Balakrishnan and Mehran Alaee
Environment Canada
Aquatic Ecosystem Protection Research Division
867 Lakeshore Road
Burlington, ON, L7R 4A6
Canada

Abstract

Dyes/pigments are produced worldwide and it is estimated that 10,000 tons are produced each year. About 10 percent of this is released into the environment in some form (such as the original compounds and degradants). Dyes and pigments have been identified as priority substances on the Chemical Management List by Environment Canada. There are many dyes/pigments in existence in the environment. An LC/Q-TOF is best suited to screen and identify many compounds in a single analysis.

Good mass accuracy (< 3 ppm) and MS/MS on an LC/Q-TOF provide powerful capability and high confidence to confirm ion identity and structure, useful for QA or unknown confirmation.

Introduction

In the past, environmental applications were carried out with GC, GC/MS, and other types of instruments. LC/MS did not have the sensitivity nor the robustness required for this field. However, in recent years, LC/MS technology has improved significantly and is now routinely used for environmental applications to monitor a list of hazardous compounds, for example, using LC/QQQ for screening and quantification of target compounds.

With the advent of new LC/MS techniques and improved performance, more compounds are being identified (new and emerging compounds). The compounds that are of interest for environmental analysis can be characterized by three categories:

1. Known knowns: the targets are known (for example, QQQ targeted analysis)
2. Known unknowns: it is known that compounds of interest are in a sample, but it is not clear what the compounds are (for example, metabolites, degradation products, or characteristic patterns/losses)
3. Unknown unknowns: it is not known what the compounds are and it is not known if they are present

A QQQ can be used to screen for category 1. However, a Q-TOF will be required for categories 2 and 3, where the compound must be identified. The routine accurate mass measurement allows a Q-TOF to find compounds via exact mass database search. The compounds found can be further confirmed by MS/MS on the Q-TOF.



Agilent Technologies

Environment Canada is tasked with risk assessment and the evaluation of environmental impact of a variety of compounds [1, 2]. Dyes and pigments have been identified as priority substances on the Chemical Management List. Dyes/pigments are produced worldwide and it is estimated that 10,000 tons are produced each year. About 10 percent of this is released into the environment in some form (such as the original compounds and degradants). There are many dyes/pigments in existence in the environment; however, there is a limited number of standards available for analytical work. Standards can be produced, but the compound of interest must first be identified and characterized.

This study is to demonstrate the mass accuracy and Q-TOF's capability to generate useful formulas from accurate masses. In addition, MS/MS combined with accurate mass can be used to confirm ion identity and structure.

Experimental

Samples

The two classes of dyes/pigments studied for the application were azo dyes and anthracenediones.

The compounds that were evaluated were: Acid Blue 80, Acid Blue 129, Sudan Green 3, Toluidine Red, and Sudan III. These are the primary targets to be characterized; however, more sample categories will be added later for evaluation. The immediate concern is screening, which requires high mass accuracy for confirmation; the secondary concern is degradation products.

Instrument Parameters

All sample analyses were performed on an Agilent 1200 SL Rapid Resolution LC coupled to an Agilent 6520 Q-TOF.

All sample analyses were performed under Q-TOF autotune conditions. Mass accuracy, sensitivity, and resolution for all samples were measured without any changes to 6520 Q-TOF instrument parameters, except ion source conditions appropriate for the spray chamber type, LC flow, and sample thermal stability.

Mobile A	5 mM NH ₄ OAc, pH 4
Mobile B	MeOH
LC column	ZORBAX XDB 2.1 x 50 mm, C-18, 3.5 µm particle size
Flow rate	0.5 mL/min
MS	Scanned at 2 scans/sec, 50–1100 <i>m/z</i>
Positive ref. ions	<i>m/z</i> 121, 922
Negative ref. ions	<i>m/z</i> 113, 1034
AutoMS/MS	2 scans/sec MS and 2 scans/ sec MS/MS
Q-TOF parameters	Set by autotune
Drying gas	13 L/min N ₂ at 300 °C
Nebulizer pressure	50 psi
ESI (+)	3 KV
Fragmentor	140 V

Results and Discussion

One of the many ways to find compounds in a Q-TOF data file is by entering compound formulas to search. The formulas can be entered individually or as a group in a database in comma-separated value (CSV) format (see Figure 1). The database entry can include compound name, formula, and exact mass. Compound retention time is optional, but is very useful for getting results you can have confidence in. Figure 2 shows the spectra of the five matches using a mass tolerance of ± 5 ppm. The protonated ion is automatically labeled with the corresponding formula. Table 1 shows the mass accuracy (found by formula) of all five target compounds used in this study. All MH⁺ and MNa⁺ ions are within 3 ppm accuracy.




Figure 1. Find compounds in a Q-TOF data file by searching a manually entered formula or a formula database.




Figure 2. The five dye compounds found by formula database search.

Table 1. The Mass Accuracy of the Five Compounds Found by Formula Match

	Formula	Exact Mass	Conc. (in MeOH)	MH ⁺	MNa ⁺
Acid Blue 80	C ₃₂ H ₃₀ N ₂ O ₈ S ₂	634.144350	10 mg/L	0.33 ppm	0.40 ppm
Acid Blue 129	C ₂₃ H ₂₀ N ₂ O ₅ S	436.109287	10 mg/L	-1.13 ppm	-0.73 ppm
Sudan Green 3	C ₂₈ H ₂₂ N ₂ O ₂	418.168119	10 mg/L	-1.65 ppm	-0.97 ppm
Toluidine Red	C ₁₇ H ₁₃ N ₃ O ₃	307.095687	10 mg/L	-2.39 ppm	-1.69 ppm
Sudan III	C ₂₂ H ₁₆ N ₄ O	352.132405	10 mg/L	-2.89 ppm	-1.28 ppm

Another way to find compounds in a data file is by using Molecular Feature Extractor (MFE). This software program looks at ion characteristics and pulls out compounds from the total ion chromatogram (TIC). Figure 3 is an overlay of TIC and the 18 compounds (signal > 100 counts) found by MFE. To confirm the identity of each found compound, all compounds are searched against an exact mass database. Figure 4 shows the database search results where five out of 18 compounds had a match. Figure 5 is a screen capture of the Mass Hunter Software showing the five compounds identified from the exact mass database search. Two of the five compounds (both identified as Sudan III) at different retention times showed very similar

spectra. By clicking the hot link built into the Mass Hunter software, a compound formula can be searched against several online databases for further confirmation. Figure 6 is the online ChemID database search results of Sudan III that showed two positional isomers that would likely give similar MS/MS information and four isomers that differ by more than position and would give dissimilar MS/MS information. Figure 7 shows the spectra from data-dependent MS/MS (auto MS/MS) that give automatic generation of MS/MS product ion formulas and loss formulas correlated with precursor ion formulas. The results show identical fragmentation of the two peaks, confirming that the two compounds were isomers of Sudan III.




Figure 3. Overlay of total ion chromatogram (TIC) and Molecular Feature Extractor (MFE) chromatograms of dye mixture. Eighteen compounds were found using the criterion of signal > 100 counts.

Name	RT	Mass	DB Formula	DB Diff (ppm)	Height
Cpd 1: Acid Blue 129	2.816	436.10981	C ₂₃ H ₂₀ N ₂ O ₅ S	-1.19	175661
Compound 2	3.72	307.25877			178040
Cpd 3: Toluidine Red	3.722	307.0967	C ₁₇ H ₁₃ N ₃ O ₃	-3.27	3385650
Compound 4	3.733	329.07803			96154
Cpd 5: Sudan III	3.775	352.13362	C ₂₂ H ₁₆ N ₄ O	-3.44	739956
Compound 6	4.299	232.1104			204562
Compound 7	4.3	334.2155			2067458
Compound 8	4.3	148.01592			191203
Compound 9	4.301	392.26843			364637
Compound 10	4.622	329.10603			141919
Compound 11	4.641	420.29968			210481
Compound 12	4.642	362.24654			471542
Compound 13	4.83	390.27811			156716
Cpd 14: Sudan III	4.84	352.13377	C ₂₂ H ₁₆ N ₄ O	-3.86	2430832
Compound 15	4.893	440.2012			281429
Compound 16	4.921	390.27759			128443
Compound 17	4.928	157.05266			100077
Cpd 18: Sudan Green	5.296	418.16943	C ₂₈ H ₂₂ N ₂ O ₂	-3.12	2842571

Figure 4. Five compounds had hits from searching the Exact Mass Database.




Figure 5. Mass Hunter software showing the five hits from the Exact Mass Database search.




Figure 6. Online ChemID database search results from the Sudan III formula hot link.




Figure 7. Examination of data-dependent MS/MS shows identical fragmentation from the two peaks, isomers of Sudan III.

Conclusions

- Compounds were found by either formula searching or by MFE and exact mass database searching, allowing a large number of compounds to be screened in a single analysis.
- Good mass accuracy (< 3 ppm) was achieved for five dye compounds, providing high confidence in results (formulas generated and compounds confirmed).
- MS/MS on Q-TOF provides powerful capability to confirm ion identity and structure, useful for QA or unknown confirmation.
- Hot link in Mass Hunter software allows quick formula searching against several online databases for compound identification and ease of use.

References

1. Jim Lau, Chin-Kai Meng, Jennifer Gushue, Robert J. Letcher, and Shaogang Chu, "Analyzing Compounds of Environmental Interest Using an LC/Q-TOF – Part 2: Fluorotelomer Unsaturated Acids," Agilent Technologies publication 5989-9132, August 2008.
2. Jim Lau, Chin-Kai Meng, Jennifer Gushue, Mark Hewitt, and Suzanne Batchelor, "Analyzing Compounds of Environmental Interest Using an LC/Q-TOF – Part 3: Imidacloprid and Manool," Agilent Technologies publication 5989-9129, August 2008.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
August 12, 2008
5989-9336EN




Agilent Technologies



Water

Volatiles
Applications

> [Return to Table of Contents](#)
> [Search entire document](#)



Ultra-Fast Total Petroleum Hydrocarbons (TPH) Analysis with Agilent Low Thermal Mass (LTM) GC and Simultaneous Dual-Tower Injection

Application Note

Environmental

Authors

Wei Luan
Agilent Technologies (Shanghai)
Co., Ltd.
412 Ying Lun Road
Shanghai 200131
China

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington DE 19808
USA

Abstract

This application note is targeted for ultra-high productivity of total petroleum hydrocarbons (TPH) analysis in environmental laboratories. Agilent's Low Thermal Mass (LTM) technology is employed here to perform ultra-fast gas chromatographic (GC) separations. The LTM technology uses a column module combining a fused silica capillary column with heating and temperature-sensing components wound around it, which can be heated and cooled very efficiently. In this application note, the speed of analysis for the hydrocarbon group eluting between C_{10} and C_{44} can be dramatically increased to about 13 times faster than a conventional method. In addition, the ultra-fast cooling function of an LTM module can reduce the total GC cycle time to 5.1 minutes. The simultaneous dual-tower injection from Agilent is used to further double productivity. The final result for TPH analysis productivity is 5.1 minutes per two samples.



Agilent Technologies

Introduction

Total petroleum hydrocarbons (TPH) is a term used to describe a large family of several hundred chemical compounds that originally came from crude oil. Many environmental laboratories in the world are analyzing the total amount of TPH at a site to evaluate the water or soil contamination by TPH, such as oil, gasoline, diesel fuel, etc.

The Agilent Low Thermal Mass (LTM) system (except for an external power supply) is built into a replacement GC oven door, which is mounted as an add-on to an Agilent 7890A GC. A version is also available for the Agilent 6890 GC. The key component of LTM system is the LTM column module combining a fused silica capillary column with heating and temperature-sensing components wound around it. The LTM system can heat and cool the column very efficiently for significantly shorter analytical cycle times as compared to conventional air bath GC oven techniques involving much higher thermal mass.

The GC method translation software from Agilent is a calculator used to scale a method between different column dimensions with equal or increased speed. In this application note, a 40-minute separation with a 30-meter column is translated into a 20-minute separation with a 15-meter column at first, without LTM technology. Then the method is further translated for LTM use with a 5-meter column within 3.1 minutes.

As a base for the LTM system, the Agilent 7890A can provide dual complete analysis channels. With a configuration of dual injection towers, single sample tray, dual split/splitless inlets, and dual detectors, the simultaneous TPH analysis can be accomplished to double lab productivity, in addition to the speed gains realized with LTM.

Experimental

Standard Preparation

The custom alkanes mix (cus-908) from Ultra Scientific (North Kingstown, Rhode Island, U.S.) contains n-alkanes from n-decane (C₁₀) to n-tetratetracontane (C₄₄) in hexane at the concentration listed in Table 1. Dilutions in dichloromethane are made up at 1.0, 5.0, 10.0, 50.0, and 100.0 µg/mL concentrations.

Table 1. Custom Alkanes Mix

Component	Concentration, mg/mL	Component	Concentration, mg/mL
n-decane	0.2	n-tetracosane	0.1
n-dodecane	0.1	n-hexacosane	0.1
n-tetradecane	0.2	n-octacosane	0.1
n-hexadecane	0.1	n-triacontane	0.1
n-octadecane	0.1	n-dotriacontane	0.1
n-eicosane	0.1	n-hexatriacontane	0.1
n-docosane	0.1	n-tetracontane	0.1
n-tricosane	0.2	n-tetratetracontane	0.1

Sample Preparation

Soil samples are mixed with sodium sulfate to remove excess moisture and then sonicated with 60-mL aliquots of dichloromethane, three times. Water samples are placed in a 2-L separate funnel. A 100-mL aliquot of dichloromethane is added and the mixture is shaken automatically for about 2 minutes. The liquid-liquid extraction is repeated two more times. For both matrices, the extract is concentrated on a steam bath to either 5 mL for a soil sample or 1 mL for a water sample. The extracts are not routinely treated with silica gel, unless specified.

Instrumentation and Conditions

Agilent 7890A GC with LTM system, consisting of:

G3440A	7890A Series GC system
#112	Split/splitless inlet with EPC (2)
#211	Capillary FID with EPC (2)
	Autoinjector modules (2)
	Autosampler tray module
G6579A	LTM system bundle for 2-channel LTM operation, for use with standard size LTM column modules (100–2000LTM DB-5 5 M × 0.32 mm id, 1.0 µm standard 5-inch LTM column module)

ChemStation 32-bit version B.04.01

Table 2. Gas Chromatograph Conditions

	Original 1X Method	2X Method	LTM Method
GC			
Agilent Technologies 7890A			
Inlet	EPC split/splitless	EPC split/splitless	EPC split/splitless
Mode	Constant pressure	Constant pressure	Ramp pressure
Injection type	Split	Split	Split
Injection volume (μL)	1.0	1.0	1.0
Inlet temp (°C)	300	300	300
Pressure, nominal (psig)	30	14.319	13.1 (0.1 min), 11.27 psi/min to 30 (1.5 min)
Liner	Helix liner, open ended, deactivated (p/n 5188-5396)	Helix liner, open ended, deactivated (p/n 5188-5396)	Helix liner, open ended, deactivated (p/n 5188-5396)
Split ratio	2:1	2:1	2:1
Gas saver	20 mL/min after 2 min	20 mL/min after 2 min	20 mL/min after 2 min
Gas type	Helium	Helium	Helium
Sample overlap	2 min after end of GC run	2 min after end of GC run	2 min after end of GC run
Oven	GC Oven	GC Oven	LTM module (p/n G6579A) with GC oven 300 °C for 3.1 min
Initial oven temp (°C)	40	40	40
Initial oven hold (min)	1	0.5	0.1
Ramp rate (°C/min)	10	20	200
Final temp (°C)	320	320	340
Final hold (min)	11	6.5	1.5
Run time (min)	40	21	3.1
Cooldown time (min)	5.4	5.4	2
Cycle time (min)	45.4	25.4	5
Column			
Type	DB-5 (p/n 123-5032)	DB-5 (p/n 123-5012)	DB-5 (p/n*)
Length (m)	30	15	5
Diameter (mm)	0.32	0.32	0.32
Film thickness (um)	0.25	0.25	1.0
FID			
Temperature (°C)	300	300	300
H ₂ flow (mL/min)	30	30	30
Air flow (mL/min)	400	400	400
Makeup flow (mL/min)	25	25	25
Sampling rate (Hz)	50	50	50

*100–2000LTM DB-5 5M x 0.32 mm id, 1.0 μm standard 5-inch LTM column module

Results and Discussion

Ultra-Fast Separation of n-alkanes Mixture with LTM System and Scale-Up Using the GC Method Translator

The application is started with the analysis of a standard mixture of n-alkanes, containing n-C₁₀, n-C₁₂, up to n-C₄₄. Figure 1 compares the chromatogram of the standard mixture using three different methods in the same time scale. With the LTM system, the GC run time can be more than 10 times faster than conventional methods. In terms of cooling down, the classical GC oven such as 7890 fast oven will take about 5.4 minutes from 320 to 40 °C. Relatively, the LTM system has a much lower thermal mass, which can perform ultra-fast cooling. In this case, the LTM system will take about 2 minutes from 340 to 40 °C, for dual parallel LTM modules. In addition, sample overlap of the 7890 sample tray can prepare the

sample after the end of the last GC run parallel with GC oven cooldown. The resulting cycle time for LTM is 5.1 minutes, which means about nine times faster than the conventional method.

Resolution is also a concern with fast analysis. Figure 2 is the expanded view of Figure 1 with the nominal time scale, which demonstrates that all the peaks of n-alkanes are baseline separated, even with the nine-times-faster LTM method (speed calculated by total cycle time). The result is calculated by total amount of TPH, not by the individual peak amount; peak-grouping of ChemStation is employed here. The calibration is checked by injecting the standard mixture in different concentration levels, ranging from 1 to 100 µg/mL. The calibration curve of the LTM method is displayed in Figure 3, with average n-alkanes response factor by peak-grouping.




Figure 1. Comparison of conventional method and LTM method.




Figure 2. Expanded view of Figure 1, with the nominal time scale.




Figure 3. Calibration curve of LTM method after peak-grouping.

Simultaneous Dual-Channel Analysis with Agilent Dual-Tower Injection

Agilent 7890A and 6890 GCs make dual-channel analysis possible, with the configuration of a single sample tray and dual injection towers, inlets, columns, and detectors. Typically, a dual-channel configuration is used to identify target compounds in one GC run, using different retention time in columns of different polarity. The purpose here is to double lab productivity using dual identical channels at a much lower cost compared to two single-channel instruments. ChemStation can provide different choices for final data file generation. Figure 4 shows one option of detection signal setting for separating the dual-tower injection into two individual data files. Figure 5 is the chromatogram of two real samples with simultaneous dual-tower injection.




Figure 4. Signal setting for dual-tower injection to generate two individual data files.




Figure 5. Chromatogram of two real samples with simultaneous dual-tower injection.

Quantitative Analysis of TPH with Peak-Grouping and Peak-Summing

Peak-grouping is used to average each n-alkane response factor. With this average response factor, the nominal calibration curve can be used for quantitation of each peak, including unidentified peaks eluting between n-C₁₀ and n-C₄₄. In this case, the compound peak-grouping details and unidentified peak calibration settings can be seen in Figure 6.

Another requirement for TPH analysis is quantitation across the whole eluting time range between n-C₁₀ and n-C₄₄ to calculate all petroleum hydrocarbons not only n-alkanes. Baseline-holding and peak-summing in the ChemStation integration events table are necessary to meet this requirement; the related setting can be seen in Figure 7. For example, the integration result of real sample is shown in Figure 8.




Figure 6. Peak-grouping (left) and unidentified peak calibration setting (right) in ChemStation.

Time	Integration Events	Value
Initial	Slope Sensitivity	10
Initial	Peak Width	0.04
Initial	Area Reject	1
Initial	Height Reject	1
Initial	Shoulders	OFF
0.000	Integration	OFF
4.560	Area Sum	ON
4.560	Baseline Hold	ON
4.560	Integration	ON
39.100	Integration	OFF
39.100	Area Sum	OFF

Figure 7. Baseline-holding and peak-summing setting in the ChemStation integration events table.




Figure 8. Integration result of real sample after baseline-holding and peak-summing.

Real Sample Analysis

After calibration by peak-grouping and integration through peak-summing, the quantitation result can be reported as the total amount of TPH in a real sample. As a comparison of quantitation results with three different acquired methods, Table 3 demonstrates that the real sample analysis result by the ultra-fast LTM method is comparable with conventional methods.

Table 3. Comparison of Quantitation Result with Three Different Acquired Methods

	TPH Concentration ($\mu\text{g/mL}$)
Original method (30 m)	1097
2X method (15 m)	920
LTM method (5 m)	909

Conclusions

The low thermal mass of the Agilent LTM system can perform very efficient column heating and cooling, and is used here to develop an ultra-fast TPH analysis to meet the requirement for high lab productivity. Dual-tower injection is also used to further double the productivity with much less cost. The final solution with the LTM system and dual-tower injection can perform TPH analyses at a rate of 5.1 minutes per two samples. The total productivity increase is 18x compared to a conventional analysis on a single-channel system.

References

1. "Agilent Low Thermal Mass (LTM) System for Gas Chromatography," Agilent Technologies publication 5989-8711EN, June 2008
2. Wei Luan, Chuanhong Tu, and Michael Woodman, "Evaluation of Total Petroleum Hydrocarbon in Soil Using LC with Fraction Collector and GC/MS," Agilent Technologies publication 5989-6012EN, April 2007

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Published in the USA
November 18, 2008
5990-3201EN



Agilent Technologies



Chlorinated Solvents and Disinfection By-Product Analysis Using Agilent J&W HP-1ms Ultra Inert and DB-1301 Capillary GC Columns

Application Note

Environmental

Authors

Doris Smith and Ken Lynam
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Trace-level chlorinated hydrocarbon analyses using methods such as US EPA Method 551.1 are important tools for assessing organochlorine contamination in water. The wide diversity of target organochlorine compounds can prove chromatographically challenging due mainly to their high volatility and limited retention. This application note shows the benefits of using an Agilent J&W HP-1ms Ultra Inert Capillary GC column as the primary column for detection in this dual-column analysis.



Agilent Technologies

Introduction

The disinfection of water for safe human consumption is a critical process worldwide. Chlorination is an effective means of achieving water disinfection, but has been shown to produce a wide variety of disinfection byproducts (DBPs). These byproducts are formed when the chlorinated disinfectant reacts with naturally present organic matter. Some of the byproducts formed include trihalomethanes, haloacetonitriles, and chloropropanones. Many of the DBPs have been linked to adverse health effects, including birth defects, bladder and colon cancer [1–3]. Because of these health concerns, the levels of the by-products are monitored to ensure they are below safety standard limits.

US EPA Method 551.1 [4] is a commonly used method for detecting organochlorine compounds in water samples by GC/ECD. This method encompasses several classes of analytes: chlorinated organic solvents, trihalomethanes (THMs), haloacetonitriles, and other DBPs. The high volatility and limited retention of several of these analytes can prove problematic chromatographically. Reliable detection at very low levels is also a challenge for this analyte set. Active sites in the sample path can compromise an analyte's response. Minimizing activity in the GC column is essential to ensure accurate quantitation. Capillary GC column activity as a potential source of result uncertainty has been effectively eliminated with the Agilent J&W Ultra Inert series of columns.

Agilent Technologies, Inc. has implemented new testing procedures for the J&W Ultra Inert column series to more effectively evaluate GC column inertness performance. This testing procedure employs deliberately aggressive probes to thoroughly investigate column inertness performance on this new series of columns. These aggressive probes, including 1-propionic acid, 4-picoline, and trimethyl phosphate, are used to verify each column's inertness performance.

A standard preparation containing chlorinated solvents, THMs, and disinfection by-products (DBPs) was analyzed to evaluate column performance. This analysis used simultaneous primary and confirmation analysis from a single injection source through an Agilent Capillary Flow Technology two-way splitter without makeup device. The primary analysis column used was an Agilent J&W HP-1ms Ultra Inert 30 m × 0.25 mm × 1.0 µm and the confirmation column was an Agilent J&W DB-1301 30 m × 0.25 mm × 1.0 µm.

Experimental

An Agilent 7890A GC equipped with dual µECDs and an Agilent 7683B automatic liquid sampler was used for this series of experiments. Table 1 lists the chromatographic conditions used for these analyses. Table 2 lists flow path consumable supplies used in these experiments.

Table 1. Chromatographic Conditions for EPA Method 551.1 Calibration Standards

GC:	Agilent 7890A
Sampler:	Agilent 7683B, 5.0 µL syringe (Agilent p/n 5181-1273) 0.5 µL splitless injection
Carrier:	Helium 25 cm/s, constant flow
Inlet:	Splitless; 200 °C, Purge flow 20 mL/min at 0.25 min
Inlet liner:	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Retention gap:	1 m 0.32 mm id deactivated fused silica high-temperature tubing (Agilent p/n 160-2855-5)
Column 1:	Agilent J&W HP-1ms Ultra Inert 30 m × 0.25 mm × 1.0 µm (Agilent p/n 19091S-733UI)
Column 2:	Agilent J & W DB-1301 30 m × 0.25 mm × 1.0 µm (Agilent p/n 122-1333)
Oven:	33 °C (14 min) to 60 °C (5 °C/min), hold 5 min, 15 °C/min to 275 °C, hold 20 min
Detection:	Dual G2397A µECD; 300 °C, const col + makeup (N ₂) = 30 mL/min

Table 2. Flow Path Supplies

CFT device:	Two-way splitter accessory without makeup gas (Agilent p/n G3181B) Alternative: Deactivated quartz y-splitter (Agilent p/n 5181-3398)
CFT fittings:	Internal nut (Agilent p/n G2855-20530) Swaging nut (Agilent p/n G2855-20555)
CFT ferrules:	SiTite ferrules, 0.32 mm id (Agilent p/n 5188-5362) SiTite ferrules, 0.25 mm id (Agilent p/n 5188-5361)
Vials:	Amber crimp cap glass vials (Agilent p/n 5183-4496)
Vial caps:	Crimp caps (Agilent p/n 5282-1210)
Vial inserts:	100 µL glass/polymer feet (Agilent p/n 5181-8872)
Syringe:	5 µL (Agilent p/n 5181-1273)
Septum:	Advanced Green (Agilent p/n 5183-4759)
Inlet liners:	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Ferrules:	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323) 0.5 mm id short; 85/15 Vespel/graphite (Agilent p/n 5062-3514)
20x magnifier:	20x magnifier Agilent p/n 430-1020)

Sample Preparation

EPA551.1 Standards

Two EPA551.1 standards containing chlorinated solvents, THMs, and DBPs were purchased from AccuStandard (New Haven, CT) and used to prepare a six-level calibration standard set. The stock solutions as delivered had a nominal concentration of 1000 µg/mL. The calibration standards were prepared at standard concentrations of 0.1, 0.05, 0.02, 0.01, 0.005, and 0.002 µg/mL. All solutions were prepared in MTBE using class A volumetric pipettes and flasks. MTBE used was Burdick and Jackson high-purity grade purchased thorough VWR International (West Chester, PA). MTBE was used as a reagent blank and syringe wash solvent.

Column Installation Using Two-Way Splitter Without Makeup Gas Capillary Flow Technology (CFT)

This analysis was performed using simultaneous confirmation from a single injector onto both the primary and confirmation columns. While a typical injector setup for dual column analysis uses a deactivated glass or quartz Y-splitter (Agilent p/n 5181-3398) to join the retention gap to the primary and confirmation columns, an Agilent Capillary Flow Technology two-way splitter without makeup gas (p/n G3181B) was employed. This device holds several advantages over the Y-splitter.

Correct assembly of a Y-splitter can be difficult, and detachment and/or leaks may occur upon thermal cycling of the oven. When using the Y-splitter, a periodic check of the


connections is recommended. The Agilent CFT splitter uses SilTite metal ferrules that minimize the likelihood of leaks or detachment, even with thermal cycling as high as 350 °C. Installation of the retention gap and columns into the splitter module uses ferrules and internal nuts similar to a typical column installation. The CFT splitter is deactivated, yielding an inert sample path. The point-of-seal of the fittings design provides extremely low dead-volume column connections, improving optimal performance.

For this analysis, a 1 m, 0.32 mm id deactivated fused silica high-temperature tubing was installed into the inlet and into the top position of the two-way splitter. For the column connections to the splitter, the column end was threaded through the internal nut, SilTite ferrule, and swaging nut. The swaging nut was then tightened, seating the ferrule onto the column. Using a column cutter, the column end was trimmed to about 0.3 mm of column extending above the ferrule. The column was then connected to the two-way splitter. A diagram of the splitter and column setup is shown in Figure 1. Because the column connections are individually installed in the splitter, column maintenance can be done independent of the other column.


Results and Discussion

Baseline Inertness Profile for Ultra Inert Columns

The basic approach for inertness verification for the Agilent J&W Ultra Inert series of capillary GC columns is QC testing with aggressive active probes at low concentration and low temperature [5]. This is a rigorous approach that establishes



Two-way splitter without makeup gas connections



Plumbing diagram for the two-way splitter without makeup gas

Figure 1. Agilent Capillary Flow Technology two-way splitter without makeup gas (p/n G3181B) and diagram of instrument setup of simultaneous confirmation from a single injection onto both the primary and confirmation columns.

consistent baseline inertness profiles for each column. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species that tend to adsorb onto active sites, particularly at trace level like the chlorinated species in this application example. Additional application examples can be found in references [6–10].

EPA 551.1 Analysis

In this application note a six-level calibration curve set was evaluated over the concentration range of 0.002 to 0.1 $\mu\text{g/mL}$ using simultaneous confirmation of a single injection. A two-way splitter without makeup capillary flow device (p/n G3181B) was used in place of a y-splitter to split the sample onto the two columns. Figure 2 shows a chromatogram for the 5 pg on column loading from a single injection of the 551.1 standard on the primary and confirmation columns.

Excellent peak resolution and peak shape were obtained on both the J&W HP-1ms Ultra Inert and the J&W DB-1301 columns as shown in Figures 3 and 4. Chloral hydrate is unstable and, as is described in the EPA method, does not resolve as a discrete peak due to selectivity on a 1301 phase

column. Figure 5 shows that chloral hydrate is well resolved and has symmetrical peak shape even at low levels on the J&W HP-1ms Ultra Inert primary column. One method criteria for primary column performance for this analysis is the resolution between bromodichloromethane and trichloroethylene. The acceptance criteria requires a resolution greater than 0.5 using the calculation described in the method. Figure 6 shows the resolution of bromodichloromethane and trichloroethylene in the 0.05 $\mu\text{g/mL}$ EPA 551.1 standard on the J&W HP-1ms Ultra Inert primary analysis column. The resolution was found to be 0.787, well above the method criteria. This resolution was also determined at the lowest and highest level standards studied in this application. The resolution was 0.825 for the 0.002 $\mu\text{g/mL}$ standard (0.5 pg on column) and 0.734 for the 0.1 $\mu\text{g/mL}$ standard (25 pg on column) as can be seen in Figure 7.

Linearity was excellent across the range studied, giving R^2 values of 0.998 or greater for the chlorinated analytes on both the J&W HP-1ms Ultra Inert primary analysis column and also on the J&W DB-1301 confirmation column. Table 3 indicates the correlation coefficients for each component on both columns.




Figure 2. Single-injection chromatogram of the 5 pg on-column EPA551.1 standard solution loading on an Agilent J&W HP-1ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 1.0 μm capillary GC column (p/n 19091S-733UI) and J&W DB-1301 30 m $\times$ 0.25 mm $\times$ 1.0 μm capillary GC column (p/n 122-1333). Chromatographic conditions are listed in Table 1. Refer to Table 4 for a peak number key.




Figure 3. Enlarged chromatogram of the 5 pg on-column EPA551.1 standard solution loading on an Agilent J&W HP-1ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 1.0 μ m capillary GC column (p/n 19091S-733UI). Chromatographic conditions are listed in Table 1. Refer to Table 4 for a peak number key.




Figure 4. Enlarged chromatogram of the 5 pg on-column EPA551.1 standard solution loading on an Agilent J&W DB-1301 30 m $\times$ 0.25 mm $\times$ 1.0 μ m capillary GC column (p/n 122-1333). Chloral hydrate (peak # 8) does not elute as a discrete peak on this column. Chromatographic conditions are listed in Table 1. Refer to Table 4 for a peak number key.

Table 3. Correlation Coefficients for the Analytes in the EPA Method 551.1 Standard Over the 0.002 to 0.1 µg/mL Range of This Study for a 0.5 µL Single Injection Loading onto the Dual Column System

Component	Agilent J&W HP-1ms UI R ²	Agilent J&W DB-1301 R ²
Chloroform	0.9997	0.9997
1,1,1-Trichloroethane	0.9999	0.9999
Carbon tetrachloride	0.9987	0.9988
Trichloroacetonitrile	0.9989	0.9979
Dichloroacetonitrile	0.9995	0.9993
Bromodichloromethane	0.9995	0.9994
Trichloroethylene	0.9998	0.9998
Chloral hydrate	0.9982	X
1,1-Dichloro-2-propanone	0.9999	0.9995
1,1,2-Trichloroethane	0.9998	0.9994
Chloropicrin	0.9995	0.9975
Dibromochloromethane	0.9995	0.9994
Bromochloroacetonitrile	0.9993	0.9981
1,2-Dibromoethane	0.9998	0.9999
Tetrachloroethylene	0.9994	0.9999
1,1,1-Trichloro-2-propanone	0.9995	0.9992
Bromoform	1.0000	0.9998
Dibromoacetonitrile	0.9984	0.9975
1,2,3-Trichloropropane	0.9999	1.0000
1,2-Dibromo-3-chloropropane	0.9995	0.9998




Figure 5. Enlarged chromatogram for a 0.5 µL injection of 0.002 µg/mL EPA 551.1 standard on the Agilent J&W HP-1ms Ultra Inert 30 m × 0.25 mm × 1.0 µm capillary GC column. Peak shape on the J&W HP-1ms Ultra Inert column is symmetrical and well resolved from the other components.




Figure 6. Enlarged chromatogram of 0.05 µg/mL EPA 551.1 standard on the Agilent J&W HP-1ms Ultra Inert 30 m × 0.25 mm × 1.0 µm capillary GC column. Method criteria for column performance is a resolution greater than 0.50 between bromodichloromethane and trichloroethylene.




Figure 7. Enlarged chromatograms of the low and high range EPA551.1 standards on the Agilent J&W HP-1ms Ultra Inert 30 m × 0.25 mm × 1.0 μm capillary GC column. Method criteria for column performance is a resolution greater than 0.50 between bromodichloromethane and trichloroethylene.

Table 4. Peak Identification Table for EPA551.1 Chromatograms Shown in Figures 2 Through 4

Peak number	Peak name
1	Chloroform
2	1,1,1-Trichloroethane
3	Carbon tetrachloride
4	Trichloroacetonitrile
5	Dichloroacetonitrile
6	Bromodichloromethane
7	Trichloroethylene
8	Chloral hydrate
9	1,1-Dichloro-2-propanone
10	1,1,2-Trichloroethane
11	Chloropicrin
12	Dibromochloromethane
13	Bromochloroacetonitrile
14	1,2-Dibromoethane
15	Tetrachloroethylene
16	1,1,1-Trichloro-2-propanone
17	Bromoform
18	Dibromoacetonitrile
19	1,2,3-Trichloropropane
20	1,2-Dibromo-3-chloropropane

Conclusions

This application successfully demonstrates the use of an Agilent J&W HP-1ms Ultra Inert capillary GC column for primary analysis of EPA 551.1 chlorinated solvents, trihalomethanes, and disinfection by-products. Linearity was excellent for all organochlorine analytes studied, yielding 0.998 or greater R^2 values down to a 0.5 pg on-column loading. One of the reasons for the excellent linearity and high R^2 values is the highly inert surface of the column. The excellent peak shape of the chloral hydrate and resolution between bromodichloromethane and trichloroethylene emphasize the advantage of the Agilent J&W HP-1ms Ultra Inert capillary GC column. The lack of chemically active sites makes this column an excellent choice for EPA Method 551.1 analysis.

References

1. John Fawell and Mark J. Nieuwenhuijsen, "Contaminants in Drinking Water," *British Medical Bulletin*, 2003; 68: 199–208
2. Susan D. Richardson, "Disinfection By-Products and Other Emerging Contaminants in Drinking Water," *Trends in Analytical Chemistry*, Vol. 22, Issue 10, November 2003, pgs. 666–684
3. Bing-Fang Hwang, Jouni J. K. Jaakkola, and How-Ran Guo, "Water Disinfection By-Products and the Risk of Specific Birth Defects: A Population-Based Cross-Sectional Study in Taiwan," *Environmental Health*, 2 June 2008
4. US EPA Method 551.1, Revision 1, 1995, "Determination of Chlorination Disinfection By-Products, Chlorinated Solvents, and Halogenated Pesticides/Herbicides in Drinking Water by Liquid-Liquid Extraction and Gas Chromatography with Electron Capture Detection"
5. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenyltrimethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
6. "Agilent J&W Ultra Inert GC Columns: A New Tool to Battle Challenging Active Analytes" Agilent Technologies publication 5989-8685EN, May 29, 2008
7. Mike Szelewski, Bill Wilson, and Pat Perkins, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270," Agilent Technologies publication 5988-3072EN, November 7, 2001
8. Kenneth Lynam, "Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column," Agilent Technologies publication 5989-8616EN, May 13, 2008
9. Kenneth Lynam and Doris Smith, "Polycyclic Aromatic Hydrocarbon (PAH) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9181EN, July 2008
10. Kenneth Lynam and Doris Smith, "Polybrominated Diphenyl Ether (PBDE) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9571EN, August 2008

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Printed in the USA
February 27, 2009
5990-3737EN



Agilent Technologies



Techniques for Optimizing the Analysis of Volatile Organic Compounds in Water Using Purge-and-Trap/GC/MS

Application

Environmental

Author

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA
(E-mail: phil_wylie@agilent.com)

Abstract

The analysis of volatile organic compounds in water is normally accomplished by purge-and-trap/gas chromatography/mass spectrometry. U.S. EPA Method 8260B with purge and trap sample introduction is widely used for the analysis of aqueous samples other than drinking water. This application note discusses problems that can arise and some easy solutions for them. These techniques have resulted in robust calibrations that meet Method 8260B calibration requirements over the range of 1–200 µg/L.

Introduction

U.S. EPA Method 8260B [1] is a general purpose method for the analysis of volatile organic compounds (VOCs) in matrices such as ground and surface water, sludges, soils and sediments, filter cakes, spent carbons, and spent catalysts. This method is only used for the analyses of target VOCs by gas chromatography with mass spectral

detection (GC/MS). It refers analysts to other U.S. EPA sample introduction methods that are appropriate for the matrix to be analyzed. This paper focuses on the analysis of VOCs in water using purge and trap (P&T) sample introduction according to U.S. EPA Method 5030C [2] coupled to GC/MS for separation and analysis (P&T/GC/MS). For simplicity, the combination of Methods 5030C with 8260B is referred to as just Method 8260B.

This P&T/GC/MS procedure is widely used in environmental laboratories for the analysis of VOCs in surface, ground, and wastewater samples. A similar method for the analysis of drinking water is described in EPA Method 524.2 [3]. Though well established, P&T/GC/MS methods can be a challenge to run successfully. There are numerous P&T, GC, and MS variables to optimize in order to obtain good recoveries for the target VOCs without undo disturbance from water and methanol that are inevitably transferred to the GC during trap desorption.

This application note describes techniques for optimizing Method 8260B using the Agilent 6890N GC and new 5973 inert mass selective detector (MSD) coupled to the new Teledyne Tekmar Velocity XPT P&T system. Included, in the paper, are suggestions for MSD tuning, sample preparation, instrument setpoints, and maintenance techniques that lead to a robust method for the analysis of VOCs in water. The discussion is applicable to most other P&T/GC/MS methods.



Agilent Technologies

Experimental

Chemical Standards, Reagents, and Vials

High purity B&J brand methanol was obtained from Honeywell Burdick & Jackson Co. (Muskegon, MI). Standard mixtures used for the preparation of calibration samples, spiking solutions, tune evaluation, and stability test samples were purchased from AccuStandard (New Haven, CT). These include the following: Part no. M-502-10X-Pak containing 60 VOC target analytes (54 liquids and 6 gases) at 2000 µg/mL each in methanol; Part no. M-8260A/B-IS/SS-10X-PAK containing p-bromofluorobenzene (BFB), chlorobenzene-d₅, dibromofluoromethane, 1,4-dichlorobenzene-d₄ (DCB-d₄), 1,2-dichloroethane-d₄, fluorobenzene (FBz), and toluene-d₈ at 2000 µg/mL each in methanol; and part no. M-524-FS-PAK containing BFB,

1,2-dichlorobenzene-d₄, and fluorobenzene (FBz) at 2000 µg/mL each in methanol.

VOC-free water was used for the preparation of standards and test samples. TraceClean 40-mL (nominal volume, actual volume is 43 mL) VOA vials (part no. 15900-022) were purchased from VWR Scientific (West Chester, PA).

Preparation of Calibration and Spiking Solutions

Secondary spiking solutions were prepared in methanol for each calibration level so that each 43-mL water sample could be spiked with 10 µL of the calibration solution (containing 60 VOCs) and 10 µL of the internal standard/surrogate mixture. Table 1 provides details on how the eight calibration standards were prepared.

Table 1. Procedure for Preparing Calibration Samples

A	B	C	D	E
Calibration level (µg/L)	Volume of 2000 µg/mL VOC Standard (µL)	Diluted to this volume in methanol (mL)	Results in this secondary standard concentration (µg/L)	Amount to spike into 43-mL vial (µL)
1	53.75	25.00	4.3	10.00
2	43.00	10.00	8.6	10.00
5	53.75	5.00	21.5	10.00
20	43.00	1.00	86	10.00
50	43.00	0.40	215	10.00
100	43.00	0.20	430	10.00
200	43.00	0.10	860	10.00
300	*	*	2000*	6.45**

Column A. Concentration of each analyte in the final aqueous calibration solution.

Column B. Volume of the 2000 µg/mL 60-component VOC standard solution which was diluted to the volume shown in column C.

Column C. Final volume of VOC solution after dilution in methanol.

Column D. Concentration of the calibration spiking solution prepared by diluting the amount of 2000 µg/mL standard in column B to the volume shown in column C.

Column E. Amount of the secondary standard solution (column D) added to 43 mL of water to prepare the calibration standard at the level shown in column A.

*The undiluted VOC standard (2000 µg/mL) was used for spiking.

**The 300 µg/L aqueous calibration standard was prepared by adding 6.45 µL of the 2000 µg/mL AccuStandard VOC solution and 3.55 µL of methanol to 43 mL of water in a VOA vial.

As discussed below, containers for storing the secondary standards (column C, Table 1) were chosen to minimize the headspace. Larger volumes were transferred to 2-mL screw top vials, while smaller volumes were transferred to crimp cap microvials of the appropriate size.

A solution of the internal standards (ISTDs) and surrogates was prepared at 215 ppm in methanol by diluting 43 μL of the 2000- $\mu\text{g}/\text{mL}$ AccuStandard solution to a volume of 400 μL . Each 43-mL water sample was spiked with 10 μL of this solution so that all samples and standards contained 50 $\mu\text{g}/\text{L}$ of each compound.

Preparation of Solutions for Repeatability Studies

Two kinds of spiked water samples were prepared for use in repeatability studies.

- System blanks consisted of clean water spiked with fluorobenzene, BFB, and 1,2-dichlorobenzene- d_4 at 10 $\mu\text{g}/\text{L}$ each.
- VOC spikes consisted of clean water with fluorobenzene, BFB, and 1,2-dichlorobenzene- d_4 at 10 $\mu\text{g}/\text{L}$ and the 60 VOC target compounds at 20 $\mu\text{g}/\text{L}$ each.

Replicate samples were prepared as follows.

- Secondary dilution standards containing fluorobenzene, BFB, and 1,2-dichlorobenzene- d_4 at 50.0 $\mu\text{g}/\text{mL}$ were prepared in 2-mL autosampler vials by diluting 25 μL of the 2000- $\mu\text{g}/\text{mL}$ AccuStandard solution with 975 μL of methanol.
- Secondary dilution standards of the 60-component VOC solution were prepared at 100 $\mu\text{g}/\text{mL}$ in 2-mL autosampler vials by diluting 50 μL of the 2000 $\mu\text{g}/\text{mL}$ AccuStandard solution with 950 μL of methanol.

System blanks were prepared by adding 100 μL of the 50.0 $\mu\text{g}/\text{mL}$ three component solution and 100- μL methanol to 500 mL of water in a 1.0-L screw-cap bottle. After inverting to mix thoroughly, this bottle was attached to the apparatus shown in Figure 1 and 11 VOA vials were filled by transferring the spiked water solution under nitrogen pressure.




Figure 1. Apparatus used to fill multiple VOA vials with the same spiked water solution.

- A) 1-L liquid chromatography solvent bottle
 B) Swagelok Tee with nothing connected to one fitting
 C) Finger used to cap fitting in order to pressurize the reservoir bottle
 D) VOA vial
 E) 1/8-inch PTFE tubing

VOA spiked samples were prepared by adding 100 μL of the 50.0- $\mu\text{g}/\text{mL}$ three component solution and 100 μL of the 100- $\mu\text{g}/\text{mL}$ 60-component VOC standard to 500 mL of water in a 1.0-L screw cap bottle. After inverting to mix thoroughly, this bottle was attached to the apparatus shown in Figure 1 and 11 VOA vials were filled by transferring the spiked water solution under nitrogen pressure.

Instrumentation and Analytical Conditions

The P&T instrumentation and setpoints are listed in Table 2. The following P&T options were not used: DryFlow trap, automatic ISTD addition, sample heating, dry purging, and sample cryofocusing. The method shown in Table 2 was derived using the wizard that is provided in the TekLink 2.2 P&T control software.

Table 2. Purge and Trap Instrumentation and Setpoints

P&T Instrument	Teledyne Tekmar Velocity XPT
Automatic sampler	Teledyne Tekmar Aquatek 70
Software control	Teledyne Tekmar VOC Teklink version 2.2
Trap	Vocarb 3000
P&T-GC interface	P&T transfer line spliced into the GC split/splitless inlet carrier gas line and GC carrier gas plumbed to the Velocity XPT
Sample size	5 mL
Valve oven temperature	150 °C
Transfer line temperature	150 °C
Sample mount temp	90 °C
Purge ready temp	45 °C
DryFlow standby temperature	175 °C
Standby flow	10 mL/min
Pressurize time	0.25 min
Fill I.S. time	0.00 (ISTDs added by hand)
Sample transfer time	0.25 min
Pre-purge time	0.00 min
Pre-purge flow	40 mL/min
Sample heater	Off (Samples not heated)
Sample preheat time	1.00 min
Preheat temperature	40 °C
Purge time	11.00 min
Purge temperature	0 °C (That is, less than the purge ready temp of 45 °C)
Purge flow	40 mL/min
Purge rinse time	0.25 min
Purge line time	0.25 min
Dry purge time	0.00 min (Dry purge not used)
Dry purge temp	40 °C
Dry purge flow	200 mL/min
GC start	Start of desorb
Desorb preheat temperature	245 °C
Desorb drain	On
Desorb time	1.00 min
Desorb temperature	250 °C
Desorb flow	200 mL/min
Bake rinse	On
Number of bake rinses	3
Bake drain time	0.50 min
Bake drain flow	400 mL/min
Bake time	3.00 min
Bake temperature	270 °C
Dry flow bake temperature	300 °C
Bake flow	400 mL/min
Focus temperature	Not used
Inject time	1.00 min
Inject temperature	180 °C
Standby temperature	100 °C

Table 3. GC/MS Instrumentation and Setpoints

Gas Chromatograph	Agilent 6890N
Inlet	Split/Splitless
Inlet liner	Single taper, deactivated (Agilent part no. 5181-3316)
Inlet temperature	250 °C
Split ratio	50:1
Column	20 m × 0.18 mm × 1.0 µm DB-VRX (Agilent part no. 121-1524)
Carrier gas	Helium at 1.0 mL/min constant flow
Oven temperature program	40 °C (3 min), 10 °C/min to 100 °C (0 min), 25 °C/min to 225 °C (3 min)
Mass Spectrometer	Agilent 5973 Inert MSD
Transfer line temperature	260 °C
Quad temperature	150 °C
Source temperature	230 °C
EM voltage	2035 volts
Scan range	35–260 <i>m/z</i>
Threshold	0
Samples	3
Solvent delay	0 min
Software	MSD Productivity ChemStation Software (Part no. G1701DA version D.01.00)

Results and Discussion

Section 1.3 of Method 8260B can be used to quantify most VOCs that have boiling points below 200 °C. It lists 123 compounds that can be determined by the method using various sample prep and sample introduction methods. Of these, seven are ISTDs or surrogates, nine are not recommended for P&T sample introduction, and three must be purged at 80 °C for efficient recovery. The remaining analytes vary considerably in their water solubility and volatility making this a challenging method to optimize. The intent of this application note is to share several techniques that one can use to optimize Method 8260B or any other P&T/GC/MSD method employed for water analysis.

For this study, the 60 VOCs listed in EPA Method 502.2 were analyzed along with three ISTDs and four surrogates (Table 4).

Table 4. Compound List with Average Response Factors (RF) and the RF %RSDs for Two Calibration Ranges: 1–300 and 1–200 µg/L

Type*	Compound	Retention time (min)	Minimum average response factor**	Maximum %RSD of calibration response factors***	Average RF 1–300 µg/L	RF %RSD 1–300 µg/L	Average RF 1–200 µg/L	RF %RSD 1–200 µg/L
T	Dichlorodifluoromethane	1.25	0.1	15	0.283	8.21	0.289	5.44
T,SPCC	Chloromethane	1.34		15	0.324	9.62	0.328	9.38
T,CCC	Vinyl chloride	1.42		30	0.220	2.47	0.220	2.66
T	Bromomethane	1.60		15	0.099	14.11	0.096	12.30
T	Ethyl chloride	1.67		15	0.152	5.57	0.154	4.27
T	Trichloromonofluoromethane	1.97	0.1	15	0.372	11.38	0.386	3.49
T,CCC	1,1-Dichloroethene	2.29		30	0.330	5.31	0.336	1.45
T	Methylene chloride	2.40		15	0.299	5.02	0.301	4.95
T	<i>trans</i> -1,2-Dichloro-ethene (E)	2.92		15	0.323	2.54	0.325	1.36
T,SPCC	1,1-Dichloroethane	3.14		15	0.444	4.93	0.446	5.22
T	<i>cis</i> -1,2-Dichloroethene (Z)	3.68	0.1	15	0.360	1.28	0.361	1.17
T	Bromochloromethane,	3.83		15	0.234	1.82	0.234	1.84
T,CCC	Chloroform	3.89		30	0.442	0.92	0.443	0.60
T	2,2-Dichloropropane	3.96		15	0.202	9.87	0.209	4.19
Sur	Dibromofluoromethane	4.01		15	0.248	0.83	0.248	0.89
Sur	1,2-Dichloroethane-d ₄	4.47	0.1	15	0.298	1.76	0.299	1.79
T	1,2-Dichloroethane	4.55		15	0.359	1.57	0.359	1.66
T	1,1,1-Trichloroethane	4.64		15	0.388	7.99	0.398	1.43
T	1,1-Dichloropropene	4.86		15	0.336	12.44	0.351	3.16
T	Carbon tetrachloride	5.01		15	0.309	13.88	0.322	7.66
T	Benzene	5.08	0.1	15	1.063	7.10	1.077	6.52
ISTD	Fluorobenzene	5.34		15		1.34		1.41
T	Dibromomethane	5.68		15	0.198	1.86	0.198	2.01
T,CCC	1,2-Dichloropropane	5.75		30	0.266	1.58	0.268	0.77
T	Trichloroethylene	5.81		15	0.288	6.79	0.295	2.14
T	Bromodichloromethane	5.85	0.1	15	0.334	5.47	0.331	5.60
T	1,3-Dichloropropene (Z)	6.64		15	0.383	5.49	0.381	5.74
T	1,3-Dichloropropene (E)	7.18		15	0.322	8.76	0.318	8.93
T	1,1,2-Trichloroethane	7.32		15	0.236	1.57	0.237	1.67
Sur	Toluene-d ₈	7.47		15	0.945	0.50	0.945	0.51
T,CCC	Toluene	7.55	0.1	30	1.098	7.47	1.126	2.07
T	1,3-Dichloropropane	7.62		15	0.428	1.28	0.428	1.20
T	Dibromochloromethane	7.86		15	0.254	12.10	0.249	11.88
T	1,2-Dibromoethane	8.15		15	0.244	1.88	0.244	2.03
T	Tetrachloroethylene	8.40		15	0.307	18.72	0.327	5.07
T	1,1,1,2-Tetrachloroethane	9.15	0.3	15	0.254	8.79	0.254	9.49
ISTD	Chlorobenzene-d ₅	9.19		15		0.98		0.81
T,SPCC	Chlorobenzene	9.22		15	0.981	5.00	0.997	2.14
T,CCC	Ethylbenzene	9.51		30	1.559	11.66	1.623	1.90
T,SPCC	Bromoform	9.72		15	0.246	14.57	0.242	15.08
T	m- & p-Xylene	9.73	0.3	15	2.510	11.97	2.614	2.75
T	Styrene	10.03		15	1.008	5.68	1.022	4.25
T,SPCC	1,1,2,2-Tetrachloroethane	10.08		15	0.395	3.41	0.394	3.46
T	o-Xylene	10.10		15	1.289	9.27	1.330	1.89
T	1,2,3-Trichloropropane	10.21		15	0.347	2.90	0.346	2.94
Sur	BFB	10.44	0.3	15	0.381	0.93	0.382	0.82
T	Isopropylbenzene	10.44		15	1.474	17.44	1.562	4.13
T	Bromobenzene	10.58		15	0.643	5.20	0.653	3.12
T	n-propylbenzene	10.82		15	1.840	17.38	1.950	3.60
T	2-Chlorotoluene	10.85		15	1.124	10.66	1.166	1.93
T	4-Chlorotoluene	10.92		15	1.184	10.23	1.224	3.75

Table 4. Compound List with Average Response Factors (RF) and the RF %RSDs for Two Calibration Ranges: 1–300 and 1–200 µg/L (Continued)

Type*	Compound	Retention time (min)	Minimum average response factor**	Maximum %RSD of calibration response factors***	Average RF 1–300 µg/L	RF %RSD 1–300 µg/L	Average RF 1–200 µg/L	RF %RSD 1–200 µg/L
T	1,3,5-Trimethylbenzene	11.08		15	1.275	14.63	1.340	3.02
T	Tertbutylbenzene	11.26		15	1.196	18.98	1.274	4.24
T	1,2,4-Trimethylbenzene	11.36		15	1.353	12.22	1.411	2.35
T	sec-Butylbenzene	11.43		15	1.729	21.91	1.858	5.67
T	1,3-Dichlorobenzene	11.44		15	1.529	10.75	1.579	5.61
T	1,4-Dichlorobenzene	11.49		15	1.597	9.97	1.643	5.99
ISTD	1,4-Dichlorobenzene-d ₄	11.47		15		1.09		1.17
T	p-Isopropyltoluene	11.58		15	2.587	19.00	2.757	3.52
T	1,2-Dichlorobenzene	11.73		15	1.485	6.33	1.516	2.74
T	Butylbenzene	11.87		15	2.355	20.68	2.522	4.81
T	1,2-Dibromo-3-chloropropane	12.06		15	0.186	13.90	0.180	11.56
T	1,2,4-Trichlorobenzene	12.95		15	1.211	12.42	1.250	8.76
T	Naphthalene	13.10		15	2.879	5.54	2.852	5.32
T	Hexachlorobutadiene	13.16		15	0.750	24.53	0.809	10.56
T	1,2,3-Trichlorobenzene	13.22		15	1.196	11.09	1.226	9.06
	Average %RSD of targets				9.07		4.60	
	Average %RSD of all compounds					8.22		4.23

*Compound designations as follows: T (target); SPCC (system performance check compound); CCC (calibration check compound); Surr (surrogate); ISTD (internal standard). Target compounds may also be designated as SPCCs or CCCs.

**The minimum average RF that must be met for the SPCCs.

***The maximum %RSD of the RFs. If any one or more of the CCC RF RSDs exceeds 30%, instrument maintenance is required. If the RF %RSD for any target compound exceeds 15%, other curve fits must be substituted for the average RF.

Method 8260B Requirements

Below is a summary of the most significant requirements of Method 8260B. If you are already very familiar with this method, you may want to skip this section.

ISTDs and surrogates: The ISTDs and surrogates listed in Table 4 are the recommended compounds for this method, although other compounds may be used instead.

Tuning requirements: Prior to running samples, the MSD must be adjusted so as to pass Method 8260B's BFB tuning specifications [1]. However, the method allows users to substitute CLP [4], Method 524.2 [3] or manufacturers' instructions for the specified BFB ion ratios. Table 5 lists the BFB tuning specifications for all three EPA methods. A scan range of 35–260 *m/z* is recommended.

Table 5. Criteria for BFB Tuning for Three Capillary GC/MS Volatiles Methods

Mass (<i>m/z</i>)	Relative abundance criteria		
	Method 524.2	Method 8260B*	CLP-SOW
50	15%–40% of 95	Same**	8%–40% of 95
75	30%–80% of 95	30%–60% of 95	30%–66 % of 95
95	Base Peak, 100%	Same	Same**
96	5%–9% of 95	Same	Same
173	<2% of 174	Same	Same
174	>50% of 95	Same	50%–120% of 95
175	5%–9% of 174	Same	4%–9% of 174
176	>95% but <101% of 174	Same	93%–101% of 174
177	5%–9% of 176	Same	Same

*Alternative tuning criteria may be used (for example, CLP or Method 524.2) including manufacturer's instructions provided that method performance is not adversely affected.

**"Same" implies that this requirement is the same as that shown for Method 524.2. Note, however, that alternative tuning criteria may be used for Method 8260B (see previous footnote).

System Performance Check Compounds (SPCCs): The SPCCs are used to check the performance of the system after calibration and before analysis of samples. These compounds are known to be sensitive to active sites and instrument contamination. They must meet a minimum RF that is specified in Table 4.

Calibration Requirements: As a minimum, Method 8260B requires a five-point calibration curve. In order to assume linearity of the calibration curve, the RF RSD of all target compounds must be less than or equal to 15%. Six analytes are designated as Calibration Check Compounds (CCCs) (Table 4). If the RF RSDs for any of these compounds exceeds 30%, it is indicative of instrument problems and repairs must be made. Compounds that exceed 15% RSD for their RFs can use alternative curve fitting methods as specified in EPA Method 8000B [5].

GC/MS Calibration Verification for Each 12-hour Shift: The P&T/GC/MSD performance must be re-evaluated every 12 hours. The most significant requirements are:

- The BFB tune must be rechecked and pass the original tuning requirements.
- A sample near the midpoint of the calibration curve must be analyzed using P&T sample introduction, demonstrating that:
 - Each SPCC meets its minimum RF.
 - The percent difference (between current and original response) must be less than 20% for each CCC.

- The retention time of each ISTD must not drift by more than 30 s.
- The ISTD areas must not change by more than a factor of 2 from the original mid-point calibration level (50% to 200%).
- A method blank must be run to show that there is no carryover or contamination of the system.

Calibration Results

Many laboratories employing Method 8260B generate five-point calibration curves between 5 and 200 µg/L. Knowing that laboratories often try to extend this range at both ends, an eight-point calibration was run at 1, 2, 5, 20, 50, 100, 200, and 300 µg/L. The signals for all analytes at 1 µg/L were sufficient to allow calibration at even lower levels. However, the lowest calibration level run for this work was 1 µg/L. Figure 2 shows a chromatogram of the targets, surrogates, and ISTDs at 50 µg/L each.




Figure 2. P&T/GC/MS analysis of a standard containing all of the compounds listed in Table 4, each at 50 µg/L in VOC-free water.

The average RF and %RSD of the RFs were calculated for each compound over the 1–300 µg/L and 1–200 µg/L ranges. As seen in Table 4, all five of the SPCCs exceeded their minimum RFs by a comfortable margin for both calibration ranges.

As mentioned above, the CCC RF RSDs must not exceed 30%. Table 4 shows that all six CCCs were significantly less than this for both calibration ranges. In fact, the average %RSD of the CCCs was only 4.90% for the 1–300 µg/L calibration and a remarkably small 1.58% in the narrower 1–200 µg/L range.

Only eight compounds exceeded the 15% RSD requirement in the 1–300 µg/L calibration range.

In all cases, the RF fell off significantly for the 300 µg/L standard, suggesting that the strong target ion response overloaded the MSD at that very high concentration.

In the 1–200 µg/L calibration range, the average RF could be used for all targets except, perhaps, bromoform which exceeded the 15% limit by 0.08%. If one justifies only two significant figures, even bromoform could use an average RF for calibrations. The average of the %RSDs for all targets was 8.9% for the 1–300 µg/L calibration and only 4.5% for the 1–200 µg/L range (Table 4). Figure 3 shows a plot of the RFs for each target compound over the 1–200 µg/L calibration range.




Figure 3. Plot of the RFs from a seven-level calibration for all of the target compounds listed in Table 4. Concentrations were at 1, 2, 5, 20, 50, 100, and 200 $\mu\text{g/L}$.

Figure 4 plots a distribution of the RF %RSD values for the 59 calibrated peaks (m- and p-Xylene were not resolved). It shows that most compounds have RFs over the 1–200 $\mu\text{g/L}$ calibration range with less than six percent RSD. More than 91% of the compounds have RSD values of 10% or less.




Figure 4. Distribution of the RF RSDs for the 59 calibrated peaks (m- and p-xylene were not resolved).

Response Stability

The longevity of any calibration depends upon having a consistent response for all compounds, even when running samples almost continuously over the course of several days, weeks, or even months. Some laboratories have observed a falloff in response over time that can jeopardize the calibration. Moreover, it has been observed that the recoveries for certain compounds may be dependent upon the presence or absence of other VOCs in the sample. A complete discussion of this problem and some simple solutions for it may be found in the “Optimization Techniques” section below.

In order to assess instrument stability over time, two types of samples were prepared. “System Blanks” contained only FBz, BFB, and 1,2-dichlorobenzene- d_4 (DCB- d_4) at 10 $\mu\text{g/L}$ in water. The first compound was used as the ISTD while the latter

two were chosen as surrogates. “Spiked” samples were the same as the system blanks but with the 60 target VOCs added at 20 $\mu\text{g/L}$ each. These samples were analyzed alternately, typically for 22 runs, but sometimes many more runs over several days.

Figure 5 is a plot of the normalized recoveries for FBz, BFB, and DCB- d_4 . It illustrates the two problems that can be observed when instrument parameters are not optimized. First, there is a gradual drop in response for all three compounds as illustrated by the sloping arrows. Superimposed upon this is a reduction in surrogate recovery in the absence of added VOCs. Because system blanks and spiked samples were alternated in the sequence, there was a “zigzag” appearance to the plot.




Figure 5. Normalized recoveries for FBz, BFB, and 1,2-DCB- d_4 . System blanks (containing only FBz, BFB, and DCB- d_4 at 10 $\mu\text{g/L}$ each) were analyzed alternately with system blanks spiked with an additional 60 VOCs at 20 $\mu\text{g/L}$ each. Arrows show a gradual loss of response over the course of the sequence. The zigzag pattern arises because the recovery of BFB and DCB- d_4 is higher in the presence of other VOCs.

The problems illustrated in Figure 5 can be avoided rather easily by not overloading the MSD's electron multiplier (EM) and by ensuring that there are no active sites in the sample flow path. Figure 6 shows normalized recovery plots for BFB and DCB-d₄ that are typical when the instrument parameters are set correctly. Once again, system blanks and spiked samples were alternated, but this time there was no drop in response over time. Surrogate recovery was independent of sample spiking. Simple solutions for resolving these problems are discussed below.




Figure 6. Normalized recovery for BFB (6A) and DCB-d₄ (6B) using the Agilent 6890N/5973 inert GC/MS coupled to the Velocity XPT P&T with optimized system parameters.

Optimization Techniques

MSD Tuning: Application Note 5988-4373EN [6] discusses three different ways to tune Agilent's 5973N MSD in order to meet BFB requirements. With the recent introduction of the 5973 inert MSD, these procedures still apply, though it is helpful to turn off the variable entrance lens setting when using the BFB autotune. The CLP Statement of Work specifications (Table 5) offers more latitude than the 8260B tuning requirements. Most importantly, ion 174 can be up to 120% of ion 95 (the reference ion). It is helpful to tune the MSD so as to produce a 174/95 ion ratio that is in the 90%–120% range because this improves the signal for bromoform (base peak = 173), which purges with poor efficiency. For this work, the “modified autotune” method was used and the 174/95 ratio was about 105%. It has been our experience that once the Agilent 5973 inert has been tuned to meet BFB requirements, the tune is stable for many weeks. It is impossible to say how long, because once tuned, it never failed to pass the BFB requirements.

MSD Parameter Optimization: When ISTD or surrogate responses fall off with repeated injections, overloading the Agilent 5973 MSD's high energy dynode (HED) EM may be the cause. The 5973 was designed to be significantly more sensitive than its predecessors and incorporates an HED in the EM. This reduces the noise and increases the signal, especially for ions of higher mass. However, this highly sensitive detector can be overloaded by continuous ion bombardment or by operating it at too high a voltage. The symptom is an unusually large loss of response over time.

Many GC/MS users erroneously believe that they can increase the sensitivity of their MSD by increasing the EM voltage. This can be done by raising the target value during tuning or by adding voltage to the tune value in the “MS SIM/Scan Parameters” window. However, in the electron impact mode, the noise increases at approximately the same rate as the signal. So, the true sensitivity (signal/noise) does not increase. The main consequence is to reduce the EM's lifetime. This can show up as a reduced response over time that might even be noticeable after several runs. (Note that these statements about signal/noise ratios do not necessarily apply to chemical ionization techniques.)

The solution to this “problem” is relatively simple. The easiest way is to reduce the EM voltage, which reduces the signal and noise, but not the signal/noise ratio. It may also be necessary to reduce the threshold value in the “Edit Scan Parameters” window in order to see the smaller ions. The default EM voltage values from an Autotune or BFB tune are usually correct, but these can be decreased somewhat if the above-mentioned symptoms occur.

It is easier to overload the EM in the selected ion monitoring (SIM) mode, because only a few ion fragments are monitored. During peak elution in the scan mode, there are “blank” spaces in all spectra where the signal is small or zero. With SIM, the signal is almost continuous and the ions monitored are usually the most abundant ones. Here again, the solution is relatively simple. One can reduce the EM voltage, decrease the SIM dwell time, and/or reduce the peak width by choosing the “High Resolution” option. The latter two values are set in the “Edit SIM Parameters” window. In any case, it is important to remember that both signal and noise are roughly proportional to the EM voltage and nothing is sacrificed by making small reductions in its value. Just remember to lower the threshold value or set it to 0 at the same time.

Reducing System Activity: When surrogate recoveries are higher in the presence of other analytes, as illustrated in Figure 5, active sites in the sample flow path are a likely cause. Surrogates can adsorb on these active sites, reducing their recovery. Surrogate recoveries improve when other analytes are present that compete for the active sites. To prevent such problems, one must use a highly inert P&T/GC/MS system and maintain its cleanliness by avoiding contamination from foaming samples. The Agilent 6890N/5973 inert GC/MS coupled to the Velocity XPT P&T showed no signs of sample adsorption. As seen in Figure 6, surrogate recoveries were highly stable with this system. If target or surrogate recoveries vary depending upon the presence of other analytes, it may be helpful to increase the temperature of the MSD source or upgrade an older 5973A or N with the new “Inert” source.

The P&T Method and Water Management: The VOC Teklink software used to control the new Teledyne Tekmar Velocity XPT concentrator and Aquatek 70 autosampler offers a “wizard” tool to help the user choose parameters for the method. Only minor modifications were made to the wizard-generated method. ISTDs were added manually to each sample so the “Fill I.S. Time” was set to 0.00 min. The bake time was increased to 3 minutes and the number of bake rinses was increased to three. The wizard chose all other parameters after the user provided information about the system configuration.

One of the primary concerns of P&T/GC/MS methods is the management of water that is inevitably purged along with the analytes. Since calibration, surrogate, and ISTD solutions are prepared in methanol, some of this solvent is also purged and retained by the trap. By starting the scan at 40 μ , methanol and water ions were not detected by the MSD. Nevertheless, transferring large amounts of water or methanol from the P&T to the GC/MS can result in poor reproducibility for those compounds that co-elute with them. Using the Velocity XPT with the Agilent 6890N/5973 inert system there were no problems that could be attributed to water. Because the P&T was configured with a Vocarb 3000 trap, the DryFlow trap was not required. Various dry purge times and flow rates were tried, but the only affect this had was to distort the peak shape of one or more early eluting peaks. Therefore, the dry purge option was not used. It is likely that some problems attributed to an excess of water actually result from overloading the MSD EM.

Standard preparation: The careful preparation of standards for calibration cannot be overemphasized. As with most laboratories, the initial dilutions were purchased as 2000 $\mu\text{g/mL}$ /component concentrates, which were stored without problem in a refrigerator. Experience in this laboratory showed that best results were obtained when observing the following guidelines:

- Prepare secondary dilutions used for sample spiking from freshly opened standards.

- Transfer secondary dilutions to appropriately sized glass containers so that there is little or no headspace in the vial. Store small quantities in microvials.
- Mininert vial closures were tried for sample storage but were prone to leakage and their use was discontinued. In addition, they were not available for microvials.
- It works well to prepare calibration standards by spiking methanolic solutions into pure water through the septum of the VOA vial. It works equally well to prepare standards in 50- or 100-mL volumetric flasks and pour the aqueous solutions into VOA vials.
- If several VOA vials of the same solution are being prepared at one time, do not prepare the solution in a single large volumetric flask. There will be some VOC loss by pouring repeatedly from the flask. Instead, spike vials individually or use the apparatus described in Figure 1 for sample transfer.
- When preparing calibration standards, transfer the same amount of methanolic solution to each VOC sample. This requires preparing secondary dilutions in methanol for each calibration level instead of spiking different amounts of a single standard.

Leaks: Leaks anywhere in the system can result in poor precision, loss of sample, and calibration failure. Leaks in the carrier gas flow path can easily be detected by the MSD as a high background of oxygen and nitrogen. To correct leaks, tighten or replace the offending fittings after finding the leaks using established techniques. A more difficult problem to detect results from leaks in the fittings that connect the purge vessel to the P&T instrument. Even the smallest leaks during the purge cycle can result in the loss of VOCs and cause poor precision. Leaks that a helium leak detector might miss, can still cause VOC loss. If all the RFs for a given calibration level seem to be low by a similar amount, or if the RF RSDs are all very similar (but too large), then P&T leaks are the likely cause. Tighten or replace the fittings associated with the purge vessel.

Conclusions

EPA Method 8260B with P&T sample introduction is one of the most widely used water analysis methods. There are numerous P&T, GC, and MS variables to optimize in order to obtain long-lasting linear calibration curves and good analytical results. This application note summarizes much of Agilent's experience in optimizing all facets of this VOC method. Most analysts know how to prepare calibration and check samples, tune the MSD, and set instrument parameters; and they find this method to be very rugged with infrequent need for retuning and recalibration. The suggestions in this paper are designed to help in case problems do arise or when an analyst runs this method for the first time. Though the focus was on Method 8260B, these techniques apply to almost any P&T/GC/MS method.

References

1. "Volatile Organic Compounds by Gas Chromatography/Mass Spectrometry (GC/MS)," U.S. Environmental Protection Agency, Office of Solid Waste, SW-846 Method 8260B, revision 2, December 1996
(<http://www.epa.gov/epaoswer/hazwaste/test/pdfs/8260b.pdf>).
2. "Purge-and-Trap for Aqueous Samples," U.S. Environmental Protection Agency, Office of Solid Waste, SW-846 Method 5030C, revision 3, May 2003
(<http://www.epa.gov/SW-846/pdfs/5030c.pdf>)
3. "Methods for the Determination of Organic Compounds in Drinking Water-Supplement III (EPA/600/R-95-131)," Method 524.2, revision 4.1, U.S. Environmental Protection Agency, Office of Research and Development, National Exposure Research Laboratory, Cincinnati, OH (1995).
4. "USEPA Contract Laboratory Program Statement of Work for Organics Analysis, Multi-Media, Multi-Concentration, OLM04.2," USEPA Contract Laboratory Program, Office of Emergency and Remedial Response
(<http://www.epa.gov/superfund/programs/clp/olm4.htm>).
5. "Determinative Chromatographic Separations," U.S. Environmental Protection Agency, Office of Solid Waste, SW-846 Method 8000B, revision 2, December 1996
(<http://www.epa.gov/epaoswer/hazwaste/test/pdfs/8000b.pdf>)
6. Philip L. Wylie, "BFB Tuning for Environmental Analysis: Three Ways to Succeed," Agilent Technologies publication 5988-4373EN
(<http://www.chem.agilent.com/temp/rad48994/00031636.pdf>)

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
February 25, 2004
5989-0603EN



Agilent Technologies



Stir Bar Sorptive Extraction: A New Way to Extract Off-Flavor Compounds in the Aquatic Environment

Application

Food and Flavors

Authors

D. Benanou, F. Acobas and M.R. De Roubin
Anjou Recherche, Analytical Research Department
1 place de Turenne
94417 Saint-Maurice
France
(E-mail: david.benanou@generale-des-eaux.net;
francoise.acobas@generale-des-eaux.net)

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA
(E-mail: phil_wylie@agilent.com)

Abstract

The objective of this study was to analyze organic off-flavors in water by gas chromatography/mass spectrometry (GC/MS) using Stir Bar Sorptive Extraction (SBSE). Six compounds were quantitatively determined using Selected Ion Monitoring (SIM): 2-methylisoborneol (MIB), geosmin, 2,4,6-trichloroanisole, 2,3,6-trichloroanisole, 2,3,4-trichloroanisole and 2,4,6-tribromoanisole. The Limit of Quantification (LOQ) was found to be from 0.1 ng/L to 0.2 ng/L for haloanisoles, 0.5 ng/L for geosmin and 1 ng/L for MIB. Relative standard deviation at the quantification limit ranges from 7% to 14.6%. Recovery was evaluated by spiking real water samples. It ranged from 80% to 120% depending on the compound. GC/MS detection in the

scanning mode combined with olfactometry were used for qualitative analysis in order to characterize new odorous compounds. Using this technique, it was possible to extract and analyze more than 20 samples a day.

Introduction

Complaints received by water companies are most often due to bad taste and odors in drinking water. Furthermore, the presence of these unpleasant tasting but otherwise harmless compounds can be taken as unsafe water by the consumer. In most cases, complaints concern chlorine and earthy/musty smelling compounds. A better understanding of the chemical causes of taste and odors in drinking water supplies would help in the control of taste and odor problems.

For 30 years, it was commonly accepted that earthy/musty aromas in drinking water were associated with the presence of geosmin, MIB and/or haloanisoles [1, 2, 3]. MIB and geosmin have strong odors, which are detectable at extremely low thresholds. MIB has a woody or camphor odor, detectable at a threshold ranging from 5 to 10 ng/L, while geosmin has a characteristic earthy odor detectable in water at a threshold ranging from 1 to 10 ng/L [4, 5]. The presence of these compounds in water was previously associated with the presence of actinomycetes or their metabolic products [6, 7, 8] in raw water, as well as cyanobacteria and fungi [9, 10, 11]. Haloanisoles have a



Agilent Technologies

musty odor at a low threshold. For instance, the threshold odor of 2,4,6-trichloroanisole ranges from 0.05 to 4 ng/L. Their formation is probably caused by microbiological methylation of halophenols during water treatment or during transport through the distribution system [12, 13, 14]. Halophenols are formed during chlorine disinfection of drinking water and some of them have been identified as natural halogenation products [15].

For a long time, the identification of these compounds in water has been a real analytical problem because they are odorous at very low concentrations. The main analytical method used to identify odorous compounds in water is Closed Loop Stripping Analysis (CLSA). With this method [16, 17], organic substances are released from the water sample in a hermetically sealed, closed circuit system, which uses air or inert gas at 40 °C to strip away the volatiles. These liberated substances are transferred to a very small amount of charcoal localized in the closed circuit. Finally, the organic substances are eluted from the charcoal with solvent and are analyzed by GC. "Purge and Trap" analysis is based on the same principles as CLSA, but it exhibits lower sensitivity and, therefore, is very useful for concentration levels above 100 ng/L. Nevertheless, these "stripping" techniques were not

efficient enough for less volatile and/or more polar compounds. Some authors have used solid phase micro extraction (SPME) [18]. From a chromatographic point of view, GC linked with MS is the only detection method, which combines high powers of separation, identification, and quantitation.

Today, a novel extraction technique that is sensitive, simple, and fast is an alternative choice to conventional stripping methods. This SBSE technique is based on sorption instead of adsorption. The principle includes a magnetic stirring bar incorporated into a glass jacket coated with a 0.5-mm layer of polydimethylsiloxane (PDMS). Extraction is performed by placing a suitable sample amount in a vial, adding a stir bar, and stirring for 30 to 120 min. After extraction, the stir bar is introduced into a glass desorption tube and placed in a thermal desorption unit where it is desorbed at 200–300 °C. Compounds are detected using GC/MS.

The aim of the present study was to analyze six odorous organic compounds in water with the SBSE technique. These compounds (Table 1) must be quantified at the subnanogram/L level, under or close to their odor threshold.

Table 1. Analyzed Odorous Compounds

Name	Abbreviation	Taste	Odor threshold, ng/L	CAS number
2-methylisoborneol	MIB	Earthy	5–10	N/A
2,4,6-trichloroanisole	2,4,6-TCA	Musty	0.1–2	6130-75-2
2,3,6-trichloroanisole	2,3,6-TCA	Musty	0.1–2	50375-10-5
Geosmin	Geosmin	Camphor	1–10	19700-21-1
2,3,4-trichloroanisole	2,3,4-TCA	Musty	0.2–2	54135-80-7
2,4,6-tribromoanisole	2,4,6-TBA	Musty	0.15–10	607-99-8

Principles of SBSE

The analysis of odorous organic compounds in aqueous environmental samples must be performed after extraction and enrichment of the solutes from the matrix. Some 10 years ago, a new method was developed called SPME. With this extraction based on sorption, a relatively thin layer of PDMS (7–100 μm) coated on the outside of a needle device was used as the extraction medium. Sorptive enrichment offers several advantages over adsorption processes. These advantages include:

- Predictable sorption thanks to calculated or experimental $K_{O/W}$ [19]
- Absence of displacement effect (no breakthrough volume)
- Faster and milder desorption

In contrast to stripping techniques, SPME and SBSE are equilibrium techniques by nature, based on the partitioning of the solutes between the PDMS phase and the aqueous (or gas) matrix. In fact, the principle of these techniques is the same as liquid-liquid extraction (LLE), but with a very low quantity of solvent (0.5 μL of PDMS for SPME and 24 to 100 μL of PDMS for SBSE).

The theory of SBSE is straightforward and similar to SPME. With the approximation that the partitioning coefficient between PDMS and water ($K_{PDMS/W}$) is proportional [19] to the octanol-water partitioning coefficient ($K_{O/W}$), it can be shown that equilibrium is based on Equation 1. Recovery (R) is based on Equation 2 where m_{PDMS} is the quantity absorbed in the PDMS phase, m_W is the quantity of non-extracted analyte, β is the ratio of the volume of water/the volume of PDMS, and m_0 is the initial quantity.

$$1. \quad K_{O/W} \approx K_{PDMS/W} = \frac{C_{PDMS}}{C_W} = \frac{m_{PDMS}}{m_W} \times \frac{m_{PDMS}}{m_W} = \frac{m_{PDMS}}{m_W} \times \beta$$

$$2. \quad R = \frac{m_{PDMS}}{m_0} = \frac{\left(\frac{K_{O/W}}{\beta}\right)}{1 + \left(\frac{K_{O/W}}{\beta}\right)}$$

The only parameter governing the recovery of an analyte from the sample is the ratio of distribution coefficient and the phase ratio between the PDMS coated on the stir bar and the water sample.

Figure 1 illustrates the extraction recovery of a compound as a function of $K_{O/W}/\beta$ ratio. At a $K_{O/W}/\beta=1$, the recovery is 50%. At low $K_{O/W}/\beta$ values, the recovery is closely proportional to $K_{O/W}/\beta$ and extraction is minimal.




Figure 1. Recovery as a function of octanol-water partitioning constant and phase ratio.

In SPME, the maximum volume of PDMS coated on the fiber is 0.5 μL . For a typical sample volume of 10 mL, the phase ratio equals 2×10^4 . This implies that quantitative extraction is only obtained for compounds with a $K_{O/W}$ in excess of 10^5 . Only a very limited number of components exhibit such high $K_{O/W}$ values and, moreover, it was recently shown [20] that this type of apolar solute strongly adsorbs onto the stir bar and glass vial, as used in SPME. In SBSE, on the other hand, the situation is more favorable. A stir bar coated with 100 μL of PDMS can easily be used to extract 10 mL of water leading to a β factor of 100, which implies that solutes with $K_{O/W}$ in excess of 500 are quantitatively extracted into the PDMS coated stir bar. This not only renders quantification straightforward but also ensures a significant sensitivity for those compounds with $K_{O/W}$ below 10^5 .

In Figure 2, the theoretical extraction recovery of analytes from a 10-mL water sample is shown for SPME and SBSE. It is clear that quantitative extraction is obtained at much lower $K_{O/W}$ in SBSE compared to SPME. This is due solely to the much lower phase ratio in SBSE. In case of incomplete extraction with SBSE, calibration is still possible using water samples with known concentrations of the target solutes.




Figure 2 . Theoretical recovery as a function of octanol-water partitioning constant and typical phase ratio for SBSE and SPME (that is, the volume of PDMS on the SPME fiber = 0.5 μ L, the volume of PDMS on the SBSE stir bar = 100 μ L, and the volume of extracted water = 10.0 mL).

So far, the discussion has been limited to the equilibrium conditions of SBSE. However, considering the thickness of the coating (0.5 or 1 mm), the speed of extraction (required equilibration time) is also an important factor to consider. Due to the thickness of the coating, it is assumed that all resistance to mass transfer is in the coating and that the sample is perfectly stirred. For this situation it is possible to apply Equation 3 [21]

$$3. \quad t_{95\%} = \frac{d_{PDMS}^2}{2D_{PDMS}}$$

where $t_{95\%}$ is the time required to reach 95% extraction, d_{PDMS} is the thickness of the PDMS layer used (in meter), and D_{PDMS} is the diffusion coefficient of the analyte under investigation in PDMS, in m^2/s . For instance, for benzene ($D_{PDMS}=2.5 \cdot 10^{-10} m^2/s$) the equilibration time is 30 minutes.

Experimental

Equipment

The gas chromatograph used was an Agilent 6890 - Agilent 5973 MSD (Agilent Technologies, Palo Alto, CA, USA)-olfactometric detector combination (GERSTEL® GmbH, Mülheim a/d Rhur, Germany). This chromatograph was equipped with a thermal desorption unit (TDSA) and a PTV inlet (CIS-4) from GERSTEL GmbH, Mülheim a/d Rhur, Germany.

Samples were extracted with 20-mm long stir bars (also called GERSTEL-Twister®) having a 0.5-mm layer of PDMS. The stir bar was thermally

desorbed in the splitless mode using the following desorption temperature program: 30 °C (0.8 min), 60 °C/min to 280 °C (5 min). The desorbed solutes were cryofocused in the CIS-4 at -100 °C. After the stir bar desorption, the PTV inlet was programmed to 300 °C at 10 °C/s and held for 2 min. Injection was done in solvent vent mode. The compounds were separated on a 30 m $\times$ 0.25 mm id $\times$ 0.25 μ m HP5-MS capillary column using helium carrier gas at 1.5 mL/min (constant flow). The oven was programmed from 50 °C (2 min) to 200 °C at 10 °C/min then to 300 °C at 25 °C/min (2 min). Detection was achieved in SIM mode for quantitative analysis and in scan mode for qualitative analysis. The olfactometer transfer line was heated at 250 °C. One-third of the effluent was directed to the mass spectrometer and two-thirds to the olfactometer.

Chemical Standards and Reagents

- Methanol (pesticide grade) obtained from Merck (Darmstadt, Germany)
- Spring water to prepare blanks and standards
- The standard compounds 2-methylisoborneol; 2,4,6-trichloroanisole; 2,3,6-trichloroanisole; 2,3,4-trichloroanisole; 2,4,6-tribromoanisole; geosmin; and 2,4,6-trichloroanisole- d_5 obtained from Promochem (France).
- A stock solution containing MIB, geosmin, and the haloanisoles at 1 μ g/L was prepared in spring water. Storage conditions for this stock solution: 4 °C for 1 month.
- An internal standard solution of 2,4,6-TCA- d_5 prepared in spring water at 20 μ g/L. Storage conditions for this solution: 4 °C for 1 month.

Extraction Procedure

Extractions were performed in duplicate by placing a Twister (20-mm long, 0.5 mm of PDMS) into a 125-mL vial with 100 mL of the water sample and 5 mL of methanol. Each vial was spiked with 40 μ L of the 2,4,6-TCA- d_5 internal standard solution. After stirring both samples for 2 hours at room temperature, the Twisters were removed from the duplicate samples and dried with a clean wipe. In order to increase sensitivity, both Twisters were introduced into a single glass desorption tube and desorbed using the conditions noted above.

Results and Discussion

Tuning the Mass Selective Detector (MSD)

To enhance sensitivity even further, the MSD was tuned manually in order to increase transmission of desired ions. Perfluoro-5,8-dimethyl-3,6,9-

trioxadodecane (PFDTD) was used as the calibrant. Conventional Autotunes are performed for optimum monitoring of the 69, 219, and 502 PFTBA ion ratios. The 219/69 and 502/69 ratios are usually about 60% and 3%, respectively, although this can vary considerably. Since the target compounds have masses ranging from 112 to 344, manual tuning was used to adjust the 219/69 ratio to 110% and the 414/69 ratio to 10%. The 414 ion was used instead of 502 because it is closer in mass to the target ions of the analytes. These ratios could be obtained using one of two procedures. The first approach was to ramp the repeller for ions 69, 219, and 414 and to choose the optimum response for 219. The second way was to perform a Target Tune by specifying the desired abundances and ion ratios for selected ions in the Agilent ChemStation.

This manual tune was used only for quantitative applications because structural information was not required. When using this manual tune, the Probability Based Matching System gave no satisfactory matching between an unknown and a reference spectrum from the NIST or Wiley libraries.

Mass Spectra of MIB, Geosmin and Haloanisoles

Figure 3 shows the experimental mass spectra for the target compounds listed in Table 1. For monitoring ions in the SIM mode, 95, 108, 110 were chosen for MIB, 112 and 125 for geosmin, 210 and 212 for the three chloroanisoles, 346 and 344 for the 2,4,6-tribromoanisole. The internal standard, 2,4,6-trichloroisole- d_5 , was monitored at m/z 217.




Figure 3. Experimental mass spectra of target compounds.

Figure 4 shows a SIM chromatogram of spring water spiked with 2 ng/L of each target compound.

Influence of Extraction Time

This experiment measured the sorption rates of compounds into PDMS. Spring water spiked with

2 ng/L of each compound was analyzed after extraction times ranging from 15 min to 300 min. Figure 5 shows the relationship between the extraction time and the response obtained for target compounds.




Figure 4. SIM chromatogram of target compounds.




Figure 5. Influence of extraction time upon quantity extracted on PDMS.

For all compounds, the sorption rate is fast for the first 120 minutes and then slows without reaching a plateau. For routine analysis with high sample throughput, an extraction time of 120 minutes was empirically chosen.

Influence of Sample Volume

According to Equation 2, maximum recovery can be estimated with the octanol/water distribution

Table 2. Octanol/Water Distribution Coefficients ($K_{O/W}$) of Investigated Compounds

Name	Experimental $\log K_{O/W}$	Calculated $\log K_{O/W}$
2-methylisoborneol	3.31	2.85
2,4,6-trichloroanisole	3.85	4.01
2,3,6-trichloroanisole	3.64	4.01
Geosmin	n/a	3.57
2,3,4-trichloroanisole	3.74	4.01
2,4,6-tribromoanisole	4.48	4.75

coefficient ($K_{O/W}$). Log $K_{O/W}$ values for the target compounds were experimentally determined and calculated using KnowWin software [19].

For this experiment, different sample volumes of spring water from 10 to 200 mL were spiked with 1 ng of each compound. Extraction was done for 2 hours with a 2-cm long Twister (47 μ L PDMS). Figure 6 shows experimental recoveries (A) compared to theoretical recoveries estimated using calculated $K_{O/W}$ (B) and experimental $K_{O/W}$ (C) values.

Experimental results were in accordance with theory (the more sample volume increases, the more the recovery decreases), but were inferior to expected values. This experiment proved that equilibrium was not reached after 2 hours of stirring. The difference between experimental and expected values increased when the sample volume increased and it was dependant on the compound.




Figure 6. Influence of sample volume on recovery. A: Experimental results, B: Theoretical results (calculated $K_{O/W}$), C: Theoretical results (experimental $K_{O/W}$).

However, the enrichment on the PDMS media increases with the sample volume as shown in Figure 7. For most of the compounds, the extracted amount increases up to 100 mL of the sample and a volume of 200 mL does not lead to a significant gain in response. In order to achieve concentrations close to the odor threshold, it was necessary to use two 100-mL aliquots of each sample and two Twisters, which were desorbed together.




Figure 7. Influence of sample volume on quantity extracted.

Influence of Storage After Extraction

Extraction of a spring water sample spiked with 2 ng/L of each compound was replicated six times; each 100-mL sample was extracted by one Twister for 2 hours. One Twister was analyzed immediately and the others were stored at 4 °C in closed vials for later analysis. Figure 8 shows the influence of storage time on the response for all compounds.

These results show that no compound loss occurs during 1 week of storage and imply that:

- It is possible to store the Twister after extraction instead of storing water samples when the chromatographic analysis cannot be done immediately.
- Instead of sending bad tasting or odorous water samples to the laboratory, it would be possible to extract off-flavor compounds directly at the consumer's home.

Method Validation

This method was validated according to the AFNOR regulation XP T 90-210. This validation determines the following:

- The scope of linearity: linearity was studied over seven concentration levels, from 0.1 to 10 ng/L, replicated five times. Calibration was done in internal standard mode with 2,4,6-TCA-d₅. Linearity is achieved when the correlation coefficient (R) is better than 0.999.
- The LOQ is validated when the relative standard deviation (RSD) of 10 replicate samples, spiked with supposed LOQ, is under 20%.
- The repeatability is expressed as %RSD and is calculated on the basis of three replicates of eight different water samples. It must be under 20%.
- The trueness is expressed as the percent recovery of spiked real water samples and must be between 80% and 120%.
- The reproducibility is expressed as a %RSD of a check calibration standard (2 ng/L). It must be under 20%.




Figure 8. Influence of Twister storage time after extraction.

The results of this validation are summarized in Table 3 and in the calibration curves shown in Figure 9.

Table 3. Validation Results for Target Compounds

	R	LOQ, ng/L	Repeatability %	Trueness %	Reproducibility %
MIB	0.9987	1	4–10	89–110	13
2,4,6-TCA	0.9998	0.1	1–5	97–110	4
2,3,6-TCA	0.9998	0.1	4–11	97–117	5
Geosmin	0.9991	0.5	2–10	83–101	9
2,3,4-TCA	0.9998	0.2	7–15	87–110	13
2,4,6-TBA	1.0000	0.2	2–9	91–104	15




Figure 9. Calibration curves for investigated compounds.

The validation criteria were achieved for all target compounds.

Application to Real Water Samples

Different water samples were analyzed following complaints about taste and odor problems.

Case 1

Two samples (A and B) were collected at the consumer's home. Sample A gave a very pronounced musty odor and sample B gave a soft musty odor and a pronounced metallic odor. Samples A and B were treated by SBSE and analyzed in SIM mode in order to detect MIB, geosmin, and the haloanisoles.

Quantitative results and chromatograms for each sample appear in Table 4 and in Figure 10.

Table 4. Concentration of Target Compounds in Sample A and B

	Sample A [C] (ng/L)	Sample B [C] (ng/L)
2-methylisoborneol	<1	<1
2,4,6-trichloroanisole	8.9	0.2
2,3,6-trichloroanisole	<0.1	<0.1
Geosmin	5.2	<0.5
2,3,4-trichloroanisole	<0.2	<0.2
2,4,6-tribromoanisole	0.4	1.3




Figure 10. SIM chromatograms for samples A and B.

The concentration levels found in both samples can certainly explain the musty odor. In order to identify the other odorous compounds, the water samples were treated another time by SBSE without internal standard, and the GC/MS was run in the scan mode.

For sample A, the olfactometric detection showed a pronounced musty odor at the retention times of 2,4,6-TCA and geosmin, but also a medicinal one at 8 minutes and a solvent-like one at 14 minutes. For sample B, the olfactometric detection gave a mild

musty odor at the retention time of 2,4,6-TBA and also a medicinal one around 8 minutes.

Interpretation of isotope ratios in the spectra for sample A showed two halogenated compounds - a brominated one (8.4 min) and a chlorinated one (13.9 min). The medicinal odor was associated with dibromiodomethane, which is a chlorination byproduct. The solvent odor was associated with tetrachlorobenzene as shown in Figure 11. For sample B, dibromiodomethane was also detected.




Figure 11. Sample A Scan chromatogram.

Case 2

In this case, an off-flavor episode occurred in a tank located near Paris. Degradation of the water's organoleptic quality was observed soon after some cracks appeared on the tank's coating and important living organisms were found on the interior surface. Following complaints, several flavor analyses were performed on water originating from the tank. Results indicated that the chlorinous taste of the treated water was masked by an intense musty taste (Threshold Test Number: 5).

Drinking water stored in this tank is produced from ground water which undergoes a two-step treatment process: the water first undergoes aeration and sand filtration for iron removal and then the water is chlorinated just prior to entering the tank. The tank's coating, which must provide an impermeable seal to the water during storage, is a synthetic coating prepared by mixing a gray elastic cement and a white synthetic resin in aqueous

solution. The theoretical mechanical and physical properties of this coating ensure high elasticity and no release of organic compounds. Filtered and chlorinated waters were treated by SBSE for quantitative analysis in order to search for the target odorous compounds.

Quantitative results and chromatograms of each sample appear in the Table 5 and in Figure 12.

Table 5. Concentration of Target Compounds in Filtered and Chlorinated Waters

	Filtered water [C] (ng/L)	Chlorinated water [C] (ng/L)
2-methylisoborneol	<1	<1
2,4,6-trichloroanisole	<0.1	<0.1
2,3,6-trichloroanisole	<0.1	<0.1
Geosmin	<0.5	<0.5
2,3,4-trichloroanisole	<0.2	<0.2
2,4,6-tribromoanisole	< 0.2	5.6




Figure 12. EIC (m/z : 346) of chlorinated and filtered water.

The only compound found among the six targets was 2,4,6-tribromoanisole at a concentration of 5.6 ng/L. The presence of 2,4,6-TBA can easily explain the significant musty taste imparted to the water. None of the target compounds was found in the filtered water.

GC with olfactometric detection of filtered water did not exhibit any of the characteristic odors. However, for chlorinated water, it gave a significant musty odor at the retention time of 2,4,6-TBA in addition to different phenolic odors at around 8, 14, and 17 minutes. In order to make phenolic compounds more amenable to GC, they were derivatized with 1 g of K_2CO_3 and 500 μ L of acetic anhydride for 100 mL of water sample. Detection was achieved in scan mode for qualitative analysis. Results obtained for both sniffing and MS detection appear in Table 6 and in the scan chromatogram in Figure 13.

Table 6. Odors Generated During the Chromatographic Run Time for Sample B

Tr (min)	Odor	Intensity	Qualification (acetate derivative)
8.5	Phenolic	++++	Phenol
13.7	Phenolic	++	2,4,6-trichlorophenol
15.9	Musty		2,4,6-tribromoanisole
16.8	Phenolic	+++	2,4,6-tribromophenol

According to these results, the hypothesis was that the tank's coating released phenol, which was halogenated to 2,4,6-TCP and 2,4,6-TBP because of the residual chlorine. 2,4,6-TBA was then synthesized by living organisms present at the surface of the coating. The authors cannot yet explain why only 2,4,6-TBA was formed by living organisms despite the presence of both 2,4,6-TCP and 2,4,6-TBP.

Case 3

This case consisted in studying deterioration in organoleptic quality of water along the network distribution system. The complaints came only from consumers who were located far from the treatment plant. Two samples were taken - the first one at the outlet of the treatment plant (sample A) and the second one at the consumer's home at the end of the network (sample B). Sample A gave only a chlorine odor whereas sample B gave musty, swampy, earthy odors (Threshold Test Number: >10).

The two samples were treated by SBSE in order to monitor MIB, geosmin, and haloanisols. The results showed that sample A was free of these compounds. In sample B, 2,4,6-TCA and 2,3,4-TCA were found at 0.1 ng/L and 0.2 ng/L, respectively. However, these concentrations cannot explain the significant taste and odor impairment. Fresh water samples were treated another time by SBSE without internal standard. These were analyzed by TDS/GC/MS in the scan mode and by olfactometry.




Figure 13. TIC of water sample after insitu-derivatization.

Olfactometry allowed the detection of various odors along the chromatographic run time for sample B, whereas nothing was smelled in sample A. The results for sample B for both sniffing and MS detection are listed in Table 7.

Table 7. Odors Generated During the Chromatographic Run Time for Sample B

Tr (min)	Odor	Qualification
7	Sweaty	Phenylacetaldehyde
7.8	Swampy	Dimethyltrisulfide
10.7	Citrus	Decanal
12	Flower	Undecanal
12.8	Sweaty	Not qualified
12.9 to 15.2	Musty	Alkylbromobenzene isomers
16.07	Rancid	Isopropyldecanoate
16.8 to 17.4	Tar	Diisopropyl-naphthalene
20.15	Tar	Dodecahydrophenanthrene

Seven different odors were detected by sniffing detection and some of them were in good agreement with the flavor profile analysis, as for instance, the swampy smell associated with dimethyl trisulfide. A musty odor was smelled from 13 to 15 minutes and was matched to different alkylbromobenzene isomers, of which the major component was 2-methyl-4-isopropylbromobenzene. Rancid and tar odors corresponded with isopropyldecanoate and dodecahydrophenanthrene, respectively. Pleasant odors like sweet and fruity (aldehyde compounds) were not detected by tasters.

Figure 14 shows the comparison of total ion chromatograms (TIC) of each compound that could be smelled in samples A and B.




Figure 14. EIC of samples A and B for dimethyltrisulfide, phenylacetaldehyde, decanal, alkylbromobenzene isomers, and diisopropyl-naphthalene.

Conclusions

- Most often, taste and odor problems in drinking water are due to very low traces of compounds present in a complex mixture. That is why GC/MS is the best separation and detection choice to quantify odorous compounds.
- A rapid SBSE-TD-GC/MS-Olfactometry method for the determination of MIB, geosmin, and haloanisol compounds in water samples was developed. The combination of TD-GC/MS and the SBSE made it possible to quantify all of the odorous components at levels close to or under their odor threshold limit.
- The influence of extraction time, sample volume, and storage time were studied in order to optimize the method's sensitivity. The final method was validated according to the AFNOR regulation. Linearity was checked with the correlation coefficient (R) ranging from 0.9987 to 1.0000. The repeatability and reproducibility values were under 15%. Recoveries were all between 87% and 117%, depending upon the compound.
- Storage time for Twisters is for at least 7 days after extraction without loss of the extracted compounds.
- When applied to real odorous water samples, SBSE showed a good correlation between flavor profile analysis, MS analysis, and olfactometric detection. In addition to the target compounds, it was possible to identify unknown odorous compounds at very low levels far more rapidly than possible using conventional techniques.

References

1. J. Mallevialle, and H. Suffet. Identification and treatment of tastes and odors in drinking water. *American Water Works Association*, Denver, Colorado. (1987).
2. S. E. Jensen, C. L. Anders, L. J. Goatcher, and S. E. Hrudey. Actinomycetes as a factor in odor problems affecting drinking water from the north Saskatchewan river. (1994) *Wat. Res.* **28(6)**, 1393-1401.
3. A. Bruchet. Solved and Unsolved Cases of Taste and Odor Episodes in the Files of Inspector Cluzeau. (1999) *Wat. Sci. Tech.* **40(6)**, 15-21.
4. H. Tuorila, T. Pyysalo, T. Hirvi. and Ad Venviläinen. Characterisation of odors in raw and tap water and their removal by ozonation. (1980) *Vatten* **3**, 191-199.
5. S. E. Hrudey, and N. J. Low. Discussion of : the effect of disinfectants on a geosmin-producing strain of *Streptomyces griseus*. (1992) *J. appl. Bact.* **73**, 445-446.
6. N. N. Gerber. Volatile substances from actinomycetes : their role in odor pollution of water. (1979) *CRC crit. Rev. Microbiol* **7**, 191-214.
7. R. C. Hoen. Causes biologiques du goût et des odeurs des approvisionnements en eau potable. OMS, (1988) *Bulletin de la qualité des eaux*, **13**, 2-3, 50-55.
8. I. E. Suffet, K. Djanette, and A. Bruchet. The Drinking Water Taste and Odor Wheel For the Millennium: Beyond Geosmin and 2-methylisoborneol. (1999) *Wat. Sci. Tech.* **40(6)**, 1-13.
9. M. Goodfellow, and S. T. Williams. Ecology of Actinomycetes. (1983) *Ann. Rev. Microbiol.* **37**, 189.
10. S. Wood, S. T. Williams, and W. R. White. Microbes as a source of earthy flavours in potable water-a review. (1983) *Int. Biodeterm. Bull.* **19**, 83-97.
11. C. P. Dionigi, D. F. Millie, A. M. Spanier, and P. B. Johnsen. Spore and geosmin production by *Streptomyces tendae* on several media. (1992) *J. Agric. F.J. Chem.* **40**, 122-125.
12. L. Malleret, and A. Bruchet. A Taste and Odor Episode caused by 246-Tribromoanisole. (2002) *Journ AWWA.* **94(7)**, 84-94.
13. A. Nyström, A. Grimvall, C. Krantz-Rülcker, R. Sävénhed, and K. Akerstrand. Drinking water off-flavour caused by 2,4,6-trichloroanisole. (1992) *At. Sci. Tech.* **25(2)**, 241-249.
14. A. Montiel, J. Ouvrard, S. Rigal, and G. Bousquet. Etude de l'origine et du mécanisme de formation de composés sapides responsables de goûts de moisi dans les eaux distribuées. (1987) *T. S.-M.-L'EAU* **82(2)**, 73-83.
15. C. Anselme, K. N'Guyen, A. Bruchet, and J. Mallevialle. Can polyethylene pipes impart odors in drinking water? (1985) *Environ. Tech-nol. Let* **6**, 477-488.
16. E. Baltussen, P. Sandra, F. David, and C. J. Cramer. Automated Sorptive Extraction-Thermal Desorption-Gas Chromatography-Mass Spectrometry. (1999) *Journ Microcol sep* **11**, 471.

17. M. J. McGuire, and G. Izaguirre. Close-Loop Stripping Analysis as a Tool for Solving Taste and Odor Problems. (1981) *Jour. AWWA* **73(10)**, 530-537.
18. L. S. De Bruin, P. D. Josephy, and J. B. Pawliszyn. Analysis of odorous compounds by SPME. (1998) *Anal. Chem.* **70**, 1986-1991.
19. W. Meylan, and P. Howard. (2000) *Log Octanol-Water Partition Coefficient estimation Program*. Syracuse Research Corporation.
20. E. Baltussen, S. Sandra, F. David, and C. J. Cramer. Stir Bar Sorptive Extraction (SBSE), a Novel Extraction Technique for Aqueous Samples: Theory and Principles. (1999) *Journ Microcol sep* **11**, 737-749.
21. J. Pawliszyn, (1997) *Solid Phase microextraction. Theory and Practice*, Wiley-VCH, p 61.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

For more information about semiconductor measurement capabilities, go to www.agilent.com/chem/semicon.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


GERSTEL and Twister are registered trademarks of GERSTEL GmbH & Co. KG.

© Agilent Technologies, Inc. 2003

Printed in the USA
March 31, 2003
5988-8900EN



Agilent Technologies



Analysis of Low Concentration Oxygenates in Environmental Water Samples Using Purge and Trap Concentration and Gas Chromatography/Mass Spectrometry

Environmental

Authors

Allen K. Vickers and Cameron George,
Agilent Technologies, Inc.
91 Blue Ravine Rd,
Folsom, CA
USA

Abstract

The frequent use of oxygenate additives in gasoline to produce clean burning fuels has led to widespread and well documented contamination of ground water and drinking water supplies. The phasing out of methyl tert-butyl ether (MTBE) as the oxygenate of choice has led to an increased interest in testing for other common additives. These other additives may be ethers, other than MTBE, but also methanol or ethanol may be considered. Traditional techniques used for the analysis of volatile organic compounds in drinking and ground waters frequently employ the use of a purge and trap concentrator interfaced with a gas chromatograph. Detectors being used range from photoionization detectors (PID) and electrolytic conductivity detectors (ELCD) to mass selective detectors (MSD). Mass spectrometry is becoming the detection mode of choice for these additives, as it provides an additional level of confirmatory confidence in the presence of many potential matrix interferences. However, the challenge of extracting extremely polar analytes from an aqueous matrix requires modification and optimization of the purge and trap concentrator from its typical settings. As laboratories are seeking to determine these polar additives in the low part-per-billion (ppb) range, it is important that all aspects of the system be optimized. This application note will discuss system settings necessary for achieving low level quantitation of additives such as methanol and ethanol.

Experimental

This work was performed using a 6890 Plus gas chromatograph equipped with a 5973 mass spectrometer (Agilent Technologies, Inc. Wilmington DE). The purge and trap (P&T) used in the study was a model 3100 obtained from Tekmar/Dohrman (Cincinnati, OH). The J&W Scientific brand capillary column used, DB-VRX, was obtained from Agilent Technologies Inc. (Folsom, CA).

All standards used were prepared in-house from neat materials. Standard solutions were prepared in purified water.

Discussion

More and more frequently environmental laboratories are being asked to analyze for oxygenated analytes in drinking, ground and wastewater samples using pre-existing P&T GC/MS technology. Analytes such as acetone, ethyl ether, methyl-*tert*-butyl ether (MTBE), *tert*-butanol (TBA) and 2-butanone (MEK) are common, but now labs are beginning to receive an increasing number of requests for methanol and ethanol. As some laboratories are reporting very low method detection limits for these polar analytes, it is becoming apparent to others that not matching these low levels may eventually result in a loss of business. This work was performed for two primary reasons:

- To optimize P&T system conditions in order to achieve the best sensitivity possible for oxygenates in water
- To ascertain whether or not the low detection levels being reported by laboratories are realistic and achievable



Agilent Technologies

The basic study design was as follows: Multiple replicates of an oxygenate standard (Table 1) were run using typical P&T conditions to establish a base response and to assure that reproducible results were being obtained. The %RSD for the multiple runs averaged 0.6%–0.8%. Once the base response was established analysts made modifications to the method parameters and charted any response changes for the same standard solution. Once the most significant modifications were defined they were combined to provide the best possible response enhancement. At this point a calibration curve was performed to establish that this technique was truly valid for quantitative work spanning a wide range of concentrations.

The oxygenate standard shown in Table 1 was prepared from neat materials in purified water and was used for all of the response enhancement work. Analytes are in solution at concentrations ranging from 5 to 500 µg/L. These concentrations were derived through experimentation using typical laboratory P&T conditions so that all of the peaks of interest were on the same scale at the beginning of the study.

Table 1. Maximizing Oxygenate Response Analyte Concentrations in Purged Standard

Compound	Concentration (µg/L)
Methanol	500
Ethanol	500
Acetone	50
Ethyl ether	5
<i>tert</i> -Butanol (TBA)	50
Methyl- <i>tert</i> -butyl ether (MTBE)	5
Methyl ethyl ketone (MEK)	50

All stock solution prepared in purified water

Figure 1 shows the chromatogram obtained for the oxygenates standard using typical P&T concentration conditions. Note that the abundance counts on the Y axis range up to approximately 35,000. This is an extracted ion chromatogram for *m/z* values of 31, 43, 73, and 59.

The primary variables considered in this work were:

- Purge gas flow
- Sample volume
- Sample temperature
- Matrix modification




Figure 1. Oxygenates standard run using typical P&T conditions and DB-VRX capillary column.

Purge Gas Flow

The purge-gas flow was not adjusted or modified from typical settings as in most cases the laboratory will use the same P&T/GC/MS system for this analysis as well as for their standard 8260B and 524.2 work. Purge flow in most, if not all, P&T systems is a manual adjustment. Purge flow has a definite impact upon analyte recovery and if it is not kept constant calibration curves may become invalid and need to be rerun. If purge flow were manually increased for the oxygenate work and manually adjusted back down to return to 8260B or 524.2 work, it may jeopardize the current calibration curve. In addition, excessive purge flow can lead to trap breakthrough for some of the more volatile analytes contained in such methods. It was deemed more important that laboratories be able to easily adopt the changes suggested here without causing any loss in productivity for other methods of interest. As such, a purge flow of 40 mL/min for 11 minutes was maintained.

Sample Volume

It was shown in O.I. Analytical application note number 13271198 that utilization of a 25 mL sample volume vs. the typical 5 mL results in better sensitivity and improved calibration reproducibility. In its simplest form, five times the sample means five times the nanogram amount in solution. This does not mean five times the response will be achieved for all analytes, but for most a significant increase in response will be noted. All subsequent work was performed using a 25 mL sample size.

Sample Temperature

Multiple runs were performed with the sample temperature at ambient, 45 °C, 55 °C, 65 °C, 75 °C and 85 °C. Figure 2 shows the response enhancement with temperature increase for each analyte in the oxygenate standard. The responses graphed are all relative to the sample purged at ambient temperature, which is considered 100% recovery. There is a consistent response increase with temperature up to 75 °C but at 85 °C a dramatic increase is noted. As the response increase was so significant at 85 °C, this temperature was considered optimum. The sample preheat (heating prior to purge) was set for 1 minute for all temperatures. In reality, after 1 minute the purge temperature had only reached approximately 55 °C. After 2 minutes the temperature was around 65 °C, 3 minutes was 75 °C and not until the 4-minute mark did the vessel actually reach 85 °C. While the temperature was not at the set-point when purging began, it was deemed as acceptable as the heating rate of the sample was very consistent and even in the worst case, with an 85 °C set-point, the sample was purged for 8 minutes at full temperature. Increasing the preheat time to 3 and 4 minutes did not result in any significant response improvement, but definitely increased the overall purge and trap cycle time, thus reducing sample throughput. One minute of preheat gave excellent response with a minimal cycle time.




Figure 2. Analyte response vs. sample temperature.

When heating the sample to this degree, the amount of moisture transferred to the sorbent trap is significant. One benefit of the Vocarb™ 3000 trap used in this work is that it is dry-purgeable. Whether or not the water is actually purged from the trap during this step or simply purged completely into an appropriate sorbent was not explored, but a benefit in chromatographic performance is evident (Figure 3).




Figure 3. Modifying P&T conditions—secondary effects of increased sample temperature.

Matrix Modification

It is well understood that increasing the ion content of an aqueous solution can lead to improved recovery of non-ionic organic species from that solution. The process of increasing the ion content is generally termed ‘Salting’. The primary considerations when salting a solution are what type of salt and how much salt to add. Table 2 refers to the benefits and drawbacks of several common salts. Considering the obvious drawbacks of sodium carbonate and potassium phosphate, this study focused on the use of sodium chloride and sodium sulfate. Figures 4 and 5 show the improved response achieved with different mass additions of both sodium chloride and sodium sulfate, respectively. Figure 6 gives a direct comparison of ‘no salt’ relative to optimum amounts of sodium chloride and sodium sulfate. It is obvious that sodium sulfate gives superior performance and, as it does not have the same corrosive characteristics as sodium chloride, it was chosen for all further work.

Table 2. The Benefits and Drawbacks of Several Common Salts

Compound	Results
Sodium chloride (NaCl)	Highly soluble in water (~8 g/25 mL), readily available, chlorine ion very reactive
Sodium sulfate (Na ₂ SO ₄)	Highly soluble in water (~6 g/25 mL), neutral pH in solution, 2 sodium ions per molecule of salt
Sodium carbonate (Na ₂ CO ₃)	Highly alkaline in solution
Potassium phosphate dibasic (K ₂ HPO ₄)	Extremely soluble in water (~37 g/25 mL), difficult to work with

Figure 4 shows the effect of sodium chloride salt quantity on response relative to the 'no salt' standard P&T conditions. Above 6 g of NaCl the salt was not dissolving completely into solution and so addition was stopped here.




Figure 4. The effect of sodium chloride salt quantity on response relative to the 'no salt' standard P&T conditions.

Figure 5 shows the effect of sodium sulfate salt amount on response relative to the 'no salt' standard P&T conditions. There is a distinct rise in response at 6 g as we approach full saturation of solution.




Figure 5. The effect of sodium sulfate salt amount on response relative to the 'no salt' standard P&T conditions.

In Figure 6, this combined bar-graph shows directly the response differences experienced with the two different types of salt (both at 6 g) relative to the 'no salt' standard P&T conditions. It is clear that there is a definite response advantage to using sodium sulfate vs. sodium chloride.




Figure 6. The response differences experienced with the two different types of salt relative to the 'no salt' standard P&T conditions.

Combining Parameters

Figure 7 shows the effect of temperature and salt addition alone, relative to standard conditions, but also shows how much more impact these modifications made once they were combined. For instance, *tert*-Butanol response was increased roughly 20 times using an 85 °C purge temperature and roughly 10 times using the addition of 6 g of sodium sulfate, but when these two modifications were combined it resulted in an overall response increase of over 75 times relative to standard P&T conditions.





Figure 7. Effect of combining optimized purge and trap parameters.

Table 3 shows the final optimized run conditions for this analysis. Figure 8 is a direct visual comparison of standard vs. optimized P&T conditions. Again, methanol and ethanol are spiked into solution at 500 ppb. Note the much smaller response for ethyl ether and MTBE in the optimized chromatogram. Recall that they are in solution at 5 ppb vs. 50 ppb for acetone, TBA and MEK and 500 ppb for methanol and ethanol.

Table 3. Optimized Run Conditions

Column:	DB-VRX
P/N:	121-1524
Length:	20 m
Diameter:	0.18 mm
Film thickness:	1.0 µm film
Carrier:	Helium at 45 cm/sec (1.0 mL/min)
Oven:	45 °C for 3.5 minutes 45–150 °C at 15 °C/min
Injector:	Tekmar 3100 Purge and Trap
Trap:	Vocarb 3000
Sample volume:	25 mL
Sample temp:	85 °C (1 minute preheat)
Purge:	11 Minutes
Dry purge:	3 Minutes
Desorb preheat:	245 °C
Desorb:	1 Minute at 250 °C
Bake:	10 Minutes at 260 °C
Line and valve temp:	125 °C
Interface:	Split injector at 200 °C, 60:1 Split ratio
Gas saver:	150 mL/min at 1 minute
Agilent 5973 MSD	
Scan range:	29-260 amu
Scan rate:	3.17 scans/sec
Quad temperature:	150 °C
Source temperature:	230 °C
Transfer line temp:	250 °C
Matrix modification:	6 g Sodium sulfate

Figure 8 shows a chromatographic comparison between typical and optimized P&T conditions. The 'Y' scales are normalized for comparative purposes.



Abundance normalized for comparative reasons

Figure 8. A chromatographic comparison between typical and optimized P&T conditions.

Performing a Calibration Curve

Eight points were used with the realistic expectation that not all analytes were going to be linear from 0.5 ppb up to 200 ppb. It was expected that the methanol and ethanol may not achieve single digit ppb levels. As expected, methanol was not able to be calibrated down to 0.5 ppb or even 5 ppb. At these lower concentrations the signal-to-noise ratio was simply too low to be reliable. At 10 ppb it was approaching a more reasonable 10:1 ratio. Figure 9 shows the calibration curve for methanol. Using linear regression per EPA methodology and a calibration range of 10–200 ppb the R-squared value was 0.9987, which is well above the EPA required 0.990 needed for valid quantitative use. Ethanol was calibrated from 0.5–200 ppb with an R-squared value of 0.998 (Figure 10). Both methanol and ethanol calibration ranges could likely be extended to well above 200 ppb.




Figure 9. Calibration curve for methanol with a calibration range of 10–200 ppb




Figure 10. Calibration curve for ethanol with a calibration range of 0.5–200 ppb.

For all components, except methanol, a calibration range of 0.5–200 ppb was achieved with R-squared values ranging from 0.990–0.998 (Table 4), all at or above the Environmental Protective Agency (EPA) requirements for valid quantitation. Methanol as stated earlier was calibrated over a range of 10–200 ppb with an R-squared value of 0.9987.

Table 4. Calibration Curve Summary Using Optimized Analysis Conditions

Compound	Calibration range (ppb)	R ² Value
Methanol	10–200	0.999
Ethanol	0.5–200	0.998
Acetone	0.5–200	0.993
Ethyl ether	0.5–200	0.994
TBA	0.5–200	0.990
MTBE	0.5–200	0.995
MEK	0.5–200	0.994

USEPA requires R² value of 0.990 or greater for quantitative use

methanol and ethanol. If the selected ion monitoring (SIM) mode of the MSD is used, per EPA method 8260B section 7.5.12, increased sensitivity will be gained. This may allow for less aggressive conditions than those used in Table 3 while still achieving low ppb quantitation levels.

Salt should be baked to remove moisture and any possible contaminants.

Dry blanks should be run often and line/valve temperatures kept hot (125–150 °C) to reduce water build-up and carryover problems. If a single purge vessel is used for all samples it should be rinsed and/or baked thoroughly after every run.

Conclusion

With optimized P&T conditions it is possible to detect and accurately quantitate low ppb levels of oxygenated contaminants in aqueous sample matrices. This application note provides some of the tools needed if this type of work is to be considered.

Additional Considerations

Automated sampler systems, that accept full VOA vials to reduce sample handling, may require some special approaches to facilitate salt addition. It may be necessary to contact the manufacturer of the autosampler to find out the feasibility of salt addition.

Many laboratories attempt to run the low level oxygenates in conjunction with their 8260 or 524.2 methods. The conditions presented in this work likely will not work well with these standardized EPA methods, but this has not yet been confirmed. If it is desired to run the oxygenates together with the full VOC list these analysis conditions may need to be pared back somewhat, though this will reduce the sensitivity for methanol and ethanol. For example, heating the sample to 65 °C with no salt addition may work for full VOCs and will likely allow for calibration down to around 100 ppb for

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Vocarb™ is a trademark of Sigma-Aldrich.

© Agilent Technologies, Inc. 2003


Printed in the USA
March 12, 2003
5988-8993EN



Application 707

Gas Phase Sample Extraction System

Analysis of Trace Organic Components in Water



Technical Overview



Application Highlights


- Bench-top or wall-mounted system
- The extraction is performed by flowing the water sample past a thin, solid, polymer barrier.
- Various detector choices allow a wide range of selectivity and sensitivity.
- Concentration ranges down to ppt levels

Optional Configurations

- Trace hydrocarbon impurities in cooling tower/exchanger water
- Trace hydrocarbon impurities in high purity drinking water
- TOGA Analysis utilizing capillary column technology
- Contaminants in discharge water

For More Information


For more information on our products and services, visit our Web site at www.agilent.com/chem.



Agilent Technologies



WASSON ECE
INSTRUMENTATION



FID output from the Agilent Gas Phase Sample Extraction System.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002


Printed in the USA
December 6, 2002
5988-7673EN



Agilent Technologies



**WASSON ECE
INSTRUMENTATION**



BFB Tuning for Environmental Analysis: Three Ways to Succeed

Application

Environmental

Author

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

John E. Pellerin
Agilent Technologies, Inc.
40 Shattuck Road
Andover, MA 01810
USA

Abstract

The United States Environmental Protection Agency methods 524.2, 8260B, and Contract Laboratory Program Statement of Work employ purge and trap concentration of volatile compounds in water samples with analysis by gas chromatography/mass spectrometry. Each method requires the mass spectrometer to meet specific tuning criteria before proceeding to actual samples. This paper summarizes these tuning criteria, and shows three different ways that the Agilent Technologies 6890/5973 gas chromatograph/mass selective detector system can be tuned to meet them. A very simple and robust procedure is described in the Modified Autotune section. A quick reference guide for this procedure is given at the end of the paper under Modified Autotune Summary.

Introduction

If you are already familiar with 4-bromofluorobenzene (BFB) tuning and evaluation procedures, you may want to go directly to the section titled “Modified Autotune Summary” found at the end of this paper. It offers an alternative approach for tuning Agilent 6890/5973 GC/MSD systems that is routinely successful in this laboratory.

The United States Environmental Protection Agency (USEPA) has developed several methods for the analysis of volatile organic compounds (VOCs) in water samples. The three most widely used procedures all employ purge and trap (P&T) sample introduction followed by capillary column gas chromatography with mass spectral detection (P&T/GC/MS). USEPA Method 524.2 revision 4¹ is used for drinking water analysis while Method 8260B revision 2² is used for wastewater. The USEPA Contract Laboratory Program Statement of Work (CLP-SOW)³ uses a similar P&T/GC/MS method for the analysis of hazardous waste.

There are many similarities among these three USEPA volatiles methods. One common requirement is that the GC/MS system must be tuned in such a way that 4-bromofluorobenzene (BFB) meets specific ion abundance criteria. This requirement helps to ensure that data are comparable between instruments of different design and



Agilent Technologies

among various laboratories. This paper summarizes USEPA method 524.2, 8260B, and CLP tuning criteria, and shows three different ways that the Agilent Technologies 6890/5973 GC/MSD system can be tuned to meet them.

Experimental

A standard containing fluorobenzene, 1,2-dichlorobenzene- d_4 , and 4-bromofluorobenzene at 2.0 mg/mL was purchased from AccuStandard (New Haven, CT). A portion of this solution was diluted in methanol (B&J HPLC and pesticide grade) to a concentration of 50 ng/ μ L.

Standards for tune evaluation were injected by syringe or P&T into several different Agilent Technologies 6890/5973 GC/MS systems. When making syringe injections into the split/splitless inlet, a liner with a 900- μ L volume was used and no more than 1.0 μ L was injected to avoid over-expansion in the inlet.

Results and Discussion

Tuning Criteria

Table 1 lists the tuning criteria for USEPA methods 524.2, 8260B, and CLP-SOW. All three methods base their tuning criteria on the ion responses of BFB. All ion responses are reported relative to m/z 95, which is assumed to be the base

peak even though ions 174 and 176 may be larger in the CLP-SOW method.

While many of the requirements in Table 1 are the same for all three methods, some important differences are worth noting. Method 8260B actually allows the analyst to use the tuning criteria specified in either of the other two methods. More importantly, it allows one to use “manufacturers tuning (sic) instructions” so long as it does not hurt method performance. However, many laboratories still follow the BFB tuning requirements specified in method 8260B or choose to substitute CLP-SOW tuning criteria.

Methods 524.2 and 8260 require that m/z 95 be the base peak in the BFB spectrum, which caps the m/z 174 relative abundance at 100% (relative to m/z 95). The CLP-SOW requirements allow m/z 174 to be up to 120% of m/z 95. Tuning procedures that reduce the response of m/z 174 too much may lead to lower overall sensitivity, especially for bromoform which has a quant ion of m/z 173. Conversely, maximizing this ratio, within the requirements of the method, can enhance overall sensitivity.

Automated BFB Tuning

The Agilent 5973 MSD uses perfluorotributylamine (PFTBA) for electron impact tuning because it exhibits good stability, the right volatility, and a wide range of fragment masses. However, USEPA volatiles methods evaluate the tune using BFB which produces an entirely different spectrum.

Table 1. Criteria for BFB Tuning for Three Capillary GC/MS Volatiles Methods

Mass (m/z)	Relative Abundance Criteria		
	Method 524.2	Method 8260B ^a	CLP-SOW
50	15 to 40% of 95	Same as 524.2	8 to 40% of 95
75	30 to 80% of 95	30 to 60% of 95	30 to 66 % of 95
95	Base Peak, 100%	Same as 524.2	Same as 524.2
96	5 to 9% of 95	Same as 524.2	Same as 524.2
173	<2% of 174	Same as 524.2	Same as 524.2
174	>50% of 95	Same as 524.2	50 to 120% of 95
175	5 to 9% of 174	Same as 524.2	4 to 9% of 174
176	>95 to <101% of 174	Same as 524.2	93 to 101% of 174
177	5 to 9% of 176	Same as 524.2	Same as 524.2

^aAlternative tuning criteria may be used (for example, CLP or Method 524.2) including manufacturer's instructions provided that method performance is not adversely affected.

Therefore, automated (or manual) tuning procedures must adjust PFTBA ion responses in order to get the desired BFB response ratios. Agilent G1701CA EnviroQuant ChemStation software automates BFB tuning so that the instrument typically passes the more restrictive USEPA Method 524.2 and 8260B requirements listed in Table 1. After tuning, the analyst must inject a BFB standard by syringe or P&T to verify that the tune passes the requirements for the method in use.

Automated BFB tuning adjusts MSD source parameters so that PFTBA ion abundances meet predetermined “targets.” The default PFTBA target values are set so that a subsequent BFB injection should meet the requirements for all three methods. Table 2 shows a portion of a BFB tune report that includes the target responses (as a percentage of m/z 69) for m/z 50, 69, 131, 219, 414, and 502. The actual abundances achieved by the tune are shown on the last line. When these targets

Table 2. A Portion of a Typical BFB Tune Report

Target Mass:	50	69	131	219	414	502
Target Abund (%) :	1.0	100.0	45.0	55.0	2.4	2.0
Actual Tune Abund (%) :	1.2	100.0	48.1	59.3	2.7	2.3

are met, the Agilent 5973 MSD normally passes any of the tuning criteria listed in Table 1.

Figure 1 shows an average spectrum obtained for a 1- μ L manual injection of BFB (50 ng/ μ L split 50:1) using the tune shown in Table 2. Agilent G1701CA EnviroQuant ChemStation Environmental Data Analysis software can evaluate the spectrum automatically and generate a report that is archived with the data file. Because BFB tuning criteria are not uniform among USEPA methods, the analyst must first specify the allowable ranges using the form shown in Figure 2. The form is accessed in Environmental Data Analysis by selecting Tuner/Edit BFB Criteria on the dropdown menu.




Figure 1. Average spectrum of BFB after performing a standard BFB automated target tune. One μ L of a methanol solution containing 50 ng/ μ L of BFB was injected by hand.

Figure 2. The Agilent G1701CA EnviroQuant ChemStation screen for entering BFB tune criteria. The user can modify the parameters to meet the requirements of the method in use. These values are used by the ChemStation for automated tune evaluation.

Having entered abundance criteria for the method in use, one can automatically assess the suitability of the tune using the EnviroQuant software (Figure 3). One can choose to "Evaluate BFB to Screen/Printer" in which case it will evaluate the current spectrum. This can be a single spectrum or an average. Alternatively, by choosing "Autofind BFB to Screen/Printer," the software automatically finds BFB in the chromatogram, averages the top three spectra and subtracts a baseline spectrum. In either case, a report such as the one in Figure 4 is generated. The most recent report is archived in the datafile.d directory in a file called tuneeval.txt.

Figure 3. Choices for automated BFB tune evaluation by the EnviroQuant software. The "Evaluate BFB..." choices use the spectrum (single or averaged) in Data Analysis window 1 for evaluation. The "Autofind..." choices automatically find the BFB peak, average the top three BFB spectra and subtract a baseline spectrum prior to evaluation.

BFB

Data File : C:\HPCHEM\1\DATA\Sep24_01\TUNE_001.D Vial: 1
 Acq On : 24 Sep 2001 2:25 pm Operator:
 Sample : BFB for tuning 1 uL Inst: GC/MS Ins
 Misc : Multiplr: 1.00
 MS Integration Params: rteint.p

Method : C:\HPCHEM\1\methods\envdef.m (RTE Integrator)
 Title :

AutoFind: Scans 1567, 1568, 1569; Background Corrected with Scan 1559

Target Mass	Rel. to Mass	Lower Limit%	Upper Limit%	Rel. Abn%	Raw Abn	Result Pass/Fail
50	95	15	40	21.6	6769	PASS
75	95	30	60	56.5	17708	PASS
95	95	100	100	100.0	31317	PASS
96	95	5	9	7.1	2209	PASS
173	174	0.00	2	0.0	0	PASS
174	95	50	100	82.8	25933	PASS
175	174	5	9	7.4	1910	PASS
176	174	95	101	99.3	25747	PASS
177	176	5	9	6.6	1702	PASS

TUNE_001.D envdef.m Mon Sep 24 16:00:27 2001 MSVOC04

Figure 4. The Agilent EnviroQuant ChemStation BFB Tune Evaluation Report for the spectrum shown in Figure 1.

In this case the automated BFB tuning procedure produced a tune that passes Method 524.2 and 8260B criteria with a 174/95 ratio of 82.8%. This ratio is limited to 100% by these USEPA methods, which specify that m/z 95 must be the base peak. To meet these strict guidelines, one has to "de-tune" the Agilent 5973 MSD which results in somewhat lower instrument sensitivity. Laboratories may want to increase the 174/95 ratio so it more closely approaches the 100% limit of Methods 524.2 and 8260B or so that it approaches the 120% limit specified in the CLP-SOW method. Most laboratories that perform Method 8260B tune their instruments to meet the CLP-SOW requirements because the method allows laboratories to use these tune criteria and the MSD performance is closer to optimum.

In addition to the automated BFB tune, there are two procedures that can be used to improve instrument sensitivity, to meet the more liberal CLP-SOW requirements, or to create a passing tune should the standard BFB autotune fail. In this laboratory, the "Modified Autotune" procedure was found to produce tunes that routinely passed BFB criteria for any of the three methods. As shown below, changing the BFB tuning targets can also produce a passing BFB tune while enhancing the signal for bromoform.

Target Tuning

Automated BFB tuning adjusts MSD source parameters to achieve the target responses required for the method in use. This is essentially a "target tune" procedure where the initial target abundances provided by the software are designed to

meet the more restrictive 524.2 and 8260B requirements. When needed, it is easy to change the target PFTBA relative abundance criteria to produce the desired affect on the BFB ions. This is done by selecting View/Manual Tune/Set Tune Targets.

For example, consider the spectrum in Figure 1 which passed all of the tuning criteria, but which had a lower than optimum m/z 174 response. Experience in this laboratory has shown that increasing the relative abundance of m/z 174 will increase the overall sensitivity of the instrument, in particular for the bromoform response at m/z 173. As shown in Figure 5, the target abundances for ions 131 and 219 were each increased to 70% from their default values of 45% and 55% respectively. These choices were saved to the BFB.U tune file and a new BFB Target Tune was run. Figure 6 shows the new BFB spectrum (average of three spectra across the apex with baseline subtraction) which passes CLP-SOW criteria (Table 1) and is, therefore, satisfactory for either CLP or 8260B volatiles methods.

Target	Value
Mass 50 target (0.3-5%):	1
Mass 131 target (20-120%):	45
Mass 219 target (20-120%):	55
Mass 414 target (0.3-10%):	3.5
Mass 502 target (0.3-10%):	2.5

Figure 5. PFTBA target abundance values (relative to m/z 69) used for "target" tuning. When these abundances are saved to the BFB.U tune file, they are used by the BFB target tune algorithm.




Figure 6. Average BFB spectrum obtained by changing the tune targets for m/z 131 and 219 to 70% (relative to m/z 69). This spectrum passes CLP-SOW tuning criteria.

Modified Autotune

With the convenience of automated tuning procedures available in the Agilent ChemStation software, most analysts have gladly given up the idea of manually tuning their 5973 MSDs. A combination of automated tuning with a slight manual modification has given excellent BFB results in this laboratory. The total process is easy and usually takes just a few extra minutes after the autotune is complete. The steps are described below and are summarized in a "quick reference" format in the next section.

1. From the Manual Tune portion of the software, perform an Autotune (select Tune/Autotune). This algorithm tunes the Agilent 5973 MSD for maximum sensitivity over the entire mass range and is widely used by methods that do not specify other tune criteria. This autotune emphasizes overall sensitivity by improving abundances for higher mass ions (for example, 502). As a result, the Autotune procedure typically gives an abundance for m/z 50 that is too low to meet 524.2 and 8260 criteria and an abundance of m/z 174 that may be too high, even for CLP-SOW tuning.
2. After completing the Autotune procedure, choose Edit MS Params (under the AdjParam menu item) which will display the screen shown in Figure 7.




Figure 7. The Edit Parameters screen found by selecting AdjParam/Edit MS Params in the main Manual Tune window.

3. Two changes are required in the default values used for adjusting parameters in this view. First, under the MoreParams menu, choose Ramp Params and change the "Stop" value for the ion focus to 140 as shown in Figure 8. Close this window and choose

AcqParams under the MoreParams window and change Mass 3 from 502 to ion 50 as shown in Figure 9. Close this window and return to the main Edit Parameters screen (Figure 7).




Figure 8. This window allows the user to set ranges for the various tuning parameters. The default ion focus "Stop" setpoint of 90 was set to 140.




Figure 9. Acquisition and Display Parameters window. M/z values of 69, 219, and 50 have been chosen so that these responses can be ramped and their relative abundances displayed.

4. Highlight the IonFocus window with the cursor and then select Ramp. This gradually ramps the ion focus voltage over the specified range while monitoring the response of ions 69, 219, and 50. After about a minute, a plot of these ion responses vs. the ion focus voltage appears in the window (Figure 10).




Figure 10. Abundances for ions 69, 219, and 50 while ramping the Ion Focus from 40 to 140.

- Under the View dropdown menu item, choose Expand. This view shows the current Ion Focus setting, the abundance of m/z 69 and the relative abundances of ions 219 and 50 (Figure 11). From the plot, it is easy to see that an increase in the Ion Focus value should increase the 50:69 ratio while reducing the 219:69 ratio. These are

exactly the changes that should enable the MSD to pass BFB tuning criteria.

Note that the ion focus ramping procedure can also be performed from the main Manual Tune screen by choosing Ramp/Ramp Ion Focus on the dropdown menu.




Figure 11. An expanded view of the SIM-Abundance-vs-Ion Focus plot obtained by selecting View/Expand. This view allows one to drag the vertical line to different setpoints while observing changes in the ion relative abundances.

- The vertical line indicates the current ion focus setpoint. Use the cursor to drag this setpoint line to the right while observing the change in the 219:69 and 50:69 ratios. Agilent laboratories have had good success by setting the Ion Focus to values between 100 and 135 V. This should result in a 219:69 ratio in the 60-80% range and a 50:69 ratio that is 0.8 or greater. If tuning to meet 524.2 requirements, the 219/69 ratio should be on the low side of this range.

An alternative to the above procedure is to select Scan in the Edit Parameters window (Figure 7) while monitoring ions 69, 219, and 50. The 219:69 and 50:69 ratios are displayed under the Relative Abundance heading and are updated with each scan. Highlight the Ion Focus setting and adjust its value using the slider bar. The effect of different Ion Focus values will be seen almost immediately in the ion ratios. These ratios will bounce around somewhat, but trends can be seen over a few scans. A good choice for the 50:69 ratio would be about 0.85.

- Click OK and return to the Manual Tune screen. Under the Calibrate menu item, choose Adjust Abundances, which will automatically reset the electron multiplier to get ion abundances in the optimum range. Save the tune, choosing a new name for the tune file (for example, BFB1.U). Return to Instrument Control (View/Instrument Control) and be sure to select this tune file for the method used to acquire the BFB checkout chromatogram. Inject or purge an appropriate amount of BFB and evaluate the tune using the software tools provided (Figures 2 through 4). Assuming that it passes, assign this tune to the P&T/GC/MS volatiles method in use.

Figure 12 shows the spectrum (average of the three scans across the apex with baseline subtraction) for a 1- μ L syringe injection (50 ng/ μ L split 50:1) of BFB using an ion focus value of 115 V. All other parameters (except for the electron multiplier) were set by the Autotune algorithm. This spectrum passes any of the tuning criteria listed in Table 1 but has a higher 174/95 ratio than was achieved using the standard BFB tune.




Figure 12. Average spectrum of BFB obtained after using the procedure described under Modified Autotune. After running a standard Autotune, the Ion Focus value was increased to 115 V.

The true test of a successful BFB tune is whether it holds up during repetitive VOC analyses and through normal instrument maintenance procedures. In one extreme test, the same BFB tune easily passed CLP-SOW criteria during a period when two different MSD sources were installed and four different filaments were used. On one Agilent 6890/5973 GC/MS instrument this procedure did not work until the MSD source was cleaned.

Finally, a note of caution is appropriate. While these techniques have worked well for the Agilent 6890/5973A and N GC/MSD systems, this does not imply that the same procedures are appropriate for older Agilent MSDs. Tuning frequency is dictated by the nature of the samples, choice of column and other factors such as column bleed and source cleanliness. If the source becomes too dirty, it must be cleaned in order to pass BFB tuning criteria, no matter which approach is taken.

Modified Autotune Summary

These steps summarize the procedure for modifying the standard Agilent 5973 Autotune to pass BFB tuning criteria. It is provided here as a quick reference guide for those who are already familiar with tuning procedures.

1. In the Manual Tune portion of the Agilent GC/MS ChemStation software, perform a standard Autotune.
2. In the Ramp Parameters window, change the Ion Focus Stop value to 140.
3. In the Acquisition & Display Parameters window, change ion 502 to 50.
4. In the Edit Parameters window click on Ion Focus and then on Ramp.
5. Adjust the Ion Focus value so that the 50/69 ratio is 0.8 or larger. The 219/69 ratio usually falls in the 60 to 80% range. When this PFTBA ion ratio is under 70%, the 174/95 ratio of BFB is usually under 100%.
6. In the Manual Tune window under the Calibrate menu item, adjust ion abundances.
7. Save the tune file with a new name, assign it to the method and verify that the tune passes by injecting a BFB sample according to the method requirements.

Conclusions

There are several ways to tune the Agilent 6890/5973 GC/MSD system to meet any of the USEPA BFB tuning criteria. However, factors such as source cleanliness, choice of column, flow rates and instrument-to-instrument variability make each GC/MSD system unique. Automated BFB and target tuning procedures are normally successful but the 174/95-ion ratio may not be high enough to meet laboratory needs. In our experience, the most robust and long-lasting BFB tunes were generated by the procedure outlined above under Modified Autotune. The procedure takes just a few minutes to complete.

References

1. *Measurement of Purgeable Organic Compounds in Water by Capillary Column Gas Chromatography/Mass Spectrometry*, Method 524.2, revision 4.1, U.S. Environmental Protection Agency, Office of Research and Development, National Exposure Research Laboratory, Cincinnati, OH (1995).
2. *Volatile Organic Compounds by Gas Chromatography/Mass Spectrometry (GC/MS)*, Method 8260B, revision 2 (1996).
3. *USEPA Contract Laboratory Program Statement of Work for Organics Analysis, Multi-Media, Multi-Concentration, OLM04.2*, USEPA Contract Laboratory Program, Office of Emergency and Remedial Response.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
November 6, 2001
5988-4373EN



Agilent Technologies



Analysis of Volatile Organic Compounds by Purge-and-Trap Gas Chromatography/Mass Selective Detection

Application

Environmental

Author

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Purge-and-trap sample concentration followed by gas chromatography with mass spectral detection is the most widely used technique for the analysis of volatile compounds in water. Using 5-mL water samples, most target compounds can be quantitated at 0.5 µg/L or lower. Analysis of 25-mL samples provides even greater sensitivity. Agilent Technologies' Purge-and-Trap/Gas Chromatography/Mass Spectral Detection system is recognized worldwide for its reliability, sensitivity and ease of use. Agilent also provides specialized environmental software, consumables, and gas chromatography columns for volatiles analysis. When combined with Agilent's service and support, laboratories have everything required to produce high-quality, reliable results.

Introduction

Without careful monitoring, many chemical by-products of modern industrial production can be released into the environment, often contaminating ground and surface water bodies upon which we all depend. In many parts of the world, public drinking water is chlorinated to kill disease-causing bacteria. Some byproducts of this process, such as the halogenated methanes, are unhealthy at

high concentrations. Therefore, chlorinated drinking water must be routinely monitored for these compounds and others to ensure public safety.

Numerous analytical techniques have been developed over the last 25 years to analyze for volatile organic compounds (VOCs) in ground and surface water, wastewater, and drinking water. Today, the most widely used analytical technique in the world for VOC analysis is purge-and-trap (P&T) sample concentration combined with gas chromatography and mass selective detection (GC/MSD).

Purge-and-trap has been adopted so widely because of its ability to remove and concentrate most or all of the VOCs in water samples. When combined with the Agilent Technologies GC/MSD, the system can be used to quantitate VOCs at concentrations as low as 0.1 µg/L (ppb). The Agilent GC/MSD has become the standard system in most environmental laboratories worldwide because it offers unmatched sensitivity, selectivity, stability, and ease-of-use. This paper illustrates use of P&T/GC/MSD as a universal technique for the analysis of VOCs in water samples.

Experimental

Table 1 lists the instrumentation and some of the conditions that were used for the analysis of VOCs in water samples. The exact conditions need to be optimized for the kind of samples that are to be analyzed. Agilent Technologies provides the necessary instrumentation, supplies and services to help ensure that laboratories adopting this technology can successfully analyze their samples.



Agilent Technologies

Table 1. P&T/GC/MSD Instrumentation

Gas chromatograph/mass spectrometer	Agilent GC/MSD
Environmental analysis software	Agilent EnviroQuant ChemStation software
Column	20-m × 0.18-mm × 1.0-μm J&W DB-VRX
GC Inlet	Split/Splitless operated in the split mode
Carrier gas	Helium
Purge-and-trap concentrator	Tekmar-Dohrmann
Trap	Vocarb 3000
Purge-and-trap automatic sampler	Tekmar-Dohrmann
Water sample size	5 or 25 mL (5-mL samples used for this work)

Standard solutions containing 60 common VOCs dissolved in methanol were purchased from AccuStandard, Inc. (New Haven, CT USA).

Results and Discussion

P&T sample concentration involves bubbling helium gas through a water sample (usually 5 mL or 25 mL) for several minutes. As the helium bubbles through the sample it sweeps dissolved VOCs out of the water and into a trap that contains one

or more adsorbents. During purging, the trap is held at 35 °C allowing the VOCs to be adsorbed on the packing material. After a suitable purging time (typically 11 minutes), the trap is heated to desorb the VOCs which are swept with the helium carrier gas into the GC/MSD.

Figure 1 shows a chromatogram obtained by P&T/GC/MSD analysis of a 5-mL water sample containing 60 different VOCs, each at a concentration of 5 μg/L. The compounds are identified in Table 2.




Figure 1. Chromatogram of the volatile organic compounds listed in Table 2. A 5-mL water sample containing each analyte at the 5-μg/L level was analyzed using the P&T/GC/MS system listed in Table 1. The internal standard and two surrogate compounds were present at 10 ppb and are designated in Table 2.

Table 2 Calibration Regression Coefficient r^2 Values

Number	Name	RT (min)	Quant Ion	Number	Name	RT (min)	Quant Ion
1	Dichlorodifluoromethane	1.17	85	33	1,1,1,2-Tetrachloroethane	8.33	131
2	Chloromethane	1.25	50	34	Chlorobenzene	8.38	112
3	Vinyl chloride	1.31	62	35	Ethyl benzene	8.55	91
4	Bromomethane	1.48	94	36	m&p-Xylene	8.69	106
5	Chloroethane	1.54	64	37	Bromoform	8.70	173
6	Trichlorofluoromethane	1.80	101	38	Styrene	8.90	104
7	1,1-Dichloroethene	2.08	96	39	1,1,2,2-Tetrachloroethane	8.94	83
8	Methylene chloride	2.16	84	40	o-Xylene	8.95	106
9	trans-1,2-Dichloroethene	2.60	96	41	1,2,3-Trichloropropane	9.03	75
10	1,1-Dichloroethane	2.79	63	42	Isopropylbenzene	9.20	105
11	cis-1,2-dichloroethene	3.30	96	43	4-Bromofluorobenzene (Surrogate)	9.20	95
12	Bromochloromethane	3.45	128	44	Bromobenzene	9.32	156
13	Chloroform	3.51	83	45	n-Propylbenzene	9.49	91
14	2,2-Dichloropropane	3.59	77	46	2-Chlorotoluene	9.52	91
15	1,2-Dichloroethane	4.29	62	47	4-Chlorotoluene	9.58	91
16	1,1,1-Trichloroethane	4.42	97	48	1,3,5-Trimethylbenzene	9.69	105
17	1,1-Dichloropropene	4.47	75	49	t-Butylbenzene	9.85	119
18	Carbon tetrachloride	4.95	117	50	1,2,4-Trimethylbenzene	9.93	105
19	Benzene	5.04	78	51	s-Butylbenzene	9.98	105
20	Fluorobenzene (Internal Standard)	5.38	96	52	1,3-Dichlorobenzene	10.00	146
21	Dibromomethane	5.76	93	53	1,4-Dichlorobenzene	10.05	146
22	1,2-Dichloropropane	5.83	63	54	4-Isopropyltoluene	10.11	119
23	Trichloroethene	5.89	95	55	1,2-Dichlorobenzene-d4 (Surrogate)	10.25	152
24	Bromodichloromethane	5.94	83	56	1,2-Dichlorobenzene	10.26	146
25	cis-1,3-Dichloropropene	6.65	75	57	1,4-Dichlorobenzene	10.36	146
26	trans-1,3-Dichloropropene	7.06	75	58	n-Butylbenzene	10.36	91
27	1,1,2-Trichloroethane	7.16	83	59	1,2-Dibromo-3-chloropropane	10.55	75
28	Toluene	7.32	92	60	1,2,4-Trichlorobenzene	11.39	180
29	1,3-Dichloropropane	7.37	76	61	Naphthalene	11.54	128
30	Dibromochloromethane	7.54	129	62	Hexachlorobutadiene	11.61	225
31	1,2-Dibromoethane	7.72	107	63	1,2,3-Trichlorobenzene	11.67	180
32	Tetrachloroethene	7.88	166				

Figure 1 and Table 2 show several places where the target compounds are not fully resolved in the chromatogram. Because different ions are used for quantitation, the overlapping peaks are no problem, as shown in Figure 2. In Figure 2a, a portion of the total ion chromatogram (TIC) has been enlarged showing peaks that overlap. As seen in

Figure 2b, the extracted ion chromatograms used for quantitation of these compounds have peaks that are fully resolved. The GC/MSD system uses a combination of chromatography and ion selectivity to resolve all of the peaks, providing faster analyses with quantitation that is precise and accurate.




Figure 2. a) A portion of the total ion chromatogram in figure 1. The peaks are identified in Table 2. *s*-Butylbenzene (51) and 1,3-dichlorobenzene (52) are partially resolved while 1,2-dichlorobenzene (56) and its deuterated analog (55) (used as a surrogate) are unresolved. b) The extracted ions used for quantifying these compounds show peaks that are fully resolved.

Figure 3 shows calibration curves for chloroform (0.5 to 100 µg/L) and 1,2-dichloroethane (0.5 to 250 µg/L) that were generated by purging 5-mL spiked water samples. The Agilent MSD typically displays good linearity over four orders of magnitude. However, the region of linearity is compound dependent, i.e., not all compounds are linear over the same calibration range. Laboratories are usually able to generate linear calibration curves over two orders of magnitude for a large number of analytes, such as those listed in Table 2.

With the high sensitivity of the Agilent GC/MSD system, laboratories usually only need to purge 5-mL samples. However, when additional sensitivity is required, the P&T system can accommodate 25-mL samples which increases the sensitivity by a factor of 5 for most compounds.

Conclusions

Automated P&T/GC/MS is the most widely used technique for the analysis of volatile organic compounds in drinking water, waste water, factory effluent and ground water. Agilent Technologies provides the necessary instrumentation, GC columns, supplies and services required for laboratories to succeed with these analyses. Agilent's EnviroQuant software has been specifically designed for the needs of environmental laboratories.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.




Figure 3. Calibration curves for: a) chloroform (0.5-100 µg/L) and b) 1,2-dichloroethane (0.5-250 µg/L).

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
November 6, 2001
5988-4463EN



Agilent Technologies



Using the Agilent 6890 Gas Chromatograph and Agilent 5973 Mass Spectrometer System for EPA Method 524.2

Application

Gas Chromatography

Authors

James Refermat and
Marcell Stephens
Quanterra Incorporated
5910 Breckenridge Parkway,
Suite H
Tampa, FL 33610
USA

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

A system comprised of a purge and trap (P&T) concentrator, a gas chromatograph (GC), and a mass spectrometer (MS) was used to determine 61 volatile organic compounds (VOCs). All U.S. EPA method 524.2 criteria were met without using cryofocusing. The P&T and GC-MS conditions listed in tables 1 and 2 detail the instrument settings. The method development for analyzing 524.2 analytes was refined by members of the GC-MS Volatile Organics Analysis (VOA) group at Quanterra in Tampa, Florida.

Introduction

U.S. EPA method 524.2 is a general-purpose method used to identify and quantify volatile organic compounds (VOCs) in surface, ground, and drinking water. The method is applicable to a wide range of organic compounds including the four trihalomethane disinfection byproducts. The 61 VOCs in this note are a subset of the 84 VOCs that can be analyzed using method 524.2.

Compounds of sufficient high volatility and low water solubility are purged from a water sample using helium and trapped on a solid sorbent held at room temperature. At the end of the purge cycle, the trap is heated and, using helium, the compounds are desorbed onto the head of a gas chromatograph (GC) column. The GC column is temperature programmed, and the analytes are eluted into the mass spectrometer (MS) ion source. The MS is used for identification and measurement. The purge and trap (P&T)-GC-MS system is controlled from a PC.

Experimental

The program requirements for which the 524.2 analysis is used must meet local state regulatory guidelines as well as EPA method 524.2 acceptance criteria and U.S. Air Force compliance guidelines under the auspices of the Air Force Center for Environmental Excellence (AFCEE) program.



Agilent Technologies

Quanterra maintains strict QA/QC procedures at all 12 facilities. Each location has a quality assurance officer (QAO) reporting directly to the corporate quality assurance director. Quanterra's network of 12 facilities in 10 states staffs over 700 employees and encompasses over 310,000 square feet of facility space, providing the capacity to handle any analytical need. Quanterra performs more than 1.5 million separate tests per year. A nationwide network of fully equipped labs, linked by advanced information management systems, assures a high standard of testing and consistent quality.

Quanterra's comprehensive quality management system (QMS) forms the foundation of their quality goals. Quanterra's QMS ensures that their clients receive high-quality analytical services that are timely and reliable, and that meet the intended purpose in a cost-effective manner. The QMS also applies to all Quanterra technical, business, and administrative functions. The principles and practices expounded in the QMS apply to all staff and are fundamental to the services they provide. As a result, Quanterra is continuously seeking ways to improve their products and services using the best technologies available. The AGILENT 6890 / AGILENT 5973 GC-MS system provides high-quality data and increased productivity.

The P&T instrumentation and conditions are listed in table 1. The Vocab 3000 trap allows for higher desorb and bake temperatures. The high desorb temperature facilitates efficient desorption of target analytes, and the high bake temperature minimizes carryover between samples. The standard transfer line provided with the P&T was replaced with a Restek 0.53-mm SilcoSteel MXT 502.2 column. The use of the analytical column as the transfer line between the P&T and GC appears to improve peak symmetry for low-level standards. The transfer line is attached directly to the AGILENT 6890 GC injection port (direct capillary interface) and runs in the split mode. A purge rate of 50 mL/min appears to improve the recovery of analytes that are known to have poor purge efficiencies. The 50-mL/min purge flow did not have an adverse effect on the recovery of the gases and, as a result, produced method and program compliant data. Traditional trap packing materials (Tenax/charcoal/ silica) usually did not hold the gases at higher purge flow rates, resulting in poor recoveries. This problem was not observed when

using the Vocab 3000 trap. The original method's desorb and bake temperature of 180 °C is a limitation associated with traditional packing material (Tenax break down).

The GC-MS instrumentation and conditions are listed in table 2. Conditions were optimized for maximum sample throughput while meeting site-specific data quality objectives. The split ratio used allows the best combination of sensitivity and peak shape. With this configuration, it is advantageous to use the electronic pressure control (EPC) inlet (option available on the AGILENT 6890 GC). With the EPC inlet pressure on, the chromatography for the gases is improved, and analytes at the end of the temperature program have much sharper peak shape. EPC also gives much better reproducibility of analyte retention times.

Each 12-hour shift (site-specific requirements allow for a 12-hour clock for the tune verification) starts with verification of the fragmentation pattern of 4-bromofluorobenzene (BFB) obtained from 25 ng on-column. A five-point calibration curve is then analyzed at concentrations of 500, 250, 125, 50, and 12.5 ng on-column. Once the calibration acceptance criteria is verified, a 100-ng (4 µg/L) laboratory control spike/laboratory control spike duplicate (LCS/LCSD) is analyzed followed by a method blank. Successful analysis of

Table 1. Purge and Trap Conditions

P&T	Tekmar LSC 3000
Automatic sampler	Tekmar ALS 2016
Trap	Vocab 3000
	Supelco part no.
	2-4920
P&T-GC interface	Custom*
Sample size	25 mL
Purge temperature	35 °C
Purge rate	50 mL/min
Purge time	11 min
Dry purge time	1 min
Desorb preheat temperature	250 °C
Desorb temperature	260 °C
Desorb time	2 min
Bake temperature	270 °C
Bake time	6 min
Bake-gas bypass on time	1 min
Line/valve temperature	100 °C
Water management	
control (WMC) temperature	310 °C

*Standard transfer line replaced with approximately 0.7-m length of Restek MXT-502.2 SilcoSteel 0.53-mm id column

Table 2. Gas Chromatograph and Mass Spectrometer Conditions

Gas chromatograph	Agilent 6890
Inlet	EPC split/splitless
Mode	Split
Inlet temperature	200 °C
Pressure	13.9 psi
Split ratio	35:1
Split flow	24.2 mL/min
Gas saver	On at 2 min
Gas saver flow	20.0 mL/min
Oven	
Initial temperature	35 °C
Initial time	4 min
Rate	15 °C/min
Final temperature	200 °C
Final time	0.1 min
Equilibration time	0.5 min
Oven max temperature	240 °C
Column	DB-624 fused silica capillary
Agilent equivalent	Agilent part no. 121-1324
Length	20 m
Diameter	180 µm
Film thickness	1.0 µm
Initial flow	0.7 mL/min
Average velocity	37.0 cm/sec
Mode	Constant flow
Inlet	Front
Outlet	MS
Outlet pressure	Vacuum
Mass spectrometer	Agilent 5973
Solvent delay	1.1 min
EM voltage	2035 volts
Low mass	35 amu
High mass	260 amu
Threshold	200
Sampling	3
Scans/sec	3.25/sec
Quad temperature	150 °C
Source temperature	200 °C
Transfer line temperature	250 °C

the LCS/LCSD and blank are followed by 20 field samples. A typical instrument sequence, when initial calibration is not required, is shown in table 3. This new sample sequence starts with an instrument tune verification (BFB analysis) followed by the analysis of the continuing calibration verification (CCV) standard. If the CCV fails, the system is recalibrated. After the CCV, a 100-ng (4 µg/L) LCS/LCSD is analyzed followed by a method blank and 20 field samples. *The LCS/LCSD QC samples are a site-specific project requirement.*

Note: The AGILENT 5973 MS only required retuning every 4 to 6 weeks during large sampling events. During these events, 26 samples were analyzed every 12 hours, operating 6 to 7 days a week.

Results

The results from the BFB tuning analysis are shown in table 4, together with the EPA method 524.2 tuning criteria. If the BFB tuning criteria are not met, typically mass 50 was low or mass 176 was high. The problem was resolved by running the auto-tune option provided with the Enviro-Quant software followed by a reanalysis of the BFB solution. If the BFB still did not pass, the problem was resolved by replacing the trap. The AGILENT 5973 MS ran for over a year before there was a need to open the analyzer and replace the filaments. The source was cleaned while the analyzer was open, and a little scorching around the filament area was observed. SW-846 method 8260B and CLP-SOW Method OLC02.1 were also performed using this instrument, often containing high levels of target and non-target analytes. As a result, finding the source and its component parts in good condition was unexpected.

A list of target analytes for this project, together with their compound number and retention time (RT), are shown in table 5. The method detection limits (MDLs) shown are based on initial calculations per 40 CFR, Part 136, Appendix B. Prior to running client samples, an instrument detection limit (IDL) study was conducted. This comprised of a five-point calibration curve followed by the CCV, method blank, and seven replicates of the 0.5-µg/L standard for 7 consecutive days. The results between replicates within the same analytical

Table 3. Instrument Sequence

Sequence No.	Description
1	1 ppb BFB, with CCV
2	10 ppb CCV
3	4 ppb LCS
4	4 ppb LCSD
5	Method blank
6	Sample 1
7	Sample 2
⋮	⋮
	Matrix spike
	Matrix spike duplicate
⋮	⋮
27	Sample 20

Table 4. BFB Tuning Criteria and Results

m/e	Ion Abundance Criteria	Ion Abundance Results
95	Base Peak, 100% relative abundance	100.00
50	15.00%-40.00% of mass 95	19.26
75	30.00%-60.00% of mass 95	46.39
96	5.00%-9.00% of mass 95	7.25
173	Less than 2.00% of mass 174	0.65
174	Greater than 50.00% of mass 95	85.07
175	5.00%-9.00% of mass 174	7.45
176	95.00%-101.00% of mass 174	100.70
177	5.00%-9.00% of mass 176	6.89

sequence demonstrated very little variation. Additionally, the results obtained between the day-to-day analytical sequences also exhibited very little variation. The IDL study and the MDL study yielded similar results with little or no statistical variation. All analyte MDLs are comfortably below

the 0.5 µg/L reporting limit for this project. Lower detection limits could be achieved with lower split ratios.

The initial calibration for this set of analyses was done in August 1997 at the following five levels: 0.5, 2.0, 5.0, 10, and 20 µg/L. Response factors were calculated for each analyte at each level. The percent relative standard deviations (%RSDs) of these response factors, listed in table 5, are all less than 20 and meet the criteria for Table 5. Target Compound List with QA\QC (continued) linearity. Hexachlorobutadiene and naphthalene had trouble meeting the daily ICV/CCV acceptance criteria on a daily basis; these compounds are known as poor purgers. Fortunately, the site-specific QA requirements allows for the use of a quadratic calibration when the acceptance criteria for linearity is not met.

Table 5. Target Compound List with QA\QC

Compound Number	Compound Name	RT	MDL	Init Cal %RSD RRF limit 0-20	CCV %D limit ± 30	LCS %Rec limit 70-130	LCSD %RPD limit 0-20
<i>Internal Standard</i>							
36	Fluorobenzene	6.651					
<i>Surrogates</i>							
63	4-Bromofluorobenzene	10.919		5.23	-12.	99.8	2.0
33	1,2-Dichlorobenzene-d(4)	12.436		6.54	-1.9	105.	7.6
<i>Target Analytes</i>							
34	Benzene	6.322	0.18	8.64	3.9	94.8	6.8
64	Bromobenzene	11.065	0.15	3.72	-12	112.	5.5
27	Bromochloromethane	5.574	0.19	15.5	-1.3	104.	2.1
40	Bromodichloromethane	7.592	0.21	10.1	-0.9	100.	5.0
61	Bromoform	10.595	0.23	15.3	-21.	111.	5.3
6	Bromomethane	1.907	0.31	13.4	4.7	82.3	1.8
79	n-Butylbenzene	12.451	0.19	10.7	-11.	97.2	8.3
74	sec-Butylbenzene	11.897	0.19	9.47	-8.5	98.7	12.
72	tert-Butylbenzene	11.682	0.20	6.21	3.0	110.	12.
31	Carbon tetrachloride	6.091	0.17	10.0	-5.3	104.	7.8
55	Chlorobenzene	9.784	0.17	6.67	-4.0	105.	3.0
7	Chloroethane	2.007	0.18	6.51	9.9	82.8	4.2
29	Chloroform	5.699	0.18	7.47	6.1	97.0	1.8
4	Chloromethane	1.510	0.19	6.77	16.	75.6	8.4
69	2-Chlorotoluene	11.264	0.18	6.53	-9.4	103.	7.1
71	4-Chlorotoluene	11.369	0.17	7.55	-11.	105.	7.6
51	Dibromochloromethane	9.188	0.17	11.1	-12.	108.	0.04
81	1,2-Dibromo-3-Chloropropane	13.215	0.30	6.44	16.	NR	NR
52	1,2-Dibromoethane	9.287	0.25	13.3	9.2	95.1	8.0
39	Dibromomethane	7.404	0.24	14.0	8.4	111.	1.0

Table 5. Target Compound List with QA\QC (continued)

Compound Number	Compound Name	RT	MDL	Init Cal %RSD RRF limit 0-20	CCV %D limit $\pm$ 30	LCS %Rec limit 70-130	LCSD %RPD limit 0-20
<i>Target Analytes (continued)</i>							
80	1,2-Dichlorobenzene	12.451	0.19	7.44	-0.4	104.	3.2
76	1,3-Dichlorobenzene	11.996	0.20	8.36	-2.5	105.	3.3
78	1,4-Dichlorobenzene	12.090	0.17	8.84	0.3	99.8	2.8
3	Dichlorodifluoromethane	1.353	0.21	6.07	15.	83.3	9.1
22	1,1-Dichloroethane	4.475	0.22	7.82	11.	88.7	5.3
35	1,2-Dichloroethane	6.342	0.20	11.2	5.3	99.8	3.5
12	1,1-Dichloroethene	2.280	0.20	7.61	8.5	99.0	6.4
25	cis-1,2-Dichloroethene	5.275	0.22	8.63	-6.3	97.2	3.6
18	trans-1,2-Dichloroethene	3.842	0.17	10.9	13.	94.8	4.9
38	1,2-Dichloropropane	7.284	0.22	10.0	8.6	88.3	2.1
49	1,3-Dichloropropane	8.957	0.12	6.56	7.4	95.7	0.76
24	2,2-Dichloropropane	5.265	0.20	9.39	4.2	92.6	0.80
32	1,1-Dichloropropene	6.097	0.18	9.13	5.0	88.3	12.
42	cis-1,3-dichloropropene	8.053	0.19	10.5	2.3	95.0	0.64
46	trans-1,3-dichloropropene	8.618	0.14	10.6	5.1	95.0	3.3
56	Ethylbenzene	9.904	0.20	8.46	3.9	89.4	8.6
83	Hexachlorobutadiene	14.229	0.24	16.1	-4.5	90.6	5.7
62	Isopropylbenzene	10.778	0.17	9.23	0.6	98.4	10.
75	4-Isopropyltoluene	12.049	0.20	9.07	11.	102.	8.9
16	Methylene chloride	3.445	0.21	9.07	-3.5	109.	5.0
98	Methyl-t-butyl ether	3.884	0.20	10.4	8.3	97.7	3.0
84	Naphthalene	14.287	0.13	19.7	5.3	76.8	5.8
67	n-Propylbenzene	11.186	0.21	6.92	-16.	108.	7.7
60	Styrene	10.422	0.18	11.8	-0.3	96.4	5.8
57	1,1,1,2-Tetrachloroethane	9.868	0.21	8.27	-5.3	102.	10.
65	1,1,2,2-Tetrachloroethane	11.065	0.18	6.57	-2.4	101.	4.8
48	Tetrachloroethene	8.942	0.21	8.61	8.6	89.0	10.
45	Toluene	8.393	0.14	9.37	-6.7	102.	9.6
85	1,2,3-Trichlorobenzene	14.528	0.18	9.13	0.7	90.7	5.5
82	1,2,4-Trichlorobenzene	14.052	0.16	11.0	-1.7	91.7	3.6
30	1,1,1-Trichloroethane	5.893	0.24	8.34	-2.9	102.	6.3
47	1,1,2-Trichloroethane	8.795	0.17	12.3	4.3	105.	1.2
37	Trichloroethene	7.059	0.16	8.77	-4.6	100.	6.7
9	Trichlorofluoromethane	2.273	0.19	5.26	6.2	99.1	3.9
68	1,2,3-Trichloropropane	11.102	0.20	5.54	2.7	101.	8.8
73	1,2,4-Trimethylbenzene	11.729	0.17	8.38	2.0	95.7	7.6
70	1,3,5-Trimethylbenzene	11.363	0.18	9.42	0.3	94.7	9.4
5	Vinyl chloride	1.609	0.15	7.54	4.4	82.1	13.
59	o-Xylene	10.411	0.13	10.7	0.3	94.0	7.5
58	m-Xylene	10.019	0.17	8.15	2.8	92.6	9.3
58	p-Xylene	10.019	0.17	8.15	2.8	92.6	9.3

After the BFB tuning verification is performed, a CCV is run at the 10-ppb level. The method requires that each analyte response factor (RF) is $\pm 30\%$ of its initial calibration value. These percent deviations (%Ds) are listed in table 5, and all analytes meet the method criteria. If one or more analytes do not meet this criteria, a new five-point calibration curve is run. The data presented here were run in September 1997, one month after the initial calibration. This system is very stable for long periods of time. A five-level calibration has only been necessary eight to ten times in the last 12 months. A total ion chromatogram (TIC) for the CCV is shown in figure 1.

This project requires analysis of a LCS and LCSD. Laboratory blank water is spiked at the 4- $\mu\text{g/L}$ level and analyzed in duplicate. The recoveries for each analyte must be between 70% and 130% for each analyte. A duplicate aliquot of the LCS, referred to as an LCSD, is then analyzed. The relative percent difference (RPD) of this LCS and the LCSD must be less than 20% for each analyte. The LCS recoveries and LCSD RPDs are shown in table 5. All analytes met the site-specific acceptance criteria.

After all of the project-specific QA/QC requirements are met, actual field samples can be analyzed. Results for three samples are shown in table 6. The samples were taken from private wells in an Area of Concern (AOC) in the northeast United States. All ion profiles met the site-specific QC acceptance criteria and all other regulatory acceptance criteria for this AOC.

A TIC for sample 1 is shown in figure 2. The excellent peak shape is typical of the system performance in our laboratory.




Figure 1. CCV total ion chromatogram.




Figure 2. Total ion chromatogram for field sample one.

Table 6. Results of Sample Analyses

Compound Number	Compound Name	RT min	Sample1	Sample2	Sample 3
<i>Internal Standard</i>			<i>Area % Difference limit ± 30</i>		
36	Fluorobenzene	6.651	-25.6	-29.2	-18.65
<i>Surrogate Standards</i>			<i>% Rec 1.0 ppb limit 80-100</i>		
33	1,2-Dichlorobenzene-d(4)	12.436	98.7	99.5	95.1
63	4-Bromofluorobenzene	10.919	85.2	93.4	89.0
<i>Target Analytes</i>			<i>[ppb]</i>	<i>[ppb]</i>	<i>[ppb]</i>
16	Methylene chloride	3.445	0.55	0.56	1.0
29	Chloroform	5.699	1.0	3.7	1.0
37	Trichloroethene	7.059	0.54	< 0.50	< 0.50
40	Bromodichloromethane	7.592	< 0.50	5.9	2.3
48	Tetrachloroethene	8.942	1.2	< 0.50	< 0.50
51	Dibromochloromethane	9.188	< 0.50	8.4	5.1
61	Bromoform	10.595	< 0.50	2.7	3.2

Conclusions

The AGILENT 6890/AGILENT 5973 GC-MS can be used to perform EPA method 524.2. All calibration, verification, and quality control criteria of the method can be met on a routine basis. The system exhibits excellent stability, minimal downtime, and sufficient sensitivity to meet the requirements for this project. The system performance, combined with expert personnel and a rigorous QA/QC program, results in high sample throughput for method 524.2. The AGILENT 6890/ AGILENT 5973 GC-MS allows Quanterra to meet clients' expectations in a timely and cost-effective manner.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright© 2001
Agilent Technologies, Inc.

Printed in the USA
April 26, 2001
5968-1257E



Agilent Technologies



Optimized Analysis of Gasoline (BTEX) in Water and Soil Using GC/FID with Purge and Trap

Application Note
228-324

Author

**Imogene L. Chang PhD, and
Zhenghua Ji, PhD**
Agilent Technologies
Wilmington, DE 19808-1610

Abstract

Gas chromatography with purge and trap analysis using their HP-1 capillary column and the Agilent 5890 Series II gas chromatograph/flame ionization detector was done to determine gasoline components in contaminated water and soil in accordance with modified EPA Methods 8015/8020. Purge and trap and gas chromatograph parameters were optimized for accurate quantitation of gasoline range organics (aliphatics, aromatics, and oxygenates) and to increase analysis speed.

Key Words

- EPA Methods 8015/8020
- Gasoline
- BTEX
- Purge and Trap
- GROs
- GC/FID analysis
- LUST

Introduction

Modified EPA Methods 8015/8020 are used to determine gasoline and gasoline components in water and soil by capillary gas chromatography (GC) with a flame ionization

detector (FID) or photo-ionization detector (PID). The hydrocarbons in gasoline encompass a wide range, from butane to decane and benzene to naphthalene, and cover a boiling point range of 50°C to 281°C. For such complex mixtures, an efficient purge and trap (P and T) system is required to concentrate samples for high-resolution gas chromatography. Detection is achieved using an FID, and quantitation is based on FID response to a gasoline standard. Other light petroleum products that can be determined in the same manner include paint stripper, Stoddard solvent, mineral spirits, petroleum naphtha, and aviation jet fuels using the pattern recognition technique.

The analysis of gasoline components, e.g., gasoline range organics (GROs), and benzene, toluene, ethylbenzene, and xylenes (BTEX) in particular is of great importance because BTEX is frequently used as a marker in the identification of gasoline-type products. Subsequently, the analysis of BTEX is often used to determine the composition and the origin of such products including weathered fuels leaking from underground storage tanks (LUST), spills in pipe lines, and run-off from surface transportation.

For the analysis of gasoline with BTEX, the sample is introduced into a sparge tube on the P and T autosampler or purge vessel or the P and T unit. The P and T concentrates the volatiles in the

sample and transfers them onto the capillary column.

Parameters affecting the efficiency of P and T sample concentration include time and temperature for sample purge, dry purge, desorption of trapped volatile organics and trap baking. Most P and T system manufacturers recommend 11 minutes of purge or a total of 440 ml purge gas through the sample. Many laboratories use the manufacturer's set purge flow of 40 ml/min which corresponds to 11 minutes of purge time, to achieve a minimum of 440 ml purge gas through the sample. In this study a Vocab-3000 trap was used because it can provide higher trapping efficiency and allow for higher desorption and baking temperature.

A typical analysis can usually be completed in 35 to 40 minutes. In this application both P and T parameters and GC conditions were optimized for accurate quantitation and analysis speed.

Experimental

Samples were concentrated using an Agilent 7695A P and T system with a Vocab-3000 trap (part no. 5182-0775) and a 5-ml frit sparger (part no. 5182-0852). Using an HP-1 column (30 m x 0.53 mm x 5.0 µm, (part no. 19095Z-623), hydrocarbons were analyzed on an Agilent 5890 Series II GC with EPC and FID. Instrument requirements and optimal GC and P and T conditions are listed in **Table 1**.



Agilent Technologies
Innovating the HP Way

Working solutions were prepared from diluting commercial gasoline, LUST-modified GROs (part no. 5182-0860), and internal standard and surrogate (part no. 8500-6007) with GC-grade methanol (Burdick and Jackson). Concentrations of GROs, gasoline, and jet fuel standards are listed in **Table 2**.

Samples were prepared from spiking 5 ml of organic-free reagent water using a 5-ml sample syringe with a luer connector (part no. 9301-1185) with standard solutions using 5- μ l to 100- μ l fixed needle syringes (HP part nos. 9301-0810, 9301-0818, 9301-0059, 9301-0063, respectively).

Results and Discussion

To obtain accurate and reproducible results, complete sample purging, managing water adequately from the P and T system, and preventing carry-over from the trap are essential. Many environmental laboratories analyze gasoline with BTEX using long sample purge (11 to 15 minutes), dry purge (2 to 4 minutes), trap desorb (2 to 4 minutes), and trap bake (10 to 20 minutes) times. Therefore, a typical run usually takes 40 to 48 minutes including 3 to 5 minutes for trap cool-down.

Figure 1 shows a GC/FID analysis of a gasoline standard and a GC/PID chromatogram of a GROs standard using an OI 4460A P and T system with a BTX trap and DB-1 column (30 m x 0.53 mm x 5 μ m). GC and P and T conditions are listed in **Table 3**. Although the GC runs were completed in 27 minutes, the actual cycle time for each run was 37 to 40 minutes.

Table 1. Instrument Requirements and Optimized Conditions

A. Recommended Instrumentation

Gas chromatograph:	5890 Series II
Injection port:	Split/splitless inlet
Column:	HP-1, 30 m x 0.53 mm x 5.0 μ m (Part no. 19095Z-623)
Detector:	FID
Injection technique:	7695A P and T
Data system:	3365 ChemStation and HP Vectra 486/100MX

B. Experimental Conditions

GC Parameters

Inlet:	220°C, split injection (split ratio 5:1)
Carrier:	Helium, 10 ml/min, constant flow (6.5 psi at 40°C)
Oven parameters:	40°C (3 min) at 7°C/min to 125°C to 250°C (3 min) at 35°C/min
Detector:	FID, 300°C; nitrogen makeup gas, 25 ml/min; H ₂ , 30 ml/min; and air, 350 ml/min PID, 250°C

P and T Parameters

Line temperature:	200°C	Purge time:	11 min
Valve temperature:	200°C	Dry purge time:	1 min
Mount temperature:	40°C	Desorb time:	2 min
MCS line temperature:	100°C	Bake time:	5 min
Purge ready temperature:	30°C	BGB time:	2 min
MCS desorb temperature:	40°C		
Desorb preheat temperature:	245°C		
Desorb temperature:	250°C		
Bake temperature:	265°C		
MCS bake temperature:	300°C		




Figure 1. Typical chromatograms of gasoline and GROs standards using a DB-1 column under the GC and P and T conditions (Table 3) used in environmental testing laboratories (see Table 2 for peak identification).

Optimized GC Run Time

With the HP-1 column (30 m x 0.53 mm id x 5 μ m) and a faster oven temperature, the GC run time was initially reduced to 21 minutes for GROs and gasoline (see **Figure 2**). Good baseline separations and sharp symmetric peaks (**Figure 2B**) were obtained for all GROs, including surrogate (α,α,α -trifluorotoluene) and internal (4-bromofluorobenzene) standard. The oven temperature program used was 40°C (3 min) at 7°C/min to 125°C to 250°C (3 min) at 35°C/min and a constant carrier flow of 10 ml/min. Under these conditions (**Table 1**), both pentane and MtBE were clearly separated from the large solvent peak (menthanol).

Even though the last GROs component (naphthalene) eluted below 200°C at 17.8 minutes, the oven temperature was increased to 250°C to bake out the high-boiling material purged from the sample. As a result, no carryovers were found even with repeated injections of gasoline standard in the 23,000-ppb level.

GC run times were further lowered by using a thinner-film HP-1 column and/or faster oven temperature programs. **Table 4** shows the benefits of using various column thicknesses, temperature ramps, and carrier flows to achieve the optimal GC run time of 17 minutes. Analytes generally elute faster from a thin-film column (**Figure 4**). In **Figure 3**, the thick-film column retained hydrocarbons longer initially until the faster oven temperature ramp (15°C/min) sped up the elution of all GROs components from the column. To avoid potential coelution (peaks 4 and 5), a comparative smaller carrier flow (4.5 ml/min) was used instead of the optimal 10 ml/min carrier flow. Reducing the GC run time, however, would be counterproductive because the total run time is dependent on the P and T cycle.

Table 2. Analytes in Working Standards

Standards	Peak No.	Components	Concentration
GROS mix	1	MtBE	100 ppm each
	2	Benzene	
	3	Toluene	
	4	Ethylbenzene	
	5	m-/p-Xylene	
	6	o-Xylene	
	7	1,2,4-Trimethylbenzene	
	8	1,3,5-Trimethylbenzene	
	9	Naphthalene	
	10	α,α,α -Trifluorotoluene (SS)	
	11	4-Bromofluorobenzene (IS)	
Gasoline standard		Gasoline	500 ppm
Gasoline		Gasoline	2,500 ppm
Jet fuel		Aviation jet fuel	1,000 ppm




Figure 2. Chromatograms for gasoline and GROs standards using an HP-1 column under the optimal GC and P and T conditions listed in Table 1. (See Table 2 for peak identification.)





Figure 3. Chromatogram of GROs standards using a thick-film HP-1 (30 m x 0.53 mm x 5 μ m) column. (See Table 2 for peak identification and Table 4 for GC conditions.)

Table 3. Typical GC and P and T Conditions for Gasoline and BTEX Analysis

GC Parameters			
Injection:	Direct injection		
Carrier flow:	Initially 10 ml/min, constant pressure mode		
Oven temperature:	50°C (hold 3 min) to 125°C at 5°C/min to 240°C (5 min) at 45°C/min		
Detector:	PID (250°C) in series with FID (300°C)		
P and T Parameters			
Trap:	BTX trap		
Purge temperature:	Ambient	Purge time:	11 min
Dry purge temperature	22°C	Dry purge time:	2 min
Desorb preheat temperature	150°C	Desorb time:	4 min
Desorb temperature	180°C	Bake time:	15 min
Bake temperature:	200°C		

Figure 4. Chromatogram of GROs standards using a thin-film HP-1 (30 m x 0.53 mm x 3 µm) column. (See Table 2 for peak identification and Table 4 for GC conditions.)

Optimized P and T Cycle Time

Further optimization of the run was dependent on obtaining the most efficient parameters for the P and T cycle. Each aspect of the cycle was optimized as follows.

Sample Purge

Experimentation showed 11 minutes of purge time, or 440 ml of helium purge gas, to be the most efficient time for analyses of gasoline and GROs because shorter purge times (8 minutes or 320 ml of purge gas) were not sufficient to purge all GROs from the sample solution. **Figure 5** shows a comparative analysis of the same GROs standard shown in **Figure 2B** using 8 minutes of purge time instead of 11 minutes of purge time. The conditions for both analyses were the same and are shown in **Table 1**. By comparison, hydrocarbon recoveries (including aromatics) for the GC runs with 8 minutes of

sample purge were not as good particularly for the high-boiling fractions, such as trimethylbenzenes and naphthalene (compare peaks 7, 8, and 9 in **Figure 5** and **Figure 2B**). The naphthalene peak in **Figure 5** (8 minutes of purge) was remarkably


small, and area counts were lower than 1% of that recovered in **Figure 2B**. Based on this finding, 11 minutes is the optimal sample purge time for the determination of gasoline with BTEX.

Dry Purge

During sample purge, a larger amount of water is purged along with the volatile organics and is collected on the trap sorbent. Sorbent material in the Vocab-3000 trap is designed to minimize water trapping and reduce the release of excessive water onto the GC column during the thermal desorption process. A 1-minute dry purge of the Vocab trap was selected because the early-eluting peaks (such as pentane, MtBE, and benzene in **Figure 2**) were not skewed by water released from the trap onto the column.

Desorption

According to Klee¹, a fast and reproducible desorption temperature is the key to good chromatography using the P and T concentration technique. The higher the desorption temperature and desorption rate, the faster the volatile analytes can be moved to the GC column, and the narrower the peak widths of the early-eluting analytes. Therefore, a short desorption time is preferred. In addition,

Figure 5. Chromatogram of GROs standard using an 8-minute sample purge. (See Table 2 for peak identification and Table 1 for GC and P and T conditions.)

Doherty² reported that peak heights and peak areas of volatile organics, including those in the GROs mix, were virtually unchanged when the desorb time changed from 4 minutes to 1 minute. Several manufacturers of P and T systems also recommend a 1-minute desorb time for the routine analysis of volatile organics. However, experimentation (**Figure 2**) using a 2-minute desorb time at 250°C accommodated sharp initial peaks as well as good separation. This study applied a 2-minute desorption time at 250°C to all analyses.

Trap Baking

Three different bake times were evaluated for the Vocarb-3000 trap (used a bake temperature of 265°C, recommended for the Vocarb-3000 trap): 10, 8, and 5 minutes. At each bake time, the gasoline sample (1000-ppb concentration) was run using an 11-minute purge time followed by a run of reagent water with no sample purge. Chromatograms of these two runs were evaluated for carryover. In all three cases (bake times of 5, 8, and 10 minutes), no carryover was observed for any gasoline component. Therefore, a 5-minute bake time at 265°C was selected as an optimal bake time for the analysis of gasoline and GROs aromatics.

For samples containing 46,000 ppb of gasoline, no carry over from the trapped analytes was observed at the 5-minute bake time. This is based on the comparison of chromatograms of reagent water (0-minute purge) run immediately after each sample. However, carry over from the purge vessel was found. Repeated rinsing of the purge vessel with reagent water reduced the amount of carry over but did not eliminate it. Therefore, after a high level sample is run, it is advisable to remove and clean the purge vessel prior to the next run.

Heavier petroleum products, such as diesel and jet fuel (**Figure 6**), that often contain volatile components are also detectable by this method. Again, carry over is a problem. Carry

Table 4. GC Run Time of 17 Minutes

HP-1 Column Thickness	Oven Ramp	Carrier Flow Time
30 m x 0.53 mm x 5 µm	40°C (3 min) at 15°C/min to 250°C	4.5 ml/min (see Figure 3)
30 m x 0.53 mm x 3 µm	40°C (3 min) at 7°C/min to 95°C to 250°C (2 min) at 45°C/min	10 ml/min (see Figure 4)

over was observed in the reagent water (used an 11-minute purge) run immediately after the jet fuel sample.

Carry over ranged from 10 ppb to 60 ppb jet fuel and was high enough to cause a false-positive identification in subsequent runs.

As demonstrated by **Figure 7B** (a chromatogram of reagent water, 0-minute purge, run immediately after

a jet fuel sample), carry over from the Vocarb trap was found to be negligible. Clearly the carry over was the result of contamination from the purge vessel (see **Figure 7A**). Although repeated rinsing reduced the amount of carry over, it did not eliminate it completely. Purge vessel carry over was eliminated completely when the purge vessel and the purge needle were removed and cleaned (see **Figure 7C**).

Figure 6. Chromatogram of 1,000-ppb aviation jet fuel standard. (See Table 1 for GC and P and T conditions.)





Figure 7. Chromatograms of reagent water following the analysis of the 1,000-ppb aviation jet fuel sample. (See Table 1 for GC and P and T conditions.) Note: The chromatograms were plotted on the same FID response scale.



Conclusion

Determination of optimized P and T parameters is critical in establishing optimized run times for the analysis of gasoline/BTEX. By reducing the P and T bake time to 5 minutes and selecting shorter dry purge (1 minute) and desorption times (2 minutes), the overall P and T cycle was shortened to 25-26 minutes. This is compatible with the run time of 21-22 minutes established for optimized GC conditions. When carry over from the purge vessel is controlled, this same application can be used successfully for the analysis of samples containing in excess of 46,000 ppb of gasoline and other volatile organics in light petroleum products.

Acknowledgment

The authors wish to thank Mr. Robert Remlinger at the Pace Laboratory in Petaluma, California for providing his GC/FID and GC/PID chromatograms.

Reference

1. Matthew S. Klee, *GC Inlets—An Introduction*, Hewlett-Packard Company, 1991, Part No. 5958-9468.
2. Linda Doherty, "The analysis of volatile organics in drinking water with an OI 4460A purge and trap and an HP GC/MS system," Hewlett-Packard Company, GC/MS Application Note, August 1991, Publication No. (23) 5091-2477E.

Copyright © 1995, 2000 Agilent Technologies
Printed in USA 04/00


Printed on recycled paper
Publication Number 5963-9968E

www.agilent.com



Agilent Technologies
Innovating the HP Way

Ambient Headspace GC and GC-MSD Analysis of Non-Polar Volatiles in Water



Application

Gas Chromatography

February 2000

Authors

Michael J. Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Bruce D. Quimby
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Ambient headspace is an ideal method for prescreening samples prior to purge and trap (P&T) analysis. Instrumentation is protected from high level contaminants and rework is reduced. The nature of the technique also makes it attractive for high sample volume applications, such as monitoring of process water in food/beverage manufacturing.

Key Words

ambient headspace, drinking water, GC-FID, GC-micro ECD, GC-AED, GC-MSD, GC-MSD screener report, prescreening, purge and trap, retention time locking (RTL), nonpolar volatile organics

Introduction

Chlorination is a common practice for the disinfection of water supplies. The reaction of chlorine with dissolved organics in the water results in the formation of non-polar halogenated compounds. The principle compounds formed are the trihalomethanes. Usually, bromide salts are also present in water, and both brominated and chlorinated compounds are formed. Water sources also may be contaminated with industrial solvents, such as benzene, tetrachloroethene and methyl tertiary butyl ether (MTBE).

The analysis of these compounds is important to suppliers of drinking water, food and beverage processing companies, and industrial operations that discharge waste water.

Government regulations require that these compounds be measured in drinking water at part-per-billion (ppb) levels. Techniques like P&T are used routinely for this analysis. While P&T allows analysis at very low levels, problems arise with samples containing unexpectedly high levels of volatiles. Instrument contamination and subsequent carryover result in reduced productivity and higher cost. Prescreening using headspace analysis can prevent instrument contamination problems. Lab productivity is also increased with prescreening,

because the approximate concentration range of analytes is known before P&T. Re-work of samples outside the P&T calibration range is eliminated.

Ambient headspace is a fast, low-cost technique for analyzing non-polar volatiles in water. It can be used instead of normal heated headspace for prescreening. For non-government regulated analyses, ambient headspace can also be used for routine work.

This application note describes a method evaluated on several different instrument systems and detectors. The choice of configuration is based on the specific measurement requirements.

Experimental

Sample Preparation

Sodium sulfate (Fisher Scientific, 10-60 mesh) and 2-mL autosampler vials (Agilent part number 5182-0543) were baked and stored at 100 °C to prevent contamination with volatiles. One-milliliter disposable serological pipettes (Corning) and aluminum crimp caps (Agilent part number 5181-1215) were used as received. Distilled water for preparation of standards and blanks was purified by constant purging with carbon-filtered helium.



Agilent Technologies
Innovating the HP Way

Water samples are prepared for analysis as follows:

1. Sodium sulfate is added to each autosampler vial to form a layer of approximately 4 mm in height.
2. One milliliter of water sample is added to the vial with a disposable pipette.
3. The vial is immediately capped and crimped.
4. The sample is vortexed for about 3 seconds.

Standards are prepared as above, except 1 μL of spiking solution in methanol is added to 1 mL of purified water just before step 3. Only 1 μL is used to minimize the amount of methanol added to the water. The concentration of individual compounds in the spiking solution is 1,000 times higher than the desired final concentration in the vial.

A standards kit of volatiles in methanol was obtained from Supelco (part number 4-8804, Bellefonte, PA). The 58 compounds are divided into six different mixes. Spikes were prepared using one mix per vial.

Instrument Conditions

Table 1 lists the instrument conditions used.

Results and Discussion

Retention Time Locking

The method is designed for use on a variety of instrument configurations. Configurations used were GC-FID, GC-micro ECD, GC-AED, and GC-MSD. To simplify data analysis and comparison across the various instruments, retention time locking (RTL) is employed. RTL is a technique that matches the retention time (RT) from column-to-column and instrument-to-instrument to approximately 0.03 minutes¹. Using RTL, compounds are identified by searching a table of retention times that have been collected under locked conditions.

This method is locked to a table of RTs of 65 volatile compounds from EPA method 8260. The table was created by running mixtures of standards

on GC-MSD to confirm RTs based on mass spectra. The table is locked using tetrachloroethene at 4.247 minutes as the locking compound. To match the GC-MSD retention times to atmospheric pressure detectors, Agilent's method translation software² (MTL) is used in combination with RTL.

The mass spectra of the 65 compounds with retention times were collected into a user library. A screener database (SCD) was then constructed from this library reference. An SCD is used to screen for compounds based on RT and ion ratios. Combining precise RT with mass spectral information in the search reduces both false positives and false negatives in identifications.

Identifications for GC-FID and GC-micro-ECD used an RT table (Table 2) constructed with the GC RTL software. For each compound entry, the table contains the RT, molecular formula, and CAS number. Each detected peak in the chromatogram is searched against the table and a list of possible identities is generated. The more accurate and precise the RT control, the shorter the list of possible compounds for each peak.

The list of possible compounds is reduced further by searching with element information in addition to retention time. The presence or absence of a specific element can rule out compounds from the list. When used with GC-AED, this filtering can be extended further by using element ratios³.

GC Column

The HP-5MS column chosen for this method is not necessarily the best or most common choice for volatiles. The desire is to use a column that is already in use in most laboratories. This column also allows ease of changing between ambient headspace and liquid injections, because the column is suitable for both. The flow characteristics of the column are compatible with the MSD and all other GC detectors.

Inlet Liner

An injection port liner used with ambient headspace is small in volume

compared to liners used for liquid injections. The sample is already a gas when injected, so there is no significant expansion. The small volume liner provides better peak shape for early eluting compounds that are not cold-trapped at the head of the column. A lower split ratio can be used, which results in better sensitivity. Liners of larger i.d. can be used successfully, but require higher split ratios to maintain peak shape.

Autoinjector

Ambient headspace is done using a gastight syringe. The largest volume syringe that can be used with the autoinjector is a 100- μL syringe (only half the volume can be injected). Note, the sampling depth of 20 mm is a critical parameter. This depth corresponds to drawing sample from the headspace and not from the water (Figure 1). Failure to set this parameter correctly will result in injecting 50 μL of salt solution into the inlet, causing instrument failure.

To minimize carryover between samples, the syringe is washed first with methanol and then water. Trace amounts of methanol in the syringe will give a peak on some detectors. The three water washes are required to minimize the residual methanol while allowing the maximum number of runs between solvent replenishment. If only trace level samples are being analyzed, the methanol wash can be eliminated, and the water washes can be reduced to one.




Figure 1. Headspace sampling from a 2 mL autosampler vial.

Table 1. Instrument Conditions**Gas Chromatograph Agilent 6890 or 6850**

Injection Port	Split/splitless
Temperature	200 °C
Liner	Deactivated 1-mm i.d. (Restek 20973)
Carrier gas	Helium
Inlet pressure	20 psi (adjusted to lock), constant pressure
Split ratio	1:1

Column	HP-5MS, 30 m x 0.25 mm x 0.25 µm, part numbers 19091S-433 (for 6890) or 19091S-433E (for 6850)
---------------	--

Initial temperature	35 °C
Initial time	2 min
Temperature ramp	18 °C/min
Final temperature	70 °C
Final time	0 min
Ramp A	45 °C/min
Final temperature A	250 °C
Final time A	0 min

Autoinjector Agilent 7683

Syringe	100-µL gastight injector, 5183-2042
Injection volume	50 µL
Solvent A	Methanol, 1 wash
Solvent B	Water, 3 washes
Sample rinses	None
Sample pumps	3
Injection speed	Fast plunger
Viscosity delay	5
Sampling depth	20 mm

FID Conditions

Temperature	250 °C
Hydrogen	40 mL/min
Air	450 mL/min
Helium makeup	45 mL/min

AED Conditions

Makeup gas	15 mL/min
Reagent gases	
Hydrogen	15 psi
Oxygen	10 psi
Temperatures	
Transfer line	250 °C
Cavity	250 °C
Solvent vent	None

5973 MSD Conditions

GC inlet pressure	6.6 psi (adjusted to lock), constant pressure
Temperatures	
Source	230 °C
Quad	150 °C
Transfer line	260 °C
Mass range	35-300 amu
Scans	5.27/sec
Samples	2
Threshold	50
EM voltage	BFB.u tune voltage
Solvent delay	None

Micro-ECD Conditions

Temperature	250 °C
Makeup gas	Nitrogen
Constant column + makeup flow	60 mL/min

Software for RTL Ambient Headspace on GC**Commercial software**

GC ChemStation software *revision A.05.04 or higher*
 GC RTL software *revision A.05.02*

User contributed software

GC RTL volatiles database
 GC RTL autolocker
 GC RTL autosearcher

Software for RTL Ambient Headspace on GC/MSD**Commercial software**

MS ChemStation software *revision B.01.00 or higher*

User-contributed software

MS RTL volatiles screener database
 MS RTL volatiles library

Table 2. Volatiles Ambient (HS)

FID RT	Compound Name	CAS No.	Molecular Formula	Weight	MSD RT	MSD Target & Qualifier Ions			
1.196	air, nitrogen	7727-37-9	N ₂ ,	28.0	1.191	14	16	30	14
1.196	air, argon	7440-37-1	Ar:1,	40.0	1.191	40	42	40	40
1.217	dichlorodifluoromethane	75-71-8	C:1,Cl:2,F:2,	120.9	1.220	85	87	101	50
1.240	chloromethane	74-87-3	C:1,H:3,Cl:1,	50.5	1.244	50	52	49	47
1.240	water	7732-18-5	H:2,O:1,	18.0	1.242	17	19	16	16
1.261	vinyl chloride	75-01-4	C:2,H:3,Cl:1,	62.5	1.266	62	64	61	60
1.267	methanol	67-56-1	C:1,H:4,O:1,	32.0	1.267	31	29	15	30
1.313	bromomethane	74-83-9	C:1,H:3,Br:1,	93.9	1.317	94	96	93	95
1.331	chloroethane	75-00-3	C:2,H:5,Cl:1,	64.5	1.333	64	66	49	51
1.403	trichlorofluoromethane	75-69-4	C:1,Cl:3,F:1,	135.9	1.407	101	103	66	105
1.496	1,1 - dichloroethylene	75-35-4	C:2,H:2,Cl:2,	96.9	1.499	61	96	98	63
1.547	methylene chloride	75-09-2	C:1,H:2,Cl:2,	84.9	1.551	49	84	86	51
1.670	trans - 1,2 - dichloroethene	156-60-5	C:2,H:2,Cl:2,	96.9	1.673	61	96	98	63
1.725	MTBE methyl-t-butyl ether	1634-04-4	C:5,H:12,O:1,	88.1	1.702	73	57	41	43
1.744	1,1-dichloroethane	75-34-3	C:2,H:4,Cl:2,	99.0	1.745	63	65	83	85
1.931	cis - 1,2 - dichloroethene	156-59-4	C:2,H:2,Cl:2,	96.9	1.933	61	96	98	63
1.982	2,2-dichloropropane	590-20-7	C:3,H:6,Cl:2,	113.0	1.983	49	130	128	
2.001	bromochloromethane	74-97-5	C:1,H:2,Cl:1,Br:1,	129.4	2.002	77	79	97	61
2.008	chloroform	67-66-3	C:1,H:1,Cl:3,	119.4	2.009	83	85	47	48
2.247	1,1,1-trichloroethane	71-55-6	C:2,H:3,Cl:3,	133.4	2.246	97	99	61	63
2.283	1,2 - dichloroethane	107-06-2	C:2,H:4,Cl:2,	99.0	2.284	62	64	49	63
2.343	1,1 - dichloropropene	563-58-6	C:3,H:4,Cl:2,	111.0	2.345	75	39	110	77
2.402	benzene	71-43-2	C:6,H:6,	78.1	2.402	78	77	51	52
2.403	carbon tetrachloride	56-23-5	C:1,Cl:4,	153.8	2.406	117	119	121	82
2.805	1,2 - dichloropropane	78-87-5	C:3,H:6,Cl:2,	113.0	2.814	95	130	132	97
2.805	trichloroethene	79-01-6	C:2,H:1,Cl:3,	131.4	2.801	63	62	39	76
2.846	dibromomethane	74-95-3	C:1,H:2,Br:2,	173.9	2.840	93	174	95	172
2.902	bromodichloromethane	75-27-4	C:1,H:1,Cl:2,Br:1,	163.8	2.902	83	85	47	48
3.339	cis - 1,3 - dichloropropene	10061-01-5	C:3,H:4,Cl:2,	111.0	3.334	75	39	77	110
3.688	trans - 1,3 - dichloropropene	10061-02-6	C:3,H:4,Cl:2,	111.0	3.677	75	39	77	110
3.700	toluene	108-88-3	C:7,H:8,	92.1	3.689	91	92	65	63
3.761	1,1,2 - trichloroethane	79-00-5	C:2,H:3,Cl:3,	133.4	3.754	97	83	99	61
3.900	chloropicrin	76-06-2	C:1,Cl:3,N:1,O:2,	162.9	3.888	76	41	78	49
3.944	1,3 - dichloropropane	142-28-9	C:3,H:6,Cl:2,	113.0	3.937	117	119	82	47
4.077	chlorodibromomethane	124-48-1	C:1,H:1,Cl:1,Br:2,	208.3	4.066	129	127	131	48
4.214	1,2 - dibromoethane	106-93-4	C:2,H:4,Br:2,	173.9	4.203	107	109	79	81
4.247	tetrachloroethene	127-18-4	C:2,Cl:4,	165.9	4.245	166	164	129	131
4.671	chlorobenzene	108-90-7	C:6,H:5,Cl:1,	112.6	4.663	112	77	114	51
4.707	1,1,1,2 - tetrachloroethane	630-20-6	C:2,H:2,Cl:4,	167.9	4.701	131	133	117	119
4.836	ethylbenzene	100-41-4	C:8,H:10,	106.2	4.821	91	106	51	65
4.913	p - xylene	106-42-3	C:8,H:10,	106.2	4.904	91	106	105	77
4.914	m-xylene	108-38-3	C:8,H:10,	106.2	4.902	91	106	105	77
5.072	bromoform	75-25-2	C:1,H:1,Br:3,	252.8	5.060	173	175	171	93
5.137	o - xylene	95-47-6	C:8,H:10,	106.2	5.129	104	103	78	51
5.143	styrene	100-42-5	C:8,H:8,	104.2	5.110	91	106	105	77
5.317	1,1,2,2 - tetrachloroethane	79-34-5	C:2,H:2,Cl:4,	167.9	5.304	83	85	95	61
5.378	1,2,3 - trichloropropane	96-18-4	C:3,H:5,Cl:3,	147.4	5.365	75	110	77	61
5.413	isopropylbenzene	98-82-8	C:9,H:12,	120.2	5.404	105	120	77	79
5.505	bromobenzene	108-86-1	C:6,H:5,Br:1,	157.0	5.463	77	156	158	51
5.646	2 - chlorotoluene	95-49-8	C:7,H:7,Cl:1,	126.6	5.626	91	120	92	65
5.646	n - propylbenzene	103-65-1	C:9,H:12,	120.2	5.639	91	126	89	63
5.680	4 - chlorotoluene	106-43-4	C:7,H:7,Cl:1,	126.6	5.671	91	126	125	63
5.760	1,3,5 - trimethylbenzene	108-67-8	C:9,H:12,	120.2	5.746	105	120	77	119
5.933	tert - butylbenzene	98-06-6	C:10,H:14,	134.2	5.924	119	91	134	77
5.944	1,2,4 - trimethylbenzene	95-63-6	C:9,H:12,	120.2	5.928	105	120	77	119
6.032	1,3 - dichlorobenzene	541-73-1	C:6,H:4,Cl:2,	147.0	6.021	146	148	111	75
6.054	sec - butylbenzene	135-98-8	C:10,H:14,	134.2	6.043	105	134	91	77
6.076	1,4 - dichlorobenzene	106-46-7	C:6,H:4,Cl:2,	147.0	6.066	146	148	111	75
6.142	p - isopropyltoluene	99-87-6	C:10,H:14,	134.2	6.127	119	134	91	117
6.227	1,2 - dichlorobenzene	95-50-1	C:6,H:4,Cl:2,	147.0	6.213	146	148	111	75
6.341	n - butylbenzene	104-51-8	C:10,H:14,	134.2	6.320	91	92	134	65
6.514	1,2 - dibromo - 3 - chloropropane	96-12-8	C:3,H:5,Cl:1,Br:2,	236.4	6.494	157	75	155	39
7.011	1,2,4 - trichlorobenzene	120-82-1	C:6,H:3,Cl:3,	181.5	6.981	180	182	184	145
7.057	naphthalene	91-20-3	C:10,H:8,	128.2	7.026	128	127	129	51
7.163	hexachlorobutadiene	87-68-3	C:4,Cl:6,	260.8	7.146	225	227	223	190
7.181	1,2,3 - trichlorobenzene	87-61-6	C:6,H:3,Cl:3,	181.5	7.151	180	182	184	145

Sample Preparation

In the analysis of trace volatile compounds, it is critical to maintain low blank levels. The sample vials, reagent water, sodium sulfate, and laboratory environment must be free of contamination by volatiles. Store the vials and sodium sulfate in a laboratory glassware oven at 100 °C. Prepare the reagent water by purging distilled water with carbon-filtered helium in a gas-washing bottle at room temperature. Purge the water continuously to keep it ready for immediate use. Contamination via laboratory air typically is due to use of solvents in the lab or by cross-contamination from garments of lab personnel. Be careful choosing the sample preparation area.

Experiments were carried out to determine the relative effects of temperature and "salting out" on the headspace extraction efficiency. Raising the temperature of the autosampler tray to 60 °C increased the recovery of most compounds. However, the addition of sodium sulfate provides similar efficiency at room temperature. In practice, the sodium sulfate and vials are allowed to cool to room temperature. Sodium sulfate is added to each vial to a height of approximately 4 mm.

Blanks and samples are treated similarly. A 1-mL aliquot is pipetted into a vial containing sodium sulfate and crimped immediately. Spikes are prepared the same way, but 1 µL of spiking solution is added with a 5-µL GC syringe just before crimping. Note, when the tip of the syringe is placed into the water, agitation is minimized.

The caps are crimped tightly enough that they cannot be rotated by hand. Baking the caps at 100 °C caused improper sealing and resulted in leaks. Therefore, the crimp caps are used unbaked.

Vortexing for 3 seconds is sufficient to transfer the volatiles to the headspace. If a vortex mixer is not available, vigorous manual shaking for 15 seconds will suffice.

GC-FID

Figure 2 shows the FID chromatogram of a 20-ppb standard spike of volatiles mix 4. The FID response to the volatiles varies significantly with halogen content. Bromochloromethane and 2,2-dichloropropane are not resolved. Peak 7, tetrachloroethene at 4.247 minutes, is the locking peak used for RTL.

In this method, the split ratio is initially set to 1. A spike containing the mixture from Figure 2 is run and the peak shape of peaks 2 and 4 are inspected for tailing. If they tail, the split ratio is increased until the tailing is just minimized. In this specific setup, the split ratio was set to 2.

The chromatogram shows that the FID can provide a broad-based screen for nonpolar volatiles in the low ppb range.

Figure 3 shows the FID chromatogram and the MSD total ion chromatogram (TIC) of a 20-ppb standard spike of methyl-t-butylether (MTBE) in blank water. MTBE is often found in groundwater due to oxygenated gasoline leaking from underground storage tanks. MTBE can be detected at low ppb levels using either detector.

In both Figures 2 and 3, a large methanol solvent peak is present. This is due to the 1-µL methanol-based spiking solution.




Figure 2. 20 ppb spiked standard (mix 4) in blank water by FID.




Figure 3. 20 ppb MTBE spike in blank water.

GC-MSD

The TICs of the six standard mixes spiked into blank water are shown in Figure 4. Using the MSD data, the following steps are taken:

1. Determine identity and retention time for each compound.
2. Create a spectral library of the 58 compounds.
3. Create a screener database by combining the results of steps 1 and 2.

There are nine pairs of compounds that overlap chromatographically. However, use of extracted ions differentiates all of the overlapped peaks. Peak identification with the screener software is accomplished using precise retention time, extracted ions, and spectral cross-correlation. The process used by the screener software is as follows:

1. Takes the retention time of the first compound in the database and extracts the target and qualifier ion chromatograms.
2. Integrates the ion chromatograms over a user specified time search window.
3. Compares the ratio of each qualifier ion to the target ion.
4. If the ratios fall within user specified criteria, the compound is marked as a "hit".
5. The results from steps 2 through 4 determine how the compound is reported.
6. Perform a cross-correlation between the sample spectrum and the library spectrum to aid in confirmation.
7. Repeat this process for each compound in the Screener Database.
8. Combine the results into a user definable report format and print the report.

Figure 5 shows the GC-MSD screener report for a tap water sample. Of the 65 compounds in the screener database, four were reported. A "?" in the status column indicates that the target ion was found, but that one or more of the qualifier ratios did not meet criteria. The out-of-range quali-




Figure 4. Six VOA calibration standard mixes by MSD.

```
Screen Report      (Not Reviewed)
```

```
Data File : D:\DATA\AHS_MSD2\Sample1.D      Vial: 6
Acq On   : 10 Aug 1999 17:20                Operator: Mikeski
Sample   : Sample1 unfiltered #2             Inst  : GC/MS Ins
Misc     :                                  Multiplr: 1.00
                                           Sample Amount: 0.00
```

```
MS Integration Params: RTEINT.P
```

```
Screen File: AMHSMOD1.RES      Extraction Window: +/- 0.150 min
Screen Database: AMHSMOD1.SCD  Qualifier Mode   : Absolute
                               Qualifier %      : 20
                               Zero qualifiers   : Included
                               Subtraction Mode  : Relative Areas
```

Compound	Status	ExpRT	Delta	Target m/z	Resp.	Qualifiers Out of Range	XCR
17 bromochloromethane	?	2.002	+0.008	49	476	130,128	0.07
18 chloroform	x	2.009	-0.003	83	4817		1.00
27 bromodichloromethane	x	2.902	-0.000	83	3091		0.98
33 chlorodibromomethane	x	4.066	+0.007	129	801		0.94

```
Screen Report Mon Aug 16 12:12:48 1999
```

Figure 5. GC-MSD Screener report.

fiers are listed in the report. An "X" in the status column means that the target ion was found and that all of the qualifier ratios met criteria. The number in the "XCR" column indicates the quality of the match of the sample spectrum to the library spectrum, with 1.0 being a perfect cross-correlation.

As an example, the extracted ion chromatograms for chlorodibromomethane found in a tap water

sample are shown in Figure 6. In this case, the search window was 0.1 minutes. The ratios of ions 127, 131, and 48 to the target ion 129, met criteria. In Figure 7, the sample spectrum matches the chlorodibromomethane library spectrum, resulting in a high XCR.

The combination of precise RT, qualifier ion ratios, and cross-correlation gives high confidence in chlorodibromomethane being present in the sample.

GC-AED

Figure 8 shows the chromatograms resulting from ambient headspace analysis on four different GC systems. Note how closely the RTs match system to system as a result of RTL.

The AED is useful in this type of analysis for the following reasons:

1. The carbon 193 nm chromatogram is very sensitive (about five times better than the FID).
2. The AED carbon channel responds to all compounds that contain carbon, even those that exhibit little or no response in the FID (examples: CO₂, CS₂, CCl₄).
3. The response factors for each element are independent of compound structure, allowing quantitation without having to run standards for all compounds.
4. With proper calibration, the element mole ratios (empirical formulae) can be calculated for unknown compounds.
5. The specificity of the AED differentiates the individual halogens in unknowns.

The chromatograms in Figure 8 show that the C 193 channel provides low-level general-purpose screening for volatiles. The chlorine and bromine channels clearly indicate which compounds contain each halogen.

Combining GC-AED with GC-MSD provides the broadest possible screening capability. The AED will show the presence of any volatile, its element content, and the concentration of the compound based on element response factors. GC-MSD identifies the volatile based on spectral information. This approach maximizes the speed and efficiency with which unknown compounds can be identified and quantitated.

GC-micro ECD

Also shown in Figure 8 is the analysis performed with GC-micro ECD. The signal-to-noise ratio is very high for those compounds that are responsive on ECD. The Agilent micro-ECD is uniquely suited for the detection of ultra low-level polyhalogenated com-




Figure 6. Extracted ions used by Screener to look for chlorodibromomethane.




Figure 7. Sample and library spectra used by Screener for cross correlation.

pounds. It has a high response factor for polyhalogenated compounds and a low response factor for other compounds, minimizing interferences.

The micro-ECD peaks in Figure 8 were searched against the GC RTL volatiles database. A portion of the search report is shown in Figure 9.

For each peak, the possible identities and information useful for GC-MSD analysis are given.

The sensitivity of the micro-ECD is demonstrated in Figure 10, where the polyhalogenates in mix four are easily detected at 20 parts per trillion. The detection limit observed with the

micro-ECD is comparable to that seen in routine P&T methods.

To further demonstrate the detection capability of the micro-ECD, Figure 11 shows the chromatogram from Figure 8 with an expanded Y axis. This tap water sample has >75 discernable peaks. One interesting compound detected was chloropicrin (trichloronitromethane). Chloropicrin was used as a chemical warfare agent in World War 1. However, its presence at ppt levels in drinking water is not surprising, as it is a known disinfection byproduct⁴. The identification of the compound was confirmed by GC-MSD with single-ion monitoring on multiple masses.

Figure 11 shows the same tap water after passage through a commercial spigot filter. The filter lowers the level of detected compounds by a factor of 100 to 300 fold.

Precision

The precision of the technique is illustrated in Figure 12. The raw area repeatability for 10 consecutive vials of a tap water sample is 6.1% RSD. Note that this is measured with a peak present in the ppt concentration range. The retention time precision is also very good, a result of the Agilent 6890 oven and pneumatics performance.

The precision over an extended period of time also was tested. A series of 15 samples spiked with 200 ppb benzene was prepared in blank water and run in groups of five. The first group was run immediately as a control. The second group was left at room temperature and run 4 hours later. The last group, also held at room temperature, was run 24 hours later. The raw area repeatability for all 15 vials was 10% RSD. This includes the uncertainty introduced with the 1- μ L spiking process. The maximum deviation of the retention time of benzene was 0.002 minutes.

Linearity

The linear dynamic range (LDR) of the technique was measured and is shown in Table 3. Five concentrations of nonpolar halogenated volatiles




Figure 8. Local tap water sample RT locked on four instrument systems.

Data File: D:\HPCHEM\1\DATA\AHS_ECD2\NIXONU_2.D	
Sample Name: Nixon U #2	
Instrument 1 9/30/99 8:44:34 AM	
=====	
Results of Table Auto-Search for Signal 1	
=====	
Search results for 2.019 +/- 0.015 minutes	
2.008 chloroform	Weight 119.38
CAS No. 67-66-3	
Mol Formula C:1,H:1,Cl:3,	
MSD RT 2.009	
MSD Target & Qualifier Ions 83 85 47 48	
Search results for 2.905 +/- 0.015 minutes	
2.902 bromodichloromethane	Weight 163.83
CAS No. 75-27-4	
Mol Formula C:1,H:1,Cl:2,Br:1,	
MSD RT 2.902	
MSD Target & Qualifier Ions 83 85 47 48	

Figure 9. GC RTL autosearch report.

covering the range of 0.02 to 200 ppb were analyzed using the micro-ECD. The correlation coefficients for six compounds are all 0.99 or better, demonstrating that the technique is linear. The upper end of the LDR in this case is limited by saturation of the micro-ECD. This data, taken with that of other detectors, indicates the linear range of the sampling technique extends at least from 0.02 ppb to 2000 ppb. In practice, the LDR is determined by the detector used.

Table 3. μ ECD Linearity, 0.02-200 ppb includes error in spiking 1 μ L

Compound	Corr. Coef.
Chloroform	0.994
1,1,1-trichloroethane	0.999
Carbon tetrachloride	0.999
Dibromomethane	0.990
Tetrachloroethene	0.998
Bromoform	0.996




Figure 10. 20 ppt mix 4 in blank water by μ ECD.




Figure 11. Local tap water sample by μ ECD.




Figure 12. Chromatograms from 10 analyses of tap water, overlaid all in the same scale.

Conclusions

Ambient headspace is a fast, low cost, simple, and robust technique for the analysis of nonpolar volatile organics in water. The technique is easily implemented on an Agilent 6890 or 6850 GC. Given the broad range of detectors available for these GCs, the sensitivity, selectivity, and linear dynamic range can be matched to analyst's needs.

Ambient headspace is an ideal method for prescreening samples prior to P&T analysis. Instrumentation is protected from high level contaminants and rework is reduced. The nature of the technique also makes it attractive for high sample volume applications, such as monitoring of process water in food/beverage manufacturing.

References

1. B. D. Quimby, L.M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking" Application Note 228-401, Publication number 5967-5820E, May 1998 (Downloadable from [agilent.com](http://www.agilent.com))
2. Agilent's GC Method Translation software (available free from the Agilent Technologies Web site, <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#mxlator>)
3. M. J. Szelewski, "Empirical Formula Determinations and Compound-Independent Calibration Using a GC-AED System", Application Note 228-382, Publication Number 5965-8144E, May 1997 (Downloadable from [agilent.com](http://www.agilent.com))
4. USEPA Method 551.1, Methods for the Determination of Organic Compounds in Drinking Water, Supplement III, ORD, USEPA, Cincinnati, Ohio 45268. EPA/600/R95/131, August 1995.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


HP® is a registered trademark of Hewlett-Packard Company.

Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5968-9455E



Agilent Technologies
Innovating the HP Way



Analysis of EDB and DBCP in Water with the Agilent 6890 Series Gas Chromatograph and Agilent 6890 Micro-Electron Capture Detector — EPA Method 504

Application

Gas Chromatography

August 1997

Authors

Imogene L. Chang
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Joseph Murphy
Roy F. Weston Company
Lionville Lab
Lionville, PA 19341
USA

Abstract

The pesticides 1,2-ethylene dibromide (EDB) and 1,2-dibromo-3-chloropropane (DMCP) were analyzed by dual-column gas chromatography with dual micro-electron capture detectors (Agilent 6890 micro-ECDs) after micro-extraction with hexane in accordance with U.S. EPA method 504.

Stability, sensitivity, and linearity of the micro-ECD were significantly better than the classical ECD. Relative standard deviation (% RSD) for the entire method was less than 7% over a

concentration range greater than two orders of magnitude with method detection limits of 0.003 µg/L or lower.

Key Words

Micro-ECD, 6890 GC, EPA Drinking Water Method 504, ethylene dibromide, 1,2-dibromo-3-chloropropane, GC/ECD analysis

Introduction

Ethylene dibromide (EDB) and 1,2-dibromo-3-chloropropane (DBCP) are volatile pesticides and suspect carcinogens. The U.S. EPA regulates maximum contaminant levels (MCLs)

for these compounds in drinking water supplies at very low levels (EDB at 0.05 µg/L and DBCP at 0.2 µg/L). Both EDB and DBCP can be determined by performing a micro-extraction with hexane and analyzing the extract by gas chromatography using an electron capture detector (ECD), as described in EPA Method 504.¹

EPA method 504 reported method detection limits (MDLs) of 0.01 µg/L for both pesticides.^{1,2} Results using an Agilent 6890 GC with the micro-ECD show that these analytes can be determined down to 0.01 µg/L with MDLs of less than 0.003 µg/L. The micro-ECD had a stable baseline and was linear from 0.010 to 1.14 µg/L.

Table 1. Experimental Conditions

Sampler	Agilent 7673, 10-µL syringe, 2-µL splitless injection
Inlet	Split/splitless; 200 °C, pulsed splitless mode (20 psi for 1 min)
Carrier	Helium, 6 psi (40 °C); 3.5 mL/min constant flow (each column)
Column	(A) 30 m, 0.53-mm id, 0.8-µm film DB-608, an equivalent of HP-608 (part number 19095S-023) (B) 30 m, 0.53-mm id, 1.0-µm film RTX-1701, an equivalent of HP-PAS 1701 (part number 19095S-123)
Oven	40 °C (4 min); 10 °C/min to 240 °C
Detector	330 °C; Makeup gas: nitrogen, constant column and makeup flow (60 mL/min)



Agilent Technologies
Innovating the HP Way

Experimental

Samples and standards were prepared as described in EPA drinking water method 504.¹ All analyses were performed using a 6890 Series GC with a single split/splitless inlet and dual micro-ECDs. Instrument conditions are listed in table 1.

A water sample (35 mL) was extracted with 2 mL of hexane. From that extract, 2 μ L were injected into the 6890 Series GC in the splitless mode. A "Y" connector was used to split the sample equally between two polar but dissimilar columns. Column A (an equivalent of the HP-608 column), which provided separation of EDB and DBCP without interference from trihalomethanes, was used as the primary analytical column. Column B (an equivalent of the HP-1701 column) was used as the confirmation column. These columns were previously installed and used in the GC system to analyze pesticides and arachnids according to U.S. EPA CLP and 8080/8081 methods.

Results and Discussion

A common problem in determining EDB and DBCP in drinking water by gas chromatography/electron capture detection (GC/ECD) is interference from chlorination disinfection by-products such as trihalogenated methanes. For example, dibromochloromethane (DBCM), commonly found in drinking water supplies in relatively high concentrations, can elute very close to EDB and thus can be misidentified as EDB.

Using the optimized GC conditions listed in table 1, EDB was clearly separated from significant levels of DBCM on both columns. Typical chromatograms of a hexane extract of a calibration standard are shown in

figure 1. Both EDB and DBCP are well separated from possible interference, including DBCM and dibromomethane (DBM).

Micro-ECD Linearity

Linearity of the 6890 micro-ECD was determined by preparing standards from 0.005 to 1.14 μ g/L in reagent water. The standards were extracted according to EPA method 504 and analyzed by gas chromatography. Typical average response factors (based on peak heights), relative standard deviations (% RSD) of response factors (RFs), and correlation coefficients of the linear curves are listed in table 2.

Figure 2 shows linear calibration curves for EDB and DBCP with correlation coefficients better than 0.999

(see table 2). The % RSD of RFs was 4% to 7%, over a concentration range greater than two orders of magnitude (0.005 to 1.14 μ g/L). This easily met method 504 requirements for 20% RSD for a similar concentration range. The micro-ECD continued to meet these requirements over a period of 2 to 3 months with little or no maintenance required except for routine septum and liner changes.

MDLs, Precision, and Accuracy

Method detection limits (MDL) were calculated according to EPA method 504 by analyzing seven replicate extracts of a low-level standard (0.02 μ g/L). As shown in table 3, the MDLs were 0.002 and 0.003 μ g/L for EDB and DBCP, respectively. These MDLs were three- to five-fold below those reported by EPA method 504




Figure 1. Hexane extract of a midpoint calibration standard (EDB/DBCP = 0.286 μ g/L each).

Table 2. Typical Linearity on Column A*

Analyte	EDB	DBCP
Average response factor (RF)	4.66E-06	2.06E-06
Standard deviation, RF	2.19E-07	1.45E-07
%RSD, RF	4.69%	7.01%
Correlation coefficient	0.9992	0.9997

* Seven-level calibration at 0.0057, 0.020, 0.0571, 0.114, 0.286, 0.571, and 1.141 μ g/L




Figure 2. Typical calibration curves on column A

Table 3. MDLs, Precision, and Accuracy

Analyte	EDB	DBCP
Spiked concentration, µg/L	0.02	0.02
Number of replicates	7	7
MDL, µg/L	0.002	0.003
Spiked concentration, µg/L	0.20	0.20
Number of replicates	6	6
Average concentration, µg/L	0.202	0.205
Reproducibility, % RSD	5.3%	5.4%
% Recovery	101%	103%

and a Collaborative Study by K. W. Edgell and J. E. Longbottom.²

Six extracts of reagent water samples fortified with 0.20 µg/L of EDB and DBCP were analyzed. Both precision and accuracy were excellent, with reproducibility at 5% RSD and recovery of around 100% (see table 3).

Ruggedness of the 6890 Micro-ECD

For the detector to meet the low detection limit requirements, the chromatographic baseline must be clean and stable. In this study, the 6890 micro-ECD provided a clean baseline with no negative deflections during continuous operation over a period of 3 months. A variety of samples were also analyzed, including

soil pesticide extracts that contained many late-eluting compounds (see figure 3). The 6890 micro-ECD showed rapid recovery even though this instrument had been switched from a drinking water method (EPA method 504) to solid waste methods (EPA method 8080/8081 and CLP method for pesticides and arochlors³), and back again.

EPA method 504 requires a continuous calibration (using a midlevel standard) for each 12-hour shift of operation or every 10- to 20-sample analyses. The retention times and the responses for these continuous calibration runs must match those from the initial calibration run with specific limits. The difference in responses (%D) between the later calibration run and the initial run must be less than 15%.

Table 4 presents the results of the sequence runs on the 1st, the 15th, and the 27th day of a month when samples were continuously analyzed according to EPA method 504. Responses of the 6890 micro-ECD proved to be quite stable over 3 to 4 weeks of continuous operation. The %D of EDB and DBCP did not vary by more than 10%, easily meeting the method requirement of 15%.

Conclusion

The Agilent 6890 Series GC with the micro-ECD can detect low levels of EDB and DBCP in drinking water and water supplies. All EPA method 504 criteria were easily met, yielding MDLs of 0.003 µg/L or less, reproducibility of 7% or less, and a linearity with correlation better than 0.999 over a concentration range greater than two orders of magnitude.

The system performance was stable for a long time (3 months), despite switching methods between EPA method 504 and CLP method for pesticides and arochlor. Stability, sensitivity, and linearity of the 6890 micro-ECD were significantly improved over the classical 6890 ECD.




Figure 3. Typical chromatograms of sample extracts*

*The soil sample was analyzed according to EPA CLP method for pesticides along with 30 to 40 other samples in a sequence run.⁴ No target pesticide was detected in this particular sample. The water sample was analyzed along with 20 other water samples based on EPA method 504 on the next day after the 6890 system was switched from the CLP method. No DBCP was found in any sample, and EDB was detected in only 3 to 4 samples. EDB in this sample was at the 0.01- to 0.02-ppb level. These chromatograms were plotted on different scales. Note the high signal for the soil sample. This demonstrates that it was possible to shift very quickly from analyzing dirty soil samples to analyzing low-level water samples using the 6890 system with micro-ECD.

Table 4. System Performance

	Run	Retention Time		Responses		%D	
	No.	EDB	DBCP	EDB	DBCP	EDB	DBCP
Day 1 Sequence							
Initial calibration	7	8.16	14.62	28486	70242		
Continuous calibration	19	8.16	14.62	29118	72434	2.2%	3.1%
Continuous calibration	30	8.16	14.61	28969	74268	1.7%	5.5%
Day 15 Sequence							
Initial calibration	7	8.11	14.58	30878	64439		
Continuous calibration	18	8.10	14.56	31684	66978	2.6%	0.8%
Continuous calibration	29	8.12	14.58	31241	71009	1.2%	6.9%
Continuous calibration	34	8.12	14.59	31219	70276	1.1%	5.8%
Continuous calibration	50	8.13	14.59	31689	72829	2.6%	9.6%
Continuous calibration	60	8.12	14.59	31627	72974	2.4%	9.8%
Day 27 Sequence							
Initial calibration	6	8.13	14.59	32203	76362		
Continuous calibration	19	8.13	14.59	31557	74711	-2.0%	- 2.2%
Continuous calibration	28	8.13	14.59	31855	75417	-1.1%	- 1.2%

* %D = (initial response - continuous calibration response) / initial response

References

1. "Methods for the Determination of Organic Compounds in Drinking Water" – Method 504, rev. 2.0, U.S. EPA (1991).
2. K. W. Edgell and J. E. Longbottom, "Determination of 1,2-Dibromoethane and 1,2-Dibromo-3-Chloropropane in Water by Microextraction and Gas Chromatography: Collaborative Study," *J AOAC Int.*, vol 77, p. 989 (1994).
3. Method 8081 – "Organochlorine Pesticides and PCBs as Arochlors by Gas Chromatography: Capillary Column Technique," September 1994 in U.S. EPA SW-836 "Test Methods for Evaluating Solid Wastes, Physical and Chemical Methods," Third Edition.
4. U.S. EPA Contract Laboratory Program "Statement of Work for Organic Analysis," OLM03.1, August 1994.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright ©2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5966-0495E



Agilent Technologies
Innovating the HP Way



Analysis of Formaldehyde and Acetaldehyde in Air by HPLC using DNPH Cartridge

Noriko Shimoi and
Hiroki Kumagai

Environment

Abstract

The monitoring of aldehydes, especially formaldehyde and acetaldehyde, is important for the monitoring of air pollution and acid rain problems. These aldehydes are analyzed by HPLC using 2,4-dinitrophenylhydrazine (DNPH) as the derivatization reagent. The cartridge of silica gel that was impregnated with DNPH (DNPH cartridge) is commonly used for the sampling and concentrating of aldehydes in air.


This application brief describes the analysis of formaldehyde and acetaldehyde in the air using DNPH cartridge.

Analyzed Compounds

Formaldehyde and acetaldehyde in air as DNPH derivatives.

Sample

Air of some location in Japan.



Conditions

Column

250 mm ~ 4.6 mm i.d. Inertsil ODS 80A

Mobile Phase

CH₃CN/H₂O = 50/50

Temperature

40 °C

Injection vol

25 µl

Diode array detector

A—365/8 nm, reference off

Figure 1
Chromatogram of DNPH derivatives of formaldehyde and acetaldehyde



Agilent Technologies

Innovating the HP Way

Sample Preparation

Sampling was performed by sucking air through the DNPH cartridge (ozone scrubber was inserted before DNPH cartridge) with a pump. Sampling time was 24 hours at a flow rate of 0.1 l/min. The actual sampling volume was measured by the flow meter.

Method performance

Limit of Detection: formaldehyde 0.25 $\mu\text{g}/\text{m}^3$, acetaldehyde 0.35 $\mu\text{g}/\text{m}^3$ (calculated from 3σ of blank values)

Repeatability of RT over 6 runs < 0.1 %

Repeatability of area over 6 runs < 0.5 %




Figure 2
Chromatogram of aldehydes in the air of city A (Japan)





Figure 3
Chromatogram of aldehydes in the air of city B (Japan)

Equipment

Agilent 1100 Series

- degasser
 - binary pump
 - autosampler
 - thermostatted column compartment
 - diode array detector
- Agilent ChemStation + software



The authors are application chemists at Yokogawa Analytical Systems Inc.

For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 06/97
Publication Number 5965-9796E



Agilent Technologies


Innovating the HP Way



Water

Semi-volatiles
Applications

> [Return to Table of Contents](#)
> [Search entire document](#)



Addressing the Challenges of Analyzing Trace Perfluorooctanoic Acid (PFOA) and Perfluorooctane Sulfonate (PFOS) Using LC/QQQ

Application

Food, Environmental

Authors

Robert D. Voyksner
LCMS Limited
PO Box 27228
Raleigh, NC 27611-7228
USA

Chin-Kai Meng
Agilent Technologies
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

An approach to the difficult task of quantifying trace quantities of perfluorooctanoic acid (PFOA) and perfluorooctane sulfonate (PFOS) in complex matrix was developed using liquid chromatography and tandem mass spectrometry (LC/MS/MS). The technique uses isotopically labeled analytes for accurate quantitation (0.4 to 400 pg on column). It is important to recognize that if using the linear chain sample as standard for calibration, the quantitation results of real-world samples (branched and linear isomers mixed) will be off by as much as 40%.

Introduction

Perfluorooctanoic acid (PFOA) is an industrial surfactant and a necessary processing aid in the manufacture of fluoropolymers [1]. Fluoropolymers have many valuable properties, including fire resistance and the ability to repel oil, stains, grease

and water. One of the most common uses of PFOA is for processing polytetrafluoroethylene (PTFE), most widely known as Teflon®. PFOA is also a by-product from direct and indirect contact with food packaging (for example, microwave-popcorn bags, bags for muffins or french fries, pizza box liners, boxes for hamburgers, and sandwich wrappers), and in the fabrication of water- and stain-resistant clothes.

Perfluorooctanesulfonic acid (PFOS) is usually used as the sodium or potassium salt and is referred to as perfluorooctane sulfonate. See Figure 1.




Figure 1. Chemical structures for PFOA and PFOS. Note that both have C8 chains.



Agilent Technologies

Analytical Methodology for PFOA/PFOS

- LC/MS/MS is the preferred detection methodology due to its high sensitivity and specificity in complex matrices.
- Multiple reaction monitoring (MRM) is used to quantitate, using two or more product ions for confirmation.
- The detection limit is typically in the range 1 to 100 pg/mL (ppt), requiring high-sensitivity detection.
- On-column or off-line solid-phase extraction (SPE) and concentration are needed to achieve low-level detection (1 pg/mL).

Measuring PFOS and PFOA

Issue 1: *What transitions should be used to give the best accuracy when quantifying with a linear standard?*

Quantification of PFOS and PFOA is usually based on a linear standard, but actual samples show a series of branched isomers together with the linear isomer. The ratio of these isomers varies based upon biodegradation and industrial processes in their formation; therefore, it is unlikely that a standard can be formulated to mimic the actual sample. The relative intensities of the MRM transitions will vary based upon branching, making some transitions better than others. Branching impacts ionization efficiency and CID energy; therefore, it affects the accuracy of analytical measurement [2].

Issue 2: *Can isotopically labeled standards in matrix be used to measure nonlabeled PFOS and PFOA?*

Most biological and environmental matrices have background levels of PFOS and PFOA; although matrix-matched calibrations are providing good results, the accuracy can be enhanced. The method of standard additions is a protocol to address this issue, but it adds several additional injections to the analysis. Matrix may have varying amount of background. Standard addition is not practical in analyzing many different matrices. Solvent calibrations do not correct for matrix effects.

Experimental

Sample Prep

- All solvent standards were prepared in methanol.

- Plasma extracts were prepared by acetonitrile precipitation and centrifuging, with the upper layer taken and spiked with known concentrations of PFOA or PFOS.

LC

- Agilent 1200 Rapid Resolution LC system
- ZORBAX Eclipse Plus C18 Rapid Resolution HT column 2.1 cm × 50 mm, 1.8-μm particles (P/N 959741-902)
- 20-μL injection, 0.4 mL/min column flow
- 0 to 100% B in 10 min, A = water with 2 mM ammonium acetate; B = MeOH

MS/MS

- Agilent QQQ
- Negative-ion detection
- 3500 V_{cap}, drying gas 9.5 L/min at 350 °C, nebulizer 45 psi
- Fragmentor voltages, collision energy (CE), and ion transitions are experimentally determined

Multiple Reaction Monitoring (MRM)

Figure 2 displays a cross-section of the Agilent 6410 QQQ above a hypothetical sequence of spectra characteristic of ion transitions within the instrument.

The ions are generated in the source shown at the far left of the figure. The precursor ion of interest is then selected from this mixture and isolated through the Q1 quadrupole, which acts as a mass filter. This is similar to selected ion monitoring (SIM). After Q1, characteristic fragments that are specific to the structure of the precursor ion are generated in the collision cell (Q2, although not a quadrupole). By using the Q3 quadrupole, these fragments are then selected for measurement at the detector. This is a selective form of collision-induced dissociation (CID), known as tandem MS/MS. By setting Q3 to a specific fragment ion existing in the collision cell, the chemical or background noise is almost totally eliminated from the analyte signal, therefore, significantly increasing the signal-to-noise ratio. Ion 210 is called the precursor ion and ions 158 and 191 are product ions. Each transition (210→191 or 210→158) is a reaction for a particular target. Typically, the QQQ is used to monitor multiple analytes or mass transitions, therefore, the term MRM. The 158 could be considered the quantitation ion, because it is the




Figure 2. A cross-section of the Agilent 6410 QQQ above a sequence of spectra characteristic of ion transitions within the instrument for a hypothetical sample (*not* PFOA or PFOS). Note that the final spectrum is very clean, containing only the desired target ions. (HED = high-energy dynode electron multiplier)

most intense, and 191 could be used for confirmation by using the area ratio of the 191 qualifier to the 158 quantifier ion as a criterion for confirmation. With MRM, most chemical noise is eliminated in Q1, and again in Q3, allowing us to get ppt detection.

The fragmentor is the voltage at the exit end of the glass capillary where the pressure is about 1 mTorr. Fragmentor and collision energies need to be optimized. A fragmentor that is too small won't have enough force to push ions through the gas. A fragmentor that is too high can cause CID of precursor ions in the vacuum prior to mass analysis, thereby reducing sensitivity. The actual voltage used is compound-, mass-, and charge-dependent, and therefore needs to be optimized to get the best sensitivity. The CE in the collision cell needs to be optimized in order to generate the most intense product ions representative of each target compound. Collision cell voltage will depend on the bond strength, the molecular weight of the compound, and the path by which the ion is formed (directly from the precursor ion or through a series of sequential intermediates). Typically each product ion will exhibit a preferential collision energy that results in the best signal abundance.

The experimental operations required to arrive at optimal conditions are exemplified by the series of experiments shown in Figures 3 to 5.

Optimization of the fragmentor voltages for the $[M-H]^-$ ions of PFOA (m/z 413) and PFOS (m/z 499) are shown in Figure 3.

Note that there is little signal detected for PFOA at the optimal fragmentor voltage for PFOS (200 V). Ions 413 and 499 are called precursor ions. PFOA is relatively fragile; its precursor signal drops off at 160 V. PFOS shows that it is harder than PFOA to break apart; the best fragmentor voltage for PFOS is 200 V.

The appropriate collision energies for product ions m/z 369 $[M-CO_2H]^-$ and m/z 169 $[C_3F_7]^-$ are experimentally determined and used to quantify PFOA. See Figure 4.

In each case the collision energy producing the most intense peak for each ion is chosen for the analysis. PFOA takes little collision energy to break into ion m/z 369 (6 V for highest intensity).




Figure 3. Determination of optimal fragmentor voltage using sequential plots of signal intensity versus applied voltage.

To maximize the intensity of the ion at m/z 169, the collision energy needs to go to 16 V.

The QQQ software can switch collision energies very rapidly. So in a method, the optimal collision voltage can be selected for each ion transition.

In the same manner, the appropriate collision energies for PFOS product ions at m/z 169, 99, and 80 are experimentally determined and used for its quantitation. The optimal collision energies for the three ion transitions are 45, 50, and 70 V. See Figure 5.




Figure 4. Signal intensity as a function of collision energy for PFOA product ions m/z 369 $[M-CO_2H]^-$ and m/z 169 $[C_3F_7]^+$.

Notice the big difference in collision energy between PFOA (6 to 16 V) and PFOS (45 to 70 V). We have seen from fragmentor optimization that PFOA is relatively fragile compared to PFOS, in which the optimum fragmentor voltages are 120 and 200 V for PFOA and PFOS, respectively. The CE reinforces that aspect.

Example calibration curves for the specified product ions used to quantitate PFOA and PFOS are shown in Figure 6. The analyst can also sum the intensities of these MRM transitions to get a calibration curve.

These five ion transitions exhibit linear correlation coefficients > 0.998, and are good for quantitation over three orders of magnitude. Notice that the lowest amount on column is 0.4 pg.

Regarding issue 1: *What transitions should be used to give the best accuracy when quantifying with a linear standard?*

This is addressed using Figures 7 to 9.

Figure 7 exhibits chromatograms from these representative transitions for PFOA and PFOS for the linear standard and samples containing branches (10-min gradient).






Figure 5. Signal intensity as a function of collision energy for PFOS product ions at m/z 169, 99, and 80.

PFOA



PFOS



Concentration range 0.02 to 20 ng/mL (0.4 to 400 pg injected on column)

Figure 6. Calibration curves for the product ions used to measure PFOA and PFOS.

Real-world samples have been detected with branched isomers due to manufacturing processes, metabolism, and degradation processes. The top chromatogram of Figure 7 shows only linear chain compounds from a standard. The bottom chromatogram is an actual sample from the environment. It shows additional peaks (shoulders) in the chromatogram resulting from branched isomers.

We examine those peaks in greater detail in Figure 8.




Figure 7. MRM chromatograms for PFOA and PFOS for both linear and branched samples.

The relative abundances for each MRM transition are dependent on the branching locations and the specific mass transitions. Figure 8 shows a 10-minute run. The chromatography can separate the linear from the branched isomers. The branched sample is typically a C7 chain with a methyl side group (isooctyl isomer). The most interesting part of the analysis is that the ion ratios for the branched compounds are very different from the linear chain compounds [3, 4, 5]. For

linear PFOA, the ion at m/z 169 is about 30 to 40% of ion 369. The branched isomer shows that the ratio changed to 90 to 100%. For linear PFOS, the ion at m/z 99 is about 50% of ion 80 and is 500% of ion 169. The branched isomer shows that ion 99 is only 20 to 30% of ion 80, and 100% of ion 169. This is a cause of concern in terms of quantitation accuracy. This shows that CID stability is very different when the analyte is branched.




Figure 8. MRM chromatograms for PFOA and PFOS for both linear and branched samples.

Another variable in the analysis is the gradient time. Figure 9 compares the effect of a 3-min versus 10-min gradient.

In the fast gradient case (on the right), the branched isomers (dashed lines) are not resolved from the linear isomers (solid lines), resulting in a significant error in the measured value (most noticeable for PFOS).

The two chromatograms on the left are the same two that are shown in Figure 8. They are used here for comparison against the unresolved analytes shown on the right (3-min run). Although we would like to cut down on the analysis time, the branched and linear isomers need to be resolved in order to get accurate quantitation results.

Two samples of the same concentration. One sample is the pure linear isomer; the other sample has a mixture of branched isomers. If their MRM responses (ion ratios) are the same, they would show the same results as when the isomers are not resolved. This example shows that the responses are not the same when the isomers are not resolved. If you add the responses of the side chain analyte and the linear chain analyte of the same sample, the area of each ion transition is different from the pure linear chain analyte ion transition, as seen in the two chromatograms on the right, most apparent is for PFOS. If using the linear chain sample as standard for calibration, the results of real-world samples (branched and linear isomers mixed) will be off by as much as 40% (see Table 1). The quantitation falls apart.




Figure 9. Comparison of PFOA and PFOS MRM chromatograms produced using both 10- and 3-minute gradients. The 3-minute gradient chromatograms are on the right.

The effect of measurement accuracy (*not* ion ratios) of total PFOA and PFOS in branched samples against a linear standard for each MRM transition is shown in Table 1.

Table 1. Measurement Accuracy (Target Is 100%) as Function of Compound, Transition, and Run Time

Compound	MRM transition	Percent response (n = 8)	
		10-min run	3-min run
PFOA	413→369	105.9	108.2
	413→169	96.4	89.4
PFOS	499→169	102.5	112.2
	499→99	75.0	73.3
	499→80	59.3	61.1

The best MRM ions are in bold type. The best results for PFOA can be obtained by averaging the results for the two MRM ions together.

Ion ratios can cause quantitation failure. For PFOA, it does not matter if it's a 3-min run or a 10-min run: the ion 369 transition response is always higher and the ion 169 transition response is always lower. The errors are larger for the 3-min run. The variations are greater for PFOS. In literature, PFOS analysis monitors the ion 80 transition, but it exhibits a large variation. It can be as low as 60%, as seen in Table 1. 499 → 169 is a good transition for quantitation. It is much more accurate, but it is less sensitive compared to 499 → 80 transition.

Regarding issue 2: Can isotopically labeled standards in matrix be used to measure non-labeled PFOS and PFOA?

This is addressed using Figures 10 to 12.

Observations regarding the effect of different matrices on signal responses are shown in Figure 10. The taller trace represents the response of PFOA in methanol. The response is lower as the same amount of PFOA is added into a plasma extract.

The matrix effect (common using electrospray ionization) can lead to signal suppression or enhancement; therefore, matrix-matched calibrations are required for accurate quantitation. Due to varying background levels of PFOS and PFOA in matrix, it may not be feasible to use matrix-matched calibrations for quantitating PFOS or PFOA concentrations in study samples. Also, the method of standard additions is not a practical alternative for many matrices with varying levels of target analytes.

As a practical alternative, measuring PFOA using isotopically labeled matrix-matched standards was examined. Results are shown in Figures 11 and 12.

Figure 11 shows that isotopically labeled standards can provide a good linear calibration curve over the quantitation range of 0.02 to 20 ng/mL (0.4 to 400 pg on column). Excellent linear correlation coefficients (≥ 0.9994) were obtained.





Figure 10. PFOA responses in MeOH and plasma extract at the same concentrations.



Calibration in plasma from 0.02 to 20 ng/mL

Figure 11. Linear correlations for PFOA using two different isotopically labeled calibration standards.




Figure 12. Both isotopically labeled PFOA compounds show good correlation to the unlabeled PFOA. The same transitions for the labeled and native forms of the PFOA were used.

Table 2. Comparison of Different Matrix-Matched Calibrations for Measuring PFOA in Plasma

	Calibration standard	Matrix for calibration	Plasma sample response (Std Dev)
1	PFOA	MeOH	71 (± 33 %)
2	PFOA [1,2- ¹³ C]	Plasma	100.4 (± 3.1 %)
3	PFOA [1,2,3,4- ¹³ C]	Plasma	97.3 (± 5.1 %)

Matrix-matched calibrations using isotopically labeled PFOA work well.

For row 1, the calibration standard used MeOH as the solvent, and the plasma sample exhibited a 71% response due to matrix suppression. Therefore, we cannot use a calibration standard in MeOH to quantitate samples in matrix; the variation can be as large as 30%. Rows 2 and 3 show that if the calibration is done using an isotopically labeled compound in matrix, the actual plasma sample yields accurate results: 100 and 97%.

Conclusions

- The Agilent LC/QQQ is an excellent instrument for quantifying trace target compounds in complex mixtures.
- The best ion transitions for analysis need to be determined experimentally.
- Fragmentor voltages and collision energies require experimental determination and optimization.
- Using MRM in the QQQ helps achieve the lowest detection limits in complex matrices.
- Branched PFOA/PFOS can affect quantitation accuracy as much as 40% unless it is corrected.
- Matrix suppression can cause the quantitation to be off by as much as 30%. Isotopically labeled analytes work well for accurate quantitation in spite of varying background levels of PFOA/PFOS in matrices.

References

1. Perfluorooctanoic Acid (PFOA), USEPA, <http://www.epa.gov/oppt/pfoa/>
2. T. J. Wallington, M. D. Hurley, J. Xia, D. J. Wuebbles, S. Sillman, A. Ito, J. E. Penner, D. A. Ellis, J. Martin, S. A. Mabury, O. J. Nielsen, and M. P. Sulbaek Andersen, "Formation of C₇F₁₅COOH (PFOA) and Other Perfluorocarboxylic Acids

During the Atmospheric Oxidation of 8:2 Fluorotelomer Alcohol," *Environ. Sci. Technol.*, 40 (3), 924–930, 2006

3. Jonathan P. Benskin, Mahmoud Bataineh, and Jonathan W. Martin, "Simultaneous Characterization of Perfluoroalkyl Carboxylate, Sulfonate, and Sulfonamide Isomers by Liquid Chromatography-Tandem Mass Spectrometry," *Anal. Chem.*, 79 (17), 6455–6464, 2007
4. I. Langlois and M. Oehme, "Structural identification of isomers present in technical perfluorooctane sulfonate by tandem mass spectrometry," *Rapid Commun. Mass Spectrom.* 20, 844–850, 2006
5. Amila O. De Silva and Scott A. Mabury, "Isomer Distribution of Perfluorocarboxylates in Human Blood: Potential Correlation to Source," *Environ. Sci. Technol.* 40, 2903–2909, 2006

Acknowledgement

Partial support and the standards for this study were provided by the Environmental Lab of the 3M Company (St Paul, MN).

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
April 23, 2008
5989-7790EN



Agilent Technologies



Fast USEPA 8270 Semivolatiles Analysis Using the 6890/5973 inert GC/MSD with Performance Electronics

Application

Environmental Analysis

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of semivolatiles using EPA Method 8270 presents challenges due to the simultaneous measurement of acids, bases, and neutrals over a wide concentration range. Due to productivity demands, laboratories want to run faster while maintaining linearity and sensitivity for even the most active compounds. The 6890/5973 inert GC/MSD system with Performance Electronics is designed to meet the criteria for fast analysis, while minimizing activity and maintaining linearity.

Introduction

USEPA Method 8270 for semivolatiles analysis is used to concurrently measure a mixture of acids, bases, and neutrals. Most laboratories analyze for 70–100 compounds with a chromatographic run time of 25–40 min. Laboratories want to reduce this run time for productivity increases. The calibration range required for the analysis varies

depending on a particular laboratory's statement of work (SOW). Historically, a range of 20–160 ng has been used. With the increased sensitivity of newer gas chromatograph/mass spectrometer (GC/MS) systems, laboratories are moving toward lower minimum detection limits (MDLs) and pushing the calibration range down to 1 ng.

The Agilent 6890/5973 *inert* GC/MSD (Gas Chromatograph/Mass Selective Detector) system with Performance Electronics was designed to meet the demand for faster runs and lower MDLs. Faster scan rates without loss of signal are now possible. This allows the use of smaller diameter columns, such as 0.18-mm id, resulting in shorter runs while maintaining sufficient data points across narrower chromatographic peaks.

The inert source allows for less material injected onto the column while maintaining mass spectrometer performance. Injection volume, therefore, can be matched to the 0.18-mm column. Performance comparisons using the inert source were published previously [1, 2].

This application note will demonstrate the use of the Agilent 6890/5973 *inert* with Performance Electronics for USEPA Method 8270. Smaller id columns with faster scan rates yield run times of 15 min while meeting Method 8270 criteria.



Agilent Technologies

Experimental

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized.

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet	EPC Split/Splitless		
Mode	Pulsed splitless, 0.5 μ L injection		
Inlet temp	250 °C		
Pressure	21.48 psi		
Pulse pres	40.0 psi		
Pulse time	0.20 min		
Purge flow	50.0 mL/min		
Purge time	1.00 min		
Total flow	54.0 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet Liner	Agilent splitless, single taper, 4-mm id, p/n 5181-3316		
Oven	240 V		
Oven ramp	°C/min	Next °C	Hold min
Initial		55	1.00
Ramp 1	25	100	0.00
Ramp 2	30	280	0.00
Ramp 3	25	320	4.60
Total run time	15 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies DB-5.625, p/n 121-5622		
Length	20.0 m		
Diameter	0.18 mm		
Film thickness	0.36 μ m		
Mode	Constant Flow = 1.0 mL/min		
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		

MSD	Agilent Technologies 5973 <i>inert</i> with Performance Electronics
Drawout lens	6-mm Large Aperture Drawout lens, p/n G2589-20045
Solvent delay	1.90 min
EM voltage	Run at DFTPP tune voltage - 153 V = 1012 V
Low mass	35 amu
High mass	500 amu
Threshold	10
Sampling	1
Scans/s	5.92
Quad temp	150 °C
Source temp	230 °C
Transfer line temp	280 °C
Emission current	DFTPP tune @ 25 μ A

Calibration Standards were obtained from Accu-standard, New Haven, CT, (p/n M-8270-IS-WL-0.25x to 10x). They contain 74 target compounds at nine concentration levels with six ISTDs at 40 ppm.

Pulsed splitless injection was used to minimize residence times of analytes in the liner, thereby reducing loss of active compounds. The column flow rate alone, without using a pulsed injection, would take too long to sweep the 900- μ L liner volume.

The inlet liner (p/n 5181-3316) is the most commonly used liner for Method 8270 analysis. It does not contain glass wool which would contribute to active compound degradation. Other liners can be used and a detailed discussion of these can be found in Reference 1.

The Agilent 6890 240 V oven was necessary for the 25 °C/min Ramp 3 used.

A 120 V oven will achieve 20 °C/min at higher temperatures and could be used, resulting in slightly longer run times.

The DB-5.625 column was recently introduced in the dimensions listed. A 0.5- μ L injection volume is well suited to this column. The excellent resolution from this column allows a higher than normal initial temperature, 55 °C vs 40 °C. This higher temperature shortens cool-down time by more

than 5 min, resulting in productivity increases for the laboratory. Benzo[b]fluoranthene and benzo[k]fluoranthene met Method 8270 resolution requirements at the 80-ppm calibration level and lower, using the operating parameters in Table 1.

Previous work has shown improved linearity across a wide calibration range using a 6-mm drawout lens instead of the standard 3-mm lens [1]. Although not shown here, that comparison was repeated on this Performance Electronics system and is still valid. The 6-mm lens is also included in Agilent Kit p/n G2860A.

The 5973 *inert* was tuned using the automatic DF TPP target tune. The following steps were taken before executing DF TPP tune to insure that Method 8270 DF TPP criteria were met on injection.

1. Using the Tune Wizard, set the Mass 50 Target Abundance to 1.3% and the Emission Current to 25, as shown in Figures 1a–1f.
2. Edit the tuning macro as follows:
 - a Copy atune73.mac from the MSDChem\msexe folder.
 - b Paste the copy of atune73.mac into the MSDChem\msexe folder. The file name should be Copy of atune73.mac. This preserves an original copy of the file.
 - c Open atune73.mac in Notepad. Refer to Figures 2a–2h.
 - d Click Edit>Find and type samples in the Find What box.
 - e Click Find Next.
 - f Change the samples value from 3 to 1.
 - g Change the averages value from 3 to 6.
 - h Save the file and Close Notepad.




Figure 1a. Starting the Tune Wizard.




Figure 1b. Accept these masses.




Figure 1c. Set Mass 50 target to 1.3.




Figure 1d. Set Emission Current to 25.



Figure 1e. Accept Standard.




Figure 1f. Type in DFTPP.U if not present and click Select to save.




Figure 2a. Select File>Open in Notepad.




Figure 2b. Select atune.73.mac and click Open.




Figure 2c. Select Edit>Find.



Figure 2d. Type samples into the Find What box, then click Find Next.




Figure 2e. Results of Find samples.



Figure 2f. Change samples from 3 to 1 and averages from 3 to 6.




Figure 2g. Select File>Save (do not use Save as).




Figure 2h. Select File>Exit to close Notepad.

Previous work has shown improved linearity across a wide calibration range using a 25- μ A emission current instead of the 35- μ A default. The tuning macro was changed so that the sampling rate during tuning matched the sampling rate during data acquisition. The system was tuned at 2¹ and data were collected at 2¹. These changes resulted in reliably passing Method 8270 criteria on injection of DFTPP.

Remember that the tune macro changes are also reflected if an Autotune is done. The copy of atune73.mac contains the macro without the changes.

The sampling rate for data acquisition was changed from the usual 2² to 2¹, while preserving sufficient sensitivity. The resultant 5.92 scans/s typically yield 10 data points across the peaks that have a width of 1.8 s.

Results

The system was calibrated at nine levels: 1, 2, 5, 20, 50, 80, 120, 160, and 200-ppm. The TIC (Total Ion Chromatogram) for the 5-ppm level is shown in Figure 3. The peak shape is excellent and the

run time is less than 15 min. The benzo[b]fluoranthene and benzo[k]fluoranthene resolution can be seen at about 11.4 min. Each calibration level contained 74 compounds together with 6 ISTDs at 40 ppm.

The RRF (relative response factor) was calculated automatically for each compound by the GC/MSD ChemStation software. Linearity was determined by calculating the %RSD (percent relative standard deviation) of the RRFs across the calibration range for each compound. This is also done automatically by the software in conjunction with Excel.

USEPA Method 8270D specifies criteria for suitable RRFs and %RSD. Minimum system performance is determined by four active compounds, the SPCCs (system performance check compounds) and is measured by the average RRF.

Table 2 lists the Method 8270D SPCC criteria and the performance of the 5973 inert. The 5973 *inert* data easily exceeds the 8270D criteria, and are very good considering the low end of the calibration range. This performance margin allows more samples to be run before system maintenance is necessary.




Figure 3. TIC for 5 ppm Method 8270 Semivolatiles.

Table 2. SPCCs and Comparison of Average RRF

	8270D Criteria	1–200 ng 5973 <i>inert</i>
N-Nitroso-di-n-propyl amine	0.050	0.963
Hexachlorocyclopentadiene	0.050	0.216
2,4-Dinitrophenol	0.050	0.133
4-Nitrophenol	0.050	0.139

Linearity is shown in Table 3. Method 8270D specifies that this group of Calibration Check Compounds (CCCs) meet a 30% RSD criteria. The %RSD is calculated across the RRFs determined at each calibration level. All CCCs pass criteria using a calibration range of 2–200 ppm. Across a 1–200 ppm range, pentachlorophenol does not pass due to its known activity.

Table 3. CCC %RSD of RRFs from 1–200 ppm and 2–200 ppm

	1–200	2–200
Phenol	6	6
1,4-Dichlorobenzene	7	6
2-Nitrophenol	6	6
2,4-Dichlorophenol	5	4
Hexachlorobutadiene	6	4
4-Chloro-3-methylphenol	5	5
2,4,6-Trichlorophenol	12	10
Acenaphthene	11	10
Diphenylamine	8	8
Pentachlorophenol	36	24
Fluoranthene	8	7
Benzo[a]pyrene	3	3

The excellent system linearity shown here is due to many factors including tuning, the large aperture drawout, and the Performance Electronics. The new electronics allow using a scan rate of 2¹, while maximizing sensitivity. This improved signal/noise together with more data points across a peak yields easier and more reproducible peak integration.

Conclusions

The Agilent 6890/5973 *inert* with Performance Electronics shows improved sensitivity at faster scan rates. The faster scan rates allow using 0.18 mm id columns for faster runs and shorter cool-down times. Analysis of 74 analytes and 6 ISTDs can be accomplished in less than 15 min. EPA Method 8270D tune criteria can be routinely achieved. SPCC performance and CCC linearity can be met over a wider calibration range than that historically used. Productivity increases are possible through shorter runs, faster cool-down, easier peak integration, and use of a wider calibration range.

References

1. M. Szelewski, B. Wilson and P. Perkins, “Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270”, Agilent Technologies, publication 5988-3072EN, www.agilent.com/chem.
2. M. Szelewski, “Fast Semivolatiles Analysis using the Agilent Technologies 6890/5973 *inert* GC/MSD”, Agilent Technologies, publication 5989-0207EN, www.agilent.com/chem.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
August 4, 2004
5989-1510EN



Agilent Technologies



Robustness of Eclipse PAH Columns for HPLC Analysis of Polycyclic Aromatic Hydrocarbons

Application

Environmental and Food

Authors

John W Henderson Jr. and Cliff Woodward
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

The Eclipse PAH (polycyclic aromatic hydrocarbon) column contains a rugged stationary phase suitable for a variety of PAH analyses. Their longevity, reproducibility, and scalability were demonstrated. The large number of available column configurations makes Eclipse PAH columns a desirable first choice to satisfy the chromatographer's unique PAH analytical requirements.

Introduction

Some HPLC column manufacturers offer a specific column for polycyclic aromatic hydrocarbon (PAH) analysis. However, because of the large number of PAHs (over 100 compounds) and broad range of PAH matrices (such as air, water, and food), many unique HPLC methods are needed, and cannot be developed on just one or two PAH column configurations. The more column lengths and diameters available, the more rugged, optimized methods can be developed.

More importantly, particle size, an additional column dimension, greatly expands method customization, meaning even more methods can be generated and optimized for a particular PAH application. Uniform chemistry between particle sizes allows methods to be scaled up or down with predictable results. Additional column possibilities are useful for such factors as sample size, sample matrix, detector choice, speed, resolution, and solvent use.

For a specialty column (bonded phase) to be useful for a multitude of similar methods it must demonstrate reproducibility between particle sizes. This allows straightforward, predictable method transfer, minimizing method redevelopment. Ideally, the column should also have longevity and reproducibility, including between manufacturing lots.

In this work we demonstrate that Eclipse PAH columns are robust: they have long life, reproducibility, and scalability.

Experimental

Eclipse PAH ruggedness was tested on an Agilent Rapid Resolution 1200 Series LC (RRLC) system that comprised:

- G1379 degasser



Agilent Technologies

- G1312B binary pump SL
 - Mobile phase A: water, B: acetonitrile. See figures for gradient conditions.
 - When using 2.1-id columns, the pump was configured in the low delay volume mode, bypassing the static mixer and pulse dampener. See reference 1 for details about using low- and standard-volume binary pump configurations.
- G1367C HiP-ALS SL autosampler
- G1316B TCC SL thermal controlled column compartment
 - Set to 25 °C. When using 2.1-id columns, the low-volume (1.6-μL) heat exchanger (G1316-8002) was used in place of the built-in 3-μL one.
- G1315C diode array detector SL
 - Set at 220, 4 nm, no reference, with a G1315-60025 flow cell (5-μL volume), response time setting of 0.5 s

Eclipse PAH Columns Available

Part Number	Description
959764-918	Eclipse PAH, 2.1 mm × 100 mm, 1.8 μm
959793-918	Eclipse PAH, 2.1 mm × 100 mm, 3.5 μm
959763-918	Eclipse PAH, 2.1 mm × 150 mm, 3.5 μm
959701-918	Eclipse PAH, 2.1 mm × 150 mm, 5 μm
959790-918	Eclipse PAH, 2.1 mm × 250 mm, 5 μm
959741-918	Eclipse PAH, 2.1 mm × 50 mm, 1.8 μm
959990-318	Eclipse PAH, 3.0 mm × 250 mm, 5 μm
959964-918	Eclipse PAH, 4.6 mm × 100 mm, 1.8 μm
959961-918	Eclipse PAH, 4.6 mm × 100 mm, 3.5 μm
959996-918	Eclipse PAH, 4.6 mm × 100 mm, 5 μm
959963-918	Eclipse PAH, 4.6 mm × 150 mm, 3.5 μm
959993-918	Eclipse PAH, 4.6 mm × 150 mm, 5 μm
959990-918	Eclipse PAH, 4.6 mm × 250 mm, 5 μm
959931-918	Eclipse PAH, 4.6 mm × 30 mm, 1.8 μm
959941-918	Eclipse PAH, 4.6 mm × 50 mm, 1.8 μm
959943-918	Eclipse PAH, 4.6 mm × 50 mm, 3.5 μm

See figures for columns used.

The PAH mixture is a certified reference material from Agilent, PN 8500-6035, diluted in acetonitrile. Elution order for all figures:

- 1 Toluene
- 2 Naphthalene
- 3 Acenaphthylene
- 4 Acenaphthene
- 5 Fluorene
- 6 Phenanthrene
- 7 Anthracene
- 8 Fluoranthene
- 9 Pyrene
- 10 Benzo(a)anthracene
- 11 Chrysene
- 12 Benzo(b)fluoranthene
- 13 Benzo(k)fluoranthene
- 14 Benzo(a)pyrene
- 15 Dibenzo(a,h)anthracene
- 16 Benzo(g,h,i)perylene
- 17 Indeno(1,2,3-c,d)pyrene

Results and Discussion

The standard mixture of polynuclear hydrocarbons specified in the EPA method 610 for municipal and industrial wastewater evaluated the robustness of Eclipse PAH columns. EPA method 610 calls for a 2.6 mm × 250 mm, 5 μm ODS column and a water/acetonitrile gradient. Alternative columns are allowed if certain conditions are met [2]. Interestingly, reference 2, section 1.3, states that the LC method with its specified column does not resolve all 16 PAHs.

Eclipse PAH does resolve all 16 PAHs, even in a 5-μm, 250-mm long configuration (Figure 1). Note that the critical pair, peaks 4 and 5, is well resolved ($R_s > 2$). We chose this minimum resolution of the critical pair to define a successful robust method. Mobile phase was adjusted to obtain this resolution for all Eclipse PAH column configurations; thus, the wide range of gradient delay times between low and high flow rates would not be a concern when developing the separation on a different column dimension. The analysis in Figure 1 takes about 26 minutes on the long 250-mm column. The analysis was shortened over four-fold when 1.8-μm particles in a 50-mm long column were used (Figure 2). The resolution of the critical pair remains greater than 2, but analysis time was reduced to 6.8 min.




Figure 1. PAH analysis on Eclipse PAH 250-mm columns has high resolution.




Figure 2. PAH analysis on RRHT Eclipse PAH 2.1 mm × 50 mm 1.8-μm column also has high resolution and faster analysis time.

Long Life and Reproducibility

Low solvent consumption and high throughput gained by using Rapid Resolution High Throughput (RRHT) columns such as the Eclipse PAH 2.1 x 50 mm in Figure 2 make RRHT columns ideal for column lifetime tests. We used the method in Figure 2 to test the longevity of Eclipse PAH columns. After 5,000 injections, the test was terminated with little loss in column performance. Figure 3 overlays chromatograms from the beginning, middle, and end of the life test. Selectivity, retention, and efficiency, and therefore resolution, remained relatively constant for 3,000 analyses and remained quite satisfactory for the next 2,000 injections. The table in Figure 3 lists the resolution factor values of the critical pair and a wider spaced pair and supports the method and column robustness. The test took 25 days of 24-hour operation and generated roughly 14.6 L of solvent waste. If a 4.6 x 250 mm column had been used, the test would have taken 122 days of nonstop operation and about 350 L of solvent would have been consumed.

Batch-to-Batch Reproducibility

Long column life is an important feature of Eclipse PAH; another necessity is batch-to-batch reproducibility. Besides 5- and 1.8- μ m particles, Eclipse

PAH is also available in 3.5 μ m. Figure 4 compares two batches of 3.5- μ m Eclipse PAH material made at different times. Note that the selectivity is identical between the batches, supporting the claim that manufacture of the Eclipse PAH particles is uniform. Similar results were obtained from 5- and 1.8- μ m material (data not shown). Each batch of material is specifically tested with PAHs for maximum reproducibility under expected operating conditions.

Scalability Between Particle Sizes

Batch-to-batch reproducibility can be broadened to particle-size-to-particle-size reproducibility, or scalability, to fully appreciate a column's robustness. Figure 5 overlays three different particle-size columns (by definition, three distinct batches as well). Additionally, the columns comprise three lengths and two diameters. Selectivity is the same, however, for all three column configurations. This is because selectivity is related to the nature of the particle surface, not to column length or diameter. The uniform selectivity between particle sizes, or scalability, contributes to Eclipse PAH's robustness.




Figure 3. Life test of Eclipse PAH 2.1 x 5 mm, 1.8 μ m. See the Experimental Section for peak identification.




Figure 4. Batch-to-batch reproducibility of Eclipse PAH 3.5-μm material.




Figure 5. Scalability of Eclipse PAH columns of various particle sizes and column dimensions.

Conclusions

Eclipse PAH is a suitable rugged stationary-phase column for a wide variety of PAH analyses. Column longevity, reproducibility, and scalability were demonstrated. The large number of column configurations makes Eclipse PAH columns a first choice for method optimization. Available Eclipse PAH column dimensions allow method customization regarding sample size, matrix, detector type, analysis speed, resolution requirements, and solvent consumption.

References

1. "High-Throughput Gradient Optimization by Easily Minimizing Delay Volume," Agilent Publication 5989-6665EN (2007)
2. Appendix A to Part 136, Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater, Method 610 Polynuclear Aromatic Hydrocarbons, United States Environmental Protection Agency

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
January 18, 2008
5989-7828EN



Agilent Technologies



Semivolatiles Retention Time Locked (RTL) Deconvolution Databases for Agilent GC/MSD Systems

Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

The G1677AA Semivolatiles Retention Time Locked database/library can provide rapid confirmation of environmental contaminants in complex matrices when used with Deconvolution Reporting Software. Separate methods and databases are included for wastewater and drinking water, with locked retention times. Compound lists are based on U.S. EPA Method 8270 (273 compounds) and Method 525 (119 compounds). Acquisition methods for both splitless and programmable temperature vaporizing inlets are provided. Full spectra are used for identification of deconvoluted analytes, not just a few extracted ions. When used with MSD ChemStation Rev E.02 or later, quantitation of the deconvoluted data from AMDIS is possible, in addition to the normal quantitation. The G1677AA Environmental Semivolatiles retention time locking database/library is an add-on product to the base deconvolution reporting software product G1716AA.

Introduction

Agilent Deconvolution Reporting Software (DRS) is a software package that combines the information from three separate processes into one easy-to-read report: 1) MSD ChemStation identification and quantitation, 2) industry standard AMDIS deconvolution with full spectrum identification 3) NIST full spectrum Search. The primary benefit of

DRS is significant time savings when interpreting results from complex matrix analyses.

Target compound identification and quantitation in environmental samples is often a tedious task and is therefore well suited to DRS. The list of target compounds varies widely, depending on geographic region, government requirements, and sample type. There is no universal list of analytes tied to specific methods that will satisfy all laboratories all of the time.

The United States Environmental Protection Agency (U.S. EPA) has published numerous GC/MSD methods for organic analytes in various matrices. U.S. EPA Method 525 is specified for drinking water and Method 8270 for wastewater, each having its own set of compounds. The compounds lists for these methods are extensive and form the basis for the deconvolution databases discussed in this note. Laboratories are not required to follow the U.S. EPA methods exactly to use the databases effectively. Compounds/spectra can easily be added by users to the databases for suitability in their own labs.

Databases/Libraries

Collections of mass spectral data are referred to as libraries or databases. DRS uses the combined general description of database/library (DBL). Retention time is a critical component of sample identification, and the compounds in these DBLs have been acquired using retention time locking (RTL).

The G1677AA Environmental Semivolatiles RTL DBL is a set of mass spectral libraries in the Agilent and NIST/AMDIS formats. There are three



Agilent Technologies

separate sets of files and methods. An 8270 set includes the mass spectra and locked retention times for 243 single-component semivolatile compounds and internal standards specified by U.S. EPA Method 8270, plus 30 additional compounds of environmental interest – a total of 273 compounds. Two different 525 sets are included, one optimized for a split/splitless inlet and one optimized for a PTV inlet, designated as “long.” Each 525 set includes mass spectra and locked retention times for the same 119 single-component semivolatile compounds and internal standards specified by U.S. EPA Method 525. A complete listing of the DBL compounds can be found in Appendix A.

Each DBL entry contains the following information:

- Mass spectrum acquired using Atune.u on a 5975 MSD
- Locked retention time determined on a 6890N/5975 or 7890A/5975 GC/MSD system. Compounds were injected at least once with phenanthrene-d10 locked to 9.500 ± 0.01 minutes. Phenanthrene-d10 was locked to 12.700 ± 0.01 minutes for the 525 PTV “long” method.
- Molecular formula
- Molecular weight (nominal mass)
- CAS number

Spectra were compared to those contained in the NIST05a Mass Spectral Library. Tests were performed on spiked samples containing hydrocarbon interferences and the results were compared to the list of spiked compounds.

Minimum system requirements for using the semi-VOAs DBLs

- G1716AA deconvolution reporting software, base product
- Agilent GC/MS system with E.02.00.xxx software preferred

Experimental

The instrument operating conditions used for acquiring the 8270 and 525 spectra and retention times are listed in Table 1. Splitless injection utilizing a split/splitless inlet with the column connected directly to the MSD was done. The thicker film 20-m column allows good separation of the early eluters from the solvent while providing a short run time of 17 min. An inlet temperature of 300 °C is optimum for later eluting PAHs but basic compounds, such as benzidine, have improved

response factors at lower inlet temperatures, 250 to 275 °C. Retention time locking to phenanthrene-d10 at 9.500 min was done in constant-flow mode, at 0.8 mL/min. The mass range of 35 to 500 is suitable for both lists of compounds. A 6-mm large-aperture drawout lens provides better high-end linearity at the expense of some sensitivity loss. The standard 3-mm lens could be used.

Table 1. 8270 and 525 Methods – Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890N or 7890A		
Inlet	EPC split/splitless – rear location		
Mode	Splitless, 0.5 µL injected		
Inlet temperature	300 °C		
Pressure	16.9 psi initial		
Purge flow	30.0 mL/min		
Purge time	0.75 min		
Gas saver	Off		
Gas type	Helium		
Liner	Agilent helix, single-taper, p/n 5188-5397		
Oven	240V		
Oven ramp	°C/min	Next °C	Hold min
Initial		40	1.00
Ramp 1	25	320	4.80
Total run time	17.0 min		
Equilibration time	0.5 min		
Oven max temp.	325 °C		
Column	Agilent Technologies DB-5.625, p/n 121-5622		
Length	20.0 m		
Diameter	0.18 mm		
Film thickness	0.36 µm		
Mode	Constant flow = 0.8 mL/min		
Pressure	16.7 psi initial		
Inlet	Rear		
Outlet	MSD		
Outlet pressure	Vacuum		
RTL	System retention time locked to phenanthrene-d10 at 9.500 min		
MSD	Agilent Technologies 5975, performance turbo		
Drawout lens	6-mm large-aperture drawout lens p/n G2589-20045		
Solvent delay	2.8 min		
Tune	Atune.u		
EM voltage	Tune voltage		
Mass range	35 to 500 amu		
Threshold	0		
Sampling	2		
Quad temperature	180 °C		
Source temperature	300 °C		
Transfer line temp.	280 °C		

The instrument operating conditions used for acquiring the 525 “long” retention times are listed in Table 2. A programmable temperature vaporizing inlet (PTV) was used with a 25-µL large volume injection (LVI). PTV-LVI is popular in labs requiring lower detection limits for drinking water. Active analytes have improved performance as they

vaporize at the lowest possible temperature compared to a hot splitless injection. Phenanthrene-d10 is used as the retention time locking compound at 12.700 min running in constant-flow mode at 1.5 mL/min. The PTV parameters are not directly transferrable to the 20-m column used in Table 1, without affecting retention times. The 30-m column provides better separation for SIM analysis, allowing more ions/compound or more SIM cycles/peak than a shorter run. Users can build their own SIM-based DBLs with a requirement of 4 ions/compound for best identification with deconvolution. Alternatively, SIM/scan data acquisition could be done with the SIM data used for quantitation and the scan data used for full-spectrum deconvolution. The 45 to 450 scan range is suitable for the 525 DBL. The sampling rate of two can be changed to one to maintain an equal number of scan cycles if SIM/scan is used.

Table 2. 525 Long Method – Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890N or 7890A		
Inlet	EPC PTV – front location		
Mode	Solvent vent – 25 uL injected		
Temp ramp	°C/min	Next °C	Hold min
Initial		20	0.60
Ramp 1	600	350	1.30
Ramp 2	10	250	0.00
Cryo	On		
Cryo use temperature	100 °C		
Cryo timeout	10.00 min (On)		
Cryo fault	On		
Pressure	11.77 psi (On)		
Vent time	0.60 min		
Vent flow	100.0 mL/min		
Vent pressure	0.0 psi		
Purge flow	50.0 mL/min		
Purge time	2.50 min		
Total flow	53.9 mL/min		
Gas saver	Off		
Gas type	Helium		
PTV Liner	Agilent multi-baffle liner, no packing, p/n 5183-2037		
Oven	120V		
Oven ramp	°C/min	Next °C	Hold min
Initial		40	2.50
Ramp 1	50	110	0.00
Ramp 2	10	320	1.10
Total run time	26 min		
Equilibration time	0.5 min		
Oven max temperature	325 °C		
Column	Agilent Technologies HP 5 MSi, p/n 19091S-433i		
Length	30.0 m		
Diameter	0.25 mm		
Film thickness	0.25 µm		
Mode	Constant flow – 1.5 mL/min		
Pressure	11.77 psi		

Inlet	Front
Outlet	MSD
Outlet pressure	Vacuum
RTL	System retention time locked to phenanthrene-d10 at 12.700 min

Front Injector	
Sample washes	0
Sample pumps	2
Injection volume	25 microliters
Syringe size	50 microliters
PreInj. Solv A washes	0
PreInj. Solv B washes	1
PostInj. Solv A washes	2
PostInj. Solv B washes	2
Viscosity delay	1 second
Plunger speed	Variable
Injection speed	50 microliters/minute
Draw speed	600 microliters/minute
Dispense speed	6000 microliters/minute
PreInjection dwell	0 minutes
PostInjection dwell	0 minutes

MSD	Agilent Technologies 5975C, performance turbo
Drawout lens	6-mm large-aperture drawout lens p/n G2589-20045
Solvent delay	4 min
Low mass	45 amu
High mass	450 amu
Threshold	0
Sampling	2
Quad temperature	180 °C
Source temperature	300 °C
Transfer line temperature	280 °C
Tune type	Autotune
EM voltage	Tune voltage, 1247 V

Results and Discussion

Retention Time Locking – or Not

Maximum productivity from DRS is realized if the GC/MSD system is retention time locked. The DRS report displays RT differences of found targets from their expected RTs, which is important for differentiating compounds with similar spectra. AMDIS parameters can be set to exclude compounds found outside their expected RT windows, which eliminates false positives. Retention time locking also eliminates the need to change SIM acquisition times, a tedious task with multiple SIM groups. Therefore, it is strongly recommended that users run with an RTL system.

Although the majority of labs run RTL, some users may choose not to do so. Two different approaches can be used in this case, each with limited success.

Approach 1 – Updating the *.cal File

The *.cal file establishes the relationship between retention times found on any given day to those

expected in the AMDIS databases (*.msl and *.cid). For the semivolatiles DBL the *.cal files contain only ISTDs and surrogates. It is assumed that other analytes will track the retention time changes of these compounds. Whenever RTs change, the *.cal file RTs must be changed. This can be done by manually editing the RTs in the *.cal file using Notepad. Once all RTs have been updated, select Save, not Save As. A second choice is to have AMDIS rebuild the *.cal file. The procedure for this is in AMDIS Help.

Approach 2 – Updating the *.msl and *.cid Files

A menu item is provided in MSD data analysis, DRS > Update AMDIS Library RTs using quant database. This will update the RTs in both necessary AMDIS files using the current MSD quant database times and will save a copy of the original two AMDIS files.

Cautions: If the quant database contains an incorrect time, that time will be used. If the quant database does not contain a compound that is in the AMDIS files, AMDIS RTs will not be updated.

Using the Semivolatiles RTL DBL

The following files are installed:

8270_DRS_Demo.D	525_DRS_Demo.D	525_Long_DRS_Demo.D
8270_DRS.L	525_DRS.L	
8270_RTL_DRS.M	525_RTL_DRS.M	525_Long_RTL_DRS.M
8270.MSL	525.MSL	525_Long.MSL
8270.CID	525.CID	525_Long.CID
8270_cal_RT.CAL	525_cal_RT.CAL	525_Long_cal_RT.CAL
8270_cal_RT.CSL	525_cal_RT.CSL	525_Long_cal_RT.CSL

The typical locations into which the CD installer places the files are as follows:

Agilent MSD ChemStation datafiles *.D and Methods *.m in
C:\msdchem\MSDemo\Semivolatiles Example Data

C:\msdchem\MSDemo\Semivolatiles Example Methods

AMDIS files *.msl, *.cid, *.cal, and *.csl in

C:\NIST05\AMDIS32\LIB



MSD ChemStation Library Files, *.L in **C:\Database**

The MSD ChemStation methods contain a retention time locked quant database with single-point calibration. These methods can be used directly in data analysis, as described later. The methods also contain data acquisition parameters and retention time locking data. Users may have to resolve differences between their system and the method configuration upon loading the method in data acquisition. Additionally, new retention time locking data may have to be acquired. In most cases users will only have to relock their system if it is configured the same as the system in Table 1 or Table 2.

DRS in MSD Data Analysis

It is strongly recommended that an operator inexperienced in DRS first proceed to the General Help file section “Generating and Interpreting A Report Using DRS Manually/Interactively.” Complete all of the the Spinach A, B and C exercises for the best fundamental understanding of DRS. Then proceed as follows.

Open AMDIS as a standalone application and then select Analyze > Settings. Verify that the settings are as shown below, then select Save. If prompted to reanalyze, select No, then exit AMDIS. The settings will be permanently saved in the AMDIS initialization file onsite.ini.




After AMDIS settings have been addressed, it will be necessary to configure a DRS method, depending on the analysis chosen. The relationship of the AMDIS and MSD ChemStation files are shown in the Table below.

MSD ChemStation method	MSD ChemStation select library	DRS configurator method	DRS configurator AMDIS target library	DRS configurator RI calibration file	DRS configurator AMDIS .ini file
8270_RTL_DRS.m	8270_DRS.L	8270_RTL_DRS	8270.msl	8270_cal_RT.cal	Onsite.ini
525_RTL_DRS.m	525_DRS.L	525_RTL_DRS	525.msl	525_cal_RT.cal	Onsite.ini
525_long_DRS.m	525_DRS.L	525_long_DRS	525_long.msl	525_long_cal_RT.cal	Onsite.ini

A DRS method must be configured for each of the applications that will be used. Let's look at one example of using the semivolatiles DBL, in this case the 8270 set.

1. Configure a NEW DRS Method using the Method Configurator as shown below.



2. Select Add then Exit > Exit and Save.
3. In the MSD ChemStation, Data Analysis View, Load Method 8270_RTL_DRS.m.
4. Load datafile 8270_DRS_Demo.D.
5. From the Data Analysis View DRS menu, select Quant + DRS Single File.

At the end of the DRS process a report similar to the one shown should be generated.

MSD Deconvolution Report

Sample Name: 5ppm 8270sm + 50GKD

Data File: C:\msdchem\1\DATA\8270_D~1.D

Date/Time: 05:00 PM Monday, Dec 17 2007

Adjacent Peak Subtraction = 1

Resolution = Medium

Sensitivity = High

Shape Requirements = Medium

The NIST library was searched for the components that were found in the AMDIS target library.

R.T.	Cas #	Compound Name	Amount (ng)		AMDIS		NIST	
			Chem station	AMDIS	Match	R.T. Diff sec.	Reverse Match	Hit Num.
2.8499	62759	N-Nitrosodimethylamine	5.56		93	-0.5	96	1
4.7302	62533	Aniline			98	4.2	96	1
5.0358	3855821	1,4-Dichlorobenzene-d4	40		99	-0.2	93	1
5.2143	106445	4-Methylphenol			66	-7.7	89	1
5.3059	98862	Acetophenone			49	-4.6		
5.3059	105055	Benzene, 1,4-diethyl-					89	1
6.2476	1146652	Naphthalene-d8	40		99	-0.1	86	1
6.2679	91203	Naphthalene	3.77		58	-0.1		
6.2679	5405798	3-Hexanone, 2,2-dimethyl-					81	1
6.787	680319	Hexamethylphosphoramid	0.28					
6.9442	91576	2-Methylnaphthalene			97	0.1	91	1
7.761	95830	4-Chloro-1,2-phenylenediamine	0.69					
7.845	5131602	4-Chloro-1,3-phenylenediamine	0.1					
7.9945	15067262	Acenaphthene-d10	40		98	-0.1	82	1
8.0256	51285	2,4-Dinitrophenol			58	0.0	68	1
8.0572	100027	4-Nitrophenol	2.44		81	-0.1	92	1
8.195	132649	Dibenzofuran	0.11					
8.3833	84662	Diethyl phthalate	0.23		78	-0.2	75	1
8.530	99558	5-nitro-o-toluidine	0.11					
8.5420	86737	Fluorene			56	0.0	80	58
8.5644	534521	4,6-Dinitro-2-methylphenol			89	-0.1	88	1
8.6164	86306	N-Nitrosodiphenylamine			45	-0.8		
8.6164	3892000	Pentadecane, 2,6,10-trimethyl-					84	1
9.2806	92671	4-Aminobiphenyl	6.1		94	-0.1	89	2
9.2829	87865	Pentachlorophenol	4.22		91	-0.1	66	11
9.4964	1517222	Phenanthrene-d10	40		97	-0.1	86	1
9.5139	120127	Anthracene			52	-3.4	70	15
9.5175	85018	Phenanthrene			68	-0.2	80	1
10.0286	84742	di-n-Butyl phthalate			74	-0.1	84	9
10.8285	92875	Benzidine	5.67		97	0.8	91	1
12.1025	91941	3,3'-Dichlorobenzidine	5.3		95	-0.4	97	1
12.1665	1719035	Chrysene-d12	40		93	-0.3	92	1
12.168	56553	Benz[a]anthracene	0.06					
12.168	218019	Chrysene	0.08					
12.168	732116	Phosmet	0.27					
13.3443	207089	Benzo[k]fluoranthene			93	-2.4	94	2
13.3443	205992	Benzo[b]fluoranthene	5.75		95	-0.2	90	2
13.381	207089	Benzo[k]fluoranthene	5.89					
13.8809	1520963	Perylene-d12	40		99	-0.6	77	1

This report is based on DRS revision A.04. Previous DRS revisions do not have AMDIS settings in the header, nor do they have a column for the amount calculated from AMDIS. The AMDIS calculated amount will be available after using QEdit in MSD ChemStation, Rev E.02 and later. Please consult the DRS A.04 Help section “Using QEdit with DRS Quantitative Data” for details.

The user can also configure DRS methods for either of the 525 sets of files, similar to that shown above for the 8270 set. Methods and demo datafiles are provided.

Conclusions

The Semivolatiles RTL DBL can provide rapid confirmation of environmental contaminants in complex matrices when used with DRS. Separate databases are provided for wastewater and drinking water, with locked retention times. Full spectra are used for identification of deconvoluted analytes. When used with MSD ChemStation Rev E.02 or later, quantitation on the deconvoluted data from AMDIS is possible, in addition to the normal quantitation. The G1677AA Environmental Semivolatiles RTL DBL is an add-on product to the base DRS product G1716AA.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Appendix A

Lists of Compounds

Combined alphabetical listing of compounds from both the 8270_DRS.L and the 525_DRS.L, including CAS number and library entry number. Italics indicate the additional 30 compounds in the 8270 DBL. Retention time information can be found in the method quant databases, the Agilent libraries, or the AMDIS databases.

Compound name	CAS #	8270_DRS.L entry #	525_DRS.L entry #	Compound name	CAS #	8270_DRS.L entry #	525_DRS.L entry #
Acenaphthene	83329	71		gamma-BHC (lindane)	58899	115	39
Acenaphthene-d10	15067262	55	1	Bis(2-chloroethoxy)methane	111911	39	
Acenaphthylene	208968	69	12	Bis(2-chloroethyl) ether	111444	13	
Acetophenone	98862	26		Bis(2-chloroisopropyl) ether	108601	21	
2-Acetylaminofluorene	53963	185		Bis(2-ethylhexyl)phthalate	117817	191	108
1-Acetyl-2-thiourea	591082	271		Bromacil	314409		58
Alachlor	15972608		54	4-Bromophenyl phenyl ether	101553	103	
Aldrin	309002	137	61	Bromoxynil	1689845	97	
Ametryn	834128		55	Butachlor	23184669		79
2-Aminoanthraquinone	117793	267		Butifos	78488		85
Aminoazobenzene	60093	253		Butyl benzyl phthalate	85687	173	95
4-Aminobiphenyl	92671	111		Butylate	2008415		8
3-Amino-9-ethylcarbazole	132321	264		Captafol	2425061	186	
Anilazine	101053	141		Captan	133062	142	
Aniline	62533	12		Carbaryl	63252	129	
o-Anisidine	90040	240		Carbazole	86748	126	
Anthracene	120127	124	43	Carbofuran	1563662	110	
Aramite	140578	155		Carbophenothion	786196	176	
Atraton	1610179		31	Carboxin	5234684		88
Atrazine	1912249		35	Chlordane (NOS)	57749	252	
Azinphos-methyl	86500	199		alpha-Chlordane	5103719		80
Azobenzene	103333	93		gamma-Chlordane	5103742		73
(conv: 1,2-diphenylhydrazine)				Chlorfenvinphos	470906	145	
Barban	101279	160		4-Chloroaniline	106478	44	
Benz[a]anthracene	56553	193	103	Chlorobenzilate	510156	164	91
Benzidine	92875	149		<i>2-Chlorobiphenyl</i>	2051607	73	16
Benzo[a]pyrene	50328	216	114	5-Chloro-2-methylaniline	95794	256	
Benzo[b]fluoranthene	205992	212	112	4-Chloro-3-methylphenol	59507	51	
Benzo[ghi]perylene	191242	223	119	3-(Chloromethyl)pyridine	3099318	276	
Benzo[k]fluoranthene	207089	213	113	1-Chloronaphthalene	90131	270	
Benzoic acid	65850	37		2-Chloronaphthalene	91587	62	
p-Benzoquinone	106514	238		Chloroneb	2675776		17
Benzyl alcohol	100516	18		2-Chlorophenol	95578	15	
alpha-BHC (alpha-HCH)	319846	104	28	4-Chloro-1,2-phenylenediamine	95830	260	
beta-BHC (beta-HCH)	319857	109	38	4-Chloro-1,3-phenylenediamine	5131602	259	
delta-BHC (delta-HCH)	319868	123	47	4-Chlorophenyl phenyl ether	7005723	84	

Compound name	CAS #	8270_DRS.L entry #	525_DRS.L entry #	Compound name	CAS #	8270_DRS.L entry #	525_DRS.L entry #
Chlorothalonil	1897456		49	3,3'-Dimethylbenzidine	119937	174	
Chlorpropham	101213		26	a,a-Dimethylphenethylamine	122098	40	
Chlorpyrifos	2921882		63	1,3-Dimethyl-2-nitrobenzene-ss	81209		3
Chrysene	218019	194	105	2,4-Dimethylphenol	105679	36	
Chrysene-d12	1719035	153	99	Dimethyl phthalate	131113	66	11
Coumaphos	56724	208		Di-n-butyl phthalate	84742	131	59
p-Cresidine	120718	237		1,2-Dinitrobenzene	528290	274	
Crotoxyphos	7700176	146		1,3-Dinitrobenzene	99650	67	
Cyanazine	21725462		64	1,4-Dinitrobenzene	100254	273	
Cycloate	1134232		25	4,6-Dinitro-2-methylphenol	534521	89	
2-Cyclohexyl-4,6-dinitro-phenol	131895	266		2,4-Dinitrophenol	51285	72	
Dacthal (DCPA)	1861321		66	2,4-Dinitrotoluene	121142	76	19
4,4'-DDD	72548	167	93	2,6-Dinitrotoluene	606202	68	15
4,4'-DDE	72559	154	86	Dinocap I	39300453	190	
4,4'-DDT	50293	179	98	Di-n-octyl phthalate	117840	207	
Demeton-O	298033	251		Dinoseb	88857	119	
Demeton-S	126750	107		Diphenamid	957517	239	68
Diallate	2303164	100		Diphenylamine	122394	91	
2,4-Diaminotoluene	95807	268		5,5-Diphenylhydantoin	57410	257	
Diazinon	333415		44	1,2-Diphenylhydrazine	122667	272	
Dibenz[a,h]anthracene	53703	222	118	Disulfoton	298044	120	45
Dibenz(a,j)acridine	224420	250		Disulfoton sulfone	2497065		75
Dibenzofuran	132649	77		Disulfoton sulfoxide	2497076		6
Dibenzo(a,e)pyrene	192654	249		Endosulfan I	959988	150	78
Dibrom (naled)	300765	94		Endosulfan II	33213659	169	92
1,2-Dibromo-3-chloropropane	96128	275		Endosulfan sulfate	1031078	182	96
Dichlone	117806	116		Endrin	72208	166	90
1,2-Dichlorobenzene	95501	19		Endrin aldehyde	7421934	172	94
1,3-Dichlorobenzene	541731	16		Endrin ketone	53494705	189	
1,4-Dichlorobenzene	106467	17		EPN	2104645	197	
1,4-Dichlorobenzene-d4	3855821	1		EPTC	759944		7
3,3'-Dichlorobenzidine	91941	192		Ethion	563122	168	
2,3-Dichlorobiphenyl	16605917	105	29	Ethoprophos	13194484		24
2,4-Dichlorophenol	120832	41		Ethyl carbamate	51796	246	
2,6-Dichlorophenol	87650	45		Ethyl methanesulfonate	62500	9	
Dichlorvos	62737	48	4	Etridiazole	2593159		13
Dicrotophos	141662	248		Famphur	52857	171	
Dieldrin	60571	161	87	Fenamiphos	22224926		82
Di(2-ethylhexyl)adipate	103231		101	Fenarimol	60168889		109
Diethyl phthalate	84662	82	22	Fensulfothion	115902	159	
Diethylstilbestrol	56531	181		Fenthion	55389	139	
Diethyl sulfate	64675	247		Fluchloralin	33245395	125	
Dimethoate	60515	108		Fluoranthene	206440	152	
3,3'-Dimethoxybenzidine	119904	265		2-Fluorobiphenyl	321608	60	
p-(Dimethylamino)azobenzene	60117	163		Fluorene	86737	86	21
7,12-Dimethylbenz[a]anthracene	57976	211		Fluridone	59756604		116

Compound name	CAS #	8270_DRS.L entry #	525_DRS.L entry #	Compound name	CAS #	8270_DRS.L entry #	525_DRS.L entry #
2-Fluorophenol	367124	7		Methyl parathion	298000	128	
Heptachlor	76448	130	53	2-Methylphenol	95487	20	
Heptachlor epoxide -isomer B	1024573	143	70	3-Methylphenol	108394	23	
2,2',3,3',4,4',5-Heptachlorobiphenyl	35065306	203		4-Methylphenol	106445	22	
2,2',3,3',4,4',6-Heptachlorobiphenyl	52663715		104	Metolachlor	51218452		62
2,2',3,4,4',5,5'-Heptachlorobiphenyl	35065293	195		Metribuzin	21087649		51
2,2',3,4,4',5',6-Heptachlorobiphenyl	52663691	187		Mevinphos	7786347	63	9
2,2',3,4',5,5',6-Heptachlorobiphenyl	52663680	184		Mexacarbate	315184	241	
1,2,3,4,6,7,8-Heptachlorodibenzo- furan	67562394	215		MGK 264 - a	113484		67
1,2,3,4,6,7,8-Heptachlorodibenzo- p-dioxin	35822469	217		MGK 264 - b	113484		69
Hexachlorobenzene	118741	106	30	Mirex	2385855	204	
2,2',3,4,4',5'-Hexachlorobiphenyl	35065282	180		Molinate	2212671		20
2,2',3,4,5,5'-Hexachlorobiphenyl	52712046	175		Monocrotophos	6923224	98	
2,2',3,5,5',6-Hexachlorobiphenyl	52663635	162		Naphthalene	91203	43	
2,2',4,4',5,5'-Hexachlorobiphenyl	35065271	170		Naphthalene-d8	1146652	30	
2,2',4,4',5,6'-Hexachlorobiphenyl	60145224		89	1,4-Naphthoquinone	130154	65	
Hexachlorobutadiene	87683	47		1-Naphthylamine	134327	80	
Hexachlorocyclopentadiene	77474	56	5	2-Naphthylamine	91598	78	
1,2,3,4,7,8-Hexachlorodibenzofuran	70648269	205		Napropamide	15299997		83
1,2,3,4,7,8-Hexachlorodibenzo- p-dioxin	39227286	209		Nicotine	54115	58	
Hexachloroethane	67721	29		5-Nitroacenaphthene	602879	255	
Hexachlorophene	70304	214		2-Nitroaniline	88744	64	
Hexachloropropene	1888717	46		3-Nitroaniline	99092	70	
Hexamethylphosphoramid	680319	245		4-Nitroaniline	100016	87	
Hexazinone	51235042		100	5-Nitro-o-anisidine	99592	254	
Hydroquinone	123319	244		Nitrobenzene	98953	32	
Indeno[1,2,3-cd]pyrene	193395	221	117	Nitrobenzene-d5	4165600	31	
Isodrin	465736	140		4-Nitrobiphenyl	92933	258	
Isophorone	78591	34	2	Nitrofen	1836755	165	
Isosafrole	120581	61		2-Nitrophenol	88755	35	
Kepone	143500	177		4-Nitrophenol	100027	74	
Leptophos	21609905	201		4-Nitroquinoline-1-oxide	56575	136	
Malathion	121755	132		5-Nitro-o-toluidine	99558	85	
Maleic anhydride	108316	243		N-Nitrosodiethylamine	55185	8	
Merphos	150505		72	N-Nitrosodimethylamine	62759	2	
Mestranol	72333	242		N-Nitrosodi-n-butylamine	924163	49	
Methapyrilene	91805	138		N-Nitrosodi-n-propylamine	621647	25	
Methoxychlor	72435	188	106	N-Nitrosodiphenylamine	86306	90	
3-Methylcholanthrene	56495	218		N-Nitrosomethylethylamine	10595956	4	
4,4'-Methylenebis (2-chloroaniline)	101144	263		N-Nitrosomorpholine	59892	27	
4,4'-Methylenebis (N,N-dimethylaniline)	101611	262		N-Nitrosopiperidine	100754	33	
Methyl methanesulfonate	66273	6		N-Nitrosopyrrolidine	930552	24	
2-Methylnaphthalene	91576	53		trans-Nonachlor	39765805		81
Methyl paraoxon	950356		46	Norflurazon	27314132		97
				2,2',3,3',4,4',5,5',6-Nonachlorobi- phenyl	40186729	210	
				2,2',3,3',4,5',6,6'-Octachlorobi- phenyl	40186718		107

Compound name	CAS #	8270_DRS.L entry #	525_DRS.L entry #	Compound name	CAS #	8270_DRS.L entry #	525_DRS.L entry #
Octachlorodibenzofuran	39001020	220		Simazine	122349		33
Octachlorodibenzo- <i>p</i> -dioxin	3268879	219		Simetryn	1014706		52
Octamethyl pyrophosphoramidate	152169	239		Stirofos (Tetrachlorvinphos)	22248799		77
4,4'-Oxydianiline	101804	261		Strychnine	57249	231	
Parathion (ethyl)	56382	134		Sulfallate	95067	230	
Pebulate	1114712		14	Sulfotepp	3689245	95	
Pentachlorobenzene	608935	75		Tebuthiuron	34014181		18
2,2',3,4,5'-Pentachlorobiphenyl	38380028	156		Terbacil	5902512		48
2,2',3',4,6'-Pentachlorobiphenyl	60233252		71	Terbufos	13071799	121	40
2,2',4,5,5'-Pentachlorobiphenyl	37680732	148		Terbutryne	886500		57
2,3,3',4',6-Pentachlorobiphenyl	38380039	158		Terphenyl-d14	1718510	157	
1,2,3,7,8-Pentachlorodibenzofuran	57117416	198		1,2,4,5-Tetrachlorobenzene	95943	54	
1,2,3,7,8-Pentachlorodibenzo- <i>p</i> -dioxin	40321764	202		2,2',3,5'-Tetrachlorobiphenyl	41464395	135	
Pentachloroethane	76017	14		2,2',4,4'-Tetrachlorobiphenyl	2437798		60
Pentachloronitrobenzene	82688	113		2,2',5,5'-Tetrachlorobiphenyl	35693993	133	
Pentachlorophenol	87865	112	37	2,3',4,4'-Tetrachlorobiphenyl	32598100	144	
cis-Permethrin	54774457		110	2,3,7,8-Tetrachlorodibenzofuran	51207319	178	
trans-Permethrin	51877748		111	2,3,7,8-Tetrachlorodibenzo- <i>p</i> -dioxin	1746016	183	
Perylene-d12	1520963	206	115	2,3,4,6-Tetrachlorophenol	58902	79	
Phenacetin	62442	101		Tetrachlorvinphos	961115	151	
Phenanthrene	85018	122	42	Tetraethylpyrophosphate (TEPP)	107493	81	
Phenanthrene-d10	1517222	88	32	Thiophenol (Benzenethiol)	108985	229	
Phenobarbital	50066	236		Thionazin	297972	83	
Phenol	108952	11		Toluene diisocyanate	584849	228	
Phenol-d5	4165622	10		o-Toluidine	95534	28	
p-Phenylenediamine	106503	50		Toxaphene	58002190	227	
Phorate	298022	102		Triadimefon	43121433		65
Phosalone	2310170	200		2,4,6-Tribromophenol	118796	96	
Phosmet	732116	196		1,2,4-Trichlorobenzene	120821	42	
Phosphamidon I	13171216	118		2,2',5-Trichlorobiphenyl	37680652	117	
Phthalic anhydride	85449	235		2,4,5-Trichlorobiphenyl	15862074		50
2-Picoline (2-Methylpyridine)	109068	5		2,4',5-Trichlorobiphenyl	16606023	127	
Piperonyl sulfoxide	120627	234		2,4,5-Trichlorophenol	95954	59	
Prometon	1610180		34	2,4,6-Trichlorophenol	88062	57	
Prometryn	7287196		56	Tricyclazole	41814782		84
Propyzamide (Pronamide)	23950585	114	41	0,0,0-Triethyl phosphorothioate	126681	38	
Propachlor	1918167		23	Trifluralin	1582098	92	27
Propazine	139402		36	2,4,5-Trimethylaniline	137177	269	
Propylthiouracil	51525	233		Trimethyl phosphate	512561	226	
Pyrene	129000	147	76	1,3,5-Trinitrobenzene	99354	99	
Pyrene-d10-ss	1718521		74	Triphenylphosphate-ss	115866		102
Pyridine	110861	3		Tris(2,3-dibromopropyl) phosphate	126727	224	
Resorcinol	108463	232		Tri- <i>p</i> -tolylphosphate	78320	225	
Safrole	94597	52		Vernolate	1929777		10

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
February 8, 2008
5989-7875EN



Agilent Technologies

Femtogram GC/MSD Detection Limits for Environmental Semivolatiles Using a Triple-Axis Detector



Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

The analysis of semivolatiles at very low levels presents challenges due to analyte activity, background contamination, and instrument sensitivity. Method requirements vary worldwide, with the least sensitive specifying 1- μ L injections and full-scan data acquisition. The lowest detection limits can be achieved using a programmable temperature vaporizing (PTV) inlet, trace ion detection (TID), and a triple-axis detector (TAD) with the MSD operating in SIM mode.

Introduction

Low-level semivolatiles analysis is used to concurrently measure a mixture of acids, bases, neutrals, and pesticides in drinking water or source water. Most laboratories analyze for > 100 compounds, with a chromatographic run time of 25 to 40 minutes. Sample extraction is accomplished using liquid-solid extraction (LSE) with C_{18} disks or cartridges. Liquid-liquid extraction with a solvent such as dichloromethane is an alternative technique. Extract injection is typically 1 μ L hot splitless with the MSD operating in full-scan mode, as specified in some commonly used methods such as USEPA Method 525.2 [1].

Sensitivity is an area where laboratories are seeking improved performance; it can be affected by sample preparation, extract volume injected, instrument tuning, signal acquisition, and overall system activity. Sensitivity is also a confusing term, with all of the following used interchangeably: maximum sensitivity, minimum sensitivity, best sensitivity, lowest detection limit, instrument detection limit (IDL), and method detection limit.

Previous publications have focused on activity/linearity, speed, productivity, and large-volume injection [2–5]. Sensitivity is a factor in all of these, and many times is a trade-off.

This application addresses the parameters that affect the IDL, that is, the “sensitivity” of the GC/MSD system. There are statistical ways to calculate the IDL, but these may not answer the questions, “How much can I actually see?” or “What is the lowest amount that will produce a peak I can integrate?”

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized. For the best sensitivity, parameters should be chosen that transfer the maximum amount of analyte onto the column. Furthermore, the entire system must be inert, as sensitivity is almost always lost on active analytes first.

Many analysts associate the use of PTV only with large-volume injection (LVI) in solvent vent mode [4]. LVI will allow lower levels of calibration, but



Agilent Technologies

Table1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 7890A or 6890N			Front Injector	
Inlet	EPC PTV			Sample washes	1
Mode	Splitless			Sample pumps	2
Temperature ramp	°C/min	Next °C	Hold min	Injection volume	2.0 µL
Initial		20	0.05	Syringe size	10 µL
Ramp 1	600	350	0.90	PreInj Solv A washes	0
Ramp 2	10	250	0.00	PreInj Solv B washes	1
Cryo	On			PostInj Solv A washes	3
Cryo use temperature	100 °C			PostInj Solv B washes	2
Cryo timeout	10.00 min (On)			Viscosity delay	0 seconds
Cryo fault	On			Plunger speed	Fast
Pressure	11.40 psi (On)			PreInjection dwell	0 minutes
Purge flow	30.0 mL/min			PostInjection dwell	0 minutes
Purge time	1.50 min			MSD	Agilent Technologies 5975C, Triple-Axis Detector
Total flow	34.4 mL/min			Drawout lens	3 mm standard aperture drawout lens
Gas saver	Off			Solvent delay	4 min
Gas type	Helium			Low mass	45 amu
PTV Liner	Agilent multi-baffle liner, no packing, p/n 5183-2037			High mass	450 amu
Oven	120V			Threshold	0
Oven ramp	°C/min	Next °C	Hold min	Sampling	2
Initial		40	2.50	Quad temp	180 °C
Ramp 1	50	110	0.00	Source temp	300 °C
Ramp 2	10	320	1.10	Transfer line temp	280 °C
Total run time	26 min			Tune type	Autotune
Equilibration time	0.5 min			EMV mode	Gain factor = 1
Oven max temperature	325 °C			MSD-SIM	
Column	Agilent Technologies HP 5 MSi, p/n 19091S-433i			AutoSIM was used to pick ions, groups and switching times	
Length	30.0 m			Number of groups	25
Diameter	0.25 mm			Compounds/group	Varied 1 to 22
Film thickness	0.25 µm			Ions/group	Varied 2 to 45
Mode	Constant flow			Dwell time, msec	Varied 5 to 50
Pressure	11.40 psi			Cycles/peak	Minimum 10
Nominal initial flow	1.4 mL/min			Calibration Standards	
Inlet	Front			Ultra Scientific, North Kingstown, RI. p/n DWK-5252. Four mixtures, co-diluted in dichloromethane, resulting in 108 compounds at 7 concentration levels: 10, 4, 1, 0.4, 0.1, 0.04, and 0.01 ppm. Each level spiked with 3 Internal Standards at 2 ppm and 4 surrogate standards at 2 ppm. Each level then diluted 1:100 in dichloromethane, resulting in 7 concentration levels: 100, 40, 10, 4, 1, 0.4, and 0.1 ppb (pg/µL) with IS/SS at 2 ppb.	
Outlet	MSD				
Outlet pressure	Vacuum				
RTL	System retention time locked to phenanthrene-d10 at 12.700 min				

method development is necessary to optimize recovery of compounds while eliminating the solvent. LVI also injects more matrix and may not improve Signal-to-Noise (S/N) due to chemical noise. The PTV has other operating modes; “cold” splitless mode was used here. Splitless injection into a cold inlet instead of a typical hot splitless inlet offers these advantages:

1. Solvent expansion is minimized; analytes do not travel outside the liner and contact metal surfaces, thereby minimizing degradation.
2. Analytes vaporize at the lowest temperature, also minimizing degradation.

3. Volatile solvent is transferred onto the column first; analyte peak shape is improved for injections of 2 to 5 µL.

Figure 1 shows the PTV temperature and flow programs together with the oven program. The PTV is held at 20 °C, a temperature below the boiling point of the solvent dichloromethane, 39.8 °C, during the fast injection period, 0.05 min. At the end of the injection period, the PTV is rapidly heated to 350 °C, transferring analytes onto the column. At the end of the splitless time, 1.5 min, the inlet is purged at 30 mL/min. The PTV is allowed to cool during the run.




Figure 1. PTV cold splitless temperature and flow programs.

The PTV program ramp can be adjusted and multiple ramps are possible. The PTV inlet liner (p/n 5183-2037) is multi-baffled and deactivated. It does not contain glass wool, which could contribute to active compound degradation. This liner has sufficient capacity to accommodate a 2- to 5- μ L injection volume at fast speed. A 2- μ L injection was used for all data presented here.

The oven program relationship to the PTV parameters is shown in Figure 1. The oven starts at 40 °C and is held there during the injection cycle and splitless transfer of analytes onto the column. The oven then programs rapidly to 110 °C, followed by a slower ramp for compound separation. There is an extra 1 min of oven hold time at 40 °C, which is between 1.5 and 2.5 min. This maintains the retention time locked (RTL) times for analytes while providing room for the injection to be scaled up to LVI, if desired. The 240V oven was used, but a 120V oven can also achieve the ramp rates found in Table 1.

The HP-5MSi column is designed for inertness and is well suited to this method. This is the latest version of the most popular column in environmental laboratories, the HP-5MS. The column was run in constant-flow mode at 1.4 mL/min to maintain peak shape and sensitivity.

The system was RTLocked to phenanthrene-d10 at 12.700 min. The primary benefit of RTL for this analysis is maintaining constant switching times for SIM groups. After clipping the column, a rerun and analysis of the locking standard is all that is needed to restore shifted peak times. Quantitation database and integration events times also do not have to be changed. Additional RTL applications detailing the numerous benefits of RTL are available at www.agilent.com/chem. It is almost impossible to use a method with this many SIM groups without RTL, in a productive laboratory.

The standard 3-mm drawout lens was used for best sensitivity. Previous work has shown improved linearity across a wide calibration range using the optional 6-mm lens [1]. Using the 6-mm lens will show a typical loss of 2 to 5x in the IDL.

The 5975C MSD was equipped with a Triple-Axis Detector (TAD) [6]. The TAD presents several advantages to the user, one of which is, "Although signal is enhanced, neutral noise is substantially reduced through the off-axis design." This increase in S/N for clean samples with minimal chemical noise can help reach a lower IDL. Trace ion detection (TID) was switched on during all data acquisition [7]. TID is a filtering routine to minimize noise and is selectable in the software.

Scan parameters are listed and data were collected in either scan mode or in SIM mode. None of the runs was made in synchronous SIM/scan mode. A sampling rate of 2 was used, as it is typical of most methods on a 250- μ m id column. This sampling rate, with a 45 to 450 mass range, resulted in at least 10 scans across each peak.

AutoSIM setup was used in combination with the scan quantitation database to pick ions, groups, and switching times. The SIM acquisition table from AutoSIM was used directly with only two modifications. Tebuthiuron (ion 156) and tricyclazole (ion 189) are known for poor peak shape. Their ions were manually added to the groups across which the peaks eluted. A target ion plus one qualifier ion were used for all internal (ISTDs) and surrogate standards (SSs). A target ion plus two qualifier ions were used for all other analytes, if they were present in sufficient abundance in the spectra. A minimum of 10 SIM data points were acquired across each peak.

A source temperature of 300 °C was used instead of the typical 230 to 250 °C range. This higher temperature has been used to minimize peak tailing, and therefore improve sensitivity for PAHs [5].

The compound list was taken from USEPA 525 and is typical of the analytes that laboratories worldwide are interested in analyzing at low levels. The USEPA 8270 list was not used, as it is targeted at higher concentrations of compounds in waste samples that contain high levels of matrix and are not comparable here. The best way to improve sensitivity for solids and waste samples is through extract cleanup. The standards were prepared in dichloromethane only for the single component analytes, except disulfoton sulfoxide and disulfoton sulfone, which were not included in the commercially available mixture. Standards were not prepared for multicomponent toxaphene or the Aroclors.

A typical calibration range for low-level semivolatiles is 0.1 to 10 ppm as defined in USEPA 525. Standards were made from 0.01 to 10 ppm, containing 2 ppm of ISTDs and SSs. A dilution of 1:100 of each of these yields a range of 0.1 to 100 ppb, with ISTDs and SSs at 20 ppb, for a lower working range. Atrazine and alachlor are present in two of the stock mixes, so their concentrations are twice that of other analytes. Pentachlorophenol is present at four times the other analyte concentrations, as described in USEPA 525.

Results

The standard solutions from 0.1 to 100 ppb were run in both SIM and scan modes. Data from the 0.1-ppb scan injections showed insufficient response or were too noisy to reproducibly integrate. The SIM data at 0.1 ppb were significantly improved compared to the scan data and could be routinely used. A listing of selected analytes with S/N measured from 1.0 ppb scan runs (2 pg) are shown in Table 2, together with data from 0.1- (0.2-pg) and 1.0-ppb SIM runs. Each value is an average of three acquisitions on one system, using peak-to-peak noise.

Table 2. Signal-to-Noise for Selected Analytes, SIM and Scan Modes

Compound	Ion	pg $\rightarrow$ RT	0.2	2.0	2.0
			SIM S/N	SIM S/N	Scan S/N
Hexachlorocyclopentadiene	237	7.960	6.3	77	7.5
Trifluralin	264	11.608	4.4	49	7.7
Simazine	201	12.274	1.0	16	2.4
Atrazine	200	12.385	3.1	30	13
Pentachlorophenol	266	12.492	2.4	20	3.7
Chlorothalonil	266	13.146	2.6	26	2.9
Aldrin	66	14.661	1.6	15	1.9
Heptachlor epoxide	353	15.429	6.2	49	3.4
4,4'-DDE	246	16.557	7.0	72	17
Carboxin	143	16.696	2.4	22	4.0
Endrin	263	17.003	2.3	22	4.1
4,4'-DDD	235	17.323	7.5	76	7.5
4,4'-DDT	235	18.000	5.9	60	5.9

There is excellent agreement between the SIM S/N values at the two levels for most compounds. This shows that the responses are real and that the entire system is inert. There is a slight loss of simazine and minimal interference for pentachlorophenol and heptachlor epoxide at the lowest level, 0.2 pg. At the 200 femtogram level, this is no surprise.

The scan S/N at 2.0 pg is lower than SIM, as expected, by 3- to 15-fold. The gains in S/N moving from scan to SIM are related to the dwell time versus the original sampling rate.

Extracted Ion Currents (EICs) from the 1.0-ppb level for both SIM and scan are shown in Figures 2a to 2d. It can clearly be seen that either the SIM or scan signals could be used for quantitation based on S/N and peak shape. Of particular note is the response and very good peak shape for pentachlorophenol, even at an 8-pg full scan.




Figure 2a. Atrazine – Extracted Ion 200, RT 12.350 min.




Figure 2b. Pentachlorophenol – Extracted Ion 266, RT 12.445 min.




Figure 2c. Aldrin – Extracted Ion 66, RT 14.616 min.




Figure 2d. 4,4'-DDT – Extracted Ion 235, RT 18.00 min.

Although linearity is not the focus of this application, it is a measure of inertness, reproducibility, and sensitivity. Linearity can be determined by the percent relative standard deviation (%RSD) of the relative response factor (RRF) for each compound across the calibration range. The %RSD and the

RRF calculations are done automatically by the GC/MSD ChemStation software in conjunction with Excel. There is no correct %RSD, as it is method dependent. The %RSDs of the RRFs for selected compounds are shown in Table 3.

Table 3. Linearity of Selected Analytes


Calibration range pg →	0.2–200 SIM %RSD	2–200 Scan %RSD
Compound		
Dichlorvos	1.9	7.0
Mevinphos	10.1	7.0
2,3-Dichlorobiphenyl	5.3	3.0
Atrazine	14.2	14.5
Pentachlorophenol	6.3	33.0
Anthracene	2.2	3.0
Chlorothalonil	7.6	25.0
Heptachlor epoxide	6.6	13.0
4,4'-DDE	4.5	9.0
4,4'-DDD	7.4	8.0
4,4'-DDT	4.0	5.9

At first glance some of the %RSD values appear high, such as pentachlorophenol (PCP) and chlorothalonil. These are calibrated, however, from 2 to 200 pg in scan mode, which is 50-fold lower than USEPA 525 mandates. The SIM data are calibrated from 0.2 to 200 pg, which is 500-fold

lower and a 10-fold wider range. This demonstrates both inertness and detectability at the femtogram level.

As an additional overall measure of system linearity, the average of all %RSDs was calculated at 8% for SIM data and 13% for scan data. Not all compounds were calibrated to the 0.1-ppb level, as they did not have a signal that could be reliably measured. The phthalates, easily detected at low levels, were excluded from these averages due to common laboratory contamination.

EICs at the 200-femtogram level, from SIM, are shown for six different compounds in Figures 3. All are easily seen and measured against noise. As an analyst's measure of sensitivity, the question from the introduction was "How much can I actually see?" The answer: very low picogram levels for most environmental semivolatiles in scan mode. The IDL using SIM is even lower, in the femtogram range.

**Figure 3. EICs at the 200 femtogram level.**

Conclusions

Traditional semivolatiles methods can be altered to achieve better instrument detection limits. There have been advancements in hardware, such as the Triple-Axis Detector (TAD), that improve sensitivity. Signal handling using Trace Ion Detection (TID) provides better S/N through lower noise. The PTV, used in “cold” splitless mode, maximizes the amount of sample on the column, while vaporizing analytes at the lowest possible temperature. Coupled with an inert column and source, the PTV provides an easy way to improve sensitivity. Methods that require only a target ion and a few qualifier ions for identification can often be changed to SIM from scan, improving S/N by 3- to 50-fold. Combining all of these hardware, software, and operating parameters can result in femtogram instrument detection limits (IDLs) and sensitivity you can use.

References

1. USEPA Method 525.2 is available from different sources listed on www.epa.gov/OGWDW/methods/where.html.
2. M. Szelewski, B. Wilson, and P. Perkins, “Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270,” Agilent Technologies, publication 5988-3072EN.
3. M. Szelewski, “Fast Semivolatiles Analysis Using the Agilent Technologies 6890/5973 inert GC/MSD,” Agilent Technologies, publication 5989-0207EN.
4. M. Szelewski, “Part-per-Trillion Calibration of Semivolatiles Using LVI-PTV-GC/MSD,” Agilent Technologies, publication 5989-6589EN.
5. M. Szelewski, “Synchronous SIM/Scan Low-Level PAH Analysis Using the Agilent Technologies 6890/5975 inert GC/MSD,” Agilent Technologies, publication 5989-4184EN.
6. H. Prest and J. Foote, “The Triple-Axis Detector: Attributes and Operating Advice,” Agilent Technologies, publication 5989-7655EN.
7. R. Roushall and H. Prest, “The 5975C Series MSDs: Method Optimization and Trace Ion Detection,” Agilent Technologies, publication 5989-6425EN.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
April 14, 2008
5989-8342EN



Agilent Technologies

Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W DB-5ms Ultra Inert Column



Application

Environmental

Author

Kenneth Lynam
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent Technologies Inc. has implemented new testing procedures to more effectively evaluate GC column inertness performance. The new testing procedure uses deliberately aggressive probes to thoroughly investigate column inertness quality. The value of using probes such as 1-propionic acid, 4-picoline, and trimethyl phosphate to establish a column inertness baseline is discussed. This baseline inertness profile is then extended to a real-world application example with challenging analytes in the semivolatile sample set. Inertness performance with analytes such as 2,4-dinitrophenol, benzoic acid, and benzidine clearly shows the advantage of using the Agilent J&W DB-5ms Ultra Inert columns for semivolatile analysis.

Introduction

Semivolatile analyses using methods similar to USEPA method 8270 [1] are important in environmental laboratories worldwide. A number of very

active analytes presents significant challenges for analysts, equipment providers, and column manufacturers in terms of inertness. Acidic compounds such as benzoic acid or 2,4-dinitrophenol and strong bases such as pyridine or benzidine are examples of active species found in the semivolatile sample set. These chemically charged species are particularly susceptible to adsorption onto active surfaces in the sample flow path, including the column itself. Both system and column inertness are critical for effective analysis of these active chemical species.

For many years Grob's mix [2] has been the standard mix to evaluate capillary GCs and columns. This mix consists of a series of alkanes, a substituted phenol (acidic component), an amine (basic component), an alcohol, and a diol. Virtually all capillary column manufacturers have used Grob's or a very similar test mix to evaluate column performance historically. These mixtures work well to evaluate column efficiency, system suitability against solute discrimination during injection, and potential solute absorption in the chromatographic flow path. Inertness evaluation based on single acidic and basic species in these mixes, though valuable, falls short of the rigorous requirements for inertness that applications on modern capillary GC columns require [3–4]. Modern GC applications demand a more comprehensive approach to properly investigate column inertness performance.



Agilent Technologies

Experimental

Baseline inertness testing of columns was on an Agilent 6890N GC equipped with a 7683B autosampler and an FID. Semivolatile application-specific chromatograms were generated using an Agilent 6890N GC/5975B MSD equipped with a 7683B autosampler.

Tables 1 and 2 list the chromatographic conditions used on each of the chromatographic systems. Table 3 lists flow path consumable supplies used in these experiments.

Table 1. Chromatographic Conditions 6890N/FID System

GC:	Agilent 6890N
Sampler :	Agilent 7683B, 0.5- μ L syringe (Agilent p/n 5188-5246), 0.02- μ L split injection, 1 ng each component on column
Carrier:	Hydrogen constant pressure 38 cm/s
Inlet:	Split/splitless; 250 °C, 1.4 mL/min column flow, split flow 900 mL/min, gas-saver flow 75 mL/min. on at 2.0 min
Inlet liner:	Deactivated single taper w/glass wool (Agilent p/n 5183-4647)
Column:	Agilent J&W DB-5ms Ultra Inert, 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 122-5532UI)
Oven:	65 °C isothermal
Detection:	FID at 325 °C, 450 mL/min air, 40 mL/min hydrogen, 45 mL/min nitrogen makeup

Table 2. Chromatographic Conditions 6890N/5975B MSD System

GC:	Agilent 6890N/5975B MSD
Sampler :	Agilent 7683B, 5.0- μ L syringe (Agilent p/n 5181-5246), 1.0- μ L splitless injection, 5 ng each component on column
Carrier:	Helium constant flow 30 cm/s
Inlet:	Split/splitless; 260 °C, 53.7 mL/min total flow, purge flow 50 mL/min on at 0.5 min, gas-saver flow 80 mL/min on at 3.0 min
Inlet liner:	Deactivated single taper w/glass wool (Agilent p/n 5183-4647)
Column:	Agilent J&W DB-5 ms Ultra Inert, 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 122-5532UI)
Oven:	40 °C (1 min) to 100 °C (15 °C/min), 10 °C to 210 °C (1 min), 5 °C/min. to 310 °C (8 min)
Detection:	MSD source at 300 °C, quadrupole at 180 °C, transfer line at 290 °C, scan range 50–550 AMU

The flow path supplies used in these experiments are listed in Table 3.

Table 3. Flow Path Supplies

Vials:	Amber screw cap (Agilent p/n 5182-0716)
Vial caps:	Blue screw cap (Agilent p/n 5282-0723)
Vial inserts:	100- μ L glass/polymer feet (Agilent p/n 5181-1270)
Syringe:	5 μ L (Agilent p/n 5181-1273)
Septum:	Advanced Green (Agilent p/n 5183-4759)
Inlet liners:	Deactivated single taper w/glass wool (Agilent p/n 5183-4647) for FID Deactivated single taper direct connect (Agilent p/n G1544-80730) for MSD
Ferrules:	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323)
20x magnifier:	20x magnifier loupe (Agilent p/n 430-1020)

Sample Preparation

Test probes for baseline inertness evaluation were purchased from Sigma Alrich (Milwaukee, WI 53201, USA). Dichloroethane used was Burdick and Jackson spectral grade purchased thorough VWR International (West Chester, PA 19380, USA). semivolatile standard (USEPA 8270) solutions were obtained either from Ultra Scientific (North Kingstown, RI 02852, USA) or AccuStandard (New Haven, CT 06513, USA).

Solutions were prepared using dichloroethane solvent and class A volumetric pipettes and flasks.

Results and Discussion

Baseline Inertness Profile for the Ultra Inert Columns

One means of quickly evaluating the suitability of a chromatographic system and the column component of that system is the deliberate injection of challenging analyte mixes on the system. Good sample recoveries and peak shapes quickly show that the injection system is functioning properly and establish a baseline inertness profile for the column. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species like those in the semivolatile sample set. The use of more demanding test mixes to certify column inertness performance is the approach taken for every column offered in the Ultra Inert series of capillary GC columns.

This application illustrates the implementation of more rigorous testing procedures to certify GC capillary column inertness. The baseline test mix selected for inertness contains 1-propionic acid, 4-picoline, trimethyl phosphate, and 1-heptanol. Key column evaluation criteria include efficiency of n-decane elution at a k' of 5, probe peak shapes, and peak height ratios of 4-picoline and trimethyl phosphate relative to closely eluting alkanes. The peak height ratio of active analytes, such as 4-picoline and trimethyl phosphate, relative to less active alkanes indicate the degree of surface activity for the reactive analyte. A higher ratio indicates better inertness. Testing with these aggressive probes provides more probative tools for evaluating inertness with problematic acidic and basic species. This testing procedure raises the bar for column inertness QC testing and sets a new industry standard for consistent column performance.

Figure 1 shows a baseline inertness chromatogram for an Ultra Inert DB-5ms column. Please note the peak shapes for trimethyl phosphate. This compound exhibits minor peak tailing in this example chromatogram and, for this analyte, represents

very good peak shape. The observable peak tailing for this analyte is what makes it an excellent tool for evaluating column inertness. On a lesser column this peak may not be seen at all.

Semivolatile Challenging Analytes

The evaluation of column performance went beyond the new baseline testing for inertness and looked at an abbreviated list of compounds specific to the USEPA Method 8270 sample set. The semivolatiles mix [5] contained N-nitrosodimethylamine, aniline, benzoic acid, 2,4-dinitrophenol, 4-nitrophenol, 2-methyl-4,6-dinitrophenol, pentachlorophenol, 4-aminobiphenyl, benzidine, 3,3'-dichlorobenzidine, benzo [b] fluoroanthene, benzo [k] fluoroanthene as well as recommended internal standards. These species were selected to range in polarity from basic to acidic species and from very early eluting nitrosamine to late eluting polynuclear aromatic hydrocarbons (PAHs). Figure 2 is a total ion chromatogram of the challenging analyte mix with a 5-ng on-column loading of each component.




Figure 1. Baseline inertness test chromatogram, 1 ng/component load on the Agilent J&W DB-5ms Ultra Inert column (Agilent p/n 122-5532UI), chromatographic conditions as in Table 1, flow path supplies as in Table 3.




Figure 2. Abbreviated semivolatile test chromatogram, 5 ng/component load on the Agilent J&W DB-5ms Ultra Inert column (Agilent p/n 122-5532UI), chromatographic conditions as in Table 2, flow path supplies as in Table 3.

One key assessment criterion for USEPA 8270 system suitability is the response factor for 2,4-dinitrophenol and its most closely eluting internal standard acenaphthene-d10. The minimum acceptable average response factor (over the entire concentration range) is 0.050 and the typical range is between 0.1 to 0.2. This response tends to decrease at lower concentrations and as the chromatographic system or the standard starts to deteriorate. In Figure 2, response factors for 2,4-dinitrophenol were greater than 0.1, and for 4-nitrophenol, they were greater than 0.2, each at a concentration of 5 µg/mL. These values are indicative of excellent column performance even at low standard concentration.

The recovery of benzidine is another key indicator of inertness performance for semivolatile analysis. This particular base is subject to thermal breakdown in the inlet and to oxidation from standing in solution. Injection temperatures above 260 °C caused benzidine recoveries to drop dramatically. It was necessary to balance benzidine recoveries with the elution of heavier PAHs when setting

injection port temperatures. An injection port temperature setting of 260 °C gave good recoveries for benzidine and was still hot enough for higher molecular weight PAHs to volatilize.

Semivolatile Large Mix

Figure 3 shows a 5-ng on-column loading of a broader range of semivolatile analytes. This large mixture was prepared by combining AccuStandard® semivolatile mixes 1, 2, 3, 4a, 4b, 5, and 6 all at a nominal concentration of 5 µg/mL. In total, 93 semivolatile compounds were included in this mix, ranging in boiling points from very low-boiling N-nitrosodimethylamine to high-boiling benzo (g,h,i) perylene. In addition, a wide diversity of analyte polarities was represented in this mix. The highlighted area in Figure 3 shows the elution and peak shape of highly basic benzidine and its response relative to the nearest eluting peak, flouranthene. Even in this large mix, benzidine gave good relative response and peak shape.

- 1 N-nitrosodimethylamine
- 2 2- Methyl pyridine
- 3 Benzidine
- 4 Fluoranthene
- 5 Benzo (g,h,i) perylene




Figure 3. Semivolatile (large mix) test chromatogram, 5 ng/component load on the Agilent J&W Ultra Inert DB-5ms column (Agilent p/n 122-5532UI), chromatographic conditions as in Table 2, flow path supplies as in Table 3. Several peaks of interest are labeled to indicate early- and late-eluting species. Benzidine (peak 3) and fluoranthene (peak 4) peaks are shown in the highlighted section.

Conclusions

Rigorous column inertness testing with aggressive probes ensures consistent and reliable column inertness performance for active analytes. Challenging probes such as 1-propionic acid, 4-picoline, and trimethyl phosphate are better predictive indicators of column behavior toward active analytes than traditional Grob style mixes used by many column manufacturers. Inertness testing with these aggressive probes produces columns with well-defined baselines for inertness performance.

Columns with well-defined inertness baselines provide a reliable platform for the analyst to begin analysis of semivolatiles. The Ultra Inert DB-5ms column used in this series of experiments demonstrates excellent inertness performance for some of the most difficult analytes in the semivolatile sample set, including N-nitrosodimethylamine, 2,4-dinitrophenol, 4-nitrophenol, and benzidine. The good recoveries and peak shapes observed for these difficult species, even with a 5-ng on-column loading, are indicative of successful semivolatile analyses on these new Ultra Inert DB-5ms columns.

References

1. US EPA Method 8270D, Revision 4, February 2007, "Semivolatile Organic Compounds by Gas Chromatography/Mass Spectrometry (GC/MS)"
2. K. Grob Jr., G. Grob, and K. Grob, "Comprehensive, Standardized Quality Test for Glass Capillary Columns," *Journal of Chromatography A*, Vol. 156, Issue 1, 21 August 1978, Pages 1–20
3. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenyltrimethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
4. Jim Luong, Ronda Gras, and Walter Jennings, "An Advanced Solventless Column Test for Capillary GC Columns," *J. Sep. Sci.*, 2007, 30, 2480–2492
5. Mike Szelewski and Bill Wilson, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270," Agilent Technologies publication 5988-3072EN

For More Information

For more information on our products and services,
visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
May 19, 2008
5989-8616EN



Agilent Technologies



EPA Method 1694: Agilent's 6410A LC/MS/MS Solution for Pharmaceuticals and Personal Care Products in Water, Soil, Sediment, and Biosolids by HPLC/MS/MS

Application Note

Environmental

Authors

Imma Ferrer and E. Michael Thurman
Center for Environmental Mass
Spectrometry
University of Colorado
Civil, Environmental, and Architectural
Engineering
ECOT 441, 428 UCB
Boulder, CO 80309
USA

Jerry Zweigenbaum
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

An analytical methodology for screening and confirming the presence of 65 pharmaceuticals in water samples was developed using the Agilent G6410A Triple Quadrupole mass spectrometer (QQQ). The method was developed following the guidelines in EPA Method 1694. Four distinct chromatographic gradients and LC conditions were used according to the polarity and extraction of the different pharmaceuticals. Positive and negative ion electrospray were used with two multi-reaction monitoring (MRM) transitions (a quantifier and a qualifier ion for each compound), which adds extra confirmation in this methodology compared with the EPA method. Linearity of response of three orders of magnitude was demonstrated ($r^2 > 0.99$) for all the pharmaceuticals studied. The analytical performance of the method was evaluated for one wastewater sample collected from Boulder Creek, Colorado; positive identifications for carbamazepine and diphenhydramine were found for this sample using the methodology developed in this work.



Agilent Technologies

Introduction

The analytical challenge of measuring emerging contaminants in the environment has been a major research focus of scientists for the last 20 years. Pharmaceuticals and personal care products (PPCPs) are an important group of contaminants that have been targeted, especially in the last decade. In the area of PPCPs there are several methods addressing the analysis of these analytes, including EPA Method 1694 [1], which was recently published (December 2007). This EPA protocol uses solid-phase extraction (SPE) for water sample preparation [1]. The extracts are then analyzed directly by a

tandem mass spectrometer using a single transition for each compound. This application note describes the Agilent solution to this method, which is demonstrated with the Agilent model 6410A LC/MS QQQ. The Agilent initial implementation for EPA Method 1694 consists of 65 analytes (of 75 total analytes) and 17 labeled internal standards (of 20 total), which are a mixture of PPCPs that are analyzed each by a single MRM transition. (Note that the other compounds and internal standards could not be obtained at this time.) The method also uses Agilent C-18 and Hydrophilic Interaction Chromatography (HILIC) columns for all analytes. To provide additional confirmation, a second MRM transition was added for 60 of the 65 analytes analyzed. This gives an even greater assurance of correct identification than prescribed by the EPA. Table 1 shows the list of pharmaceuticals studied here.

Table 1. Analytes Studied in This Work

List of Group 1 Compounds EPA 1694: 46 Analytes

Acetaminophen	Codeine	Flumequine	Penicillin V	Sulfanilamide
Ampicillin	Cotinine	Fluoxetine	Roxithromycin	Thiabendazole
Azithromycin	Dehydronifedipine	Lincomycin	Sarafloxacin	Trimethoprim
Caffeine	Digoxigenin	Lomefloxacin	Sulfachloropyridazine	Tylosin
Carbadox	Diltiazem	Miconazole	Sulfadiazine	Virginiamycin
Carbamazepine	1,7-Dimethylxanthine	Norfloxacin	Sulfadimethoxine	Digoxin*
Cefotaxime	Diphenhydramine	Ofloxacin	Sulfamerazine	
Ciprofloxacin	Enrofloxacin	Oxacillin	Sulfamethazine	
Clarithromycin	Erythromycin	Oxolinic acid	Sulfamethizole	
Cloxacillin	Erythromycin anhydrate	Penicillin G	Sulfamethoxazole	

*Compound formed intractable Na adduct with current conditions.

List of Group 2, 3, and 4 Compounds: EPA 1694: 19 Analytes

Anhydrotetracycline (2)	Doxycycline (2)	Minocycline (2)	Triclocarban (3)
			Triclosan (3)
			Warfarin (3)
Chlorotetracycline (2)	4-Epianhydrotetracycline (2)	Tetracycline(2)	Albuterol (4)
		Meclocycline (2)	Cimetidine (4)
			Metformin (4)
Demeclocycline(2)	4-Epitetracycline(2)	Gemfibrozil (3)	Ranitidine (4)
		Ibuprofen (3)	
		Naproxen (3)	

List of Labeled Internal Standards

$^{13}\text{C}_2$ - ^{15}N -Acetaminophen	$^{13}\text{C}_2$ -Erythromycin	$^{13}\text{C}_6$ -Sulfamethazine	$^{13}\text{C}_3$ -Trimethoprim
$^{13}\text{C}_3$ -Atrazine	Fluoxetine- d_6	$^{13}\text{C}_6$ -Sulfamethoxazole	Warfarin- d_5
$^{13}\text{C}_3$ -Caffeine	Gemfibrozil- d_6	$^{13}\text{C}_6$ -2,4,5-Trichloro-phenoxycetic acid	Carbamazepine- d_{10} (Extra compound, not EPA list)
$^{13}\text{C}_3$ - ^{15}N -Ciprofloxacin	$^{13}\text{C}_3$ -Ibuprofen	$^{13}\text{C}_6$ -Triclocarban	
Cotinine- d_3	^{13}C -Naproxen- d_3	$^{13}\text{C}_{12}$ -Triclosan	

Experimental

Sample Preparation

Pharmaceutical analytical standards were purchased from Sigma, (St. Louis, MO). All stable isotope labeled compounds used as internal standards were obtained from Cambridge Isotope Laboratories (Andover, MA). Individual pharmaceutical stock solutions (approximately 1,000 µg/mL) were prepared in pure acetonitrile or methanol, depending on the solubility of each individual compound, and stored at -18 °C. From these solutions, working standard solutions were prepared by dilution with acetonitrile and water.

Water samples were collected from the wastewater treatment plant at the Boulder Creek outfall (Boulder, CO) and extracted as per the EPA method. Agilent has introduced a polymeric SPE sorbent with hydrophilic/lipophilic properties that may also be appropriate for this application. "Blank" wastewater extracts were used to prepare the matrix-matched standards for validation purposes. The wastewater extracts were spiked with the mix of pharmaceuticals at different concentrations (ranging from 0.1 to 500 ng/mL or ppb) and subsequently analyzed by LC/MS/MS.

LC/MS/MS Instrumentation

The analytes were subdivided in groups (according to EPA protocol for sample extraction) and LC conditions for the chromatographic separation of each group are as follows.

LC Conditions for Group 1-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	10% ACN and 90% H ₂ O with 0.1% HCOOH
Flow rate	0.2–0.3 mL/min
Gradient	t ₀ = 10% ACN, 0.2 mL/min t ₅ = 10% ACN, 0.2 mL/min t ₈ = 10% ACN, 0.3 mL/min t ₂₄ = 60% ACN, 0.3 mL/min t ₃₀ = 100% ACN
Injection volumes	15 µL

LC conditions for Group 2-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	10% ACN and 90% H ₂ O with 0.1% HCOOH
Flow rate	0.2 mL/min
Gradient	t ₀ = 10% ACN t ₁₀ = 10% ACN t ₃₀ = 100% ACN
Injection volumes	15 µL

LC conditions for Group 3-acidic extraction, negative electrospray ionization (ESI-) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	40% MeOH and 60% H ₂ O with 5 mM ammonium acetate, pH 5.5
Flow rate	0.2 mL/min
Gradient	t _{0.5} = 40% MeOH t ₇ = 100% MeOH
Injection volumes	15 µL

LC conditions for Group 4-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX HILIC Plus 2.1 × 100 mm, 3.5 µm (p/n 959793-901 custom order until November 1, 2008)
Column temperature	25 °C
Mobile phase	98% ACN and 2% H ₂ O with 10 mM ammonium acetate, pH 6.7
Flow rate	0.25 mL/min
Gradient	t ₀ = 98% ACN t ₅ = 70% ACN t ₁₂ = 70% ACN
Injection volumes	15 µL

The mass spectrometer conditions were general to all groups and are as follows.

MS Conditions

Mode	Positive and negative (depending on group) ESI using the Agilent G6410A Triple Quadrupole mass spectrometer
Nebulizer	40 psig
Drying gas flow	9 L/min
V capillary	4000 V
Drying gas temperature	300 °C
Fragmentor voltage	70–130 V
Collision energy	5–35 V
MRM	2 transitions for every compound as shown in Table 1
Dwell time	10 msec

Results and Discussion

Optimization of LC/MS/MS Conditions

The initial study consisted of two parts. First was to optimize the fragmentor voltage for each of the pharmaceuticals studied in order to produce the largest signal for the precursor ion. Typically the protonated molecule was used for the precursor ion. Each compound was analyzed separately using an automated procedure (MassHunter Optimizer software, Agilent Technologies, Santa Clara, CA) to check the fragmentor at each voltage. The data was then selected for optimal fragmentor signal and each compound was optimized again to determine automatically the collision energies for both the quantifying and qualifying ions. Optimal collision energies varied between 5 and 35 V. The MRM transitions and optimized energies used for this study are shown in Tables 2A to 2D.

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1 (The labeled standards are bold.)

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Acetaminophen	90	152 → 110 152 → 65	15 35
¹³C₂-¹⁵N-Acetaminophen	90	155 → 111 155 → 93	15 25
Ampicillin	70	350 → 160 350 → 106	10 15
¹³C₃-Atrazine	120	219 → 177 219 → 98	15 25
Azithromycin	130	749.5 → 591.4 749.5 → 158	30 35
Caffeine	110	195 → 138 195 → 110	15 25
¹³C₃-Caffeine	110	198 → 140 198 → 112	15 25
Carbadox	80	263 → 231 263 → 130	5 35
Carbamazepine	110	237 → 194 237 → 179	15 35
Carbamazepine-d₁₀	110	247 → 204 247 → 202	15 35
Cefotaxime	90	456 → 396 456 → 324	5 5
Ciprofloxacin	110	332 → 314 332 → 231	20 35
¹³C₃-¹⁵N-Ciprofloxacin	110	336 → 318 336 → 235	15 35

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1
(The labeled standards are bold.) continued

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Clarithromycin	110	748.5 → 158 748.5 → 590	25 15
Cloxacillin	90	436 → 160 436 → 277	15 15
Codeine	130	300 → 215 300 → 165	25 35
Cotinine	90	177 → 98 177 → 80	25 25
Cotinine-d₃	90	180 → 80 180 → 101	25 25
Dehydronifedipine	130	345 → 284 345 → 268	25 25
Digoxigenin	90	391 → 355 391 → 337	15 15
Digoxin	No response, Na adduct		
Diltiazem	130	415 → 178 415 → 150	25 25
1,7-Dimethylxanthine	90	181 → 124 181 → 99	15 15
Diphenhydramine	70	256 → 167 256 → 152	15 35
Enrofloxacin	130	360 → 316 360 → 342	15 15
Erythromycin	90	734.5 → 158 734.5 → 576	35 15
¹³C₂-Erythromycin	90	736.5 → 160 736.5 → 578	25 15
Erythromycin anhydrate	90	716.5 → 158 716.5 → 116	25 25
Flumequine	90	262 → 174 262 → 244	35 15
Fluoxetine	90	310 → 148	5
Fluoxetine-d₆	90	316 → 154	5
Lincomycin	110	407 → 126 407 → 359	25 15
Lomefloxacin	130	352 → 308 352 → 265	15 25
Miconazole	90	415 → 159 415 → 69	35 25
Norfloxacin	70	320 → 302 320 → 276	15 15
Ofloxacin	110	362 → 318 362 → 261	15 25

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1 (The labeled standards are bold.) continued

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Oxacillin	70	402 → 160 402 → 243	15 5
Oxolinic acid	90	262 → 244 262 → 216	15 25
Penicillin G	90	335 → 160 335 → 176	5 5
Penicillin V	70	351 → 160 351 → 114	5 25
Roxithromycin	130	837.5 → 679 837.5 → 158	15 35
Sarafloxacin	130	386 → 299 386 → 368	25 25
Sulfachloropyridazine	90	285 → 156 285 → 92	10 25
Sulfadiazine	110	251 → 156 251 → 92	15 25
Sulfadimethoxine	80	311 → 156 311 → 92	20 35
Sulfamerazine	110	265 → 156 265 → 92	15 25
Sulfamethazine	90	279 → 156 279 → 186	15 15
¹³C₆-Sulfamethazine	90	285 → 186 285 → 162	25 25
Sulfamethizole	80	271 → 156 271 → 92	10 25
Sulfamethoxazole	110	254 → 156 254 → 92	15 25
¹³C₆-Sulfamethoxazole	110	260 → 162 260 → 98	15 25
Sulfanilamide	70	173 → 156 173 → 92	5 15
Thiabendazole	130	202 → 175 202 → 131	25 35
¹³C₆-2,4,5-Trichlorophenoxyacetic acid	110	259 → 201 259 → 165	5 25
Trimethoprim	110	291 → 230 291 → 261	25 25
¹³C₃-Trimethoprim	110	294 → 233 294 → 264	25 25
Tylosin	110	916.5 → 174 916.5 → 772	35 35
Virginiamycin	110	526 → 508 526 → 355	5 15

Table 2B. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 2

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Anhydrotetracycline	90	427 → 410 427 → 154	15 25
Chlorotetracycline	110	479 → 462 479 → 197	15 35
Demeclocycline	130	465 → 430 465 → 448	25 15
Doxycycline	110	445 → 428 445 → 154	15 25
4-Epianhydrotetracycline (EATC)	90	427 → 410 427 → 105	15 35
4-Epitetracycline (ETC)	110	445 → 410 445 → 427	15 5
Minocycline	90	458 → 441	15
Tetracycline (TC)	110	445 → 410 445 → 427	15 5

Table 2C. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 3

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Gemfibrozil	100	249 → 121	5
Gemfibrozil-d₆	100	255 → 121	5
Ibuprofen	75	205 → 161	5
¹³C₃-Ibuprofen	75	208 → 163	5
Naproxen	75	229 → 169 229 → 170	25 5
¹³C-Naproxen-d₃	75	233 → 169 233 → 170	25 5
Triclocarban	100	313 → 160 313 → 126	10 25
¹³C₆-Triclocarban	90	319 → 160 319 → 132	5 25
Triclosan	75	287 → 35	5
¹³C₁₂-Triclosan	75	299 → 35	5
Warfarin	125	307 → 117 307 → 161	35 15
Warfarin-d₅	90	312 → 161 312 → 255	15 25

Table 2D. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 4

Compound	Fragmentor voltage	MRM transitions (m/z)	Collision energy (eV)
Albuterol (Salbutamol)	90	240 $\rightarrow$ 148	15
		240 $\rightarrow$ 166	5
Cimetidine	100	253 $\rightarrow$ 159	10
		253 $\rightarrow$ 95	25
Metformin	80	130 $\rightarrow$ 60	10
		130 $\rightarrow$ 71	25
Ranitidine	110	315 $\rightarrow$ 176	15
		315 $\rightarrow$ 130	25

Chromatographic separation was done independently for each group and a dwell time of 10 msec was used for every MRM transition. Figures 1A to 1D show the chromatograms corresponding to 100 ppb standard on column for all the pharmaceuticals studied. Extracted ion chromatograms are overlaid for each one of the target analytes according to their respective protonated molecule and product-ion MRM transitions.




Figure 1A. MRM extracted chromatogram for pharmaceuticals in Group 1. Three time segments were used in this chromatographic separation.




Figure 1B. MRM extracted chromatogram for pharmaceuticals in Group 2. Only one transition shown. See Table 2B for compound identification.




Figure 1C. MRM extracted chromatogram for pharmaceuticals in Group 3. Only one transition shown. See Table 2C for compound identification.




Figure 1D. MRM extracted chromatogram for pharmaceuticals in Group 4.

Application to Wastewater Samples

To confirm the suitability of the method for analysis of real samples, matrix-matched standards were analyzed in a wastewater matrix from an effluent site, at eight concentrations (0.1, 0.5, 1, 5, 10, 50, 100, and 500 ng/mL or ppb concentrations). Figure 2 shows an example standard curve for acetaminophen in the wastewater matrix. In general, all compounds gave linear results with excellent sensitivity over three orders of magnitude, with r^2 values of 0.99 or greater.




Figure 2. Calibration curve for acetaminophen in a wastewater matrix using a seven-point curve from 0.1 to 100 ng/mL (ppb) using a linear fit with no origin treatment.

Finally, a “blank” wastewater sample was analyzed and the presence of two pharmaceuticals, carbamazepine and diphenhydramine, could be confirmed with two MRM transitions. Figure 3 shows the ion ratios qualifying for these two compounds in a wastewater extract. As shown in Figure 3 in the two ion profiles, both pharmaceuticals were easily identified in this complex matrix due to the selectivity of the MRM transitions and instrument sensitivity.




Figure 3. MRM chromatograms of a wastewater sample for carbamazepine and diphenhydramine using two transitions.

Conclusions

The results of this study show that the Agilent 6410A Triple Quadrupole is a robust, sensitive, and reliable instrument for the study of pharmaceuticals in water samples, using high throughput methods. The Agilent 6410A Triple Quadrupole has been shown to be a successful instrument for the implementation of EPA Method 1694.

References

1. EPA Method 1694: Pharmaceuticals and personal care products in water, soil, sediment, and biosolids by HPLC/MS/MS, December 2007, EPA-821-R-08-002.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Printed in the USA
September 19, 2008
5989-9665EN



Agilent Technologies



Semivolatile Organics Analysis Using an Agilent J&W HP-5ms Ultra Inert Capillary GC Column

Application Note

Environmental

Author

Doris Smith and Kenneth Lynam
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Trace-level semivolatile organics analyses using methods such as USEPA Method 8270 are important tools for assessing environmental contaminants worldwide. The wide-ranging chemical diversity of target semivolatiles can prove chromatographically challenging. This application note demonstrates the benefits of using an Agilent J&W HP-5ms Ultra Inert Capillary GC column with electron impact single quadrupole scanning mass spectrometry for trace-level semivolatiles analysis.

Agilent Technologies has implemented new testing procedures to more effectively evaluate GC column inertness performance. These new testing procedures employ deliberately aggressive probes to thoroughly investigate column inertness and quality. These aggressive probes, including 1-propionic acid, 4-picoline, and trimethyl phosphate, are used to verify each column's inertness performance.



Agilent Technologies

Introduction

USEPA Method 8270 [1] is a commonly used method for detecting semivolatile organic compounds in environmental samples by GC/MS. This method encompasses several classes of analytes, including amines, alcohols, polycyclic aromatic hydrocarbons, and phenols. The acidic and basic nature of many of the analytes makes minimizing any column or instrument activity critical to good chromatography and reliable results.

Minimizing activity in the GC column is essential in maximizing an analyte's response. Nitrophenols are among the most active compounds in semivolatiles series. 2,4-Dinitrophenol in particular is notorious for showing low response through adsorption onto active sites in the flow path during analysis. At low concentrations, the response factor (RF) for 2,4-dinitrophenol can fall below the minimum average RF of 0.050 required by USEPA 8270 due to interaction between the analyte and sample flow path. Capillary GC column activity as a potential source of result uncertainty has been effectively eliminated with the Ultra Inert series of columns.

A custom standard containing an abbreviated list of analytes specific to USEPA Method 8270 was analyzed to evaluate column performance. This semivolatiles "short mix" contained n-nitrosodimethylamine, aniline, benzoic acid, 2,4-dinitrophenol, 4-nitrophenol, 2-methyl-4,6-dinitrophenol, pentachlorophenol, 4-aminobiphenyl, benzidine, 3,3'-dichlorobenzidine, benzo[b]fluoranthene, and benzo[k]fluoranthene, along with the recommended internal standards. These target analytes were chosen based on their chemical activity, as well as their poor chromatographic behavior. The short mix is particularly useful for rapid evaluation of system performance for semivolatiles analysis. Challenging analytes from early-eluting nitrosoamines through late-eluting PAHs are represented in this mix and chromatographic performance can be assessed quickly.

A second "large mix" standard containing a broader selection of semivolatiles was also evaluated to show the Ultra Inert's performance when analyzing a more complex sample. This standard contained a variety of acidic, basic, and neutral groups, which ranged from very low-boiling components to high-boiling polycyclic aromatic hydrocarbons.

Experimental

An Agilent 6890N GC/5975B MSD equipped with a 7683B autosampler was used for this series of experiments. Table 1 lists the chromatographic conditions used for these analyses. Table 2 lists flow path consumable supplies used in these experiments.

Table 1. Chromatographic Conditions for EPA Method 8270 Calibration Standards

GC:	Agilent 6890N/5975B MSD
Sampler:	Agilent 7683B, 5.0- μ L syringe (Agilent p/n 5181-1273) 1.0 μ L splitless injection
Carrier:	Helium 30 cm/s, constant flow
Inlet:	Splitless; 260 °C, purge flow 50 mL/min at 0.5 min Gas saver 80 mL/min at 3 min
Inlet liner:	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Column:	Agilent HP-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 19091S-433UI)
Oven:	40 °C (1 min) to 100 °C (15 °C/min), 10 °C/min to 210 °C (1 min), 5 °C/min to 310 °C, hold 8 min
Detection:	MSD source at 300 °C, quadrupole at 180 °C, transfer line at 290 °C, scan range 45 to 450 amu

Table 2. Flow Path Supplies

Vials:	Amber screw top glass vials (Agilent p/n 5183-2072)
Vial caps:	Blue screw caps (Agilent p/n 5182-0723)
Vial inserts:	100 μ L glass/polymer feet (Agilent p/n 5181-8872)
Syringe:	5 μ L (Agilent p/n 5181-1273)
Septum:	Advanced Green (Agilent p/n 5183-4759)
Inlet liners:	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Ferrules:	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323)
20x magnifier:	20x magnifier loupe (Agilent p/n 430-1020)

Sample Preparation

A 12-component custom semivolatiles mix was purchased from Ultra Scientific (Kingston, RI) and used to prepare a seven-level calibration standard set. The stock semivolatiles solution as delivered had a nominal concentration of 2,000 μ g/mL. An internal standard mix as recommended by USEPA Method 8270 was purchased from AccuStandard (New Haven, CT). The internal/surrogate solution as delivered had a

nominal concentration of 4,000 µg/mL. The calibration standards were prepared with component and internal standard concentrations of 80, 40, 20, 10, 5, 2, and 1 µg/mL. All solutions were prepared in dichloromethane using class A volumetric pipettes and flasks. The dichloromethane used was Burdick and Jackson spectral grade purchased thorough VWR International (West Chester, PA). Dichloromethane was used as a reagent blank and syringe wash solvent.

The EPA 8270 Calibration Level 2 standard set was purchased from AccuStandard containing 83 semivolatile components and internal standards. The large mix calibration standard was prepared at an analyte concentration of 5 µg/mL.

Results and Discussion

Baseline Inertness Profile for Ultra Inert Columns

The basic approach for inertness verification for the Agilent J&W Ultra Inert series of capillary GC columns is testing with aggressive active probes at low concentration and low temperature. This is a rigorous approach that establishes consistent baseline inertness profiles for each column in the Agilent J&W Ultra Inert GC column series. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species that tend to adsorb onto active sites, particularly at trace level like the semivolatiles in this

application example. A more detailed description of the test mix and additional application examples can be found in references 2 through 7.

Semivolatiles Analysis (USEPA 8270)

In this application note a seven-level semivolatile calibration curve set was evaluated over the concentration range of 1 to 80 µg/mL on an Agilent J&W Ultra Inert HP-5ms 30 m × 0.25 mm × 0.25 µm (p/n 19091S-433UI). An example chromatogram of a 1-µL injection of the 1 µg/mL short mix calibration standard is shown in Figure 1. Scanning mode was used exclusively for this analysis.

Pentachlorophenol and benzidine are two components that are used to verify inlet and column inertness. Excessive peak tailing of these components would indicate column activity. Analysis of the short mix standard yielded sharp, symmetrical peak shapes for the problematic analytes as shown in Figure 2. Good separation was obtained in the analysis of the 5-ng on-column 8270 large mix standard for each of the semivolatiles, which is shown in Figure 3.

Semivolatile analysis by USEPA Method 8270 requires a minimum average RF of 0.050 for a system performance check compound such as 2,4-dinitrophenol. 2,4-Dinitrophenol is a highly active analyte that has proven to be one of the most challenging compounds, often yielding lower than expected




Figure 1. Total ion chromatogram (SCAN mode) of the 1-ng on-column EPA8270 short mix standard solution loading on an Agilent J&W HP-5ms Ultra Inert 30 m × 0.25 mm × 0.25 µm capillary GC column (p/n 19091S-433UI). Chromatographic conditions are listed in Table 1.




Figure 2. Enlarged section of the total ion chromatogram for a 1- μ L injection of 1.0 μ g/mL EPA 8270 short mix standard. The peaks of interest noted in the figure are two semivolatiles that are prone to peak tailing. Chromatographic conditions are listed in Table 1.




Figure 3. Total ion chromatogram (SCAN mode) of 5-ng on-column loading of EPA 8270 calibration (large mix) standard solution on an Agilent J&W HP-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 19091S-433UI). Chromatographic conditions are listed in Table 1.

response factors at lower concentrations. In the analysis of the short mix calibration standard, the response for 2,4-dinitrophenol was greater than 0.1 at the 1-ng level. The average response was 0.15 over the concentration range studied. An example chromatogram for the signal-to-noise ratio for a 1-ng on-column loading of 2,4-dinitrophenol is shown in Figure 4. The signal-to-noise ratio for this difficult analyte was greater

than 16 to 1. This demonstrates the excellent performance of the HP-5ms Ultra Inert GC column.

Linearity was excellent across the range studied, giving R^2 values of 0.990 or greater for even the more difficult phenols. Figure 5 indicates the correlation coefficients for several of the more active analytes.




Figure 4. Enlarged section of the total ion chromatogram (scan mode) for a 1- μ L injection of 1 μ g/mL EPA Method 8270 short mix standard on an Agilent J&W HP-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 19091S-433UI). The peak in the figure is 2,4-dinitrophenol, one of the more demanding semivolatiles. This injection represents an on-column loading of 1 ng per component. Chromatographic conditions are listed in Table 1.




Figure 5. Correlation coefficients for some of the more challenging analytes in the EPA Method 8270 short mix standard over the 1 to 80 μ g/mL range of this study and an example linear regression plot for benzidine.

Conclusions

This application successfully demonstrates the use of an Agilent J&W HP-5ms Ultra Inert capillary GC column for low-level semivolatile organics. Linearity was excellent for all semivolatiles studied, yielding 0.99 or greater R^2 values down to a 1-ng column loading of each component. One of the reasons for excellent linearity and high R^2 values is the highly inert surface of the column. The lack of chemically active sites makes these columns an excellent choice for semivolatiles analyses.

This study was done using SCAN mode on an Agilent 6890N/5975B GC/MSD equipped with an inert electron impact source. The signal-to-noise ratio for a 1-ng on-column loading of 2,4-dinitrophenol was greater than 16 to 1 with this system. This result clearly shows the power of using an Agilent J&W HP-5ms Ultra Inert column for low-level semivolatile organics analysis. Lower limits of quantification are expected when using one of Agilent's latest GC/MS offerings, such as the 7890A/5975C GC/MSD Triple-Axis Detector coupled with an Agilent J&W HP-5ms Ultra Inert GC capillary column.

References

1. US EPA Method 8270D, Revision 4, February 2007, "Semivolatile Organic Compounds by Gas Chromatography/Mass Spectrometry (GC/MS)"
2. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenyltrimethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
3. "Agilent J&W Ultra Inert GC Columns: A New Tool to Battle Challenging Active Analytes," Agilent Technologies publication 5989-8685EN, May 29, 2008
4. Mike Szelewski and Bill Wilson, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270," Agilent Technologies publication 5988-3072EN, November 7, 2001
5. Kenneth Lynam, "Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column," Agilent Technologies publication 5989-8616EN, May 13, 2008
6. Kenneth Lynam and Doris Smith, "Polycyclic Aromatic Hydrocarbon (PAH) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9181EN, July 2008
7. Kenneth Lynam and Doris Smith, "Polybrominated Diphenyl Ether (PBDE) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9571EN, August 2008

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Published in the USA
January 20, 2009
5990-3416EN



Agilent Technologies

Determination of Sub-ppb Level of Phthalates in Water by Auto-SPME and GC-MS



Application

Environmental

Author

Wenmin Liu
Agilent Technologies (Shanghai) Co. Ltd.
412 Ying Lun Road
Waigaoqiao Free Trade Zone
Shanghai, 200131, P.R. China

Abstract

A solid-phase microextraction (SPME) method for the analysis of phthalates in water samples was developed on the CTC CombiPAL autosampler GC-MS platform. In this method, the sample preparation process was automated by using a CombiPAL autosampler, including the SPME fiber precondition, adsorption, and desorption, which improve the precision of the SPME method. The extraction temperature, extraction time, and salt-out effect are also studied. The optimized condition was applied to the analysis of real samples. The detection limits of the phthalates in this method are at the sub-ppb level.

Introduction

Phthalic acid esters (phthalates, PAEs) are key additives in many plastics to keep the plastics soft at room temperature. Because phthalates are not chemically but only physically bound to the plastic structure, the phthalates can leach from the plastic products. Due to their widespread use, relatively large amounts of these compounds are released into the environment. In recent years, considerable attention has been paid to human exposure to phthalates because of their suspected carcinogenic and estrogenic properties.

Liquid-liquid extraction (LLE) techniques have been widely used to isolate of PAEs from aqueous samples. These procedures are typically time-consuming, labor-intensive, and use a large amount of solvent. Solid-phase microextraction (SPME) is a fast, sensitive, solventless, and economical sample preparation method for gas chromatography analysis. The main advantages of SPME compared to solvent extraction are the reduction in solvent use, the combination of extraction and analysis into one step, and the ability to examine smaller sample sizes. It can also provide high sensitivity and can be used for polar and nonpolar analytes in a wide range of matrices with direct injection to both the gas chromatograph (GC) and the liquid chromatograph (LC).

Extraction of analytes from aqueous samples can be performed either by direct immersion of the fiber into the liquid phase or by headspace sampling. Adsorbed analytes are then thermally desorbed in the injection port of a GC and analyzed using an appropriate column and detector.

The CombiPAL provides a fully automated SPME sample preparation process. All movements of the SPME fiber from precondition, adsorption, and desorption are software controlled for optimum precision. Prior and during extraction, the samples can be shaken and heated. This approach dramatically reduces sample preparation time for semi-volatile compounds. Variable vial penetration depth allows compound extraction to be performed in liquid phase or in the headspace. After the compounds are thermally desorbed in the hot GC injector, the fiber may be regenerated in a heated and purged cleaning station.



Agilent Technologies

In this application, an automated SPME sample preparation process is demonstrated by using CombiPAL combined with GC-MS to determine plasticizers in a water sample.

Experimental

CombiPAL

Pre-incubation time:	60 s
Incubation temperature:	40 °C
Pre-inc. agitator speed:	500 rpm
Agitator on time:	5 s
Agitator off time:	2 s
Vial penetration:	25 mm
Extraction time:	1200 s
Desorb to:	GC Inj1
Injection penetration:	54 mm
Desorption time:	120 s
Post fiber condition time:	300 s

SPME

SPME fiber is from Supelco company (595 North Harrison Road Bellefonte, PA, USA), the fiber type is polydimethylsiloxane/divinylbenzene (PDMS/DVB) and the coating thickness is 65 µm.

6890 GC

Inlet temperature:	270 °C
Gas type:	Helium
Oven condition:	50 °C Ramps 10.00 °C /min to 260 °C (3.00 min)
Column:	DB-5ms 30 m × 250 µm, 0.25 µm
Mode:	Constant flow
Flow rate:	1.3 mL/min

5975 MS

Acquisition mode:	Synchronous SIM/scan
Mass range:	40–300
Sample:	3
Dwell time:	30 ms
MS source:	230 °C
MS quad:	150 °C
For other parameters, see Table 1.	

The PAEs standards (shown in Table 1) were bought from Guo Yao Group (Shanghai, China).

The PAEs were dissolved in methanol at a concentration of 1,000 ng/mL and diluted by MilliQ water to the tested concentration.

Results and Discussion

Because PAEs are semivolatile compounds, immersion extraction mode was selected, and the sample volume was 18 mL.

Lots of unrelated peaks emerged in GC chromatograms when the extraction temperature was over 40 °C, which would shorten the lifetime of fiber, so a compromise has to be made between the lifetime of the extraction phase and the rate of equilibrium. We chose 40 °C for all extractions in the following experiments.

The effect of extraction time versus amount extracted at 40 °C was studied. The extraction efficiency for different compounds was proportional to extraction time. Figure 1 shows the profile of extraction time versus response. As seen in Figure 1, when the extraction time was over 20 minutes, the responses changed slightly, which means that the extraction of most compounds reached equilibrium at this point. In this experiment, 20 minutes was selected as the extraction time.

Salting-out effects by adding NaCl in the sample were also studied. The results showed that the extraction efficiency of DEP, DMP, and DBP was improved when salt was added, and that of DCHP, DEHP, and DPP (see compound names in Table 1) was decreased as shown in Figure 2. In this experiment, 20% (W/V) salt concentration was chosen. Figure 3 shows the SIM chromatogram of PAEs at the optimized condition. The chromatogram shows that improvements can be made to shorten the analysis time by adjusting the oven program.

Table 1. Compound Information

Compound name	Abbreviation	Retention time (min)	SIM ions
Phthalic acid, bis-n-pentyl ester	DPP	10.179	135, 149, 163, 177
Phthalic acid, bis-isononyl ester	DEHP	11.862	93, 105, 149, 177
Di-cyclohexyl phthalate	DCHP	15.749	93, 104, 149, 167
Diethyl phthalate	DEP	17.517	93, 105, 149, 177
Dimethyl phthalate	DMP	20.666	104, 135, 163, 194
Dibutyl phthalate	DBP	20.836	93, 149, 104, 205




Figure 1. The profile of extraction time versus response (at 40 °C).




Figure 2. The effect of salt concentration on extraction.




Figure 3. SIM of PAEs at the optimized extraction condition.

The linearity of the analytes was determined by calibration solutions with the concentration range from 0.5 ppb to 1 ppm at the optimized extraction condition. Table 2 shows the concentration ranges and correlating coefficients. The precision of the analysis, represented as relative standard deviations (RSDs) at 1 ppb, is also shown in Table 2. The RSDs for the organic esters are less than 10% except that of DPP; the detection limit is calculated at S/N of 3.

To demonstrate the performance of the optimized SPME method, tap water, potable water, and purified water from a water dispenser were analyzed for the phthalates' presence. Table 3 shows the phthalates detected in these three samples.

Conclusions

The CombiPAL autosampler with SPME is used for the analysis of PAEs in water. The precondition, extraction, adsorption, and desorption of SPME are automated and precisely controlled, which improves the precision of SPME method. Because the analytes concentrate into the coating of SPME, trace-level contaminants can be detected by using SPME. In this application, the detection limits for PAEs are down to sub-ppb level.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Table 2. Method Validation Results

	Linear range (ng/mL)	Correlation coefficients (r^2)	RSD(%) N=7 (1 ppb)	Detection limits (ng/mL)
DPP	1–1000	0.996	12	0.34
DEHP	1–1000	0.996	8.6	0.29
DCHP	0.5–1000	0.989	8.9	0.08
DEP	1–1000	0.999	7.8	0.29
DMP	1–1000	0.998	7.1	0.38
DBP	1–1000	0.970	5.6	0.23

Table 3. Sample Analysis Results (quantitation unit = ng/mL)

	Tap water	Potable water	Purified water
DPP	n.d. ¹	n.d.	n.d.
DEHP	n.d.	n.d.	n.d.
DCHP	40.5	n.d.	n.d.
DEP	n.d.	78.9	n.d.
DMP	n.d.	23.6	n.d.
DBP	61.3	45.7	25.0

¹ None detected

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
January 14, 2008
5989-7726EN



Agilent Technologies

Analysis of Semivolatiles Using High Efficiency Capillary GC Columns



Application Brief

Ken Lynam and Mike Szelewski

Introduction

U.S. EPA Method 8270 is broadly applicable for analysis of semi-volatiles using capillary gas chromatography with mass spectral detection. EPA 8270 is widely used in both contract analytical and government environmental laboratories. The method is capable of concurrently measuring a mixture of 70 to 100 acidic, basic, and neutral species. Shifting these important analyses from 0.25-mm id to 0.18-mm id or high efficiency GC columns is a viable means of obtaining faster results and improving laboratory productivity.

In this example, 77 compounds of interest and six internal standards are resolved on a 0.18-mm id high efficiency GC column using 7 minutes of analysis time. The same compounds and internal standards were also resolved using a 0.25-mm id column where 25 minutes of analysis time was required. Analysis speed using the high efficiency column was 8 minutes faster, resulting in a 32% reduction in analysis time.

Experimental

Method translation software available from Agilent Technologies translates chromatographic parameters from an existing method to the new column format with a few simple keystrokes [1].

Column dimensions, flow, and temperature parameters from an existing method are entered into a table along with the desired new column dimensions. The software then generates flow and temperature setpoints for the new translated method. Often these new setpoints yield a successfully translated method with the same separation and elution order with no additional method development. In this example, one-to-one phase-ratio correspondence was maintained between the 0.25-mm and 0.18-mm id column formats, enhancing the reliability of the software's predicted conditions. Keeping the phase ratio constant helps maintain peak elution order on the new column.

Instrument conditions are described in Table 1, and Figures 1 and 2.

Highlights

- 0.18-mm id, also known as high-efficiency GC columns, deliver faster results for U.S. EPA 8270 analyses.
- 32% reduction in analysis time when translating 0.25-mm id column method to the 0.18-mm id format.
- Resolution of 77 peaks of interest is maintained for the faster 0.18-mm id separation.
- DB-5.625 column: Agilent DB-5.625 column in 0.18-mm id provides faster sample analysis without loss of resolution.



Agilent Technologies

Table 1. Experimental Conditions

Column:	Figure 1. 30 m x 0.25 mm x 0.50 μ m DB-5.625 column, Agilent Technologies part number 122-5632 Figure 2. DB-5.625 20 m x 0.18 mm x 0.36 μ m column, Agilent Technologies part number 121-5622
Carrier:	He constant-flow mode 1.1 mL/min
Oven:	40 °C for 1.00 min, 25 °C/min to 320 °C 4.80 min hold
Injection:	Splitless 0.5 μ L injected at 300 °C, Quick-Swap pressure 5.0 psi during acquisition, 80.0 psi during backflush with inlet set to 1.0 psi during backflush
Detector:	Agilent Technologies 5975C Performance Turbo MSD equipped with a 6-mm large-aperture draw-out lens, Agilent Technologies part number G2589-20045




Figure 1. U. S. EPA Method 8270, 5 ng/mL System Performance Check Compounds Chromatogram using a 30-m x 0.25-mm x 0.50- μ m DB-5.625 column, Agilent Technologies part number 122-5632. Please refer to Table 1 for instrument conditions.




Figure 2. U.S. EPA Method 8270, 5 ng/mL System Performance Check Compounds Chromatogram using a 20-m x 0.18-mm x 0.36- μ m DB-5.625 column Agilent Technologies part number 121-5622. Please refer to Table 1 for instrument conditions.

Discussion of Results

Figures 1 and 2 depict the resolution of 77 compounds of interest along with six internal standards first on a 30 m x 0.25 mm x 0.5 μ m (Agilent part number 122-5632) standard-bore capillary column (Figure 1) and second on a 20 m x 0.18 mm x 0.36 μ m (Agilent part number 121-5622) high efficiency column (Figure 2). Peak resolution and quantification are comparable, and in both cases meet EPA 8270 criteria for System Performance Check Compounds (SPCCs) and Continuous Calibration Compounds (CCCs) over a calibration range from 1 to 200 ppm; 5 ppm SPCC chromatograms were selected for visualization purposes.

Significant improvement in analysis time was achieved by shifting the column used from a 0.25-mm id standard-bore capillary to a 0.18-mm id high efficiency GC column example; the 0.25-mm id column required 25 minutes of run time, and the 0.18-mm id column required 17 minutes. In this semi-volatile analysis example, 25 minutes of run time were required for the 0.25-mm id column, and 17 minutes were required on the 0.18-mm id column. Moving the analysis to a 0.18-mm id column yielded 8 minutes in time savings or 32% faster sample analysis.

Typical run time for EPA 8270 analysis using 0.25-mm id or standard-bore capillary columns is 25 minutes, excluding post-analysis bakeout and system cooldown time often required for dirty samples. When bakeout and subsequent system cooldown periods are accounted for, the overall cycle time climbs to 57 minutes. As shown above, a time saving of 8 minutes was achieved by using a high efficiency column. Further improvements in the cycle time for EPA 8270 analysis are achieved through the use of several advanced features on the Agilent 7890A GC. A QuickSwap device installed in a 7890A can be used to backflush heavy material matrix contaminants back out of the inlet, dramatically reducing matrix bakeout time [2]. Faster cooldown and thermal isolation features available on the 7890A GC also reduce system cycle times for dirty samples. The combination of a high efficiency column and the unique features of the 7890A reduce sample analysis time from 57 minutes to 24.3, a 32.7-minute time saving per sample run.

Conclusions

High efficiency GC columns provide a straightforward way to obtain faster results for EPA 8270 analysis without compromising resolution.

References

1. Method translation software: free download of method translation software available at <http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>.
2. Mike Szelewski, "Significant Cycle Time Reduction Using the Agilent 7890A/6975C GC/MSD for EPA Method 8270," Agilent Technologies publication 5989-6026EN

For More Information

For more information on our new line of high efficiency GC columns, please visit this link:
<http://www.chem.agilent.com/scripts/PDS.asp?lpage=60005>.

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
November 30, 2007
5989-7500EN



Agilent Technologies



Separation of Explosives in EPA 8330: Column Choices Optimize Speed, Resolution, and Solvent Use

Application

Environmental

Authors

John W. Henderson Jr. and William J. Long
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

ZORBAX Extend-C18 columns separate the explosive compounds in EPA method 8330, and the variety of column configurations available allows customized HPLC methods based on resolution, speed, and even solvent usage. For example, a fast method for the explosive-materials standard (EPA 8330) uses 1.8- μ m, short length columns. The method was then customized using two other Extend-C18 column configurations. Each column highlights a combination of resolution, speed, and/or solvent savings. The advantage is being able to choose which combination of resolution, speed, and solvent usage is needed by simple column substitution.

Introduction

The ZORBAX Rapid Resolution High Throughput (RRHT, 1.8 μ m) LC column line has over 120 column choices, including 11 bonded phases and silica, three column diameters, and six lengths. In addition, there are another 150+ Rapid Resolu-

tion (3.5 μ m) column choices, allowing customization of HPLC methods to meet the analyst's tailored objectives. Many ZORBAX column choices are available because the stationary phase chemistry (both silica support and bonded phase) between 5-, 3.5- and 1.8- μ m particles is uniform.

EPA 8330 explosives residues are typically analyzed by a 4.6 mm $\times$ 250 mm, 5 μ m C18 column [1] but can be improved by newer technology: smaller 1.8- μ m or 3.5- μ m ZORBAX particles and Extend-C18 bonded phase. Many different Extend-C18 columns can be chosen (the combination of column length, diameter, and particle size) to provide a satisfactory separation, and each separation exemplifies a newer column technology's benefit and supports the end user's choice of speed, resolution, and solvent usage.

High-efficiency 1.8- μ m particles in 100-mm length columns reduce analysis time and have about the same efficiency compared to 5- μ m particles in 250-mm columns. Therefore, they are helpful by saving time in method development or generating more data in a limited amount of time. But these columns will generate a higher back pressure that some people may not desire. It is still possible to obtain the same resolution but using a longer 3.5- μ m column. The end result is an analysis time still shorter than that achieved with a 250-mm, 5- μ m column.



Agilent Technologies

Experimental

The Agilent 1200 Rapid Resolution LC (RRLC) system:

- G1312B binary pump SL with mobile phase
A: 5 mM ammonium formate in water,
B: methanol
- G1376C automatic liquid sampler (ALS) SL
- G1316B Thermally Controlled Column (TCC) Compartment SL using the low-volume heat exchanger kit (PN G1316-80003)
- G1365C multiwavelength detector (MWD) at 254 nm, with a G1315-60024 micro flow cell (3-mm path, 2- μ L volume), response time setting of 0.5 s

ZORBAX columns:

- Rapid Resolution High Throughput (RRHT) Extend-C18, 4.6 mm $\times$ 100 mm, 1.8 μ m, PN 728975-902
- Rapid Resolution (RR) Extend-C18, 4.6 mm $\times$ 100 mm, 3.5 μ m, PN 764953-902
- Solvent Saver Plus Extend-C18, 3.0 mm $\times$ 100 mm, 3.5 μ m, PN 764953-302

The sample is a 1:1 mix of EPA 8330 Mix A (cat. no. 47283) and EPA 8830 Mix B (cat. no. 47284) from Sigma-Aldrich (Bellefonte, PA), diluted in methanol:water.

Results and Discussion

Selectivity, or the relative band spacing between two peaks, is different among C18 columns. In many cases the difference is small, so adjusting mobile phase organic strength can fine tune the retention to achieve comparable resolution between one C18 column and an alternative C18 column. Temperature may also influence selectivity, and small adjustments in temperature can fine tune the resolution.

For complex mixtures, fine tuning organic strength and temperature could be used to improve resolution and ultimately make a method more robust. Determining the combination of temperature, % organic, and what column (stationary phase) is best is frequently discovered by experimentation. This is time consuming at the very least and often daunting. Fortunately, research narrows the testing.

Consider an explosive residue standard of 14 nitroaromatic and nitramine compounds. Trace residues of these explosives were analyzed by time-of-flight LCMS by Kinghorn et al. using an Extend-C18, 4.6 mm $\times$ 250 mm, 5- μ m column and a methanol/water gradient at a temperature of 40 °C [2]. Additionally, EPA method 8330 describes an HPLC method for the 14 compounds using an isocratic methanol/water mobile phase and a C18 column. Temperature is not specified, but the method states, *"If column temperature control is not employed, special care must be taken to ensure that temperature shifts do not cause peak misidentification."* [1]

In both methods a lack of selectivity required a TOF detector or additional analysis by an orthogonal stationary phase to confirm peak identity.

We separated the 14 compounds with enough resolution to make the MS detector or secondary analysis by a different stationary phase redundant.

The above methods narrowed our method-development starting conditions to:

- Extend-C18 (from successful Kinghorn method)
- Isocratic mobile phase A: 5 mM ammonium formate, B: Methanol (so new method is similar to EPA 8330). The ammonium formate was selected based on recommendations from a pre-existing method. The difference between water and 5 mM ammonium formate was not investigated.
- 40 °C controlled temperature (to ensure constant selectivity)
- RRHT column configuration 4.6 mm $\times$ 100 mm, 1.8 μ m (for rapid analyses with efficiency comparable to the 4.6 mm $\times$ 250 mm, 5- μ m columns used in the Kinghorn and EPA methods)

The methanol composition of the mobile phase was lowered incrementally from 50 to 25% until all 14 were reasonably resolved. A critical pair (peaks 6 and 7) persisted as partially resolved. Further decreasing organic strength would result in excessive retention of peaks 12, 13, and 14. Temperature was then optimized. A one-degree temperature increase (41 °C) provided enough selectivity to resolve the critical pair. Figure 1 demonstrates temperature's selectivity effect on these compounds.




Figure 1. Temperature optimizes critical pair resolution.

Extend-C18 provides ample selectivity for the 14 nitroaromatics and nitramines identified in the EPA 8330 method; excellent resolution is obtained in a reasonable time. Figure 2 shows the separation using a RRHT 4.6 mm × 100 mm, 1.8 μm, Extend-C18. Resolution of all peaks is baseline or better ($R_s > 1.5$). High resolution makes it easier to quantify the analytes. For example, the EPA 8330 method warns, “2,4-DNT and 2,6-DNT elute at similar retention times ($R_s < 1.5$) and a large

concentration of one isomer may mask the other; therefore, if it is not apparent that both isomers are present, an isomeric mixture should be reported” [1]. When baseline resolution is obtained, retention times differ significantly, avoiding peak masking. If higher resolution is the most important objective, then the Extend-C18 4.6 mm × 100 mm, 1.8-μm column using the conditions in Figure 2 is an excellent choice.




Figure 2. EPA 8330 explosive standard high-resolution separation on Extend-C18.

Table 1 names the 14 explosives and their abbreviations used in the figures.

Table 1. EPA 8330 Explosives and Their Abbreviations

Name	Abbreviation
Cyclotetramethylene-tetranitramine	HMX
Cyclotrimethylene-trinitramine	RDX
1,3,5-trinitrobenzene	135TNB
1,3-dinitrobenzene	13DNB
Nitrobenzene	NB
2,4,6-trinitrophenyl-N-methylnitramine	tetryl
2,4,6-trinitrotoluene	TNT
2-amino-4,6-dinitrotoluene	2A DNT
4-amino-2,6-dinitrotoluene	4A DNT
2,4-dinitrotoluene	24 DNT
2,6-dinitrotoluene	26 DNT
2-nitrotoluene	2NT
4-nitrotoluene	4NT
3-nitrotoluene	3NT

If higher throughput is important, isocratic methods can be sped up by increasing flow rate. The 25% methanol mobile phase flowing 1.7 mL/min through the 4.6 mm × 100 mm, 1.8- μ m column generates a system pressure of about 500 bar, leaving

a small range to increase flow rate. An alternative is to substitute the 1.8- μ m column with a 3.5- μ m column. Pressure decreases substantially, allowing faster flow rates.

Figure 3 overlays two Extend-C18 chromatograms. The top chromatogram is a 4.6 mm × 100 mm column with 3.5- μ m particles at a 2.5 mL/min flow rate. Compared to Figure 2, the 32% increase in flow rate reduces analysis time by roughly 40%. The price for the considerable time savings is less resolution of closely neighboring peaks. Resolution is still sufficient, as a resolution factor (R_s) of 1.25 for equally sized peaks means 99.4% of peak area is not overlapped. If one peak is 1/32 as tall as the other, an R_s of 1.0 still means 99.2% of the peak areas do not overlap [3].

Figure 3's bottom chromatogram is a different column substitution, replacing the 4.6-mm-id column with the Solvent Saver 3.0-mm-id column. Flow rate was reduced from 2.5 to 1.1 mL/min. for equivalent mobile phase linear velocity. The outcome is similar retention and resolution, but only half of the solvent is consumed.

Table 2 summarizes the customization benefits.




Figure 3. Rapid resolution options for EPA 8330 explosive standard on Extend-C18.

Table 2. Column Dimensions Highlight Resolution, Speed, and Solvent Savings

	RRHT (4.6 mm id, 1.8 µm)	RR (4.6 mm id, 3.5 µm)	Solvent Saver Plus (3.0 mm id, 3.5 µm)
Resolution: Rs 7,6	2.3	1.3	1.3
Resolution: Rs 8,7	1.6	1.6	1.4
Resolution: Rs 9,8	2.3	1.5	1.6
Analysis time	26 min	16 min	16 min
Solvent consumption	44.2 mL/analysis	40 mL/analysis	17.6 mL/analysis

Table 2 suggests that another column configuration could be valuable for this analysis: Solvent Saver HT Extend-C18, 3.0 mm × 100 mm, 1.8-µm column (PN 728975-302). This would produce high resolution like the RRHT column and produce time and solvent savings from the smaller column diameter. The Solvent Saver HT Extend-C18 column was not evaluated in this work.

Conclusions

Highly efficient (1.8 µm) short columns (100 mm) are ideal for method development compared to 5-µm, 150-mm or 250-mm columns because shorter analysis time increases productivity and allows more analyses to be performed in a fixed time frame.

Selectivity is manipulated by changing stationary phase, mobile phase, and temperature.

An isocratic HPLC method for complex mixtures of explosive materials was quickly created from highly efficient 100-mm columns, Extend-C18's unique selectivity, and temperature optimization. The selectivity and column configurations make Extend-C18 a compelling choice for the analysis of explosive substances named in EPA method 8330. Extend-C18's selectivity provides ample resolution with negligible peak coelution; this may eliminate an additional analysis to confirm peak identity.

The ZORBAX column family, including Extend-C18, has consistent stationary-phase chemistry between 3.5- and 1.8-µm particles, enabling simple column substitution for method customization. The high-resolution 4.6 x 100, 1.8-µm configuration, however, requires flexibility to work at operating pressures above 400 bar. The chromatographer can choose benefits such as higher resolution, faster analysis time, or less solvent usage based on column dimensions.

References

1. EPA Method 8330, *Nitroaromatics and Nitramines by High Performance Liquid Chromatography (HPLC)*, revision 0, September 1994
2. R. Kinghorn, C. Milner, J. Zweigenbaum, "Analysis of Trace Residues of Explosive Materials by Time-of-Flight LC/MS," Agilent publication 5989-2449EN (2005)
3. L. R. Snyder, J. J. Kirkland, *Introduction to Modern Liquid Chromatography*, 2nd ed., pp. 38–42, 1979

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2007

Printed in the USA
November 21, 2007
5989-7632EN



Agilent Technologies

Parts-per-Trillion Level Calibration of Semivolatiles Using LVI-PTV-GC/MSD



Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

The analysis of semivolatiles in the parts-per-trillion range presents challenges due to analyte activity, background contamination, and instrument sensitivity. Method requirements vary worldwide, with the least sensitive specifying 1- μ L injections and full scan data acquisition. Lower level calibrations can be achieved using large volume injection (LVI) with a programmable temperature vaporizing (PTV) inlet and the MSD operating in SIM mode. Decreased sample preparation can be used as a trade-off for these lower detection limits.

Introduction

Low-level semivolatiles analysis is used to concurrently measure a mixture of acids, bases, neutrals, and pesticides in drinking water or source water. Most laboratories analyze for > 100 compounds with a chromatographic run time of 25 to 40 minutes. Sample extraction is accomplished using liquid-solid extraction (LSE) with C_{18} disks or cartridges. Liquid-liquid extraction with a solvent such as dichloromethane is an alternative tech-

nique. Extract injection is typically 1 μ L hot splitless with the MSD operating in full scan mode, as specified in some commonly used methods, such as U.S. EPA Method 525.2 [1].

Sensitivity is an area where laboratories are seeking improved performance. Sensitivity can be affected by sample preparation, extract volume injected, instrument tuning, signal acquisition, and overall system activity.

A PTV inlet provides better sensitivity through large-volume injection. Instead of 1 μ L, 25 μ L of relatively clean sample extracts can be routinely injected. Active analyte degradation is minimized on a PTV, providing lower detection limits than using hot splitless injection.

Methods for semivolatiles usually require identification of analytes with retention time (RT) and ratios of qualifier ions to a target ion. Selected ion monitoring (SIM) acquisition can be used in place of full scan with a sensitivity, or signal-to-noise ratio, increase of 10 to 50x.

A typical calibration range for low-level semivolatiles is 0.1 to 10 ppm as is found in U.S. EPA Method 525. This application note will demonstrate a calibration 1,000x lower and 10x wider that is from 0.1 to 100 ppb. LVI-PTV with SIM data acquisition on a retention time locked (RTL) GC/MSD system was used to achieve this performance. This application is a follow-up note to reference 2, where additional background information can be found.



Agilent Technologies

Experimental

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These conditions may have to be optimized for use in another laboratory.

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC				Front Injector	
Agilent Technologies 7890A or 6890N				Sample washes	0
Inlet	EPC PTV			Sample pumps	2
Mode	Solvent vent			Injection volume	25 microliters
Temp ramp	°C/min	Next °C	Hold min	Syringe size	50 microliters
Initial		20	0.60	Preinj solv A washes	0
Ramp 1	600	350	1.30	Preinj solv B washes	1
Ramp 2	10	250	0.00	Postinj solv A washes	2
Cryo	On			Postinj solv B washes	2
Cryo use temp	100 °C			Viscosity delay	1 second
Cryo timeout	10.00 min (On)			Plunger speed	Variable
Cryo fault	On			Injection speed	50 microliters/minute
Pressure	11.77 psi (On)			Draw speed	600 microliters/minute
Vent time	0.60 min			Dispense speed	6,000 microliters/minute
Vent flow	100.0 mL/min			Preinjection dwell	0 minutes
Vent pressure	0.0 psi			Postinjection dwell	0 minutes
Purge flow	50.0 mL/min			MSD	
Purge time	2.50 min			Agilent Technologies 5975C, Trace Ion Detection	
Total flow	53.9 mL/min				
Gas saver	Off			Drawout lens	6 mm large aperture drawout lens, part number G2589-20045
Gas type	Helium			Solvent delay	4 min
PTV Liner	Agilent multi-baffle liner, no packing, part number 5183-2037			Low mass	45 amu
Oven	240V			High mass	450 amu
Oven ramp	°C/min	Next °C	Hold min	Threshold	0
Initial		40	2.50	Sampling	1
Ramp 1	50	110	0.00	Quad temp	180 °C
Ramp 2	10	320	1.10	Source temp	300 °C
Total run time	26 min			Transfer line temp	280 °C
Equilibration time	0.5 min			Tune type	Autotune
Oven max temp	325 °C			EM voltage	Tune voltage, 1,247 V
Column	Agilent Technologies HP 5 MSi, part number 19091S-433i			MSD-SIM	
Length	30.0 m			AutoSIM was used to pick ions, groups, and switching times	
Diameter	0.25 mm			Number of groups	25
Film thickness	0.25 µm			Compounds/group	Varied 1 to 22
Mode	Constant flow			Ions/group	Varied 2 to 45
Pressure	11.77 psi			Dwell time, msec	Varied 5 or 10
Nominal initial flow	1.5 mL/min			Cycles/peak	Minimum 10
Inlet	Front			Calibration Standards	
Outlet	MSD			Ultra Scientific, North Kingstown, RI. Part number DWK-5252.	
Outlet pressure	Vacuum			Four mixtures, codiluted, resulting in 108 compounds at 4 concentration levels, spiked with 3 Internal Standards at 50 ppb and 4 surrogate standards at 50 ppb.	
RTL	System retention time locked to phenanthrene-d10 at 12.700 min			Calibration standards made separately in both dichloromethane and ethyl acetate.	

The newer 7890A GC offers significant speed advantage over the older 6890N. Cooldown time from 320 °C to 40 °C is reduced from 7 minutes to 4.3 minutes. The MSD can optionally be mounted in the new rear position on a 7890A GC. With the PTV also installed in the back inlet position, the oven insert or “pillow” can be used to further reduce cooldown time to 3.3 minutes.

The PTV was operated in the Solvent Vent mode. Figure 1 shows the PTV temperature and flow programs together with the oven program. The PTV is held at 20 °C, a temperature below the boiling point of the solvent dichloromethane, 39.8 °C, during the injection period, 0.6 minute. The solvent is slowly evaporated through the vent line, held at 0 psi, with helium flow at 100 mL/minute. At the end of the injection period, the vent line is closed, inlet pressure is raised to 11.77 psi, and the PTV is rapidly heated to 350 °C. The vent line is re-opened at the end of the splitless time, 1.3 minutes, and the inlet is purged at 50 mL/min. The PTV is allowed to cool during the run.

While the vent line is closed, the PTV is in the classical splitless mode with respect to flow. Because of the programmed temperature, compounds are vaporized and transferred onto the column at the lowest possible temperature. This

significantly reduces loss of active analytes, such as pesticides and bases, which are often specified in semivolatiles methods.

The PTV inlet liner, 5183-2037, is multibaffled and deactivated. It does not contain glass wool, which could contribute to active compound degradation. This liner has sufficient capacity to accommodate the 25- μ L injection volume at a correct injection speed.

The oven program relationship to the PTV parameters is shown in Figure 1. The oven starts at 40 °C and is held there during the injection/solvent vent cycle and splitless transfer of analytes onto the column. The oven then programs rapidly to 110 °C followed by a slower ramp for compound separation. The 240V oven was used but a 120V oven can also achieve the ramp rates found in Table 1.

The HP-5MSi column is designed for inertness and is well suited to this method. This is the latest version of the most popular column in environmental laboratories, the HP-5MS. The column was run in constant flow mode at 1.5 mL/min to maintain peak shape and sensitivity.

The system was retention time locked to phenanthrene-d10 at 12.700 minutes. The funda-




Figure 1. PTV temperature and flow programs.

mentals of RTL for GC/MSD systems can be found in reference 3. The primary benefit of RTL for this analysis is maintaining constant switching times for SIM groups. After clipping the column, a rerun and analysis of the locking standard is all that is needed to restore shifted peak times. Quantitation database and integration events times also do not have to be changed. Additional RTL application notes detailing the numerous benefits of RTL are available at www.agilent.com/chem. It is almost impossible to use a method with this many SIM groups, without RTL, in a productive laboratory.

Previous work has shown improved linearity across a wide calibration range using a 6 mm draw-out lens instead of the standard 3 mm lens [4]. Although this application uses a lower calibration range, the linearity improvement is still valid. The signal/noise loss using the 6 mm lens, even at low levels, was minimal compared to the linearity gain. The 6 mm lens is also included in Agilent Kit part number G2860A.

Scan parameters are listed even though the calibration was done using SIM data. All runs were made in synchronous SIM/scan mode, acquiring both SIM and scan data with a single injection. A sampling rate of 1, combined with the lower noise characteristics of the 5975C, was used to optimize signal/noise. This sampling rate, with a 45 to 450 mass range, resulted in approximately 10 scans across the peaks. The full scan data could be used to identify total unknowns by library searching, if present in sufficient amount. If full scan data is not needed, SIM/scan can be turned off and only SIM data collected. This will provide approximately 2x the number of data points across a peak.

AutoSIM setup was used in combination with the quantitation database to pick ions, groups, and switching times. Details of AutoSIM can be found in reference 5. The SIM acquisition table from AutoSIM was used directly with only two modifications. Tebuthiuron (ion 156) and tricyclazole (ion 189) are known for poor peak shape. Their target and qualifier ions were manually added to the groups across which the peaks eluted. A target ion plus one qualifier ion were used for all internal standards (ISTDs) and surrogate standards (SSs). A target ion plus two qualifier ions were used for all other analytes, if present in sufficient abundance in the spectra. The 10 SIM data points acquired across an average peak were used for calibration.

A source temperature of 300 °C was used instead of the typical 230 °C to 250 °C range. This higher temperature has been used to minimize peak tail-

ing, and therefore increase sensitivity, for PAHs [6] and to improve performance for semivolatiles [2].

Calibration standards were prepared in dichloromethane only for the single-component analytes. Standards were not prepared for toxaphene or the Aroclors. Disulfoton sulfoxide and disulfoton sulfone were not included in the commercially available mixture. A separate set of calibration standards was prepared in ethyl acetate.

Results and Discussion

The system was calibrated at four levels, 0.1, 1.0, 10, and 100 ppb, with the standards in dichloromethane. Tebuthiuron, known to be problematic, was the only analyte that showed insufficient response at the lowest level. The SIM total ion chromatogram (TIC) for the 1.0 ppb level run in SIM/scan mode is shown in Figure 2. Each calibration level contained 108 compounds plus three ISTDs and four SSs at 50 ppb. Intermediate calibration levels are specified by some methods but were not needed here to demonstrate system performance.

The best overall performance was accomplished using the PTV parameters in Table 1. Successful PTV injections are a balance of injection speed, temperature, vent flow rate, and vent time.

Injection speeds of 150, 100, and 50 $\mu\text{L}/\text{min}$ were tried. Faster injection rates showed decreased abundance for most analytes, regardless of RT. Sample passes through the liner, before solvent evaporation, and is swept out the vent line.

The initial PTV temperature was tested at 10, 20, 30, and 40 °C. Higher temperatures showed loss of the early eluters, those with volatility closer to that of the solvent. Lower temperatures preserve early eluters but hinder solvent venting.

The vent flow was tested at 50, 100, 200, and 300 mL/min . Increasing either the flow rate or vent time can decrease recovery of the early eluters. Decreasing the flow rate or vent time can result in excess solvent on the column and therefore poor chromatography. The minimum vent time must be matched to the injection time. In this case the injection takes 0.5 min (25 μL at 50 $\mu\text{L}/\text{min}$), so a vent time of 0.6 min was used.

Ethyl acetate is used in some methods as a solvent for solid phase extractions. Calibrations with standards in ethyl acetate showed worse performance




Figure 2. SIM TIC for the 1.0 ppb level run in SIM/scan mode.

than standards in dichloromethane. Ethyl acetate does not wet the stationary phase evenly, resulting in misshapen peaks, as the PTV did not eliminate 100% of the solvent. Adjusting the PTV parameters to account for the higher boiling point of ethyl acetate resulted in measurable losses of the early eluters. As a general rule, the earliest eluter for which quantitative recovery is required should have an elution temperature at least 100 °C greater than the solvent's boiling point. Ethyl acetate can be used successfully, but the lowest calibration point may be higher for some analytes.

Linearity can be determined by the percent relative standard deviation (%RSD) of the relative response factor (RRF) for each compound across the calibration range. The %RSD and the RRFs calculations are done automatically by the GC/MSD ChemStation software and can be reported in Excel. There is no correct %RSD as it is method dependent. As an example, U.S. EPA Method 525 has a criterion of < 30%RSD, but only for a subset of the compound list. The %RSDs of the RRFs for selected compounds are shown in Table 2.

Table 2. Signal-to-Noise and Linearity for Selected Analytes

Compound	RT	Target Ion	S/N 100 ppt	%RSD
Dichlorvos	7.01	109	6.5	4
Mevinphos	8.90	127	7.1	17
Simazine	12.24	201	4.8	6
Atrazine	12.35	200	20	6
Pentachlorophenol	12.48	266	22	24
Chlorpyrifos	14.78	197	2.7	12
2,2',3',4,6'-pentachlorobiphenyl	15.55	326	12	9
Phenamiphos	16.30	303	3.2	25
p,p'-DDT	18.00	235	13	9

At first glance some of the %RSD values appear high, such as pentachlorophenol (PCP) and the organophosphorus pesticides (OPPs). PCP is a known difficult compound and is commonly analyzed at significantly higher levels as in Method 525. The OPPs are very active and system inertness is critical to their successful analysis. Given this and the wide calibration range, the data shown here are excellent. As an additional overall measure of system linearity, the average of all %RSDs was 12% for SIM data in this study. The phthalates, easily detected at low levels, were excluded from this overall number due to common laboratory contamination. The %RSDs of the SSs ranged from 2% to 4%, demonstrating good repeatability.

As a further measure of system inertness, the %RSD for p,p'-DDT is 9%. The breakdown products

in an active system are p,p'-DDD and p,p'-DDE. Their %RSDs were 6% and 4%, respectively, indicating minimal breakdown. A separate mixture of p,p'-DDT and endrin was also analyzed for breakdown, using the classical U.S. EPA criteria. The p,p'-DDT % breakdown was 1.2 and Endrin was 1.9, well below the required 15%.

The signal-to-noise values are also shown in Table 2. Peak-to-peak noise was used, as this is what the analyst sees and has to work with. Atrazine and PCP values are sufficiently high that they could be calibrated and measured at a lower concentration. Chlorpyrifos and phenamiphos have S/N values below 5 and are near the limit of reproducible integration and hence quantitation. Extracted ions for PCP and chlorpyrifos are shown in Figure 3. In all cases the analytes exhibited sufficient S/N for successful calibration at the 100 ppt level.




Figure 3. Extracted ions for PCP and chlorpyrifos.

As a trade-off to lower calibration levels and method detection limits, a laboratory could reduce sample preparation, shown in Table 3. The first column, "Traditional," assumes 1 liter of water is extracted, concentrated to 1 mL, and 1 uL is injected. Methods using this approach have a lowest calibration level of 100 ppb (0.1 ppm) in scan mode. As described in this application, the "7890A-5975C" column maintains the same sample preparation but increases the sensitivity by a factor of 1,000, to the ppt level. The "Fast Prep" column shows extracting only 10 mL and still lowering the method limits by 10x compared to Traditional. Extracting 10 mL of sample is significantly easier and faster than 1 liter. Better recoveries may also be realized by needing less concentration of the extract. The Quick Screen extraction is accomplished directly in a 2-mL vial (Agilent p/n 5182-3454) with an integral pointed bottom. The dichloromethane extract is withdrawn from the bottom of the vial by the autosampler syringe. Variations of these examples can be used to maximize sensitivity and minimize sample preparation time.

Conclusions

Traditional semivolatiles methods can be altered to achieve better detection limits. Large volume injection-PTV coupled with SIM allows calibration to the 100-ppt level. Linearity is excellent for the wide calibration range used, even for active analytes. Using RTL saves the analyst time by preserv-

ing SIM group switching times. The 7890A reduces cycle times by rapid oven cooling. Laboratories can choose to lower method calibration limits and/or save time through reduced sample preparation.

References

1. U.S. EPA Method 525.2 is available from different sources listed on this Web site: www.epa.gov/OGWDW/methods/where.html
2. M. Szelewski, "Drinking Water Semivolatiles Analysis Using the 6890N/5975B Inert GC/MSD," Agilent Technologies publication 5989-5421EN.
3. K. Weiner, N. Mata, and P. Wylie, "Retention Time Locking with the G1701BA MSD Productivity ChemStation," Agilent Technologies publication 5968-3433E.
4. M. Szelewski, B. Wilson, and P. Perkins, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with U.S. EPA Method 8270," Agilent Technologies publication 5988-3072EN.
5. H. Prest and D. Peterson, "New Approaches to the Development of GC/MS Selected Ion Monitoring Acquisition and Quantitation Methods," Agilent Technologies publication 5988-4188.
6. M. Szelewski, "Synchronous SIM/Scan Low-Level PAH Analysis Using the Agilent Technologies 6890/5975 Inert GC/MSD," Agilent Technologies publication 5989-4184EN.

Table 3. Sample Preparation and Calibration Limits

	Traditional	7890A-5975C	Fast Prep	Quick Screen
Sample concentration, ppb	0.1	0.0001	0.01	0.02
Lowest cal level, ppb	100	0.1	0.1	0.1
Injection volume, µL	1	25	25	25
Extract volume, mL	1	1	1	0.25
Sample size, mL	1000	1000	10	1.25

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
April 13, 2007
5989-6589EN



Agilent Technologies

Significant Cycle Time Reduction Using the Agilent 7890A/5975C GC/MSD for EPA Method 8270

Application Brief

Mike Szelewski

U.S. EPA Method 8270 for semivolatiles analysis is used to concurrently measure a mix of 70–100 acids, bases, and neutrals. Laboratories want to reduce the typical 25–60-minute cycle time for productivity increases. The Agilent 7890A/5975C GC/MSD system meets this demand using a smaller id column, faster cooling oven, and backflushing. Criteria for system performance check compounds (SPCCs) and continuing calibration compounds (CCCs) are met using a calibration range of 1–200 ppm.

The system was calibrated at 10 levels using the conditions in Table 1. The SPCCs and CCCs all meet 8270 criteria, the results shown in Table 2. The overall average %RSD for all 77 analytes was 11%.

Cycle time savings are shown in Table 3. Historically, a 30 m × 0.25 mm column is used in 6890 systems. The 20 m × 0.180 mm column used here cuts the run time by 8 min, a 5 ppm standard shown in Figure 1A.

Highlights

- Productivity increases > 55% with the Agilent 7890A/5975C GC/MSD system.
- The oven heats faster, cools down faster, and reduces cycle time.
- Backflushing reduces analysis time and increases column life while reducing maintenance time and frequency.




Figure 1. Time savings using backflush.



Agilent Technologies

Bake-out of matrix often takes longer than the run time for analytes of interest. A heavy hydrocarbon, typical of an 8270-type extract, is shown in Figure 1B, eluting in ~40 min. The elution time on a 30-m column is > 50 min. All of this material is usually eluted into the MSD.

A backflush of the heavy material from a sample spiked with standard is shown in Figure 1C. The 4-min backflush is accomplished by raising the pressure in the QuickSwap and lowering the inlet pressure. The matrix elutes into the inlet and is swept out the split vent line.

Figure 1D shows a blank solvent run after the backflush. The heavy hydrocarbon matrix is not on the column nor in the liner.

The Agilent 7890A has faster oven cool-down, from 320–40 °C. Additionally, the MSD can be interfaced in a new rear oven position, along with the inlet in the rear. An oven insert, the “pillow,” can occupy the front half of the oven. This allows even faster heating and cooling. The times are shown in Table 3.

Additional time savings are realized by using QuickSwap. Liner and column maintenance or changing can be done without venting the MSD.

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 7890A		
Inlet	EPC split/splitless		
Mode	Splitless, 0.5 µL injected		
Inlet temp	300 °C		
Pressure	25.0 psi		
Purge flow	30.0 mL/min		
Purge time	0.75 min		
Gas saver	Off		
Gas type	Helium		
Liner	Agilent Helix single taper liner with a narrow o.d. for both split and splitless, proprietary deactivation, Part # 5188-5397		
Oven	240V		
Oven ramp	°C/min	Next °C	Hold min
Initial		40	1.00
Ramp 1	25	320	4.80
Total run time	17.0 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies DB-5.625, Part # 121-5622		
Length	20.0 m		
Diameter	0.18 mm		
Film thickness	0.36 µm		
Mode	Constant flow = 1.1 mL/min		
Inlet	Front		
Outlet	QuickSwap, Agilent Part # G3185B		
QuickSwap pressure	5.0 psi during acquisition, 80.0 psi during backflush with inlet set to 1.0 psi during backflush		
MSD	Agilent Technologies 5975C, Performance Turbo		
Drawout lens	6 mm large aperture drawout lens, Part # G2589-20045		
Solvent delay	2.8 min		
EM voltage	Tune voltage		
Mass range	35–500 amu		
Sampling	1		
Quad temp	180 °C		
Source temp	300 °C		
Transfer line temp	250 °C		
Emission current	25 µamp		

Calibration Standards

Accustandard, New Haven, CT. Part # M-8270-IS-WL-0.25x to 10x

77 compounds at 10 concentration levels with 6 internal standards at 40 ppm

Table 2. SPCC and CCC, Criteria and Results

	8270 criteria	7890A-5975C with QuickSwap (range)
4 SPCCs minimum average RRF	0.050	0.110–0.405
13 CCCs %RSD	< 30%	2% –20%

Table 3. Cycle Time Savings Using the 7890A-5975C

	Typical 6890	7890A	Minutes Saved
Run time without matrix bake-out, includes equip	25	17	8
Run time with matrix bake-out 6890 or QuickSwap 7890A	50	21	29
Cool down time from 320 to 40	7	4.3	2.7
Cool down time from 320 to 40 with pillow	n/a	3.3	3.7
Total time savings using a 7890A-5975C with the 20-m column, QuickSwap for backflush, rear position for MSD and pillow	57	24.3	32.7

Significant cycle time savings can be realized, depending on sample complexity and column and instrument configuration. Analyzing dirty samples on a 30-m column can take 57 minutes or more with a 6890. Using an Agilent 7890A, QuickSwap, the 20-m column, and rear oven position, cycle time is < 25 minutes. This is a direct productivity increase of > 55%.

Mike Szelewski is an application chemist based at Agilent Technologies, Wilmington, Delaware, USA.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
January 10, 2007
5989-6026EN



Agilent Technologies



Drinking Water Semivolatiles Analysis using the 6890N/5975B inert GC/MSD

Application

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

The analysis of semivolatiles in drinking water presents challenges due to the required detection limits, desired calibration range, and analyte activity. In the United States (U.S.), method requirements are typically those found in USEPA 525.2 (525), but can vary widely outside the U.S. This application is based on 525 with differences described for laboratories that do not require 525. The 6890N/5975B inert GC/MSD system is designed to meet the criteria for semivolatiles analysis in drinking water through excellent sensitivity, minimal activity, and extended linearity.

Introduction

USEPA Method 525.2 for semivolatiles analysis is used to concurrently measure a mixture of acids, bases, neutrals, and pesticides in drinking water or source water [1]. Most laboratories analyze for >100 compounds with a chromatographic run time of 25 to 40 minutes. Sample extraction is accomplished using liquid-solid extraction (LSE) with C₁₈ disks or cartridges. A 1-μL hot splitless injection is specified with the MSD operating in full scan mode.

Sensitivity and linearity are two areas where laboratories are seeking improved performance. Sensitivity can be affected by sample preparation, extract volume injected, instrument tuning, signal processing, and overall system activity. Linearity can be affected by source design, tuning, activity, data acquisition mode, and system reproducibility.

This application will demonstrate the use of the 6890N/5975B inert for USEPA Method 525.2. Performance has been improved through the use of inert columns, high-temperature inert source, and manual tuning. Additional specific areas for improved performance will be discussed for laboratories that are not required to follow 525 mandates.

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized.

Pulsed splitless injection was used to minimize residence times of analytes in the liner, thereby reducing loss of active compounds. The column flow rate alone, without using a pulsed injection, would take too long to sweep the 700-μL liner volume.

The inlet liner, G1544-80700, has shown the best performance for active compounds at low levels. It does not contain glass wool, which would contribute to active compound degradation. This liner



Agilent Technologies

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890N			RTL	System retention time locked to phenanthrene-d10 at 11.400 min
Inlet	EPC split/splitless			MSD	Agilent Technologies 5975B inert
Mode	Pulsed splitless, 1.0 µL injected			Drawout lens	6 mm large-aperture drawout lens, part number G2589-20045
Inlet temperature	250 °C			Solvent delay	4.00 min
Pressure	11.56 psi			EM voltage	Run at Autotune voltage = 1294 V
Pulse pressure	40.0 psi			Low mass	45 amu
Pulse time	0.10 min			High mass	450 amu
Purge flow	30.0 mL/min			Threshold	25
Purge time	1.00 min			Sampling	2
Total flow	34.6 mL/min			Scans/second	3.54
Gas saver	Off			Quad temperature	180 °C
Gas type	Helium			Source temperature	300 °C
Inlet liner	Agilent direct connect, dual taper, 4 mm i.d., part number G1544-80700			Transfer line temperature	280 °C
Oven	240V			Emission current	Autotune @ 35 µamp
Oven ramp	°C/min	Next °C	Hold min	MSD-SIM	
Initial		40	1.00	AutoSIM was used to pick ions, groups, and switching times	
Ramp 1	50	110	0.00	Number of groups	26
Ramp 2	10	320	0.60	Compounds/group	Varied 1 to 22
Total run time	24.0 min			Ions/group	Varied 2 to 55
Equilibration time	0.5 min			Dwell times	Varied 5 to 10 ms
Oven max temperature	325 °C			Cycles/peak	Minimum 10
Column	Agilent Technologies HP 5 MSi, part number 19091S-433i			Calibration standards	
Length	30.0 m			Ultra Scientific, North Kingstown, RI. Part number DWK-5252.	
Diameter	0.25 mm			Four mixtures codiluted, resulting in 108 compounds at 10 concentration levels, spiked with 3 Internal Standards at 5 ppm and 4 Surrogate Standards at 5 ppm.	
Film thickness	0.25 µm				
Mode	Constant flow = 1.5 mL/min				
Inlet	Front				
Outlet	MSD				
Outlet pressure	Vacuum				

connects directly to the column and has a tapered top, minimizing contact with metal in the inlet. Other liners can be used; a detailed discussion of these can be found in Reference 2.

The 6890N 240V oven was used but a 120V oven can also achieve the ramp rates found in Table 1.

The HP-5MSi column is designed for inertness and is well suited to this method. This is the latest version of the most popular column in environmental laboratories, the HP-5MS. The column was run in constant flow mode at 1.5 mL/min to maintain peak shape and sensitivity.

The system was retention time locked to phenanthrene-d10 at 11.400 min. The fundamentals of retention time locking (RTL) for GC/MSD systems can be found in Reference 3. The primary benefit of RTL for the environmental laboratory is the ability to maintain retention times after clipping or changing the column. Quantitation database and integration events times do not have to be changed. For laboratories performing SIM analyses, switching group times remain constant. Additional RTL application notes detailing the numerous benefits of RTL are available at www.agilent.com/chem.

Previous work has shown improved linearity across a wide calibration range using a 6-mm drawout lens instead of the standard 3-mm lens [1]. Although 525 uses a lower calibration range, the linearity improvement is still valid. The signal/noise loss using the 6-mm lens, even at low levels, was minimal compared to the linearity gain. The 6-mm lens is also included in Agilent Kit part number G2860A.

EPA method 525 requires that the system meet DFTPP tune criteria, but in this case the 5975B inert was tuned using Autotune. A new entrance lens (EL) value was then manually input at half the tune value (16 versus 32). DFTPP was injected and tune criteria were checked. If the injection passed DFTPP criteria, the EL value was raised 4 volts and DFTPP was reinjected. This process continued until the highest EL value that allowed DFTPP to pass criteria was determined.

A sampling rate of 2, combined with the lower noise characteristics of the 5975B inert, was used to optimize signal/noise. This sampling rate resulted in 3.54 scans/sec, with a 45 to 450 scan range, typically yielding 10 data points across the peaks.

A previous publication [4] detailed steps to match sampling rates in tune with those used in data acquisition. This process is no longer necessary. The automatic tuning has been significantly improved in the 5975B inert. Valid tune parameters are stored for all data acquisition sampling rates. These parameters are automatically called and used based on the method sampling rate.

AutoSIM setup was used in combination with the quantitation database to pick ions, groups, and switching times. Details of AutoSIM can be found in Reference 5. The SIM acquisition table from AutoSIM was used directly with only two modifications. Tebuthiuron (ion 156) and tricyclazole (ion 189) are known for poor peak shape. Their ions were manually added to the groups across which the peaks eluted.

A source temperature of 300 °C was used instead of the typical 230 °C to 250 °C range. This higher temperature has been used to minimize peak tailing, and therefore increase sensitivity, for PAHs [6]. Lower source temperatures have historically been used to maintain performance of the active pesticides. At 300 °C, the inert source shows equivalent or better performance for all but 14 compounds, compared to 230 °C. Of the 14 compounds, 10 still had single-digit percent relative standard deviations (%RSDs). More importantly, the average %RSD for all 115 analytes was reduced almost 2× using a source temperature of 300 °C versus 230 °C.

Calibration standards in dichloromethane were prepared only for the single component analytes. Standards were not prepared for toxaphene or the Aroclors. Disulfoton sulfoxide and disulfoton sulfone were not included in the commercially available mixture.

Alternatives to EPA Method 525

There are many laboratories both within the U.S. and in other geographies that are not required to follow 525 mandates. Many of these laboratories use 525 as a framework or starting point for drinking water analyses. This section will discuss areas in 525 that can be modified for improved performance. None of these have been approved as alternatives to Method 525 by the USEPA.

LSE is required by 525 for sample preparation, with ethyl acetate and dichloromethane (DCM) as

the final extract solvents. An alternative is a liquid-liquid extraction (LLE) using only DCM. Specific analyte recoveries should be determined just as they are with LSE and 525. The initial sample and final extract volumes are sized to meet the laboratory's detection limits. Traditionally, a liter or more of water is extracted with 3×100 mL aliquots of DCM. The aliquots are combined and concentrated. Some laboratories use 40-mL screw-cap vials, extracting 30 mL of water with 3 mL of DCM, with extract concentration as needed. Other laboratories, for screening purposes, use a tapered bottom 2-mL sample vial. A 1.25-mL water sample is extracted with 0.25 mL of DCM. The DCM layer is injected directly from the bottom taper of the vial. LLE of small volumes of water increases laboratory productivity compared to LSE.

A 1- μ L hot splitless injection is specified by 525. A cool-on-column inlet is allowed, with the same 1- μ L injection volume. Lower detection limits can be achieved using a programmable temperature vaporizing (PTV) inlet and large-volume injection (LVI) inlet [7]. A single 25- μ L injection of a DCM extract can easily be made using the PTV in solvent evaporation mode. Additionally, thermally labile compounds are less likely to degrade. The PTV is held near the solvent's boiling point during injection. As the inlet is programmed, analytes are transferred onto the column at the lowest possible temperature. This can result in better performance for active compounds.

Full scan data acquisition is mandated by 525. As an alternative, selected ion monitoring (SIM) could be used. With a defined compound list, quantitation (target) ions and qualifier ions/ratios are known or can be easily determined. Using SIM typically results in a sensitivity increase of 10 to 100× compared to scan [7]. Using either PTV or SIM increases laboratory throughput by allowing a wider calibration range on the GC/MSD system. Sample and extract volumes need less manipulation and fewer reruns are required to have results fall within the calibration range. Using SIM and PTV together can lower the detection limit up to 2,500× compared to a 1- μ L injection in scan mode [7].

The 6890N/5975B inert GC/MSD can acquire both SIM and scan data in the same run [6]. This is an attractive alternative for laboratories that want a wider calibration range (SIM) but also want full scan spectra for confirmation. A SIM acquisition table is easily constructed using AutoSIM setup. A

check box is selected in data acquisition and both signals are collected. If SIM/scan is used, typically the scan sampling rate should be halved – in this case from 2 to 1.

Tuning to meet DFTPP criteria is required by 525. This enhances the response at lower m/z values but decreases the response at higher m/z values. With enhanced responses for higher m/z values as a result of Autotune, more unique ions can be used for identification. Most laboratories have found that DFTPP tuning also decreases the overall instrument sensitivity 3 to 6× compared to Autotune. To maintain maximum instrument sensitivity, Autotune should be used. Qualifier ion ratios are established for each system as a routine laboratory practice and will stay consistent using Autotune. Library matches against NIST are excellent using Autotune, as most NIST spectra were not obtained under DFTPP tune conditions.

Results

The 5975B inert passed DFTPP tune criteria for 525 with a 1- μ L splitless injection of 5 ppm. This was accomplished using the procedure discussed in the Instrument Operating Parameters section instead of using the DFTPP menu item. The sensitivity loss of 3 to 6× usually seen with DFTPP tuning was less than 2× with this manual procedure. Sensitivity loss is usually a result of DFTPP tuning with a low repeller in combination with the entrance lens offset (ELO) values. In the manual procedure, the repeller stays at its Autotune value, which is best above 20. The EL value is lowered only enough to allow passing.

The system was calibrated at seven levels, 0.1, 0.2, 0.5, 1, 2, 5, and 10 ppm in scan mode, with the 0.2 ppm level not required by 525. The total ion chromatogram (TIC) for the 0.5 ppm level in scan mode is shown in Figure 1. Each calibration level contained 108 compounds plus 3 internal standards (ISTDs) and 4 surrogate standards (SSs) at 5 ppm. Not all compounds showed a response at all levels as is stated in 525 and therefore expected. A listing of problem compounds and reasons can be found in Method 525.2, Section 13.2.

Full method-detection limits must be established in each laboratory using the sample preparation procedure as described in 525.2, Section 9.




Figure 1. TIC for 0.5 ppm 525 semivolatiles – scan 45 to 450 m/z for 115 compounds

For SIM acquisition, three additional calibration levels were run: 0.01, 0.02, and 0.05 ppm. The TIC for the 0.05 ppm level in SIM mode is shown in Figure 2.

USEPA Method 525 does not specify minimum RRFs for system performance check compounds (SPCCs). USEPA Method 8270 for semivolatiles in wastewater does have criteria for SPCCs and should not be confused with 525.

Linearity can be determined by the %RSD of the relative response factor (RRF) for each compound across the calibration range. The %RSD and the RRF calculations are done automatically by the GC/MSD Chemstation software in conjunction with Microsoft Excel. Not all compounds meet the 525 criteria of <30%, which is allowed, with the most active compounds showing the highest %RSD. However, as an overall measure of system linearity, the average of all %RSDs was 8% for scan data. The %RSDs are summarized in Table 2.

Linear regression is allowed by 525 as an alternative to mean RRF and %RSD. When linear regression is used, a continuing calibration check (CCC) must report values of $\pm 30\%$ of the true value for each compound. A CCC was run and all but one of the 108 compounds were within the criteria. USEPA method 525 allows up to 10% of the compounds to miss the CCC criteria on a single day.

The SIM data were reduced two ways, using a seven-level calibration or a 10-level calibration,

including three lower concentrations. For the seven-level SIM, the average %RSD of all 108 compounds was 6%. The ISTDs were 4% and SS ranged from 1 to 3%. For the 10-level SIM, the average %RSD for all compounds was 11%; ISTDs at 4% and SS ranged from 1 to 5%.

Table 2. Summary of Linearity for Scan and SIM Calibrations

	Avg %RSD 108 Analytes	%RSD Range 3 ISTDs	%RSD Range 4 SS
Scan 7-level cal	8	6 to 8	1 to 3
SIM 7-level cal	6	4	1 to 3
SIM 10-level cal	11	4	1 to 5

Conclusions

The 6890N/5975B inert meets USEPA Method 525.2 criteria. Analysis of 108 analytes and 7 ISTDs/SSs is accomplished in 24 minutes. The 525 DFTPP tune criteria are routinely achieved, and sensitivity is increased through manual tuning. Linearity is met over the method calibration range in scan mode; CCC requirements of $\pm 30\%$ are also attained. Laboratories that are not required to follow 525 mandates can achieve productivity gains. Autotune can be used for better sensitivity compared to DFTPP tuning. PTV can reduce sample preparation and reduce detection limits. SIM further lowers detection limits, extends the calibration range, and improves




Figure 2. TIC for 0.05 ppm 525 semivolatiles — SIM 115 compounds in 26 groups

linearity. SIM/scan mode has all of the benefits of SIM with full scan spectra available for analyte confirmation.

References

1. USEPA Method 525.2 is available from different sources listed on this Web site: www.epa.gov/OGWDW/methods/where.html.
2. M. Szelewski, B. Wilson, and P. Perkins, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270," Agilent Technologies, publication 5988-3072EN, www.agilent.com/chem.
3. K. Weiner, N. Mata, and P. Wylie, "Retention Time Locking with the G1701BA MSD Productivity ChemStation," Agilent Technologies, publication 5968-3433E, www.agilent.com/chem.
4. M. Szelewski, "Fast USEPA 8270 Semivolatiles Analysis Using the 6890/5973 Inert GC/MSD with Performance Electronics," Agilent Technologies, publication 5989-1510EN, www.agilent.com/chem.
5. H. Prest and D. Peterson, "New Approaches to the Development of GC/MS Selected Ion Monitoring Acquisition and Quantitation Methods," Agilent Technologies, publication 5988-4188, www.agilent.com/chem.
6. M. Szelewski, "Synchronous SIM/Scan Low-Level PAH Analysis Using the Agilent Technologies 6890/5975 Inert GC/MSD," Agilent Technologies, publication 5989-4184EN, www.agilent.com/chem.
7. C.K. Meng, "Identification and Quantitation of Pesticides in the Parts-per-Trillion Range Using Retention Time Locking and GC/MS," Agilent Technologies, publication 5988-4392EN, www.agilent.com/chem.

For More Information


For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
July 31, 2006
5989-5421EN



Synchronous SIM/Scan Low-Level PAH Analysis Using the Agilent Technologies 6890/5975 inert GC/MSD

Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of Polynuclear Aromatic Hydrocarbons (PAHs) presents challenges due to the tendency of the PAHs to adsorb on surfaces in the chromatographic system. Selected Ion Monitoring (SIM) analysis is needed for low-level analysis, while scan data are desired for confirmation. The 6890/5975 inert GC/MSD system is designed for improved PAH analysis using synchronous SIM/scan while maintaining linearity across a wide calibration range.

Introduction

PAHs are produced during combustion of organic material and are suspected carcinogens. The high amounts and widespread occurrence of these compounds in our environment requires reliable, sensitive, and very robust analytical methods.

PAHs tend to be adsorbed on any active or cold site in a GC/MSD system, such as inlets and ion sources. The 6890/5975 inert includes the inert source with high temperature filaments described previously [1]. Using the proper inlet liner also improves chromatographic peak shape and sensitivity.

Many laboratories calibrate for PAHs from 0.1 ppm to 10 ppm using SIM for low-level work. Historically, SIM has been necessary because of instrument sensitivity and loss of PAHs at the lower concentration levels. Full scan data is preferred for further confirmation of the compounds. The 5975 inert can acquire both SIM and scan data in a single run.

This application note will show the performance of the 6890/5975 inert for PAHs using a calibration range of 0.01 ppm–10.0 ppm in synchronous SIM/scan mode with linearity equal to that of many SIM only methods.

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized.



Agilent Technologies

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet	EPC Split/Splitless		
Mode	Pulsed Splitless, 1 µL injected		
Inlet temp	300 °C		
Pressure	13.00 psi		
Pulse pressure	40.0 psi		
Pulse time	0.20 min		
Purge flow	30.0 mL/min		
Purge time	0.75 min		
Total flow	34.6 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet Liner	Description	Agilent part number	
	Direct connect, dual-taper, 4-mm id	G1544-80700	
	or Splitless liner, single-taper, 4-mm id	5181-3316	
Oven 240 V			
Oven ramp	°C/min	Next °C	Hold min
Initial		55	1.00
Ramp 1	25	320	3.00
Total run time	14.60 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS	19091S-433	
Length	30.0 m		
Diameter	250 µm		
Film thickness	0.25 µm		
Mode	Constant Flow = 1.5 mL/min		
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
RTL	System Retention Time Locked to Triphenyl phosphate at 10.530 min		
MSD	Agilent Technologies 5975		
Drawout lens	6-mm ultra-large aperture	G2589-20045	
Solvent delay	4.00 min		
EM voltage	Run at Autotune voltage = 1294 V		
Low mass scan	45 amu		
High mass scan	450 amu		
SIM	12 groups, 3–6 ions/group, 10 ms dwell/ion		
Threshold	0		
Sampling	1		
Cycles/s	5.55 each, SIM and scan		
Quad temp	180 °C		
Source temp	300 °C		
Transfer line temp	280 °C		
Emission current	Autotune value = 34.6 µamp		

Calibration Standards

Calibration standards were diluted in dichloromethane from a stock mix of 16 PAHs. The 10 levels made were 10, 5, 2, 1, 0.5, 0.2, 0.1, 0.05, 0.02 and 0.01 ppm. The perylene-d12 internal standard and the three surrogate standards, 1,3-dimethyl-2-nitrobenzene, pyrene-d10 and triphenylphosphate, were added to each calibration level at 1.0 ppm.

The 6890 inlet temperature was set to 300 °C, instead of the typical 250 °C, to minimize compounds adsorbing on the liner surface. Pulsed injection was used to facilitate quantitative transfer of the heavier PAHs onto the column, minimizing inlet discrimination. Pulsed injection parameters are easily set in the ChemStation software and are automatically controlled by the EPC (Electronic Pneumatic Control) module.

The Direct Connect inlet liner allows for complete transfer of analytes onto the column. The column inlet end attaches to the liner and minimizes analyte exposure to the stainless steel annular volume in the inlet. The splitless liner, 5181-3316, yields better peak shapes for early eluters at the expense of lower amounts of analytes transferred to the column. Neither of these liners is well suited for split injections. Higher concentration samples requiring split injection would need a cyclosplitter-type liner, also suitable for splitless.

The 6890N 240V oven was necessary for the 25 °C/min ramp used up to the final temperature of 320 °C. A 120 V oven will achieve 20 °C/min at these higher temperatures and could be used, resulting in slightly longer run times.

The HP-5MS column is the most widely used column for environmental analysis. It has excellent lifetime and stability at elevated temperatures.

The system was Retention Time Locked to Triphenyl phosphate at 10.530 min. See the fundamentals of Retention Time Locking (RTL) for GC/MSD systems [2]. The primary benefit of RTL for the environmental laboratory is the ability to maintain retention times after clipping or changing the column. Quant database and integration events times do not have to be changed. For laboratories

performing PAH SIM analyses, reproducible retention times are a must so SIM group times remain constant. Additional RTL application notes are available at www.agilent.com/chem, detailing the numerous benefits of RTL.

The 5975 inert was tuned using Autotune. The automatic DF-TPP target tune, as required by some government methods, can also be used. The ultra-large aperture drawout lens was used to maintain linearity across the wide calibration range of 0.01–10.0 ppm. Source temperature was set to 300 °C, which is now possible with the high temperature filaments. This higher source temperature in combination with the new source material produces better peak shapes for the PAHs.

Data were collected using the synchronous SIM/scan mode available with the 5975 inert. A quant database is first setup using full scan data. SIM ions and groups are then determined automatically using Generate AutoSIM Method. A checkbox in data acquisition is used to acquire SIM and scan data in the same run. For details of synchronous SIM/scan, see reference 3.

Results

The system was calibrated at 10 levels: 0.01, 0.02, 0.05, 0.1, 0.2, 0.5, 1.0, 2.0, 5.0, and 10.0 ppm using the SIM data from SIM/scan acquisition. The calibration table allows the user to choose either the SIM or scan data. The TIC (Total Ion Chromatogram) for the 0.2 ppm level is shown in Figure 1, both SIM and scan traces. Each calibration level contained 16 PAHs, perylene-d12 (ISTD) and the three surrogate standards, 1,3-dimethyl-2-nitrobenzene, pyrene-d10, and triphenyl phosphate.




Figure 1. Sixteen PAHs at 0.2 ppm each with surrogates and ISTD at 1.0 ppm each, using synchronous SIM/scan mode.

The RRF (relative response factor) was calculated automatically for each compound at each level by the GC/MSD ChemStation software. Linearity was determined by calculating the %RSD (percent relative standard deviation) of the RRFs across the calibration range for each compound. This is also done automatically by the software in conjunction with Excel.

Linearity is excellent with the average of all %RSDs = 6 %. This compares favorably with other methods that are SIM only or those that only calibrate down to 0.1 ppm.

There were 5.55 SIM cycles/s and 5.55 scans/s acquired throughout the run. This yields 11 SIM data points and 11 scan data points across a typical peak.

Full scan data are also available for further PAH confirmation using library searching. Figure 2 shows a full scan spectrum from benzo[ghi]perylene, together with its library match. Unknown peaks for which SIM data were not acquired can also be library searched. A more reliable, faster method for identifying all the peaks is the use of Deconvolution Reporting Software [4].




Figure 2. Spectrum from scan at 13.662 min with NIST05 Library match.

Conclusions

The 6890/5975 inert shows much improved response and peak shape for PAHs due to the inert source material and higher allowable source temperature. This improved response gives better linearity across the calibration range. Analysis of PAHs can be accomplished using synchronous SIM/scan data acquisition over a calibration range of 0.01 ppm to 10 ppm, while maintaining performance similar to SIM methods. Sensitivity of SIM is achieved while providing full scan data for confirmation of PAHs and identification of unknowns in a single run.

References

1. Mike Szelewski, "Full Scan Low Level Polynuclear Aromatic Hydrocarbon Analysis using the Agilent Technologies 6890/5973 inert Gas Chromatograph/Mass Selective Detector", Agilent Technologies, publication 5989-0264EN, www.agilent.com/chem.
2. K. Weiner, N. Mata and P. Wylie, "Retention Time Locking with the G1701BA MSD Productivity ChemStation", Agilent Technologies, publication 5968-3433E, www.agilent.com/chem.
3. Chin-Kai Meng, "Improving Productivity with Synchronous SIM/Scan", Agilent Technologies, publication 5989-3108EN, www.agilent.com/chem.
4. Philip L. Wylie, Michael J. Szelewski, Chin-Kai Meng, and Christopher P. Sandy, "Comprehensive Pesticide Screening by GC/MSD using Deconvolution Reporting Software", Agilent Technologies publication 5989-1157EN, www.agilent.com/chem.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
November 9, 2005
5989-4184EN



Agilent Technologies



Applying the 5975 inert MSD to the Higher Molecular Weight Polybrominated Diphenyl Ethers (PBDEs)

Application

Environmental, Component Testing

Author

Harry F. Prest
Agilent Technologies, Inc.
Santa Clara, CA
USA

This note presents the full scan spectra obtained for the PBDEs over the extended mass range of the 5975 inert MSD. The polymeric sample preparation and extraction protocols are cited elsewhere and supply two approaches to PBDE determinations [1].

Abstract

A previous application note presented results for analysis of the polybrominated diphenyl ethers (PBDEs) in polymers using the 5973N inert MSD [1]. Mass spectra were presented and interpreted for all of the important PBDEs. The new 5975 inert MSD provides many new features and improvements with expanded mass range to 1050 u being but one. This note presents the full spectra of the octa-, nona and decabrominated biphenyls ethers including ions that appear beyond the mass range of the previous 5973 MSD platform.

Introduction

PBDEs have become the “new PCBs” due to their widespread detection throughout the ecosystem. They have some structural and consequently mass spectral features in common with the polychlorinated biphenyls (PCBs) as well. The series of fragments formed by loss of chlorines ($M-nCl_2$) generates a number of intense ions useful in their determination. The PCBs also show relatively intense molecular ion clusters that assist in distinguishing the congeners. Similar attributes are expected and hoped for the PBDEs which show much more analytical difficulty than the PCBs.

Experimental

PBDE standards were acquired from Cambridge Isotope Laboratories (Andover, MA) and AccuStandard (New Haven, CT).

Instrumental Configuration and Conditions

The 6890 GC configuration and conditions are given in the previous application note [1]. The 5975 inert MSD system was operated in scan mode for acquisition of the PBDE spectra. The MSD scan operating parameters are cited in Table 1.

Table 1. 5975 inert MSD Configuration and Parameters

Mass spectrometer parameters	
Ionization mode	Electron impact
Ionization energy	70 eV
Tune parameters	Autotune
Electron multiplier voltage	Autotune + 400V
Scan mode	200–1000 u
Quadrupole temperature	150 °C
Inert source temperature	300 °C

Full conditions and parameters, as appropriate to the polymer analysis cited in reference 1, are available in the eMethod for this analysis (www.agilent.com/chem/emethods).



Agilent Technologies

Results

EI Spectra of the Higher Molecular Weight PBDEs

Figures 1, 2, and 3 present the full-scan spectra of an octa-, nona- and the decabromodiphenyl ether. Note that most intense ions in all cases are the $[M-Br_2]^+$ and the corresponding to $[M-Br_2]^{+2}$ ions. The relative abundance of the molecular ion clusters $[M]^+$ are under 30%. Figure 4 compares the

theoretical isotopic pattern to that experimentally obtained by the 5975 inert MSD. Agreement is good in both the abundance of the isotopes and the mass accuracy using the standard system Autotune. Mass accuracy agrees to within 0.2 m/z of the theoretical and experimental values. Table 2 presents the important ions for the PBDEs greater than the dibromode. These ions are those most important to characterizing the technical mixtures used as additives to polymers.




Figure 1. Electron impact ionization spectrum of an octabromodiphenyl ether (PBDE-203) from 200 to 810 m/z .




Figure 2. Electron impact ionization spectrum of a nonabromodiphenyl ether (PBDE-208) from 200 to 890 m/z .




Figure 3. Electron impact ionization spectrum of the decabromodiphenyl ether (PBDE-209) from 200 to 1000 m/z .




Figure 4. Experimental spectrum of the decabromodiphenyl ether (PBDE-209) molecular ion cluster $[M]^+$ versus theory.

Table 2. Important Ions for the PB_nDEs ($n > 2$)

PBDE bromination	$[M]^+$	$[M-Br_2]^+$	$[M-Br_2]^{+2}$
3	405.8	246.0	123.0
4	485.7	325.9	162.9
5	563.6	403.8	201.9
6	643.5	483.7	241.9
7	721.5	561.6	(280.8 **)
8	801.4	641.5	320.8
9	879.3	719.4	359.7
10	959.2	799.3	399.7

**The 280.8 and 281.8 m/z ions can be compromised by column bleed interferences so these have not been used in acquisition although they provide a useful diagnostic for column degradation.

The user should note the ion source and quadrupole temperature settings in Table 1. Figure 5 presents SIM acquisitions of several higher molecular weight PBDEs at source temperatures of 300 °C and 230 °C. Notice the signal height roughly doubles on average for the PBDEs at the higher ion source temperature. The insert in the figure shows the improvement in the peak shape for the hexabrominated diphenyl ether. This peak sharpening accounts for the increase in signal height. Since these compounds elute at higher temperatures

among other high boiling components that belong to the matrix, heating the quadrupole is important for robust and low maintenance operation in samples.




Figure 5. Overlaid RIC SIM acquisitions of five PBDEs at ion source temperatures of 230 °C and 300 °C. Insert is expanded view of hexa-BDE overlays near baseline.

Conclusions

The new 5975 inert MSD has an expanded set of features including mass range. High mass accuracy under standard autotuning is obtained even at the high masses typical of the brominated diphenyl ethers. As users survey higher mass compounds, the heated quadrupole and high temperature capabilities of the 5975 inert MSD will become even more important to rugged and robust analyses in complicated samples.

More details on the other relevant instrumental parameters are available in the eMethod (www.agilent.com/chem/emethods).

Reference

1. C. Tu, and H. Prest, Determination of polybrominated diphenyl ethers in polymeric materials using the 6890 GC/5973N Inert MSD

with electron impact ionization. Agilent Technologies, publication 5989-2850EN, www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
June 13, 2005
5989-3142EN



Agilent Technologies



Fast USEPA 8270 Semivolatiles Analysis Using the 6890N/5975 inert GC/MSD

Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808

Abstract

The analysis of semivolatiles using EPA Method 8270 presents challenges due to the simultaneous measurement of acids, bases, and neutrals over a wide concentration range. Due to productivity demands, laboratories want to run faster while maintaining linearity and sensitivity for even the most active compounds. The 6890N/5975 inert GC/MSD system is designed to meet the criteria for fast analysis, while minimizing activity and maintaining linearity.

Introduction

USEPA Method 8270 for semivolatiles analysis is used to concurrently measure a mix of acids, bases and neutrals. Most laboratories analyze for 70–100 compounds with a chromatographic run time of 25–40 minutes. Laboratories want to reduce this run time for productivity increases. The calibration

range required for the analysis varies dependent on a particular laboratory's statement of work. Historically, a range of 20–160 ppm (parts-per-million) has been used. With the increased sensitivity of newer GC/MS systems, laboratories are moving toward lower minimum detection limits (MDLs) and pushing the calibration range down to 1 ppm.

The 6890N/5975 inert GC/MSD (gas chromatograph/mass selective detector) system was designed to meet the demand for faster runs and lower MDLs. Faster scan rates without loss of signal are now possible. This allows the use of smaller id columns, such as 0.18 mm, resulting in shorter runs, while maintaining sufficient data points across narrower chromatographic peaks.

The inert source allows for less material injected onto the column while maintaining mass spectrometer performance. Injection volume can therefore be matched to the 0.18-mm column. Performance comparisons using the inert source were previously published [1, 2, and 3].

This application note will demonstrate the use of the 6890N/5975 inert for USEPA Method 8270. Smaller id columns with faster scan rates yield run times of 15 minutes while meeting 8270 method criteria.



Agilent Technologies

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized.

Pulsed splitless injection was used to minimize residence times of analytes in the liner, thereby reducing loss of active compounds. The column flow rate alone, without using a pulsed injection, would take too long to sweep the 900- μ L liner volume.

The inlet liner, Agilent p/n G1544-80700, has shown the best performance for active compounds at low levels. It does not contain glass wool, which would contribute to active compound degradation. Other liners can be used and a detailed discussion of these can be found in Reference 1.

The 6890N 240 V oven was necessary for the 25 °C/min ramp used up to the final temperature of 320 °C/min. A 120 V oven will achieve 20 °C/min at these higher temperatures and could be used resulting in slightly longer run times.

The DB-5.625 column was recently introduced in the dimensions listed. A 0.5- μ L injection volume is well suited to this column. The excellent resolution from this column allows a higher than normal initial temperature (55 °C versus 40 °C). This higher temperature shortens cool-down time by more than 5 minutes, resulting in productivity increases for the laboratory. Benzo[b]fluoranthene and benzo[k]fluoranthene met 8270 resolution requirements at the 80-ppm calibration level and lower, using the operating parameters in Table 1.

The system was Retention Time Locked to Phenanthrene-d10 at 8.700 minutes. The fundamentals of Retention Time Locking (RTL) for GC/MSD

systems can be found in Reference 4. The primary benefit of RTL for the environmental laboratory is the ability to maintain retention times after clipping or changing the column. Quantitative database and integration events times do not have to be changed. For laboratories performing SIM analyses, switching group times remain constant. Additional RTL application notes detailing the numerous benefits of RTL are available at www.agilent.com/chem.

Previous work [1] showed improved linearity across a wide calibration range using a 6-mm drawout lens instead of the standard 3-mm lens. Although not shown here, that comparison was repeated on this 5975 inert system and is still valid. The 6-mm lens is also included in Agilent Kit p/n G2860A.

The 5975 inert was tuned using the automatic DFTPP target tune. A previous publication [3] detailed steps to match sampling rates to those used in data acquisition. This process is no longer necessary. The automatic tuning was significantly improved in the 5975 inert. Valid tune parameters are stored for all data acquisition sampling rates. These parameters are automatically called and used based on the method sampling rate.

Previous work showed improved linearity across a wide calibration range using a 25- μ amp emission current, instead of the default 35 μ amp. The emission current can be set by the user in the Tune Wizard. A mass 50 target = 0.7% was also set in the Tune Wizard.

The sampling rate was changed from the default of 2 to 1, while preserving sufficient sensitivity. The resultant 5.92 scans/s typically yield 10 data points across the peaks.

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890N		
Inlet	EPC Split/Splitless		
Mode	Pulsed splitless, 0.5- μ L injected		
Inlet temp	250 °C		
Pressure	21.29 psi		
Pulse pressure	40.0 psi		
Pulse time	0.20 min		
Purge flow	30.0 mL/min		
Purge time	0.75 min		
Total flow	34.0 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet liner	Agilent direct connect, dual taper, 4-mm id, p/n G1544-80700		
Oven	240 V		
Oven ramp	°C/min	Next °C	Hold min
Initial		55	1.00
Ramp 1	25	320	3.80
Total run time	15.4 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies DB-5.625, p/n 121-5622		
Length	20.0 m		
Diameter	0.18 mm		
Film thickness	0.36 μ m		
Mode	Constant Flow = 1.0 mL/min		
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
RTL	System Retention Time Locked to Phenanthrene-d10 at 8.700 min		
MSD	Agilent Technologies 5975 inert		
Drawout lens	6-mm Large Aperture Drawout lens p/n G2589-20045		
Solvent delay	1.90 min		
EM voltage	Run at DFTPP tune voltage - 153 V = 1282 V		
Low mass	35 amu		
High mass	500 amu		
Threshold	0		
Sampling	1		
Scans/s	5.92		
Quad temp	180 °C		
Source temp	230 °C		
Transfer line temp	280 °C		
Emission current	DFTPP tune @ 25 μ amp		
Calibration standards	Accustandard, New Haven, CT. p/n M-8270-IS-WL 0.25X to 10X, 77 compounds at 10 concentration levels with 6 Internal Standards at 40 ppm		

Results

The 5975 inert passed DFTPP tune criteria for Method 8270 at both 50 ppm and 5 ppm.

The system was calibrated at 10 levels: 1, 2, 5, 10, 20, 50, 80, 120, 160, and 200 ppm. The TIC (total ion chromatogram) for the 10-ppm level is shown in Figure 1. Each calibration level contained 77 compounds together with six ISTDs (internal standards) at 40 ppm.




Figure 1. TIC for 8270 semivolatiles at 10 ppm.

The RRF (relative response factor) was calculated automatically for each compound by the GC/MSD ChemStation software. Linearity was determined by calculating the %RSD (percent relative standard deviation) of the RRFs across the calibration range for each compound. This is also done automatically by the software in conjunction with Excel.

USEPA Method 8270D specifies criteria for suitable RRFs and %RSD. Minimum system performance is determined by four active compounds, the SPCCs (system performance check compounds), and is measured by the average RRF.

Table 2 lists the Method 8270D SPCC criteria, and performance of the 5975 inert. The 5975 inert data easily exceeds 8270D criteria and are very good considering the low end of the calibration range. The average RRF of 0.156 for 2,4-Dinitrophenol is difficult to achieve in other systems. This performance margin allows more samples to run before system maintenance is necessary.

Table 2. SPCCs, Comparison of Average RRF

	8270 D Criteria	1-200 ppm 5975 inert
N-Nitroso-di-n-propylamine	0.050	1.270
Hexachlorocyclopentadiene	0.050	0.243
2,4-Dinitrophenol	0.050	0.156
4-Nitrophenol	0.050	0.172

Linearity is shown in Table 3. Method 8270D specifies that this group of Calibration Check Compounds (CCCs) meet a 30% RSD criteria. The %RSD is calculated across the RRFs determined at each calibration level. All CCCs pass criteria using the full calibration range of 1–200 ppm. Pentachlorophenol is a very difficult compound on which to pass criteria. The average of all 77 compound %RSDs is 7%, significantly better than the method criteria of 15%.

Table 3. CCC %RSD of RRFs from 1–200 ppm

	%RSD
Phenol	6
1,4-Dichlorobenzene	3
2-Nitrophenol	5
2,4-Dichlorophenol	8
Hexachlorobutadiene	3
4-Chloro-3-methylphenol	9
2,4,6-Trichlorophenol	16
Acenaphthylene	6
Diphenylamine	5
Pentachlorophenol	25
Fluoranthene	5
Benzo[a]pyrene	3

The excellent system linearity shown here is due to many factors including tuning, the large aperture drawout, and the new electronics. The new electronics allow using a scan rate of 2¹, while maximizing sensitivity. This improved signal/noise together with more data points across a peak yields easier and more reproducible peak integration.

Conclusions

The 6890N/5975 inert meets USEPA Method 8270D criteria. Faster scan rates allow using 0.18-mm id columns for faster runs and shorter cool-down times. Analysis of 77 analytes and six ISTDs can be accomplished in 15 minutes. USEPA Method 8270D tune criteria are routinely achieved. SPCC performance and CCC linearity can be met over a wider calibration range than that historically used. Productivity increases are possible through faster runs, faster cool-down, easier peak integration, and use of a wide calibration range.

References

1. M. Szelewski, B. Wilson, and P. Perkins, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270", Agilent Technologies, publication 5988-3072EN, www.agilent.com/chem.
2. M. Szelewski, "Fast Semivolatiles Analysis using the Agilent Technologies 6890/5973 inert GC/MSD", Agilent Technologies, publication 5989-0207EN, www.agilent.com/chem.
3. M. Szelewski, "Fast USEPA 8270 Semivolatiles Analysis using the 6890/5973 inert GC/MSD with Performance Electronics ", Agilent Technologies, publication 5989-1510EN, www.agilent.com/chem.
4. K. Weiner, N. Mata and P. Wylie, "Retention Time Locking with the G1701BA MSD Productivity ChemStation" Agilent Technologies, publication 5968-3433E, www.agilent.com/chem.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
April 27, 2005
5989-2981EN



Agilent Technologies



Determination of Polybrominated Diphenyl Ethers in Polymeric Materials Using the 6890 GC/5973N inert MSD with Electron Impact Ionization

Application

Environmental, Component Testing

Authors

Chuanhong Tu
Agilent Technologies, PuDong
Shanghai CHINA

Harry F. Prest
Agilent Technologies, Inc.
Santa Clara, CA
USA

Abstract

Due to their ubiquitous appearance in the ecosphere, various polybrominated diphenyl ether formulations have been banned. A major application of PBDEs is to impart fire retardancy to plastics used in electronics and electrical applications. This application note details an approach to determining the PBDEs present in the technical formulations in polymers. The instrumental analysis uses GC/MS with selected-ion monitoring (SIM) to determine tri-BDEs through the decaBDE in 15 minutes. Full scan spectra are presented for the PBDEs with interpretation and to provide an explanation of the choices in SIM ions. To insure correct identification of the PBDE isomers and allow rapid and convenient implementation in the laboratory, Retention Time Locking is applied to an internal standard. A sample preparation scheme referenced in this document provides two flexible and simple approaches to processing polymeric materials for this instrumental technique. PentaBDE, OctaBDE and DecaBDE technical formulations are characterized under the method and results for a typical high-impact polystyrene sample are also presented.

Introduction

Polybrominated diphenyl ethers (PBDEs) are a major issue in discussions of persistent organic contaminants. The detection of PBDEs in essentially all compartments of the ecosystem, including human serum and breast milk, has resulted in a ban of the manufacture and use of certain PBDE formulations by the European Union (EU). Some companies have made it a policy not to allow these compounds in their components and have insisted their suppliers comply. Because the PBDEs are added at percent concentrations (as w/w), the usage of these formulations has been prodigious. Global consumption in 2001 was estimated at 7500, 3790, 56100 metric tons, for the PentaBDE, OctaBDE and DecaBDE technical formulations, respectively.

PBDE analysis even at these relatively high concentrations is challenging in several respects. The PBDEs are a complicated class of compounds and their utility in suppressing combustion also makes them relatively fragile and subject to degradation in GC analysis. This was demonstrated by using shorter GC columns to improve PBDE responses, the most significant improvement being for the deca-BDE (BDE 209) [1]. The loss in congener resolution is less important in this application because the technical mixtures most frequently applied in polymers predominantly consist of isomers extending from the tri-BDEs to the deca-BDE and far less than the 209 possible congeners. Distinguishing congeners on the basis of their electron impact (EI) mass spectrum may be possible since there appears to be some differences in their spectra, however the most reliable index remains retention time (RT). For this reason, compound



Agilent Technologies

Retention Time Locking (RTL) is used to simplify identification and reproduction of the method in the user's laboratory.

Another complication is in sample preparation. There are several methods for extracting PBDEs from polymers each with advantages and disadvantages [2]. Of the many methods, the two approaches applied in processing samples for this application note are relatively inexpensive, simple, universal in application and in their acceptance, and allow for high sample throughput with minimal polymeric interferences. They are polymer dissolution and soxhlet extraction.

Experimental

Polymer samples were obtained from Agilent customers in the electrical and electronic component industries. Specific details of the polymer dissolution and soxhlet extraction methods are presented elsewhere [3]. In summary, the methods extract PBDEs from the sample via solvent, a dilution is made into toluene and PCB 209 is added to follow the dilution factor. Prior to injection, PCB 207 is added as an internal (injection) standard. Standards were made taking into account the potential percent concentration range of the PBDEs in polymeric samples and dilution factors used in the method.

PBDE standards were acquired from Cambridge Isotope Laboratories (Andover, MA) and AccuStandard (New Haven, CT). PCBs 209 and 207 were acquired from AccuStandard (New Haven, CT). Solutions were made in toluene of Burdick & Jackson solvent (VWR Scientific, San Francisco, CA).

Instrumental Configuration and Conditions

The 6890 GC and 5793N-inert MSD (mass selective detector) system configuration and conditions are given in Table 1. The GC is operated under constant flow conditions developed by applying RTL to lock the PCB 209 internal standard RT at 9.350 minutes. The 5793N inert MSD was equipped with the new Performance Electronics upgrade and allowed a single SIM group containing 24 ions to be used. The SIM ions are listed in Table 1 and were acquired with a dwell of 10-ms. This single SIM group method can be used to develop a preliminary method that can be further refined into multiple SIM groups by applying the AUTOSIM utility if the user wishes [4]. This is recommended for 5793-MSDs using standard electronics and targeting only congeners known to predominate in the particular technical mixture.

Table 1. GC and MSD Configuration and Parameters

Injection parameters

Injection mode	Pulsed splitless		
Injection volume	1 μ L		
Injection port temperature	320 °C		
Pulse pressure and time	15.8 psi	1.80 min	
Purge flow and time	50.0 mL/min	2.00 min	
Gas saver flow and time	20.0 mL/min	3.00 min	

DB-5ms Column and oven parameters

GC column	DB-5ms (15 m $\times$ 0.25 mm id, 0.1 μ m film) (p/n: 122-5511)		
Flow and mode	1.8 mL/min	Constant flow	
RTL parameters	9.350 min	RTL compound PCB 209	
Detector and outlet pressure	MSD	Vacuum	
Oven temperature	90 °C	1.00 min	
program	20 °C/min	340 °C	2.00 min
Oven equilibrium time	1.0 min		
Total program time	15.5 min		
MSD transfer line temp	320 °C		

Mass spectrometer parameters

Tune parameters	Autotune		
Electron multiplier voltage	Autotune + 400V		
Solvent delay	6.5 min		
Quadrupole temperature	150 °C		
Inert source temperature	300 °C		

Mass spectrometer SIM ions for single group

405.8	246.0	123.0
485.7	325.9	162.9
563.6	403.8	201.9
643.5	483.7	241.9
721.5	561.6	320.8
799.4	641.5	360.7
719.4	461.7	399.7
463.7	497.7	499.7

*Optional addition of m/z 280.8

Miscellaneous parts

Septa	5182-0739	BTO septa (400 °C)
Liner	5181-3315	Deactivated 4-mm id double taper
GC column ferrule	5181-3323	250 μ m Vespel/Graphite
MSD interface ferrule	5062-3508	0.4-mm id preconditioned vespel/graphite

Results

Chromatography

After evaluating a series of columns the DB-5ms phase seems the best choice overall, which is consistent with the literature [1]. The literature shows that the shorter columns and thinner films are of benefit to improving the PBDE responses, especially deca-BDE (PBDE-209) [1] and this approach is applied here. The benefit appears in both response and also in shorter analysis times; elution of deca-BDE occurs in less than 15 minutes. The separation on the DB-5ms phase seems sufficient for characterizing PBDE additives in polymers since the desire is not so much the complete separation as it is the overall composition and contribution of the various isomers [5]. Nonetheless, the short analysis time makes RT reproducibility and accuracy more critical for correct assignments of the various PBDE isomers and this is greatly enhanced by applying RTL. A list of the Retention Time Locked elutions of the most prominent PBDEs is presented in Table 2. For reference, Figures 1, 2 and 3 present chromatograms of PentaBDE, OctaBDE, and DecaBDE technical mixtures with approximate elution windows of the various isomers.

Table 2. Prominent PBDE Congeners and their Locked RTs

Compound name	RTL RT (min)
PCB 207	8.69
PCB 209 (locking compound)	9.350
PBDE 17 (tri Br)	6.89
PBDE 28 (tri Br)	7.08
PBDE 71 (tetra Br)	7.97
PBDE 47 (tetra Br)	8.09
PBDE 66 (tetra Br)	8.25
PBDE 100 (penta Br)	8.82
PBDE 99 (penta Br)	9.06
PBDE 85 (penta Br)	9.43
PBDE 154 (hexa Br)	9.62
PBDE 153 (hexa Br)	9.93
PBDE 138 (hexa Br)	10.31
PBDE 183 (hepta Br)	10.73
? hepta PBDE	11.07
PBDE 190 (hepta Br)	11.23
PBDE 204 (octa)	11.62
PBDE 203 (octa)	11.78
? PBDE 196 (octa)	11.84
PBDE 205 (octa)	12.00
PBDE 208 (nona)	12.56
PBDE 207 (nona)	12.64
PBDE 209 (deca Br)	13.60

Note - tentative identification of PBDE 196 was based on reference [1]




Figure 1 Reconstructed ion chromatogram (RIC) for the GC/MS EI-SIM acquisition of a PentaBDE technical mixture (Cambridge Isotope Laboratories).




Figure 2 RIC for the GC/MS EI-SIM acquisition of a OctaBDE technical mixture (Cambridge Isotope Laboratories)




Figure 3 RIC for the GC/MS EI-SIM acquisition of a DecaBDE technical mixture (Cambridge Isotope Laboratories).

PBDE Spectral Interpretation

The EI ionization mass spectra of the PBDE congeners are rich in details and partially described in the literature [7]. Among the isomers the spectra are expected to be approximately identical in pattern and fragmentation pathway. Figure 4 presents a full scan spectrum of a hexabrominated-DE, PBDE-138, obtained at a source temperature of 300 °C. The spectrum shows the isotope cluster due to the molecular ion (643 m/z) and an intense cluster (484 m/z) consistent with the loss of Br₂. The mass assignment of the m/z 484 cluster is consistent with the result of $[M-Br_2]^+$, that is, $[C_{12}H_4OBr_4]^+$, and shows the tetrabrominated pattern (18 : 69 : 100 : 65 : 16). The next highest abundance isotope cluster appears around 242 m/z . Figure 4 shows this cluster and the cluster at m/z 484, $[M-Br_2]^+$. The isotope cluster patterns are similar, which suggests the same degree of

bromination, but the fragment mass assignments are half those of the 484 cluster and mass spacing is not 2 but 1 m/z unit. While it is possible this is due to overlapping fragments, the close correspondence in patterns lead the authors to propose that this isotope cluster is due to double-charged fragments; that is, $[M-Br_2]^{+2}$. Recently, this assignment was confirmed by high-resolution MS and the results will be published elsewhere [8]. This $[M-Br_2]^{+2}$ fragment is common among the PBDEs congeners and grows in relative abundance as the degree of bromination increases: approximately in 10% tetraBDEs; 15% in pentaBDEs; 20%–25% in hexaBDEs and heptaBDEs; 45% in octaBDEs; 60% in nonaBDEs; and > 80% in decaBDE. Figures 5, 6, 7, 8 and 9 show spectra for several PBDEs. We have also observed the same phenomena for the polybrominated biphenyls (PBBs). We also find the ratios vary within an isomeric series more than in PCBs.




Figure 4 Normalized EI mass spectrum of a hexabrominated-DE, PBDE-138, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 5 Sections of the normalized EI mass spectrum of the hexabrominated-DE, PBDE-138, for the $[M-Br_2]^+$ and proposed $[M-Br_2]^{+2}$ clusters.




Figure 6 Normalized EI mass spectrum of a pentabrominated-DE obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 7 Normalized EI mass spectrum of a heptabrominated-DE obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 8 Normalized EI mass spectrum of an octabrominated-DE, PDBE-203, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 9 Normalized EI mass spectrum of a nonabrominated-DE, PDBE-208, obtained in scan from 150–800 m/z at a source temperature of 300 °C.

In considering the EI spectrum of the decabromodiphenyl ether, PBDE-209, the same observations apply, Figure 10. Although the cluster of the molecular ion at 959 u, eludes the mass range limitation of the 5973N-MSD, the loss of Br₂ forms an intense isotope cluster at m/z 799, [M-Br₂]⁺ and the doubly charged fragment(s) for the [M-Br₂]⁺² at m/z 400 (399.6) as shown in Figure 11. Other data has shown that the intensity of the molecular ion cluster (959 u) is far less than that of the fragments at m/z 799 as is the trend for the PBDEs.




Figure 10 Normalized EI mass spectrum of the decabrominated-DE, PDBE-209, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 11 Normalized EI mass spectrum of the decabrominated-DE, PDBE-209, obtained in scan from 150–800 m/z at a source temperature of 300 °C.

Therefore these ions (that is, $[M-Br_2]^+$, $[M-Br_2]^{+2}$ and $[M]^+$ where available), and compound RTs, identify and allow determination of the deca-BDE and other PBDEs to the ability of the 15-m column to separate the isomers, which appears quite effective and sufficient for characterizing additives. The monitored ions are given in Table 3 with the ions for the internal standards used in this analysis. Obviously, the bromines provide other ions displaced in mass by two units (except for the doubly-charged ions) that offer other additional ions for quantitation or confirmation.

Using the ions listed in Table 3 to identify the PBDE isomers, the regions in the chromatograms presented in Figures 1, 2 and 3 were labeled with the isomer elution windows. These ions and their ratios were also used to characterize PBDEs not available in the standards but found to occur within the samples and technical mixtures (for example, PBDE 196).

Results for Polymeric Samples

Extracting PBDEs from polymers requires that the entrained PBDEs permeate the polymer into the extracting medium. Apparently “melting” the polymer closes the transport corridors in the polymer and impedes extraction. However, “swelling” the polymer with a proper solvent, greatly improves the kinetics of extraction. Beyond deciding the proper solvent, the optimal time of the extraction must be experimentally determined for each plastic based on its consistency and response to the solvent. For the polymer dissolution and soxhlet extraction methods used here, solvent contact

times or the number of soxhlet cycles for near complete extraction was determined by serial extraction. Other concerns are described in the sample preparation protocols [3].

Figure 12 shows the chromatogram for an extracted HIPS (high-impact polystyrene) polymer sample supplied by an Agilent customer and Table 4 shows the results for replicate extractions and analysis. Note the chromatogram and its major components closely resembles the chromatogram for the OctaBDE technical mixture (Figure 2) and indicates the specificity of the selected ions and most importantly, the lack of polymeric interferences. The reproducibility of the component compositions is a testament to the reproducibility of the total method. A good portion of the variance is introduced by the high dilution factors used in the method to bring the polymer extract concentrations with the scale of the PBDE standards and therefore discriminates against the lower abundance components producing a higher degree of variation and absolute detection. A series of 25 replicate injections of an extracted sample showed negligible degradation in response or chromatography. The robust performance is largely due to the high MSD ion source and quadrupole operating temperatures of 300 °C and 150 °C, respectively. These high temperatures mitigate the effect of co-extracted polymeric residues on the ion source optics to render robust performance. The high operating temperature of the quadrupole provides a very long lifetime without cleaning or maintenance even when analyzing very dirty matrices such as these.

Table 3. Quantitation and Confirmation Ions for the PB_nDEs (n>2)

PBDE bromination	$[M]^+$	$[M-Br_2]^+$	$[M-Br_2]^{+2}$	Confirmation ion
3	405.8	246.0	123.0	403.8
4	485.7	325.9	162.9	483.7
5	563.6	403.8	201.9	561.6
6	643.5	483.7	241.9	641.5
7	721.5	561.6	(280.8 **)	563.6/719.4
8	799.4	641.5	320.8	643.5
9	—	719.4	360.7	721.5
10	—	799.4	399.7	—
PCB 207	463.7	461.7	—	—
PCB 209	497.7	499.7	—	—

**The 280.8 and 281.8 m/z ions can be compromised by column bleed interferences so these were not used in acquisition although they provide a useful diagnostic for column degradation.




Figure 12 RIC of the GC/MS SIM acquisition of an extracted HIPS polymer sample.

Table 4. Extraction Results for Replicate Analysis of a Polymer Sample for PBDE Composition Using the Two Extraction and Sample Preparation Protocols [3]

Soxhlet polymer extraction protocol results						
Sums	Replicate 1 (%)	Replicate 2 (%)	Replicate 3 (%)	Replicate 4 (%)	Replicate 5 (%)	SD
HexaBDEs	9.1	9.5	8.9	8.7	9.1	0.3
HeptaBDEs	53.3	52.5	51.7	53.1	53.1	0.7
OctaBDEs	29.5	29.5	30.7	29.5	29.8	0.5
NonaBDEs	8.0	8.4	8.6	8.7	8.1	0.3

Polymer Dissolution Extraction Protocol Results*				
Sums	Replicate 1 (%)	Replicate 2 (%)	Replicate 3 (%)	SD
HexaBDEs	9.9	10.0	9.7	0.2
HeptaBDEs	55.3	56.2	55.9	0.5
OctaBDEs	34.8	33.8	34.4	0.5

SD standard deviation

No tri-BDEs, tetraBDEs, pentaBDEs, or decaBDE were detected.

*A difference in analyte lists used to quantitate the soxhlet extracts slightly skews the results, specifically the addition of the nona-BDE analytes. Removing this group, the results agree within 3%.

Remarks

Figure 13 presents two overlaid reconstructed ion chromatograms of the SIM acquisitions of two splits of a single PBDE standard. One of the splits was contained in a clear vial and was exposed to laboratory light for about a week and the other split was stored in amber vial and in a freezer as a reference. The most impressive feature is the dramatic loss of the decaBDE and the possible appearance of another intense nonaBDE (around 11.8 minutes). Note the nonaBDEs in the standard showed no degradation while the octaBDEs and heptaBDEs showed varying degrees of loss in concentration. A number of small peaks appear in the baseline that suggest, on the basis of their fragments, ion ratios, and proximity to existing PBDEs in the standard, the presence of other BDE isomers. Assigning any identification in SIM without a standard reference compound to confirm RT and fragment ratios, or a full scan acquisition, must be considered highly speculative. However, the data does indicate a degradation of the decaBDE and some other PBDEs, and suggests possible isomerization of the some PBDEs under the influence of typical laboratory fluorescent lights. Time and resources do not allow us to pursue this matter,

but we provide these observations since there are implications in sample handling and standard preparation and storage.

Conclusions

The 5973N inert MSD equipped with performance electronics allows a single SIM group to survey for PBDE isomers important to characterizing the technical formulations of the PBDEs. Using a single group has the advantages of allowing many formulations to be studied without regard to the particular elution of the congeners (which would require careful maintenance of SIM windows), simplified setup and very rapid analysis. Implementing RTL allows specific congeners to be characterized and quantitated with high confidence. The intense fragmentation of the PBDEs and their universal propensity to form $[M-Br_2]^+$ and $[M-Br_2]^{+2}$ ions provides a unique fingerprint for each degree of bromination. The 15-m column used here provides rapid analysis and sufficient class separation. The method is universally applicable regardless of the sample preparation scheme as demonstrated here by replicate polymer analysis by two techniques, soxhlet extraction and polymer dissolution.




Figure 13. PBDE standard unexposed (green) and exposed to laboratory light. Delta (Δ) indicates change in response as Exposed-Unexposed (with negative signs indicating loss in response and positive an increased response).

References:

1. J. Bjorklund, et al., "Influence of the injection technique and the column system on gas chromatographic determination of polybrominated diphenyl ethers", (2004) *Journal of Chromatography A*, **1041**(1-2): p. 201-210.
2. A. M. Altwaiq, M. Wolf, and R. van Eldik, "Extraction of brominated flame retardants from polymeric waste material using different solvents and supercritical carbon dioxide", (2003) *Analytica Chimica Acta*, **491**(1): p. 111-123.
3. H. Prest. and C. Tu, "Sample Preparation Protocols for Polybrominated Diphenyl Ethers in Polymeric Materials for GC-MS analysis", (2005), available to Agilent customers by request through their Agilent sales agents. www.agilent.com/chem
4. H. Prest and D.W. Peterson, "New approaches to the development of GC-MS selected ion monitoring acquisition and quantitation methods", (2001), Agilent Technologies, publication 5988-4188EN www.agilent.com/chem
5. P. Korytar, et al., "Retention-time database of 126 polybrominated diphenyl ether congeners and two Bromkal technical mixtures on seven capillary gas chromatographic columns", (2005) *Journal of Chromatography A*, **1065**(2): p. 239-249.
6. V. Giarrocco, B. Quimby, and M. Klee, "Retention Time Locking: Concepts and Applications", (1998), Agilent Technologies, publication 5966-2469EN www.agilent.com/chem
7. S. Huber, and K. Ballschmiter, "Characterisation of five technical mixtures of brominated flame retardants", (2001) *Fresenius Journal of Analytical Chemistry*, **371**(6): p. 882-890.
8. Q. Zhang, et al., Rapid Communications in Mass Spectrometry, in preparation.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
April 5, 2005
5989-2850EN



Agilent Technologies



Effect of Sample Matrix on Suppression of Ionization in Water Samples Using LC-ESI-MS

Application

Authors

Neil Cullum
Anglian Water Services Laboratories
Hinchingsbrooke Business Park
Kingfisher Way, Huntingdon, PE29 6FL
UK

Chin-Kai Meng and Paul Zavitsanos
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Liquid chromatography electrospray ionization mass spectrometry is a very powerful technique that combines the liquid chromatography separation with highly selective and sensitive mass detection, but the ionization process is susceptible to matrix signal suppression. Signal suppression, therefore, presents a challenge in doing quantitative liquid chromatography/mass spectrometry applications. Using the Agilent Technologies 1100 series quadrupole mass spectrometry system coupled to an Agilent Technologies 1100 series liquid chromatography system revealed that the greatest part of the ion suppression phenomenon is largely due to compounds in the extracted sample that were carried through the extraction.

Introduction

Liquid chromatography (LC) electrospray ionization mass spectrometry (ESI-MS) is a very powerful technique in analyzing organic compounds. The technique combines the LC separation with highly selective and sensitive mass detection. However,

one drawback of ESI-MS is that the ionization process is susceptible to matrix signal suppression. The liquid chromatography/mass spectrometry (LC/MS) response obtained from a standard can differ significantly from matrix samples. Therefore, signal suppression presents a challenge in doing quantitative LC/MS applications.

Previous studies have shown that the ion suppression effects are due mainly to the competition between matrix components and the analytes to get charges or to gain access to the droplet surface for gas-phase emission [1]. Other factors include surface tension [2, 3], sample pH [4], and compound polarity [5]. Published approaches to minimize the ion suppression effects include: using a more selective extraction procedure for matrix cleanup [6], providing more chromatographic retention of analytes [6, 7], changing buffer and its concentration [3, 8, 9], flow-splitting [10] or nanospray [11], post-column addition [12], and 2-dimensional chromatography [13]. All the approaches to minimize suppression seem to develop a uniform spray with fine droplets.

In this application note, a target compound in different water matrices was used to study the effects of sample matrix on signal suppression. In the case of potable waters, in particular water samples derived from surface water sources, the suppression was likely to be due to humic and fulvic acids, which elute very early in high aqueous mobile phase conditions [4]. These acids are organic acids that arise naturally in decomposing organic material called humus. The ionization suppression can lead to an apparent reduction in recovery values for certain compounds. The suppression effect in different water matrices was reported recently [4, 14].



Agilent Technologies

Imazapyr (see Figure 1) is a compound that has shown differences in overall recovery with varying water matrices [15]; it has shown, a 73% recovery from groundwater and 48% recovery from potable water derived from a surface water source.




Figure 1. The structure of Imazapyr, the chemical standard used in this study.

A series of experiments were conducted to study the effects of varying sample matrix as measured by Total Organic Carbon (TOC) content to show if indeed sample matrix was the cause of apparent variation in overall compound recovery and also to observe if any other parameters affect the suppression.

Experimental

All analyses were performed using an Agilent 1100 series quadrupole MS system coupled to an Agilent 1100 series LC system consisting of a vacuum degasser, binary pump, autosampler, and diode array detector (DAD). The quadrupole mass

spectrometer was operated with the Agilent atmospheric pressure electrospray ionization (API-ESI) source. Figure 2 shows the mass spectrum of 10 mg/L Imazapyr in negative ion mode at fragmentor voltage of 75 V. This spectrum was obtained using the flow injection analysis (FIA) mode while varying the fragmentor voltage.

The TOC of all sample matrices was determined using an automated Labtoc TOC analyzer. The samples are first acidified using concentrated orthophosphoric acid and purged with helium to remove inorganic carbon. The samples are then digested with sodium persulphate and ultraviolet (UV) light to convert the organic carbon to carbon dioxide. The carbon dioxide concentration is measured using infrared detection.

Four sample matrices were chosen for the initial work:

- Deionized water, with a TOC measurement of less than 0.1 mg/L
- Borehole water with TOC measurement equal to 0.5 mg/L
- Potable tap water with a TOC measure equal to 5 mg/L
- River water with a TOC measurement equal to 15.5 mg/L

The first three matrices were also used for the matrix stripping experiments.

All samples were spiked at 5 $\mu\text{g/L}$ with Imazapyr. At this concentration, the samples were within the working range of the DAD and could be analyzed by the MS in the full scan mode.




Figure 2. The mass spectrum of Imazapyr at 10 mg/L in negative ion mode at fragmentor voltage of 75 V.

The chemicals and consumables used for this study include:

TBME, 99.8%	HPLC Grade	Sigma- Aldrich part number 29,321-0
Methanol	HPLC Grade	Rathburn Chemicals Ltd part number RH1019
Acetonitrile	HPLC Grade	Rathburn Chemicals Ltd part number RH1015
Water	HPLC Grade	Rathburn Chemicals Ltd part number 1020
Formic acid, 98%	AR Grade	Fisher Scientific part number F/1900/PB08
Hydrochloric acid, 37%		J. T. Baker part number 6011/2.5
Imazapyr standard, 99%		Qmx Laboratories part number C142830
Oasis HLB (60 mg, 3 mL) cartridges		Waters Corporation part number WAT094226
Oasis MAX (60 mg, 3 mL) LP cartridges		Waters Corporation part number 186000368

Sample Preparation

Fully automated solid phase extraction (SPE) using Tekmar Autotrace SPE workstations and Oasis HLB, 60 mg, 3-mL cartridges and a set of solutions:

- 90:10 *tert*-butyl methyl ether (TBME):methanol (0.01% formic acid)
 - Methanol (0.01% formic acid)
 - HPLC grade water
 - HPLC grade water (0.25% hydrochloric acid)
- Initially condition each cartridge with sequential additions.

Solvent	mL of solution
a	5
b	5
c	3
d	3

- Dilute an aqueous sample of 50 mL to 200 mL with deionized water and acidify with 0.75 mL of concentrated hydrochloric acid. This step is done to reduce matrix effects and to give enough sample to pump through the cartridges.
- Pump a diluted sample of 100 mL through the conditioned cartridge at 10 mL/min.
- Dry the cartridge for 10 minutes, using forced air.
- Elute the cartridge with solution (a) twice using 1.5 mL and once using 1 mL, total 4 mL.

- Evaporate the extract to dryness on a 45 °C heated block, using a gentle air stream.
- Dissolve the residue in 0.25 mL of 90:10 water (0.01% formic acid):methanol solution.

Matrix Stripping Procedures

Ion suppression phenomena often appear to be extraction recovery effects. To decouple the effects of ion suppression from extraction recovery a series of experiments was conducted on matrix that had been stripped by an SPE procedure.

Two different stripping chemistries were investigated for their impact on ion suppression.

MAX (anion) cartridges

MAX cartridges were used to remove suspected humic acids from the matrix. The MAX cartridges (60 mg, 3 mL) were conditioned with 3-mL methanol and 3-mL HPLC grade water. The sample was pumped through the cartridge to collect the water. The collected water was spiked with Imazapyr at 5 µg/L and re-extracted as per standard method.

HLB cartridges

The different water matrices were pumped through HLB cartridges that were conditioned using the standard method [15] and the water samples were collected. The collected water was spiked with Imazapyr at 5.0 µg/L and re-extracted as per standard method.

Liquid Chromatograph Conditions

Column	Zorbax Eclipse XDB-C18, 2.1 mm × 150 mm × 3.5 µm at 60 °C	
Column flow	Binary pump, isocratic mode	
Mobile phase A	0.01% Formic acid in water	85%
Mobile phase B	Acetonitrile	15%
Flow rate	0.3 mL/min	
Sample size injected	50 µL	
DAD	230 nm (Spectra acquired from 200–400 nm)	

Mass Spectrometer Conditions

V _{cap}	2500 V (Negative), 3000 V (Positive)
Fragmentor voltage	75 V
Full scan range	100–400 amu
Nebulizer pressure	50 psi
Drying gas flow rate	13 L/min
Drying gas temperature	350 °C

Results and Discussion

The ratio of the mass selective detector (MSD) recovery result to the LC DAD result was used to measure the ion suppression effect. The recovery of the target compound based on UV measurement was not significantly affected by any of the matrices tested. The recovery value for the UV reference measurement was 84.1% ± 1.7% over all samples and matrix types (Table 1). This method precision suggests an extraction and measurement system that will yield repeatable results in distilled, tap, and borehole waters, as well as stripped water samples. The deionized water extracts were spiked at relatively high value of 5.0 µg/L for three reasons. First, to avoid complicating the investigation of the suppression effect with low level extraction non-linearities. Second, by working at this concentration it was possible to work in scan mode thereby saving the data from the spectral domain for all the experiments. It would then be possible to see whether the causes of ion suppression could be explained by spectral data. Third, at this level it was possible to use the measurement by DAD to provide a predictable, repeatable, and

matrix-independent reference-recovery value. Consequently, the expected value obtained for both MSD and DAD should be *circa* 5.0 µg/L.

The MS parameters listed in the application note [15] were the starting point for this study. Under the conditions of these experiments the presence of a cluster ion at m/z 195 in the background spectra indicated that the desolvation characteristics of the source required some optimization. The presence of this cluster ion in the background was predictive of low response in the negative ion for the target analyte. Under source conditions that exhibited inadequate desolvation and cluster formation, the system exhibited a low-recovery result for the deionized water sample (MSD/DAD = 0.77); the MSD result in negative ion was 77% of the reference DAD recovery result. Therefore, the nebulizer pressure, drying gas temperature, and flow rate were adjusted until the cluster ion was no longer present. Under source conditions that produced no cluster ion at m/z 195, the MSD recovery result for the deionized water sample, as compared to the reference DAD recovery result, improved significantly to 91%.

Table 1. DAD and MSD Recovery Data from Different Matrices


Water samples		Samples spiked before SPE						Matrix stripped with MAX			Matrix stripped with HLB		
		DAD	Neg. ESI	Ratio	DAD	Pos. ESI	Ratio	DAD	Neg. ESI	Ratio	DAD	Neg. ESI	Ratio
Deionized	MEAN	4.17	4.16	1.00	4.10	4.03	0.98	4.21	4.1	0.97	4.22	4.15	0.98
	SD	0.12	0.13		0.08	0.14		0.16	0.09		0.11	0.24	
	%RSD	3	3.2		2.06	3.38		3.8	2.2		2.6	5.8	
Borehole TOC=0.5 mg/L	MEAN	4.35	2.96	0.68	3.98	4.03	1.01	4.1	3.91	0.95	4.3	4.04	0.94
	SD	0.15	0.05		0.11	0.19		0.12	0.13		0.18	0.29	
	%RSD	3.4	1.6		2.76	4.66		2.9	3.2		4.1	7.1	
Tap TOC=5 mg/L	MEAN	4.29	1.55	0.36	3.94	4.14	1.05	4.13	2.45	0.59	4.17	3.57	0.86
	SD	0.15	0.14		0.13	0.11		0.09	0.09		0.07	0.17	
	%RSD	3.4	8.7		3.30	2.71		2.2	3.6		1.8	4.8	
River TOC=15.5 mg/L	MEAN	3.04	0.9	0.30	3.04	2.88	0.95						
	SD	0.1	0.05		0.1	0.11							
	%RSD	3.4	6		3.4	3.9							

A thorough source cleaning of the metal surfaces and a rinse with 50:50 isopropanol:water followed by a mass axis calibration and ion transmission tune, increased the MSD recovery result for the deionized water sample, as compared to the reference DAD recovery result to 97%. The %RSD for these ratios was approximately 3%. Clearly, the desolvation and declustering characteristics of the source had a large impact on the instrumental contribution to the suppression effect for clean samples.

As can be seen from Table 1, the positive ion results for this compound, as extracted from spiked samples, show no evidence of ion suppression regardless of matrix. In addition to the reference characteristics of the DAD data, the positive

ion results provide an ESI-based reference for the study of the origin of these suppression effects in ESI. Comparison of negative ion ESI results to both the DAD and positive ion ESI results permits a closer correlation between the magnitude of the suppression and the chemical nature of the suppressant in the matrix.

The nature of the negative ion suppression can be investigated from the data presented in Table 1. No suppression is observed for samples extracted from distilled water. The TOC for this water is at least an order of magnitude lower than the next highest content matrix. The negative ion ESI spectrum (Figure 3) was not significantly greater than background. Moreover, there were few significant ions other than those in the background.

**Figure 3. The mass spectrum of Imazapyr in deionized water spiked at 5.0 µg/L.**

Borehole water has a TOC measurement of 0.5 mg/L. Recovery results obtained from the MSD were 68% of those obtained from the reference DAD signal. This represents significant ion suppression. In addition, the spectral data (Figure 4) indicated that there were significant numbers of background ions from mass 300 and higher due to the sample matrix. The spectrum above m/z 300 shows the beginnings of what appears to be a spectral envelope analogous to the ESI spectra observed for complex polymers.

Tap water (TOC at 5 mg/L) recovery results obtained from the MSD were 36% of those obtained from the reference DAD signal. The spectral data (Figure 5) indicated that there were significant numbers of background ions from mass 200 and higher due to the sample matrix. The impression of the low-mass end of a polymer's spectral envelope is further strengthened. Both the intensity and the number of ion have increased relative to the previous sample.




Figure 4. The mass spectrum of Imazapyr in borehole water spiked at 5.0 µg/L. Notice the significant numbers of background ions from m/z 300 and up due to the sample matrix.




Figure 5. The mass spectrum of Imazapyr in tap water spiked at 5.0 µg/L. From m/z 200 upward, there was a vast increase in the number of ions due to the increase in matrix content.

To further explore the effect of matrix, a high TOC (15.5 mg/L) river water sample was collected and analyzed without any matrix stripping. The sample was spiked with Imazapyr at 5.0 $\mu\text{g/L}$ and extracted, as described in the sample preparation section. The extracted sample was analyzed in both positive and negative ionization modes as well as with the DAD. The extraction method was not developed with raw river water in mind, so some differences were expected as compared to the simpler matrices. The only major difference between the results from the river water samples and the simpler matrices was extraction efficiency. Consequently, the DAD recovery results were significantly lower due to the extraction efficiency from the high organic load matrix. Despite the lower DAD recovery results, the chromatographic and ESI spectral data were excellent at the concentration of 5 $\mu\text{g/L}$. The recovery relationships are expected to hold even though the method was not specifically engineered for river water. Comparison of the positive ion MSD recovery to the DAD recovery results showed that, while extraction efficiency was lower in these river water samples, the high organic content sample exhibited no noticeable suppression in the positive ion mode. The positive ion mode spectrum of this extracted sample was very similar to that of tap water as shown in Figure 6.

However, the negative ion mode showed a large suppression effect. The ratio of negative ion MSD recovery to the reference DAD recovery results was only at 30% obtained by the DAD.

At the same level of extraction efficiency, DAD recovery results showed very similar values for all matrices, as did the positive ion results. Therefore, the ion suppression observed was directly related to the negative ion ESI process and the chemical nature of the species producing the spectral envelope observed in Figures 4 and 5. The suppression, negative ion spectral complexity and negative ion spectral envelope intensity increased with increasing organic content in the matrix as measured by the TOC. The relationship between TOC and recovery ratio as well as the deviation from back-calculated data is graphed in Figure 7 and 8. As can be seen from the graph, even a low TOC level can result in significant suppression.

To further test these observations, a matrix-stripping experiment was carried out for each of distilled, borehole, and tap waters using two different stripping chemistries.

The HLB cartridge was used to test the stripping effect under the same extraction conditions, while the Oasis MAX chemistry was used to investigate the effect of an anion exchanger on the suppression.




Figure 6. The mass spectrum of Imazapyr in HLB cartridge extracted tap water, positive ion mode, showing low background ion abundances for m/z 200 and higher.




Figure 7. Normalized recovery ratio versus TOC.

In all negative ion ESI cases the matrix stripping prior to analyte spiking dramatically increased the ratio of the ESI recovery result to the reference DAD recovery result regardless of stripping chemistry. In all cases the stripping chemistry reduced the intensity of the ion continuum above m/z 200 from 50% to 90%. The greater the intensity reduction of this spectral envelope, the greater the ratio of MSD-to-DAD recovery result and the smaller the extent of ion suppression. This is strong evidence that the portion of the suppression effect not due to inadequate desolvation, is largely a matter of matrix compounds bleeding through the extraction procedure into the extracted sample. The chemical nature of these suppressant compounds would have to be remarkable given their persistence under a wide range of extraction chemistries.

It was expected that the agents causing the suppression effects were humic acids and were expected to be preferentially removed by the anion exchange chemistry of the MAX cartridge. This proved not to be the case. The HLB cartridge stripping chemistry proved more effective at reducing the suppression than was the MAX chemistry. Either the humic acids were not effectively removed due to extraction conditions or the compounds causing suppression were not entirely humic acids.

Ion suppression in the ESI-MS analysis of water samples was reported under a wide variety of extraction and measurement conditions. A compound class, complex enough to produce the higher mass ion continuum seen in this work,




Figure 8. Residuals from back calculated data for Figure 7.

would likely be extremely diverse. Such a diverse mixture could carry through virtually any simple extraction procedure. An ideal technique would have to be extremely discriminating to be free from members of such a compound class.

Conclusions

Two main points of conclusion about the ion suppression effect in negative ion ESI analysis of water samples can be suggested. The first is that ion suppression is aggravated by instrumental conditions that favor incomplete desolvation and that such conditions can be indicated by the presence of extensive clustering.

The second conclusion is that the greatest part of the ion suppression phenomenon is largely due to compounds in the sample vial that were carried through the extraction. The presence of these compounds is evidenced in the spectrometry. The suppressants are seen as a higher mass continuum of ions starting at about m/z 200 and above in negative ion mode. The majority of the continuum exists at higher m/z than is used in measurement and so its effects are felt in the recovery results as ion suppression but not seen in the chromatographic signal. The effect would be especially frustrating in highly specific tandem techniques. The higher the intensity of this ion continuum, the greater the suppression. In these samples the positive ion response of the ions in the continuum were much lower as compared to the negative ion mode. Interestingly enough there is no ion suppression in positive ion mode.

This work underscores the often-repeated message that a clean sample extract is essential in producing reliable methodologies. A clean extract reduces the need for tandem techniques and often rare and expensive isotopically labelled internal standards.

Future work would focus on a more precise identification of this compound class and on isolation techniques that embody a more powerful discrimination than simple SPE.

References

1. Constantopoulos T. L., Jackson G. S., and Enke C. G. (1999) "Effects of salt concentration on analyte response using electrospray ionization mass spectrometry", *J. Am Soc Mass Spectr* **10** (7): 625-634.
2. Ikononou M. G., Blades A. T., and Kébarle P., (1991) "Electrospray Mass-Spectrometry of methanol and water solutions suppression of electric-discharge with SF₆ gas", *J. Am Soc Mass Spectr* **2** (6): 497-505.
3. Apffel A., Fischer S., Goldberg G., et al. (1995) "Enhanced Sensitivity for peptide-mapping with electrospray liquid-chromatography mass-spectrometry in the presence of signal suppression due to trifluoroacetic acid-containing mobile phases", *J. Chromatogr A* **712** (1): 177-190.
4. Steen R. J. C. A., Leonards P. E. G., and Brinkman U. A. T., et al. (1999) "Ecological risk assessment of agrochemicals in European estuaries", *Environ Toxicol Chem* **18** (7): 1574-1581.
5. Bonfiglio R., King R. C., and Olah T. V., et al. (1999) "The effects of sample preparation methods on the variability of the electrospray ionization response for model drug compounds", *Rapid Commun Mass Sp* **13** (12): 1175-1185.
6. Matuszewski B. K., Constanzer M. L., and Chavez-Eng C. M. (1998) "Matrix effect in quantitative LC/MS/MS analyses of biological fluids: A method for determination of finasteride in human plasma at picogram per milliliter concentrations", *Anal Chem* **70** (5): 882-889.
7. Muller C., Schafer P., and Stortzel M., et al. (2002) "Ion suppression effects in liquid chromatography-electrospray-ionisation transport-region collision induced dissociation mass spectrometry with different serum extraction methods for systematic toxicological analysis with mass spectra libraries", *J Chromatogr B* **773** (1): 47-52.
8. Choi B. K., Hercules D. M., and Gusev A. I., (2001) "LC-MS/MS signal suppression effects in the analysis of pesticides in complex environmental matrices", *Fresen J. Anal Chem* **369** (3-4): 370-377.
9. Kuhlmann F. E., Apffel A., and Fischer S. M., et al. (1995) "Signal enhancement for gradient reverse-phase high-performance liquid chromatography electrospray ionization mass spectrometry analysis with trifluoroacetic and other strong acid modifiers by postcolumn addition of propionic acid and isopropanol", *J. Am Soc Mass Spectr* **6** (12): 1221-1225.
10. Gangl E. T., Annan M., and Spooner N., et al. (2001) "Reduction of signal suppression effects in ESI-MS using a nanosplitting device", *Anal Chem* **73** (23): 5635-5644.
11. Bahr U., Pfenninger A., Karas M., and Stahl B. (1997) "High sensitivity analysis of neutral underivatized oligosaccharides by nanoelectrospray mass spectrometry", *Anal Chem* **69** (22): 4530-4535.
12. Choi B. K., Gusev A. I., and Hercules D. M. (1999) "Postcolumn introduction of an internal standard for quantitative LC-MS analysis", *Anal Chem* **71** (18): 4107-4110.
13. Pascoe R., Foley J. P., and Gusev A. I. (2001) "Reduction in matrix-related signal suppression effects in electrospray ionization mass spectrometry using on-line two-dimensional liquid chromatography", *Anal Chem* **73** (24): 6014-6023.
14. Draper W. M. (2001) "Electrospray liquid chromatography quadrupole ion trap mass spectrometry determination of phenyl urea herbicides in water", *J. Agr Food Chem* **49** (6): 2746-2755.
15. Cullum N., Stephens P., and Evans S. (2002) "Determination of acidic herbicides in ground-water and potable water by LC/MSD using selective ion monitoring". Agilent Technologies publication, 5988-5882EN.
www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
February 18, 2004
5989-0371EN



Agilent Technologies



Full-Scan Low-Level Polynuclear Aromatic Hydrocarbon Analysis Using the Agilent Technologies 6890/5973 inert Gas Chromatograph/Mass Selective Detector

Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of polynuclear aromatic hydrocarbons presents challenges due to the tendency of the polynuclear aromatic hydrocarbons to adsorb on surfaces in the chromatographic system. This results in calibrations that are not linear and the need to run selected ion monitoring for low-level analysis. The Agilent Technologies 6890/5973 inert gas chromatograph/mass selective detector system is designed for improved polynuclear aromatic hydrocarbons analysis using full scan while maintaining linearity across a wide calibration range.

Introduction

Polynuclear aromatic hydrocarbons (PAHs) are produced during combustion of organic material and are suspected carcinogens. The high amounts and widespread occurrence of these compounds in our environment requires reliable, sensitive, and very robust analytical methods.

PAHs, especially the high molecular weight ones, tend to be adsorbed on any active or cold site in a gas chromatographic system. Additionally occurring inlet discrimination often further reduces the number of compounds with higher boiling points that are transferred onto the column. Therefore, typical PAH analyses on a gas chromatography (GC) or gas chromatography/mass selective detector (GC/MSD) system show decreasing response and sensitivity with increasing molecular weight.

The Agilent 6890/5973 inert GC/MSD system has features to overcome this negative trend, including a new uncoated solid-source material and higher temperature filaments. Using a direct-connect inlet liner also improves chromatographic peak shape and sensitivity.

Many laboratories calibrate for PAHs from 0.1 to 10 ppm using Selected Ion Monitoring (SIM) for low level work. Historically, SIM has been necessary because of instrument sensitivity considerations and loss of PAHs at the lower concentration levels, although full scan data is preferred for further confirmation of the compounds.

This application note will show the performance of the Agilent 6890/5973 inert for PAHs using a calibration range of 0.1 to 10.0 ppm in full scan mode with linearity equal to that of many SIM methods.



Agilent Technologies

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet	EPC split/splitless		
Mode	Pulsed splitless, 1 µL injected		
Inlet temperature	300 °C		
Pressure	12.64 psi		
Pulse pressure	30.0 psi		
Pulse time	0.30 min		
Purge flow	30.0 mL/min		
Purge time	1.0 min		
Total flow	34.6 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet liner	Direct Connect, deactivated, 4-mm id, Agilent part number G1544-80700		
Oven			
Oven ramp	°C/min	Next °C	Hold min
Initial		50	1.00
Ramp 1	25	200	0.00
Ramp 2	8	316	0.00
Total run time	21.50 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS part number 19091S-433		
Length	30.0 m		
Diameter	250 µm		
Film thickness	0.25 µm		
Mode	Constant flow		
Flow	1.5 mL/min		
Initial pressure	12.64 psi		
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
MSD	Agilent Technologies 5973 inert		
Drawout lens	6-mm ultralarge aperture, Agilent part number G2589-20045		
Solvent delay	3.00 min		
EM voltage	Run at DFTPP tune voltage = 1000 V		
Low mass	45 amu		
High mass	450 amu		
Threshold	0		
Sampling	2		
Scans/s	3.58		
Quad temp	180 °C		
Source temp	300 °C		
Transfer line temperature	280 °C		
Repeller voltage	DFTPP tune value		
Emission current	DFTPP tune value = 34.6 µamp		

Calibration standards

Calibration standards were diluted in dichloromethane from a stock mix of the 13 PAHs. The seven levels made were 10, 5, 2, 1, 0.5, 0.2 and 0.1 ppm. The perylene-d12 internal standard (ISTD) and the two surrogate standards, 1,3-dimethyl-2-nitrobenzene and triphenylphosphate, were added to each calibration level at 2.0 ppm.

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions that may have to be optimized.

The Agilent 6890 inlet temperature was set to 300 °C, instead of the typical 250 °C, to minimize compounds adsorbing on the liner surface. Pulsed injection was used to facilitate quantitative transfer of the heavier PAHs onto the column, minimizing inlet discrimination. Pulsed injection parameters are easily set in the ChemStation software and are automatically controlled by the electronic pneumatic control (EPC) module.

The Direct Connect inlet liner allows for complete transfer of analytes onto the column. The column inlet end attaches to the liner and minimizes analyte exposure to the stainless steel annular volume in the inlet.

The Agilent 5973 inert was tuned using the automatic DFTPP target tune, as required by some Government methods. The ultralarge aperture drawout lens was used to maintain linearity across the wide calibration range. Source temperature was set to 300 °C, which is now possible with the high temperature filaments. This higher source temperature in combination with the new source material produces better peak shapes for the PAHs.

Results

The system was calibrated at seven levels, 0.1, 0.2, 0.5, 1.0, 2.0, 5.0, and 10.0 ppm using full scan data acquisition. The total ion chromatogram (TIC) for the 0.2-ppm level is shown in Figure 1. Each calibration level contained 13 PAHs, perylene-d12 internal standard (ISTD) and the 2 surrogate standards, 1,3-dimethyl- 2-nitrobenzene and triphenylphosphate.

The relative response factor (RRF) was calculated automatically for each compound by the GC/MSD ChemStation software. Linearity was determined by calculating the percent relative standard deviation (%RSD) of the RRFs across the calibration range for each compound. This is also done automatically by the software in conjunction with Microsoft® Excel.

Linearity is shown in Table 2. The %RSD of the RRFs are shown for each of the PAHs. All RSDs are less than 5%. This level of performance is equal to that of most SIM methods for PAHs.




Figure 1. Thirteen PAHs at 0.2 ppm each with surrogates and ISTD at 2.0 ppm each.

As further proof of system inertness and sensitivity, a 0.01-ppm level spike was analyzed. This sample was quantitated against the seven level calibration curve using average response factor. The results are shown in Table 2. These results are excellent considering this is full scan data and the spike level was 10× lower than the lowest calibration point.

Table 2. %RSD of RRF from Seven Level Calibration and 0.01-ppm Spike Results

	%RSD	0.01 ppm Spike
Perylene-d12	3	—
1,3-dimethyl-2-nitrobenzene	1	2.100
Acenaphthylene	3	0.011
Fluorene	3	0.010
Phenanthrene	3	0.010
Anthracene	3	0.011
Pyrene	3	0.010
Triphenylphosphate	1	1.940
Chrysene	2	0.009
Benz[a]anthracene	3	0.010
Benzo[b]fluoranthene	2	0.009
Benzo[k]fluoranthene	4	0.010
Benzo[a]pyrene	2	0.010
Indeno(123-cd)pyrene	4	0.010
Dibenz(ah)anthracene	2	0.007
Benzo(ghi)perylene	3	0.011

Conclusions

The Agilent 6890/5973 inert shows much improved response and peak shape for PAHs due to the inert source material and higher allowable source temperature. This improved response gives better linearity across the calibration range. Analysis of PAHs can be accomplished using full scan data acquisition over a calibration range of 0.1 to 10 ppm, while maintaining performance similar to SIM methods.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Microsoft is a U.S. registered trademark of Microsoft Corporation.

© Agilent Technologies, Inc. 2003


Printed in the USA
November 11, 2003
5989-0264EN

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.



Agilent Technologies



Fast Semivolatiles Analysis using the Agilent Technologies 6890/5973 inert GC/MSD

Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of semivolatiles presents challenges due to the simultaneous measurement of acids, bases, and neutrals over a wide concentration range. Due to productivity demands, laboratories want to run faster while maintaining linearity and sensitivity for even the most active compounds. The Agilent Technologies 6890/5973 inert gas chromatography/mass selective detector system is designed to meet the criteria for fast analysis, while minimizing activity and maintaining linearity.

Introduction

Semivolatiles analysis concurrently measures a mix of acids, bases, and neutrals. This mix presents a challenge for instrument design due to the interaction of the analytes with the instrument and consumables. Most laboratories analyze for 70–100 compounds with a chromatographic run time of

25–40 minutes. The calibration range required for the analysis varies dependent on a particular laboratory's statement of work. Historically a range of 20–160 ng was used. With the increased sensitivity of newer gas chromatography/mass spectrometry (GC/MS) systems, laboratories are moving toward lower minimum detection limits (MDLs) and pushing the calibration range down to 5 ng.

The Agilent 6890/5973 inert gas chromatograph/mass selective detector (GC/MSD) system was designed to meet the demand for these lower MDLs. A new uncoated solid source material has shown improved performance for the most active compounds, such as 2,4-dinitrophenol.

This inert source allows for less material injected onto the column while maintaining mass spectrometer performance. Split injections are possible where only splitless would suffice before. The ability to do split injections matches very well with smaller diameter columns such as 100 μm . These smaller columns provide for run times of 10 minutes or less.

This application note will show the performance of the Agilent 6890/5973 inert for semivolatiles using a 100- μm id column with a run time of 7.5 minutes and a calibration range of 5–200 ng.



Agilent Technologies

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized.

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet	150 psi EPC split/splitless		
Mode	Split, 1 µL injected		
Split ratio	10:1		
Inlet temp	250 °C		
Pressure	118 psi		
Split flow	22.8 mL/min		
Total flow	26.9 mL/min		
Gas saver	Off		
Inlet liner	Siltek™ Cyclosplitter, 4-mm id, Restek part number 20706-214.1		
Oven	240 V		
Oven ramp	°C/min	Next °C	Hold min
Initial		40	0.20
Ramp 1	45	320	1.58
Total run time	8.0 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS Custom		
Length	12.5 m		
Diameter	100 µm		
Film thickness	0.1 µm		
Mode	Ramped flow		
Flow	mL/min ²	mL/min	Hold min
Initial		2.3	0.10
Ramp 1	10	0.8	0.00
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
MSD	Agilent Technologies 5973 inert		
Solvent delay	0.95 min		
EM voltage	Run at DFTPP tune voltage = 1200 V		
Low mass	35 amu		
High mass	500 amu		
Threshold	0		
Sampling	1		
Scans/s	5.92		
Quad temp	150 °C		
Source temp	230 °C		
Transfer line temp	280 °C		
Repeller voltage	DFTPP tune value		
Emission current	DFTPP tune at 35 µamp, run at 25 µamp		

Calibration standards

Accustandard, New Haven, CT. Part number M-8270-IS-WL-0.25x to 10x, 77 compounds at eight concentration levels with six ISTDs at 40 ppm.

The Agilent 6890 with a 150 psi inlet (option) is necessary for both the initial high flow during injection and to maintain constant flow during the run. A 10:1 split is used to match the column capacity to the calibration concentration range. Higher splits can be used but splitting less or using splitless will cause peak overload and too much distortion for good integration.

The inlet liner was found to be of low activity, as it does not contain glass wool. Proper mixing for split injections is done by the internal liner geometry. This liner was also found to perform adequately for higher split ratios and for splitless.

The Agilent 6890 240 V oven was necessary for the 45 °C/min oven program ramp used.

The custom order HP-5MS column was obtained in a 20 m length and cut down to 12.5 m. The ramp flow allows for faster transfer of analytes onto the column to minimize exposure to the inlet liner. Ramp flows are easily set by the software and are accomplished with electronic pneumatic control (EPC).

The Agilent 5973 inert was tuned using the automatic DFTPP target tune, as required by some Government methods. After tuning, the emission current was manually set to 25 µamp. This was done to maximize linearity for easily ionized compounds. The sampling rate was changed from the default of 2 to 1, while preserving sufficient sensitivity. The resultant 5.92 scans/s yields a minimum of eight data points across the narrowest peaks.

Results

The system was calibrated at eight levels, 5, 10, 20, 50, 80, 120, 160, and 200 ppm. The total ion chromatogram (TIC) for the 5-ppm level is shown in Figure 1. Each calibration level contained 77 compounds together with six internal standards (ISTDs) at 40 ppm.

The relative response factor (RRF) was calculated automatically for each compound by the GC/MSD ChemStation software. Linearity was determined by calculating the percent relative standard deviation (%RSD) of the RRFs across the calibration range for each compound and was performed automatically by the software in conjunction with Microsoft® Excel.




Figure 1. Five ppm each 77 semivolatiles and six ISTDs at 40 ppm each.

There are published Government Methods, such as USEPA Method 8270D for Semivolatiles, that specify criteria for suitable RRFs and %RSD. In Method 8270D, minimum system performance of four active compounds, the system performance check compounds (SPCCs) is measured by the average RRF.

Table 2 lists the Method 8270D SPCC criteria, and performance of the Agilent 5973 inert together with an Agilent 5973 system. The Agilent 5973 inert data exceeds the 8270D criteria. The Agilent 5973 inert also shows exceptional results compared to the Agilent 5973. These results are superior because they were run 10:1 split, putting 10× less compound on column than those run on the Agilent 5973.

Table 2. SPCCs, Comparison of Average RRF

	8270D Criteria	Agilent 5973 inert	Agilent 5973
Calibration range, ppm		0.5–20	5–160
N-Nitroso-di-n-propyl amine	0.050	1.146	0.970
Hexachlorocyclopentadiene	0.050	0.284	0.253
2,4-Dinitrophenol	0.050	0.188	0.075
4-Nitrophenol	0.050	0.236	0.162

Linearity is shown in Table 3. The 77 compounds were grouped as indicated. The RSDs of the RRFs were averaged to show performance for entire compound classes, not just a few selected analytes. The linearity of the Agilent 5973 inert is significantly better than the Agilent 5973 across the same concentration range and across an extended range.

Table 3. Average RSDs of RRFs by Compound Class

	Agilent 5973 inert	Agilent 5973 inert	Agilent 5973
Calibration range, ppm	0.5–20	2–16	20–160
Miscellaneous base neutrals (19)	8	5	11
Acids (17 phenols, dinitrophenols)	8	5	11
Bases (12)	8	6	12
Phthalates, ethers (13)	9	6	12
PAHs (16)	7	5	8

Conclusions

The Agilent 6890/5973 inert shows improved response for active compounds such as nitrophenols at low levels. This improved response gives better linearity across the calibration range. Split injections are now possible while maintaining sufficient response and fast analysis can be done using 100- μ m columns. Analysis of 77 analytes and six ISTDs can be accomplished in less than 8 minutes over an extended calibration range of 0.5 ppm to 20 ppm.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Microsoft® is a U. S. registered trademark of Microsoft Corporation.
Siltek™ is a trademark of the Restek Corporation.

© Agilent Technologies, Inc. 2003

Printed in the USA
October 29, 2003
5989-0207EN



Agilent Technologies



Solid-phase Extraction and Retention-Time Locked GC/MS Analysis of Selected Polycyclic Aromatic Hydrocarbons (PAHs)

Application

Environment

Author

Harry Prest
Agilent Technologies, Inc.
1601 California Ave
Palo Alto, CA 94304
USA

Abstract

Many of the compounds referred to as polycyclic aromatic hydrocarbons have been characterized as carcinogens, mutagens and teratogens. Therefore the presence of polycyclic aromatic hydrocarbons in water is regulated and monitored around the world by environmental agencies. Determinations of aqueous levels of polycyclic aromatic hydrocarbons typically employ solid phase extraction which offers a simplified approach to the concentration of compounds present at trace levels in water. This work describes the application of Retention-Time Locking (RTL) to the determination of polycyclic aromatic hydrocarbons by GC/MS. Thirty-five common, native polycyclic aromatic hydrocarbons, and 27 surrogate polycyclic aromatic hydrocarbons are characterized under RTL conditions on the DB-5ms column in a runtime of less than 18 minutes. Using this RTL-GC/MS method, spike and recovery experiments were conducted at 50 ppt using 16 common (U.S. EPA listed) polycyclic aromatic hydrocarbons and solid-phase extraction with the AccuBond® ODS-C18 cartridge. The method allows a 1 L water sample to be processed in less than 50 minutes using the ODS-C18 cartridge with analyte reproducibilities and accuracy better than 5% at 50 ppt. Description is given of a tube heater concentration technique which was used to condense and solvent exchange the ODS-C18 dichloromethane eluant

into isooctane. This method has advantages over nitrogen blow-down in reducing time and labor as well as the potential for recovering the dichloromethane to prevent its release.

Introduction

Polycyclic aromatic hydrocarbons (PAHs) are ubiquitous in the environment. Both naturally occurring and man-made PAHs appear to have similar origins; pyrolytic transformation of organic materials. During the European industrial revolution, coal replaced wood as a fuel source and Dr. Percival Pott (1775) connected the testicular cancers appearing in English chimney sweeps to their exposure to soot (the combustion product). More recent work has demonstrated the carcinogenic, mutagenic and teratogenic behavior of many of the PAHs. In view of this, PAHs are considered compounds of concern by every environmental organization and, to protect human health and the ecosystem, their concentrations in waters are strictly regulated.

The colloquial terms “polycyclic aromatic hydrocarbons”, “polynuclear aromatic hydrocarbons”, etc., have been used to refer to this group of fused, unsaturated rings that may or may not contain other elements beyond carbon and hydrogen, such as sulfur or nitrogen. Strictly speaking, only structures following Hückel’s $4n+2$ rule should be considered aromatic so a more appropriate term for this class of compounds would be benzenoid hydrocarbons. In view of the widespread use of the term “PAHs”, that abbreviation will be used herein as the generic term for this class of compounds.



Agilent Technologies

The PAHs selected for extraction studies are those of the minimal list of 16 PAHs designated as “priority pollutants” and regulated by the U.S. Environmental Protection Agency (EPA). Table 1 lists the compounds and some of their properties. This wide range in PAH properties, especially volatility and solubility, makes consistent extraction and concentration difficult. The higher molecular weight PAHs tend to be insoluble and readily adsorbed on surfaces. The lower molecular weight compounds tend to be volatile and readily lost during concentration steps. It is worth noting the extremely low solubilities, (i.e., sub-ppb) of the larger multi-ring PAHs when contemplating spike and recovery experiments.

A more expanded list of PAH compounds is characterized by Retention Time Locking (RTL) in this work [1-3]. The more expanded list contains PAHs likely to be encountered by extraction of typical environmental samples and will assist analysts in the identification of additional isomers that may be misidentified without the use of RTL. This method should also serve as a framework to build a larger and more complete analytical list by

adding those components that are routinely appearing in samples. For example, the retention time and ions for 2,3,5-trimethylnaphthalene are included and intended to represent the C₃-naphthalenes in general. Extension of the extraction methodology to these additional compounds is straightforward.

In view of the comments on the range of PAH properties, extensive use is made, and should be made of deuterated surrogates or carbon-13 labeled internal standards for the PAHs. PAH properties vary greatly between isomers and even within isomers. For example, personal experience has shown calculated amounts of methyl-naphthalenes will be over-estimated if a correction by d₃-naphthalene surrogate recoveries is applied. Similarly, anthracene and phenanthrene, and other higher-ring isomers have different behaviors, especially with respect to their photochemical stability, and require individual deuterated surrogates. These improvements in the analytical method allow full advantage of the additional dimension of information that mass spectrometry provides and results in higher quality data

Table 1. Physicochemical Properties of the 16 US EPA "Priority Pollutant" PAHs [4]

Compound	CAS Number	Molecular formula	Nominal molecular mass	log ₁₀ K _{ow}	Henry's Law constant (Pa m ³ /mol)	Aqueous solubility mg/L (25 °C)
Naphthalene	91-20-3	C ₁₀ H ₈	128	3.4	49	30
Acenaphthene	83-32-9	C ₁₂ H ₁₀	154	3.9	6.4	3.9
Acenaphthylene	208-96-8	C ₁₂ H ₈	152	4	11.4	3.9
Fluorene	86-73-7	C ₁₃ H ₁₀	166	4.2	10	2
Phenanthrene	85-01-8	C ₁₄ H ₁₀	178	4.5	4	1.2
Anthracene	120-12-7	C ₁₄ H ₁₀	178	4.6	16	0.07
Fluoranthene	206-44-0	C ₁₆ H ₁₀	202	5.2		0.26
Pyrene	129-00-0	C ₁₆ H ₁₀	202	5.2	6	0.13
Benzo[a]anthracene	56-55-3	C ₁₈ H ₁₂	228	5.9		0.01
Chrysene	218-01-9	C ₁₈ H ₁₂	228	5.7		0.002
Benzo[b]fluoranthene	205-99-2	C ₂₀ H ₁₂	252	6.2	3.55	0.014
Benzo[k]fluoranthene	207-08-9	C ₂₀ H ₁₂	252	6.2		0.008
Benzo[a]pyrene	50-32-8	C ₂₀ H ₁₂	252	6		0.004
Indeno[1,2,3-cd]pyrene	193-39-5	C ₂₂ H ₁₂	276			
Dibenzo[a,h]anthracene	53-70-3	C ₂₂ H ₁₄	278	6.2		.0005
Benzo[g,h,i]perylene	191-24-2	C ₂₂ H ₁₂	276	7		.00026

Experimental

PAH standards were obtained as mixtures from a number of sources. The 16 PAHs for the spike and extraction studies were obtained from Ultra Scientific (North Kingston, RI). Deuterated PAHs were purchased from Cambridge Isotope Laboratories (Andover, MA). Dilutions were made in acetone or isooctane (pesticide grade, VWR Scientific, San Francisco, CA) appropriate to their purpose as spikes and surrogates or standards and injection internal standards, respectively. Dichloromethane, hexane and methanol for SPE elution and conditioning also were of pesticide grade. Sodium sulfate (analytical grade, VWR Scientific, San Francisco, CA) was kilned at 500 °C and stored in a vacuum bottle and desiccator.

Empty 6-mL cartridges and frits were obtained from Agilent Technologies Inc. (Wilmington, DE) for use as drying cartridges. AccuBond^{II} ODS-C18 Cartridges containing 500 milligrams of octadecyl sorbent in a 6-mL cartridge were obtained from Agilent Technologies Inc. (Wilmington, DE). A summary of the equipment and consumables is given in Table 2.

Table 2. Equipment and Consumables Summary

Component	Agilent part number
Silanized amber vials	5183-4496
Vial crimp caps	5181-1210
AccuBond ^{II} ODS-C18 (500 mg)	188-1356
6-mL cartridge, box of 30	
Empty SPE cartridges reservoirs, 6 mL, box of 50	700-4006
Frits for 6-mL cartridges reservoirs, 100/pk	700-4031
Stopcock valves, 10/pk	5185-5758
SPE Manifold, 10-port	5185-5754
SPE Manifold, 20-port	5185-7565

Solid-phase Extraction Experiments

For an initial demonstration of the accuracy and precision of the ODS-C18 extraction approach, a 1.0 L deionized, reverse osmosis (RO) water sample was spiked with the 16 PAHs at 50 ng/L or 0.05 ppb (as 25 µL of 2 ng PAHs/µL acetone). Deuterated PAHs corresponding to each of the 16 PAHs were added at 250 ng/L as recovery surrogates (as 50 µL of 5 ng d_x-PAHs/µL acetone). “Calibrators” were also made at that time by adding the spike and surrogates to an amber GC vial.

The ODS-SPE cartridge was conditioned by sequentially rinsing with three cartridge volumes of dichloromethane (DCM), hexane, methanol, and RO water. At no time after the initial addition of DCM was the SPE column allowed to run dry.

The 1 L water sample was then pulled through the SPE cartridge at a flow between 20 and 25 mL/min such that the sample was processed in less than 50 minutes. The SPE cartridge was dried briefly by drawing clean laboratory air through the cartridge for about 5 minutes while occasionally tapping the cartridge body to dislodge bound water. DCM rinses were made of the amber sample bottle and applied to elute the cartridge. The SPE cartridge was eluted with approximately 8 to 9 mL of DCM. The DCM eluant was dried using a cartridge filled with anhydrous sodium sulfate.

At this stage the usual approach is to condense the DCM eluant to 1-mL final volume by nitrogen blow-down. However in this work the dried DCM eluant was condensed and solvent exchanged into isooctane by use of a tube heater. This process is described in Appendix 1. Samples and calibrators were adjusted to 1 mL with isooctane and spiked to 20 ng dibromooctafluorobiphenyl/mL (as 10 µL of 2 ng/µL isooctane) which served as the injection internal standard.

A method blank, the calibrators and samples were then analyzed using an Agilent 6890 Plus GC and 5973N MSD according to operating parameters listed in Table 3. A press-fit connector joined the DB-5ms capillary column to a 5-meter uncoated, deactivated guard column.

Table 3. GC Injection, Oven and MSD Parameters

Injection parameters for isooctane		
Injection mode	Pulsed splitless	
Injection volume	2 µL	
Injection port temperature	275 °C	
Pulse pressure and time	25.0 psi	0.25 min
Purge flow and time	50.0 mL/min	0.75 min
Gas saver flow and time	20.0 mL/min	3.00 min

DB-5ms Column and oven parameters for isooctane		
GC column	DB-5ms (30 m × 0.25 mm id, 0.25 µm) (Part no.: 122-5532) with 5 m deactivated precolumn (0.25 mm id)	
Flow and mode	1.3 mL/min	Constant flow
Detector and outlet pressure	MSD	Vacuum
Oven temperature program	80 °C	1.00 min
20.00 °C/min	115 °C	1.00 min
10.00 °C/min	130 °C	0.00 min
25.00 °C/min	295 °C	0.25 min
1.00 °C/min	300 °C	0.00 min
30.00 °C/min	340 °C	0.00 min
Oven equilibrium time	0.50 min	
Total program time	18.43	
MSD Transfer line temp	325 °C	
Injection parameters for dichloromethane		
Injection mode	Pulsed splitless	
Injection port temperature	275 °C	
Pulse pressure and time	25.0 psi	0.25 min
Purge flow and time	50.0 mL/min	0.75 min
Gas saver flow and time	20.0 mL/min	3.00 min

Table 3. GC Injection, Oven and MSD Parameters (continued)

DB-5ms Column and oven parameters for dichloromethane

GC column	DB-5ms (30 m × 0.25 mm id, 0.25 µm) (Part no.: 122-5532) with 5-m deactivated precolumn (0.25 mm id)	
Flow and mode	1.3 mL/min	Constant flow
Detector and outlet pressure	MSD	Vacuum
Oven temperature program	40 °C	0.48 min
33.00 °C/min	115 °C	1.00 min
10.00 °C/min	130 °C	0.00 min
25.00 °C/min	295 °C	0.25 min
1.00 °C/min	300 °C	0.00 min
30.00 °C/min	340 °C	0.00 min
Oven equilibrium time	0.50 min	
Total program time	18.43	
MSD Transfer line temp	325 °C	

Mass spectrometer parameters

Tune parameters	Autotune
Electron multiplier voltage	Autotune +400V
Solvent delay	5.00 min
Scan parameters	50–300 <i>m/z</i>
Quadrupole temperature	150 °C
Source temperature	230 to 250 °C

Miscellaneous parts

Septa	5182-0739	BTO septa (400 °C)
Liner	5181-3315	Deactivated 4 mm id double taper
GC Column ferrule	5181-3323	250 µm Vespel/graphite
MSD Interface ferrule	5062-3508	0.4 mm id preconditioned Vespel/graphite

Results

In general, PAH analysis requires that samples and standards be protected from light by use of amber vials, foil, etc., and should take place under “gold” lamps due to the potential for photochemical

destruction by fluorescent lamps and/or sunlight. Figure 1 illustrates the importance of this issue raised in the Introduction. Although gold lamps were not available in this particular laboratory, as many precautions as possible were taken to avoid photochemical losses.




Figure 1. Illustration of photochemical degradation of selected PAHs. Total ion chromatograms (TICs) for benzo[a]pyrene (upper) and benzo[g,h,i]perylene (lower) in PAH standards stored in a clear vial, amber vial and from a master standard. The clear vial and amber vial were left in the laboratory in ambient light for several days then injected with a master standard that was stored at 4 °C until just prior to injection. The master and amber vial TICs for the analytes are essentially identical and overlap. The analyte TIC for the clear vial is visibly reduced in intensity. The losses are significant - on the order of 20% and 25%, respectively.

Gas Chromatography

A first concern is chromatography. Figure 2 shows a total ion chromatogram for selected PAHs under locked conditions. D₁₀-phenanthrene, a surrogate present in both samples and standards was chosen as the “locking compound” and was locked to elute at 9.750 minutes. Notice the run time is quite short; benzo[g,h,i]perylene elutes in less than 17.5 minutes. Besides allowing higher oven temperatures at injection, isooctane has several other features that make it superior to DCM as a solvent. At a high injector temperature, which is preferred for PAH

analysis, DCM expands to 2.5 times the volume of isooctane and can overflow the liner if not (carefully) injected using pressure pulsing or ramped flow injection. Isooctane is a better “keeper” and storage solvent than DCM which is highly volatile and requires almost immediate re-sealing after injection. DCM rapidly “extracts” a pierced septum on the vial to create a “silicone” series in subsequent injections of the sample unless a pure Teflon septum is used (which is usually impractical). Evaporation of DCM by nitrogen blowdown is labor intensive as opposed to the tube heater approach used here.




Figure 2. Total ion chromatogram of more than 50 PAHs injected from isooctane.

However, injecting from DCM is widely performed so a GC method with similar run time and program was created using the fast ramping available with either the 240-V oven or the oven insert for the standard oven (Agilent part no. G2646-60500). There are some minor shifts in retention times but the locking compound and overall runtime are maintained. The injection port temperature used

here (275 °C) represents a compromise for the DCM injection. As mentioned earlier, a higher temperature can be used with isooctane, which is attractive for the higher ring PAHs and port cleanliness. The locked PAH retention times and nominal quantitation and qualifying ions are listed in Table 4 for both the isooctane and dichloromethane solvent GC programs.

Table 4. The PAH compound list, locked retention time for the isooctane and dichloromethane GC programs, and nominal values of relevant MS ions. The RTL compound is d₁₀-phenanthrene and locked at 9.750 under both programs. Compound RTs are ±0.006 min maximum. The first MS ion for each compound is the quantitation ion.

Compound	Isooctane program	DCM Program	Quantitation ions (<i>m/z</i>)
D ₈ -naphthalene	5.513	5.770	136, 137
¹³ C ₆ -naphthalene	5.560	5.800	134, 133, 132, 135
Naphthalene	5.556	5.800	128, 127, 129
Benzo[b]thiophene	5.645	5.870	134, 135, 136, 89
D ₁₀ -2-methylnaphthalene	6.623	6.740	152, 150
2-methylnaphthalene	6.673	6.790	142, 141
D ₁₀ -1-methylnaphthalene	6.763	6.870	152, 150
1-methylnaphthalene	6.816	6.920	142, 141
D ₁₀ -biphenyl	7.318	7.390	164, 162
Biphenyl	7.350	7.410	154, 153
D ₁₂ -2,6-dimethylnaphthalene	7.497	7.560	168, 150
1-ethylnaphthalene	7.486	7.550	141, 156
1,2-dimethylnaphthalene	7.658	7.710	156, 141
D ₁₈ -hexamethylbenzene	7.726	7.770	162, 180
D ₁₀ -acenaphthylene	7.877	7.920	160, 158
Acenaphthylene	7.895	7.940	152, 151
D ₁₂ -1,8-dimethylnaphthalene	7.515	8.040	168, 150
D ₁₀ -acenaphthene	8.078	8.110	164, 162
Acenaphthene	8.117	8.150	153, 154
4-methylbiphenyl	8.153	8.180	168, 167
D ₈ -dibenzofuran	8.303	8.330	176, 146
2,3,5-trimethylnaphthalene	8.582	8.600	170, 155
D ₁₀ -fluorene	8.694	8.710	176, 174
Fluorene	8.729	8.730	166, 165
Dibromooctafluorobiphenyl	9.060	9.070	296, 227, 278
1-methylfluorene	9.371	9.380	165, 180
D ₈ -dibenzothiophene	9.622	9.620	192, 193
Dibenzothiophene	9.643	9.640	184, 139
D ₁₀ -phenanthrene	9.751	9.750	188, 189
¹³ C ₆ -phenanthrene	9.770	9.770	184, 182, 183, 185
Phenanthrene	9.775	9.770	178, 176
D ₁₀ -anthracene	9.811	9.810	188, 189
Anthracene	9.829	9.830	178, 176
2-methylphenanthrene	10.309	10.310	192, 191, 189
9-methylanthracene	10.563	10.560	192, 191, 189
3,6-dimethylphenanthrene	10.735	10.740	206, 191, 189
D ₁₀ -fluoranthene	10.976	10.970	212, 211
Fluoranthene	10.993	10.990	202, 200

Table 4. Continued

Compound	Isooctane program	DCM Program	Quantitation ions (<i>m/z</i>)
D ₁₀ -pyrene	11.201	11.200	212, 211
Pyrene	11.223	11.220	202, 200
1-methylpyrene	11.440	11.440	216, 215, 213, 217
Benzo[b]naptho[2,1-d]thiophene	12.179	12.180	234, 235, 232
D ₁₂ -benz[a]anthracene	12.423	12.410	240, 236
Benz[a]anthracene	12.451	12.450	228, 226
D ₁₂ -chrysene	12.459	12.450	240, 236
¹³ C ₆ -chrysene	12.490	12.490	234, 232, 233, 235
Chrysene	12.491	12.490	228, 226
D ₁₂ -benzo[b]fluoranthene	13.849	13.830	264, 263, 265
Benzo[b]fluoranthene	13.888	13.870	252, 250, 253
D ₁₂ -benzo[k]fluoranthene	13.899	13.880	264, 263, 265
Benzo[k]fluoranthene	13.934	13.910	252, 250, 253
D ₁₂ -benzo[a]pyrene	14.390	14.370	264, 265, 263
Benzo[e]pyrene	14.343	14.310	252, 250, 253
Benzo[a]pyrene	14.432	14.410	252, 250, 253
D ₁₂ -perylene	14.529	14.510	264, 265
Perylene	14.576	14.550	252, 250, 253
3-methylcholanthrene	15.088	15.060	268, 252
D ₁₂ -indeno[1,2,3-c,d]pyrene	16.710	16.740	288, 289
Indeno[1,2,3-c,d]pyrene	16.775	16.740	276, 277, 274
D ₁₄ -dibenz[a,h]anthracene	16.764	16.730	292, 293
Dibenz[a,h]anthracene	16.847	16.810	278, 276, 274
D ₁₂ -benzo[g,h,i]perylene	17.338	17.310	288, 289
Benzo[g,h,i]perylene	17.402	17.370	276, 277, 274

There are several closely eluting PAHs which can convolute quantitation. For the 16 PAHs, there are four “critical pairs”: phenanthrene and anthracene; benzo[a]anthracene and chrysene; benzo[b]fluoranthene and benzo[k]fluoranthene; and indeno[1,2,3-c,d]pyrene and dibenzo[a,h]anthracene. The first three of these critical pairs involve isomers, so a conflict between the common quantitation ions (for example, the most intense ions) is the issue, while the last pair involves a conflict between the quantitation ion and a confirmation ion. GC programs can be used to completely resolve these components but this requires slow oven ramps and consequently long method run times (approximately 30 to 40 minutes). The method developed here aims at a compromise between resolution and run time. The resulting

resolution under this method for the 4 critical pairs at 1 ng injected are shown in Figures 3, 4, 5, and 6. Note that the required resolution for accurate quantitation is always a function of the analyte amounts and related to column capacity. It is possible to overwhelm a nearby peak when large analyte concentration disparities exist [5]. As long as analyte concentrations remain below a few nanograms, the resolution should be sufficient. For this method, only the integration of the last critical pair, especially the surrogate, d₁₂-indeno[1,2,3-c,d]pyrene, needs to be carefully policed. If issues arise, quantitating on peak height may provide some improvement. Increased sensitivity available through RTL-GC/MS selected-ion-monitoring is easy to implement and will improve detection limits [6].




Figure 3. Total ion chromatogram showing resolution of phenanthrene and anthracene at 1 ng each. Calculated resolution for the valley for the common 178 m/z ion = 99%.




Figure 4. Total ion chromatogram showing resolution of benz[a]anthracene and chrysene at 1 ng each. Calculated resolution for the valley for the common 228 m/z ion = 95%.




Figure 5. Total ion chromatogram showing resolution of benzo[b]fluoranthene and benzo[k]fluoranthene at 1 ng each. Calculated resolution for the valley for the common 252 m/z ion = 84%.




Figure 6. Total ion chromatogram showing resolution of indeno[1,2,3-cd]pyrene and dibenzanthracene at 1 ng each. Calculated resolution for the valley for the total ion current = 80%.

ODS-SPE Spike and Recovery Experiments

Table 5 shows the results for five ODS-SPE experiments at 50 ppt using the tube heater concentrator. There is good sensitivity in scan and the SPE surrogate recoveries averaged 77% ($\pm 3\%$). Accuracy was also very good with the average deviation from the expected value of 5%. Even naphthalene showed a high average recovery (70%) with good precision for both the surrogate ($\pm 6\%$) and the native ($\pm 2\%$). Anthracene was the only outlier

showing slightly elevated values due to disproportionate loss of the d_{10} -surrogate. The data seems to suggest there may be a slight systematic error for a few of the analytes most likely due to spiking at these low levels.

Detection limits can be improved through RTL-GC/MS with selected-ion-monitoring which is easy to implement through the newly developed AutoSIM software [6].

Table 5. Results for five ODS-C18 SPE spike and recovery experiments at 50 ppt. Deuterated surrogates appear in the table just prior to the analyte they correct. The average deuterated surrogate recoveries are given under the "Average Recovery" heading as percent recovery and the relative standard deviation (RSD) in the surrogate is given under "RSD". For the native PAHs, the average amount of the five determinations is given next to the analyte as ng/L or ppt in the "Average" column followed by the RSD for the native value (precision). The "Average deviation" gives the average absolute deviation from the true value of 50 ppt as percent and indicates the degree of accuracy.

Surrogate compound	Average recovery (%)	RSD (%)	Native compound	Average (ng/L)	RSD (%)	Average deviation (%)
d_8 -naphthalene	70	3	Naphthalene	53	2	6
d_{10} -acenaphthylene	80	4	Acenaphthylene	51	2	2
d_{10} -acenaphthene	77	5	Acenaphthene	53	3	5
d_{10} -fluorene	78	5	Fluorene	54	3	8
d_{10} -phenanthrene	79	5	Phenanthrene	53	1	5
d_{10} -anthracene	71	5	Anthracene	57	4	13
d_{10} -fluoranthene	81	4	Fluoranthene	52	2	5
d_{10} -pyrene	81	5	Pyrene	52	2	4
d_{12} -benz[a]anthracene	79	6	Benz[a]anthracene	52	3	4
d_{12} -chrysene	77	6	Chrysene	52	1	4
d_{12} -benzo[b]fluoranthene	80	7	Benzo[b]fluoranthene	52	1	5
d_{12} -benzo[k]fluoranthene	79	10	Benzo[k]fluoranthene	52	2	5
d_{12} -benzo[a]pyrene	74	7	Benzo[a]pyrene	52	5	4
d_{12} -indeno[1,2,3-c,d]pyrene	77	5	Indeno[1,2,3-c,d]pyrene	50	4	1
d_{14} -dibenz[a,h]anthracene	77	8	Dibenz[a,h]anthracene	48	4	4
d_{12} -benzo[g,h,i]perylene	77	8	Benzo[g,h,i]perylene	50	4	0.3

Summary

The retention-time locked GC/MS method for PAHs presented here provides sufficient separation for good quantitation in under 18 minutes. More than 60 PAHs and their common surrogates are characterized under RTL conditions to assist in unknown PAH identification.

AccuBond^{II} ODS-C18 cartridges demonstrate reproducibility and accuracy better than 5% for extraction of the 16 PAHS of the U.S. EPA at 50 ppt in water (0.05 µg/L). Using a tube heater for concentration and solvent exchange to isooctane provides a better injection and storage solvent than dichloromethane, allows more rapid processing with less effort than nitrogen blowdown with the opportunity to recover vaporized solvent.

References

1. D. Agnew, et al., Retention Time Locking with the G1701BA MSD Productivity ChemStation, Agilent Technologies, (23), 5968-3433E.
2. V. Giarrocco, B. Quimby, and M. Klee, Retention Time Locking: Concepts and Applications, Agilent Technologies, 5966-2469E, www.chem.agilent.com/scripts/Literature-Search.asp

3. H. Prest, and P. Cormia, Retention Time Locking: Advantages in GC/MS SIM Analysis, Agilent Technologies, Application Brief (23), 5967-3797E, www.agilent.com/chem
4. D. Mackay, W.Y. Shiu, and K.C. Ma, Illustrated Handbook of Physical-Chemical Properties and Environmental Fate for Organic Chemicals: Polynuclear Aromatic Hydrocarbons, Polychlorinated Dioxins, and Dibenzofurans. 1st ed. Vol. 2. 1992, Chelsea, Michigan: Lewis.
5. J. W. Dolan, Peak Tailing and Resolution. LCGC, 2002. 20 (5): p. 430-436.
6. H. Prest, and D.W. Peterson, New approaches to the development of GC-MS selected ion monitoring acquisition and quantitation methods, Agilent Technologies, 5988-4188EN, www.agilent.com/chem

Acknowledgements

The author gratefully acknowledges Angelica Reese and Cameron George for their assistance with column procurement. He is also indebted to Phil Wylie for his editorial comments and assistance.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Appendix 1.

Concentrating Dichloromethane Using a Tube Heater

Harry Prest, Senior Applications Chemist, Agilent Technologies

CAUTION

This method is ONLY to be applied to dichloromethane and is to be executed by skilled chemists! Other organic solvents are very flammable and must NOT be used.

This operation MUST be performed in a hood with all flames extinguished!

Agilent Technologies shall not be liable for any consequences or damages in connection with this method or material.

Motivation

Dichloromethane is a widely used solvent. SPE, size-exclusion chromatography (SEC) and open column chromatography (silica, alumina or Florsil) fractions can often be completely dichloromethane. Concentrating dichloromethane and retaining the more volatile compounds is always problematic. A variety of approaches are possible such as rotovap or nitrogen blowdown or others. Most methods require considerable expertise and attention to perform well. The method described here is simple, rapid, rugged, inexpensive, requires very little operator intervention, allows for convenient solvent exchange, and can be modified to collect the vaporized dichloromethane. Further, a number of samples can be rapidly concentrated at a single time. This method has been successfully applied in the author's laboratory at the University of California Santa Cruz to 50 mL volumes of dichloromethane from SEC. Recoveries are very good even for typically difficult compounds such as naphthalene, the hexachlorocyclohexanes, hexachlorobenzene and others.

Summary

This appendix describes the procedure for concentrating dichloromethane and exchanging into isooctane using a tube heater. One milliliter of isooctane and two Teflon boiling chips are added to approximately 10 mL (± 1 mL) of dichloromethane (DCM) in a 16 mm $\times$ 125 mm test tube. The tube is placed in the aluminum tube heater manifold (at 77 °C) and allowed to boil until the only the isooctane “keeper” remains, approximately 20 to 30 mins. Transfer to GC vial with isooctane as routinely performed.

Materials

Test tubes 16 $\times$ 125 mm or 16 $\times$ 100 mm (check fit of tubes to heater manifold holes prior to use)

Blanked isooctane and dichloromethane

Solvent rinsed Teflon Boiling chips

Aluminum manifold for Kontes Tube Heater pre-drilled for 16 mm tubes

Glass “chimneys” to fit tubes

Procedure

1. Extinguish all flames in the laboratory or objects that may create a spark. Place the tube heater in the hood and pre-heat the manifold to 77 °C ± 3 °C.
2. Add ~ 1 mL of isooctane and two solvent rinsed boiling chips to the test tube containing the DCM fraction. In this case, about 10 mL of DCM.
3. Place tube in the pre-heated aluminum tube heater manifold (77 °C ± 3 °C). Place glass “chimney” around the tube. This MUST be done in a fume hood.
4. Allow tube to boil. Do not remove from heater until condensed. When a very small amount of boiling is all that remains, remove tube from heater. There will be about $\frac{1}{2}$ mL of isooctane left.
5. After cooling, transfer with isooctane to GC vial and adjust volume.

Remarks

This method is tailored to eliminate some acetone and the majority of DCM and exchange into isooctane “keeper”. It is not possible to eliminate all the DCM or acetone. If the tubes are removed too early and some DCM remains, early eluting analytes will show some chromatographic indications that this is the case such as eluting slightly earlier than expected versus standards in pure isooctane, etc.

Modifying the glass chimney to a condenser design will allow collection of the DCM with very high efficiency and has the added benefit of minimizing cross contamination. In fact, micro-scale organic glassware can be easily modified for this purpose.

Validation

Using the GC/MS parameters described in the accompanying application note, the tube heater concentration method was validated using 16 PAHs and their deuterated surrogates. Ten milliliters of DCM was spiked with 250 ng of deuterated PAH surrogates and 50 ng of native PAHs. After tube heater concentration and exchange into isooctane, transfer was made into amber GC vials and the volume adjusted to 1 mL. Dibromooctafluorobiphenyl was used as an injection internal standard. Analyte concentrations were corrected by their corresponding surrogate. At these concentrations, recoveries were essentially 100% for all PAHs and greater than 95% for naphthalene.

Table A1 cites the reproducibility and accuracy (as average absolute deviation from 50 ng) for trials on 2 different days. In general, accuracy and reproducibility is better than 5% and essentially limited by integration error.

Table A1. Surrogate corrected accuracy and reproducibility for 16 PAHs at 50 ng for trials on 2 separate days. Relative standard deviation (RSD) and accuracy is the average absolute deviation from 50 ng expressed as percent. The number of trials is given by n.

Compound	Trial no. 1		Trial no. 2	
	Percent accuracy (n=5)	Percent RSD (n=5)	Percent accuracy (n=6)	Percent RSD (n=6)
Naphthalene	1.8	2.3	1.8	1.6
Acenaphthylene	2.6	3.4	1.0	1.2
Acenaphthene	1.4	1.8	1.3	0.7
Fluorene	1.2	1.3	1.6	1.5
Phenanthrene	2.4	2.4	2.2	2.3
Anthracene	4.4	5.0	2.3	1.9
Fluoranthene	1.6	2.5	1.1	1.3
Pyrene	1.9	2.6	0.8	1.0
Benz[a]anthracene	4.9	1.8	3.1	1.0
Chrysene	2.8	3.0	1.3	1.7
Benzo[b]fluoranthene	3.2	3.8	1.9	2.6
Benzo[k]fluoranthene	3.0	2.5	1.7	2.4
Benzo[a]pyrene	5.8	5.5	2.2	2.7
Indeno[1,2,3-c,d]pyrene	2.0	2.2	4.6	5.7
Dibenz[a,h]anthracene	3.0	4.3	4.1	3.0
Benzo[g,h,i]perylene	3.7	3.0	1.6	2.4





Figure A1. Tube heater apparatus.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
July 12, 2002
5988-7150EN



Solid-Phase Extraction and Gas Chromatography/Mass Spectrometry Analysis of Selected Phenols

Application

Environmental

Authors

Angelica A. Reese
Agilent Technologies, Inc.
91 Blue Ravine Road
Folsom, CA 95630
USA

Harry Prest
Agilent Technologies, Inc.
1601 California Ave
Palo Alto, CA 94304
USA

Abstract

Solid-phase extraction offers a simplified approach to the concentration of compounds present at trace levels in water. Polymeric resins, such as polystyrene-divinylbenzene, offer advantages over the commonly used octadecyl and similar silica-substrate solid-phase extraction adsorbents, especially for more polar compounds. Recently Agilent Technologies has expanded its offering of solid-phase extraction products to include a polystyrene-divinylbenzene solid-phase extraction material specifically for environmental applications, the AccuBond® ENV cartridge. Using the retention time locked gas chromatography/mass spectrometry analytical method previously described [1], this note makes an initial demonstration of the accuracy and precision that can be achieved for selected phenols at 10 ppb in water using this polystyrene-divinylbenzene solid-phase extraction material. The solid-phase extraction procedure is rapid, uses reduced drying times, and requires only two surrogates. The cartridge design has been optimized to provide increased recoveries for phenol, which

typically has low and irreproducible recoveries. Recoveries for phenol exceeded 70% and other phenols were greater than 90%. Precision was better than 5% and accuracy, as indicated by average absolute deviation as percent, was better than 8% for all phenols except 2-cyclohexyl-2,4-dinitrophenol. Sample delivery rate is high (20 to 25 mL/min) so a 1-liter sample can be extracted in less than an hour.

Introduction

Solid-phase extraction (SPE) has evolved to be a powerful tool for isolation and concentration of trace analytes in a variety of sample matrices. SPE has grown to replace liquid/liquid extraction due to the minimal use of solvent, the simplicity and flexibility of the approach, and the increased selectivity for analytes available. Beginning in and throughout the last decade, a large number of SPE applications were developed for compounds in matrices of environmental interest. The major focus of these applications was the collection and concentration of trace analytes from water. Most of the analytes were non-polar and strongly hydrophobic in nature such as polychlorinated biphenyls (PCBs), the organochlorine pesticides, polynuclear aromatic hydrocarbons (PAHs), for example, as these were relatively easy candidates for the technique and of widespread concern. More polar compounds like the phenols offer particular challenges.

SPE exploits the similarity in physicochemical properties of a class of analytes, their interaction with the SPE material, and their differences from the matrix. The phenols encompass a wide range in polarities and solubilities as shown in Table 1.



Agilent Technologies

The pKa values indicate that the dinitrophenol and the tetra- and penta-chloro phenols are fairly acidic and therefore are predominately dissociated in water at near-neutral pHs. Acid-base equilibrium considerations require that the water sample be acidified to at least 2 pH units below that of the lowest pKa value(s) to generate phenols primarily in their non-ionized form. Octanol-water partition constants (K_{ow}) and water solubilities of the undissociated compounds range over a factor of more than several thousand. The high aqueous solubilities and low K_{ow} s of phenol and the monosubstituted phenols make these the most difficult phenols to capture and retain.

Table 1. Physicochemical Properties of Some Phenols

Compound	$\log_{10} K_{ow}$	pKa	Solubility _(aq) g/L
Phenol	1.46	9.89	0.0884
4-chlorophenol	2.4	9.18	.027
4-methylphenol	1.96	10.26	.02
3-methylphenol	1.98	10	.022
4-nitrophenol	1.91	7.08	.013
2,4-dichlorophenol	3.2	7.68	.0045
2,4-dimethylphenol	2.35	10.6	.0088
2,4-dinitrophenol	1.67	4.09	.00034
2,4,6-trichlorophenol	3.69	7.42	.00043
2,3,4,6-tetrachlorophenol	4.45	5.38	.00018
Pentachlorophenol	5.05	4.92	0.000014

Polymeric resins were used early in the history of solid-phase extraction. These early materials needed extensive cleanup prior to use to avoid interferences obscuring analytes of interest. New generations of these polymers such as polystyrene-divinylbenzene (PS-DVB) have much lower backgrounds due to improvements in manufacturing processes. The use of PS-DVB polymers as an absorbent material has been demonstrated to provide improved recoveries for phenolic compounds as compared to the traditional and more commonly applied C18 material [2]. The details provided here ensure that analysts will observe less breakthrough of phenol, greatly improving overall recoveries.

The objective of this work was to develop a simple approach to SPE extraction and gas chromatography/mass spectrometry (GC/MS) analysis for selected phenols and perform a preliminary demonstration of accuracy and precision. A previous application note describes the retention-time locked GC/MS method in detail [1].

Experimental

The phenols were obtained from Ultra Scientific (North Kingstown, RI) and AccuStandard (New Haven, CT) as mixtures. Dilutions were made in acetone and in dichloromethane (Burdick and Jackson Grade, VWR Scientific, San Francisco, CA) for surrogates or spiking and standards, respectively. Sodium sulfate (analytical grade, VWR Scientific, San Francisco, CA) was kilned at 500 °C and stored in a desiccator.

Empty 6-mL cartridges and frits were obtained from Agilent Technologies Inc. (Wilmington, DE) for use as drying cartridges. AccuBond^{II} ENV PS-DVB cartridges containing 1000 milligrams of PS-DVB sorbent in a 6-mL cartridge were obtained from Agilent Technologies Inc. (Wilmington, DE). A summary of the equipment and consumables is given in Table 2.

Table 2. Equipment and Consumables Summary

Description	Part Number
Silanized amber vials	5183-4496
Vial crimp caps	5181-1210
AccuBond ^{II} ENV PS-DVB polymeric resin as 1000 mg / 6-mL cartridge, box of 30	188-3060
Empty SPE Cartridges Reservoirs, 6 mL, box of 50	700-4006
Frits for 6 mL cartridges reservoirs, 100/pk	700-4031
Stopcock valves, 10/pk	5185-5758
SPE Manifold, 10-port	5185-5754
SPE Manifold, 20-port	5185-7565

Spike and Recovery Experiments

For the initial demonstration of the accuracy and precision of the approach, 1.0 L of deionized RO water was spiked with 21 phenols at 10 pbb each. Deuterated phenol, 2,4-dibromophenol, and 2,4,6-tribromophenol were added at 10 ppb as recovery surrogates. Three “calibrators” were also made at that time by adding the spike and surrogates to a silanized vial containing some dichloromethane (DCM) as a keeper. The solution was mixed and the pH lowered to ≤ 2 with 5N HCl.

The PS-DVB SPE cartridge was conditioned by sequentially rinsing with 9 to 12 mL of DCM, 9 to 12 mL of methanol, and 9 to 12 mL of 0.05N HCl. At no time after the initial addition of DCM was the column allowed to run dry.

The 1-L water sample was then pulled through the SPE cartridge at a flow between 20 and 25 mL/min such that the sample was processed in less than 1 hour. The SPE cartridge was dried briefly by drawing clean laboratory air through the cartridge for about 2 minutes while tapping the cartridge body to dislodge bound water. The SPE cartridge was then eluted with 9 mL of DCM. The DCM eluant was dried using a cartridge filled with anhydrous sodium sulfate.

The dried DCM eluant was evaporated under dry, filtered nitrogen and transferred to a silanized amber vial. At this point, the volumes of the sample and the three calibrators were brought to approximately 0.9 mL and 100 μ L of a solution containing 2,5-dibromotoluene and 2,2',5,5'-tetrabromobiphenyl at 0.05 μ g/ μ L in DCM was added as internal (injection) standards. A solvent blank, the three calibrators and the sample were then

analyzed using an Agilent 6890 Plus GC and 5973N MSD according to operating parameters given in a previous note [1].

Results and Discussion

Corrected and uncorrected results of inter-day replicates for selected phenols are shown in Table 3. Phenol values were corrected to the deuterated phenol while all other compounds were corrected to 2,4-dibromophenol recoveries. With the exception of the 2-cyclohexyl-2,4-dinitrophenol, all RSD values and deviations are under 5% and 8%, respectively. The average RSD and absolute deviation for all the compounds are 4% and 6%, respectively. These indicate very good reproducibility and accuracy. An anomalously high value in the third trial seems to have inflated the deviation for 2-cyclohexyl-2,4-dinitrophenol.

Table 3. Spike and recovery results for accuracy and precision at 10 ppb using the AccuBond[®] ENV SPE cartridge. The average deviation is calculated as the relative average of the absolute deviations from 10 ppb and expressed as percentages. RSD represents the relative standard deviations.

Trial Number: Compound	Trial #1		Trial #2		Trial #3		RSD %	Average Deviation
	Uncorrected	Corrected	Uncorrected	Corrected	Uncorrected	Corrected		
Phenol	7.8	10.7	7.2	10.3	7.7	11.0	3%	7%
2-chlorophenol	9.8	9.3	9	8.9	10.3	9.3	3%	8%
2-methylphenol	9.9	9.4	9.1	9.0	10.5	9.5	3%	7%
3- & 4-methylphenol	9.8	9.3	9.2	9.1	10.4	9.4	2%	7%
2,4-dimethylphenol	9.9	9.4	9.4	9.3	10.5	9.5	1%	6%
2-nitrophenol	10.0	9.5	9.1	9.0	10.7	9.6	4%	6%
2,4-dichlorophenol	9.9	9.4	9.1	9.0	10.5	9.5	3%	7%
2,6-dichlorophenol	9.7	9.2	9.1	9.0	10.4	9.4	2%	8%
4-chloro-3-methylphenol	10.1	9.6	9.3	9.2	10.7	9.6	3%	5%
2,4-dibromophenol	10.5		10.1		11.1			
2,4,6-trichlorophenol	9.7	9.2	9.1	9.0	10.6	9.5	3%	7%
2,4,5-trichlorophenol	9.8	9.3	9.1	9.0	10.4	9.4	2%	8%
4-nitrophenol	10.0	9.5	9.8	9.7	11.5	10.4	4%	4%
2,3,4,5-tetrachlorophenol	9.7	9.2	9.3	9.2	10.7	9.6	3%	6%
2,3,5,6-tetrachlorophenol	9.9	9.4	9.1	9.0	10.4	9.4	2%	7%
2,3,4,6-tetrachlorophenol	9.8	9.3	9.3	9.2	10.6	9.5	2%	6%
2,4-dinitrophenol	10.6	10.1	9.8	9.7	11.9	10.7	5%	4%
2,4,6-tribromophenol	9.7	9.2	9.6	9.5	10.7	9.6	2%	5%
2-methyl-4,6-dinitrophenol	10.1	9.6	9.5	9.4	11.4	10.3	5%	4%
Pentachlorophenol	9.8	9.3	9.5	9.4	11.1	10.0	4%	4%
Dinoseb	10.2	9.7	9.4	9.3	11.5	10.4	5%	4%
2-cyclohexyl-4,6-dinitrophenol	11.2	10.7	10.6	10.5	14.4	13.0	12%	14%
2,2',5,5'-tetrabromobiphenyl	10.5	10.0	10.5	10.4	12.3	11.1	5%	5%

Typically, a 1-gram sorbent cartridge is considered an excessive use of material. However, work with 500-mg cartridges showed recoveries for phenol near and below 50%. Tandem cartridges revealed substantial phenol on the second cartridge. Increasing the polymer mass to 1 gram reduced breakthrough and consequently increased phenol recoveries. The methylphenols also demonstrated this behavior to a lesser degree and supported the change in sorbent bed mass.

Using a single surrogate to correct all the substituted phenols seems a tremendous simplification since the behavior and chemistries of the phenols differ widely. It is likely that this will become apparent at lower concentrations and most likely for the nitrophenols. Data does imply that the tetrabromobiphenyl (included in Table 3) may allow a better correction of the injection volume for the late eluters.

Conclusions

These preliminary results show that phenols can be extracted from aqueous samples accurately and precisely using AccuBond^{II} ENV PS-DVB polymeric resin. Coupled with a gas chromatographic analysis and retention time locking GC/MS [1], extraction, identification and quantitation of phenolic compounds can be done confidently, accurately and reproducibly. This method is a modification of U.S. EPA Method 528 [3]. The procedure here for the extraction of phenols from drinking water by polymeric SPE results in improved recoveries and greatly reduced drying times (2 minutes compared to 20 minutes), which increases sample throughput. The next steps in developing a full method

would be an exploration of detection limits which will require extraction of replicates at lower concentrations. It is expected that the behavior of the more "active" compounds may suggest an expanded suite of surrogates.

References

1. Reese, A. and H. Prest, *Retention Time Locked GC/MS Analysis of Phenols*, 5988-3934EN, www.agilent.com/chem
2. Rodriguez, Llompart and Cela, *Solid-phase extraction of phenols*, Journal of Chromatography A, 885 (2000) 291-304.
3. Munch, EPA Method 528, *Determination of Phenols in Drinking Water by Solid-Phase Extraction and Capillary Column Gas Chromatography/Mass Spectrometry (GC/MS)* Revision 1 (April 2000).

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
January 15, 2002
5988-5255EN





Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270

Application

Environmental

Author

Mike Szelewski
Bill Wilson, Ph.D.
Agilent Technologies
2850 Centerville Road
Wilmington, DE 19808
USA

Pat Perkins, Ph.D.
Agilent Technologies
1601 California Avenue
Palo Alto, CA 94304
USA

Abstract

Method 8270 presents challenges due to the simultaneous measurement of acids, bases and neutrals over a concentration range that varies from lab to lab. Laboratories want GC/MS instruments that are linear and inert over a wide concentration range. Changes have been made to the 6890/5973 GC/MSD system in the inlet, column, and source areas based on feedback from our customers. System performance has been improved by maximizing linearity and minimizing activity.

Introduction

USEPA Method 8270 (including versions A, B, C and D) is used to determine the concentration of semivolatile organic compounds in extracts prepared from many types of solid waste matrices, soils, air sampling media and water. The January 1998, revision 4, 8270D lists 240 possible analytes that can be measured. Most laboratories analyze for a significantly smaller number of compounds, usually 70 to 100.

Regardless of the number of analytes, there is usually a mix of acids, bases and neutrals that must be measured concurrently. This mix presents a challenge for instrument design due to the interaction of the analytes with the instrument and consumables.

The calibration range required for the analysis varies depending on a particular laboratory's statement of work. Method 8270 does not specify a calibration range, yet traditionally a range of 20 to 160 ng (nanograms) has been used as a carry-over from the USEPA Contract Lab Program (CLP). With the increased sensitivity of newer GC/MS systems, laboratories are moving toward lower minimum detection limits (MDLs) and pushing the 8270 calibration range down to 5 ng.



Agilent Technologies

The 6890/5973 GC/MSD (Gas Chromatograph/Mass Selective Detector) system was designed to meet demand for these lower MDLs. To further enhance performance, two main areas of improvement were identified in communications with users.

The first was improving the linearity of the GC/MSD system at the high end of the calibration range where roll off or flattening out of the calibration was observed. The relative response factors (RFs) were lower than they should have been at higher concentrations. This was seen for phthalates and for PAHs (Polyaromatic Hydrocarbons).

The second area for improvement was recovery at the low end of the calibration range for active compounds. The most active compounds, the nitrophenols, showed lower RFs at the low end of the calibration range than what was expected on some systems. The most active of these, 2,4-dinitrophenol, showed RFs below method requirements on some systems.

A study was undertaken to address the high end linearity and the low end activity. The primary goals of the study were to meet the following 8270 requirements:

1. Minimum Average RF of 0.050 for the System Performance Check Compounds (SPCCs) (Method 8270D, section 7.3.4.2)
2. Maximum Relative Standard Deviation (RSD) of 30% for the Calibration Check Compounds (Method 8270D, section 7.3.5.2)
3. Maximum Mean Relative Standard Deviation of 15% across all compounds (Method 8000B, section 7.5.1.2.1)

Additional study goals to ensure maximum productivity for the user were:

1. Minimize activity in the entire GC/MSD system to maximize RFs for active compounds—this gives the user a greater margin for system degradation when analyzing dirty samples.
2. Maximize linearity in the GC/MSD system at the high end without losing significant sensitivity at the low end—this improves overall RSDs.
3. Preserve method resolution requirements for benzo[b]fluoranthene and benzo[k]fluoranthene when using thinner film columns for shorter analysis times.

Experiments were done to meet the study goals by dividing the system into three main sections :

GC column, GC inlet, and MSD. Each of these areas is treated separately in a following section of this note.

Column

Column test system

To reduce the complexity of the chromatographic system and to provide the best possible sample introduction and detection, a COC/FID (Cool-On-Column/Flame Ionization Detector) system was used to test column performance. On-column injection eliminates any inlet activity while FID gives sensitive and essentially universal response for the analytes. The FID also provides directly comparable response information that can be used to validate analyte introduction between systems.

Test mix

To establish a test mix for evaluating the column and other components in the system, both anecdotal information and suggestions in the method were reviewed. Section 1.4 of 8270D points out the following compounds as potentially troublesome:

1.4.1 Benzidine may be subject to oxidative losses during solvent concentration and its chromatographic behavior is poor.

1.4.4 N-nitrosodimethylamine is difficult to separate from the solvent under the chromatographic conditions described.

1.4.6 Pentachlorophenol, 2,4-dinitrophenol, 4-nitrophenol, benzoic acid, 4,6-dinitro-2-methylphenol, 4-chloro-3-methylphenol, 2-nitroaniline, 3-nitroaniline, 4-chloroaniline, and benzyl alcohol are subject to erratic chromatographic behavior, especially if the GC system is contaminated with high boiling material.

Furthermore, the method cites several mixes of compounds for evaluating system performance. The DFTPP (decafluorotriphenylphosphine) mix adds 4,4'-DDT to the previously cited compounds. The system performance check compounds add N-nitroso-di-n-propylamine and hexachlorocyclopentadiene. Finally, the calibration check compounds add six more phenols as well as seven base/neutral compounds.

From anecdotal information, the phenols presented the greatest challenge. If the phenols cited are combined, the list is essentially all the phenols in EPA Method 604. While more test solute information was being collected, the phenols were run by COC/FID. Table 1 shows the RSD values for relative response factors from 5 to 160 ng on column. The last four compounds prove to be the most troublesome with 2,4-dinitrophenol being noticeably worse. Even so, the RSD values are all below 8%, indicating that COC/FID can be used to evaluate column performance. When done with unoptimized conditions/consumables in splitless sample

Table 1. Cool-on-column FID, RSD of RFs from 5 to 160 ng on column

Solute	RSD
Phenol	3.0
2-Chlorophenol	3.1
2-Nitrophenol	3.2
2,4-Dimethylphenol	3.3
2,4-Dichlorophenol	3.1
4-Chloro-3-methylphenol	3.2
2,4,6-Trichlorophenol	3.3
2,4-Dinitrophenol	6.9
4-Nitrophenol	3.8
4,6-Dinitro-2-methylphenol	4.3
Pentachlorophenol	4.5

introduction, the RSD values become unusable for these difficult compounds. With this information and the anecdotal performance data, a more comprehensive mix was devised.

The “short mix” is comprised of the four phenols from above, several bases, several neutral compounds, and the internal standards at 40 ng/μL. The compounds were selected so that they were easily resolved and unambiguously detected by COC/FID. Figure 1 shows a sample chromatogram of the short mix on a 0.5 μm column.

Column testing

8270D states that a 30 m × 0.25 mm × 1 μm silicone coated capillary column be used in the analysis. However, the method also makes provisions for split injections, allowing a thinner film to be used. Because of the obvious time pressure to perform environmental analyses, thinner film columns are widely used. From customer inputs, film thickness ranged from 0.25 to 1 μm; consequently, 0.25, 0.5, and 1 μm film thickness columns were evaluated. Each of the columns had already passed the Agilent 5MS column checkout and were used as received. In addition, columns from another supplier were also tested, yielding similar results to the Agilent columns.




Figure 1. COC-FID Chromatogram and identification of short mix compounds.

The instrument parameters followed the 8270 method operating conditions as closely as possible. The COC inlet was run in oven track mode, the column flow was constant at 1.3 mL/min, and the FID was set to 300 °C. The oven program followed the 8270 method except that the program rate (10 °C/min) was adjusted for the different film thickness to resolve the test compounds.

Numerous columns from each film thickness were tested. It is important to remember that all of these columns passed the standard column testing protocol. An arbitrary metric was set for pass/fail criteria. This value was 10% RSD for the 2,4-dinitrophenol RFs from 5 to 160 ng on column. Of all the columns tested, only a fraction gave results below this metric. Film thickness was not a factor since the same fraction of columns passed for each film thickness. Some of the columns were so active that the column alone could cause the system to fail the method qualifying criteria. For this reason, it is imperative that a stringent test protocol be utilized for evaluating columns and that only specifically tested columns be used for 8270D. A comparison of a column that passed and one that failed the arbitrary criteria is shown in Table 2.

Table 2. COC-FID Results on a "Pass" and a "Fail" 0.5 µm Column, 5 to 160 ng

Solute	"Pass"		"Fail"	
	RSD	Avg RF	RSD	Avg RF
N-Nitrosodimethylamine	0.78	0.54	0.30	0.52
Aniline	1.2	1.45	0.59	1.43
2,4- Dinitrophenol	7.5	0.33	21.	0.28
4-Nitrophenol	0.49	0.52	2.9	0.50
4,6-Dinitro-2-methylphenol	4.7	0.40	14.	0.37
4-Aminobiphenyl	1.0	0.94	3.3	1.02
Pentachlorophenol	5.0	0.34	15.	0.26
Benzidine	2.6	0.74	2.8	0.72
3,3'-Dichlorobenzidine	7.9	0.57	0.58	0.62

Column selection

Since all the film thicknesses studied can meet the method objectives, the column selection is typically based on other analysis needs. As in all chromatographic systems, there is a balance between speed of analysis, resolution, and column capacity. The 0.25 µm film thickness columns offer the fastest analysis possible but with a compromise in resolution and capacity. Conversely, the 1.0 µm columns provide the best capacity but at a cost of time. Using the Agilent method translation tool, the 0.5 µm film column is only a factor of two slower than the thin film column while providing a twofold increase in capacity. The 0.5 µm film

thickness column offers a good compromise between speed and capacity.

Inlet

There are many inlet related factors that affect 8270 performance. These include: split vs. splitless injection, syringes, injection volume, septa, inlet temperature, inlet seal, liners, using wool or not in the liner, and using a pulsed (flow programmed) vs a normal injection. Some of these parameters were studied to determine their contribution to low end activity and to high end linearity.

Split injection is allowed if the MSD has enough sensitivity. Split injections put less material on column, making it easier to meet resolution requirements on thinner film columns and at the same time improving peak shapes. However less material on column results in noticeable losses of active compounds due to column or MSD activity. High end linearity could be improved using split injections but the issue was solved as described in the source section of this note. Splitless injection is almost universally used and will be the focus of this inlet section.

A syringe experiment was not done as part of this study. Previous data show better reproducibility when using a 5 µL syringe in an ALS (Automatic Liquid Sampler). All injections were made using a 5 µL syringe with a tapered needle.

Injection volume was always 1 µL for the study. 8270 allows for 1 to 2 µL injection volumes, but previous data show worse reproducibility when using 2 µL injections. This is most likely due to expansion outside the liner and subsequent loss of analytes. Additionally, more residue is introduced with larger injection volume, negatively impacting instrument uptime.

Septa types were not studied and green septa were used. Inlet temperature was held at 250 °C. A new gold inlet seal was fitted with each liner, although changing the seal for a direct connect liner may not be necessary. Stainless steel (SS) seals were not used.

The inlet study focussed on liner types, carrier gas flow through the column during injection and the presence or absence of glass wool. The five different liner types that were used are described in Table 3. Two of the liners, the G1544-80700 and G1544-80730 are new designs. The column makes a direct connection into the liner bottom, similar to a capillary column connector.

Table 3. 2,4-Dinitrophenol Average RFs Using Various Inlet Liners, COC-FID

Splitless time Column flow		ng injected	0.2 min 1 mL/min		0.2 min 3 mL/min		0.75 min 1 mL/min		0.75 min 3 mL/min	
Part number	Liner		Avg RF	RSD	Avg RF	RSD	Avg RF	RSD	Avg RF	RSD
5062-3587	Single taper with glass wool	5	0.007	63	0.023	55	0.017	58	0.072	38
		160	0.122		0.198		0.187		0.228	
5181-3316	Single taper	5	0.092	37	0.136	21	0.105	33	0.125	22
		160	0.279		0.232		0.261		0.207	
5181-3315	Dual taper	5	0.203	14	0.215	11	0.201	15	0.216	12
		160	0.285		0.255		0.296		0.287	
G1544-80730	Single taper direct contact	5	0.287	5	0.269	7	0.272	6	0.229	9
		160	0.311		0.316		0.310		0.285	
G1544-80700	Dual taper direct contact	5	0.289	5	0.280	6	0.275	7	0.278	7
		160	0.331		0.330		0.327		0.328	
	COC	5	0.311	3	0.311	3	0.331	3	0.311	3
		160	0.331		0.331		0.331		0.331	

All liner experiments were performed using an FID to eliminate any affect an MSD would have on the results. RFs are not identical for MSD and FID due to inherent response differences. An approximate conversion is $RF_{fid} \times 0.7 = RF_{msd}$. Cool-on-column injection was done as a baseline for inlet performance.

The short mix was injected at the 5, 20, 80 and 160 ng levels, four replicates at each level. This series of 16 injections was made on each liner at each set of inlet conditions. There were four sets of inlet conditions. The splitless time was either 0.2 minute or 0.75 minute. The carrier flow through the column was either 1.0 mL/min or 3.0 mL/min held for the splitless time + 0.05 minute, then reduced to 1.2 mL/min. This is similar to a “pulsed splitless” injection, however flow programming gives the analyst control over the depressurization rate. The COC injections were made at a fixed column flow and the splitless time is not relevant.

Table 3 shows the results of these analyses. The average RFs for 2,4-dinitrophenol at the 5 ng and 160 ng levels are shown together with the RSD of all 16 RFs for each liner type/inlet conditions.

The 3587 liner shows the worst performance. 2,4-dinitrophenol has been eaten by the glass wool and low end activity is at its worst. Unfortunately most analysts use glass wool in the liner to prevent solids from contaminating the column.

The 3316 liner is the same as the 3587 but without the wool. Loss of 2,4-dinitrophenol can be attributed to contact with the gold inlet seal, the polyimide coating on the column outside and the stainless steel at both the top and bottom of the inlet. There could also be analyte contact with the stainless steel in the annular volume outside the liner.

The 3315 liner is the same as the 3316, but with a narrower opening at the top. This minimizes contact with the top of the inlet and there is an increase in 2,4-dinitrophenol response.

The new 80730 liner minimizes analyte contact with the polyimide on the column outside, the gold inlet seal and the inlet annular volume. Response for 2,4-dinitrophenol was significantly improved using this liner, even though it has a wide top similar to the 3316.

The new 80700 liner has the advantages of the 80730 and has a narrower top opening similar to the 3315. An additional increase is seen in 2,4-dinitrophenol response because analyte contact with inlet surfaces is minimized at both the top and bottom. Performance with this liner is nearly equal to that of COC and low end activity is minimized for the inlet only.

Figure 2 shows performance of the five liners and COC with one set of conditions that was used. The splitless time was 0.75 minute and the column flow was 3 mL/min during the injection. Each of the

bars shows the average RF for 2,4-dinitrophenol of the four replicate injections at each level. The order is 5 ng at the top increasing to 160 ng at the bottom. Above each bar is listed the average RF and RSD across all 16 injections. The 3587 liner with the wool shows the worst performance and the new 80700 liner with the direct connect bottom and narrow top shows the best performance. The COC data show column performance isolated from a hot splitless inlet. There is a slight drop-off in COC RFs comparing 5 ng to higher levels. Data for the other three sets of experimental conditions show similar trends and are not presented.




Figure 2. 2,4-Dinitrophenol RFs using five different liners.

Figure 3 shows performance of the 3587 liner at the four sets of experimental conditions. These data are shown as liners with wool are widely used. Comparing the first two bars shows the difference between a column flow of 1 mL/min and 3 mL/min during injection, both with a 0.2 minutes splitless time. Higher flow sweeps the inlet faster minimizing contact with the wool resulting in better 2,4-dinitrophenol performance. The higher column flow also means a higher inlet pressure. Previous work has shown that higher inlet pressures can keep the expanded solvent vapor contained in the liner. This holds true comparing the third and fourth bars with a 0.75 minute splitless time. The longer splitless time also results in a more complete transfer of 2,4-dinitrophenol onto the column at a fixed flow. In all cases performance suffers compared to COC.

In addition to 2,4-dinitrophenol, RFs and RSD were tracked for the other analytes in the short mix. Similar improvements were seen for the other active compounds although the liner effects were not as dramatic due to better performance of these

compounds initially. No adverse effects were seen for the neutral or basic compounds when the acidic compounds improved.

Another factor that was monitored was ISTD (internal standard) reproducibility. Using the new direct connect liners showed variability in ISTD areas on some test systems greater than that using the standard liners. These systems still met the -50%/+100% 8270 ISTD criteria. Using a column flow of 3 mL/min during the injection period minimized this ISTD variability.

The high end linearity issue is not caused by the inlet although inlet parameters can affect it. The low end activity issue is directly related to inlet activity, including liner, seal, wool and stainless steel. Activity can be minimized by using pressure programmed flow and optimized splitless time. The liner and the presence of wool have the largest affect on low end activity. The liner must be chosen based on sample type, allowing for a trade-off of activity vs dirtiness of extract.




Figure 3. 2,4-Dinitrophenol RFs using a 3587 liner.

Source

The position of the column in the ion source, ion source materials, dimensions of the ion source, and parameters used for operation all affect the response of the system in this method.

In general, the column should be positioned beyond the end of the interface but not too far into the ion source. If the column tip is positioned inside of the interface guide tube, compounds are exposed to the hot metal surface of the interface and may decompose. On the other hand, if a significant length of column is exposed inside the ion source, the polyimide coating of the column can take on a static charge due to the ions and electrons in the ion source, and this charge interferes with the ejection of ions from the ion source chamber. In practice, a 2 to 3 mm extension of the column out of the interface has been found to yield the best results. This position may be set by one of two methods:

- 1 Put the column nut and ferrule on the column; open the analyzer door; push the column through the interface until 2 to 3 mm is sticking out of the end; then tighten down on the column nut; or
- 2 Put the column nut and ferrule on the column; open the analyzer door; push the column through the interface until it is just beyond the end of the interface. Tighten the nut only finger tight. Hold the MSD analyzer door closed, and then slide the column in until it just bottoms out (stops). You have now hit the left side of the source. Mark the column with typewriter correction fluid in the oven next to the nut. You can release the MSD analyzer door. Back the column out 12.5 mm (the source i.d.). Tighten the column nut. There should be 2 to 3 mm of column visible at the MSD end of the transfer line. You have now positioned the column just inside the source.

Method 1 above has the advantage that you can see what is happening, but a disadvantage is that it is difficult to measure the 2 to 3 mm column length inside the vacuum manifold. Method 2 has a few more steps but gives reproducible results, if followed exactly.

The material used for the standard MSD ion source may decompose some analytes under some conditions, especially when the source temperature is high. The Ultra source (patent applied for) has been found to reduce low end activity under the conditions typically used for this method. Table 4 shows a comparison of RFs for 2,4-dinitrophenol using different source materials. It also shows that the new Ultra source can be abrasively cleaned with minimal loss in performance.

The high end linearity is a function of the density of ions produced in the ion source. Reducing the ion source pressure improves the high end linearity. Therefore, increasing the size of the holes in the ion source improves the high end linearity, attended by some loss in sensitivity. To improve high end linearity, the hole in the drawout lens is made 6 mm in diameter rather than the standard 3 mm diameter. The change in dimension allows for a better match between the instrument's linear working range and the requirements of the method.

Another way of improving the high end linearity is to alter the operating parameters used in the method. A combination of a lower emission current (20 μ A) and a high repeller setting (25 V) was determined to improve high end linearity so that the RSD of the analytes with strong response were single digit values. These analytes are the PAHs and phthalates. The emission current of 20 μ A is set by the analyst. The revised tuning macros automatically set the repeller voltage to 25 V.

Table 4. 2,4-Dinitrophenol Average RFs Using Various Ion Sources

ng Injected	COC-MSD Avg RFs of 2,4-dinitrophenol, n=4				
	5	20	80	160	Avg
Ultra source	0.121	0.185	0.229	0.244	0.194
Ultra source air baked at 150 °C	0.120	0.185	0.228	0.244	0.194
Ultra source cleaned with 400 grit SC paper	0.119	0.181	0.220	0.231	0.188
Ultra source cleaned with metal polish	0.107	0.169	0.209	0.221	0.177
Standard source B	0.036	0.073	0.132	0.152	0.098
Standard source A	0.025	0.036	0.063	0.086	0.052

Data

As a result of this study, the G2860A 8270 Semi-Volatiles Applications Kit has been developed. The kit provides modified and/or pretested components to improve system performance for USEPA Method 8270. The kit includes an Ultra source, specially tested column, inlet liners and tune macros. The data in Table 5 are an average result of four Ultra source/column combinations. These can be considered typical of a 6890/5973 system with the applications kit installed.

The data in Table 5 are from calibrations at 5, 10, 20, 50, 80, 120 and 160 ng. This extended range exceeds the typical range of 20 to 160 ng. The data meet the 8270 criteria listed in the Introduction section of this application note. The minimum average RF is well above the required 0.050 for all of the SPCCs. The RSDs for all the CCCs are significantly less than 30% required. The mean RSD of 7% across all compounds easily meets the minimum criteria of 15%.

Table 5. Typical results from a 6890/5973 GC/MSD System with the G2860A Applications Kit Installed, 5 to 160 ng, 1 µL Splitless Injection

	Avg RF	RSD		Avg RF	RSD
ISTDs					
1,4-Dichlorobenzene-d4		8	2-Chloronaphthalene	1.003	5
Naphthalene-d8		7	2-Nitroaniline	0.482	10
Acenaphthene-d10		7	Acenaphthylene	1.512	5
Phenanthrene-d10		8	Dimethylphthalate	1.187	4
Chrysene-d12		9	2,6-Dinitrotoluene	0.272	6
Perylene-d12		9	Acenaphthene (CCC)	0.958	5
Analytes					
Pyridine	1.436	6	3-Nitroaniline	0.265	8
N-Nitrosodimethylamine	0.799	6	2,4-Dinitrophenol (SPCC)	0.130	25
2-Fluorophenol	1.189	4	Dibenzofuran	1.421	4
Aniline	1.576	6	2,4-Dinitrotoluene	0.364	9
Phenol-d5	1.639	6	4-Nitrophenol (SPCC)	0.205	11
Phenol (CCC)	1.783	4	Fluorene	1.152	5
bis(2-chloroethyl) ether	1.280	5	4-Chlorophenyl-phenylether	0.566	6
2-Chlorophenol	1.293	4	Diethylphthalate	1.177	5
1,3-Dichlorobenzene	1.320	3	4-Nitroaniline	0.223	9
1,4-Dichlorobenzene (CCC)	1.371	3	4,6-Dinitro-2-methylphenol	0.135	16
1,2-Dichlorobenzene	1.275	3	Diphenylamine (CCC)	0.518	6
Benzyl alcohol	0.895	7	2,4,6-Tribromophenol	0.109	8
bis(2-chloroisopropyl)ether	2.273	9	Azobenzene	0.177	5
2-Methylphenol	1.356	7	4-Bromophenyl-phenylether	0.206	5
Hexachloroethane	0.615	3	Hexachlorobenzene	0.198	4
N-Nitroso-di-n-propylamine (SPCC)	1.508	5	Pentachlorophenol (CCC)	0.123	9
4-Methylphenol	1.243	7	Phenanthrene	1.064	4
Nitrobenzene-d5	0.489	3	Anthracene	1.017	4
Nitrobenzene	0.452	3	Carbazole	0.734	7
Isophorone	0.770	3	Di-n-butylphthalate	1.248	7
2-Nitrophenol (CCC)	0.188	7	Fluoranthene (CCC)	1.184	5
2,4-Dimethylphenol	0.309	8	Pyrene	1.344	5
bis(2-Chloroethoxy)methane	0.407	4	Benzidine	0.295	9
Benzoic acid	0.154	39	Terphenyl-d14	0.963	5
2,4-Dichlorophenol (CCC)	0.282	7	Butylbenzylphthalate	0.707	8
1,2,4-Trichlorobenzene	0.289	4	3,3'-Dichlorobenzidine	0.322	8
Naphthalene	0.919	4	Benzo[a]anthracene	1.213	5
4-Chloroaniline	0.340	9	Chrysene	1.168	3
Hexachlorobutadiene (CCC)	0.191	5	bis(2-Ethylhexyl)phthalate	0.906	4
4-Chloro-3-methylphenol (CCC)	0.341	6	Di-n-octylphthalate (CCC)	1.650	9
2-Methylnaphthalene	0.606	4	Benzo[b]fluoranthene	1.197	9
Hexachlorocyclopentadiene (SPCC)	0.267	11	Benzo[k]fluoranthene	1.108	8
2,4,6-Trichlorophenol (CCC)	0.370	8	Benzo[a]pyrene (CCC)	0.995	7
2,4,5-Trichlorophenol	0.368	6	Indeno[1,2,3-cd]pyrene	0.807	8
2-Fluorobiphenyl	1.222	4	Dibenz[a,h]anthracene	0.689	9
			Benzo[g,h,i]perylene	0.741	8
			Average of analyte RSDs		7

Continued

The additional study goals were also met. Method resolution requirements for benzo[b]fluoranthene and benzo[k]fluoranthene can be met when using thinner film columns depending on inlet parameters used. Linearity has been maximized at the high end without losing significant sensitivity at the low end. This improves overall RSDs. Activity in the entire GC/MSD system has been reduced thereby maximizing RFs for active compounds such as the nitrophenols. This gives the user a greater margin for system degradation when analyzing dirty samples.

These system improvements ensure maximum productivity for the analyst using an Agilent Technologies 6890/5973 GC/MSD for USEPA Method 8270.

Instrument Operating Parameters

Two sets of recommended instrument operating parameters are listed in Table 6 and Table 7. These are starting conditions and may have to be optimized.

The ramped flow and splitless times in Table 6 result in less material on column, better peak shape and resolution of benzo[b]fluoranthene and benzo[k]fluoranthene using a 0.5 μm column as provided in the G2860A 8270 Semi-Volatiles Applications Kit. However, less material on column may result in lower response factors for active compounds.

The ramped flow and splitless times in Table 7 result in more material on column, resulting in worse peak shape and benzo[b]fluoranthene and

benzo[k]fluoranthene are not resolved. However, more material on column may result in higher response factors for active compounds.

The 0.5 μm film thickness column is a compromise of speed versus resolution. A 1.0 μm film thickness column is recommended in 8270 for best resolution and best peak shape at higher analyte concentrations. Using a 1.0 μm film thickness column also results in the longest run times. A 0.25 μm film thickness column will give shorter run times, but capacity suffers and consequently so does peak shape. Some laboratories meet method resolution requirements using split injections on a 0.25 μm column.

Many users have had success keeping this method running by clipping the front end of the column on a regular basis, daily if needed. The first compounds to suffer degradation from not clipping the column are the phenols.

The 5181-3316 liner is also a compromise. The absence of wool helps to preserve active analytes but potentially subjects the column to degradation from dirty samples. Adding a wisp of wool will help protect the column but active analytes will decompose. The new direct connect liners are the best choice for clean samples or for minimizing inlet activity.

The method operating parameters given here should only be considered a good starting point. Optimization of the parameters by the analyst are dependent on the analytes and calibration ranges required by the individual laboratory's statement of work.

Table 6. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet Liner	5181-3316, single taper, 4 mm i.d., deactivated		
Inlet	EPC Split/splitless		
Mode	Splitless, 1 µL		
Inlet temp	250 °C		
Pressure	9.24 psi		
Purge flow	30 mL/min		
Purge time	0.35 min		
Gas saver	Off		
Oven			
Oven ramp	°C/min	Next °C	Hold min
Initial		40	1.00
Ramp 1	15	100	0.00
Ramp 2	20	240	0.00
Ramp 3	10	310	6.00
Total run time	25 min		
Equilibration time	1.0 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS, 19091S-133, specially tested		
Length	30 m		
Diameter	0.250 mm		
Film thickness	0.5 µm		
Mode	Ramped flow		
Flow	mL/min	mL/min	Hold min
Initial		1.2	0.00
Ramp 1	99	2.0	0.35
Ramp 2	10	1.2	0.00
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
MSD	Agilent Technologies 5973 with Ultra Source		
Solvent delay	3.2 min		
EM voltage	DFTPP tune - 75 volts		
Low mass	35 amu		
High mass	500 amu		
Threshold	50		
Sampling	2		
Scans/sec	3.25		
Quad temp	150 °C		
Source temp	230 °C		
Transfer line temp	310 °C		
Repeller voltage	25 V as set by new tuning macro		
Emission current	20 µA set by the analyst		

Table 7. Alternate Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet Liner	5181-3316, single taper, 4 mm i.d., deactivated		
Inlet	EPC Split/splitless		
Mode	Splitless, 1 µL		
Inlet temp	250 °C		
Pressure	23.14 psi		
Purge flow	30 mL/min		
Purge time	0.50 min		
Gas saver	Off		
Oven			
Oven ramp	°C/min	Next °C	Hold min
Initial		40	1.00
Ramp 1	15	100	0.00
Ramp 2	20	240	0.00
Ramp 3	10	310	6.00
Total run time	25 min		
Equilibration time	1.0 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS, 19091S-133, specially tested		
Length	30 m		
Diameter	0.250 mm		
Film thickness	0.5 µm		
Mode	Ramped flow		
Flow	mL/min	mL/min	Hold min
Initial		3.0	0.55
Ramp 1	10	1.2	0.00
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
MSD	Agilent Technologies 5973 with Ultra Source		
Solvent delay	3.2 min		
EM voltage	DFTPP tune - 200 volts		
Low mass	35 amu		
High mass	500 amu		
Threshold	50		
Sampling	2		
Scans/sec	3.25		
Quad temp	150 °C		
Source temp	230 °C		
Transfer line temp	310 °C		
Repeller voltage	25 V as set by new tuning macro		
Emission current	20 µA set by the analyst		

Conclusion

In this paper, we have demonstrated a process for examining the performance of various components on a complex analytical method composed of many compounds. The challenges of analyzing different classes of compounds in the shortest time while meeting the method requirements are difficult.

This study has led to the development of a 25-minute 8270D method suitable for an extended calibration range of 5 to 160 ng. The G2860A 8270 Semi-Volatiles Applications Kit provides the components necessary to convert an existing 6890/5973 to perform this analysis.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
November 7, 2001
5988-3072EN



Agilent Technologies



A New Approach to the Analysis of Phthalate Esters by GC/MS

Application

Gas Chromatography/Mass Spectrometry
March 2001

Authors

Cameron George
Agilent Technologies, Inc.
91 Blue Ravine Road
Folsom, California 95630-4714
USA

Harry Prest
Agilent Technologies, Inc.
1601 California Avenue
Palo Alto, California 94304-1111
USA

Abstract

A new instrumental method for the determination of 29 phthalate esters, including six recently banned from baby toys by the European Union, using positive chemical ionization and retention-time locking is described. Positive chemical ionization provides a high degree of selective ionization for the phthalates, primarily producing spectra in which the protonated molecule ($M+1$) is the base peak. This provides easy discrimination among the phthalates on the basis of their molecular weight, while retention-time locking increases confidence in the identification of the various isomers.

In this approach, both pure compounds and technical mixtures are considered. Although this work focuses on the more commonly used 1,2-substituted esters, the 1,3-isomers and 1,4-isomers are also characterized.

The combination of positive chemical ionization and retention-time locking makes the method rugged, durable and applicable to a wide variety of matrices.

Introduction

The widespread use and manufacture of plastics have made the phthalate esters one of the most ubiquitous classes of compounds in our everyday environment. These “plasticizers” increase polymer flexibility due to their function as intermolecular “lubricants”. Because they are additives and not reagents, they are not chemically bound in the polymer and are available to leach from the matrix. Phthalates are also components of cosmetics, detergents, building products (flooring, sheeting, films), lubricating oils, PCB substitutes, carriers in pesticide formulations and solvents. Consequently, the potential for human exposure is very high. Toxicological studies have linked some of these compounds to liver and kidney damage, and to possible testicular or reproductive-tract birth defect problems, characterizing them as endocrine disruptors. Scientists at the U.S. Centers for Disease Control have, for the first time, documented human exposure to phthalates by determinations of the monoester metabolites in human urine [1]. Their work leads to the conclusion that “phthalate exposure is both higher and more common than previously suspected.”

Of particular concern were the significantly higher concentrations of the dibutyl phthalate metabolite in urine of women of childbearing age (20-40 years) than in other portions of the population.

The presence of phthalate esters in polyvinyl chloride (PVC) toys has generated the most



Agilent Technologies

controversy. While regulators in Greece have completely banned soft PVC toys, Austria, Denmark, Finland, France, Germany, Norway and Sweden have unilaterally banned phthalates in PVC toys for children under three years old. In December of 1999, the European Union (EU), concerned with a “serious and immediate risk” to children, placed an emergency ban on six of the phthalate esters in soft PVC toys and childcare products meant to be placed in the mouths of children under the age of three [2]. None of the six banned phthalates may exceed 0.1% by weight.

These heightened concerns suggest the need for an improved method of detecting and characterizing phthalate esters which is applicable to a wide variety of matrices. This application note describes such an analytical method.

Phthalate Structure and Mass Spectra

The three primary structures of phthalates are shown in Figure 1. Although there are three possible positions for the ester linkages, the most commonly used phthalates are based on the 1,2-benzenedicarboxylic acid structure (top). There are an infinite number of possible alkyl side chains, (R) and an infinite number of combinations of the side groups (R and R'). For example, the diisononyl phthalate consists of an array of compounds due to the isomeric branched-chain alkyl groups on both side chains.

For phthalate esters with saturated alkyl side chains (without oxygen), the most intense peak in the electron impact (EI) ionization mass spectrum at 70 eV is always at m/z 149 due to the rapid formation and stability of the ion shown in Figure 2. (The only exception is $R=R'=\text{CH}_3$ where the base peak is at m/z 163).






Figure 1. Phthalic ester (top) or the 1,2-benzenedicarboxylic acid ester, isophthalic ester (middle) or the 1,3-benzenedicarboxylic acid ester, and terephthalic ester (bottom) or the 1,4-benzenedicarboxylic acid ester. R and R' represent alkyl side chains which may be branched and contain oxygen.




Figure 2. The most abundant ion in the mass spectra of the phthalate esters with saturated alkyl side chains; m/z 149. The exception is for dimethyl phthalate where both R and R' are CH_3 and so the H on the oxygen is replaced by CH_3 and consequently m/z 163 becomes the base peak.

Invariably, the molecular ion is very weak or altogether absent; other fragments that provide information on the phthalate identity are also of very low abundance. As an example, consider the EI mass spectrum of dibutyl phthalate, one of the six banned by the EU, and bis(4-methyl-2-pentyl) phthalate in Figure 3. Identifying fragments have relative intensities of less than 10%. Gas chromatography provides some separation of the phthalates, but with the array of possible isomers and essentially a single identifying ion (i.e., m/z 149), distinguishing the individual phthalates of concern is difficult. More confident identification of the phthalates is possible using chemical ionization mass spectrometry in conjunction with retention-time locking (RTL).




Figure 3. Electron impact ionization mass spectra of di-n-butyl phthalate (upper panel) and bis(4-methyl-2-pentyl) phthalate (lower panel) from m/z 50 to 350 at 70 eV. Notice the lack of intense fragments and molecular ions. The molecular weights are 278 and 334 g/mole, respectively.

Retention-time locking allows compound retention times achieved on any one Agilent 6890 gas chromatograph (GC) to be replicated to within a few seconds on any other Agilent 6890 gas chromatograph (GC) applying the same GC method [3-5]. RTL is a powerful approach to compound identification. RTL allows the creation of compound acquisition methods and quantitation databases that can be reproduced in any laboratory, anywhere, because a compound can have a universally fixed and reproducible retention time. It is important that RTL be applied in conjunction with the appropriate detection scheme and sample preparation methods.

Chemical ionization provides a more selective form of ionization than electron impact [6]. By judicious choice of the reagent gases, the degree of compound fragmentation can be controlled to a certain extent. In positive chemical ionization, methane reagent gas usually provides more fragmentation than gases of higher proton affinity such as ammonia. Less fragmentation would be helpful in identifying the phthalates. Instead of all phthalates generating a single, similar ion, positive ionization can provide phthalate ester molecular weights.

Experimental

Phthalate esters were obtained from Ultra Scientific (North Kingstown, RI), AccuStandard (New Haven, CT), and ChemServices (West Chester, PA) as neat compounds and mixtures. Dilutions were made in isooctane (Burdick and Jackson Grade, VWR Scientific).

The configuration and operating parameters of the Agilent 6890Plus GC (standard 120V or "faster ramping" 220V), 7683 Automatic Liquid Sampler and 5973N MSD with CI option used for acquiring the data are given in the following tables. PCI reagent gas purities were 99.99% or higher.

Injection Parameters

Injection Mode	Pulsed Splitless	
Injection Port Temperature	300°C	
Pulse Pressure & Time	25.0 psi	1.00 min
Purge Flow & Time	20.0 mL/min	3.00 min
Gas Saver Flow & Time	20.0 mL/min	3.00 min

Oven Parameters

Temperature Program	80°C	1.00 min
50.00°C/min	200°C	0.00 min
15.00°C/min	350°C	2.00 min
Oven Equilibrium Time	0.25 min	
MSD Transfer Line Temp	325°C	

Column Parameters

GC column (122-5532)	DB-5MS 30 m; 0.25 mm i.d.; 0.25 µm film	
Initial Flow & Mode	1.2 mL/min	Constant Flow
Detector & Outlet Pressure	MSD	Vacuum

Mass Spectrometer Parameters

Tune Parameters	PCI Autotune (NH ₃)	
Electron Multiplier Voltage	Autotune + 400V	
Solvent Delay	4.00 min	
Scan Parameters	194 - 550 m/z	
Quadrupole Temperature	150°C	
Source Temperature	250°C	
Ammonia Gas Flow (MFC setting)	0.5 mL/min (10%)	

Miscellaneous Parts

Septa	5182-0739	BTO septa (400°C)
Liner	5062-3587	Deactivated 4 mm i.d. single taper
GC column ferrule	5181-3323	250 µm Vespel
MSD interface ferrule	5082-3508	0.4 mm i.d. graphitized Vespel

Results and Discussion

As expected using methane as the reagent gas, the PCI mass spectra of the phthalates show ions corresponding to the protonated molecule $[M+H]^+$ and adducts $[M+C_2H_5]^+$ and $[M+C_3H_5]^+$. Because of the relatively vigorous fragmentation produced by methane, the spectra of the dialkyl phthalate esters still resemble that produced in EI. In most cases, the fragment at m/z 149 is the base peak, however ions at m/z $M+1$, $M+29$ and $M+41$ are relatively intense with $[M+H]^+$ from 10% to 30% (Figure 5). The dialkyl phthalate spectra also show a fragment corresponding to loss of one of the alkyloxy side chains to produce an ion shown in Figure 4. This is the most intense fragment for the dimethyl and diethyl phthalates and for the dibutyl and dipentyl (diamyl) phthalates, about 75% of the 149 base peak. As the length of ester alkyl chain increases, the intensity of this fragment decreases. (Apparently, in the dialkyl isophthalates, loss of the alkyl side chain not accompanied by the oxygen may be a preferred route.)

Although positive chemical ionization with methane provides more information than EI on phthalate identity, the methane reagent is still rather unselective in ionization and will produce more chemical noise in the background, complicating identification in complex matrices.




Figure 4. One of the most intense fragments in the methane PCI spectra of the phthalate esters is formed by loss of one of the alkyloxy side groups.

Applying ammonia as the reagent gas in PCI to reduce chemical noise and enhance identification of the phthalates is a more useful approach. The relatively gentle ionization produces protonation of the dialkyl phthalates, with m/z $M+1$ the base peak in their spectra. When combined with retention-time locking, identification of phthalates becomes further simplified. Compare the spectra of the di-n-butyl phthalate acquired using methane versus ammonia as the reagent gas (Figure 5). The protonated molecule is the single dominant peak in the ammonia PCI mass spectrum of the di-n-butyl phthalate, and the adduct at m/z 296 ($[M+NH_4]^+$) is relatively small.





Figure 5. PCI methane (upper panel) and ammonia (lower panel) mass spectra of di-n-butyl phthalate. The PCI methane mass spectrum shows substantial fragmentation but relative to the EI spectrum in Figure 3, high abundance for the higher m/z ions such as the protonated molecule at m/z 279. The ion at m/z 205 is generated by loss of an oxybutyl fragment; a process described in Figure 4. The PCI-ammonia mass spectrum consists almost completely of the protonated molecule.

This implies an easy method for identification. Whereas the EI spectra of the phthalates most frequently result in a base peak at m/z 149, the dialkyl phthalate PCI-ammonia spectra have base peaks at $m/z = M+1$. All dialkyl phthalates molecular formulas can be expressed as



These phthalates have (nominal) molecular masses given by

$$M = 166 + (x + y) \cdot 14, \text{ or}$$

$$M = 166 + (w) \cdot 28,$$

where x and y are the side chain lengths, and the second formula applies to symmetrical side chains (i.e., $x = y = w$). For example, di-*n*-butyl phthalate has $x = y = 4$, and therefore a (nominal) molecular mass of 278 which produces m/z 279 as the base

peak. Interestingly, the PCI-ammonia spectra of the dialkyl isophthalates and terephthalates appear to have base peaks at m/z $M+18$ due to $[M+NH_4]^+$. Because of the greater steric access to the ester linkages, adduct formation may be preferred.

Table 1 gives the phthalate names, CAS numbers, molecular formula, nominal molecular mass, base peak in the PCI-ammonia spectrum and the RTL elution times. These retention times are "locked" relative to diphenyl phthalate, which has been chosen as the RTL locking compound and locked to elute at 9.450 min. Notice that the branched chain isomers elute prior to their straight chain forms on this column phase.

Table 1. Phthalate compound names, Chemical Abstracts Services numbers (CAS), molecular weights (M. Wt.), molecular formulas, nominal base peak in the PCI-ammonia spectrum and retention time (RT) in minutes. Retention times are locked relative to diphenyl phthalate (9.450 min). Retention time ranges are given for the isoalkyl phthalate technical mixtures. Phthalates banned by the EU are indicated by an asterisk*. Benzyl benzoate is included since it is used as a surrogate in U.S. Environmental Protection Agency Method 8061.

Name	CAS	M. Wt.	Molecular Formula	Base Peak	RT (min)
dimethyl phthalate	131-11-3	194	$C_8H_4O_4(CH_3)_2$	195	4.32
dimethyl isophthalate	1459-93-4	194	$C_8H_4O_4(CH_3)_2$	212	4.54
diethyl phthalate	84-66-2	222	$C_8H_4O_4(C_2H_5)_2$	223	4.81
diethyl terephthalate	636-09-9	222	$C_8H_4O_4(C_2H_5)_2$	240	5.06
benzyl benzoate	120-51-4	212	$C_{14}H_{12}O_2$	230	5.62
diisobutyl phthalate	84-69-5	278	$C_8H_4O_4(C_4H_9)_2$	279	5.95
di- <i>n</i> -butyl phthalate*	84-74-2	278	$C_8H_4O_4(C_4H_9)_2$	279	6.40
bis(2-methoxyethyl) phthalate	117-82-8	282	$C_8H_4O_4(C_2H_4OCH_3)_2$	283	6.57
diamyl phthalate	131-18-0	306	$C_8H_4O_4(C_5H_{11})_2$	307	6.94
bis(2-ethoxyethyl) phthalate	605-54-9	310	$C_8H_4O_4(C_2H_4OC_2H_5)_2$	311	7.13
butyl benzyl phthalate*	85-68-7	312	$C_8H_4O_4(C_4H_9)(CH_2C_6H_5)$	313	8.42
diphenyl phthalate	84-62-8	318	$C_8H_4O_4(C_6H_5)_2$	319	9.45
diphenyl isophthalate	744-45-6	318	$C_8H_4O_4(C_6H_5)_2$	319	10.30
dicyclohexyl phthalate	84-61-7	330	$C_8H_4O_4(C_6H_{11})_2$	331	9.32
bis(4-methyl-2-pentyl) phthalate	146-50-9	334	$C_8H_4O_4(CH_3C_5H_{10})_2$	335	6.93
diisohexyl phthalates	146-50-9	334	$C_8H_4O_4(C_6H_{13})_2$	335	7.55 - 8.28
dihexyl phthalate	84-75-3	334	$C_8H_4O_4(C_6H_{13})_2$	335	8.34
dibenzyl phthalate	523-31-9	346	$C_8H_4O_4(CH_2C_6H_5)_2$	347	10.51
hexyl-2-ethylhexyl phthalate	75673-16-4	362	$C_8H_4O_4(C_2H_5C_6H_{12})(C_6H_{13})$	363	8.84
bis(2- <i>n</i> -butoxyethyl) phthalate	117-83-9	366	$C_8H_4O_4(C_2H_4OC_4H_9)_2$	367	8.98
bis(2-ethylhexyl) phthalate*	117-81-7	390	$C_8H_4O_4(C_2H_5C_6H_{12})_2$	391	9.32
di- <i>n</i> -octyl phthalate*	117-84-0	390	$C_8H_4O_4(C_8H_{17})_2$	391	10.28
dioctyl isophthalate	137-89-3	390	$C_8H_4O_4(C_8H_{17})_2$	408	10.84
diisononyl phthalates*	28553-12-0	418	$C_8H_4O_4(CH_3C_8H_{17})_2$	419	9.40 - 11.10
dinonyl phthalate	84-76-4	418	$C_8H_4O_4(C_9H_{19})_2$	419	11.19
diisodecyl phthalates*	26761-40-0	446	$C_8H_4O_4(CH_3C_9H_{18})_2$	447	10.16 - 11.86
didecyl phthalate	84-77-5	446	$C_8H_4O_4(C_{10}H_{21})_2$	447	12.05
diundecyl phthalate	3648-20-2	474	$C_8H_4O_4(C_{11}H_{23})_2$	475	12.87
didodecyl phthalate	2432-90-8	502	$C_8H_4O_4(C_{12}H_{25})_2$	503	13.65
ditridecyl phthalate	119-06-2	530	$C_8H_4O_4(C_{13}H_{27})_2$	531	12.01 - 13.81

Technical formulations of the isoalkyl phthalates tended to contain substantial amounts of the straight chain isomer, which may convolute quantitation as well as peaks that may be construed as originating from nonequivalent side chains i.e., $x \neq y$ in equation 1). These impurities can be detected as $M \pm 14$ around the mass of the nominal isomer. For example, technical grade diisononyl phthalate contains compounds that generate ions at m/z 391 (minor), 405, 433, and 447 in addition to the nominal diisononyl phthalate compound at m/z 419. The “gentle” ionization of ammonia reagent gas, the elution times and the study of the

spectra of other pure isomers, such as the dinonyl phthalate, suggest that these fragments are not formed by the PCI process but are due to these different alkyl side chain impurities (Figure 6). To demonstrate the utility of the PCI-ammonia compared to conventional EI analysis, consider the chromatograms presented in Figure 7. The EI spectra of the phthalates produce m/z 149 as the base peak for all the phthalates present; distinguishing ions are minor constituents (<10% relative intensity), making identification complicated. However, by examining the appropriate PCI-ammonia ions, the various phthalates are easily distinguished.




Figure 6. PCI-Ammonia extracted ion chromatogram of technical diisononyl phthalate. The diisononyl appears as the major component at m/z 419 while ions at m/z 405, 433, and 447 indicate alkyl chains shorter by one CH_2 unit and longer by one and two CH_2 units respectively.




Figure 7. Chromatograms of dinonyl, diisononyl, didecyl, diisodecyl, diundecyl, didodecyl, ditridecyl phthalate esters in EI (upper panel), EI as an extracted ion chromatogram at m/z 149 (middle panel), and PCI-extracted ion chromatogram with ions selected for the individual phthalate classes as given in Table 1. The EI information is insufficient to identify coeluting phthalates. For example, the dinonyl and diundecyl phthalates are "buried under" the signals from the isodecyl and ditridecyl phthalates.

Conclusions

Applying GC - electron impact (EI) mass spectrometry to the determination of phthalates requires full chromatographic separation. The EI spectra of the phthalates are distinguished only by ions of very low intensity. In EI, the phthalates produce a single common ion (m/z 149) as the most intense spectral peak, regardless of the alkyl side chain substitution. Applying tandem mass spectrometry (i.e., EI/MS/MS) gains nothing, because there is a common parent ion, and therefore any daughter ions would also be non-unique. However, the combination of positive chemical ionization with retention-time locking allows even complex mixtures of phthalates to be characterized. Ammonia reagent gas produces the protonated molecule as the base peak, which immediately allows the phthalates to be distinguished on the basis of their substitution. PCI is also an advantage in complex matrices, where the non selective ionization of EI produces a high chemical background. This method should therefore be suitable for use in phthalate determinations in environmental media, plastics, cosmetics and many other matrices.

"Locking" the retention time enhances confidence in the characterization of the various phthalate isomers on the basis of their definitive retention time. This is especially helpful for determinations using selected ion monitoring (SIM), since SIM groups need not be edited after column maintenance [4]. The data in Table 1 facilitate the development of a SIM method. The extension of the method to phthalates which elute at higher temperatures ($>350^{\circ}\text{C}$) is also easily accomplished.

References

1. Blount, B.C., et al., Levels of seven urinary metabolites in a human reference population. *Environmental Health Perspectives*, 2000. 108 (10): p. 979-982.
2. *Official Journal of the European Communities, Decision 198/815/EC*. 1999, European Commission; European Union Scientific Committee on Toxicology, Ecotoxicology, and the Environment.
3. Giarrocco, V., B. Quimby, and M. Klee, *Retention Time Locking: Concepts and Applications*. 1998, Publication number (23) 5966-2469E, Agilent Technologies.
4. Prest, H. and P. Cormia, *Retention Time Locking: Advantages in GC/MS SIM Analysis*. 1999, Publication number (23) 5967-3797E, Agilent Technologies.
5. Prest, H. and K. Weiner, *Retention Time Locking: Creating Custom Retention Time Locked Screener Libraries*. 1999, Publication number (23) 5968-8657E, Agilent Technologies.
6. Harrison, A.G., *Chemical Ionization Mass Spectrometry*. Second ed. 1992: CRC Press.

For more information

For more information on our products and services, you can visit our site on the World Wide Web at: <http://www.agilent.com/chem>.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright © 2001
Agilent Technologies
All rights reserved. Reproduction and adaptation are prohibited.

Printed in the U.S.A.
March 7, 2001
5988-2244EN



Agilent Technologies



Analysis of Nitroaromatics and Nitro-Polycyclic Aromatic Hydrocarbons by Capillary Gas Chromatography with the Agilent 6890 Micro-ECD

Application

Gas Chromatography

March 1997

Authors

F. David
Research Institute for
Chromatography,
Kennedypark 20, B-8500
Kortrijk, Belgium

P. Sandra
University of Gent,
Krijgslaan 281, S4, B-9000
Gent, Belgium, Eindhoven
University of Technology,
The Netherlands

Matthew S. Klee
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A new electron capture detector (ECD) for the Agilent 6890 Series gas chromatograph (GC) allows very sensitive detection of nitroaromatic compounds at low picogram levels with a linear response over three orders of magnitude.

This application note describes the performance of the new 6890 Series Micro-ECD when analyzing two types of nitro-aromatic compounds—explosives and nitrated polycyclic aromatic hydrocarbons (nitro-PAHs).

Introduction

Electron capture detection is most often used for the sensitive and selective detection of halogenated compounds. However, other compound classes also have electron capturing properties and can, therefore, be detected at low levels using an electron capture detector (ECD). Compounds containing a nitro-function—particularly nitroaromatics—are strong electron-capturing molecules. The ECD provides a very sensitive tool for trace analysis of these solutes.

This application note demonstrates that the 6890 Series Micro-ECD provides an extremely sensitive alternative to the typical NPD or MS detection^{1,2} for nitro-PAHs and explosives.

Experimental

The analyses were performed on an 6890 Series GC. Injection was automated splitless using an Agilent 7673 automatic sampler. The instrument configuration and analytical conditions used for the analysis of the nitro-PAHs and explosives are summarized in table 1.

Results and Discussion

The sensitivity of the ECD depends on the makeup flow rate. The 6890 Micro-ECD optimized the argon/5% methane (Ar/CH₄) makeup gas flow rate for the analysis of nitro-PAHs. Nitropyrene was used as test solute. The makeup flow rate was varied from 10 to 80 mL/min; at each setting, five runs were made.

Figure 1 shows the mean peak areas plotted versus the makeup flow rate. The optimum flow rate was obtained between 20 to 30 mL/min. At lower flow rates, the peak area decreased and the detector became less stable, shown in the increasing standard deviation on peak area. At higher flow




Agilent Technologies

Innovating the HP Way

Table 1. Instrumental Configuration and Analytical Conditions

Chromatographic System	
Gas chromatograph	6890 Series
Inlet	Split/splitless
Detector	Micro-ECD
Automatic sampler	7673 Series
Liner	Single taper deactivated (part number 5181-3316)
Data handling	ChemStation (DOS Series)
Column	30 m x 0.25 mm id x 0.25 μ m HP-5 MS (part number 19091S-433)
Experimental Conditions	
Inlet temperature	250 °C
Injection volume	1 μ L
Injection mode	Splitless
Purge time	0.75 min
Purge flow	50 mL/min
Carrier gas	Hydrogen
Head pressure	58 kPa at 50 °C
Carrier gas mode	Constant flow
Flow, velocity	1.4 mL/min, 40 cm/s
Oven temperature	50 °C, 1 min initial, 20 °C/min to 320 °C, 0.5 min hold
Detector temperature	320 °C
Detector gases	Argon/5% methane: 20 mL/min

**Figure 1. Peak area of 1-nitropyrene versus argon/5% methane makeup gas flow rate.**

rates, the detector was stable (exhibiting a small standard deviation), but sensitivity drastically decreased.

Nitrogen is an alternative makeup gas for electron capture detection. It can usually be used interchangeably with Ar/CH₄; similar results for the effect of makeup gas flow rate are expected.

Next, the linearity of the detector response was measured. Using nitropyrene as the test solute, standard solutions of 1, 10, 50, 100 and 1,000 ppb were analyzed. The calibration curve for this compound, as shown in figure 2, exhibits a very

good correlation coefficient ($r = 0.99996$).

Nitrated Polycyclic Aromatic Hydrocarbons

Nitro-PAHs are an important class of environmental pollutants.³ Polycyclic aromatic compounds are formed during incomplete combustion of organic material. In the presence of nitrogen oxides (NO_x), the neutral PAHs (such as naphthalene or pyrene) are converted into nitro-PAHs.³⁻⁵

The nitro-PAHs have much higher mutagenic and carcinogenic activity

than the neutral PAHs, but their extremely low concentration (measured as pg/m³) in environmental samples, particularly air particulates, makes them difficult to monitor. Very sensitive detection is needed.

Using the optimized GC conditions, a mixture of 11 nitro-PAHs, each having a concentration of 40 pg/mL (40 ppb), was analyzed. The chromatogram for this analysis is shown in figure 3. Good peak shapes were obtained for all compounds. The detection limit, which varied from 0.1 to 1 pg for the different PAHs, is at least one order of magnitude lower than that obtained by nitrogen-phosphorus detection (NPD), mass spectrometry (MS), or MS-MS.² It can, therefore, be concluded that the 6890 Micro-ECD offers greater sensitivity for the detection of these nitro-PAHs than other methods.

Explosives

Explosives can be present as residues at chemical waste sites or on materials close to an explosion. Sensitive and fast methods are needed for analyzing and monitoring these compounds for environmental remediation or forensic evidence.

Although explosives are often analyzed by high pressure liquid chromatography (EPA method 8330), capillary gas chromatography (CGC) can provide a good alternative for most solutes using NPD or MS. Some of the nitro-aromatics are included in the target compound lists of EPA methods 8090 and 8270 (CGC-MS).

Explosives such as TNT (2,4,6-trinitrotoluene) contain one or more nitro-functions. CGC-ECD can provide a very sensitive and fast screening method for detecting these compounds.

The chromatogram in figure 4 shows the results of a standard mixture of explosives using the analytical conditions in table 1. The concentration of the test solutes was 100 pg/mL




Figure 2. Calibration curve for 1-nitropyrene from 1 to 1,000 ppb

(100 ppb), except for 1,2-dinitrobenzene, which was present as an impurity. As the chromatogram shows, the different nitro-, dinitro-, trinitro-, and amino-nitro-compounds are well separated and elute with good peak shape.

The ECD response is dependent on the number of nitro-groups. For the mono-nitroaromatics, the detection limit is around 10 pg, while for the di- and tri-nitroaromatics the detection limit is below 1 pg. This example confirms that CGC-ECD can be used as a fast screening method for the analysis of this category of explosives.

Conclusion

The Agilent 6890 Series Micro-ECD allows very sensitive detection of nitroaromatic compounds. The detector was successfully used for the analysis of nitrated polycyclic aromatic hydrocarbons and explosives. Detection limits below 1 pg were obtained, and the detector was found to give a linear response over three orders of magnitude.




Figure 3. CGC-ECD analysis of nitrated polycyclic aromatic hydrocarbons (solute concentration: 40 ppb)




Figure 4. CGC-ECD analysis of explosives (solute concentration: 100 ppb)

References

1. L. Warzecha, *J High Resolution Chromatography* 19 (1996) p. 639.
2. A. Medvedovici, F. David, G. Desmet, and P. Sandra, *Journal of Microseparations*, 1997 (in press).
3. C. M. White (Ed.), "Nitrated Polycyclic Aromatic Hydrocarbons," Huthig Verlag, Heidelberg, 1985.
4. P. Ciccioli, A. Cecinato, E. Brancaleoni, R. Draisci, and A. Liberti, *Aerosol Science and Technology* 10 (1989) p. 296.
5. R. Atkinson, J. Arey, B. Zielinska, and J. M. Ashmann, *International Journal of Chem Kinetics* 22 (1990) p. 999.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5965-8015E



Agilent Technologies
Innovating the HP Way



LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Eric Grosjean and Daniel Grosjean,
DGA, Inc., Ventura, CA

Peter G. Green, Environmental Analysis Center,
Environmental Engineering Science, California
Institute of Technology, Pasadena, CA

John M. Hughes, Agilent Technologies,
Pleasanton, CA

Abstract

A simple and sensitive LC/MS method has been developed for the analysis of carbonyl compounds derivatized with (2,4-dinitrophenyl)hydrazine (DNPH) using the Agilent 1100 LC/MSD system. Detection is carried out simultaneously with the diode-array detector and the LC/MSD using negative ion atmospheric pressure chemical ionization (APCI).¹ The method was applied to 78 carbonyls including 1-alkanals (from formaldehyde to octadecanal), saturated and unsaturated aliphatic aldehydes and ketones, aromatic carbonyls (including hydroxy- and/or methoxy-substituted compounds), aliphatic dicarbonyls, and aliphatic carbonyl esters.

Introduction

The ability to identify carbonyls and to measure their concentrations at levels of parts per billion (ppb) or lower in complex mixtures is important in many areas, including biomedical research and environmental chemistry—especially air pollution. A well-established method utilizing UV detection of the DNPHs of both simple and multifunctional carbonyl compounds^{2,3} has been extended to include simultaneous MS detection using APCI in negative ion mode. Concentration of the compounds

of interest from ambient air samples and subsequent derivatization is simplified by the use of C18 SPE cartridges impregnated with the derivatizing reagent. The combined methodology has been applied to several studies involving air pollution phenomena.¹

Experimental

The system included an Agilent 1100 Series binary pump, vacuum degasser, autosampler, thermostatted column compartment, diode-array detector, and an LC/MSD. The LC/MSD was used with the APCI source. Complete system control and data evaluation were carried out using the Agilent ChemStation for LC/MS.

Sample Collection and Preparation

Carbonyl-DNPH standards were synthesized in our laboratory as described previously.^{2,3} Carbonyls were purchased from commercial suppliers (Aldrich Chemical Co., Lancaster Synthesis, Wiley Organics, Fluka Chemical Corp.) or were prepared as described in previous work.^{2,3}

Air samples were collected by drawing air at 1 liter/minute through C18 Sep-Pak cartridges (Waters Corporation) impregnated with (2,4-dinitrophenyl)hydrazine/phosphoric acid.⁴ Collected carbonyl compounds were derivatized to (2,4-dinitrophenyl)hydrazones on the cartridge, and were then eluted with 2 mL of acetonitrile. The eluate was analyzed directly by LC/MS. The sample can be concentrated for the analysis of the higher molecular weight carbonyls, which are present at lower levels in ambient air.

Results and Discussion

DNPH derivatives are used to analyze carbonyl compounds by liquid chromatography to maximize detection of small, polar molecules, many of which cannot be analyzed using gas chromatography. The original LC/UV method for the analysis of DNPH derivatives of carbonyls was first improved by the use of a diode-array detector and HP particle beam LC/MS interface to provide positive identification of about 40 carbonyls at ppb levels in laboratory studies of air pollution chemistry⁵ and in urban air.⁶ The mass spectrometer provided extra dimensions of information to the already-rich data of the diode-array LC method, allowing the quantitation of coeluting analytes and the identification of unknowns for which standards were not initially available. However, the particle beam interface could not provide the detection limits necessary for measurement of carbonyls in ambient air, due to the significant percentage of water in the LC gradient required for the separation of the more complex mixtures.

To overcome this limitation, API-LC/MS was evaluated for this application. Both electrospray (ESI) and APCI in positive ion and negative ion modes were evaluated. APCI negative ion detection was found to provide the most sensitive and specific information about these compounds, giving 1–2 orders of magnitude better sensitivity than either ESI positive or negative ion or APCI positive ion detection.

Parameters for the acquisition of mass spectral data were automatically optimized by carrying out multiple injections of a standard mixture of 13 carbonyl-DNPH derivatives, using the system's Flow Injection Analysis Series capability. A fragmentor setting was chosen to obtain maximum $[M-H]^-$ for all 13 compounds present in the test mixture. Further optimization of the fragmentor voltage for specific compounds could be carried out to obtain distinct fragments, as the fragmentor voltage is time-programmable during acquisition. Those compounds which required a high percentage of acetonitrile for elution (eluting after 33 minutes) were found to have much better response with a corona current of 10 μ A versus 4 μ A for the smaller, early-eluting analytes. The scan range can be lowered

to 50 amu if significant fragment ions below 125 amu are generated by in-source collision-induced dissociation (CID); the chemical noise, especially in the TIC, is lower when starting the scan at 125 amu.

Mobile phases containing acetonitrile often do not give optimal response in APCI compared to methanol/water eluents, and acetonitrile seems to form carbon on the corona needle more quickly than methanol. However, for this analysis, adequate separation of carbonyls in a reasonable analysis time could not be achieved using methanol/water instead of acetonitrile/water, even trying a variety of columns. Nonetheless, maintenance of the APCI spray chamber after extended use with high flow rates of acetonitrile/water only required cleaning of the corona needle and spray shield with mild abrasive cloth and solvent.

Early work with this method was carried out using a similar column but with dimensions of 4.6 mm i.d. $\times$ 150 cm at a flow rate of 1.4 mL/min, with results comparable to those obtained on the 3mm i.d. column. An additional gradient has also been developed utilizing THF as a mobile phase modifier. This gradient method is capable of better separation of C3 and C4 carbonyl compounds which co-elute using the acetonitrile/water gradient.

Tables 1–6 (shown on pages 9–14) list the first 78 carbonyl compounds that have been analyzed with this method, along with chromatographic and spectral details. The method has been used for more than 140 carbonyl compounds, including several with molecular weights of approximately 650 Da.

Figure 1 shows the 360 nm and MS total ion chromatograms of a mixture of the DNPH derivatives of 13 carbonyls. The amount injected per component is 60 ng (as carbonyl). The UV chromatogram is labeled with the identity of the peaks and the MS chromatogram with the mass of the base peak in the spectrum ($[M-H]^-$ anion).

Figure 2 shows extracted ion chromatograms from the data in Figure 1, illustrating how the specificity of the MS detector can help with coelution, sometimes even allowing quantitation of coeluting peaks.

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones




Figure 1. Liquid chromatography analysis of a mixture of the DNPH derivatives of 13 carbonyls by ultraviolet absorption at 360 nm (diode array detector, top) and by atmospheric pressure negative chemical ionization mass spectrometry (total ion current, bottom): C1, formaldehyde; C2, acetaldehyde; C3K, acetone; ACR, acrolein; C3, propanal; CR, crotonaldehyde; MEK, 2-butanone; MTH, methacrolein; C4, butanal; BZ, benzaldehyde; C5, pentanal; TOL, *m*-tolualdehyde; C6, hexanal.

Chromatographic Conditions

Column: Nucleosil 100-5 C18 HD 5 μ m,
3 $\times$ 250 mm
Guard column: Phenomenex Security Guard C18,
3 mm i.d. $\times$ 4 mm
Mobile phase: A = water
B = acetonitrile
Gradient: Start with 49% B
at 26 min 49% B
at 40 min 100% B
Post-time: 5 minutes
Flow rate: 1.0 ml/min
Column temp: 38°C
Injection vol: 20 μ l
Diode-array
detector: Signal: 360, 40; 385, 40; 430, 40 nm
Reference: 540, 40 nm

MS Conditions

Source: APCI
Ionization mode: Negative
Vcap: 1500 V
Corona current: 10 μ A
Nebulizer: 60 psig
Drying gas flow: 4 l/min
Drying gas temp: 350°C
Vaporizer temp: 500°C
Scan: 125–600 amu,
Threshold: 150 counts
Gain: 5
Step size: 0.1 amu
Peak width: 0.1 min
Time filter: On
Fragmentor: 50 V

LC/DAD/MS Analysis of Carbonyl
(2,4-Dinitrophenyl)hydrazones




Figure 2. Extracted ion chromatograms for the region of Figure 1 containing acrolein (m/z 235), acetone and propanal (m/z 237), crotonaldehyde and methacrolein (m/z 249), and MEK (2-butanone) and butanal (m/z 251).

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Figure 3 shows mass spectra of two carbonyl DNPHs from the data in Figure 1: formaldehyde DNPH and hexanal DNPH. Using conditions optimized for best detection of the $[M-H]^-$ ion, these spectra show little fragmentation even with the high vaporizer temperature (500°C) found to be optimal for the method.

Figure 4a shows the MS total ion chromatogram of a sample taken from a study of the reaction of the unsaturated ketone 4-hexen-3-one with ozone in a laboratory smog chamber. The LC/MS analysis allows the identification of unreacted 4-hexen-3-one,

and of the carbonyl reaction products acetaldehyde, 2-oxobutanal, formaldehyde, glyoxal, and cyclohexanone (the latter a product of oxidation of cyclohexane, added to scavenge any OH radical which may form as a side product of the ozone-unsaturated ketone reaction). Figure 4b shows the mass spectra of the DNPH derivatives of cyclohexanone and of the dicarbonyl compound 2-oxobutanal. The spectra contain the ion m/z 182, which is characteristic of many carbonyl DNPHs and can be used to help locate and identify carbonyl DNPHs in complex mixtures.




Figure 3. Atmospheric pressure negative chemical ionization mass spectra of analytes in Figure 1: (top) formaldehyde DNPH, (bottom) hexanal DNPH.




Figure 4a. Atmospheric pressure negative chemical ionization mass spectrometry analysis of the carbonyl products of the reaction of ppb levels of ozone with 4-hexen-3-one in the presence of cyclohexane: (a) total ion current chromatogram with DNPH derivatives of unreacted 4-hexen-3-one (three peaks due to syn/anti isomers of DNPH) and of the reaction products formaldehyde (C1), acetaldehyde (C2), cyclohexanone, glyoxal, and 2-oxobutanal.




Figure 4b. Atmospheric pressure negative chemical ionization mass spectra of DNPHs of cyclohexanone and 2-oxobutanal.

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Figure 5a shows the UV and MS chromatograms from the LC/MS analysis of an ambient air sample collected during early morning peak traffic in Porto Alegre, Brazil, where the mixture of vehicle fuels is unique in the world.⁷ The MS data is shown using the base peak chromatogram (BPC), a very useful tool for helping to filter noise from the MS data. The BPC reconstructs an MS chromatogram using only the most intense ion (the base peak) from each spectrum, rather than adding up the abundances of all ions in each spectrum as does the total ion chromatogram (TIC).

Figure 5b shows an expanded view of the region of the UV and MS chromatograms, in which the C6 to C18 straight-chain alkanals elute. In Figure 5c, the extracted ion chromatograms for specific compounds show the distinctive masses of the $[M-H]^-$ ions, which confirm and/or identify the peaks detected with the UV detector.




Figure 5a. LC/MS analysis of an ambient air sample collected in Porto Alegre, Brazil, during early morning peak traffic: (top) UV 360 nm chromatogram; (bottom) APCI negative ion base peak chromatogram (BPC).

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones




Figure 5b. Expanded region from C6 to C18 alkanals of the analysis in Figure 5b: (top) UV 360 nm chromatogram; (bottom) APCI negative ion base peak chromatogram (BPC).




Figure 5c. Extracted ion chromatograms of the $[M-H]^-$ ion for 1-alkanal DNPH derivatives in Brazil air sample. Each EIC is labeled with the carbon number of the 1-alkanal DNPH derivative and the observed mass of the M-H ion.

Summary and Conclusions

This note describes the straightforward addition of API mass spectrometry to a well-established LC method for carbonyl analysis. The resulting APCI-LC/MS method is robust and sensitive, with application not only to simple aldehydes and ketones, but also to hydroxy carbonyls, dicarbonyls, carbonyl esters and keto acids as well. This development has improved a long-standing technique in environmental research, and is applicable to many other fields in which carbonyl-containing compounds are important but difficult to analyze with adequate selectivity, sensitivity, and/or confidence in identification.

Acknowledgments

The authors would like to thank **Christine Miller** of Agilent Technologies for review and helpful comments.

References

1. Grosjean, E., Grosjean, D., Green, Peter G., Anal. Chem. 1999, 71, 1851–1861.
2. Druzik, C. M., Grosjean, D., Van Neste, A., Parmar, S. S., Int. J. Environ. Anal. Chem. 1990, 38, 495–512.
3. Grosjean, E., Grosjean, D., Int. J. Environ. Anal. Chem. 1995, 61, 47–64.
4. Grosjean, E., Grosjean, D., Int. J. Environ. Anal. Chem. 1995, 61, 343–360.
5. Grosjean, E., Grosjean, D. J., Atmos. Chem. 1997, 27, 271–289.
6. Grosjean, E., Grosjean, D., Fraser, M. P., Cass, G. R., Environ. Sci. Technol. 1996, 30, 2687–2703.
7. Grosjean, E., Grosjean, D., Gunawardena, R., Rasmussen, R. A., Environ. Sci. Technol. 1998, 32, 736–742.

Authors

Eric Grosjean is a research chemist at DGA, Inc., and **Daniel Grosjean** is president of DGA, Inc., Ventura, CA.

Peter Green is a senior scientist at the Environmental Analysis Center, Environmental Engineering Science, California Institute of Technology, Pasadena, CA.

John Hughes is a senior applications consultant at Agilent Technologies, Pleasanton, CA.

Table 1. Summary of Data for the DNPH Derivatives of 1-Alkanals.

Carbonyl	Carbonyl-DNPH			
	RRT ^a	UVmax ^b	MW ^c	BP ^{de}
formaldehyde	1.00	355	210	209
acetaldehyde	1.40	364	224	223
propanal	2.30	365	238	237
butanal	3.65	366	252	251
pentanal	5.98	367	266	265
hexanal	7.92	366	280	279
heptanal	8.54	366	294	293
octanal	8.96	365	308	307
nonanal	9.28	363	322	321
decanal	9.52	362	336	335
undecanal	9.74	362	350	349
dodecanal	9.92	361	364	363
tridecanal	10.09	361	378	377
tetradecanal	10.24	361	392	391
pentadecanal	10.43	361	406	405
hexadecanal	10.62	361	420	419
heptadecanal	10.85	360	434	433
octadecanal	11.12	360	448	447

^a RRT = retention time of carbonyl-DNPH relative to that of formaldehyde-DNPH (4.08 ± 0.02 min).

^b UV max = wavelength of maximum absorption, nm, from 200–600 nm absorption spectrum recorded with diode array detector.

^c MW = molecular weight of carbonyl-DNPH.

^d BP = base peak (most abundant ion), *m/z*, in atmospheric pressure negative chemical ionization mass spectrum.

^e No ions other than BP and ¹³C contribution to BP (see text) were present in the spectra of the DNPH derivatives of 1-alkanals.

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Table 2. Summary of Data for the DNPH Derivatives of Other Saturated Aliphatic Carbonyls.^a

Carbonyl	Carbonyl-DNPH				
	RRT	UV max	MW	BP	Other Ions ^b
ALDEHYDES					
2-methylpropanal	3.69	363	252	251	none
3-methylbutanal	5.51	363	266	265	none
2-methylbutanal	5.70	363	266	265	263 (1)
2,2-dimethylpropanal	5.66	364	266	265	none
cyclohexylmethanal	8.09	366	292	291	none
KETONES					
acetone	2.01	368	238	237	none
acetone- <i>d</i> ₆	1.98	367	244	243	237–242 ^c
2-butanone	3.44	369	252	251	none
2-pentanone	5.51	371	266	265	none
3-pentanone	5.51	370	266	265	263 (2)
3-methyl-2-butanone	5.52	370	266	265	263 (2)
3,3-dimethyl-2-butanone	7.78	370	280	279	263 (1)
2,4-dimethyl-3-pentanone	8.27	370	294	293	277 (8)
cyclohexanone	5.36	373	278	277	275 (23)
2-methylcyclohexanone	7.94	371	292	291	289 (25)
nopinone ^d	8.30	372	318	317	315 (5)

^a RRT, UV max, MW, and BP are defined in footnotes *a–d* of Table 1.

^b *m/z*; Not including ¹³C contribution to BP; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

^c Abundances relative to that of BP = 3% (*m/z* = 237), 4% (238), 6% (239), 13% (240), 24% (241), and 44% (242).

^d 6,6-Dimethylbicyclo [3.1.1] heptan-2-one.

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Table 3. Summary of Data for the DNPH Derivatives of Unsaturated Aliphatic Carbonyls.^a

Carbonyl	Carbonyl-DNPH				
	RRT	UV max	MW	BP	Other Ions ^b
ALDEHYDES					
acrolein	2.01	380	236	235	none
crotonaldehyde ^c	3.08	382	250	249	none
methacrolein	3.44	381	250	249	none
2-ethylacrolein	5.55	379	264	263	none
<i>trans</i> -2-hexenal	7.60	382	278	277	275 (7)
2-methyl-2-pentenal	7.67	384	278	277	275 (3)
<i>cis</i> -4-heptenal	7.78 ^d	365	292	291	289 (7)
	7.95 ^e (2%)	366	292	291	289 (7)
<i>trans</i> -2-decenal	9.41	381	334	333	331 (6)
<i>trans</i> -2-undecenal	9.64	380	348	347	345 (5)
KETONES					
methyl vinyl ketone	2.68 ^e (13%)	368	250	249	none
	2.87 ^e (3%)	372	250	249	none
	3.06 ^d	379	250	249	none
1-penten-3-one	4.76 ^d	378	264	263	247 (8)
	4.99 ^e (12%)	376	264	263	247 (9)
3-penten-2-one	4.43 ^e (3%)	382	264	263	none
	4.83 ^d	384	264	263	none
4-methyl-3-penten-2-one	6.94	386	278	277	263 (3)
4-hexen-3-one ^c	7.12 ^e (4%)	385	278	277	none
	7.38 ^e (35%)	357	278	277	none
	7.72 ^d	357	278	277	none
6-methyl-5-hepten-2-one ^f	8.27	368	306	305	289 (4)
4-acetyl-1-methylcyclohexene	8.64	369	318	317	301 (4)

^a RRT, UV max, MW, and BP are defined in footnotes *a–d* of Table 1.

^b *m/z*; not including ¹³C contribution to base peak; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

^c Predominantly the *trans* isomer.

^d Largest peak.

^e Smaller peak; percent of largest peak (peak height basis at 360 nm) given in parentheses.

^f Two coeluting peaks.

Table 4. Summary of Data for the DNPH Derivatives of Aromatic Carbonyls.^a

Carbonyl	Carbonyl-DNPH				
	RRT	UV max	MW	BP	Other Ions ^b
benzaldehyde	4.75	384	286	285	none
<i>o</i> -tolualdehyde	7.13	386	300	299	none
<i>m</i> -tolualdehyde	7.29	385	300	299	none
<i>p</i> -tolualdehyde	7.35	388	300	299	none
acetophenone	6.77	382	300	299	none
2,5-dimethylbenzaldehyde	8.15	389	314	313	none
2-hydroxybenzaldehyde (salicylaldehyde)	2.97	391	302	301	none
4-methoxybenzaldehyde (<i>p</i> -anisaldehyde)	4.98	398	316	315	none
3,4-dimethoxybenzaldehyde	3.07	398	346	345	none
4-hydroxy-3-methoxybenzaldehyde (vanillin)	1.75	402	332	331	329 (2), 315 (1)
4-hydroxy-3-methoxyacetophenone (acetovanillone)	2.37	393	346	345	343 (5), 329 (45), 313 (4), 298 (2)
3,5-dimethoxy-4-hydroxybenzaldehyde (syringaldehyde)	1.54	436	362	361	360 (40), 359 (1), 345 (1)
4-hydroxy-3-methoxycinnamaldehyde (coniferyl aldehyde)	2.67	415	358	357	356 (12), 355 (22), 325 (5), 310 (10)

^a RRT, UV max, MW, and BP are defined in footnotes *a–d* of Table 1.

^b *m/z*; not including ¹³C contribution to BP; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

Table 5. Summary of Data for the DNPH Derivatives of Dicarbonyls.^a

Carbonyl	Carbonyl-DNPH					
	RRT	UV max	MW (mono)	MW (di)	BP	Other Ions ^b
glyoxal	6.09	415	238	418	417	237 (14), 238 (16)
methylglyoxal	7.90	432	252	432	431	251 (14), 249 (17)
2-oxobutanal ^c	8.31	410	266	446	445	263 (12)
2,3-butanedione	1.50 ^e (1%)	362	266		265	none
	1.79 ^e (2%)	369	266		265	none
	8.31 ^d	403		446	445	265 (7), 263 (48)
succinic dialdehyde	0.81 ^e (5%)	360	266		265	
	1.55 ^{d,f}	338 ^f			247 ^f	
	6.42 ^e (12%)	368		446	445	263 (80)
glutaraldehyde	7.34	368	280	460	459	279 (10)
2,3-pentanedione	8.72	402	280	460	459	443 (8), 279 (15)
2,4-pentanedione	1.03	310	280	460	262	302 (14), 232 (6), 360 (7), 279 (0.1), 288 (5)
3,4-hexanedione	8.89	400	294	474	473	293 (5), 291 (12)
pinonaldehyde ^g	3.73 ^e (9%)	368	348		347	none
	9.07 ^d	368		528	527	345 (16)

^a RRT, UV max, and BP are defined in footnotes *a*–*d* of Table 1. MW (mono) and MW (di) are the molecular weights of the mono-DNPH derivative and di-DNPH derivative, respectively.

^b *m/z*; not including ¹³C contribution to BP; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

^c Prepared by reaction of ozone with 1-penten-3-one, 2-ethylacrolein, and 4-hexen-3-one.

^d Largest peak.

^e Smaller peak; percent of largest peak (peak height basis at 360 nm) is given in parentheses.

^f This compound is not the mono-DNPH derivative; see text.

^g (2,2-Dimethyl-3-acetylcyclobutyl) ethanal, prepared by reaction of ozone with pinene.

**LC/DAD/MS Analysis of Carbonyl
(2,4-Dinitrophenyl)hydrazones****Table 6. Summary of Data for the DNPH Derivatives of Other Carbonyls.^a**

Carbonyl	Carbonyl-DNPH				
	RRT	UV max	MW	BP	Other Ions ^b
methyl glyoxylate ^c	0.89 ^f (60%)	355	268	267	none
	1.72 ^e	357	268	267	none
ethyl glyoxylate	1.24 ^f (65%)	356	282	281	none
	2.71 ^e	359	282	281	none
2-oxoethyl acetate ^d	1.14 ^e	360	282	281	249 (18)
	1.22 ^f (13%)	356	282	281	249 (16)
methoxyacetone	1.59 ^e	363	268	267	none
	2.25 ^f (30%)	370	268	267	none
2-furaldehyde	2.14 ^e	392	276	275	none
	3.00 ^f (25%)	383	276	275	none

^a RRT, UV max, MW, and BP are defined in footnotes *a–d* of Table 1.

^b *m/z*; not including ¹³C contribution to base peak; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

^c Prepared by reaction of ozone with methyl acrylate and with methyl *trans*-3-methoxyacrylate (MTMA).

^d Prepared by reaction of ozone with MTMA and with *trans*-2-hexenyl acetate.

^e Largest peak.

^f Smaller peak; percent of largest peak (peak height basis at 360 nm) is given in parentheses.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

Copyright © 2000

Agilent Technologies

All rights reserved.

Reproduction and adaptation is prohibited.

Printed in the U.S.A. January 2000

(23) 5968-8850E



Measuring Hydrocarbon Oil Index according to ISO 9377-2 (DIN H53)

Environmental Application

Gas Chromatography

Bernhard Wüst

Abstract

Agilent Technologies developed this analytical method to comply with ISO 9377-2 and DIN H53 Standards. The method employs a simple instrument configuration consisting of a Gas Chromatograph (GC) equipped with a Split/Splitless (S/SL) inlet and Flame Ionisation Detector (FID), making the method both easy to implement and robust to operate. The combination of an Agilent GC system (see configuration above), selected capillary GC column, proprietary injection port liner, appropriate chemical standards as well as method installation and support by an Agilent Applications Specialist, provide a *complete solution* for the measurement of the Hydrocarbon Oil Index.

Introduction

The Hydrocarbon Oil Index (HOI) is defined as the total amount of compounds which can be extracted from the sample (potable water, surface water and waste water) with a non-polar solvent having a boiling point between 39°C and 69°C (replacing the use of halogenated solvents). In addition, the compounds must not absorb on Florisil and must elute between n-decane ($C_{10}H_{24}$) and n-tetracontane ($C_{40}H_{82}$) when analysed by GC using an apolar analytical column. Restrictions on the use of halogenated hydrocarbons as solvents for analytical applications combined with the increasing cost of and reduced availability of technical grade halogenated solvents as well as documented environmental

considerations resulted in the change to a non-polar solvent for HOI determinations.

This analytical method complies with the ISO Standard 9377-2 for the determination of the Hydrocarbon Oil Index by Gas Chromatography. The method is suitable for HOI determinations in concentrations above 0.1 mg/L in drinking waters, surface waters, waste waters and waters from sewage treatment plants.

Experimental

The Agilent 6890 and Agilent 6850 Gas Chromatographs are well suited to the HOI application. Both instruments use the same Split/Splitless inlet system and identical Flame Ionisation Detector. Discrimination effects on higher boiling compounds are the most critical aspect of the analysis and are prevented by the use of a special injection port liner which, in combination with the Agilent S/SL inlet system, produces robust and reliable data. Additional benefits such as reduced maintenance time and faster analytical cycle times are also available by using a S/SL inlet as compared to a Cool-on-Column inlet.

The Agilent GC ChemStation standard software is able to subtract background signals to produce a chromatogram with any column bleed removed. In addition, both the Agilent 6890 and 6850 are able to save column compensation signals in memory and subsequently subtract the column background from the sample data and provide a background-subtracted signal to the ChemStation or data integration system. Standard ChemStation software tools are used to control the GC and perform the data analysis required of the sample data. A custom report template is included with the HOI method and generates a report conforming to the ISO Standard (see figure 3).

Instrument Parameters

Oven temperature profile	Isothermal 35°C (1.5 min), ramp 5°C/min to 60°C hold 0 min, ramp 15°C/min to 350°C hold 5 min.
Inlet (S/SL)	375°C Splitless Mode
Detector (FID)	375°C
Analytical Column	Agilent Part Number 19095Z-221E (HP1, 15m x 0.53mm x 0,15 µm)
Inlet Liner	Agilent Part Number 5183-4647
Carrier Gas	Helium
Carrier Gas Flow Rate	7.4 ml/min Constant Flow Mode
Injection Mode	Automated (Agilent 7683) Fast Injection
Injection Volume	1.0 µl

Calibration Curve





Figure 1: Oil Standards – Calibration Curve



Discrimination Test:

25 sequential injections of a standard containing tetracontane C-40 and decane C-10 were run to test for discrimination effects within the analytical system. The data obtained is presented in Figure 3 and demonstrates the robustness of the method and that the analytical system clearly passes the discrimination test specified in the ISO Standard.

Results and Discussion

The Agilent 6890 and 6850 Gas Chromatographs equipped with a Split/Splitless inlet and Flame Ionisation Detector can be used for Hydrocarbon Oil Index determinations in accordance with ISO 9377-2 (DIN H53) standard. In addition, the analytical system is easy to operate and requires minimal maintenance. Together, the Agilent GC, analytical capillary column, special inlet liner, custom report template, selected chemical standards and Agilent applications expertise provide a complete analytical solution for Hydrocarbon Oil Index determinations.





Figure 3: Discrimination Test

```
Data file : C:\HPCHEM\1\DATA\HYC2509\008F0802.D
Sample Name : 1000 mg/l
=====
Injection Date : 9/26/2000 3:23:50 AM      Seq Line : 8
Sample Name : 1.0 mg/ml                  Vial No. : 8
Acq Operator : bervuest                  Inj. No. : 2
                                           Inj. Vol. : -
```

```
Acq.Method : HYCA04.M
Analysis Method : C:\HPCHEM\1\METHODS\ISO93774.M
Last Changed : Fri, 29. Sep. 2000, 10:04:10 am
```

Analysis of Hydrocarbon Index according to Iso 9377-4 and DIN H53



Hydrocarbon Index Report

```
Calib. Data Modified : Fri, 29. Sep. 2000, 08:25:56 am
Multiplier : 1.000000
```

```
Hydrocarbon Index : 1.052 mg/ml
Low Boilers : 9.061 mg/l
High Boilers : not detectable mg/l
```

Detailed Report

Name	StartTime	EndTime	Ret Time	Total Area	Res.F	Amount
Low Boilers	2.00	4.00	-	239.48	0.03784	9.06
Decane C10	-	-	4.21	213.73	0.03784	8.09
Hydrocarbon Index	4.31	22.37	13.33	15408.08	0.00006	1.05
Tetracontane C40	-	-	22.53	205.67	0.03247	7.94
High Boilers	-	-	-	-	-	n.d.

Figure 4: Report Printout

*Bernhard Wüst is an application chemist
based at
Agilent Technologies GmbH
Hewlett Packard Str. 8
76337 Waldbronn
Germany*

For more information on our products and
services, visit our website at:
www.agilent.com/chem

Copyright © 2000 Agilent Technologies
All Rights Reserved.

Reproduction, adaptation or translation
without prior written permission is
prohibited, except as allowed under the
copyright laws.

Agilent Technologies shall not be liable
for errors contained herein or for
incidental or consequential damages in
connection with the furnishing,
performance, or use of this material.

Information, descriptions and
specifications in this publication are
subject to change without notice.

Publication Number 5988-0621EN



An approach to the determination of N-nitrosodimethylamine at part-per-quadrillion levels using Positive Chemical Ionization and Large-Volume Injection

Harry F. Prest^a and Richard E. Herrmann^b

^a Senior Applications Chemist, Agilent Technologies, California Analytical Division, 1601 California Avenue, Palo Alto, CA 94304

^b Applications Chemist, APEX Technologies, Inc., 1095 Nimitzview Drive, Suite 100, Cincinnati, OH 45230

Introduction

N-nitrosodimethylamine (NDMA, Figure 1) is one of a series of nitroso compounds known to be carcinogenic. NDMA is found in nitrate-cured or smoked meats,¹ cheeses,² tobacco smoke,³ cooked foods and in beverages such as beer⁴ (both foreign and domestic⁵⁻⁷). The presence of NDMA in surface waters designated for use drinking water use is of particular concern and the U.S. Environmental Protection Agency (EPA) has promulgated a regulatory standard for these waters of 0.7 ng/l (700 ppq). When in 1998 NDMA was detected in California drinking water, the source was associated with the production and use of a rocket fuel component, unsymmetrical dimethylhydrazine. In response, the California Department of Health Services (DHS) announced an action level in drinking water of 2 ng/l (2 ppt). However, the best available methods in the literature provide *detection* limits on the order of 1–3 ng/l. EPA methods 625 and 1625 specify a detection limit for NDMA of 50 ppb—25,000 times the California DHS action level and 70,000 times the EPA regulatory standard. It follows that using existing methodologies, *any* detection of NDMA represents a violation.




Figure 1. N-nitrosodimethylamine, $(\text{CH}_3)_2\text{N}_2\text{O}$, 74 g/mole, CAS Registry No. 62-75-9

Determining NDMA at ppt or ppq concentrations in water is an analytical challenge. The extraction methods that have been applied, such as liquid-liquid or solid-phase extraction,⁸⁻¹⁰ produce concentration factors of 500 to 1000, but overall recoveries are generally low. The high polarity and volatility of NDMA contribute to lowered recoveries and extensive extract concentration by evaporation can lead to high losses.

To increase sensitivity and specificity, one prevalent detection scheme involves use of the chemiluminescent nitrogen detector. Electron impact mass spectrometry has also been used but the fragmentation pattern is not very favorable (Figure 2). While the molecular ion at 74 m/z may be a reliable quantitation ion, the confirming ions at 42 and 43 m/z are hardly unique and are easily compromised by fragments from interferences.




Figure 2. Electron impact ionization mass spectrum of NDMA

An approach to the determination of N-nitrosodimethylamine at part-per-quadrillion levels using Positive Chemical Ionization and Large-Volume Injection

One approach to overcoming the unfavorable electron impact (EI) ionization mass spectrum of NDMA is to apply positive chemical ionization (PCI). PCI can provide enhanced analyte selectivity and sensitivity. Utilizing large-volume injection (LVI) should lower the concentration of NDMA that can be detected in an extracted sample. This note describes the combined application of these two techniques as a possible approach to determining NDMA at ppt and ppq concentrations.

Experimental

NDMA standards were made by serial dilution in 1-ml of dichloromethane from a 100 ng/μl standard (Ultra Scientific, Kingstown, RI; part number NS-100). Dichloromethane was chosen as the solvent, because this solvent is used in both liquid-liquid and solid-phase extraction techniques.

Instrumental Section

The 6980 Plus GC / 5973 MSD with chemical ionization option was operated in the selected-ion-monitoring mode (SIM) with ammonia reagent gas. An HP-210 GC column 50%-trifluoropropyl-50%-methylsiloxane (30-m, .25 mm i.d., 0.5 μm film thickness, Part Number 19091C-733) was used with a 5-m, 0.32 mm i.d. uncoated retention gap (Part Number 19091-60600) joined by a press-fit connector (Part Number 5062-3555). A 100-μl syringe was used in the integrated automated liquid sampler 7683 injector for the 50-μl injections. GC oven conditions and mass selective detector settings are given in Tables 1 and 2.

Table 1. GC and Injector parameters

Oven Temperature Program	Temp	Time
Initial Temperature	45°C	3.00 min
Ramp 50°C / min	180°C	0.50 min
GC Oven Equilibrium Time		3.00 min
MSD Transfer Line		225°C
Inlet Mode		Split
Split Flow		50 ml / min
Gas Saver		Off
Column Flow (Helium carrier gas)		2.0 ml / min
Mode		Constant Flow
Outlet Pressure		Vacuum
Injection Volume		50 μl
Syringe Size		100 μl
Plunger Speed		Slow
Solvent Washes A, B	Methanol*	Dichloromethane

* A solvent that "wets" the glass bore improves syringe life.

Table 2. MSD parameters

Tune File *	PCINH3.U
Ammonia Reagent Gas Flow	10 %
EM Voltage	PCI CH ₄ AutoTune + 400V
MS Quadrupole Temp	106°C
MS Source Temp	250°C
Acquisition Mode	SIM
Solvent Delay	5.25 min
SIM Ions	Dwell
75.1 amu	80 msec
92.1 amu	80 msec

* PCI Autotune parameters were used for these experiments. Autotune provides high sensitivity over a large mass range, but even greater sensitivity for these low molecular weight ions can be achieved by manual adjustment of the tuning parameters.

Large-Volume Injections

The APEX ProSep™ 800 Series XT Plus Preseparation System Inlet (APEX Technologies, Cincinnati, OH) was used as the inlet for large-volume injections.^{11, 12} Injections were made into a fused-silica preseparation column packed with deactivated fused-silica wool in the top 3 to 7 cm of the column (available from APEX). The ProSep Precolumn Temperature Module and Flow Module parameters that were successful for this particular preseparation column are given in Tables 3 and 4. This is a very flexible device, and the parameters given can be further optimized to provide better performance for particular extracted matrices. For example, a higher final precolumn temperature than 180°C can be applied to remove high-boiling contaminants.

Table 3. ProSep Precolumn Temperature Program

	Target	Duration
Initial	45°C	0.05 min
250°C / min	180°C #	6.00 min

Higher bake-out temperatures are recommended for extracted samples.

Table 4. ProSep Precolumn Mode Program

	Mode	Duration
Initial	Split	0.05 min
1	Splitless	0.07 min*
2	GC Split **	2.50 min*

*These times should be appropriately optimized.

** It is recommended that ProSep Split be implemented instead of simply GC Split due to superior venting.

An approach to the determination of N-nitrosodimethylamine at part-per-quadrillion levels using Positive Chemical Ionization and Large-Volume Injection

Results

The application of PCI with ammonia reagent gas to NDMA produces a simplified mass spectrum consisting only of protonated NDMA, $[\text{NDMA}+\text{H}]^+$, and the ammonium adduct, $[\text{NDMA}+\text{NH}_4]^+$, which correspond to 75 m/z and 92 m/z, respectively. PCI provides a three-fold advantage over the EI approach. First, the relatively non-unique 74, 43, 42 m/z ions of the EI have been replaced by higher-mass ions. Second, PCI provides increased sensitivity for NDMA and a reduction in low-mass, “background” ions which enhances the signal-to-noise ratio. Third, by manipulating the ammonia gas flow, the abundances of the 92 m/z and 75 m/z ions can be controlled. As the ammonia flow into the source is increased, the abundance of the $[\text{NDMA}+\text{NH}_4]^+$ adduct also increases, allowing the ratio of 92 m/z to 75 m/z to be controlled by the analyst. For example, at 0.4 ml/min of ammonia—a relatively low flow setting of the reagent gas mass flow controller (8% of the total 5-ml/min provided by the controller)—the ratio of the protonated form to adduct is biased toward the protonated form: $[\text{NDMA}+\text{H}]^+ : [\text{NDMA}+\text{NH}_4]^+ = 4 : 3$. At higher flows, the situation reverses and $[\text{NDMA}+\text{NH}_4]^+$ predominates, e.g., at 0.9 ml/min ammonia (18% flow setting) $[\text{NDMA}+\text{H}]^+ : [\text{NDMA}+\text{NH}_4]^+ = 1 : 5$. It is therefore possible to produce an intense confirming ion for quantitative applications. A good compromise between signal intensities and ion abundances was achieved at a




Figure 3. Extracted ion chromatogram for NDMA at 40-fg/ μl using PCI-SIM with NH_3 reagent gas.

0.5 ml/min ammonia flow setting. Figure 3 shows the 75 m/z and 92 m/z SIM signals for a 40-fg/ μl standard for this flow. Under these conditions, $[\text{NDMA}+\text{H}]^+$ is 79% of $[\text{NDMA}+\text{NH}_4]^+$ according to the integrated signal areas.

Figure 4 shows the results of a linear regression of the response of the 92 m/z ion for 50- μl injections of NDMA standards from 20-fg/ μl to 4000-fg/ μl . The regression fit was very good, $r^2 = 0.999$, considering the propagation of error in the dilutions. The relative standard deviation in the response factors was less than 6% and could be improved by using a perdeuterated or ^{15}N -labeled NDMA surrogate.




Figure 4. Linear regression of response of the 92 m/z ion versus NDMA concentration from 20-fg/ μl to 4000 fg/ μl , $r^2 = 0.999$.

Table 5 shows the excellent degree of reproducibility in the ratio of 75 m/z confirming ion to 92 m/z target ion over a wide range of concentrations. The absolute value of the ratio was 0.79, with a relative standard deviation of $< 3\%$. This high precision is important to the degree of confidence in confirming and quantitating NDMA.

Table 5. Reproducibilities of the ratio of the integrated areas of 75 m/z : 92 m/z and the response of the 92 m/z target ion for 5 injections at 5 concentrations.

Concentration as fg NDMA / μl	RSD Ratio 75 m/z / 92 m/z	RSD Response by 92 m/z area
20	2.9%	2.4%
40	2.2%	3.2%
200	0.7%	0.8%
2000	0.7%	1.7%
4000	0.3%	0.9%

Table 5 also shows the excellent reproducibility of the response of the 92 m/z ion for replicate 50- μl injections. Even at the 20-fg/ μl concentration, precision is better than 3%.

An approach to the determination of N-nitrosodimethylamine at part-per-quadrillion levels using Positive Chemical Ionization and Large-Volume Injection

Conclusions

Concentration and recovery factors for NDMA using present published methodologies suggest effective pre-concentration of NDMA in samples to be on the order of 500, e.g., 60–70% recovery of NDMA in extraction of a 1-liter water sample. This implies that the low 20-fg/ μ l NDMA standard corresponds to a sample concentration of 40 pg/l, or 40 parts-per-quadrillion. Alternatively, to quantitate NDMA at 0.5 ppt in water, which is 4 times lower than the California DHS limit and slightly lower than the EPA regulated limit, quantitating at 20 fg/ μ l is equivalent to requiring the extraction of *only* 80 ml of water even if recoveries are still only 50%. Extracting small volumes presents a significant simplification of the process and offers savings in solvent and related materials, and in processing time.

With NDMA eluting in about 5 ¹/₂ minutes, the analysis is fast, and the run-to-run cycle time is short—less than 13 minutes between injections. The method may be further optimized for even more rapid analysis.

The 5973 MSD provides very stable ratios for the confirming ion that can be optimized for quantitative purposes as described. In contrast to EI, in which many possible interfering fragment ions are possible that may distort the ratio of the target and confirming ion(s), PCI with ammonia is unlikely to cause fragmentation-induced interferences because of the relatively “gentle” nature of ammonia reagent gas. Interferences could occur involving compounds with molecular weights of 74 or 91 g/mole eluting at the same retention time but that is unlikely scenario.

The high degree of reproducibility in the injections, even at very low NDMA concentrations, demonstrates the robustness of large-volume injections using the APEX ProSep with the 6890/5973 MSD. It should be emphasized that the reproducibility of 2.4% for the replicate 50- μ l injections of the 20-fg/ μ l standard reported here was for the *absolute* response. Use of an internal standard should further lower the deviation in response and improve quantitation.

Using this approach it should now be possible to satisfy the 2 ppt action level for NDMA set by the State of California and the 700 ppq regulatory standard promulgated by the U.S. EPA.

References

1. Pensabene, J.W., W. Fiddler, and J.G. Phillips, Gas-chromatographic—chemiluminescence method for determination of volatile N-nitrosamines in minced fish-meat and surimi-meat frankfurters: collaborative study. *J-Assoc-Off-Anal-Chem.* Nov–Dec 1990; **73**(6): p. 947–952.
2. Dellisanti, A., G. Cerutti, and L. Airoidi, *Volatile N-nitrosamines in selected Italian cheeses.* *Bull-Environ-Contam-Toxicol.* Jul 1996; **57**(1): p. 16–21.
3. Mahanama, K.R.R. and J.M. Daisey, *Volatile N-nitrosamines in environmental tobacco smoke: sampling, analysis, emission factors and indoor air exposures.* *Environ-Sci-Technol.* May 1996; **30**(5): p. 1477–1484.
4. Markl, K.S. and R.A. Latimer, *Analytical methodology and determination of N-nitrosodimethylamine in beer, wort and malt.* *J-Am-Soc-Brew-Chem.* 1981; **39**(2): p. 59–64.
5. Gloria, M.B.A., J.F. Barbour, and R.A. Scanlan, *N-nitrosodimethylamine in Brazilian, U.S. domestic, and U.S. imported beers.* *Journal of Agricultural and Food Chemistry*, 1997; **45**: p. 814–816.
6. Izquierdo-Pulido, M., J.F. Barbour, and R.A. Scanlan, *N-nitrosodimethylamine in Spanish beers* *Food and Chemical Toxicology*, 1996; **34**: p. 297–299.
7. Stacchini, P. and M. Baldini, *Nitrosodimethylamine in the beer: Study on the presence in foreign and Italian beers.* *Rivista di Scienza dell’Alimentazione*, 1994; **23**: p. 187–192.
8. Jenkins, S.W.D., et al., *N-nitrosodimethylamine in drinking water using a rapid, solid-phase extraction method.* *Environmental Science and Pollution Research International*, 1995; **2**: p. 207–210.
9. Tomkins, B.A. and W.H. Griest, *Determination of N-nitrosodimethylamine at part-per-trillion concentrations in contaminated ground waters and drinking waters featuring carbon-based membrane extraction discs.* *Anal-Chem.* 1 Aug 1996; **68**(15): p. 2533–2540.

(references continued . . .)



10. Tomkins, B.A., W.H. Griest, and C.E. Higgins, *Determination of N-nitrosodimethylamine at part-per-trillion levels in drinking waters and contaminated groundwaters*. Anal-Chem. 1 Dec 1995; **67**(23): p. 4387-4395.
11. anon, *APEX ProSep Pre-column Separation Inlet (PSI)*, Agilent Technologies, Technology Note (23)-5968-4462E, www.hp.com/go/chemsupplies.
12. Prest, H.F., J.S. Hollis, and G. O'Neil, *The APEX ProSep 800 XT Plus Precolumn Separation Inlet: advantages of a chromatographic zone as GC inlet system*, Agilent Technologies, Application Note (23) 5968-5747E, www.hp.com/go/chemsupplies.

Acknowledgments

Harry Prest is very grateful to Dr. William Steeber of the California Department of Health Services, Los Angeles, CA and John M. Hughes of the Gas Phase Chemists Council for their review of the manuscript.


Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

Copyright © 1999
Agilent Technologies
All rights reserved. Reproduction and adaptation is prohibited.

Printed in the U.S.A. September 1999
(23) 5968-7799E

Revision 1.0 - December 1999



Enviromental

Improved Data Quality in the Automated HPLC Analysis of PNAs (PAHs)

Application Note

Angelika Gratzfeld-Hüsgen
Rainer Schuster

This note describes an improved method for analyzing polycyclic aromatic hydrocarbons (PNAs) by HPLC. During the investigations the major focus was on improving precision of retention times and peak areas by using vacuum degassing and stable, low ambient temperatures. Thorough degassing prevented quenching effects in fluorescence detection and improved retention-time stability. Thermostating the column temperature slightly below ambient temperature improved resolution of critical peak pairs. With this method the retention-time stability was within 0.05 – 0.2 % RSD. The RSD for the area in the low ng range was in general below 2 %. An improved diode-array detection system allowed PNAs to be detected at ppb levels and their identity at less than 1 mAUFS confirmed automatically by UV-Visible spectral library search.



Agilent Technologies
Innovating the HP Way

Introduction

Hydrocarbons with multiple-ring structures are collectively referred to as polynuclear aromatic hydrocarbons, commonly abbreviated as PNAs or PAHs (figure 1).

This class of compounds are suspected to be carcinogenic or mutagenic. This has lead to legislative restrictions on their release into the environment. They are mainly formed due to incomplete combustion of organic material, such as fossil fuels.

Analysis by HPLC with UV-Visible diode-array and/or fluorescence detection has become a well-established method for the determination of PNAs in soil, water, sludge air and food. However, despite the common use of this method, degassing techniques and temperature stability still cause problems with qualitative and quantitative evaluation.

The best separation of PNAs is achieved at or slightly below ambient temperatures. Without column cooling this often results in unstable retention times caused by ambient temperature fluctuation. To get optimum sensitivity in fluorescence detection, excitation and emission wavelength switching is required. This implicates not only good resolution of the compounds but also stable retention times.

Traces of oxygen in the mobile phase deteriorate fluorescence sensitivity because of quenching effects. Helium degassing and other conventional techniques however will not give highest sensitivity compared to the vacuum system used in this study.

For samples with higher contamination levels a UV-Visible diode-array detector was used to get spectral information for identification and peak-purity control. A major improvement in the sensitivity of this detector allowed spectra to be taken at ppb levels with identification at less than 1 mAUFS.

Current evaluation software for diode-array detectors focuses on interactive spectral evaluation. This is very time consuming, requires sophisticated operators and is impractical for routine analysis.

Traditionally standard columns of about 4 mm id are used for PNA analysis, requiring high solvent amounts with high purchase and disposal costs. Although narrow-bore columns with 2 mm id are available, ideally suited for use at lower flow rates and give higher mass sensitivity they are still not widely used. Further, much of the currently-available routine HPLC equipment does not give reliable results for gradient operation at low flow rates.

In this study we investigated the Agilent 1100 Series HPLC system to determine to what extent this new system could solve some or all of the problems described.




Figure 1
Examples of PNAs (PAHs)

Experimental

The system comprised an Agilent 1100 Series quaternary gradient pump, vacuum degasser, auto-sampler, thermostatted column compartment, diode-array detector and HP 1046A fluorescence detector. Complete system control and data evaluation was done on the Agilent ChemStation for HPLC. The thermostatted column compartment included a Peltier element for precise temperatures above, below and at ambient temperature.

For the separation we used a dedicated PNAs column that allowed the separation of PNA isomers. For economic reasons we used a column with an internal diameter of 2.1 mm that allowed a solvent flow of 0.4 ml/min. For evaluation of separation we used the 16-component EPA standard spiked with some other components that may be present in typical environmental samples and that may chromatographically interfere with the compounds of interest.




Figure 2
Schematic of instrumentation used

Column 250 _ 2.1 mm PAH column, 5 mm
(Agilent part no. 79918PAH-582)
Buffer A water
Buffer B acetonitrile

Temperature 18 °C, 25 °C, 30 °C, see figure

Flow rate 0.4 ml/min

Gradient 50 % B to 60 % in 3 min
to 90 % in 14.5 min
to 95 % in 22.5 min

Detector Sample wavelength 270 nm,
bandwidth 40 nm

Samples See table 1




Figure 3
Separation of DIN/EPA standards at different column temperatures

Results

Impact of column temperature on separation

We investigated the impact of column temperature on the separation at three different temperatures: 30, 25 and 18 °C. The 16 EPA compounds could be separated at all temperatures (see figure 3), however a temperature of 18 °C had several advantages:

- The resolution between critical compound pairs such as benzo(ghi)perylene and indeno(1,2,3-cd)pyrene was better. This allowed trouble-free switching of excitation and emission wavelengths when using a programmable fluorescence detector.
- Additional interfering compounds such as anthrachinon could be separated from the PNAs. Figure 3 clearly shows the improved separation of PNAs far below 30 °C.

Peak #	Name of compound	RSD t_R (15 runs)	RSD area (15 runs)
1	Naphthalene	0.12%	1.41
2	Anthrachinon	0.05%	3.70
3	Acenaphthylene	0.10%	3.51
4	Acenaphthene	0.09%	3.71
5	Fluorene	0.08%	1.76
6	Phenanthrene	0.06%	1.72
7	Anthracene	0.05%	1.42
8	Fluoranthene	0.05%	1.40
9	Pyrene	0.05%	1.62
10	Benzo(a)anthracene	0.05%	1.59
11	Chrysene	0.06%	1.60
12	Benzo(b)fluoranthene	0.07%	1.90
13	Benzo(k)fluoranthene	0.08%	1.96
14	Benzo(a)pyrene	0.08%	1.76
15	Dibenzo(a,h)anthracene	0.09%	1.62
16	Benzo(ghi)perylene	0.09%	1.99
17	Indeno(123-cd)pyrene	0.11%	2.50

Table 1
Precision of retention times at 18 °C column temperature, with ambient temperature of 25 °C

Precision of retention times and peak areas

Stable retention times are important for correct identification of complex environmental matrices. When using a time-programmable fluorescence detector stable retention times are also important to avoid wavelength switching during an analyte's elution.

Precision of peak areas is important for obtaining reliable quantitative data.

Table 1 demonstrates typical RT precision of better than 0.2 %, obtained over 15 runs at 7 degrees below ambient. Peak-area precision for the low ng range is below 2 % RSD in general, if the peaks are well separated. It goes up to 4 % RSD if the peaks are not baseline separated.

Impact of vacuum degassing on fluorescence detection

PNAs can be quantified reproducibly down to the low picogram range with the correct fluorescence detection method. Careful selection of excitation and emission wavelengths and the use of mobile phase degassing, ensure high-sensitive PNA analysis. It is well known that the presence of oxygen in the mobile phase deteriorates detection limits because of quenching effects. Therefore thorough degassing is of utmost importance. We investigated the influence of no degassing, helium degassing and vacuum degassing on the response of critical compounds. As figure 4 demonstrates, the best results were achieved with vacuum degassing.

Spectral information with diode-array detection

For highly contaminated samples UV-Visible absorbance diode-array detection offers additional analytical tools using the spectral domain: peak-identity and peak-purity confirmation. Acenaphthylene (EPA compound) does not fluoresce, so for this compound UV-Visible absorption is the detection method of choice. An ideal detection method for PNAs is the serial detection with fluorescence and UV-Visible diode-array instrumentation. Here highest sensitivity is combined with optimum selectivity and additional identification tools for highly contaminated samples.




Figure 4

Quenching by dissolved oxygen can be avoided with a suitable mobile phase degassing technique

Automated positive identification of PNAs in soil with diode-array detection

Figure 5 shows the analysis of a soil extract using UV-Visible diode-array detection. The oven temperature was 22 °C. This still gave good resolution for early eluting peaks and allowed sensitive detection of late eluting peaks, for example, coronene.

The Agilent ChemStation's spectral search routine used here compares each spectrum with those stored in a spectral library compiled from analyses of standards run beforehand. The software recognizes those spectra that match each other closely within the tolerance window specified. In those cases where a retention time has been tagged to the library records, the spectral match can be further qualified before being pronounced as specified. Figure 6 shows spectral overlay of sample spectra with library pyrene spectrum in the low mAU range. Normalization was done on the spectra library's spectra.

The complete method — HPLC separation with data acquisition, data evaluation, quantification, and identification — can be automated for multiple, unattended analyses. The reports that are generated include sample amounts, purity and library identity information.




Figure 5
Analysis of PNAs in soil sample (extraction was made with super critical fluid extraction)1




Figure 6
Identification of pyrene using spectral library search with report containing quantitative and qualitative results

Conclusion

The new Agilent 1100 Series HPLC systems solved the problems usually associated with the analysis of PNAs.

The Peltier thermostatted column compartment allowed the analysis of PNAs at ambient and subambient column temperatures with high precision. Peltier cooling was preferred to water cooling systems, because no additional equipment was needed and control and setup was easier and convenient.

The vacuum degasser enabled quenching-free fluorescence detection of PNAs at lowest detection limits due to the highly-efficient removal of oxygen from the mobile phase.

The Agilent ChemStation for HPLC gave full automation capabilities starting with complete control of all modules, data acquisition, data evaluation and report presentation with spectrally confirmed *qualitative* and *quantitative* results.

The quaternary gradient pump, vacuum degasser and Peltier thermostatted column compartment provided excellent retention-time stability at a flow of 0.4 ml/min. This saved purchase and disposal costs for solvents and allowed to work with a factor of four lower sample volumes.

References

- 1
Helmut Schulenberg-Schell,
Rainer Schuster (Agilent
Technologies, Waldbronn,
Germany), unpublished results
presented as a poster at the 3rd
*International Capillary
Chromatography Conference*,
Riva del Garda, **1993**.

Angelika Gratzfeld-Hüsgen and
Rainer Schuster are application
chemists based at Agilent
Technologies, Waldbronn
Analytical Division, Germany.

For the latest information and services visit our
world wide web site:
<http://www.agilent.com/chem>

Copyright © 1995 Agilent Technologies
All Rights Reserved. Reproduction, adaptation
or translation without prior written permission
is prohibited, except as allowed under the
copyright laws.

Publication Number 5964-3540E




Agilent Technologies
Innovating the HP Way



Water

Pesticides and Residues Applications

> [Return to Table of Contents](#)
> [Search entire document](#)



Contract Laboratory Program (CLP) Pesticide Analysis with 0.18 mm ID High-Efficiency GC Columns Utilizing Helium Carrier Gas

Application

Environmental

Authors

Ken Lynam and William Long
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, Delaware 19808
U.S.A.

Abstract

Contract Laboratory Program (CLP) pesticide analysis is demonstrated on high-efficiency GC columns (20 m × 0.18 mm id × 0.18 μm film thickness) with helium carrier gas. DB-17ms stationary phase is used for primary analysis and DB-XLB stationary phase for confirmation. Primary analysis and confirmation of 22 CLP pesticides in the protocol is achieved in an 11-minute analysis, a 35% reduction in analysis time versus 0.32 mm id columns.

Method translation software is successfully employed to translate an original set of conditions with hydrogen carrier gas to a new set of conditions using helium carrier gas. Elution order and degree of separation are shown to translate precisely from the original method to the new method through use of this software (available for free download) [1].

Introduction

The determination of organochlorine pesticides (OCPs) in environmental remediation samples are important, high-volume analyses in the competitive contract laboratory marketplace. A standard Contract Laboratory Program (CLP) pesticide method is used for these analyses. In many cases a lab will analyze large numbers of samples over the course of a given project, adding costs to both the lab and its

client. Here, 0.18 mm id high-efficiency GC columns are demonstrated as a means of enhancing laboratory productivity. These columns are fully compatible with standard gas chromatographs and helium carrier gas operation. The high efficiency these columns offer coupled with their full compatibility with existing GCs provide laboratories with a powerful tool for enhancing sample throughput. When analysis times for 30 m × 0.32 id and 20 m × 0.18 mm id columns were compared, a 17-minute analysis was reduced to only 11 minutes and with improved resolution [2].

Helium carrier gas was selected as a means to show the utility of 0.18 mm id columns in doing CLP pesticide analyses and to demonstrate the full compatibility of these columns with standard gas chromatographs. The operating gas pressures for these 20 m × 0.18 mm id columns range from 33 psi initially to 50 psi at the high point of the temperature program. The gas pressure range used with helium carrier gas with these 0.18 mm id columns was well within the operating range for standard chromatographs.

Experimental

This work was accomplished using an Agilent 6890N GC equipped with dual μECDs and a 7683B autosampler. A single split/splitless injection port was used for sample introduction at the head of a retention gap column connected through a Y-splitter with two analytical columns. Details of the chromatographic conditions are presented in Table 1.



Agilent Technologies

Table 1. Chromatographic Conditions

GC	Agilent 6890N
Sampler:	Agilent 7683B, 5 μ L syringe (Agilent p/n 5181-1273), 0.5 μ L injection
Inlet	Split/splitless; 250 °C pulsed splitless (35 psi for 0.5 min)
Inlet liner	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Carrier	Helium (constant flow, 49.5 cm/sec at 120 °C, purified through big universal trap Agilent p/n RMSH-2)
Retention gap	5 m $\times$ 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	
1	20 m $\times$ 0.18 mm $\times$ 0.18 μ m DB-17ms (Agilent p/n 121-4722)
2	20 m $\times$ 0.18 mm $\times$ 0.18 μ m DB-XLB (Agilent p/n 121-1222)
Oven	120 °C (0.49 min); 85 °C/min to 160 °C; 20 °C/min to 260 °C (0.20 min); 25 °C/min to 285 °C; 40 °C/min to 300 °C (3.5 min)
Detection	μ ECD 325 °C; nitrogen makeup; constant column + makeup flow 60 (mL/min)

The flow path supplies used in these experiments are listed in Table 2 below.

Table 2. Flow Path Supplies

		Agilent p/n
Vials	Amber screw cap	5182-0716
Vial caps	Blue screw cap	5282-0723
Vial inserts	100 μ L glass/polymer feet	5181-1270
Syringe	5 μ L	5181-1273
Septum	Advanced green	5183-4759
Inlet liner	Deactivated single taper direct connect	1544-80730
Ferrules	0.4 mm id short; 85/15 Vespel/graphite	5181-3323
Y-splitter	Quartz deactivated	5181-3398
Sealing resin	Polyimide sealing resin	500-1200
20x magnifier	20x magnifier loop	430-1020
Tubing cutter	Ceramic wafer column cutter	5181-8836

Sample Preparation

CLP pesticide standard solutions were purchased from AccuStandard, New Haven, CT 06513-USA. ULTRA RESI ANALYZED grade 2,2,4 trimethylpentane was purchased from J. T. Baker, Phillipsburg, NJ 08865-USA. CLP-023R-160X and CLP-024R-160X concentrates were diluted separately into two

100-mL volumetric flasks in 2,2,4 trimethylpentane and then combined in subsequent serial dilutions. Volumetric flasks and pipettes used were all class A. Standard concentration range for low-level target compounds in the protocol was from 1.6 to 40 ng/mL. On-column loading ranged from 0.4 to 10 pgs for low-level target compounds when a 0.5- μ L injection over both columns is considered.

Column Installation Tip on Using Y Splitters

Installation of the Y splitter was accomplished by coating the outside of the fused silica tubing to be inserted into the Y splitter with a thin film of polyimide sealing resin prior to cutting the tubing. The cut was then made through the coated section of tubing. The cut end was then checked with a 20x magnification loop to make sure that the cut was clean and that excess sealant had not diffused inside the column. Once a clean cut was obtained, the fused silica with the polyimide sealant on the outside only was inserted into the desired branch of the Y and held for approximately 45 seconds to seal. Good sealing was indicated by a thin ring of sealant at the point of contact. The process was done first with the analytical columns and then repeated for the trunk of the Y into the retention gap. This approach gave tight, reliable connections that have lasted without any difficulty for more than 2 months (to date) and hundreds of oven temperature program cycles.

Results and Discussion

The starting point for this application was a set of conditions for CLP pesticide analyses using hydrogen carrier gas and 0.18-mm high-efficiency columns developed by Wool and Decker [3]. Using hydrogen carrier and flow programming, they were able to achieve primary separation and confirmation analysis of CLP pesticides in a 7-minute analysis. The chromatographic parameters for the hydrogen carrier separation were input as initial setpoints in method translation software to convert the method to use with helium carrier. Helium carrier was selected for use in laboratories reluctant to work with hydrogen carrier due to site safety policy or individual preference. High-efficiency GC columns give the chromatographer the option to work with either helium or hydrogen carrier gases and still achieve faster analyses.

Wool and Decker [3] indicated in their paper that frequent trimming of the front of the column was necessary for use with heavy matrix samples due primarily to the lower sample capacity of 0.18-mm columns. In this work a 5-m 0.25-mm id retention gap and Y connector were installed ahead of the

analytical columns to help offset the diminished sample capacity relative to wider bore capillary columns. Use of a retention gap will also shield the analytical columns from deleterious matrix effects and extend the useful lives of the columns.

Agilent's method translation software simplifies conversion from established laboratory GC methods to parallel sets of conditions suitable for high-efficiency GC columns. Chromatographic conditions from the original method, along with the new column dimensions, are entered into a menu-driven table within the software. The software then generates a translated method table with all the new chromatographic setpoints for the translated method. The new translated method setpoints produced by the software are often all that is required to successfully translate a method.

Three primary modes of method translation are available in the method translation software: translate only, best efficiency, and fast analysis. The "translate only" mode produces a set of conditions that most closely resembles the original method in terms of relative position on the Van Deemter curve, degree of separation, and elution order. The "best efficiency" mode generates a set of conditions where column efficiency is prioritized. The "fast analysis" mode generates a set of conditions where analysis speed is prioritized. By using the various modes available a translated method specific to a particular application can be developed quickly with a few keystrokes and iterative passes through the software.

The software is very useful in porting methods from the use of one carrier gas to another. Translation from the original method using one carrier to a method using another carrier is accomplished by entering the original method setpoints, the new column dimensions, and the desired carrier. The software then generates the translated method setpoints for the new column and carrier. For additional information on Agilent's method translation software, please visit this link: <http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>.

Flow programming is not addressed in the method translation software, so minor adjustments to flow rate parameters may be required to achieve desired results. When translating flow-programmed methods, initial or intermediate flow rates can be entered into the original method parameters table to visualize the effect on the other parameters' output in the translated method table. The operator can then collect data at several different flow rates and select the best set of conditions for the application.

In this CLP pesticide example, the original method used a hydrogen carrier and flow programming. The initial flow parameters were entered into the method translation software, along with the new column dimensions, specifying helium as the carrier gas. Translate-only mode was selected in the software and produced the translated method setpoints that appear in Figure 1.

Original Method		Translated Method	
Column			
Length, m	20.00	☐ 20.00	
Internal Diameter, µm	180.0	☐ 180.0	
Film		☐ Unlock	
Thickness, µm	0.180	☒ 0.180	
Phase Ratio	250.0	☐ 250.0	
Carrier Gas	Hydrogen	Helium	
Enter one Setpoint			
Head Pressure, psi	25.756	37.597	
Flow Rate, mL/min	1.7943	1.4354	
Outlet Velocity, cm/sec	155.58	124.47	
Average Velocity, cm/sec	77.30	49.42	
Hold-up Time, min	0.431220	0.674472	
Outlet Pressure (absolute), psi	14.696	☐ 14.696	
Ambient Pressure (absolute), psi	14.696	☐ 14.696	
Oven Temperature 3-ramp Program			
	Ramp Rate	Final Temp.	Final Time
	°C/min	°C	min
Initial	120.00	0.490	
Ramp 1	59.400	160.00	0.000
Ramp 2	23.700	260.00	0.000
Ramp 3	35.600	300.00	1.690
	Ramp Rate	Final Temp.	Final Time
	°C/min	°C	min
	37.977	160.00	0.000
	15.152	260.00	0.000
	22.761	300.00	2.643

Figure 1. Method translation using translate-only mode.

Figure 2 shows the resulting CLP pesticide separations produced using translate-only mode in the method translation software on the DB-17ms column. Note that all 22 species are baseline resolved on the DB-17ms column where there is a partially separated triplet consisting of gamma chlordane, alpha chlordane, and endosulfan 1 on the DB-XLB column (Figure 3). This partially separated triplet was also observed in the original DB-XLB separation using hydrogen carrier.

Table 3 is a standard compound key for the numbered peaks in the chromatograms. Separation characteristics such as degree of separation and elution order were maintained exactly as they were in the original method using the new translated method with helium carrier. The original method

was successfully translated with no additional method development.

Unfortunately, the unresolved triplet on DB-XLB observed in the original method remained unresolved in the translated method. Additional method development attempts focused on resolving the partially separated triplet on the DB-XLB confirmation column and reduction of analysis time. Some success was achieved; however, the trailing two peaks in the triplet remained partially resolved on the DB-XLB confirmation column while analysis time was reduced to 11 minutes. The DB-17ms column resolved all of the species in the protocol throughout these experiments (Figure 4). Triplet resolution on the DB-XLB (Figure 5), though not ideal, is adequate for the purpose of peak confirmation of well-resolved species on the DB-17ms.




Figure 2. Translate-only separation (conditions as in Figure 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 0.4 pg/component loading for low-level target compounds.

Table 3. CLP Standard Compound List Key

1. Tetrachloro-m-xylene	12. 4,4' DDE
2. Alpha BHC	13. Dieldrin
3. Gamma BHC	14. Endrin
4. Beta BHC	15. 4,4' DDD
5. Delta BHC	16. Endosulfan II
6. Heptachlor	17. 4,4' DDT
7. Aldrin	18. Endrin aldehyde
8. Heptachlor epoxide	19. Endosulfan sulfate
9. Gamma chlordane	20. Methoxychlor
10. Alpha chlordane	21. Endrin ketone
11. Endosulfan I	22. Decachlorobiphenyl




Figure 3. Translate-only separation (conditions as in Figure 1) on 20 m × 0.18 mm × 0.18 μm DB-XLB (Agilent p/n 121-1222) with a 0.4 pg/component loading for low-level target compounds.




Figure 4. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 0.4 pg/component loading for low-level target compounds.




Figure 5. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-XLB (Agilent p/n 121-1222) with a 0.4 pg/component loading for low-level target compounds.

Detector Sensitivity and Linearity

The 0.5-μL injections were split between two columns for an on-column loading of 0.4 pg per component of the low-level target compounds. The data suggest that detection limits of at least an order of magnitude lower are possible. Sensitivity and linearity measurements conducted with these chemical species using μECD detection support this assertion [4]. Analyte

concentration range investigated here was from 1.6 – 40 ng/mL. This range meets the 16-fold low- to high-check standard criteria for the protocol and appears to cover only the middle of the dynamic range the detector is capable of fielding. Figure 3 shows the DB-17ms separation where low-level component loading was 0.4 pg. Figure 6 shows the same separation with a 10-pg loading for the same components.




Figure 6. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 10-pg/component loading for low-level target compounds.

Conclusions

Complete separation and confirmation of all 22 species in the CLP pesticide protocol were accomplished in an 11-minute analysis with helium carrier gas. These results demonstrate the utility of these 0.18-mm id high-efficiency GC columns for CLP pesticide analysis. Using a 0.5- μ L injection of pesticide standard solutions over a concentration range of 1.6 – 40 ng/mL gave excellent results. These results easily meet the 16x high/low dynamic range requirement for the protocol and suggest that expanding the range to both lower and higher concentrations is certainly possible with these 0.18-mm columns.

Full compatibility for use of these columns with standard GC equipment and helium carrier was also established by this successful separation. Operating pressure for use of these columns at the high point of the temperature program (300 °C) was 50 psi, well within the operation pressure range for standard GC equipment.

Method translation software successfully translated the original method using hydrogen carrier to the new method using helium carrier. Separation characteristics from the original method, such as elution order and degree of separation, were matched exactly in the translated method. This exercise served once again to validate the simplicity of

method translation using the software. Method development beyond the translated method setpoint only became necessary when improvements to the original separation were attempted.

References

1. To download Agilent Method Translation software, please visit this link: <http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>.
2. C. George, "Rapid Analysis of CLP Pesticides Using High-Temperature DB-35ms and DB-XLB Columns," Application Note 5988-4973EN, December 18, 2001
3. L. Wool and D. Decker, "Practical Fast Gas Chromatography for Contract Laboratory Program Pesticide Analysis," *Journal of Chromatographic Science*, Vol. 40 September 2002
4. I. L. Chang, M. S. Klee, and J. Murphy, "Validation Analysis of EPA CLP Target Organochlorine Pesticides with the Agilent 6890 Series GC and Micro-ECD," Application Note 5966-3742E, February 1998

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
January 16, 2008
5989-7818EN



Agilent Technologies



A Direct Column-Performance Comparison for Rapid Contract Laboratory Program (CLP) Pesticide Analysis

Application

Environmental

Authors

Ken Lynam and John W. Henderson, Jr.
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent J&W High Efficiency GC columns with internal diameter of 0.18 mm for Contract Laboratory Program (CPL) pesticide analyses gave superior results for CPL pesticide primary analysis and confirmation. Chromatograms depicting peak shape characteristics, peak resolution, and baseline stability for two sets of 0.18-mm id columns are presented in a head-to-head comparison. Complete primary and confirmatory analysis of the 20 pesticides in the protocol is accomplished in less than 6 minutes using hydrogen carrier gas and flow programming. Successful primary and confirmatory analyses were achievable only on Agilent J&W High Efficiency GC columns.

Introduction

The analyses of organochlorine pesticides (OCPs) in environmental remediation samples are important, high volume, analyses in the competitive contract laboratory marketplace. A standard Contract Laboratory Program (CLP) pesticide method is used for these analyses. In many cases a lab will analyze large numbers of samples over the course of a given project, accumulating costs to both the lab and its client. Use of Agilent J&W 0.18-mm id High Efficiency GC columns is a means of enhancing laboratory productivity [1-3].

Wool and Decker [3] reported their findings at the U.S. Environmental Protection Agency (Region VI, Houston, TX) laboratory and described the value of columns in the 20 m × 0.18 mm format for CLP pesticide analysis. Their suggestion to use a retention gap to protect the analytical columns from deleterious matrix effects and to help offset the lower sample capacity of these columns relative to wider bore columns was incorporated into this column comparison. Deactivated 5 m × 0.25 mm id retention gaps were used in this series of experiments on each column set used.

Columns with 0.18 mm id capable of doing CPL pesticide analysis are available from several leading column manufacturers. Agilent's suggested pair for CLP pesticide analysis in the 0.18 mm id format is a DB-17ms column for primary analysis and a DB-XLB column for confirmation. Vendor R's offering is a set of proprietary phase 0.18 mm id columns for both primary and confirmation analysis of CLP pesticides.

Experimental

The chromatograph used was an Agilent 6890N GC equipped with dual electron capture detectors (μ ECDs) and a 7683B autosampler. Sample introduction was done by a single split/splitless injection port at the head of a retention gap column connected through a Y-splitter with two analytical columns. Details of the initial chromatographic conditions appear in Table 1.



Agilent Technologies

Table 1. Chromatographic Conditions

GC :	Agilent 6890N
Sampler:	Agilent 7683B, 5 µL syringe (Agilent p/n 5181-1273), 0.5 µL injection
Carrier:	Hydrogen (flow programmed, 69 cm/s at 120 °C, ramped at 99 mL/min to 106 cm/s at 4.4 minutes, purified through a Big Universal Trap (Agilent p/n RMSH-2)
Inlet:	Split/splitless; 220 °C, pulsed splitless (35 psi for 0.5 min, purge flow of 40 mL/min on at 1 minute, gas saver flow 20 mL/min on 3 minutes
Inlet liner:	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Retention gap:	5 m × 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter:	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	1 20 m × 0.18 mm × 0.18 µm DB-17ms (Agilent p/n 121-4722)
	2 20 m × 0.18 mm × 0.18 µm DB-XLB (Agilent p/n 121-1222)
Oven:	120 °C (0.32 min); 120 °C/min to 160 °C; 30 °C/min to 258 °C (0.18 min); 38.81 °C/min to 300 °C (1.5 min)
Detection:	µECD 320 °C; nitrogen makeup; constant column + makeup flow (60 mL/min)

The flow path supplies used in these experiments are listed in Table 2.

Table 2. Flow Path Supplies

	Description	Agilent p/n
Vials:	Amber screw cap	5182-0716
Vial caps:	Blue screw cap	5282-0723
Vial inserts:	100 µL glass/polymer feet	5181-1270
Syringe:	5 µL	5181-1273
Septum:	Advanced green	5183-4759
Inlet liner:	Deactivated single taper direct connect	1544-80730
Ferrules:	0.4 mm id short; 85/15 Vespel/graphite	5181-3323
Y-splitter:	Quartz deactivated	5181-3398
Sealing resin:	Polyimide sealing resin	500-1200
20x magnifier:	20x magnifier loupe	430-1020
Tubing cutter:	Ceramic wafer column cutter	5181-8836

Both sets of columns used in this comparison were installed into the GC in the same manner. The same retention gap and inlet liner were used for both sets of columns. The chromatographic conditions (except for the columns) in Tables 1 and 2 were used to evaluate both the proprietary columns recommended by Vendor R and Agilent's columns. The primary analysis column from Agilent was a 20 m × 0.18 mm × 0.18 µm DB-17ms. The column from Vendor R was a 20 m × 0.18 mm × 0.18 µm with a proprietary stationary phase. The confirmatory analysis column from Agilent was a 20 m × 0.18 mm × 0.18 µm DB-XLB. The column from Vendor R was a 20 m × 0.18 mm × 0.14 µm with a proprietary stationary phase.

Sample Preparation

CLP pesticide standard solutions were purchased from AccuStandard (New Haven, CT 06513 USA). ULTRA RESI ANALYZED grade 2,2,4 trimethylpentane was purchased from J.T. Baker (Phillipsburg, NJ 08865 USA).

CLP-023R-160X and CLP-024R-160X concentrates were diluted first into 50-mL volumetric flasks in 2,2,4 trimethylpentane and then serially diluted. Volumetric flasks and pipettes used were all class A. The standard concentration range for low-level target compounds in the protocol was from 3.2 to 80 ng/mL. On-column loading ranged from 0.8 to 20 pg for low-level target compounds when a 0.5-µL injection over both columns is considered.

Column Installation Using Y Splitters

Installation of the Y splitter was accomplished by coating the outside of the fused silica tubing to be inserted into the Y splitter with a thin film of polyimide sealing resin prior to cutting the tubing. The cut was then made through the coated section of tubing. The cut end was then checked with a 20x magnification loupe to make sure that the cut was clean and that excess sealant had not diffused inside the column. Once a clean cut was obtained, the fused silica with the polyimide sealant on the outside only was inserted into the desired branch of the Y and held for approximately 45 seconds to seal. Good sealing was indicated by a thin ring of sealant at the point of contact. The process was done first with the analytical columns and then repeated for the trunk of the Y into the retention gap. This approach has given tight, reliable connections that have lasted without difficulty for over 2 months and through hundreds of oven temperature program cycles.

Method Translation Software/Path to Successful Conditions

The starting point for this comparison was the conversion of a successful set of separation conditions using helium carrier on Agilent's DB-17ms and DB-XLB 0.18 mm id columns [4] to a set of conditions using hydrogen carrier. The chromatographic parameters for the helium carrier separation were keyed into the translation table in the Agilent GC Method Translation software [5–6] to convert the method to use with hydrogen carrier. In the software, the "Translate Only" mode was used to convert the 11-minute helium carrier method to a 7.3-minute hydrogen carrier method using the same columns.

Method development effort beyond conversion from helium carrier to hydrogen carrier gas became necessary only when the goal of the analysis shifted to emphasize speed of analysis using flow programming. Flow programming is outside the scope of the Method Translation software. In this series of experiments, flow programming helped to elute highly retained peaks faster. Further temperature program modifications also increased the speed of analysis with minimal loss of resolution on the Agilent columns.

Results and Discussion

Successful separation of CLP pesticides using hydrogen carrier was demonstrated on Agilent's DB-17ms and DB-XLB 0.18-mm id columns using the conditions shown in Table 1. Vendor R's 0.18-mm ID columns were evaluated using the following conditions: the conditions shown in Table 1, the conditions obtained on Vendor R's Web site (to the extent practical), and with a set of conditions optimized specifically on Vendor R's columns for this analysis. The goal throughout these experiments was to show as fair and objective a comparison as possible.

To compare chromatograms, injections at a standard concentration of 3.2 ng/mL for low-level target species in the CLP protocol were selected. Using this concentration consistently provides a fixed point of reference and at the same time alleviates the potential for masking deleterious chromatographic effects often seen at higher concentrations. Inclusion of a Y scale in each chromatogram provides another fixed reference within each figure to facilitate comparison. Key aspects to

look for in the example chromatograms are peak resolution, indications of peak tailing, and temperature-dependent drift on the μ ECD.

An Agilent DB-17ms column was used as the primary analysis column in these experiments. An example chromatogram from an injection at a nominal concentration of 3.2 ng/mL for low target level pesticides is shown in the upper portion of Figure 1. This column resolved all the peaks of interest in less than 6 minutes, gave sharp symmetrical peaks, and had minimal background drift on the μ ECD. A compound label key for the numbered peaks in the chromatogram is located in Table 3.

An Agilent DB-XLB 20 m x 0.18 mm x 0.18 μ m column was used for confirmatory analysis on these experiments. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in the lower portion of Figure 1. This column resolved 20 of the peaks of interest in less than 6 minutes and gave near baseline resolution of peaks 10 and 11. Again, sharp symmetrical peaks and minimal temperature-dependent baseline drift were observed on the μ ECD. Although complete resolution of 20 of the 22 peaks of interest on the confirmatory columns is not ideal, the observed resolution is satisfactory for peak confirmation.

The peak identification table applies to Figure 1, depicting CPL pesticide separation on Agilent's column only. Elution order for these columns with their particular selectivity was established in previous work. To establish elution order on Vendor R's columns with different selectivity, injection of individual standards or mass spectral confirmation is required.

Table 3. CLP Standard Compound List Key

1. Tetrachloro-m-xylene	12. 4,4' DDE
2. Alpha BHC	13. Dieldrin
3. Gamma BHC	14. Endrin
4. Beta BHC	15. 4,4' DDD
5. Delta BHC	16. Endosulfan II
6. Heptachlor	17. 4,4' DDT
7. Aldrin	18. Endrin aldehyde
8. Heptachlor epoxide	19. Endosulfan sulfate
9. Gamma chlordane	20. Methoxychlor
10. Alpha chlordane	21. Endrin ketone
11. Endosulfan I	22. Decachlorobiphenyl




Figure 1. Chromatogram of 0.5- μ l injection of 3.2 ng/ml low-level target pesticide standard solution injected through a Y-splitter onto DB-17ms (Agilent p/n 121-4722) primary analysis column and a DB-XLB (Agilent p/n 121-1222) confirmatory analysis column, conditions as in Table 1.

The primary analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.18 μ m with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 2. This column gave resolution of 20 of the 22 peaks of interest, peak tailing for some species, and minimal temperature dependent baseline drift on the μ ECD. The arrows within the figure point to co-eluting and tailing peaks.

The confirmatory analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.14 μ m with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 2. This column yielded resolution of all 22 peaks of interest, indication of peak tailing for some species, and significant temperature-dependent baseline drift on the μ ECD. The arrows within the figure point to tailing peaks and highlight baseline drift, in this case over 100 Hz.

Vendor R's suggested separation conditions for their column pair were unsuccessful at producing results equivalent to those shown on their Web site. This appears to stem from an oversight on their part. Suggested conditions found in a figure caption on the Web site called for a 2-min hold 10° C above the maximum recommended temperature. A temperature of 330 °C was called for; however, the label on the column box listed the upper temperature program limit as 320 °C for the confirmation column. Vendor R's confirmation column demonstrated significant bleed even with a temperature program that reached only 300 °C, a full 20 °C below the upper limit.

A series of attempts to resolve the co-eluting pair of pesticides on Vendor R's primary analysis column gave improved but still incomplete resolution. It was necessary to substantially reduce flow rate and modify both temperature and flow programming parameters to achieve the results shown in Figure 3. The chromatographic conditions used for these injections appear in Table 4; the flow path supplies were the same as those listed in Table 2.




Figure 2. Chromatogram of 0.5 μL injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary analysis column and confirmatory columns, conditions as in Table 1. Figure 2. Chromatogram of 0.5 μL injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary analysis column and confirmatory columns, conditions as in Table 1.

The primary analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.18 μm with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 3. This column still gave resolution of 20 of the 22 peaks of interest, indication of peak tailing for some species, and minimal temperature-dependent baseline drift on the μECD . The arrows within the figure point to the unresolved peaks and tailing peaks.

The confirmatory analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.14 μm with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 3. This column yielded resolution of all 22 peaks of interest, indication of peak tailing for some species, and significant temperature-dependent baseline drift on the μECD . The arrows within the figure point to tailing peaks and highlight baseline drift.




Figure 3. Chromatogram of 0.5- μ L-injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary and confirmatory analysis columns, conditions as in Table 4.

Table 4. Chromatographic Conditions

GC:	Agilent 6890N
Sampler:	Agilent 7683B, 5 μ L syringe (Agilent p/n 5181-1273), 0.5 μ L injection
Carrier:	Hydrogen (flow programmed, 45 cm/s at 120 $^{\circ}$ C, ramped at 99 mL/min to 72 cm/s at 4.4 minutes, purified through a Big Universal Trap (Agilent p/n RMSH-2))
Inlet:	Split/splitless; 220 $^{\circ}$ C pulsed splitless (35 psi for 0.5 min, purge flow 40 mL/min on 1 minute, gas saver 20 mL/min at 3 minutes)
Inlet liner:	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Retention gap:	5 m $\times$ 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter:	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	1 20 m $\times$ 0.18 mm $\times$ 0.18 μ m primary analysis column 2 20 m $\times$ 0.18 mm $\times$ 0.14 μ m confirmatory analysis column
Oven:	120 $^{\circ}$ C (0.50 min); 60 $^{\circ}$ C/min to 160 $^{\circ}$ C; 30 $^{\circ}$ C/min to 260 $^{\circ}$ C; 40 $^{\circ}$ C/min to 300 $^{\circ}$ C (2.0 min)
Detection:	μ ECD 320 $^{\circ}$ C; nitrogen makeup; constant column + makeup flow 60 (mL/min)

Conclusions

Agilent's 0.18-mm id primary analysis column is superior to Vendor R's offering. All 22 peaks of interest were resolved on the DB-17ms primary analysis column in less than 6 minutes with sharp, symmetrical peaks and minimal baseline drift. Vendor R's primary analysis column resolved 20 of 22 peaks of interest and displayed evidence of peak tailing for some of the peaks of interest.

Agilent's 0.18-mm id confirmatory analysis column offering is superior to Vendor R's offering. Twenty of 22 peaks of interest were resolved on the DB-XLB, with the other two peaks being almost baseline resolved in less than 6 minutes, with sharp, symmetrical peaks and minimal temperature-dependent baseline drift. Resolution of 20 of 22 peaks is less than ideal but should serve well for peak confirmation. Vendor R's confirmatory column resolved all 22 peaks of interest but showed evidence of peak tailing and an unacceptable level of temperature-dependent baseline drift.

The DB-17ms and the DB-XLB columns used in these experiments gave very low bleed profiles on the μ ECDs. The stable baselines produced by both of these columns can lead to lower detection limits,

simpler integration and more reliable results over time. These columns also have the versatility of use with other analyses beyond CLP pesticides.

Reliable CLP pesticide primary and confirmation analyses are achievable using Agilent J&W high-efficiency GC columns in less than 6 minutes with standard gas chromatographic equipment.

References

1. I. L. Chang, M. S. Klee, and J. Murphy, "Validation Analysis of EPA CLP Target Organochlorine Pesticides with the Agilent 6890 Series GC and Micro-ECD," Agilent publication 5966-3742E, February 1998
2. C. George, "Rapid Analysis of CLP Pesticides Using High-Temperature DB-35ms and DB-XLB Columns," Agilent publication 5988-4973EN, December 18, 2001
3. L. Wool and D. Decker, "Practical Fast Gas Chromatography for Contract Laboratory Program Pesticide Analysis," *Journal of Chromatographic Science*, Vol. 40, September 2002
4. K. Lynam and W. Long, "Contract Laboratory Program (CLP) Pesticide Analysis with 0.18 mm ID High Efficiency GC Columns Utilizing Helium Carrier Gas," Agilent publication 5989-7818EN, January 7, 2008
5. To download Agilent Method Translation software please visit the link below:
<http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>
6. K. Lynam, "Agilent J&W High-Efficiency Capillary Columns: Productivity-Enhancing Tools for Fast GC Applications," Agilent publication 5989-7499-EN, November 7, 2007

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
February 26, 2008
5989-8031EN



Agilent Technologies

Analysis of Atrazine in Drinking Water at the ppb Level Using New Agilent Reversed Phase LC Columns



Application

Environmental

Author

Rongjie Fu
Agilent Technologies, Inc.
412 Ying Lun Road
Pu Dong, Shanghai 200131
China

Abstract

The herbicide atrazine was analyzed in drinking water samples using the new Agilent reversed phase columns, Agilent TC-C18(2) and HC-C18(2). These columns provided good resolution from interfering or coeluting compounds as well as highly symmetrical peaks and a high performance result. The limit of detection (LOD) is 0.5 ng, which meets China's drinking water standards. The method on these new columns is very suitable for atrazine analysis in drinking water.

Introduction

Atrazine, which is one of the triazine herbicides (structure shown in Figure 1), is a widely used herbicide for control of broadleaf and grassy weeds in the U.S. and some other countries. Atrazine is highly persistent in soil and is leached directly from the soil into groundwater, surface water, and drinking water. Atrazine has potential short-term and long-term health effects. Short-term potential health effects include heart, lung, and kidney congestion, as well as low blood pressure and muscle spasms. Potential health effects from longterm exposure at low levels include weight loss, retinal degradation, cardiovascular damage, and, potentially, even cancer. Therefore, actions have been taken to control this compound and require mea-

suring amounts in drinking water. The maximum contamination level (MCL) regulated by the EPA (U.S. Environmental Protection Agency) is 3 ppb [1]. In China's new drinking water standards, the MCL is set at 2 ppb [2].




Figure 1. Structure of atrazine.

The HPLC method shown here was developed to meet the requirements for atrazine analysis in drinking water in China's new drinking water standards. We chose AccuBond C18 SPE sample cartridges for sample preparation instead of traditional liquid-liquid extraction because of the concentration effect on the atrazine. After water enrichment, the sample was then analyzed with Agilent TC-C18(2) and HC-C18(2) columns, which provide symmetrical peak shape and high sensitivity. It's a simple, fast, and high recovery method that is fit for quality control of drinking water.

Experimental

Standards for Calibration Curve

Accurately weigh 0.01 g atrazine standard and dissolve in methanol to a volume of 100 mL. This is a stock standard solution of 100 µg/mL. Dilute aliquots of the stock standard solution with



Agilent Technologies

methanol into a series of standard solutions of 0, 0.05, 0.1, 0.5, 1.0, and 5 µg/mL.

Sample Preparation

We used the sample preparation method described by Yang et al. [3]. An AccuBond C18 SPE cartridge (Agilent p/n 188-1356) was used to extract the water sample and concentrate the atrazine in the water. Each cartridge was washed with 5-mL aliquots of methanol and reagent water successively, and the cartridge was kept wet after the reagent water wash. The entire sample was vacuum filtered through the cartridge at a flow rate 5 mL/min. The cartridge was washed with 5 mL reagent water and allowed to drain after washing. The sample was eluted from the cartridge with 5-mL portions of methanol and evaporated with a stream of N₂ to a volume of 1 mL. Following the same procedure, 50 mL of reagent water and tap water spiked with 5 ppb standard were treated to get the recovery sample.

HPLC Conditions

Instrument	Agilent 1200SL with DAD
Columns	Agilent TC-C18(2) (p/n: 588935-902) and HC-C18(2) (p/n: 588915-902), 4.6 mm × 150 mm, 5 µm
Mobile phase	55% Methanol:45%Water
Flow rate	1 mL/min
Wavelength	254 nm
Temperature	40 °C
Injection volume	10 µL

Results and Discussion

The standard solutions were analyzed by injecting 10 µL of each of the standard solutions in methanol onto the Agilent TC-C18(2) and HC-C18(2) columns. The calibration curve resulting from these standard injections on the TC-C18(2) column is shown in Figure 2. The method shows excellent linearity, being very close to 1.0 (0.9998). The chromatograms from the standard atrazine injections (Figure 3) show high performance and symmetrical peaks. Some differences in retention were seen on the two columns, which have different carbon loads (the HC-C18(2) has a load of 17% and the TC-C18(2) has a lower load of 12%). These differences impact retention, and nonpolar and moderately polar compounds are typically more retained on the HC-C18(2) column compared with the TC-C18(2) column. The mobile phase for this method used 55% methanol, which is suitable for both columns, but the TC-C18(2) provided a slightly shorter analysis time at just over 7 minutes. We therefore chose the TC-C18(2) for this method.

To evaluate the reproducibility of this method on the TC-C18(2) column, 5 ng of atrazine was injected 10 times. The reproducibility of the peak area is 2.7% and of the retention times is 0.03%; therefore, the TC-C18(2) column provided excellent reproducibility.




Figure 2. Calibration curve of atrazine on TC-C18(2) and HC-C18(2), 4.6 mm × 150 mm, 5 µm columns.




Figure 3. Chromatogram of atrazine standard on TC-C18(2) and HC-C18(2), 4.6 mm × 150 mm, 5 μm columns.

Figure 4 shows a chromatogram for a 0.5-ng atrazine injection. The signal-to-noise ratio is 3:1, so the LOD of this method is about 0.5ng which meets China's new drinking water standards.

An AccuBond C18 SPE cartridge was used in this method to extract trace atrazine in the water sample. The average recovery achieved is 88.2% (n = 3, RSD = 4.1%). This sample preparation method is simple and fast, and a low volume of

organic solvents was consumed, making it an economical sample preparation method as well.

The chromatograms of reagent water and tap water and their spiked samples are shown in Figures 5 and 6. All the potential interfering compounds in reagent and tap water are well separated from the target compound atrazine; therefore, the method selectivity was also very good.




Figure 4. Chromatogram of standard with 0.5-ng injection on TC-C18(2), 4.6 mm × 150 mm, 5 μm columns.




Figure 5. Chromatogram of reagent water and its spiked sample on TC-C18(2), 4.6 mm × 150 mm, 5 μm) columns.




Figure 6. Chromatograms of tap water and its spiked sample on TC-C18(2), 4.6 mm × 150 mm, 5 μm columns.

Conclusions

The herbicide atrazine in drinking water can be easily analyzed at low levels and is well separated from potential interfering compounds in about 7 minutes using a new Agilent TC-C18(2) column. The AccuBond C18 SPE cartridge was used for sample preparation to concentrate the sample and meet the detection limits required of 0.5 ng on column. This total method can be used effectively to measure atrazine in drinking water quickly.

References

1. United States Environmental Protection Agency, "Determination of Chlorinated Pesticides, Herbicides, and Organohalides by Liquid-Solid Extraction and Electron Capture Gas Chromatography," Method 508.1, 1995, EPA Environmental Monitoring Systems Laboratory, Office of Research and Development, Cincinnati, Ohio 45268.
2. Standards of People's Republic of China, Standard Examination Methods for Drinking Water-Pesticides, GB/T 5750.9-2006:26
3. Lifang Yang, et al, "Solid Phase Extraction-HPLC Determination of Atrazine in Drinking Water, Chemical Measure and Analysis," 2007, 16(2):53

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
April 1, 2008
5989-8328EN



Agilent Technologies

Determination of Estrone-3-Sulfate in Water at Sub-ppt Level by LC-(ESI-)-MS/MS



Application

Environmental

Authors

Emmanuelle Bichon, Soazig Elaudais, and Bruno Le Bizec
Laboratoire d'Étude des Résidus et Contaminants dans les
Aliments (LABERCA)
USC INRA 2013
École Nationale Vétérinaire de Nantes (ENVN)
BP 50707
44307 Nantes Cedex 3, France

Abstract

Using solid phase extraction (SPE) and liquid chromatography/tandem mass spectrometry (LC-MS/MS), in negative electrospray mode, estrone-3-sulfate was analyzed down to sub-ppt level ($< \text{ng L}^{-1}$).

Introduction

The occurrence of steroids in the aquatic environment and their effects on normal endocrine function in aquatic organisms are subjects of current concern. Several studies have also shown that birds, reptiles, and mammals in polluted areas undergo alterations of the endocrine-reproductive system.

At present, a multitude of chemicals have been demonstrated to be endocrine disrupters. Among these, natural and synthetic estrogens already show adverse effects at the lower ng/L. Their efficient control in environmental waters is made possible nowadays thanks to numerous analytical approaches available in the literature. This is the case for estradiol (E2), estrone (E1), estriol (E3),

and ethinylestradiol (EE2) measurement. Estrone-3-sulfate (E1S) should also be highlighted, because of its stability in the environment, but until now fewer papers address this xenobiotic.

In this context, this application deals with the development of an analytical method dedicated to the quantification of estrone-3-sulfate in water. Identification relies upon the 2002/657/EC decision to confirm unambiguously the presence of steroids, even at ultra-trace levels ($< 1 \text{ ng.L}^{-1}$).

Experimental

Sample Preparation Procedure

1. Add 10 ng internal standard (boldenone-sulfate- d_3).
2. If needed, filter water samples using 0.45- μm glass fiber filters.
3. Load the water sample onto an MM4 SPE cartridge (1 g, 6 mL) (Interchim, France).
4. Elute the compounds with 12 mL MeOH/ NH_4OH (98:2, v/v).
5. Evaporate the extract to dryness.
6. Reconstitute the extract in 50 μL MeOH/ H_2O (80:20, v/v).

Calibration Curve

Six calibration samples were fortified at 0, 1, 2, 3, 4, and 5 ng/L (ppt) and extracted using the described sample preparation procedure.



Agilent Technologies

LC-MS/MS Measurement (Negative Electrospray Mode)

LC: Agilent 1200
Column: Gemini (50 mm x 2 mm, 3 µm) C18 110 A (Phenomenex)/Agilent equivalent: Extend-C18 3.5 µm, 2.1 x 50 mm (p/n 735700-902)
Column temperature: 40 °C
Mobile phases: A: Ammonium acetate buffer 25 mM, pH 9.2
B: Acetonitrile (ACN)
Flow rate: 0.3 mL/min

Table 1. Elution Gradient

	Time (min)	%B
	0	5
	0.5	5
	15.5	100
	18.5	100
	21	5
	26	5

Injected volume: 10 µL

MS: Agilent 6410 LC/MS Triple Quadrupole
Ionization: ESI (–)
Capillary: 3500 V
Nebulizer pressure: 40 psi
Drying gas: 13 L/min
Gas temperature: 275 °C

MS/MS Parameters

Table 2. MS/MS Parameters

Molecule	Precursor ion	MS1 resolution	Product ion	MS2 resolution	Dwell time (ms)	Fragmentor	Collision energy
Boldenone sulphate-d ₃	368.3	Wide	353.3	Widest	200	120	15
Estrone-3-sulfate T1	349.2	Wide	269.2	Widest	300	200	35
Estrone-3-sulfate T2	349.2	Wide	145.2	Widest	300	200	60

Results and Discussion

Analytical Performance

Validation relies upon the 2002/657/EC decision to assess the methodology performances at sub-ppt levels. Various water samples coming from different origins (surface water or groundwater) were analyzed as blank samples. Five calibration curves were realized from spiked samples (1, 2, 3, 4, and 5 ppt of estrone-3-sulfate). All these samples were extracted according to the sample preparation procedure described previously. Two diagnostic signals (MRM transitions) were monitored for estrone-3-sulfate and one for boldenone-sulfate-d₃. Figure 1 illustrates the high specificity of the signals monitored and the good performance in terms of linearity.




Figure 1. Illustration of the main performance parameters for the developed method (specificity, sensitivity and linearity).

Validation parameters

Table 3 presents the performances measured for each transition in term of linearity (for five different calibration curves), repeatability (at 1, 2, 3, 4, and 5 ppt fortified levels, on five different water), detection limit ($CC\alpha$), and detection capability ($CC\beta$).

Table 3. Validation Parameters

	Linearity (range of R^2 on five calibration curves)	Repeatability (n=25) (5 replicates for each of the 5 tested concentration levels)	$CC\alpha$ (ng.L ⁻¹)	$CC\beta$ (ng.L ⁻¹)
Estrone-3-sulfate				
349.2 → 145.2	0.954 – 0.977	6.8 – 22.6 %	0.08	0.15
349.2 → 269.2	0.976 – 0.991	3.9 – 17.2 %	0.10	0.53

Analysis of Unknown Samples

Figure 2 illustrates the results obtained after application of the developed method to a batch of surface and groundwater samples. These results confirmed the efficiency of the method, demonstrating sensitivity and specificity.




Figure 2. Typical MRM chromatograms obtained for routine analysis series (including spiked, standard, blank, and two unknown water samples).

Conclusions

The developed method, focused on estrone-3-sulfate, associates a selective SPE preparation and a specific LC-MS/MS detection (Gemini column, Phenomenex, Agilent 6410 LC-MS/MS system). The performed validation according to 2002/657/EC criteria allowed unambiguous confirmation of steroid presence, even at ultra-trace levels ($< 1 \text{ ng.L}^{-1}$).

For More Information

For more information on this application, you may also contact Agilent Technologies, Inc., Attention:

Lea Bonnington, European Field Support Centre, Hewlett-Packard Strasse 8, 76337 Waldbronn, Germany.

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
June 24, 2008
5989-8480EN



Agilent Technologies



Analysis of Carbaryl and Carbofuran in Drinking Water with Post-Column Derivatization Using Agilent's New LC Column and SampliQ SPE Cartridges

Application Note

Environmental

Author

Rongjie Fu
Agilent Technologies, Inc.
412 Ying Lun Road
Pu Dong, Shanghai 200131
China

Abstract

The herbicides carbaryl and carbofuran were analyzed in drinking water samples using Agilent's new reversed-phase columns, Agilent TC-C18(2), and Agilent's new line of SampliQ C18 SPE cartridges. To meet the requirements of EPA Method 531.1 [1], we tried a 400- μ L direct injection onto the new column. Even with such a large injection volume, the new column provided good resolution from interfering or coeluting compounds, as well as highly symmetrical peaks and a high performance result, which gives high sensitivity. In addition, post-column derivatization and a fluorescence detector were used, making the limit of detection (LOD) less than 0.01 ng on column, a lower LOD than that specified in China's drinking water standards [2]. This method used new Agilent SampliQ C18 cartridges to concentrate the water samples and made it possible to determine carbaryl and carbofuran in drinking water at the ppt level. This total solution is very suitable for trace-level analysis of carbaryl and carbofuran in drinking water.



Agilent Technologies

Introduction

Carbaryl and carbofuran are N-methyl carbamate pesticides (structure shown in Figure 1), which are classified as broad-spectrum insecticides and are mostly used on rice and corn crops. Excess pesticide can contaminate ground water, surface water, and drinking water. Because this kind of pesticide has been shown to create health problems with blood and with the nervous and reproductive systems, actions have been taken to control these compounds and require that their amounts be measured in drinking water.

Regulatory methods are set in many countries. The China drinking water standards published in 2006 restrict the maximum limit of carbofuran in drinking water to 7 ppb and use liquid-liquid extraction to test the water samples. The U.S. Environmental Protection Agency (EPA) Method 531.1 sets the maximum contamination level (MCL) at 40 ppb and uses direct aqueous injection [1]. Each method has its own disadvantages. Liquid-liquid extraction is laborious, time-consuming work that requires a large amount of organic solvents. Direct aqueous injection is a simple method with less inter-ferential peaks; however, it is not suitable for measuring lower levels of compounds in drinking water.

Solid-phase extraction (SPE) is often used for the enrichment of water samples. This process is typically done using a standard SPE vacuum manifold but can be easily automated for the enhanced sensitivity required to measure low-level organic compounds in drinking water.

This application note describes an improved method for determining low levels of carbaryl and carbofuran in drinking water. The method applies an automated procedure of sample concentration and post-column derivatization to successfully measure carbaryl and carbofuran in drinking water at the ppt level. New Agilent SampliQ C18 SPE cartridges were used for sample enrichment from water. The sample was then analyzed with Agilent TC-C18(2) columns, which provide symmetrical peak shape and high sensitivity. Last, the separated compounds were derivatized before detection with a fluorescence detector. The derivatization reaction is shown in Figure 2. Carbaryl and carbofuran are first hydrolyzed under basic conditions at high temperature into methylamine and then react with o-phthalaldehyde (OPA) and 2-mercaptoethanol into isoindole, which has strong fluorescence. This is a simple, automated, fast, and high recovery method that is fit for quality control of drinking water.




Figure 1. Structures of carbaryl and carbofuran.




Figure 2. Derivatization reaction of carbaryl and carbofuran.

Experimental

Instruments

HPLC Conditions

Instrument	Agilent 1100 or 1200 with fluorescence detector (FLD): A multidraw upgrade kit (p/n G1313-68711) can be installed when 400-µL injections are needed.
Column	Agilent TC-C18(2) 4.6 × 150 mm, 5 µm (p/n 588935-902)
Mobile phase	A: Water, B: Methanol 0 min 42% B, 5 min 55% B, 12 min 60% B, 13 min 42% B, stop time 15 min, post-run 2 min
Flow rate	1.0 mL/min
Column temperature	30 °C
FLD detector	Ex 339 nm; Em 445 nm
Injection volume	10 µL
Pinnacle PCX derivatization instrument	Pickering Laboratories, Inc.

Post-Column Reaction Conditions

Flow rate of reagents	0.1 mL/min
Reactor temperature	95 °C
Derivatization temperature	Room temperature

Caliper LS Autotrace SPE Workstation

Caliper Life Sciences, Inc.

SPE Cartridges Agilent Technologies, Inc.

SampliQ C18, 6ml/500mg (p/n 5982-1165)

TurboVap II Evaporation System

Caliper Life Sciences, Inc.

Standards for Calibration Curves

Accurately weigh 10 mg of carbofuran and 12.2 mg of carbaryl standards and separately dissolve in methanol to a volume of 10 mL. Make the stock solution by mixing 60 µL of the carbofuran and 40 µL of the carbaryl solutions into a 10 mL volumetric flask. Dilute to volume with methanol to obtain a concentration of 4.88 µg/mL of carbaryl and 6.0 µg/mL of carbofuran. Dilute aliquots of the stock standard solution with methanol into a series of standard solutions shown in Table 1.

Table 1. Standard Solutions for Calibration Curves

Level	1	2	3	4	5
Carbaryl (ppb)	48.8	97.6	244.0	488.0	976.0
Carbofuran (ppb)	60.0	120	300.0	600.0	1200

Derivatization Reagents

Sodium hydroxide	0.05 N – Dissolve 2.0 g of sodium hydroxide (NaOH) in reagent water. Dilute to 1.0 L with reagent water. Filter and degas just before use.
Mercaptoethanol (1+1)	Mix 10.0 mL of 2-mercaptoethanol and 10.0 mL of acetonitrile. Cap. Store in hood.
Sodium borate	0.05 N – Dissolve 19.1 g of sodium borate (Na ₂ B ₄ O ₇ ·10H ₂ O) in reagent water. Dilute to 1.0 L with reagent water. The sodium borate will completely dissolve at room temperature if prepared a day before use.
OPA reaction solution	Dissolve 100 ± 10 mg of o-phthalaldehyde (melting point = 55 to 58 °C) in 10 mL of methanol. Add to 1.0 L of 0.05 N sodium borate. Mix, filter, and degas. Add 100 µL of 2-mercaptoethanol (1 + 1) and mix. Make up fresh solution daily.

Other reagents

Methanol	HPLC grade
Water	Milli-Q water as mobile phase and reagent water; tap water as sample
Acetic acid	AR grade
Sodium thiosulfate	AR grade
Dichloromethane	HPLC grade

Sample Preparation Method

We used an automated SPE workstation for sample preparation instead of traditional liquid-liquid extraction in China drinking water standard. Before extraction with SPE, acetic acid was added to the water sample to a concentration of 0.1%. If tap water is used, sodium thiosulfate should be also added to a concentration of 80 mg/L.

The SPE extraction procedure is as follows:

1. Wash syringe with 5.0 mL of CH₂Cl₂.
2. Condition cartridge with 5.0 mL of CH₂Cl₂ into solvent waste.
3. Wash syringe with 5.0 mL of methanol.
4. Condition cartridge with 5.0 mL of methanol into solvent waste.
5. Condition cartridge with 5.0 mL of reagent water into aqueous waste.
6. Load 1,000.0 mL (1 L) of sample onto column.
7. Rinse cartridge with 5.0 mL of reagent water into aqueous waste.
8. Dry cartridge with N₂ for 10 minutes.
9. Wash syringe with 5.0 mL of CH₂Cl₂.
10. Soak for two minutes with 5.0 mL CH₂Cl₂ and collect the eluent.
11. Repeat step 10.
12. Collect 5.0-mL fractions into sample tube using air.
13. Evaporate the eluted sample with a stream of N₂ to a volume of 0.5 mL.
14. Inject 10 µL into HPLC for analysis.

Flow Rates Set

Condition flow	1.0 mL/min
Load flow	5.0 mL/min
Rinse flow	1.0 mL/min
Elute flow	1.0 mL/min
Condition air push	15.0 mL/min
Rinse air push	10.0 mL/min
Elute air push	5.0 mL/min

If you do not have an automated SPE workstation, an Agilent vacuum manifold (p/n 5182-9110 or 5182-9120) is recommended. To automatically pull the water sample through, attach an adapter (p/n 5182-9109) with a pipe onto the SPE cartridge. The water sample should be pulled through the SPE by vacuum at the flow rate of no more than 5 mL/min for good recovery.

Results and Discussion

Separation

The standard solutions were analyzed by injecting 10 μL of each of the standard solutions onto the Agilent TC-C18(2) column. The chromatograms from the standard injections (Figure 3) show high performance, high resolution, and symmetrical peaks. We have also run this on an HC-C18(2) column. A little longer retention was achieved with almost the same performance as with the TC-C18(2) column. These columns have a different carbon load: 17 percent for the HC-C18(2) column and 12 percent for the TC-C18(2) column. These differences impact retention, with the HC-C18(2) column typically retaining nonpolar and moderately polar compounds more when compared with the TC-C18(2) column. We prefer the column providing a shorter analysis time but resolving all the peaks. Although both columns are suitable for this method, we chose the TC-C18(2) because it provided a slightly shorter analysis time.




Figure 3. Chromatogram of carbofuran and carbaryl standards on Agilent TC-C18(2), 4.6 $\times$ 150 mm, 5 μm columns.

Linearity, Reproducibility, and Limit of Detection

The calibration curves resulting from these standard injections on the TC-C18(2) column are shown in Figure 4. The method shows excellent linearity, being very close to 1.0 (0.9997). To evaluate the reproducibility of this method on the TC-C18(2) column, two concentrations of carbofuran and carbaryl were each injected 10 times. The reproducibility of the peak areas is shown in Table 2; the absolute peak area reproducibility is superior. The average relative standard deviation (RSD) is below 3 percent. We calculate the LOD from the level 1 standard with a signal-to-noise ratio of 3. The LOD is 0.066 ng for carbofuran and 0.080 ng for carbaryl, which is three to four times better than the 0.25 ng that is regulated by China's drinking water standard.




Figure 4. Calibration curves of carbofuran and carbaryl [Agilent TC-C18(2), 4.6 $\times$ 150 mm, 5 μm columns].

Table 2. Reproducibility of Standards Injections

Analyte	RSD (%) n = 10	
	Carbofuran 48.8 ppb	Carbofuran 488 ppb
Carbofuran	2.3	1.6
Carbaryl	1.8	1.5

Recovery

Two different levels were spiked in reagent water and tap water, respectively, and then followed the sample preparation procedure. The recovery data are good, with a typical recovery in the range of 80 to 110 percent (Table 3).

To better match the China drinking water method, in which dichloromethane is used for liquid-liquid extraction, we chose dichloromethane as the SPE cartridge eluent. That provided us clean chromatograms.

It has been reported that the two compounds are not stable under neutral and basic conditions. [1,3] So the water samples were stabilized by the addition of 0.1 percent acetic acid. According to the China drinking water regulatory method, the residual chlorine present in tap water may result in low recovery, thus sodium thiosulfate should be added to the tap water to eliminate the residual chlorine. We therefore compared the recovery of the tap water with and without sodium thiosulfate. The recovery values obtained without sodium thiosulfate were significantly lower than those with sodium thiosulfate. Therefore, to get good recovery values, we added 80 mg/L of sodium thiosulfate to the tap water sample.

Table 3. Recovery for Carbofuran and Carbaryl from Tap Water and Reagent Water

Analyte	Spiked level (ppb)	Tap water R (%) n = 6	Tap water RSD (%) n = 6	Pure water R (%) n = 3	Pure water RSD (%) n = 3
Carbofuran	0.1	107.8	13.5	84.4	9.5
	0.5	98.8	9.2	98.1	6.8
Carbaryl	0.084	87.0	10.1	83.7	6.2
	0.41	91.8	9.6	94.3	3.3

The chromatograms of reagent water and tap water and their spiked samples are shown in Figures 5 and 6. All the potential interfering compounds in reagent and tap water are well separated from the target compounds, demonstrating good method selectivity.




Figure 5. Chromatograms of reagent water and its spiked sample [Agilent TC-C18(2), 4.6 × 150 mm, 5 μm columns].




Figure 6. Chromatograms of tap water and its spiked sample [TC C18(2), 4.6 × 150 mm, 5 μm columns].

Direct Injection

A large-volume 400-μL direct injection was applied as described in EPA Method 531.1. We tried a 400-μL injection by using the multidraw attachment on the LC and the TC-C18(2) column. The column has a large surface area (290 m²/g), which allows large-volume injections. The chromatograms in Figure 7 show superior peak shape and high performance. Retention of the two target peaks was excellent and greater-than-baseline resolution was achieved. In addition, the peaks were eluted in a region without any interferences. The column, therefore, can be used for EPA Method 531.1.




Figure 7. Chromatograms of pure water and tap water spiked with carbofuran and carbaryl.

Conclusions

This total solution enables you to easily analyze drinking water for low levels of the herbicides carbaryl and carbofuran. The Agilent TC-C18(2) column and the new SampliQ C18 SPE cartridge were used for their high sensitivity and low LOD of the two compounds. This method can be used to measure carbaryl and carbofuran in drinking water effectively and quickly.

References

1. United States Environmental Protection Agency, "Measurement of N-Methylcarbamoyloximes and N-Methylcarbamates in Water by Direct Aqueous Injection HPLC with Post Column Derivatization," Method 531.1, 1989, EPA Environmental Monitoring Systems Laboratory, Office of Research and Development, Cincinnati, Ohio 45268.
2. Standards of People's Republic of China, "Standard Examination Methods for Drinking Water – Pesticides, GB/T 5750.9-2006:15.
3. Yuliang Su, et al., "Determination of Carbaryl in Water by HPLC with Direct Injection," *Modern Scientific Instruments*, 2007, 5:125.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Published in the USA
October 20, 2008
5989-9802EN



Agilent Technologies



Organophosphorus Pesticides Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column

Application Note

Environmental

Authors

Doris Smith and Kenneth Lynam
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Agilent Technologies Inc. has implemented new testing procedures to more effectively evaluate GC column inertness performance. This new testing procedure employs deliberately aggressive probes to thoroughly investigate and verify column inertness and quality. In challenging separations, knowing that the GC column has been thoroughly investigated for column inertness gives analysts higher confidence in the accuracy of their results.

Trace- and ultra trace-level pesticide analyses are important tools for accessing food supply and environmental quality worldwide. In this application note, trace-level organophosphorus pesticide analysis is demonstrated using electron impact single quadrupole scanning mass spectrometry. Agilent's J&W DB-5ms Ultra Inert capillary GC column provides excellent peak shape for even the most problematic pesticides.



Agilent Technologies

Introduction

Pesticides are commonly used in agricultural and residential applications throughout the world. Organophosphorus pesticides make up approximately 70 percent of the insecticides currently in use. Unfortunately, these highly toxic materials have three main routes of human exposure: inhalation, ingestion, and skin penetration. Sources of these exposures include consumption of foodstuff containing pesticide residues, aerosol inhalation, and dermal contact during pesticide application. [1]

Organophosphorus pesticides use the same mechanism of action as deadly nerve agents such as sarin, soman, and VX. These pesticides affect the nervous system of insects, mammals, and wildlife by inhibiting the enzyme cholinesterase, important in helping regulate nerve impulses. Inactivation of cholinesterase leads to the accumulation of the neurotransmitter acetylcholine in the central and peripheral nervous system, which leads to depressed motor function and respiratory depression. Human toxicities for this class of molecules have shown acute as well as chronic effects from pesticide poisoning. [2,3]

Organophosphorus pesticides tend to be difficult to quantify due to poor peak shape, as evidenced by broad, asymmetrical peaks. An EPA Method 525.2 standard containing organophosphorus pesticides along with a custom pesticide mix acquired from Ultra Scientific (North Kingstown, RI) were analyzed to highlight the value of using a 30-m Agilent J&W DB-5ms Ultra Inert capillary GC column for difficult pesticide analysis. Many pesticides are sensitive to chromatographic system activity and will readily breakdown. The Ultra Scientific custom mix contains several types of these pesticides, which are useful in quickly evaluating system performance with particularly challenging pesticide analytes. Capillary GC column activity as a potential source of result uncertainty has been virtually eliminated with the Ultra Inert series of columns. [4]

Experimental

An Agilent 6890N GC/5975B MSD equipped with a 7683B autosampler was used for this series of experiments. Table 1 lists the chromatographic conditions used for these analyses. Table 2 lists flow path consumable supplies used in these experiments.

Table 1A. Chromatographic Conditions for EPA Method 525.2 Calibration Standards

GC	Agilent 6890N/5975B MSD
Sampler	Agilent 7683B, 5.0- μ L syringe (Agilent p/n 5181-1273) 1.0- μ L splitless injection
Carrier	Helium 44 cm/s, constant flow
Inlet	Pulsed splitless; 250 °C, 40 psi until 0.75 min, purge flow 50 mL/min at 1.0 min
Inlet liner	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Column	Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 122-5532UI)
Oven	40 °C (1 min) to 110 °C (50 °C/min), 7 °C/min to 190 °C, 12 °C/min to 285 °C, hold 2 min.
Detection	MSD source at 250 °C, quadrupole at 150 °C, transfer line at 280 °C, EI mode, scan range 45–450 amu

Table 1B. Chromatographic Conditions for Ultra Scientific Calibration Standards

GC	Agilent 6890N/5975B MSD
Sampler	Agilent 7683B, 5.0- μ L syringe (Agilent p/n 5181-1273) 1.0- μ L splitless injection
Carrier	Helium 52 cm/s, constant flow
Inlet	Pulsed splitless; 250 °C, 40 psi until 0.75 min, purge flow 50 mL/min at 1.0 min
Inlet liner	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Column	Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 122-5532UI)
Oven	75 °C to 175 °C (15 °C/min), 10 °C/min to 275 °C (1 min)
Detection	MSD source at 250 °C, quadrupole at 150 °C, transfer line at 280 °C, EI mode, scan range 45–450 amu

Table 2. Flow Path Supplies

Vials	Amber crimp-top glass vials (Agilent p/n 5183-4496)
Vial caps	Crimp caps with 11-mm septa (Agilent p/n 5181-1210)
Vial inserts	100- μ L glass/polymer feet (Agilent p/n 5181-8872)
Syringe	5 μ L (Agilent p/n 5181-1273)
Septum	Advanced Green (Agilent p/n 5183-4759)
Inlet liners	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Ferrules	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323)
20x magnifier	20x magnifier loupe (Agilent p/n 430-1020)

Sample Preparation

A six-component EPA Method 525.2 pesticide standard mix and internal/surrogate standard mix were purchased from Accu-Standard (New Haven, CT) and used to prepare a six-level calibration standard set. The stock pesticide solution as delivered had a nominal concentration of 1,000 µg/mL. The internal/surrogate solution as delivered had a nominal concentration of 500 µg/mL. The calibration standards were prepared with component concentrations of 10, 5, 2, 1, 0.5, and 0.1 µg/mL and a constant level of 5 µg/mL of internal/surrogate standard as per EPA Method 525.2. All solutions were prepared in acetone using class A volumetric pipettes and flasks. Acetone used was JT Baker Ultra Resi Grade purchased thorough VWR International (West Chester, PA). Acetone was used as a reagent blank and syringe wash solvent.

An 11-component pesticide standard mix was purchased from Ultra Scientific and used to prepare a seven-level calibration standard set. The stock pesticide solution as delivered had a nominal concentration of 1,000 µg/mL. The calibration standards were prepared with component concentrations of 10, 5, 2.5, 1, 0.5, 0.25, and 0.1 µg/mL. All solutions were prepared in 2,2,4-trimethylpentane using class A volumetric pipettes and flasks. The 2,2,4-trimethylpentane used was JT Baker Ultra Resi Grade purchased thorough VWR International (West Chester, PA). 2,2,4-Trimethylpentane was used as a reagent blank and syringe wash solvent.

Results and Discussion

Baseline Inertness Profile for Ultra Inert Columns

The basic approach for inertness verification for the Agilent J&W Ultra Inert series of capillary GC columns is testing with aggressive active probes at low concentration and low temperature. [5] This is a rigorous approach that establishes consistent baseline inertness profiles for each column in the Agilent J&W Ultra Inert GC column series. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species that tend to adsorb onto active

sites, particularly at trace level, like the organophosphorus pesticides in this application example. A more detailed description of the test mix and additional application examples can be found in references 6 through 8.

Organophosphorus Pesticide Analysis

In this application note, a multilevel pesticide calibration curve set was evaluated over the concentration range of 0.1 to 10 µg/mL on an Agilent J&W Ultra Inert DB-5 ms 30 m × 0.25 mm × 0.25 µm (Agilent p/n 122-5532UI). Separate calibration curves were developed for both the EPA 525.2 organophosphorus and Ultra Scientific standards. The standard levels used for the 525.2 calibration were 0.1, 0.5, 1, 2, 5, and 10 µg/mL, while the Ultra Scientific calibration levels were 0.1, 0.25, 0.5, 1, 2.5, 5, and 10 µg/mL. The custom pesticide standard from Ultra Scientific was used to determine system performance by analyzing difficult pesticides, such as endrin and p,p'-DDT, which are prone to analyte breakdown.

No tailing was observed for any of the organophosphorus pesticide peaks across the range studied in either standard set. Sharp, symmetrical peak shapes were noted for all the organophosphorus pesticides analyzed. Good resolution was obtained for each of the pesticides investigated.

Linearity for the 525.2 standard components was excellent across the range studied, giving R^2 values of 0.997 or greater in all cases but fenamiphos, which had an R^2 value of 0.978. This value increases to 0.991 at the midlevel concentrations as suggested by EPA Method 525.2 Sec. 13.2.3.3. Figure 5 indicates the correlation coefficients for each of the individual pesticides and shows an example linear regression plot for disulfoton.

Linearity for the Ultra Scientific standard components was also quite good across the range studied. R^2 values of 0.990 or greater were obtained for the organophosphorus pesticides. Figure 6 indicates the correlation coefficients for each of the individual pesticides and shows an example linear regression plot for mevinphos.

- | | |
|-------------------------------------|-----------------------------|
| 1. 1,3-Dimethyl-2-nitrobenzene (SS) | 7. Ametryn |
| 2. Acenaphthene-d10 (IS) | 8. Fenamiphos |
| 3. Cycloate | 9. Tribufos (DEF) |
| 4. Prometron | 10. Triphenylphosphate (SS) |
| 5. Phenanthrene-d10 (IS) | 11. Chrysene-d12 (IS) |
| 6. Disulfoton | 12. Perylene-d12 (SS) |




Figure 1. Total ion chromatogram (scan mode) of the 1-ng on-column EPA Method 525.2 standard solution loading on an Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 122-5532UI). Chromatographic conditions are listed in Table 1A.




Figure 2. Enlarged section of the total ion chromatogram (scan mode) for a 1- μ L injection of 1.0 μ g/mL EPA Method 525.2 standard pesticide mix. The peaks noted in the figure are the three organophosphorus pesticides of interest. Chromatographic conditions are listed in Table 1A.




Figure 3. Total ion chromatogram (scan mode) of the 0.1-ng on-column Ultra Scientific standard solution loading on an Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 122-5532UI). Chromatographic conditions are listed in Table 1B.




Figure 4. Enlarged section of the total ion chromatogram (scan mode) for a 1- μ L injection of 0.1 μ g/mL Ultra Scientific standard pesticide mix on an Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 122-5532UI). The peak in the figure is mevinphos, an organophosphorus pesticide of interest. This injection represents an on-column loading of 0.1 ng per component. Chromatographic conditions are listed in Table 1B.

Component	R ²
Cycloate	1.000
Prometon	0.999
Disulfoton	0.999
Ametryn	0.999
Fenamiphos	0.978
Tribufos (DEF)	0.997




Figure 5. Correlation coefficients for the EPA Method 525.2 pesticide components over the 0.1 to 10 $\mu\text{g/mL}$ range of this study and an example linear regression plot for disulfoton.

Component	R ²
1,3-Dimethyl-2-nitrobenzene	0.999
Mevinphos	0.990
Pentachlorophenol	0.989
Terbufos	0.996
Bromacil	0.988
Aldrin	0.999
Carboxin	0.996
Endrin	0.998
p,p'-DDT	0.996
Triphenylphosphate	0.997
DEHP	0.996




Figure 6. Correlation coefficients for the Ultra Scientific pesticide components over the 0.1 to 10 $\mu\text{g/mL}$ range of this study and an example linear regression plot for mevinphos.

Conclusions

This application successfully demonstrates the use of an Agilent J&W DB-5ms Ultra Inert capillary GC column for trace-level organophosphorus pesticides. Linearity was excellent for all organophosphorus pesticides studied, yielding 0.99 or greater R^2 values down to a 0.1-ng on-column loading of each component. One of the reasons for excellent linearity and high R^2 values is the highly inert surface of the column. The lack of chemically active sites makes these columns an excellent choice for trace-level applications.

This study was done using scan mode on an Agilent 6890/5975B GC/MSD equipped with an inert electron impact source. The signal-to-noise ratio for a 0.1-ng on-column loading of mevinphos was greater than 5 to 1 with this system. This result shows clearly the power of using an Agilent J&W DB-5ms Ultra Inert column for trace-level organophosphorus pesticides analysis. Lower limits of quantification are expected when using one of Agilent's latest GC/MS offerings, such as the 7890/5975C GC/MSD Triple-Axis Detector coupled with an Agilent J&W DB-5ms Ultra Inert GC capillary column.

References

1. J. Routt Reigart and James R. Roberts, *Recognition and Management of Pesticide Poisoning*, 5th Ed, 1999, pp 34–47 [Online] Available: www.epa.gov/oppfead1/safety/healthcare/handbook/handbook.htm
2. Kenneth D. Katz, et al, "Organophosphate Toxicity," [Online]. Available: www.emedicine.com/med/TOPIC1677.HTM (Article last updated May 30, 2008)
3. K. Steenland, "Chronic Neurological Effects of Organophosphate Pesticides," *BMJ*, May 25, 1996; 312(7042): 1312 – 1313.
4. J. W. Eichelberger, et al., US EPA Method 525.2 Revision 2.0, "Determination of Organic Compounds in Drinking Water by Liquid-Solid Extration and Capillary Column Gas Chromatography/Mass Spectrometry," National Exposure Research Laboratory, USEPA, Cincinnati, Ohio, 1995.
5. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenyl-dimethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
6. "Agilent J&W Ultra Inert GC Columns: A New Tool to Battle Challenging Active Analytes," Agilent Technologies publication 5989-8685EN, May 29, 2008
7. Kenneth Lynam, "Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column," Agilent Technologies publication 5989-8616EN, May 13, 2008
8. Kenneth Lynam and Doris Smith "Polycyclic Aromatic Hydrocarbon (PAH) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9181EN, in press

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Published in the USA
November 12, 2008
5989-9879EN



Agilent Technologies



A Rapid Method for Trace Analysis of Organophosphorus Pesticides in Drinking Water

Application Note

Environmental

Authors

Min Cai and Yun Zou
Agilent Technologies Co. Ltd,
412 Ying Lun Road
Waigaoqiao Free Trade Zone
Shanghai 200131
China

Abstract

A simple and quick method for the determination of organophosphorus pesticides (OPs) in drinking water has been developed. After sample extraction with methylene chloride, analysis was directly carried out without further treatment using GC with a specific detector FPD on a DB-1701P column. A linear relationship between concentration and peak area was obtained within the range of 0.005 to 0.500 ng with correlation coefficients greater than 0.999 and detection limits less than 0.03 µg/L.

Recoveries of six OPs at spiked levels of 0.50, 2.50, and 4.50 µg/L ranged from 88 to 104%. These OPs were reproducibly detected well below the maximum residue limits (MRLs) of EPA Method 525 and European Union regulations for pesticide residues in drinking water.



Agilent Technologies

Introduction

Organophosphorus pesticides (OPs) are among the most common pesticides used in industrialized countries. These compounds are very toxic when absorbed by human organisms because of acetylcholinesterase deactivation. Due to their universal application in agriculture, OPs represent an important source of environmental contamination. Maximum residue limits (MRLs) have been established for pesticides in foodstuff and drinking water in most countries to avoid any adverse impact on public health. U.S. Environmental Protection Agency (EPA) Method 525 has a maximum allowable risk level for OPs in drinking water ranging from 0.001 to 0.25 mg/L [1]. In the European Union (EU), a maximum allowable concentration of 0.0001 mg/L for each individual pesticide in drinking water is in force. For evaluation of environmental waters and water sources for preparation of drinking water, highly sensitive methods for the determination of OPs in surface water, ground water, and drinking water are required.

Most analytical methods for pesticide analysis of OPs in aqueous samples are based on chromatographic techniques. Gas chromatography (GC) with nitrogen-phosphorus detection [2] (NPD), mass spectrometry [1] (MS), and flame photometric detection [3] (FPD) has traditionally been the method of choice for the analysis of OPs. FPD is a highly selective and sensitive detector that works by measuring the emission of phosphorus- (or sulfur-) containing species, which will minimize interferences from materials that do not contain phosphorus. Since the chromatograms of extracts were free from interfering peaks, no cleanup was needed. For the OPs analysis, FPD is a potentially efficient detector for monitoring water samples.

OPs are active compounds that can be adsorbed onto active sites throughout the sample flow path, including the injection port, liner, golden seal, capillary column, and any metal detector parts. A capillary column is one of the major sources of active sites owing to its large surface area and the long residence time of an analyte in the column. Peak tailing, response loss, and compound degradation will occur for these active compounds when the column is not inert.

The DB-1701P column was specially designed for the analysis of pesticides [4]. It has a better inertness for active compounds, which offers improved resolution, better selectivity, and higher sensitivity for OPs analysis. This application note presents a sensitive method developed on a DB-1701P column using GC/FPD for the analysis of OPs in drinking water.

Experimental

Instrument

An Agilent 7890 GC equipped with split/splitless capillary inlets and FPD was used for this work. The inlets were fitted with a long-lifetime septa (P/N 5183-4761) and single-taper helix liner (P/N 5188-5397). Injections were done using 10- μ L syringes (P/N 9301-0714).

Many analytes will degrade on reactive sites in the chromatographic system. Analysts must ensure that injectors and splitters are free from contamination and are silanized. Columns should be installed and maintained properly.

GC Conditions

Column	DB-1701P, 30 m $\times$ 0.32 mm $\times$ 0.25 μ m (P/N 122-7732)
Carrier gas	Helium, constant pressure mode, 25 psi
Inlet	Split/splitless @ 270 $^{\circ}$ C, splitless
Oven temperature	60 $^{\circ}$ C (1 min); 30 $^{\circ}$ C/min to 180 $^{\circ}$ C (7 min); 15 $^{\circ}$ C/min to 220 $^{\circ}$ C (3 min)
Detector	250 $^{\circ}$ C, FPD in phosphorus mode
Detector gas	H ₂ 75 mL/min, air 100 mL/min, makeup (N ₂) 60 mL/min
Injection size	1 μ L

Standard Solution

Six OP stock solutions (see Table 1) were purchased from China National Standards Research Center. These six OPs are commonly used in agriculture and are strictly monitored. A mix stock solution (10 mg/L) of OPs was prepared in acetone. Six calibration standards solutions were prepared by diluting the stock solution with acetone. The calibration standard solutions should be stored in tightly sealed bottles at temperatures below 5 $^{\circ}$ C.

Table 1. Six Organophosphorus Pesticides Solutions

Compound	Molecular formula	Molecular weight	Standard solution (mg/mL) in methanol
1 Dichlorvos	C ₄ H ₇ Cl ₂ O ₄ P	220.98	0.89
2 Dimethoate	C ₆ H ₁₂ NO ₃ PS ₂	229.28	1.00
3 Chlorpyrifos	C ₉ H ₁₁ Cl ₃ NO ₃ PS	350.59	1.00
4 Methylparathion	C ₈ H ₁₀ NO ₅ PS	263.63	1.00
5 Malathion	C ₁₀ H ₁₉ O ₆ PS ₂	330.36	1.02
6 Parathion	C ₁₀ H ₁₄ NO ₅ PS	291.26	1.00

Sample Preparation

100 mL of water sample was transferred to a 250-mL separatory funnel. After adding 20 mL of methylene chloride, the separatory funnel was sealed and then shaken vigorously for 1 to 2 minutes with periodic venting to release excess pressure. Once the funnel was still for 10 minutes, the extract for the organic layer was collected. The extraction was repeated twice, using fresh portions of solvent. The resulting three portions of the extracts were combined and dried with anhydrous sodium sulfate, then evaporated to near dryness. The residue was dissolved with 1 mL of acetone and transferred into the sample vial for GC analysis.

Results and Discussion

The separation of six OPs is illustrated in Figure 1. As you can see, all OPs can be baseline separated with highly efficient and symmetrical peaks on the DB-1701P column, which demonstrated significantly reduced peak tailing and adsorption for these challenging analytes.

Linearity and Reproducibility

FPD is a selective detector for sulfur and phosphorus compounds in complex mixtures. The response of the FPD is linear in phosphorus mode. Table 2 shows the linearity range, r^2 values for six OPs calculated from the study. The calibration curve was constructed from data obtained by 1- μ L injections of standards at six levels. All the OPs exhibit a wide linear range from 0.005 to 0.500 ng, with r^2 values higher than 0.999, suggesting a good linearity range for low-level OP quantification in drinking water.

Table 2. Linearity and Limit of Detection ($S/N = 3$)

Compound	Linearity (ng)	Correlation coefficient (R^2)
1 Dichlorvos	0.004 ~ 0.445	0.9993
2 Dimethoate	0.005 ~ 0.500	0.9991
3 Chlorpyrifos	0.005 ~ 0.500	0.9994
4 Methylparathion	0.005 ~ 0.500	0.9993
5 Malathion	0.005 ~ 0.510	0.9993
6 Parathion	0.005 ~ 0.500	0.9993

The reproducibility of the method was investigated by replicate analysis of three levels of OPs (0.050, 0.250, and 0.450 ng) in Table 3. The relative standard deviation (RSD) of the retention time (RT) of the six OPs was lower than 0.017%. Peak areas were reproducible with an RSD of less than 4.0%. Good RT and peak area repeatability ensure reliable qualitative and quantitative analyses.

Table 3. Reproducibility of Peak area and Retention time ($n \geq 10$)

Compound	RSD (%) ($n \geq 10$)					
	0.050 ng		0.250 ng		0.450 ng	
	Area	RT	Area	RT	Area	RT
1 Dichlorvos	3.364	0.011	1.680	0.007	1.620	0.011
2 Dimethoate	3.904	0.015	1.497	0.017	1.752	0.011
3 Chlorpyrifos	1.303	0.008	1.476	0.010	1.196	0.009
4 Methylparathion	1.963	0.011	1.642	0.009	1.169	0.008
5 Malathion	1.084	0.009	1.842	0.005	1.426	0.006
6 Parathion	1.750	0.006	1.666	0.008	1.300	0.007




Figure 1. Chromatograms of six OPs standard solution on DB-1701P column.

Recovery and Limit of Detection (LOD)

Table 4 presents the recoveries for spiked water samples. Replicate samples of 100-mL ultrapure water were spiked with OPs at 0.50, 2.50, and 4.50 µg/L. During the study, no target OPs were found in the ultrapure water, so it is regarded as blank water. The spiked samples were treated according to the procedure described in the sample preparation. Excellent recoveries were obtained for all the compounds, ranging from 88 to 104%. Duplicate samples were analyzed and demonstrated that the method has a good repeatability at trace levels (see Figure 2).

Table 4. Recovery of Three Levels of OPs

Compound	Recovery (%)		
	0.50 µg/L	2.50 µg/L	4.50 µg/L
1 Dichlorvos	88.7	90.0	91.2
2 Dimethoate	103.5	98.5	100.7
3 Chlorpyrifos	90.3	90.4	91.0
4 Methylparathion	92.8	92.5	91.6
5 Malathion	92.2	91.6	92.5
6 Parathion	91.8	90.4	91.8

Table 5 lists the LODs of the method and the MRLs of EPA Method 525. The LODs were determined at a signal-to-noise ratio of 3. It demonstrates the high sensitivity of FPD for trace analysis of OPs. The developed method enables quantitative determination of OPs in water solutions at concentration levels lower than 0.03 µg/L, which is about 100 times lower than

the MRLs in EPA Method 525. It also meets the requirement of EU limits (0.1 µg/L) in drinking water.

Table 5. Limit of Detection in 100-mL Water Sample

Compound	LOD (µg/L)	MRLs* (µg/L)
1 Dichlorvos	0.012	1
2 Dimethoate	0.030	80
3 Chlorpyrifos	0.027	30
4 Methylparathion	0.021	20
5 Malathion	0.023	250
6 Parathion	0.020	3

* MRLs in EPA Method 525

Real Sample

In order to check the applicability of the proposed method to real matrices, tap water samples and ultrapure water samples were collected. A 100-mL aliquot of each sample was analyzed following the procedure described in the sample preparation section. Peak areas were used for quantitation. The use of FPD eliminates the interferences that do not contain phosphorus. None of the samples gave peaks that interfered with the determination of the six OPs (Figure 3). In these samples, no OPs were found above the method's LOD.




Figure 2. Overlay chromatogram of 0.50-µg/L spiked samples on DB-1701P column.




Figure 3. Chromatogram of real water samples on DB-1701P column.

Conclusions

This application note describes a method for the quantification of OPs in drinking water samples. After liquid-liquid extraction and concentration, the sample extracts were directly analyzed on a DB-1701P column using an Agilent 7890 Series GC with FPD. The method provides good linearity, repeatability, and high recovery. It is adequate to determine OPs LODs lower than 0.03 µg/L, which is in full compliance with the MRLs in EPA Method 525 and EU regulations in drinking water. The local drinking water samples were determined to be free of OP contamination.

It is a fast, simple, and economic method to analyze OPs at micro-trace levels. Therefore, it is suitable to control the water quality for OPs according to the MRLs specified in the regulations.

References

1. United States Environmental Protection Agency Method 525, "Determination of Organic Compounds in Drinking Water by Liquid-Solid Extraction and Capillary Column Gas Chromatography/Mass Spectrometry."
2. Chuanhong Tu, "Analysis of Organophosphorus Pesticides with Agilent 6820 Gas Chromatograph/Nitrogen Phosphorus Detector," Agilent Technologies publication 5989-1335EN, August 2004.
3. China National Standard Method GB/T 5750.9-2006, "Determination of Organophosphorus in Drinking Water."
4. Ultra Inert Brochure APFO, Agilent Technologies publication 5989-8672ENA, May 2008.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Published in the USA
November 13, 2008
5990-3158EN



Agilent Technologies



Analysis of Organochlorine Pesticides in Drinking Water by Agilent 7820 Gas Chromatograph/Micro-Electron Capture Detector

Wenmin Liu and Chunxiao Wang

Application Brief

Environmental

The Agilent 7820 GC configured with a micro-electron capture detector (μ ECD) provides high sensitivity, good linearity, and stability for the analysis of organochlorine pesticides in drinking water. The results achieved are better than the requirements stated in the Chinese National Standard Method GB/T 5750.9-2006 [1,2].

Experiment

Analytical Conditions

Inlet	260 °C, Split/splitless, Liner (5062-3587)
Injection volume	1 μ L
Column	30 m $\times$ 0.32 mm $\times$ 0.25 μ m (Agilent J&W 123-0732)
Carrier gas	N ₂ , Constant flow: 1 mL/min
Oven	50 °C (3 min) 30 °C/min 210 °C (30 min)
Detector	ECD, 300 °C, Makeup flow (N ₂): 60 mL/min
Data analysis system	Agilent EZChrom Elite Compact

Results

The Agilent 7820 μ ECD's high sensitivity ensures reliable and rugged trace pesticide analysis in drinking water. The method can be easily transferred across geographies and labs. Figure 1 shows the chromatogram of 500 ng/L pesticides using the Agilent 7820 μ ECD with excellent signal to noise (S/N).

The design of the μ ECD ensures a wide linear dynamic range for the analytes. Table 1 shows linearity (R^2) for the pesticides.

Highlights

- The Agilent 7820 configured ECD provides high sensitivity for the analysis of organochlorine pesticides.
- ALS and EPC ensure good repeatability and ease of use.
- Using N₂ as the carrier gas significantly lowers analysis cost compared with the use of He.
- Agilent EZChrom Elite Compact software is designed for the Agilent 7820 is used for easy data acquisition and analysis.



Agilent Technologies





Figure 1. Chromatogram of organochlorine pesticides at 500 ng/L.

Table 1. Pesticide Linearity Data

Peak no.	Compounds	Linear range (ppb)	R ²
1	α-BHC	0.5–500	0.9998
2	β-BHC	0.5–500	0.9998
3	Lindane	0.5–500	1
4	σ-BHC	0.5–500	0.9996
5	p,p'-DDE	1–500	0.9998
6	o,p'-DDT	1–500	0.9998
7	p,p'-DDD	0.5–500	0.9999
8	p,p'-DDT	0.5–500	0.9993

The use of an automatic liquid sampler (ALS) and EPC ensure the ease of use of the 7820 and its good repeatability. The response factors (RFs) and their relative standard deviations (RSDs) (n = 10) are less than 20%, much better than the precision requirements for RFs in the contract laboratory program of the United States Environmental Protection Agency (USEPA).

Proven reduced susceptibility to contamination on the μECD improves the analysis of dirty matrix samples. Figure 2 shows the chromatograms of pesticide standards and spiked water sample (10 ppb). The recoveries of each analyte are shown in Table 2. The sample preparation method refers to standard GB/T 5750.9-2006.



Wenmin Liu and Chunxiao Wang are application chemists based at Agilent Technologies (Shanghai), Co. Ltd., 412 Ying Lun Road, Waigaoqiao Free Trade Zone, Shanghai, 200131 China

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Figure 2. Chromatograms of organochlorine pesticides standard at 10 µg/L (A) and spiked drinking water (B).

Table 2. Recoveries of Analytes

Compounds	α -BHC	β -BHC	Lindane	σ -666	p,p'-DDE	o,p'-DDT	p,p'-DDD	p,p'-DDT
Recovery (%)	101.5	96.6	85.7	99.2	92.7	92.2	86.3	97.9

References

1. Chinese National Standard Methods for Drinking Water – Pesticides Parameters, GB/T 5750.9-2006
2. Tu Chuanhong, "Analysis of Organochlorine and Pyrethroid Pesticides with Agilent 6820 Gas Chromatograph/Micro-Electron Capture Detector," Agilent Technologies publication 5989-1333EN

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Printed in the USA
January 23, 2009
5990-3473EN



Agilent Technologies



Achieving the Desired Prescribed Sensitivities of Selected Herbicides by Direct On-Column Aqueous Injection of Potable and Environment Samples Using the Agilent 6410BA LC/QQQ

Application Note

Environmental

Authors

Neil Cullum
Anglian Water Services Laboratory
Huntingdon
Cambridgeshire
United Kingdom

Paul Stephens
Agilent Technologies UK Ltd.
Winnersh
Berkshire
United Kingdom

Dr Peter J. W. Stone
Agilent Technologies Inc.
Stevens Creek Boulevard
Santa Clara, CA, 95051
USA

Abstract

Here we describe the analysis of 20 selected herbicides by direct on-column aqueous injection of environmental water samples of several matrices with little pretreatment. We demonstrate that this approach fulfills sufficient sensitivity requirements outlined by the UK Drinking Water Inspectorate. Precision data obtained were typically in the range of 2.2 to 7.0% and analyte recoveries were between 90.2 to 104.7%. Limits of detection were less than 10 ng/L (10 ppt) for all of the compounds in this suite.



Agilent Technologies

Introduction

Several sample preparation/analysis approaches are available for the determination of herbicides in water samples, typically LC/MS after solid phase extraction (SPE) and even LC/MS employing on-line analyte enrichment [1]. Solid phase extraction is time consuming and adds an expense to the method with consumable materials and additional man-hours. On-line enrichment [ibid], on the other hand, requires the purchase of additional LC hardware, such as switching valves and an additional LC pump. With the introduction of affordable, reliable and sensitive LC/QQQ instrumentation such as the Agilent 6410BA triple quadrupole LC/MS system, it is now possible to achieve prescribed analysis requirements by injecting

aqueous samples directly onto the analytical column using conventional injection volumes of up to 100 μL .

The aim of this application note is to demonstrate a reliable and robust analytical method for the analysis of 20 selected herbicides in potable and environmental water samples, with a performance criteria of < 12.5% analyte precision, analyte recoveries in the range of 90 to 110%, and limits of detection < 10 ng/L (10 ppt).

The method presented here describes the analysis of a mixture of 20 acidic, neutral, and basic herbicides (Figure 1) in different water matrices by direct aqueous injection. An overview of the full validation data is summarized.




Figure 1. Suite of neutral, acidic, and basic herbicides.

Experimental

This analysis was performed using an Agilent LC/QQQ 6410BA mass spectrometer upgraded with a hotbox kit coupled to an Agilent 1200 Series LC system. The LC system consisted of a binary pump (G1312B), vacuum degasser (G1379B), automatic liquid sampler (G1367C), thermostatted column compartment (G1316B), and MassHunter data system. The hotbox upgrade kit (G2573A) comprised an additional MS turbo-pump with controller and replacement entrance and exit lenses for the collision cell.

Sample Preparation

Minimal sample preparation was required, which was simple acidification of all standards and samples. These were acidified to a concentration of 0.1% formic acid, which was used as the pH modifier.

Instrumentation

LC Conditions

Column:	Agilent ZORBAX SB-C18, 2.1 × 100 mm 1.8 µm thermostatted at 70 °C			
Mobile phase	A: 0.1% formic acid in HPLC water B: methanol			
Gradient program:	Time (min)	A (%)	B (%)	Flow rate (mL/min)
	Initial	95	5	0.3
	0.5	95	5	0.3
	1.0	80	20	0.3
	20.0	20	80	0.3
	20.1	95	5	0.3

Injection volume:	100 µL
Total run time:	26.0 min

QQQ MS Conditions

Source Conditions

Electrospray AP-ESI:	Positive ionization polarity
Drying gas temperature and flow:	300 °C, 10 L/min
Nebulizer gas pressure:	40 psi
Capillary voltage:	3000 V
Fragmentor voltage:	See Table 1
MRM parameters:	See Table 1

MRM Parameters

Table 1. MRM Transitions for Herbicide Suite

Time seg	Time (min)	Delta EMV (V)	Compound	Precursor ion (m/z)	Product ions (m/z)	Fragmentor voltage (V)	Collision energy (V)	Dwell time (msec)
2	0.2	600	Clopyralid	192.0	146.2	75	19	400
			Clopyralid	192.0	174.2 (q)*	75	6	100
3	6.4	600	Picloram	241.0	223.1	95	9	400
			Picloram	241.0	195.0 (q)*	95	18	100
4	7.6	400	Metamitron	203.1	175.1	115	14	90
			Metamitron	203.1	104.1 (q)*	115	22	90
			Imazapyr	262.2	234.3	130	14	90
			Imazapyr	262.2	217.2 (q)*	130	17	90
			Chloridazon	222.1	104.2	135	22	90
			Chloridazon	222.1	92.1 (q)*	135	27	90
5	10.0	400	Carbetamide	237.1	192.3	80	2	70
			Carbetamide	237.1	72.2 (q)*	80	22	70
			Monuron	199.1	72.2	105	16	70
			Monuron	199.1	126.1 (q)*	105	25	70
			Cyanazine	241.2	214.2	125	12	70
			Cyanazine	241.2	104.1 (q)*	125	31	70
			Simazine	202.1	132.2	125	16	70
			Simazine	202.1	104.1 (q)*	125	27	70
6	14.5	400	Chlorotoluron	213.1	72.2	110	21	250
			Chlorotoluron	213.1	140.2 (q)*	110	24	250
7	15.6	400	Diuron	233.1	72.2	110	22	90
			Diuron	233.1	160.3 (q)*	110	26	90
			Atrazine	216.2	174.2	120	15	90
			Atrazine	216.2	104.1 (q)*	120	32	90
			Isoproturon	207.2	72.2	110	22	90
			Isoproturon	207.2	165.3 (q)*	110	10	90
8	17.0	400	Prometryn	242.2	200.3	135	17	30
			Prometryn	242.2	158.2 (q)*	135	24	30
			Terbutryn	242.2	186.2	120	17	30
			Terbutryn	242.2	91.2 (q)*	120	30	30
			Linuron	249.1	182.1	105	18	100
			Linuron	249.1	160.3 (q)*	105	12	100
			Propazine	230.2	188.2	125	15	30
			Propazine	230.2	146.1 (q)*	125	24	30
			Terbuthylazine	230.2	174.2	110	15	30
			Terbuthylazine	230.2	104.1 (q)*	110	30	30
			Propyzamide	256.1	190.1	95	12	30
			Propyzamide	256.1	173.0 (q)*	95	22	30
9	19.6	400	Trietazine	230.2	202.2	130	18	250
			Trietazine	230.2	99.2 (q)*	130	24	250

*(q) = Qualifier ion

Results and Discussion

The total ion chromatogram (TIC) for a 0.5 µg/L (500 ppb) standard consisting of this 20 herbicide suite is shown in Figure 2, which also illustrates the positioning of the time segmentation.

Five levels of calibration standards were used to prepare the calibration curves over the concentration range of 0.0, 0.05, 0.10, 0.30, and 0.50 µg/L. Selected and representative calibration curves are shown in Figures 3a through 3c.




Figure 2. MRM overlay showing 20 herbicides from 0.5 µg/L standard.




Figure 3a. Monuron calibration curve.




Figure 3b. Simazine calibration curve.




Figure 3c. Propyzamide calibration curve.

Validation of the method was carried out on 11 batches of samples. Borehole groundwater, potable water (which was from a surface water source), and river water were spiked at two levels (0.01 and 0.10 µg/L). Deionized water was spiked at three levels with analytical quality control material at 0.01, 0.10, and 0.40 µg/L. Each batch of samples was analyzed in duplicate and in a random order. The limit of detection (LOD) for each herbicide was calculated from the within-batch standard deviation ($5 \times sw$) of the deionized water spiked at 0.01 µg/L. Recovery for the groundwater, potable water, and river water was calculated from the 0.1 µg/L spike.

Experimental results are shown in Table 2.

Table 2. Validation Data: %Recovery, $\pm\%$ RSD, and Limit of Detection (LOD)

Compound	Borehole groundwater %Rec	Potable water %Rec	River water %Rec	LOD (µg/L)
Clopyralid	100.8 $\pm$ 5.7	104.7 $\pm$ 5.7	101.4 $\pm$ 7.0	0.007
Picloram	99.7 $\pm$ 4.0	94.2 $\pm$ 4.0	94.3 $\pm$ 5.5	0.005
Metamitron	100.5 $\pm$ 4.3	96.2 $\pm$ 3.9	97.1 $\pm$ 3.4	0.003
Imazapyr	101.7 $\pm$ 3.4	97.9 $\pm$ 3.2	97.3 $\pm$ 3.9	0.005
Chloridazon	99.7 $\pm$ 3.5	93.0 $\pm$ 4.5	92.9 $\pm$ 4.5	0.004
Carbetamide	98.0 $\pm$ 5.2	90.2 $\pm$ 4.7	93.8 $\pm$ 3.9	0.009
Monuron	99.8 $\pm$ 3.3	92.5 $\pm$ 3.8	90.8 $\pm$ 3.5	0.005
Cyanazine	99.4 $\pm$ 4.5	91.0 $\pm$ 4.5	92.7 $\pm$ 3.2	0.004
Simazine	100.1 $\pm$ 2.9	98.9 $\pm$ 2.9	98.2 $\pm$ 3.1	0.004
Chlorotoluron	99.5 $\pm$ 3.2	99.9 $\pm$ 3.8	99.7 $\pm$ 3.7	0.003
Diuron	98.3 $\pm$ 3.7	100.2 $\pm$ 5.0	98.9 $\pm$ 5.3	0.006
Atrazine	99.4 $\pm$ 2.2	99.4 $\pm$ 2.9	100.5 $\pm$ 3.5	0.002
Isoproturon	99.1 $\pm$ 3.8	99.7 $\pm$ 3.7	99.0 $\pm$ 3.9	0.003
Prometryn	99.7 $\pm$ 2.9	100.1 $\pm$ 3.0	100.5 $\pm$ 3.5	0.003
Terbutryn	99.0 $\pm$ 2.9	99.1 $\pm$ 3.4	99.7 $\pm$ 3.3	0.002
Linuron	99.3 $\pm$ 5.8	100.2 $\pm$ 3.3	102.4 $\pm$ 6.4	0.003
Propazine	99.6 $\pm$ 3.2	99.9 $\pm$ 3.3	99.4 $\pm$ 2.9	0.002
Terbuthylazine	99.8 $\pm$ 3.8	99.0 $\pm$ 3.0	100.6 $\pm$ 2.9	0.003
Propyzamide	101.4 $\pm$ 4.4	99.4 $\pm$ 3.3	99.8 $\pm$ 3.8	0.004
Trietazine	99.9 $\pm$ 2.8	100.0 $\pm$ 2.7	101.0 $\pm$ 2.5	0.002
Overall suite	99.7 $\pm$ 3.8	97.8 $\pm$ 3.7	98.0 $\pm$ 4.0	0.004

Selected and representative examples of MRM chromatograms derived from real sample matrices are shown in Figure 4.




Figure 4a. MRM chromatogram of carbetamide (river water matrix).




Figure 4b. MRM of simazine (river water matrix).




Figure 4c. MRM of trietazine (river water matrix).

Conclusions

The data show that the method herein presented is capable of sensitive and quantitative analysis for the 20 herbicides in a single analytical suite by a direct aqueous injection of 100 µL sample volumes onto the analytical column. Only sample acidification was undertaken as a preparation stage. All the method performance criteria are met, which are < 12.5% analyte precision, recoveries in the range of 90 to 110%, and limits of detection < 10 ng/L (10 ppt).

We demonstrate in this application note that direct aqueous injection of 100 µL samples onto the analytical column achieves the required method performance levels and is possible due to the sensitivity and selectivity of the Agilent LC/QQQ 6410BA instrumentation. The net benefit of such an approach to this methodology is a direct cost reduction in the form of consumable items (solid phase cartridges), which are no longer required, together with significant man-hour cost reductions since only minimal sample preparation is undertaken (acidification).

Reference

1. "Determination of Phenyl Urea and Triazine Herbicides in Potable and Groundwaters by LC/MS Using AP-ESI Selective Ion Monitoring and Direct Large Volume Aqueous Injection," Agilent Technologies publication 5989-0813EN.

For More Information

For more details concerning this application note, please contact Neil Cullum at Anglian Water Services Laboratory, Huntingdon, Cambridgeshire, UK.

Reference herein to any specific commercial products or non-profit organization, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government and shall not be used for advertising or product endorsement purposes.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Printed in the USA
March 31, 2009
5990-3762EN



Agilent Technologies

The Use of Accurate Mass, Isotope Ratios, and MS/MS for the PPCPs in Water



Application

Environmental

Authors

Michael Zumwalt
Agilent Technologies, Inc.
9780 S Meridian Blvd.
Englewood, CO 80112-5910
USA

David Weil
Agilent Technologies, Inc.
10 N. Martingale Road, Suite 550
Schaumburg, IL 60173-2292
USA

Chin-Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

An Agilent 6510 Quadrupole Time-of-Flight Mass Spectrometer (QTOF) is used to analyze several surface water samples for the presence of pharmaceutical compounds. A simple gradient elution is carried out on a Rapid Resolution High Throughput Extend C18 column (particle size 1.8 μm). Of 54 potential compounds, as many as 11 are identified in one of the samples using an algorithm known as the Agilent Molecular Feature Extractor (MFE). To make comparisons among several samples, another algorithm, known as Mass Profiler, is applied to the data processed by the MFE. Since the MFE may generate thousands of potential compounds known as features, Mass Profiler makes statistical comparisons of the features between two different samples to determine what is unique and what is common. All of this work is done with the full-scan mass spectral data. When compounds of interest are determined, accurate mass full-scan MS/MS

can be invoked for structural elucidation. The results of full-scan MS/MS applied to caffeine are included as an example and are relevant because many medications include caffeine as an ingredient.

Introduction

During the three decades prior to the year 2000, the study of chemical pollution was confined primarily to pesticides. Following a seminal article by C. Daughton [1], this focus began to shift to the emerging environmental concern for pharmaceuticals and personal care products (PPCPs). Many of these pharmaceuticals, including estrogen, have been known as endocrine disruptors, or chemicals that disrupt the physiological function of hormones in organisms. In 2004 a report from the United States Geological Survey [2] was made as a result of discovering a high preponderance of intersex (male fish exhibiting female characteristics) in smallmouth bass of the Potomac River.

The USGS has found pesticides, flame retardants, and personal-care products containing known or suspected endocrine-disrupting compounds in the Potomac River. Many of these compounds continue to be known as emerging contaminants because they are still being discovered and don't exist on any currently regulated target lists. As such, it is important to use adequate techniques to help identify these compounds and possible metabolites.

Using accurate mass in full-scan (mass range) mass spectrometry (MS), compound empirical formulas can be determined for purposes of identification. Furthermore, the high degree of spectral resolution allows for selective identification among co-eluting compounds. Isotope ratios are an additional tool because they help identify com-



Agilent Technologies

pounds with high carbon numbers as well as those that contain elements like chlorine and sulfur. Although these tools do a lot to confirm chemical formula, it may still be left to the user to decide which of the possible structures of isobaric compounds apply.

To assist in the analytical need for structural elucidation, selective MS/MS by using the quadrupole time-of-flight mass spectrometer (QTOF) is implemented. Because the Agilent QTOF also has very accurate mass at the MS/MS level, it is easier to determine the structures of the product ions, which correspond as substructures of the precursor ion and thereby reduce the number of possible structures pertaining to the derived empirical formulas from several to one.

The list of pharmaceuticals to look for in the environment is ever-increasing and many of them are metabolites with unknown structures. Identifying these compounds requires the technology of the QTOF. Furthermore, the fast scanning capability is necessary for identifying 10s to 100s of these compounds in samples with relatively short run times. The Agilent QTOF is capable of acquiring full-scan MS data at the rate of 20 spectra/sec. The resulting large amount of data representing a possibly large number of compounds needs to be converted into useful information. The Agilent Molecular Feature Extractor (MFE), which is a standard part of the MassHunter Qualitative Analysis software, carries out the following steps:

- Persistent chemical background removed

- Co-eluting interferences resolved
- Isotopic clusters recognized and grouped
- 2D/3D data visualization
- Chemical identification (accurate mass, isotope matching)
- Database searching (NIST, ChemIDPlus)

In addition to applying the algorithm Mass Feature Extractor to pull out the features from the chromatographic data, which could be compounds, another algorithm, known as Mass Profiler, is applied to the list of features among different samples to determine differences and commonalities. Each sample is injected three times, or multiple samples from the same source could be used to determine what is statistically consistent in terms of the features derived for the sample by MFE. The result is called a group. Two groups representing two different sample sources can then be compared to see what features differ, are unique, or are common, and, if common, whether they differ in abundance.

A batch of water samples is filtered and extracted using solid-phase extraction, which resulted in an approximate 1,000-fold increase in concentration. Samples analyzed in this work are believed to contain compounds at the 10 to 100 ppb level, which corresponds to the 10 to 100 ppt range in the original water sample. The compounds that may be in these samples are included with their exact neutral masses in Table 1.

Table 1. List of Compounds with Corresponding Neutral Masses That May Be in a Given Sample

Compound	Neut. mass	Compound	Neut. mass	Compound	Neut. mass
Acetaminophen	151.06333	Diphenhydramine	255.16231	Paroxetine	329.14272
Albuterol	239.15214	Duloxetine	297.11873	Ranitidine	314.14126
Aspirin	180.04226	Enalaprilat	348.16852	Sertraline	305.07380
Bupropion	239.10769	Erythromycin	573.51210	Simvastatin	418.27192
Caffeine	194.08038	Fluoxetine	309.13405	Sulfachloropyridazine	284.01347
Carbamazepine	236.09496	Fluvoxamine	318.15551	Sulfadimethoxine	310.07358
Cimetidine	252.11572	Furosemide	330.00772	Sulfamethazine	278.08375
Clofibric acid	214.03967	Gemifrozil	250.15698	Sulfamethizole	270.02452
Citalopram	324.16379	HCTZ	296.96447	Sulfamethoxazole	253.05211
Codeine	299.15215	Ketoprofen	254.09429	Thiabendazole	201.03607
Cotinine	176.09496	Miconazole	413.98602	Triclocarban	313.97805
Dehydronifedipine	344.10084	Naproxen	230.09429	Triclosan	287.95116
Diclofenac	295.01668	Norfluoxetine	295.11840	Trimethoprim	274.14298
Diltiazem	414.16133	Norsertaline	293.05000	Venlafaxine	267.12593
		1,7-dimethylxanthine	180.06473	Warfarin	308.10486

Experimental

Sample Preparation

Prepared samples are provided by the United States Geological Service National Water Quality Laboratory (USGS/NWQL) in Denver, Colorado. The details of the procedure used are not included in this application, but are available upon request. Pharmaceuticals are typically extracted from surface water by using disposable polypropylene syringe cartridges that contain 0.5 g of polymeric sorbent. One liter of sample is pumped through the solid-phase extraction (SPE) cartridge. The analyte material is later eluted into 1 mL of methanol, resulting in a concentration increase of three orders of magnitude.

LC/MS Method Details

LC Conditions

Agilent 1100 Series binary pump, degasser, wellplate sampler, and thermostatted column compartment

Column	Agilent ZORBAX RRHT Extend C18 2.1 mm × 50 mm, 1.8 μm Agilent p/n: 727700-902		
Column temperature	40 °C		
Mobile phases	A = 0.1% formic acid in water B = 0.1% formic acid in acetonitrile		
Flow rate	0.3 mL/min		
Injection volume	5 μL		
Gradient			
	Time (min)	%B	
	0.0	0	
	10.0	67	Stop time: 15 min
	11.0	100	Post run: 10 min

MS Conditions

Mode	Positive electrospray ionization using the Agilent G3251A Dual ESI source
Nebulizer pressure	40 psig
Drying gas flow	9 L/min
Drying gas temp.	350 °C
V _{cap}	3500 V
Scan range	<i>m/z</i> 50–1000
Scan speed	1 scan/sec

MS/MS Conditions

Collision energy	30 V
Scan range	<i>m/z</i> 50–1000
Scan speed	1 scan/sec

Results and Discussion

Of the several samples analyzed, results for Samples 4 and 10 will be considered here. To get an idea of the task at hand, an overlay of the total ion and base peak chromatograms for the first injection of Sample 4 is shown in Figure 1. The base peak chromatogram is generated to help the analyst identify peaks in the chromatogram corresponding to real compounds. Figure 2 shows the spectrum at the apex of one such peak. Note the complexity of this spectrum and the difficulty involved in not only determining which spectral peaks are of value, as they may pertain to co-eluting compounds, but then having to apply this reasoning to several peaks in the chromatogram.

Applying the algorithm of the Molecular Feature Extractor program to this data file results in the display of the processed chromatogram and the corresponding contour plot shown in Figure 3. The upper left-hand chromatogram is the unprocessed TIC, same as shown in Figure 1. On the right is the processed chromatogram after applying the steps listed in the Introduction. Random background noise has been removed. Below each of these chromatograms are shown the corresponding contour plots, which are the presentations of spectral data points in an *m/z* versus chromatographic retention time plots. The contour plot at the lower left-hand corner of the display shows a very dense distribution of data points, most of which correspond to random noise.

The contour plot at the lower right-hand corner is the result of processing the data so that a significant amount of molecular features are derived for closer examination. In fact, using the following settings for filtering the data, some 5,431 features are derived for this sample in the first injection:

- Spectral S/N > 2
- Mass range: *m/z* 150 to 800
- [M + Na]⁺ and [M + NH₄]⁺ adducts considered
- Relative intensity in the spectrum > 0.1%
- Each feature must contain at least 2 ions




Figure 1. Overlay of total ion chromatogram (TIC) and base peak chromatogram (BPC) for Sample 4.

If we now investigate some of the features that have been found we can begin with the peak apex spectrum examined in Figure 2. The retention time is 6.445 minutes and MFE has derived features at 6.448 minutes as shown in Figure 4. The unprocessed spectrum at the top of the figure matches

that of Figure 2. However, removing random noise and using the filtering rules above a processed spectrum containing 12 features is derived and shown at the bottom. A subset of the list of features is shown at right.




Figure 2. Spectrum at apex of base peak with retention time of 6.445 minute.




Figure 3. Both unprocessed and processed data of Sample 4 using MFE.




Figure 4. Twelve features shown at derived retention time of 6.448 minutes.

If we want to filter the data to only show compounds corresponding to the list at the beginning of this article, we can place the neutral masses into an inclusion list of MFE as shown in Figure 5. We also assume that the compounds of interest do not elute until after 4 minutes and the mass range of interest is 150 to 600, which corresponds to the compounds of Table 1.

After applying the filtering of data with the compound list shown in Figure 5, eight features appear to be found in Sample 4 as shown in Figure 6. The corresponding chromatogram containing these eight features is also shown.

Before looking more closely at any one of these compounds, the data of Sample 4 is now going to be compared with data from another sample, Sample 10. The comparison will be carried out using an algorithm known as Mass Profiler. In

order to use Mass Profiler, at least three injections of each sample must be made to determine what is consistently there and what is random and should be disregarded. In this work each sample is injected three times. The data is first processed by MFE to generate features. Mass Profiler filters out features that are inconsistent among the three injections for each sample. The resulting data is called a Group. Therefore, in comparing Samples 4 and 10 Mass Profiler will be referring to them as Group 4 and Group 10.

In Figure 7, Mass Profiler shows a plot of features common to both Groups 4 and 10 and displays them as mass versus retention time. By clicking on any one of the feature points in the display, one can see the common feature for both Groups along with possible empirical formulas for the derived neutral mass.

Display Filters

Feature Position

☐ Use all the available data

RT Min: 4.0 Max: 15.0 min.

Mass Min: 150 Max: 600 Da

Special Masses

☐ Exclude ☒ Limit to these Tolerance: 0.0050 Da

284.0135	287.9512	293.0500	295.0167	295.1184
296.9645	297.1187	299.1521	305.0738	308.1049
309.1341	310.0736	313.9781	314.1413	318.1555
324.1638	329.1427	330.0077	344.1008	348.1685
413.9880	414.1613	418.2719	573.5121	

Masses from Table 1

Isotope Pattern

Formula Custom

formula

normalized height error: 0.15

Mass Defect

☐ Peptide Like

target defect = 0.00 (Da) + 0.00000 x mass

deviation allowed: 0.50 Da

Features of Unknown Mass

☒ included ☐ excluded ☐ limited to these

Number of Ions

☒ >= 2 ☐ <

Abundance

Relative Absolute Top

Min Relative Abundance: 0.100 %

Neutral Losses

Tolerance: 0.0050 Da

OK Cancel

Figure 5. Display filter settings for finding features that match compound list of Table 1.

Export features:8 / groups:8													
	Group	RT	mass	mass SD	abund.	satur.	height	#ions	minZ	maxZ	#z	width	#features
1	1	9.629	236.0961		915731		267469	2	1	1	1	0.045	1
2	2	5.678	299.1536		431858		91085	2	1	1	1	0.083	1
3	3	8.095	236.0961		382835		96590	2	1	1	1	0.052	1
4	4	8.671	299.1527		229538		23883	3	1	1	1	0.121	1
5	5	6.064	299.1525		146722		26146	2	1	1	1	0.076	1
6	6	11.598	250.1607		134252		19366	2	1	1	1	0.128	1
7	7	8.262	252.1204		63528		12743	2	1	1	1	0.058	1
8	8	5.307	296.9660	0.0019	28147		3522	4	1	1	1	0.072	1




Figure 6. Eight features found corresponding to the neutral masses of Table 1. Corresponding processed chromatogram also shown.




Figure 7. Features present in both Groups 4 and 10 total 346.

For example, in comparing features between the two sample groups a differential analysis plot can be generated as shown in Figure 8. In this plot, the features of Group 10 that are more or less abundant than the corresponding features in Group 4 are represented. More specifically, at a retention time of 8.495 minutes there is a data point in Figure 8 that corresponds to a feature in Group 10 that is approximately 4× intensity over the corresponding feature in Group 4, which corresponds to

a log 2 ratio of 2. By clicking on this data point in the display of Figure 8 one can see that this feature is identified as diphenhydramine, with a chemical formula of $C_{17}H_{21}NO$ and accurate mass of 0.7 ppm. See Figure 9.

With Mass Profiler it is also possible to compare two samples in terms of what features are in one sample that are not in the other. In Figure 10 we see such a comparison.




Figure 8. Features common to Groups 4 and 10 but differing in magnitude.




Figure 9. Feature at 8.495 minutes retention time corresponds to diphenhydramine.




Figure 10. Features only in Group 4 (highlighted with boxes) or in Group 10.

Mass Profiler has determined that there are 33 features only in Group 4 or in Group 10 and are not common to the two samples. Since the display in Mass Profiler is in color the features exclusive to Group 4 are blue and the features exclusive to Group 10 are red. Since Agilent applications are normally published in black and white, boxes have been placed around the blue features for Group 4 for viewing convenience.

So far, all of the data have been collected in full-scan MS mode. Once features are identified as compounds needing more structural information, or it is of interest to perform some quantitation, a targeted MS/MS analysis can be performed in which the ion mass of the feature is considered as precursor ion and fragmented to form accurate mass product ions. The accurate mass of these product ions can determine their chemical formula and possible structures. Because the QTOF also has a high degree of spectral resolution in MS/MS mode, very narrow extracted ion chromatograms may be generated for each ion and then summed together for quantitation signal.

In Figure 11 we see the accurate mass MS/MS fragmentation of caffeine using the MS/MS settings noted in the LC/MS Method Details. Caffeine is of environmental interest because many medications contain it as an ingredient. Chemical formulas for each product ion is derived based on the possible arrangements of C, H, N, and O. Knowing the structure of caffeine, structures of the fragment ions can be proposed using their corresponding chemi-


cal formula. The fragment structures are generated using ACD/MS Fragmentor (ACD Labs Release v. 10, Advanced Chemistry Development, Inc., Toronto, ON, Canada).

Conclusions

The QTOF is an excellent instrument for identifying compounds using accurate mass in full-scan MS and MS/MS. Accurate mass leads to chemical formula, which can also give structural information when forming product ions in MS/MS. As a lot of data is acquired by this type of instrument to look at samples that may contain large amounts of known and unknown compounds, it is important to have algorithms like Molecular Feature Extractor that can filter usable features out of the chemical background. These features are generated from spectra as a result of removing random background signal and finding clusters of isotopes that make sense.

While this analysis is useful for one sample it may also be important to make comparisons among multiple samples as well. Another algorithm known as Mass Profiler makes such comparisons. More specifically, comparisons such as what is common to two samples and how they differ in amount. Or, what features are in one sample that aren't in the other. Once the feature is considered for more investigation, targeted MS/MS may be carried out on that feature to get structural information based on the generation of product ions.

Calculate chemical formula given accurate mass measurement and using elements C, H, N, and O



Proposed Structures

Figure 11. Targeted MS/MS mode for caffeine-producing product ions that may be used for structural elucidation as well as quantitation.

References

1. C. G. Daughton and T. A. Ternes, "Pharmaceuticals and Personal Care Products in the Environment: Agents of Subtle Change?," *Environmental Health Perspectives*, 107, Suppl. 6, Dec 1999.
2. D. B. Chambers and T. J. Leiker, "A Reconnaissance for Emerging Contaminants in the South Branch Potomac River, Cacapon River, and Williams River Basins, West Virginia, April–October 2004," Open File Report 2006-1393, United States Geological Survey, <http://pubs.usgs.gov/of/2006/1393/>.

Acknowledgments

The authors gratefully acknowledge the assistance of Stephen Werner and Ed Furlong of the National Water Quality Lab – United States Geological Survey (Lakewood, CO) for providing the samples analyzed in this work.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

For more details concerning this application, please contact Michael Zumwalt at Agilent Technologies, Inc.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
October 12, 2007
5989-7339EN



Agilent Technologies



Rapid Analysis of Herbicides by Rapid Resolution LC with Online Trace Enrichment Application

Environmental

Author

Michael Woodman
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Environmental and Food Safety agencies are constantly updating methods to improve detection limits and to resolve interfering compounds. One particular method, EPA 555, is used for the analysis of chlorinated phenoxy acid herbicides in drinking water. A mandated trace enrichment step significantly impacts the ease of use and reliability of the method. The method uses 5- μm analysis columns and online trace enrichment. The variation here uses small ZORBAX 3.5- and 1.8- μm RRHT columns and an autoSPE (Solid Phase Extraction) cartridge with an automated switching valve mounted in the column compartment. Combined with sample introduction via direct injection to the autoSPE cartridge, instead of the loading pump specified in the EPA method, we dramatically reduce the overall analysis time and virtually eliminate the potential of sample cross-contamination.

Introduction

Trace analyte detection in relatively clean matrices is an excellent application for online SPE procedures. Compared to manually loading samples with

disposable SPE cartridges, which require an elution step into a vial prior to analysis, online SPE assures 100% sample transfer to the analysis column and dramatically increases sensitivity by increasing the analyte mass delivered to the column. In EPA Method 555, 20 mL of drinking water is loaded through a pump to an SPE cartridge mounted on a high-pressure switching valve on the HPLC system. Because few, if any, autosamplers can inject this large volume, the sample must be pumped onto the cartridge. Contamination of the loading pump with prior samples is always a concern, and adequate flushing and blank runs become an important part of the overall method procedure.

To reduce the sampling volume sufficient for available automatic preparative samplers, without losing sensitivity in the method, it is necessary to reduce the analysis column size while preserving resolving power. Ancillary benefits of using smaller columns generally include reduced analysis time and solvent consumption, and greater compatibility with ionization sources in mass spectrometers.

If the ratios of their column length to particle size are equal, columns are considered to have equal resolving power. Significant reductions in column volume can be made by reducing the length and/or internal diameter of the column. In the latter case, the flow rate would normally be reduced as in Equation 1.



Agilent Technologies

$$\text{Flow}_{\text{col. 1}} \times \left[\frac{\text{Diam}_{\text{column2}}}{\text{Diam}_{\text{column1}}} \right]^2 = \text{Flow}_{\text{col. 2}} \quad (\text{eq. 1})$$

The combined effect of reduced length and diameter contributes to a reduction in solvent consumption. We normally scale the injection mass to the size of the column and a proportional injection volume would be calculated from the ratio of the void volumes of the two columns, multiplied by the injection volume on the original column, as in Equation 2 below.

$$\text{Inj. vol.}_{\text{col. 1}} \times \left[\frac{\text{Volume}_{\text{column2}}}{\text{Volume}_{\text{column1}}} \right] = \text{Inj. vol.}_{\text{col. 2}} \quad (\text{eq. 2})$$

Short columns packed with small particle sizes are typically operated at high linear velocities. The increase in elution speed will decrease absolute peak width and may require the user to adjust data acquisition rates and reduce signal filtering parameters. This will ensure that the chromatographic separation is accurately recorded in the acquisition data file.

For gradient elution separations, where the mobile phase composition increases through the initial part of the analysis until the analytes of interest have been eluted from the column, successful method conversion to smaller columns requires that the gradient slope be preserved. We can express the gradient slope as in Equation 3.

$$\% \text{ Gradient slope} = \left[\frac{(\text{End}\% - \text{Start}\%)}{\# \text{Column volumes}} \right] \quad (\text{eq. 3})$$

Note that the use of % change per column volume rather than % change per minute frees the user to control gradient slope by altering gradient time and/or gradient flow rate. A large value for gradient slope yields very fast gradients with minimal resolution, while lower gradient slopes produce higher resolution at the expense of increased solvent consumption and somewhat reduced sensitivity. Longer analysis time may also result unless the gradient slope is reduced by increasing the flow rate, within acceptable operating pressure ranges, rather than by increasing the gradient time.

Resolution increases with shallow gradients because the effective capacity factor, k^* , is increased. Much like in isocratic separations, where the capacity term is called k' , a higher value directly increases resolution. The effect is quite dramatic up to a k value of about 5–10, after which

little improvement is observed. In the subsequent examples, we will see the results associated with the calculations discussed above.

Experimental Conditions

See figure 1 for configuration.

System

Agilent 1200 Series Rapid Resolution LC consisting of:
 G1379B micro degasser
 G1312B binary pump SL
 G1312A binary pump with solvent selection valve option, or
 G1354A quaternary pump
 G1367C HiP ALS autosampler SL, and
 G2258A Dual Loop Prep autosampler 5 ml
 G1316B Thermostatted column compartment SL with 6- or 10-port
 2-position switching valve
 G1315C UV/VIS diode array detector (DAD) SL, flow cell as indicated in individual chromatograms
 ChemStation 32-bit version B.02.01

Columns

Agilent ZORBAX SB-C18, 4.6×250 mm, $5 \mu\text{m}$
 Agilent ZORBAX SB-C18, 3.0×150 mm, $3.5 \mu\text{m}$
 Agilent ZORBAX SB-C18, 2.1×80 mm, $1.8 \mu\text{m}$
 Agilent ZORBAX SB-Aq, 4.6×12.5 mm, $5 \mu\text{m}$

Mobile phase conditions

Organic solvent: Acetonitrile
 Aqueous solvent: 25 mm phosphoric acid in Milli-Q water

Gradient conditions

Gradient slope: 7.8 or 2.3% per column volume, as indicated. See individual chromatograms for flow rate and time

Sample

EPA 555 Group A chlorinated phenoxy acid herbicides (picloram, chloramben, dicamba, bentazon, 2,4-D, dichlorprop, 2,4,5-TP, acifluorfen), 100 $\mu\text{g/mL}$ in methanol or diluted to 20 ng/L (20 ppb) in reagent water acidified with 25 mm phosphoric acid.

Results

The separation was initially performed via direct injection of concentrated standard on a 4.6×250 mm, $5\text{-}\mu\text{m}$ ZORBAX SB-C18 column, thermostatted to 25°C , using conditions referenced in US EPA method 555 (Figure 2). The described trace enrichment procedure using pump A as the loading pump was performed (Figure 3). The method was then scaled in flow and time for exact translation to a 3.0×150 mm $3.5\text{-}\mu\text{m}$ column (Figure 4) using 5-mL trace enrichment injection. Finally, a 2.1×80 mm $1.8\text{-}\mu\text{m}$ configuration (50-mm plus 30-mm columns in series) is used to demonstrate the feasibility of this separation under conditions for trace enrichment requiring less than 1.5-mL injection. (Figure 5)


Load/Wash position**Elute/Analyze position**

Figure 1. Trace enrichment autoSPE scheme.

Figure 1 shows the schematic placement of modules and columns in the system. The A pump is the loading pump in case of volumes exceeding the 5-mL capacity of the G2258A Dual Loop Autosampler, thus pump A uses one line for sample and a second line for the aqueous eluent, 25 mM phosphoric acid. If direct injection from the autosampler is used, pump A is delivering 25 mM phosphoric acid. If the A pump is fitted with a degasser, the sampling line should bypass the degasser module to minimize contamination with sample solutions. To conduct sampling through the A pump, the valve should be in position B while the new sample is flushed through the A pump. Then switch the valve to the A position and load the required 20 mL sample volume. The analysis

begins when the valve is returned to the B position, at which time the sampling line on the A pump would be flushed with reagent water or the next sample, as appropriate.

Figures 2 and 3 show the standard separation by direct injection and pumped trace enrichment, respectively. With column regeneration steps, this results in a total analysis time of 60 minutes. Translation of the gradient to the 3.0- × 150-mm column requires a reduction in flow rate, due to the smaller diameter, and a reduction in gradient time because of the shorter column length. The resulting analysis is reduced from 60 to 36 minutes and solvent consumption is proportionately reduced from 60 mL to 15.5 mL.





Figure 2. Gradient separation of herbicides on 4.6 mm × 250 mm, 5 μm ZORBAX SB-C18.



Conditions

EPA Method 555 with ZORBAX SB-C18 columns and fast DAD detector

ZORBAX SB-C18 4.6 mm × 250 mm, 5 µm

Column temp: 25 °C

Gradient: 25-mM H₃PO₄, ACN, 10% to 90% ACN in 30 min

Gradient slope: 7.8% ACN/column volume


Analysis flow rate: 1 mL/min

Group A compounds: 20 mL of 20 µg/L trace enrichment

Total analysis time: 60 min

Detection: UV 230 nm, 10-mm 13-µL flow cell, filter 2 seconds (default)

Figure 3. Trace enrichment (20 mL) of 20-ppb solution on 4.6 × 250 mm 5-µm ZORBAX SB-C18.



Conditions:

EPA Method 555 with ZORBAX SB-C18 columns and fast DAD detector

ZORBAX SB-C18 3 mm × 150 mm, 3.5 µm

Column temp: 25 °C

Gradient: 25 mM H₃PO₄, ACN, 10% to 90% ACN in 18 min

Gradient slope: 7.8% ACN/column volume

Analysis flow rate: 0.43 mL/min

Group A compounds: 5 mL of 20 µg/L (20 ppb)

Detection: UV 230 nm, 3-mm 2-µL flow cell, filter 0.2 seconds

Total analysis time: 36 min

Figure 4. Trace enrichment (5 mL) of 20-ppb solution on 3.0 × 150 mm, 3.5-µm ZORBAX SB-C18.

The last peak in Figure 4 is missing due to a valve timing error that was not detected until sometime after the lab work was completed. Peak 8 was not eluted from the trace enrichment column before

the valve switched offline for regeneration and equilibration. Note the baseline shift that occurs after peak 7, not seen in other autoSPE examples.




Figure 5. High-speed gradient separation of herbicides on 2.1 × 80 mm, 1.8-μm ZORBAX SB-C18.

In Figure 5 we see the combination of highest speed and resolution, using the full capability of the 1200 Rapid Resolution LC. Operating pressure was, at the maximum point, about 520 bar. We maintain comparable resolution to the original 4.6 × 250 mm, 5-μm method, a 60-minute run time, with an analysis time of only 6 minutes.

Conclusion

As is the case for many existing methods, it is both possible and practical to modernize this method to improve throughput and overall performance. Here we see the potential for a 10-fold increase in analysis speed and elimination of the loading pump scheme found in the original method. Approximately 1.3 mL of sample solution, injected to the autoSPE setup using the 2.1 × 80 mm configuration, is all that is needed to replace the 20-mL injection previously loaded through the pump. This approach can greatly improve productivity and ensure minimal sample cross-contamination.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
March 30, 2007
5989-5176EN



Agilent Technologies



Determination of Pesticides in Water by SPE and LC/MS/MS in Both Positive and Negative Ion Modes

Application

Environmental

Authors

Chin-Kai Meng
Agilent Technologies
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Stephen L. Werner and Edward T. Furlong
National Water Quality Laboratory
U.S. Geological Survey
PO Box 25046, MS 407, Building 95, Denver Federal Center
Denver, CO 80225
USA

Abstract

Using solid phase extraction (SPE) and liquid chromatography/tandem mass spectrometry (LC/MS/MS), 46 pesticides in positive ion mode and 14 pesticides in negative ion mode were analyzed at low pg level on column without any derivatization. Good linearity was observed for all analytes from 5 pg to 1 ng on column.

Introduction

To monitor trace pesticide residues in surface and ground water, an effective sample preparation and analysis method is required. In 1996, US Geological Survey National Water Quality Laboratory (NWQL) developed and implemented a graphitized carbon-based SPE and high-performance liquid chromatography (HPLC) method to determine polar pesticide concentrations [1].

Subsequently, the NWQL developed an HPLC-mass spectrometry (MS) method to improve the sensitivity and selectivity. This method is capable of quantifying pesticides and pesticide metabolites in filtered water at concentrations as low as 10 ng/L.

Taking advantage of the Multiple Reaction Monitoring (MRM) technique, any interference and matrix signal from organic matter in the water can be minimized from the target compound signals for better confirmation and quantitation. In this application, SPE and LC/MS/MS methods are described to analyze 46 pesticides in positive ion mode and 14 pesticides in negative ion mode.

Experimental

Sample Preparation Procedure See reference 1 for more information

1. Filter water samples in the field or laboratory using 0.7- μ m glass fiber filters.
2. Pump 1 L of the filtered water sample, at a flow rate of 20 mL/min, through a Carboapak-B SPE cartridge containing 0.5 g of graphitized carbon sorbent.
3. Elute the compounds with 1.5 mL methanol, followed by 13 mL of an 80:20 methylene chloride:methanol mixture that has been acidified with trifluoroacetic acid anhydride (0.2%).
4. Reduce the two fractions to near dryness and then combine. The final volume of the extract is 1 mL.



Agilent Technologies

Calibration Samples

Separate stock solutions of either positive ion mode or negative ion mode analytes were diluted 1 to 10 to make the calibration standard solutions. The concentrations of the seven calibration solutions were 5, 10, 50, 100, 200, 500, and 1,000 pg/ μ L (ppb).

Instrumentation

Positive Ion Mode			Negative Ion Mode		
LC:	1200 LC		LC:	1200 LC	
Column:	ZORBAX Extend-C-18, RRHT, 2.1 mm $\times$ 100 mm, 1.8 μ m		Column:	ZORBAX Extend-C-18, RRHT, 2.1 mm $\times$ 100 mm, 1.8 μ m	
Column temperature:	40 $^{\circ}$ C		Column temperature:	60 $^{\circ}$ C	
Mobile phases:	A: 0.1% formic acid in water, add NH_4OH buffer to pH 5.5 B: Acetonitrile (ACN)		Mobile phases:	A: 0.04% glacial acetic acid in water B: Acetonitrile (ACN)	
Flow rate:	0.3 mL/min		Flow rate:	0.3 mL/min	
Gradient:	Time	%B	Gradient:	Time	%B
	0	0		0	0
	15	100		1	40
	20	100		2	52
	21.5	0		3	60
				4	100
				8	100
				9	0
Injection volume:	1.0 μ L		Injection volume:	1.0 μ L	
MS:	G6410A QQQ		MS:	G6410A QQQ	
Ionization:	ESI (+)		Ionization:	ESI (–)	
Mass range:	100–500 amu		Mass range:	120–400 amu	
Scan time:	300 ms		Scan time:	300 ms	
Capillary:	3500 V		Capillary:	3500 V	
Nebulizer P:	40 psi		Nebulizer P:	40 psi	
Drying gas:	9 L/min		Drying gas:	9 L/min	
Gas temperature:	350 $^{\circ}$ C		Gas temperature:	200 $^{\circ}$ C	
Skimmer:	35 V		Skimmer:	35 V	

The MRM parameters for positive ion mode and negative ion mode are listed in Tables 1 and 2, respectively.

Table 1. Positive Ion Mode MRM Method Parameters

Name	RT	Precursor	Quant ion	Qual ion	Collision V	Dwell	Segment
3(4 chlorophenyl) methyl/urea	8.05	185	128	93	10	30	4
3-Keto Carbofuran	8.24	236	179	151	10	30	4
3-OH Carbofuran	6.90	238	163	181	10	40	3
Aldicarb	8.20	116	89	70	5	30	4
Aldicarb sulfone	5.52	223	76	86	5	50	2
Aldicarb sulfoxide	4.99	207	89	132	5	150	1
Atrazine	9.86	216	174	96	20	40	5
Bendiocarb (Ficam)	9.32	224	167	109	5	40	5
Benomyl	6.61	192	160	132	30	40	3
Bensulfuron	10.86	411	149	182	15	60	7
Bromacil	8.44	261	205	162	20	30	4
Caffeine	5.48	195	138	110	15	50	2
Carbaryl	9.69	202	145	127	15	40	5
Carbofuran	9.36	222	165	123	10	40	5
Chlorimuron ethyl	11.57	415	186	213	10	60	8
Cycloate	14.52	216	83	154	15	60	8
Desethyl atrazine	7.06	188	146	79	15	40	3
Desisopropyl atrazine	5.94	174	68	104	30	50	2
Desisopropyl desethyl atrazine	1.76	142	86	57	15	150	1
Diphenamid	10.82	240	134	167	20	60	7
Diuron	10.02	233	72	160	20	75	6
Fenuron	6.90	165	72	92	15	40	3
Flumetsulam	7.49	326	129	262	20	30	4
Fluometuron	9.70	233	72	168	20	40	5
Hydroxy-atrazine	6.82	198	156	114	20	40	3
Imazaquin	7.68	312	267	252	20	30	4
Imazethapyr	6.99	290	177	69	30	40	3
Imidacloprid	7.01	256	175	209	15	40	3
Linuron	11.45	249	160	182	15	60	7
Metalaxyl (Apron)	10.15	280	220	192	10	75	6
Methiocarb	11.28	226	169	121	5	60	7
Methomyl	5.77	163	88	106	5	50	2
Metsulfuron methyl	8.43	382	167	199	15	30	4
Neburon	12.99	275	57	88	20	60	8
Nicosulfuron (Accent)	7.97	411	182	213	15	30	4
Norflurazon	10.51	304	284	160	30	75	6
Oryzalin	12.58	347	288	305	10	60	8
Oxamyl (Vydate)	5.59	237	72	90	10	50	2
Propham	10.68	138	120	92	10	75	6
Propiconazole (Tilt)	12.89	342	156	69	20	60	8
Propoxur (Baygon)	9.26	210	111	168	5	40	5
Siduron	11.12	233	137	94	15	60	7
Siduron isomer	11.28	233	137	94	15	60	7
Sulfometuron, methyl ester	9.25	365	150	199	15	40	5
Tebuthiuron	8.14	229	127	116	15	30	4
Terbacil	8.69	161	144	88	15	30	4

Table 2. Negative Ion Mode MRM Method Parameters


Name	RT	MW	Quant	Qual	Frag V	Collision V	Dwell	Segment
Clopyralid	3.47	191	190 > 146	192 > 148	80	5	70	1
Picloram	3.69	240	239 > 195	241 > 198	80	5	70	1
Dicamba	4.31	220	219 > 175	219 > 145	60	0	50	2
DCPA	4.49	330	273 > 215	271 > 213	100	5	50	2
Bentazone	4.69	240	239 > 132	239 > 197	120	25	50	2
2,4-D	5.02	220	219 > 161	221 > 163	80	15	25	3
Bromoxynil	5.06	275	274 > 79	274 > 81	120	25	25	3
MCPA	5.09	200	199 > 141	201 > 143	100	10	25	3
Triclopyr	5.26	255	254 > 196	256 > 198	80	10	25	3
2,4-DP	5.42	234	233 > 161	235 > 163	80	5	25	3
2,4-DB	5.66	248	247 > 161	249 > 163	80	10	40	4
MCPB	5.70	228	227 > 141	229 > 143	80	5	40	4
Acifluorfen	5.89	361	360 > 316	360 > 286	60	5	40	4
Dinoseb	6.50	240	239 > 193	239 > 163	120	25	40	4

Results and Discussion

Figure 1 shows the total ion chromatogram (TIC) for the positive ion mode. As seen in Figure 1, the analysis time is less than 15 minutes for the 46 analytes. Using a 1.8 μ m particle size column, the

peak widths of these analytes are about 0.1 minute. The narrower peak width helps to achieve a higher signal-to-noise (s/n) ratio.

Analysis time in negative ion mode is less than 7 minutes for the 11 analytes, as seen in Figure 2.

**Figure 1. Positive ion mode TIC of 46 pesticides.**

A few compounds, for example, Dicamba, MCPB and 2,4-DB, are sensitive to heat from the drying gas. Higher drying gas temperature (350 °C) will lower the intensity of the precursor ion.

Therefore, in the negative ion mode, the drying gas temperature was set to 200 °C. Figure 3 shows the overlaid chromatograms of all 14 pesticides, each at 5 pg on column, from the negative ion mode MRM analysis.




Figure 2. Negative ion mode TIC of 14 pesticides.




Figure 3. Overlay of the MRM results from 14 pesticides in negative ion mode.

Table 3 shows the linearity results for 14 pesticides over the range of 5, 10, 50, 100, 200, 500, and 1,000 pg on column. The calibration model used was a linear model that included origin with no weighting. All analytes showed excellent linearity.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Table 3. Pesticide linearity: 5, 10, 50, 100, 200, 500, 1,000 pg on column

Pesticide	R ² (linear fit, include origin, no weighting)
Clopyralid	0.9976
Picloram	0.9993
Dicamba	0.9975
DCPA	0.9994
Bentazone	0.9975
2,4-D	0.9990
Bromoxynil	0.9999
MCPA	0.9980
Triclopyr	0.9990
2,4-DP	0.9948
2,4-DB	0.9887
MCPB	0.9847
Acifluorfen	0.9969
Dinoseb	0.9905

Conclusions

Using SPE and LC/MS/MS, 46 pesticides in positive ion mode and 14 pesticides in negative ion mode were analyzed at low pg level on column without any derivatization. Good linearity of responses was observed from 5 pg to 1 ng of analytes on column.

Reference

1. U.S. Geological Survey Water-Resources Investigations Report 01-4134, <http://nwql.usgs.gov/Public/pubs/WRIR01-4134.html>

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
July 25, 2006
5989-5320EN



Agilent Technologies



Determination of Pharmaceuticals in Water by SPE and LC/MS/MS in Both Positive and Negative Ion Modes

Application

Environmental

Authors

Chin-Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Stephen L. Werner and Edward T. Furlong
National Water Quality Laboratory
U.S. Geological Survey
PO Box 25046, MS 407, Building 95, Denver Federal Center
Denver, CO 80225
USA

Abstract

Using solid phase extraction (SPE) and liquid chromatography/tandem mass spectrometry (LC/MS/MS), 19 pharmaceuticals in positive ion mode and 11 pharmaceuticals in negative ion mode were analyzed at low picogram level on column without any derivatization. Good linearity was observed for analytes from 1 pg to 1 ng on column.

Repeatability from six injections of analytes at 5 pg on column showed RSDs below 15%, for all target compounds except for fluoxetine at 23%.

Introduction

Many articles in leading medical journals and newspapers reported sexual development and reproductive problems in animals and humans, for example, low sperm counts, genital deformities, male fish making eggs, and others. Scientists suggested that man-made chemicals (for example, pesticides and pharmaceuticals) are disrupting the endocrine system.

Compounds like antibiotics, over-the-counter medicines, and caffeine drain through the sewage system largely unaltered into rivers and streams, and even get into the drinking water supply in very small amounts. In order to monitor the trace pharmaceuticals in surface and ground water, an effective sample preparation and analysis method is required.

In 1999, the US Geological Survey National Water Quality Laboratory (NWQL) developed and implemented an OASIS HLB, solid-phase extraction (SPE), and a high-performance liquid chromatography (HPLC)-mass spectrometry (MS) method to analyze pharmaceuticals.

Using the Multiple Reaction Monitoring (MRM) technique, any interference and matrix signal from organic matters in the water can be minimized from the target compound signals for better confirmation and quantitation. In this application, SPE and LC/MS/MS methods are described to analyze 19 pharmaceuticals in positive ion mode and 11 pharmaceuticals in negative ion mode.



Agilent Technologies

Experimental

Sample Preparation Procedure

See Reference 1 for more information.

1. Filter water samples in the field or laboratory using 0.7- μ m glass fiber filters.
2. Pump 1 L of the filtered water sample, at a flow rate of 10 mL/min, through an Oasis HLB (SPE) cartridge containing 0.5 g of sorbent.
3. Elute the HLB column with 6 mL of methanol followed by 4 mL of 0.1% TFA (trifluoroacetic acid) in methanol.

Instrumentation

Positive Ion Mode

LC:	1200 LC	
Column:	ZORBAX Extend-C-18, RRHT, 2.1 mm $\times$ 100 mm, 1.8 μ m	
Column temperature:	40 $^{\circ}$ C	
Mobile phases:	A: 0.1% formic acid in water, add NH_4OH buffer to pH 5.5 B: Acetonitrile (ACN)	
Flow rate:	0.3 mL/min	
Gradient:	Time	%B
	0	0
	15	100
	20	100
	21.5	0
Injection volume:	1.0 μ L	
MS:	G6410A QQQ	
Ionization:	ESI-(+)	
Mass range:	125 to 800 amu	
Scan time:	300 ms	
Capillary:	3500 V	
Nebulizer P:	40 psi	
Drying gas:	9 L/min	
Gas temperature:	350 $^{\circ}$ C	
Skimmer:	35 V	

4. The resulting solvent extract is then concentrated to approximately 100 μ L.
5. Add internal standard (ISTD). The extract is reconstituted to 1 mL.

Calibration Standards

For positive ion mode, nine calibration solutions were prepared: 1, 5, 10, 20, 40, 100, 200, 400, and 1,000 pg/ μ L. For negative ion mode, six levels were used: 10, 20, 40, 80, 400, and 800 pg/ μ L.

Negative Ion Mode

LC:	1200 LC	
Column:	ZORBAX Extend-C-18, RRHT, 2.1 mm $\times$ 100 mm, 1.8 μ m	
Column temperature:	60 $^{\circ}$ C	
Mobile phases:	A: 0.04% Glacial acetic acid in water B: Acetonitrile (ACN)	
Flow rate:	0.3 mL/min	
Gradient:	Time	%B
	0	0
	1	40
	2	52
	3	70
	6	100
	13	100
	14	0
Injection volume:	1.0 μ L	
MS:	G6410A QQQ	
Ionization:	ESI (-)	
Mass range:	120–800 amu	
Scan time:	300 ms	
Capillary:	3500 V	
Nebulizer P:	40 psi	
Drying gas:	9 L/min	
Gas temperature:	200 $^{\circ}$ C	
Skimmer:	35 V	

The MRM parameters for positive ion mode and negative ion mode are listed in Tables 1 and 2, respectively.

Table 1. Positive Ion Mode MRM Method Parameters

Name	RT	MW	Precursor	Quant ion	Collision V	Dwell	Segment
Metformin HCl	0.856	129	130.4	71.5	15	300	1
Acetaminophen	4.591	151	152.3	110.3	18	30	2
Salbutamol	4.717	239	240.4	148.4	15	30	2
Cimetidine	4.815	252	253.4	94.9	17	30	2
1,7,-Dimethylxanthine	4.89	180	181.3	123.9	20	30	2
Cotinine	5.24	176	177.3	118.3	29	30	2
Codeine	5.321	299	300.4	164.9	30	30	2
Caffeine	5.493	194	195.3	137.9	22	30	2
Trimethoprim	5.935	290	291.4	122.8	25	30	2
Thiabendazole	7.194	201	202.3	131.3	35	100	3
Sulfamethoxazole	7.309	253	254.3	156.0	15	100	3
Azithromycin	7.326	749	375.5	157.9	16	100	3
Diphenhydramine	8.446	255	256.5	167.1	5	100	4
Diltiazem HCl	8.693	414	415.4	177.6	18	100	4
Carbamazepine	8.912	236	237.4	194.0	20	100	4
Fluoxetine HCl	9.71	309	310.4	148.5	0	100	5
Dehydronifedipine	10.635	344	345.4	283.9	27	100	5
Warfarin	11.152	308	309.4	163.3	15	100	5
Miconazole nitrate salt	12.865	416	417.2	159.3	30	300	6

Table 2. Negative Ion Mode MRM Method Parameters

Name	RT	MW	Precursor	Quant ion	Frag. V	Collision V	Dwell	Segment
Hydrochlorothiazide	3.42	297	296	269	140	20	70	1
Aspirin	3.49	180	179	122	120	15	70	1
Enalaprilat	3.71	348	347	114	120	10	70	1
Furosemide	4.51	330	329	285	140	15	70	1
Ketoprofen	5.17	254	253	209	80	5	70	2
Clofibric acid	5.20	214	213	127	80	10	70	2
Napoxen	5.20	230	229	170	80	10	70	2
Diclofenac sodium salt	5.84	294	294	250	100	10	100	3
Ibuprofen	6.03	206	205	161	80	0	100	3
Ibuprofen-d3	6.03	209	208	164	80	0	100	3
Gemfibrozil	6.49	250	249	121	120	25	150	4
Triclocarban	6.66	314	313	160	140	15	150	4

Results and Discussion

The total ion chromatogram (TIC) in negative ion mode is shown in Figure 1. The analysis time in negative ion mode is less than 7 minutes for the 11 analytes. Their peak widths are about 0.1 minute, using a 1.8- μm particle size column. The narrower peak width gives a higher signal-to-noise (s/n) ratio compared to a 3.5- μm or larger particle size column.




Figure 1. Negative ion mode TIC of 11 pharmaceuticals.

A few compounds, for example, ketoprofen (Figure 2), are sensitive to heat from the drying gas. Higher drying gas temperature (350 °C) lowers the intensity of the precursor ions. Therefore, in the negative ion mode, the drying gas temperature was set to 200 °C.




Figure 2. Higher drying gas temperature lowers precursor intensity for certain compounds.

In Figure 3, it was interesting to see that the fragment ion actually had a higher m/z value than the precursor ion. For azithromycin, the doubly charged ion showed higher intensity than the singly charged ion and was chosen as the precursor. Therefore, depending on the precursor chosen, it is sometimes necessary to set the upper mass of

the product ion scan to be higher than the precursor ion.

Figure 4 shows the overlaid chromatograms of 19 pharmaceuticals, each at 5 pg on column, from the positive ion mode MRM analysis.




Figure 3. Doubly charged precursor results in a fragment at higher m/z .




Figure 4. Overlaid MRM chromatograms of the 19 pharmaceuticals in positive ion mode.

Figure 5 shows the overlaid chromatograms of 10 pharmaceuticals, each at 10 pg on column, from the negative ion mode MRM analysis. In both Figures 4 and 5, the analysis times were relatively short and s/n ratios were high.




Figure 5. Overlay of MRM results from the 10 pharmaceuticals in negative ion mode.

Table 3 shows the linearity results of all 19 pharmaceuticals (ESI+) over the range of 1, 5, 10, 20, 40, 100, 200, 400, and 1,000 pg on column. Two calibration models were used: a linear model and a quadratic model that both included origin with no weighting. Some of the compounds showed significant fitting improvement from the linear model to the quadratic model. This is the nature of these compounds.

Table 3. Linearity: 1, 5, 10, 20, 40, 100, 200, 400, and 1,000 pg on Column (ESI+), Origin Included, No Weighting

Compound	R ² (linear fit)	R ² (quadratic fit)
Metformin HCl	0.9975	0.9999
1,7,-Dimethylxanthine	0.9998	0.9998
Acetaminophen	0.9852	0.9999
Caffeine	0.9992	0.9997
Cimetidine	0.9968	0.9998
Codeine	0.9989	0.9997
Cotinine	0.9971	0.9998
Salbutamol	0.9850	0.9994
Trimethoprim	0.9980	0.9999
Azithromycin	0.9633	0.9998
Sulfamethoxazole	0.9998	0.9999
Thiabendazole	0.9997	0.9998
Carbamazepine	0.9926	0.9999
Diltiazem HCl	0.9997	0.9997
Diphenhydramine	0.9975	0.9998
Dehydronifedipine	0.9985	0.9993
Fluoxetine HCl	0.9984	0.9997
Warfarin	0.9989	0.9997
Miconazole nitrate salt	0.9989	0.9995

Table 4 shows the repeatability results from six injections of 5 pg of each analyte on column. In general, the RSDs are below 15%, except for fluoxetine, which was at 23%.

Table 4. Repeatability from Six Injections at 5 pg/μL (5 pg on column), ESI(+)

Compound	%RSD
Metformin HCl	12.4
1,7,-Dimethylxanthine	8.6
Acetaminophen	6.1
Caffeine	5.7
Cimetidine	4.1
Codeine	16.2
Cotinine	10.5
Salbutamol	3.7
Trimethoprim	3.6
Azithromycin	9.4
Sulfamethoxazole	10.7
Thiabendazole	5.3
Carbamazepine	2.8
Diltiazem HCl	4.7
Diphenhydramine	3.7
Dehydronifedipine	5.4
Fluoxetine HCl	23.4
Warfarin	4.4
Miconazole nitrate salt	2.9

Table 5 shows the linearity results of all 11 pharmaceuticals (ESI-) over the range of 10, 20, 40, 80, 400, and 800 pg on column. All the R² values were above 0.99, except triclocarban, which was about 0.97.

Table 5. Linearity: 10, 20, 40, 80, 400, and 800 pg on Column (ESI-), Origin Included, No Weighting

Compound	R ² (linear fit)
Hydrochlorothiazide	0.9999
Aspirin	0.9977
Enalaprilat	0.9981
Furosemide	0.9997
Ketoprofen	0.9988
Clofibric acid	0.9997
Naproxen	0.9994
Diclofenac Na salt	0.9993
Ibuprofen	0.9997
Ibuprofen-d3	0.9998
Gemfibrozil	0.9993
Triclocarban	0.9655

Once the method is established, one can screen and quantitate target analytes in water. Figures 6, 7, and 8 are MRM analyses of actual water sample extracts in positive and negative ion modes.




Figure 6. Pharmaceuticals screening in positive ion mode.




Figure 7. Pharmaceuticals screening in negative ion mode.




Figure 8. Pharmaceuticals screening in negative ion mode.

Figure 6 shows several of the pharmaceuticals, for example, diphenhydramine and acetaminophen, that were common to several of the water samples. Some of the antibiotics were also found in the samples. Interestingly enough, in Figures 7 and 8, the most common pharmaceuticals in the water samples were related to high blood pressure and cholesterol medications.

Conclusion

Using SPE and LC/MS/MS, 19 pharmaceuticals in positive ion mode and 11 pharmaceuticals in negative ion mode were analyzed at low picogram level on column without any derivatization. Good linearity was observed for analytes from 1 pg to 1 ng on column.

Repeatability study from six injections of target analytes at 5 pg on column showed RSDs below 15%, except for fluoxetine at 23%.

This method was applied to water sample extracts, finding that several target pharmaceutical drugs were commonly found among the analyzed samples.

Reference

1. USGS SOP: Instrumental Analysis for Determination of Human Health Pharmaceuticals in Water by Chemically Modified Styrene-Divinylbenzene Resin-Based Solid-Phase Extraction and High-Performance Liquid Chromatography/Mass Spectrometry, by Steve Werner, 2006.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
July 25, 2006
5989-5319EN



Agilent Technologies



Screening for 926 Pesticides and Endocrine Disruptors by GC/MS with Deconvolution Reporting Software and a New Pesticide Library

Application Note

Food and Environmental

Authors

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Rd.
Wilmington, DE 19808-1610
USA

Abstract

An updated and greatly expanded collection of mass spectral libraries has been introduced, replacing Agilent's RTL Pesticide Library and DRS pesticide solution. The new library contains 926 pesticides, endocrine disruptors, and related compounds – 359 more than the original library. Included are all compounds specified for GC/MS analysis in the new Japanese "Positive List" regulations. All compounds have locked retention times that can be accurately reproduced using an Agilent GC/MS system with the ChemStation's Retention Time Locking software. The new Database can be used as a standard GC/MS library for compound identification or with Agilent's Screener software for identifications based upon retention time and mass spectral matching. The greatest benefit accrues when these libraries are used with Agilent's new version of Deconvolution Reporting Software (part number G1716AA version A.03.00). This solution allows one to screen GC/MS files for all 926 pesticides and

endocrine disruptors in about two minutes per sample. Deconvolution helps identify pesticides that are buried in the chromatogram by co-extracted materials. The new database was compared to the smaller one for the DRS analysis of 17 surface water samples. With the new database, DRS found 99 pesticides, metabolites, fire retardants, and related contaminants that were not contained in the original RTL Pesticide and Endocrine Disruptor Library.

Introduction

Several years ago Agilent Technologies introduced Retention Time Locking (RTL) for gas chromatography (GC) and GC with mass spectral detection (GC/MS). RTL software makes it possible to reproduce retention times from run-to-run on any Agilent GC or GC/MS, in any laboratory in the world, so long as the same nominal method and GC column are used (1). Since any laboratory can reproduce retention times generated in another, it is possible to create mass spectral libraries that contain locked retention times. By locking their method to the published database, users can screen GC/MS files for all of the library's compounds. "Hits" are required to have the correct retention time as well as the correct spectrum, which eliminates many false positives and gives more confidence in compound identifications (2).



Agilent Technologies

More recently, Agilent introduced Deconvolution Reporting Software (DRS) that incorporates mass spectral deconvolution with conventional library searching and quantification. DRS results from a marriage of three different GC/MS software packages:

- 1) The Agilent GC/MS ChemStation,
- 2) The National Institute of Standards and Technology (NIST) Mass Spectral Search Program with the NIST '05 MS Library, and
- 3) The Automated Mass Spectral Deconvolution and Identification System (AMDIS) software, also from NIST.

The original DRS software was intended to be a comprehensive solution for pesticide analysis and, therefore, included the mass spectra (in AMDIS format) and locked retention times for 567 pesticides and suspected endocrine disruptors (3).

Recently, Agilent introduced an updated and greatly expanded Pesticide and Endocrine Disruptor Database (part number G1672AA) that now contains 926 entries. This represents the addition of 359 new compounds to the original library. At the same time, Agilent introduced a new version of the DRS software (part number G1716AA version A.03.00) that can be used with any Agilent-provided or user-developed DRS library.

Pesticide and Endocrine Disruptor Database Contents

The G1672AA Pesticide and Endocrine Disruptor Database contains virtually all GC-able pesticides, including those introduced very recently. In addition, the database includes numerous metabolites, more endocrine disruptors, important PCBs and PAHs, certain dyes (for example, Sudan Red), synthetic musk compounds, and several organophosphorus fire retardants.

This new database includes:

- A conventional mass spectral library for use with Agilent GC/MS ChemStations

- A screener database for use with Agilent's powerful screener software that is integrated into the GC/MS ChemStation
- Locked Retention Times for all 926 compounds that any Agilent 5975 or 5973 GC/MS user can reproduce in their laboratory
- Files for use with Agilent's G1716AA (A.03.00) Deconvolution Reporting Software
- An e-method that can be loaded into Agilent's G1701DA (version D.02.00 SP1 or higher) with instrument parameters for acquiring GC/MS files and analyzing the data with DRS. These parameters are listed in Table 1.
- Example files
- Application notes

On November 29, 2005, the Japanese Government published a "Positive List" system for the regulation of pesticides, feed additives, and veterinary drugs. Maximum Residue Limits (MRL) have been set for 758 chemicals while 65 others have been exempted from regulation. Fifteen substances must have no detectable residues. Other agricultural chemicals not mentioned have a uniform MRL of 0.01 ppm (4). This new regulation is scheduled to take effect on May 29, 2006.

Of the pesticides in the Japanese Positive List, 265 are to be analyzed by GC/MS. The new G1672AA Pesticide library contains mass spectra and locked retention times for all of these compounds. Thus, a laboratory could screen for all 265 "positive list" compounds and several hundred more pesticides in just 1–3 minutes after the GC/MS run.

Experimental

Table 1 lists the instrumentation, software, and analytical parameters used by Agilent for pesticide analysis. Depending upon the desired injection volume, a PTV inlet or split/splitless inlet can be used.

Table 1. Instrumentation and Conditions of Analysis

Gas Chromatograph	Agilent 6890N
Automatic Sampler	Agilent 7683 Injector and AutoSampler
Inlet	Agilent PTV operated in the solvent vent mode or Split/Splitless
Column	Agilent 30 m × 0.25 mm × 0.25 µm HP-5MSi (part number 19091S-433i)
Carrier gas	Helium in the constant pressure mode
Retention time locking	Chlorpyrifos-methyl locked to 16.596 min (nominal column head pressure = 17.1 psi)
Oven temperature program	70 °C (2 min), 25 °C/min to 150 °C (0 min), 3 °C /min to 200 °C (0 min), 8 °C /min to 280 °C (10–15 min)
PTV inlet parameters	Temp program: 40 °C (0.25 min), 1600 °C/min to 250 °C (2 min); Vent time: 0.2 min; Vent flow: 200 mL/min; Vent pressure: 0.0 psi; Purge flow: 60.0 mL/min; Purge time: 2.00 min
Injection volume	15 µL (using a 50-µL syringe)
Mass Selective Detector	Agilent 5975 inert
Tune file	Atune.u
Mode	Scan (or SIM with SIM DRS library)
Scan range	50–550 u
Source, quad, transfer line temperatures	230, 150, and 280 °C, respectively
Solvent delay	4.00 min
Multiplier voltage	Autotune voltage
Software	
GC/MSD ChemStation	Agilent part number G1701DA (version D02.00 sp1 or higher)
Deconvolution Reporting Software	Agilent part number G1716AA (version A.03.00) Deconvolution Reporting Software
Library searching software	NIST MS Search (version 2.0d or greater) (comes with NIST '05 mass spectral library – Agilent part number G1033A)
Deconvolution software	Automated Mass Spectral Deconvolution and Identification Software (AMDIS_32 version 2.62 or greater; comes with NIST '05 mass spectral library – Agilent part number G1033A)
MS Libraries	NIST '05 mass spectral library (Agilent part number G1033A) Agilent RTL Pesticide and Endocrine Disruptor Libraries in Agilent and NIST formats (part number G1672AA)

Results and Discussion

DRS, which has been described in preceding papers (3,5,6), can be summarized as follows:

Three separate, but complimentary, data analysis steps are combined into the DRS. First, the GC/MS ChemStation software performs a normal quantitative analysis for target pesticides using a target ion and up to three qualifiers. An amount is reported for all calibrated compounds that are detected. For other compounds in the database, an estimate of their concentration can be reported based upon an average pesticide response factor

that is supplied with the DRS software. The DRS then sends the data file to AMDIS, which deconvolutes the spectra and searches the Agilent RTL Pesticide Library using the deconvoluted full spectra. A filter can be set in AMDIS, which requires the analyte's retention time to fall within a user-specified time window. Because RTL is used to reproduce the RTL database retention times with high precision, this window can be quite small – typically 10–20 seconds. Finally, the deconvoluted spectra for all of the targets found by AMDIS are searched against the 147,000-compound NIST mass spectral library for confirmation; for this step, there is no retention time requirement.

This approach was rapidly adopted by many laboratories because of its ability to identify pesticides in complex chromatograms containing high levels of co-extracted interferences. Indeed, the solution proved to be so useful that users began to create their own DRS libraries (7). Therefore, the DRS was unbundled from the pesticide database so that it could be used with any agilent-provided or user-created database.

The original 567-compound RTL Pesticide Library (G1049A) included pesticides, a few metabolites, and most of the GC-amenable endocrine disruptors that were known at the time. The new version of the library includes many more pesticides, endocrine disruptors, and metabolites. This update also contains important compounds from other classes of contaminants that have been found in food and water supplies. Included are eighteen polychlorinated biphenyls (PCBs), four polybrominated biphenyls (PBBs), several polynuclear aromatic hydrocarbons (PAHs), several organophosphorus fire retardants, three important toxaphene congeners, and three Sudan dyes.

Advantages of Deconvolution

Figure 1 shows a screen from AMDIS that illustrates the power of this deconvolution software. The white trace in Figure 1A is the total ion chromatogram while the other three are extracted ions of a deconvoluted peak (a “component” in AMDIS terminology). Note that the TIC and extracted ions are not scaled to each other and this component is actually obscured by co-eluting compounds. Figure 1B juxtaposes the deconvoluted component spectrum (white) with the complete “undeconvoluted” spectrum (black). Clearly, this component is buried under co-eluting peaks that would ordinarily obscure the analyte. Figure 1C shows that the deconvoluted peak (white spectrum) is a good library match for norflurazon (black spectrum). The locked retention time for norflurazon in the RTL Pesticide Database is 26.933 min, which is just 2.3 seconds away from its observed RT in this chromatogram. Confidence in peak identifications is greatly enhanced by the combination of spectral deconvolution and locked retention time filtering.




Figure 1. AMDIS screen showing the identification of norflurazon.

- A) The total ion and extracted ion chromatograms where norflurazon elutes.
- B) The deconvoluted component spectrum (white) juxtaposed with the spectrum at 26.972 min (black).
- C) The deconvoluted component matched to the library spectrum of norflurazon.

Surface Water Analysis - Revisiting an Earlier Study

In an earlier study, a comparison was made between Agilent's DRS and conventional pesticide analysis (3). The California Department of Food and Agriculture (CDFA) provided data files for 17 surface water extracts that had been analyzed in their laboratory. Since the GC/MS chromatograms were locked to the Agilent pesticide method, it was possible to analyze these data files using DRS without having to re-run the samples. The original DRS analysis was made using the 567-compound RTL Pesticide Database. For comparison, these same data files were re-analyzed using the new 926-compound RTL Pesticide Database. The chromatogram (Figure 2) and the DRS report (Figure 3) from one of these samples are shown below.

Excluding phthalates, seven new compounds (shown with bold type in Figure 3) were identified using the 926-compound database: 4-chlorophenyl isocyanate (a phenylurea herbicide metabolite); 3,4-dichlorophenyl isocyanate (diuron metabolite); tris(2-chloroethyl) phosphate (a fire retardant); caffeine (a stimulant); Cyprodinil (a fungicide); desmethyl-norflurazon (a metabolite of norflurazon, an herbicide); and tris(2-butoxyethyl) phosphate (a fire retardant). Although caffeine is not generally considered to be dangerous, it is included in the database because it has been found frequently in sewage effluent and in numerous waterways together with a various pharmaceuticals and pesticides (8).




Figure 2. Chromatogram of a surface water extract that was analyzed by DRS using the new RTL Pesticide and Endocrine Disrupter Database. The results of this analysis are shown in Figure 3.

MSD Deconvolution Report

Sample Name: E02-557

Data File: C:\MSDCHEM\1\DATA\CDFA surface water data\E02-557.d

Date/Time: 11:24 AM Tuesday, Apr 4 2006

The NIST library was searched for the components that were found in the AMDIS target library.

RT	Cas #	Compound name	Agilent ChemStation amount (ng)	AMDIS match	RT Diff (sec.)	NIST reverse match	Hit number
4.4689	106445	4-Methylphenol		62	3.2		
4.4689	0000	3-Carbobenzyloxy-4-ketoproline				48	1
4.8840	104121	4-Chlorophenyl isocyanate		84	-1.8	86	2
6.3879	102363	Diuron Metabolite [3,4-Dichlorophenyl isocyanate]		99	3.1	95	1
6.8357	759944	EPTC		84	2.0	85	1
7.6988	95761	3,4-Dichloroaniline		93	2.1	89	2
7.9342	131113	Dimethylphthalate		67	1.7	84	2
8.1112	25013165	Butylated hydroxyanisole		63	-7.7		
8.1112	0000	7-Methoxy-2,2,4,8-tetramethyltricyclo [5.3.1.0(4,11)]undecane				62	1
8.941	29878317	Tolyltriazole [1H-Benzotriazole, 4-meth-]	1.29				
9.7903	134623	N,N-Diethyl-m-toluamide		85	2.2	84	2
10.0019	84662	Diethyl phthalate		98	2.6	92	1
10.7109	119619	Benzophenone		86	2.6	88	2
10.9684	126738	Tributyl phosphate		96	3.0	90	1
11.6491	1582098	Trifluralin		83	0.7	74	1
12.9326	122349	Simazine		88	1.4	86	2
13.4309	115968	Tris(2-chloroethyl) phosphate		79	1.0	78	1
13.7478	1517222	Phenanthrene-d10		95	1.3	83	1
15.4048	58082	Caffeine		80	1.6	74	1
15.9474	84695	Diisobutyl phthalate		90	3.2	88	4
16.5988	5598130	Chlorpyrifos Methyl		97	0.4	90	1
17.3653	7287196	Prometryn		90	1.5	84	1
18.4213	84742	Di-n-butylphthalate		99	0.4	94	1
18.9214	51218452	Metolachlor		90	0.7	87	1
20.5633	121552612	Cyprodinil		69	-0.1		
20.5633	76470252	9,9-Dimethoxy-9-sila-9, 10-dihydroanthracene				70	1
26.4247	23576241	Norflurazon, Desmethyl-		87	-4.5	69	2
26.9700	27314132	Norflurazon		87	1.5	79	1
26.9992	85687	Butyl benzyl phthalate		94	-0.5	94	1
27.3984	51235042	Hexazinone		89	0.8	83	1
28.0127	78513	Tris(2-butoxyethyl) phosphate		75	3.3	83	1
29.6537	117817	Bis(2-ethylhexyl)phthalate		98	0.3	90	3
33.9298	84764	Di-n-nonyl phthalate		65	-1.9		
33.9298	0000	Phthalic acid, 3,4-dichlorophenyl propyl ester				71	1
13.739		Phenanthrene-d10	10				

Figure 3. DRS report from the analysis of a surface water sample. The compounds shown in bold type were found by the new RTL Pesticide Database but not the original one because these compounds were not included.

For this sample, the ChemStation identified only tolyltriazole at 8.941 min, but AMDIS did not confirm this assignment, nor could it be confirmed manually. Butylated hydroxyanisole was tentatively identified by AMDIS with a low match value, but the retention time is off by -7.7 seconds which is considerably more than most other hits. This compound is not in the NIST library so it could not be confirmed. The ChemStation method used for this analysis required that all three qualifier ions fall within $\pm 20\%$ (relative) which is a rigorous requirement for such a complex sample. This explains why so few compounds were found by the ChemStation.

Cyprodinil (20.563 min) was identified by AMDIS but the NIST library search failed to confirm its presence. The next line shows that the best NIST library match is an anthracene derivative that is nothing like cyprodinil. This result was obtained when AMDIS was configured to “use uncertain peaks” as shown in Figure 4. When this feature is

turned off in DRS Compound Identification Configuration, the best NIST library hit for this spectrum is, indeed, cyprodinil. When a compound's identity is ambiguous, as with cyprodinil, it may be useful to perform the DRS search both ways and compare the results.

In the comparison described earlier (3), DRS was able to identify all 37 pesticides found by the CDFA chemist. However, DRS completed the task for all 17 samples in about 20 minutes compared to ~8 hours for the manual procedure (Table 2). Moreover, DRS identified one false positive in the CDFA report and found 34 additional pesticides and related compounds.

Using the new 926-compound Database, it took 32 minutes to analyze all of the samples and DRS was able to find an additional 99 pesticides, metabolites, fire retardants, and related compounds (Table 2).




Figure 4. DRS configuration screen for the method called **Tri_Pest**. When the box labeled “Use Uncertain Peaks” is checked, AMDIS will use uncertain peaks for library searches. When unchecked, AMDIS ignores uncertain mass spectral peaks. Sometimes, this can affect the quality of a library match.

Table 2. Comparison of the Results Obtained by Screening 17 Surface Water Extracts Using Traditional Methods (CDFA) and Using DRS With Two Different Databases – the G1049A With 567 Compounds and the G1672AA With 926 Entries

	CDFA	Agilent DRS (Original G1049A database)	Agilent DRS (G1672 AA database)
Targets found (not counting ISTD)	37	Same 37 +34 more	Same 37 +99 more
False positives	1	0	0
Processing time	~8 hrs (ChemStation only)	20 minutes	32 min

Handling Stereoisomers

Many pesticides have multiple stereoisomers with virtually identical mass spectra. For example, cyfluthrin has four diastereomers arising from its three chiral centers. It is very difficult and sometimes impossible to determine the elution order of these isomers and most analysts report them as a sum of the isomer amounts. Agilent's G1049A RTL Pesticide database arbitrarily assigned each isomer a Roman numeral with I for the earliest eluting isomer, II for the next, and so on. The same Chemical Abstracts Service number (CAS #) was assigned to all of the isomers. Generally, it was a CAS # for the compound with "unstated stereochemistry." This caused some incompatibility with AMDIS as explained below.

AMDIS software differentiates among compounds using a "chemical identification number." The easiest and most consistent approach is to use each compound's CAS #. The default setting for AMDIS is to allow each CAS # to be used only once when analyzing a GC/MS data file. While this seems logical, it requires that each database entry have a different CAS #. It is possible to allow multiple hits per compound by checking the box in AMDIS found in the drop down menu under Analyze/Settings/Identif. However, this allows multiple peaks to be assigned the same compound name.

In the new RTL Pesticide Database (G1672AA), the Roman numeral designations remain and the first isomer in the series is given its genuine CAS #. Subsequent isomers in the series are given unique, but fictitious "CAS #s" generated by Agilent. The compound's real CAS # appears in braces after the compound name. For example, the cyfluthrin isomers are entered into the database as shown in Table 3.

Table 3. Method for Listing Compounds with Multiple Stereoisomers in the New G1672AA RTL Pesticide Database

RT	Compound name*	CAS #**
32.218	Cyfluthrin I	68359-37-5
32.359	Cyfluthrin II {CAS # 68359-37-5}	999028-03-4
32.477	Cyfluthrin III {CAS # 68359-37-5}	999029-03-7
32.536	Cyfluthrin IV {CAS # 68359-37-5}	999030-03-4

* In a series, the earliest eluting isomer is identified with "I" and is assigned its legitimate CAS #. Subsequent isomers are assigned unique, but fictitious CAS #s (see footnote **). Their actual CAS # is put in braces behind the compound name.

** Cyfluthrin I has been given its genuine CAS #. Cyfluthrin II-IV have been given unique numbers that can be distinguished from actual CAS numbers because they all have six digits before the first hyphen (9 total) and all begin with the series 999.

Figure 5 shows how permethrin was identified in a spinach sample using both databases with AMDIS configured to allow one hit per compound. Using the older 567-compound database (G1049A) only one permethrin isomer was identified because its CAS # could be used only once. With the new format used in the 926-compound RTL Pesticide Database (G1672AA), both isomers of permethrin were identified. Not surprisingly, the NIST library search found no hits with the same fictitious CAS # assigned to permethrin II. So, the software printed the best match on the following line. This compound, a cyclopropanecarboxylic acid derivative, is a permethrin isomer.

So long as the NIST library search is turned on in DRS, it will always print another line after reporting a compound with a fictitious CAS #. Note that these fictitious CAS #s always contain 9 digits and begin with 999.

A)

RT	Cas #	Compound name	Agilent	AMDIS match	RT Diff (sec.)	NIST	Hit number
			ChemStation amount (ng)			reverse match	
31.6158	52645531	Permethrin II		88	3.9	91	3

B)

RT	Cas #	Compound name	Agilent	AMDIS match	RT Diff (sec.)	NIST	Hit number
			ChemStation amount (ng)			reverse match	
31.4127	52645531	Permethrin I		78	2.6	81	3
31.6088	999046036	Permethrin II {CAS # 52645-53-1}		65	3.5		
31.6088	51877748	Cyclopropanecarboxylic acid, 3-(2,2-dichlorovinyl)-2,2-dimethyl-, (3-phenoxyphenyl)methyl ester, (1R-trans)-				95	1

Figure 5. A) A single isomer of permethrin was identified by DRS using the G1049A 567-compound database when AMDIS was not allowed to use multiple hits per compound. B) Two permethrin isomers are identified by DRS with the G1672AA 926-compound database under the same circumstances.

Conclusions

The new G1672AA RTL Pesticide and Endocrine Disruptor library contains substantially more target analytes than its predecessor. With the addition of 359 new compounds, it is the most comprehensive library of its type available today. Many new pesticides, metabolites, and endocrine disruptors were added along with important PCBs, PBBs, PAHs, synthetic musk compounds, Sudan dyes, and organophosphorus fire retardants. The database contains all of the analytes specified for GC/MS analysis in the new Japanese “Positive List” regulations.

When combined with the complete DRS solution, one can screen GC/MS data files for all 926 compounds in about two minutes per sample. This is the fastest, most comprehensive, most accurate, and least tedious method for screening food and environmental samples for these compounds.

References

1. V. Giarocco, B. Quimby, and M. Klee, “Retention Time Locking: Concepts and Applications,” Agilent Technologies, publication 5966-2469E, www.agilent.com/chem
2. H. Prest, P. Wylie, K. Weiner, and D. Agnew, “Efficient Screening for Pesticides and Endocrine Disruptors Using the 6890/5973 GC/MSD System,” Agilent Technologies, publication 5968-4884E, www.agilent.com/chem
3. P. L. Wylie, M. J. Szelewski, C.-K. Meng, C. P. Sandy, “Comprehensive Pesticide Screening by GC/MSD using Deconvolution Reporting Software,” Agilent Technologies, publication 5989-1157EN, www.agilent.com/chem
4. “Introduction of the Positive List System for Agricultural Chemical Residues in Foods Department of Food Safety, Ministry of Health, Labour and Welfare” <http://www.mhlw.go.jp/english/topics/food-safety/positivelist060228/introduction.html>
5. C. P. Sandy, “A Blind Study of Pesticide Residues in Spiked and Unspiked Fruit Extracts using Deconvolution Reporting Software,” Agilent Technologies, publication 5989-1564EN, www.agilent.com/chem
6. C. Lesueur and M. Gartner, “Routine Identification and Quantification of Pesticide Multi-residues in Fruit and Vegetable Samples with Full Scan, SIM, and Deconvolution Reporting Software,” 2005 *Ernährung/Nutrition*, **29** (11) 466–471
7. X. Ping, C.-K. Meng, and M. Szelewski, “Building Agilent GC/MSD Deconvolution Reporting Libraries for any Application,” Agilent Technologies, publication 5989-2249EN, www.agilent.com/chem
8. “Large-scale studies of the occurrence and distribution of new contaminants in the environment – Reconnaissance studies,” *USGS, Contaminant Occurrence Studies*, http://toxics.usgs.gov/topics/reconnaissance_studies.html

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Acknowledgments

The author wishes to thank Dr. G. Kempe of the Landesuntersuchungsanstalt Sachsen, Institut, Chemnitz, Germany for his help in acquiring much of the data for this library update. The author also thanks Dr. Mark Lee and Mr. Steve Siegel of the California Department of Food and Agriculture for providing the surface water extract data files.

Appendix A

Lists of Compounds in Databases

1,2,4-Trichlorobenzene	2,6-Dimethylaniline	Acetochlor
1,2-Dibromo-3-chloropropane	2-[3-Chlorophenoxy]propionamide	Acifluorfen methyl ester
1,3,5-Tribromobenzene	2-Chlorophenol	Aclonifen
1,3-Dichlorobenzene	2-Ethyl-1,3-hexanediol	Acrinathrin
17 α -Ethinylestradiol	2-ethyl-6-methylaniline	Alachlor
1-naphthalenol	2-Hydroxyestradiol	Aldrin
2-(1-naphthyl)acetamide	2-Methyl-4,6-dinitrophenol	Allidochlor
2-(2-Butoxyethoxy)ethyl thiocyanate	2-Methylphenol	Ametryn
2-(Octylthio)ethanol	2-Nitrophenol	Amidithion
2,3,4,5-Tetrachloronitrobenzene	2-Phenoxypropionic acid	Aminocarb
2,3,4,5-Tetrachlorophenol	3,4,5-Trimethacarb	Amitraz
2,3,4,6-Tetrachlorophenol	3,4-Dichloroaniline	Amitraz metabolite [Methanimidamide, N-(2,4-dimethylphenyl)-N'-methyl-]
2,3,5,6-Tetrachlorophenol	3,5-Dichloroaniline	Ancymidol
2,3,5,6-Tetrachloro-p-terphenyl	3-Aminophenol	Anilazine
2,3,5-Trichlorophenol	3-Chloro-4-fluoroaniline	Aniline
2,3,5-Trimethacarb	3-Chloro-4-methoxyaniline	Anilofos
2,3,6-Trichloroanisole	3-Chloroaniline	Anthracene
2,3,7,8-Tetrachlorodibenzofuran	3-Hydroxycarbofuran	Aramite I
2,3,7,8-Tetrachlorodibenzo-p-dioxin	3-Indolylacetoneitrile	Aramite II {CAS # 140-57-8}
2,4,5,6-Tetrachloro-m-xylene	3-Trifluormethylaniline	Atraton
2,4,5-T methyl ester	4,4'-Dichlorobenzophenone	Atrazine
2,4,5-Trichloroaniline	4,4'-Oxydianiline	Atrazine-desethyl
2,4,5-Trichlorophenol	4,6-Dinitro-o-cresol (DNOC)	Azaconazole
2,4,5-Trichloro-p-terphenyl	4-Aminodiphenyl	Azamethiphos
2,4,5-Trimethylaniline	4-Bromoaniline	Azibenzolar-S-methyl
2,4,6-Tribromoanisole	4-Chloro-2-methylaniline	Azinphos-ethyl
2,4,6-Tribromophenol	4-Chloro-3-methylphenol	Azinphos-methyl
2,4,6-Trichloroanisole	4-Chloroaniline	Aziprotryn metabolite [2-Amino-4-isopropylamino-6-methylthio-1,3,5-triazine]
2,4,6-Trichlorophenol	4-Chlorophenyl isocyanate	Aziprotryne
2,4-D methyl ester	4-Isopropylaniline	Azobenzene
2,4-D sec-butyl ester	4-Methylphenol	Azoxybenzene
2,4-DB methyl ester	4-Nitrophenol	Azoxystrobin
2,4'-Dichlorobenzophenone (2,4'-Dicofol decomposition product)	4-Nonylphenol	Barban
2,4-Dichlorophenol	5,7-Dihydroxy-4'-methoxyisoflavone	Beflubutamid
2,4-Dichlorophenyl benzenesulfonate	9,10-Anthraquinone	Benalaxyl
2,4-Dimethylaniline	Acenaphthene	Benazolin-ethyl
2,4-Dimethylphenol	Acenaphthylene	Bendiocarb
2,6-Dichlorobenzamide	Acephate	Benfluralin
2,6-Dichlorobenzonitrile	Acequinocyl	
	acetamiprid	

Benfuracarb	Bromophos-ethyl	Chlordimeform
Benfuresate	Bromopropylate	Chlorethoxyfos
Benodanil	Bromoxynil	Chlorfenapyr
Benoxacor	Bromoxynil octanoic acid ester	Chlorfenethol
Bentazone	Bromuconazole I	Chlorfenprop-methyl
Bentazone methyl derivative	Bromuconazole II {CAS # 116255-48-2}	Chlorfenson
Benthiocarb	Bufencarb	Chlorfenvinphos
Benzene, 1,3- <i>bis</i> (bromomethyl)-	Bupirimate	Chlorfenvinphos, <i>cis</i> -
Benzenesulfonamide	Buprofezin	Chlorfenvinphos, <i>trans</i> -
Benzidine	Butachlor	Chlorflurecol-methyl ester
Benzo(a)anthracene	Butafenacil	Chlormefos
Benzo(a)pyrene	Butamifos	Chlornitrofen
Benzo[b]fluoranthene	Butoxycarboxim	Chlorobenzilate
Benzo[g,h,i]perylene	Butralin	Chloroneb
Benzo[k]fluoranthene	Butyl benzyl phthalate	Chloropropylate
Benzophenone	Butylate	Chlorothalonil
Benzoximate metabolite	Butylated hydroxyanisole	Chlorotoluron
Benzoylprop ethyl	Cadusafos	Chlorpropham
Benzyl benzoate	Cafenstrole	Chlorpyrifos
b-Estradiol	Caffeine	Chlorpyrifos Methyl
BHC alpha isomer	Captafol	Chlorthal-dimethyl
BHC beta isomer	Captan	Chlorthiamid
BHC delta isomer	Carbaryl	Chlorthion
BHC epsilon isomer	Carbetamide	Chlorthiophos
Bifenazate metabolite (5-Phenyl-o-anisidine)	Carbofuran	Chlorthiophos sulfone
Bifenox	Carbofuran-3-keto	Chlorthiophos sulfoxide
Bifenthrin	Carbofuran-7-phenol	Chlozolate
Binapacryl	Carbophenothion	Chrysene
Bioallethrin	Carbosulfan	Cinerin I
Bioallethrin S-cyclopentenyl isomer	Carboxin	Cinerin II
Bioresmethrin	Carfentrazone-ethyl	Cinidon-ethyl
Biphenyl	Carpropamid	cis-Chlordane
<i>Bis</i> (2,3,3,3-tetrachloropropyl) ether	Carvone	Clodinafop-propargyl
<i>Bis</i> (2-butoxyethyl) phthalate	Cashmeran	Clomazone
<i>Bis</i> (2-ethylhexyl)phthalate	Cekafix	Cloquintocet-mexyl
Bisphenol A	Celestolide	Coumaphos
Bitertanol I	Chinomethionat	Crimidine
Bitertanol II {CAS # 55179-31-2}	Chloramben methyl ester	Crotoxyphos
Boscalid (Nicobifen)	Chloranocryl	Crufomate
Bromacil	Chlorbenside	Cyanazine
Bromfenvinphos-(E)	Chlorbenside sulfone	Cyanofenphos
Bromfenvinphos-(Z)	Chlorbicyclen	Cyanophos
Bromobutide	Chlorbromuron	Cyclafuramid
Bromocyclen	Chlorbufam	Cycloate
Bromophos	Chlordecone	Cyclopentadecanone
	Chlordene, <i>trans</i> -	Cycluron

Cyflufenamid	Dichlofluanid metabolite (DMSA)	Dinocap I
Cyfluthrin I	Dichlone	Dinocap II {CAS # 39300-45-3}
Cyfluthrin II {CAS # 68359-37-5}	Dichlormid	Dinocap III {CAS # 39300-45-3}
Cyfluthrin III {CAS # 68359-37-5}	Dichlorophen	Dinocap IV {CAS # 39300-45-3}
Cyfluthrin IV {CAS # 68359-37-5}	Dichlorprop	Di-n-octyl phthalate
Cyhalofop-butyl	Dichlorprop methyl ester	Dinoseb
Cyhalothrin I (lambda)	Dichlorvos	Dinoseb acetate
Cyhalothrin (Gamma)	Diclobutrazol	Dinoseb methyl ether
Cymiazole	Diclocymet I	Dinoterb
Cymoxanil	Diclocymet II {CAS # 139920-32-4}	Dinoterb acetate
Cypermethrin I	Diclofop methyl	Di-n-propyl phthalate
Cypermethrin II {CAS # 52315-07-8}	Dicloran	Diofenolan I
Cypermethrin III {CAS # 52315-07-8}	Dicrotophos	Diofenolan II {CAS # 63837-33-2}
Cypermethrin IV {CAS # 52315-07-8}	Dicyclohexyl phthalate	Dioxabenzofos
Cyphenothrin <i>cis</i> -	Dicyclopentadiene	Dioxacarb
Cyphenothrin <i>trans</i> - {CAS # 39515-40-7}	Dieldrin	Dioxathion
Cyprazine	Diethyl ethyl	Diphacinone
Cyproconazole	Diethofencarb	Diphenamid
Cyprodinil	Diethyl dithiobis(thionoformate) (EXD)	Diphenyl phthalate
Cyprofuram	Diethyl phthalate	Diphenylamine
Cyromazine	Diethylene glycol	Dipropetryn
d-(<i>cis-trans</i>)-Phenothrin-I	Diethylstilbestrol	Dipropyl isocinchomeronate
d-(<i>cis-trans</i>)-Phenothrin-II {CAS # 260002-80-2}	Difenoconazol I	Disulfoton
Dazomet	Difenoconazol II {CAS # 119446-68-3}	Disulfoton sulfone
DDMU [1-Chloro-2,2-bis(4'-chlorophenyl)]	Difenoxuron	Ditalimfos
Decachlorobiphenyl	Diflufenican	Dithiopyr
Deltamethrin	Diisobutyl phthalate	Diuron
Demephion	Dimefox	Diuron Metabolite [3,4-Dichlorophenyl isocyanate]
Demeton-S	Dimepiperate	Dodemorph I
Demeton-S-methylsulfon	Dimethachlor	Dodemorph II {CAS # 1593-77-7}
Desbromo-bromobutide	Dimethametryn	Drazoxolon
Desmedipham	Dimethenamid	Edifenphos
Desmetryn	Dimethipin	Empenthrin I
Dialifos	Dimethoate	Empenthrin II {CAS # 54406-48-3}
Di-allate I	Dimethomorph-(E)	Empenthrin III {CAS # 54406-48-3}
Di-allate II {CAS # 2303-16-4}	Dimethomorph-(Z) {CAS # 110488-70-5}	Empenthrin IV {CAS # 54406-48-3}
Diamyl phthalate	Dimethylphthalate	Empenthrin V {CAS # 54406-48-3}
Diazinon	Dimethylvinphos(z)	Endosulfan (alpha isomer)
Diazinon-oxon	Dimetilan	Endosulfan (beta isomer)
Dibenz[a,h]anthracene	Dimoxystrobin	Endosulfan ether
Dicamba	Di-n-butylphthalate	Endosulfan lactone
Dicamba methyl ester	Di-n-hexyl phthalate	Endosulfan sulfate
Dicapthon	Diniconazole	Endrin
Dichlofenthion	Dinitramine	Endrin aldehyde
Dichlofluanid	Di-n-nonyl phthalate	Endrin ketone
	Dinobuton	

EPN	Fenoprop methyl ester	Fluoxastrobin <i>cis</i> -
Epoxiconazole	Fenothiocarb	Fluquinconazole
EPTC	Fenoxanil	Flurenol-butyl ester
Erbon	Fenoxaprop-ethyl	Flurenol-methylester
Esfenvalerate	Fenoxycarb	Fluridone
Esprocarb	Fenpiclonil	Flurochloridone I
Etaconazole	Fenpropathrin	Flurochloridone II {CAS # 61213-25-0}
Ethalfuralin	Fenpropidin	Flurochloridone, deschloro-
Ethidimuron	Fenson	Fluroxypyr-1-methylheptyl ester
Ethiofencarb	Fensulfothion	Flurprimidol
Ethiolate	Fensulfothion-oxon	Flurtamone
Ethion	Fensulfothion-oxon -sulfone	Flusilazole
Ethofenprox	fensulfothion-sulfone	Fluthiacet-methyl
Ethofumesate	Fenthion	Flutolanil
Ethofumesate, 2-Keto	Fenthion sulfoxide	Flutriafol
Ethoprophos	Fenthion-sulfone	Fluvalinate-tau-I
Ethoxyfen-ethyl	Fenuron	Fluvalinate-tau-II {CAS # 102851-06-9}
Ethoxyquin	Fenvalerate I	Folpet
Ethylenethiourea	Fenvalerate II {CAS # 51630-58-1}	Fonofos
Etoxazole	Fepropimorph	Formothion
Etridiazole	Fipronil	Fosthiazate I
Etridiazole, deschloro- (5-ethoxy-3-dichloromethyl-1,2,4-thiadiazole)	Fipronil, desulfinyl-	Fosthiazate II {CAS # 98886-44-3}
Etrimfos	Fipronil-sulfide	Fuberidazole
Eugenol	Fipronil-sulfone	Furalaxyl
Exaltolide [15-Pentadecanolide]	Flamprop-isopropyl	Furathiocarb
Famoxadon	Flamprop-methyl	Furilazole
Famphur	Fluacrypyrim	Furmecyclox
Fenamidone	Fluazifop-p-butyl	Halfenprox
Fenamiphos sulfoxide	Fluazinam	Haloxypop-methyl
Fenamiphos-sulfone	Fluazolate	Heptachlor
Fenarimol	Flubenzimine	Heptachlor epoxide isomer A
Fenazaflor	Fluchloralin	Heptachlor exo-epoxide isomer B
Fenazaflor metabolite	Flucythrinate I	Heptenophos
Fenazaquin	Flucythrinate II {CAS # 70124-77-5}	Hexabromobenzene
Fenbuconazole	Fludioxonil	Hexachlorobenzene
Fenchlorazole-ethyl	Flufenacet	Hexachlorophene
Fenchlorphos	Flumetralin	Hexaconazole
Fenchlorphos-oxon	Flumiclorac-pentyl	Hexazinone
Fencloirim	Flumioxazin	Hexestrol
Fenfuram	Fluometuron	Hydroprene
Fenhexamid	Fluoranthene	Imazalil
Fenitrothion	Fluorene	Imazamethabenz-methyl I
Fenitrothion-oxon	Fluorodifen	Imazamethabenz-methyl II {CAS # 81405-85-8}
Fenobucarb	Fluoroglycofen-ethyl	Imibenconazole
Fenoprop	Fluoroimide	Imibenconazole-desbenzyl
	Fluotrimazole	

Indeno[1,2,3-cd]pyrene	Mecoprop methyl ester	Monocrotophos
Indoxacarb and Dioxacarb decomposition product [Phenol, 2-(1,3-dioxolan-2-yl)-]	Mefenacet	Monolinuron
Ioxynil	Mefenpyr-diethyl	Musk amberette
Ioxynil octanoate	Mefluidide	Musk Ketone
Ipconazole	Menazon	Musk Moskene
Iprobenfos	Mepanipirim	Musk Tibetene (Moschustibeten)
Iprodione	Mephosfolan	Musk xylene
Iprovalicarb I	Mepronil	Myclobutanil
Iprovalicarb II {CAS # 140923-25-7}	Metalaxyl	N,N-Diethyl-m-toluamide
Irgarol	Metamitron	N-1-Naphthylacetamide
Isazophos	Metasystox thiol	Naled
Isobenzan	Metazachlor	Naphthalene
Isobornyl thiocynoacetate	Metconazole I	Naphthalic anhydride
Isocarbamide	Metconazole II {CAS # 125116-23-6}	Naproanilide
Isocarbophos	Methabenzthiazuron [decomposition product]	Napropamide
Isodrin	Methacrifos	Nicotine
Isufenphos	Methamidophos	Nitralin
Isufenphos-oxon	Methfuroxam	Nitrapyrin
Isomethiozin	Methidathion	Nitrofen
Isoprocarb	Methiocarb	Nitrothal-isopropyl
Isopropalin	Methiocarb sulfone	N-Methyl-N-1-naphthyl acetamide
Isoprothiolane	Methiocarb sulfoxide	Nonachlor, <i>cis</i> -
Isoproturon	Methomyl	Nonachlor, <i>trans</i> -
Isoxaben	Methoprene I	Norflurazon
Isxadifen-ethyl	Methoprene II {CAS # 40596-69-8}	Norflurazon, desmethyl-
Isxaflutole	Methoprotryne	Nuarimol
Isxathion	Methoxychlor	o,p'-DDD
Jasmolin I	Methoxychlor olefin	o,p'-DDE
Jasmolin II	Methyl (2-naphthoxy)acetate	o,p'-DDT
Jodfenphos	Methyl paraoxon	Octachlorostyrene
Kinoprene	Methyl parathion	o-Dianisidine
Kresoxim-methyl	Methyl-1-naphthalene acetate	o-Dichlorobenzene
Lactofen	Methyldymron	Ofurace
Lenacil	Metobromuron	Omethoate
Leptophos	Metolachlor	o-Phenylphenol
Leptophos oxon	Metolcarb	Orbencarb
Lindane	Metominostrobin (E)	<i>ortho</i> -Aminoazotoluene
Linuron	Metominostrobin (Z) {CAS # 133408-50-1}	Oryzalin
Malathion	Metrafenone	Oxabetrinil
Malathion-o-analog	Metribuzin	Oxadiazon
MCPA methyl ester	Mevinphos	Oxadixyl
MCPA-butoxyethyl ester	Mirex	Oxamyl
MCPB methyl ester	Molinate	Oxycarboxin
m-Cresol	Monalide	Oxychlordan
Mecarbam		Oxydemeton-methyl
		Oxyfluorfen

p,p'-DDD	Phenanthrene	Promecarb
p,p'-DDE	Phenanthrene-d10	Promecarb artifact [5-isopropyl-3-methylphenol]
p,p'-DDM [<i>bis</i> (4-chlorophenyl)methane]	Phenakpton	Prometon
p,p'-DDT	Phenol	Prometryn
p,p'-Dibromobenzophenone	Phenothiazine	Propachlor
p,p'-Dicofol	Phenothrin I	Propamocarb
Paclobutrazol	Phenothrin II	Propanil
Paraoxon	Phenoxyacetic acid	Propaphos
Parathion	Phenthoate	Propargite
PBB 52 Tetrabrombiphenyl	Phorate	Propargite metabolite [Cyclohexanol, 2-(4-tert-butylphenoxy)]
PBB 101	Phorate sulfone	Propazine
PBB 15	Phorate sulfoxide	Propetamphos
PBB 169 Hexabrombiphenyl	Phorate-oxon	Propham
PCB 101	Phosalone	Propiconazole-I
PCB 105	Phosfolan	Propiconazole-II {CAS # 60207-90-1}
PCB 110	Phosmet	Propisochlor
PCB 118	Phosphamidon I	Propoxur
PCB 126	Phosphamidon II {CAS # 13171-21-6}	Propyzamide
PCB 127	Phthalide	Prosulfocarb
PCB 131	Phthalimide	Prothioconazole-desthio
PCB 136	Picloram methyl ester	Prothiofos
PCB 138	Picolinafen	Prothoate
PCB 153	Picoxystrobin	Pyracarbolid
PCB 169	Pindone	Pyraclofos
PCB 170	Piperalin	Pyraflufen-ethyl
PCB 180	Piperonyl butoxide	Pyrazon
PCB 30	Piperophos	Pyrazophos
PCB 31	Pirimicarb	Pyrazoxyfen
PCB 49	Pirimiphos-ethyl	Pyrene
PCB 77	Pirimiphos-methyl	Pyrethrin I
PCB 81	Plifenat	Pyrethrin II
p-Dichlorobenzene	p-Nitrotoluene	Pyributicarb
Pebulate	Potasan	Pyridaben
Penconazole	Prallethrin, <i>cis</i> -	Pyridaphenthion
Pendimethalin	Prallethrin, <i>trans</i> - {CAS # 23031-36-9}	Pyridate
Pentachloroaniline	Pretilachlor	Pyridinitril
Pentachloroanisole	Probenazole	PyrifenoX I
Pentachlorobenzene	Prochloraz	PyrifenoX II {CAS # 88283-41-4}
Pentachloronitrobenzene	Procymidone	Pyriftalid
Pentachlorophenol	Prodiamine	Pyrimethanil
Pentanochlor	Profenofos	Pyrimidifen
Permethrin I	Profenofos metabolite (4-Bromo-2-chlorophenol)	Pyriminobac-methyl (E)
Permethrin II {CAS # 52645-53-1}	Profluralin	Pyriminobac-methyl (Z) {CAS # 136191-64-5}
Perthane	Prohydrojasmon I	
Phantolide	Prohydrojasmon II {CAS # 158474-72-7}	
Phenamiphos		

Pyriproxyfen	Tecnazene	Triadimenol
Pyroquilon	Tefluthrin, <i>cis</i> -	Tri-allate
Quinalphos	Temephos	Triamiphos
Quinoclamine	Terbacil	Triapenthenol
Quinoxifen	Terbucarb	Triazamate
Quintozene metabolite (pentachlorophenyl methyl sulfide)	Terbufos	Triazophos
Quizalofop-ethyl	Terbufos-oxon-sulfone	Tributyl phosphate
Rabenzazole	Terbufos-sulfone	Tributyl phosphorotrithioite
Resmethrin	Terbumeton	Trichlamide
Resmethrine I	Terbuthylazine	Trichlorfon
Resmethrine II {CAS # 10453-86-8}	Terbuthylazine-desethyl	Trichloronate
Rotenone	Terbutryne	Triclopyr methyl ester
S,S,S-Tributylphosphorotrithioate	Tetrachlorvinphos	Triclosan
Schradan	Tetraconazole	Triclosan-methyl
Sebuthylazine	Tetradifon	Tricresylphosphate, <i>meta</i> -
Sebuthylazine-desethyl	Tetraethylpyrophosphate (TEPP)	Tricresylphosphate, <i>ortho</i> -
Secbumeton	Tetrahydrophthalimide, <i>cis</i> -1,2,3,6-	Tricresylphosphate, <i>para</i>
Silafluofen	Tetramethrin I	Tricyclazole
Silthiopham	Tetramethrin II {CAS # 7696-12-0}	Tridemorph, 4-tridecyl-
Simazine	Tetrapropyl thioldiphosphate	Tridiphane
Simeconazole	Tetrasul	Trietazine
Simetryn	Thenylchlor	Triethylphosphate
Spirodiclofen	Theobromine	Trifenmorph
Spiromesifen	Thiabendazole	Trifloxystrobin
Spiroxamine I	Thiazopyr	Triflumizole
Spiroxamine II {CAS # 118134-30-8}	Thifluzamide	Trifluralin
Spiroxamine metabolite (4-tert-butylcyclohexanone)	Thiofanox	Triphenyl phosphate
Sudan I	Thiometon	Tris(2-butoxyethyl) phosphate
Sudan II	Thionazin	Tris(2-chloroethyl) phosphate
Sudan Red	Thymol	Tris(2-ethylhexyl) phosphate
Sulfallate	Tiocarbazil I	Triticonazole
Sulfanilamide	Tiocarbazil II {CAS # 36756-79-3}	Tryclopyrbutoxyethyl
Sulfentrazone	Tolclofos-methyl	Tycor (SMY 1500)
Sulfotep	Tolfenpyrad	Uniconazole-P
Sulfur (S8)	Tolyfluanid	Vamidothion
Sulprofos	Tolyfluanid metabolite (DMST)	Vernolate
Swep	Tolyltriazole [1H-Benzotriazole, 4-methyl-]	Vinclozolin
Tamoxifen	Tolyltriazole [1H-Benzotriazole, 5-methyl-]	XMC (3,4-Dimethylphenyl N-methylcarbama
TCMTB	Tonalide	XMC (3,5-Dimethylphenyl N-methylcarbama
Tebuconazole	Toxaphene Parlar 26	Zoxamide
Tebufenpyrad	Toxaphene Parlar 50	Zoxamide decomposition product
Tebupirimifos	Toxaphene Parlar 62	
Tebutam	<i>trans</i> -Chlordane	
Tebuthiuron	Transfluthrin	
	Traseolide	
	Triadimefon	

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
April 18, 2006
5989-5076EN



Agilent Technologies



Identifying Pesticides with Full Scan, SIM, μ ECD, and FPD from a Single Injection Application

Food Safety, Environmental

Authors

Chin-Kai Meng and Bruce Quimby
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

In this application note, a gas chromatography/mass spectrometry (GC/MS) system capable of providing up to four signals from a single injection is described. When a three-way micro-fluidic splitter is added to the end of the column, two additional signals from GC detectors can be acquired together with the MS data from a single injection. This multi-signal configuration provides: full-scan data for library searching, selective ion monitoring (SIM) data for trace analysis, micro-electron capture detector and flame photometric detector data for excellent selectivity and sensitivity from complex matrices. A combination of element selective detectors, SIM/Scan, and deconvolution reporting software makes a very powerful pesticide analysis system. Examples for trace-level compound quantitation/confirmation or for screening are discussed.

Introduction

Many laboratories in the world are analyzing pesticide residue levels in both foods and the environment to protect human health. The process usually involves homogenizing the sample, extracting the pesticides, and analyzing the target compounds with a Gas Chromatograph (GC) or a Liquid

Chromatograph (LC) depending on the nature of the compounds. For GC amenable compounds, the traditional detectors are NPD (Nitrogen Phosphorus Detector), μ ECD (micro-Electron Capture Detector), and FPD (Flame Photometric Detector) for their excellent sensitivity and selectivity. However, even with dual-column confirmation analysis, these GC detectors cannot be used to verify the identity of the compounds with high confidence.

Full scan mass spectral data and library searching are typically used for final compound verification. However, full-scan analysis has a worse (higher) detection limit (DL) compared to selective detectors on a GC. To improve the DL, the technique selective ion monitoring (SIM) is often used. With SIM, the MS monitors only a few characteristic ions for each target compound within the retention time (RT) range that the target elutes from the column. By monitoring only a few specific ions, the signal-to-noise ratio (S/N) improves significantly. The ions monitored are time programmed in groups corresponding to the RTs of the targets. SIM analyses with closely eluting targets require precise alignment of chromatographic RTs with the time programming of SIM groups. The Retention Time Locking (RTL) technique can be applied to eliminate the need to adjust SIM group time-windows after column maintenance or replacement.

In this application note, a GC/MS system capable of providing up to four signals from a single injection is described. The benefits of the multi-signal detection include:

- Confirmatory information – Full-scan data for library search capability




Agilent Technologies

- Maximum sensitivity – SIM data enables trace analysis
- Excellent selectivity – μ ECD and FPD detect trace-level hetero-compounds from complex matrices

Experimental

A recent technical note describes “Synchronous SIM/Scan”, which takes advantages of the Performance Electronics in the 5975 inert MSD to get both SIM and full-scan signals in a single run without sacrificing performance [1]. The SIM method can be easily developed automatically using the ChemStation’s AutoSIM tool [2]. By simply selecting a checkbox in the method, the SIM and full-scan data can be acquired together. The trade-off is giving up some cycles per second but gaining an additional signal (full-scan data or SIM data) for the whole analysis. With properly chosen acquisition parameters, for example, increasing the scan speed, the decrease of cycles per second is usually not significant and does not affect peak quantitation or the quality of results (for example, S/N).



At the end of the column, effluent flow is split three ways according to the length and diameter of the capillary tubing (restrictor) used.

Figure 1. A schematic of the multi-signal configuration.
Note: the EPC flow adds to the column flow into the splitter.

Besides the SIM/Scan data, the ChemStation software can simultaneously acquire up to two additional GC detector signals, for example, FPD (in phosphorus- or sulfur- mode) and NPD (nitrogen-phosphorus detector) signals or both P- and S- signals from a dual-wavelength FPD (DFPD). See Figure 1.

Figure 1 is a schematic for multi-signal detection. At the end of the column, a three-way micro-fluidic splitter was used to split the column effluent to different detectors [3]. For this study, an FPD and a μ ECD were installed. Notice on the figure that an Auxiliary Electronic Pneumatics Control (Aux EPC) gas channel was connected to the splitter to maintain the pressure at the end of the column so that the split ratios/flows are kept constant throughout a run. Figure 2 shows a close-up view of the micro-fluidic splitter installed in the GC oven.




Figure 2. A close-up view of the micro-fluidic three-way splitter in the 6890 GC oven.

The size of the micro-fluidic plate is 1.25 inches (3.2 cm) wide and 2.5 inches (6.4 cm) tall. The device was designed to eliminate the common problems of large thermal mass, excess dead volume, and leaky connection due to oven temperature cycling etc. The splitter's flow paths and connection points are laid out and etched onto a thin, stainless steel plate using photolithography and chem-milling technologies. The plate is diffusion bonded, mounted with column connectors, and surface deactivated, resulting in an integrated and compact micro-fluidic splitter. Metal ferrules are used at the connectors that are leak-free after temperature cycling and will not absorb solvents or sample matrix, improving sensitivity for trace analysis applications.

Deactivated capillary tubing between the splitter and each detector was used as a flow restrictor. Aux EPC pressure and the restrictor dimensions were determined using a spreadsheet-like calculator program to achieve the proper split ratio among all detectors. The three-way splitter can easily turn into a two-way splitter when a connector is capped.

Other advantages of a splitter include back-flushing [3] and quick-swapping. The Aux EPC flow can be run-time programmed to a higher pressure, while at the same time the inlet pressure is lowered to near ambient. This causes the column flow to reverse direction, back-flushing the less volatile materials out of the split vent of the inlet. The Aux EPC on the splitter also allows column changing and inlet maintenance without cooling and venting the MSD. The splitter's flow paths and connection points were designed in such a way

that when the column fitting is removed, the helium gas from the Aux EPC purges the fitting, preventing air from entering the splitter/MSD. See Table 1 for hardware details and settings.

Table 1. Gas Chromatograph, Mass Spectrometer, and Three-Way Splitter Operating Parameters

GC	Agilent Technologies 6890		
Inlet	EPC Split/Splitless		
Mode	Splitless, 1.0 µL injected (7683 ALS)		
Inlet temp	280 °C		
Pressure	~27 psi (chlorpyrifos methyl RT locked to 16.596 min)		
Purge flow	50.0 mL/min		
Purge time	0.75 min		
Total flow	55.3 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet liner	Siltek Cyclosplitter, 4-mm id, Restek p/n 20706-214.1		
Oven			
Oven ramp	°C/min	Final (°C)	Hold (min)
Initial		70	2.00
Ramp 1	25	150	0.00
Ramp 2	3	200	0.00
Ramp 3	8	280	15
Total run time	46.87 min (last standard elutes around 35 min)		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP 5-ms, p/n 19091S-433		
Length	30.0 m		
Diameter	0.25 mm		
Film thickness	0.25 µm		
Mode	Constant pressure		
Nominal initial flow	2.5 mL/min		
Outlet	Unspecified		
Outlet pressure	3.8 psi (Aux EPC pressure to splitter)		
Front detector (FPD)			
Phosphorus mode			
Hydrogen flow:	75.0 mL/min	Sulfur mode	Hydrogen flow: 50.0 mL/min
Oxidizer flow:	100.0 mL/min	Oxidizer flow:	60.0 mL/min
Temperature:	250 °C		
Oxidizer gas type:	Air		
Mode:	Constant makeup flow		
Makeup flow:	60.0 mL/min		
Makeup gas type:	Nitrogen		
Lit offset:	2.00		
Data rate:	5 Hz		

Table 1. Gas Chromatograph, Mass Spectrometer, and Three-Way Splitter Operating Parameters (Continued)**Back detector (μECD)**

Temperature:	300 °C
Mode:	Constant makeup flow
Makeup flow:	60.0 mL/min
Makeup gas type:	Nitrogen
Date rate:	5 Hz

Thermal AUX 2

Use:	MSD Transfer line heater
Initial temp:	280 °C

Pressure AUX 5

Gas type:	Helium
Initial pressure:	3.80 psi
Initial time:	0.00 min (this value will follow oven ramp)

MSD Agilent Technologies 5975 inert MSD

Tune file	Atune.U
Mode	Scan
Solvent delay	3.00 min
EM voltage	Atune voltage
Low mass	45 amu
High mass	555 amu
Threshold	100
Sampling	2
A/D Samples	4
Scans/s	2.89
Quad temp	150 °C
Source temp	230 °C

Three-way splitter Agilent 6890N Option 890, when installed on the GC during factory assembly

Split ratio	10:10:1 MSD:FPD:μECD
MSD restrictor	1.444 m × 0.18-mm id Deactivated fused silica tubing
FPD restrictor	0.532 m × 0.18-mm id Deactivated fused silica tubing
μECD restrictor	0.507 m × 0.10-mm id Deactivated fused silica tubing
Flow to MSD (at 280 °C)	1.53 mL/min
Flow to FPD (at 280 °C)	1.53 mL/min
Flow to μECD (at 280 °C)	0.153 mL/min
Makeup flow (at 280 °C)	1.38 mL/min

Software Used in this Application Note

GC/MSD ChemStation	G1701DA
Deconvolution Reporting Software (DRS)	G1716AA
NIST Library	G1033A
AMDIS (included for free with the NIST library CD)	

Results and Discussion

Figure 3 shows four signals that were simultaneously acquired from a single injection of a pesticide mixture. Due to the high sensitivity of the μ ECD, the split ratios for the three detectors was set to MSD:FPD: μ ECD = 10:10:1. This split ratio distributes the sample of a 1- μ L splitless injection of a 1-ppm (1000 pg/ μ L) sample to the different detectors as labeled in Figure 3.




Figure 3. Signals acquired simultaneously from a 1- μ L splitless injection of 1-ppm standard. The split ratios were MSD:FPD: μ ECD = 10:10:1.

Figure 4 shows the signals when the pesticide standard was diluted 100-fold in a produce matrix. The total ion chromatogram (TIC) from full scan was not shown due to the lack of sensitivity. The FPD(P) and μ ECD were able to detect all the pesticides spiked in this extract. For trace-level target compound analysis, the SIM signal can be used for quantitation and the GC signals used for further confirmation.




Figure 4. Data of a produce extract spiked at 10 ppb. FPD and μ ECD were able to detect the respective standards spiked into the extract.

Another application for this multi-signal system is for screening. In screening, no target list is available for the analysis; therefore, SIM acquisition or MS/MS is not possible. Figure 5 shows three signals (no SIM) from a produce extract.




Figure 5. Full-scan, FPD(P), and μ ECD data for extract 13-10927.

The Deconvolution Reporting Software (DRS) [3, 4] found several pesticides in the TIC as shown in Figure 6.

MSD Deconvolution Report
Sample Name: 13-10927
Data File: C:\MSDCHEM\1\DATA\051905-spike-4sig\13-10927-2^2.40ms-Q.D
Date/Time: 09:06:39 AM Wednesday, May 25 2005

The NIST library was searched for the components that were found in the AMDIS target library.

R.T.	Cas #	Compound Name	Agilent ChemStation Amount (ng)	AMDIS Match	R.T. Diff sec.	NIST Reverse Match	Hit Num.
8.7747	90437	o-Phenylphenol		81	-0.1	84	2
9.962	84662	Diethyl phthalate	0.09	85	0.9	82	1
10.3407	114261	Propoxur		80	-0.7		
10.3407	6280962	Phenol, 2-propoxy-				88	1
10.6840	119619	Benzophenone		61	1.0	64	2
16.6138	5598130	Chlorpyrifos Methyl		71	0.3	70	2
18.4548	84742	Di-n-butylphthalate		88	1.6	92	1
21.0934	148798	Thiabendazole		79	8.8	80	2
24.6063	41394052	Metamitron		62	9.5		
24.6063	2009247	7H-Furo[3,2-g][1]benzopyran-7-one, 9-hydroxy-				86	1

Done My Computer

Figure 6. Report for extract 13-10927 generated from DRS.

The possible pesticides in the sample were benzophenone, chlorpyrifos methyl, and thiabendazole. Propoxur and metamitron were not confirmed by both AMDIS and NIST; therefore, they were most likely false positives.

Due to the complexity of the sample matrix and other interferences, it is sometimes difficult to get a high library match factor from peaks in the TIC, even after background subtraction. Therefore, element selective detectors would be very useful in providing the supporting information for compound confirmation. The multi-signal system was retention time locked, therefore, from the RT and the aligned peaks from the FPD(P) and the μ ECD responses, chlorpyrifos methyl ($C_7H_7Cl_3NO_3PS$) was confirmed.

It usually takes less than 3 minutes to turn off the FPD photomultiplier, swap the P-filter with the S-filter, and turn the photomultiplier back on. After the swap, adjust the detector gas flows to optimize the response in either P- or S- mode. A new injection of the same extract was made in FPD(S) mode. The FPD(S) result is shown with previously acquired signals in Figure 7. Two major peaks were seen on the FPD(S) chromatogram. From the peak RTs, they supported the presence of chlorpyrifos methyl and thiabendazole ($C_{10}H_7N_3S$) respectively. Note that the full-scan TIC barely showed a peak for either compound, which made it impossible for traditional data analysis to identify both compounds. The FPD(S) mode is very selective, but it is not as sensitive as the FPD(P) mode. Although the μ ECD is very sensitive, it is not as selective as the FPD. A combination of GC detectors, SIM/Scan, and DRS makes a very powerful pesticide analysis system.

Conclusion

The Synchronous SIM/Scan provides users with library searchable full-scan spectra as well as trace level SIM data in a single analysis. When a three-way micro-fluidic splitter is added to the end of the column, two additional signals from element selective detectors can be acquired together with the MS data from a single injection. This configuration makes it very attractive for the analysis of trace-level pesticide residues in foods or environmental samples.

This multi-signal configuration provides: full-scan data for library searching, SIM data for trace analysis, μ ECD and FPD data for excellent selectivity and sensitivity from complex matrices. In this application note, examples of μ ECD signal and FPD signal (P- or S- mode) were acquired together with the SIM/Scan data from a single injection for trace-level compound quantitation/confirmation, or for screening.




Figure 7. Full-scan, FPD(S), and FPD(P) data for extract 13-10927.

References

1. Chin-Kai Meng, "Improving Productivity with Synchronous SIM/Scan", Agilent Technologies, publication 5989-3108, www.agilent.com/chem
2. Harry Prest and David W. Peterson, "New Approaches to the Development of GC/MS Selected Ion Monitoring Acquisition and Quantitation Methods", Agilent Technologies, publication 5988-4188, www.agilent.com/chem
3. Michael J. Szelewski and Bruce Quimby, "New Tools for Rapid Pesticide Analysis in High Matrix Samples" Agilent Technologies, publication 5989-1716, www.agilent.com/chem
4. Philip L. Wylie, Michael J. Szelewski, Chin-Kai Meng, and Christopher P. Sandy, "Comprehensive Pesticide Screening by GC/MSD Using Deconvolution Reporting Software" Agilent Technologies, publication 5989-1157, www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
July 6, 2005
5989-3299EN



Agilent Technologies



Comprehensive Pesticide Screening by GC/MSD using Deconvolution Reporting Software Application

Food Safety

Author

Philip L. Wylie, Michael J. Szelewski, and Chin-Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Christopher P. Sandy
Agilent Technologies, Inc.
Block A, CSC Eskdale Road
Winnersh Triangle Estate
Wokingham, Berk RG41 5DZ
United Kingdom

Introduction

According to The Pesticide Manual, more than 700 pesticides are currently approved for use around the world [1]. About 600 more were used in the past, but are either banned or no longer marketed. In spite of their discontinuance, some of these still persist in the environment where they may bioaccumulate in the flora and fauna. Many pesticides or their degradation products can be found at trace levels in food and beverages; in soil, water, and air; in aquatic and terrestrial flora and fauna; and in human blood, adipose tissue, and breast milk. The World Health Organization has classified pesticides into five groups based upon their acute toxicity to humans [2]. The categories range from “Acutely Hazardous” to those that are “Unlikely to Present Acute Hazard in Normal Use.” Certain pesticides are classified as persistent organic pollutants (POPs), carcinogens, teratogens, or endocrine disrupters. It is now common to analyze for

pesticides in food and environmental samples to track their distribution in the environment and to ensure a safe food supply.

Current analytical methods target only a subset of the possible compounds. Whether for food or environmental samples, analyses are often complicated by the presence of co-extracted natural products. Food or tissue extracts can be exceedingly complex matrices that require several stages of sample cleanup prior to analysis [3]. Even then, it can be difficult to detect trace levels of contaminants in the presence of the remaining matrix.

For efficiency, multiresidue methods (MRMs) must be used to analyze for most pesticides. Traditionally, these methods have relied upon gas chromatography (GC) with a constellation of element-selective detectors to locate pesticides in the midst of a variable matrix [4, 5, 6]. GC with mass spectral detection (GC/MS) has been widely used for confirmation of hits. Liquid chromatography (LC) has been used for those compounds that are not amenable to GC [2]. Today, more and more pesticide laboratories are relying upon LC with mass spectral detection (LC/MS) and GC/MS as their primary analytical tools [7, 8]. Still, most MRMs are target compound methods that look for a small subset of the possible pesticides. Any compound not on the target list is likely to be missed by these MRMs.

Using the techniques of retention time locking (RTL) [9, 10, 11] and spectral deconvolution [12], a method has been developed to screen for 567 pesticides and suspected endocrine disrupters in a single GC/MS analysis. Spectral deconvolution



Agilent Technologies

helps to identify pesticides even when they are buried under co-eluting matrix compounds. RTL helps to eliminate false positives and gives greater confidence in the results. Users can easily add compounds to the method if they wish.

Experimental

Table 1 lists the instrumentation, software, and analytical parameters used by Agilent for pesticide analysis. Depending upon the desired injection volume, a PTV inlet or split/splitless inlet can be used.

Samples

Vegetable extracts were obtained from Dr. Mark Lee and Stephen Siegel at The California Department of Food and Agriculture (CDFA; Sacramento, CA USA) and from Dr. J.G.J. Mol at TNO Nutrition and Food Research (Zeist, The Netherlands). Seventeen data files from the GC/MS analysis of surface water samples were also contributed by CDFA and were processed in this laboratory using the Deconvolution Reporting Software (DRS). GC/MS data files (locked to the Agilent Pesticide Method) for 17 crop extracts were supplied by NRM Laboratories, Berkshire, UK.

Table 1. Instrumentation and Conditions of Analysis

Gas chromatograph	Agilent 6890N
Automatic sampler	Agilent 7683
Inlet	Agilent PTV operated in the solvent vent mode
Column	Agilent 30 m × 0.25 mm × 0.25 µm HP-5MS (p/n 19091S-433)
Carrier gas	Helium in the constant pressure mode
RTL	Chlorpyrifos-methyl locked to 16.596 min (nominal column head pressure = 17.1 psi)
Oven temperature program	70 °C (2 min), 25 °C/min to 150 °C (0 min), 3 °C /min to 200 °C (0 min), 8 °C /min to 280 °C (10–15 min)
PTV inlet parameters	Temp program: 40 °C (0.25 min), 1600 °C/min to 250 °C (2 min); Vent time: 0.2 min; Vent flow: 200 mL/min; Vent pressure: 0.0 psi; Purge flow: 60.0 mL/min; Purge time: 2.00 min
Injection volume	15 µL (using a 50-µL syringe)
Mass Selective Detector (MSD)	Agilent 5973 inert
Scan range	50–550 amu
Source, quad, transfer line temperatures	230, 150, and 280 °C, respectively
Solvent delay	4.00 min
Multiplier voltage	Autotune voltage
Software	
GC/MSD ChemStation	Agilent p/n G1701DA (Version D01.00 sp1)
Deconvolution Reporting Software (DRS)	Agilent p/n G1716AA
Library searching software	NIST MS Search (version 2.0) (included with NIST '02 mass spectral library, Agilent p/n G1033A)
Deconvolution software	Automated Mass Spectral Deconvolution and Identification Software (AMDIS) (included with NIST '02 mass spectral library, Agilent p/n G1033A)
MS Libraries	NIST '02 mass spectral library (Agilent p/n G1033A); Agilent RTL Pesticide Library (p/n G1049A)

Results and Discussion

RTL and RTL Databases

RTL is a technique developed by Agilent that allows users to match analyte retention times (RTs) on any Agilent 6890 GC, in any laboratory in the world, so long as the same nominal GC method and capillary column are used [13]. Using RTL, Agilent has developed several retention-time-locked databases for GC and GC/MS that include the locked retention time, compound name, CAS number, molecular formula, molecular weight, and mass spectrum (GC/MS databases only) for each entry [14]. The Agilent RTL Pesticide Library contains this information for almost all GC-amenable pesticides, as well as several endocrine disruptors - 567 compounds in all. For use with the DRS discussed below, this library was converted into the NIST format [15]. Separate Automated Mass Spectral Deconvolution and Identification Software (AMDIS) libraries for the RTs and compound information were created from the original RTL Pesticide Library. Users can easily augment these libraries with newer pesticides or other compounds of interest [15].


Basics of Deconvolution

In GC/MS, deconvolution is a mathematical technique that “separates” overlapping mass spectra into “cleaned” spectra of the individual components. Figure 1 is a simplified illustration of this process. Here, the total ion chromatogram (TIC) and apex spectrum are shown. As is often the case, the peak is composed of multiple overlapping components and the apex spectrum is actually a composite of these constituents. A mass spectral library search would give a poor match, at best, and certainly would not identify all of the individual components that make up the composite “spectrum.”

The deconvolution process finds ions whose individual abundances rise and fall together within the spectrum. In this case, it first corrects for the spectral skew that is inherent in quadrupole mass spectra and determines a more accurate apex RT of each chromatographic peak. As illustrated in Figure 1, deconvolution produces “clean” spectra for each overlapping component. These individual spectra can be library searched with a high expectation for a good match.

The AMDIS that is incorporated into the Agilent DRS is supplied by the National Institute of Science and Technology (NIST) [12].

TIC and spectrum



Deconvoluted peaks and spectra




Figure 1. An illustration of mass spectral deconvolution process.

DRS

Agilent's DRS results from the combination of three different GC/MS software packages: 1) the Agilent GC/MS ChemStation, 2) the NIST Mass Spectral Search Program with the NIST '02 MS Library, and 3) the AMDIS software, also from NIST. Included in the DRS, are mass spectral and locked RT libraries for 567 pesticides and suspected endocrine disrupters.

Three separate, but complimentary, data analysis steps are combined into the DRS. First, the GC/MS ChemStation software performs a normal quantitative analysis for target pesticides using a target ion and up to three qualifiers. An amount is reported for all calibrated compounds that are detected. For other compounds in the database, an estimate of their concentration can be reported based upon an average pesticide response factor

(RF) that is supplied with the DRS software. The DRS then sends the data file to AMDIS, which deconvolutes the spectra and searches the Agilent RTL Pesticide Library (in AMDIS format) using the deconvoluted full spectra. A filter can be set in AMDIS, which requires the analyte's RT to fall within a user-specified time window. Because RTL is used to reproduce the RTL database RTs with high precision, this window can be quite small - typically 20 seconds or less. Finally, the deconvoluted spectra for all of the targets found by AMDIS are searched against the 147,000-compound NIST mass spectral library for confirmation; for this step, there is no RT requirement.

Once the appropriate method is loaded, the DRS report can be generated with a single mouse click as shown in Figure 2. The software can run automatically after each analysis or at a later time on a single file or a batch of files.




Figure 2. ChemStation pull down menu showing options for running the DRS on single or multiple files.

Pesticides in an Herbal Mix

Figure 3 shows a TIC from the extract of an herbal mix. Figure 4 shows the MSD Deconvolution Report for this sample, which is produced in html format so it can easily be emailed or copied into a spreadsheet. This sample was chosen because herbs are among the most difficult vegetable products to analyze. Their extracts contain a large number of natural products that interfere with pesticide analysis.




Figure 3. TIC of an herbal mix.

Document - Microsoft Internet Explorer provided by Agilent Technologies, Inc.

File Edit View Favorites Tools Help

Address: C:\MSDCHEM\1\DATA\Hans Mol Data Feb 04 samples\Mar03_X4\MOL_4A.D\MOL_4A.htm

MSD Deconvolution Report
 Sample Name: Herbal Mix Control
 Data File: C:\MSDCHEM\1\DATA\Hans Mol Data Feb 04 samples\Mar03_X4\MOL_4A.D
 Date/Time: 02:03:11 PM Tuesday, Apr 27 2004

The NIST library was searched for the components that were found in the AMDIS target library.

R.T.	Cas #	Compound Name	Agilent ChemStation Amount (ng)	AMDIS Match	R.T. Diff sec.	Reverse Match	Hit Num
13.038	1610180	Prometon		84	2.5	71	1
18.468	84742	Di-n-butylphthalate	1.7	90	2.5	84	1
23.654	38727558	Diethyl ethyl		69	3.2	73	1
24.079	72559	p,p'-DDE		64	3.3	55	1
27.436	51235042	Hexazinone		61	3.3	80	1
29.681	117817	Bis(2-ethylhexyl)phthalate	0.62	92	2.7	88	3
29.770	21609905	Leptophos		87	3.0	71	1
29.864	2365655	Mirex	0.06	63	2.4	86	2
34.344	51630581	Fenvalerate I		70	5.3	83	2
34.779	102851069	Fluvalinate-tau-I		63	4.6		
34.779	69409945	Fluvalinate				71	1
13.766		Phenanthrene-d10	10				

Done My Computer

Figure 4. MSD Deconvolution Report generated for the herbal mix extract shown in Figure 3.

The DRS report in Figure 4 lists the RT, CAS number, and compound name for each hit. Phenanthrene- d_{10} , listed at the bottom of the report, is the internal standard (ISTD) used by the ChemStation to estimate the quantity of each compound that it found. Since an average pesticide response factor was used for all 567 target compounds, the amounts listed in column 4 are only estimates. Experience has shown that most estimates reported using an average pesticide response factor fall within a factor of 10 of their actual values. True quantitation requires calibration with pesticide standards in the normal way, but this is not practical for all of the pesticides in the database. A laboratory would normally generate calibration curves for their target set of pesticides and use the average RF for the remaining compounds in the database. In this way, when a new compound is detected, the lab can immediately get a rough estimate of its concentration and decide if it should be added to the calibration list.

Column 5 in the report shows the match factor obtained through AMDIS deconvolution and RTL Pesticide Library searching using the deconvoluted full spectra. In this case, several more targets were identified by AMDIS than were found by the ChemStation software (for example, Prometon and p,p'-DDE), which is typical for complex samples. When locked RTs are available, it is a significant advantage to set a RT requirement in the AMDIS software. In this case, hits that did not fall within ± 10 seconds of the database RT were eliminated. Column 6 shows the RT difference (in seconds) between the compound's library RT and its actual value in the chromatogram.

Figure 4 shows that the software identified two phthalates (suspected endocrine disruptors) in addition to the pesticides. Phthalates are ubiquitous in the environment and are extremely difficult to remove from the background. In this case, no attempt was made to determine if the phthalates were actually extracted from the sample or were introduced in the laboratory.

The last two columns in the DRS report show the results from searching all of the AMDIS hits against the NIST 147,000-compound mass spectral library. When the NIST library search finds a compound in the top 100 matches (a user-settable value) that agrees with the AMDIS results, its match factor is listed in column seven. The hit number is shown in the last column, with "1" being the best match (highest match factor) in the NIST database. Occasionally, the NIST library search does not find the AMDIS hit among the top

100 spectral matches. In this case, the next line in the report shows the best library match for that spectrum. This is evident for fluvalinate-tau-I (Figure 4), which eluted at 34.779 min. The next line shows the best NIST library match for that spectrum - fluvalinate. In this case, no compound with the same CAS number as fluvalinate-tau-I is contained in the NIST mass spectral library. In fact, fluvalinate-tau-I is the D isomer, while fluvalinate is the DL isomer mixture.

Blind Comparison Between DRS and Traditional Data Review

Many comparisons have shown that the DRS is much better than conventional methods at identifying target compounds in complex samples, such as food and environmental extracts. Two such studies are described here. In the first case, 17 unspiked crop samples were analyzed by NRM Laboratories in Berkshire, UK using Agilent's RT-locked pesticide method. The data files, but not their list of pesticide hits, were sent to Agilent for analysis using the new DRS. Table 2 shows a comparison of the results from the two laboratories. Using manual data review, NRM identified 28 pesticides in the 17 samples, four of which were below their lowest calibration level. Using the same data files, the DRS identified 33 pesticides.

Agilent's automated method did not identify azoxystrobin in the spring onion sample because it is not included in the RTL pesticide library. While it can be found in the NIST library, it has a molecular ion at 403 amu and method used at NRM only scanned to 400 amu. The DRS method confirmed all four pesticides that were below the NRM calibration range and found five more (terbacil, pyrimethanil, methiocarb, pyridaben, and propamocarb) that were not included in their method.

The agreement between the manual and automated methods was excellent. However, the DRS looks for many more pesticides and was able to find several that were missed by the manual method. In addition, manual data review took a chemist about 7 hours for the 17 samples while the DRS finished the task in 50 minutes of unattended computer time.

Table 2. A Comparison of the Pesticides Found in 17 Unspiked Crop Samples Using Conventional Data Review and Agilent's DRS. Pesticides that Were Found by Only One Method Are Underlined

Sample	Agilent DRS results*	NRM Manual Analysis**
Coriander	Propyzamide Chlorthal-dimethyl p,p'-DDE	Propyzamide Chlorthal-dimethyl p,p'-DDE
Rosemary	<u>Terbacil</u> Pirimicarb Chlorthal-dimethyl	Not found*** Pirimicarb Chlorthal-dimethyl
Spring Onion	Propyzamide <u>Pyrimethanil</u> Pirimicarb Metalaxyl Iprodione Not in DRS library†	Propyzamide Not found*** Pirimicarb Metalaxyl Iprodione <u>Azoxystrobin</u>
Chives	<u>Methiocarb</u> Iprodione	Not found*** Iprodione
Cherry Tomato	Procymidone <u>Pyridaben</u>	Procymidone Not found***
Courgette	<u>Propamocarb</u>	Not found***
Aubergine	Procymidone Buprofezin Endosulfan sulfate Iprodione	Procymidone Buprofezin Endosulfan sulfate Iprodione
Flat Leaf Parsley	Chlorthal-dimethyl	Chlorthal-dimethyl
Lambs Lettuce	Iprodione	Iprodione†††
Cos Lettuce	Dimethoate Metalaxyl Procymidone Terbuconazole Omethoate††	Dimethoate Metalaxyl Procymidone Terbuconazole††† Omethoate
Fine Endive	Procymidone lamda-Cyhalothrin	Procymidone lamda-Cyhalothrin
Red Potato	Chloroprotham Pirimicarb	Chloroprotham Pirimicarb†††
Fine Endive	Pirimicarb	Pirimicarb†††

* Pesticides found by re-analyzing NRM datafiles using Agilent's DRS software.

** Pesticides found by NRM using target compound analysis and manual verification.

*** This compound was not in the NRM target compound list.

† This compound is not included in the Agilent RTL Pesticide Library or the DRS software.

†† Found by the Agilent ChemStation but not found by AMDIS or NIST library searching after deconvolution. After careful review of this hit, omethoate was judged not to be in the sample.

††† Compound was detected but was below the calibration range.

Analysis of Surface Water Samples: In another study, the CDFA analyzed 17 surface water extracts for pesticides. TICs for two typical samples are shown in Figure 5. The CDFA used RTL and RTL database searching but without the benefit of spectral deconvolution. The same data files were then analyzed using the DRS for comparison.

Table 3 shows the results from the CDFA manual analysis of the 17 samples compared to results using the DRS. The CDFA found 38 pesticide hits in the 17 samples, some of which were for the same pesticide in multiple samples. It took a skilled analyst about 8 hours to review the results, eliminate false positives, and verify all of the hits. The DRS found 37 of the compounds seen by the CDFA and identified one CDFA hit as a false positive. In addition, 34 more pesticides were

found for a total of 71 hits in the 17 samples. The process was fully automated and took about 20 minutes of unattended computer time to process all of the data files.

Table 3. A Comparison of Results from the Analysis of 17 Surface Water Samples by GC/MS. The CDFA Used RTL and RTL Database Searching, but No Deconvolution. Agilent's DRS Was Used to Analyze the Same Data Files

	CDFA	DRS
Number of pesticide hits	37	Same 37 + 34 additional
Number of false positives	1	0
Time required for analysis	~ 8 hours	20 minutes




Figure 5. TICs of typical surface water extracts provided by the CDFA.

Conclusions

Agilent's new DRS solution for pesticide analysis offers laboratories a number of real benefits.

- **Ease of use:** This software solution is very simple to use and takes no more skill than is needed to operate the 6890N/5973 inert GC/MS system. There is no need for the user to learn about the intricacies of deconvolution or to master a new software package.
- **Automation:** The deconvolution report can be generated automatically after each run or a batch of samples can be processed all at once.
- **Time savings:** Data review is reduced from hours to minutes.
- **Quality:** It produces results with the fewest false positives and false negatives.
- **Reproducibility:** Results are not dependent upon the skill or experience of the operator.
- **Accuracy:** Comparisons such as those discussed in this application note show that the DRS finds pesticides with greater accuracy than manual methods of data analysis. It is particularly useful for relatively complex samples where co-eluting matrix components might obscure traces of target pesticides.
- **Comprehensive:** This method screens for almost all GC-amenable pesticides as well as several suspected endocrine disrupters in a single GC/MS run. With 567 compounds in the method, it is the most comprehensive pesticide-screening tool available. Users can add more compounds to the method as needed.
- **Produces quantitative, semi-quantitative, and qualitative results:** All calibrated compounds can be quantified. The concentrations of any other compounds can be estimated using an average pesticide response factor provided with the software.

Use of the DRS is not limited to pesticide analysis. Other target compound mass spectral libraries can be converted into the AMDIS format and used with this software. For example, one could use existing libraries for forensic drugs, flavors and fragrances, organic pollutants, etc. Users can even generate their own libraries and use them with the DRS. While not required, it is a big advantage to have an RTL library with locked RTs for each entry, as this will give the fewest false positives.

Acknowledgements

The authors wish to thank Dr. Mark Lee and Stephen Siegel of the California Department of Food and Agriculture, Dr. J.G.J. Mol of TNO Research, The Netherlands, and the management and staff at NRM Laboratories, UK, for their contribution of samples and data.

References

1. C.D.S Tomlin, editor. The Pesticide Manual, 13th edition, British Crop Protection Council, Surry, UK (2003).
2. http://www.who.int/pcs/docs/Classif_Pestic_2000-02.pdf
3. J. Cook, M.P. Beckett, B. Reliford, W. Hammock, and M. Engel (1999) *J. AOAC Int.*, **82** (6), 1419-1435.
4. M.A. Luke, J.E. Froberg, and H.T. Masumoto, (1975) *J. Assoc. Off. Anal. Chem.* **58**, 1020-1026.
5. M. Luke, J. Froberg, G. Doose, and H. Masumoto, (1981) *J. Assoc. Off. Anal. Chem.* **64**, 1187-1195.
6. B. McMahon and N. Hardin (1994) Pesticide Analytical Manual, Vol. 1, 3rd Ed., U.S. Food and Drug Administration, Washington, DC.
7. J. Fillion, R. Hindle, M. Lacroux, and J. Selwyn (1995) *J. AOAC Int.* **78**, 1252-1266.
8. J. Fillion, F. Sauvé, and J. Selwyn (2000) *JAOAC Int.*, **83**, 698-712.
9. P. Wylie and B. Quimby, "A Method Used to Screen for 567 Pesticides and Suspected Endocrine Disrupters," Agilent Technologies, publication 5967-5860E www.agilent.com/chem.
10. H. Prest, P. Wylie, K. Weiner, and D. Agnew, "Efficient Screening for Pesticides and Endocrine Disrupters Using the 6890/5973 GC/MSD System," Agilent Technologies, publication 5968-4884E www.agilent.com/chem.
11. K. Weiner and H. Prest, "Retention Time Locking: Creating Custom Retention Time Locked Screener Libraries," Agilent Technologies, publication 5968-8657E www.agilent.com/chem.
12. National Institute of Standards and Technology, AMDIS Literature and Downloads website: http://www.amdis.net/What_is_AMDIS/AMDIS_Literature_and_Downloads/amdis_literature_and_downloads.html.

13. V. Giarocco, B. Quimby and M. Klee, "Retention Time Locking: Concepts and Applications," Agilent Technologies, publication 5966-2469E www.agilent.com/chem.
14. <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#RTL>.
15. M. Szelewski and C.K. Meng, "Building and Editing RTL Screener Databases and Libraries," Agilent Technologies, publication 5989-0916EN www.agilent.com/chem.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
May 19, 2004
5989-1157EN



Agilent Technologies



Validated Method for the Determination of Phenyl Urea and Triazine Herbicides in Potable and Groundwater by LC/MS Using Selective Ion Monitoring

Application

Environmental

Authors

Neil Cullum
Anglian Water Services Laboratories
Huntingdon
UK

Paul Stephens
Agilent Technologies, Ltd.
Bracknell
UK

Abstract

This application note describes a validated liquid chromatography/mass spectrometry method for phenyl urea and triazine herbicides in potable and groundwater using an atmospheric pressure electrospray ionisation source in both positive and negative ion mode. The performance requirements set by the Drinking Water Inspectorate for standard deviation, bias, and total error are all met for each of the 16 herbicides studied.

Introduction

This application note describes the analysis of a single analytical suite composed of five phenyl urea herbicides including eight triazine herbicides, carbetamide (a carbamate herbicide), chloridazon (a pyridazinone herbicide), and metamitron

(a triazinone herbicide). Phenyl urea herbicides, such as isoproturon, are widely used for weed control in crops. The triazine herbicides, such as atrazine, are extensively used general weed control agents. Both phenyl urea and triazine herbicides are found in environmental samples and are detected in drinking water.

The Prescribed Concentration or Value (PCV) for an individual pesticide in drinking water in the UK, as defined by the Water Supply (Water Quality) Regulations, is set at 0.1 µg/L. Ideally, the method of analysis should be capable of detecting 10% to 20% of the PCV, that is 0.01 to 0.02 µg/L.

Standard methods for the determination of these herbicides in water matrices involve either liquid-liquid extraction or, more recently, solid phase extraction (SPE) followed by high performance liquid chromatography (HPLC) with ultra violet (UV)/diode array detection for both classes of herbicide, but more typically gas chromatograph/nitrogen phosphorus detector (GC/NPD) or gas chromatography/mass spectrometry (GC/MS) detection for the triazines. The phenyl urea herbicides are not suited to GC analysis as they are thermally labile. This application note details the extraction method (SPE) and analysis using liquid chromatography/mass spectrometry (LC/MS) as a combined suite, using a relatively small volume of sample.



Agilent Technologies

Experimental

All analyses were performed using the Agilent 1100 series LC/MS quadrupole coupled to an Agilent 1100 series LC system consisting of a binary pump, autosampler, thermostated column compartment, and vacuum degasser. The system also had a diode array detector in-line before the mass spectrometer, as a trouble shooting tool. The quadrupole mass spectrometer was operated with an atmospheric pressure electrospray ionisation (API-ES) source in positive and negative ion modes.

LC Conditions

Column:	Zorbax Eclipse XDB-C8 50 mm long x 2.1 mm id, 3.5 µm particles,		
	40 °C		
Flow rate;	0.5 mL/min		
Injection volume:	25 µL		
Mobile phase:	A = 0.001% formic acid in water B = Methanol		
Gradient program:		A	B
	Initial	90%	10%
	2.0 min	90%	10%
	15.0 min	30%	70%
	15.1 min	90%	10%
	22.0 min	90%	10%

MS Conditions

Ionisation mode:	Positive/Negative API-ES
Drying gas flow:	13.0 L/min
Nebulizer pressure:	40 psig
Drying gas temperature:	350 °C
V _{cap} voltage:	3000 V (positive), 2500 V (negative)

The selected ion monitoring (SIM) ions and fragmentor voltages listed in the SIM table parameters of Table 1 were all optimised using Flow Injection Analysis (FIA). Ten mg/L standard solutions of each herbicide were injected using scan mode 150 – 400 amu and the fragmentor voltage was ramped from 70 to 150 V in steps of 5 V.

Sample Preparation

SPE was performed using automated equipment and Baker SDB1 200 mg, 3 mL cartridges. The cartridges were conditioned with 5 mL of ethyl acetate, followed by 5 mL methanol, followed by 2 mL HPLC grade water. Fifty mL of sample was diluted to 200 mL using de-ionised water. One hundred mL of the diluted solution was pumped through the conditioned cartridge at 10 mL/min. Cartridges were dried for 25 minutes by forcing air through, followed by elution using ethyl acetate 1 × 1.5 mL and 1 × 1 mL. The final extracts were evaporated to dryness using a heated block set at 45 °C

Table 1. SIM Table parameters, positive ion mode

Compound #	Compound	Time	Group	SIM ions, Quantitation, Qualification (q)	Fragmentor voltage
1	Metamitron	2.50	1	203.0, 204.0q	70
2	Chloridazon			222.0, 224.0q	100
3	Monuron	7.50	2	199.0, 201.0q	115
5	Simazine			202.0, 204.0q	70
4	Carbetamide			237.0, 238.0q	95
6	Cyanazine			241.0, 243.0q	130
9	Isoproturon	10.25	3	207.0, 208.0q	140
7	Chlortoluron/ Isoproturon-d6			213.0, 215.0q	130
8	Atrazine			216.0, 218.0q	135
12	Propazine	12.40	4	230.0, 232q	130
13	Terbuthylazine				
15	Trietazine				
14	Prometryn			242.0, 243.0q	130
16	Terbutryn				
SIM Table parameters, negative ion mode					
10	Diuron	2.50	1	231.0, 233.0q	130
11	Linuron			247.0, 249.0q	115

q Qualifier ion

and a gentle stream of air. The residue was redissolved in 250 μ L 90:10 HPLC grade water:methanol. The final make-up solution contains an internal standard at a concentration of 0.1 μ g/L. The internal standard used is isoproturon-d6. Isoproturon-d6 is also present in the calibration standards at the above concentration for all levels of the calibration.




Figure 1. Chromatogram for the low level standard in positive ion mode.




Figure 2. Chromatogram for the low level standard in negative ion mode.




Figure 3. Extracted ion chromatogram from a spiked tap water sample containing chlortoluron at 0.10 μ g/L. The isoproturon-d6 internal standard (IS) is also shown.

Results

A typical chromatogram for the low level standard (each compound at 0.1 µg/L) appears in Figures 1 and 2 in both positive and negative ion modes respectively. Figure 3 shows an extracted ion chromatogram from a spiked tap water sample containing chlortoluron (0.10 µg/L) and the isoproturon-d6 internal standard.

Validation of the method was done on 11 batches of samples. Standards were spiked at three levels: 0.01, 0.10, and 0.40 µg/L. The borehole raw water was spiked at two levels: 0.01 and 0.10 µg/L. The potable tap water (which was from a surface water source) was also spiked at two levels: 0.01 and 0.10 µg/L. All samples were analysed in duplicate in each batch in a random order. See Table 2.

The limit of detection (LOD) for each herbicide was calculated from the within-batch standard deviation of the standard spiked at 0.01 µg/L. Recovery for both the groundwater and potable water samples was calculated from the 0.10 µg/L spike after the subtraction of 0.01 µg/L, hence the recovery value is based on 0.09 µg/L.

Calibration curves were produced using three calibration levels at 0.1, 0.3, and 0.5 µg/L. The calibration curves were all produced using a quadratic fit and forced through the origin and referenced against an internal standard. Typical correlation values are 0.9997 or better for all the herbicides in the suite.

Discussion

All 16 compounds could be analysed in positive ionisation mode, but diuron and linuron were analysed in negative ionisation mode because some interferences were observed around the 0.01 µg/L level. No interferences were observed for these compounds in negative ionisation mode and good limits of detection were obtained.

The recovery values obtained for all compounds in both water matrices tested are all in agreement. It appears that there is no suppression of ionisation, which has not been the case for other methods [1] where suppression is noted by a reduction in the recovery of individual compounds in some matrices.

Complete separation of all 16 compounds was not achieved by this method. Compounds 5 and 6 coeluted as well as compounds 15 and 16. However, all compounds were still quantitatively analysed as they differ in molecular weight. For instance, since compound 5 (simazine) has a molecular weight of 201 amu ($[M + H]^+ = 202\ m/z$) and compound 6 (cyanazine) has a molecular weight of 240 amu ($[M + H]^+ = 241\ m/z$), they were distinguished by selected ion mass spectroscopy. The same is applicable for compounds 15 and 16. Three compounds 12, 13, and 15 are isomers and all have a molecular weight of 229, but all three compounds show good chromatographic separation.

Table 2. Results

Compound	Groundwater sample		Potable water sample		LOD µg/L
	Recovery %	RSD %	Recovery %	RSD %	
Atrazine	83.4	5.1	83.3	5.6	0.00146
Carbetamide	92.0	7.5	88.5	7.8	0.00544
Chloridazon	94.8	5.8	94.0	4.6	0.00293
Chlortoluron	89.5	3.9	89.5	4.6	0.00219
Cyanazine	95.1	4.3	96.3	4.7	0.00352
Diuron	92.7	4.6	94.3	4.5	0.00348
Isoproturon	93.0	2.6	93.2	3.3	0.00209
Linuron	89.4	4.9	91.0	4.6	0.00330
Metamitron	102.4	2.8	102.8	3.1	0.00257
Monuron	96.6	4.6	97.3	4.8	0.00221
Prometryn	81.8	4.6	82.6	4.4	0.00208
Propazine	85.8	5.8	85.6	6.2	0.00218
Simazine	91.0	4.7	91.1	4.8	0.00179
Terbuthylazine	78.1	8.3	80.2	6.8	0.00397
Terbutryn	81.9	4.4	83.6	4.6	0.00268
Trietazine	79.1	4.7	78.7	4.8	0.00179

Figure 4 shows an extracted ion chromatogram, at 230 m/z ($[M + H]^+$) for compounds 12, 13, and 15. Two other compounds, 14 and 16, are also isomers with a molecular weight of 241 amu ($[M + H]^+ = 242\ m/z$). Compounds 14 and 16 are also separated by the chromatography.




Figure 4. Extracted positive ion chromatogram, 230 m/z , for compounds 12, 13, and 15.

Conclusion

The data shows that the method presented is capable of quantitative analysis for the 16 herbicides in a single analytical suite. The performance requirements set by the Drinking Water Inspectorate (DWI) for standard deviation, bias, and total error are all met for each individual herbicide. Although spiked recovery targets of 90%–110% are not achieved in all cases, this can be compensated for by the application of recovery factors calculated from the performance data.

References

1. N. Cullum, P. Stephens and S. Evans, "Determination of Acidic Herbicides in Groundwater and Potable Water by LC/MSD Using Selective Ion Monitoring." Agilent Technologies, publication 5988-5882EN www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2003

Printed in the USA
April 2, 2003
5988-8595EN



Agilent Technologies



Identification of Steroids in Water by Ion Trap LC/MS/MS

Application

Environmental

Author

Paul Zavitsanos and Christine Miller
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analytical boundaries for the rapid and sensitive identification and analysis of eight representative steroids were investigated using several LC/MS options including ion trap LC/MS/MS. Analysis was favored by direct large volume injections of aqueous sample and the appropriate choice of MS methodology.

Introduction

Synthetic steroids, potent hormones that can impact ecosystems at very low levels, are capable

of causing significant and undesirable mutations in fauna. They can enter the environment from many real and potential sources and eventually enter into water drainage systems to lakes and seas. There is, therefore, a need to develop efficient and sensitive methods to monitor these compounds.

This paper summarizes an investigation to determine the analytical boundaries for the identification and analysis of these compounds in water using ion trap MS/MS methodology.

Experimental

Eight steroids, representing three different substituent classes, and diethylstilbestrol, were investigated and are shown in Figure 1. They were dissolved in water or selected solvents, injected into a liquid chromatograph for separation and characterized using several mass spectroscopic modes.



Agilent Technologies




Figure 1. The compounds investigated.

Sample Preparations

The experimental steroids used here were USP reference standards, and diethylstilbestrol was obtained from Aldrich. Experimental standards and their mixtures were prepared in isopropyl alcohol (IPA).

Instrument

Agilent 1100 Series LC/MSD Trap VL

LC Conditions

Column:	Zorbax Eclipse XDB-C18, 5 cm long × 2.1 mm id, 3.5 µm particles	
Mobile phase A:	0.25 mM ammonium acetate in water	
Mobile phase B:	Acetonitrile (ACN)	
Gradient:	Time, min	% ACN
	0	20
	0.2	35
	8	90
	9	90
	9.7	20

Flow:	0.25 mL/min
Run time:	9.8 min
Post time:	8 min
Sample size injected:	1 to 100 µL, to deliver each at 5 to 50 ng on column
Binary pump with UV/VIS diode array detector (DAD)	

Ion Trap Mass Spectrometry

Vaporizer:	475 °C average
Nebulizer:	30 psi
Dry gas:	8 L/min, 300 °C
V _{cap} :	-3.0 KV for APCI positive ion mode
V _{cap} :	+1.5 KV for APCI negative ion mode
V _{cap} :	+2.0 KV for APPI negative ion mode

Chromatography

A liquid chromatogram of the test compounds is shown in Figure 2. Both name and a peak number identify the steroid peaks. These same peak numbers will be used to identify the peaks in other figures.




Figure 2. Liquid chromatogram of target compounds, detected by ion trap MS.

Injection Volume

The effect of strong solvent injection, using IPA as an example, on the chromatography is shown in Figure 3. It is obvious that there is substantial loss of resolution as the injection volume increases.




Figure 3. DAD chromatograms using injection volumes of 1, 3, 5, and 10 µL on column, in IPA.

Solvent Choice

The effect of solvent choice on the sharpness of chromatographic peaks is shown in Figure 4. Here the reciprocal of peak width is plotted against injection volume for both water and IPA solutions. As much as 100 μL of an aqueous sample can be injected and still obtain the same peak width as a 1 μL IPA solution of the same concentration, which in this case is 5.0 $\mu\text{g}/\text{mL}$.




Figure 4. The effect of solvent choice on the maximum allowable injection volume.

Figure 5 compares the DAD chromatograms obtained from these solutions. Note that the water solution exhibits 10 times the signal intensity using a tenth of the concentration.




Figure 5. Comparison of DAD chromatograms produced from water and IPA solutions of the target compounds.

Vaporizer Temperature

Signal intensity is a function of both target compound and vaporizer temperature. The relationship for four steroids is shown in Figure 6. The signal intensity for estriol is greatest when the vaporizer temperature is about 450 °C, while for the others the signal intensity keeps increasing up to the experimental limit. When analyzing for all compounds in this set the vaporizer temperature must be a compromise, hence the 475 °C setting.




Figure 6. Signal intensity vs. vaporizer temperature relationship for estriol, norethindrone, norgestrel, and hydroxyprogesterone caproate.

Atmospheric Pressure Ionization and Mass Spectrometry

Several mass spectrometric options were evaluated and described. The major ions observed in these experiments are identified in Table 1. In the negative ion experiments the indicated solvents were added post column. We note that certain steroids were not detected by all modes. We also note that estriol and estradiol lose water during APCI positive ionization.

Table 1. Ions Observed Using Different Atmospheric Pressure Ionization Modes

No.	Steroid	MW	APCI positive ion			APCI negative ion, CH ₂ Cl ₂			APPI negative ion, acetone		
			Expected m/z	Measured m/z	Ion	Expected m/z	Measured m/z	Ion	Expected m/z	Measured m/z	Ion
1	Estriol	288	289	271	[M+H-H ₂ O] ⁺	287	287	[M-H] ⁺	287	287	[M-H] ⁺
2	Estradiol	272	273	255	[M+H-H ₂ O] ⁺	271	271	[M-H] ⁺	271	271	[M-H] ⁺
3	Estrone	270	271	271	[M+H] ⁺	269	269	[M-H] ⁺	269	269	[M-H] ⁺
4	Norethindrone	298	299	299	[M+H] ⁺	297	Not found		297	Not found	
5	Norgestrel	312	313	313	[M+H] ⁺	311	Not found		311	Not found	
6	Progesterone	314	315	315	[M+H] ⁺	313	313	[M-H] ⁺	313	Not found	
7	Medroxyprogesterone acetate	386	387	387	[M+H] ⁺	385	385	[M-H] ⁺	385	Not found	
8	Hydroxyprogesterone caproate	428	429	429	[M+H] ⁺	427	427	[M-H] ⁺	427	427	[M-H] ⁺

The mass spectra for the APCI positive ions are stacked and shown in Figure 7. Arrows indicate the peaks chosen for additional dissociation to produce the second generation mass spectra shown in Figure 8.

APCI Positive ion




Figure 7. Stacked APCI positive ion mass spectra for the target compounds.

Auto MS/MS

One major feature of the Agilent LC/MSD trap is its ability to automatically sense, from an initial scan of a chromatographic peak, the major masses worthy of MS². The compound mixture was processed this way and the resulting second generation mass spectra are shown in Figure 8. Here

only one MS² spectrum is shown for each target compound, although many could have been automatically selected had the precursor ion exceeded threshold. Arrows in Figure 7 indicate the precursor ions chosen for further dissociation in the trap. Two precursor ions exceeding threshold were allowed for MS² in these Auto MS/MS experiments.




Figure 8. Stacked second generation (MS²) mass spectra for one of each target compound's precursor ions.

Chromatograms were generated using both first (MS) and second-generation (MS²) data for each chromatographic peak at compound concentrations of 5 and 50 ng on column. These are compared in Figure 9. The separate chromatograms at each concentration represent different order MS data as indicated in the figure key. The MS/MS chromatograms represent sums of product ions from each parent. The ability to use multiple precursor ions is an analytical advantage when there are overlapping chromatographic peaks exhibiting similar primary dissociation ions.




Figure 9. MS and MS/MS chromatograms at 5 and 50 ng on column for the target compounds.

Multiple Reaction Monitoring (MRM)

MRM is an analytical option, which directly produces the desired second-generation mass spectrum. This is useful when the compound's primary mass spectrum is already known and further analysis will only use second generation data from pre-selected primary ions.




Figure 10. MRM second generation chromatograms of target compounds at two concentration levels using two precursor ions per compound.

Another useful analytical option is the ability to add signal intensities derived from multiple secondary ions from the same chromatographic peak to further enhance sensitivity. This is shown in Figure 11. Note the dramatic signal intensity increase for peaks 4, 5, and 6 when compared to

neighboring peaks 3 and 7. This is most advantageous for situations where the secondary dissociation produces many low intensity peaks and complex MS/MS spectra. (For example, MS/MS spectra of northindrone, norgestrel, and progesterone in Figure 8.)




Figure 11. Comparison of MRM signal intensities using single and multiple product ion contributions.

Observations and Conclusions

- Chromatographic properties favor direct large volume aqueous sample injection. Rapid analysis is possible.
- Estriol, Estradiol and DES are best detected using negative ion APCI with 450–475 °C vaporizer temperature; all others are best detected in positive ion mode and at maximum temperature.
- APPI is very selective for some compounds under these conditions.
- Ionization in positive ion mode is usually simple. Some compounds lose water in the CID¹ region.
- Positive ion APCI is best for analysis of weak ionic strength mobile phases.
- Auto MS/MS is possible in scan mode to 5 ng of compound on column. TRAP SL optics is expected to give significantly better sensitivity and speed [1].
- MRM allows product ion scans to better than 5 ng on column. TRAP SL optics is expected to give significantly better sensitivity and speed [1].
- Monitoring the sum of product ions is best for compounds with complex product ion spectra.

¹Collision induced dissociation

References

1. Supporting Agilent documents viewable via www.agilent.com
 - a. Publication 5988-2870EN, June 1, 2001
 - b. Publication 5988-3619EN, January 17, 2002
 - c. Publication 5988-3620EN, October 31, 2001

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
August 7, 2002
5988-6926EN



Agilent Technologies



Rapid Screening Method for the Analysis of Paraquat and Diquat by LC/MSD Using Selective Ion Monitoring and Large Volume Injection


Application

Environmental


Author

Neil Cullum
Anglian Water Laboratories
Huntingdon, UK

Paul Stephens
Agilent Technologies, Ltd.
Bracknell, UK



Paraquat



Diquat

Abstract

A rapid and sensitive method for the analysis of paraquat and diquat was developed using LC/MS, electrospray ionisation (ESI), positive ion mode, selective ion monitoring (SIM) large volume injections, and minimal sample preparation. No trace enrichment was required to obtain limits of detection (LOD) below 1 µg/L, which is well below the World Health Organisation (WHO) advisory value of 10 µg/L.

Introduction

Paraquat and diquat, bipyridilium salts, are used in agriculture as non-selective contact herbicides. They are also commonly used in commercial weed killer formulations for domestic weed control.

Standard analytical methods for these herbicides in water matrices involve solid phase extraction as the enrichment technique and analysis by liquid chromatography using diode array detection (DAD) [1]. The LOD for paraquat and diquat is reported to be less than 0.4 µg/L.

This application note gives details for the screening of these herbicides using liquid chromatography/mass spectrometry (LC/MS) and a direct aqueous injection of the sample, thereby eliminating the trace enrichment step.

The WHO has set an advisory value of 10 µg/L for paraquat in drinking water. In this application, a LOD of well below 1 µg/L is achieved for paraquat and diquat, as well as for amitrole and chlormequat.

The method presented uses an ion-pairing reagent to help separate the compounds and to prepare



Agilent Technologies

the analyte as an ion. Typical ion-pairing reagents such as hexanesulphonic acid are non-volatile and cause the ion-pair complex to become non-volatile. The ion-pair reagent used in this application is tridecafluoroheptanoic acid (TDFHA), which has been reported as suitable for the analysis of basic pesticides and sufficiently volatile for the electrospray interface [2].

Experimental

All analyses were performed using Agilent 1100 series LC/MSD quadrupole coupled to an Agilent 1100 series LC system consisting of a quaternary pump, autosampler, thermostated column compartment, vacuum degasser and diode array detector. The quadrupole mass spectrometer was operated with an atmospheric pressure electrospray ionisation (API-ES) source in positive ion mode.

HPLC conditions

Column:	Zorbax Extend C18, 150 mm long × 2.1 mm id, 3.5 µm particles, 60 °C
Flow rate:	0.4 mL/min
Injection volume:	250 µL
Mobile phase:	Isocratic elution A: 5 mM TDFHA in water (75%) B: Acetonitrile (ACN) (25%)

MS conditions

Ionisation mode:	API-ES, Positive
Drying gas flow:	13.0 L/min
Nebulizer gas pressure:	30 psig
Drying gas temperature:	350 °C
V _{cap} voltage:	3500 V

The SIM ions and fragmentor voltages listed in the SIM table parameters were all optimised using Flow Injection Analysis (FIA). Ten mg/L standard solutions of each herbicide were prepared in 5 mM TDFHA and injected using scan mode 50 to 1000 amu. The fragmentor voltage was ramped from 50 to 200 V in 10 V steps. The fragmentor voltage generating the maximum response for each SIM ion was selected.

Table 1. SIM Table Parameters

Compound	Time	Group	SIM ion	Frag volt	Gain	Res
Amitrole	0	1	85.1	120	1.0	Low
Chlormequat			122.0	130		
Diquat			183.0	140		
Paraquat			185.0	140		

Mass spectra for diquat and paraquat appear in Figures 1 and 2 respectively.




Figure 1. Mass spectrum of diquat.




Figure 2. Mass spectrum of paraquat.

Sample Preparation

The only preparation required is that both working calibration standards and samples contain TDFHA at a concentration of 5 mM.

Figure 3 shows a typical chromatogram for a 10 µg/L calibration standard.




Figure 3. Total ion chromatogram of mixed standard, 10 µg/L, 250 µL injection, 2.5 ng on column.

Figures 4 and 5 show extracted ion chromatograms for diquat and paraquat, respectively, spiked into borehole water at a concentration of 1 µg/L.




Figure 4. Extracted ion chromatogram of 1 µg/L diquat in raw borehole water.




Figure 5. Extracted ion chromatogram of 1 µg/L paraquat in raw borehole water.

Conclusion

The data shows that the method presented is capable of screening for the four herbicides with a run time of 20 minutes per sample. No trace enrichment is required to obtain limits of detection below 1 µg/L with minimal sample preparation.

References

1. Analysis of Paraquat and Diquat by HPLC.
Agilent publication number 5966-1875E, 1997.
2. Impact of Ion-pair Reagents on LC/MS Analysis.
Agilent publication number 5968-8659E, 2000.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
August 7, 2002
5988-7220EN



Agilent Technologies

Analyzing Phenyl Ureas and Carbamate Pesticides Using ESI-, APPI-, and APCI-LC/MSD

Application

Environmental and Food

Author

Chin-Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Carbamates (a class of highly effective insecticides) and phenyl ureas (a class of herbicides) were successfully analyzed by liquid chromatography/mass spectrometry using electrospray ionization (ESI), atmospheric pressure chemical ionization (APCI), and atmospheric pressure photo ionization (APPI) sources. APPI and APCI exhibited lower background signals and fewer background peaks than ESI. Phenyl ureas, in general, exhibited better signal-to-noise ratios (S/N) from APCI or APPI than from ESI. However, it was just the opposite for carbamates. The S/N was better from ESI than from APCI or APPI. A small amount of post-column acetone was needed in the APPI source as a photoionizable dopant for charge transfer to the analyte.

Introduction

Carbamates, a class of highly effective insecticides, are widely used worldwide to protect crops from pests. Phenyl ureas, a class of herbicides, are highly potent chemicals for agricultural weed control. All are potential endocrine disrupters found in ground- and surface-water samples.

Gas chromatography/mass spectrometry (GC/MS) systems have traditionally been used for analyzing pesticides in environmental samples. Due to the thermally labile nature of these compounds, liquid chromatography has been the method of choice for the separation of these pesticides. Many of the pesticides within the same class exhibit similar ultra-violet (UV) spectra. With the development of atmospheric pressure ionization (API) techniques, liquid chromatography/mass spectrometry (LC/MS) systems have become the preferred method for the analysis of ground- and surface-water contaminants. The LC/MS provides better sensitivity and specificity than typical diode array detectors (DAD), even if the analytes are not fully resolved from neighboring eluants.

Three different API sources were used in this study for comparison: electrospray ionization (ESI), chemical ionization (APCI) [1], and photo ionization (APPI) [2]. In ESI, the ionization process happens before the solvent evaporation process. It is, therefore, a more universal ionization for polar compounds. In APCI and APPI, the analyte is not ionized until after solvent evaporation. APCI involves a charge transfer (proton or electron) between ionized reagent gas and the analyte. APPI requires that the analytes and/or a dopant be photoionized by absorbing photons from the 10.6 eV krypton light. The dopant then transfers the charge to the analyte, which could be thought of as photon-induced chemical ionization.



Agilent Technologies

Experimental

A mixture of carbamates and urea pesticides at 10 ppm (ng/ μ L) in acetonitrile was purchased from AccuStandard (New Haven, CT). A series of dilutions in acetonitrile were made for the linearity studies. The compounds and their structures are shown in Figures 1 and 2, respectively. All experiments were performed on two G1946D LC/MSD systems equipped with ESI on one and APCI/APPI on the other. The LC/MS conditions are listed in Table 1.




Figure 1. The 12 carbamates used in this study.




Figure 2. The seven phenyl ureas used in this study.

Table 1. LC/MS Conditions

	ESI	APCI	APPI
Column	Zorbax Eclipse XDB-C8, 4.6 x 50 mm, 3.5 μ m (p/n 935967-906)		
Column temperature	30 $^{\circ}$ C	30 $^{\circ}$ C	30 $^{\circ}$ C
Column flow rate	1 mL/min	1 mL/min	1 mL/min
Solvent A	H ₂ O, 0.1% acetic acid or as specified	H ₂ O	H ₂ O
Solvent B	Acetonitrile, 0.1% acetic acid or as specified	Acetonitrile	Methanol
Post column	n/a	n/a	40 μ L/min acetone added as dopant
Solvent gradient	B: 10% at 0 min, 30% at 4 min, 80% at 10 min, 80% at 16 min	B: 30% at 0 min, 40% at 4 min, 70% at 13 min, 80% at 16 min or as specified in the figure	
Injection volume	2 μ L	2 μ L	2 μ L
Drying gas flow	12 L/min	11 L/min	11 L/min
Drying gas temperature	350 $^{\circ}$ C	275 $^{\circ}$ C	275 $^{\circ}$ C
Fragmentor voltage	60 V	110 V	110V
Vcap	3500 V	4500 V	4500V
Nebulizer pressure	60 psi	35 psi	35 psi
Vaporizer	n/a	225 $^{\circ}$ C	225 $^{\circ}$ C
Step size	0.1	0.1	0.1
Peak width (min)	0.15	0.15	0.15
Time filter	Off	Off	Off
Scan (<i>m/z</i>)	150–800	115–500	115–500
Polarity	Positive	Positive	Positive

Results and Discussion

Figure 3 shows the effect of adding a post-column dopant (acetone) in APPI to significantly improve the responses of the analytes. Acetone at a flow rate of 40 $\mu\text{L}/\text{min}$ was introduced to the column effluent before entering the nebulizer. A gain of 1000 $\times$ in peak height was seen for some of the analytes. The difference in peak-height gain among the analytes may be due to their structural difference and the charge transfer efficiency with the dopant.




Figure 3. TICs show the effect of adding post-column acetone to enhance analyte signal in APPI. Methanol was used as solvent B for both TICs.

The LC mobile phase in APPI can interfere with ionization if the solvent has more affinity for the proton than the analyte. Figure 4 shows that acetonitrile can be a problem for baseline stability and it is always best to also try methanol in APPI.

Typical background spectra between 15 and 15.5 minutes from the three sources appear in

Figure 5. Because ESI is a more universal ionization source for polar compounds and ionic modifiers are used in ESI, the baseline has a lot more peaks and the noise is usually 5 to 15 times higher than APCI and APPI.




Figure 4. TICs show that methanol is a better mobile phase than acetonitrile in APPI. Acetone was used as dopant.




Figure 5. Baseline noise of the three sources are compared. ESI exhibits higher noise and more peaks in the baseline.

The spectra of 20 ng Diuron on column from the three sources (ESI, APCI, and APPI) appear in Figures 6, 7, and 8. The peak at mass 233 is the $[M+H]^+$ peak. Peaks at masses 233, 235, and 237 match the isotope peak-intensity pattern for two chlorine atoms, which is additional information for compound confirmation. Although ESI gives better response compared to the other two sources, it has lower signal-to-noise ratio (S/N).




Figure 6. The TIC of all target compounds from ESI. The bottom half is the ESI spectrum of 20 ng Diuron on column.





Figure 7. The TIC of all target compounds from APPI. The bottom half is the APPI spectrum of 20 ng Diuron on column.





Figure 8. The TIC of all target compounds from APCI. The bottom half is the APCI spectrum of 20 ng Diuron on column.

Figure 9 shows the spectra of Siduron (protonated ion at m/z 233) from all three sources. Protonated dimer (m/z 465) and sodiated dimer (m/z 487) of Siduron are fairly significant peaks in the ESI spectrum. However, only negligible amounts of protonated dimers (no sodiated dimers) were observed in the APPI and APCI spectra. This is mainly due to the different sequence of desolvation and ionization steps. In ESI, ionization happens before desolvation. In APPI and APCI, ionization comes after desolvation.




Figure 9. Spectra of Siduron from APPI, APCI, and ESI. Significant dimer peaks are observed in ESI.

Figure 10 compares the S/N of some of the target compounds analyzed by the three sources. The figure shows that carbamates, in general, give better S/N from ESI than from APCI or APPI. However, it is just the opposite for phenyl ureas, for example, the S/N is better from APCI or APPI than from ESI. It is also worth noting that APPI shows consistently higher S/N than APCI for this study.

A calibration based on the Methomyl $[M+H]^+$ (m/z 163) is linear over the concentration range of 20–2000 pg on column. Figure 11 shows the ESI calibration curve with the linear correlation coefficient of 0.9996. Four of the Methomyl peaks that were used for the linearity calibration appear in Figure 12.




Figure 10. The S/N of four analytes from the three ionization modes.




Figure 11. The calibration curve of Methomyl, by ESI in SIM mode (mass 163), shows good linearity over the concentration range of 20–2000 pg on column (2- μ L injection).¹

¹The calibration curve was generated using the PE Sciex Analyst™ software.




Figure 12. The Analyst™ software shows four of the Methomyl peaks (163 amu) that were used for generating the calibration curve in Figure 11.

Three different modifiers (formic acid, ammonium acetate, and acetic acid) were used in the ESI mode to compare their effectiveness. The results in Figure 13 show that, in general, the peak intensities are comparable among three modifiers. However, the elution order of the peak Mexacarbate (as well as Aminocarb) was different. Therefore, a single selected-ion-monitoring (SIM) method should not be used for different modifiers.




Figure 13. Different modifiers in ESI resulted in comparable peak intensities but changed the peak elution order.

Conclusions

Carbamates and phenyl ureas were successfully analyzed using ESI, APCI, and APPI sources. APPI and APCI have lower background signals and fewer background peaks than ESI. The results show that carbamates, in general, give better S/N from ESI than from APCI or APPI. However, it is just the opposite for phenyl ureas, for example, the S/N is better from APCI or APPI than from ESI. A small amount of post-column acetone was needed in the APPI source as a dopant. The dopant is photoionizable and is used to transfer charge to the analyte.

The typical ESI quantitation limit for these compounds is 20 pg on column using SIM. Some carbamates and phenyl ureas (for example, Propoxur, Carbofuran, and Siduron) exhibited protonated and sodiated dimers in the full scan ESI spectra.

References

1. "Basics of LC/MS," Agilent Technologies Primer, Publication 5988-2045EN, February 15, 2001.
2. "PhotoMate Atmospheric Pressure Photoionization Source from Syagen Technology," Agilent Technologies Brochure, Publication 5988-3130EN, May 25, 2001.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
May 24, 2002
5988-6635EN



Agilent Technologies



Analysis of the Active Compound in an Agricultural Fungicide Formulation by Liquid Chromatography Application

Agricultural, Speciality Chemical, Environmental, Ag Chem

Author

James D. McCurry
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Liquid chromatography was shown to be an excellent tool for the routine analysis of the active ingredient in an agricultural fungicide formulation. No extensive sample preparation or cleanup was required to remove the active ingredient from the rest of the sample matrix. The active ingredient was easily separated and detected using conventional reverse-phase conditions with a UV/VIS detector.

Introduction

Agricultural chemical formulations usually contain an active ingredient and several inert components, such as surfactants, that are designed to enhance the efficacy of the product. Gas chromatographic analysis of these formulations cannot be performed due to the polarity or thermal instability of the active ingredient as well as the high molecular weight and polarity of the surfactants. Therefore, liquid chromatography offers the best solution for the routine analysis of the active ingredients in an agricultural formulation.

This work was done on a commercially available fungicide formulation. The active ingredient in this product is 6.5 % (wt) of N,N-[1,4-piperazinediylbis(2,2,2-trichloroethylidene)] bisformamide. This is also known as triforine (CAS registry number 26644-46-2) and the structure is shown in Figure 1. The “inactive” ingredients in this formulation are listed as cyclohexanone, N-methyl pyrrolidone and Atlox 3406-F. The Atlox 3406-F is an agricultural dispersant that contains ionic and nonionic surfactants and mixed aromatic solvents. Electrospray ionization liquid chromatography/mass spectrometry (LC/MS) analysis has shown that the triforine can be easily separated and identified in the formulation [1].




Figure 1. Chemical structure of triforine, the active ingredient in some commercial fungicide formulations.



Agilent Technologies

Experimental

A 10% (v/v) solution of the fungicide formulation was made in acetonitrile. This solution was run on the Agilent 1100 Series LC System. This system included a vacuum degasser, a binary pump, an autoinjector, a thermostated column compartment, and a diode array UV/VIS detector. LC instrument conditions for this analysis are shown in Table 1.

Table 1. LC Analysis Conditions

Liquid chromatograph conditions	
Column:	Zorbax® XDB-C8, 150 × 4.6 mm, 5 µm (p/n 993967-906)
Mobile phase A:	0.1% Formic acid in water
Mobile phase B:	Acetonitrile
Mobile phase gradient:	30% B at 0 min, 50% B at 7 min, 95% B at 10 min
Flow rate:	1.0 mL/min
Injection volume:	1 mL
Column temperature:	30 °C
Detector:	Diode array
Signal wavelength:	254 nm
Signal bandwidth:	10 nm
Reference wavelength:	500 nm
Reference bandwidth:	40 nm

Results and Discussion

Figure 2 shows the chromatogram of the fungicide formulation. The active ingredient in the formulation, triforine, elutes as two chromatographic peaks between 7.5 minutes and 7.8 minutes. The presence of two triforine peaks is due to the stereochemistry of the structure. Figure 3 shows the four triforine stereoisomers. These four configurations can be grouped into two pairs of mirror images that are diastereoisomers. The S,R and R,S configurations are mirror images that are superimposable, resulting in a meso compound that exhibits no optical activity or differences in physical properties. Therefore, because the S,R and R,S configurations are identical, they will elute as one chromatographic peak. The second pair of mirror images are the R,R and S,S configurations. These are not superimposable and are, therefore, enantiomers that will have different optical activity, but identical physical properties. Conventional reverse-phase liquid chromatography cannot separate these enantiomers, and they will co-elute as a single peak. However, these enantiomers can be separated from the meso compound by reverse-phase LC. This is why there are two triforine peaks, one for the meso compound and one for the enantiomers. Without pure standards of the stereoisomers, it is not possible to determine which configurations can be attributed to the observed chromatographic peaks.




Figure 2. LC of an agricultural fungicide formulation containing the active ingredient triforine. The two peaks at 7.554 min and 7.757 min were shown to be optical isomers of triforine.




Figure 3. The four trifluorine stereoisomers arising from the two chiral carbons in the structure. These two pairs of mirror images account for the two trifluorine peaks observed in the chromatogram.

Conclusions

Liquid chromatography was shown to be an excellent tool for the routine analysis of the active ingredient in an agricultural fungicide formulation. No extensive sample preparation or cleanup was required to remove the active ingredient from the rest of the sample matrix. The active ingredient was easily separated and detected using conventional reverse-phase conditions with a UV/VIS detector.

References

1. McCurry, J.D., and Zavitsanos, P., "Analysis of Components, Contaminants, and Impurities in Fungicide Chemical Formulations by GC/MS and LC/MS," Agilent Technologies Application Note, Publication 5988-6085EN, April 2002.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
May 14, 2002
5988-6686EN




Agilent Technologies



High-Resolution Separation of Sulfonylurea Pesticides

Application
Agrichemical
Robert Ricker



Courtesy of Dr. rer.nat. Claus Schlett, Gelsenwasser AG

Conditions:
Column: ZORBAX SB-C18, 3.0 x 250 mm (Agilent Part No. 880975-302)
Mobile Phase:
A 0.01% Acetic Acid in H₂O
B Acetonitrile, 0.01% Acetic Acid
Inj. Vol.: 50 µl **UV:** (230, 270 nm); **Flow:** 0.5 mL / min.; 40°C

Gradient Time	%A	%B
2	90	10
70	55	45
85	55	45
89	10	90
94	10	90
95	90	10
110	90	10

Highlights

- An example of excellent selectivity and peakshape for a new family of pesticides.
- ZORBAX SB-C18 has a sterically protected, bonded phase that permits reliable results run-after-run.



Agilent Technologies

Sample preparation

The sulfonyleureas are extracted from water as follows:

1. *The samples (1L) are filtered through a glass-fiber filter and are brought to a pH of 3-4 using hydrochloric acid. Then, 10 ml of methanol are added.*
2. *Solid-phase extraction is carried out using 2 g of sorbent.*
3. *The cartridges are conditioned with 6 bed-volumes of H₂O (adjusted to pH 3-4) followed by 6 bed-volumes of methanol.*
4. *The samples are passed through the cartridge at a rate not exceeding 500 ml/hr.*
5. *The cartridges are dried for 45 min with nitrogen gas at a rate of 90 ml/min.*
6. *The samples are eluted from the extraction column using acetone (3 washes of 3 ml each).*
7. *The acetone is carefully evaporated from the eluted sample, and the sample re-dissolved in 100µl acetonitrile, 400µl H₂O, 0.01% acetic acid.*

Robert Ricker is an application chemist based at Agilent Technologies, Wilmington, Delaware.

For more information on our products and services, visit our website at:
www.agilent.com/chem

Copyright© 2002 Agilent Technologies, Inc.
All Rights Reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Printed in the USA
April 25, 2002
5988-6287EN

ACKNOWLEDGMENT

Agilent Technologies Inc. wishes to thank Dr. rer.nat. Claus Schlett, Gelsenwasser AG, who developed the method and provided this chromatogram.



Agilent Technologies




Pesticides


Analysis of Pesticides in Drinking Water

Application
Environmental
Robert Ricker

Standard (500ng/L)



Surface Water Sample



Courtesy of Dr. rer.nat. Claus Schlett, Gelsenwasser AG

1. Desisopropylatrazine
2. Metamitron
3. Fenuron
4. Chloridazon
5. Desethylatrazine
6. Metoxuron
7. Carbetamid
8. Bromacil
9. Hexazinon
10. Simazine
11. Metribuzin
12. Desethylterbutylazine
13. Carbutilat
14. Methabenzthiazuron
15. Chlortoluron
16. Atrazine
17. Monolinuron
18. Diuron
19. Isoproturon
20. Metobromuron
21. Metazachlor
22. Buturon
23. Propazine
24. Dimefuron
25. Terbutylazine
26. Linuron
27. Chlorbromuron
28. Chloroxuron

Highlights

- The 3mm-diameter ZORBAX Low-Volume Columns offer significant advantages over standard 4.6 mm i.d. columns:
 - A 2-fold increase in detection sensitivity -- less sample required
 - A 50% solvent savings -- and reduced solvent-disposal costs
- ZORBAX SB-C18 has a sterically protected bonded phase that permits reliable results run after run.
- 28 pesticides are separated with good resolution and peak shape in a single run using simple mobile phases.

Conditions:

ZORBAX SB-C18 (3.0 x 250 mm) (Agilent P/N: 880975-302)
Mobile Phase: A=2mM Sodium Acetate (pH 6.5) with 5% ACN
B=100% Acetonitrile (ACN)
Gradient Elution: 2min, 10% B; 10 to 45% B in 70 min.
Injection volume 25µl, 0.35 mL/min, 40°C, Detect. UV (245 nm)



Agilent Technologies

SUMMARY

A variety of pesticides have had extensive use in many countries around the world over the last twenty years. These chemicals are currently present in surface water in very low concentrations, and need to be analyzed. High-Performance Liquid Chromatography with diode-array detection is an excellent tool for analysis of these compounds.

Robert Ricker is an application chemist based at Agilent Technologies, Wilmington, Delaware.

TECHNICAL DETAILS

Drinking-water regulations have been developed in many locations that set limits for maximum allowable levels of pesticides. A reliable method of analysis is required to monitor these levels, preferably in a single run. HPLC using diode-array detection after solid-phase extraction can meet this need. Generally, substances can be detected in concentrations less than 0.1 mg/L (i.e., the maximum level set in the drinking-water regulation of Germany).

For more information on our products and services, visit our website at:
www.agilent.com/chem

ACKNOWLEDGMENT

Agilent Technologies, Inc. wishes to thank Dr. rer.nat. Claus Schlett, Gelsenwasser AG who developed the method and provided this chromatogram.

Copyright© 2002 Agilent Technologies, Inc.
All Rights Reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Printed in the USA
April 25, 2002
5988-6341EN



Agilent Technologies



Analysis of Components, Contaminants, and Impurities in Fungicide Formulations by GC/MS and LC/MS

Application

Agriculture, Specialty Chemical, Environmental, Ag Chem

Author

James D. McCurry
Paul Zavitsanos
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A commercially available fungicide formulation was analyzed by both gas chromatography/mass spectrometry (GC/MS) and electrospray ionization liquid chromatography/mass spectrometry (ESI-LC/MS). The GC/MS analysis provided a detailed look at the volatile components in the formulation, but did not yield any results for the active ingredient, triforine. The ESI-LC/MS provided information on the stereoisomers of triforine as well as the nonvolatile surfactants and contaminants in the formulation. This paper demonstrates the complementary nature of these two analytical techniques when trying to fully characterize a complex chemical formulation containing a broad range of components.

Introduction

Gas chromatography/mass spectrometry (GC/MS) is an indispensable tool for solving complex problems in the chemical industry. This fast and powerful technique yields detailed information about the expected compounds in the mixture along with any

unexpected impurities and breakdown products that can affect product quality. However GC/MS can only provide meaningful information for compounds that are volatile, nonionic, thermally stable, and have relatively low molecular weight. Liquid chromatography is much better suited to analyzing compounds that are nonvolatile, ionic, polar, thermally labile, or have high molecular weight. This includes about 80% of all known organic compounds [1]. When coupled with a modern atmospheric pressure ionization (API) mass spectrometer, LC/MS offers a complementary tool to GC/MS in the chemical diagnostic laboratory.

Commercial pest control formulations contain one or more active compounds along with a recipe of ingredients that can play an important role in the product's efficacy. These "inactive" ingredients are often a combination of solvents and surfactants that allow for easy application and dispersal of the active ingredient onto the target substrate. For this work, an over-the-counter fungicide formulation was purchased at a local home products store. The active ingredient in this product is 6.5 % (wt) of N,N-[1,4-piperazinediylbis(2,2,2-trichloroethylidene)] bisformamide. This is also known as triforine (CAS registry number 26644-46-2), and the structure is shown in Figure 1. The "inactive" ingredients in this formulation are listed as cyclohexanone, N-methyl pyrrolidone, and Atlox 3406-F. The Atlox 3406-F is an agricultural dispersant that contains ionic and nonionic surfactants and mixed aromatic solvents.



Agilent Technologies




Figure 1. Chemical structure of triforine, the active ingredient in some commercial fungicides. The nominal molecular weight is 432, and the structure contains two optically active carbons.

A complete analysis of this formulation requires GC/MS to separate and identify the volatile components and LC/MS for the surfactants and polar components. Analysis of the active ingredient, triforine, presents a separate challenge. References for triforine analysis cite gas chromatography as the method of choice when analyzing environmental residues [2]. However, the melting point is reported to be 155 °C with decomposition, indicating that gas chromatography may only be possible with on-column injection.

Experimental

Gas Chromatography/Mass Spectrometry (GC/MS)

A 1% (v/v) solution of the triforine formulation was made in acetonitrile and the GC/MS analysis was performed with an Agilent 5973 GC/MS system. The components in this system were a 6890N gas chromatograph, a 7683 autoinjector, and a 5973 mass spectrometer. A cool-on-column inlet in the Agilent 6890 GC was used to avoid decomposition of the triforine. Instrument conditions for the GC/MS analysis are listed in Table 1.

Table 1. GC/MS Analysis Conditions

Gas chromatograph conditions

Column:	30 m × 0.25 mm HP5-MS, 0.25 μm (p/n 19091S-433)
Carrier gas:	Helium at 13.00 psi
Flow rate:	1.6 mL/min., constant flow mode
Inlet:	Cool on-column at 50 °C, oven track mode
Oven temperature program:	50 °C for 3 min 10 °C/min to 275 °C 275 °C for 4 min
MS Transfer line:	280 °C
Injection volume:	1 μL

Mass spectrometer conditions

Electron multiplier:	1400 V
Solvent delay:	3 min
Scan range:	30 to 800 <i>m/z</i>
Scan threshold:	50 counts
A/D Samples:	2
Scan rate	1.95 scans/s

Electrospray Ionization Liquid Chromatography/Mass Spectrometry (ESI-LC/MS)

The same fungicide sample was run on the Agilent 1100 Series LC/MSD. This system included a vacuum degasser, a binary pump, an autoinjector, a thermostatted column compartment, and the LC/MSD SL quadrupole mass spectrometer. LC/MS instrument conditions for this analysis are shown in Table 2.

Results and Discussion

Gas Chromatography/Mass Spectrometry (GC/MS)

The complex nature of this fungicide formulation is revealed when one looks at the GC/MS data. Figure 2 shows the total ion chromatogram (TIC) of the fungicide sample. The volatile components

Table 2. LC/MS Analysis Conditions**Liquid chromatograph conditions**


Column:	150 × 4.6 mm Zorbax® XDB-C8, 5 µm (p/n 993967-906)
Mobile phase A:	0.1% Formic acid in water
Mobile phase B:	0.1% Formic acid in acetonitrile
Mobile phase gradient:	30% B at 0 min; 50% B at 7 min; 95% B at 10 min
Flow rate:	1.0 mL/min
Column temperature:	30 °C
Injection volume:	1 µL

Mass spectrometer conditions

Source:	Electrospray
Drying gas flow:	12 L/min
Nebulizer:	40 psig
Drying gas temperature:	350 °C
V _{cap} :	3500 V (positive) and 3000 V (negative)
Stepsize:	0.1 amu
Peak width:	0.1 min
Time filter:	On
Scan range	120 to 1200 <i>m/z</i>
Fragmentor	Fixed at 60 V

in the formulation are easily identified from the mass spectral data. The major solvents, cyclohexanone and N-methyl-2-pyrrolidone, dominate the chromatogram while smaller amounts of C9 aromatics, C10 aromatics, and substituted naphthalenes are easily separated and identified.

There were no peaks in the TIC whose spectra matched the triforine reference spectra from the Wiley mass spectral library. An extracted ion profile using the triforine base peak of 203 *m/z* did not produce any chromatographic peak indicating the presence of triforine. From this data, it appears that the triforine did not elute from the column into the mass spectrometer. However, a spectral average of the large hump between 18 and 20 minutes shows an isotope pattern indicating one chlorine atom (Figure 3A). Since no chlorine-containing species other than triforine are components in the formulation, the presence of chlorine and the broad peak shape indicates triforine decomposition in the gas chromatograph. The peak at approximately 20-minute retention time also has a mass spectrum containing an isotope pattern indicating the presence of two chlorine atoms in the structure (Figure 3B). This peak could be a decomposition product or a contaminant in the formulation.

**Figure 2. GC/MS TIC showing the complex volatile components in the commercial fungicide formulation.**




Figure 3. (A) Average mass spectrum of broad hump between 18 and 20 minutes of TIC. Isotope patterns of the peaks at m/z 145, 158 and 187 indicate the presence of one chlorine atom. (B) Mass spectrum of the peak at 20 minutes shows the presence of two chlorine atoms in the structure.

Electrospray Ionization Liquid Chromatography/Mass Spectrometry (ESI-LC/MS)

The positive ion ESI-LC/MS chromatogram is shown in Figure 4. Several major peaks are observed along with several minor components. The spectra of the three peaks eluting between 0 and 2 minutes are shown in Figure 5. Since electrospray is a “soft” ionization technique, these spectra do not exhibit the detailed fragmentation

needed to interpret structures for these three compounds. However, peak number 2 does have an isotopic pattern indicating the presence of two chlorine atoms in the structure. This compound could be a contaminant related to triforine production or a triforine decomposition product. Figure 6 shows the spectra of the three peaks between 10.5 and 13 minutes. These compounds are the various surfactants that make up the agricultural dispersant used in the formulation.




Figure 4. TIC from positive ion ESI-LC/MS of fungicide formulation.




Figure 5. Electrospray spectra from LC/MS peaks 1, 2, and 3. The spectra from peak 2 shows an isotope pattern indicating two chlorine atoms in this structure. This compound may be a contaminant in the formulation from the active ingredient triforine.




Figure 6. Electrospray mass spectra of LC/MS peaks 6, 7, and 8 from Figure 4. These compounds are the surfactants used in the formulation.

The spectra of LC/MS peaks 4 and 5 (Figure 7) are identical and correspond to the active ingredient, triforine. The protonated molecular ion is observed at m/z 433 along a sodium adduct at m/z 455. The multiplets for m/z 433 to 439 and m/z 455 to 461 exhibit an isotopic pattern consistent with six chlorine atoms. The ion at m/z 388 is due to a rearrangement and subsequent loss of a formamide group from the protonated molecular ion (m/z 433). This is also confirmed by the isotopic pattern indicating six chlorine atoms (m/z 388 to 396).

The presence of two triforine peaks in Figure 4 can be explained by the stereochemistry of the structure. Triforine contains two optically active carbons that give rise to four stereoisomers. Figure 8 shows the four configurations that can be grouped into two pairs of mirror images that are diastereomers. The S,R and R,S configurations are mirror

images that are superimposable, resulting in a meso compound that exhibits no optical activity or differences in physical properties. Therefore, because the S,R and R,S configurations are identical, they will elute as one chromatographic peak. The second pair of mirror images are the R,R and S,S configurations. These are not superimposable and are, therefore, enantiomers that will exhibit different optical activity, but identical physical properties. Conventional reverse-phase liquid chromatography cannot separate these enantiomers, and they will co-elute as a single peak. However, these enantiomers are not mirror images of the meso compound and can be chromatographically separated from the meso compound. This is why there are two triforine peaks, one for the meso compound and one for the enantiomers. Without pure standards of the stereoisomers, it is not possible to determine which configurations can be attributed to the observed chromatographic peaks.




Figure 7. Electrospray mass spectra of peaks 4 and 5 from Figure 4. Both spectra show a protonated molecular ion at m/z 433 representing the active ingredient triforine. There is also a sodium adduct (m/z 455) of triforine observed for both peaks. A rearrangement and loss of a formamide group from the protonated molecular ions give rise to the multiplet at m/z 388 to 396.




Figure 8. The four triforine stereoisomers arising from the two chiral carbons in the structure. These two pairs of mirror images account for the two triforine peaks observed in the chromatogram (Figure 4).

The fungicide formulation was also run by ESI-LC/MS in the negative ion mode. The results of this analysis are shown in Figure 9. The negative ion mass spectra for these two peaks are shown in Figure 10. For both triforine peaks, the most stable negative ion species is the chloride adduct (m/z 467). However, the spectra for the first peak contains a

deprotonated molecular ion (m/z 431) and a formate adduct (m/z 477) that is not observed in the spectra of the later eluting peak. This selective adduct formation is likely related to the stereochemistry of the triforine, but again, without pure standards, the correct configurations cannot be assigned to the chromatographic peaks.




Figure 9. TIC from negative ion ESI-LC/MS of fungicide formulation.




Figure 10. Negative ion electrospray mass spectra of the two triforine peaks. The spectra from peak at 7.554 minutes shows a deprotonated molecular ion (m/z 431) and a formate adduct (m/z 477) that is not seen in the later eluting peak (7.757 minutes).

Conclusions

This paper demonstrates the complimentary nature of GC/MS and LC/MS when trying to characterize a formulation that is composed of many different chemical species. The volatile compounds in the formulation can be easily separated and identified by GC/MS. In this case, polar solvents such as cyclohexanone and N-methyl-2-pyrrolidone were the major components while 1-hexanone, C9 aromatics, C10 aromatics, and substituted naphthalenes were present as minor components or contaminants. However, GC/MS did not yield any information on the active fungicidal ingredient, triforine, a hexachlorinated compound. This was most likely due to thermal decomposition during GC/MS analysis. Evidence for this was seen in a broad chromatographic hump containing chlorine-containing constituents.

The nonvolatile components in this fungicide were quickly analyzed by ESI-LC/MS. This analysis yielded information on several polar contaminants, some containing chlorine, which may be by-products of triforine production or triforine breakdown products. Also observed were several surfactants that are used in agricultural products as dispersants. The LC/MS analysis did yield significant information on the triforine active ingredient, showing a distribution of stereoisomers in the formulation.

References

1. Willoughby, R., Sheehan, E, and Mitrovich, S. A., Global View of LC/MS: How to Solve your Most Challenging Problems, p. 80, Global View Publishing, 1998.
2. The Pesticide Manual 9th Edition, Worthing, C.R. and Hance R.J. eds., p. 853, The British Crop Protection Council, 1991.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
April 24, 2002
5988-6085EN



Agilent Technologies



Determination of Acidic Herbicides in Groundwater and Potable Water by LC/MSD Using Selective Ion Monitoring

Application

Environmental

Authors

Neil Cullum
Anglian Water Laboratories
Huntingdon
UK

Paul Stephens and Stan Evans
Agilent Technologies, Ltd.
Bracknell
UK

Abstract

A validated liquid chromatography/mass spectrometry method for acidic herbicides in groundwater and potable water is described using atmospheric pressure electrospray ionisation in negative ion mode and selective ion monitoring. No derivatisation step is required and only small volumes of sample are used. Detection levels of 10 to 20% of the Prescribed Concentration or Value for an individual herbicide in drinking water in the UK are attained.

Introduction

A validated method is described for the analysis of 19 acidic herbicides and one amide herbicide, Propyzamide, as a single analytical suite. The various herbicides cannot be characterized as a single class but belong to several different groups: chlorophenoxy acids such as mecoprop, are well represented.

The Prescribed Concentration or Value (PCV) for an individual herbicide in drinking water in the UK, as defined by the Water Supply (Water Quality) Regulations, is set at 0.1 µg/L. Ideally, the method of analysis is capable of detecting 10 to 20% of the PCV, that is, 0.01 to 0.02 µg/L. This method clearly attains these lower limits of detection.

Standard analytical methods for these herbicides in water matrices involve either liquid-liquid extraction or solid phase extraction (SPE), followed by a derivatisation using diazomethane or pentafluorobenzyl bromide and analysis by gas chromatography (GC) or gas chromatography/mass spectrometry (GC/MS). The derivatisation step involves use of potentially hazardous chemicals.

This application note gives details of a validated liquid chromatography/mass spectrometry (LC/MS) method requiring no derivatisation step and which uses a relatively small volume of sample.

Experimental

All analysis was performed using an Agilent 1100 series LC/MS quadrupole system coupled to an Agilent 1100 series LC system consisting of a quaternary pump, autosampler, thermostated column compartment and vacuum degasser. A diode array detector, in-line before the mass spectrometer was used as a troubleshooting tool. The quadrupole mass spectrometer was operated with the Agilent atmospheric pressure electrospray ionisation (API-ES) source in negative ion mode.



Agilent Technologies

Sample Preparation

1. Fully automated SPE used Oasis HLB, 60 mg, 3 mL cartridges and a series of solutions: #1) 90:10 TMBE: methanol (0.01% formic acid), #2) methanol (0.01% formic acid), #3) HPLC grade water, and #4) HPLC grade water (0.25% hydrochloric acid).
2. Each cartridge was initially conditioned with sequential additions of 5 mL of solution #1, 5 mL of solution #2, 3 mL of solution #3, and 3 mL of solution #4.
3. An aqueous sample of 50 mL was diluted to 200 mL with deionised water and acidified with 0.75 mL of hydrochloric acid.
4. A diluted sample of 100 mL was pumped through the conditioned cartridge at 10 mL/min.
5. Cartridge was dried 10 minutes, using forced air.
6. Cartridge was eluted with solution #1 twice using 1.5 mL and once using 1 mL.
7. The extract was evaporated to dryness in a 45 °C heated block, using a gentle air stream.
8. Residue was dissolved in 250 µL of solution #1.

LC conditions

- Column: Zorbax Eclipse XDB-C18, 150 mm long, 2.1 mm id, 3.5 µm particles, 60 °C
- Pre-column quaternary pump
- Mobile phase A: 0.01% Formic acid in water
- Mobile phase B: Acetonitrile
- Gradient program:

	A	B
Initial	90%	10%
37.5 min	43%	57%
38.0 min	90%	10%
48.0 min	90%	10%

- Pre-column flow rate: 0.3 mL/min
- Sample size injected: 50 µL
- Binary pump with diode array detector (DAD)

Instrument: Agilent 1100 LC/MS with API-ES in Negative Ion Mode

- Drying gas temperature and flow: 300 °C, 11 L/min
- Nebulizer gas pressure: 30 psig
- V_{cap}: 2500 Volts
- Fragmentor voltage: Variable, see Table 1
- SIM ions: See Table 1

Table 1. SIM Parameters

Compound	Time	Group number	SIM ions Quantitation, Qualification (q)	Fragmentor voltage
2,3,6-TBA	1.00	1	178.9, 180.9 q	90
Clpyralid			190.1, 192.0 q	75
Picloram			238.9, 240.9 q	120
Imazapyr			260.1, 261.1 q	75
Dicamba	12.0	2	174.9, 177.0 q	85
Benazolin	17.0	3	169.9, 171.9 q	140
Fluroxypyr			195.0, 196.9 q	145
Bentazone			239.0, 240.1 q	140
Bromacil			259.0, 261.0 q	135
MCPA	24.5	4	199.0, 201.0 q	150
2,4-D			219.0, 220.9 q	150
Bromoxynil			275.9, 278.0 q	140
Dichloroprop	28.0	5	160.9, 162.9 q	150
2,4,5-T			195.0, 196.9 q	150
Triclopyr			195.9, 198.0 q	150
Mecoprop			213.0, 215.0 q	150
Ioxynil			369.9, 371.0 q	145
2,4-DB	33.5	6	160.9, 163.0 q	150
MCPB			227.1, 229.1 q	70
Propyzamide	36.25	7	254.1, 256.0 q	120

The SIM ions and fragmentor voltages listed in Table 1, page 2, were all optimized using Flow Injection Analysis (FIA). Standard solutions of 10 mg/L of each herbicide were injected using scan mode range 150 to 400 amu, and fragmentor voltage ramped from 70 to 150 V in 5 V steps. A typical FIA pattern for dicamba appears in Figure 1, and the peak area relationship appears in Figure 1A.




Figure 1. Dicamba TIC versus fragmentor voltage.




Figure 1A. Dicamba 174.9 m/z area vs. fragmentor voltage.

Using the FIA data, the fragmentor voltage generating the maximum response was selected. For dicamba, this corresponded to 80–85 V.

The mass spectrum of each herbicide was obtained at the optimum fragmentor voltage. The mass spectrum of dicamba, which has a molecular weight of 220, appears in Figure 2.

This shows the M-H ion at 219 with the expected two chlorine isotope pattern, but with a much stronger 174.9 ion, corresponding to the additional loss of CO₂. For maximum sensitivity the 174.9 ion was chosen for quantitation and the 177.0 ion as the qualifier ion (q). This process was repeated for all 20 herbicides.




Figure 2. Mass spectrum of dicamba at 85 fragmentor voltage.

Results

A typical chromatogram for the low level standard is shown in Figure 3. This is equivalent to a concentration of 0.1 µg/L.




Figure 3. Low level standard chromatogram equivalent to 0.1 µg/L.

Figure 4 shows an extracted ion chromatogram from a real sample found to contain bentazone at a concentration of 0.08 µg/L. The mass spectrum is also shown.




Figure 4. Borehole sample containing 0.08 µg/L bentazone.

Calibration curves were also produced using three calibration levels at 0.1, 0.3 and 0.5 $\mu\text{g/L}$. The calibration curves are all produced using a quadratic fit and forced through the origin. Typical correlation values are 0.9999 or better for all the herbicides in the suite. A typical calibration curve is shown in Figure 5.




Figure 5. Typical calibration plot.

Validation of the method was carried out on 11 batches of samples. The borehole groundwater was spiked at three levels: 0.01 $\mu\text{g/L}$, 0.10 $\mu\text{g/L}$, and 0.40 $\mu\text{g/L}$. The potable tap water (which was from a surface water source) was spiked at two levels: 0.01 $\mu\text{g/L}$ and 0.10 $\mu\text{g/L}$. Each batch of samples was analysed in duplicate and in a random order. The limit of detection (LOD) for each herbicide was calculated from the within-batch standard deviation of the borehole sample spiked at 0.01 $\mu\text{g/L}$. Recovery for both the groundwater and potable water samples was calculated from the 0.10 $\mu\text{g/L}$ spike after subtraction of the 0.01 $\mu\text{g/L}$ standard. Hence the recovery value is based on 0.09 $\mu\text{g/L}$.

Experimental results are shown in Table 2.

Table 2. Comparison of Spike Recoveries from Groundwater and Potable Water Samples

Compound	Groundwater samples		Potable water samples		LOD µg/L
	Recovery %	RSD %	Recovery %	RSD %	
Clopyralid	89.4	10.1	61.1	12.9	0.00658
Picloram	67.1	9.4	67.7	9.3	0.00477
Imazapyr	73.1	11.0	47.5	13.6	0.00631
2,3,6-TBA	93.4	6.4	83.5	9.0	0.00335
Dicamba	92.6	6.5	83.0	7.5	0.00882
Benazolin	83.7	7.4	67.6	7.5	0.00629
Fluroxypyr	84.8	7.6	72.7	7.6	0.00694
Bromacil	89.2	7.9	61.6	9.2	0.00702
Bentazone	106.8	4.1	98.6	4.9	0.01034
Bromoxynil	99.5	4.2	94.0	5.1	0.00666
2,4-D	85.1	8.8	76.7	6.1	0.00603
MCPA	91.5	8.1	83.2	4.9	0.00526
Triclopyr	97.7	7.4	85.0	6.8	0.00704
loxynil	100.2	6.3	99.8	4.5	0.00653
Dichloroprop	95.8	6.1	89.8	4.4	0.00545
2,4,5-T	86.7	7.3	83.0	5.7	0.00562
Mecoprop	96.6	5.9	93.9	4.6	0.00593
2,4-DB	90.7	6.3	81.6	5.7	0.00488
MCPB	93.2	5.8	84.2	7.9	0.00647
Propyzamide	86.8	5.9	87.5	5.3	0.00574
Average	90.2	7.1	80.1	7.1	0.00630

Discussion

The data produced clearly show that there is a difference in recovery between the two sample matrices tested. This is in part due to different extraction efficiencies from the two different water types, with the potable water in general showing a lower recovery. This potable water sample typically has a Total Organic Carbon (TOC) content of about 4 mg/L, compared to the borehole sample with a typical TOC of about 0.5 mg/L. The higher organic content of the potable water may well lead to slightly lower spiked recoveries.

The other factor involved, especially with the earlier eluting compounds (for example, clopyralid and imazapyr), is suppression of the ionisation. This occurs where there is competition for ionisation in the spray chamber from other compounds in the sample. In the case of potable waters, in particular waters derived from surface water sources, these are likely to be due to humic and fulvic acids, which elute very early in the analytical run. Hence ionisation suppression will lead to an apparent reduction in recovery values obtained. Consequently, when analyzing samples routinely, the

recovery correction should be made from reference values obtained from an appropriate matrix, or adjusted by the use of an internal standard(s) where available.

Conclusion

The data shows that the method presented is capable of quantitative analysis for the 20 herbicides in single analytical suite. The performance requirements set by the Drinking Water Inspectorate (DWI) for standard deviation, bias and total error are all met. Although spiked recovery targets of 90 to 110% are not achieved in all cases, this can be compensated for by the application of recovery factors which are calculated from the performance data. The method was granted UKAS accreditation at the laboratory where the method was validated.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
April 19, 2002
5988-5882EN



Agilent Technologies



Analysis of Glyphosate and Aminomethyl Phosphonic Acid by Liquid Chromatography/Mass Spectrometry

Application

Environmental

Authors

Paul Zavitsanos* and Chin-Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Lorna Grey, Bick Nguyen, and Paul Yang
Ontario Ministry of Environment
Ontario Canada

Abstract

A liquid chromatography/mass spectrometry method using an electrospray ionization source in positive ion mode was developed for the analysis of glyphosate (N-phosphonomethyl glycine) and its metabolite, aminomethyl phosphonic acid in water. Both glyphosate and its metabolite were derivatized using 9-fluorenylmethyl chloroformate in buffer solution prior to reversed phase high performance liquid chromatography separation. The method cleanly resolved both target molecules with excellent sensitivity in both positive and negative ion modes.

Background

Glyphosate (N-phosphonomethyl glycine), $(\text{HO})_2\text{P}(\text{O})\text{-CH}_2\text{-NH-CH}_2\text{CO}_2\text{H}$, is a global herbicide widely used in forest management, agricultural applications, and urban landscape management. Glyphosate is recognized as a benign, environmentally friendly herbicide with low toxicity [1]. However, there are health and environmental concerns

over its toxicity, which are documented in a recent review [2].

Judging from the scope and quantity of glyphosate in use worldwide, it is important that a rugged, routine method be available for the accurate determination of both glyphosate and its metabolite, aminomethyl phosphonic acid (AMPA), $(\text{HO})_2\text{P}(\text{O})\text{-CH}_2\text{-NH}_2$, in environmental matrices. Any analytical method must analyze for both, since an absence of glyphosate may have been caused by its conversion to AMPA.

Because of the highly polar nature of these compounds, organic solvents cannot extract them from environmental matrices. This has made their determination a difficult challenge. Many analytical methods for these molecules were reported by Stalikas and Konidari [3] listing diverse techniques including gas chromatography (GC), high performance liquid chromatography (HPLC), ion chromatography (IC), enzyme-linked immunosorbent assays, and capillary electrophoresis (CE). Although, gas chromatography/mass spectrometry (GC/MS) based methods are economical and have good selectivity and sensitivity, they use complicated derivatization processes and require highly specialized personnel. HPLC methods suffer from the relatively poor response of these molecules to ultraviolet (UV) detection.

The present method, offering a liquid chromatography/mass spectrometry (LC/MS) approach with pre-column derivatization, combines simplicity and sensitivity, adequate for a 10–50 ppb determination, given a 100-mL water sample.

*Corresponding author



Method

Sample Preparation

1. Prepare reagent solution: 10 mg/mL 9-fluorenylmethyl chloroformate (FMOC) in acetonitrile.
2. Prepare buffer solution: 5% sodium tetraborate decahydrate ($\text{Na}_2\text{B}_4\text{O}_7 \cdot 10 \text{H}_2\text{O}$), pH = 9.1
3. To 50 μL of sample extract, add 50 μL of buffer solution and mix.
4. Add 50 μL of reagent solution.
5. Let stand 4 hrs.

Instrument: Agilent 1100 LC/MS with electrospray ionization (ESI) in Positive Ion Mode

- Drying gas: 12 L/min, 350 °C
- Nebulizer gas: 60 psi
- V_{cap} : 3500 V
- Fragmentor: 100 V for both scan and SIM runs
- SIM ions: 334 and 392 m/z
- Scan range: 120 to 1000 m/z

LC conditions

- Column: ZORBAX XDB-C8, 4.6 mm id $\times$ 50 mm long, 5 μm particles, 40 °C
- Precolumn pump: Agilent 1100 binary
- Mobile phase A: 50 mM ammonium acetate, aqueous
- Mobile phase B: acetonitrile, 0 to 95% in 5 min, hold 3 min
- Pre-column flow rate: 0.7 mL/min
- Sample size injected: 1 μL
- Post-column pump: Agilent 1100 isocratic. Flow: 0.3 mL/min of 0.6% formic acid
- Binary pump with diode array detector (DAD) and well-plate sampler

Results

Figure 1 shows molecular structures for the starting compounds and their derivatized products. It is these derivatives that are analyzed and depicted in subsequent figures.




Figure 1. Derivatization reactions for glyphosate and AMPA with FMOC.

Figure 2 displays the mass spectra of both derivatized molecules. Positive ions 392 and 334, representing glyphosate and AMPA respectively, were chosen for further analysis.




Figure 2. Mass spectra of target molecules.

Figure 3 is a stacked extracted ion chromatogram of the derivatized target molecules at low concentration.




Figure 3. Low level extracted ion chromatograms for both target molecules.

Figure 4 is a similar stacked plot, but at a higher concentration.




Figure 4. Higher level extracted ion chromatograms for both target molecules.

Figures 5 and 6 are abundance vs. concentration plots for the derivatized target molecules, as the positive ions for glyphosate and AMPA, respectively.




Figure 5. Abundance vs. concentration for derivatized glyphosate, detected as $[M+H]^+$, 392 m/z .]




Figure 6. Abundance vs. concentration for derivatized AMPA, detected as $[M+H]^+$, 334 m/z .]

The non-linearity of the positive ion experiments at the higher concentrations is believed due to insufficient FMOc used in this initial experiment. This belief is strengthened by the work of Yang, et al [4] where linearity was achieved over a comparable concentration range with an optimized derivatization, also using FMOc, but analyzed in negative ion mode.

Figures 7 and 8 show abundance vs. concentration data, per Yang [4], for the derivatized target molecules as the negative ions, 390 and 332 m/z for glyphosate and AMPA, respectively.




Figure 7. Abundance vs. concentration for derivatized glyphosate, detected as $[M-H]^-$, 390 m/z .




Figure 8. Abundance vs. concentration for derivatized AMPA, detected as $[M-H]^-$, 332 m/z .

Conclusions

- Both glyphosate and AMPA, as FMOc derivatives, can be readily and sensitively detected using LC/MS with electrospray ion source in positive or negative ion mode.

- Chromatography is excellent with good separation between parent and breakdown product.
- Instrument can easily measure 10–20 ng on column.
- Sensitivity is adequate for a 10–50 ppb determination given a 100 mL water sample size.
- In positive ion mode, linearity is good below 200 ng on column. Non-linearity at higher concentrations is caused by depletion of FMOc. A drop in FMOc's UV response at higher target concentrations supports this, even though absorbencies were well within the UV detector linear range.
- The present positive ion work can be a starting point for further method development to increase both linear range and applicable matrices.
- The negative ion method shows what a fully engineered method can accomplish.
- Full sample extraction procedures can be found in Reference 4.
- This work represents an example of how derivatization can enhance the power of LC/MS. Generally, derivatization is not thought of as an LC/MS option.
- Other derivatization strategies can be studied for similar compounds.

References

- Glyphosate: A unique global herbicide. *ACS Monograph 189*, Washington D.C., American Chemical Society.
- Cox, C., Herbicide Fact Sheet. Glyphosate (Roundup). *Journal of Pesticide Reform*, 1989, 18, 3-17.
- Stalikas, C. D. and C. N. Konidari, Analytical methods to determine phosphonic and amino acid group-containing pesticides. *J. Chromatography*, 2001 A 907 1-19.
- L. Grey, B. Nguyen, and P. Yang "High Performance/Electrospray Ionization/Isotopic Dilution Mass Spectrometry Analysis of N-phosphonomethyl glycine and mass spectrometry analysis of aminomethyl phosphonic acid in environmental water and vegetation matrices", *J. AOAC*, 2001, 84(6), 1770-1780.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.


Information, descriptions and specifications in this publication are subject to change without notice.

© Agilent Technologies Inc. 2002

Printed in the U.S.A.
February 20, 2002
5988-4981EN



Agilent Technologies



Identification and Quantitation of Pesticides in the Parts-per-Trillion Range Using Retention Time Locking and GC/MS Application

Environmental, Food

Author

C. Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The typical pesticide quantitation limit for a mass spectrometer in the Scan mode is in the sub-ppm range. By using a selected ion monitoring method, a lab can lower the target compound quantitation limit to the low parts-per-billion (pg/ μ L) range using a retention time locked gas chromatography/mass spectrometry method. By adding large volume injection capability to the method, target compounds at parts-per-trillion can be quantified.

A specially developed 567-compound retention time locking pesticide mass spectral library can automatically screen an acquired sample's data file for all 567 compounds in seconds. The library can also be applied for rapid screening of samples acquired in selected ion monitoring method. Using the compound library information, a selected ion monitoring method for 80 target compounds was created in less than 2 hours without running any analyses.

Introduction

Most pesticides are typically analyzed on a gas chromatograph (GC) with element-selective detectors (ESDs). Although these ESDs provide low ppb

detection limits and are easy to operate, the data do not provide sufficient information to confirm a compound's presence with confidence. Due to the universal nature of mass spectrometric detection, a mass spectrometer (MS) provides additional information and increased confidence in the assignment of compound identity. With recent advances in GC/MS hardware and software and the decrease in cost of ownership, more and more laboratories are routinely analyzing pesticide residue samples with MS detection.

To match the GC/ESD detection limits and/or to eliminate sample concentration steps, a user must lower the MS detection limit by 2 to 3 orders of magnitude. This application note, discusses the following approaches.

- Run the MS in single ion monitoring (SIM) mode
- Make large volume injections (LVIs)
- Use higher electron multiplier voltage (EMV)

For compound identification, a specially developed 567-compound retention time locking (RTL) [1] pesticide library could perform the entire 567-compound screening in seconds using Scan data. A subset of the library could be screened in seconds from SIM data.

Experimental

A pesticide standard mixture was used to compare the lowest detection limits of splitless injection and LVI under Scan and SIM modes.



Agilent Technologies

System Configuration for Screening and Quantitation:

- 6890 GC with a programmable temperature vaporizer (PTV) [2,3] inlet
- 5973 Mass Selective Detector (MSD)
- 7683 Automatic Liquid Sampler (ALS) tray and autoinjector
- HP-5MS capillary column (30 m × 0.25 mm × 0.25 µm), P/N 19091S-433
- G1701BA version B.00.00 MSD ChemStation software or higher
- G1049A MSD RTL Pesticide Database/Library

Table 1. GC Method Parameters

Oven	70(2)/25/150(0)/3/200(0)/8/280(10) = 41.87 min
Inlet	PTV
Inlet pressure	17.30 psi (locked to methyl chlorpyrifos at 16.593 min), constant pressure mode

Table 2. Injection Parameters

Injection mode	Solvent vent	Splitless
Injection volume (syringe)	25 µL (50-µL syringe, P/N 5183-0318)	1 µL (10-µL syringe, P/N 9301-0713)
Injection speed	Inject @ 100 µL/min Draw @ 300 µL/min Dispense @ 4500 µL/min	Fast
Inlet temp	40(0.35)/600/320 (3)/50/200 (Hold until end)	280 °C
Vent	Vent time = 0.29 min Vent flow = 150 mL/min Vent pressure = 0.00 psi	
Purge	60 mL/min @ 2 min	60 mL/min @ 2 min
Liner	Deactivated, Multi Baffled (P/N 5183-2037)	Deactivated, Multi Baffled (P/N 5183-2037)
Inlet cooling	Liquid CO ₂	None

Table 3. MS Method Parameters

Solvent delay	3 min
Tune file	Atune.u
Transfer line	280 °C
MS Quad	150 °C
MS source	230 °C
Threshold	150
Sample #	2
Scan range	35 to 500 amu (in Scan mode)
Forty (40) SIM groups (in SIM mode)	

Table 4. Pesticide Screening Parameters for the SIM Method

Extraction window	±0.100 minute
Qualifier mode	Absolute
Qualifier %	30
Zero qualifiers	Included
Subtraction mode	Average start/stop
Screen database	Rtlpest.SCD

Results and Discussion

RTL [1] was used to:

1. Expedite data comparison in overlay format
2. Achieve lower target compound detection limit
3. Allow rapid pesticide screening using the RTL pesticide database/library
4. Help to differentiate isomers by their retention time (RT) differences
5. Eliminate the tedious SIM method RT updating process after column maintenance
6. Simplify the editing of the SIM ion groups

A mixture from the California Department of Food and Agriculture (CDFA) of 80 pesticides at 5000 pg/µL each was used as the stock solution for this study. The mixture contained carbamate, organochlorine, organophosphorus, and organonitrogen pesticides. Figure 1 is an offset overlay of three total ion chromatograms (TIC) with 50, 100, and 500 pg of each of the pesticides injected. These TICs were obtained in the Scan mode from 1-µL splitless injections. For many of these pesticides the quantitation limit in the Scan mode is about 500 pg on column.




Figure 1. Total ion chromatograms from 1- μ L splitless injections of 80 pesticides with 50, 100, and 500 pg of each compound injected.

SIM Mode

To lower the detection limit, a SIM method was created. Instead of the traditional way of making a SIM method, a user can use the information in the RTL Pesticide Database to build a SIM method

without running an analysis. Here are the steps for editing SIM ion group parameters:

1. List the MSD RTL Pesticide Database from the ChemStation (Figure 2 is a partial listing) and paste the complete listing into a spreadsheet.

Scdlist.txt - Notepad

File Edit Search Help

SCD Compound List Report

Screen Database : C:\DATABASE\RTLPEST.SCD
Total SCD Cpnds : 567

Cpd#	Compound Name	Tion	Exp_RT	Q1	Q2	Q3
1	Diethylene glycol	45	3.39	75	76	44
2	Aniline	93	3.55	66	65	92
3	p-Dichlorobenzene	146	3.88	148	111	75
4	Dicyclopentadiene	66	4.00	132	67	65
5	Dimefox	44	4.01	110	154	42
6	o-Dichlorobenzene	146	4.09	148	111	75
7	2-Methylphenol	108	4.25	107	77	79
8	4-Methylphenol	107	4.42	108	77	79
9	m-Cresol	108	4.42	107	79	77
10	1,2-Dibromo-3-chloropropane	157	4.53	155	75	159
11	2,4-Dimethylaniline	121	5.19	120	106	77
12	2,6-Dimethylaniline	121	5.20	106	120	77
13	2,4-Dichlorophenol	162	5.19	164	63	98
14	1,2,4-Trichlorobenzene	180	5.29	182	184	145
15	Ethiolate	100	5.41	72	161	44
16	3-Chloroaniline	127	5.45	129	65	92
17	4-Chloroaniline	127	5.48	129	65	92
18	2-Ethyl-1,3-hexanediol	56	5.51	55	73	57
19	p-Nitrotoluene	91	5.57	137	65	107
20	Methamidophos	94	5.66	95	141	47
21	Dichlorvos	109	5.83	185	79	187
22	Allidochlor	41	6.18	56	138	132
23	2,3,5-Trichlorophenol	196	6.63	198	200	160
24	2,6-Dichlorobenzonitrile	171	6.75	173	136	100

Figure 2. A partial listing of the pesticide screener database. The listing includes the compound number, compound name, target ion, expected retention time, and three qualifier ions.

- In the spreadsheet, delete the rows of the compounds not needed in the method.
- Separate target compounds into groups (see the added "Group #" column on Figure 3) using these criteria:
 - One to three compounds in each group, and
 - The RTs of the adjacent compounds in adjacent groups are at least 0.2 minute apart. For example, compounds 42 and 51 are more than 0.2 minute apart, so they are in different groups. Compounds 51 and 55 are less than 0.2 minute apart, so they are in the same group.
- Use the average RT of the adjacent compounds in adjacent groups as the SIM group RT (see the added "Group RT" column on Figure 3). For example, the average retention time of compound 42 (7.91 min, in group 2) and compound 51 (8.78 min, in group 3) is 8.35 minute which is used as the starting retention time of group 3. When all the group numbers and respective starting retention times are determined, make a hardcopy of the spreadsheet for easy entry into the "MS SIM/Scan Parameters" in the next step.
- Enter the target ion and qualifier ion(s) (Q1, Q2, and/or Q3) of all compounds into the respective ChemStation SIM group (Figure 4). Notice that all the information for building the SIM groups came from Figure 3.

#	Compound Name	MSD_RT	T	Q1	Group #	Group RT
24	2,6-Dichlorobenzonitrile	6.75	171	173	1	3.00
35	Mevinphos	7.60	127	192		
42	Propham	7.91	93	179	2	7.75
51	o-Phenylphenol	8.78	170	169	3	8.35
55	Pentachlorobenzene	8.95	250	252		
76	Propoxur	10.35	110	152	4	9.60
82	Diphenylamine	10.52	169	168		
92	Chlorpropham	11.05	127	213	5	10.76
98	Ethalfuralin	11.28	276	316		
102	Bendiocarb	11.54	151	126	6	11.41
103	Trifluralin	11.64	306	264		
104	Benfluralin	11.73	292	264		
111	Phorate	11.96	75	121	7	
113	BHC alpha isomer	12.09	181	219		
117	Hexachlorobenzene	12.38	284	286		
120	Dicloran	12.56	206	176		
122	Demeton-S	12.63	88	60		
124	Dimethoate	12.68	87	93		
129	Simazine	12.91	201	186		

Figure 3. A spreadsheet of target compounds separated into different SIM groups with RTs of the adjacent compounds in adjacent groups at least 0.2 minute apart. The starting retention time of each group was determined by calculating the average RT of the adjacent compounds in adjacent groups.

The number of qualifier ions used in a SIM method depends on the number of analytes of interest. For a method monitoring 20 to 30 compounds, all three qualifier ions should be used in the SIM method. As the list of target compounds grows, fewer qualifier ions should be used in the method to maintain a reasonable and comparable ion dwell time and sampling rate.

In general, 10 scans (cycles) per peak are recommended for quantitation purposes. For example, if an analyte peak is 6 seconds wide, about 1.7 cycles per second should be maintained for that SIM ion group. Once the number of cycles per second is determined, the dwell time of the ions can be varied to meet that. As the dwell time is entered for each ion, the ChemStation automatically shows the number of cycles per second. In Figure 4, Group 6 has 3.03 cycles per second.




Figure 4. A screen capture of the MSD ChemStation showing the MS and SIM parameters. The SIM parameters (group ID, group retention time, and ions) were all derived from Figure 3.

Figure 5 shows two chromatograms obtained from 1-μL splitless injections at 50 pg/μL using both Scan and SIM modes. The Scan mode has significantly higher baseline noise than the SIM mode. Some of the compounds, especially the late eluters, were not detected in the Scan mode. When the Scan method was changed to a SIM method at this concentration, the signal-to-noise ratio (S/N) increased by a factor of 100. It is worth pointing out that a SIM method does not record background ions from the sample matrix, therefore minimizing the baseline noise and improving the S/N.




Figure 5. Chromatograms of 1- μ L splitless injections at 50 pg/ μ L from Scan and SIM modes.

In a SIM method, the retention times of the ion groups normally need updating after column maintenance. By using RTL, a user can not only eliminate the tedious RT updating process [4] but also decrease the detection limit. With reproducible known RTs of target compounds, the start and end time of each ion group can be determined optimally. By narrowing the time windows of an ion group to monitor only one or two compounds at a time, the MS can monitor fewer ions in each window, allowing more sampling time for the target ions.

Ideally, a SIM method will have the maximum number of ion groups and the minimum number of ions in each group. In this way, each ion group can get more scans per unit time resulting in better peak shape and more accurate quantitation.

LVI

To decrease the detection limit further, a user can put more sample on column using the LVI technique. The typical “solvent-vent” approach is to inject the sample slowly into a PTV inlet at a temperature just below the solvent boiling point and let solvent evaporate before ramping up the inlet temperature to move the compounds onto the capillary column. Figure 6 compares a 1- μ L splitless injection with a 25- μ L solvent-vent injection. Both injections resulted in 50 pg per compound on column. Note that the solvent-vent ion chromatogram is plotted upside down for ease of comparison with the splitless ion chromatogram. It is obvious from the figure that the two techniques provide very similar results. This demonstrates that the solvent-vent technique is a viable approach for sample introduction.




Figure 6. SIM results of 50 pg on column using either a 1-µL splitless or a 25-µL solvent-vent injection.

Higher EMV

It is known that the signal increases with higher EMV on the MS. In Figure 7, the upper signal, after 10-fold magnification, is a 25-µL LVI of 0.5 pg/µL at tune voltage. The bottom signal is the same injection with the electron multiplier set to tune +400 V. Adding 400 V to the EMV increases

the signal by 10X, which makes the integration more accurate. However, the baseline noise also increases by 10X, so the S/N stays the same.

Although increasing the EMV does help to bring small peaks over the detection threshold, it shortens the life of the multiplier. In general, the EMV should be kept at the tune voltage.




Figure 7. SIM results of 12.5 pg on column using either EMV at Tune voltage or Tune +400 V.

LVI in Combination with SIM Methods

Combining LVI and SIM, Figures 8 and 9 show quantifiable peaks of three compounds at as low as 5 pg on column. In Figure 8, ion chromatograms of endosulfan sulfate and p,p'-DDT at 0.2 and 500 pg/ μ L are shown. The top chromatogram was from a 25- μ L solvent-vent SIM method and the bottom chromatogram was from a 1- μ L splitless Scan method. By using LVI and SIM, it is interesting to see that similar S/N ratios were achieved

even with a 2500-fold decrease (from 500 to 0.2 pg/ μ L) in sample concentration.

By increasing the injection volume to 100 μ L, samples at concentration as low as 0.05 pg/ μ L can also be quantified as shown in Figure 9. The top portion shows the chlorthal-dimethyl extracted ion chromatograms (EIC) of mass 299 and 301 from a 100- μ L full Scan run. The bottom portion shows the same ions from a 100- μ L SIM run. The SIM method shows better peak shape and lower baseline noise.




Figure 8. Ion chromatograms of endosulfan sulfate and p,p'-DDT at 0.2 and 500 pg/ μ L. The top chromatogram was from a 25- μ L solvent-vent SIM method and the bottom chromatogram was from a 1- μ L splitless Scan method.




Figure 9. Ion chromatograms of 100-μL chlorthal-dimethyl injected at 0.05 pg/μL. The top portion was from a full Scan run and the bottom portion was from a SIM run.

Target Compound Screening

Combining RTL and the G1049A MSD RTL Pesticide Database/Library, a user can screen for 567 pesticides and suspected endocrine disruptors from any Scan run [5]. A user can screen a subset of the library with improved sensitivity using a SIM method. The MSD ChemStation can generate a

567-compound screening report automatically in less than 30 seconds. Figure 10 is a report of the 0.5 pg/μL sample (25 μL injected in SIM mode) that lists the “probable hits” (marked with an x) and “possible hits” (marked with a ?). All target compounds at this 12.5 pg on column level were found by the software.

MultiVu - [C:\SYS_X\DATA\80MIX\0403SIM\0_5PG2.D\scrntemp.txt]

File Edit Search Window

Screen Report (Not Reviewed)

Data File : C:\SYS_X\DATA\80MIX\0403SIM\0_5PG2.D Vial: 16
 Acq On : 3 Apr 2001 10:26 Operator: 40 SIMgrps, 40gr
 Sample : CDFA 80 mix 10000:1 Inst : GC/MS Ins
 Misc : CDFA 80 mix = 5 ng/ μ L Multiplr: 1.00
 Sample Amount: 0.00

MS Integration Params: events.e

Screen File: Rtlpest.RES Extraction Window: +/- 0.100 min
 Screen Database: Rtlpest.SCD Qualifier Mode : Absolute
 Qualifier % : 30
 Zero qualifiers : Included
 Subtraction Mode : Sub Average Start/Stc

Compound	Status	ExpRT	Delta	Target m/z	Resp.	Qualifiers Out of Range	XCR
16 3-Chloroaniline	?	5.453	+0.034	127	11386	129	0.92
17 4-Chloroaniline	?	5.478	+0.009	127	17984	129	0.92
24 2,6-Dichlorobenzonitrile	x	6.752	-0.031	171	171652		0.97
35 Mevinphos	x	7.595	-0.035	127	101291		0.96
42 Protham	?	7.908	-0.039	93	107866	119,137	0.76
51 o-Phenylphenol	?	8.782	-0.038	170	204523	141	0.94
55 Pentachlorobenzene	?	8.947	-0.048	250	121353	248	0.85
76 Propoxur	x	10.353	-0.050	110	212997		0.99
82 Diphenylamine	x	10.516	-0.056	169	257621		0.94
92 Chlorprotham	?	11.045	-0.034	127	81328	153,154	0.75
102 Bendiocarb	?	11.540	-0.040	151	94050	166	0.85
103 Trifluralin	x	11.637	-0.011	306	41880		0.93
104 Benfluralin	x	11.725	-0.013	292	62933		0.96
111 Phorate	?	11.962	-0.042	75	63143	121,260	0.88
113 BHC alpha isomer	?	12.084	-0.045	181	46666	219,183,217	0.60
117 Hexachlorobenzene	?	12.377	-0.055	284	91832	282,288	0.00

Figure 10. Typical report from the GC/MS pesticide screener showing probable "hits" (marked with an x) and possible hits (marked with a ?). Other information includes the library retention time followed by the RT difference in this chromatogram, the target ion, its abundance, out of range qualifier(s), and a cross correlation value with the library spectrum.

Conclusions

Using the information (compound names, retention times, and ion masses) in the RTL pesticide database, a SIM method of 80 target compounds can be created in less than 2 hours without running any analyses. The examples show that both LVI and SIM are effective techniques to decrease the quantitation limit of target compounds from sub-ppm to ppt.

Any lab can decrease the quantitation limit by a factor of 100 without any hardware modification. Lowering the quantitation limit from 500 pg down to 5 pg on column can be done using a SIM method and RTL. By adding LVI to the system, target compounds in femtogram/ μ L can be quantified.

Acknowledgement

The author would like to acknowledge Alex Chung and Mark Lee at CDFA for providing the pesticide mixture used in this study.

References

1. Vince Giarrocco, Bruce Quimby, and Matthew S. Klee, *Retention Time Locking: Concepts and Applications*, Agilent Technologies Application note, 5966-2469E, printed March 2000, www.agilent.com/chem
2. Bill Wilson, Philip L. Wylie, and Matthew S. Klee, *Large Volume Injection for Gas Chromatography Using a PTV Inlet*, Agilent Technologies Application note, 5965-7770E, printed February 2000, www.agilent.com/chem

3. Philip L. Wylie, *Trace Level Pesticide Analysis by GC/MS Using Large-Volume Injection*, Agilent Technologies Application note, 5966-1214E, printed April 2000, www.agilent.com/chem
4. Prest, H. and P. Cormia, *Retention Time Locking: Advantages in GC/MS SIM Analysis*, Agilent Technologies Application Note, 5968-3797E, printed December 1999, www.agilent.com/chem
5. Harry Prest, Philip L. Wylie, Ken Weiner, and Doug Agnew, *Efficient Screening for Pesticides and Endocrine Disrupters Using the 6890/5973 GC/MSD System*, Agilent Technologies Application note, 5968-4884E, printed December 1999, www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
November 14, 2001
5988-4392EN



Agilent Technologies



Analysis of Simazine, Thiobencarb, and Thiuram by Liquid Chromatography/Mass Spectrometry Application

Environmental

Author

Hiroki Kumagai

Abstract

A liquid chromatography/mass spectrometry method using electrospray ionization in positive ion mode was successfully applied to the sensitive and simultaneous determination of the pesticides Simazine, Thiobencarb, and Thiuram.

Background

In recent years, the potential contamination of water supplies by runoff of many kinds of pesticides from golf courses and agricultural fields has become a societal problem. Many governments have established guidelines for pesticide use and water quality standards to limit such contamination. In Japan, the concentration limits in drinking water for the pesticides Simazine, Thiobencarb, and Thiuram are 3, 20, and 6 ppb, respectively.

Typically, gas chromatography-mass spectrometry (GC/MS) is used to determine Simazine and Thiobencarb in drinking water, while Thiuram is determined by high-performance liquid chromatography (HPLC) with ultraviolet (UV) detection. However, the Thiuram method used to date has problems with both selectivity and sensitivity. A better method of analysis is needed for this chemical. Such a method is described below.

Method

- Instrument: Agilent 1100 Liquid Chromatograph/Mass Spectrometer (LC/MS) with electrospray ionization (ESI) positive ion mode
Drying gas: N_2 (8 L/min, 350 °C)
Nebulizer: N_2 40 psi
Fragmentor: 40 V (Thiuram), 70 V
Mass range: 100–500 amu

• LC Conditions:

Mobile phase A: $CH_3OH/30\text{ mM } CH_3COONH_4$ (50/50)
Mobile phase B: CH_3OH
Gradient: 0 % to 100 % B in 20 min
Flow rate: 0.2 mL/min
Oven temperature: 40 °C
Injection volume: 50 μ L

- Column: Inertsil ODS3, 3.1 mm id $\times$ 250 mm long $\times$ 5 μ m

Sample Analysis

All three pesticides were determined simultaneously using the Agilent 1100 LC/MS. The following figures illustrate both the sensitivity and applicability of this method.




Figure 1. Total ion chromatogram of target pesticides, each at 5 ng.



Agilent Technologies




Figure 2. Mass spectra of target pesticides.




Figure 3. SIM chromatograms of target pesticides.

Conclusion

The LC/MS method described above is suitable for the simultaneous determination of the pesticides Simazine, Thiuram, and Thiobencarb. The peaks are well separated with detection limits of 0.02, 2.5, and 1 ppb, respectively, approximately 1/10 of the Japanese concentration limits.

Hiroki Kumagai is an application chemist at Agilent/Yokogawa Analytical Systems, Tokyo, Japan.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright© 2001
© Agilent Technologies, Inc.

www.agilent.com/chem


Printed in the USA
October 18, 2001
5988-4233EN



Agilent Technologies

The Analysis of Organophosphate Pesticides by LC/MS

Application



LC-MS

Authors

Paul Zavitsanos
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Paul Yang
MOE
Ontario Canada

Lorna Grey
MOE
Ontario Canada

Abstract

Organophosphate pesticides were readily analyzed using liquid chromatography-mass spectrometry with electrospray ion source. Sensitivity and selectivity were significantly better than using a diode-array UV detector.

Overview

Liquid chromatography-mass spectrometry (LC-MS) is rapidly becoming a routine technique for efficient trace analysis of polar pesticides in various types of samples. In comparison to existing methodologies, such as gas chromatography-mass spectrometry (GC-MS) and ultraviolet (UV) detection, LC-MS considerably simplifies cleanup procedures, reducing both time of analysis and method development time.¹

LC-MS with an electrospray ion (ESI) source avoids the thermal degradation of labile pesticides encountered with GC and eliminates the need for preliminary derivatization to increase compound volatility.

Additionally, LC-MS provides unequivocal identification of each pesticide, even if the pesticide was not completely resolved from neighboring eluants. Traditional UV detection cannot provide the required specificity because many of the pesticides within the same class exhibit similar UV spectra.

Sample case

A mixture of organophosphate pesticides and an internal standard were analyzed using an Agilent 1100 LC/MS with an ESI source (Table 1).

Table 1. Mixture of Organophosphate Pesticides

Elution order	Compound	[M+H] ⁺	Concentration $\mu\text{g/mL}$
1	Mevinphos isomer 1	225	0.2
2	Dimethoate	230	0.5
3	Mevinphos isomer 2	225	0.5
4	Dichlorvos	221	0.5
5	Azinphos methyl	318	0.05
6	Parathion methyl	264	0.2
7	Malathion	331	0.5
8	Diazinon	305	0.2
9	Triphenyl orthophosphate*	327	1.0
10	Parathion ethyl	292	0.1
11	Phorate	261	0.1
12	Reldan	322	0.5
13	Ronnel	321	0.1
14	Terbuphos	289	0.2
15	Dursban	350	0.1
16	Ethion	385	0.2
17	Temephos	467	0.1

* Internal standard



Agilent Technologies

Method summary

- Column 2.1 mm id × 5 cm long, filled with 3.5 μ m particles, C18 chemistry
- 20 mM ammonium acetate vs. acetonitrile mobile phase gradient
 - 5 % to 95 % acetonitrile in 4 minutes
 - Hold 2 minutes
- Splitless 400 μ L/min flow
- 3 μ L injection volume
- Scan data 120 to 600 m/z
- SIM data as per Table 1. 95 msec dwell/ion in two groups

Results

Simultaneous UV (220 nm) and MS detector outputs are compared in Figure 1. The MS plot is a composite of all the individual extracted ion chromatograms. Each was obtained at the $[M+H]^+$ value given in Table 1, and are separated and stacked in Figure 2 for easy comparison.




Figure 1. Comparison of UV and MS chromatograms.




Figure 2. Stacked normalized extracted ion chromatograms for compounds 1 through 17.

Figures 3 through 6 show the resulting normalized mass ion spectra for each compound included in Table 1.




Figure 3. Stacked normalized ion mass spectra for compounds 1 through 4.




Figure 4. Stacked normalized ion mass spectra for compounds 5 through 8.




Figure 5. Stacked normalized ion mass spectra for compounds 9 through 12.




Figure 6. Stacked normalized ion mass spectra for compounds 13 through 17.

Conclusions

When determining organophosphate pesticides using LC-MS with an ESI source:

- All the tested organophosphate pesticides ionized well and gave definite $[M+H]^+$ ions
- Sensitivity and selectivity are significantly better than using diode-array UV detector
- Overall chromatography and analysis is simple and straightforward
- Positive identification and quantification are performed using integrated software

For more information, contact your local Agilent sales representative, or visit www.agilent.com.

Reference

1. Elbert Hogendoorn and Peit van Zoonen, *Journal of Chromatography A*, 892 (2000) 435-453.


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright© 2001
© Agilent Technologies, Inc.

Printed in the USA
September 13, 2001
5988-3774EN





Application of Online Solid-Phase Extraction Ion Trap Mass Spectrometry in Environmental Matrices

Application Note

Robert D. Voyksner and Jennifer A. Townsend
LCMS Limited

Introduction

Sulfonylureas are a class of potent herbicides that are characterized as acetolactate synthase-inhibiting (ALS). Compared with other herbicides and pesticides, sulfonylureas are considered to be highly potent and are consequently used at much lower application rates for such purposes as agricultural weed control. This ultimately results in lower concentration levels found in real environmental samples, compared with levels found from use of other herbicides/pesticides. Sulfonylureas are thermally labile compounds and are directly metabolized in the environment. While the level of toxicity to animals from these compounds is low, their ability to persist in soil and water can cause damage to crops in later years. Therefore, in order to successfully detect, confirm, and quantify trace levels of these compounds in complex matrices such as environmental samples, LC/MS techniques are needed.

Applications involving the analysis of sulfonylurea herbicides in environmental matrices have already been investigated via several techniques.^{1, 2, 3}

Typically, the rate limiting steps in these determinations are the time-consuming (~13 hours) and labor-intensive, non-automated extraction and cleanup steps.

This application describes the technique of turbulent-flow solid-phase extraction (SPE) with ion trap mass spectrometric detection for the analysis of sulfonylureas in environmental samples. This whole procedure can be accomplished on line in approximately 45 minutes per sample, by combining sample extraction, cleanup, and detection into one process. This application uses a small-bore (0.5–1 mm) SPE column, typically containing 50 micron C₁₈ particles, permitting sample introduction at flow rates from 1 to 10 ml/min (turbulent-flow conditions). These flow conditions minimize the time required for loading, washing, and eluting the analytes onto and off of the extraction column. Under these conditions, lipophilic analytes are efficiently trapped on the extraction column, while salts, biological materials, and other hydrophilic materials are flushed from the column with water. The retained analytes are then quickly eluted off of the extraction



Agilent Technologies

column and loaded onto the analytical column. Post column addition is used after the extraction column in order to adjust the organic content of the mobile phase to allow for more efficient trapping of the hydrophilic analytes onto the analytical column. Through the use of gradient elution programming, the level of organic content in the mobile phase is gradually increased until the analytes are eluted off the analytical column and are subsequently introduced into the ion trap mass spectrometer. The ion trap offers the advantage of MS/MS to improve specificity and detection limits in dirty matrices, which would not be achievable with UV or single-MS operation.

Experimental

All experiments were conducted using samples obtained from North Carolina sources of surface water. Samples of lake, pond, and runoff water were initially spiked at the 0.2 and 2.0 part-per-billion (ppb) levels using a 1 mg/ml solution of 12 sulfonfylureas and 1 sulfonamide herbicide standard prepared in acetonitrile. A method blank was prepared in the same manner from the unspiked well water. Solvent standards were prepared in deionized water and spiked at 0.1, 0.3, 1.0, 3.0 and 10 ppb levels.

Online SPE LC/MS/MS was performed using a modified Cohesive 2300 High Throughput Liquid Chromatography system coupled to an Agilent Technologies ion trap mass spectrometer. The components of the LC system were as follows: an Agilent 1100 Series isocratic pump and autosampler, a Perkin-Elmer series 200 binary pump, and a Cohesive Technologies 2300 valve switching unit. A Cohesive Turbo-C18 (1.0 x 50 mm, 50 μ m) column was used as the online extraction column. A Metasil Basic (2.0 x 100 mm, 5 μ m) column was used as the analytical column. Four solvents were used to achieve online extraction and chromatography: loading solvent (A) = water (0.1 M ammonium acetate and 0.1% (v/v) acetic acid); extraction solvent (B) = 9:1 acetonitrile/ water; binary solvent (C) = 95:5 water/acetonitrile (v/v) with 1% acetic acid (v/v); and binary solvent (D) = 60:40 acetonitrile/water with 1% acetic acid (v/v).

The Cohesive 2300 valve switching unit has two valves: a column direction valve and a source/destination valve, which are operated independently. The system can be plumbed in either a single-column mode or dual-column mode (Figure 1). In the single-column mode, the first valve controls the direction of flow through the extraction column, while the second valve simultaneously controls the source of flow to the extraction column (binary pump or isocratic pump) and the destination of the extraction column eluent (mass spectrometer or waste). In the dual-column mode, the first valve controls direction of flow through the extraction column and diverts the flow path prior to the extraction column through a 100 μ l loop. The second valve selects the destination of the eluent from the first extraction column either to waste or to the second analytical column. Experiments for this application were conducted in dual-column mode.

The online SPE LC/MS/MS process was initiated by the injection of 1.8 ml of the spiked water samples into the analytical system. Each sample was first passed through a 0.45 μ m filter and then loaded onto the extraction column with the loading solvent (A). Elution of the analytes from the extraction column was carried out with the extraction solvent (B), which was contained in the 100 μ l loop. Although a strong organic content (90%) elution solvent is required to elute the analytes from the extraction column, it presents a problem with the subsequent retention of some analytes on the analytical column. Due to the strong organic content of (B), some of the more hydrophilic analytes will not be retained on the analytical column. Therefore, a binary solvent (C) is added post extraction column, via a mixing tee, to reduce the organic content from 90% to approximately 17%. This allows all analytes to be more efficiently retained. This was followed by a gradient chromatographic separation from the analytical column using binary solvents (C) and (D) and then introduction into the ion trap mass spectrometer for mass analysis. For these MS/MS mass determinations, the $[M+H]^+$ ion for each compound was isolated. In addition to MS/MS mode, the ion trap was also operated in full scan mode.




Figure 1. Analytical system with valve switching unit plumbed in dual-column mode

Results and Discussion

Several parameters for the MS/MS experiments on the ion trap had to be optimized in order to maximize the $[M+H]^+$ ion for each compound of interest as observed in full scan mode. Isolation times, fragmentation times, and fragmentation energies were all optimized to maximize the signal-to-noise ratio for a single product ion for each compound. For the detection of numerous target compounds, it was shown that the dual-column SPE approach was superior to the single-column configuration. The time-programmed chromatographic separation provided adequate separation for each compound, allowing MS/MS to occur with sufficient points across each peak to result in the best possible sensitivity and quantitative accuracy.

Figures 2 and 3 show a comparison of LC/UV, LC/MS (selected ion monitoring, single-quadrupole MS), and SPE LC/MS/MS (ion trap MS/MS) chromatograms of all 13 compounds at the limit of quantitation (LOQ)—200 pg/ml. Figure 2 represents the solvent standard, while Figure 3 shows the dirtiest matrix (marsh water sample). Chromatograms (A) and (B) represent 50 ng on column, while chromatogram (C) represents 400 pg on column. It can be seen that MS/MS removes the background noise allowing an increase in specificity and sensitivity for all compounds, especially in the dirtiest matrix. The 200 pg/ml LOQ could not be achieved using LC/UV or LC/MS in this matrix. Figures 4 and 5 show LC/ion trap MS/MS spectra for two representative sulfonylureas in marsh water. Ions observed for each compound, their respective RSDs, and recoveries are shown in Table 1. Table 2 shows the linearity and dynamic range over the calibration range of 100–10,000 pg/ml.




Figure 2. Chromatographic results for LC/UV (A), LC/MS (B), and SPE LC/MS/MS (C) analysis of solvent standard (0.2 ppb)




Figure 3. Chromatographic results for LC/UV (A), LC/MS (B), and SPE LC/MS/MS (C) analysis of marsh water sample (dirtiest matrix)




Figure 4. LC/ion trap MS/MS mass spectrum of metsulfuron methyl obtained from a 1 ng/ml spike of sulfonylureas in marsh water. The CID mass spectrum was generated from the $[M+H]^+$ ion.

Figure 5. LC/ion trap MS/MS mass spectrum of chlorimuron ethyl obtained from a 1 ng/ml spike of sulfonylureas in marsh water. The CID mass spectrum was generated from the $[M+H]^+$ ion.




Table 1. SPE LC/MS/MS results (LOQ = 200 pg/ml)

Compound	[M+H] ⁺ (m/z)	MS/MS Fragment Ions (m/z)	Solvent Standard		Marsh Water	
			% Recovery	% RSD	% Recovery	% RSD
Flumetsulam	326	129*, 192, 262	92	5.9	58	6.7
Oxasulfuron	407	150*, 210, 284, 258	112	9.4	95	8.0
Thifensulfuron methyl	388	141, 167*	104	13.0	62	14.0
Metsulfuron methyl	382	141, 167*	114	32.0	81	23.0
Sulfometuron methyl	365	106, 150*, 199, 333	124	18.0	85	7.2
Triasulfuron	402	141, 167*, 359	108	7.5	87	7.6
Chlorsulfuron	358	167*	73	19.0	55	9.7
Ethametsulfuron methyl	411	142, 168, 196*	110	2.8	97	7.3
Sulfosulfuron	471	165, 211*, 265	100	5.9	88	6.1
Bensulfuron methyl	411	119, 149*, 182, 213	116	5.2	102	7.1
Prosulfuron	420	141*, 167	110	2.0	78	3.3
Chlorimuron ethyl	415	186*, 213, 369	101	12.0	74	6.7
Triflurosulfuron methyl	493	238, 264*, 460	98	3.8	95	3.6

*ion used for quantitation

Table 2. Linearity and dynamic range for SPE LC/MS/MS over the calibration range of 100–10,000 pg/ml

Peak Number	Compound	Linear Correlation Coefficient	Residual
1	Flumetsulam	0.9987	2.8
2	Oxasulfuron	0.9988	17.1
3	Thifensulfuron methyl	0.9977	6.9
4	Metsulfuron methyl	0.9987	1.8
5	Sulfometuron methyl	0.9994	4.4
6	Triasulfuron	0.9990	5.2
7	Chlorsulfuron	0.9989	1.3
8	Ethametsulfuron methyl	0.9993	3.5
9	Sulfosulfuron	0.9987	7.8
10	Bensulfuron methyl	0.9971	−4.4
11	Prosulfuron	0.9968	3.6
12	Chlorimuron ethyl	0.9843	−13.6
13	Triflurosulfuron methyl	0.9970	8.7

Recoveries from the solvent-standard sample range from 73% to 124%, with percent RSDs for 11 of the 13 compounds < 15%. Both of these parameters are within acceptable EPA tolerances. The few excessively large RSDs are likely due to interfering compounds in the sample extracts. The recoveries from the marsh water sample range from 55% to 102%, with percent RSDs for 12 of the 13 compounds < 15%. It can be seen from Table 2 that the linear correlation coefficients are all < 0.985 with residuals all less than ±18%, using quadratic fits.

In comparison to the method used here, the current North Carolina State Laboratory and EPA methods for the analysis of sulfonylurea and sulfonamide herbicides include an off-line SPE pre-concentration step, a sample cleanup step with anion-exchange and alumina cartridges, and a 50-minute chromatographic separation with detection by UV and/or MS.¹ The methods employed here reduce the time of extraction and analysis by 94%.

Conclusions

This application has shown that turbulent-flow SPE is an excellent time-saving technique when combined with ion trap MS/MS for the analysis of environmental samples. Time of extraction and analysis was reduced dramatically (45 minutes vs. 765 minutes), sample size reduced (1.8 ml vs. 250 ml), and a lower LOQ (0.2 ppb vs. 2–10 ppb) was established over the current EPA method. Fouling of the mass spectrometer or analytical column due to dirty samples was also avoided.

Recovery and reproducibility are acceptable under EPA criteria; sensitivity and specificity were shown to have increased. Some loss in recoveries was noted with the dirtier matrices. This may be due to matrix effects and suppression of ionization. The increase in specificity and sensitivity provided by the use of MS/MS can partially compensate for the loss of recoveries due to matrix effects.

Future work targeting increasing trapping efficiency through the use of other SPE column dimensions and/or packing materials will attempt to further increase the time efficiency of the online analysis and allow applications to multi-residue and multi-matrix analyses.

References

1. Chau, N., and M. Roby. HPLC Determination of Selected Sulfonylurea, Sulfonamide, and Imidazolinone Herbicides in Aqueous Samples; Science Applications International Corp., **1997**.
2. Rodriguex, M. and Orescan, D. B. Confirmation and Quantitation of Selected Sulfonylureas, Imidazolinones and Sulfonamide Herbicides in Surface Water Using Electrospray LC/MS; *Anal. Chem.* 70, 2710–2717, **1998**.
3. Volmer, D., Wilkes, J. G. and Levenson, K. Liquid Chromatography Mass/Spectrometry Multiresidue Determination of Sulfonylureas after On-Line Trace Enrichment; *Rapid Commun. Mass Spectrom.* 9, 767–771, **1995**.

Authors

Robert D. Voyksner and Jennifer A. Townsend
LCMS Limited
P.O. Box 13348
Durham, NC 27709

www.agilent.com/chem

Copyright © 2001
Agilent Technologies


Information, descriptions and specifications in this publication are subject to change without notice. Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

All rights reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

Printed in the U.S.A. August 15, 2001
5988-3649EN



Agilent Technologies



The Analysis of Dioxin Using a Benchtop Mass Spectrometer Application

6890/5973 Gas Chromatograph/Mass Selective Detector

Authors

Patrick D. Perkins
Agilent Technologies Company
Palo Alto, CA 94304
USA

Abstract

Currently the analysis of dioxins uses high resolution mass spectrometry, (HRMS); often considered a prohibitively expensive technique. To move to a more cost-effective approach, improvements in the analytical method (sample cleanup and chromatographic separation) as well as improvements in sensitivity of benchtop mass spectrometers were needed.^{1, 2}

Compared to earlier generations of benchtop mass spectrometers, the 5973 mass selective detector offers measurably greater sensitivity for electron-impact-based detection due to a number of innovative enhancements.³

Analysis via the GC/MSD System

This work focused on determining the detection limit for 2,3,7,8-tetrachlorodibenzo-p-dioxin with a GC/MSD system configured as outlined in this note. The desired analytical goal was to detect 0.2 pg.

A submitted sample [5 pg/ μ L (ppb); 2,3,7,8-TCDD in 95/5 hexane/ether] was diluted by a factor of 100 with pure hexane. (The hexane was analyzed for response at the appropriate masses prior to use to verify its purity with respect to this analyte.)

For both concentrations, the mass ratio 319.9/321.9 was measured to confirm appropriate isotopic performance. Moreover, the response factors for $m/z = 321.9$ were determined for both levels and compared to verify linearity over a large concentration range.

Results

The mass ratio of 319.9/321.9 is 78%, correctly reflecting appropriate isotopic abundances. Comparing the response ratios of 0.05 pg and 5 pg injections (1 μ L each level), we observed that those were nearly equal: 24.6 and 23.0 ($2302.6 \div 100$).



Agilent Technologies

The signal/noise for the 0.05 pg injection is about 4:1 peak/peak, representing an approximate detection limit on the system used.

The conclusion is that the sensitivity of a 5973 MSD operating as an electron impact instrument is well-suited to trace analysis of dioxins, making it a cost-effective instrument for use in EPA Methods 625 and 613.⁴ For 2,3,7,8-TCDD, the detection limit with the 5973 is comparable to using HRMS. Note, however, that the ultimate method detection limits will depend on other factors — e.g., the sample matrix, type of sample cleanup used, etc. Additional sensitivity may be

possible by using large volume injection techniques.³ Future experiments will aim at evaluating the NCI (negative chemical ionization) performance of the 5973 for further gains in sensitivity and selectivity.

This will mean that a laboratory manager can choose configurations of both the chromatograph and the MSD to best match the needs of a laboratory workload. The work on the system described here demonstrated greatly enhanced sensitivity provided by cost-effective benchtop mass spectrometry.




Figure 1. The match of the spectrum for 5 pg 2,3,7,8-tetrachlorodibenzo-p-dioxin with the library search (lower panel). The match quality was 90%.





Figure 2. The TIC at m/z 321.9 for injection quantities of 5 pg (a.) and 0.05 pg (b.) in SIM mode.

6890 with 5973 MSD

Injection	• Pulsed splitless single taper liner with glass wool plug, P/N 5062-3587. • 250 °C • 1 µL injection volume • Viscosity delay, 1 sec • Sample washes, 3; post-injection solvent washes, 4
Column	HP-5MS: 30 m × 250 µm, 0.25 µm film (crosslinked 5% Ph Me Siloxane), P/N 19091S-433
Carrier	Helium, 37 cm/sec; vacuum compensation, on.
Temperature	Initial: 70 °C for 1.50 min
Program	Rate 1: 25.00 °C/min to 150 °C Rate 2: 10.00 °C/min to 280 °C Final: 280 °C for 0.00 min
Pressure	25.0 psi for 1.50 min; then
Program	1.0 mL/min constant flow rate
MSD	• Temperatures Transfer line = 300 °C Source = 230 °C Quadrupole = 106 °C • Tune = autotune • Emission current = 35 µamp • SIM mode, EMV = Autotune + 400 V • Solvent delay = 14.00 min • Dwell per ion = 125 msec • SIM Ions (<i>m/z</i>): 319.9, 321.9
Autosampler	7673B
ChemStation	G1701AA

References

1. P. R. Gardinali et al, Chemosphere 32 (1), pp. 1-11 (1996).
2. R. Malisch et al, Chemosphere 32 (1), pp. 31-44 (1996).
3. L. Doherty, "Enhancing Pesticide Analysis with a Highly Sensitive GC/MSD System," Application Note, Pub. No. (23) 5966-0370E (1997).
4. Code of Federal Regulations, Title 40, Vol. 13, Parts 136-149, Appendix A. Revised, July 1, 1997. U.S. Government Printing Office (via GPO Access; CITE: 40CFR136). Method 613 - 2,3,7,8-tetrachloro-dibenzo-p-dioxin by GC/MS (SIM). Method 625 - Base/Neutrals and Acids, Semivolatiles by GC/MS (SCAN).

For more information on our products and services, visit our worldwide website at <http://www.chem.agilent.com>.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright© 2001
Agilent Technologies, Inc.

Printed in the USA
April 2, 2001
(23) 5966-4294E



Agilent Technologies

Fast Screening of PCB Congeners Using the Agilent 6890/5973N GC/MSD System



Application

Gas Chromatography

May 2000

Authors

C. Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Michael J. Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent Technologies' fast GC/MSD method can significantly speed up the screening of PCB congeners. Agilent's GC method translation software (available free from the Agilent Technologies Web site, <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#mxlator>) was used in developing the new method based on a standard 42-min method. A 15-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS column was used to increase analysis speed up to four-fold. The time savings were implemented in increments (down to 10.5 minutes) to verify the predictability of scaling and the affect of scaling on the signal-to-noise ratio.

Key Words

RTL, PCB, polychlorinated biphenyls, congeners, environmental, screening, fast GC, method translation, 5973, 6890, MTL

Introduction

Polychlorinated biphenyls (PCBs) are a group of 209 individual compounds (known as congeners) with varying harmful effects. Chronic (long term) exposure to some PCB formulations by inhalation in humans results in respiratory tract symptoms, gastrointestinal effects, mild liver effects, and effects on the skin and eyes such as chloracne, skin rashes, and eye irritation.

PCBs are no longer produced in the United States and are no longer used in the manufacture of new products. Smaller amounts of PCBs may be released to the air from disposal sites containing transformers, capacitors, and other PCB wastes, incineration of PCB-containing wastes, and improper disposal of the compounds to open areas. Today, PCBs are still detected in water and soil due to the environmental recycling of the compound. PCBs have been detected in foods and they bio-accumulate through the

food chain, with some of the highest concentrations found in fish.

The analysis of PCBs normally is accomplished using GC with an electron-capture detector (ECD). Because of the drastically different toxicity of the different congeners, it is of great interest to identify the individual congeners using a mass spectrometer (MS).

Agilent Technologies has developed techniques to solve the peak identification problem based on Agilent's retention time locking (RTL) and a mass spectral library that contains the locked retention times and characteristic ions for all 209 PCB congeners. A GC/MSD method was developed based on a standard 42-min method¹ to screen for all congeners. A specific combination of column stationary phase, carrier-gas flow rate, and oven temperature programming is required to lock all the compounds to an expected retention timetable². Compound identification based only on spectral searching alone is difficult when the isomers have the same mass spectra.

The screening tool, integrated within Agilent's ChemStation for MSD software, searches for all 209 congeners by first checking and integrating the



Agilent Technologies

Innovating the HP Way

expected target ion within the expected time window. If the target ion is found, the software will then search and integrate the three qualifier ions within the expected time window. Last, the software will print out a report showing "hits" and "possible hits" (ratios of characteristic ions that do not match the expected values in the library within specified limits).

In order to improve laboratory productivity, we scaled the method for four-fold speed-up. While a 30-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS column is used for standard speed, a 15-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS column is used for the four-fold speed. These faster methods were able to be scaled exactly as predicted by using a combination of Agilent's method translation (MTL) and RTL software.

Often, when speeding up GC methods, an analyst trades resolution for increased analysis speed. This loss of resolution can complicate peak identification, even with a mass selective detector (MSD). However, because scaling was exact, the faster methods can be used with precisely scaled congener libraries, making the screening process even more powerful and adaptable to individual needs.

Experimental

The GC method translation software tool was used to find operating conditions for the faster methods. Figure 1 is a screen capture of the MTL software data entry showing the original conditions and the new chromatographic conditions for a four-fold speed gain. The column flow rate, which is helpful to avoid exceeding MSD pumping capacity³, also is found in the table. In this study, a turbo pump that could handle the 3.8 mL/min carrier flow was used. The program also determined the required column head pressure and corresponding oven ramp. The Agilent 6890 GC fast oven option (220/240V in the U.S.) was required

GC Method Translation - 15M-4X.MXD

Criterion: ☐ Translate Only ☐ Best Efficiency ☐ Fast Analysis ☒ None Speed gain: 4.00000

		Original Method	Translated Method	
Column				
Length,	m	30.00	☐ 15.00	
Internal Diameter,	μ m	250.0	☐ 250.0	
Film				
Thickness,	μ m	0.250	☐ 0.250	
Phase Ratio		250.0	☒ 250.0	
Carrier Gas				
Enter one Setpoint		Helium	Helium	
Head Pressure,	psi	18	☒ 18.000	
Flow Rate,	mL/min	1.9015	☐ 3.8030	
Outlet Velocity,	cm/sec	Very large	Very large	
Average Velocity,	cm/sec	50.30	☐ 100.60	
Hold-up Time,	min	0.994049	☐ 0.248512	
Outlet Pressure (absolute),	psi	0.000	☒ 0.000	
Ambient Pressure (absolute),	psi	14.696	☒ 14.696	
Oven Temperature 3-ramp Program				
	Initial	Ramp Rate	Final Temp.	Final Time
		$^{\circ}$ C/min	$^{\circ}$ C	min
	Ramp 1	25.000	150.00	0.000
	Ramp 2	3.000	200.00	0.000
	Ramp 3	8.000	280.00	10.000
		100.000	150.00	0.500
		12.000	200.00	0.000
		32.000	280.00	2.500
Sample Information Liquid				
Injected Volume,	μ L	1.0	☒ 1.0	
Split Ratio		0.00	☐ 0.41	
Effective on-Column Volume,	μ L	1.0	0.71	
Nominal Column Capacity,	μ L	0.017	0.012	

Figure 1. Screen capture showing the method translation (MTL) software data entry used in a 4X speed-gain translation.

for the faster oven ramp used in this study.

General chromatographic conditions are listed in Table 1. The RTL standard used was a mixture of pesticides and PCB congeners at 10 ppm. A 15-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS column (part number 19091S-431) was used. The head pressure determined by the method translation software (18 psi) was used as the starting point for retention time locking. The column head pressure required to lock retention times of the compounds to the library (the original retention time divided by four) was determined using the automated RTL process integrated within the Agilent ChemStation for MSD.

A very important modification to the

MS method is changing the default values of "Use mass range from" to **-0.50 to +0.50** amu (the default values are -0.3 to +0.7). The changes can be made from the "Extracted Ion Chromatograms..." dialog box selected from the "Chromatogram" on the menu bar.

Figure 2 shows the results of the shortened analysis times. The two chromatograms look extremely similar, except that the time axis is scaled proportionally. It is interesting to note that the last peak in the 4X analysis came out *before the first peak of the 1X analysis*. Because MTL followed by RTL scales methods very precisely, scaled screening libraries for corresponding time

reductions can be obtained by dividing the retention times in the library by the speed gain (which does not have to be an integer).

Conclusion

The highly accurate and reproducible pressure and temperature control of the Agilent 6890 GC allows precise scaling of a standard 42-min GC/MSD method. The run time was shortened to 10.5 minutes using a fast oven ramp rate and a 15-meter 250-micron column. The combination of MTL and RTL facilitated scaling and yielded exact scaling. RTL libraries can be scaled accurately to correspond to the faster analyses. The GC/MSD conditions used are the same as the fast pesticide method⁴, which allows for screening pesticides and PCB congeners in a single analysis.

References

1. B. D. Quimby, L.M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking," Application Note 228-401, Agilent publication number 5967-5820E, May 1998.
2. H. Prest, P. L. Wylie, K. Weiner, and D. Agnew, "Efficient Screening for Pesticides and Endocrine Disrupters Using the HP 6890/5973 GC/MSD System," Agilent publication number 5968-4884E, April 1999.
3. H. Prest, "GC Column Selection and Pumping Considerations for Electron and Chemical Ionization MSD operation," Agilent publication number 5968-7958E, November 1999.
4. C. Kai Meng and Michael Szelewski, "Fast Screening of Pesticides and Endocrine Disrupters Using the Agilent 6890/5973N GC/MSD System, Part II", Agilent publication number 5980-1057E, May 2000.

Table 1. Chromatographic Conditions

Speed	Standard	Four-fold
GC	110 V	220/240 V
Column	30-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS (part number 19091S-433)	15-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS (part number 19091S-431)
Injection mode	Splitless	Splitless
Column head pressure	18.0 psi	18.0 psi
Column flow (mL/min)	1.9	3.8
Inlet control mode	Constant pressure	Constant pressure
Carrier gas	Helium	Helium
Injector Temperature	250 °C	250 °C
Oven Temperature	70 (2 min)	70 (0.5 min)
Ramp 1	25 °C/min	100
	150 (0 min)	150 (0 min)
Ramp 2	3 °C/min	12
	200 (0 min)	200 (0 min)
Ramp 3	8 °C/min	32
	280 (10 min)	280 (2.5 min)
Oven equilibration	2 min	2 min
Injection volume	1 μ L	1 μ L
Liner	5183-4647	5183-4647

MS Conditions (Turbo pump)		
Solvent delay	3 min	0.9 min
Tune file	Atune.u	Atune.u
Low mass	50 amu	50 amu
High mass	550 amu	550 amu
Threshold	200	200
Sampling	3	1
Scans/sec	1.52	5.56
Quad Temperature	150 °C	150 °C
Source Temperature	230 °C	230 °C
Transfer line Temperature	280 °C	280 °C
Acquisition mode	Scan (EI)	Scan (EI)




Figure 2. The TICs of the standard speed and fast (4X) analyses. The standard analysis (1X) was 42 minutes long.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 5/2000
5980-1472E



Agilent Technologies
Innovating the HP Way

Fast Screening of Pesticides and Endocrine Disruptors Using the Agilent 6890/5973N GC/MSD System, Part II



Application

Gas Chromatography
May 2000

Authors

C. Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, Delaware 19808-1610
USA

Michael J. Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent Technologies' new, fast GC/MSD method can significantly speed up the screening of pesticides. Agilent's GC Method Translation software (available free from the Agilent Technologies Web site, <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#mxlator>) was used in developing the new method based on the standard 42-min method. A 15 m × 0.25 mm × 0.25 μm Agilent HP-5MS column was used to increase analysis speed up to fourfold. The time savings were implemented in increments (down to 10.5 minutes) to verify the predictability of scaling and the effect of scaling on the signal-to-noise ratio.

Key Words

RTL, pesticide, environmental, screening, fast GC, method translation, 5973, 6890, MTL

Introduction

Analysts want faster analyses to improve laboratory productivity. Often, when speeding up GC methods, an analyst will trade resolution for increased analysis speed. This loss of resolution can complicate peak identification, even with a mass selective detector (MSD).

Agilent Technologies has developed new techniques to solve the peak identification problem based on Agilent's retention time locking (RTL) and a new mass spectral library that contains the locked retention times and characteristic ions

for 567 of the most common pesticides and endocrine disruptors of concern worldwide. A GC/MSD method was developed based on the standard 42-min method¹ to screen for all 567 of the most common analytes. A specific combination of column stationary phase, carrier gas flow rate, and oven temperature programming is required to lock all the compounds to an expected retention timetable². Compound identification based only on spectral searching alone is difficult when analyzing extracts containing significant sample matrix content because of overlapping peaks and noisy baselines.

The new screening tool, integrated within Agilent's ChemStation for MSD, searches for all 567 compounds. It first checks and integrates four characteristic ions within the expected time window and then prints a report showing "hits" and "possible hits" (ratios of characteristic ions that do not match the expected values in the library within specified limits).

In Part I of the MSD fast screening application brief³, a 10 m × 0.1 mm × 0.1 μm Agilent HP-5 column was used to increase analysis speed up to fourfold. In this application brief, a 15 m × 0.25 mm × 0.25 μm Agilent HP-5MS column was used. The faster methods were scaled exactly as predicted by using a combination of Agilent's method translation (MTL) and RTL software. Because scaling was exact, these faster methods can be used with precisely-scaled pesticide libraries, making the screening process even more powerful and adaptable to individual needs.



Agilent Technologies
Innovating the HP Way

Experimental

The GC method translation software tool was used to find operating conditions for the faster methods. Figure 1 is a screen capture of MTL software data entry showing the original conditions and the new chromatographic conditions for a fourfold speed gain. The column flow rate, which is helpful to avoid exceeding MSD pumping capacity⁴, also is found in the table. In this study, a turbo pump was used, which could handle the 3.8 mL/min carrier flow. The program also determined the required column head pressure and corresponding oven ramp. The Agilent 6890 GC fast oven option (220/240V in the U.S.) was required for the faster oven ramp used in this study.

General chromatographic conditions are listed in table 1. The standard used was a mixture of 26 pesticides at 10 ppm. A 15 m × 0.25 mm × 0.25 µm Agilent HP-5MS column (part number 19091S-431) was used. The head pressure determined by the method translation software (18 psi) was used as the starting point for retention time locking. The column head pressure required to lock retention times of the compounds to the library (the original retention time divided by 4) was determined using the automated RTL process integrated within the Agilent ChemStation for MSD.

GC Method Translation - 15M-4X.MXD

Criterion: ☐ Translate Only ☐ Best Efficiency ☐ Fast Analysis ☒ None Speed gain: 4.00000

		Original Method	Translated Method
Column			
Length,	m	30.00	☐ 15.00
Internal Diameter,	µm	250.0	☐ 250.0
Film			
Thickness,	µm	0.250	☐ Unlock
Phase Ratio		250 n	☐ 0.250
			☒ 250 n
Carrier Gas		Helium	Helium
Enter one Setpoint			☒ Unlock
Head Pressure,	psi	18.000	☐ 18.000
Flow Rate,	mL/min	1.9015	☐ 3.8030
Outlet Velocity,	cm/sec	Very large	Very large
Average Velocity,	cm/sec	50.30	☐ 100.60
Hold-up Time,	min	0.994049	☐ 0.248512
Outlet Pressure (absolute),	psi	0.000	☒ 0.000
Ambient Pressure (absolute),	psi	14.696	☒ 14.696
Oven Temperature 3-ramp Program			
		Ramp Rate	Final Temp.
		°C/min	°C
			min
	Initial	70.00	2.000
	Ramp 1	25.000	150.00
	Ramp 2	3.000	200.00
	Ramp 3	8.000	280.00
			10.000
		32.000	280.00
			2.500
Sample Information Liquid			☐ Unlock
Injected Volume,	µL	1.0	☒ 1.0
Split Ratio		0.00	☐ 0.41
Effective on-Column Volume,	µL	1.0	0.71
Nominal Column Capacity,	µL	0.017	0.012

Figure 1. Screen capture showing the method translation (MTL) software data entry used in a 4X speed gain translation.

This process (first translate the method then lock the retention times) was repeated for the 2.5X time reductions.

Figure 2 shows the results of the shortened analysis times. The three chromatograms look extremely similar, except that the time axis is scaled proportionally. Because MTL followed by RTL scales methods very precisely, scaled screening libraries for corresponding time reductions can be obtained by dividing the retention times in the library by the speed gain (which does not have to be an integer). Using the same injection method (1- μ L splitless), the peak heights of the faster runs were twice those from the original

Table 1 Chromatographic Conditions

Speed	Onefold	Two and a half fold	Fourfold
GC	110 V	220/240 V	
Column	30 m × 0.25 mm × 0.25 μm HP-5MS (P/N 19091S-433)	15 m × 0.25 mm × 0.25 μm HP-5MS (P/N 19091S-431)	
Injection mode	Splitless	Splitless	
Column head pressure	18.0 psi	5.74 psi	18.0 psi
Column flow (mL/min)	1.9	1.49	3.8
Inlet control mode	Constant pressure	Constant pressure	
Carrier gas	Helium	Helium	
Injector Temp.	250 °C	250 °C	
Oven Temp.	70 (2 min)	70 (0.8 min)	70 (0.5 min)
Ramp 1	25 °C/min	62.5	100
	150 (0 min)	150 (0 min)	150 (0 min)
Ramp 2	3 °C/min	7.5	12
	200 (0 min)	200 (0 min)	200 (0 min)
Ramp 3	8 °C/min	20	32
	280 (10 min)	280 (4 min)	280 (2.5 min)
Oven equilibration	2 min	2 min	
Injection volume	1 μL	1 μL	
Liner	5183-4647	5183-4647	
MS Conditions (Turbo pump)			
Solvent delay	3 min	1.44 min	0.9 min
Tune file	Atune.u	Atune.u	
Low mass	35 amu	35 amu	
High mass	500 amu	450 amu	
Threshold	150	250	
Sampling	2	2	1
Scans/sec	3.15	3.50	6.54
Quad Temp.	150 °C	150 °C	
Source Temp.	230 °C	230 °C	
Transfer line Temp.	280 °C	280 °C	
Acquisition mode	Scan (EI)	Scan (EI)	

analysis. A faster oven ramp and the shorter column made the peaks narrower and higher, so an improvement in the signal-to-noise ratio is realized with the faster methods.

Conclusion

The highly accurate and reproducible pressure and temperature control of the Agilent 6890 GC allows precise scaling of the standard 42-min GC/MSD pesticide method. Run time was shortened to 10.5 minutes using a fast oven ramp rate and a 15-meter, 250-micron column. The combination of MTL and RTL facilitated scaling and yielded exact scaling. RTL libraries can be scaled accurately to correspond to the faster analyses.

References

1. B. D. Quimby, L.M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking," Application Note 228-401, Agilent publication number 5967-5820E, May 1998.
2. H. Prest, P. L. Wylie, K. Weiner, and D. Agnew, "Efficient Screening for Pesticides and Endocrine Disruptors Using the HP 6890/5973 GC/MSD System," Agilent publication number 5968-4884E, April 1999.
3. C. K. Meng and M. Szelewski, "Fast Screening of Pesticide and Endocrine Disruptors Using the Agilent 6890/5973N GC/MSD System," Agilent publication number 5968-9220, January 2000.
4. H. Prest, "GC Column Selection and Pumping Considerations for Electron and Chemical Ionization MSD operation," Agilent publication number 5968-7958E, November 1999.




Figure 2. The TICs of the 2.5X and 4X speedups. The standard analysis (1X) was 42 minutes long.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 5/00
5980-1057E



Agilent Technologies
Innovating the HP Way



Fast Dual-Column GC/ECD Analysis of Chlorinated Pesticides—EPA Methods 608 and 8080

Application Note
228-305

Author

Imogene L. Chang, Ph.D.
Agilent Technologies
Wilmington, DE 19808-1610

Abstract

Dual-column analysis with HP-35 and HP PAS-1701 columns was used to analyze chlorinated pesticides targeted in EPA Methods 608 and 8080 for wastewater and solid wastes. GC parameters were optimized using the Agilent 5890 Series II gas chromatograph (GC) with electronic pressure control (EPC), a dual injector, and a dual electron capture detector (ECD) system. The analysis of 18 pesticides was completed in 12 minutes.

Introduction

Currently, many testing laboratories use dual-column/dual-ECD GC systems to analyze the chlorinated pesticides specified in EPA Methods 608 and 8080^{1,2}. For this application, EPC was used with an HP-35 column (35% phenyl, 65% methyl polysiloxane phase) as the primary column and the HP PAS-1701 column for confirmation.

The unique selectivity of the HP-35 column for this set of chlorinated pesticides permitted focus on the optimization of oven temperature for the HP PAS-1701 column. Individual EPC ports for each injector permitted individual regulation of column flow for both the HP-35 and the HP PAS-1701.

Experimental

EPA Method 608 and 8080 targeted pesticides were separated using 30 m x 0.53 mm x 1.0 μ m HP-35 and HP PAS-1701 columns (part no. 19095G-123 and 19094U-023, respectively). Analyses were performed on an HP 5890 Series II GC with EPC, dual split/splitless inlets, and dual ECDs. An Agilent 7673 automatic liquid sampler was used to process the simultaneous splitless injections. A deactivated single-tapered glass liner with a small plug of glass wool (part no. 5181-3316) and a Merlin

Microseal septum (part no. 5181-8816) were used with each split/splitless inlet. Instrumentation and GC conditions are listed in **Table 1**.

A test mix containing 18 pesticides (50 ppb per component) and two surrogates was prepared from the dilution of certified standard mixes with pesticide-grade hexane (Burdick & Jackson). Pesticides in the test mix are listed in **Table 2**.

Table 1. Experimental Conditions

Instrument Requirement	
Gas Chromatograph	Agilent Technologies 5890 Series II with EPC
Injection Ports	Dual split/splitless inlets
Column	HP-35, 30 m x 0.53 mm x 1.0 μ m (Part no. 19095G-123) HP PAS-1701, 30 m x 0.53 mm x 1.0 μ m (Part no. 19095S-123)
Detector	Dual ECD
Sample Introduction	7673 automatic sampler with dual injectors
Data Collection	3365 ChemStation and HP Vectra 486/33T PC
Experimental Conditions	
Injection	Splitless 1 μ l, purge delay, 0.75 min, inlet temperature of 250°C
Carrier gas	(A) HP-35, pressure program: 8.6 psi (1 min) at 0.5 psi/min to 12 psi and at 3.0 psi/min to 25 psi (0 min) (B) HP-1701, helium, 10 ml/min constant flow
Oven	160°C (1 min) to 280°C at 10°C/min and to 300°C (2 min) at 25°C/min
Detector	ECD (300°C), 120 ml/min N ₂ makeup, 6 ml/min anode purge



Agilent Technologies
Innovating the HP Way

Results and Discussion

In a dual-column/dual-ECD system, samples introduced in a single injection can be split between two columns using a Y-connector and detected by different ECDs. However, when using a Y-connector without EPC, the split sample flow to each column cannot be optimized, and equal and consistent sample splits cannot be presumed. The only variable that can be optimized, in dual-column ECD analysis using a Y-connector is the oven temperature program, which can be optimally balanced for the two dissimilar columns. Using dual-column GC/ECD without EPC, it would typically require 45 to 60 minutes to obtain baseline separations for EPA Method 608 and 8080 targeted pesticides (see **Figure 1**).

A typical run from an environmental testing laboratory for a test mix containing 18 targeted pesticides and two surrogates is shown in **Figure 1. A**

Table 2. Chlorinated Pesticides.

Peak No.	Pesticides
1	Tetrachloro-m-xylene (SS1)
2	alpha-BHC
3	Lindane
4	beta-BHC
5	Heptachlor
6	delta-BHC
7	Aldrin
8	Heptachlor epoxide
9	Endosulfan I
10	4,4'-DDE
11	Dieldrin
12	Endrin
13	4,4'-DDD
14	Endosulfan II
15	4,4'-DDT
16	Endrin aldehyde
17	Endosulfan sulfate
18	Methoxychlor
19	Endrin ketone
20	Decachlorobiphenyl (SS2)

Yconnector was used to split samples for both columns, DB-608 and DB-1701, and good baseline separations were obtained for most analytes. This dual-column run was completed in 45 to 53 minutes using the following oven temperature program: 150°C (1 minute) to 260°C (18.34 minute) at 3°C/minute, then to 275°C (5 minutes) at 25°C/minute. Clearly this oven temperature program was optimized to separate critical pairs, such as DDE/dieldrin, DDD/endosulfan II, endosulfan sulfate/methoxychlor, and methoxychlor/endrin ketone for both columns.

Figure 2 shows chromatograms of the same pesticide test mix using the HP-35 and HP PAS-1701 columns and EPC. The oven program, 160°C (1 minute) to 280°C at 10°C/minute and to 300°C (2 minutes) at 25°C/minute, was optimized to separate the critical pairs, endosulfan




Figure 1. Typical chromatograms of a pesticides standard mix using DB-608 and DB-1701 columns under GC conditions used in environmental testing laboratories. (See Table 2 for peak identification.)




Figure 2. Chromatograms of a pesticides standard mix using HP-35 and HP PAS-1701 columns under the GC conditions listed in Table 1. (See Table 2 for peak identification.)

II/DDT and methoxychlor/endosulfan sulfate, for the HP PAS-1701 column. In this run, EPC provided a constant 10 ml/minute helium flow to the HP PAS-1701 column throughout the entire run.

For the HP-35 column, the following pressure program was used: 8.6 psi (hold 1 minute) at 0.5 psi/minute to 12 psi and at 3.0 psi/minute to 25 psi (hold for constant flow for the remainder of the run). This pressure program actually provided a 10 ml/minute constant flow to elute most of the pesticides and an increased flow (up to 20 ml/minute) near the end of the run to elute the last analyte, surrogate decachlorobiphenyl and other high-boiling materials from the column.

GC parameters optimized for dual-column/dual-injector/dual-ECD analysis of chlorinated pesticides reduced analysis time to less than

12 minutes. In addition to speed, all EPA Methods 608 and 8080 targeted pesticides and surrogates were well resolved with good sharp peaks for accurate quantitation.

Conclusion

The use of EPC permitted individual column flow control to each ECD. The unique selectivity of the HP-35 column for chlorinated pesticides permitted focus on the optimization of oven temperature for the HP PAS-1701 column. Run time was 11.5 minutes with good baseline separations for all 20 target pesticides and surrogates. The result was a reduction in sample turnaround time from 54 to 11.5 minutes for a 400% increase in productivity. This is more than a twofold improvement in productivity when compared with conventional methods currently used at many environmental testing laboratories with DB-608 and DB-1701 columns.


Acknowledgement

The author wishes to thank Ms. Joann Faulkner and her colleagues at the Pace Laboratory in Petaluma, California, for providing chromatograms and pesticide standards.

References

1. USEPA SW-846 "Test methods for Evaluating Solid Wastes," Methods 8000 and 8080, September 1986.
2. USEPA "Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater," Method 608, 1982.
3. I. L. Chang, "The Analysis of Chlorinated Pesticides and PCBs Using the HP-608 Capillary Column," Agilent Application Note 228-236, Publication No. 5091-7567E.





Validation Analysis of EPA CLP Target Organochlorine Pesticides with the Agilent 6890 Series GC and Micro-ECD

Application

Gas Chromatography

February 1998

Authors

Imogene L. Chang and
Matthew S. Klee
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Joseph Murphy
Roy F. Weston Company
Lionville Laboratory
Exton, PA 19341
USA

Abstract

Generating environmental data for organochlorine pesticides in various matrices can be time-consuming for laboratories and engineering firms. To keep a gas chromatograph/electron capture detector (GC/ECD) system operating within control limits, precious analytical time must be spent on tasks such as recalibration, reinjection of samples, detector cleaning, and reintegration of chromatographic peaks. These tasks take time away from running billable samples and adversely affect laboratory throughput.

The Agilent 6890 Series Micro-ECD used in this study shows improved performance in several key areas:

increased linear working range (greater than 4 orders of magnitude for some components), increased sensitivity (organochlorine pesticides at sub-ppb levels), increased stability, and increased resistance to contamination.

Introduction

Organochlorine pesticides (OCPs) and polychlorinated biphenyls (PCBs) are found worldwide in the environment. Because many of these pesticides are suspected to be carcinogenic and/or endocrine hormone disrupters^{1,2}, determination of their presence in water, air, soil, and food is required by governmental agencies such as the U.S. EPA, the FDA, and the World Health Organization.

The U.S. EPA provides several comprehensive guidelines^{3,4} and regulations^{5,6} for analysis of OCPs and PCBs by gas chromatography with electron capture detectors (GC/ECD). These include EPA method 8081 for wastewater/solid wastes, EPA methods 505 and 508 for drinking water/water supplies, EPA method 608 for municipal and industrial discharges, and the Contract Laboratory Program (CLP) method for waste/clean-up sites. Most contract laboratories competing for the large number of potential CLP

samples find that competition is strong and profit margins very low compared with other environmental methods.

CLP methods have very specific performance criteria that can be very time-consuming for laboratories to meet consistently. To keep a GC/ECD system operating within control limits, precious analytical time must be spent on tasks such as recalibration, reinjection of samples, detector cleaning, reintegration of chromatographic peaks, etc. Spending too much time with any of these tasks takes time away from running billable samples, and adversely affects the throughput and profitability of the laboratory.

In this study, the 6890 Series Micro-ECD greatly reduced the time required to meet CLP quality control criteria for CLP analysis of OCPs and PCBs. Validated results show four key improvements: increased linear working range (greater than 4 orders of magnitude), increased sensitivity (detecting OCPs at sub-ppb level), more stable calibration, and increased resistance to contamination (more robust, fast detector recovery and reduced maintenance).



Agilent Technologies

Innovating the HP Way

Experimental

Water and soil samples were extracted after spiking with surrogates tetrachloro-m-xylene (TCX) and decachlorobiphenyl (DBC). Extracts of OCPs were analyzed in accordance with EPA CLP method OLM03.1⁶. Typically, a 1-L volume of water sample was extracted with methylene chloride by liquid-liquid extraction or a 30-g aliquot of soil/sediment sample extracted with 1:1 acetone/methylene chloride by sonication. These extracts were concentrated and solvent-exchanged into a 10-mL volume of hexane.

Working standards for checking linearity and CLP QA/QC criteria were prepared from certified standards (available commercially) in hexane, as described in the CLP method⁵.

All analyses were performed using a 6890 Series GC with an automatic liquid sampler, a single split/splitless inlet, a pair of primary and confirmatory columns, and two 6890 Micro-ECDs. Instrument conditions are listed in table 1.

A sample extract or working standard (1 μ L) was injected into the 6890 Series GC in the splitless mode. A guard column (equivalent to a 5-m retention gap, part no. 19095-60610) was used. It was connected to a "Y" glass butt connector that split the sample equally between the pair of columns.

Column A (an equivalent of the Agilent HP-608 column) was used as the primary analytical column, and column B (an equivalent of the Agilent HP-1701 column) was used as the confirmatory column, in accordance with the CLP method.

In the case of poor chromatography or a failing control limit for inlet degradation, routine maintenance was performed. This involved changing the inlet septum, installing a new inlet liner, and clipping a short piece of the retention gap. Columns were routinely conditioned to remove late-eluting column contaminants. When CLP criteria could not be met after routine maintenance, columns were replaced with new columns of the same type.

Results and Discussion

Sensitivity

Figures 1 and 2 show chromatograms of CLP target organochlorine pesticides on column A using the GC conditions listed in table 1. All 20 OCPs in the midpoint calibration standards (mix A and mix B) were baseline resolved with both the primary analytical column (column A) and the confirmation column (column B, shown in figure 3). The amount of individual OCPs in the midpoint calibration standard was 20–40 pg on-column (methoxychlor was 200 pg). Table 2 lists the concentration of midpoint calibration standards, peak identification, and the Contract Required Quantitation Limits (CRQLs)⁶ for all CLP target OCPs.

Table 1. Experimental Conditions

Sampler	Agilent 7673, 10- μ L syringe, 1- μ L injection
Inlet	Split/splitless; 200 °C, pulsed splitless mode (28 psi for 1 min)
Carrier	Helium, 16.8 psi (150 °C); 3.5 mL/min constant flow (each column)
Column	(1) 30 m, 0.53 mm id, 0.8- μ m film DB-608, an equivalent of Agilent HP-608 (part no. 19095S-023) (2) 30 m, 0.53 mm id, 1.0- μ m film RTX-1701, an equivalent of Agilent HP PAS-1701 (part no. 19095S-123)
Oven	150 °C (0.5 min); 5 °C/min to 280 °C (5–15 min).
Detector	330 °C; makeup gas: nitrogen, constant column and makeup flow (60 mL/min)

Figures 1 and 2 also show good responses for dilute OCPs (0.25–0.5 pg on-column, 1/20th of the concentration of those for CRQLs). Quantitation at this level was easy with the micro-ECD; most OCPs exhibited a signal-to-noise ratio greater than 10 (see the lower chromatograms in figures 1 and 2). These results, confirmed by column B and the second micro-ECD (see figure 3), show that the 6890 Series Micro-ECD can easily detect low levels of OCPs (lower than 1/20 of those required by CLP). This is in good agreement with Chang⁷, who reported detection of OCPs as low as 0.050 pg on-column. However, detection of this low level is not necessary because the CRQLs⁵ range from 5 to 10 pg (methoxychlor at 50 pg) on-column (see table 2).




Figure 1. Pesticides in CLP calibration mix A on the primary column (A). 20 pg/μL (upper chromatogram) and 0.25 ng/μL (lower chromatogram) for methoxychlor (peak 9).




Figure 2. Pesticides in CLP calibration mix B on the primary column (A).

To ensure reliable results, three-point initial calibrations were routinely performed in accordance with CLP requirements using standards of 5, 20, and 80 pg/μL for lindane. Table 2 lists typical response factors and percent relative standard deviation (% RSD) for all CLP target OCPs. Typical % RSDs ranged from 2 percent for beta-BHC to 14 percent for endrin aldehyde, easily meeting the CLP criterion of 20.0 percent or less over the CLP calibration range.

Micro-ECD Linearity

Although classical electron capture detectors can provide sensitive detection, they are notorious for nonlinear response toward OCPs. For example, linearity is problematic for isomers of BHCs, particularly at the high concentration level. On the other hand, linearity as well as low response is problematic for methoxychlor, particularly at the low concentration level. These problems were not encountered using the 6890 Series GC system with micro-ECDs.




Figure 3. Pesticides on the confirmatory column (B). 20 to 40 pg/μL each, 200 pg/μL for methoxychlor.

Table 2. CLP Target Organochlorine Pesticides and Responses

	Peak	Pesticides	Mid-Level Standard pg/μL (4X)	CRQLs (on column) pg	Response Factors*	
					Average (peak height)	% Relative Standard Deviation
Mix A	1	alpha-BHC	20	5	23052	10.90
	2	gamma-BHC(lindane)	20	5	21729	6.51
	3	Heptachlor	20	5	17661	3.40
	4	Endosulfan I	20	5	15536	2.68
	5	Dieldrin	40	10	16204	4.83
	6	Endrin	40	10	10515	4.54
	7	4,4'-DDD	40	10	14334	5.06
	8	4,4'-DDT	40	10	12418	7.65
	9	Methoxychlor	200	50	4652	5.55
	21	TCX	20	50	16567	2.13
Mix B	22	DCB	40	10	5752	14.73
	10	beta-BHC	20	5	16190	2.40
	11	delta-BHC	20	5	10586	5.40
	12	Aldrin	20	5	20609	11.58
	13	Heptachlor epoxide	20	5	16482	7.01
	14	alpha-Chlordane	20	5	15929	5.20
	15	gamma-Chlordane	20	5	16527	5.69
	16	4,4'-DDE	40	10	15913	5.29
	17	Endosulfan II	40	10	16791	9.52
	18	Endrin aldehyde	40	10	8453	14.20
	19	Endosulfan sulfate	40	10	8926	5.59
	20	Endrin ketone	40	10	2144	3.39
	21	TCX	20	5	10114	3.01
	22	DCB	40	10	5667	14.97

* Typical three-point calibration from column A (concentrations: 1X, 4X, and 16X)

Linearity of the micro-ECD was determined by analyzing a series of dilutions of OCPs at concentrations ranging from 0.1 pg/μL to 3.2 ng/μL for lindane (see the 15-level calibration in table 3). For most OCPs, correlation coefficients were better than 0.99 over a concentration range greater than 5 orders of magnitude (0.1 to 3.2 pg/μL for lindane).

Table 3. Linearity Study

Pesticides		15-Point Calibration		10-Point Calibration			
		Concentration pg/μL	Correlation Coefficients	Concentration pg/μL	Response Factors		Correlation Coefficients
					Average	% Relative Standard Deviation	
Mix A	alpha-BHC	0.1 to 32,000	0.995	1 to 1,600	52,557	19.3	0.998
	Lindane	0.1 to 32,000	0.997	1 to 1,600	46,635	17.3	0.997
	Heptachlor	0.1 to 32,000	0.997	1 to 1,600	35,712	18.0	0.997
	EndosulfanI	0.1 to 32,000	0.997	1 to 1,600	31,858	13.9	0.998
	Dieldrin	0.2 to 64,000	0.995	2 to 3,200	35,718	19.0	0.995
	Endrin	0.2 to 64,000	0.992	2 to 3,200	24,849	19.5	0.996
	4,4'-DDD	0.2 to 64,000	0.995	2 to 3,200	33,903	17.3	0.996
	4,4'-DDT	0.2 to 64,000	0.992	2 to 1,600	20,618	18.2	0.993
	Methoxychlor	1 to 320,000	0.990	10 to 4,000	8,199	16.1	0.998
	TCX	0.1 to 32,000	0.997	1 to 1,600	72,423	10.8	0.998
DCB	0.2 to 64,000	0.996	2 to 3,200	23,956	17.2	0.998	
Mix B	beta-BHC	0.1 to 32,000	0.995	1 to 1,600	21,388	11.6	0.998
	delta-BHC	0.1 to 32,000	0.993	1 to 1,600	47,532	17.0	0.997
	Aldrin	0.1 to 32,000	0.994	1 to 1,600	35,851	14.3	0.997
	Heptachlor epoxide	0.1 to 32,000	0.994	1 to 1,600	36,234	11.9	0.998
	alpha-Chlordane	0.1 to 32,000	0.995	1 to 1,600	34,958	12.2	0.997
	gamma-Chlordane	0.1 to 32,000	0.995	1 to 1,600	35,250	11.3	0.997
	4,4'-DDE	0.2 to 64,000	0.989	2 to 3,200	40,065	18.6	0.996
	Endosulfan II	0.2 to 64,000	0.991	2 to 1,600	24,212	16.4	0.997
	Endrin aldehyde	0.2 to 64,000	0.990	2 to 3,200	18,628	16.6	0.995
	Endosulfan sulfate	0.2 to 64,000	0.992	2 to 3,200	27,644	14.7	0.996
	Endrin ketone	0.2 to 64,000	0.990	2 to 3,200	20,803	13.6	0.996

For a smaller concentration range (3 orders of magnitude), correlation improved and % RSDs of calibration factors for most OCPs were within 20 percent as required by CLP (see the 10-point calibration in table 3). Figure 4 shows a linear curve for lindane (1 to 1,600 pg/ μ L), typical of most OCPs in this concentration range. Figure 4 also shows the linear curve for methoxychlor (10 to 4000 pg/ μ L), a pesticide that typically responds poorly to classical ECD. This concentration range, typically from 1 to 1,600 or from 2 to 3,200 pg/ μ L for most OCPs, represents a 100-fold improvement over that required by CLP (CLP specifies 5 to 80 pg/ μ L for lindane). This wider linearity range allows more analyses for samples without requiring rework (dilution/concentration and re-analysis). If dilution of samples is required, the higher linearity of the detector results in more accurate estimations of correct dilution factors to bring sample concentrations within the CLP range.

Calibration Stability and System Robustness

The 6890 Series GC system with 6890 Micro-ECDs was regularly calibrated in accordance with CLP requirements. Analyses of blanks, continuous calibration using the midlevel standards, and performance evaluation mix were performed for each 12 hours of operation or every 10 to 20 samples. If results of these analyses failed to meet CLP breakdown, retention time, and response criteria, routine maintenance (such as changing inlet septum and liner or clipping a few inches off the guard column) was performed. If necessary, the instrument was recalibrated (using a three-point initial calibration). No cleaning or baking of the micro-ECD was required, even though a wide variety of samples was analyzed, including some dirty soil extracts⁸.




Figure 4. Linear calibration curves for lindane and methoxychlor over extended ranges.

At a minimum, CLP requires that system stability be monitored by analyzing midpoint calibration standards every 12 hours. In this study, system (or calibration) stability was based on verification of the calibration factors and retention times of target OCPs to match those from the initial calibration run within specific limits. The difference in calibration response (RPD—relative percent difference) between the later midpoint calibration run and the initial calibration run must be less than ± 25 percent (upper and lower RPD control limits).

Figure 5 is a continuous calibration verification (CCV) control chart of RPD for lindane and methoxychlor on column A over a 6 month period, typical of most OCPs on both column A and column B.

Throughout this study, the system was within RPD control limits and other calibration verification criteria for several days at a time without per-

forming any re-calibration. When any OCP failed to meet CLP calibration verification criteria (that is, when an OCP was outside the RPD control limits of the CCV), nonintrusive system maintenance was conducted and a new initial calibration was performed. These steps were also done when the instrument was switched for 1 or 2 weeks to analyze a different type of sample, requiring a different GC method. When the instrument was switched back to the original CLP analysis of OCPs and PCBs, the instrument still met calibration verification criteria (within the RPD control limits). This represents a significant improvement over previous designs that usually required full recalibration after switching between methods and indicates that using the micro-ECD saved time and improved laboratory productivity.

Over a period of 6 months, the 6890 Series GC/dual micro-ECD system was in continuous operation

and performed several different methods. For example, the system was used for 2 to 3 weeks to analyze pesticides and aroclors by the CLP method and solid waste method (EPA method 8081). The system was then switched to a drinking water method⁸ for a few weeks and later returned to the CLP method for OCPs. In other instances, the system was switched to analyze herbicides (EPA method 8150), then to drinking water (EPA method 504), and back again to the CLP method or method 8081 for OCPs and aroclors. In each case, the stabilization of the micro-ECDs was fast, requiring only a few injections of hexane blanks prior to running the CCV calibration standards.

Throughout this study (which included continuous operations over 6 months), even though routine column and inlet maintenance was needed (columns were replaced once during the course of the study), no micro-ECD maintenance was needed.

Conclusion

The improved performance of the Agilent 6890 Series GC/dual micro-ECD system met all CLP criteria for the analysis of OCPs over a period of 6 months. System validation was performed throughout this period for a wide variety of samples and analyses of different EPA methods. The 6890

Series GC with micro-ECDs easily met and maintained CLP criteria during the study. In addition, the micro-ECD showed improved sensitivity, greater dynamic and linear operating ranges, and more stable response. Moreover, it required minimal maintenance, and showed rapid recovery after switching between methods. Use of the Agilent 6890 Micro-ECD has a high potential to save time, improve quality of data, and increase laboratory productivity.




Figure 5. CCV control chart demonstrating stability of response and performance during the study.

References

1. U.S. Environmental Protection Agency, *Special Report on Environmental Endocrine Disruption: An Effects Assessment and Analysis, Risk Assessment Forum*, EPA/630/R-96/012, February 1997.
2. Colborn, T., Dumanoski, D., and Myers, J. P., *Our Stolen Future*, Penguin Books UAA Inc., New York, NY, 1996.
3. U.S. Environmental Protection Agency, *Methods for the Determination of Organic Compounds in Drinking Water*, Methods 505 and 508, rev 2.0, 1991.
4. U.S. Environmental Protection Agency SW-836, "Organochlorine Pesticides and PCBs as Aroclors by Gas Chromatography: Capillary Column Technique," Method 8081, *Test Methods for Evaluating Solid Wastes, Physical and Chemical Methods*, third edition, 1994.
5. U.S. Environmental Protection Agency, *Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater*, Method 608, EPA-600/4-82-059, 1982.
6. U.S. Environmental Protection Agency, "Statement of Work for Organic Analysis," *Contract Laboratory Program*, OLM03.1, August 1994.
7. Channel, I., and Chang, I. L., "Analysis of Organochlorine Pesticides and PCB Congeners with the Agilent 6890 Micro-ECD," Agilent Technology, Application Note 228-384, Publication No. (23) 5965-8556E, June 1997.
8. Chang, I. L., and Murphy, J., "Analysis of EDB and DBCP in Water with the 6890 Series Gas Chromatograph and 6890 Micro-Electron Capture Detector, EPA Method 504," Agilent Technology, Application Note 228-385, Publication No. (23) 5966-0495E, August 1997.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 4/2000
5966-3742E



Agilent Technologies
Innovating the HP Way

Trace Level Pesticide Analysis by GC/MS Using Large-Volume Injection



Application

Gas Chromatography

September 1997

Author

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Large-volume injection (LVI) using the Agilent programmable temperature vaporizing (PTV) inlet can improve gas chromatography system detection limits by one to two orders of magnitude over standard methods that call for 1- or 2- μ L injections. An Agilent 6890 Series gas chromatograph (GC), configured with a PTV inlet, a 6890 Series automatic liquid sampler (ALS), and an Agilent 5973 mass selective detector (MSD), was used for the analysis of pesticides in standards and several food extracts. By making 100- μ L injections, several pesticides could be identified by scanning gas chromatography/mass spectrometry (GC/MS) at the 100 ppt (100 ng/L) level. The PTV inlet tolerated dirty food extracts very well; more than 1,500 μ L of such samples

were injected into a single PTV liner. This application note includes recommendations for doing LVI using the PTV/6890/5973 GC/MSD system.

Introduction

More than 700 pesticides are registered for use in the world¹, and many more continue to persist in the environment, even though they are no longer being applied. For the protection of human health and the environment, pesticide residues are routinely monitored in food, water, soil, and tissue samples. "Acceptable" residue limits have been set for various foods and environmental samples by agencies such as the United States Environmental Protection Agency (U.S. EPA), the Codex Alimentarius Commission², and many other governmental organizations around the world. A great many methods have been developed to screen for pesticides in food³⁻⁷ and the environment⁸⁻¹⁰ to ensure that risks associated with pesticide use are minimized.

Recently, concern has increased that certain pesticides and other synthetic chemicals may be acting as pseudo hormones which disrupt the normal function of the endocrine system in wildlife and humans. Birth defects, behavioral changes, breast cancer, lowered sperm counts, and reduced intelligence are among the many disorders that have been blamed on these "endocrine disrupting" compounds, though much research must be done to verify these assertions. In 1996, Colborn, Domanoski, and Myers¹¹ brought these issues into the public spotlight with the publication of their book *Our Stolen Future*. Recently, the United States Congress passed legislation calling for increased testing of suspected endocrine disrupters and monitoring their levels in food¹² and water¹³ supplies. Because the endocrine system can be exquisitely sensitive to extremely low hormone concentrations, there is a need to measure concentrations of suspected endocrine disrupters (many of which are pesticides) at very low levels. Initiatives such as the Pesticide Data Program, developed by the United States Department of Agriculture¹⁴, seek to



Agilent Technologies

Innovating the HP Way

determine the lowest measurable pesticide levels in various foods to develop a total exposure model. Clearly, there is pressure to push pesticide detection limits to even lower levels than are routinely achieved today. Most residue measurements are made by gas chromatography using a variety of element-selective or mass spectral detectors (GC/MS). Therefore, to achieve lower detection limits, it is necessary to improve the detection limits of these GC methods.

In GC, there are primarily four ways to improve method detection limits: 1) increase the concentration of analytes in a sample, usually by reducing the volume of an extract; 2) increase the sensitivity of the detector; 3) increase the selectivity of the detector to reduce chemical background "noise" or 4) increase the volume of sample injected. Because GC/MS can be highly selective and extremely sensitive, it is often the method of choice for pesticide analysis and/or confirmation. However, for the reasons discussed above, there are occasions when even greater sensitivity is required. This application note describes a method for increasing GC/MS system detection limits by making large-volume injections (LVI) using Agilent's new programmable temperature vaporizing (PTV) inlet. Because this LVI technique is detector-independent, it is applicable to other GC configurations that may be used for pesticide residue analysis.

Experimental

Pesticide Standard Solution

Stock solutions of 14 pesticides were prepared at 1 mg/mL by adding 10 mg each of trifluralin, hexachlorobenzene, pentachloronitrobenzene, dichloran, chlorothalonil, chlorpyrifosmethyl, chlorpyrifos, endosulfan

I, p,p'-DDE, propargite, iprodione, methoxychlor, and fenvalerate (mix of isomers I and II) to individual 20mL vials and diluting with 10.0 mL of acetone. Permethrin was obtained as a mixture of permethrin I and permethrin II comprising 32 percent and 27 percent of the sample, respectively, so 16.95 mg of this mixture was diluted with 10 mL of acetone giving a solution in which the combined permethrins represented 1 mg/mL. A stock mixture was prepared by adding 4 mL of the permethrin and fenvalerate solutions and 1 mL of each of the other stock solutions to a 100-mL volumetric flask and diluting to volume with acetone. The resultant solution contained 40 ng/ μ L each of the combined permethrin and fen-

valerate isomers and 10 ng/ μ L each of the other 12. This sample was diluted further with acetone to prepare standards that were analyzed by LVI. All these pesticides were obtained in neat form from Chem Service (West Chester, PA USA).

Extracts

Fruit and vegetable extracts were obtained from the Florida Department of Agriculture and Consumer Services (Tallahassee, FL USA). Commodities were extracted using a version of the Luke procedure¹⁵⁻¹⁷ that gave a final sample representing 1.75 g of the commodity per mL of extract.

Table 1. Instrumentation and Conditions Used for Pesticide Samples

GC/MS System	
Gas chromatograph	6890 Series GC
Automatic liquid sampler	6890 Series ALS
Mass spectral detector	5973 Series MSD
Programmable temperature vaporizing inlet	PTV with CO ₂ cooling
Computer for data acquisition and analysis	HP Vectra XU 6/200
Software	G1701AA Version A.03.00 running Microsoft® Windows™ 95
Column	30 m x 0.25 mm x 0.25 μ m Agilent HP-5MS
Instrumental Conditions	
GC Parameters	
Carrier gas	Helium
Inlet liner	Prototype deactivated borosilicate with fritted glass on interior walls (part no. 5183-2041)
Syringe size	50 μ L
Injection volume	100 μ L (Inject 10 μ L 10 times)
Injection delay	12 sec
Inlet temperature program	40 °C (4.2 min), 200 °C/min to 320 °C (2 min)
Vent flow	400 mL/min Vent pressure 0.0 psi for 4.00 min
Purge flow to split vent	50.0 mL/min at 6.50 min
Column head pressure	0 psi (4 min) then 17.3 psi (constant pressure)
Oven temperature program	50 °C (6.13 min), 30 °C/min to 150 °C (2 min), 3 °C/min to 205 °C (0 min), 10 °C/min to 250 °C (20 min)
MSD Parameters	
Acquisition mode	Scan (35-550 amu)
Temperatures	Transfer line = 280 °C, MS quad = 150 °C, MS source = 230 °C

Instrumentation

Table 1 lists the instrumentation and chromatographic conditions used for LVI and GC/MS analysis of pesticide samples.

Brief PTV Tutorial

Before focusing on the PTV/GC/MS analysis of pesticides, it is important to understand how the PTV inlet operates in the solvent vent mode for large-volume injections.

The PTV Inlet

The PTV inlet has the same basic functions as the split/splitless inlet except that it is temperature programmable from -60 °C (using CO₂ cooling) or -160 °C (using liquid N₂ cooling) to 450 °C at rates up to 720 °C/min. However, the PTV's design has been optimized for its main uses—LVI and cold split/splitless injection. Although hot split and splitless injections may be made with or without a pressure pulse, care must be taken not to exceed the small internal volume of the PTV inlet. In practice, it is best to choose the Agilent split/splitless inlet for hot injections and the PTV inlet for LVI and cold split/splitless techniques.

Most GC pesticide methods call for injecting 1–2 µL; splitless injection is used because it is compatible with dirty extracts of food, soil, or water. Pulsed splitless injection allows one to make injections of up to 5 µL using standard equipment¹⁸. Enormous gains in system sensitivity can be realized by using the PTV inlet in the "solvent vent" mode, which is compatible with injections of 5–1,000 µL. These large injections may be made manually or automatically using either a standard 6890 Series ALS in the multiple injection mode or by using a controlled speed injector available from Gerstel¹⁹. Because the injection process may take several minutes,

manual injections are usually impractical and good precision may be hard to achieve.

The 6890 Series ALS is designed to make one or more injections of up to 25 µL into the PTV inlet. After the desired number of injections has been made, the inlet is heated and the chromatography begins. Though the system controls allow up to 99 injections, a reasonable upper limit is about 10, making 250 µL the typical injection volume limit for this system. For even larger injections, the controlled speed injector¹⁹ should be used. For all of the analyses described below, 100 µL were injected by making 10 sequential injections of 10 µL each.

How the PTV Works in the Solvent Vent Mode

Figure 1 shows a diagram of the PTV inlet. For large-volume injections, three steps are required. These are: 1) injection and solvent elimination; 2) splitless sample transfer to the GC column; and 3) chromatographic separation and, if desired, a simultaneous inlet bake-out step. The steps are described more completely below.

Injection and Solvent Elimination (Step 1)

During injection, the column head pressure is set to 0 psi to eliminate or, in the case of GC/MS, reduce the flow through the column. When mass spectral detection is used, there is still






Figure 1. The PTV inlet shown with the septumless head. The inlet is also available with a septum head that may be equipped with a standard septum or a Merlin Microseal. (Figure reproduced with permission of Gerstel GMBH.)

some flow because the column outlet is under vacuum. At the same time, a steady stream of carrier gas passes through the inlet and out through the split vent. This flow is typically between 100 and 500 mL/min. The sample is injected into the cool liner where it remains as a liquid, dispersed over the liner walls or any packing material that may be in the liner. The steady flow of carrier gas through the liner causes the solvent (and any volatile fraction of the sample) to evaporate and be swept with the carrier gas out through the split vent. This is analogous to "blowing down" a sample with a stream of inert gas, except that this takes place inside the PTV inlet. When most of the solvent has evaporated, the next injection is made and the evaporation process repeats, accumulating more sample in the inlet. To recover an analyte completely, its boiling point should be at least 100 °C greater than that of the solvent; most pesticides fall into this category.



A Sample is injected too rapidly



B Solvent evaporates completely between injections

Figure 2. Chromatograms A and B illustrate the result of poor timing of multiple injections.

The timing of these multiple injections can be important. If the sample is introduced too rapidly, the liner may become flooded and liquid will be forced out through the split vent. Chromatographically, this shows up as reduced area counts for all analytes (see figure 2A). If there is too much time between injections, all of the solvent may evaporate and more of the volatile analyte fraction may be lost too. This results in poor recovery of volatiles but 100 percent recovery of the less volatile compounds (see figure 2B). Set-points such as inlet temperature, vent flow, and injection delay times can affect recovery of volatiles. Note that for 100 percent recovery, an analyte should have a boiling point at least 100 °C greater than the solvent. One can adjust the delay between injections by entering the desired value in the ChemStation software. Some experimentation is usually necessary when setting this delay for a new method. It will be dependent upon such factors as the solvent type, injection volume, vent flow, and inlet temperature.

Splitless Sample Transfer to the GC Column (Step 2)

Once the desired number of injections has been made, the column head pressure is restored and the vent flow is turned off. At this point, the inlet temperature is programmed up to a value that is sufficient to transfer all of the desired analytes to the GC column. This step is similar to

a splitless injection, except that instead of flash vaporization, the sample is transferred as the inlet temperature is programmed up. For the most gentle treatment of labile analytes, slow ramp rates may be used. This allows analytes to be flushed into the column at the minimum temperature needed for volatilization. When sample decomposition is not a problem, the inlet may be heated as fast as 720 °C/min.

Chromatographic Separation (Step 3)

During sample transfer, the oven temperature is usually held between 30 °C below and 20 °C above the solvent's atmospheric boiling point, depending on whether the solvent effect is needed to focus the more volatile fraction of the analytes. Again, some experimentation is necessary to optimize peak shapes. After the sample has been transferred in step 2, the oven temperature is programmed up and chromatography begins.

After the inlet has reached its maximum temperature and sufficient time has elapsed to transfer the sample to the column, a purge flow of 30-50 mL/min is restored to the split vent. If desired, one can set a very large split flow for a few minutes and bake out the inlet at a higher temperature to remove nonvolatile impurities. To conserve carrier gas, gas saver should be turned on at the end of this bake-out step.

Entering PTV Inlet Parameters into the Agilent ChemStation

When preparing the PTV portion of a GC method, one should first decide on the sample size and how many injections are required. In this work, ten 10- μ L injections were made for a total of 100 μ L. When entering parameters into the ChemStation screen, the Injector icon is first selected (figure 3) under the "GC edit parameters" menu. Next, the Configure button is pressed to enter the syringe size and enable multiple injections. From the main injector screen, the injection volume (10 μ L) and number of injections are entered¹⁰. For this work, a 12-second delay was chosen between injections to allow for solvent evaporation.

The estimated total injection time is listed on the Inlets screen (figure 4). This is helpful when setting the inlet and oven parameters. First, the vent flow rate (400 mL/min for these analyses) is chosen, which sets the vent pressure to 0 psi until the injection sequence is done and solvent from the last injection has largely evaporated (4.00 min in figure 4). This is done by entering these values in the following fields:

Vent Flow 400 mL/min
Vent pressure 0.0 psi until
4.00 min

Next, the purge flow and elapsed time are set by entering values in the following field:

Purge Flow to Split Vent
50.0 mL/min @ 6.50 min

Note that as an aid in setting up the method, the "estimated total injection time" is shown just above the previous data entry fields.

In this example, the normal column head pressure was restored and the vent flow was turned off at 4.00 min. This prepares the inlet for the splitless transfer of the sample to the column. The vent flow remained off until it was set to 50 mL/min at 6.5 min. Thus, there is a 2.5-min period for inlet temperature

programming and splitless sample transfer to the column. In this example, the inlet was held at 40 °C for 4.2 min, enough time to make 10 injections, turn off the purge flow, and restore the column head pressure; the PTV was then programmed to 320 °C at 200 °C/min (figure 4).




Figure 3. The injector screen from Agilent GC and GC/MS ChemStation software showing the setpoints available for multiple injections. To configure the sampler for multiple injections, set the syringe size, and choose slow injection, click on the Configure button.




Figure 4. The inlets screen from Agilent GC and GC/MS ChemStation software showing the setpoints available for operation of the PTV inlet in the solvent vent mode.

Although not done for these analyses, the inlet could be baked out by setting the "purge flow to split vent" to a large value (perhaps 500 mL/min) at the end of the splitless time (6.50 min) and at the same time, program the inlet to a higher temperature. After the bake-out period, the inlet temperature is programmed downward and gas saver is turned on.

Normally, the GC oven is held at its starting temperature until the splitless injection is complete (6.50 min in this case) at which time oven temperature programming is begun. For this work, the oven temperature program was begun at 6.13 min so that the pesticide retention times would match a retention time data base that was in use. Figure 5 diagrams the PTV and GC oven setpoints used for this work.

PTV Inlet Liner Considerations

The correct liner choice is critical to the success of any pesticide analysis by PTV injection. The liner must be thoroughly deactivated or many labile pesticides may decompose or adsorb in the inlet. In general, any liner containing glass wool will be unsatisfactory for the analysis of labile pesticides, whether or not the glass wool is deactivated. At this time, two PTV liners are suggested for pesticide analysis:

- Part no. 5183-2037 is a deactivated, open multibaffled liner with no internal packing that may be used for single or multiple injections of 5 μ L or less. This liner gives very good recovery for pesticides, even extremely difficult ones such as acephate and methamidophos.

- Part no. 5183-2041 is a deactivated liner with an internal coating of sintered glass to give it more surface area and is, therefore, suitable for single or multiple 25- μ L injections. This liner gives better than 70 percent recovery for most pesticides, although tests have shown that acephate and methamidophos cannot be analyzed using this liner, and that recoveries of guthion are often less than 50 percent. A prototype version of this liner was used for all of the work described in this application note.






Figure 5. Illustration of the GC and sampler setpoints used for 100- μ L injections of pesticide samples. Note that normally, the GC oven hold period would have been at least 6.5 min for this method. A value of 6.13 min pesticide retention times to a data base.

Results and Discussion

When compared to a typical 2- μ L splitless injection, 100- μ L PTV injections can often result in a 50-fold improvement in system detection limits. Selective detectors such as the MSD can help the analyst to realize the full measure of this sensitivity improvement by excluding background that may be introduced from solvent impurities, vial cap extract, and indigenous compounds coextracted with the analytes. In this application, it was possible to see most of the pesticides in the 14-component mixture at 100 ppt in the scan mode (400 ppt for the isomer mixes of permethrin and fenvalerate). Figure 6 shows extracted ion chromatograms for trifluralin and hexachlorobenzene (HCB) at 100 ppt. Library searching gave a match quality of 93 for the HCB peak. Fenvalerate isomers I and II were found in the solution in a ratio of about 78:22. Figure 7 shows extracted ion chromatograms for fenvalerate I at a concentration of 311 ppt.



A Extracted ion current chromatograms of trifluralin



B Extracted ion current chromatogram of HCB with its mass spectrum and library match

Figure 6. Scanning GC/MS results for a pesticide standard containing Trifluralin and Hexachlorobenzene at 100 ppt. (Ten 10- μ L injections were made using the PTV inlet.)




Figure 7. Extracted ion current chromatograms of Fenvalerate I at a concentration of 311 ppt in a pesticide standard. (Ten 10- μ L injections were made using the PTV inlet.)

Analysis of a bell pepper extract revealed several pesticide residues. As seen in figure 8, chlorpyrifos and the endosulfans were easily detected. The Florida Department of Agriculture determined the concentration of chlorpyrifos, alpha-endosulfan, beta-endosulfan, and endosulfan sulfate to be 0.210, 0.011, 0.018, and 0.013 ppm, respectively. It is important to note that these compounds could be detected with very high selectivity by extracting high mass ions that are characteristic of these pesticides but not of the matrix. Using LVI, there is ample signal from these less abundant ions for good quantitation. With normal injection volumes, selectivity may have to be compromised and the most abundant ions extracted in a pesticide spectrum to gain sensitivity.

Phosmet, captan, and propoxur were all easily detected in a pear sample. The total ion current chromatogram (TIC) is shown in figure 9 along with spectrum obtained for captan juxtaposed with the library spectrum. Figure 10 shows the propoxur peak along with 2,4,6-tribromoanisole and 2,4,6-tribromophenol, two other compounds that were surprising to find in a pear sample. Though the origin of these brominated compounds is not known, a recent paper by Hoffmann and Sponholz 20 suggests that tribromophenol is used to treat storage pallets for the prevention of fire and mold growth, and that the anisole is formed from the phenol microbiologically. Perhaps these pears were shipped in containers that had been similarly treated.




Figure 8. GC/MS Analysis of a bell pepper extract. (Ten 10- μ L injections were made using the PTV inlet.) Using LVI, there was sufficient signal to use high mass ions with smaller abundances to achieve greater selectivity.




Figure 9. TIC of a pear extract resulting from a 100- μ L Injection (10 x 10 μ L). Captan was easily detected, and its spectrum gave a library match quality of 96.




Figure 10. TIC of a pear extract resulting from a 100- μ L Injection (10 x 10 μ L). Propoxur and two brominated phenolics were easily identified.

A single sintered glass coated liner of the type described above (part no. 5183-2041) was used for about ten 50- and ten 100- μ L injections (ca. 1,500 μ L total) of vegetable extracts before it was replaced. All of the extracts were rather dirty, and an inlet bake-out step was not used. Although the liner looked somewhat discolored for about 2 cm where injections were made, it still performed well at the time it was replaced.

Conclusion

Using the PTV inlet in the solvent vent mode, it is relatively simple to increase system detection limits by one or two orders of magnitude. When combined with the Agilent 6890 Series automatic liquid sampler,

multiple injections of up to 25 μ L each into the inlet can be made, allowing the solvent to vent while pesticides and other less volatile analytes accumulate. After the desired sample volume has been introduced (typically 5-250 μ L), the solvent vent is closed and the sample is transferred to the column in a temperature-programmed splitless injection. By making 100- μ L injections into a PTV-equipped Agilent 6890 Series GC coupled to the Agilent 5973 MSD, it was possible to see several pesticides at the 100 ng/L level (100 ppt) in the scan mode. With such low detection limits, less abundant ions can be used to identify and quantitate pesticides at low ppb levels, thereby gaining in selectivity as well.

When performing LVI, there are several parameters to adjust and some method development time is usually required. However, the method described herein worked well and can be duplicated for the PTV/GC/MS analysis of pesticides in food.

Acknowledgment

The author wishes to thank Ms. Joanne Cook of the Florida Department of Agriculture and Consumer Services for supplying the food extracts used in these experiments and Dr. Bill Wilson (Agilent Technologies) for supplying liner deactivation test results.

References

1. Tomlin, Clive, ed (1994), *The Pesticide Manual, Tenth Edition*, British Crop Protection Council, Surry, UK.
2. Miller, R. W., *This is Codex Alimentarius*, Secretariat of the Joint FAO/WHO Food Standards Programme, Food and Agriculture Organization of the United Nations, Rome.
3. McMahon, B. M. and Hardin, N. F. eds. (1994), *Pesticide Analytical Manual, Vol I, Third Edition*, U.S. Food and Drug Administration, Washington, DC.
4. Lee, S. M., Papathakis, M. L., Feng, H.-M. C., Hunter, G. G., and Carr, J. E. (1991), *Fresenius' A. Anal Chem* 339, 376-383.
5. Fillion, J., Hindle, R., Lacroix, M., and Selwyn, J. (1995), *J AOAC Int* 78, 1252-1266.
6. Working Group on Development and Improvement of Residue-analytical Methods (1996), *Analytical Methods for Pesticide Residues in Food-stuffs*, General Inspectorate for Health Protection, Ministry of Public Health, Welfare & Sport, The Netherlands.
7. Luke, M. A., Froberg, J. E., Doose, G. M., Masumoto, H. T. (1981), *J Assoc Off Anal Chem* 64, 1187-1195.
8. Stan, H. J., ed. (1995), *Analysis of Pesticides in Ground and Surface Water II*, Springer-Verlag, Berlin, Germany.
9. Wagner, R. E., Kotas, W., and Yogis, G. A., eds. (1994), *Guide to Environmental Analytical Methods, 2nd Edition* Genium, Schenectady, NY.
10. U.S. Environmental Protection Agency, *Test Methods for Evaluating Solid Waste, SW-846, Draft Method 8085: Pesticides by GC/AED*.
11. Colborn, T., Dumanoski, D., and Myers, J. P. (1996), *Our Stolen Future*, Penguin, New York, NY.
12. *Food Quality Protection Act of 1996*, Public Law 104-170, Congressional Record pp. H8127-H8141.
13. *Safe Drinking Water Act Amendments of 1996*, Public Law 104-182, Congressional Record pp. H9680-H9700.
14. *Pesticide Data Program Annual Summary Calendar Year 1994*, U.S. Department of Agriculture, Agricultural Marketing Service, Washington, DC.
15. Luke, M. A., Froberg, J. E., Doose, G. M., and Masumoto, H. T. (1981), *J Assoc Off Anal Chem* 64, 1187-1195.
16. Luke, M. A., and Doose, G. M. (1983), *Bull Environ Contamin Toxicol* 30, 110-116.
17. Sawyer, L. D. (1985), *J Assoc Off Anal Chem* 68, 64-71.
18. Wylie, P. L., Phillips, R. J., Klein, K. J., Thompson, M. Q., and Hermann, B. W. (1991), *J High Resol Chromatog* 14, 649-655.
19. The controlled speed injector is available from Gerstel US, 1510 Caton Center Dr., Baltimore, MD 21227 USA.
20. Hoffmann, A. and Sponholz, W. (March 1997), *American Laboratory*, 22-23.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Microsoft is a U.S. registered trademark and Windows™ is a U.S. trademark of Microsoft Corporation.

HP® is a registered trademark of Hewlett-Packard Company.


Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 4/2000
5966-1214E



Agilent Technologies

Innovating the HP Way



The Analysis of Chlorinated Pesticides and PCBs Using the HP-608 Capillary Column

Application Note
228-236

Authors
Imogene L. Chang, PhD
Winfred J. Sanders, PhD

Abstract

Chlorinated pesticides and PCBs targeted in EPA Methods 608, 8080, 8081, and CLP pesticides for wastewater and solid wastes are analyzed under optimum conditions at a constant flow of 2.4 ml/min. The merits of splitless and on-column injection techniques using the Agilent 5890 Series II GC with electronic pressure control (EPC) are compared.

Key Words: chlorinated pesticides, PCBs, on-column injection, splitless injection, HP-608 capillary column, EPA 608, EPA 8080/8081, CLP pesticides, electronic pressure control.

Introduction

Chlorinated pesticides and PCBs have been banned in the U.S. for several years. However, because of their persistence in the environment, EPA methods 8080/8081 and CLP pesticides target 16 to 20 chlorinated organic pesticides in the evaluation of solid waste. This includes pesticides, their degradation products, technical grades of chlordane, toxaphene, and PCBs in solid waste.^{1,2} EPA Method 608 targets similar pesticides in industrial and wastewater discharges.³ EPA Methods 608 and 8080 prescribe packed-column analysis, whereas Methods 8081 and CLP pesticides prescribe capillary column analysis.

These EPA Methods allow laboratories to substitute columns of their choice provided that performance data such as chromatographic resolution, analyte breakdown, and MDLs (minimum detectable levels) are equal to or better than those provided with the EPA methods.

The HP-608 is a wide bore (530 μ m-id) capillary column specially designed for the analysis of organic pesticides. GC/ECD separations of chlorinated pesticides and PCBs were done using the HP-608 column with both on-column and splitless inlet sample introductions. In both cases, the HP-608 provided superior chromatographic resolution, excellent reproducibility, and minimal analyte breakdown for the analysis of pesticides and PCBs.

Experimental

A 30 m x 530 μ m x 0.5 μ m HP-608 column (part no. 19095S-023) was used under constant carrier gas flow using the 5890 Series II GC with EPC equipped with a split/splitless inlet and a cool on-column inlet. Equipment included the 7673 automatic sampler with tray and the electron capture detector (ECD).

Samples were introduced in both the on-column and splitless modes. The MerlinTM Microseal septum (part no. 5181-8816) was used in the split/splitless inlet to replace the conventional inlet septum. A deactivated tapered glass liner (part no. 5181-3316) was used for all splitless injection runs. GC conditions were controlled using the HP 3365

Table 1. Experimental Conditions

Instrument Requirements	
Gas chromatograph:	Agilent 5890 Series II with EPC
Injection ports:	Split/splitless inlet with temperature and pressure programmable features On-column inlet with temperature and pressure programmable features
Column:	HP-608, 30 m x 530 μ m x 0.5 μ m (Part number 19095S-023)
Detector:	ECD
Sample introduction:	7673 splitless fast injection On-column injection
Data collection:	3365 ChemStation and HP Vectra 486/133T
Experimental Conditions	
Column:	HP-608, 30 m x 530 μ m x 0.5 μ m (Part number 19095S-023)
Carrier gas:	He, 20 cm/sec, 2.2 psi at 80°C with EPC under constant flow of 2.4 ml/min
Oven:	First ramp: 80°C (hold 1 min) to 190°C at 30°C/min Second ramp: 190°C to 280°C (hold 1 min) at 6°C/min Third ramp: 280°C to 300°C (hold 2 min) at 20°C/min
Injection:	Splitless: 1 μ l, inlet temperature of 250°C On-column: 1 μ l oven track for inlet temperature program
Detector:	ECD (330°C), 65 ml/min N ₂ makeup, 6 ml/min anode purge
Sample:	Pesticides and PCB standard solutions in isoctane



Agilent Technologies
Innovating the HP Way

ChemStation. Data was managed with a HP Vectra PC (486/33T). Instrument parameters and experimental conditions are listed in **Table 1**.

Pesticide solutions containing 16 to 22 components were prepared from the dilution of certified standards (part no. 8500-5873 and 8500-5876, mixes A and B: level 2) with iso-octane (pesticide residue grade from Burdick & Jackson). Pesticide standards (part no. 5062-3589), including four vials of 16 EPA-608 pesticides and two vials of two component inlet check solutions (endrin/DDT concentrations are 50 ppb/100 ppb), were used without further dilution. These pesticide compounds are listed in **Table 2**.

Figure 1. Chromatograms of the 16 chlorinated pesticides under optimum GC conditions, 100 pg of each pesticide injected. Peak identification in Table 2.




Figure 1A. Splitless Injection




Figure 1B. On-Column Injection

Table 2. Chlorinated Pesticides

Peak No.	EPA-608	Compound Name EPA-8080/8081	EPA-CLP Pesticides
1	alpha-BHC	alpha-BHC	alpha-BHC
2	Lindane	Lindane	Lindane
3	beta-BHC	beta-BHC	beta-BHC
4	Heptachlor	Heptachlor	Heptachlor
5	delta-BHC	delta-BHC	delta-BHC
6	Aldrin	Aldrin	Aldrin
7	Heptachlor epoxide	Heptachlor epoxide	Heptachlor epoxide
8		Chlordane-gamma	Chlordane-gamma
9			Chlordane-alpha
10	Endosulfan I	Endosulfan I	Endosulfan I
11	4,4'-DDE	4,4'-DDE	4,4'-DDE
12	Dieldrin	Dieldrin	Dieldrin
13	Endrin	Endrin	Endrin
14	4,4'-DDD	4,4'-DDD	4,4'-DDD
15	Endosulfan II	Endosulfan II	Endosulfan II
16	4,4'-DDT	4,4'-DDT	4,4'-DDT
17	Endrin aldehyde	Endrin aldehyde	Endrin aldehyde
18	Endosulfan sulfate	Endosulfan sulfate	Endosulfan sulfate
19		Methoxychlor	Methoxychlor
20	a-Degradation product		Endrin ketone
SS1			Tetrachloro-m-xylene
SS2			Decachlorobiphenyl

Results and Discussion

Splitless Analysis

Figure 1A shows the analysis of a standard solution containing the 16 EPA-608 targeted pesticides at a constant column flow of 2.4 ml/minute. One microliter of sample (100 pg of each component) was introduced in splitless mode at 250°C under the conditions⁴ listed in **Table 1**. All 16 components were well resolved in sharp symmetric peaks, and the analysis was completed in less than 17 minutes. The 30-m HP-608 (530 µm id) column possesses sufficient efficiency to completely resolve the complex pesticides mix, including chlorinated compounds with similar or isomeric structures. The absence of coeluting peaks on the HP-608 column permitted fast and accurate identification and quantitation.

Low-Temperature On-Column Analysis

Figure 1B shows the same pesticides standard mix using the cool on-column injection technique. On-column injection of 1 µl of sample at 80°C resulted in little sample degradation, minimal byproducts, and good sensitivity (see **Table 3**). Common to both **Figures 1A** and **1B** is the absence of tailing peaks, including the endrin aldehyde peak (peak 17), indicating the HP-608 column surface is very inert.

Reproducibility

Reproducibility for the analysis of chlorinated pesticides using HP-608 columns with the HP GC/ECD system was excellent (see **Table 3**). The RSD (relative standard deviation) in absolute area counts for all 16 EPA targeted pesticides was less than 2% for on-column runs (two sets of six replicate injections). Similarly, the peak area counts reproducibility for all splitless injection runs (three sets of six replicate injections) was in the 1% to 2% RSD range using the same standard sample.

The standard deviation of retention times was within 0.003–0.005 minutes and 0.002 minutes for on-column and splitless runs, respectively. In comparison, the standard deviation of retention times for EPA Method 8081 analysis (**Table 10**, reference 1) using wide-bore capillary columns ranged from 0.007 minutes to 0.013 minutes for the same set of pesticides. This clearly demonstrates that chromatographic reproducibility obtained using the HP-608 capillary column is better than that obtained using the capillary columns stipulated in EPA Method 8081.

Table 3. Reproducibility of Pesticide Analysis

Pesticides	Retention Times, min			Area Counts		
	Mean	Std Dev	% RSD	Mean	Std Dev	% RSD
A. On-column injection (100 pg each component)						
alpha-BHC	8.423	0.004	0.047	431643	7497	1.74
Lindane	9.225	0.004	0.046	393514	6496	1.65
beta-BHC	9.352	0.004	0.046	208287	3428	1.65
Heptachlor	9.984	0.004	0.042	310294	5430	1.75
delta-BHC	10.181	0.005	0.044	390027	7428	1.90
Aldrin	10.760	0.004	0.039	359246	6996	1.95
Heptachlor epoxide	12.385	0.003	0.028	359586	5740	1.60
Endosulfan I	13.036	0.004	0.031	321622	5478	1.70
4,4'-DDE	13.623	0.004	0.026	341930	7070	2.07
Dieldrin	13.838	0.004	0.027	336042	4832	1.44
Endrin	14.814	0.004	0.025	268560	5298	1.97
4,4'-DDD	15.135	0.004	0.024	254389	3017	1.19
Endosulfan II	15.311	0.004	0.025	297580	4326	1.45
4,4'-DDT	15.975	0.003	0.021	259369	3881	1.50
Endrin aldehyde	16.208	0.004	0.022	205588	1876	0.91
Endosulfan sulfate	16.570	0.003	0.021	281397	4143	1.47
a, Degradation product	18.690	0.003	0.017	3416	97	2.83
B. Splitless injection (100 pg each component)						
alpha-BHC	8.351	0.002	0.020	376446	7222	1.92
Lindane	9.146	0.002	0.020	317405	6592	2.08
beta-BHC	9.273	0.002	0.018	165105	3129	1.90
Heptachlor	9.898	0.002	0.018	207924	4637	2.23
delta-BHC	10.097	0.001	0.013	301779	6113	2.03
Aldrin	10.671	0.002	0.015	308689	6422	2.08
Heptachlor epoxide	12.289	0.001	0.011	289985	6216	2.14
Endosulfan I	12.938	0.002	0.014	253489	5496	2.17
4,4'-DDE	13.527	0.001	0.011	313249	6102	1.95
Dieldrin	13.735	0.002	0.014	209054	3925	1.88
Endrin	14.710	0.002	0.013	160235	3104	1.94
4,4'-DDD	15.034	0.002	0.013	168113	3094	1.84
Endosulfan II	15.207	0.002	0.015	228810	4868	2.13
4,4'-DDT	15.874	0.002	0.012	168810	2129	1.26
Endrin aldehyde	16.103	0.002	0.010	148655	3687	2.48
Endosulfan sulfate	16.467	0.002	0.013	190284	3003	1.58
a, Degradation product	18.584	0.002	0.012	21513	1747	8.12

Comparison of Sample Introduction Techniques



For all on-column injection runs, degradation was negligible due to the low initial column temperature (80°C) and the direct introduction of a liquid sample plug into an inert column. As a result, inlet-related sample discrimination, alteration, and degradation were eliminated, while the advantages of solvent focusing and stationary phase focusing were maximized. Routine analysis of the inlet check solution (specified by the EPA methods) showed that the average degradation was less than 3% for endrin and 1% for DDT.

As demonstrated by the clean baseline in **Figure 1A**, little sample degradation occurred at an inlet temperature of 250°C. However, a small endrin ketone peak (RT of 18.69 minutes) appeared on the chromatograms from the GC runs with both on-column and splitless injection shown in **Figures 1A** and **1B**. A closer look (**Table 3**), shows that the area counts for endrin ketone (peak a, a byproduct of endrin degradation) measured 5 times larger in the splitless runs than for the on-column runs (average absolute area counts of 3,400 versus 21,000). The GC runs of the inlet check standard (after 200 repeated splitless injections), showed a 7% endrin degradation and 10% DDT degradation. These values were well below the EPA requirement of 15% degradation for both endrin and DDT.

Use of the Merlin™ Microseal⁵ and the deactivated glass liner also contributed directly to the low degradation rate in the splitless mode. The Microseal is designed to provide a good inlet seal without using a conventional septum. By eliminating the introduction of particulates into the inlet liner from conventional septum, useful life for the inlet liner is extended, down time (to change a liner and a conventional septum) is reduced, and laboratory throughput is increased.

The use of splitless injection technique may also prevent interference from extraneous and high boiling

Figure 2. Chromatograms of isooctane under optimum GC conditions, 1 µl injected. (b,k=solvent contaminants)



materials in dirty samples. This is demonstrated in **Figures 2A** and **2B**. **Figure 2** shows the analysis of isooctane solvent (pesticide-residue grade) using both splitless (**Figure 2A**) and on-column injection (**Figure 2B**). The late-eluting peak (peak k), at 16.69 minutes retention time in the on-column run, does not appear in the chromatogram of the splitless run (**Figure 2A**).

This peak, possibly a high boiling contaminant in isooctane, appears again in **Figure 3B**. **Figures 3A** and **3B** show analyses of a 10-ppb pesticide standard using splitless injection and on-column injection, respectively. The peak (peak k) eluting just before endosulfan sulfate

(peak 18) may cause a higher value for the determination of trace endosulfan sulfate in the sample.

Both area counts and peak heights for the splitless runs were smaller than those for the on-column injection runs (see **Table 3**). For example, the average counts of lindane from the splitless runs were approximately 80% of those from the on-column injections (**Table 3**). Therefore, on-column injection is a good choice for clean samples and trace analyses demanding high sensitivity and low detection limits (large area counts).

Analysis of PCBs and EPA Methods 8080, 8081, and CLP Pesticides

For wastewater and solid waste samples, the EPA recommends splitless injection for the determination of pesticides and PCBs. Using splitless injection under optimum 5890 Series II GC conditions, all 17 pesticides targeted by EPA Method 8080B are resolved as shown in **Figure 4**.

Among the 20 components targeted by EPA Methods 8081 and CLP pesticides, all but alpha-chlordane and endosulfan I (they are partially separated) are well resolved by the HP-608 column (**Figure 5**). Since the HP-608 column can effectively separate the complex mix of these pesticides, it is a good column choice for the determination of PCBs and multiple-peak response pesticides such as chlordane and toxaphene. **Figure 6** shows a comparison of chromatograms for technical grade chlordane and toxaphene, while **Figure 7** is a comparison of chromatograms for seven PCBs, all analyzed under the same GC conditions using the HP-608 capillary column.

Figure 3. Chromatograms of dilute pesticides mix under optimum GC conditions; 10 pg of each pesticide injected. (Peak ID, see Table 2)






Figure 4. Chromatograms of the EPA-Method 8080 pesticides under optimum GC conditions. Splitless injection of 100–200 pg per component. (Peak ID, see Table 2)



Conclusion

Under optimal conditions, the HP-608 column separates 16 EPA-608 pesticides in 17 minutes and 20 EPA-CLP pesticides (and EPA-8081 pesticides) in 19 minutes (22 minutes including the surrogate, decachlorobiphenyl). Both splitless and on-column injections yield little sample degradation and provide excellent reproducibility of retention times and area responses. On-column injection is more suitable for clean samples and trace analysis, while splitless injection is better used for wastewater and waste samples.

Figure 5. Chromatogram of pesticides targeted in EPA-method 8081 and CLP pesticides under optimum GC conditions. Splitless injection of 50–100 pg per component. (Peak ID, see Table 2)




Figure 6. Chromatogram of technical grade toxaphene and chlordane under optimum GC conditions. Splitless injection of 1 µl 2.5 ppm mix





Figure 7. A comparison of seven PCBs under optimum GC conditions. Splitless injection of 1 μ l 2.5 ppm each



Acknowledgment

The authors wish to thank
Dr. D. Pautler for his many
helpful discussions.


References

1. EPA Method 8080B and 8081,
“Test Methods for Evaluating
Solid Waste,” SW-846, Revision 2,
Nov. 1990.
2. U.S. EPA Contract Laboratory
Program Statement of Work for
Organics Analysis Document
Number OLM01.0, 1990.
3. EPA Method 608, “Methods for
Organic Chemical Analysis of
Municipal and Industrial
Wastewater”, PB82-201798, 1982.
4. I. L. Chang and W. J. Sanders,
“Method Development for EPA-
608 Analysis Using a HP-608
Capillary Column,” Hewlett-
Packard Application Note 1993
(in preparation).
5. “Introducing the Merlin
Microseal™ Septum,”
Pub. No. 5091-3197EUS, 1991.

www.agilent.com



Analysis of Organochlorine Pesticides and PCB Congeners with the Agilent 6890 Micro-ECD



Application

Gas Chromatography

June 1997

Authors

Isabelle Chanel
Agilent Technologies, Inc.
European Marketing Group
76337 Waldbron
Germany

Imogene Chang
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A new electron capture detector (ECD) for the Agilent 6890 Series gas chromatograph (GC) was used to analyze polychlorinated biphenyl congeners and organochlorine pesticides. The linearity of the 6890 Micro-ECD in the calibration range of 2 to 400 ppb was evaluated. The micro-ECD easily meets the linearity requirements of U.S. EPA contract laboratory programs for pesticides. Its limit of detection for these compounds goes down to less than 50 ppt. The micro-ECD also exhibits good reproducibility.

Key Words

Organochlorine pesticides, PCB congeners, 6890 GC, micro-ECD; pesticide analysis, ECD.

Introduction

The electron capture detector (ECD) is the detector of choice in many Contract Laboratory Programs (CLP)¹ and EPA methods for pesticide analysis because of its sensitivity and selectivity for halogenated compounds. However, there are drawbacks to the ECD design. The ECD is inherently nonlinear², with a limited linear range. The limited linear range means that dilution and reanalysis are frequently required for samples that are outside the calibration range.

Also, the typical ECD is designed to be compatible with both packed and capillary columns. This results in a flow cell that is larger than that required for capillary columns alone, which reduces detector sensitivity.

To address these problems, a new ECD was developed for the 6890 Series gas chromatograph (GC). The 6890 Micro-ECD has a smaller flow cell optimized for capillary columns and was redesigned to improve the linear operating range.

This application note examines the linearity, reproducibility, and limit of detection of the new ECD with mixtures of polychlorobiphenyl (PCB) congeners and organochlorine pesticides (OCPs).

Experimental

All experiments were performed on an 6890 Series GC with electronic pneumatics control (EPC) and the 6890 Micro-ECD. Table 1 shows the experimental conditions for PCB congeners and OCPs.

Table 1. Experimental Conditions for PCB Congener and OCP Analysis.

System Conditions	PCB Congener Analysis	OCP Analysis
Oven	80 °C (2 min); 30 °C/min to 200 °C; 10 °C/min to 320 °C (5 min).	80 °C (2 min); 25 °C/min to 190 °C; 5 °C/min to 280 °C; 25 °C/min to 300 °C (2 min).
Inlet	Split/splitless; 300 °C	Split/splitless; 250 °C
Carrier	Helium, 16.8 psi (80 °C); 1.3-mL/min constant flow	Helium, 23.9 psi (80 °C); 2.2-mL/min constant flow
Sampler	Agilent 7673, 10- μ L syringe, 1- μ L splitless injection	7673, 10- μ L syringe, 1- μ L splitless injection
Column	30-m, 250- μ m id, 0.25- μ m film HP-5MS (part no. 19091S-433)	30-m, 250- μ m id, 0.25- μ m film HP-5MS (part no. 19091S-433)
Detector	330 °C; makeup gas: nitrogen, constant column and makeup flow	330 °C; makeup gas: nitrogen, constant column and makeup flow



Agilent Technologies
Innovating the HP Way

The solutions were prepared by making appropriate dilutions of a stock solution with isooctane. For PCB congeners, the stock solution was an EPA PCB congener calibration check solution (from Ultra Scientific Company, part number RPC-EPA-1). For OCPs, the solution was an OCP calibration check solution (part number 8500-5876).

Results and Discussion

Linearity and Response Factors

A series of dilutions of the PCB mixture from 2 ppb to 200 ppb and of the OCP mixture from 2 ppb to 400 ppb was injected into the 6890 Micro-ECD system. The linearity was determined by calculating the correlation coefficient from the resulting calibration curve.

Figures 1 and 2 present typical chromatograms of OCPs and PCBs at 20 or 40 ppb and 50 ppb, respectively. Figure 3 is a calibration curve of decachlorobiphenyl, typical of other PCB congeners. Figure 4 shows the calibration curve of 4, 4' DDE, typical of OCPs. The correlation coefficient,




Figure 1. Typical chromatogram of OCPs at 20 or 40 ppb.
See table 1 for conditions. See table 5 for peak identification.




Figure 2. Typical chromatogram of PCB congeners at 50 ppb.
See table 1 for conditions. See table 4 for peak identification.




Figure 3. Typical linearity of PCB congener analysis: decachlorobiphenyl from 2-200 ppb.




Figure 4. Typical linearity of OCP analysis: 4,4' DDE from 4 to 400 ppb.

average response factors, and percent relative standard deviation (%RSD) for the response factors for each analyte are shown in tables 2 and 3.

All correlation coefficients were at least 0.9996. In these experiments, the 6890 Micro-ECD is linear over this range. The typical range required by CLP methods is 5-80 ppb¹, so the 6890 Micro-ECD exceeds the range by almost twofold.

In addition, the CLP method requires the percent RSD of the response factors for most components to be less than 20 percent for a three-point calibration curve (5 to 80 ppb). As shown in tables 2 and 3, the percent RSD of the response factors ranged from 0.55 percent to 12.5 percent for the PCB congeners and from 2.8 percent to 10 percent for the OCPs over a concentration range of two orders of magnitude (2 to 400 ppb). Furthermore, the average response factor of each analyte was so consistent and reproducible that the internal standard technique can be used to quantify all OCPs and PCB congeners.

Table 2. PCB Congener Analysis: Linearity of the 6890 Micro-ECD 2 ppb to 200 ppb.
See table 1 for conditions.

Peak	Name	Average Response Factor	%RSD of Response Factor	Correlation (%)
1	2,4-Dichlorobiphenyl	2e-2	12.5	99.97
2	2,2',5-Trichlorobiphenyl	2e-2	11.1	99.97
3	2,4,4'-Trichlorobiphenyl	8.5e-3	7.5	99.99
4	2,2',5,5'-Tetrachlorobiphenyl	1.3e-2	10.2	99.97
5	2,2',3,5-Tetrachlorobiphenyl	1e-2	9.4	99.98
6	2,3,4,4'-Tetrachlorobiphenyl	8e-3	6.7	99.99
7	2,2',4,5,5'-Pentachlorobiphenyl	9e-3	8.8	99.98
8	3,3',4,4'-Tetrachlorobiphenyl	1.2e-2	12.6	99.97
9	2,3,4,4',5-Pentachlorobiphenyl	8e-3	5.5	99.99
10	2,2',4,4',5,5'-Hexachlorobiphenyl	8e-3	8.1	99.98
11	2,3,3',4,4'-Pentachlorobiphenyl	6e-3	1.9	99.99
12	2,2',3,4,4',5-Hexachlorobiphenyl	6.5e-3	3.8	99.99
13	3,3',4,4',5-Pentachlorobiphenyl	9e-3	6.5	99.99
14	2,2',3,4,5,5',6-Heptachlorobiphenyl	8e-3	5.7	99.99
15	2,2',3,3',4,4'-Hexachlorobiphenyl	5.6e-3	1.8	99.99
16	2,2',3,4,4',5,5'-Heptachlorobiphenyl	5.8e-3	1.0	99.99
17	2,2',3,3',4,4',5-Heptachlorobiphenyl	5.8e-3	0.57	99.99
18	2,2',3,3',4,4',5,6-Octachlorobiphenyl	6e-3	0.78	99.99
19	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	8e-3	3.1	99.96
20	Decachlorobiphenyl	1e-2	9.5	99.98

Table 3. OCP Analysis: Linearity of the 6890 Micro-ECD 2 or 4 ppb to 200 or 400 ppb.
See table 1 for conditions.

Peak	Name	Average Response Factor	% RSD of Response Factor	Correlation (%)
1	2,4,5,6-Tetra-m-xylene	4.2e-3	5.3	99.97
2	beta-BHC	1.1e-2	7.1	99.99
3	delta-BHC	6.4e-3	4.7	99.99
4	Aldrin	4.7e-3	9.5	99.97
5	Heptachlor epoxide	4.7e-3	5.4	99.99
6	gamma-Chlordane	6.6e-3	6.6	99.99
7	alpha-Chlordane	5e-3	4.3	99.98
8	4,4' DDE	5e-3	2.8	99.99
9	Endosulfan II	2.9e-3	4.4	99.98
10	Endrin aldehyde	4.5e-3	5.9	99.94
11	Endosulfan sulfate	5.1e-3	5.3	99.97
12	Endrin ketone	4.7e-3	9.0	99.89
13	Decachlorobiphenyl	3.7e-3	9.9	99.96

Reproducibility

The reproducibility of the 6890 Micro-ECD was established by analyzing each mixture using identical conditions five times. Each analyte in the PCB congener mixture was injected at a concentration of 50 ppb, and the analytes in the OCP mixture were 20 or 40 ppb. The results are shown in tables 4 and 5. The highest %RSD for any analyte is 3.69 percent for aldrin, which is well below the CLP maximum allowable RSD of 15 percent.¹

Table 4. PCB Congener Analysis: Reproducibility of the 6890 Micro-ECD 50 ppb; N=5.
See table 1 for conditions.

Peak	Name	Average	RSD
		Area	(%)
1	2,4-Dichlorobiphenyl	2229	1.26
2	2,2',5-Trichlorobiphenyl	2547	1.29
3	2,4,4'-Trichlorobiphenyl	5687	1.41
4	2,2',5,5'-Tetrachlorobiphenyl	3721	1.43
5	2,2',3,5-Tetrachlorobiphenyl	4941	1.46
6	2,3,4,4'-Tetrachlorobiphenyl	5943	1.40
7	2,2',4,5,5'-Pentachlorobiphenyl	5089	1.47
8	3,3',4,4'-Tetrachlorobiphenyl	3822	1.72
9	2,3,4,4',5-Pentachlorobiphenyl	6203	1.62
10	2,2',4,4',5,5'-Hexachlorobiphenyl	6189	1.44
11	2,3,3',4,4'-Pentachlorobiphenyl	8375	1.68
12	2,2',3,4,4',5-Hexachlorobiphenyl	7538	1.56
13	3,3',4,4',5-Pentachlorobiphenyl	5092	2.02
14	2,2',3,4,5,5',6-Heptachlorobiphenyl	6224	1.69
15	2,2',3,3',4,4',5-Hexachlorobiphenyl	8921	1.67
16	2,2',3,4,4',5,5'-Heptachlorobiphenyl	8527	1.82
17	2,2',3,3',4,4',5-Heptachlorobiphenyl	8625	1.91
18	2,2',3,3',4,4',5,6-Octachlorobiphenyl	8338	2.13
19	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	6097	2.55
20	Decachlorobiphenyl	4622	2.85

Table 5. OCP Analysis: Reproducibility of the 6890 Micro-ECD; N=5.
See table 1 for conditions.

Peak	Name	Concentration	Average	RSD
		(ppb)	Area	(%)
1	2,4,5,6-Tetra-m-xylene	20	4785	0.7
2	beta-BHC	20	1802	0.81
3	delta-BHC	20	3251	1.50
4	Aldrin	20	402	3.69
5	Heptachlor epoxide	20	4316	1.58
6	gamma-Chlordane	20	2958	1.23
7	alpha-Chlordane	20	4219	1.06
8	4,4' DDE	40	4103	1.76
9	Endosulfan II	40	7176	1.27
10	Endrin aldehyde	40	4719	0.85
11	Endosulfan sulfate	40	4040	3.04
12	Endrin ketone	40	4386	2.52
13	Decachlorobiphenyl	40	5369	0.85

Detection Limit

To establish the lower limit of detection for the 6890 Micro-ECD with PCBs and OCPs, 1- μ L injections were made at gradually decreasing concentrations. Figures 5 and 6 show chromatograms with analyte concentrations of 50 to 100 ppt.

All the analyte peaks for both the PCB congener and OCP mixtures are still easy to quantitate, and in fact smaller concentrations can be reliably analyzed. Aldrin, which has the lowest response of the OCPs, still exhibits an adequate signal-to-noise ratio at the 50 ppt level under these analysis conditions.

Conclusion

The Agilent 6890 Micro-ECD response was linear over the concentration range of 2 to 200 ppb, produced reproducible results, and exhibited excellent sensitivity for mixtures of PCB congeners and OCPs.

References

1. U.S. EPA Contract Laboratory Program, "Statement of Work for Organic Analysis," OLM03.1, August 1994.
2. R. Buffington and M.K. Wilson, eds., *Detectors for Gas Chromatography*, Agilent Technologies, Inc., Part Number 5958-9433, 1987.




Figure 5. PCB congener mixture at 50 ppt each.

See table 1 for conditions. See table 4 for peak identification.




Figure 6. OCP Mixture at 50 to 100 ppt.

See table 1 for conditions. See table 5 for peak identification.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5965-8556E



Agilent Technologies
Innovating the HP Way

Analysis of Sulfur and Phosphorus Compounds with a Flame Photometric Detector on the Agilent 6890 Series Gas Chromatograph



Application

Gas Chromatography

February 1997

Authors

William H. Wilson
Matthew S. Klee
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A gas chromatograph (GC) with a flame photometric detector (FPD) is frequently employed in analyzing complex samples for specific compounds. The wavelength filter of the FPD can be set to select for many elements, but it is most commonly used to detect sulfur and phosphorus. This application note discusses the uses of the FPD in gas chromatography, demonstrates the linearity and method detection limits (MDL) of the 6890 Series GC with an FPD, and gives examples of analyses of organophosphorus pesticides using the 6890 GC with an FPD.

Key Words

Gas chromatography, flame photometric detector, FPD, sulfur analysis, phosphate analysis, pesticides, organophosphorus pesticides, EPA method 1618, EPA method 622.

Introduction

The flame photometric detector is one of the most widely used selective detectors in gas chromatography. The FPD consists of a reducing flame that produces chemiluminescent species. These species emit characteristic light that is optically filtered for the desired wavelength; the wavelength selection determines which compound is detected. The filtered light is measured by a photomultiplier and transduced into a signal. A second photomultiplier can be added, which allows simultaneous detection of a second signal.

FPD filters can be selected for many different compounds, but the most common uses are for the selective detection of sulfur and phosphorus compounds in complex mixtures. The selectivity of classical FPDs is typically (as a ratio by weight to carbon) 10^5 for sulfur and 10^6 for phosphorus. The FPD operates over a dynamic range of 1×10^3 for sulfur and 1×10^4 for phosphorus.¹

Gas chromatography with an FPD can be used to detect sulfur compounds in crude oil and sulfur contaminants in natural gas.

In food analysis it is used to detect off-flavors resulting from the libera-

tion of volatile sulfur compounds. It is also used to simultaneously detect sulfur and phosphorus in chemical warfare agents. In the environmental area, the FPD is used for detection of organophosphorus pesticides and herbicides. Several EPA methods for pesticide detection, including EPA methods 1618² and 622³, specify the use of an FPD.

A schematic of a single FPD for the 6890 Series GC is shown in figure 1. A dual wavelength version is available that has a second photomultiplier mounted perpendicular to the first for simultaneous detection of a second wavelength. The 6890 GC is available with either a single or dual FPD.

The sensitivity of any FPD is affected by detector temperature, flame chemistry, and filter wavelength.

- **Detector temperature.** To protect the photomultiplier, the maximum temperature limit for the 6890 FPD is 250 °C. Photomultiplier tube (PMT) noise increases with setpoint temperature, so the detector temperature should be as low as possible. Generally, the temperature should be set about 25 °C above the highest temperature reached in the oven program. To prevent water condensation and clouding of the window, the minimum operating temperature is 120 °C.⁴



Agilent Technologies
Innovating the HP Way

- **Flame chemistry.** FPD sensitivity is highly dependent on detector gas flows. On the 6890 GC, the gas flows are electronically controlled. This allows rapid and precise optimization of flow rates. Sulfur and phosphorus modes have different optimum flow requirements, so the ability to easily set and reset flows increases the quality of results and saves time.
- **Filter wavelength.** For the FPD, filters of specific wavelength are physically installed in the detector. A 394-nm filter is used for sulfur detection, and 526-nm filter for phosphorus detection.




Figure 1. Single photomultiplier tube FPD for 6890 Series GC

Experimental

All experiments were performed on a 6890 Series GC with electronic pneumatics control (EPC) and an Agilent 7673 automatic liquid sampler (ALS). An Agilent 1707A ChemStation was used for instrument control and data acquisition. Chromatography conditions are shown with the individual chromatograms in figures 2, 3, and 4.

Table 1. MDL and Linearity over 10² Range Sulfur Mix on the FPD

Peak Number	Compound Name	MDL pgS/sec n = 11	Linearity r ² n = 15
1	2,5-dimethylthiophene	26.22	0.9986
2	sec-butylsulfide	20.10	0.9983
3	1,4-butanedithiol	22.27	0.9972
4	dodecanethiol	16.90	0.9985
5	octyl sulfide	16.14	0.9979

Results and Discussion

Linearity and MDL

In sulfur mode, the response of the FPD is proportional to analyte concentration squared. The calculated MDL and r² values from linearity experiments for a single photomultiplier in sulfur mode are listed in table 1, and the chromatogram for a 20–40 ppb sample from the experiment is shown in figure 2. The square of the concentration was used to calculate regression statistics. When using a ChemStation for data analysis, a quadratic calibration fit is used for sulfur.




Figure 2. 1 μ L of 1.5 ppm sulfur standard, FPD in sulfur mode (The peaks are identified in table 1.)


The response of the FPD is linear in phosphorus mode. Table 2 shows the r^2 values for an organo-phosphorus pesticide mixture and the MDL calculated from the study. Figure 3 shows the chromatogram. A standard linear curve fit is used for phosphorus when using a ChemStation for data analysis.

Analysis of EPA Method 1618

Figure 4 shows the chromatogram obtained from the analysis of organophosphorus pesticides according to EPA method 1618. The injected concentration of each compound was 1–2 ppm.

Table 2. MDL and Linearity over 10^3 Range for Organophosphorus Pesticides on the FPD

Peak Number	Compound Name	MDL pgPesticide/sec n = 11	Linearity r^2 n = 15
1	phorate	1.85	0.9996
2	demeton	1.13	> 0.9998
3	disulfoton	1.31	> 0.9999
4	diazinon	1.74	> 0.9999
5	malathion	1.74	> 0.9999
6	fenthion	1.75	> 0.9999
7	parathion	1.84	> 0.9999
8	trichloronate	2.27	> 0.9999
9	tokuthion	2.51	> 0.9999
10	fensulfothion	—	> 0.9999
11	ethion	1.29	> 0.9999
12	sulprofos	2.36	> 0.9999
13	guthion	1.24	> 0.9999
14	coumaphos	2.08	> 0.9999



Conditions	
Injection:	1 μ L splitless
Oven program:	60 °C, hold 1 minute; 20 °C/min to 250 °C, hold 7 minutes
Single FPD in phosphorus mode:	150 mL/min H_2 , 110 mL/min air, 60 mL/min N_2 makeup at 250 °C
Column:	HP-5, 30 m x 320 μ m at 25 psi constant pressure

Figure 3. 1 μ L Splitless injection of 20–40 ppb organophosphorus pesticide standard, FPD in phosphorus mode (The peaks are identified in table 2.)




Figure 4. Analysis of organophosphorus pesticides according to EPA method 1618, 1 μ L on-column injection of 1–2 ppm standard, FPD in phosphorus mode (The peaks are identified in table 2.)

Conclusions

The Agilent 6890 Series GC with an FPD can be used for the sensitive, and selective measurement of sulfur- and phosphorus-containing compounds in complex mixtures. The electronic pneumatics control on the Agilent 6890 GC ensures rapid and accurate gas flow control, provides for easier method setup and documentation, and simplifies optimization.

3. EPA Method 622, *USEPA Method 622: The Determination of Organophosphorus Pesticides in Municipal and Industrial Wastewater*, USEPA Report #600/4-82-008, NTIS #82-156027.
4. *Operating Manual, Flame Photometric Detector*, Agilent Technologies, Part Number G1535-90100.

References

1. *Detectors for Gas Chromatography*, Agilent Technologies, Part Number 5958-9433E, 1991.
2. EPA Method 1618, *USEPA Method 1618: Organo-halide Pesticides, Organo-phosphorus Pesticides, and Phenoxy-Acid Herbicides by Wide-Bore Capillary Column Gas Chromatography with Selective Detectors*, Revision A, 1989, Office of Water Regulations and Standards.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5965-7442E



Agilent Technologies
Innovating the HP Way

A Method Used to Screen for 567 Pesticides and Suspected Endocrine Disrupters



Application

Gas Chromatography

May 1998

Authors

Philip L. Wylie and
Bruce D. Quimby
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A gas chromatographic (GC) method has been developed that can be used to screen for 567 pesticides and suspected endocrine disrupters. In principle, it can be used to screen for any GC-amenable pesticide, metabolite, or endocrine disrupter. The method relies on a technique called retention time locking (RTL). RTL is a procedure that allows the chromatographer to reproduce analyte retention times independent of GC system, column length, or detector so long as columns with the same stationary phase, nominal phase ratio, and diameter are used. Because RTL increases retention time precision and predictability, raw retention times can be used as a more reliable indicator of compound identity. The chromatographer first locks the GC method so that all retention times match those listed in a 567-compound pesticide and

endocrine disrupter retention time table. After analyzing a sample by GC with atomic emission detection (GC-AED), the analyst enters a peak's retention time and known elemental content (presence or absence of heteroatoms) into a dialog box. If element-selective detectors are used, detector response can be entered in addition to or in place of GC-AED data. The software then searches the pesticide table for those compounds that elute at the correct retention time and have the right elemental content or detector response. Most often, the software finds just one compound that meets these criteria, and rarely does it find more than three. Confirmation is performed by GC with mass spectral detection (GC-MS) or by calculation of elemental ratios using GC-AED data. With retention time locking, pesticides have the same retention time on all GC systems; this makes GC-MS confirmation much easier because the analyte's retention time is already known.

Key Words

Pesticides, endocrine disrupters, gas chromatography, retention time locking, RTL

Introduction

*The Pesticide Manual*¹ lists 759 compounds and biological agents that are used currently as active ingredients in various pesticide formulations. Many compounds, though no longer used, still persist in the environment. For the protection of human health and the environment, acceptable limits in food and water have been set by governmental bureaus such as the United States Environmental Protection Agency (USEPA) and the Codex Alimentarius Commission.² Numerous methods have been developed to screen for pesticide contamination in food³⁻⁷ and the environment⁸⁻¹⁰ to ensure that these standards are met.

Certain pesticides and other synthetic chemicals have been suspected of behaving as pseudo hormones, disrupting normal functions of the endocrine system in wildlife and humans. Maladies such as birth defects, behavioral changes, breast cancer, lowered sperm counts, and reduced intelligence have been blamed on exposure to endocrine disrupters.¹¹ The 1996 publication of *Our Stolen Future*, a book by Colborn,



Agilent Technologies
Innovating the HP Way

Dumanoski, and Myers,¹¹ brought these concerns to the attention of the public. Recently passed legislation in the U.S. calls for more testing of suspected endocrine disrupters and monitoring of them in food¹² and water¹³ supplies. To facilitate more research into the endocrine disrupter issue, methods are needed to detect suspected compounds at trace levels.

Because so many pesticides are in use, it is usually impractical to screen for large numbers of them individually and, therefore, multiresidue methods are preferred. Most laboratories that analyze for pesticides in food or the environment screen for only a few dozen compounds because it is often very difficult to screen for more. Recently however, methods have been developed using gas chromatography with mass spectral detection (GC-MS), that can screen for more than 200⁵ or even 300⁶ pesticide residues.

Still, there is no universal method to analyze for all GC-amenable pesticides. While GC-MS methods are gaining in popularity, there are still some limitations. When methods employ selected ion monitoring (SIM) or tandem mass spectrometry (MS-MS), method development is more tedious and any shift in GC retention times requires that individual analyte retention time windows be shifted accordingly. These methods are only capable of detecting compounds on the target list; there are still hundreds of pesticides, metabolites, and suspected endocrine disrupters that could be missed. On the other hand, methods based on scanning GC-MS alone may require more sample cleanup to avoid interferences from co-extracted indigenous compounds. Typically, these methods do not screen for many pesticide metabo-

lites, endocrine disrupters, or other environmental contaminants. A method that could be used to screen for endocrine disrupters and almost all of the volatile pesticides and metabolites would offer a better means of monitoring the food supply and the environment.

This paper describes a universal method that, in principle, could be used to screen for any pesticide, metabolite, or endocrine disrupter that can elute from a gas chromatograph. The screening procedure relies on a new gas chromatographic technique called retention time locking (RTL)¹⁴⁻¹⁶ with database searching based on retention time and elemental content or detector response. This technique is used to narrow an analyte's identity to a few possibilities. Confirmation is performed by GC-MS or by calculation of a compound's elemental ratio using GC with atomic emission detection (GC-AED).

Experimental

Standards and Extracts

Pesticide standards used to develop the retention time table were obtained from Chem Service (West Chester, PA, USA), Promochem Ltd (Welwyn Garden City, Hertfordshire, England), Dr. Ehrenstorfer (Augsburg, Germany), Hayashi Pure Chemical Industries, Ltd (Osaka, Japan), Wako Pure Chemical Industries, Ltd (Osaka, Japan), and GL Sciences Inc (Tokyo, Japan).

Fruit and vegetable extracts were obtained from the Florida Department of Agriculture and Consumer Services (Tallahassee, FL, USA). Samples were extracted with acetonitrile followed by solid-phase extraction (SPE) using a C-18 cartridge. Extracts

intended for analysis by halogen-selective detectors were also subjected to floracil SPE.

Pesticide Retention Time Table

The table containing GC and GC-MS retention times for 567 pesticides, metabolites, and suspected endocrine disrupters was obtained from Agilent Technologies, Wilmington, DE, USA (G2081AA).

Instrumentation

Table 1 lists the instrumentation and chromatographic conditions used for GC-AED screening and GC-MS confirmation.

Software for Method Translation

Software for use in translating the normal GC method to one that runs three times faster was obtained from Agilent Technologies, Wilmington, DE, USA.¹⁷

Results and Discussion

Retention Time Locking

Key to the development of this method is a new concept in gas chromatography called retention time locking (RTL).¹⁴⁻¹⁶ Agilent RTL software allows the chromatographer to match analyte retention times from run to run, independent of the GC system, detector, or manufacturing variations in column dimensions. The only requirement is that the columns used have the same stationary phase and the same nominal diameter and phase ratio. For example, with RTL it is possible to match analyte retention times on a GC-AED and a GC-MS even though the MS operates under vacuum and the AED operates at 1.5 psi above ambient pressure. The

procedure also compensates for differences in GC column length resulting from variations in manufacturing or from column cutting required during routine maintenance.

RTL is accomplished by adjusting the GC column head pressure until a given analyte, such as an internal standard, has the desired retention time. When this is done, all other analytes in the chromatogram will have the correct retention times as well. Software has been developed that can be used to determine the column head pressure that will lock the retention times correctly after one or two “scouting” runs.

With RTL, it is possible to measure pesticide retention times using a given GC method, and then reproduce those retention times in subsequent runs on the same or different instruments. With this increased retention time precision and predictability, retention times become a far more useful indicator of analyte identity. For many years, relative retention times^{3,6} or retention indices^{18,19} have been used to identify compounds. These techniques were developed to compensate for the fact that retention times were not predictable from day to day, column to column, or instrument to instrument. With the increased retention time precision of the Agilent 6890 GC and RTL, it seemed that raw retention times could be used for compound identification instead of retention indices. The chromatographer could simply scan a table of pesticide retention times, eliminating all possibilities but those with close elution times under the same locked GC conditions.

Table 1. Instrumentation and Conditions of Analysis

Agilent GC-AED System	
Gas chromatograph	6890
Automatic sampler	6890 Series automatic sampler
Atomic emission detector	G2350A atomic emission detector
Computer for data acquisition and analysis	HP Vectra XM Series 4 5/150
Software	G2360AA GC-AED software running on Microsoft® Windows™ 3.11
Column	30 m × 0.25 mm × 0.25 µm HP-5MS (part no. 19091S-433)
GC inlet	Split/splitless, 250 °C or 260 °C
Inlet liner	Single-tapered deactivated (part no. 5181-3316) with 2-cm deactivated glass wool plug centered ~ 3 cm from the top
Injection volumes	3–5 µL splitless when running method at 3× speed; 2–3 µL splitless at 1× speed
Inlet pressure (splitless)*	87.5 psi constant pressure for method at 3× speed; 27.6 psi constant pressure for 1× speed
Inlet pressure program (pulsed splitless)*	60 psi (2.01 min), 10 psi/min to 27.9 psi (hold)
Oven temperature program	70 °C (2 min), 25 °C/min to 150 °C (0 min), 3 °C/min to 200 °C (0 min), 8 °C/min to 280 °C (10 min)
AED transfer line temperature	290 °C
AED cavity temperature	320 °C
AED elements and wavelengths (nm)	Group 1: Cl 479, Br 478 Group 2: C 193, S 181, N 174 Group 3: P 178 Group 4: F 690 (optional)
Agilent GC-MS System	
Gas chromatograph	6890
Automatic sampler	6890 Series automatic sampler
Mass selective detector	5973 MSD
Computer for data acquisition and analysis	HP Vectra XU 6/200
Software	G1701AA Version A.03.00 running on Microsoft® Windows® 95
Column	30 m × 0.25 mm × 0.25 µm HP-5MS (part no. 19091S-433)
Inlet	Split/splitless, 250 °C
Inlet liner	Single-tapered deactivated with small amount of glass wool at the bottom (part no. 5062-3587)
Injection volume	2 µL
Inlet pressure*	15.5 psi (constant pressure)
Oven temperature program	Same as GC-AED
MSD parameters	
Acquisition mode	Scan (35–550 amu)
EM voltage	200 rel
Solvent delay	3.20 min
Threshold	150
Scans/sec	2.86
Temperatures	Transfer line = 280 °C, MS quad = 150 °C, MS source = 230 °C

*The column head pressures shown are typical values. Exact values were determined as part of the retention time locking procedure.

Pesticides almost always contain heteroatoms and often have several in a single molecule. The most frequently encountered heteroatoms are O, P, S, N, Cl, Br, and F. GC with atomic emission detection (GC-AED) has been shown to be a useful tool for pesticide screening because it is selective for all of the elements found in these compounds.^{20–22} Thus, GC-AED screening provides valuable information about the elemental content of an unknown molecule. By including this elemental information along with the retention time, it should be possible to narrow pesticide “hits” to just a few possibilities.

To implement this screening procedure, a table of pesticide and endocrine disrupters retention times had to be created using a suitable method under locked conditions.

GC Method for Pesticide Screening

First, a GC method was needed that could elute hundreds of pesticides and endocrine disrupters in a reasonable time with adequate separation. However, the goal was not to separate every possible analyte in a single GC run. Because the intention was to build a table of locked retention times using this method, it had to reproduce these retention times under a variety of conditions. For example, the method needed to accommodate a variety of injection techniques including splitless, pulsed splitless,^{23,24} cold splitless using a PTV inlet, and on-column injection which is occasionally used for the more labile pesticides.

The method also needed to perform well with samples dissolved in common solvents such as acetone and methylene chloride. Because a retention gap (or guard column) is sometimes added to protect the analytical column, the method had to be

tested to see if it could still be locked with a retention gap installed.

The column chosen for the method was a 30 m × 0.25 mm × 0.25 μm HP-5MS because the same column could be used with any GC-detector combination. In particular, this column was chosen for its low bleed at high temperatures and because its optimum column flow is compatible with GC-MS. The 5% phenyl methyl silicone phase in this column has been widely used for pesticides.

Method translation software^{17,25,26} can be used to increase the speed of a method while retaining the same relative retention times. This can be done by translating the method to a column having the same phase ratio but a smaller id or by increasing the flow rate and oven temperature program while using the same column. The final goal was to design a method that could run at three times the normal speed on the 30-m × 0.25-mm × 0.25-μm HP-5MS column or be translated to a 100-μm id column.

After several weeks of method development, the GC oven temperature program shown in figure 1a was chosen because it met all of the development criteria. Chlorpyrifos-methyl (C₇H₇Cl₃NO₃PS) was chosen as the locking standard. It is an ideal choice because chlorpyrifos-methyl elutes near the middle of the chromatogram (16.596 minutes), has good peak shape, and can be seen by most element-selective detectors. Because GC-AED requires three runs to generate element-selective chromatograms for C, Br, Cl, N, S, and P, the method was translated to run three times faster using software for method translation.^{17,25,26} The faster oven temperature program used by this method requires 6890 GC systems that are configured for fast oven tem-

perature ramping. The method translation software can be used to speed up the method by any desired factor; even 120-V 6890 GCs can run the method two times faster. However, the original method must be used for GC-MS because of the restriction in flow rates into the MSD. Figure 1b lists the threefold (3×) faster GC method.

Pesticide Retention Time Table

Once developed, this method was employed to create a table of locked retention times for the 567 pesticides, metabolites, and suspected endocrine disrupters. Increasing international food trade requires the analysis of pesticides that may be used in the supplying country but not in the recipient country. The goal was to create a table that included pesticides used around the world so pesticide standards were obtained from sources in Europe, Japan, and the USA.

A list of suspected endocrine disrupters was compiled from various lists published on the World Wide Web.^{27–31} Many of these compounds are, in fact, pesticides. Most of the GC-amenable endocrine disrupters were analyzed and their retention times appear in the table. However, the 209 polychlorinated biphenyl congeners were not included because their inclusion might actually complicate the identification of organochlorine pesticides.

Standards, diluted to 10 ppm in acetone, were first analyzed by GC-MS using the oven temperature program shown in figure 1a and instrumental conditions listed in table 1. Compound identities were verified by matching their spectra to library entries,³² by comparison with a published spectral compendium,³³ or by matching spectra to a list of charac-

teristic ions.⁶ When reference spectral information was not available, the pesticides were verified by spectral interpretation. Samples were then analyzed on two different 6890 GC-FID instruments under the same locked conditions (chlorpyrifos-methyl retention time = 16.596 minutes). The GC-MS retention time and the average of the two GC-FID retention times were tabulated for each compound along with its molecular formula, molecular weight, and CAS number. In addition to these fields, there are four user-definable columns in table 2 that can be used to add such things as mass spectral information, internal catalog numbers, or comments. Table 2 lists a small portion of the database. It must be noted that all retention time values were created using constant column head pressure. This is because GC-MS retention times are very close to those obtained with other detectors when constant pressure is used. In this mode, GC-MS and GC-FID retention times match within ± 0.1 minute except for three compounds that elute at the very end of the chromatogram. Even in this case, the differences are no more than 0.2 minute. The discrepancy between GC-MS and GC-FID retention times is larger in the constant flow mode.

Pesticide Screening Method

Figure 2 diagrams the pesticide screening method. First, RTL was used to match GC-AED and GC-MS analyte retention times to those listed in the pesticide table. Software for RTL¹⁴⁻¹⁶ was used to determine the




Figure 1. a) GC oven temperature program for the Agilent pesticide method at normal speed. When using this method, chlorpyrifos-methyl must be locked to 16.596 minutes. This method is used by GC-MS and can be used by any other GC system. b) GC oven temperature program for the Agilent pesticide method translated to run three times faster. This method may be used with 6890 GCs configured with any detector except an MSD so long as the GC is configured for fast oven temperature ramping. Chlorpyrifos-methyl must be locked to 5.532 minutes.

Table 2. Small Portion of the Pesticide and Endocrine Disrupter Retention Time Table That Contains 567 Entries. The retention times shown here are for the pesticide method run at normal speed as shown in figure 1a. Chlorpyrifos-methyl was locked to 16.596 minutes (± 0.015 minute for the collection of the tabulated retention time values. The table includes four additional columns for user-defined information.

FID RT	Name	CAS No.	Molecular Formula	MW	MSD RT
16.542	Acetochlor	34256-82-1	C:14,H:20,Cl:1,N:1,O:2,	269.77	16.542
16.549	Fuberidazole	3878-19-1	C:12,H:8,N:2,O:1,	196.21	16.549
16.583	Methyl parathion	298-00-0	C:8,H:10,N:1,O:5,P:1,S:1,	263.20	16.594
16.596	Chlorpyrifos methyl	5598-13-0	C:7,H:7,Cl:3,N:1,O:3,P:1,S:1,	322.53	16.593
16.637	Vinclozolin	50471-44-8	C:12,H:9,Cl:2,N:1,O:3,	286.11	16.630
16.650	Plifenat	21757-82-4	C:10,H:7,Cl:5,O:2,	336.43	16.641
16.689	Terbucarb	001918-11-2	C:17,H:27,N:1,O:2,	277.41	16.686
16.730	Chloranocryl	2164-09-2	C:10,H:9,Cl:2,N:1,O:1,	230.09	16.736
16.752	3-Hydroxycarbofuran	16655-82-6	C:12,H:15,N:1,O:4,	237.26	16.741
16.773	Heptachlor	76-44-8	C:10,H:5,Cl:7,	373.32	16.796
16.800	Carbaryl	63-25-2	C:12,H:11,N:1,O:2,	201.22	16.806

column head pressure needed to produce a retention time of 16.596 minutes for chlorpyrifos-methyl. When analyzing samples by GC-AED, the method was usually run at 3× speed and chlorpyrifos-methyl was locked to 5.532 minutes.

Figure 3 shows the RTL software screen that is used to develop the retention time calibration. To accomplish this for the pesticide method, one should install the 30 m × 0.25 mm × 0.25 µm HP-5MS column (part no. 19091S-433) and set the column head pressure to one of the appropriate nominal values as shown below, making sure to use the constant pressure mode.

- 26 psi for atmospheric pressure detectors run at normal speed (eg, NPD, FPD)
- 16 psi for GC-MSD operated at normal speed
- 27.5 psi for GC-AED operated at normal speed
- 88 psi for GC-AED operated at 3× speed

To prepare a calibration table similar to the one shown in figure 3, the chromatographer must make five analyses of chlorpyrifos-methyl at the following column head pressures: the nominal pressure, the nominal pressure + 20%, the nominal pressure + 10%, the nominal pressure – 10%, and the nominal pressure – 20%. Because of the first run affect, it is usually wise to make one or two blank runs before performing the five calibration runs. The five pressures and the chlorpyrifos-methyl retention times are entered into the table provided by the RTL software. This calibration table stays with the method and can be used to lock, or re-lock, the GC




Figure 2. Diagram of the screening method that uses retention time locking and retention time table searching to identify pesticides and suspected endocrine disrupters.

	Pressure	Ret Time
Run 1	22.08	17.831
Run 2	24.84	17.006
Run 3	27.6	16.302
Run 4	30.36	15.683
Run 5	33.12	15.145

Pressure Units:

Desired Ret Time:

Min relock pressure:

Max relock pressure:

Column:

Compound Name:

Buttons: OK, Cancel, Print, Help

Figure 3. RTL software screen showing typical retention time locking calibration data for the pesticide method run at normal speed using a GC detector that operates at atmospheric pressure.

method as long as that method is used. That is, the five calibration runs only need to be made once for a given method.

The software screen for locking the GC method is shown in figure 4. To lock the method, one enters the retention time of chlorpyrifos-methyl and clicks on the “Calc new pressure” button. The RTL software calculates the pressure needed to lock the chlorpyrifos-methyl peak at the desired retention time. By clicking on the “Update current 6890 Method” button, this value is entered automatically into the method.

One can use Agilent’s software for method translation¹⁷ to convert the method to other speeds (eg, 1.9×) and determine the nominal column head pressure required. If this is done, the pesticide table must be exported to a spreadsheet program where the analyte retention times can be divided by the appropriate factor (1.9 in this case). This new table can then be imported back into the ChemStation for use with the new method.

After locking the method to the table, GC-AED element-selective chromatograms were obtained for C, Cl, Br, N, S, P, and sometimes F. From the GC-AED chromatograms, it was usually possible to determine which heteroatoms were present or absent in the suspected pesticide peak. RTL software was then used to search the database by retention time and elemental content. Figure 5 shows the RTL software screen used for retention time table searching. One can enter the elements known to be present or not present in the GC-AED peak of interest. Up to six other element-selective detectors can be configured for use in the search algorithm. When the presence or absence of a heteroatom is uncertain,

(Re)Lock current method

Retention time:
Enter current retention time of:
chlorpyrifos-methyl
16.581 Minutes
Then select button 'Update Method' to calculate a new pressure and enter it in the method.

Method Information:
Current Method: RLPESCHK.
Column: 1
Pressure used: 26.39 psi
Desired RT: 16.596 Minutes
Calc new pressure: 26.33 psi

Update current HP6890 Method Print Done Help

Figure 4. RTL software screen used to calculate the column head pressure needed to lock or re-lock a method. In this case, the chlorpyrifos-methyl retention time was 16.581 minutes and the pressure needed to re-lock the method was calculated to be 26.33 psi. By clicking on the “Update current 6890 Method,” button, the new pressure is entered automatically into the GC method.

Search Retention Time Table

Load Table... HPPSTRC5.RTT : HP Pesticide RT Table Release Candidate 5

16.638 Search RT, minutes
0.2 Search Window, minutes

Compound contains these elements:
☐ Br ☐ Cl ☐ F ☒ N ☐ O ☒ P ☒ S
☐ ☐ ☐ ☐ ☐ ☐ ☐

Does not contain these elements:
☒ Br ☒ Cl ☐ F ☐ N ☐ O ☐ P ☐ S
☐ ☐ ☐ ☐ ☐ ☐ ☐

Compound detected with:
 NPD ☐
 FPD (P) ☐
 FPD (S) ☐
 ELCD ☐

Not detected with:
 NPD ☐
 FPD (P) ☐
 FPD (S) ☐
 ELCD ☐

Search Cancel Help

Figure 5. RTL software screen used to search a retention time table on the basis of retention time and known elemental content. In this case, the software will search the Agilent pesticide table at 16.638 ± 0.1 minutes for compounds that contain N, P, and S but do not contain Br or Cl. If element-selective detectors (such as the NP) are used, this information can be provided to the search routine. Up to six different element-selective detectors can be configured as shown for NP, FP, and ELCD.

nothing is added to the search routine for that element.

One must choose a search time window wide enough to include the correct analyte, but narrow enough to eliminate as many extraneous “hits”

as possible. Experience has shown that the normal speed method requires a search window of 0.2 to 0.3 minute. The 3× speed method can use a search window of 0.1 minute. If the heteroatom content is known for a peak, retention time table searching

with these search windows most often finds just one pesticide and rarely finds more than three possibilities.

Confirmation is usually done by GC-MS under locked conditions so that all GC-MS retention times match the values listed in the pesticide retention time table. This was found to be of enormous benefit. Prior to GC-MS confirmation, the analyst already knows which pesticides to look for and their expected retention times. Alternatively, when there is adequate signal to quantitate the analyte in multiple AED element-selective chromatograms, it is often possible to confirm a pesticide's identity simply by calculating its heteroatom ratio. GC-AED software for element ratioing facilitates this procedure.

Analysis of a Green Onion Extract

Numerous samples of fruit and vegetable extracts have been analyzed using this methodology. The results for a green onion extract illustrate the versatility and potential of this method.

Green onion extracts are usually very dirty and contain a large number of co-extracted sulfur compounds that can obscure sulfur-containing pesticides. The onion chromatograms shown in figure 6 were run under locked conditions at 2× speed in Tallahassee, Florida, by the Department of Food and Agriculture using a 5890 SERIES II/5921A GC-AED system. Retention time searching indicated that folpet was present in the sample, but it could not be confirmed at the time. The same sample was sent to the Agilent Technologies Little Falls Site in Wilmington, DE, where it was analyzed by scanning GC-MS using an 6890/5973 system. As shown in figure 7, folpet was

easily confirmed at the expected retention time. In addition, the pesticides trichlorophenol, chlorothalonil, propoxur, and prochloraz were identified. Searching the CI peak at about 6 minutes gave no pesticide hits. However, GC-MS suggested the presence of a trichloronaphthalene isomer at the corresponding retention time in the GC-MS chromatogram (about 12 minutes because the GC-MS was operated at normal speed). Though not a pesticide, trichloronaphthalene is considered to be a hazardous compound that should not be in food.

The same green onion sample was then analyzed by the newer model GC-AED system (6890/G2350A) at 3× speed (figure 8). Several more pesticides were identified by searching the pesticide/ endocrine disrupter table using a 0.1-minute retention time window. Table 3 lists the pesticide hits that were obtained for each retention time search using the available GC-AED data. Sulfur was not included in any of the searches

because onion extracts have such a high sulfur background.

Confirmation by GC-MS was much easier because the GC-MS retention time for each pesticide hit was printed out with the RT search report. Thus, the retention times and probable identities of each pesticide were already known before the GC-MS analysis was run. As is shown in figure 7 for folpet, one can simply extract the ions characteristic for each pesticide hit and look in the extracted ion chromatogram at the expected retention time.

Quantitative Analysis

The Agilent pesticide screening method is a qualitative tool to identify any of the 567 pesticides and endocrine disrupters listed in the retention time table. This, of course, is the first step in any pesticide screening method. Quantitative analysis can be performed in one of two ways.




Figure 6. CI- and N-selective chromatograms of a green onion extract from an 5890/5921A GC-AED system. The analysis was performed at 2× speed under locked conditions in Tallahassee, Florida, by the Department of Agriculture and Consumer Services. In addition to folpet, trichlorophenol, propoxur, and prochloraz were identified by retention time table searching and confirmed by GC-MS at their expected retention times. There were no hits for the CI peak at about 6 minutes, which was identified by GC-MS as a trichloronaphthalene isomer.

The traditional method is to inject standards into the GC, GC-AED, or GC-MS system to determine response factors from which quantitative results are calculated by the ChemStation software. However, because the GC-AED elemental response is almost independent of molecular structure, compound-independent calibration (CIC) can be used to quantitate all of the pesticides and endocrine disrupters that are found. For example, one could spike chlorpyrifos-methyl ($C_7H_7Cl_3NO_3PS$) at a known concentration into each pesticide extract and obtain element-specific calibration curves for Cl, N, P, and S. These curves could then be used to calibrate for any other compound containing one or more of these elements. Because the GC-AED is quite stable, external standard CIC often works just as well. The GC-AED software facilitates CIC. Unfortunately, this procedure determines the amount of a compound that reaches the AED and does not compensate for losses due to decomposition or adsorption in the inlet or column.

Conclusions

Most screening procedures in use today are capable of finding only a fraction of the pesticides that are registered around the world. This new method has the capability of screening for virtually any volatile pesticide, metabolite, or endocrine disrupter. Although confirmation is usually required, GC-MS analysis is made much easier and more reliable because the pesticide's retention time and probable identity are already known.




Figure 7. Confirmation of folpet in a green onion extract. The tabulated GC-MS retention time is 21.594 minutes, and folpet was detected in this sample at 21.637 minutes by simply extracting its characteristic ions.




Figure 8. Element-selective chromatograms obtained for the same green onion extract shown in figure 6. These chromatograms were obtained at 3× speed using an 6890/G2350A GC-AED system.

While GC-AED is an ideal tool for element-selective pesticide screening,^{20–22} many laboratories rely on a combination of other selective detectors. It is still possible to apply this method if each GC system runs the Agilent pesticide method under the same locked conditions. Any combination of GC-AED and/or element-selective detector response data can be entered into the RTL searching software.

When combined with RTL and retention time searching, GC-AED and GC-MS provide the most comprehensive and reliable screening method available for pesticides, metabolites, and suspected endocrine disrupters. Unlike most target compound methods in use today, this procedure has a good chance of finding and identifying unexpected or unknown pesticides, even in complex food extracts. RTL software makes it easy to add more compounds to the method, simply by determining their retention times under the same locked conditions.

Retention time locking with database searching could easily be applied to similar types of analyses. For example, one might use the procedure to identify polychlorinated biphenyls, polynuclear aromatics, drugs of abuse, or flavor and fragrance compounds.

Acknowledgments

The authors wish to thank the following people for their contributions to the development of this method: Joanne Cook and Marc Engel (Florida Department of Agriculture and Consumer Services) for supplying a green onion chromatogram, for contributing fruit and vegetable extracts, and for

Table 3. Green onion pesticide "hits" obtained by searching the 567-compound pesticide/endocrine disrupter RT table using a 0.1-minute RT window and element-selective GC-AED data. Compounds confirmed by GC-MS are shown for comparison. The GC/MS (figure 7) and GC-AED (figure 8) chromatograms were obtained at normal and 3X speeds, respectively. Sulfur peaks were not used to narrow the search because of the high background of sulfur-containing compounds in the onion extract.

GC-AED RT	RT Search Hits	Confirmed by GC-MS
1.933	Dichlorvos	Dichlorvos
2.281	2,4,6-Trichlorophenol 2,4,5-Trichlorophenol	2,4,5-Trichlorophenol
3.440	Fenobucarb Propoxur 4,6-Dinitro-o-cresol	Propoxur
3.854	No pesticide hits	Trichloronaphthalene isomer
4.955	Terbacil Chlorothalonil	Chlorothalonil
5.538	Chlorpyrifos-methyl	Chlorpyrifos-methyl
7.232	Folpet Chlorbenside	Folpet
9.965	Mirex	Mirex
10.588	Prochloraz	Prochloraz

beta testing the method; Matthew Klee and Leonid Blumberg for many useful discussions; and James Green and Takeshi Otsuka for their help in developing the retention time table.

References

1. C. Tomlin (Ed.), *The Pesticide Manual*, Eleventh Edition, British Crop Protection Council, Farnham, Surrey, UK, 1997.
2. R. W. Miller, *This is Codex Alimentarius*, Secretariat of the Joint FAO/WHO Food Standards Programme, Food and Agriculture Organization of the United Nations, Rome.
3. B. M. McMahon and N. F. Hardin (Eds.), *Pesticide Analytical Manual*, Vol. I, Third Edition, U.S. Food and Drug Administration, Washington, D.C., 1994.
4. S. M. Lee, M. L. Papathakis, H.-M. C. Feng, G. G. Hunter, and J. E. Carr, *Fresenius' J Anal Chem* **339**, 376–383, 1991.
5. J. Fillion, R. Hindle, M. Lacroix, and J. Selwyn, *J AOAC Int* **78**, 1252–1266, 1995.
6. Working Group on Development and Improvement of Residue-analytical Methods, *Analytical Methods for Pesticide Residues in Foodstuffs*, General Inspectorate for Health Protection, Ministry of Public Health, Welfare and Sport, The Netherlands, 1996.
7. M. A. Luke, J. E. Froberg, G. M. Doose, and H. T. Masumoto, *J Assoc Off Anal Chem* **64**, 1187–1195, 1981.
8. H.-J. Stan (Ed.), *Analysis of Pesticides in Ground and Surface Water II*, Springer-Verlag, Berlin, Germany, 1995.
9. R. E. Wagner, W. Kotas, and G. A. Yogis (Eds.), *Guide to Environmental Analytical Methods*, 2nd Edition Genium, Schenectady, NY, 1994.
10. U.S. Environmental Protection Agency, *Test Methods for Evaluating Solid Waste*, SW-846, Draft Method 8085: Pesticides by GC-AED.

11. T. Colborn, D. Dumanoski, and J. P. Myers, *Our Stolen Future* Penguin, New York, NY, 1996.
12. Food Quality Protection Act of 1996, Public Law 104-170, Congressional Record, pp. H8127–H8141.
13. Safe Drinking Water Act Amendments of 1996, Public Law 104-182, Congressional Record pp. H9680–H9700.
14. V. Giarrocco, B. Quimby, and M. Klee, Retention Time Locking: Concepts and Applications, Application Note 228-392, Publication (23) 5966-2469E, December 1997.
15. P. L. Wylie and B. D. Quimby, Abstracts of the 1st European Pesticide Residue Workshop, Alkmaar, The Netherlands, Paper # O-023, June 10–12, 1996.
16. M. Klee and T. Sullivan, Environ. Testing and Analysis, pp. 16–17 and 44–45, March/April 1998.
17. Hewlett Packard Company, *Software for Method Translation*, Available on the World Wide Web at: <http://www.chem.agilent.com/cag/servsup/usersoft/main.html>.
18. M. L. Lee, F. J. Yang, and K. D. Bartle, *Open Tubular Column Gas Chromatography, Theory and Practice*, Wiley, New York, NY, pp. 217–218, 1984.
19. C. Bicchì, A. D'Amato, and A. Binello, *J High Resol Chromatogr* **19**, 80–84, 1996.
20. S. M. Lee and P. L. Wylie, *J Agric Food Chem* **39**, 2192–2199, 1991.
21. P. L. Wylie and R. Oguchi, *J Chrom* **517**, 131–142, 1990.
22. N. L. Olson, R. Carrell, R. K. Cummings, and R. Rieck, *LC-GC* **12**, 142–154, 1994.
23. P. L. Wylie and K. Uchiyama, *J AOAC Int* **79**, 571–577, 1996.
24. P. L. Wylie, K. L. Klein, M. Q. Thompson, and B. W. Hermann, *J High Resol Chromatogr* **15**, 571–577, 1992.
25. W. D. Snyder and L. M. Blumberg, *Proceedings of the Fourteenth International Symposium on Capillary Chromatography*, Baltimore, MD, pp. 28–38, May 25–29, 1992.
26. B. D. Quimby, L. M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking," Application Note 228-401, Publication 5967-5820E, April 1998.
27. <http://www.nij.gov/hse/enviro/edsub/substancesnew.html>.
28. <http://www.wwfcanada.org/hormone-disruptors>.
29. <http://www.epa.gov/opptintr/opptendo/index.htm>.
30. <http://www.osf-facts.org/basics.chemlist.html>.
31. <http://www.mst.dk/liste.htm>.
32. Hewlett-Packard Company. Mass Spectral Libraries: HP Pest library, Wiley 275 library, NBS75K Library, Palo Alto, CA.
33. Pesticide Reference Spectra, Vol. 1–4, Spectral Service GmbH, Köln, Germany and Riedel-de Haën AG, Seelze, Germany, 1992.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Microsoft® and Windows NT® are U.S. registered trademarks. HP® is a registered trademark of Hewlett-Packard Company.

Copyright ©2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5967-5860E



Agilent Technologies
Innovating the HP Way



Analysis of EDB and DBCP in Water with the Agilent 6890 Series Gas Chromatograph and Agilent 6890 Micro-Electron Capture Detector — EPA Method 504

Application

Gas Chromatography

August 1997

Authors

Imogene L. Chang
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Joseph Murphy
Roy F. Weston Company
Lionville Lab
Lionville, PA 19341
USA

Abstract

The pesticides 1,2-ethylene dibromide (EDB) and 1,2-dibromo-3-chloropropane (DMCP) were analyzed by dual-column gas chromatography with dual micro-electron capture detectors (Agilent 6890 micro-ECDs) after micro-extraction with hexane in accordance with U.S. EPA method 504.

Stability, sensitivity, and linearity of the micro-ECD were significantly better than the classical ECD. Relative standard deviation (% RSD) for the entire method was less than 7% over a

concentration range greater than two orders of magnitude with method detection limits of 0.003 µg/L or lower.

Key Words

Micro-ECD, 6890 GC, EPA Drinking Water Method 504, ethylene dibromide, 1,2-dibromo-3-chloropropane, GC/ECD analysis

Introduction

Ethylene dibromide (EDB) and 1,2-dibromo-3-chloropropane (DBCP) are volatile pesticides and suspect carcinogens. The U.S. EPA regulates maximum contaminant levels (MCLs)

for these compounds in drinking water supplies at very low levels (EDB at 0.05 µg/L and DBCP at 0.2 µg/L). Both EDB and DBCP can be determined by performing a micro-extraction with hexane and analyzing the extract by gas chromatography using an electron capture detector (ECD), as described in EPA Method 504.¹

EPA method 504 reported method detection limits (MDLs) of 0.01 µg/L for both pesticides.^{1,2} Results using an Agilent 6890 GC with the micro-ECD show that these analytes can be determined down to 0.01 µg/L with MDLs of less than 0.003 µg/L. The micro-ECD had a stable baseline and was linear from 0.010 to 1.14 µg/L.

Table 1. Experimental Conditions

Sampler	Agilent 7673, 10-µL syringe, 2-µL splitless injection
Inlet	Split/splitless; 200 °C, pulsed splitless mode (20 psi for 1 min)
Carrier	Helium, 6 psi (40 °C); 3.5 mL/min constant flow (each column)
Column	(A) 30 m, 0.53-mm id, 0.8-µm film DB-608, an equivalent of HP-608 (part number 19095S-023) (B) 30 m, 0.53-mm id, 1.0-µm film RTX-1701, an equivalent of HP-PAS 1701 (part number 19095S-123)
Oven	40 °C (4 min); 10 °C/min to 240 °C
Detector	330 °C; Makeup gas: nitrogen, constant column and makeup flow (60 mL/min)



Agilent Technologies
Innovating the HP Way

Experimental

Samples and standards were prepared as described in EPA drinking water method 504.¹ All analyses were performed using a 6890 Series GC with a single split/splitless inlet and dual micro-ECDs. Instrument conditions are listed in table 1.

A water sample (35 mL) was extracted with 2 mL of hexane. From that extract, 2 μ L were injected into the 6890 Series GC in the splitless mode. A "Y" connector was used to split the sample equally between two polar but dissimilar columns. Column A (an equivalent of the HP-608 column), which provided separation of EDB and DBCP without interference from trihalomethanes, was used as the primary analytical column. Column B (an equivalent of the HP-1701 column) was used as the confirmation column. These columns were previously installed and used in the GC system to analyze pesticides and arachnids according to U.S. EPA CLP and 8080/8081 methods.

Results and Discussion

A common problem in determining EDB and DBCP in drinking water by gas chromatography/electron capture detection (GC/ECD) is interference from chlorination disinfection by-products such as trihalogenated methanes. For example, dibromochloromethane (DBCM), commonly found in drinking water supplies in relatively high concentrations, can elute very close to EDB and thus can be misidentified as EDB.

Using the optimized GC conditions listed in table 1, EDB was clearly separated from significant levels of DBCM on both columns. Typical chromatograms of a hexane extract of a calibration standard are shown in

figure 1. Both EDB and DBCP are well separated from possible interference, including DBCM and dibromomethane (DBM).

Micro-ECD Linearity

Linearity of the 6890 micro-ECD was determined by preparing standards from 0.005 to 1.14 μ g/L in reagent water. The standards were extracted according to EPA method 504 and analyzed by gas chromatography. Typical average response factors (based on peak heights), relative standard deviations (% RSD) of response factors (RFs), and correlation coefficients of the linear curves are listed in table 2.

Figure 2 shows linear calibration curves for EDB and DBCP with correlation coefficients better than 0.999

(see table 2). The % RSD of RFs was 4% to 7%, over a concentration range greater than two orders of magnitude (0.005 to 1.14 μ g/L). This easily met method 504 requirements for 20% RSD for a similar concentration range. The micro-ECD continued to meet these requirements over a period of 2 to 3 months with little or no maintenance required except for routine septum and liner changes.

MDLs, Precision, and Accuracy

Method detection limits (MDL) were calculated according to EPA method 504 by analyzing seven replicate extracts of a low-level standard (0.02 μ g/L). As shown in table 3, the MDLs were 0.002 and 0.003 μ g/L for EDB and DBCP, respectively. These MDLs were three- to five-fold below those reported by EPA method 504




Figure 1. Hexane extract of a midpoint calibration standard (EDB/DBCP = 0.286 μ g/L each).

Table 2. Typical Linearity on Column A*

Analyte	EDB	DBCP
Average response factor (RF)	4.66E-06	2.06E-06
Standard deviation, RF	2.19E-07	1.45E-07
%RSD, RF	4.69%	7.01%
Correlation coefficient	0.9992	0.9997

* Seven-level calibration at 0.0057, 0.020, 0.0571, 0.114, 0.286, 0.571, and 1.141 μ g/L




Figure 2. Typical calibration curves on column A

Table 3. MDLs, Precision, and Accuracy

Analyte	EDB	DBCP
Spiked concentration, µg/L	0.02	0.02
Number of replicates	7	7
MDL, µg/L	0.002	0.003
Spiked concentration, µg/L	0.20	0.20
Number of replicates	6	6
Average concentration, µg/L	0.202	0.205
Reproducibility, % RSD	5.3%	5.4%
% Recovery	101%	103%

and a Collaborative Study by K. W. Edgell and J. E. Longbottom.²

Six extracts of reagent water samples fortified with 0.20 µg/L of EDB and DBCP were analyzed. Both precision and accuracy were excellent, with reproducibility at 5% RSD and recovery of around 100% (see table 3).

Ruggedness of the 6890 Micro-ECD

For the detector to meet the low detection limit requirements, the chromatographic baseline must be clean and stable. In this study, the 6890 micro-ECD provided a clean baseline with no negative deflections during continuous operation over a period of 3 months. A variety of samples were also analyzed, including

soil pesticide extracts that contained many late-eluting compounds (see figure 3). The 6890 micro-ECD showed rapid recovery even though this instrument had been switched from a drinking water method (EPA method 504) to solid waste methods (EPA method 8080/8081 and CLP method for pesticides and arochlors³), and back again.

EPA method 504 requires a continuous calibration (using a midlevel standard) for each 12-hour shift of operation or every 10- to 20-sample analyses. The retention times and the responses for these continuous calibration runs must match those from the initial calibration run with specific limits. The difference in responses (%D) between the later calibration run and the initial run must be less than 15%.

Table 4 presents the results of the sequence runs on the 1st, the 15th, and the 27th day of a month when samples were continuously analyzed according to EPA method 504. Responses of the 6890 micro-ECD proved to be quite stable over 3 to 4 weeks of continuous operation. The %D of EDB and DBCP did not vary by more than 10%, easily meeting the method requirement of 15%.

Conclusion

The Agilent 6890 Series GC with the micro-ECD can detect low levels of EDB and DBCP in drinking water and water supplies. All EPA method 504 criteria were easily met, yielding MDLs of 0.003 µg/L or less, reproducibility of 7% or less, and a linearity with correlation better than 0.999 over a concentration range greater than two orders of magnitude.

The system performance was stable for a long time (3 months), despite switching methods between EPA method 504 and CLP method for pesticides and arochlor. Stability, sensitivity, and linearity of the 6890 micro-ECD were significantly improved over the classical 6890 ECD.




Figure 3. Typical chromatograms of sample extracts*

*The soil sample was analyzed according to EPA CLP method for pesticides along with 30 to 40 other samples in a sequence run.⁴ No target pesticide was detected in this particular sample. The water sample was analyzed along with 20 other water samples based on EPA method 504 on the next day after the 6890 system was switched from the CLP method. No DBCP was found in any sample, and EDB was detected in only 3 to 4 samples. EDB in this sample was at the 0.01- to 0.02-ppb level. These chromatograms were plotted on different scales. Note the high signal for the soil sample. This demonstrates that it was possible to shift very quickly from analyzing dirty soil samples to analyzing low-level water samples using the 6890 system with micro-ECD.

Table 4. System Performance

	Run	Retention Time		Responses		%D	
	No.	EDB	DBCP	EDB	DBCP	EDB	DBCP
Day 1 Sequence							
Initial calibration	7	8.16	14.62	28486	70242		
Continuous calibration	19	8.16	14.62	29118	72434	2.2%	3.1%
Continuous calibration	30	8.16	14.61	28969	74268	1.7%	5.5%
Day 15 Sequence							
Initial calibration	7	8.11	14.58	30878	64439		
Continuous calibration	18	8.10	14.56	31684	66978	2.6%	0.8%
Continuous calibration	29	8.12	14.58	31241	71009	1.2%	6.9%
Continuous calibration	34	8.12	14.59	31219	70276	1.1%	5.8%
Continuous calibration	50	8.13	14.59	31689	72829	2.6%	9.6%
Continuous calibration	60	8.12	14.59	31627	72974	2.4%	9.8%
Day 27 Sequence							
Initial calibration	6	8.13	14.59	32203	76362		
Continuous calibration	19	8.13	14.59	31557	74711	-2.0%	- 2.2%
Continuous calibration	28	8.13	14.59	31855	75417	-1.1%	- 1.2%

* %D = (initial response - continuous calibration response) / initial response

References

1. "Methods for the Determination of Organic Compounds in Drinking Water" – Method 504, rev. 2.0, U.S. EPA (1991).
2. K. W. Edgell and J. E. Longbottom, "Determination of 1,2-Dibromoethane and 1,2-Dibromo-3-Chloropropane in Water by Microextraction and Gas Chromatography: Collaborative Study," *J AOAC Int.*, vol 77, p. 989 (1994).
3. Method 8081 – "Organochlorine Pesticides and PCBs as Arochlors by Gas Chromatography: Capillary Column Technique," September 1994 in U.S. EPA SW-836 "Test Methods for Evaluating Solid Wastes, Physical and Chemical Methods," Third Edition.
4. U.S. EPA Contract Laboratory Program "Statement of Work for Organic Analysis," OLM03.1, August 1994.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright ©2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5966-0495E



Agilent Technologies
Innovating the HP Way

Fast Screening of Pesticide and Endocrine Disruptors Using the Agilent 6890/5973N GC/MSD System, Part I



Application

Gas Chromatography
January 2000

Authors

C. Kai Meng
Agilent Technologies
2850 Centerville Road
Wilmington, Delaware 19808-1610
USA

Michael Szelewski
Agilent Technologies
2850 Centerville Road
Wilmington, Delaware 19808-1610
USA

Abstract

Agilent Technologies' new, fast GC/MSD method can significantly speed up the screening of pesticides. Agilent's GC method translation software (available free from the Agilent Technologies Web site, <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#mxlator>) was used in developing the new method based on the standard 42-min method. A 10 m x 0.1 mm x 0.1 μ m HP-5 column was used to increase analysis speed up to fourfold. The time savings were implemented in increments (down to 10.5 minutes) to verify the predictability of scaling and the effect of scaling on the signal-to-noise ratio.

Key Words

RTL, pesticide, environmental, screening, fast GC, method translation, 5973, 6890, MTL

Introduction

Analysts want faster analyses to improve laboratory productivity. Often, when speeding up GC methods, an analyst will trade resolution for increased analysis speed. This loss of resolution can complicate peak identification, even with a mass selective detector (MSD).

Agilent Technologies has developed new techniques to solve the peak identification problem based on Agilent's retention time locking (RTL) software and a new mass spectral library that contains the locked

retention times and characteristic ions for 567 of the most common pesticides and endocrine disruptors of concern worldwide. A GC/MSD method was developed based on the standard 42-min method¹ to screen for all 567 of the most common analytes. A specific combination of column stationary phase, carrier gas flow rate, and oven temperature programming is required to lock all the compounds to an expected retention timetable². Compound identification based only on spectral searching alone is difficult when analyzing extracts containing significant sample matrix content because of overlapping peaks and noisy baselines.

The new screening tool, integrated within Agilent's ChemStation for MSD, searches for all 567 compounds by first checking and integrating four characteristic ions within the expected time window, and second by printing out a report showing "hits" and "possible hits" (ratios of characteristic ions that do not match the expected values in the library within specified limits).

In one application, the analysis time of the standard pesticide method was reduced by one half, two-thirds, and three-fourths. The faster methods were scaled exactly as predicted by using a combination of Agilent's method translation (MTL) and RTL software. Because scaling was exact, these faster methods can be used with precisely-scaled pesticide libraries, making the screening process even more powerful and adaptable to individual needs.



Agilent Technologies
Innovating the HP Way

The GC method translation software tool was used to find operating conditions for the faster methods. Figure 1 is a screen capture of MTL software data entry showing the original conditions and the new chromatographic conditions for a twofold speed gain. The column flow rate, which is helpful to avoid exceeding MSD pumping capacity³, is also found in the table. A 16:1 split ratio was suggested in the table as a proportional scaling from the original column to the smaller i.d. column with corresponding lower capacity. The program also determined the required column head pressure and corresponding oven ramp. The Agilent 6890 GC fast oven option (220/240V in the U.S.) was required for the faster oven ramp used in this study.

GC Method Translation - RTL2X.MXD

Criterion: ☐ Translate Only ☐ Best Efficiency ☐ Fast Analysis ☒ None Speed gain: 2.00000

		Original Method	Translated Method																																				
Column																																							
Length,	m	30.00	☐ 10.00																																				
Internal Diameter,	μm	250.0	☐ 100.0																																				
Film			☐ Unlock																																				
Thickness,	μm	0.250	☐ 0.100																																				
Phase Ratio		250.0	☒ 250.0																																				
Carrier Gas		Helium	☐ Helium																																				
Enter one Setpoint			☒ Unlock																																				
Head Pressure,	psi	18.000	☐ 30.715																																				
Flow Rate,	mL/min	1.9015	☐ 0.2817																																				
Outlet Velocity,	cm/sec	Very large	Very large																																				
Average Velocity,	cm/sec	50.30	☐ 33.53																																				
Hold-up Time,	min	0.994049	☐ 0.497025																																				
Outlet Pressure (absolute),	psi	0.000	☒ 0.000																																				
Ambient Pressure (absolute),	psi	14.696	☒ 14.696																																				
Oven Temperature 3-ramp Program		<table border="1"> <thead> <tr> <th>Ramp Rate</th> <th>Final Temp.</th> <th>Final Time</th> </tr> <tr> <th>°C/min</th> <th>°C</th> <th>min</th> </tr> </thead> <tbody> <tr> <td>Initial</td> <td>70.00</td> <td>2.000</td> </tr> <tr> <td>Ramp 1</td> <td>25.000</td> <td>150.00</td> </tr> <tr> <td>Ramp 2</td> <td>3.000</td> <td>200.00</td> </tr> <tr> <td>Ramp 3</td> <td>8.000</td> <td>280.00</td> </tr> </tbody> </table>	Ramp Rate	Final Temp.	Final Time	°C/min	°C	min	Initial	70.00	2.000	Ramp 1	25.000	150.00	Ramp 2	3.000	200.00	Ramp 3	8.000	280.00	<table border="1"> <thead> <tr> <th>Ramp Rate</th> <th>Final Temp.</th> <th>Final Time</th> </tr> <tr> <th>°C/min</th> <th>°C</th> <th>min</th> </tr> </thead> <tbody> <tr> <td>Initial</td> <td>70.00</td> <td>1.000</td> </tr> <tr> <td>Ramp 1</td> <td>50.000</td> <td>150.00</td> </tr> <tr> <td>Ramp 2</td> <td>6.000</td> <td>200.00</td> </tr> <tr> <td>Ramp 3</td> <td>16.000</td> <td>280.00</td> </tr> </tbody> </table>	Ramp Rate	Final Temp.	Final Time	°C/min	°C	min	Initial	70.00	1.000	Ramp 1	50.000	150.00	Ramp 2	6.000	200.00	Ramp 3	16.000	280.00
Ramp Rate	Final Temp.	Final Time																																					
°C/min	°C	min																																					
Initial	70.00	2.000																																					
Ramp 1	25.000	150.00																																					
Ramp 2	3.000	200.00																																					
Ramp 3	8.000	280.00																																					
Ramp Rate	Final Temp.	Final Time																																					
°C/min	°C	min																																					
Initial	70.00	1.000																																					
Ramp 1	50.000	150.00																																					
Ramp 2	6.000	200.00																																					
Ramp 3	16.000	280.00																																					
Sample Information Liquid			☐ Unlock																																				
Injected Volume,	μL	1.0	☒ 1.0																																				
Split Ratio		0.00	☐ 16																																				
Effective on-Column Volume,	μL	1.0	0.058																																				
Nominal Column Capacity,	μL	0.017	0.00099																																				

Figure 1. Screen capture showing the method translation (MTL) software data entry used in a twofold speed gain translation.

General chromatographic conditions are listed in table 1. The standard used was a mixture of 26 pesticides at 10 ppm. A 10 m x 0.1 mm x 0.1 µm HP-5 column (part number 19091J-141) was used. The head pressure determined by the method translation software (30.72 psi) was used as the starting point for retention time locking. The column head pressure required to lock retention times of the compounds to the library (the original retention time divided by 2) was determined using the automated RTL process integrated within the Agilent ChemStation for MSD. This process (first translate the method then lock the retention times) was repeated for the threefold and fourfold time reductions.

Table 1. Chromatographic Conditions

Speed	Onefold (1X)	Twofold (2X)	Threefold (3X)	Fourfold (4X)
GC	110 V	220/240 V		
Column	30 m x 0.25 mm x 0.25 µm HP5-MS (P/N 19091S-433)	10 m x 0.1 mm x 0.1 µm HP-5 (P/N 19091J-141)		
Injection mode	Splitless	16:1 split		
Column head pressure	18.0 psi	36.55 psi	63.17 psi	90.0 psi
Column flow (mL/min)	1.5	0.4	0.8	1.5
Inlet control mode	Constant pressure	Constant pressure		
Carrier gas	Helium	Helium		
Injector temperature	250 °C	250 °C		
Oven temperature	70 (2 min)	70 (1 min)	70 (0.67 min)	70 (0.5 min)
Ramp 1	25 °C/min	50	75	100
	150 (0 min)	150 (0 min)	150 (0 min)	150 (0 min)
Ramp 2	3 °C/min	6	9	12
	200 (0 min)	200 (0 min)	200 (0 min)	200 (0 min)
Ramp 3	8 °C/min	16	24	32
	280 (10 min)	280 (5 min)	280 (3.33 min)	280 (2.5 min)
Oven equilibration	2 min	2 min		
Injection volume	1 µL	1 µL		
Liner	5183-4647	5183-4647		
MS Conditions				
Solvent delay	3 min	1.8 min	1.2 min	0.9 min
Tune file	Atune.u	Atune.u		
Low mass	35 amu	35 amu		
High mass	500 amu	450 amu		
Threshold	150	250		
Sampling	2	2	1	1
Scans/sec	3.15	3.50	6.54	6.54
Quad temperature	150 °C	150 °C		
Source temperature	230 °C	230 °C		
Transfer line temperature	280 °C	280 °C		
Acquisition mode	Scan (EI)	Scan (EI)		

Figure 2 shows the results of the shortened analysis times. The three chromatograms look extremely similar, except that the time axis is scaled proportionally. Because MTL followed by RTL scales methods very precisely, scaled screening libraries for corresponding time reductions can be obtained by dividing the retention times in the library by the speed gain (which does not have to be an integer). The peak heights from all the methods are very similar. Although the sample was split 16:1 for the smaller column, the small column i.d. and faster oven ramp combination made the peaks narrower and higher, so there was minimal loss in the signal to noise ratio.

Conclusion

The highly accurate and reproducible pressure and temperature control of the Agilent 6890 GC allows precise scaling of the standard 42-min GC/MSD pesticide method. Run time was shortened to 10.5 minutes using a fast oven ramp rate and a 10-meter 100-micron column. The combination of MTL and RTL facilitated scaling and yielded exact scaling. RTL libraries can accurately be scaled to correspond to the faster analyses.

References

1. B. D. Quimby, L.M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking," Application Note 228-401, Agilent publication number 5967-5820E, May 1998.
2. H. Prest, P. L. Wylie, K. Weiner, and D. Agnew, "Efficient Screening for Pesticides and Endocrine Disruptors Using the HP 6890/ 5973 GC/MSD System," Agilent publication number 5968-4884E, April 1999.
3. H. Prest, "GC Column Selection and Pumping Considerations for Electron and Chemical Ionization MSD operation," Agilent publication Number 5968-7958E, November 1999.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright © 2000
Agilent Technologies

Printed in USA 2/00
5968-9220E




Figure 2. Three TICs of the 2X, 3X, and 4X speedups. The standard analysis (1X) was 42 minutes long. The two vertical lines on the figure are used as references to show the similarity of the TICs.



Agilent Technologies
Innovating the HP Way



Analysis of Bendiocarb and Metabolite by HPLC

Rainer Schuster

Environmental

Abstract

The bendiocarb insecticide can be extracted from soil either with Soxhlet equipment or by ultrasonic treatment in solution and from water by either a liquid–solid or a liquid–liquid technique.

Separation

Figure 1 shows the separation on a 2.1 mm internal diameter Hypersil ODS column. A constant oven temperature of 40 °C is important here.

- UV-visible detection
- Diode-array detection—for simultaneous multiple wave-lengths and peak identity confirmation by spectra.




Figure 1
Separation of a 20 µl injection containing aldicarb, bendiocarb and metabolite monitored at 212 nm

Conditions

Column

100 x 2.1-mm Hypersil ODS C18, 5 µm

Mobile phase

Water–acetonitrile
(65:35 isocratic mixture)

Flow rate

0.36 ml/min

Temperature

40 °C

Detection

212 nm (16 nm bandwidth)
reference 450 nm (100 nm bandwidth)

Diode array detector performance

Detection limit 4 µg/l
(without sample enrichment)



Agilent Technologies

Innovating the HP Way

Sample preparation


Narrow-bore technology for
lowest solvent consumption and highest sensitivity.

Equipment

Agilent 1100 Series

- binary pump
- autosampler
- thermostatted column compartment
- diode array detector

Agilent ChemStation +
software



Rainer Schuster is application
chemist at Agilent
Technologies, Waldbronn,
Germany.

For more information on our
products and services, visit
our worldwide website at
<http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 10/97
Publication Number 5966-1876E



Agilent Technologies

Innovating the HP Way



Analysis of Paraquat and Diquat by HPLC

Rainer Schuster

Environmental

Abstract

The paraquat and diquat herbicides can be extracted from soil either with Soxhlet equipment or by ultrasonic treatment in solution and from water by either a liquid–solid or a liquid–liquid technique.

Separation

Figure 1 shows the separation on a 2.1-mm internal diameter Hypersil ODS column.

- UV-visible detection
- Diode-array detection—for simultaneous multiple wavelengths and peak identity confirmation by spectra.




Figure 1
Separation of 10 µl injection of a paraquat and diquat standard

Conditions

Column

100 x 2.1 mm Hypersil ODS C18, 5 µm

Mobile phase

Hexane sulfonic acid
0.35 % triethylamine
pH 2.5 (H₃PO₄)

Flow rate

0.4 ml/min

Detection

256 nm (10 nm bandwidth),
310 nm (10 nm bandwidth)
reference 450 nm (100 nm bandwidth)

Diode array detector performance

Detection limit 4 µg/l
1 ng (absolute) with enrichment factor
of 100



Agilent Technologies

Innovating the HP Way

Sample preparation


Narrow-bore technology for lowest solvent consumption and highest sensitivity.

Equipment

Agilent 1100 Series

- binary pump
- autosampler
- thermostatted column compartment
- diode array detector

Agilent ChemStation + software



Rainer Schuster is application chemist at Agilent Technologies, Waldbronn, Germany.


For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 10/97
Publication Number 5966-1875E



Agilent Technologies

Innovating the HP Way



Gradient LC analysis of herbicides and polyaromatic hydrocarbons by isocratic Capillary Electrochromatography

Gordon Ross,
Thomas Adam
and Monika Dittmann

Environmental/chemical

Abstract

Capillary Electrochromatography (CEC) combines the separation principle of HPLC (partitioning between mobile and stationary phases) with the high efficiency of capillary electrophoretic separation methods. In CEC the electroosmotic flow (EOF) inherent in capillary electrophoretic separations is used to transport solute and mobile phase through a packed capillary column. The properties of the EOF provides higher efficiencies than can be realized with LC. This can be sufficient to allow the transfer of methods conventionally performed by gradient LC to be performed by isocratic CEC.

Experimental

All CEC experiments were performed using the Agilent CE system, equipped for CEC operation and with a built in diode array detector. The system includes an Agilent ChemStation for system control, data collection and data analysis. CEC columns were supplied by Agilent Technologies. Buffer salts were of the highest purity available and organic solvents were HPLC grade. All buffers were filtered and degassed prior to use. Buffers/mobile phase were adjusted to pH prior to the addition of organic modifiers.




Figure 1
Isocratic CEC alternative to gradient HPLC separation of herbicides

Figure 1 shows the separation of a series of herbicides by CEC. The separation is normally achieved using gradient elution LC. The same is true for figure 2. Here the analysis is of polyaromatic hydrocarbons

Conditions

Column

250 mm × 100 µm; Spherisorb ODS1

Mobile Phase

60 % acetonitrile/40 % 25 mM TRIS pH 8

Voltage

30 kV

Temperature

15 °C



Agilent Technologies

Innovating the HP Way




Figure 2
Fast CEC separation of EPA 16 PAH standard on CEC hypersil C18

which are of environmental significance and interest. Conventional analysis of these compounds can be achieved in a similar time however with isocratic CEC operation there is no inter-analysis time required for re-generation of the LC column.

Conclusions

Some gradient LC separations can be successfully performed using isocratic CEC. Very similar separations can be achieved in the same time frame. Time for re-equilibration of the LC column is not needed and therefore the overall analysis time is reduced.

Conditions

Column

CEC Hypersil C18, 250 mm (350 mm) $\times$ 0.1 mm i.d., 2.5 μ m

Cell Standard

Eluent

90 % TRIS-HCl 50 mM, pH 8


Voltage 30 kV

Temperature 20 $^{\circ}$ C

Pressure 10 bar both sides

Equipment

- Agilent Capillary Electrophoresis System
- Agilent ChemStation + software



Monika Dittmann is an R&D chemist and Gordon Ross is an application chemist at Agilent Technologies, Waldbronn, Germany. Thomas Adam is at the University of Mainz, Germany.

For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 06/97
Publication Number 5965-9032E



Agilent Technologies

Innovating the HP Way




A Comparison of Pre- and PostColumn Sample Treatment for the Analysis of Glyphosate

Application Note

Environmental Analysis

R. Schuster and
A. Gratzfeld-Hüsgen



The active ingredient in several sports field weedkillers, glyphosate, and its main metabolite aminomethyl phosphonic acid (AMPA) can be analyzed to low (1–5) ppb levels by HPLC, although the absence of chromophores in both compounds makes labeling with fluorogenic reagents necessary. Precolumn derivatization with fluorenylmethyl chloroformate (FMOC) gives low detection limits and has the advantage of simplicity, since it uses the automated injector program facility of the HP 1050 Series autosampler. Post-column oxidation of the glyphosate with hypochlorite, followed by derivatization with *o*-phthalaldehyde (OPA) requires additional equipment, but has the advantage of superior selectivity. It is thus better suited to samples in complex matrices.



Agilent Technologies
Innovating the HP Way

Introduction

Glyphosate, the N-(phosphonomethyl) derivative of the amino acid glycine, is a widely-used broad-spectrum, non-selective and post-emergence herbicide. Its application to plants inhibits the production of specific enzymes so that the synthesis of aromatic amino acids is interrupted. Compared with triazines, glyphosate is strongly absorbed on soil particles and subsequently undergoes microbial degradation to the main metabolite, aminomethyl phosphonic acid (AMPA) (figure 1) and finally to ammonia and carbon dioxide.¹ It is the active ingredient of several commercial weedkillers, and is used against weeds, for example couch grass, in the farming of cereals, potatoes, vines and mushrooms; it is very often used to maintain sports fields and lawns.

The wide use of glyphosate in agriculture can result in its presence in ground water, vegetable matter and milk. Because of the suspected toxicity of glyphosate and its metabolite, tolerance levels have been set for food and drinking water. German regulations, for example, limit the maximum residue limits (MRL) to 80 mg/kg for mushrooms, 10 mg/kg for cereals, and 0.1 mg/kg for plant food, and the limit set by the European Community for drinking water is 0.1 µg/l.² The United States Environmental Protection Agency (EPA) has set a detection limit for glyphosate in drinking water of 6 µg/l.³

Because of the low MRLs and the wide variety of matrices, selectivity and sensitivity play an important role in the analysis of glyphosate. High selectivity is required

for complex matrices such as food samples and the highest sensitivity is needed to monitor glyphosate and its metabolite in water samples.

Many different methods for the analysis of glyphosate and its metabolite AMPA have been described, including gas chromatography,⁴ thin-layer chromatography⁵ and high performance liquid chromatography (HPLC). All these methods, however, require special manual derivatization steps or tedious cleanup procedures making them time-consuming. For the HPLC analyses, the absence of chromophores makes it necessary for the analytes to be labeled with reagents either before the column⁶ or after the column.⁷ We have compared pre- and postcolumn derivatization methods in the light of the different requirements for the analyses of drinking water and agricultural produce.




Figure 1
Glyphosate and its main metabolite aminomethyl phosphonic acid (AMPA)

Experimental

For the chromatographic analyses, we used the HP 1050 Series autosampler with variable-volume auto-injector, the HP 1050 Series quaternary pump with temperature-controlled column compartment and the HP 1046A programmable fluorescence detector. We used the programmable injection facility of the auto-injector for automated precolumn derivatization. For postcolumn derivatization, we used a Postcolumn Reaction System (PRS) from Pickering Laboratories. Figure 2 shows a schematic diagram of the complete analysis setup.




Figure 2
Analysis set-up for postcolumn derivatization




Figure 3
Precolumn reaction for glyphosate with FMOC

Automated precolumn derivatization

The reaction of glyphosate with fluorenylmethyl chloroformate FMOC,⁸ used for the automated precolumn derivatization, is shown in figure 3. The reaction was performed automatically in the auto-injector, using an injector program. Table 1 lists the various program steps of the automated precolumn derivatization.

In step 1 of the program, a borate buffer (necessary to maintain the correct reaction pH of 10.4), was drawn into a capillary, then FMOc (step 3), sample (step 5) and again FMOc (step 7) were drawn into the capillary. Between each step, the surface of the needle was cleaned by washing with acetonitrile (steps 2, 4, 6 and 8). The sample and reagent volumes were mixed by moving them back and forth inside the capillary (step 9). The resulting FMOc derivatives of glyphosate and AMPA were injected after a 1 minute wait. Derivatization was performed at ambient temperature. The derivatives were separated on a reversed phase column and were detected with a fluorescence detector using an excitation wavelength of 266 nm and an emission wavelength of 305 nm, with a 280 nm cut-off filter.

1	draw :	2 µl from vial 2	draws borate buffer (0.4N, pH 10.4)
2	draw :	0 µl from vial 3	rinses tip by dipping in vial containing acetonitrile
3	draw :	1 µl from vial 1	draws FMOc (1mg/ml in acetonitrile)
4	draw :	0 µl from vial 3	rinses tip by dipping in vial containing acetonitrile
5	draw :	1 µl from sample	
6	draw :	0 µl from vial 3	rinses tip by dipping in vial containing acetonitrile
7	draw :	1 µl from vial 1	draws FMOc
8	draw :	0 µl from vial 3	rinses tip by dipping in vial containing acetonitrile
9	mix :	7 µl cycles: 10	mixes reagent and sample for derivatization reaction
		mixing speed: 300 µl/min	
10	wait :	1 min	
11	inject		

Table 1
Injector program for derivatizing glyphosate and its metabolite AMPA

Postcolumn derivatization

For postcolumn derivatization experiments a Pickering glyphosate Postcolumn Reaction System EG5000XX (Pickering laboratories, Inc. 1951 Colony Street, Mountain View, CA 94043) was connected between the HPLC column and the fluorescence detector. After separation on the anion exchange column, the glyphosate underwent a two-stage derivatization which is shown in figure 4. The glyphosate was first hydrolyzed to glycine by an hypochlorite solution and the glycine then derivatized with *o*-phthalaldehyde (OPA) reagent to form a fluorescent isoindole. The amino group of AMPA (see figure 1) reacted directly with the OPA. The isoindole derivatives were detected by fluorescence with excitation wavelength of 230 nm or 338 nm and an emission wavelength of 450 nm with a




Figure 4
Two step postcolumn reaction for glyphosate

370 nm cut-off filter.

Chemicals and solvents were obtained from Baker (FRG).

The hydrolysis solution was made up by dissolving 8 g dipotassium hydrogen phosphate, 5 g potassium chloride and 150 ml sodium hypochlorite solution (5% active chloride, supplied by Aldrich-Chemie D7924 Steinheim) in 1 liter of water. pH was measured as 9.1. If necessary, the sodium hypochlorite solution can be replaced by 15 mg calcium hypochlorite. The fluorogenic reagent can be either a premixed OPA solution (Fluoraldehyde®, Pierce), or a mix of 1 g *o*-phthalaldehyde and 1 ml 2-mercap-

toethanol dissolved in 10 ml methanol and added to 1 l of 0.05 N sodium borate solution (19.1 g sodium borate in water). pH was measured as 9.2.

The analysis was performed according to a method published by the EPA³ for the analysis of glyphosate in drinking water. This method requires that the two compounds, glyphosate and AMPA, are monitored at maximum residue limits of 6 ppb (6 µg/l).

Because of the amphoteric character of glyphosate (–NH– and –COOH, –PO₃H₂), the separation of glyphosate and AMPA can be performed on either an anion

exchange (SAX) with 0.0025 M potassium dihydrogen phosphate, adjusted to pH 2.1 with phosphoric acid, as mobile phase (elution order AMPA–glyphosate) or on a cation exchange (K⁺ form) with 0.005 M potassium dihydrogen phosphate, adjusted to pH 2.0 with phosphoric acid, (elution order glyphosate–AMPA). We chose the anion-exchange column (SAX-300 100 × 4.6 mm id, part number 79919QA-754) for our experiments. At pH 2.1, any amino acids in the matrix (for example from food samples) behave like neutral molecules and are not retained. Additionally, if sample enrichment is necessary, glyphosate can be retained on an anion exchange column at neutral pH.⁹

Column	ODS Hypersil, 100 × 4.6 mm, 5 µm
Eluant	Channel A 0.002M KH ₂ PO ₄ 7% acetonitrile adjusted to pH 7.0
	Channel B acetonitrile
Column temperature	40°C
Fluorescence detection	λ _{ex} 266 nm λ _{em} 305 nm with a cut-off filter at 280 nm.
Injection volumes	1 µl and 10 µl




Figure 5
Analysis of two samples after precolumn derivatization (upper trace 1 µl injection of 350 ppb glyphosate and 260 ppb AMPA, lower trace 10 µl of a 100-fold dilution)

Results and discussion

Automated precolumn derivatization

Figure 5 (previous page) shows the separation of glyphosate and AMPA. The upper trace shows the results of a 1 μ l injection of water containing 350 ppb glyphosate and 260 ppb AMPA. The lower trace shows the results of a 10 μ l injection of water containing 3.5 ppb glyphosate and 2.6 ppb AMPA. The additional peaks in the chromatogram derive from either FMOc reagents or from by-products of the derivatization.

We found that the derivatization yield was constant for volumes of up to 10 μ l of sample, resulting in a detection limit of approximately 1 ppb of each compound. Over eight runs, the method's repeatability was better than 0.5% RSD for retention times and better than 2.5% for peak areas when injecting 10 μ l and better than 5% when injecting 1 μ l sample volume.




Figure 6
Analysis of 100 μ l injection after manual derivatization of glyphosate and AMPA at different concentrations (upper trace 350 ng/l glyphosate, 260 ng/l AMPA, lower trace 70 ng/l glyphosate, 52 ng/l AMPA)

For lower detection limits, larger sample volumes have to be used. There are three possible solutions :

a) 25 ml sample is derivatized manually with FMOc then extracted with two 30 ml aliquots of methylene chloride, as described by Gauch, Leuenberger and Mueller.¹⁰ The methylene chloride extracts are concentrated and 20 μ l are injected. Detection limits are 20 ng/l;

b) The sample is derivatized manually with FMOc, and a large volume (up to 500 μ l) is injected without extraction or concentration. Figure 6 shows chromatograms of standards at different amounts, and figure 7 shows chromatograms of standards overlaid on a water sample taken from a well. The detection limits were below 50 ng/l;




Figure 7
Analysis of 100 ml of well water overlaid with a standard

c) The sample is derivatized automatically with FMOC in the larger volume of a sample vial (rather than the capillary) using the HP 1050 Series autosampler with the extended 100 vial tray and rotary mixer accessory. Reagents and borate buffer (20 µl each) are added to a 500 µl sample vial and mixed in the vial using the rotary mixer; all steps are performed automatically using the injector program. The derivatization is completed within one minute, and volumes as large as 100 µl can be injected onto the column. An example of a large volume injection is shown in figure 8. Injection of volumes larger than 100 µl should be avoided because compounds from reagents may interfere with the analytes' derivatives. With the injection volume of 100 µl, the detection limit is about 50 ng/l for AMPA and 100 ng/l for glyphosate. Further investigations to improve the reproducibility of this method of derivatization are in progress.




Figure 8
Analysis of 10 ml of sample after automated precolumn derivatization in the vial using a rotary mixer (35 µg glyphosate and 26 µg AMPA)

Postcolumn derivatization

Chromatograms of the separation of glyphosate and AMPA at different concentrations are shown in figure 9. In the lower chromatogram, 2.6 ng AMPA and 3.5 ng

glyphosate in 500 µl are injected representing 5.2 µg/l AMPA and 7 µg/l glyphosate. Compared with the chromatograms obtained after precolumn derivatization, the selectivity is

Column	SAX 300, 100 x 4.6 mm
Eluant	0.34g/l KH ₂ PO ₄ , 0.1% H ₃ PO ₄ , adjusted to pH 2.1
Flow rate	0.8 ml/min
Column temperature	40°C
Fluorescence detection	λ _{ex} 230 nm λ _{em} 450 nm with a cut-off filter at 370 nm
Injection volume	500 µl




Figure 9
Chromatogram of glyphosate and AMPA with post-column derivatization

impressively high. No peaks from reagents or side reactions are visible. Detection limits are in the low ppb range. If lower detection limits are required, the sample can be enriched by passing it through an anion-exchange column at pH 7.2. A procedure for this has been described.¹¹

Reproducibility of the method was measured over 10 runs. The standard deviation of the retention times was 0.8% RSD and the repeatability of the peak areas was 2.1% RSD for a 35 pg sample and 100 µl injection volume.

Conclusion

Glyphosate and its metabolite AMPA can be determined by either pre- or postcolumn automated derivatization techniques. Detection limits for precolumn derivatization are slightly better and the instrumentation is simpler, requiring no more than the HP 1050 Series autosampler with injector program. The advantage of the postcolumn reaction method is higher selectivity. This is important for the analysis of food samples, where the matrix contains amino acids that are derivatized during the precolumn derivatization and interfere with glyphosate and AMPA in the chromatography. Thus the determination of glyphosate and its metabolite in water samples is dealt with adequately by precolumn derivatization, while more complex matrices are better handled by the postcolumn derivatization technique.

References

- 1 M. Rueppel, B.B. Brightwell, J. Schaefer and J.T. Mervel, *J. Agric. Food Chem.*, **1977**, *25*, 517–528
- 2 “Drinking Water Directive” (EEC), **1980**, 80/778/EEC
- 3 EPA method 547 “Analysis of glyphosate in drinking water by direct aqueous injection HPLC with post-column derivatization”, *Office of Research and Development, United States Environmental Protection Agency, Cincinnati, Ohio, July 1990*
- 4 H.A. Moye and C.L. Deyrup, *J. Agric. Food Chem.*, **1986**, *32*, 192–195
- 5 C. Young, S.U. Khan and P.B. Marriage, *J. Agric. Food Chem.*, **1977**, *25*, 918–922
- 6 L.N. Lundgren, *J. Agric. Food Chem.*, **1986**, *34*, 535–538
- 7 H.A. Moye, C.J. Miles and S.J. Scherer, *J. Agric. Food Chem.*, **1983**, *31*, 69–72
- 8 C.J. Miles, L.R. Wallace and H.A. Moye, *J. Assoc. Off. Anal. Chem.*, **1986**, *69*, 280–282

- 9 L.G.M.Th. Tuinstra and P.G.M. Kienhuis, *Chromatographia*, **1987**, *24*, 696–700
- 10 R. Gauch, Urs Leuenberger and Urs Mueller, *Z. Lebensm. Unters. Forsch.*, **1989**, *188*, 36–38
- 11 R.L. Glass, *J. Agric. Food Chem.*, **1983**, *31*, 280–282

Angelika Gratzfeld-Hüsken and Rainer Schuster are HPLC application chemists based at Agilent Technologies Waldbronn site in Germany.

For the latest information and services visit our world wide web site:
<http://www.agilent.com/chem>

Copyright © 1992 Agilent Technologies
All Rights Reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

Publication Number 5091-3621E



Agilent Technologies
Innovating the HP Way




Water

Inorganics
Applications

> [Return to Table of Contents](#)
> [Search entire document](#)

Quantitative Analysis of Perchlorate by Ion Chromatography MS/MS



Application

Environmental

Authors

Johnson Mathew
USEPA Region 6
10625 Fallstone Rd.
Houston, TX 77099
USA

Jay Gandhi
Technical Manager
Metrohm-Peak, LLC
12521 Gulf Freeway
Houston, TX 77034
USA

Sheher Mohsin
Agilent Technologies, Inc.
10 N. Martingale Rd., Suite 550
Schaumburg, IL, 60173
USA

Michael Zumwalt
Agilent Technologies, Inc.
9780 S. Meridian Blvd.
Englewood, CO, 80112
USA

Abstract

Perchlorate in water is analyzed using a Metrohm Ion Chromatography system interfaced to an Agilent 6410 Triple Quadrupole (QQQ) Mass Spectrometer. Quantitation is based on the sum of two multiple reaction monitoring (MRM) transitions corresponding to both chlorine isotopes (^{35}Cl and ^{37}Cl) of perchlorate. Excellent linearity among calibration standards ranging from 0.5 to 25 ppb is

established using the Metrohm conductivity detector with a resulting coefficient of linearity of $R^2 > 0.999$. Linearity for the QQQ mass spectrometer is $R^2 > 0.998$ over the range of 0.01 to 10 ppb. Reproducibility among seven replicate injections of standards is also excellent for the QQQ, with seven replicates at the 0.1 ppb level resulting in a peak area relative standard deviation (RSD) of only 5.33%.

Confirming the presence of perchlorate by QQQ mass spectrometry involves measuring the peak area ion ratio of the two MRM transitions, corresponding to the ^{35}Cl and ^{37}Cl isotopes. The transitions are $101 > 85$ and $99 > 83$. The sum of the two is used for quantitation and the latter is used as a qualifier so that as long as all analyzed samples have qualifier to quantifier peak area ion ratios within $\pm 20\%$ of the value determined using one of the calibration standards, the presence of perchlorate is confirmed.

Perchlorate in the presence of the total dissolved solids (TDS) of chloride, carbonate, and sulfate in reagent water is also analyzed. For example, at the 3,000 ppm TDS concentration, reproducibility among seven replicate injections of perchlorate at 1 ppb is only 0.2%, when using the IC conductivity detector. Tandem IC conductivity and MSMS yields very similar results. The advantage of MSMS is to have confirmation and Metrohm Suppressor de-salts the matrix to yield better sensitivity for MSMS.

When using the QQQ mass spectrometer to analyze perchlorate in the presence of salt water, the reproducibility is very good. For example, at 1 ppb perchlorate in 1,000 ppm salt water, the peak area reproducibility among three injections is only 0.63% RSD.



Agilent Technologies

Introduction

Perchlorate is commonly used as an oxidant in solid fuel propellants for rockets and missiles. Recently, perchlorate contamination was found in many aquifers associated with the Colorado River (CA). Other sites were also identified, but by far the widest contamination problem is in California, Nevada, and Arizona. Perchlorate was also found at elevated levels in crops that use contaminated water for irrigation. Ion chromatograph (IC) with conductivity detection can be used to measure perchlorate levels in drinking and waste waters (as per EPA Method 314). The method is reliable to approximately 1 to 5 ppb in drinking water, but sensitivity decreases dramatically as the complexity of the matrix is increased (such as in surface and waste waters). Both false positive and false negative results may occur due to matrix effects and co-eluting substances detected by nonspecific conductivity detection. Lower detection limits (DLs) for perchlorate are needed as the EPA and state environmental agencies are looking to target levels in the 1 to 2 ppb range. Reliability of the measurement in heavy matrix samples is also important.

The use of a mass spectrometer as a detector for perchlorate at much lower DLs (50 to 100 ppt) has shown promise; however, reliability issues and problems related to suppression of the electrospray ionization (ESI) signals in typical matrices are well documented phenomena. The key to reducing suppression is to ensure that analyte and high concentrations of matrix are well separated and do not enter the ion source and interface at the same time.

In addition to ion suppression in the source, the m/z attributed to the perchlorate anion (99 and 101) have isobaric interferences that can be attributed to minor sulfate isotopes and from organic material that can be present and bleed from the column used for IC and the associated cation suppressor. The selection of separation column and suppressor are critical for reduction of sample bleed and for efficient separation of high levels of interfering ions, particularly sulfate.

Two USEPA methods (EPA Method 332.0 and SW-846 Method 6860) have been developed and published for this analyte using ion chromatography mass spectrometry (ICMS) and/or ICMSMS. The advantage of using tandem mass spectrometers is that interference from the hydrogen sulfate ion (HSO_4^- , m/z 99) can be completely eliminated

because in secondary fragmentation, the perchlorate transition is $99 > 83$ (loss of ^{16}O) but sulfate (HSO_4^-) ion is completely destroyed and does not even interfere. This helps to quantify the perchlorate ion with an excellent isotope ratio for chlorine ($^{35}\text{Cl}/^{37}\text{Cl}$) without any distortion. Data in this application is demonstrated. This application is also applicable to complex matrices like green leafy vegetables, fruits, plants (bio-accumulation of perchlorate), wines, and liquid medicines.

The chemical structure of perchlorate is shown in Figure 1. The compound is an excellent candidate for negative polarity electrospray ionization as it exists as an ion in solution.




Figure 1. Chemical structure of perchlorate.

Experimental

Sample Preparation

The following samples are prepared for use in the analysis:

Perchlorate stock standard (1,000 ppm) is prepared from sodium perchlorate (Sigma p/n S-1513, MW 122.4, CAS 7601-89-0). The stock standard is spiked into reagent-grade water to make up both calibration levels and lowest concentration minimum reporting limits (LCMRL). The LCMRL samples are used as quality controls and a reproducibility evaluation is made from replicate injections at differing concentrations.

Total dissolved solid (TDS) samples, which contain 3,000 ppm each of chloride, carbonate, and sulfate, dissolved in reagent water, are made up using ACS-grade sodium chloride, sodium carbonate, and sodium sulfate purchased from Aldrich (Milwaukee, WI).

Isotopic (^{18}O) enriched sodium perchlorate is used as internal standard and spiked into all TDS samples, calibrators, and LCMRLs at 10 ppm. The internal standard solution is purchased commercially from SPEX (Metuchen, NJ).

IC/MS/MS Details

Metrohm IC components

Metrohm Model 818 Inert Dual Piston Pump
Metrohm Model 819 Conductivity Detector
Metrohm Model 820 Separation Center (with two injection valves)
Metrohm Model 830 Interface
Metrohm Model 833 MSM-II
Metrohm Model 853 Sequential Suppressor
Metrohm Model 838 Auto Sample Processor
Metrosep ASUPP7-250 column (4.0 mm id × 250 mm length)
Metrosep RP Guard disc

Ion Chromatography Conditions

Eluent 10 mM sodium carbonate (Na_2CO_3) + 35% acetonitrile
Column temperature 45 °C
Column flow rate 0.7 mL/min
Injection volume 100 μL
Conductivity detector Range and full scale = 100 $\mu\text{Siemens/sec}$

The mass spectrometry component is the **Agilent 6410 Triple Quadrupole Mass Spectrometer**.

Mass Spectrometry Conditions

Mode Negative ESI using the Agilent G1948B ionization source
Nebulizer 45 psig
Drying gas flow 12 L/min
Drying gas temp 350 °C
 V_{cap} 1750 V
Resolution (FWHM) Q1 (unit) = 0.7 amu; Q2 (unit) = 0.7 amu
Fragmentor 120 V
Collision energy 30 V
Dwell time 200 msec
MRM transitions:
Perchlorate (sum of both Cl^{35} and Cl^{37} isotopes) = m/z 99 > 83 + 101 > 85
Perchlorate internal standard (O^{18}) = m/z 107 > 89

Results and Discussion

Part 1: Calibration Levels and LCMRLs

The conductivity calibration curve using the signal generated from the Model 819 conductivity detector of the Metrohm IC system is shown in Figure 2. Conductivity is measured in units of micro-Siemens per sec ($\mu\text{S/sec}$). The calibration curve fit has a coefficient of linear regression $R^2 > 0.999$ over the calibration level range of 0.5 to 25 ppb.




Figure 2. Conductivity calibration curve.

The calibration curve for the QQQ mass spectrometry analysis of this work is shown in Figure 3. The measured signal is the sum of two MRM transitions coming from both the ^{35}Cl ($99 > 83$) and ^{37}Cl ($101 > 85$) isotopic ion contributions. The lowest three levels are expanded to demonstrate excellent accuracy with respect to the curve as well as excellent

reproducibility of the lowest level LCMRL samples at 0.1 ppb. Reproducibility is further detailed in Table 1 as the percent relative standard deviation (% RSD) of the calculated concentrations for seven replicate injections. The reproducibility is also demonstrated in Figures 4a through 4c as overlaid chromatographic traces.




Figure 3. Good MS linearity for perchlorate over three orders of magnitude with excellent accuracy shown at lower end.

Table 1 Reproducibility of Calculated Concentrations for LCMRLs

LCMRL replicate	0.1 ppb Calc. conc.	0.5 ppb Calc. conc.	1 ppb Calc. conc.
1	0.1191	0.5546	1.0713
2	0.1089	0.5267	1.0863
3	0.1110	0.5149	1.0897
4	0.1140	0.5206	1.0809
5	0.1073	0.5417	1.1000
6	0.1087	0.5406	1.0888
7	0.1002	0.5534	1.0975
Standard dev	0.006	0.016	0.010
Average	0.110	0.536	1.088
% RSD	5.33	2.92	0.90




Figure 4a. MS chromatographic overlay of 0.1 ppb LCMRL.




Figure 4c. MS chromatographic overlay of 1 ppb LCMRL.




Figure 4b. MS chromatographic overlay of 0.5 ppb LCMRL.

For confirming the presence of the perchlorate ion the less intense ³⁷Cl MRM transition can be used as a qualifier ion. As long as all samples have ion ratios within $\pm 20\%$ of the expected value, the presence of perchlorate in that sample is confirmed. An example involving one of the 0.5 ppb LCMRL injections is shown in Figure 5.

Part 2: TDS Samples

These samples are made up of reagent water, spiked perchlorate analyte, and internal standards, as well as 3,000 ppm each of chloride, carbonate, and sulfate.

Figure 6 shows the Metrohm conductivity trace of perchlorate in the presence of the 3,000 ppm TDS and the need to have a relatively long elution time of approximately 21 minutes in order to chromatographically separate the perchlorate from the TDS matrix. The reproducibility of seven replicate injections is demonstrated in Figure 7, with corresponding peak area reproducibility shown in Table 2.




Figure 5. Confirmation of perchlorate using qualifier/quantifier peak area ion ratios.




Figure 6. Chromatographic trace of 1 ppb perchlorate (RT = 21 min) in the presence of 3,000 ppm TDS. Plot of conductance ($\mu\text{S}/\text{sec}$) vs. time (min).




Figure 7. Overlay of seven 1-ppb perchlorate replicate injections in 3,000 ppm TDS.

Table 2. Reproducibility of Seven Replicate Injections at 1 ppb Perchlorate in 3,000 ppm TDS (Calculated concentrations based on conductivity calibration of Figure 2.)

Sample id	Perchlorate ug/L
MDL-1	1.220
MDL-2	1.221
MDL-3	1.223
MDL-4	1.221
MDL-5	1.216
MDL-6	1.220
MDL-7	1.219
Average	1.220
Standard dev	0.002
% RSD	0.177
True value	1.200
% Recovery	101.67

In Figure 8, three of the injections for perchlorate in the 3,000 ppm TDS are shown. The peak area reproducibility is not very good and is obviously affected by the presence of the chloride, carbonate, and sulfate, dissolved in reagent water. The peak area RSD is about 41%, even though the minimum peak-to-peak signal-to-noise ratio (p-p S/N) is 25:1.

And yet, when using the QQQ mass spectrometer to analyze perchlorate in the presence of salt water, the reproducibility is very good. For example, at 1 ppb perchlorate in 1,000 ppm salt water the peak area reproducibility among three injections is only 0.63% RSD, as shown in Figure 9.




Figure 8. Peak area reproducibility for three injections of 1 ppb perchlorate in 3,000 ppm TDS is 41% RSD.




Figure 9. Peak area reproducibility for three injections of 1 ppb perchlorate in 1,000 ppm salt water is 0.63% RSD.

Conclusions

The analysis of perchlorate in water using a Metrohm Ion Chromatography system interfaced to an Agilent 6410 QQQ Mass Spectrometer is carried out on several calibration standards in reagent water and at various concentrations in the presence of TDS consisting of chloride, carbonate, and sulfate and also in the presence of reagent water. A linearity coefficient of $R^2 > 0.999$ is established for perchlorate standards ranging in concentration from 0.5 to 25 ppb. Linearity for the QQQ mass spectrometer is $R^2 > 0.998$ over the range of 0.01 to 10 ppb. Reproducibility among seven replicate injections of standards is also excellent for the QQQ, with seven replicates at the 0.1 ppb level resulting in a peak area RSD of only 5.33%.

The confirmation of perchlorate by QQQ mass spectrometry is also done by using qualifier ion ratios.

Perchlorate at the 3,000 ppm TDS concentration shows excellent reproducibility among seven replicate injections of 1 ppb perchlorate with an RSD of only 0.2% when using the IC conductivity detector. However, in negative ion electrospray ionization mode, the QQQ mass spectrometer shows a 41% RSD at the same level, even though all peaks have a peak-to-peak signal-to-noise ratio of at least 25:1.

When using the QQQ mass spectrometer to analyze perchlorate in the presence of salt water, the reproducibility is very good. For example, at 1 ppb perchlorate in 1,000 ppm salt water, the peak area reproducibility among three injections is only 0.63% RSD.

Acknowledgements

M. Johnson gratefully acknowledges the support of David Neleigh, Rick McMillin, and Dr. Melvin Ritter of EPA Region 6.

Disclaimer

Reference herein to any specific commercial products or nonprofit organization, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government and shall not be used for advertising or product endorsement purposes.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

For more details concerning the ion chromatography portion of this application, please contact Jay Gandhi at Metrohm-Peak, LLC.

For more details concerning the mass spectrometry portion of this application, please contact Sheher Mohsin at Agilent Technologies, Inc.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
February 4, 2008
5989-7907EN



Agilent Technologies



High-Speed Environmental Analysis Using the Agilent 7500cx with Integrated Sample Introduction System – Discrete Sampling (ISIS–DS)

Application Note

Environmental

Authors

Steve Wilbur
Agilent Technologies, Inc.
3380 146th Place SE, Suite 300,
Bellevue Washington, 98007
USA

Takeo Kuwabara and Tetsushi Sakai
Agilent Technologies
Tokyo Analytical Division
9-1 Takakura-cho, Hachioji
Tokyo 192-0033
Japan

Abstract

Agilent has further improved the sample throughput capabilities of its 7500cx ICP-MS with Octopole Reaction System (ORS) using a newly configured Integrated Sample Introduction System–Discrete Sampling (ISIS-DS) accessory, and helium collision mode. Employing this new methodology, a complete suite of 30 or more elements can be analyzed in compliance with USEPA criteria (spectrum mode, three replicates, and sub-ppb MDLs) in approximately 75 seconds, sample to sample, with excellent removal of polyatomic interferences. Performance data showing stability, interference control, accuracy, precision, and washout are presented. The new system is applicable to labs requiring extremely high sample throughput and with its low sample consumption of ~2.2 mL/sample, for applications where sample volume is limited.



Agilent Technologies

Introduction

The Agilent Integrated Sample Introduction System (ISIS) has always permitted the highest sample throughput, using either high-speed uptake with constant flow nebulization or discrete sampling using a six-port valve and sample loop with time-resolved acquisition. In keeping with Agilent's continual focus on product enhancement, ISIS Discrete Sampling (ISIS-DS) has been reconfigured to further improve productivity. The resulting enhanced ISIS-DS sampling mode takes advantage of the ability of the 7500cx ICP-MS to analyze environmental samples using a single collision cell mode (He mode). This new mode of operation permits USEPA-compliant analysis (spectrum mode, three replicates, and sub-ppb MDLs) of a complete suite of 30 or more elements in approximately 75 seconds, sample to sample.

ISIS Configuration

Figure 1 shows the ISIS configuration used. It is a typical discrete sampling configuration with a couple of important modifications. Pump 1 (P1) is the large ISIS sample uptake peristaltic pump. Pump 2 (P2) is the standard 7500 nebulizer pump.

The ISIS uptake pump (P1), which is located downstream of the valve, draws the sample from the autosampler into the sample loop. As a result, the sample loaded in the sample loop is never exposed to peristaltic pump tubing, thereby eliminating a common source of contamination and carryover. This high-speed, high-capacity peristaltic pump is capable of rinsing and filling the sample loop in approximately 10 seconds when using the Cetac ASX-520 autosampler with the wide-bore 0.8 mm id probe. The other modification is the addition of the tee joint between the valve and nebulizer to allow the use of online internal standard addition. By minimizing both the length and diameter of the tubing between the valve and nebulizer, the time from rotation of the valve (sample injection) to the realization of a constant analyte signal is less than 15 seconds. A 300- μ L loop is sufficient to allow more than 30 seconds of continuous spectrum mode acquisition. Larger loop sizes can be used to achieve any duration of acquisition required. After acquisition has completed, the valve returns to the load position, flushing any remaining sample to waste and rinsing the nebulizer and spray chamber with clean rinse solution. At this point, approximately 15 seconds is required for the signal to return to baseline in preparation for the next analysis (Figure 2).




Figure 1. ISIS-DS sampling with online internal standard configuration. Valve in "load" position on left and in "inject" position on right.




Figure 2. Analyte and internal standard profile during discrete sampling analysis (log scale for signal intensity). Time 0 – autosampler probe enters the sample and loop is loaded. Inject at 10 seconds, 15 seconds acquisition delay, 30 seconds acquisition, 10 seconds rinse, 10 seconds overhead. Total time is approximately 75 seconds.

Experimental

A sequence of 216 samples was analyzed in 4 hours 29 minutes using the new ISIS-DS sampling configuration depicted in Figure 1 and the acquisition conditions listed in Table 1. The 7500cx was operated in a single cell mode (He collision mode) resulting in both excellent removal of polyatomic interferences and very fast acquisitions since no cell gas switching or stabilization was required¹. The sequence consisted of a single initial calibration at 0.1, 1, 10, and 100 ppb for all elements, followed by repeated (n = 26) analyses of a block of samples consisting of:

- 50 ppb calibration check (CCV)
- NIST 1643e water
- CCB (blank)
- USEPA Interference Check Solution – A (ICS-A)
- Blank
- USEPA ICS-AB (spiked with all analytes at 100 ppb to monitor carryover)
- Blank
- Blank

¹ This is a key benefit over reaction cell ICP-MS instruments that have to operate in multiple cell modes to cover all analytes. While it is possible to use multiple cell modes with discrete sampling, the resulting acquisition time is significantly lengthened, minimizing the benefits in terms of both run time and matrix exposure. If multiple cell modes are employed using the Agilent Octopole Reaction System, the small cell volume and very rapid gas switching reduce the cost in time and matrix exposure.




Figure 4. CCV recoveries (50 ppb) for entire sequence. USEPA limits for CCV recoveries in both Method 200.8 and 6020 are $\pm 10\%$ (shown in red).

Accuracy

Long-term accuracy and precision were also determined through repeated analysis of NIST 1643e Certified Reference Water ($n = 26$). Results are tabulated in Table 2, showing recoveries within $\pm 10\%$ or better of certified values and relative standard deviations near 1% for most elements. Be and Se had higher %RSDs due to the short integration times used

and slightly lower count rates for these elements in He mode. Longer integration times can be used if higher counts or better precision are required for these elements. When ultimate DLs for Se are required (low ppt), H_2 mode is recommended. Due to the fast switching time of the ORS, Se can be measured in H_2 mode with only ~30 seconds added to the sample to sample run time.

Table 2. Precision (%RSD) and Mean Recovery of NIST 1643e Water for 26 Separate Analyses

Mass/ element	Mean measured value (µg/L)	RSD (%)	Certified value (µg/L)	Mean recovery (%)
9 Be	13.8	2.5	14.0	101.0
23 Na	22689.2	2.0	20740.0	109.4
24 Mg	7300.3	2.1	8037.0	90.8
27 Al	142.3	3.3	141.8	100.4
39 K	1837.8	1.1	2034.0	90.4
43 Ca	32170.1	0.7	32300.0	99.6
51 V	37.8	1.1	37.9	99.8
53 Cr	19.2	1.7	20.4	93.9
55 Mn	38.0	0.9	39.0	97.6
56 Fe	98.1	3.9	98.1	100.0
59 Co	28.8	0.7	27.1	106.4
60 Ni	59.2	0.8	62.4	94.9
63 Cu	23.2	0.8	22.8	101.9
66 Zn	70.0	0.5	78.5	89.2
75 As	54.3	0.9	60.5	89.8
78 Se	10.0	3.4	12.0	83.2
95 Mo	121.7	1.1	121.4	100.3
107 Ag	1.1	1.4	1.1	101.1
111 Cd	6.2	0.8	6.6	94.3
121 Sb	59.5	0.9	58.3	102.0
205 Tl	7.4	0.8	7.4	100.0
208 Pb	19.6	0.9	19.6	99.7

Washout

Washout is always a concern in high sample throughput applications, particularly when analyzing high-matrix, variable samples. In order to evaluate the washout for each element, two sequential blank samples were measured immediately after each spiked ICS-AB sample. The spiked ICS-AB contained 100 ppb of all calibrated elements, plus very high concentrations of Na, Mg, Al, K, and Fe. Memory effects were determined by measuring the blank immediately following the ICS-AB. Any subsequent carryover was measured in the sec-

Table 3. Washout Performance (Mean value of 26 ICS-AB spikes [100 ppb], each immediately followed by two consecutive blanks. Percent reduction calculated as $1 - ([\text{mean Blank}] / [\text{mean ICS-AB}])$ in percentage.)

Mass/ element	ICS-AB spike Mean	Blank 1 Mean	Percent reduction Mean	Blank 2 Mean	Percent reduction Mean
9 Be	94.9315	0.0199	99.979	0.0097	99.990
23 Na	96707.6923	19.6032	99.980	13.5090	99.986
24 Mg	79238.8462	14.2332	99.982	9.8046	99.988
27 Al	75758.0769	11.7913	99.984	7.8004	99.990
39 K	82694.2308	17.6441	99.979	13.2657	99.984
43 Ca	9092.8462	1.4105	99.984	0.9697	99.989
53 Cr	95.7327	0.0419	99.956	0.0441	99.954
55 Mn	94.8977	0.0132	99.986	0.0069	99.993
56 Fe	77021.9231	12.5122	99.984	8.0837	99.990
57 Fe	75266.5385	12.0863	99.984	7.7304	99.990
59 Co	106.8577	0.0140	99.987	0.0092	99.991
60 Ni	101.3692	-0.0161	100.016	-0.0129	100.013
63 Cu	98.5700	0.0163	99.984	0.0043	99.996
66 Zn	99.9350	0.0055	99.994	0.0011	99.999
75 As	95.8615	0.0290	99.970	0.0171	99.982
78 Se	94.0162	0.0841	99.911	0.0428	99.955
95 Mo	1862.3077	1.4281	99.923	0.6278	99.966
107 Ag	96.8769	0.0181	99.981	0.0098	99.990
111 Cd	104.0538	0.0134	99.987	0.0084	99.992
121 Sb	109.1346	0.2629	99.759	0.1077	99.901
205 Tl	93.4731	0.0339	99.964	0.0131	99.986
208 Pb	92.4704	-0.0175	100.019	-0.0241	100.026

ond blank (Table 2). In all cases, greater than 3 orders of magnitude reduction (> 99.9%) was achieved before the first blank, even for the high-concentration matrix elements. The second blank showed nearly no additional reduction, indicating that essentially complete washout was achieved during the configured sample uptake and rinse-out steps of the analysis. Even "sticky" elements, such as Mo, Sb, and Tl, demonstrated the same high degree of washout. This level of washout is comparable to or better than standard peristaltic pumped systems using much longer rinse times.

Conclusions

The results of this simple experiment illustrate that discrete sampling in spectrum mode (as opposed to time-resolved mode) using the Agilent Integrated Sample Introduction System can achieve extremely high sample throughput for typical environmental analyses using USEPA criteria. These data highlight that this novel method, using ISIS, easily exceeds the demanding USEPA requirements for stability, interference control, accuracy, precision, and washout.

The ISIS-DS system offers several advantages over other discrete sampling systems: Full integration into the ICP-MS mainframe, fully integrated software, compatibility with the industry standard ASX 520 autosampler, no vacuum pump and associated pump valve to wear and replace, very low sample consumption (~2.2 mL/sample), and the flexibility to use the ISIS for other supported sample-introduction tasks, such as constant-flow nebulization, autodilution, or hydride generation.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Printed in the USA
March 11, 2009
5990-3678EN



Agilent Technologies



Rapid Analysis of High-Matrix Environmental Samples Using the Agilent 7500cx ICP-MS

Application

Environmental

Author

Steven Wilbur
Agilent Technologies, Inc.
3380 146th Place, SE, Suite 300
Bellevue, WA 98007
USA

Abstract

The new Agilent 7500cx with Octopole Reaction System (ORS) is capable of analyzing most typical environmental samples using only one mode of analysis: helium mode. For the first time, it is possible to analyze an entire environmental suite of elements, including Hg and the major elements such as Na, K, Ca, Mg, Al, and Fe, in less than 2.5 minutes per sample, under conditions that remove or reduce practically all matrix-based interferences.

Introduction

Contract analytical laboratories, particularly those focused on the analysis of environmental samples, face challenges that are significantly different from those of research institutes in government and academia. The samples are typically more numerous, unknown and highly variable in composition, and generally require rapid turnaround. Despite these challenges, the environmental laboratory must ensure that the data produced is of high quality and is supported by extensive analytical quality control (AQC) in order to remain productive and profitable. The recent great improvement in productivity (and, consequently, profitability) of the metals section in contract environmental labs is largely due to the increasing use of ICP-MS, with its rapid multi-element capability, wide elemental cov-

erage and dynamic range, low detection limits, and ease of use. With the advent of collision/reaction cell (CRC) ICP-MS, the ability of the technique to eliminate or significantly reduce the effects of polyatomic interferences in complex matrices has further improved its usability for many applications. However, until recently, the improved accuracy delivered by CRC ICP-MS came at a significant cost to productivity. Typical CRC ICP-MS systems must use reactive cell gases to specifically target known interferences, which requires time-consuming, matrix-specific method development. Furthermore, multiple cell conditions are necessary depending on the matrix and analyte list, which can add minutes to each sample analysis.

Agilent pioneered the use of helium (collision) mode coupled with kinetic energy discrimination (KED) on the 7500c instrument, allowing most polyatomic interferences to be removed using a single set of cell conditions. Subsequent advances in instrument design and in the understanding of the collision mechanisms involved have resulted in the 7500cx, an ICP-MS capable of analyzing typical environmental samples using only helium mode. By eliminating the need for both hydrogen (reaction) mode¹ and no-gas mode, sample throughput is significantly improved and routine operation is greatly simplified. Coupled with improvements in uptake and rinse-out speed through various hardware and software innovations, it is now possible to analyze an entire environmental suite of elements, including Hg and the major elements such as Na, K, Ca, Mg, Al, and Fe, in less than 2.5 min-

¹ Trace level selenium analysis (i.e., below 0.2 ng/mL) requires the use of hydrogen mode to eliminate the Ar₂⁺ interferences on the preferred isotopes at mass 78 and 80.



Agilent Technologies

utes per sample, under conditions that remove or reduce all matrix-based interferences. This application documents the performance of the 7500cx for the high-throughput analysis of long sequences of typical high-matrix environmental samples.

Instrumentation

A standard Agilent 7500cx ICP-MS with a glass concentric nebulizer was used for all analyses. The instrument was tuned for standard robust plasma conditions (Table 1) and the ORS was operated in helium mode only. This means that all elements were measured under identical helium mode collision conditions and no mode switching was necessary. Furthermore, the helium mode conditions used are generic and do not have to be set up or modified for specific sample matrices. Method parameters are shown in Table 1.

Table 1. Instrument Tune and Acquisition Conditions Used

Instrument	7500cx
Sampler	Ni (standard)
Skimmer	Ni (standard)
Nebulizer	MicroMist (standard)
Plasma torch	Quartz, 2.5 mm (standard)
Integration Time	
Li, Be, As, ⁷⁸ Se, ¹¹¹ Cd	0.3 sec x 1 point
All other	0.1 sec x 1 point
Tune Parameters	
RF power	1550 W
Sample depth	8.5 mm
Carrier gas	0.80 L/min
Makeup gas	0.23 L/min
Extract 1	0V
Extract 2	-120 V
Energy discrimination	2 V
Reaction gas	He 5.0 mL/min
CeO/Ce	0.52%
Ce ⁺⁺ /Ce	2.06%

Sensitivity in Helium Mode

Real sensitivity, as determined by practical limits of detection (LOD), is a function of signal to background (high signal, low background) and the precision of the background measurement. The greatest analytical benefit in using helium mode will be realized for analytes that suffer from polyatomic ion overlaps (essentially every isotope of every element from mass 45 to 82). However, it is important to assess the possible degradation in performance for elements that do not suffer from polyatomic interference where helium mode is used for all analytes. Poorer signal to noise for

noninterfered elements is a possibility, as any ICP-MS operating with the cell pressurized (in collision or reaction mode) will suffer some loss of signal for low-mass elements when compared with no-gas mode. This signal loss occurs as a result of collisions between analyte ions and gas molecules in the cell. However, in most cases, the reduction in background more than compensates for the loss of signal, so real detection limits for noninterfered elements are not significantly impacted. In order to measure actual sensitivity under helium conditions, signal-to-background ratios and 3 sigma instrument detection limits (IDLs) were determined in helium mode for all commonly measured elements². For nearly all elements, IDLs are in the low- to sub-ppt range. More important for environmental applications are the background equivalent concentrations (BECs) and IDLs for those elements that typically suffer from interferences in high-matrix samples. Table 2 compares the BECs, IDLs, and equivalent concentration of interferences for several critical elements in no-gas and helium mode in USEPA Interference Check Solution (ICS-A³ - see Table 3 for composition). Note the significant reduction in all three measurements for all isotopes, showing that helium mode is capable of simultaneously removing interferences on multiple elements (and even multiple isotopes) in complex matrices.

Interference Removal in Helium Mode

USEPA Method 6020 specifies an interference check sample (ICS-A) designed specifically to monitor the effect of polyatomic interferences resulting from high concentrations of common matrix components. Traditionally, these interferences have been compensated for through the use of mathematical correction equations. However, experienced ICP-MS users know that in the case of multiple interferences on a single analyte or interferences from uncommon matrix components, mathematical correction is unreliable. Additionally, many polyatomic interferences cannot be corrected mathematically because of the lack of a free mass at which to monitor the interferent. A common example is the interference from ⁴⁰Ar²³Na on ⁶³Cu. This is a significant interference in saline matrices, but because Na is monoisotopic (at mass 23), it is not possible to derive a mathematical cor-

² Performance characteristics of the Agilent 7500cx ICP-MS. Agilent application note 5989-6663EN.

³ ICS-A is the USEPA-specified "Interference Check Solution" designed to alert the user to the possibility of isobaric, doubly charged, polyatomic and memory interferences in high-matrix samples. ICS-AB is the same high-matrix solution spiked with 100 to 200 ppb of each analyte element in order to measure the effects of high matrix on analyte recovery. In this work, the target analytes were spiked much lower (20 ppb, ICS-AB Modified) in order to test the effectiveness of interference removal at trace analyte levels.

Table 2. Comparison of No-Gas Mode and Helium Mode on BEC, IDL, and Measured Concentration in ICS-A Solution (Note the much higher measured concentration values obtained in no-gas mode due to polyatomic interferences. Se 77 and 78 values do not agree in no-gas mode, and V gives a negative concentration reading.)

	No Gas Mode			Helium Mode		
	BEC (ppt)	IDL (ppt)	Measured conc (ppb)	BEC (ppt)	IDL (ppt)	Measured conc (ppb)
⁵¹ V	1461	143	-1.35	107	45	0.13
⁷⁵ As	1945	186	3.23	120	149	0.70
⁷⁷ Se	9973	540	12.31	401	204	0.50
⁷⁸ Se	9738	313	3.84	342	162	0.43

rection based on the abundance of a second ArNa polyatomic ion. This has typically led ICP-MS users to select the alternative (and much lower abundance) Cu isotope at mass 65. However, ⁶⁵Cu suffers from a much higher level of S-based interferences (S₂ and SO₂) than ⁶³Cu as well as a significant ²⁵Mg⁴⁰Ar interference, so switching to ⁶⁵Cu to avoid the ArNa overlap can result in compromised data quality in many sample types.

Cr is another example of an element that commonly suffers from polyatomic interferences (⁴⁰Ar¹²C, ³⁵Cl¹⁶OH, ³⁶Ar¹⁶O, and ³⁸Ar¹⁴N on ⁵²Cr, and ³⁷Cl¹⁶O, ⁴⁰Ar¹³C, and ³⁶Ar¹⁶OH on ⁵³Cr), which cannot be reliably corrected mathematically due to the lack of a free reference mass. For these reasons, helium mode, with its ability to remove all polyatomic interferences regardless of sample matrix composition, is vastly more reliable and more widely applicable than the use of mathematical corrections⁴.

Figure 1 shows overlaid spectra for USEPA ICS-A, measured from mass 73 to 82 in no-gas, helium, and hydrogen modes. The spectra have been normalized on the bromine peak at *m/z* 79 to compensate for differences in sensitivity between modes. The differences in spectral complexity are clear, with almost every mass showing some level of interference in no-gas mode, while helium mode has reduced all of these interferences to background levels.

Table 3. Composition of ICS-A and ICS-AB (modified)³ (ICS-AB was prepared by spiking ICS-A with a 20-ppb standard containing all analyte elements of interest.)

Component	ICS-A concentration (mg/L)	ICS-AB concentration (mg/L)
Al	100.0	100.0
Ca	300.0	300.0
Fe	250.0	250.0
Mg	100.0	100.0
Na	250.0	250.0
P	100.0	100.0
K	100.0	100.0
S	100.0	100.0
C	200.0	200.0
Cl	2000.0	2000.0
Mo	2.0	2.0
Ti	2.0	2.0
As	0.0	0.02
Cd	0.0	0.02
Cr	0.0	0.02
Co	0.0	0.02
Cu	0.0	0.02
Mn	0.0	0.02
Hg	0.0	0.02
Ni	0.0	0.02
Se	0.0	0.02
Ag	0.0	0.02
V	0.0	0.02
Zn	0.0	0.02

⁴ Note that because helium mode works only on polyatomic interferences, it is not capable of removing elemental isobaric interferences (e.g., ⁴⁰Ar on ⁴⁰Ca) or doubly charged interferences. Fortunately, these types of interferences are rare, and simple methods are available to avoid them, such as choosing an alternative analyte isotope.




Figure 1. Overlaid spectra of ICS-A obtained in no-gas, hydrogen, and helium modes over the range from mass 73 to 82 to show interferences on As and Se. Spectra normalized on Br signal at m/z 79. Note that while H_2 mode is effective for the removal of the Ar_2^+ overlap at mass 80 (main isotope of Se) in simple matrices, it is not effective for several other interferences at this mass in ICS-A ($ArCa$, Ca_2 , S_2O , SO_3 , etc.). Ar_2^+ is completely removed by H_2 mode at m/z 78, which is therefore the preferred isotope.

Experimental

A 12-hour, 300-sample sequence, representing a typical environmental batch, was analyzed after a single initial calibration consisting of a blank and standards at 1, 10, 50, and 100 ppb (Figure 2). The sequence consisted of repeated blocks of 10 samples, including NIST 1640 standard reference water, ICS-A, ICS-AB, and two commercially available high total dissolved solids (TDS) mineral water samples. After each block, blank check and calibration check samples (USEPA sample types continuing calibration blank [CCB] and continuing calibration verification [CCV]) were automatically inserted to check for memory effects and calibration accuracy. No recalibrations were performed during the 12-hour run.




Figure 2. Schematic of analytical sequence. 300 sample analyses were performed, including an initial calibration and 22 repeated analyses of a block of samples containing 10 samples followed by 2 CCV samples and a CCB.

Long-Term Stability

Analysis of CCV Samples

As a check on calibration stability for all analyte elements, a CCV standard (50 ppb for all analytes except Hg – 1 ppb) was analyzed repeatedly throughout the sequence. USEPA Methods 200.8 and 6020 require that the measured CCV values fall within $\pm 10\%$ of the true value in order to report samples. Figure 3 shows the results of 25 measurements of the CCV sample over the 12-hour sequence, indicating no failures throughout the run, despite the fact that no recalibrations were performed after the initial calibration.

Analysis of High-Matrix Samples

In order to simulate difficult, high-matrix sample types, ICS-A and ICS-AB were each analyzed twice

in each 10-sample block (giving a total of 48 replicate analyses of each), in addition to the two high-TDS mineral water samples. ICS-A and ICS-AB were selected because they are well characterized and were specifically designed by the USEPA to challenge the ICP-MS's ability to handle high-matrix samples in terms of controlling interferences, managing ionization suppression, eliminating memory effects, and maintaining long-term stability. Long-term precision and accuracy for trace-level measurement in high-matrix samples can be determined by examining the results of repeated analysis of ICS-AB. Recoveries ranged from 97 to 104% with %RSDs ranging from less than 1% to approximately 5% over the 12-hour sequence (Figure 4).




Figure 3. Measured values of 50 ppb CCV samples (n = 25) over the course of the sequence. USEPA criteria are $\pm 10\%$ (i.e., 45 to 55 ppb).




Figure 4. Spike recovery (20 ppb, 1 ppb Hg) for ICS-AB over 12 hours (n = 44).

Analysis of Certified Reference Material

NIST 1640 certified reference water was analyzed repeatedly (n = 44) as part of the sequence. Results are shown in Table 4.

Table 4. Results of Repeated Analysis of NIST 1640 (n = 44) Over a 12-Hour Sequence

Element	Mean (n = 44)	RSD (%)	Certified value (µg/L)	Recovery (%)
⁹ Be	32.36	4.72	34.94	92.6
²⁷ Al	48.62	3.90	52.00	93.5
⁴² Ca	6652.25	2.59	7045	94.4
⁵¹ V	12.66	1.40	12.99	97.4
⁵² Cr	36.14	3.19	38.60	93.6
⁵⁵ Mn	114.96	3.87	121.50	94.6
⁵⁹ Co	19.64	2.27	20.28	96.8
⁶⁰ Ni	26.76	2.86	27.40	97.7
⁶³ Cu	84.95	2.16	85.20	99.7
⁶⁶ Zn	52.64	2.66	53.20	99.0
⁷⁵ As	25.28	1.52	26.67	94.8
⁷⁸ Se	20.69	4.61	21.96	94.2
⁸⁸ Sr	118.03	1.31	124.20	95.0
¹⁰⁷ Ag	7.15	1.67	7.62	93.8
¹¹¹ Cd	21.31	1.26	22.79	93.5
¹²¹ Sb	13.48	1.68	13.79	97.7
¹³⁷ Ba	140.78	1.03	148.00	95.1
²⁰⁰ Hg	0.10	12.23	—	—
²⁰² Hg	0.10	9.83	—	—
²⁰⁴ Pb	26.98	3.62	27.86	96.9
²⁰⁵ Tl	0.01	54.91	—	—
²⁰⁶ Pb	25.04	1.06	27.86	89.9
²⁰⁷ Pb	26.94	1.11	27.86	96.7
²⁰⁸ Pb	26.17	0.86	27.86	94.0
²³² Th	0.05	45.36	—	—
²³⁸ U	0.73	2.90	—	—

Average Analysis Time

One of the major goals of using a single ORS mode is to improve productivity. To ensure that this end was met:

- Integration times were kept short, typically 0.1 second per point.
- A single point per mass was used.
- Intelligent and pre-emptive rinse functions were employed (minimizes wasted time in uptake and rinseout and ensures that carryover could not occur).

Figure 5 graphically shows the time savings possible. In a conventional CRC system, after sample uptake and initial stabilization, acquisition occurs in the first of several CRC modes, followed by cell evacuation, repressurization, and restabilization (top). The process continues until all necessary modes have been completed (typically 3). In the 7500cx helium mode (bottom), initial uptake and stabilization are the same. After that, helium mode acquisition can begin immediately, since no cell evacuation or repressurization is necessary, followed by rinse. Pre-emptive rinsing begins up to 60 seconds before acquisition has finished, and intelligent rinse monitors rinseout, ensuring complete washout without any wasted time. The total acquisition time for all analytes and internal standards was 9.7 seconds per replicate. Three replicates were acquired according to USEPA methods,

resulting in a total acquisition time of 29.2 seconds. Overall, the average run-to-run time based on 300 runs beginning at 4:44 p.m. and ending at 5:04 a.m. the following morning was 2.46 minutes per run. As the data in Table 4 illustrate, despite the short acquisition time, precision was not compromised and all data returned excellent %RSDs over the 12-hour period.

Conclusions

Since helium mode is universal, all interferences are removed without prior sample knowledge. Tuning is simplified and problems associated with reactive cell processes such as the creation of new interferences or loss of analyte or internal standard are avoided. Stability is not compromised since cell conditions are static and run times are

markedly improved through the elimination of multiple cell conditions along with the associated stabilization times.

For many applications, particularly commercial analysis of high-matrix environmental samples, the use of helium mode offers significant benefits in productivity, data reliability, and ease of use.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.




Figure 5. Typical multimode CRC operation (top), and 7500cx using helium mode and pre-emptive rinse software (bottom).

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2007

Printed in the USA
September 20, 2007
5989-7297EN



Agilent Technologies

Determination of Organic and Inorganic Selenium Species Using HPLC-ICP-MS



Application

Environmental

Authors

Maïté Bueno, Florence Pannier, and Martine Potin-Gautier
Laboratoire de Chimie Analytique Bio Inorganique et Environnement
Université de Pau et des Pays de l'Adour, 64000 Pau
France

Jérôme Darrouzes
Agilent Technologies
France

Abstract

A methodology based on coupling isocratic high-performance liquid chromatography (HPLC) and inductively coupled plasma mass spectrometry (ICP-MS) with optimized collision/reaction cell conditions has been developed for the simultaneous analysis of organic and inorganic selenium species in natural water samples. Selenium concentrations found in total and speciation analysis of a number of water samples showed good agreement. Because HPLC-ICP-MS coupling is easily automated, the method can be considered robust and applicable to the routine monitoring of selenium species in environmental and nutritional samples.

Introduction

In the last 20 years, there has been increasing interest in the determination of the different

chemical forms in which an element can exist, that is, in the determination of its speciation. Indeed, knowledge of total concentrations of elements is not sufficient to assess their effects on human health or the environment. Among the elements of concern, there is a growing interest in selenium. Selenium is a very important element from an ecotoxicological point of view due to the narrow concentration range between its essential and toxic effects. Selenium compounds are distributed throughout the environment as a result of human activities (industrial and agricultural uses) and natural processes (weathering of minerals, erosion of soils, and volcanic activity). In waters, concentrations can vary from 2 ng/L to 1,900 µg/L depending on the system [1]. The natural cycle of selenium shows its existence in four oxidation states (-II, selenide; 0, elemental selenium; +IV, selenite; and +VI, selenate) and in a variety of inorganic and organic compounds. The organically bound Se(-II) compounds include seleno-amino acids and volatile forms (dimethylselenide and dimethyldiselenide), which are less toxic relative to other species and result from various detoxification pathways. The toxic dose of selenium as a function of its chemical form is shown in Table 1.



Agilent Technologies

Table 1. Selected Selenium Compounds and Their Toxicity

Compound	Formula	Lethal dose–LD-50*	Ref.
Dimethylselenide (–II)	(CH ₃) ₂ Se	1600 mg/kg (Int.)	[2]
Hydrogen selenide (–II)	H ₂ Se	0.02 mg/L (Resp.)	[3]
Trimethylselenonium (–II)	(CH ₃) ₃ Se ⁺	49 mg/kg (Int.)	[3]
Selenocystine (–I)	[HO ₂ CCH(NH ₂)CH ₂ Se] ₂	35.8 mg/kg (Or.)	[4]
Selenomethionine (–II)	CH ₃ Se(CH ₂) ₂ CH(NH ₂)CO ₂ H	4.3 mg/kg (Int.)	[3]
Selenite (+IV)	SeO ₃ ^{2–}	3.5 mg/kg (Int.)	[5]
Selenate (+VI)	SeO ₄ ^{2–}	5.8 mg/kg (Int.)	[5]

*Lethal doses obtained on mice or rats by intraperitoneal (Int.), oral (Or.), or respiratory (Resp.) absorption.

A number of analytical procedures exist for the determination of selenium and its various species in samples from different environmental sources. Existing methods can be divided in three groups, depending on selenium concentration:

- Total selenium
- Selenite species
- Species including inorganic and organic forms of selenium

Various redox reactions are often used to determine selenite species. However, the series of required reagents and pretreatment steps increases the possibility of element loss and contamination. Speciation results can also be distorted as back-oxidation of selenite to selenate may occur during sample pretreatment. Moreover, selenite and selenate are distinguished by two separate analyses, which is not the case for individual organic selenium species that remain unidentified. Hence, methods able to separate and quantify different selenium species simultaneously, in a single analysis, are preferred and are becoming more widespread.

In this application, the coupling of high-performance liquid chromatography (HPLC) with inductively coupled plasma mass spectrometry (ICP-MS) is presented for selenium speciation analysis with emphasis on its application to natural water samples.

Instrumentation

A 7500ce ICP-MS from Agilent Technologies (Tokyo, Japan), equipped with an Octopole Reaction System (ORS) cell, was used for this study; see Table 2 for operating parameters. The sample introduction system consisted of a concentric nebulizer (Meinhard Associates, California, USA) and a Scott double-pass spray chamber cooled to 2 °C. Nickel sampler and skimmer cones were used.

Table 2. Instrumental Parameters for Agilent 7500ce ORS ICP-MS

Parameter	Value
RF power	1590 W
Ar plasma gas flow	15.0 L/min
Ar auxiliary gas flow	0.86 L/min
Ar nebulizer gas flow	1–1.1 L/min
Spray chamber temperature	2 °C
Integration time per isotope for speciation analysis	400 ms
<i>m/z</i> ratio monitored	77 to 82
Integration time per isotope for elemental analysis	100 ms

Chromatographic separation was carried out using the Agilent 1100 Series HPLC pump, equipped with an autosampler and variable volume sample loop. The analytical column was a Hamilton PRPX-100, 10 µm particle size, 25 cm length × 4.1 mm internal diameter (id). The chromatographic separation of selenocystine (SeCyst), selenomethionine (SeMet), selenite (SeIV), and selenate (SeVI) was adapted from Ge et. al. [6] and performed using a 5 mmol/L ammonium citrate buffer with pH adjusted to 5.2. Injection volume was fixed at 100 µL. Methanol (2% v/v) was added to the mobile phase to improve sensitivity [7]. The mobile phase was delivered at 1 mL/min isocratically. The HPLC-ICP-MS interface consisted simply of polyetheretherketone (PEEK) tubing.

Polyatomic Interference Removal

ICP-MS is the detector of choice for trace element analysis due to its high sensitivity and selectivity. It is also one of the most often used detection systems for total and speciation analyses of selenium. Nevertheless, selenium detection limits obtained with a conventional ICP-MS (quadrupole filter without collision/reaction cell system) are not sufficient when dealing with selenium determinations in natural waters. Difficulties in Se determination by ICP-MS are mainly due to its high first ioniza-

tion potential (9.75 eV) compared to argon (15.75 eV) and, as a consequence, its low ionization in an Ar plasma (around 33% [8]). Secondly, argon polyatomic interferences, especially $^{40}\text{Ar}^{40}\text{Ar}^+$ and $^{40}\text{Ar}^{38}\text{Ar}^+$ dimers, prevent selenium determination from its most abundant isotopes ^{80}Se (49.6% abundance) and ^{78}Se (23.8% abundance). Hence, the less interfered and less abundant ^{82}Se isotope (9.2% abundance) is generally monitored. The problem of argon-based polyatomic interferences can be solved with the use of ICP-MS systems equipped with a collision/reaction cell (CRC). A 10- to 20-fold improvement in total Se and speciation analysis detection limits was observed using the ORS cell of the Agilent 7500ce. Speciation analysis detection limits are below 15 ng/L based on monitoring ^{80}Se (see Table 3). Better detection limits were achieved for ^{80}Se compared to ^{78}Se because the 7500ce was optimized on ^{80}Se .

Table 3. Optimization of ORS Operating Conditions

Instrument	Agilent 7500ce	
Cell gases	5.5 mL/min H ₂ 0.5 mL/min He*	
Elemental Analysis		
	⁷⁸ Se	⁸⁰ Se
Detection limit (ng/L)	6	4
Repeatability (%)	2	2
HPLC Coupling		
	⁷⁸ Se	⁸⁰ Se
Detection limit (ng/L)	14–30	7–15
Repeatability (%)	2	2

*Addition of He is optional. Similar detection limits should be achievable without He.

The use of CRC technology allows efficient removal of argon-based interferences, resulting in improved ICP-MS detection power for selenium by permitting monitoring of its most abundant isotope, ^{80}Se . However, such improvements are mitigated, in some cases, by reaction cell induced interferences. Indeed, hydrogen, or impurities contained in gases, can cause hydride formation from elements such as bromine, selenium, or arsenic [9-11]. Therefore, in samples containing bromine, as in the case of natural waters, there would be an interference on ^{80}Se and ^{82}Se from bromine hydride. As a result, the ^{78}Se signal should be monitored to avoid misinterpretation of the results and alleviate the need for correction equations.

Selenium concentrations determined in different mineral and spring waters, under the ICP-MS operating conditions described in Table 3, are summarized in Table 4. Results for certified simulated rain water (TM-Rain 95 from National Water Research Institute, [Ontario, Canada]) are also given. Total Se was established by measuring the ^{78}Se isotope without correction equations.

Experimental

Figure 1 shows a chromatogram of 1 $\mu\text{g}(\text{Se})/\text{L}$ per species standard obtained using HPLC-ICP-MS. The method was then applied to the mineral and spring water samples previously analyzed for their total selenium content. The results of selenium species concentrations are summarized in Table 4, together with the total selenium data.




Figure 1. Chromatogram of standard, 1 $\mu\text{g}(\text{Se})/\text{L}$ per species; 100 μL injected, Hamilton PRP X-100 column, citrate buffer pH 5.2 and 2% methanol as mobile phase.

Table 4. Selenium Concentrations Determined in Different Natural Waters [units: ng(Se)/L]

Natural Water	Elemental Analysis	HPLC Coupling			
	^{78}Se	^{78}Se SeIV	SeVI	^{80}Se SeIV	SeVI
TM-Rain 95	$622 \pm 19^*$	629 ± 7	< DL	615 ± 8	< DL
A	67 ± 1	< DL	69 ± 2	< DL	72 ± 6
B	142 ± 24	< DL	140 ± 9	< DL	143 ± 4
C	240 ± 20	< DL	232 ± 13	< DL	267 ± 13
D	467 ± 17	< DL	475 ± 4	< DL	492 ± 5
E	1890 ± 160	55 ± 2	1840 ± 30	57 ± 6	1920 ± 20

*Certified value 740 ± 290 ng(Se)/L

Concentrations found in total and speciation analyses are in complete agreement, showing the suitability of the method when applied to natural water samples. Although the bromine hydride interference on m/z 80 is present, it is separated chromatographically without overlapping with the selenium species. The chromatogram of water sample “C” (Figure 2) shows bromine elutes after the selenate peak.

Selenate, commonly found in oxygenated waters, was determined in commercial waters A-D. Selenite was identified in TM-Rain 95 water, which is only certified for its total selenium content. Only water “E,” a noncommercial ground water, contained both inorganic selenite and selenate species (see Figure 3).




Figure 2. Chromatogram of natural water “C” showing reaction cell induced interference from bromine hydride elutes after the selenate peak.




Figure 3. Chromatogram of natural water "E," the only sample to contain both inorganic species. First peak is SeIV, second peak is SeVI.

Conclusions

Interest in selenium speciation has grown in recent years due to its characteristics as both an essential and toxic element. However, the complete speciation of selenium, including organic and inorganic forms, is still a major challenge. This is particularly true when exploring selenium speciation in natural waters due to the low levels of Se present. A hyphenated technique consisting of isocratic HPLC coupled to ICP-MS with optimized collision/reaction cell conditions allows for a quick and precise simultaneous analysis of organic and inorganic selenium species. Moreover, as HPLC-ICP-MS coupling is easily automated, it can be considered a robust routine method to monitor selenium species levels in environmental and nutritional samples.

References

1. J. E. Conde and M. Sanz Alaejos, *Chem. Rev.* 97 (1997) 1979.
2. M. A. Al Bayati, O. G. Raabe, and S. V. Teague, *J. Toxicol. Environ. Health* 37 (1992) 549.
3. C. G. Wilber, *Clin. Toxicol.* 17 (1980) 171.
4. Y. Sayato, T. Hasegawa, S. Taniguchi, H. Maeda, K. Ozaki, I. Narama, K. Nakamuro, *Eisei Kagaku* 39 (1993) 289.
5. World Health Organization (W.H.O.) (1987) Environmental health criteria 58 : selenium.
6. H. Ge, X. J. Cai, J. F. Tyson, P. C. Uden, E. R. Denoyer, and E. Block, *Anal. Commun.* 33 (1996) 279.
7. E. H. Larsen and S. Stürup, *J. Anal. At. Spectrom* 9 (1994) 1099.
8. A. R. Date and A. R. Gray (Eds), "Applications of Inductively Coupled Plasma Mass Spectrometry," Blackie & Son, 1989.
9. L. Hinojosa-Reyes, J. M. Marchante-Gayon, J. L. Garcia-Alonso, and A. Sanz-Medel, *J. Anal. At. Spectrom*, 18 (2003) 11.
10. D. Wallschlager and J. London, *J. Anal. At. Spectrom*, 19 (2004) 1119.
11. J. Darrouzes, M. Bueno, G. Lespes, and M. Potin-Gautier, *J. Anal. At. Spectrom*, 20 (2005) 88.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
July 25, 2007
5989-7073EN



Agilent Technologies



Determination of Butyltin Compounds in Environmental Samples by Isotope Dilution GC-MS

Application

Environmental

Authors

Giuseppe Centineo, Pablo Rodríguez-González, and
J. Ignacio García Alonso
Department of Physical and Analytical Chemistry
University of Oviedo
Spain

Abstract

A GC-MS with electron impact ionization was used for the development of a speciation method for the simultaneous determination of monobutyl-, dibutyl-, and tributyltin in environmental samples (waters, sediments, and biota). The method is based on the use of a mixed spike containing ^{119}Sn -enriched monobutyltin (MBT), dibutyltin (DBT), and tributyltin (TBT) for isotope dilution analysis. The mixed ^{119}Sn -enriched spike was applied to the simultaneous determination of MBT, DBT, and TBT in waters, sediments, and mussel tissue samples with satisfactory results. A single injection allows the concentration of all three butyltin compounds in the sample to be computed quickly using standard spreadsheet software.

Introduction

Recently, the EU has included TBT in the list of compounds to be measured regularly in fresh waters. Thus, analytical methods for the determi-

nation of organotin compounds should provide enough sensitivity, selectivity, and accuracy to be applied routinely by testing laboratories. Most reported methods so far combine a separation technique such as gas chromatography (GC) hyphenated to element-specific detection systems, including atomic absorption spectrometry (AAS), flame photometric detection (FPD), mass spectrometry (MS), or inductively coupled plasma mass spectrometry (ICP-MS).

Isotope dilution (ID) methodologies, on the other hand, can produce superior accuracy and precision compared to more common calibration strategies provided that the first solid-liquid extraction step is quantitative or true isotope equilibration between the added spike and the analyte is achieved. Since quantitation is done by ratio measurements, subsequent nonquantitative analyte recoveries do not affect the final results. Identification for trace element speciation has been widely applied using ICP-MS for detection after HPLC or GC separation. However, ICP-MS is an expensive and not generally available instrument and similar results can be obtained with standard GC-MS instrumentation using electron impact ion sources. This application describes this analytical method, which could be applied routinely by testing laboratories.



Agilent Technologies

Experimental

Reagents

Tributyltin (TBT) chloride (96%), dibutyltin (DBT) dichloride (96%), and monobutyltin (MBT) trichloride (95%) were obtained from Aldrich (Steinheim, Germany). Stock solutions were prepared by dissolving the corresponding salt in a 3:1 mixture of acetic acid (Merck, Darmstadt, Germany) and methanol (Merck). All organometallic standards solutions were kept in the dark at -18°C and diluted working solutions were prepared by weight daily before the analysis. Acetic acid (Merck) and methanol (Merck) were used for the extraction of the organotin compounds from the solid matrices. Ethylation of the butyltin species was performed using sodium tetraethylborate (Galab, Geesthacht, Germany).

The spike solution (^{119}Sn -enriched butyltin mixture) was obtained from ISC-Science (Oviedo, Spain), diluted by weight with a mixture of methanol and acetic acid (3:1), and stored in the dark at -18°C . Table 1 shows the isotopic composition as well as the concentration of the butyltin species in the spike solution.

Table 1. Isotope Composition and Concentration of MBT, DBT, and TBT in the ^{119}Sn -Enriched Butyltin Mix (Uncertainty Corresponds to 95% Confidence Interval)

Isotopic composition					
Isotopes	116	117	118	119	120
Abundance (%)	0.029	0.114	14.33	82.40	3.127
Uncertainty	0.008	0.005	0.12	0.15	0.032
Concentration ($\mu\text{g Sn/g}$)					
MBT	DBT	TBT			
0.121 ± 0.005	0.748 ± 0.009	1.019 ± 0.017			

Reference materials tested were PACS-2 purchased from National Research Council of Canada (NRCC) (Ottawa) and CRM 477 obtained from Bureau Communautaire de Référence (BCR). Sea and fresh water samples were spiked with natural abundance butyltin compounds to check for recovery.

Instrumentation

Chromatographic analysis was performed with an Agilent Technologies gas chromatograph model 6890N, fitted with a split/splitless inlet and an HP-5MS capillary column (cross-linked 5% phenyl methyl siloxane, $30\text{ m} \times 0.25\text{ mm id} \times 0.25\text{ }\mu\text{m}$ coating). The gas chromatograph was equipped with an Agilent mass spectrometric detector model 5973 Network MSD (quadrupole based).

Helium was employed as the carrier gas with a constant flow of 1.2 mL/min . The column temperature was initially held at 60°C for 1 min, increased at 30°C/min to a final temperature of 300°C . Injection was performed using a split/splitless inlet in splitless mode. The transfer line and ion source temperatures were at 280°C and 230°C , respectively. Electron impact ionization was performed at an electron energy of 70 eV. A mass range from m/z 40 to 400 was recorded in the full-scan mode to check for spectral interferences. The measurement of isotope ratios for each butyltin compound was performed on the M-29 molecular ion (loss of an ethyl group) using 10-ms dwell-time per mass. Five m/z values were used for the selective ion monitoring (SIM) mode for each butyltin compound. Daily optimization of the GC-MS conditions was performed using the “autotune” option of the software supplied with the GC-MS instrument. For this purpose, perfluorotributylamine (PFTBA) was used as the tuning compound for all GC-MS autotunes, because it provides ions at 31, 50, 69, 100, 131, 219, 264, 414, 464, 502, 576, and 614 amu. Using this option, mass calibration and sensitivity optimization over the entire mass range was performed using the m/z 69, 219 and 502.

Procedures

Extraction and Derivatization of Organotin Compounds from Sediments

Approximately 0.2 g of sample was spiked with a diluted solution of the ^{119}Sn -enriched mixture of MBT, DBT, and TBT. A 4-mL mixture of acetic acid and methanol (3:1) was immediately added. The resulting slurry was exposed to ultrasound (30 W) for 8 minutes. A volume of 200 μL of the extract was derivatized as described below.

Extraction and Derivatization of Organotin Compounds from Mussel Tissue

Approximately 0.2 g of sample was spiked with a diluted solution of the ^{119}Sn -enriched mixture of MBT, DBT, and TBT. A 4-mL mixture of acetic acid and methanol (3:1) was immediately added. The resulting slurry was heated in a water bath at 37°C for 1 hour. A volume of 250 μL of the extract was derivatized as described below.

Derivatization of Sn Compounds

Ethylation of the tin species was carried out in 7 mL clear glass vials with screw caps (Supelco, Bellefonte, PA). The pH was adjusted to 5.4 with

4 mL of 1 M acetic acid/sodium acetate buffer. Ethylation was performed using 0.5 mL of 2% w/v sodium tetraethylborate in 0.1 M NaOH. After 10 min of manual shaking, the organic layer was transferred to a glass vial and stored at -18°C until measurement. The organic layer was then evaporated under a gentle stream of nitrogen to approximately 10 μL . Finally, 1 μL was injected in the GC instrument.

Extraction and Derivatization of Organotin Compounds from Water Samples

A sample of 100 mL of seawater is measured in a precleaned all-glass volumetric flask and mixed with a diluted solution of the mixed ^{119}Sn -enriched spike. In order to correct for volumetric errors, the amounts of sample and spike added were controlled gravimetrically. The spiked sample was shaken manually and left to equilibrate for 15 min prior to derivatization. Then, 1 mL of acetate buffer, to adjust the pH to 5.4, and 100 μL of a 2% w/v sodium tetraethylborate in 0.1M NaOH were added for the ethylation of the organotin compounds. Finally, 1 mL of hexane was introduced into the flask in such a way that it remained in the narrow neck of the flask. All these procedures can be performed under clean-room conditions to reduce the blank levels. The volumetric flasks were shaken manually for 10 min, the phases allowed to separate, and most of the organic layer was transferred to a 2-mL chromatographic vial with the help of a Pasteur pipette. Then, the hexane phase was evaporated under a gentle stream of nitrogen to approximately 10 μL . Finally, 1 μL of this volume was injected in the GC instrument.

Results and Discussion

Isotope Ratio Measurements by GC-MS

While elemental isotope ratios can be easily obtained with ICP-MS, in GC/MS the isotopic pattern in molecular ions is different from that of the naturally occurring elements due to the contributions from the organic groups attached to the metal because of the presence of ^{13}C . The contribution of ^{13}C to the observed $m+1$ and $m+2$ ions can be calculated in a fairly straightforward way, by applying equations 1 and 2:

$$I_{m+1} = I_m \cdot nX_{^{13}\text{C}} \quad (1)$$

$$I_{m+2} = I_m \cdot 1/2 \cdot n(n-1)^2 \cdot X_{^{13}\text{C}}^2 \quad (2)$$

where $x_{^{13}\text{C}}$ is the relative abundance of ^{13}C with respect to ^{12}C (0.0111/0.9899), n is the number of C atoms in the molecular ion and I is the intensities of the ions m , $m+1$ and $m+2$, respectively. The contributions to $m+1$ and $m+2$ of the butyltin compounds were corrected by monitoring five molecular ions for each analyte, corresponding to the ^{116}Sn , ^{117}Sn , ^{118}Sn , ^{119}Sn , and ^{120}Sn isotopes. The measured signal intensities at the different masses were corrected taking into account the ^{13}C contributions to $m+1$ and $m+2$. The intensity (I) correction equations used were:

$$^{116}\text{Sn} = ^{116}\text{I} \quad (3)$$

$$^{117}\text{Sn} = ^{117}\text{I} - x(^{116}\text{Sn}) \quad (4)$$

$$^{118}\text{Sn} = ^{118}\text{I} - x(^{117}\text{Sn}) - y(^{116}\text{Sn}) \quad (5)$$

$$^{119}\text{Sn} = ^{119}\text{I} - x(^{118}\text{Sn}) - y(^{117}\text{Sn}) \quad (6)$$

$$^{120}\text{Sn} = ^{120}\text{I} - x(^{119}\text{Sn}) - y(^{118}\text{Sn}) \quad (7)$$

Where x is the contribution factor $m+1$ and y the contribution factor $m+2$. The contributions of ^{114}Sn and ^{115}Sn can be neglected owing to their very low natural abundances, and therefore the signal intensity measured for ^{116}Sn can be considered free of $m+1$ and $m+2$ contributions. The selected molecular clusters for the measurement of MBT, DBT, and TBT by GC-MS and the contribution factors x and y are given in Table 2. The selected molecular cluster for TBT ($m/z = 287$ to 291) in the sample, spike, and mixture can be observed in Figure 1.

Table 2. Monitored Masses and Contribution Factors for MBT, DBT, and TBT

Corresponding tin isotope	MBT (BuEt ₂ Sn ⁺)	DBT (Bu ₂ EtSn ⁺)	TBT (Bu ₃ Sn ⁺)
116	231	259	287
117	232	260	288
118	233	261	289
119	234	262	290
120	235	263	291
$x (M + 1)$	0.088	0.110	0.132
$y (M + 2)$	0.0038	0.0060	0.0086




Figure 1. TBT mass spectra for the selected molecular clusters ($m/z = 287$ to 291) in the sample, spike, and mixture.

Analytical Characteristics of the Method

The analytical characteristics of the method are listed in Table 3. Method detection limits were calculated as three times the standard deviation of the blanks after measuring the concentration of MBT, DBT, and TBT in nine blank replicates by isotope dilution analysis following the methodology given in the procedures. The reproducibility of the method was studied by analyzing a natural seawater sample containing approximately 10 ng/kg of TBT. Recovery studies for seawater analysis were performed at three different levels to cover the range of concentrations that could be found in the real samples. The two high levels were obtained by addition of a natural MBT, DBT, and TBT standard to a real sample of coastal seawater (low content of butyltins) and the low level by addition of the natural standard to an artificial seawater sample. As can be observed, quantitative recoveries were obtained for all compounds at all concentration levels studied.

Table 3. Analytical Characteristics of the Method for the Analysis of Seawater Samples

			MBT	DBT	TBT
Limit of detection (3σ) (ng/Kg)			0.2	0.1	0.2
Limit of quantification (10σ) (ng/Kg)			0.8	0.5	0.7
Reproducibility (% RSD) ($n = 9$)			1.4	1.6	2.8
Recoveries (%)					
Sample Concentration (ng/Kg)					
Artificial seawater	2	($n = 3$)	98 ± 7	101 ± 2	102 ± 9
Seawater	20	($n = 3$)	103 ± 3	97 ± 2	104 ± 1
Seawater	100	($n = 3$)	101 ± 2	98 ± 2	101 ± 3

Analysis of reference materials

Mono-, di- and tributyltin were determined in two reference materials: a sediment (PACS-2) and a mussel tissue (CRM 477), by the proposed ID procedure. Three independent spiking experiments were made on each certified reference material and each sample was injected three times in GC-MS systems. The overall results obtained for the two reference materials by GC-MS are summarised in Table 4 (PACS-2) and Table 5 (CRM 477).

The concentration values for TBT and DBT obtained for PACS-2 (Table 4) were within the certified range (890 ± 105 ng/g for TBT and 1047 ± 64 ng/g for DBT). Values found for MBT were substantially higher than the original certified value (450 ng g^{-1}) at the time the analyses were made. Recently, PACS-2 was recertified for MBT and the new “recommended value” for MBT is 600 ng/g – close to the values found by our method. The corresponding results obtained for CRM-477 certified mussel tissue (Table 5) show an excellent agreement between the certified and found values for each individual butyltin species.

Table 4. Determination of MBT, DBT, and TBT in PACS-2 Using the $120/119$ Isotope Ratio for Quantitation; data in ng/g as Sn

Replicate	MBT	DBT	TBT
1	623 ± 2	1022 ± 7	872 ± 9
2	605 ± 4	971 ± 10	863 ± 2
3	617 ± 17	996 ± 1	849 ± 10
Average	615 ± 9	996 ± 25	849 ± 10
RSD (%)	1.5	1.5	1.5
<i>Certified values</i>	<i>600*</i>	<i>1047 $\pm$ 64</i>	<i>890 $\pm$ 105</i>

*information value only due to lack of independent methods

Table 5. Determination of MBT, DBT, and TBT in CRM- 477; data in ng/g as Sn

Replicate	MBT	DBT	TBT
1	1154 ± 9	761 ± 7	816 ± 6
2	1173 ± 18	766 ± 3	817 ± 2
3	1207 ± 19	787 ± 4	841 ± 2
Average	1178 ± 27	772 ± 14	825 ± 14
RSD (%)	2.3	1.9	1.7
<i>Certified values</i>	<i>1014 ± 182</i>	<i>786 ± 61</i>	<i>902 ± 78</i>

Conclusions

A fast, precise, and accurate method for the simultaneous determination of mono-, di-, and tributyltin in water, sediments, and mussel tissue has been developed. The detection at masses corresponding to ^{116}Sn and ^{117}Sn permits one to correct for the m+1 and m+2 contributions of ^{13}C on the ^{118}Sn , ^{119}Sn , and ^{120}Sn masses with simple mathematical equations. A single injection allows the concentration of all three butyltin compounds in the sample to be computed quickly without the need for time-consuming calibration, standard addition or recovery correction procedures. The method corrects for all possible errors in the speciation of butyltin compounds, provides extremely low detection limits, and is fast and simple to apply by non-trained personnel. The price of the enriched spike is no longer a limitation as a single determination in water samples requires less than 2 ng of the enriched compounds. In brief, the proposed ID-GC-MS technique appears to be a practical alternative to other measurement procedures, such as GC-AED or GC-FPD. The results obtained by this method are similar to those obtained by GC-ICP-MS.

The advantages provided by the proposed methodology are not only the less expensive instrumentation and high-quality analytical results, but also a drastic minimization of the time required both in the sample preparation steps and in the analytical measurement. Using such isotope dilution analysis methods and a GC-MS equipped with an autosampler, more than 15 samples can be analyzed by one operator per day from sample reception to analysis report. These advantages have been demonstrated in practice with the implementation of the proposed methodology in several routine testing laboratories and its subsequent accreditation according to the requirements of UNE-EN ISO/IEC 17025 by the Spanish National Accreditation Body.

References

- G. Centineo, P. Rodríguez-González, E. Blanco González, J. I. García Alonso, and A. Sanz Medel, "Simultaneous Determination of Mono-, Di- and Tributyltin in Environmental Samples Using Isotope Dilution Gas Chromatography Mass Spectrometry," *J. Mass Spectrom*, 2004, **39**, 485–494.
- G. Centineo, P. Rodríguez-González, E. Blanco González, J. I. García Alonso, A. Sanz-Medel, N. Font Cardona, J. L. Aranda Mares, and S. Ballester Nebot, "Isotope Dilution GC-MS Routine Method for the Determination of Butyltin Compounds in Water," *Anal Bioanal Chem*, 2006, **384**, 908–914.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
July 23, 2007
5989-7001EN



Agilent Technologies



Faster, Simpler, More Accurate Semiquantitative Analysis Using the Agilent 7500cx ICP-MS

Application

Author

Steven Wilbur
Agilent Technologies, Inc.
Bellevue, WA
USA

Abstract

The new Agilent 7500cx allows the user to achieve the full potential of ICP-MS for semiquantitative elemental screening of a wide range of sample types. Complex, unknown samples can be analyzed with better speed, accuracy, and data integrity than ever before, since all matrix interferences are removed in the Octopole Reaction System (ORS) using helium collision mode. Results are presented for three different certified reference materials.

Introduction

Semiquantitative elemental analysis (semiquant) by ICP-MS is a powerful tool for quick screening of unknown samples for a wide range of trace elements. The ability to perform accurate semiquant is a strength of ICP-MS that is not shared by other elemental analysis techniques. It is based on the fact that the relative response of any element can be estimated from the response of any other element under a given set of conditions. These relative responses are determined by the unique

properties of each element as well as the instrument and operating conditions, and can be stored in a semiquant response factor database. The use of internal standards or other calibration elements allows the database to be updated as needed to reflect the specific acquisition and matrix conditions. In practice, however, spectral interferences have limited the usefulness of semiquant for a number of elements in many common matrices.

Collision/Reaction Cell ICP-MS and Semiquant

In most collision/reaction cell (CRC) instruments, specific information about the matrix and target analytes is required in order to set up the correct collision/reaction chemistry to eliminate the interferences. Additionally, the conditions required to eliminate one interference in one matrix are generally not effective for all analytes in all matrices. For this reason, multiple sets of collision/reaction conditions are typically used. However, accurate semiquant response factors cannot be determined for elements acquired under different CRC conditions. As a result, it has not previously been possible to use CRC technology to reduce interferences in semiquant in the same way as in full quantification. However, the unique ability of Agilent's Octopole Reaction System (ORS) to eliminate polyatomic interferences using carefully controlled kinetic energy discrimination (KED) in helium collision mode permits all elements to be acquired under a single, universal set of CRC conditions.



Agilent Technologies

KED eliminates the transmission of the larger polyatomic ions from the collision cell to the quadrupole by placing an energy barrier between the collision cell and quadrupole. Since polyatomic ions are always larger than atomic (analyte) ions of the same mass (Figure 1), they undergo more energy-reducing collisions with the helium cell gas

than do the smaller atomic ions. As a result, the polyatomic ions have insufficient residual energy to cross the energy barrier at the cell exit, and so are excluded from the ion beam. Figure 2 depicts the effects of KED on ion energy. Only the high-energy atomic ions exceed the stopping potential




Figure 1. Graphic representation of the relative diameter of an atomic ion (Cu) compared with the polyatomic ions that can interfere. Most elemental ions are smaller than 150-picometer radius, while most polyatomic ions are larger.





Figure 2. Diagrammatic representation of Kinetic Energy Discrimination after energy-reducing collisions within the Octopole Reaction System cell.

and are transmitted. Since helium is a nonreactive gas, no new interferences are formed in the cell and no analyte signal is lost by reaction, as occurs with any reactive cell gas.

The use of helium collision mode with semiquant conveys all the advantages normally associated with the use of CRC technology in full quant. It also solves the previously critical limitations of semiquant due to unresolved interferences. The advantages include:

- Semiquant is simple, fast, accurate, and interference-free for all analytes in any matrix.
- Helium collision mode allows the use of HCl, H₂SO₄, or other acids in digestion without danger of chlorine- or sulfur-based interferences on elements such as As, Cr, Se, V, Zn, etc.
- Improved stability for elements like Ag, Hg, Sb, Sn, and the Pt group due to the ability to add HCl to samples and standards.
- Ability to select the most abundant isotope for the best sensitivity, or multiple isotopes for absolute data confidence.
- Freedom to use any internal standards.

Table 1. Tune Conditions Used for NIST 1640 Semiquant Analysis in Helium Collision Mode

RF power	1550 W
Sample depth	8.0 mm
Carrier gas flow rate	0.90 L/min
Makeup gas flow rate	0.23 L/min
Sample flow rate	0.4 mL/min
Spray chamber temperature	2 °C
Helium flow rate	5 mL/min
KED	2V

Table 2. Semiquant Acquisition Parameters for NIST 1640

Total run time	170 seconds
Acquisition mode	Spectrum - peak hopping
Number of masses	250
Integration time[sec] masses 2 - 260	0.1 sec/point
Number of points per mass	1
Acquisition time	50.9 [sec]
Number of replicates	1
Uptake time	20 sec
Stabilization time	60 sec
Post acquisition rinse	30 sec
Preemptive rinse	On (time = 30 sec)

Experimental

The 7500cx ICP-MS was tuned for the same typical robust plasma conditions that are used in routine quantitative analysis (Table 1). No special tuning is required. Semiquant acquisition parameters are listed in Table 2.

A single calibration standard containing 200 ppb of Ag, Al, As, Ba, Be, Bi, Ca, Cd, Co, Cr, Cs, Cu, Fe, Ga, K, Li, Mg, Mn, Na, Ni, Pb, Rb, Se, Sr, Th, Tl, U, V, and Zn made up in 1% HNO₃/0.5% HCl was used to update the semiquant response factor database for a range of elements across the mass range. Non-calibrated elements are updated by interpolating between calibrated isotopes, which the ChemStation does automatically. Any number of calibration elements may be used, but increasing the number of calibration elements will improve semiquantitative accuracy. Internal standardization was applied using a typical suite of internal standard elements distributed across the mass range.

Results and Discussion

Tables 3 and 4 show the results of a semiquantitative screen of three standard reference materials, NIST 1640 water, LGC 6010 hard drinking water,

Table 3. Results of Helium Collision Mode Semiquant Analysis NIST 1640 Standard Reference Water

Element	NIST 1640 certified value	SQ conc.	Unit	Recovery (%)
9 Be	34.94	33.42	µg/L	95.6
11 B	301.1	335.83	µg/L	111.5
23 Na	29.35	22.25	mg/L	75.8
24 Mg	5.819	4.24	mg/L	72.9
27 Al	52	48.92	µg/L	94.1
39 K	994	919.17	µg/L	92.5
42 Ca	7.045	5.81	µg/L	82.4
51 V	12.99	12.83	µg/L	98.8
52 Cr	38.6	36.58	µg/L	94.8
55 Mn	121.5	121.67	µg/L	100.1
56 Fe	34.3	30.92	µg/L	90.1
59 Co	20.28	19.75	µg/L	97.4
60 Ni	27.4	25.83	µg/L	94.3
63 Cu	85.2	81.17	µg/L	95.3
66 Zn	53.2	51.83	µg/L	97.4
75 As	26.67	27.75	µg/L	104.0
78 Se	21.96	24.08	µg/L	109.7
88 Sr	124.2	122.50	µg/L	98.6
95 Mo	46.75	46.17	µg/L	98.8
107 Ag	7.62	7.31	µg/L	95.9
111 Cd	22.79	21.50	µg/L	94.3
121 Sb	13.79	12.83	µg/L	93.1
137 Ba	148	139.17	µg/L	94.0
208 Pb	27.89	23.5	µg/L	84.3

Table 3 has been simplified to show only those elements with some reference values, although many other elements were determined in each reference material.

Table 4. Results of Helium Collision Mode Semiquant Analysis of LGC 6010 Hard Drinking Water and LGC 6177 Landfill Leachate Standard Reference Materials

Element	LGC 6010 hard drinking water			LGC 6177 landfill leachate		
	LGC certified value (µg/L)	SQ conc. (µg/L)	Recovery (%)	LGC certified value (µg/L)	SQ conc. (µg/L)	Recovery (%)
10 B	N/A	83	N/A	9,800	6,700	68.4
23 Na	21,900	20,000	91.3	1,750,000	1,500,000	85.7
24 Mg	4,200	3,700	88.1	73,500	62,000	84.4
27 Al	208	160	76.9	N/A	110	N/A
31 P	N/A	670	N/A	11,500	12,000	104.3
39 K	5,100	5,100	100.0	780,000	810,000	103.8
44 Ca	83,200	73,000	87.7	74,800	77,000	102.9
52 Cr	48	51	106.3	180	160	88.9
55 Mn	48	45	93.8	140	130	92.9
56 Fe	236	240	101.7	3,800	3,300	86.8
60 Ni	48	42	87.5	210	170	81.0
66 Zn	542	540	99.6	260	250	96.2
75 As	55	49	89.1	N/A	86	N/A
78 Se	9.5	13	136.8	N/A	< 16.00	N/A
107 Ag	6.2	4.3	69.4	N/A	1.8	N/A
121 Sb	11.9	13	109.2	N/A	5	N/A
137 Ba	116	110	94.8	N/A	770	N/A
208 Pb	95	92	96.8	N/A	17	N/A

Table 4 has been simplified to show only those elements with some reference values, although many other elements were determined in each reference material.

and LGC 6177 landfill leachate. No attempt was made to matrix-match; tune conditions used were as shown in Table 1; and all elements were acquired in helium collision mode. In all cases, for every certified element, the semiquantitative result was within $\pm 40\%$ of the certified concentration, from as low as 7 ppb for Ag in NIST 1640 to over 1700 ppm for Na in the LGC 6177 landfill leachate.

Conclusions

Semiquant has always been a powerful tool available to the ICP-MS analyst for quickly estimating the concentration of unknown, uncalibrated elements in a variety of simple matrices. However, in complex matrices, polyatomic interferences could render the results for many elements useless. Collision/reaction cell technology, which requires more than one set of conditions for all masses, cannot be used since it would result in deviation from the standard relative response tables upon which semiquant is based. Helium collision mode coupled with kinetic energy discrimination in the Agilent 7500cx can overcome these limitations. By effectively removing polyatomic interferences, rapid, accurate, semiquantitative screening of a wide

range of sample types for most analyte elements is possible. In this work, a full mass range, 250 isotope semiquant screen was performed in less than 3 minutes total sample-to-sample time with accuracy comparable to full quantification, for most elements, when measuring three different certified reference materials.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
May 4, 2007
5989-6662EN



Agilent Technologies



Achieving Optimum Throughput in ICP-MS Analysis of Environmental Samples with the Agilent 7500ce ICP-MS

Application

Environmental

Authors

Steven Wilbur
Agilent Technologies, Inc.
Bellevue, WA
USA

Craig Jones
Agilent Technologies, Inc.
Santa Clara, CA
USA

Fred Fryer
Agilent Technologies, Inc.
Sydney, Australia

Abstract

Throughput enhancements in ICP-MS can be achieved by minimizing sample uptake and rinse-out time through various techniques as well as by reducing data acquisition time. Depending on the application and data quality objectives, significant reductions in average run-to-run time are possible. In this work, we present some practical tips as to how to optimize several areas within the conventional ICP-MS sample introduction and data acquisition systems and make use of new rinse modes within the new Agilent ChemStation to improve productivity. The new methodology is supported by application to the analysis of the entire suite of 21 EPA method 200.8 elements plus 5 mineral elements and internal standards in a mixed run of drinking waters, leachates, and high-matrix wastewaters in approximately 4.5 minutes.

Introduction

High throughput in ICP-MS depends not only on accurate, high-speed data acquisition, but on rapid and complete sample wash-in and wash-out. In fact, as instrument scan speed and data processing speed have improved, it is sample wash-in/wash-out that remains the main limiting factor in achieving minimum run-to-run times and best detection limits, especially for memory-prone elements like Hg, Ag, Sb, Mo, and Tl. Complex, discrete sampling or flow injection techniques have successfully reduced sample uptake and rinse-out times to very low levels. However, until now, little systematic work has been done to efficiently optimize the conventional ICP-MS sample introduction system for highest possible throughput.

The topic of this application note is the maximization of sample throughput through:

- Understanding uptake and rinse out
- Optimization of the conventional sample introduction system on the Agilent 7500 Series ICP-MS for maximum productivity
- Minimization of acquisition time
- Use of intelligent software functions that eliminate wasted time in sample uptake and rinse out



Agilent Technologies

Understanding Uptake and Rinse Out

In theory, minimizing the time it takes to get the sample into and out of the ICP-MS involves only two simple principles, one physical and one chemical.

First, minimize the time required for the sample to flow to the nebulizer. This can be done by minimizing the volume of the flow path and/or maximizing the flow while avoiding mixing at the interface between subsequent samples/blanks as much as possible. At the same time, it is desirable to minimize higher than optimum sample flow to the nebulizer itself to reduce plasma and interface overloading.

Second, minimize chemical interactions such as adsorption/desorption of soluble components in the sample to the sample introduction system. This is especially critical for the analysis of Hg, which must frequently be measured at ultra-trace levels and is very memory prone. These can be addressed by controlling the solution chemistry, sample introduction materials, and the contact surface area and exposure time.

Optimizing the Plumbing

Optimizing the plumbing involves minimizing the total volume of the sample introduction system, including the autosampler probe, peristaltic pump tubing, and sample transfer tubing. The internal diameters of these components should also be minimized in order to reduce the total wetted surface area. The mixing tee where the internal standard and sample are mixed is relocated to the top of the peristaltic pump in order to shorten the distance to the nebulizer as much as possible. The “tails” are clipped from the sample peristaltic pump tubing, leaving only about 1 cm beyond the stops, significantly reducing both the volume and surface area. Of all the polymer components used in the sample introduction system, polyvinyl chloride (PVC), used for the peristaltic pump tubing, is the most prone to causing carryover. Therefore, in order to further reduce the volume and surface area, smaller diameter peripump tubing can be used. In this case, the pump speed must be increased accordingly to maintain proper nebulizer flow. Pump speed correction factors are shown in Table 1. To convert from the standard 1-mm internal diameter (ID) tubing to a smaller

Table 1. Correction Factors for Various Internal Diameter Peristaltic Pump Tubes Used to Maintain Correct Nebulizer Flow

Peristaltic pump tubing ID (mm)	Correction factor
0.89	1.3
0.76	1.8
0.64	2.55

size, multiply the normal pump speed used with the 1-mm tubing by the factor shown to maintain the same flow. Switching from 1-mm tubing to 0.64-mm tubing can reduce the sample rinse-out time by as much as 50%.

Minimization of Data Acquisition Time

Significant improvements in ICP-MS quadrupole, detector, and electronic technology have resulted in much better sensitivity and precision than earlier instruments. As a result, shorter integration times can be used while detection limit performance can be maintained or even improved. Total acquisition time is also reduced in Agilent ICP-MS instruments through the use of intelligent, variable quadrupole settling time, which reduces time between mass jumps. In the case of collision/reaction cell instruments such as the Agilent 7500ce or 7500cs, minimization of stabilization time during cell mode switching is also critical. Agilent's Octopole Reaction System (ORS) features a very small-volume cell that minimizes the time needed for gas switching and stabilization. Typically, 15 seconds is sufficient to achieve stable conditions after gas switching.

New Intelligent Software Capabilities (Revision B.03.03)

The ChemStation's new software features have been designed to eliminate wasted time in both sample uptake and rinse out, significantly reducing run times without compromising data quality. Customers with earlier revisions can upgrade to the newest B.03.03 revision by contacting their Agilent sales or service representative.

Pre-emptive Rinse

Pre-emptive Rinse utilizes the volume of the sample introduction tubing (autosampler probe,

sample tubing, and peristaltic pump tubing) to maintain sample flow to the nebulizer *after* the autosampler probe has moved to the rinse position and begun rinsing. On conventional ICP-MS systems, the autosampler probe moves to the rinse position only after acquisition has finished; as much as 30 to 60 seconds can be wasted with the probe sitting in the sample vial waiting for the acquisition to finish. With Pre-emptive Rinse enabled, the autosampler probe moves from the sample to the rinse port at a preset time *before* acquisition has finished, using the sample still in the uptake tubing for the remaining data acquisition. This provides two benefits:

1. No time is wasted while sample flushes from the sample introduction system after acquisition has finished.
2. When the peristaltic pump speed is increased to rinse after a sample, it is pumping rinse solution, not the previous sample. This significantly reduces the total matrix load on the interface since only rinse solution and not sample is introduced at a high rinse flow rate. As a result, interface maintenance is reduced and stability is enhanced.

Intelligent Rinse

Intelligent Rinse is designed to ensure that the absolute minimum amount of time is spent washing out each sample — *independent* of analyte concentration. On systems without Intelligent Rinse, the fixed, postsample rinse time must be long enough to wash out the highest anticipated analyte concentrations, and the most memory-prone analytes, to blank levels. This means that for back-to-back samples of similar concentration or very clean samples, unnecessary time is wasted in rinsing. Intelligent Rinse monitors the background level of up to 10 user-selected elements (or element ratios) to determine when sufficient rinsing has occurred. Since Intelligent Rinse supports internal standard correction (or any other count ratio), it is not necessary to update the background thresholds if the instrument sensitivity changes. Only Agilent Intelligent Rinse provides this level of sophistication. Intelligent Rinse supports up to three distinct rinse steps (for different rinse solutions) in addition to the probe rinse port on the autosampler. Each of these rinse steps can be controlled with respect to rinse time and uptake speed. Any of these rinse steps, including the probe rinse port, can be selected as the Intelligent Rinse step. When using Intelligent Rinse, in many cases, background levels are achieved immediately and the rinse terminates after only a few seconds.

Peristaltic Pump Program

Before Acquisition:
 Uptake Speed: 0.50 rps
 Uptake Time: 20 sec
 Stabilization Time: 40 sec

After Acquisition (Rinse Port):
 Rinse Speed: 0.50 rps
 Rinse Time (Sample): 5 sec
 Rinse Time (STD): 5 sec

After Acquisition (Rinse Vial):

	Step1	Step2	Step3
Rinse Vial:	1	2	2
Rinse Speed:	0.10	0.50	0.50 rps
Rinse Time:	90	30	30 sec (max)
Rinse Port Rinse Time:	0	0	0 sec

☒ Intelligent Rinse out After Acquisition

☒ Execute Pre-emptive Rinse
 Pre-emptive Time: 60 sec

☒ Terminate a Rinse Step at the end of Acq.

Intelligent Rinse:
 Rinse Step: Step3
 Threshold (CPS)

Mass or Ratio	Sample	STD
9	7	2.000E-03
98	72	2.000E-03
201	209	3.500E-03
121	115	6.000E-03
205	209	1.500E-02
63	72	7.000E-01
111	115	3.000E-04
208	209	5.000E-02
75	72	2.500E-02
52	45	8.000E-01

Load masses from acq. parameters

Stability check time window: 5 sec

Action on failure: Next Sample

OK Cancel Help

Figure 1. Peristaltic pump program setup panel showing typical settings for both Intelligent and Pre-emptive Rinse functions.

The result is that the shortest possible rinse times that allow complete washout are always achieved. The peristaltic pump control panel that is used to configure Intelligent Rinse is shown in Figure 1.

Putting It All Together

By combining optimized plumbing, Pre-emptive and Intelligent Rinse functions, and streamlined data acquisition parameters, typical average run-to-run times for complex environmental samples — including sticky elements such as Hg — can be reduced by almost 50%.

Rinse Program

The rinse program is shown in Figure 1. Pre-emptive Rinse time is set to 60 seconds, which immediately reduces the run time by a minute and reduces matrix loading on the plasma and interface. By the time the acquisition is finished, the rinse solution (Step 1 in this case) has nearly reached the nebulizer and most of the system is already rinsed. Between each rinse step, a small bubble is introduced into the line, helping to partition the solutions and minimize mixing. Step 2 is the main rinse and the only step using high-speed rinse out. Step 2 is set to 30 seconds, though much shorter times are often sufficient. Step 3 is the Intelligent Rinse step, which is functionally a monitor step. This means that the system will only rinse in Step 3 until the specified background elements reach the set points, or up to a maximum of 30 seconds in this case. At that point, rinsing is




Figure 2. Graphical representation of sample analysis time using conventional uptake and rinse program (top) versus uptake and rinse utilizing Pre-emptive Rinse and Intelligent Rinse (bottom).

Table 2. Comparison of Total Sample Introduced Under Typical Conditions Using Normal Rinse Program Versus Pre-Emptive Rinse. Up to 20% Less Sample Is Introduced Using Pre-Emptive Rinse

	Standard mode	Pre-emptive rinse
Sample uptake	1.2 mL/min * 20 sec = 0.4 mL	1.2 mL/min * 20 sec = 0.4 mL
Stabilization	0.4 mL/min * 30 sec = 0.2 mL	0.4 mL/min * 20 sec = 0.13 mL
Sample analysis	0.4 mL/min * 180 sec = 1.2 mL	0.4 mL/min * 180 sec = 1.2 mL
Rinse out	1.2 mL/min * 15 sec = 0.3 mL	0
Total sample	2.1 mL	1.73 mL

finished and the next sample is introduced. Figure 2 is a graphical representation of the different ways in which Pre-emptive Rinse and Intelligent Rinse reduce sample analysis time.

Streamlined Data Acquisition

Table 3 depicts the additional time savings by optimizing the acquisition integration times, taking into account the high sensitivity provided by the 7500ce¹. In this case, the entire suite of 21 EPA method 200.8 elements (including Hg, plus the five mineral elements (Na, Mg, K, Ca, and Fe), plus internal standards were analyzed using optimized cell conditions (three modes — H₂, He, and no gas) in 4.5 minutes average sample-to-sample time. Excellent (ppt level) method detection limits (MDLs) were achieved. Carryover, as indicated by the analysis of a blank solution run immediately after a 100 ppb (10,000 ppb for the mineral elements) standard was extremely low. When data quality objectives permit, switching to a single ORS mode (either no gas or He only) can reduce the average analysis time to less than 3 minutes.

Table 3. Typical Data Showing Blank Concentration Directly After a 100/10,000 ppb Standard and Calculated Method Detection Limits (3 Sigma) from 10 Separate Replicate Analyses of a 0.1 ppb Standard

1 point/peak acquisition Average analysis time – 4.5 mins			
Sample	Cal 100.0/ 10000 (ppb)	Blank (ppb)	MDL (ppb)
Be/9 [#3]	99.89	0.020	0.0205
Na/23 [#2]	9987	0.088	4.6245
Mg/24 [#2]	9946	1.419	1.7648
Al/27 [#3]	99.61	-0.028	0.0239
K/39 [#2]	9951	0.573	2.0353
Ca/40 [#1]	10020	2.387	1.9820
V/51 [#2]	99.98	-0.010	0.0193
Cr/52 [#2]	99.69	0.003	0.0156
Mn/55 [#2]	99.69	0.015	0.0258
Fe/56 [#1]	9986	2.731	0.6361
Co/59 [#2]	99.63	0.013	0.0092
Ni/60 [#2]	99.43	0.015	0.0100
Cu/63 [#2]	99.26	0.012	0.0292
Zn/66 [#2]	99.59	-0.020	0.0288
As/75 [#2]	100	0.003	0.0286
Se/78 [#1]	99.77	0.019	0.0299
Mo/95 [#3]	101.8	0.018	0.0219
Ag/107 [#3]	99.32	0.021	0.0085
Cd/111 [#3]	99.97	0.012	0.0167
Sb/121 [#3]	100.7	0.026	0.0168
Ba/137 [#3]	99.92	0.009	0.0256
Hg/201 [#3]	2.012	0.004	0.0048
Tl/205 [#3]	100.3	0.021	0.0089
Pb/208 [#3]	100.5	0.012	0.0127
Th/232 [#3]	100.8	0.020	0.0104
U/238 [#3]	101.1	0.015	0.0084

¹Acquisition parameters of 1 point per peak were used, with integration times per point from 0.1 to 0.5 seconds depending on the element and ORS mode.

#1 — H₂
#2 — He
#3 — no gas

Conclusions

Faster Sample Runs, Higher Confidence

Sensitivity is maintained, maintenance is reduced, confidence in results is improved, and valuable time is never wasted. Pre-emptive Rinse reduces the total sample-to-sample pre-emptive time by at least 60 seconds, while also exposing the system to less total sample matrix (Table 2). More importantly, the sample matrix is never delivered to the nebulizer at high flow rates, thereby significantly increasing the number of samples that can be run between maintenance intervals.

Intelligent Rinse ensures that, after very clean samples, the rinse thresholds will be met immediately and almost no time will be spent in the final rinse solution, eliminating most of the 30- to 60-second available time. Furthermore, Intelligent Rinse can be counted on to rinse as long as necessary (up to a user-defined limit), ensuring that adequate rinsing will always occur. Rinse time will always be as long as necessary and never any longer. Additionally, the user has the choice of determining which elements need the most complete rinse out. Critical elements, like Hg, that require very low detection limits and are very memory-prone can be analyzed with confidence at ppt levels, even in unknown samples, while the washout threshold of high-level mineral elements such as Na can be set at a much higher level, or ignored if desired.

An illustration of high productivity made possible by the new Agilent ChemStation rinse modes is given by the following example: A 7500ce ORS instrument, analyzing a mixed run of drinking waters, leachates, and high-matrix wastewaters, operating in three modes (H₂, He, and no-gas), covering a full environmental analyte suite including the mineral elements and Hg, has an average sample-to-sample analysis time of 4.5 minutes — without any risk of carryover from unexpectedly high samples.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
August 10, 2006
5989-5001EN



Agilent Technologies



Ultra-Trace Analysis of Beryllium in Water and Industrial Hygiene Samples by ICP-MS

Application

Environmental

Authors

Steve Wilbur and Emmett Soffey
Agilent Technologies, Inc.
Bellevue, WA
USA

Craig Jones
Agilent Technologies, Inc.
Santa Clara, CA
USA

Abstract

Exposure to airborne beryllium can lead to adverse health effects in humans. Consequently, many countries have legislation in place to ensure the health and safety of workers and the wider environment. Because even very low concentrations of Be in air constitute a toxic threat to health, analytical methodology that is capable of extremely high-sensitivity measurement is required. Although trace-level analysis of the element is difficult by some ICP-MS instrumentation, the Agilent 7500ce ICP-MS can achieve Be detection limits in the sub-ppt range directly in water and in acid digests of air filters under routine analytical conditions. Long-term precision and accuracy data recorded over 8 hours of continuous analysis of a highly diluted certified reference material (NIST 1640) is presented. Recoveries were greater than 97% and precision was in the order of 1 to 2%. Comparable performance was obtained when measuring spiked membrane filters, indicating that the method is applicable to the ultra-trace analysis of Be in air samples collected on filters.

Introduction

Workplace exposure to beryllium (Be) can pose significant chronic and acute health risks and is receiving increased scrutiny from regulators and industrial hygiene professionals. Be is a metallic element belonging to Group IIA of the periodic table. It has an atomic weight of 9.012 and is monoisotopic. It occurs naturally in the earth's crust at concentrations ranging from 2 to 10 ppm. The average concentration in U.S. soils is about 0.6 ppm, and during the late 1970s and 1980s Be was measured at between 0.03 and 0.4 ng/m³ in air [1]. In its natural ore state, beryllium is relatively nontoxic. However, all other commercially important Be compounds exhibit significant pulmonary toxicity. Humans are exposed to Be from a number of sources, including food, water, and air. Clinically, the most important exposure pathways are airborne, including smoke from coal combustion, cigarette smoke, and airborne particulates from various Be manufacturing processes. Be use spans numerous industries, including electronics, aerospace, nuclear, and metallurgical. Exposure to airborne Be can lead to pulmonary disease either as Acute Beryllium Disease (ABD) or Chronic Beryllium Disease (CBD), depending on level and duration of exposure. Both can be fatal, and CBD symptoms may only appear after a latency period of up to 25 to 30 years. The U.S. Environmental Protection Agency (EPA) has also classified Be as a "probable human carcinogen" [1]. EPA-developed toxicity values for Be exposure are shown in Table 1. The National Institute for Occupational Safety and Health (NIOSH) exposure limit for Be in air is 0.05 µg/m³. The limit of detection (LOD) by



Agilent Technologies

Table 1. Chemical Toxicity Values for Beryllium Via Oral and Inhalation Exposure Pathways as Determined by the U.S. EPA [1].

Cancer Risk	Non-Cancer Effect	
Inhalation UR*	Oral RfD*	Inhalation RfC*
2.4 per mg/m ³	0.002 mg/kg-day	0.00002 mg/m ³

*UR – (inhalation unit risk): estimate of number of people per million that likely will get cancer from continuous exposure to Be in air at a concentration of 1mg/m³.

*RfD – (oral reference dose): An estimate (with uncertainty spanning perhaps an order of magnitude) of a daily oral exposure of a chemical to the human population (including sensitive subpopulations) that is likely to be without risk of deleterious noncancer effects during a lifetime.

*RfC – (inhalation reference concentration): An estimate (with uncertainty spanning perhaps an order of magnitude) of a continuous inhalation exposure of a chemical to the human population through inhalation (including sensitive subpopulations) that is likely to be without risk of deleterious noncancer effects during a lifetime.

Inductively Coupled Plasma Optical Emission Spectroscopy (ICP-OES) according to NIOSH 7301 [2] is 5 ng/filter, which requires air sampling volumes between 1,250 and 2,000 liters. By contrast, the LOD by ICP-MS using the Agilent 7500ce as described in this paper is 50 ppq in solution (0.00005 ng/mL), which is equivalent to 0.00125 ng/filter or a 4000× improvement in sensitivity.

Analytical Challenges

From an analytical standpoint, Be poses several challenges. Because of the toxicity of very low concentrations in air, extremely high sensitivity is desired. Traditional NIOSH and Occupational Safety and Health Administration (OSHA) methods for Be in airborne samples utilize ICP-OES with approximate detection limits of 0.005 µg/filter (NIOSH 7301), which may require a sampling volume of up to 2,000 liters. By using a much more sensitive technique such as Inductively Coupled Plasma Mass Spectrometry (ICP-MS), adequate sensitivity can be had at much lower sampling volumes and absolute detection limits can be lowered significantly. While ICP-MS can provide numerous advantages over other techniques in terms of sensitivity and throughput, there are some challenges as well. Be exhibits two characteristics that have traditionally made trace-level ICP-MS analysis difficult. Be is low mass and has a high first ionization potential (9.32 eV). Being low mass (atomic weight = 9), Be ions are subject to scattering in the presence of other higher mass ions (space charge effects), for example other metals in the sample. This can limit the sensitivity by an order of magnitude or more on some ICP-MS instruments. High ionization potential has a similar effect. Since the ICP-MS measures ions, elements that are difficult to ionize like Be have much higher detection limits than elements that ionize easily. Therefore, in

order to achieve maximum sensitivity for Be, these two obstacles must be overcome. By specifically designing the plasma and ion optics for maximum ionization and minimum space charge, Agilent Technologies has effectively achieved Be detection limits in the sub ppt range under routine analytical conditions with the 7500 Series instruments. These design characteristics include a unique digitally synthesized 27 MHz RF generator and low flow sample introduction system to ensure maximum plasma temperatures as well as the avoidance of any type of shadow stop in the path of the ion beam that would cause loss of low mass sensitivity.

Instrumentation

An Agilent 7500ce ICP-MS was used for this work in standard configuration. While the 7500ce is a collision cell instrument, it was used in “no-gas mode”; meaning, the collision cell was unpressurized and no collision/reaction chemistry was employed. The work was done under standard laboratory conditions of cleanliness, no clean room or special apparatus of any type were utilized. Instrument parameters are listed in Table 2.

Table 2. ICP-MS Parameters

Agilent 7500ce Instrument Conditions	
Plasma forward power	1500 W
Carrier gas flow	0.8 L/min
Nebulizer	Glass concentric
Sample flow	400 µL/min
Spray chamber temp	2 ° C
Extraction lens 1	2 V
Extraction lens 2	–110 V
Reaction mode	Off
Isotopes monitored	6, 9, 45
Integration time for ⁹ Be	5 seconds per replicate/3 replicates per analysis
Total run time	3 minutes

Experimental

The initial determination of performance was based on simple calibrations in dilute nitric acid and repeated analyses of diluted certified reference water (NIST 1640) for Be. This is because there are currently no standard reference materials available for Be in air samples. In the initial work, a sequence of 163 separate samples (dilutions of NIST 1640, Figure 2) was performed over 8.5 hours in order to determine the robustness and precision of the method (Figure 3). Calibrations were performed from 1 ppt to 50 ppt as shown in Figure 1.




Figure 1. Calibration for Be in dilute nitric acid at 0, 1, 10, and 50 ppt (standard concentrations in the data table at the top right are expressed in ppb). The expanded area shows linearity from 1 to 10 ppt. ^6Li was used as the internal standard.

Estimated detection limits based on calibration linearity, response factor, and background were calculated to be 5.2×10^{-5} ppb (52 ppq) or 0.000052 ng/mL, compared with published values of 0.2 ng/mL by ICP-OES (NIOSH 7300). Subsequent work included the analysis of spiked 47 mm diameter cellulose ester membrane filters (0.8 μm pore size) according to the NIOSH 7301 (modified) method. Digestion conditions are outlined in Table 3. The method was slightly modified to use a Hot Block digester and the final diluent was 1% nitric acid. The intent was to determine the suitability and performance of the method to the matrix containing the dissolved filters.




Figure 2. The analytical sequence used to test long-term accuracy and precision through continuous repeat measurements of certified reference material (NIST 1640 water)




Figure 3. Results of a long-term stability study using repeat analysis of NIST 1640 diluted 1,000 and 10,000 . 1000 and 10,000 samples were analyzed alternately for 8.5 hours. Actual certified concentration in the diluted samples was 34.9 ppt and 3.49 ppt (1000 and 10,000).

Table 3. Modified NIOSH 7301 Digestion Procedure Utilizing Hot Block Digester for Analysis of Be on Filter Samples by ICP-MS.

Digestion Step	Procedure	Notes
1	Place filter into pre-leached 50 mL poly centrifuge tube. Add 5 mL 1:3 HNO ₃ :HCl. Cover with a plastic watch glass. Let stand 30 min at room temperature.	Start a reagent blank at this step. Some species of Al, Be, Co, Cr, Li, Mo, Sb, W, and Zr may not be completely solubilized by this procedure. Alternative solubilization techniques for these elements can be found elsewhere [2].
2	Heat on hot block (120 °C) until ca. 0.5 mL remains.	Hot block substituted for hot plate.
3	Add 2 mL 1:3 HNO ₃ and repeat step 2. Repeat this step until the solution is clear.	PVC filters will not completely dissolve after repeated additions of ashing acid.
4	Remove watch glass and rinse into the digestion tube with distilled water.	
5	Increase the temperature to ~140 °C and take the sample to near dryness (ca. 0.5 mL)	
6	Bring to final volume of 25 mL with 1% nitric acid.	Final solutions ranged from hazy clear to dark amber. Internal standards added at this point. Solutions allowed to settle overnight prior to analysis of supernatant.

Precision and Accuracy in Waters

Precision and accuracy was evaluated by examining the results of the replicate analyses of the 1,000 and 10,000× dilutions of NIST 1640. The certified value for Be in NIST 1640 is 0.03494 ppm. Therefore, after dilution, values were 0.03494 and 0.003494 ppb. During the course of the analytical sequence (Figure 2), NIST 1640 was analyzed 113 times over 8.5 hours, 56 times at 1/1,000 dilution and 57 times at 1/10,000 dilution. The results are shown in Table 4.

Table 4. Analysis of Be in NIST 1640 – Standard Reference Water. Accuracy and Precision of Replicate Measurements of NIST 1640 at 1,000 and 10,000 Dilution Over 8.5 Hours of Continuous Analysis

DF	n	Average measured concentration (ppt)	%RSD	Average % recovery
1,000	56	34.13	0.988	97.67
10,000	57	3.41	2.51	97.49

Precision and Accuracy on Filter Samples

In order to determine the performance of the method for the analysis of Be contained on membrane filter samples according to NIOSH 7301 (modified), replicate filters (10 filter blanks and 10 5-ppt spiked filters) were analyzed. Spike recoveries were performed since no standard reference materials for Be on filters are available. Results are given in Table 5.

Table 5. Summary Results of Replicate Analyses of Spiked Membrane Filters and Blanks for Be

	n	Mean conc. (ppt)	% RSD	% Recovery
Reagent blank	–	–0.08 (n = 2)	–	–
Blank filters	10	0.481	58.8	–
Spiked filters (5 ppt)	10	5.25	4.73	95.3

Conclusions

The Agilent 7500 Series ICP-MS is capable of measuring Be directly in waters and in acid digests of air filters according to NIOSH 7301 at levels up to 4,000 times lower than the published DLs using ICP-OES. By using proprietary Agilent ion optics designed specifically to minimize the effects of space charge on low mass analytes such as Be and very high plasma temperatures, the obstacles to ultra trace determination of Be by ICP-MS have been overcome, allowing measurements at the ppq level ($<0.0006 \text{ ng/m}^3$ for a 2,000 L sample). In addition, the long term precision and accuracy, as determined by measuring highly diluted certified reference material (NIST 1640) shows recoveries of greater than 97% and precision on the order of 1 to 2% over more than 8 hours of continuous analysis. Similar performance was obtained when measuring spiked membrane filters, indicating that the method is applicable to the ultra-trace analysis of Be in air samples collected on filters. The very high sensitivity and precision can permit the use of shorter sampling times and/or significantly lower limits of detection.

References

1. <http://www.epa.gov/ttn/atw/hlthef/berylliu.html#ref2>
2. NIOSH Manual of Analytical Methods (NMAM), Fourth Edition

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
August 10, 2006
5989-5438EN



Agilent Technologies

Determination of Methyl Mercury in Water and Soil by HPLC-ICP-MS

Application

Environmental

Authors

Dengyun Chen
Agilent Technologies Co., Ltd. (China)
Beijing, 100022, China

Miao Jing and Xiaoru Wang
The First Institute of Oceanography, S.O.A.
Qingdao, 266061, China

Abstract

This application note describes a method based on high-performance liquid chromatography (HPLC) coupled to inductively-coupled plasma mass spectrometry (ICP-MS) for the separation and determination of methyl and ethyl mercury. Because the different chemical forms of mercury exhibit different toxicities, separating elemental mercury from the alkylated forms provides vital information on the actual risk posed by a sample. The HPLC-ICP-MS method is applied to the analysis of water and soil samples. The method detection limits in water for MeHg, EtHg, and Hg^{2+} are better than 10 ng/L, and recoveries between 80% and 120% were obtained for the Hg species extracted from the soil samples.

Introduction

Heavy metals are among the most significant pollutants in natural waters. Within this group of pollutants, mercury (Hg) is of particular concern because of its toxicity and accumulative nature in the food chain. It is found throughout the ecosystem in trace amounts in air, water, soil, and living

organisms. The different physical and chemical forms of this trace element have significantly different properties [1]. It is well known that the toxicity of Hg is highly dependent on its chemical form, with inorganic and organic Hg species presenting different toxicities. Methylmercury (MeHg) is the most commonly occurring organo-mercury compound in environmental and biological materials and the most toxic Hg species, whereas ethylmercury (EtHg) and phenylmercury are rarely present in the environment. MeHg is 10–100 times more toxic than inorganic Hg compounds [2, 3], and certain levels of MeHg exposure in humans can lead to neurological problems [4]. Because of its high-lipid solubility, MeHg penetrates the blood-brain barrier and readily diffuses into cell membranes [5]. Fetuses are particularly vulnerable because of their rapid brain development. The main source of Hg is air emissions from power generation and other industrial activities. Once in the environment, biological activity will typically methylate Hg to either MeHg, or less commonly, di-methyl mercury. Because fish and other seafood products are the main source of MeHg in the human diet, pregnant women are advised to limit the consumption of certain fish. Recently, the Joint FAO/WHO Expert Committee on Food Additives (JECFA) recommended the Provisional Tolerable Weekly Intakes (PTWI) of MeHg be reduced to 1.6- $\mu\text{g}/\text{kg}$ body weight per week, down from 3.3- $\mu\text{g}/\text{kg}$ body weight per week. See Table 1.



Agilent Technologies

Table 1. Regulated levels (PTWI) of MeHg in Foods

Authority	MeHg ($\mu\text{g}/\text{kg}$ body weight)
Food and Agriculture Organization of the United Nations (FAO)	1.6
World Health Organization (WHO)	1.6

PTWI = Provisional Tolerable Weekly Intakes.

In China, the permitted level for MeHg in the “discharge standard of pollutants for municipal wastewater treatment plant of China (GB 18918-2002)” is “undetectable”, that is, below the detection limit (DL) of the recommended method (10 ng/L) [6].


There are several means of determining total Hg in environmental samples, but the simultaneous determination of inorganic and organic Hg is difficult. This is because the typical concentration of MeHg is much lower than for inorganic Hg. The most common methods of Hg speciation are gas chromatography (GC) or HPLC coupled to a Hg-specific detector (fluorescence, photometry, or

other elemental detector). The low concentration of Hg in natural waters leads to the need for processing very large sample volumes. A preconcentration step is also required because the target reporting limit is often below the sensitivity of the detector used.

In China, the recommended method for MeHg measurement (GB/T14204-93) uses GC with an electron capture detector (ECD). Limitations of the method include:

- Method detection limit (MDL) of 10 ng/L, despite a complicated enrichment procedure
- Method is not element specific
- Method suffers from interferences, leading to false positive results or low recoveries

The objective of this study was to develop a sensitive and specific MeHg analysis method by combining HPLC with ICP-MS – see Figure 1.

**Figure 1. Agilent 1100 HPLC schematic.**

Instrumentation

An Agilent 1100 HPLC was interfaced to an Agilent 7500a via the Agilent HPLC-ICP-MS interface. PEEK 20 μ L, 100 μ L, and 1000 μ L sampling loops were selected. The operating parameters of the HPLC and ICP-MS are listed in Table 2a and 2b.

Table 2a. Working Parameters of HPLC

Column	ZORBAX Eclipse XDB-C18, 2.1-mm id $\times$ 50 mm, 5 μ m
Mobile Phase	0.06-mol/L ammonium acetate, 5% v/v methanol, 0.1% 2-mercaptoethanol, pH = 6.8
Flow rate	0.4 mL/min
Injection volume	100 μ L

Table 2b. Working parameters of Agilent 7500a ICP-MS

RF power	1550 W
Nebulizer	PFA concentric 100 μ L/min
Spray chamber	Quartz, Scott double pass, chilled to -5°C
Torch	Quartz one piece Fassel type, 2.5-mm injector
Sampling depth	4.5 mm
Carrier gas flow rate	0.75 L/min
Make-up gas flow rate	0.40 L/min

Stability and Sensitivity

To monitor the stability of the instrument, 1.0 μ g/L bismuth (Bi) was added to the methanol eluent as an internal standard (ISTD). The 7500a was tuned for maximum sensitivity by optimizing the Bi signal. During the testing period of 10 hours, the RSD of the ISTD was less than 5%. Because the drift was minimal, there was no need for an ISTD correction. No Bi or any other ISTD was used for the actual analyses.

HPLC Column

For best results, precondition the HPLC column (ZORBAX Eclipse XDB-C18, 2.1 mm id $\times$ 50 mm, 5 μ m) by pumping HPLC grade methanol at 0.4 mL/min for at least 2 hours, and then condition with eluent (same flow rate) for at least half an hour. Without this conditioning procedure, the inorganic Hg will be affected by contamination in the system leading to poor recovery or peak splitting.

Results and Discussion

Chromatographic Separation Using Standard Solutions

Using the operating conditions stated in Table 2a and Table 2b, a mixed Hg species standard in pure water was injected into the HPLC. The resulting total ion chromatogram (TIC) showed good separation of target species. See Figure 2.




Figure 2. HPLC-ICP-MS TIC of three mixed Hg species standards in pure water: MeHg 2.48 min, Hg²⁺ 3.21 min, and EtHg 6.54 min, 100- μ L loop. 1.0 ppb each.

Table 3. Integration Results of Hg Species Measurement by HPLC-ICP-MS

RT (min)	Species	Hg Conc. (µg/L)	Area
2.48	MeHg	1.0	5.09E+06
3.21	Hg ²⁺	0.8	3.87E+06
6.54	EtHg	1.0	4.91E+06

Efficiency of Detection

Because 1.0 µg/L of each Hg species was analyzed, the peak areas for the three species are similar (see Table 3). The slight difference is probably due to the purity of the standards or the error introduced during preparation of the standards.

One of the advantages of an HPLC-ICP-MS system is the ability of the argon plasma to decompose and ionize an element, irrespective of the chemical structure of the species. This independence of signal to original structure is called compound independence, and allows a calibration to be constructed based upon Hg molar concentration (Compound Independent Calibration or CIC). Reported results for all species identified will be fairly accurate, even when the compound is unidentified (unknown species).

Linearity

When the sample was diluted 100 times (10 ng/L for MeHg and EtHg, 8 ng/L for Hg²⁺), the Hg species could still be measured, as shown in Figure 3. The retention times (RTs) also remained fairly stable. The minor peak with a RT of 1.35 min was caused by column contamination. When the column was cleaned with methanol, the peak disappeared.

The chromatogram in Figure 3 shows that the MDLs for the Hg species are better than 10 ng/L. If the eluent contamination problem can be solved by using higher purity reagents, sub ng/L MDLs will be achievable.

A series of calibration standards was prepared from 10 ng/L to 100 µg/L by diluting the mixed Hg species stock solution (1.0-µg/mL Hg for MeHg and EtHg, 0.8 µg/mL Hg for Hg²⁺ in pure water). A 20-µL injection loop was used throughout, except for the 10-ng/L data, which was obtained using a 100-µL loop. The peak areas were integrated for the different concentration levels of three mixed Hg species. The linear range of the calibration curves (Table 4 and Figure 4) for Hg speciation by the HPLC-ICP-MS method was at least 4 orders. This range covers expected real sample levels, and so the method is appropriate for direct determination of water samples without the application of complicated preconcentration procedures.




Figure 3. The HPLC-ICP-MS TIC of 10-ng/L Hg species standards in pure water. (Contaminant 1.35 min, MeHg 2.35 min, Hg²⁺ 3.10 min, and EtHg 6.59 min, 100-µL loop)




Figure 4. Calibration curves for MeHg, Hg^{2+} , and EtHg.

Table 4. Integration Peak Areas for Different Concentration Hg Species by HPLC-ICP-MS (Hg^{2+} Concentrations were 80% of the Shown Values)

Conc.(ng/L)	MeHg	Hg^{2+}	EtHg
100000	1.07E+08	5.03E+07	9.83E+07
10000	1.06E+07	4.61E+06	9.24E+06
1000	1.17E+06	5.72E+05	9.44E+05
100	1.30E+05	1.23E+05	1.02E+05
10	5.86E+04	3.55E+04	5.86E+04

Chromatographic Separation of Hg Species in 3% NaCl

In order to test the ability of the method for high matrix sample analysis, the stock Hg species solution was diluted into 3% NaCl (w/v in water)

to obtain 100 ng/L MeHg, EtHg, and Hg^{2+} . The solution was filtered through a 0.45- μm membrane before analysis. A 20- μL injection loop was used for the measurement. The ^{202}Hg ion chromatogram was overlaid with the corresponding ion chromatogram of the pure water diluted solution at the same concentration, as shown in Figure 5. The peak areas of the Hg species in 3% NaCl were also integrated and the recoveries were between 90% and 110% relative to standards in pure water. This demonstrates that the method is suitable for even high matrix samples such as seawater.




Figure 5. Overlaid HPLC-ICP-MS ion chromatograms for 100-ng/L Hg species standards in pure water (upper) and in 3% NaCl (w/v, lower) (20- μL loop).

Application to Soil Samples

When the HPLC-ICP-MS method is applied to solid samples such as tissues, soils, or sediments, sample preparation is necessary. The extraction of Hg species from the solid samples is a crucial step due to the presence of inorganic Hg in environmental samples at low levels. The Hg species, especially MeHg, are easy to lose or transform to other species. To prevent the possible destruction of the MeHg species in a digestion procedure, a number of methods have been reported, including extraction of the compound from samples using dilute hydrochloric acid or chelating agents [7]. Published methods for the extraction of both inorganic and organo-mercury compounds are time-consuming, labor-intensive, and require large amounts of high-purity solvents or special reagents. In the present work, a simple extraction method based on diluted hydrochloric acid was used. The spike recoveries of the soil samples were between 80% and 120%. Further testing of the method and the MeHg containing reference soil sample are planned.

Hg Species Extraction Method

1. Weigh 1.00 g soil sample into a 20-mL plastic centrifuge tube.
2. Spike 0 to 90 μ L of a 100 ng/L mixed Hg species standard solution into the soil samples. Shake to mix.
3. Add 9.0-mL 7.6% HCl (w/v) and 1.0-mL 10% 2-mercaptoethanol to each tube. Place samples in an ultrasonic bath for 30 minutes to assist the extraction.
4. Centrifuge the samples at 3000 rpm for 5 minutes to partition the particulate matter.
5. Transfer 2.0 mL of the upper (clear) solution in to a 50-mL clean PET bottle. Add 15.0 mL of pure water.
6. Use 10% ammonia solution to adjust the pH of the solution to pH 6.8.
7. Add pure water to the solution until the final solution weight is 20.0 g.
8. Filter the solution through a 0.45- μ m membrane before HPLC-ICP-MS measurement.

The HPLC-ICP-MS TIC for the soil sample extraction by 7.6% HCl is shown in Figure 6. The soil sample was spiked with 90-ng (as Hg) mixed Hg species standard. The peak height of Hg^{2+} in the spectrum is higher than the other two peaks because of the presence of inorganic Hg in the soil. Analysis of the unspiked soil sample showed an insignificant level of MeHg and EtHg. The measured results for the spike recovery test are shown in Table 5.




Figure 6. HPLC-ICP-MS TIC for soil sample, S-A-03, extracted by 7.6% HCl, spiked with 0.9-ng (as Hg) mixed Hg species standard. MeHg 2.55 min, Hg^{2+} 3.24 min and EtHg 6.53 min, 100- μ L loop.

Table 5. Spike Recoveries of Hg Species in Soil Samples by HPLC-ICP-MS

Sample	Hg-Species	True Value (pg)	Measured value (pg)	Recovery (%)
S-BLK-1	MeHg	NA	2	NA
	Hg ²⁺	61	63	103
	EtHg	NA	+	NA
S-BLK-2	MeHg	NA	9	NA
	Hg ²⁺	61	65	107
	EtHg	NA	+	NA
S-A-03	MeHg	90	85	95
	Hg ²⁺	151	185	122
	EtHg	90	82	91
S-A-04	MeHg	90	80	89
	Hg ²⁺	151	181	120
	EtHg	90	75	83
S1-1	MeHg	36	34	94
	Hg ²⁺	97	88	91
	EtHg	36	28	77
S1-2	MeHg	36	37	104
	Hg ²⁺	97	105	108
	EtHg	36	35	97
S1-3	MeHg	36	41	113
	Hg ²⁺	97	98	101
	EtHg	36	43	120

NA Not applicable

+ No measurements made

The spike recoveries were all between ~80% and 120%, confirming the suitability of the sample preparation procedure for soil sample analysis by HPLC-ICP-MS.

Conclusions

HPLC-ICP-MS is appropriate for water samples analysis, even when the matrix in the water sample is high. The MDLs for MeHg, EtHg, and Hg²⁺ are better than 10 ng/L and meet current regulatory requirements. When the method is applied to soil samples, Hg species extraction by 7.6% HCl is appropriate, with recoveries between 80% and 120%.

References

1. J. O. Nriagu (Ed.), The Biogeochemistry of Mercury in the Environment, Elsevier/North-Holland Biomedical Press, Amsterdam, 1979.
2. National Academy of Science, An Assessment of Mercury in the Environment, National Research Council, Washington, DC, 1978.
3. R. Hartung, B. D. Dinman (Eds.), Environmental Mercury Contamination, Ann Arbor Science, Ann Arbor, MI, 1972.
4. M. Berlin, 1986. Mercury. In: Friberg, L., Nordberg, G., Vouk, V. (Eds.), Handbook on the Toxicology of Metals. Elsevier, Amsterdam, pp. 387–444.
5. J.S. Felton, E. Kahn, B., Salick, F.C. van Natta, and M.W. Whitehouse, (1972) Heavy metal poisoning: mercury and lead. *Ann. Intern. Med.* **76**, 779–792.
6. Discharge standard of pollutants for municipal wastewater treatment plant of China, GB 18918-2002, 2002.
7. M. Jackie, A. C. Vikki, and H.E.G. Philip., *J. Anal. At. Spectrom.*, (2002), **17**, 377–381.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
September 6, 2005
5989-3572EN



Agilent Technologies



Ion Chromatography (IC) ICP-MS for Chromium Speciation in Natural Samples

Application

Environmental

Authors

Tetsushi Sakai
Agilent Technologies
Musashino Center Building
1-19-18 Naka-cho Musashino-shi
Tokyo 180-0006
Japan

Ed McCurdy
Agilent Technologies
Lakeside, Cheadle Royal Business Park
Stockport
United Kingdom

Steve Wilbur
Agilent Technologies, Inc.
3380 146th PI SE Suite 300
Bellevue, WA 98007
USA

Abstract

Trace measurements of the element chromium (Cr) are of interest in a wide range of applications and matrices. In the environment, Cr exists in two different oxidation states, the trivalent Cr(III) cation and hexavalent Cr(VI) anion. In mammals, Cr(III) is an essential element involved in the regulation of glucose; however, the element in its hexavalent form demonstrates mutagenic and carcinogenic effects at relatively low levels. Because of this duality, total Cr measurements do not provide sufficient information to establish potential toxicity. In order to assess the potential toxicity of the Cr level in a sample, it is the Cr(VI) concentration that must be measured, rather than the total Cr concentration. A new method was developed to couple Ion Chromatography to Octopole Reaction Cell ICP-MS (inductively coupled plasma mass

spectrometry), to give a simple and reliable method for the separation and measurement of Cr(III) and Cr(VI), and so provide an accurate indication of the toxicity of the Cr level in a sample. This method has the merit of being applicable to high matrix samples, such as hard drinking water, due to the optimization of the sample preparation method and the chromatography. Also, the ICP-MS method provides excellent signal to noise, as a result of the removal of potentially interfering background species in the reaction cell, allowing the accurate determination of toxicologically useful levels of Cr(VI), at concentrations below 0.1 µg/L.

Introduction

The measurement of chromium toxicity is a requirement across a wide range of sample types, including drinking water, foodstuffs, and clinical samples (the latter used primarily to assess occupational exposure). However, it is the hexavalent form of Cr - Cr(VI) that is the toxic form, while the trivalent form - Cr(III) is an essential element for human nutrition. Methods to establish the potential toxicity of Cr must therefore determine the concentration of Cr(VI), rather than simply total Cr.

Two common approaches are used to address the issue: First, if the total Cr level measured is below the toxic level for Cr(VI), then it is reasonable to state that the Cr level will not be toxic, even if all of the Cr is present as Cr(VI). However, this approach can lead to a large number of false positives if samples contain a high concentration of Cr(III), so a more accurate approach is to separate and measure the Cr(VI) itself or, ideally, separate and measure both forms of Cr, giving an indication of the level of total Cr AND the level of toxic



Agilent Technologies

Cr(VI), from a single analysis.

Separating and detecting individual forms or species of elements is usually a straightforward analytical challenge, but Cr is an unusual case in this respect. This is because the common forms of Cr in natural samples such as water are chromate (CrO_4^{2-}) for Cr(VI) and chromic ion (Cr^{3+}) for Cr(III). Chromate is an anion and the chromic ion is cationic, so a single ion exchange method will not work for both forms under the same conditions. A further problem is that Cr(III) is the most stable oxidation state in samples such as water, whereas Cr(VI) ions are strong oxidizing agents and are readily reduced to Cr(III) in the presence of acid or organic matter. Consequently great care must be taken during sample collection, storage and preparation, to ensure that the Cr species distribution present in the original sample is maintained up to the point of analysis.

Experimental

The method described in this application note used an optimized sample stabilization method, in which the samples were incubated at 40 °C with EDTA, which forms a complex with the Cr(III), allowing a single chromatographic method to be used to separate the Cr(III)EDTA complex and the Cr(VI). The reaction to form the Cr(III)EDTA complex is dependent on the incubation time and temperature, with complete conversion occurring after less than 1 hour at 60 °C or 3 hours at 40 °C. Complete conversion did not occur even after 7 hours incubation

at room temperature.

Note that a relatively high concentration of EDTA is required for this method to be applicable to natural water samples, since other ions, such as Ca and Mg, which are commonly present at 10's or 100's mg/L in hard drinking water for example, would compete with the Cr(III) to form EDTA complexes, leading to low and matrix dependent Cr(III) recovery.

The combination of the separation of the Cr species using ion chromatography (IC), together with analysis of the separated species using ICP-MS, offers an ideal analytical method, as it permits the individual Cr species to be separated using a simple, low cost IC configuration. ICP-MS detection also allows the separated Cr species to be measured at extremely low concentrations, providing accurate assessment of exposure levels, even for natural or background Cr concentrations.

ICP-MS has excellent sensitivity and so is a good detector for many trace elements. The introduction of collision/reaction cells (CRC's) for ICP-MS allows Cr to be measured even more accurately and with better sensitivity, using the main isotope at mass 52, with removal of the primary matrix-based interferences ArC and ClOH. The sample preparation method, column type and chromatographic conditions used for Cr speciation are shown in Table 1. Note that, in addition to the stabilization of the samples with Na EDTA, EDTA was also added to the mobile phase, to stabilize the Cr(III) complex during separation. In addition, it was found that the use of pH 7 was essential for species stabilization and

Table 1. Chromatographic Conditions for Cr Speciation

Cr column	Agilent part number G3268A, 30 mm × 4.6-mm id
Mobile phase	5 mM EDTA (2Na), pH 7 adjust by NaOH
Flow rate	1.2 mL/min
Column temperature	Ambient
Injection volume	50–500 µL
Sample preparation	
Reaction temperature	40 °C
Incubation time	3 h
EDTA concentration	5–15 mM pH 7 adjust by NaOH

optimum chromatographic separation.

The IC configuration used for the work presented in this note is illustrated in Figure 1. Note that the nonmetal IC pump (Metrohm 818 IC Pump) was used to deliver the mobile phase, but the sample loop was filled and switched using the optional Integrated Sample Introduction System (ISIS) of the Agilent 7500ce ICP-MS. While this configuration maintains the high precision and relatively high pressure of the IC pump, it provides a much simpler and lower-cost alternative to a complete IC or HPLC system,




Figure 1. IC-ICP-MS configuration used for Cr speciation.

since only the IC pump module is required in addition to the ICP-MS system.

Results and Discussion

Under the conditions described above, with ICP-MS detection using the Agilent 7500ce in H_2 cell gas mode to remove the ArC and ClOH interferences on Cr at mass 52, detection limits (DLs) of <20 ng/L were obtained for the individual Cr species, as shown in Table 2. Many international regulations for hexavalent Cr specify a maximum allowable concentration of 1 $\mu\text{g/L}$, with a required DL of one-tenth of this level (100 ng/L), and even the small sample volume injection of 100 μL easily meets these

Table 2. DLs for Cr Species by IC-ICP-MS

Inject/ μ L	RT/min		Peak height/counts		Peak area/counts		DL (ng/L)*	
	Cr(III)	Cr(VI)	Cr(III)	Cr(VI)	Cr(III)	Cr(VI)	Cr(III)	Cr(VI)
50	0.79	2.09	8548	4261	1082295	914804	69.5	139.4
100	0.79	2.09	13688	7173	1704312	1525147	43.4	82.8
250	0.85	2.21	33967	20830	4939876	4546219	17.5	28.5
500	0.97	2.39	44870	37502	10268086	9398651	13.2	15.8

*Detection limits calculated as three times the peak-to-peak signal-to-noise as measured on standard chromatograms.

requirements. However, increasing the injection volume to 500 μ L allowed the DLs to be reduced to 13.2 ng/L for Cr(III) and 15.8 ng/L for Cr(VI).

For a simple standard solution, these conditions give an excellent signal to noise for both Cr species, as illustrated in Figure 2. This chromatogram shows the separation of the two Cr species each at a concentration of 0.1 μ g/L (ppb), using an injection




Figure 2. Separation and detection of Cr(III) and Cr(VI) at a concentration of 0.1 μ g/L each species.

volume of 500 μ L. Clearly the peaks are easily detected above the background and the baseline separation of the two species in a total time of about 3 minutes is also illustrated.

Using a series of synthetic standard solutions at low concentrations, a calibration was created for each of the two Cr species. Quantification was based on




Figure 3. Calibration for Cr(III) - Standard concentrations 0.05, 0.1, 0.5 and 1.0 μ g/L.




Figure 4. Calibration for Cr(VI) - Standard concentrations 0.05, 0.1, 0.5 and 1.0 μ g/L.

peak area. The calibrations obtained for Cr(III) and Cr(VI) are illustrated in Figures 3 and 4, respectively, each showing excellent sensitivity and linearity.

In addition to sensitivity, species stability, chromatographic separation and calibration linearity, for the method to be suitable for routine analysis, it is essential that it provides acceptable long-term stability. In chromatographic analysis, stability is governed by two factors, RT stability and peak area stability. The data in Table 3 illustrates both of these parameters and indicates that the stability of the method is certainly acceptable for routine operation.

Routine Analysis

Of more interest for the routine analysis of chromium species (or specifically hexavalent Cr) in natural water samples is the maintenance of this excellent sensitivity, stability and chromatographic separation in samples that contain a high concentration of other ions. In order to test the suitability of the method for these real-world sample types, the method was applied to the determination of both Cr species in both spiked and unspiked mineral water samples.

The first sample evaluated was a leading French mineral water referred to in this study as mineral water A. Figure 5 shows the chromatogram of the two Cr species in the unspiked and spiked samples of mineral water A. The major element composition of the water is also shown in the table inset in Figure 5, indicating the typical drinking water com-

Table 3. Stability of RT and Peak Area for Multiple 500 μ L Injections of 0.5 μ g/L Each Cr Species

Number	RT/min		Peak height/counts		Peak area/counts	
	Cr(III)-EDTA	Cr(VI)	Cr(III)-EDTA	Cr(VI)	Cr(III)-EDTA	Cr(VI)
1	0.969	2.338	23514	18437	5331427	4621752
2	0.969	2.338	22642	18784	5280683	4758462
3	0.969	2.338	22832	18615	5220349	4742259
4	0.952	2.338	24104	19944	5470760	4800723
5	0.969	2.372	22797	19203	5287094	4726640
6	0.969	2.405	23830	19328	5498172	4760285
7	0.985	2.338	23971	19479	5481984	4824934
8	0.969	2.338	23393	19675	5474510	4883193
9	0.969	2.355	23070	20097	5355106	4892160
10	0.969	2.372	23826	19896	5428247	4886400
Avg	0.97	2.38	23398	19346	5382833	4789681
STD	0.008	0.014	534.45	581.88	100413.18	85782.42
RSD%	0.80	0.57	2.28	3.01	1.87	1.79




Figure 5. Major element composition (mg/L) and chromatogram for spiked and unspiked mineral water A.

position of about 100 mg/L Ca and between 5 mg/L and 20 mg/L of the other major elements K, Mg and Na.

The spike recovery data for mineral water A is shown in Table 4, indicating the very low level at which the Cr species were quantified (0.005 µg/L

Table 4. Spike Recovery Data for 0.1 µg/L Spikes of Cr(III) and Cr(VI) in Mineral Water A

Element	Original mineral water A	Found (µg/L)		Recovery (%)
		Spike added	Spike found	
Cr(III)	0.005	0.10	0.105	100.0
Cr(VI)	0.055	0.10	0.150	95.0

and 0.055 µg/L for Cr(III) and Cr(VI), respectively), and the excellent spike recovery accuracy for the low concentration spikes in this sample - better than 5% error in both cases.

The second mineral water sample analyzed was another French mineral water, referred to as mineral water B, which has among the highest levels of calcium and sulfates of any commonly available mineral water (over 450 mg/L Ca and more than 1000 mg/L sulfates). As for the mineral water A sample, mineral water B was analyzed with and




Figure 6. Major element composition (mg/L) and chromatogram for spiked and unspiked mineral water B.

without a spike of the two Cr species and the spike recovery was assessed. The results for the measured chromatograms are shown in Figure 6, while the spike recovery data are shown in Table 5.

As shown for the mineral sample A, the major element composition of the mineral water is shown as an inset in the chromatogram, illustrating the very high mineral levels in mineral water B. Despite these high major element levels, the optimized sample preparation and chromatographic method gave good chromatographic separation and excellent spike recovery results for both Cr species. A higher spike level was used for mineral water B, due to the higher baseline (unspiked) concentration for the Cr species in this sample.

The ability to recover low concentration spikes for both Cr species in such a high matrix sample indicates the effectiveness of the optimized method for sample stabilization, which ensures that a high enough concentration of EDTA is available for complete complexation of the Cr(III) species, even in the presence of a high level of competing ions.

Furthermore the accurate recovery of low concentration spikes of both species indicates that potential problems of species interconversion (reduction of Cr(VI) to Cr(III)) was avoided through the selection of an appropriate pH for the samples and the

mobile phase, together with the use of EDTA in the mobile phase as well as for sample stabilization. See Table 5.

Conclusions

A new method for the stabilization and analysis of Cr(III) and Cr(IV) in natural, high matrix water samples was developed and optimized with DLs in the region of 0.05 µg/L for 100-µL injections, or 0.015 µg/L for larger, 500-µL injections.

Reliable and stable separation of the Cr(III) and Cr(VI) species was achieved in a method taking approximately 3 minutes per sample and the separation and accurate quantification of the two species could be maintained even in the presence of a high concentration of competing ions, such as >500 mg/L mineral elements in the highly mineralized water.

Accurate and interference-free determination of Cr at the low concentrations (0.1 µg/L) required by international regulations was made possible by the simple and consistent operation of the Agilent 7500ce in reaction mode, using H₂ as a cell gas. This mode of operation does not preclude the simultaneous analysis of other analytes of interest, such as As, in contrast to the use of highly reactive cell gases such as CH₄ or NH₃.

Table 5. Spike Recovery Data for 1.0 µg/L Spikes of Cr(III) and Cr(VI) in a Highly Mineralized Water (B)

Element	Original mineral water B	Found (µg/L)		
		Spike added	Spike found	Recovery (%)
Cr(III)	0.05	1.0	1.10	105
Cr(VI)	0.24	1.0	1.27	102

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
April 27, 2005
5989-2481EN



Agilent Technologies



A Comparison of the Relative Cost and Productivity of Traditional Metals Analysis Techniques Versus ICP-MS in High Throughput Commercial Laboratories

Application

Author

Steve Wilbur
Agilent Technologies, Inc.
3380 146th Pl SE Suite 300
Bellevue, WA 98007 USA

Abstract

A financial model was developed to help the metals laboratory using graphite furnace atomic absorption and inductively coupled plasma optical emission spectroscopy calculate the potential savings by switching to inductively coupled plasma mass spectrometry. Results based on several typical laboratory examples are presented.

Introduction

The past 5 years have seen significant growth in the use of inductively coupled plasma mass spectrometry (ICP-MS) for the analysis of trace metals in many applications in the environmental, semiconductor, geological, and health sciences industries. This growth is driven by three factors. First is the need for increasingly lower limits of detection for many metals in many applications. Second is the significantly improved performance, reliability, and ease of use of modern ICP-MS instruments. And third is economics.

Traditionally, most elemental analysis has been performed by either atomic absorption (AA) or optical emission spectroscopy (OES). Generally, the ultratrace (sub-ppb) elements were measured by graphite furnace atomic absorption (GFAA), a highly sensitive single-element technique. The trace and minor (ppb to ppm) elements were measured

by inductively coupled plasma optical emission spectroscopy (ICP-OES), which is less sensitive but capable of simultaneous multi-element analysis.

As the need for sub-ppb detection limits extends to more elements in more samples, ICP-OES becomes less useful and the reliance on GFAA increases. However, GFAA, while sensitive, is slow, expensive to operate, and has limited dynamic range. Because GFAA is much slower than ICP-OES, many routine labs have a dedicated GFAA instrument for each analyte that is required to be measured by GFAA - multiple GFAAs working with one ICP-OES. Furthermore, the analysis of mercury will add the need for a third technique, either cold vapor AA or atomic fluorescence. However, in the interest of simplicity, a separate mercury analyzer was not considered in the examples used. Each of these techniques may require separate sample handling and preparation, as well as separate analysis, data processing and archival, significantly increasing the cost per sample.

The subject of this application note is to evaluate the productivity and cost effectiveness of ICP-MS as a routine, highly sensitive, multi-element technique where a single ICP-MS instrument has the potential to replace an ICP-OES, multiple GFAAs, and a mercury analyzer for most routine elemental analyses. The analytical applicability of ICP-MS to many types of samples is already well established. More recently, the introduction of the Octopole Reaction System on the 7500 Series ICP-MS instruments from Agilent has removed the final performance barriers that have prevented ICP-MS being proposed as a complete replacement for GFAA and ICP-OES.



Agilent Technologies

Methods

To facilitate this study, a spreadsheet-based sample cost comparison model was developed in Excel. This tool allows the user to provide detailed parameters related to numbers and types of samples, as well as associated costs of sample preparation, instrumentation, and analysis. Output is simply cost of analysis per sample. Also reported are the total time required for sample analysis per month, the number of analysts required, and the number of instruments. The model compares the results for GFAA, ICP-OES, and ICP-MS. While it will allow almost any values to be entered for most parameters, the results presented here are based on values obtained from several commercial laboratories doing these analyses. No model can exactly predict the results for all situations and still be simple enough to be useful. Therefore, in the interest of simplicity, a number of assumptions were made in the design of the model and in the example data entered. We feel that the assumptions are realistic and do not impart significant bias on the results. The tool is easy to use and can allow a laboratory to quickly and simply evaluate the cost effectiveness of the three techniques based on laboratory-specific information.

Assumptions

- GFAA system costs US\$30K
- ICP-OES system costs US\$100K
- ICP-MS system costs US\$180K
- Cost of funds (finance) is 6%
- General facilities costs, such as laboratory space, utilities etc., are ignored since they are difficult to estimate and do not significantly affect the results in most cases.

- An instrument operator can keep a modern, automated GFAA, ICP-OES, or ICP-MS running for two shifts (16 hours) per day. When analysis times exceed 16 hours per day for any technique, additional instrumentation and operators will be required. Instruments are added in increments of one; operators are added in fractions since it is assumed that they can be shared with other tasks in the laboratory and cost calculations are based only on the portion of time the operator spends on the specific analysis.
- GFAA is a single element technique. Instruments with multiple lamps still perform a single analysis at a time. Typical analysis time is 90 seconds per element and each element requires two replicate analyses (burns).
- ICP-OES and ICP-MS are multi-element techniques and the number of elements does not significantly effect the analysis time. This is not strictly true, but the assumption is reasonable for the sake of simplicity.
- GFAA will use pressurized argon and the consumption is 40 hours of use per cylinder (\$100).
- GFAA graphite tubes and platforms cost \$50 per set and last for 100 burns.
- ICP-MS and ICP-OES will use liquid argon and the typical consumption is 3 weeks of use per dewar (\$250).
- ICP-MS detectors last typically for 3 years and the cost per year is amortized based on 3-year lifetime.

Results

Several typical laboratory scenarios were evaluated by varying the current instrument complement of the laboratory, and by varying the current and anticipated number of samples to be analyzed per month. Also examined was the effect of the number of elements that must be analyzed by GFAA (in the case of laboratories without ICP-MS) to meet required DLs.

Scenario 1

Laboratory currently has one GFAA plus one ICP-OES, which are paid for. ICP-MS must be purchased and amortized over 3 years. See Table 1.

Table 1. Scenario 1

Samples/ month	GFAA elements	# GFAA required	Cost/sample GFAA + ICP-OES	# ICP-MS required	Cost/ sample ICP-MS	Savings/ month
400	8	1	\$41	1	\$30	\$4,536
1000	8	2	\$33	1	\$15	\$18,196
5000	8	9	\$31	2	\$9	\$112,968

Scenario 2

Laboratory currently has two GFAA plus one ICP-OES, which are paid for. ICP-MS must be purchased and amortized over 3 years. See Table 2.

Table 2. Scenario 2

Samples/ month	GFAA elements	# GFAA required	Cost/sample GFAA + ICP-OES	# ICP-MS required	Cost/ sample ICP-MS	Savings/ month
400	8	1	\$41	1	\$30	\$4,536
1000	8	2	\$32	1	\$15	\$17,283
5000	8	9	\$31	2	\$9	\$112,055

Scenario 3

Laboratory currently has no instrumentation and must decide on purchasing GFAA plus ICP-OES versus ICP-MS. See Table 3.

Table 3. Scenario 3

Samples/ month	GFAA elements	# GFAA required	Cost/sample GFAA + ICP-OES	# ICP-MS required	Cost/ sample ICP-MS	Savings/ month
400	8	1	\$51	1	\$30	\$8,491
1000	8	2	\$37	1	\$15	\$22,151
5000	8	9	\$32	2	\$9	\$116,923

Scenario 4

Comparison of costs per sample as a function of number of GFAA elements. (All instruments must be purchased.) See Table 4.

Table 4. Scenario 4

Samples/ month	GFAA elements	# GFAA required	Cost/sample GFAA + ICP-OES	# ICP-MS required	Cost/ sample ICP-MS	Savings/ month
1000	2	1	\$24	1	\$14	\$9,601
1000	4	1	\$28	1	\$14	\$12,751
1000	8	2	\$38	1	\$14	\$22,151
1000	10	3	\$42	1	\$14	\$27,490

Discussion

In all cases, even when the laboratory already owns two graphite furnaces and one ICP-OES (a common configuration) and must purchase the ICP-MS, the cost per sample is lower for ICP-MS. This is mainly due to the high cost of consumables for GFAA plus the fact that GFAA and ICP-OES requires two separate sample prep steps. Additionally, as the number of samples increases from a conservative number of 400 per month to 1000 and 5000 per month, the differential becomes much greater. This is caused by rapidly increasing labor costs for GFAA, as well as the much higher sample capacity of ICP-MS, lower consumables costs, and requirements for only a single sample prep.

Return on Investment for ICP-MS

A simple return on investment (ROI) can be calculated from the above tables. In this case, the cost per month of the new ICP-MS system is approximately US \$5500.00 (assuming purchase price of US\$180K financed for 3 years at 6%). Figure 1 shows the payback times for a laboratory that already owns two GFAAs and one ICP-OES as a function of the sample load. The y-axis represents the accumulated monthly savings of using ICP-MS versus GFAA + ICP-OES for three different sample loads compared to the unpaid balance on the ICP-MS instrument. As can be seen, the accumulated savings of ICP-MS is equal to the payoff amount after just 4 months when analyzing 2000 samples per month. Even when analyzing as few as 400 samples per month, the accumulated savings is sufficient to pay off the ICP-MS instrument in around 20 months. In this case, eight furnace elements are assumed. Other assumptions are as above.




Figure 1. Cumulative return on investment of ICP-MS purchase for three sample levels plotted against the monthly unpaid balance on the ICP-MS. In this case, it is assumed that the accumulated revenue will be used to pay off the loan when the balance equals the residual loan amount. At that point, the net monthly revenue is increased by the loan amount. In this example, laboratories running 2000 samples per month will be able to pay off the ICP-MS in about 4 months, 1000 sample laboratories in about 8 months, and 400 sample laboratories in about 20 months. At the end of 36 months (the original loan period), net revenue exceeds \$200K for the 400 sample lab, \$750K for the 1000 sample lab, and \$1.7 million for the 2000 sample lab.

Conclusions

For almost any metals laboratory, analyzing at least 100 samples per week (400 per month) and using a combination of GFAA and ICP-OES for the analysis, converting to ICP-MS will save money. Depending on the number of samples, the payback for the ICP-MS can be as short as a few months. The cost advantages are not reduced significantly, even if the laboratory already owns its GFAA and ICP-OES instruments. They are also not significantly affected by the number of GFAA elements. As Scenario 4 shows, for the laboratory analyzing at least 1000 samples per month with only two elements by GFAA, the cost savings of switching to ICP-MS is approximately \$10,000 per month. Add to this the increased confidence in results obtained by ICP-MS, the ability to analyze all analyte elements at GFAA (or better) DLs, and the robustness and simplicity of operation of modern ICP-MS instruments, and the choice becomes simple. The productivity of ICP-MS in a high-volume laboratory can quickly pay off the purchase price and increase laboratory profitability significantly.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
January 17, 2005
5989-1585EN



Agilent Technologies



Fast and Accurate Determination of Arsenobetaine (AsB) in Fish Tissues Using HPLC-ICP-MS

Application

Foods

Author

Raimund Wahlen
LGC Limited, Queens Road, Teddington,
Middlesex, TW11 0LY, United Kingdom

Abstract

A high performance liquid chromatography-inductively coupled plasma mass spectrometry method was developed for the fast and accurate analysis of arsenobetaine in fish samples extracted by accelerated solvent extraction. The combined extraction and analysis approach was validated using certified reference materials for arsenobetaine in fish and during a European intercomparison exercise with a blind sample. Up to six species of arsenic can be separated and quantified in the extracts within a 10-min isocratic elution. The method was optimized so as to minimize time-consuming sample preparation steps and to allow for automated extraction and analysis of large sample batches. A comparison of standard addition and external calibration showed no significant difference in the results obtained, which indicates that the liquid chromatography-inductively coupled plasma mass spectrometry method is not influenced by severe matrix effects. The extraction procedure could process up to 24 samples in an automated manner while the robustness of the developed high performance liquid chromatography-inductively coupled plasma mass spectrometry approach is highlighted by the capability to run more than 50 injections per sequence which equates to a total run-time of more than 12 hours. The method can therefore be used to rapidly and accurately assess the proportion of nontoxic arsenobetaine in fish samples with high total arsenic content during toxicological screening studies.

Introduction

The element Arsenic (As) has long been thought of as poisonous and highly toxic. However, it has since been shown that the toxicity of As is largely dependent on the form or “species” the arsenic is in. Arsenic is ubiquitous in the environment due to natural and anthropogenic sources, and the relative contribution of these factors is estimated as roughly 60% and 40% respectively. In the environment, As behaves in similar ways to the Group V elements nitrogen (N) and phosphorus (P). As a result of these similarities, arsenic gets taken into the biochemical pathways of N and P. This results in the formation of compounds such as arsenobetaine (AsB) in fish and arsenic-sugars, which are found in marine algae. The toxicity of the inorganic As-species (such as arsenite, As(III) and arsenate, As(V)) is far greater than the organic forms, such as monomethylarsonic and dimethylarsinic acid (MMAA and DMA) and AsB. The International Agency for Research on Cancer (IARC) has classified inorganic arsenic as a human carcinogen, whereas AsB, the predominant form of As in most marine organisms [1], is considered nontoxic to humans. Although AsB is the major form of As in many marine organisms, it is not present in all fish species [2]; therefore, an evaluation of the proportion of AsB to the total As determined can give a useful and rapid estimate of the toxicological significance of a sample. In order to determine the toxicity of seafood, the determination of the total As alone is of limited value, and the different species of As have to be extracted, separated, and determined. Fast, reliable, and practical methods are therefore required that can provide speciation information for the screening of large sample batches.



Agilent Technologies

Aims and Objectives

The aim of this study was to develop a semi-automated analytical method for the extraction and determination of As-species in fish tissues. Requirements for high sample throughput analysis were the automation of the extraction procedure as well as a fully automated separation and detection method capable of analyzing large sample batches (up to 50 injections per run) during overnight runs. In order to streamline the analytical procedure, an attempt was made to develop a method with a minimal number of sample preparation steps. It was intended that the method should be established using calibration by external calibration curves, rather than the lengthy alternative of standard additions. The use of an isocratic liquid chromatography (LC) elution can be favorable in terms of time-efficiency during the liquid chromatography-inductively coupled plasma mass spectrometry (LC-ICP-MS) analysis because it negates the need for column re-equilibration between injections.

Calibration Standards

The following standards were obtained from Fluka (Sigma-Aldrich, Gillingham, UK): di-sodium hydrogen arsenate heptahydrate ($\text{AsHNa}_2\text{O}_4 \cdot 7\text{H}_2\text{O}$) $\geq 98.5\%$, sodium (meta)arsenite (AsNaO_2) $\geq 99.0\%$, and cacodylic acid (dimethylarsinic acid, DMA, $\text{C}_2\text{H}_2\text{AsO}_2$) $\geq 99.0\%$; monomethylarsonic acid disodium salt (MMAA, $\text{CH}_3\text{AsNa}_2\text{O}_3$) $> 98\%$ was obtained from Argus Chemicals (Vernio, Italy). Arsenobetaine (AsB , $\text{C}_5\text{H}_{11}\text{AsO}_2$) was obtained from BCR (Brussels, Belgium) as a solution of AsB in water at 1031 ± 6 (95% C.I.) mg/kg (BCR 626).

Extraction

Accelerated solvent extraction (ASE) has been used previously for As-speciation [3, 4] and was chosen as the sample preparation method because it allows for the automated extraction and online filtration of up to 24 samples. In addition, the extraction solution is collected in glass vials, which negates further sample preparation steps such as filtration or centrifuging.

The samples were extracted using a Dionex ASE 200 accelerated solvent extractor. Sample sizes from 0.1–0.3 g were weighed accurately into 11-mL stainless steel extraction cells fitted with filter papers and PTFE liners. The extraction program was set up as shown in Table 1.

Table 1. Extraction Conditions Used for ASE

Instrument	Dionex ASE 200
Preheat	2 min
Heat	5 min
Extraction steps	5×2 min
Temperature	100 °C
Pressure	1500 psi
Solvent	Methanol

HPLC-ICP-MS Methodology

The HPLC-ICP-MS instrumentation consisted of an Agilent Technologies 1100 HPLC system coupled to an Agilent Technologies 7500i ICP-MS fitted with a second roughing pump, which enhances sensitivity by increasing ion transmission across the interface. The HPLC system comprised a quaternary pump module, a vacuum degasser, a temperature controlled autosampler, and column compartment. The ICP-MS instrument was tuned for sensitivity, reduced oxides, and doubly charged species prior to connection to the liquid chromatograph by performing a standard instrument tune using a 10 ng/g solution of Li, Y, Ce, and Th in 1% HNO_3 . The pulse to analog (P/A) factor was adjusted on a daily basis using a solution containing ~50 ng/g Li, Mg, Mn, Cu, As, Gd, Y, Cd, Pb, and Ba. After this optimization, a 50 ng/g solution of As in 1% HNO_3 was used to specifically optimize the sensitivity for arsenic. The ICP-MS nebulizer was then connected to the HPLC-column using a length of PEEK tubing (yellow, 1/16-inch od, 0.007-inch id). See Table 2 for the ICP-MS conditions used.

Table 2. ICP-MS Conditions Used for HPLC-ICP-MS Determination of As-Species

RF Power	1430–1550 W
RF Matching	1.89–1.92 V
Sampling depth	4.0–4.8 mm
Carrier gas flow	0.89–0.93 L/ min
Make up gas flow	0.10–0.14 L/ min
Optional gas	Oxygen at 5%
Spray-chamber temperature	0 °C
Cones	Platinum
Isotopes monitored	^{75}As ^{103}Rh ^{77}Se ($^{40}\text{Ar}^{37}\text{Cl}$) to monitor Cl interferences ^{53}Cr ($^{40}\text{Ar}^{13}\text{C}$) to monitor C interferences
Other parameters	Injector diameter: 2.4 mm Nebulizer 100 $\mu\text{L}/\text{min}$ PFA, Two interface pumps used

In order to develop a rapid chromatographic separation of the main As-species in fish tissues, an anion exchange column (Hamilton PRP X-100) was chosen in combination with an isocratic elution profile. Several mobile phases were tested and the best separation of AsB and As(III) as well as DMA and MMAA was achieved within 10 min using 2.2-mM NH_4HCO_3 /2.5-mM tartaric acid at pH 8.2 delivered at 1 mL/min isocratic flow. This evaluation was carried out initially using matrix-free calibration standards containing the species of interest and refined using an oyster tissue extract that contained arsenocholine (AsC), two arsenosugars (As-sug. B and As-sug. D), TMAAs^+ and several unknown species in addition [5]. The injection volume for samples and standards was 50 μL .

In order to enhance the ionization of the As-species [6, 7], methanol was added to the mobile phase at concentrations ranging from 0.5% to 5% v/v. At concentrations above 1%, the chromatographic separation degraded significantly to the degree that base-line resolution between AsB and As(III) was no longer achieved. However, the addition of 1% MeOH to the mobile phase resulted in a significant improvement in the sensitivity (3–4-fold increase in peak height) for all analytes. A chromatogram for a 5-ng/g mixed calibration standard with the final chromatography conditions is shown in Figure 1.

Variations in Signal Response for Different As-Species

The chromatogram shows that the four species analyzed here have very different response factors with this method, even when made up to contain the same concentration of As in solution. This is further illustrated by the calibration curves and their respective slopes, as shown in Figure 2. Such differences in the analyte signal intensity were reported previously in the literature [7] and appear to be due to a combination of the ICP-MS hardware used and the plasma conditions, which are in turn affected by the mobile phase composition. This points to possible differences in the nebulization, transport and/or ionization of different species by such methods. In order to determine whether this effect could be attributed to the coupling of the ICP-MS with a liquid chromatograph, aqueous standards of AsB and As(III) were made up to equivalent concentrations as As and analyzed by direct aspiration without chromatography. This indicated that the signal response of AsB was ~10%–15% higher compared to the inorganic As standard and, therefore, the difference in signal response does not appear to be related to the coupling with a liquid chromatograph.




Figure 1. Chromatography A: 2.2-mM NH_4HCO_3 , 2.5-mM tartaric acid, 1% MeOH, pH 8.2, Hamilton PRP X-100 column. Concentration of standard ~ 5 ng/g as As.




Figure 2. Calibration curves for AsB, DMA, MMAA and As(III) over a range of 0–50 ng/g as As.

In order to increase the signal intensity for species such as As(III) and MMAA by the approach described here, additional MeOH was added via a T-piece post-column so as not to impact on the chromatographic resolution. Although the relative volume of MeOH could be increased by 50%–70% in this way without deteriorating plasma stability, the relative signal responses of the four species were not influenced significantly. Because the relative signal response was stable on a day-to-day basis, no further attempts were made to equalize the signal responses.

The instrumental detection limit for AsB by this method was 0.04 ng/g as As. The linearity obtained, as indicated by the correlation coefficient of the calibration line, was 0.999–1.000 over a calibration range of 0–700 ng/g as As.

Plasma Disturbance Due to Elution of MeOH

During the analysis of fish samples, which had been extracted under the ASE conditions highlighted in Table 1, a disturbance of the plasma was observed between ~2.3 to 4.3 min after injection. This affected all of the isotopes monitored and the effect on ^{75}As and ^{103}Rh is highlighted in Figure 3. As can be seen from the chromatogram, the effect on these two isotopes is nonlinear. The ^{103}Rh signal decreases significantly during this time, whereas the ‘shoulder’ on the tailing side of the AsB peak indicates an increase in the ^{75}As signal.




Figure 3. Signals for ^{103}Rh and ^{75}As in an undiluted fish extract. Notice the increase in the ^{75}As signal at the tailing side of the major peak (AsB) coinciding with the decrease in the ^{103}Rh signal.

The observed fluctuation in the signal intensities for the different isotopes coincides with the elution of the organic methanol fraction of the fish extracts from the analytical column. This effect could be reduced slightly by lowering the temperature of the spray-chamber from 5 °C to 0 °C, but the effect was not completely eliminated. During the injection of undiluted sample extracts, the volume of methanol that passes through the column and into the ICP-MS is ~10%. It has already been discussed that the addition of MeOH enhances the ^{75}As signal by increasing the ionization efficiency of this analyte; this effect is observed on a small scale here. Although there is no detectable As(III) in this fish material, the accurate quantitation of this compound (compared to aqueous calibration standards) could obviously lead to an overestimation if the signal of this analyte is enhanced due to the simultaneous elution of MeOH from the column. In this case, a standard addition calibration would represent a more accurate approach for quantitation. However, the spiking of each sample extract at different levels, which is necessary for this type of calibration, would make such an approach less suitable for a high sample-throughput application. In addition, the accurate integration of AsB is influenced by the signal increase on the tailing side of the peak.

In order to eliminate the effect of these signal variations on the accurate quantitation of the As-species in the methanolic extracts, the methanol fraction could either be reduced by evaporation or dilution with water. Dilution was chosen as the preferred option over evaporation in order to avoid possible analyte losses and because of time-efficiency. Whereas evaporation would either involve passing an inert gas over the solution or using rotary evaporation equipment, gravimetric dilutions were easily and quickly achieved by pipetting an aliquot of the extract into a sealed HPLC autosampler vial, weighing, and then adding the appropriate amount of water. In order to observe the effect of different dilution factors on the observed plasma disturbance, a fish extract was diluted 10-, 5-, and 2-fold in water and also injected undiluted. The effects of the different dilutions on the ^{103}Rh signal are shown by the chromatograms in Figure 4.

As demonstrated in Figure 4, a 10-fold dilution is sufficient to eliminate the plasma disturbance sufficiently; therefore, all extracts were diluted 1:10 in water prior to injection.




Figure 4. Signal of the internal standard ^{103}Rh , for fish sample extracts a) undiluted and diluted b) 2-fold, c) 5-fold and d) 10-fold.

Comparison of External Calibration and Standard Addition for the Quantitation of AsB in Fish Tissues

Due to the fact that arsenic is mono-isotopic, isotope dilution analysis cannot be used for the high-accuracy quantitation of this compound by LC-ICP-MS. In such circumstances, calibration by standard additions is often used in order to achieve matrix matching of standards and samples. It is also a useful technique in chromatographic applications where the possibility of retention time (RT) shifts of analytes due to matrix components exists. This can result in misidentification, and thus erroneous results. However, standard addition calibration can be very time-consuming because several aliquots of the sample require spiking with different levels of a calibration standard, and at least three levels of standard addition are needed for accurate quantitation of the same sample. External calibration by non-matrix matched standards can be used for applications where the difference in the matrix between samples and standards does not influence the accuracy of the result to a significant extent.

Standard addition calibration and non-matrix matched external calibration were compared for AsB in two certified reference materials (DORM-2, Dogfish muscle, NRC Canada and BCR 627, Tuna Fish, BCR EU) in order to assess whether the

calibration technique used significantly influenced the accuracy or precision of the analytical result. The results showed that there was no significant difference in the mean results determined by the different calibration techniques with this method. The mean results for repeat analysis of both materials showed that the difference in the DORM-2 material was less than 1.4% and less than 4.5% for the BCR 627 material. When taking into account the standard deviations (SD) associated with the mean result obtained by each calibration technique, there was no statistically significant difference between the AsB results obtained by either approach in either of the fish tissue certified reference materials (CRMs).

Results of CRM Analysis

In order to test the accuracy of the developed ASE extraction and HPLC-ICP-MS method, a variety of certified and candidate reference materials of marine origin were extracted and analyzed. The samples included the certified fish reference materials DORM-2 and BCR 627, as well as an oyster tissue material (BCR 710)*, which is pending certification.

* The "MULSPOT" project has been financed by the SM&T Program (EU) (Contract SMT4-CT98-2232) and coordinated by ENEA (IT). The Project is at the certification stage and the material is not yet available on the market.

Table 3. Data Obtained for AsB in Two CRMs and a Candidate Reference Material

Expressed as mg/kg As unless otherwise stated	Measured value	Certified value
DORM-2 (Dogfish muscle)	16.3 ±0.9 (±1 SD)	16.4 ±1.1 (±95% C.I.)
BCR 627 (Tuna fish)	3.69 ±0.21 (±1 SD)	3.90 ±0.22 (±95% C.I.)
BCR 710 (Oyster tissue) [†] (Concentration as species)	31.8 ±1.1 (±1 SD)	32.7 ±5.1 (±1 SD)

[†] The data shown for this material is based on the consensus mean of the final certification round after the removal of statistical outliers.

Subsamples of the different materials (n = 4–6) were extracted, diluted in water, and analyzed as described above. The data for AsB determined in these samples is shown in Table 3. A chromatogram of the tuna fish material BCR 627 is shown in Figure 5.

The chromatogram indicates that the major species in this sample is AsB with two minor species, which were also extracted and detected. One peak was identified as DMA, and the peak labelled P1 is most likely to be AsC from RT matching. The data in Table 3 shows that the combined ASE/HPLC-ICP-MS methodology is capable of delivering accurate and reproducible results for AsB in these matrices. In addition, the extraction of other minor species, such as DMA and AsC, was achieved in the fish tissues; up to six species were extracted and separated in the oyster material, although none of these (apart from DMA) were quantified during this study. This DMA data for BCR 710 (730 ±30 ng/g DMA) showed a good agreement with the consensus mean value of the certification round (820 ±200 ng/g DMA).

Evaluation of Method Performance During a CRM Feasibility Study

The method performance was assessed in comparison to a number of European expert laboratories during the “SEAS” feasibility study organized by the The University of Plymouth Enterprise Limited and sponsored by the European Union (BCR, EU)[‡]. A fish material was prepared for this intercomparison by the University of Plymouth and distributed to participating laboratories. Participants were asked to determine AsB in a fish material from two different bottles using a methodology of their choice and making their determinations, at least, in duplicate on separate days.

The developed As-speciation method was used to extract and analyze the fish samples provided. A total of 12 subsamples from the two bottles were

[‡]The “SEAS” feasibility study was co-ordinated by The University of Plymouth Enterprise Limited (Plymouth, UK) under the EC contract: G6RD CT2001 00473 “SEAS” with the title: ‘Feasibility Studies for Speciated CRMs For Arsenic in Chicken, Rice, Fish and Soil and Selenium in Yeast and Cereal’.




Figure 5. Chromatogram of a tuna fish extract (BCR 627) enlarged to show the detection of minor species in this material.

extracted and analyzed on 3 different days. The data were combined to provide the value labelled “LGC” in Figure 6 below. The error bars indicate the SD of the mean of individual results. The mean of all result (excluding a statistical outlier) together with 1 SD above and below the mean is indicated by the solid and dashed horizontal lines, respectively. The data provided by the combined ASE extraction and developed LC-ICP-MS methodology (94.92 ± 3.95 mg/kg AsB) is in very good agreement with the mean result of all labs (95.72 ± 7.79 mg/kg AsB, $n = 11$). The precision achieved was also satisfactory at 4.2% (RSD) for 12 subsamples from different bottles analyzed on 3 separate days. The performance of the method in this international intercomparison is highlighted by the good agreement with data provided by several European expert laboratories with longstanding expertise in As-speciation analysis. It should also be noted that the intercomparison was carried out with a blind sample of unknown concentration, rather than based on the analysis of a CRM with known certified values.

Conclusions

A robust and practical method has been developed based on accelerated solvent extraction and HPLC-ICP-MS analysis for the fast and accurate determination of AsB in fish samples. The benefits of the methods include automated extraction of up to 24 samples, minimal sample preparation steps (dilution only) after extraction, and rapid and automated analysis by HPLC-ICP-MS. The separation of four to six species of toxicological interest is achieved within 10 min using an isocratic elution. This increases the sample throughput by negating the column equilibration period needed with most gradient elution profiles.

The method was validated using commercially available CRMs and during a European intercomparison study with a fish sample of unknown concentration. The performance of the method was very satisfactory in terms of both accuracy and precision compared to several other expert laboratories.

This method can be used to rapidly determine the nontoxic proportion (AsB) in fish samples with high total As content and could therefore be used to determine whether a particular sample poses a toxicological risk in the food chain.




Figure 6. Comparison of data submitted by 12 participants for the determination of AsB in fish during the “SEAS” feasibility study. The error bars associated with the individual data points represent 1 SD of analysis of separate subsamples.

Acknowledgements

The work described in this application note was supported under contract with the Department of Trade and Industry (UK) as part of the National Measurement System Valid Analytical Measurement (VAM) program.

References

1. S. Branch, L. Ebdon, and P. O'Neill (1994) *J. Anal. At. Spectrom.*, **9**, 33-37.
2. J. S. Edmonds, Y. Shibata, K. A. Francesconi, R.J. Rippingale, and M. Morita (1997) *Appl. Organomet. Chem.*, **11**, 281.
3. P. A. Gallagher, S. Murray, X. Wei, C. A. Schwegel, and J. T. Creed (2002) *J. Anal. At. Spectrom.*, **17**, 581-586.
4. J. W. McKiernan, J. T. Creed, C. A. Brockhoff, J. A. Caruso, and R. M. Lorenzana (1999) *J. Anal. At. Spectrom.*, **14**, 607-613.
5. S. McSheehy, P. Pohl, R. Lobinski, and J. Szpunar, (2001) *Analyst*, **126**, 1055-1062.
6. E. H. Larsen and S. Stürup (1994) *J. Anal. At. Spectrom.*, **9**, 1099-1105.
7. U. Kohlmeier, J. Kuballa, and E. Jantzen (2002) *Rapid Commun. Mass Spectrom.*, **16**, 965-974.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2003

Printed in the USA
October 14, 2003
5988-9893EN



Agilent Technologies



Speciation of Organic Compounds, Using a Newly Developed, Experimental GC-ICP-MS Interface

Application Note

ICP-MS

Environmental

Michiko Yamanaka* and O.F.X. Donard**

* Agilent Technologies, Tokyo Analytical Division, Tokyo, Japan

** Laboratoire de Chimie Analytique Bioinorganique & Environment, University of Pau, Pau, France

Introduction

Tin has been an important metal for thousands of years, having been used in the formulation of alloys such as bronze, in mirrors and in the production of glass. More recently, organotin compounds have been used as industrial materials such as stabilizers in polymers. The trialkylated forms are efficient biocides and fungicides and their properties have been used in many applications. For example, triphenyltin (TPhT) has been used as a pesticide and tributyltin (TBT) was used extensively both as a wood preservative and as the active component in marine anti-fouling paints, applied to the hulls of sailing vessels. While organotin compounds degrade rapidly under photolytic conditions, some trialkyltin compounds are persistent once introduced in the environment (e.g. TBT). Despite of the fact that TBT has been banned from use on small boats for over a decade, it is still commonly used on the hulls of large ships, to prevent the growth of marine organisms. In 1989, TBT was banned in all states of the USA on vessels of 25 meters or less in length. Despite a general reduction in the use of organotin compounds, they can accumulate in sediments over many

years and can be ingested and absorbed by marine organisms, leading to accumulation in the marine

food chain and ultimately presenting a potential threat both to the environment and later to human consumption.

Recent studies provide strong evidence that many organotin compounds can act as endocrine disruptors, even at very low concentrations. Endocrine disruptors interfere with the action of many hormones, and can be very damaging to the development of animal embryos. As a consequence, there is an increasing demand for a new analytical method for these compounds, which is fast, sensitive and offers high chromatographic resolution.

Capillary Gas Chromatography (GC) offers fast and high-resolution speciation, and is well suited for organotin compounds. Measurement limits using currently available GC detectors (FPD, MS and AED) are good, but the need for determination of organotins at ever-lower levels of concentration has fuelled the investigation of alternative detection systems. Further the presence of sulfur compounds in many of the samples requires a highly selective and sensitive detector.

Inductively Coupled Plasma Mass Spectrometry (ICP-MS) offers ultra trace detection limits and high selectivity for most elements. The principles of ICP-MS are summarized in Figure 1. Samples are introduced into a high temperature argon plasma, where they are decomposed, atomized

and ionized. The resultant ions are transported, through a sampling interface, into a mass spectrometer for measurement. The high temperature in the ICP source means that all forms of an element are decomposed into individual atoms, so ICP-MS results represent total element levels. However, in combination with an on-line separation technique, such as Liquid Chromatography (LC), Ion Chromatography (IC) or Capillary Electrophoresis (CE), ICP-MS is increasingly being used as a sensitive and highly specific detector in a wide variety of speciation applications.

Combining the separation capabilities of a GC with the selectivity and sensitivity of ICP-MS could offer benefits in the measurement of ultra-trace levels of organically bound metals. In this paper, we describe some initial investigations into the coupling of GC to ICP-MS, for the analysis of organotin compounds.



Agilent Technologies
Innovating the HP Way




Figure 1. Schematic of an ICP-MS

The interface is not yet commercially available, but it shows some promise. We have used the GC-ICP-MS device to separate and quantify organotin compounds – monobutyltin (MBT), dibutyltin (DBT), tributyltin (TBT), monophenyltin (MPhT), diphenyltin (DPhT), and triphenyltin (TPhT) - in marine environmental samples of oyster tissue and sediment, collected from the same locality.

Instrumentation

The GC used in these studies was a model 5890, and the ICP-MS was a 4500, both from Agilent Technologies.

The general principal of combining GC with ICP-MS is simple. The end of the capillary GC column is fastened to the base of the ICP torch, so that separated species are carried directly into the plasma by a heated Ar flow.

Using a heated transfer line to connect the GC to the ICP-MS prevents material condensing within the interface and so enables the analysis of high boiling point compounds. Figure 2 is a schematic that describes the interface used during these experiments. Xenon was added to the argon make-up gas as a means of optimizing the ICP-MS operating conditions. The Xe:Ar gas mixture

was preheated by passing it through a stainless steel coil mounted within the GC oven.

Initial evaluations of the interface were undertaken at the laboratory of O.F.X. Donard at the University of Pau in France. Figure 3 is a chromatogram of a GC-ICP-MS separation of a 1µL injection of a standard, which contained a mixture of organotin species. Each peak in Figure 3 represents the equivalent of 5 pg tin.






Figure 2. Schematic of the GC-ICP-MS and Interface




Figure 3. GC-ICP-MS Chromatogram of a 1uL Injection of a 5ppb Organotin Mixed Standard

Table 1 GC-ICP-MS Acquisition Conditions

GC	
Injection mode	Splitless
Injection volume	1uL
Inlet temp	290° C
Column	Non-polar capillary – HP-1 (30m,0.32mm, 0.25um)
Carrier gas	He – 1.0mL/min
Oven program	70°C (1 min):ramp to 190°C (30°C/min): ramp to 270°C (15°C/min)
Interface temperature	250° C
ICP-MS	
RF power	1300W
Sampling depth	8mm
Carrier gas flow	0.8L/min
Oxygen gas flow	0.02L/min (added to auxiliary gas)

Ethylation using sodium tetraethylborate (NaBEt_4) was chosen as the derivatization method for this work. The reaction between the organotin compound and the NaBEt_4 is in aqueous conditions, which makes it much more suitable for environmental and biological samples than a normal Grignard reagent.


As the chromatogram illustrates, the peak shapes obtained are excellent, suggesting little or no broadening caused by the interface.

Initial results

Preliminary studies on organotin content of oysters and sediments were done in collaboration with the University of Pau . We have taken here samples from the Bay of Arcachon since it is one of the most productive areas for oyster farming. Despite of the fact that organotin concentrations have declined in the water and the sediment of the bay, organotin compounds can be found in oysters, due to bioaccumulation. In general there is an increasing concern

about the occurrence of organotin in shellfish worldwide, particularly as many species are used for human consumption. Samples of oysters and sediment were collected and analysed using the GC with ICP-MS detection.

Some care had to be exercised in the preparation of the oyster tissue, to prevent any potential decomposition of the analyte. The sample preparation method is summarized in Figure 4. Tripropyl tin (TPrT) was added to each sample as an internal standard.

**Figure 4. Sample Preparation Steps for the Oyster Tissue**





Figure 5. Sample Preparation Steps for the Sediment

A similar procedure was used for the preparation of sediment samples (Figure 5), except that acetic acid was used instead of Tetramethyl ammonium hydroxide (TMAH).

Figure 6 is a typical GC-ICP-MS chromatogram from one of the oyster extracts, illustrating excellent separation and peak shape. As the data show, there are substantial and measurable amounts of a variety of organotin compounds in the sample.



upper 118m/z, lower 120m/z
obtained simultaneously note different vertical scale

1 Sn (inorganic), 2 MBT(0.2pg), 3 TPrT (IS, 2.5pg),
4 DBT(1.8pg), 5 TBT(4.0pg), 6 TPhT(0.3pg)
other peaks are not identified

Figure 6. GC-ICP-MS Chromatogram from the Analysis of One of the Oyster Tissue Samples

Table 2. Results Summary from the Analysis of Oyster Samples across Arachon Bay, Plus Analysis of a Sediment Sample

Area	water(%)	concentration / ng/g (Dry)					
		MBT	DBT	TBT	MPhT	DPhT	TPhT
Area1	85	8.3	13	28	0.3	N.D.	N.D.
Area2	81	0.8	9.5	21	N.D.	N.D.	1.6
Area3	85	3.7	15	46	1.3	N.D.	N.D.
Area4	81	1.1	12	42	N.D.	N.D.	N.D.
Area5	86	0.7	11	51	N.D.	N.D.	2.1
Area6	83	1.8	13	39	N.D.	N.D.	N.D.
Area7	81	0.5	5.3	16	N.D.	N.D.	1.6
Area8	82	1.7	18	54	N.D.	N.D.	N.D.
Area9	83	2.4	20	141	N.D.	N.D.	N.D.
sediment	36	6.0	5	7	3.0	N.D.	2.0

Table 2 summarizes data from oysters sampled in and around Arachon Bay, as well as a sediment sample. Tributyltin (TBT) is the single largest component in each case, although there are several other species present at significant levels. Monobutyltin (MBT) and Dibutyltin (DBT) are breakdown products of TBT. Although the use of TBT in marine antifouling paints has been discontinued in France, the organotin compound still exists in the sediment where the oysters develop. Of particular interest is Area 9, which is a part of the Bay where oyster production has been poor. This also coincides with the largest level of TBT.

The exceptional resolution of the chromatographic separation allows an anticipation of the formation of metabolite products from organotin compounds (e.g. methylation of butyltin compounds) opening the way to new understanding of environmental and biometabolic pathways for these contaminants after further identification.

Summary

These preliminary results suggest that GC-ICP-MS offers a highly sensitive and selective method for the determination of organometallic compounds in environmental matrices. The exceptional chromatographic separation capability of the CGC,


coupled to the sensitivity, selectivity and multielemental capability of the ICP-MS detector, certainly makes this combination a very promising tool for environmental studies. The interface used in these studies is not yet commercially available and will require some further refinement and characterization. The robustness of the heating system will require some refinement to ensure long-term reliability. Future applications work is under way evaluating the potential of this interface for the simultaneous determination of other organometals such as tin, lead and mercury compounds.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2003
 Agilent Technologies, Inc.
 Printed in Japan (07/03)
 5980-0336E



Meeting Worldwide Regulatory Requirements for the Analysis of Trace Metals in Drinking Water Using the Agilent 7500c ICP-MS

Application

Environmental

Authors

Steven Wilbur, Emmett Soffey
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The Agilent 7500c ICP-MS can be used to meet the regulatory requirements for trace metals in drinking water around the world. Elements previously relegated to other techniques, such as GFAA or ICP-OES due to very high or low concentrations or the presence of interferences, can now be measured in a single analysis.

Introduction

Virtually all developed countries have adopted programs and regulations to monitor and maintain the quality of public water systems. In the US, water quality is regulated by the United States Environmental Protection Agency (USEPA) as mandated by the *Safe Drinking Water Act of 1974*. In the European Union, drinking water is regulated by the *Council Directive 98/83/EC of 3, November, 1998 on the Quality of Water Intended for Human Consumption*. In Japan, quality of drinking water is regulated by the *Japan Water Supply Act*, dating from 1957, and most recently updated in 2001. Most of the rest of the world's developed countries have adopted drinking water quality standards based on World Health Organization (WHO) Standards, *Guidelines for Drinking Water Quality*, 1996, 1998, or on the USEPA standards. While

these guidelines, as they pertain to trace metals, vary somewhat in their lists of regulated metals and concentrations, they are fundamentally similar. They all require accurate, precise measurement of multiple toxic metals in drinking waters at the lowest practical limits of quantification. This application note will demonstrate that the sensitivity, accuracy, and precision requirements for the analysis of trace metals in drinking water worldwide can be met by a single, robust technique using the Agilent 7500c ICP-MS system with Octopole Reaction System (ORS) technology.

US Regulations

In the US, the quality of public drinking water is safeguarded by the provisions of the Safe Drinking Water Act of 1974.

The Safe Drinking Water Act (SDWA) was originally passed by Congress to protect public health by regulating the nation's public drinking water supply. The law, amended in 1986 and 1996, requires many actions to protect drinking water and its sources in rivers, lakes, reservoirs, springs, and ground water wells (SDWA does not regulate private wells, which serve fewer than 25 individuals). SDWA authorizes the USEPA to set primary national health-based standards for drinking water to protect against both naturally-occurring and man-made contaminants that may be found in drinking water. These primary national drinking water standards include maximum contaminant level goals (MCLGs), levels below which there is no known or expected health risk. From these MCLG values, EPA determines maximum contaminant levels (MCLs), which are



Agilent Technologies

enforceable levels that may not be exceeded. The MCLs are set as closely as possible to the MCLGs and are based on best available current technology and economic feasibility. These limits are reviewed and updated periodically as new information becomes available and technology improves.

Japanese Regulations

Drinking water quality in Japan is regulated by the Japan Water Supply Act, which was first promulgated in 1957 with the Quality Standard for Drinking Water set the following year. This standard currently regulates the drinking water quality of more than 97% of the population. The Quality Standard sets maximum allowable concentrations (MAC) for 17 metals. It also requires that quantification limits be set at 1/10 of the MAC to assure accurate measurements at trace levels. Because of this, in 2001 the Drinking Water Test Method was revised and expanded to include the use of ICP-MS for 14 of the 17 metals. The approval of the use of ICP-MS has eliminated the need for costly and time

consuming preconcentration, which was required to meet the required detection limits using ICP-OES.

European Union Regulations

Currently, water quality in the European Union (EU) is regulated by Council Directive 80/778/EEC. This directive applies to all waters intended for human consumption, except natural mineral waters or waters which are medicinal products. As of December 2003, Directive 80/778/EEC will be repealed and replaced by Council Directive 98/83/EC *Directive on the Quality of Water Intended for Human Consumption*, which came into force on December 25, 1998. The standards are based largely on recommendations by the WHO¹. Member states of the European Community, while they must comply fully, are permitted to implement regulation and enforcement locally. As a result, no single regulation exists for the analysis of trace metals in water throughout Europe.

¹World Health Organization Guidelines and International Standards for Drinking-Water Quality, 1998

Table 1. Drinking Water Standards for Trace Metal Content from WHO Recommendations, EU Regulations, Japan Drinking Water Regulations and USEPA.

Analyte	WHO Standard (mg/L)	EC Directive 98/83/EC (mg/L)	Japan Drinking Water Standard (mg/L)	USEPA Primary MCL (mg/L)	Agilent 7500c MDLs*** (mg/L)
Aluminum (Al)		0.2	0.2	0.02-0.2*	0.000054
Antimony (Sb)	0.005**	.005	0.002	0.006	0.000035
Arsenic (As)	0.01**	.01	0.01	0.01	0.000052
Barium (Ba)	0.7			2	0.000027
Beryllium (Be)				0.004	0.000028
Boron (B)	0.5**	1	1.0		
Cadmium (Cd)	0.003	0.005	0.01	0.005	0.000025
Chromium (Cr)	0.05**	0.05		0.1	0.000019
Copper (Cu)	2**	2	1.0	1.3	0.000023
Iron (Fe)		0.2	0.3	0.3*	0.00125
Lead (Pb)	0.01	.01	0.05	0.015	0.000017
Manganese (Mn)	0.5**	.05	0.05	0.05*	0.000020
Mercury (Hg)	0.001	0.001	0.0005	0.002	0.000005
Molybdenum(Mo)	0.07				0.000030
Nickel (Ni)	0.02**	0.02	0.01		0.000024
Selenium (Se)	0.01	0.01	0.01	0.05	0.000047
Silver (Ag)				0.01*	0.000027
Sodium (Na)		200	200		0.0276
Thallium (Tl)				0.002	0.000021
Uranium (U)	0.002**		0.002	0.030	0.000015
Zinc (Zn)				5.0*	0.000101

*Secondary Standard, **Provisional Guideline Value, ***MDLs Calculated as Three Sigma of 10 Replicates of Low Standard, as Described in this Work. MDLs Reported in mg/L to Match Regulatory Requirements.

Table 1 includes the trace metals that are regulated by various worldwide regulatory and advisory agencies. ICP-MS is the only analytical technique capable of meeting all the required detection limits for all the regulated trace metals. Therefore, while not mandated as the only acceptable technique for most regulations, ICP-MS is becoming the instrument of choice for trace metals analysis in water worldwide.

While the details of QA/QC criteria and reporting requirements vary significantly from jurisdiction to jurisdiction, Table 1 shows that the actual detection limit requirements are very similar. In addition, the fundamental goals of the QA/QC requirements in all jurisdictions are the same. This is to insure that the reported values for all samples meet commonly accepted guidelines for accuracy and precision. Typically, these guidelines are met through the analysis of periodic QC samples inserted into the sample queue. Such QC samples should include: a check on the accuracy of the initial instrument calibration; a control sample of known concentration similar to that of the analytes in a similar matrix; a sample designed to test the ability of the system to eliminate interferences as false positives; a sample designed to detect sample carryover or memory problems; and periodic calibration check samples to check for instrument drift. If samples are to be analyzed outside the calibration range of the analytical method, then a linear range check sample must also be analyzed. It is outside the scope of this application note to detail the specific QA/QC requirements for each regulation where they exist at all. Instead, a general QA/QC protocol will be outlined which will demonstrate the ability of the Agilent 7500c to meet generally accepted guidelines while easily meeting the required reporting limits for drinking water monitoring worldwide. Simple modifications to this procedure can be implemented to insure strict compliance with detailed local requirements.

Advantages to the Use of the ORS for Drinking Water Analysis

Generally, drinking water is not considered a particularly difficult matrix for analysis by ICP-MS. There are, however, a few significant challenges.

These challenges are due to the very low desired reporting limits for several elements (Table 1), as well as the possibly high concentrations for others, such as Ca and Na. This combination of very low and very high analyte concentrations presents a challenge that no other analytical technique can overcome. In order to measure all elements simultaneously, the ICP-MS must be able to accurately measure mercury at 0.05 ppb or less and Na or Ca as high as 1000s of ppm. In addition, the ICP-MS must be able to eliminate common interferences on Fe, As, Se, Cu, V, and other elements which originate in the plasma and interface region. If unmanaged, these interferences make trace level analysis of the above elements difficult or impossible in many water samples.

The ORS serves two purposes. First, it uses collision/reaction cell technology to virtually eliminate polyatomic interferences on most elements. This allows the analyst to select the most abundant isotope of each analyte for analysis and avoid the use of mathematical correction factors. The result is sub-ppb detection limits for virtually all elements of interest. Second, it allows the analyst to use passive collisions in the ORS to reduce the ion current for high concentration, low-mass elements such as Na and Ca. In this way, the dynamic range for these elements is shifted to allow accurate, linear measurement at levels previously impossible by ICP-MS. It is this ability to simultaneously improve the sensitivity for ultra-trace analytes and extend the dynamic range upward for matrix analytes that is unique to the ORS system.

Instrument Conditions

Table 2 shows the instrument conditions used for typical water analysis. Listed are the preferred isotope, the tune mode (normal, hydrogen reaction, or helium collision), integration time, calibration range, and approximate detection limit based on normal commercial laboratory conditions. RF power is typically set high, 1400–1500 W, to maximize decomposition of the matrix. Other tune conditions such as ion optics, quadrupole, and detector parameters are set according to standard instrument tune guidelines. No special tuning is required.

Table 2. Elements of Interest with Appropriate Isotopes, ORS Acquisition Mode, Integration Time, Calibration Range and Measured MDLs for Each Isotope

Analyte	Isotope	ORS mode	Integration time (s)	Calibration range (ppb)	~MDL (ppb)
Aluminum (Al)	27	Normal	0.1	0.5–100	0.054
Antimony (Sb)	121	Normal	0.1	0.5–100	0.035
Arsenic (As)	75	Helium	0.5	0.5–100	0.052
Barium (Ba)	137	Normal	0.1	0.5–100	0.027
Beryllium (Be)	9	Normal	0.1	0.5–100	0.028
Boron (B)	10	Normal	0.1	0.5–100	
Cadmium (Cd)	111	Normal	0.1	0.5–100	0.025
Calcium (Ca)	40	Hydrogen	0.1	50–200,000	2.02
Chromium (Cr)	52	Helium	0.5	0.5–100	0.019
Copper (Cu)	63	Helium	0.5	0.5–100	0.023
Iron (Fe)	56	Hydrogen	0.1	50–200,000	1.25
Lead (Pb)	Sum of isotopes 206, 207, 208	Normal	0.1	0.5–100	0.017
Manganese (Mn)	55	Normal	0.1	0.5–100	0.020
Mercury (Hg)	202	Normal	1.0	0.05–1.0	0.005
Molybdenum (Mo)	95	Normal	0.1	0.5–100	0.030
Nickel (Ni)	60	Helium	0.5	0.5–100	0.024
Potassium (K)	39	Helium	0.5	50–200,000	3.02
Selenium (Se)	78	Hydrogen	0.5	0.5–100	0.047
Silver (Ag)	107	Normal	0.1	0.5–100	0.027
Sodium (Na)	23	Hydrogen	0.1	50–200,000	27.6
Thallium (Tl)	205	Normal	0.1	0.5–100	0.021
Uranium (U)	238	Normal	0.1	0.5–100	0.015
Vanadium (V)	51	Helium	0.5	0.5–100	0.034
Zinc (Zn)	66	Normal	0.1	0.5–100	0.101
Useful Internal Standards					
6Li	6	Normal	0.1	50	
Sc	45	All	0.1	50	
Ge	70,72,74	All	0.1	50	
Y	89	Normal	0.1	50	
In	115	Normal	0.1	50	
Tb	159	Normal	0.1	50	
Pt	195	Normal	0.1	50	
Bi	209	Normal	0.1	50	




Figure 1. Summary of general water analysis protocol.

Figure 1 depicts the general flow of sample analysis and QA/QC that would be performed to meet the daily requirements of most drinking water regulations. Specific QA/QC details vary from jurisdiction to jurisdiction and are not outlined here. In addition to the daily requirements, less frequent, periodic QA/QC documentation must be performed to ensure ongoing accuracy and precision. Such periodic requirements include: verification of method detection limits, dynamic range,

management of interferences (both isobaric and memory effects), as well as general instrument condition and performance. Specific examples of these requirements are found in USEPA Method 200.8 and the UK Drinking Water Inspectorate publication, “NS-30.”

Interference Correction

Because the ORS is capable of efficiently removing polyatomic interferences and most isobaric

elemental interferences in unknown, complex matrices, the use of mathematical interference correction is all but eliminated. The elements which typically require interference correction in water, Ca, V, Fe, As, Se, Mo, and Cd can all be analyzed without the need for mathematical correction. This simplifies the analysis and improves confidence in the results. In this work, only Li-6, In-115, and Pb are corrected (see Table 3). The Li-6 correction is used to correct the abundance of the Li-6 internal standard in the presence of high concentrations of Li-7 in some samples. The In-115 correction is used to correct an internal standard, In, in the presence of high concentrations of tin. Neither of these cases is common and normally these can be ignored. The Pb correction is used to normalize the lead response in the case of varying lead isotope ratios and is not an interference correction.

Table 3. Typical Mathematical Corrections Used for Water Matrices with the Agilent 7500c ORS System

Mass	Equation
6	$(6)^*1 - (7)^*0.082$
115	$(115)^*1 - (118)^*0.014$
208	$(208)^*1 + (206)^*1 + (207)^*1$

Experiment

The following data and results were all obtained from a single sequence of 44 analyses of standards, blanks, QC samples, unknown groundwater samples, and seawater samples. All calibrations are based on a single set of standards prepared in 1% nitric acid/0.5% hydrochloric acid. No attempt at matrix matching beyond simple acidification was made. The instrument and conditions were like those of a typical commercial environmental laboratory. "Clean room" conditions or ultra-high purity reagents were not employed. The Agilent 7500c ICP-MS with ORS and Integrated Sample Introduction System (ISIS), configured for autodilution, was used.

Quality Control

Quality control in this experiment consisted of four components:

- Verification of tune performance for each ORS mode
- Initial Calibration linearity check
- Verification of accuracy of initial calibration using NIST 1640 standard reference water
- Periodic verification of calibration accuracy through measurement of continuing calibration verification (CCV) samples

Autodilution

The Agilent 7500c was configured with an ISIS for rapid sample uptake and autodilution. ISIS uses flowing stream autodilution rather than discrete sample dilution. This greatly enhances the throughput and minimizes the possibility of contamination compared with other types of autodiluters. In the ISIS autodiluter, the sample stream is mixed with a flowing stream of diluent in an entirely closed system. Dilution factor is controlled by high precision peristaltic pumps that are automatically and periodically monitored for accuracy throughout the run. Autodilution is invoked automatically by the intelligent sequencing software whenever the system encounters a user-definable out-of-range condition, such as an analyte outside the calibration range or an internal standard outside predefined bounds. Autodilution was invoked in a number of the samples in this work. An excellent check on both the linearity of the instrument and the accuracy of the autodilution can be obtained by comparing the results for diluted and undiluted samples. If the results match well, both the instrument linearity and autodilution accuracy are in control. Tables 5 and 7 show excellent examples of this.

Results

QC results are depicted in Tables 4 (CCV results) and 5 (NIST 1640 results). Examples of calibration linearity are depicted in Figures 2, 3, and 4, which are representative. Calibration "R" values of .9998 or greater are considered linear.

Table 4. Recovery of Periodic Calibration Check Standard in a Sequence of Water Samples Including Drinking Waters, Ground Waters, and Seawaters. Calibration Checks were Run After 30 and 43 Real Samples in this Experiment

	CCV		%	%	
	Actual value	CCV 50/5000/0.5	Recovery	CCV 50/5000/0.5	Recovery
Total DF:		1		1	
File:		031_CCV.D#		044_CCV.D#	
Be/9 [#1]	50	50.62	101.2	50.01	100.0
Na/23 [#2]	5000	4933.00	98.7	4838.00	96.8
Mg/24 [#1]	5000	4700.00	94.0	4802.00	96.0
Al/27 [#1]	50	47.09	94.2	46.84	93.7
K/39 [#3]	5000	5260.00	105.2	5076.00	101.5
Ca/40 [#2]	5000	5053.00	101.1	5063.00	101.3
V/51 [#3]	50	51.52	103.0	50.84	101.7
Cr/52 [#3]	50	51.43	102.9	50.78	101.6
Mn/55 [#1]	50	49.92	99.8	50.89	101.8
Fe/56 [#2]	5000	5067.00	101.3	5068.00	101.4
Co/59 [#1]	50	49.88	99.8	50.16	100.3
Ni/60 [#3]	50	51.99	104.0	51.36	102.7
Cu/63 [#3]	50	52.64	105.3	51.74	103.5
Zn/66 [#1]	50	49.27	98.5	49.44	98.9
As/75 [#3]	50	51.63	103.3	51.58	103.2
Se/78 [#2]	50	50.90	101.8	50.61	101.2
Se/80 [#2]	50	51.45	102.9	51.10	102.2
Mo/95 [#1]	50	49.44	98.9	48.11	96.2
Ag/107 [#1]	50	48.73	97.5	47.02	94.0
Cd/111 [#1]	50	49.34	98.7	48.40	96.8
Sb/121 [#1]	50	47.71	95.4	47.03	94.1
Ba/137 [#1]	50	50.35	100.7	49.19	98.4
Hg/202 [#1]	0.5	0.49	98.3	0.47	94.8
Tl/205 [#1]	50	49.68	99.4	50.46	100.9
Pb/208 [#1]	50	49.41	98.8	49.25	98.5
Th/232 [#1]	50	48.54	97.1	49.09	98.2
U/238 [#1]	50	49.46	98.9	49.84	99.7

Values in brackets after element mass are tune mode, 1= normal, 2 = hydrogen, 3 = helium.

Table 5. Analysis of Certified Reference Water NIST 1640 as a Calibration Check. Sample was Measured Neat and Autodiluted 1/20 (actual measured DF = 21.72), since Na Value Exceeded Upper Calibration Limit. Note that Even in the Undiluted Sample, the Recovery for Na is 101.2%

	Certified value (ppb)	NIST 1640 1	% Recovery undiluted	NIST 1640 21.72	% Recovery diluted
Total DF:					
Be/9 [#1]	34.94	35.750	102.3	34.860	99.77
Na/23 [#2]	29350	29690.000	101.2	29140.000	99.28
Mg/24 [#1]	5819	5893.000	101.3	6154.000	105.76
Al/27 [#1]	52	49.180	94.6	69.290	133.25
K/39 [#3]	994	947.900	95.4	858.800	86.40
Ca/40 [#2]	7045	7328.000	104.0	7488.000	106.29
V/51 [#3]	12.99	13.030	100.3	12.930	99.54
Cr/52 [#3]	38.6	37.470	97.1	38.540	99.84
Mn/55 [#1]	121.5	119.500	98.4	120.100	98.85
Fe/56 [#2]	34.3	35.840	104.5	31.820	92.77
Co/59 [#1]	20.28	19.400	95.7	20.010	98.67
Ni/60 [#3]	27.4	26.920	98.2	28.000	102.19
Cu/63 [#3]	85.2	86.450	101.5	92.350	108.39
Cu/65 [#3]	85.2	86.350	101.3	91.340	107.21
Zn/66 [#1]	53.2	55.380	104.1	55.560	104.44
As/75 [#3]	26.67	26.910	100.9	28.080	105.29
Se/78 [#2]	21.96	21.990	100.1	20.930	95.31
Mo/95 [#1]	46.75	45.310	96.9	43.280	92.58
Ag/107 [#1]	7.62	7.210	94.6	7.497	98.39
Cd/111 [#1]	22.79	22.560	99.0	22.420	98.38
Sb/121 [#1]	13.79	13.090	94.9	12.590	91.30
Ba/137 [#1]	148	143.900	97.2	142.100	96.01
Hg/202 [#1]		0.017		0.019	
Tl/205 [#1]		0.009		-0.042	
Pb/208 [#1]	27.89	26.690	95.7	26.370	94.55
Th/232 [#1]		0.011		-0.429	
U/238 [#1]		0.725		0.698	

Values in brackets after element mass are tune mode, 1= normal, 2 = hydrogen, 3 = helium.

Table 6. Replicate Analyses of Low Standard After Sequence of 33 High Level Samples, Standards, and Blanks for MDL Calculations. Three Sigma MDL are Calculated in ppb

	MDL rep 01	MDL rep 02	MDL rep 03	MDL rep 04	MDL rep 05	MDL rep 06	MDL rep 07	MDL rep 08	MDL rep 09	MDL rep 10	3 Σ MDL
Be/9 [#1]	0.50	0.50	0.49	0.49	0.50	0.47	0.49	0.49	0.50	0.49	0.028
Na/23 [#2]	53.45	47.78	43.96	39.85	40.52	36.48	34.69	30.58	30.17	22.08	27.617
Mg/24 [#1]	49.82	49.13	49.75	48.94	48.83	48.92	49.32	48.84	48.24	48.41	1.530
Al/27 [#1]	0.30	0.26	0.25	0.25	0.25	0.23	0.24	0.24	0.25	0.26	0.054
K/39 [#3]	56.28	55.34	55.09	53.35	55.02	55.15	53.73	53.25	54.17	53.70	3.023
Ca/40 [#2]	52.33	51.76	51.55	51.81	52.32	51.86	51.28	51.33	53.42	51.15	2.023
V/51 [#3]	0.51	0.53	0.53	0.53	0.54	0.51	0.53	0.50	0.52	0.52	0.034
Cr/52 [#3]	0.52	0.52	0.51	0.51	0.50	0.51	0.52	0.51	0.51	0.51	0.019
Mn/55 [#1]	0.49	0.49	0.49	0.47	0.48	0.48	0.49	0.48	0.48	0.47	0.020
Fe/56 [#2]	53.84	53.69	53.43	53.46	53.97	53.18	53.10	52.91	53.17	52.65	1.251
Co/59 [#1]	0.48	0.48	0.49	0.48	0.48	0.48	0.49	0.49	0.48	0.47	0.016
Ni/60 [#3]	0.50	0.49	0.49	0.48	0.50	0.48	0.48	0.49	0.48	0.49	0.024
Cu/63 [#3]	0.48	0.48	0.46	0.47	0.46	0.48	0.48	0.47	0.46	0.47	0.023
Zn/66 [#1]	0.50	0.45	0.43	0.43	0.43	0.42	0.42	0.46	0.44	0.42	0.074
As/75 [#3]	0.50	0.53	0.53	0.49	0.54	0.54	0.54	0.53	0.52	0.52	0.052
Se/78 [#2]	0.52	0.51	0.53	0.52	0.49	0.52	0.52	0.51	0.48	0.51	0.047
Se/80 [#2]	0.58	0.62	0.56	0.56	0.55	0.57	0.58	0.55	0.54	0.57	0.066
Mo /95 [#1]	0.47	0.46	0.46	0.46	0.45	0.46	0.48	0.44	0.47	0.45	0.030
Ag/107 [#1]	0.45	0.47	0.46	0.44	0.46	0.46	0.46	0.45	0.44	0.45	0.027
Cd/111 [#1]	0.45	0.43	0.44	0.44	0.44	0.44	0.44	0.44	0.45	0.43	0.025
Sb/121 [#1]	0.46	0.45	0.44	0.45	0.43	0.44	0.46	0.45	0.43	0.45	0.035
Ba/137 [#1]	0.49	0.47	0.47	0.49	0.48	0.47	0.47	0.47	0.46	0.48	0.027
Hg/202 [#1]	0.04	0.04	0.04	0.05	0.04	0.04	0.04	0.04	0.04	0.04	0.005
Tl/205 [#1]	0.40	0.42	0.42	0.43	0.42	0.42	0.42	0.42	0.41	0.41	0.021
Pb/208 [#1]	0.46	0.46	0.46	0.45	0.46	0.45	0.45	0.45	0.45	0.45	0.017
Th/232 [#1]	0.29	0.34	0.34	0.34	0.34	0.34	0.34	0.34	0.34	0.34	0.050
U/238 [#1]	0.43	0.44	0.44	0.43	0.43	0.43	0.44	0.44	0.43	0.43	0.015

Values in brackets after element mass are tune mode, 1= normal, 2 = hydrogen, 3 = helium.

Detection Limits

The method detection limits reported in Table 6 were generated at the end of a sequence of 33 real world samples, standards, and blanks. Column one lists the isotope and ORS acquisition mode, #1 = Normal Mode, #2 = Hydrogen Mode, #3 = Helium Mode. Actual method detection limits will vary depending on instrument and laboratory conditions. These detection limits should be achievable with normal levels of laboratory cleanliness, using trace metal grade acids and ASTM type 1 water. The instrument used for this work was equipped with the ISIS, which typically improves DLs somewhat by increasing sample introduction precision and minimizing carryover.

Dynamic Range

One of the advantages of using the ORS is its ability to reduce interferences on certain trace level analytes and simultaneously attenuate the signal on high concentration or matrix elements. In this work, calibrations were generated from a low of 50 ppt for Hg to a high of 200 ppm for the mineral elements, Na, K, Ca, Mg, and Fe. Sample calibration curves follow. Additionally, while Na was calibrated only as high as 200 ppm, which is the highest regulated concentration in any of the elements in the worldwide drinking water regulations (see Table 1), it yields linear response at much higher concentrations.

Table 7. A Series on Analyses on Three High Dissolved Solids Ground Water Samples. Each Sample was Analyzed Undiluted and Automatically Autodiluted. Elements which were Undetected were Removed for Simplicity.

	Water 1	Water 1	Water 2	Water 2	Water 3	Water 3
Total DF:	1	21.72	1	21.72	1	21.72
File:	014SMPL.D	015SMPL.D	016SMPL.D	017SMPL.D	018SMPL.D	019SMPL.D
Na/23 [#2]	489100.000	492500.000	330500.000	324100.000	563700.000	554000.000
Na/23 [#3]	480300.000	505800.000	337200.000	342800.000	563000.000	571800.000
Mg 24 [#1]	559.000	599.900	511.700	534.800	3099.000	3407.000
K/39 [#3]	1564.000	1365.000	794.000	721.400	2513.000	2333.000
Ca/40 [#2]	8708.000	8760.000	2337.000	2255.000	13350.000	13400.000
Mo/95 [#1]	0.776	0.773	1.482	1.535	49.070	49.180
Ba/137 [#1]	17.070	16.990	29.250	28.800	5.263	5.154
U/238 [#1]	0.043	0.037	0.036	0.034	0.115	0.103

Values in brackets after element mass are tune mode, 1 = normal, 2 = hydrogen, 3 = helium.

Table 7 shows the results of the analysis of three brackish ground water samples. Each sample was analyzed directly and then autodiluted. Both sets of results show both the dynamic range of the Agilent 7500c and the accuracy of the autodilution. The autodilution factor of 21.72 is the result of the system automatically calibrating the dilution

factor at the beginning of the sequence and periodically, as needed. Note that for the uranium result, where the undiluted concentration is only 30–40 ppt, the autodiluted result agrees very well. This translates to accurate measurement of uranium in the diluted samples of $\sim 35/21.7 = 1.6$ ppt.

Table 8. Results of Analysis of a 1/10 "Synthetic Seawater" Blank (High Purity 0.3% NaCl) Plus a Spike at 5 ppb for Trace Elements and 500 ppb for Matrix Elements.

	1/10 Synth Sea H₂O	Spike 1/10 Synth Sea H₂O + 5 ppb	% Recovery 5/500 ppb spike
File:	020SMPL.D#	021SMPL.D#	
Be/9 [#1]	0.000	4.591	91.8
Na/23 [#1]	over range	over range	N/A
Na/23 [#2]	1233000.000	1215000.000	N/A
Na/23 [#3]	1193000.000	1193000.000	N/A
Mg/24 [#1]	2.382	477.000	94.9
I/27 [#1]	-0.409	4.250	93.2
K/39 [#1]	13.730	491.500	95.6
K/39 [#2]	8.195	548.600	108.1
K/39 [#3]	16.510	597.400	116.2
Ca/40 [#2]	6.740	532.600	105.2
V/51 [#3]	0.031	5.426	107.9
Cr/52 [#3]	0.045	5.287	104.8
Mn/55 [#1]	-0.003	4.497	90.0
Fe/56 [#2]	-0.258	508.600	101.8
Co/59 [#1]	0.122	4.569	89.0
Ni/60 [#1]	0.024	4.318	85.9
Ni/60 [#3]	-0.040	4.801	96.8
Cu/63 [#3]	-0.117	4.691	96.2
Cu/65 [#3]	-0.117	4.564	93.6
Zn/66 [#1]	0.025	4.520	89.9
Zn/67 [#1]	0.007	4.714	94.1
As/75 [#3]	0.011	5.027	100.3
Se/78 [#2]	0.006	4.366	87.2
Se/80 [#2]	0.143	4.620	89.5
Mo/95 [#1]	0.043	5.040	99.9
Ag/107 [#1]	-0.010	4.254	85.3
Cd/111 [#1]	0.033	4.545	90.2
Sb/121 [#1]	0.034	4.598	91.3
Ba/137 [#1]	0.010	4.789	95.6
Hg/202 [#1]	0.017	0.020	N/A
Tl/205 [#1]	-0.003	4.883	97.7
Pb/208 [#1]	0.175	5.066	97.8
U/238 [#1]	0.000	4.968	99.4

Values in brackets after element mass are tune mode, 1 = normal, 2 = hydrogen, 3 = helium.

Table 8 shows the results of the analysis of a 0.3% 3000 ppm NaCl or 1180.5 ppm Na, both unspiked and spiked with trace elements and other matrix elements. Recoveries are reported in column 4. Note that in this case, for demonstration purposes, Na was acquired in all three ORS modes (normal, hydrogen, and helium). As expected, in the normal mode, the sodium signal was over range and the detector was protected from excessive signal. However, sodium was measurable in both hydrogen

and helium modes at 1233 and 1193 ppm respectively, yielding recoveries of 104% and 101% respectively without further dilution or any other manipulation of instrument conditions. Under identical conditions, in the same run at the same time, Arsenic in the spike was also measured using He collision mode at 5.03 ppb to give 100.3% recovery.

1180.5 ppm sodium




Figure 2. Calibration curve for Na in Helium collision mode showing linearity from 50 ppb to 1180 ppm (0.3% NaCl).




Figure 3. Arsenic calibration acquired in helium collision mode (same as Na in Figure 2) from 0.5 to 100 ppb.




Figure 4. Mercury calibration acquired in normal (no gas) mode from 0.05–1 ppb.

The calibration curves in Figures 2–4 were all acquired from the same mixes of standard elements in dilute nitric/hydrochloric acid. That means that the low standard contained 50 ppt of mercury, 500 ppt of the other trace elements and 50 ppb of the mineral elements (Na, K, Ca, Mg, and Fe), and so on through the levels. In the sodium curve, the actual calibration was performed up to 200 ppm (level 7 in Figure 2); the 1180.5 ppm level was the 1/10 “synthetic seawater” NaCl solution.

Conclusions

While the specific details for drinking water monitoring vary from country to country around the world, the overall requirements, both from a reporting limit and quality control standpoint, are

very similar. Currently, of the many available techniques for monitoring trace metals in water, only ICP-MS has the sensitivity and elemental coverage to meet all worldwide requirements. In addition, the use of collision/reaction cell technology in the form of the Agilent 7500c ORS allows the user both to easily meet the strictest ultra-trace reporting limits and to measure mineral or matrix elements at 1000s of ppm simultaneously, without fear of false positives from polyatomic interferences or out-of-range elements.

For More Information

For more information on our products and services, visit our web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2003

Printed in the USA
February 19, 2003
5988-8902EN



Agilent Technologies



A Comparison of GC-ICP-MS and HPLC-ICP-MS for the Analysis of Organotin Compounds

Application

Environmental

Author

Raimund Wahlen
LGC Limited, Queens Road
Teddington, Middlesex
TW11 0LY, United Kingdom

Abstract

An inductively coupled plasma mass spectrometer (ICP-MS) was used as a detector for gas chromatography (GC) and high performance liquid chromatography (HPLC) analysis of organotin compounds. ICP-MS is a highly sensitive detector with detection limits in the pg-ng range, as well as enabling calibration by isotope dilution mass spectrometry (IDMS). Calibrating using isotopically labeled organotin species reduces measurement uncertainties and leads to greater precision compared to external calibration methods. This application note details the relative merits of the two techniques for the analysis of organotin compounds.

Introduction

The toxic effects of organotin compounds in the environment have been well documented [1] and have led to extensive research into analytical methodologies for their determination in a variety of matrices. The widespread use of organotin compounds has resulted in their detection in most marine and fresh-water sediments as well as in open-ocean waters [2]. In recent years, the focus of research in organotin analysis has begun to include matrices with human health implications, such as seafood [3], manufactured products (PVC pipes used for drinking water distribution [4]), and human blood samples [5].

Organotin analysis has traditionally been performed by chromatographic separation (gas chromatography (GC) or high performance liquid chromatography (HPLC)) coupled to a variety of detectors. GC separations enable the analysis of many different groups of organotin compounds (for example, butyl-, phenyl-, octyl-, and propyl) in a single analysis after derivatization [6]. However, derivatization is time-consuming and yields may vary between species and in terms of efficiency depending on matrix components. GC-ICP-MS has the potential to facilitate simultaneous multi-elemental speciation analysis, because species of Se [7], Pb [8], Hg [9], and Sn [10] have volatile forms and could be analyzed in a single analysis. Organotin separations by HPLC offer the advantage that derivatization is not required, which eliminates a potential source of uncertainty in the final result and can reduce analysis time significantly. However, the range of compounds that can be analyzed in a single run are limited compared to GC. The use of ICP-MS as a detector enables calibration by isotope dilution mass spectrometry as well as providing very low limits of detection (pg-ng range). In conjunction with isotopically labeled organotin species, this approach offers many advantages from an analytical point of view including reduced measurement uncertainties and greater precision compared to external calibration methods.

Experimental

Reagents and Standards

Acetonitrile (UpSTM ultra-purity solvent grade) was obtained from Romil (Cambridge, UK). Glacial



Agilent Technologies

acetic acid (TraceSelect) and anhydrous sodium acetate (Microselect $\geq 99.5\%$ NT) were obtained from Fluka (Gillingham, Dorset, UK). Triethylamine, methanol and hexane were used as HPLC grade. Deionized water was obtained from a water purification unit at $>18\text{M}\Omega$ (Elga, Marlow, UK). Sodium tetra-ethylborate (NaBEt_4) was obtained from Aldrich (Gillingham, Dorset, UK).

Tributyltinchloride (TBTCI), Dibutyltinchloride (DBTCI_2), Triphenyltinchloride (TPhTCI) and Diphenyltinchloride (DPhTCI₂) were obtained from Aldrich and purified according to the procedure described by Sutton et al [11]. The ^{117}Sn isotopically enriched TBTCI was synthesized according to the procedure described in the same paper. Monobutyltinchloride (MBTCI_3) and Tetrabutyltinchloride (TeBTCI) were obtained from Aldrich, and Dioctyltin (DOT), Tripropyltin (TPrT), and Tetrapropyltin (TePrT) were obtained from Alfa Aesar (Johnson Matthey, Karlsruhe, Germany).

Instrumentation

Accelerated solvent extraction was carried out using a Dionex ASE 200 system. An Agilent 7500i ICP-MS was used for time-resolved analysis of ^{120}Sn , ^{118}Sn , and ^{117}Sn . The ShieldTorch system was used, and a second roughing pump was added in-line to increase sensitivity.

An Agilent Technologies (Palo Alto, California, USA) 1100 HPLC system was used for HPLC separations. All stainless steel parts of the HPLC system that come into contact with the sample were replaced by polyether ether ketone (PEEK) components. A 100-cm length piece of PEEK tubing was used to connect the analytical column to the $100\text{-}\mu\text{L min}^{-1}$

PFA MicroFlow nebulizer of the ICP-MS. Optimization of the ICP-MS conditions was achieved prior to HPLC analysis by adjusting the torch position and tuning for reduced oxide and doubly charged ion formation with a standard tuning solution containing 10 ng g^{-1} of ^7Li , ^{89}Y , ^{140}Ce , and ^{205}Tl in 2% HNO_3 . After this preliminary optimization, the HPLC system was coupled to the nebulizer and a final optimization was carried out using ^{103}Rh added to the HPLC mobile phase. To reduce the solvent loading on the plasma, the double-pass spray-chamber was Peltier-cooled to $-5\text{ }^\circ\text{C}$. Oxygen (0.1 L min^{-1}) was mixed into the make-up gas and added post-nebulization to convert organic carbon to CO_2 in the plasma and avoid a carbon build-up on the cones. The final optimization was important because the nebulizer gas and make-up gas flows had to be adjusted to ensure plasma stability with the organic mobile phase conditions. HPLC separations were performed using a C-18 ACE column ($3\text{-}\mu\text{m}$ particle size, $2.1\text{ mm} \times 15\text{ cm}$) with a mobile phase of $65:23:12:0.05\%$ v/v/v/v acetonitrile/water/ acetic acid/TEA. The flow rate was 0.2 mL min^{-1} , and $20\text{ }\mu\text{L}$ of sample blends and mass-bias blends were injected. See Table 1.

GC separations were performed on an Agilent 6890 GC. The Agilent G3158A GC interface [12] was used to couple the GC to the ICP-MS. The GC method was used as described by Rajendran et al [6]. The analytical column was connected to a length of deactivated fused silica, which was inserted along the ICP transfer line and injector. After installation of the interface, the torch position and the ion lenses were tuned using a 100-ppm xenon in oxygen mixture, which was added to the ICP-MS carrier gas at 5% volume via a T-piece. The isotope monitored for this adjustment was ^{131}Xe .

Table 1. ICP-MS Parameters Used

	HPLC-ICP-MS Platinum	GC-ICP-MS Platinum
Interface cones		
Plasma gas flow	$14.5\text{--}14.9\text{ L min}^{-1}$	$14.5\text{--}14.9\text{ L min}^{-1}$
Carrier gas flow	$0.65\text{--}0.75\text{ L min}^{-1}$	$0.80\text{--}0.85\text{ L min}^{-1}$
Make-up gas flow	$0.15\text{--}0.25\text{ L min}^{-1}$	Not used
RF power	$1350\text{--}1550\text{ W}$	$1100\text{--}1200\text{ W}$
Sampling depth	$4\text{--}7\text{ mm}$	$6.5\text{--}7.5\text{ mm}$
Integration time per mass	300 ms	100 ms
Isotopes monitored	^{120}Sn ^{117}Sn ^{103}Rh	^{120}Sn ^{118}Sn ^{117}Sn
Other parameters	ICP torch injector diameter: 1.5 mm Peltier cooled spray chamber at $-5\text{ }^\circ\text{C}$ 5% O_2 added post-nebulization ShieldTorch fitted	5% N_2 or O_2 added to enhance sensitivity ShieldTorch fitted

Extraction of Organotin Compounds

The ASE extraction cells were fitted with PTFE liners and filter papers and filled with dispersing agent. The sediment and the isotopically enriched spike were added and left to equilibrate overnight. Each cell was extracted using five 5-minute cycles at 100 °C and 1500 psi after a 2-minute preheat and 5-minute heat cycle. 0.5 M sodium acetate/ 1.0 M acetic acid in methanol was used as the extraction solvent [13]. A calibrated solution (mass-bias blend) was prepared by adding the appropriate amounts of both ^{120}Sn TBTCI and ^{117}Sn TBTCI into an ASE cell filled and extracting under the same conditions as the samples. Digestion blanks were prepared by extracting ASE cells filled with hydromatrix and PTFE liners. After the extraction, each cell was flushed for 100 seconds with 60% of the volume and purged with N_2 . Prior to analysis, the extracts were diluted two- to five-fold in ultrapure water for HPLC-ICP-MS analysis. For GC-ICP-MS analysis, 5 mL of sample-, blank-, and mass-bias blend solutions were derivatized with 1 mL of 5% NaBEt_4 and shaken for 10 minutes with 2 mL of hexane. An aliquot of the hexane fraction was then injected for analysis.

Isotope Dilution Mass Spectrometry (IDMS) Methodology

The method used for IDMS consisted of analyzing a blend of the sample together with a mass-bias calibration blend. Each sample blend was injected four times and bracketed by injections of the mass-bias calibration blend. The mass-bias calibration blend was prepared to match the concentration and isotope amount ratio in the sample by mixing the same amount of spike added to the sample with a primary standard of the analyte of interest [14], [15]. The estimation of the standard uncertainties for the measured isotope amount ratios was different to the one described in [14] as they were calculated as peak area ratios and not spectral measurement intensities. The chromatographic peaks were integrated manually using the RTE integrator of the Agilent ICP-MS chromatographic software. The mass fraction obtained from the measurement of each sample blend injection was then calculated according to:

$$w'_X = w_Z \cdot \frac{m_Y}{m_X} \cdot \frac{m_{Zc}}{m_{Yc}} \cdot \frac{R_Y - R'_B \cdot \frac{R_{Bc}}{R'_{Bc}}}{R'_B \cdot \frac{R_{Bc}}{R'_{Bc}} - R_Z} \cdot \frac{R_{Bc} - R_Z}{R_Y - R_{Bc}}$$

R'_B	Measured isotope amount ratio of sample blend (X+Y)
R'_{Bc}	Measured isotope amount ratio of calibration blend (Bc=Z+Y)
R_{Bc}	Gravimetric value of the isotope amount ratio of calibration blend (Bc=Z+Y)
R_Z	Isotope amount ratio of Primary standard Z (IUPAC value)
R_Y	Isotope amount ratio of spike Y (value from certificate)
w'_X	Mass fraction of Sn in sample X obtained from the measurement of one aliquot
w_Z	Mass fraction of Sn in primary standard Z
m_Y	Mass of spike Y added to the sample X to prepare the blend B (=X+Y)
m_X	Mass of sample X added to the spike Y to prepare the blend B (=X+Y)
m_{Zc}	Mass of primary standard solution Z added to the spike Y to make calibration blend Bc (=Y+ Z)
m_{Yc}	Mass of spike Y added to the spike Y primary standard solution Z to make calibration blend Bc (=Y+ Z)

The representative isotopic composition of Sn taken from IUPAC was used to calculate the isotope amount ratios of the primary standard. For the spike TBTCI, the isotopic composition was obtained from the certificate supplied with the ^{117}Sn enriched material from AEA Technology plc (UK). For the measured isotope amount ratio of the calibration blend (R'_{Bc}), the average of the two ratios measured before and after each sample blend isotope amount ratio (R'_B) were taken. A mass fraction was calculated for each sample blend injection and the average of the bracketing mass-bias calibration blend injections. The average of the four mass fractions was then reported as the mass fraction obtained for the blend analyzed. The final mass fraction was recalculated back to the original sample and corrected for moisture content.

Results and Discussion

General Comparison

Analysis of mixed organotin standard solutions showed that the GC method could separate a greater number (10–12) of compounds in a single run compared to HPLC-ICP-MS (5–6). The injection-to-injection time was ~40% shorter for HPLC-ICP-MS, due to the temperature profile used for GC separations. Because of the cost of the derivatizing agent, the reagent cost per sample is approximately double for GC sample preparation.

Sensitivity Enhancement of GC-ICP-MS by Using Additional Gases

Figure 1 and Table 2 illustrate the effect of adding different additional gases on the signal response

for a range of organotin compounds. Adding 5% O₂ results in an increase in the measured peak area ranging from 9-fold (DBT and MPhT) to 12-fold (MBT). The addition of N₂ results in a further increase compared to analysis without addition of an optional gas. Response factors range from 105 (DBT and TPhT) to 136 for MBT and 150 for TeBT. This translates to a reduction of the method detection limit (3s) for TBT from 0.4 ng mL⁻¹ (no gas) to 0.03 ng mL⁻¹ (with 5% O₂ added) to 0.006 ng mL⁻¹ (with 5% N₂ added). The table below summarizes detection limits based on analysis of a calibration standard for MBT, DBT, and TBT.

Detection limits (ng mL⁻¹ as Sn) by GC-ICP-MS

	No gas added	5% N ₂ added
MBT	0.7	0.01
DBT	0.5	0.008
TBT	0.4	0.006




Figure 1. Sensitivity increase on a 20 ng mL⁻¹ mixed standard by using a) no additional gas, b) 5% O₂, and c) 5% N₂.

Table 2. Effect of Different Additional Gases on Sensitivity of Organotin Compounds by GC-ICP-MS

Compound	Retention time (min)	a) No gas added (peak area)	b) 5% O ₂ added (peak area)	Response factor compared to a)	c) 5% N ₂ added (peak area)	Response factor compared to a)	Response factor compared to b)
MBT	5.57	2274	27029	12	309702	136	12
DBT	6.38	3247	29238	9	340436	105	12
MPhT	6.84	2026	18173	9	215182	106	12
TBT	7.02	3490	33132	10	399868	115	12
TeBT	7.54	3717	34225	9	558916	150	16
DPhT	8.46	3181	29665	9	338057	106	11
TPhT	9.81	4287	41119	10	450803	105	11

Comparison of HPLC-ICP-MS and GC-ICP-MS for Analysis of TBT in Sediment

Table 3 shows the comparative data obtained by analysis of the same sediment extracts by both methodologies. There is no statistically significant difference between the two data sets. This confirms that the chromatographic separation and the different sample pretreatment (dilution/derivatization) used has no influence on the analytical result obtained. The chromatography for both methods appears in Figure 2 and Figure 3. The isotope amount ratio measurement precision, measured for 15 injections over a 6–8 hour period, is good for both methods (1.6% for HPLC-ICP-MS and 1.7% for GC-ICP-MS). The uncertainty estimates provided by HPLC-ICP-MS tend to be larger than for GC

separations. This is a result of broader peaks (50–60s by HPLC, compared to 4–6s by GC) and greater baseline noise.

Detection limits for sediment analysis are estimated by peak height measurements (3s) as 3 pg TBT as Sn for HPLC-ICP-MS and 0.03 pg TBT as Sn for GC-ICP-MS with 5% O₂ addition. This demonstrates the superior sensitivity of GC-ICP-MS even without sample preconcentration.

The accuracy of the analytical procedure was evaluated by measuring extractions of the certified reference sediment PACS-2 (NRC, Canada). The mean mass fraction obtained by the HPLC-ICP-MS analysis of four extracts was 864 ±35 ng g⁻¹ TBT as Sn compared to a certified value of 980 ±130 ng g⁻¹ TBT as Sn.

Table 3. TBT Data for Sediment Extracts

Sample	HPLC-ICP-MS (ng/g as Sn) n = 4	Standard uncertainty k = 1 (ng/g as Sn)	GC-ICP-MS (ng/g as Sn) n = 4	Standard uncertainty k = 1 (ng/g as Sn)
1	827	19	853	12
2	805	38	846	13
3	845	9	838	8
Mean	826	22	846	11
Expanded uncertainty (k = 2)	±87		±39	




Figure 2. HPLC-ICP-MS chromatogram.




Figure 3. GC-ICP-MS chromatogram.

Conclusions

Both HPLC-ICP-MS and GC-ICP-MS offer advantages for organotin speciation analysis. While there is no statistical difference in the results obtained, HPLC-ICP-MS can be used for cheaper and faster determinations of large sample batches, while the superior sensitivity and the greater number of analytes separated make GC-ICP-MS an ideal tool for monitoring studies at the ultratrace level.

References

1. S. Nicklin and M. W. Robson, (1988) *Applied Organometallic Chemistry*, **2**, 487–508.
2. H. Tao, R. B. Rajendran, C. R. Quetel, T. Nakazato, M. Tominaga, and A. Miyazaki, (1999) *Anal. Chem.*, **71**, 4208–4215.
3. J. C. Keithly, R. D. Cardwell, and D. G. Henderson, (1999) *Hum. Ecol. Risk Assess.*, **5**, No. 2, 337–354.
4. A. Sadiki, and D. T. Williams, (1996) *Chemosphere*, **32**, 12, 2389–2398.
5. S. Takahashi, H. Mukai, S. Tanabe, K. Sakayama, T. Miyazaki, and H. Masuno, (1999) *Environmental Pollution*, **106**, 213–218.
6. R. B. Rajendran, H. Tao, T. Nakazato, and A. Miyazaki, (2000) *Analyst*, **125**, 1757–1763.
7. J. L. Gomez-Ariza, J. A. Pozas, I. Giraldez, and E. J. Morales, (1998) *J. Chromatogr. A.*, **823** (1–2): 259–277.
8. I. A. Leal-Granadillo, J. I. Garcia-Alonso, and A. Sanz-Medel, (2000) *Anal-Chim-Acta.*, **423** (1): 21–29.
9. J. P. Snell, I. I. Stewart, R. E. Sturgeon, and W. J. Frech, (2000) *J. Anal. At. Spectrom.*, **15** (12): 1540–1545.
10. J. R. Encinar, P. R. Gonzalez, J. I. Garcia Alonso, and A. Sanz-Medel, (2002) *Anal. Chem.*, **74**, 270–281.
11. P. G. Sutton, C. F. Harrington, B. Fairman, E. H. Evans, L. Ebdon, and T. Catterick, (2000) *Applied Organometallic Chemistry* **14**, 1–10.
12. Agilent Technical Note “GC-ICP-MS Interface” publication 5988-3071EN.
13. C. G. Arnold, M. Berg, S. R. Müller, U. Dommann, and R. P. Schwarzenbach, (1998) *Anal. Chem.*, **70**, 3094–3101.
14. T. Catterick, B. Fairman, and C. J. Harrington, (1998) *J. Anal. At. Spectrom.* **13**, 1109.
15. *Guidelines for achieving high accuracy in isotope dilution mass spectrometry*, edited by M. Sargent, C. Harrington, and T. Harte RSC London, 2002.

Acknowledgments

The work described in this application note was supported under contract with the Department of Trade and Industry (UK) as part of the National Measurement System Valid Analytical Measurement (VAM) program.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
August 7, 2002
5988-6697EN



Agilent Technologies



Measuring Elemental Ratios in Corals by LA-ICP-MS

Application

Environmental

Author

Stewart Fallon
The Australian National University
E-mail: Stewart.Fallon@anu.edu.au

Malcolm McCulloch
The Australian National University
E-mail: Malcolm.McCulloch@anu.edu.au

Michael Shelley
The Australian National University
E-mail: Mike.Shelley@anu.edu.au

Abstract

A rapid analytical technique of laser ablation inductively coupled plasma mass spectrometry was developed to measure trace element constituents in corals and hard sponges. This technique is illustrated by measuring B, Mg, Ca, Mn, Zn, Sr, Ba and U in a *Porites* coral collected from the Great Barrier Reef, Australia. The accuracy of laser ablation inductively coupled plasma mass spectrometry for the measurement of Sr/Ca and Ba/Ca in corals by comparison with solution isotope dilution inductively coupled plasma mass spectrometry is discussed. We demonstrate the significance of the Sr/Ca ratio by correlation with in situ sea surface temperature data to show that Sr/Ca in corals provides a means to retrospectively measure sea surface temperature prior to available instrumental records. Coral Ba/Ca ratios as an indicator of riverine sediment input during times of runoff into the Great Barrier Reef are also examined.

Introduction

General circulation models (GCM's) describe the time-evolving circulation and thermodynamics of the atmosphere and oceans, the two main components of the Earth's climate system. Understanding the processes that control the Earth's climate and making accurate predictions of future changes in climate requires computer models of the climate system that are more realistic than those currently available. One of the principal impediments to the development of better models is the lack of accurate reconstructions of paleoclimate records (e.g. sea surface temperature).

Reliable high-resolution paleoclimate records are needed to understand the patterns and mechanisms of natural climate variability. Tropical air-sea interactions that affect the global distribution of water vapor (the most potent greenhouse gas) are largely dependent on sea surface temperature (SST) and sea surface salinity. Therefore, understanding the sensitivity of tropical SST and salinity in response to major global climate change is of particular importance. Until a good understanding of natural climate variability is obtained, the impacts on climate attributable to anthropogenic causes (increases of CO₂, etc.) cannot be fully understood.

An organism capable of providing this information is reef-building coral (Figure 1). Corals provide a continuous "time series record" of the marine environment through chemical records preserved in their aragonite skeletal lattice. Elemental ratios



Agilent Technologies

(Sr/Ca) in corals have been shown to provide geochemical proxies for reconstructing the SST during the corals growth. Obtaining long time series by traditional methods (thermal ionization mass spectrometry, solution ICP-MS) is very time consuming and expensive. The development of rapid multi-element analysis by laser ablation inductively coupled plasma mass spectrometry (LA-ICP-MS) improves the quantity and quality of information that can be extracted from corals, an essential prerequisite for their practical application as environmental proxies.



Figure 1. A diver drilling a Porites coral to obtain a core for geochemical analysis.

LA-ICP-MS is gaining wide use as an analytical tool for the analysis of trace elements in a diverse range of sample materials. Semi-quantitative and quantitative elemental concentrations using LA-ICP-MS are being reported using chemically and matrix-matched standards as well as the NIST Standard Reference Material glass suite (NIST 610, 612, 614). Laser ablation has the technical advantage of analyzing elements in situ without time-consuming sample dissolution, thereby providing a rapid and relatively non-destructive technique. In this paper, we describe the LA-ICP-MS method used to measure the Sr/Ca ratio in corals as a monitor of sea surface temperature variations and the Ba/Ca ratio as an indicator of terrestrial runoff from the Great Barrier Reef.

Experimental

Coral Collection

The massive Porites coral can live for hundreds of years. To measure elemental ratios in corals, we

take a core from the center of the coral colony using an underwater drilling system (Figure 1). The 5-cm diameter core is sliced into 7-mm thick slabs and X-rayed to show the growth bands (Figure 2). The coral is then cut into 45 × 25 mm pieces to fit into the laser-sampling chamber.




Figure 2. X-Ray positive of a Porites coral core slab. Light and dark bands correspond to different coral skeletal densities and growth. The red line indicates the track the laser follows along a main growth axis.

ICP-MS

Our LA-ICP-MS system uses an ArF excimer laser (193 nm wavelength) coupled to an Agilent 7500s. The operating parameters for the ICP-MS are listed in Table 1. The laser system consists of an in-house constructed sample chamber that holds a 45 × 25 mm coral piece for ablation. The laser illuminates a rectangular aperture which is imaged onto the flat surface of a coral slice and with each laser pulse ablates a rectangle 0.1 microns deep, 50 μm wide parallel to the growth axis, and 500 μm wide perpendicular to the growth axis (Figure 3). This rectangular laser beam is a crucial component of LA-ICP-MS of corals to ensure representative analysis across the interlocking branch-like structural elements of the corals. The long focal length (150 mm) of our excimer laser optical system and this large sampling window minimizes the depth related fractionation observed for material removed from the bottom of holes. The time resolution depends on the growth rate of the coral and the slit width, and we usually obtain sub-weekly resolution in corals (>100 samples year⁻¹). The fast mass switching (1 msec mass to mass, or 2 msec for large jumps) and high sensitivity of the 7500s allows us to measure many elements together without compromising this spatial resolution. A significant time interval between masses would result in noisy element ratios because a combination of the

coral surface topography and the sample cell and carrier gas transport system gives signal intensity variations with about a 1-second time constant. The laser has a pulse length of 25 nsec and the power density on the sample surface is 0.32 GW/cm^2 .

For coral analysis, the laser is pulsed at 5 Hz. The material is ablated in helium and entrained in argon for analysis by ICP-MS. A side view of the laser sample cell is shown in Figure 4. The isotopes ^{10}B , ^{25}Mg , ^{46}Ca , ^{55}Mn , ^{66}Zn , ^{84}Sr , ^{138}Ba and ^{238}U are measured with ^{46}Ca (0.004% abundance) as an internal standard to compensate for variations in ablation yield due to coral surface porosity. The data is standardized to a pressed powder disc

Table 1. Agilent 7500s Operating Parameters

	Laser Mode
ICP-MS	Agilent 7500s
Forward power	1250 W
Reflected power	< 1 W
<i>Gas flow rate:</i>	
Cool gas	14 L min ⁻¹
Carrier gas Ar	1.14 L min ⁻¹
Optional gas He (into cell)	0.3 L min ⁻¹
Cone composition	Nickel
Detector mode	Dual simultaneous
Acquisition mode	Time resolved
Isotope dwell time	25 to 60 ms
Points per peak	3
Time slice	~ 1 s




Figure 3. Laser sampling on a coralline sponge showing parallel tracks (right side) and close up of boxed section (left side) of the laser sampling slit. Laser tracks are not visible on corals due to surface porosity.




Figure 4. Side view of the laser sample cell. Coral is ablated in a sealed Perspex chamber under a helium atmosphere. The sample stream is entrained in argon and enters a smoothing manifold before entrance to the Agilent 7500s ICP-MS. The sample is viewed by CCD video camera. A DC motor with a high-ratio gearbox scans the sample beneath the laser, enabling continuous sampling.

prepared from a cleaned and finely crushed Porites coral from the Great Barrier Reef. Some other elements we routinely measure are lead and rare earth elements. They are standardized using the NIST 614 glass. The dual simultaneous detector system of the Agilent 7500s enables us to measure the low concentration elements (manganese and zinc) simultaneously with the more abundant elements (Figure 5).

The analytical procedure is shown in Figure 5. Background and standards are collected for 60 seconds each before and after the coral analysis, a motor scans the coral sample and standards beneath the laser at a speed of 0.03 mm s^{-1} . The entire protocol takes around 40 minutes for each piece of coral.

Results and Discussion

Accuracy: Comparison with Isotope Dilution Solution ICP-MS

One of the methods used to check the accuracy of LA-ICP-MS was analysis of three other calcium carbonate samples. A coral from the Huon Peninsula, Papua New Guinea, an aragonite coralline sponge and a calcite coralline sponge were finely crushed and pressed to form pellets. The Sr/Ca and Ba/Ca




Figure 5. LA-ICP-MS protocol for coral analysis, in counts per second for each isotope.

concentration of the bulk powders was measured by isotope dilution solution ICP-MS. The pressed powder samples were also analyzed with LA-ICP-MS by scanning 2 to 3 mm long sections. The coral sample was measured 12 times over a 1-month period, the aragonite sponge sample 50 times over a 3-month period and the calcite sponge sample five times in 1 day. The LA-ICP-MS and solution measurements agree within the statistical error (Figure 6). Using a pressed powder

standard constructed from a calibrated coral provides accurate fully quantitative LA-ICP-MS for CaCO_3 (corals and sponges) with differing concentrations.

Sea Surface Temperature Proxy: Sr/Ca

A Porites coral from the Great Barrier Reef was analysed with the LA-ICP-MS. The comparison between the coral Sr/Ca ratio and the known sea




Figure 6. Accuracy of LA-ICP-MS method. Comparing solution ID ICP-MS (x axis) with LA ICP-MS (y axis) of three samples, a calcite sponge, a coral, and an aragonite sponge. Error bars and linear regression for the three samples are shown. A) Sr/Ca B) Ba/Ca.

surface temperature for about 90 mm of the core is shown in Figure 7. The correlation coefficient between the two data sets is $r = -0.93$, or approximately 86% of the Sr/Ca variation is attributable to SST, indicating the value of coral Sr/Ca as a SST proxy. Sr/Ca has been measured by various labs and in many corals from different locations and it has been proven to be robust in terms of its ability to record SST. With such a calibration between Sr/Ca and SST, it is possible to reconstruct water temperatures before the advent of instrumental records from a particular reef.

Terrestrial Runoff: Ba/Ca

The Ba/Ca ratio in corals can be influenced by the upwelling of nutrient rich water, and in coastal corals by river runoff. This coral was collected

from near shore on the Great Barrier Reef (GBR) near a major river system, the Burdekin. Sediment input to the GBR has elevated levels of barium, and heavy river flooding brings higher than normal barium into the surrounding seawater. The inshore corals of the Great Barrier Reef register floods by an increased Ba/Ca ratio. The influence of river runoff on GBR corals is also recorded as luminescent or fluorescent lines/bands in the coral skeletons. This coral records the floods of 1996, 1997 and 1998 (Figure 8). The relation between river discharge and coral Ba/Ca is not necessarily linear; with factors such as wind and ocean current conditions affecting the path of the flood plumes. Nevertheless the Ba/Ca runoff proxy in corals can be used as an indicator of sediment input into the GBR and for other areas around the globe.




Figure 7. Measured coral Sr/Ca in red (right. axis) vs. in situ sea surface temperature record in black (left axis).




Figure 8. Comparison between terrestrial runoff (Burdekin River in mega liters, log scale) on the left axis and Coral Ba/Ca (mol/mol) on the right axis.

Conclusions

Laser ablation inductively coupled plasma mass spectrometry (LA-ICP-MS) provides a rapid analytical technique for measuring B, Mg, Ca, Mn, Zn, Sr, Ba and U concentrations in corals. The power of this technique lies in its ability to measure these elements simultaneously with appropriate spatial resolution regardless of coral growth rate.

Researchers have collected long coral cores spanning several centuries from various locations throughout the globe but producing long time series at monthly or higher resolution has previously been very time consuming and prohibitively expensive. The LA-ICP-MS discussed here makes it practical to produce long high-resolution climate reconstructions from corals, to enable a greater understanding of the role of the oceans in the dynamics of the Earth's climate.

Further Reading

Fallon S. J., McCulloch M. T., van Woesik R., and Sinclair D. J. (1999) *Corals at their latitudinal limits: Laser ablation trace element systematics in Porites from Shirigai Bay, Japan*. Earth Planet. Sci. Lett. 172(3-4), 221-238.

McCulloch M. T., Tudhope A. W., Esat T. M., Mortimer G. E., Chappell J., Pillans B., Chivas A. R., and Omura A. (1999) *Coral record of equatorial sea-surface temperatures during the penultimate deglaciation at Huon Peninsula*. Science 283, 202-204.

Sinclair D., Kinsley L., and McCulloch M. (1998) *High resolution analysis of trace elements in corals by laser ablation ICP-MS*. Geochim. Cosmochim. Acta 62(11), 1889-1901.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
November 13, 2001
5988-3742EN



Agilent Technologies



Automated Real-Time Determination of Bromate in Drinking Water Using LC-ICP-MS and EPA Method 321.8 Application

ICP-MS

Author

Jason A. Day, Anne Vonderheide, Joseph A. Caruso
University of Cincinnati
Cincinnati, OH 45220
USA

Thomas J. Gluodenis, Jr.,
Agilent Technologies Inc.,
2850 Centerville Rd,
Wilmington, DE 19808
USA

Abstract

The suitability of coupling an HPLC to an ICP-MS for the fully automated, routine analysis of bromate in drinking water as per the proposed EPA Method 321.8 was investigated. The necessity to monitor the carcinogen bromate in ozonated drinking waters at single ppb levels has led the USEPA to investigate HPLC-ICP-MS as an alternative technique to the ion chromatography with conductivity detection method currently specified. During this investigation, a series of rigorous performance checks were used to assess the implementation of the proposed method including the determination of bromate in a series of EPA disinfection byproduct (DBP) standards.

Introduction

Ozonation is a common method used for the disinfection of drinking waters. In waters containing bromide (Br^-), such as those found in coastal regions subject to salt-water intrusion, a disinfection byproduct (DPB) of the ozonation process is the bromate ion (BrO_3^-). The bromate ion, produced by the oxidation of bromide, is very carcinogenic, with an estimated lifetime cancer risk of 1:10,000

for a concentration of 5 ppb.¹ The current method specified by the USEPA for the determination of bromate in drinking water uses ion chromatography (IC) with conductivity detection. One disadvantage of this method is the need for a tedious and time consuming sample pretreatment step.

The need for sample pretreatment arises from the potential for co-elution of chloride and bromide ions present in the sample, potentially resulting in false positive results. In order to prevent this from occurring, chloride present in the sample is precipitated out of solution using silver cartridges with subsequent pre-concentration of the bromate ions. This time consuming and lengthy clean-up procedure and pre-concentration step can result in pre-concentration of sulfate ions present in the water. Sulfate can subsequently displace the bromate ions on the resonating column resulting in false negatives.

For these reasons, ICP-MS has been investigated as an alternative, ion selective detector for this analysis. ICP-MS provides the resolution necessary to separate the bromate and chloride ion, thereby eliminating the need for a matrix elimination step. Furthermore, ICP-MS has been used successfully for the analysis of bromate in water samples containing concentrations of chloride in excess of 5000 ppb - much higher than the typical content of ozonated drinking water - without the need for sample pretreatment.²

This study will investigate the suitability of ion chromatography coupled to ICP mass spectrometry (ICP-MS) as an automated, real-time measurement approach, to determine low levels of bromate in ozonated drinking water samples, using the proposed EPA Method 321.8.³



Agilent Technologies

Instrumentation

The Agilent Technologies 1100 Series HPLC system, coupled to a 7500 Series ICP mass spectrometer using the real-time Plasma Chromatographic software was used for this study. This system was specifically designed for the rigors of automated trace element speciation work, mainly in response to laboratory demands, particularly in the environmental, clinical and food application areas, that need to carry out routine elemental speciation. Its design takes advantage of Agilent's expertise in chromatography and its recognized leadership position in ICP-MS.

During the past few years, the potential of ICP-MS as a detector for elemental speciation studies has been realized.⁴ When coupled to a chromatographic separation device, ICP-MS offers unmatched detection capability for laboratories interested in quantifying different species, forms, oxidation states or biomolecules associated with trace elements.^{2,5} Traditional approaches of coupling ICP-MS to chromatography devices are cumbersome, labor intensive and not readily automated. In fact, the majority of ICP-MS chromatography data handling software packages were designed specifically for liquid and gas chromatography (LC, GC) applications and required modification for use with ICP-MS. Some approaches even analyzed the chromatographic spectral peaks "post-run", meaning the data had to be imported into another software package after the analysis was completed, for quantitation purposes. It was clear that there was a real demand for a fully automated system, designed specifically for trace element speciation analysis. Agilent Technologies answered that demand with a fully integrated package for trace element speciation, comprising an 1100 Series HPLC system, coupled to a 7500 Series ICP mass spectrometer, using the Agilent ChemStation and real-time Plasma Chromatographic software.⁶

Methodology

ICP-MS Conditions

The ICP-MS instrumental conditions were optimized to give maximum signal at m/z 79, the most sensitive mass for Br. Because bromine is not completely ionized in argon ICP, sampling depth,

nebulizer flow, RF power and ion lens voltages have to be optimized very carefully to guarantee the most efficient sampling of bromide ions. Operating conditions for the 7500 are shown in Table 1. These conditions gave an instrument response of 110,000 cps for a 100 ppb bromate standard, with a background of 1,800 cps (partially due to trace levels of bromide in the 18 M Ω deionized water).

Table 1: Optimized Operating Conditions for ⁷⁹Br Using the Agilent 7500 ICP-MS

Parameter	Optimized conditions
Nebulizer	Meinhard concentric - glass
Nebulizer flow rate	1.05 L/min
Spray chamber	Scott double pass - glass
Spray chamber temperature	2 °C
Sample flow rate	1 mL/min
RF power	1200 W
Sampling depth	Optimized for max signal at ⁷⁹ Br
Ion lens voltages	Optimized for max signal at ⁷⁹ Br

Chromatographic Conditions

See Table 2 for the chromatographic conditions for the separation. The column eluent was passed via a short length of PEEK tubing to a six-port Rheodyne injector equipped with a 100 μ L (or 500 μ L depending on the measurement) PEEK loop. A post column injection was performed at the beginning of each run (for internal standard purposes, specified in the proposed EPA Method) at the exact time the data acquisition began on the ICP-MS. See Figure 1 for a schematic of the HPLC instrumentation coupled to the ICP-MS.

Table 2: Chromatographic Conditions for the Bromate Study

Parameter	Specification
Eluent mobile phase	25 mM Ammonium nitrate, 5 mM Nitric acid (~pH 2.7) in 18 M Ω Deionized water
Injection volumes	100 μ L, 500 μ L loops
Post-column injector	Used for internal standardization
Pump flow rate	1 mL/min
Column	Dionex CarboPac PA-100 (94 $\times$ 250 mm) - with guard




Figure 1: A schematic of the 1100 HPLC instrumentation coupled to the 7500 ICP-MS used for the bromate study.

Sample Preparation

The blank was 18 MΩ deionized water adjusted to pH 10 with NaOH. Standards were prepared daily from a USEPA 1 mg/mL bromate stock solution.

Demonstration of Instrument and Method Performance

As a way of maintaining data quality, the EPA uses performance checks to monitor the instrument and also ensure that the methodology is working correctly. Some of the more important performance checks for this proposed EPA method 321.8 include the measurement of:

- Abundance Sensitivity of ICP Mass Spectrometer
- Method Detection Limit
- Chromatographic Interferences
- Laboratory Fortified Blank
- Laboratory Fortified Matrix
- DBP Performance Sample

These measurements were used to assess the performance of the integrated system used for this study.

Abundance Sensitivity

A large argon dimer, $^{40}\text{Ar}^{40}\text{Ar}^+$ at mass 80 adjacent to the bromate ion $^{79}\text{Br}^+$ at mass 79, has the potential to bias results in the determination of bromate by ICP-MS. It is therefore critical that the abundance sensitivity, which is a measure of the instrument's ability to separate a trace peak from a major one,⁷ is optimized to allow for maximum rejection of the ions at mass 80. The very high operating vacuum of the 7500, and the high frequency of its quadrupole, combined with optimization of the rod-bias voltages, ensures that it achieves clean separation of both peaks, even at a mass of 79.5 amu, where the tail of the $^{40}\text{Ar}^{40}\text{Ar}^+$ might interfere with the Br^+ at mass 79. The excellent abundance sensitivity of the quadrupole's hyperbolic rods is demonstrated in Figure 2, which shows a spectral scan of 2% HNO_3 . The effect of the large signal at mass 80 is shown to have minimal affect on the small bromine signal at mass 79.




Figure 2: Mass spectrum showing clean separation of $^{79}\text{Br}^+$ from the argon dimer $^{40}\text{Ar}^{40}\text{Ar}^+$.

Method Detection Limit (MDL)

Two method detection limits were performed - one using a 500 μL loop, as specified in the method, and another using a 100 μL loop. A blank and three calibration standards (1, 5, and 25 ppb bromate) were used for both method detection limit tests.

Seven individually prepared bromate standards of 1 ppb (for the 100 μL loop) and 0.5 ppb (for the 500 μL loop) were then analyzed to determine the method detection limit (MDL). From this, an MDL was calculated for each loop by multiplying the standard deviation of the seven replicate results by 3.14, as indicated in the EPA method. Individual MDL replicate concentrations and statistics for both loops are shown in Table 3.

Table 3: Method Detection Limit Data for a 100 μL and 500 μL Loops

Replicate #	100 μL Loop Concentration (ppb)	500 μL Loop Concentration (ppb)
MDL-1	1.1	0.46
MDL-2	0.98	0.39
MDL-3	0.77	0.35
MDL-4	0.77	0.46
MDL-5	0.97	0.45
MDL-6	0.83	0.48
MDL-7	0.90	0.41
Mean	0.90	0.42
SD	0.131	0.044
RSD (%)	14.6	10.5
MDL	0.41	0.14

Chromatographic Interferences

To show that other halogenated compounds do not elute at similar retention times as bromate, a haloacetic acid standard (HAA) standard solution, provided by the EPA, was analyzed. The stock solution was diluted 1:100 yielding final concentrations of six different halogenated compounds reported in Table 4.

Table 4: Concentrations of Six Haloacetic Acid Compounds that Could Potentially Interfere with the Determination of Bromate

Compound	Concentration (ppb)
Monochloroacetic acid	15
Dichloroacetic acid	15
Trichloroacetic acid	5
Monobromoacetic acid	10
Dibromoacetic acid	5
Bromochloroacetic acid	10

A chromatogram containing the haloacetic acid mixture and a 10 ppb bromate standard is shown in Figure 3. The retention time for bromate is 3.5 minutes. The bromine-containing HAA standards elute at 2.5 minutes, 5.9 minutes and 7.1 minutes indicating no chromatographic interference with bromate. Average bromate recovery ($n = 2$) for this standard spiked with 10 ppb bromate was 102%.




Figure 3: A chromatogram containing haloacetic acid mixture and a 10 ppb bromate standard.

Laboratory Fortified Blank

Ten replicates of a laboratory-fortified blank (LFB) were analyzed at a concentration of 5 ppb, which was approximately ten times the MDL. The LFB samples consisted of 18 MΩ deionized water adjusted to pH 10 with NaOH and spiked with 5 ppb bromate standard. The average for the replicates was 4.7 ppb (8.9% RSD) with a 93% recovery.

Laboratory Fortified Matrices

Four fresh samples supplied by the EPA, taken from ozonation utilities in the U.S., were analyzed using this methodology. Each sample was adjusted to pH 10 with NaOH, and analyzed twice, unfortified and fortified with 10 ppb bromate. The results for all four samples are shown in Table 5. The recovery results for these matrices are all within the EPA guidelines of 70-130% for this method.

Table 5: Bromate Results from Ozonation Utilities

Sample ID	Concentration of bromate in unfortified sample (ppb)	Concentration of bromate in fortified sample (ppb)	% Recovery
A	2.0	12	102%
B	2.7	12	89%
C	4.0	16	118%
D	8.9	18	100%

USEPA DBP Performance Evaluation Check

An EPA check ampule (USEPA ICR PE ampule for inorganic DBPs - Study 9), whose concentration was not known at the time of analysis, was also analyzed as a blind check sample. The ampule was prepared in duplicate by diluting 1:100 and analyzing immediately. Results are shown in Table 6. Once again, the recoveries are both within the recommended guidelines.

Table 6: Recovery of Inorganic DBPs in EPA Check Ampules

Sample	Concentration in original ampule (ppb)	% Recovery (917 ppb true value)
Ampule 1	1120	120
Ampule 2	1040	113

Conclusion

The ability to measure bromate in ozonated drinking waters at sub-ppb levels is essential to understanding its risk assessment as a carcinogen. Once USEPA Method 321.8 is validated for use, ICP-MS detection coupled to HPLC will become an approved method for achieving this. It has been shown that the instrumentation used in this study surpasses all the performance criteria specified in

the methodology, achieving a method detection limit of 0.14 ppb, with a 500 µL loop and 0.41 ppb with a much smaller injection volume (100 µL). Furthermore, this has been implemented in an automated fashion with real time data analysis using the Agilent 1100 LC and 7500 Series ICP-MS demonstrating that the technique is well suited for use as a routine analytical tool.

References

1. WHO, *Guidelines for Drinking Water Quality*, 2nd Edition, Vol. 1, Recommendations of the World Health Organization, 1993
2. J. T. Creed, M. L. Magnuson, J. D. Pfaff, C. A. Brockhoff, *Journal of Analytical Chromatography*. 753, 261-267, 1996.
3. Determination of bromate in drinking waters by ion chromatography inductively coupled plasma - mass spectrometry. *USEPA Method 321.8*
4. M. Yamanaka. Specific determination of bromate and iodate in ozonized water by ion chromatography with two detection methods: Post-column derivatization and ICP-MS. *Journal of Analytical Chromatography*, 779, 259-265, 1997
5. J. T. Creed, M. L. Magnuson, C. A. Brockhoff, *Environmental Science and Technology*. 31, 2059-2063, 1997.
6. Technical Features of the ICP-MS Plasma Chromatographic Software: *Agilent Technologies Application Note* 5968-5943EN, Feb 2001
7. Practical Benefits of Abundance Sensitivity in ICP-MS: *Agilent Technologies Application Note* 5964-9024EN, Feb 2001


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright© 2001
Agilent Technologies, Inc.

Printed in the USA
June 22, 2001
5988-3161EN





Determination of Mercury in Drinking Water Samples by ICP-MS Using EPA Method 200.8

Application Note Environmental



Abstract

The quantitative determination of mercury in drinking water samples, simultaneously with 20 other elements (as described in the EPA Method 200.8) is presented. To avoid the Hg memory effects normally experienced with conventional nebulizer/spray chamber sample introduction systems, gold was added off-line to all standards and samples to act as a complexing agent. The addition of gold and the design of the 4500 ICP-MS assure fast washout time and allow the determination of all elements, including mercury, in drinking water by a single ICP-MS run.



Introduction

EPA Method 200.8¹ describes the multi-element determination of trace metals waters and wastes by inductively coupled plasma-mass spectrometry (ICP-MS). This method provides procedures for determination of dissolved elements in ground waters, surface waters and drinking water. It may also be used for the determination of total recoverable element concentrations in these waters as well as waste waters, sludges and solid waste samples. EPA Method 200.8 is applicable to 21 elements, including mercury, enabling all required elements to be analyzed by a single technique - ICP-MS. This application note describes the additional sample preparation necessary for the successful determination of mercury.

As stated in the method, samples may be analyzed directly by pneumatic nebulization without acid digestion if the samples have been properly preserved with acid and have turbidity of < 1 NTU at the time of analysis. This total recoverable determination procedure is referred to as *direct analysis* (section 1.4 - EPA Method 200.8).

For the *direct analysis* of water samples which do not require digestion/extraction prior to analysis, and for which turbidity is < 1 NTU, the combined concentrations of inorganic and organo-mercury species in solution can be determined provided gold is added off-line to both samples and standards alike (section 1.6 - EPA Method 200.8)¹.

System Design

The 4500 ICP-MS was developed with the routine user in mind: innovative hardware and software design has resulted in the automation of routine tasks such as the optimization of ion lenses, plasma conditions, and adjustment of the ICP torch position. By making optimization independent of the operator, performance becomes more consistent, even in a multi-user environment.

A programmable computer-controlled peristaltic pump system allows for a selection of the optimum rinse time to accommodate both high sample throughput and effective elimination of memory effects. An example of a peristaltic pump program is shown in Figure 1.

The pump speed and time both before acquisition (sample uptake) and after acquisition (rinse) can be set by the user. Pumping the sample into the system at high speed reduces sample uptake time, and a stabilization time allows the system to stabilize at the normal acquisition uptake rate prior to the commencement of data acquisition. The system can also be programmed to rinse longer after standards than samples, minimizing total rinse time. A second optional rinse following acquisition is also available, enabling the use of two different rinse solutions for special applications.

Memory Interferences

Memory interferences, commonly referred to as *memory effects* arise when analyte signal is enhanced due to contribution

Peristaltic Pump Program

Before Acquisition

Uptake Speed: 0.50 rps

Uptake Time: 45 sec

Stabilization Time: 5 sec

After Acquisition (Rinse Port)

Rinse Speed: 0.50 rps

Rinse Time(Sample): 5 sec

Rinse Time(STD): 5 sec

After Acquisition (Optional Rinse)

Rinse Vial: 2

Rinse Speed: 0.50 rps

Rinse Time: 15 sec

OK Cancel Help

Figure 1.
Peristaltic Pump Program

from a previous high concentration sample. Memory effects can result from the adsorption/desorption of the analyte anywhere in the sample introduction system: Peristaltic pump tubing, nebulizer, spray chamber, torch or interface.

In acidic solution, mercury has a tendency to be retained on the glassware, particularly on the injector tip of the torch and in the spray chamber. As a result, the analyst has to program long washout times, and the aspiration of a sample containing very high levels of mercury will require the sample introduction system to be dismantled and thoroughly cleaned. The off-line addition of gold to the sample solution dramatically reduces washout times, since gold complexes with mercury presumably forming an amalgam, allowing it to be washed effectively from the system. The addition of gold to both standards and samples enables determination of mercury in the same analysis as for the other 20

elements in the EPA Method 200.8, allowing all elements to be measured in a single run by ICP-MS alone.

Instrumentation

The instrument used for this work was a 4500 ICP-MS fitted with a Babington-type nebulizer, glass spray chamber and quartz one-piece torch. An ASX-500 autosampler (CETAC Technologies Inc., Omaha, NE), was also fitted.

Reagents, Standards and Labware

The importance of good quality of reagents used was discussed in the Agilent Application Note (publication No. 5964-4277E)². For this work, a Milli-Q SP point-of-use deionized water system (Millipore, Bedford, MA) was used to prepare all standards.

Plasma gas flow rate	15.0 L/min	
Aux. gas flow rate	1.0 L/min	
Carrier gas flow rate	1.17 L/min	
RF Power	1300 W	
Nebulizer	PEEK, Babington - type	
Spray chamber	Glass, double pass	
Spray chamber temp	1 deg C	
ICP torch injector	Quartz, 2.5 mm	
Sample uptake rate	0.4 mL/min	
Sampler cone	Nickel	
Skimmer cone	Nickel	
Sampling depth	6.4 mm	
Acquisition parameters	Quantitative	Monitoring
Points/mass	3	6
Integration time/mass	0.99 sec	0.6 sec
Total acquisition time/replicate	36 sec	139 sec
Replicates	3	1
Total acquisition time/sample	109 sec	139 sec

Table 1.
4500 ICP-MS Operating Parameters

Fresh mercury standards were prepared daily from a 10 mg/L (ppm) stock solution. Gold was added off-line to all standards and

samples at the level of 100 mg/L (ppb), along with the internal standard (Tb at 50 µg/L). Both standards were prepared from




Figure 2.
Monitoring of the Mercury Washout Time

1,000 mg/L stock solutions (Inorganic Ventures, Lakewood, NJ). All standards and samples were acidified with 1% (v/v) ultrapure nitric acid (Optima Grade - Fisher Scientific, Pittsburgh, PA)

Experimental

To study the effect of gold addition on mercury washout, a 5 µg/L Hg solution was spiked with 100µg/L Au and aspirated by the 4500 ICP-MS. The washout of the mercury signal with a gold wash solution was measured by monitoring the signal in time resolved mode. Two mercury isotopes were monitored, plus bismuth for the purpose of background monitoring. Figure 2 shows the washout characteristics observed for a 5 ppb mercury standard solution. For ²⁰²Hg, the signal counts measured at readings signal counts 30 seconds apart are shown. Two orders of magnitude washout for mercury was achieved in less than one minute, demonstrating much better washout than in acidic solution without the addition of gold. Operating parameters for both the washout study and routine quantitative analysis are given in Table 1.

A graphical representation of the acquisition method printed from the Agilent ChemStation software is shown in Figure 3. This method was applied for all 21 elements listed in EPA Method 200.8, including Mercury. A mercury calibration containing standards at 0, 2 and 5 ppb Hg was constructed and is shown in Figure 4. Terbium (mass 159) was used as the internal standard (IS). As can be seen, an excellent fit was obtained, and from the slope of the curve, detection limits in the low ng/L range can be estimated.

Figure 3. Acquisition Parameters for Quantitative Determination of 21 Elements (including Mercury) by ICP-MS According to EPA Method 200.8




Figure 4. Mercury Calibration Curve (Tb used as internal standard)

EPA Method 200.8 (section 7.4.1) specifies the maximum concentration of the calibration standard to be 5 ppb.

Conclusions

The determination of mercury has been shown to be easily incorporated into the standard multi-elemental analysis protocol of water samples using ICP-MS. Mercury carry-over was readily eliminated by the off-line addition of gold. This procedure allowed the analysis of mercury in the same run as the other analytes, enabling the measurement of all required elements by a single instrument. The addition of gold to the samples at the time of collection will minimize losses of mercury in sampling vessels.

References

- ¹ EPA Method 200.8 EMMC version. Revision 5.4. EMSL Cincinnati OH 45268 - May 1994
- ² Analysis of Drinking Water and Waste Water by ICP-MS Using EPA Method 200.8. Agilent Application Note (publication No5964-4277E), December 1997

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5965-5383E



Agilent Technologies

Innovating the HP Way



The Determination of As in Samples Containing High Concentrations of Chloride by ICP-MS

Technical Note

Michiko Yamanaka

Introduction

One of the main advantages of ICP-MS over ICP-AES is its relative freedom from spectral interferences. There are, however, a few cases where spectral overlap is a problem. One example is the determination of As in samples containing high (%) levels of chloride. The polyatomic ion $^{40}\text{Ar}^{35}\text{Cl}$ interferes with ^{75}As , and in addition $^{40}\text{Ar}^{37}\text{Cl}$ interferes with ^{77}Se . The interference of ArCl on Se is not a problem since a different Se isotope can be selected. As, however is monoisotopic, so no alternate isotope is available. One method to overcome such polyatomic overlaps is to resolve the interference using high resolution. In this case, however, a resolving power of >7500 is required to effectively separate As and ArCl. At this resolution, ion transmission is only $\sim 1\%$ of the transmission at unit mass resolution and so detection limits are compromised.

The 4500 ICP-MS offers the precise, routine determination of As




Fig. 1
Isotopic patterns of As, Se and ArCl

even in very high concentrations of chloride by the use of mathematical correction. Elemental (interference correction) equations resident in the 4500 ICP-MS ChemStation software correct for the interferences on both As and Se simultaneously. Most importantly, the inherent ion signal sta-

bility of the 4500 ICP-MS allows for very precise correction, making it possible for the 4500 ICP-MS to determine As at the ppb and sub-ppb level even in 5% HCl. This technical note examines the effect of increasing Cl concentration on the observed As signal, and determines the ability of the 4500 ICP-



Agilent Technologies

Innovating the HP Way

MS to measure As in HCl. The derivation and use of elemental equations is also explained.

Elemental equations

In samples containing chloride, the ion signal measured at mass 75 is the sum of ^{75}As and $^{40}\text{Ar}^{35}\text{Cl}$. This is shown in Fig. 1, which depicts the elemental ratios of As, Se and ArCl. This diagram is for graphical representation only; the intensities of the bars are arbitrary and do not relate to concentration values of each individual species. Also, Ar_2 species have been omitted for clarity. The ratio of the ArCl species at masses 75 and 77 is the same as the ratio of the Cl isotopes at masses 35 and 37. Therefore, the signal intensity of ArCl at mass 75 can be derived from the ArCl signal at mass 77. However, Se also has an isotope at mass 77, so the presence of Se will increase the observed signal at mass 77. Thus the contribution of Se to the total signal intensity at mass 77 must also be calculated using an alternate Se isotope. For Se correction, mass 82 is normally chosen, since the 78 and 80 isotopes suffer interference from Ar_2 . In practice, this correction is simply and automatically performed by the ChemStation software using elemental equations. In this example, the equation given in EPA method 200.8 (trace metals in drinking water and wastewater by ICP-MS) was used and is shown in Fig. 2.

Influence of Cl Concentration on As Signal

To study the effectiveness of using elemental equations to correct for Cl interference, a series of 1 $\mu\text{g/l}$ (ppb) As solutions were spiked with Cl at 0, 100, 200, 500 and

$$\begin{aligned} &\text{As signal intensity (mass 75)} \\ &= 1.000 * (^{75}\text{C}) - 3.127[(^{77}\text{C}) - (0.815) * (^{82}\text{C})] \\ &= 1.000 * (^{75}\text{C}) - 3.127 * (^{77}\text{C}) + 2.549 * (^{82}\text{C}) \end{aligned}$$

($^{\text{M}}\text{C}$): ICP-MS signal (counts) at mass M

Fig. 2
Elemental equation for As




Fig. 3
Influence of Cl on As signal

1000 mg/l (ppm). The solutions were measured for As, both with and without the use interference correction. A plot of observed As concentration vs. added Cl is shown in Fig. 3. Without correction, the observed As signal increased with added Cl, as expected. At 1000 mg/l Cl, the apparent increase in As was approx. 1 $\mu\text{g/l}$. Using interference correction, however, no increase in As concentration was reported, demonstrating the effectiveness of interference correction. The 4500 ICP-MS generates a very stable ion signal from both elemental and polyatomic ions, allowing precise, reproducible correction for ArCl. Ion signal stability (typically <1%RSD over 2 hours) is due mainly to the mechanical and electronics design of the 4500 ICP-MS, but also partly

due to the precise temperature control of the spray chamber ($\pm 0.1^\circ\text{C}$), enabling a very stable sample aerosol to be generated.

Determination of As in Cl Matrix

To study the effectiveness of applying interference correction to the quantitative determination of As in a chloride matrix, a series of standard solutions in a 5% HCl matrix were prepared. The As concentrations were 0, 1, 5, 10, 50, 100 and 200 $\mu\text{g/l}$. The standards were measured using the 4500 ICP-MS - the operating parameters used are given at the bottom of this page. No internal standards were used. Calibration plots for As were constructed, both with and without interference correction selected. The data was




Fig. 4-1
As calibration plots in 5% HCl without interference correction




Fig. 4-1
As calibration plots in 5% HCl with interference correction

not blank subtracted. The plots shown in Fig. 4-1 were generated without applying interference correction. Although the correlation was good, the high background due to ArCl can be seen. The scale is expanded on the right to show the low concentration points. Below 10 µg/l, the calibration plot becomes essentially flat. In contrast, when interference correction is applied (Fig. 4-2), excellent correlation and linearity were obtained, even at the 1 µg/l level. Clearly, the combination of interference correction and good ion signal stability (elemental and polyatomic) allow the 4500 ICP-MS to precisely determine As even in a chloride matrix. The ability to detect As at sub-ppb levels in the presence of chloride is particularly important to the study of toxic metals in foods, biomedical, environmental and clinical applications. In addition, the demonstrated ability of interference correction to compensate for polyatomic overlap at low ion concentrations can be applied to other classic ICP-MS interferences. Other interferences will be studied in future Agilent Technical Notes.

Operating conditions

RF power	: 1.3 kW
Sampling depth	: 8 mm
Plasma gas	: 16 l/min.
Auxiliary gas	: 1.0 l/min.
Carrier gas	: 1.15 l/min.
Nebulizer	: Concentric type

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5963-9561E



Agilent Technologies

Innovating the HP Way



The Determination of Selenium by ICP-MS, Using the ShieldTorch

Application Note

Ed McCurdy
Glenn Woods



Selenium is an element of considerable interest in environmental and biomedical applications. Several instances of selenium deficiency and toxicity in agricultural livestock have been reported, whilst there is increasing interest in Se as it relates to human physiology.

Se is an essential trace element in humans, but there is a narrow range between Se deficiency and Se toxicity. An excess of Se leads to seleniosis, whilst deficiency has been implicated in coronary heart disease, arthritis, cirrhosis and cancer. Se is available in several forms as a dietary supplement, many of which are derived from yeasts.

The determination of Se by ICP-MS has been one of the most enduring challenges for the technique, due to a combination of factors.



Agilent Technologies
Innovating the HP Way

Firstly, Se is typically present at relatively low levels in natural (uncontaminated) biological materials and the total concentrations present may comprise several different forms of Se, which can have an impact on certain methods of analysis.

Secondly, whilst the Ar plasma is probably the most capable source yet devised for atomic spectrometry, it does suffer from certain limitations with respect to the ionisation environment and the background spectrum. In the case of Se, these two factors conspire to give a low analyte signal level and a relatively high blank signal.

Se has a high first ionisation potential, which means that a smaller proportion of the Se atoms in the plasma are converted into ions. The signal for Se is around 10% of the signal which would be obtained for a fully ionised element, so the signal to noise is about 10x poorer than it could be. Furthermore, all of the Se isotopes are potentially overlapped by polyatomic interferences from plasma or matrix-based peaks, which restricts the choice of Se isotopes which can be used for quantitation. The available Se isotopes and their respective potential overlaps are shown in Table 1.

Clearly, many of these potential interferences are Ar-based, which makes them difficult to avoid in an Ar plasma. Several techniques have been suggested to alleviate the problems associated with these overlaps, each of which has its own advantages and limitations.

The various techniques which have been used are discussed in the following paper, together with

Se Isotopic Mass	Isotopic Abundance (%)	Potential Overlap(s)
74	0.89	$^{36}\text{Ar}^{38}\text{Ar}$
76	9.36	$^{38}\text{Ar}^{38}\text{Ar}$ and $^{36}\text{Ar}^{40}\text{Ar}$
77	7.63	$^{40}\text{Ar}^{37}\text{Cl}$
78	23.78	$^{38}\text{Ar}^{40}\text{Ar}$
80	49.61	$^{40}\text{Ar}^{40}\text{Ar}$
82	8.73	^{82}Kr and $^{81}\text{Br}^1\text{H}$

Table 1.
Selenium Isotopic Abundances and Potential Interferences

a novel approach which relies on the selective ionisation of the analyte in a plasma environment which is optimised for the reduction of the Ar-based polyatomic ions.

Hydride generation can be used for Se measurements, either utilising a stand-alone hydride generation instrument, or using a hydride generation accessory as the sample introduction method for ICP-MS. The transport efficiency of hydride generation is certainly improved over the use of a conventional spraychamber, but there are several chemical limitations to the technique, most notably that all of the Se must be converted to a form which will form hydrides. In addition, with hydride generation-ICP-MS, the main problem of Ar_2 overlaps on 4 of the Se isotopes is not addressed.

Alternative plasmas have been used, particularly He-based microwave induced plasmas (MIP). This solution offers the dual benefit of a more highly ionising plasma environment (as He has a higher ionisation potential than Ar), together with the removal of the Ar-based polyatomic species. However, these systems are expensive to run, and are not widely available or established as commercial instrumentation.

In common with most polyatomic interferences, the Ar-based overlaps on the Se isotopes can be separated from the analyte peak through the use of a high-resolution magnetic sector mass spectrometer. In addition to offering a very expensive and non-routine solution to the problem, high-resolution mass spectrometers do not address the fundamental problem of the presence of the interfering peak. In order to separate a polyatomic from an adjacent analyte peak, a theoretical resolution is normally calculated, based on equal heights for the 2 peaks and separation only to the 10% valley definition. However, in the case of a trace analyte (such as Se) adjacent to a major interference (such as Ar_2), these calculations are not appropriate. A much higher resolution setting will typically be required and the transmission and sensitivity will therefore be severely compromised. Typically, operation at resolutions of several thousand (as needed even for the separation of equal height peaks) will result in a reduction in transmission of around 95%, i.e. only around 5% of the original signal remains.

Techniques have been investigated for the removal of various polyatomic species using selective collisions with a gas which is introduced into the mass




Figure 1.
Schematic of Shield Torch System on the 4500 ICP-MS Series

Forward Power	1000 W
Sampling Depth	13 mm
Carrier Gas Flow	1.2 L/min
Blend Gas Flow	0.8 L/min
Ion Lens Tuning	Typical Cool Plasma Settings
Acquisition Time	21 seconds/repeat
Number of Repeats	3 (10 for LOD blank)

Table 2.
4500 ICP-MS Operating Conditions for Se Analysis

spectrometer vacuum chamber. These techniques have not, as yet, proved robust in their ability to decompose specific polyatomics without the introduction of numerous additional clusters ions, which can result in an increase in the overall complexity of the spectrum. Furthermore, collision cells have been shown to be highly susceptible to contamination from matrix components, resulting in poor tolerance to natural samples. Whilst an individual poly-atomic ion can be attenuated, albeit

usually with severe attenuation of the analyte signal, it has been demonstrated that different optimum conditions are required for each poly-atomic ion, so the technique is appropriate only on a single-element batch processing basis.

A simple and elegant solution to the problem of Se analysis has been developed by Agilent Technologies application staff, working with the ShieldTorch System on the 4500 ICP-MS.

The ShieldTorch system comprises a grounded metal plate which lies between the plasma RF load coil and the plasma torch, as shown in Figure 1. This has the effect of removing the capacitive coupling between the coil and the plasma, so the plasma is held at the same potential (ground) as the mass spectrometer interface.

Combined with changes to the operating parameters of the plasma (gas flows and sampling depth), which reduce the temperature of the central channel of the plasma, this leads to a background spectrum which is virtually free from Ar-based peaks. Since Se has a relatively high first ionisation potential, it might be expected that reducing the plasma temperature would dramatically reduce the Se signal. However, it is straightforward to optimise the 4500 ICP-MS to give minimal Ar₂ signal whilst retaining good sensitivity for Se. The principal operating parameters are outlined in Table 2.

Under these conditions, the Ar₂ background is much reduced, as shown in Figure 2, whilst Se can be measured at the low ppb level, also shown in the same Figure. From these spectra, it is clear that the Se isotopic pattern matched the theoretical isotopic abundance, indicating that the Ar₂ polyatomics have been effectively removed. This analytical methodology was applied to the measurement of Se in HCl. With the robustness of the higher-power Cool Plasma of the 4500 ICP-MS, this change in matrix did not require any further optimisation or re-tuning of the plasma parameters or ion lenses.

For the quantitative measurement of low concentrations of analytes,




Figure 2.
Selenium Isotopic Pattern in 10ppb Standard and Blank (inset)

Isotope	Dwell time/point (s)	Dwell time/mass (s)
76	2.0	6.0
77	2.0	6.0
78	0.4	1.2
80	0.2	0.6
82	2.0	6.0

Table 3.
Integration Times Used for Selenium Analysis

it is normal to concentrate the integration time on the peaks of interest. For this reason, a peak jumping acquisition was used, where the quadrupole settles only at the top of each set mass. This ensures that the best signal to noise is achieved, although the spectral information is much more limited. The integration times used for the Se isotopes in this study are shown in Table 3. Different integration times were used, in approximately inverse proportion to the isotopic abundance of the individual isotopes, so approximately equal counts (in raw counts) were collected for each.

The calibrations obtained for the Se isotopes at mass 76, 78, 80 and 82, measured in a matrix of 4% HCl, are shown in Figures 3 to 6. In each case, the calibration was in the range from 0ppb to 5ppb. The linearity for each calibration was 1.000.

No blank subtraction was used, no interference correction was required and no internal standard was added.

In HCl, a further possible polyatomic peak might be encountered, due to the formation of $^{40}\text{Ar}^{37}\text{Cl}$, which would overlap the

Se isotope at mass 77. Whilst there are 4 Se isotopes which are free from interference (as shown in Figures 3 to 6), it would be useful if a further isotope could be measured as well. A greater number of available isotopes increases the possibility of carrying out stable isotope tracer analyses in biological systems, as well as extending the possibility of conducting isotope dilution analysis to improve the accuracy of measurements at ultra-trace levels.

The fit of the Se isotopic template to the spectrum for 10ppb Se in 4% HCl is shown in Figure 7. Inset in this spectrum is the spectrum for the blank 4% HCl, on the same intensity scale. The residual ArCl peak at mass 77 is equivalent to about 3ppb, suggesting that the ^{77}Se isotope might be analytically useful at the sub-10ppb level, in addition to the other 4 Se isotopes shown in Figures 3 to 6.




Figure 3.
Calibration for Selenium 76




Figure 4.
Calibration for Selenium 78

The calibration for Se at mass 77 is shown in Figure 8. As with all of the other calibrations shown in Figures 3 to 6, this calibration was generated using the method of standard additions, so the intercept on the y-axis indicates the contribution from the ArCl background. Even in the presence of this background, an acceptable calibration was obtained at the sub-5ppb level.

The 4% HCl Blank was repeated 10 times and the detection limit for each Se isotope was calculated based on the multi-point calibration in 4% HCl. The 3 sigma detection limits calculated are shown in Table 4. Note that these are conservative detection limits, as they are based on the analysis of a matrix blank (4% HCl) analysed as a real sample, immediately following the analysis of the calibration standards. Detection limits a factor of 2-5 lower than these values have been obtained under optimum analytical conditions. Also shown in Table 4 are the background equivalent concentrations for each of the Se isotopes, indicating that backgrounds well below 100ppt were achieved for the 3 Se isotopes.

To be useful in real analysis, it must be demonstrated that good precision can be obtained at analytically useful concentrations. The calibration graphs show the good precision obtained on each calibration standard and Table 4 shows the actual precision obtained at the 1ppb level.

The analysis of Se is of increasing interest in human nutrition and toxicology. The ability to measure trace Se concentrations without resorting to separate analytical techniques is beneficial. The




Figure 5.
Calibration for Selenium 80




Figure 6.
Calibration for Selenium 82

Shield Torch System of the 4500 ICP-MS allows operation of the ICP-MS under optimum conditions for Se analysis, without the limitations in matrix tolerance

associated with collision or reaction cells. The possibility of mass spectrometric determination of multiple Se isotopes, allowing stable isotope tracers to be used,

is an exciting development in the growing applications for higher power cool plasma analysis using the ShieldTorch System on the 4500 ICP-MS.




Figure 7.
Selenium Isotopic Pattern in 4% HCl Blank (inset) and 10ppb Standard




Figure 8.
Calibration for ^{77}Se in 4% HCl

Se Isotope	BEC (ppt)	3s LOD (ppt)	Precision at 1ppb (%)
76 Se	172.8	38.04	2.61
77 Se	2880	81.12	2.47
78 Se	89.5	49.14	5.24
80 Se	29.6	59.82	4.97
82 Se	31.1	59.7	2.35

Table 4.
Summary of Detection Limit Data for Selected Se Isotopes

Ed McCurdy is a Sales Specialist and Glenn Woods is an Application Chemist both at Agilent Technologies, Inc. Manchester, UK

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5968-7598E



Agilent Technologies

Innovating the HP Way



The Determination of Trace Elements in Soils and Sediments by ICP-MS

Application Note Environmental

Concerns regarding “safe” levels of contaminants in the environment, particularly heavy metals, continue to grow. The requirement for analysis of more elements at ever decreasing concentrations is exposing the limitations of currently used analytical techniques. Further improvements in sensitivity and elemental coverage are required. While GFAAS (Graphite Furnace Atomic Absorption Spectrometry) and ICP-OES (Inductively Coupled Plasma Optical Emission Spectrometry) are still the most commonly used techniques in environmental elemental analysis, ICP-MS is the only technique that offers the improvements in sensitivity that will be demanded in the near future. The 4500 ICP-MS benchtop ICP-MS offers high throughput multielement analysis at the sub ug/ml (ppb) level with the robustness and ease of operation required for true routine use. In this application brief, the analysis of two typical environmental solids - lake sediment and soil - is described. The




Fig. 1.
Qualitative spectrum of SL-1 (Lake sediment)

samples analyzed were standard reference materials - IAEA (International Atomic Energy Agency) SL-1 (lake sediment), and IAEA SOIL-7 (soil).

Sample Preparation

0.1g of each sample was digested with 1ml of pure water, 0.3ml of hydrofluoric acid (38%) and 0.7ml of nitric acid (68%) using microwave digester for 1 hour. After digestion the sample was diluted to 100ml with deionized water.



Agilent Technologies
Innovating the HP Way

Procedure

An internal standard mix containing Be, In and Bi was added to each sample. The sample solutions were quantified by external standardization, by measuring them against multi-element standards.

Operating conditions

RF power : 1.3 kW
Sampling depth : 8 mm
Plasma gas : 16 l/min.
Auxiliary gas : 1.0 l/min.
Carrier gas : 1.15 l/min.
Nebulizer : Babington type

Results

Lake sediment

Fig.1 demonstrates the qualitative spectrum of SL-1. A large number of elements, ranging from Li at low mass to U at high mass can be clearly observed, even though the total analysis time was only 100 sec.

The quantitative results and the certified values are given in Table 1. The major constituents in this sample are shown in Table 2. After digestion, Fe, Mn, Mg, K and Al were present in solution at levels ranging from a few mg/l(ppm) to 100s of mg/l(ppm), giving rise to the possibility of interference due to spectral overlap. The 4500 ICP-MS's excellent abundance sensitivity and low levels of polyatomic species ensured that the analyte values obtained were in good agreement with certified values.

Soil

Fig.2 shows the qualitative spectrum obtained from SOIL-7. The presence of over 20 elements can be clearly observed, although the




Fig. 2.
Qualitative spectrum of SOIL-7

Element	m/z	Certified	Measurement
V	51	170±15	169
Cr	52	104±9	115
Mn	55	3400±160	3520
Co	59	19.8±1.5	20.2
Ni	60	44.9±8.0	49.6
Cu	65	30±5.0	32.0
Zn	66	223±10	222
As	75	27.5±2.9	29.6
Se	82	*2.9	1.10
Cd	114	0.26±0.05	0.38
Sb	121	1.31±0.12	1.20
Pb	208	37.7±7.4	40.7
Units: mg/kg			

Table 1.
Quantitative values: SL-1
* Not certified - information only

elemental composition is quite different to SL-1, even from visual inspection of the qualitative spectra.

Quantitative results and the certified values are given in Table 3 and again very good agreement was obtained. The main components of this sample are also given in Table 4. As can be seen, the sam-

Element	Content
Fe	6.7
Mn	0.34
Ti	0.52
Na	0.17
Al	8.9
Ca	0.25
K	1.5
Mg	2.9
S	1.2
Units: %	

Table 2.
Main constituents of SL-1

ple matrix contains Ca at over 20%, which can affect the determination of Co and Ni, due to interference from CaO. Nevertheless, the 4500 ICP-MS values for Co and Ni agree well with the values supplied, which demonstrates the applicability of this technique to real life sample matrices, even where analytes are present at trace levels in the sample digest.

Element	m/z	Certified Conc.	Confidence interval	Measurement
V	51	66	59-73	67.3
Cr	52	60	49-74	60.7
Mn	55	631	604-650	629
Co	59	8.9	8.4-10.1	8.60
Ni	60	*26	*21-37	24.1
Cu	65	11	9-13	9.85
Zn	66	104	101-113	104.4
As	75	13.4	12.5-14.2	13.8
Se	82	*0.4	*0.2-0.8	3.11
Cd	114	*1.3	*1.1-2.7	1.20
Sb	121	1.7	1.4-1.8	1.60
Pb	208	60	55-71	61.7
Units: mg/kg				

Table 3.
Results of SOIL-7
*** Not certified - information only**

Component	Content
Al ₂ O ₃	8.9
CaO	22.9
Fe ₂ O ₃	3.7
K ₂ O	2.9
MgO	1.9
Na ₂ O	0.6
SO ₃	0.3
SiO ₂	38.5
TiO ₂	0.5
Loss on ignition (900°C)	20.5
Units: %	

Table 4.
Matrix components of SOIL-7

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>
Copyright © 2000

Agilent Technologies, Inc.
Printed 4/2000
Publication number 5963-7138E



Agilent Technologies

Innovating the HP Way



Specific Determination of Bromate and Iodate in Ozonized Water by Ion Chromatography with Two Detection Methods : Postcolumn Derivatization and ICP-MS Detection

Submitted to : Journal of Chromatography A, 789, 259-265 (1997)

Application Note Environmental

Michiko Yamanaka

Abstract

A specific determination for bromate, iodate and other halogen anions in drinking water by direct injection using ion chromatography (IC) with either inductively coupled plasma mass spectrometry (ICP/MS), or the postcolumn derivatization is described. The advantages of ICP/MS as an element selective detector was evaluated for bromate and iodate by considering the comparison with the postcolumn derivatization. Samples were directly injected into the IC column, and halogen anions were separated. The eluates were directly introduced into ICP/MS and detected at 79 and 127 amu. The detection limit ($S/N = 3$) for bromate and iodate with injection of 0.5 mL were 0.45 $\mu\text{g Br/L}$ and 0.034 $\mu\text{g I/L}$, respectively. The IC combined with ICP/MS was applied to the simultaneous determination of bromate, bromide and other halogen anions in raw and ozonized water. Good agreement was obtained for the determined values by IC-ICP/MS and postcolumn derivatization. Furthermore, several bromine species different from bromate or bromide were detected by IC-ICP/MS.



Agilent Technologies
Innovating the HP Way

Introduction

Bromate can be formed by the oxidation of bromide ions during ozonation and possibly by other oxidants in water treatment [1-4]. Bromate has been estimated as a potential carcinogen, and has been classified in Group 2B by the International Agency of Research on Cancer (IARC). The concentration of bromate in drinking water associated with an excess lifetime cancer risk of 10^{-5} corresponds to 3 µg/L [5]. The World Health Organization (WHO) recommended the provisional guideline value of 25 µg/L which is associated with an excess lifetime cancer risk of 7×10^{-5} , because of limitation in available analytical and treatment methods [5].

Ion chromatography (IC) with a pretreatment method [6] or an on-line preconcentration method [7-8] has been reported for the determination of trace bromate. However, the peak of bromate at the detection limit level will often vanish in that of chloride which is always present in water at a level of three orders of magnitude higher. The authors have developed a sensitive and selective ion chromatographic determination method of bromate with postcolumn conversion into tribromide by hydrobromic acid [9]. Sub-µg/L of bromate in water was determined by using the developed postcolumn derivatization. Furthermore, other disinfectant by-products such as chlorite and iodate were also detected with similar detection limits.

On the other hand, inductively coupled plasma mass spectrometry (ICP/MS) combined with liquid chromatography or IC (LC-ICP/MS or IC-ICP/MS) is an effective

technique for the speciation study of metallic and organometallic species because of its element selectivity and sensitivity. The combined technique has been also applied to the determination of halogen species, especially, iodine that can be sensitively detected by ICP/MS [10-14].

In the present work, the specific determination of bromate, iodate and other halogen species in drinking water by direct injection using IC with ICP/MS and the postcolumn derivatization is described. The advantages of ICP/MS as an element selective detector was evaluated for bromate and iodate by considering the comparison with the postcolumn derivatization. Furthermore, the IC-ICP/MS system was applied to the simultaneous determination of halogen anions in raw and ozonized water.

Experimental

Reagents

All reagents used were purchased from Wako Pure Chemical Industries (Osaka, Japan). Stock solutions (1000 mg/L as elements) for each anion were prepared by dissolving with pure water and stored in refrigerator. Analytical solutions were prepared by diluting the stock solution to the required concentration just before use. Pure water was obtained from Milli-Q system (Nihon Millipore, Tokyo, Japan).

Instrument

Ion chromatograph used in this experiment was Model IC7000S (Yokogawa Analytical Systems Inc., Japan) equipped with a UV/VIS detector, and ICP/MS was Model 4500 (Agilent Technologies, Inc. USA). Excelpak ICS-A23 and ICS-A13 (7.6 mm x 4.6 mm i.d.

each, Yokogawa Analytical Systems Inc.) were chosen as separation columns. ICS-A23 and ICS-A13 were packed with hydrophilic and semi-hydrophilic anion exchange resin with 0.05 mequiv./g of dry, respectively.

IC-ICP/MS

Ion chromatograph and ICP/MS were connected by 500 mm x 0.3 mm i.d. of ETFE tube. Ammonium carbonate was chosen as a mobile phase. Ammonium salt was used to prevent a salt deposition and clogging at sampling orifice of ICP/MS caused by sodium in a mobile phase. The operating conditions of ICP/MS are described in Table 1.

Postcolumn derivatization

Two Excelpak ICS-A13 columns in series were chosen to separate the halogen species according to the previous paper [9]. The operating conditions of the postcolumn derivatization are described in Table 2.

Results and Discussion

Separation of halogen anion

First of all, the separation of halogen anions using ICS-A13 as the separation column according to previous paper [9] was examined to establish appropriate separation conditions. The chromatography behaviour of iodide on anion-exchange resins has been described [15]. In this experiment, however, the peak of iodide showed a broad and tailing shape, while bromate, bromide and iodate showed good peak shapes. It was also noted that the retention time was long (more than 30 min) and depended on its concentration. It was not drastically improved in spite of a series of change of mobile phase.

RF power	1300 W
RF reflected power	<1 W
Plasma gas	16.0 L/min
Auxiliary gas	1.00 L/min
Carrier gas flow	1.06 L/min
Sampling depth	7.5 mm
Mass	79 amu (Br), 127 amu (I)
Integration time	0.5 sec
Number of scans	1

Table 1
Operational conditions of ICP-MS.

Ion Chromatography	
column	Excellpak ICS-A13 x 2
mobile phase	5×10^{-3} mol/L Na_2CO_3 / 1×10^{-3} mol/L NaHCO_3 , 1.0 mL/min
column temp.	40 °C
injection volume	0.1 mL
Reagent preparation	
reagent	5 mg/L NaNO_2 in 0.5 mol/L NaBr, 1.0 mL/min
preparation reagent	0.75 mol/L H_2SO_4 , 1.0 mL/min
cation hollow fiber	5 m
Postcolumn derivatization	
reaction coil	3 m x 0.5 mm i.d.
reaction temp.	40 °C
detection	UV-268 nm

Table 2
Operating conditions of postcolumn derivatization




Fig. 1
Chromatograms of halogen anion standards by IC-ICP/MS. Peaks: BrO_3^- (10 $\mu\text{g/L}$), Br^- (10 $\mu\text{g/L}$), IO_3^- (1 $\mu\text{g/L}$), and I^- (2 $\mu\text{g/L}$).
Experimental conditions: column, Excellpak ICS-A23; mobile phase, 0.03 mol/L $(\text{NH}_4)_2\text{CO}_3$; flow rate, 1.0 mL/min; column temperature, 40 °C; injection volume, 0.5 mL.


Therefore, ICS-A23 was used on behalf of ICS-A13 because of increase of hydrophilicity of packing materials. The use of the ICS-A23 with 0.03 mol/L ammonium carbonate solution (pH 9.2) made it possible to improve peak shape and retention time of iodide. Fig. 1 shows the chromatograms of halogen anion standards by direct injection with a 0.5 mL sample. Four halogen anions were completely separated within 8 minutes. The analytical time will be reduced by increasing the concentration or pH of mobile phase. For the purpose of this work, that is the simultaneous separation of many halogen species, these separation conditions were a compromise between the number of determinants and analytical time.

Evaluation of IC-ICP/MS

The linearity, detection limits and repeatability for bromate and iodate were determined. The linear range of bromate and iodate was more than 3 orders of magnitude, from 0.5×10^{-3} to 1 mg/L and from 0.1×10^{-3} to 1 mg/L, respectively. Equally, good linearity for bromide and iodide was also obtained. The detection limits ($n = 3$) for bromate, bromide, iodate and iodide were 0.45 $\mu\text{g/L}$, 0.44 $\mu\text{g/L}$, 0.034 $\mu\text{g/L}$ and 0.051 $\mu\text{g/L}$, respectively. The repeatability ($n = 6$) for 1.0 $\mu\text{g/L}$ of bromate, 1.0 $\mu\text{g/L}$ of bromide, 0.1 $\mu\text{g/L}$ of iodate and 0.2 $\mu\text{g/L}$ of iodide was 8.1 %, 8.0 %, 6.2 % and 6.8 %, respectively.

In the standard method for water quality, the quantitative limit is determined by the sample concentration which gives 10 % of relative standard deviation (RSD) [16]. The quantitative limits of this method were obtained from the

a) BrO_3^-



b) IO_3^-




Fig. 2
Relationships between the RSD and sample concentration for bromate a) and iodate b). Experimental conditions are same as those given in Fig. 1.

RSD values which were calculated for each set of 10 measurements of bromate and iodate solutions at various concentrations.

Fig. 2 shows the relationships between the RSD and the sample concentration. The concentrations of bromate and iodate at 10 % of RSD were 0.42 $\mu\text{g/L}$ and 0.051 $\mu\text{g/L}$, respectively. Fig. 2 also shows the signal stability in the concentrations which give sufficient sensitivity for bromate and iodate.

In both species, RSDs were saturated around 1% even in high concentrations. The saturated RSD is considered to be affected by ICP-MS stability.

Interference by coexistent substance


The interference from coexistent substances such as chloride, sulfate and nitrate has been reported by Creed and others[14]. They reported that bromate can be determined in a chloride matrix with 5-6 orders of magnitude higher. However, a retention time shift for bromate in 1000 mg/L of chloride matrix was observed. So, the interference from coexistent substances such as fluoride, chloride, nitrite, phosphate and sulfate was examined. Mixed anion standard solutions ranging in concentration from 5 to 50 mg/L of anions were injected. Peaks of these anions were not observed on the chromatogram. The retention time

shift for halogen anions in the concentration below 50 mg/L of anions matrix was not observed. However, one peak was observed at void volume in chromatogram of 79 amu. This peak was recognized to be a polyatomic ion ($^{40}\text{Ar}^{39}\text{K}^+$) formed by combination of potassium in sample solution with argon as the plasma gas, because it appeared at the retention time of potassium that was observed in 39 amu. Conclusively, this peak due to potassium will be neglected on the determination of bromate because it is eluted at the void volume of the anion exchange column and completely separated from that of bromate under these separation conditions.

Application to the determination of halogen anions in the water

The presented method was applied to the determination of halogen anions in several water samples. The chromatograms of the ozonized water by using IC-ICP/MS and the postcolumn derivatization were shown in Fig. 3. The determined concentrations of halogen anions in raw (river) and ozonized water are listed in Table 3. The concentrations of halogen anions determined by both method were relatively in agreement. However, some iodate values obtained using ICP-MS were slightly higher than that of postcolumn derivatization. The disagreement could be due to lack of precision in such low concentration. Furthermore, there could be interference from other iodine-containing species coeluting with iodate, because ICP-MS would detect any species containing iodine, and it would give positive error in the iodate values. Bromate values by ICP-MS were a little lower than that of postcolumn method. The reason is

a) ICP/MS



b) postcolumn derivatization




Fig. 3

Chromatograms of ozonized water (sample B) using IC-ICP/MS a) and postcolumn derivatization b). Peaks: a) BrO_3^- (13.0 $\mu\text{g/L}$), Br^- (17.8 $\mu\text{g/L}$), IO_3^- (3.57 $\mu\text{g/L}$), and I^- (3.56 $\mu\text{g/L}$) b) IO_3^- (4.13 $\mu\text{g/L}$), BrO_3^- (15.7 $\mu\text{g/L}$) Experimental conditions are same as those given in Fig. 1 and Table 2. Unit of the concentrations is $\mu\text{g/L}$ as species.

samples	determined concentrations [$\mu\text{g/L}$ as species]					
	IC-ICP-MS				postcolumn	
	BrO_3^-	Br^-	IO_3^-	I^-	BrO_3^-	IO_3^-
A. raw water	0.26	28.9	0.44	0.63	0.29	0.09
B. ozonized sample A	13.0	17.8	3.57	3.56	15.7	4.13
C. raw water	1.64	59.1	1.26	2.97	1.65	0.60
D. ozonized sample C	1.88	38.5	5.66	0.14	2.31	4.98
E. ozonized water	1.87	5.73	5.45	0.05	1.85	4.77

Table 3

Comparison of determined concentrations of halogen anions in raw and ozonized water. Experimental conditions are same as those given in Fig. 1 and Table 2.

not clear because bromate values in this postcolumn reaction procedure doesn't suffer from interference from other oxidants [9].

Bromate and iodate with the concentration of $\mu\text{g/L}$ level were detected even in the raw water. Probably, the contamination of river water with trace bromate was caused by a waste water. On the other hand, the existence of iodate in mineral water has been also reported [17]. The concentrations of bromate and iodate in the ozonized water were rather increased than those in the corresponding raw water, while that of bromide was decreased by ozonation. Apparently, bromate and iodate will be formed during ozonation for the water treatment. However, the material balances of bromine and iodine were absolutely incompatible. These results suggest the halo-oxyacids are produced by oxidation of the corresponding halides, but that they are not always produced by the same mechanism.

Sample E gave a distinctive chromatogram at 79 amu (Fig. 4). Several unidentified species different from bromate or bromide were detected. These species are estimated as bromine compounds because no interferences from other elements are observed at 79 amu. The existence of other bromine species suggests that these species could lead to bromate during ozonation. It can also explain that the sum of bromate and bromide was not constant for ozonized water and its raw water (sample D and C) in Table 3. Furthermore, a large unidentified peak with a broad peak shape was also detected at the retention time of about 40 minutes in the chromatograms of ICP/MS at 127 amu. Heumann




Fig. 4
Chromatograms of ozonized water (sample E). Peaks: BrO_3^- (1.87 $\mu\text{g/L}$), Br^- (5.73 $\mu\text{g/L}$), IO_3^- (5.45 $\mu\text{g/L}$), and I^- (0.05 $\mu\text{g/L}$). Experimental conditions are same as those given in Fig. 1. Unit of the concentrations is $\mu\text{g/L}$ as species.

et al. reported that organoiodide exists in river water, because the peaks with exactly the same retention time were obtained in both chromatograms of ICP/MS and UV detector at 254 nm [13].

Therefore, the detection of these unidentified peaks by a simultaneous detection using ICP/MS and UV detector was examined. No peaks in the chromatogram of UV at 254 nm were observed at the retention times of these unidentified peaks in the chromatogram of ICP/MS. Furthermore, the retention behaviors of the unidentified peaks were evaluated by adding ethanol to the mobile phase. The retention times were drastically decreased as the concentration of ethanol increased. Clearly, these species were retained by their hydrophobicity, not ionicity. The elucidation of the unidentified peaks detected at 79 amu will be very difficult because of their lower amounts. The unidentified peak detected at 127 amu might be based on inorganic iodine

rather than organoiodine but its chemical structure is not still determined. These unidentified peaks might be concerned in the production mechanism of the halo-oxyacids by the ozonation. A further detailed examination would be necessary to elucidate these unidentified peaks.

Conclusions

A specific determination for bromate, iodate and other halogen anions in drinking water by direct injection using IC with ICP/MS and the postcolumn derivatization is presented. Bromate and iodate in ozonized water were determined at the $\mu\text{g/L}$ level without any interference from other anions. The sensitivity of the ICP/MS detector for halogens was also very high similar to that of metals and greater than that of other detectors for halogens. The proposed method will be effective for the simultaneous determination of halogen anions.

References

1. M. S. Siddiqui, G. L. Amy, and R. G. Rice, *J. AWWA*, **87** (1995) 59.
2. J. C. Kruithof, and J. C. Schippers, *Water Supply*, **11** (1992) 121.
3. J. C. Kruithof and R. T. Meijers, *Water Supply*, **13** (1995) 93.
4. J. C. Kruithof and R. T. Meijers, *Water Supply*, **13** (1995) 117.
5. WHO, "Guidelines for Drinking-water Quality", 2nd Ed., vol. 1. Recommendations, the World Health Organization, Geneva, 1993.
6. F. Sacher, A. Matschi, and H.-J. Brauch, *Acta Hydrochim. Hydrobiol.*, **23** (1995) 26.
7. R. J. Joyce, and H. S. Dhillon, *J. Chromatogr. A*, **671** (1994) 165.
8. H. Weinberg, *J. Chromatogr. A*, **671** (1994) 141.
9. Y. Inoue, T. Sakai, H. Kumagai and Y. Hamaoka, *Anal. Chim. Acta*, in press.
10. V. V. Salov, J. Yoshinaga, Y. Shibata and M. Morita, *Anal. Chem.*, **64** (1992) 2425.
11. K. Takatera and T. Watanabe, *Anal. Chem.*, **65** (1993) 759.
12. D. T. Heitkemper, L. A. Kaine, D. S. Jackson and K. A. Wolink, *J. Chromatogr. A*, **671** (1994) 101.
13. K. G. Heumann, L. Rottmann and J. Vogl, *J. Anal. At. Spectrom.*, **9** (1994) 1351.
14. J. T. Creed, M. L. Magnuson, J. D. Pfaff and C. Brockhoff, *J. Chromatogr. A*, **753** (1996) 261.
15. K. Ito, E. Shoto and H. Sunahara, *J. Chromatogr. A*, **549** (1991) 265.
16. "Standard Methods for the Examination of Water", Japanese Water Supply Society, (1993) 38.
17. K. G. Heumann, and H. Seewald, *Fresenius' Z. Anal. Chem.*, **320** (1985) 493.

Michiko Yamanaka is an Application Chemist
at Yokogawa Analytical Systems, Inc. Tokyo,
Japan

Agilent Technologies shall not be liable for
errors contained herein or for incidental or
consequential damages in connection with the
furnishing, performance or use of this material.

Information, descriptions and specifications in
this publication are subject to change without
notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5968-3049E



Agilent Technologies

Innovating the HP Way



Meeting UK Drinking Water Inspectorate Requirements for Trace Metals Analysis Using the 4500 ICP-MS

Application Note Environmental

Glenn D. Woods
Ed McCurdy

Abstract

Inductively Coupled Plasma Mass Spectrometry (ICP-MS) has gained wide acceptance for the determination of many trace elements, but is less frequently used for the determination of higher levels of elements, due to its perceived limitations in dynamic range and matrix tolerance.

Several applications require the measurement of trace and minor elements in the same sample, which generally means that laboratories must employ multiple techniques to perform a complete analysis. One such application is the measurement of inorganic components in drinking water, where the analyte concentrations that must be measured range from sub-ug/L (ppb) to 100's of mg/L (ppm). Traditionally, this analysis would have been carried out using a combination of Inductively Coupled Plasma Optical Emission Spectrometry (ICP-OES), Graphite Furnace Atomic Absorption Spectrometry (GFAAS) and hydride and fluorescence techniques specifically for As, Se, Sb and Hg.

This paper discusses the validation of the 4500 ICP-MS for this analysis, allowing all of the controlled elements to be measured in a single run, using a single technique. Results are presented from the performance testing of the 4500 ICP-MS for the analysis of 26 trace and minor elements in Drinking Water, using the validation and quality control criteria defined in the NS-30 "A Manual on Analytical Quality Control for The Water Industry" by the UK Water Authority.



Agilent Technologies
Innovating the HP Way

Introduction

Inductively coupled plasma mass spectrometry (ICP-MS) has been used for the determination of many trace and minor elements in various samples from diverse fields including environmental, geological, metallurgical, semiconductor, petrochemical and biomedical. One of the principal benefits which has led to the widespread use of ICP-MS has been its wide elemental coverage and excellent detection limits for a range of elements which are impossible to measure by a single alternative technique. In particular, for the measurement of trace elements at ug/L and ng/L levels, ICP-MS has often been able to replace Inductively Coupled Plasma Optical Emission Spectrometry (ICP-OES), Graphite Furnace Atomic Absorption Spectrometry (GFAAS), hydride generation and fluorescence techniques, allowing all important toxic trace elements to be measured in a single analysis.

Typically, however, ICP-MS has been perceived as inappropriate for the determination of higher levels of analytes, due to limited matrix tolerance and excessive sensitivity, which limits the upper calibration level. Although most ICP-MS instruments have the capability to measure over a wide dynamic range (8 orders of magnitude), this usually requires regular and time consuming cross calibration across two detector modes and still allows measurement only up to a few 10's mg/L.

(1) Drinking Water Quality

In the United Kingdom, drinking water quality is monitored by the Drinking Water Inspectorate (DWI), using the Water Supply (Water Quality) Regulations of

1989. These regulations list a total of 56 parameters, including colour, turbidity, organic compounds, anions and inorganic elements, which must be monitored in drinking water supplies. The list includes 21 inorganic elements, ranging from Ca (maximum concentration or Prescribed Concentration Value (PCV) of 250 mg/l) to Hg (PCV of 1 ug/L). The regulation requires that the detection limit (calculated from $4.65 \times$ the standard deviation of the blank) for each determinand must be less than one tenth of the PCV, so the detection limit of Hg, for example, must be less than 0.1 ug/L.

Under the Drinking Water Regulations, each laboratory is required to performance test the analytical systems for each parameter before that analytical system can be used for routine analysis of compliance samples. The design of the performance testing and calculation of the performance characteristics should be in accordance with the guidance given in the publication "NS-30", a manual on analytical quality control in the Water Industry.

(2) Requirements for Acquisition of Performance Testing Data

Taking into account the DWI requirements and NS-30 guidelines, the following protocol for performance testing is typical for metals analysis:

- 1) The calibration range should be such that all results fall within the range.
- 2) The calibration must have at least 3 points plus blank, to demonstrate a straight line.

3) Samples and standards must be prepared fresh, before each batch.

4) A maximum of 2 batches can be analysed on any one day, provided the instrument is switched to overnight conditions between batches.

5) Samples must be analyzed in random order.

6) Samples must be analysed in replicate, in at least 5 batches. In practice, analysis of duplicate samples in 11 batches satisfies the DWI condition on degrees of freedom.

7) A batch of samples must consist of the following: Blank, Standards (typically at concentrations appropriate to the PCV and the levels found in representative samples) and Samples of the type to be measured routinely.

(3) Requirements for Statistical Validation

After acquiring the concentration data, the results must satisfy the following QC criteria:

- 1) The maximum tolerable error of individual results should not exceed 1/10 of the PCV or 20% of the result, whichever is the greater.
- 2) The maximum tolerable standard deviation of individual results should not exceed 1/40 of the PCV or 5% of the result, whichever is the greater.
- 3) The maximum tolerable systematic error (or bias) of individual results should not exceed 1/20 of the PCV or 10% of the result, whichever is the greater.

4) The estimates of total standard deviation must not be significantly greater at the 95% confidence level than the specified maximum tolerable total standard deviation at the relevant concentration.

5) The recovery of an added spike should not be significantly less than 95%, or significantly greater than 105%.

6) The limit of detection must be lower than 1/10 of the PCV.

The performance testing protocol described in NS-30 validates not only an analytical instrument, but also the entire laboratory protocol. If any aspect of sample or calibration standard preparation is not reproducible, then the error will be observed in the between batch variation. For this reason, it is essential that sample and standard preparation techniques are well developed and carried out reproducibly.

In a large analyte suite, there may be several issues that must be addressed regarding element stability, compatibility and cross-contamination, in addition to straightforward issues of the selection of appropriate glass/plasticware to avoid element leaching or adsorption. As Hg was one of the required analytes, Au was added to the standards and samples at 100 ug/L final concentration to stabilize Hg. In the absence of Au, the Hg signal is found to be unstable and exhibits extended washout times. The internal standard (IS) mixture, which contained Be, Sc, Y, In, Tb and Tl, was added to the standards and samples automatically by means of the on-line IS addition system.

The 4500 ICP-MS was validated for the 21 controlled elements (B, Na, Mg, Al, P, K, Ca, Cr, Fe, Mn, Ni, Cu, Zn, As, Se, Ag, Cd, Sb, Ba, Hg and Pb) in drinking water, according to the NS-30 protocol. At the same time, the 4500 ICP-MS was also validated for a further 5 elements (Li, V, Co, Sr and Sn). Whilst NS-30 lists 21 inorganic components which must be monitored, additional elements may also be measured, provided that the NS-30 protocol has been followed and validation requirements have been met. Thus, each lab can extend the validated elemental range of the technique to meet their own needs and also their customer's specific requirements.

Instrumentation

The ICP-MS instrument used was a standard Hewlett-Packard 4500 ICP-MS, in conjunction with a Cetac ASX-500 random access autosampler. The 4500 ICP-MS was configured with the standard sample introduction system, which consists of a Agilent High Solids nebuliser, quartz spray chamber, quartz one-piece torch and Ni sample and skimmer cones. The standard 4500 ICP-MS sample introduction system is ideally suited to the analysis of high-matrix environmental samples, as discussed below:

• Low Sample Uptake Rate

The sample uptake rate of the 4500 ICP-MS is only 0.1 to 0.4mL/min, compared to between 0.8mL/min and 2.5mL/min, which is typical for conventional ICP-MS or ICP-OES instrumentation. This lower solution flow rate means that matrix loading on the plasma is minimised. In turn, this means that the plasma can dry,

decompose, dissociate, atomise and ionise the sample analytes and matrix more efficiently, resulting in reduced spectral interferences and reduced sample matrix effects.

The matrix tolerance capabilities of the Babington-type nebuliser are well known, but commercially available versions of these nebulisers tend to require very high solution flow rates and can be prone to pulsing and poor washout. The Agilent High Solids nebuliser is a modified Babington-type design, manufactured for the 4500 ICP-MS. It features a wide, square section groove cut into an angled front face and optimised to produce a stable aerosol at low sample uptake rates. The design of the groove ensures that no sample solution is trapped on the nebuliser face, which in turn prevents spiking during washout due to sample re-nebulisation.

• Low Polyatomic Ion Formation

Some of the most troublesome interferences in ICP-MS are caused by the overlap of polyatomic ions formed from combinations of oxygen with the argon carrier gas or matrix ions. If the sample introduction area, in particular the spray chamber, is maintained at a constant low temperature (0-2 °C), the water vapour loading in the sample aerosol can be reduced and so the cooling effect of the aerosol on the plasma is reduced. This results in a higher plasma temperature and gives more efficient breakdown of oxide species.

The normal method for monitoring the likely impact of oxide overlaps in the ICP-MS spectrum is by measuring cerium. Of all elements,

cerium has one of the highest metal-oxide (MO) bond strengths. The CeO/Ce ratio can therefore be used as a “worst-case” indicator of the likely interference problems an ICP-MS instrument will suffer in real sample analyses, where high levels of elements such as S, Cl, Al, Mg, Ca, etc. (all of which will form oxide species at much lower levels than Ce) might be encountered.

On the 4500 ICP-MS, the typical CeO/Ce ratio is <0.5%, partly due to the use of a cooled spray chamber, but also as a result of the use of a wide bore injector (2.5mm diameter) in the plasma torch. The wide injector diameter ensures that the sample aerosol is relatively diffuse in the central channel of the torch and so the plasma energy can decompose the sample matrix more efficiently, breaking up any refractory oxide species. Furthermore, the wide torch injector reduces gas velocity through the central channel giving a longer sample residence time in the plasma, which also assists matrix oxide decomposition.

• Linear Calibration

In order to determine high and low level elements in the same run, an ICP-MS instrument should have a wide dynamic range. Most ICP-MS instruments achieve this using a detector that can be operated in both pulse-count and analog mode for the measurement of low intensity and high intensity signals respectively. The 4500 ICP-MS has the capability to construct a single linear calibration line for all elements, from ng/L to 100's mg/L levels, without regular adjustment of detector or tuning parameters. The cross-calibration of the 2 detector modes is achieved using

a single solution, analysed once, and the calibration is stable over long periods of analysis.

Standard and Sample Preparation

Calibration stock standards were obtained from BDH and a series of working stock solutions was prepared, each stock containing compatible groups of the analytes. Ca, Na, Mg, K, Al, Fe, Cu and Zn were prepared from 10,000 mg/L stock solutions while the other elements were prepared from 1,000 mg/L single element stocks. Calibration standard solutions were prepared at concentrations appropriate to the levels normally found in the sample types to be tested. Hg and Se were prepared in a separate stock from the other elements. In order to analyze Ag, all samples and calibration standards were prepared in 1% v/v HNO₃ and 0.5% v/v HCl solution.

Two tap waters, one river derived and the other borehole derived, were analyzed as samples and two Blanks, two Analytical Quality Control (AQC) solutions and two Spiked solutions were prepared. Two vials were prepared for each blank, sample, spike and AQC. All the standard and sample solutions were freshly prepared for each batch.

The Internal Standard solution, which contained Be, Sc, Y, In, Tb and Tl, was added to the samples and standards by means of the on-line IS addition system of the 4500 ICP-MS. After on-line dilution in the sample stream, the final concentration of the internal standards was approximately 0.1mg/L, with the exception of Be, which was 10x higher to compensate for its low degree of ionisation.

Automatic setup of the pulse count/analog (P/A) factor of the detector was carried out using a tuning solution which contained Ca, B, P, Fe, Ba, Na, Mg, Al, K, Cu Zn and Sr at concentrations between 0.1mg/L and 100mg/L.

The appropriate concentration for each element was selected, to give an acceptable count-rate in both detector modes.

Experimental

(1) Instrumental Conditions

After turning on the plasma and allowing 15 minutes for the system to warm up, the instrument was tuned by using 3 of the elements present in the internal standard solution (Be, Sc and Tl).

The instrument was tuned by monitoring mass 9, 45 and 205, to give a sensitivity of around 200,000, 200,000 and 300,000 counts per second, respectively. This represents at least a factor of 10 lower sensitivity than can be achieved when the instrument is tuned for maximum sensitivity. i.e. the system was “detuned”. With a system tuned for maximum sensitivity, the higher level analytes such as Na and K would be “over-range”, i.e. above the maximum measurable concentration of the instrument.

For the successful analysis of environmental samples by ICP-MS, several sample introduction and plasma parameters must be considered, namely RF power, carrier gas flow, sample uptake rate and sampling depth. Higher plasma temperature and longer residence time of the analytes are critical parameters in order to decompose heavy matrices effectively and to minimize oxide formation. Table 1 shows the parameters used for routine

Parameter	Setting
Forward power	1350W
Peri-pump speed (analysis)	0.1 rps
Peri-pump speed (uptake/rinse)	0.3 rps
Sampling depth	8.5 mm
Carrier gas flow	1.25 L/min
Rinse time	30 sec
Acquisition Time	73 sec
Number of repeats	3

Table 1
4500 ICP-MS Operating Conditions for the Analysis of High Matrix Samples

1. Blank 1	13. Tap water A + Spike (L) 1
2. Blank 2	14. Tap water A + Spike (L) Hg/Se 1
3. AQC (L) 1	15. Tap water A + Spike (L) 2
4. AQC (L) Hg/Se 1	16. Tap water A + Spike (L) Hg/Se 2
5. AQC (L) 2	17. Tap water B 1
6. AQC (L) Hg/Se 2	18. Tap water B 2
7. AQC (H) 1	19. Tap water B + Spike (H) 1
8. AQC (H) Hg/Se 1	20. Tap water B + Spike (H) Hg/Se 1
9. AQC (H) 2	21. Tap water B + Spike (H) 2
10. AQC (H) Hg/Se 2	22. Tap water B + Spike (H) Hg/Se 2
11. Tap water A 1	23. Drift
12. Tap water A 2	24. Drift Hg/Se

polyatomics. Although HNO₃ and HCl were intentionally added to all samples in order to stabilise the solutions and allow the analysis of Ag, interference correction worked well and excellent results were obtained for all of these elements.

analysis of environmental samples using the 4500 ICP-MS.

(2) Sample Analysis

Each analytical batch consisted of the blanks, samples, spikes and AQC's shown below. Following analysis of the calibration standards, the sample batch was analysed in random order. A different random order was used for each batch, ensuring that no bias was introduced by running the test solutions in a constant order. Drift check solutions, which do not form part of the validation sequence, were analyzed at the end of each batch.

The analysis of Hg and Se was separated from the other elements for two reasons:

1) Following successful validation of the method, the mixed calibration standards should be stable for a week. However, Hg would not be expected to be stable over this period, so the Hg standards would need to be prepared fresh daily.

2) The Ca standard solution contained a small amount of Se. This contamination introduced a bias into the Se calibration at low level, so Se was calibrated using a standard mix that contained no Ca.

With regard to Fe, As and V, which are considered difficult elements to analyse by ICP-MS due to polyatomic overlaps from ArN, ArCl and ClO respectively, an interference correction equation was used to correct for background contributions from these

Results and Discussion

(1) Calibration Curves

Figures 1 shows the calibration curves of some of the major elements, determined at concentrations up to 300mg/L. Figure 2 shows calibrations for some of the trace elements, calibrated at low ug/L levels. Linear calibrations were obtained in all cases.




Figure 1
Calibrations for Selected Major Elements




Figure 2
Calibrations for Selected Trace Elements

(2) NS-30 Performance Testing Results

Once quantitative results had been obtained from all of the batches, the statistical processing defined in NS-30 was carried out. Tables 2 and 3 show the calculated results of one high and one low concentration element found in the tap water samples (Na and Hg respectively)

Na (23) IS – Sc	Blank	AQC(L)	AQC(H)	Sample 1	Spike 1	Sample 2	Spike 2
Mean (mg/L)	-0.7005	53.0727	123.1818	34.0273	155.954	44.0409	95.8818
M1	6.0556	16.3264	32.9273	8.1404	67.2455	9.9548	19.7033
M0	0.0002	2.6527	13.0909	0.7782	10.5909	1.4223	5.8182
F value	26122.086	6.1546	2.5153	10.4607	6.3494	6.9992	3.3865
Significant	p=0.001	p=0.01	NS	p=0.001	p=0.01	p=0.01	p=0.05
Sw	0.0152	1.6287	3.6181	0.8821	3.2544	1.1926	2.4121
Sb	1.7400	2.6147	3.1493	1.9186	5.3223	2.0655	2.6349
St	1.7401	3.0805	4.7968	2.1117	6.2384	2.3851	3.5722
F 0.05	1.8307	1.7202	1.6228	1.7522	1.7202	1.7202	1.6435
Calc. F	0.2153	0.6748	0.6065	0.3171	0.6401	0.4045	0.5552
Degree F	10	13	17	12	13	13	16
Bias OK?		Pass	Pass				
SD OK ?		Pass	Pass	Pass	Pass	Pass	Pass
Recovery		107.55	103.24		101.61		103.68
95% Conf. Limits		2.83	1.55		2.48		2.79
Recovery OK ?					Pass		Pass
Limit of Detection	0.077 mg/L						
LOD OK?	Pass						

Table 2
NS-30 Performance Test Results for Na

Hg (202) IS – Au	Blank	AQC(L)	AQC(H)	Sample 1	Spike 1	Sample 2	Spike 2
Mean (mg/L)	-0.0011	0.2121	1.0650	0.0105	1.0623	0.0138	0.2295
M1	0.0001	0.0004	0.0011	0.0001	0.0012	0.0002	0.0004
M0	0.0002	0.0003	0.0006	0.0001	0.0009	0.0002	0.0007
F value	1.2233	1.4911	1.8473	2.3750	1.4631	1.2303	1.8405
Significant	NS	NS	NS	NS	NS	NS	NS
Sw	0.0127	0.0163	0.0244	0.0077	0.0292	0.0134	0.0260
Sb	0.0000	0.0081	0.0159	0.0064	0.0140	0.0045	0.0000
St	0.0127	0.0182	0.0291	0.0100	0.0324	0.0141	0.0260
F 0.05	1.5558	1.5705	1.5865	1.6228	1.5705	1.5558	1.5705
Calc. F	0.2562	0.5278	0.2990	0.1589	0.3711	0.3194	1.0840
Degree F	21	20	19	17	20	21	20
Bias OK?		Pass	Pass				
SD OK ?		Pass	Pass	Pass	Pass	Pass	Pass
Recovery		106.61	106.61		105.18		107.841
95% Conf. Limits		3.57	1.23		1.07		3.4205
Recovery OK ?					Pass		Pass
Limit of Detection	0.064 ug/L						
LOD OK?	Pass						

Table 3
NS-30 Performance Test Results for Hg

Tables 4 and 5 show the summary results of all elements. In every case, all of the statistical analysis indicated that the 4500 ICP-MS gave acceptable results under the requirements of the protocol defined in NS-30.

Elements	PCV	Units	LOD	AQC	Recovery	Spike	Recovery	95% SD
Li		ug/L	0.328	40	102.52	40	100.00	2.48
B	2000	ug/L	99.453	400	104.41	400	91.34	4.50
Na	150	mg/L	0.077	50	106.15	50	103.68	2.79
Mg	50	mg/L	0.064	10	102.77	10	105.42	2.43
Al	200	ug/L	1.562	200	102.34	200	100.68	2.06
P	2200	ug/L	4.524	500	97.07	500	98.34	3.44
K	12	mg/L	0.021	6	104.97	6	98.91	1.56
Ca	250	mg/L	0.338	100	103.32	100	97.73	2.70
V		ug/L	0.606	10	101.09	10	100.10	2.74
Cr	50	ug/L	1.332	10	104.09	10	98.46	3.64
Fe	200	ug/L	14.692	200	98.84	200	98.94	2.90
Mn	50	ug/L	0.900	50	100.45	50	101.69	2.40
Co		ug/L	0.052	10	102.36	10	105.24	1.02
Ni	50	ug/L	0.869	10	108.91	10	105.58	2.05
Cu	3000	ug/L	1.173	500	101.78	500	100.60	0.71
Zn	5000	ug/L	2.632	500	107.12	500	102.08	1.34
As	50	ug/L	1.067	10	93.13	10	98.51	2.49
Se	10	ug/L	0.837	2	102.77	2	108.95	5.96
Sr		ug/L	1.062	120	104.47	120	90.34	3.29
Ag	10	ug/L	0.055	3	102.47	3	100.17	2.09
Cd	5	ug/L	0.130	1	105.91	1	104.59	3.29
Sn		ug/L	0.107	10	102.86	10	103.53	1.88
Sb	10	ug/L	0.032	2	100.73	2	101.46	1.20
Ba	1000	ug/L	1.029	200	101.93	200	101.03	1.15
Hg	1	ug/L	0.064	0.2	106.05	0.2	107.84	3.42
Pb	50	ug/L	0.130	50	100.52	50	100.00	1.23

Table 4
NS-30 Performance Test Summary Results For All Elements Low AQC & Spike

Elements	PCV	Units	AQC	Recovery	Spike	Recovery	95% SD
Li		ug/L	180	101.14	180	100.15	2.02
B	2000	ug/L	2000	97.77	2000	97.40	1.85
Na	150	mg/L	120	102.65	120	101.61	2.48
Mg	50	mg/L	50	103.95	50	103.80	2.38
Al	200	ug/L	1800	99.81	1800	100.53	1.41
P	2200	ug/L	2200	98.74	2200	103.53	1.70
K	12	mg/L	12	103.97	12	101.31	1.26
Ca	250	mg/L	250	100.96	250	93.62	1.20
V		ug/L	50	98.84	50	97.70	2.26
Cr	50	ug/L	50	99.78	50	96.95	2.36
Fe	200	ug/L	1600	97.78	1600	95.99	2.94
Mn	50	ug/L	120	99.13	120	99.78	1.88
Co		ug/L	50	98.87	50	98.52	0.92
Ni	50	ug/L	50	101.14	50	98.76	1.45
Cu	3000	ug/L	3000	99.73	3000	98.17	0.90
Zn	5000	ug/L	5000	100.72	5000	98.47	1.36
As	50	ug/L	50	93.36	50	96.84	2.38
Se	10	ug/L	10	100.73	10	105.16	3.71
Sr		ug/L	600	100.48	600	94.38	0.76
Ag	10	ug/L	10	103.91	10	99.38	1.63
Cd	5	ug/L	5	103.58	5	102.52	1.71
Sn		ug/L	50	102.88	50	103.04	2.11
Sb	10	ug/L	10	100.50	10	100.65	0.61
Ba	1000	ug/L	1000	100.23	1000	98.48	1.08
Hg	1	ug/L	1	106.50	1	105.18	1.07
Pb	50	ug/L	90	99.70	90	100.26	1.12

Table 4
NS-30 Performance Test Summary Results For All Elements High AQC & Spike

Conclusions

The 4500 ICP-MS was applied to the analysis of drinking water, following the methodology defined in NS-30. Linear calibrations were obtained for trace elements at low and sub-ug/L levels, in the same acquisition as the major elements at 100's mg/L.

All QC criteria were met, and the system was validated for 21 NS-30 elements plus an additional 5 elements. Operating in a reduced sensitivity mode allowed for the measurement of high concentration elements, such as Na and Ca, while the wide dynamic range of the instrument still allowed detection limit criteria for trace elements such as Hg to be met.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5968-7602E



Agilent Technologies

Innovating the HP Way



New ASTM Standard: Recommended operating conditions for the Agilent Capillary Electrophoresis system

Maria Serwe

Environmental

Abstract

ASTM Subcommittee D19.05 on Inorganic Constituents in Water approved a new standard test method for determination of dissolved inorganic anions in aqueous matrices using capillary ion electrophoresis and chromate electrolyte¹. The Agilent Capillary Electrophoresis system provided equivalent performance during the inter-laboratory study preceding approval (c/w sect. 17.6 in test method). This document (reference B1.16 in test method) describes equivalent method parameters specific for the Agilent system equipped with DAD detection and computer control through Agilent ChemStation.




Figure 1
Analysis of waste water from a municipal waste treatment plant

Method Entries

Lift offset	4 mm
Cassette temp.	25° C
Preconditioning	
flush 1.1 min from flush buffer vial into waste vial	
Electric	on
Polarity	negative
Voltage	system limit
Current	0.00 µA
Power	system limit
Low current limit	0.00 µA
Time table	
0.3 min, current = 14.00 µA	
Injection	
by pressure, 50 mbar x 6.2 sec (37 nl)	
UV-detection	
Signal = 470/50 nm, reference = 275/10 nm, response time = 0.2 sec (PW > 0.01 min)	
Integration	
peak top type = center of gravity	
Calibration	
calculate with corrected areas	



Agilent Technologies

Innovating the HP Way

Method parameters

The parameters described here are supplementary to the test method (see also reference 2).

Capillary

Standard bare fused silica capillary ($L = 64.5$ cm, $l = 56$ cm, $75\text{ }\mu\text{m}$ id), fitted with a blue alignment interface. A new capillary is prepared by flushing 0.5 N NaOH for 5 min, water for 1 min and run buffer for 3 min (at 1 bar). If the current on a new capillary must be tested (c/w sect. 11.4), a voltage of 18.5 kV should be applied. If the system is idle overnight, leave the capillary in buffer. For long-term storage flush the capillary with water followed by air.

Vials


2-mL glass vials with polyurethane caps are used as buffer or waste container. 1-mL capped polypropylene vials are used as sample container. The buffer vials (inlet, outlet and flush buffer vial) are filled to 1 mL, the waste vial is filled with 0.6 mL buffer. For best migration time stability the run buffer vials should be replaced after 10 runs. It is not recommended to use the replenishment system with the Waters IonSelect™ High Mobility Anion Electrolyte.

Sample preparation

The waste water samples were diluted (1:20) and filtered through a $0.45\text{ }\mu\text{m}$ filter prior to injection.

Equipment

- Agilent Capillary Electrophoresis system
- Agilent ChemStation



References

1. D6508-00 (2000)
2. M. Serwe and J. Krol, "Determination of Dissolved Inorganic Anions in Aqueous Matrices Using Capillary Ion Electrophoresis and Chromate Electrolyte" Poster presentation at HPCE 2000 in Saarbrücken, Germany.

Maria Serwe is an application chemist at Agilent Technologies, Waldbronn, Germany.


For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 2000 Agilent Technologies
Released 03/2000
Publication Number 5968-8660E



Agilent Technologies

Innovating the HP Way



Analysis of Arsenic, Selenium and Antimony in Seawater by Continuous-Flow Hydride ICP-MS with ISIS

Application Note

ICP-MS

Environmental

Steve Wilbur

Analysis of arsenic and selenium in seawater at trace levels presents a number of challenges. While ICP-MS is generally considered to be a highly sensitive, interference free technique for analysis of trace metals in environmental samples, matrix effects can result in unacceptably high detection limits for these two elements. These matrix effects are based on two phenomena; 1) ionization suppression in the plasma of high ionization energy elements such as As (9.81 eV) and Se (9.75 eV) in the presence of a significant excess of easily ionizable elements such as Na (5.14 eV) and 2) spectral interferences by argon based polyatomic species such as ArCl and ArAr. For example, ArCl interferes

with the only isotope of arsenic and all the significant selenium isotopes suffer from polyatomic interferences of Ar, Cl, or Br. Optimum sensitivity therefore requires some mechanism for separating the analyte from the matrix and reducing or eliminating the argon based polyatomic species. Since arsenic, selenium and a number of other elements (Sb, Te, Bi, Ge, Sn, Pb) are known to form gaseous hydrides under specific reducing conditions, these elements can be removed from the matrix (for example the Na and Ca) and analyzed as gasses

in a flowing stream of argon. Reduction or elimination of argon polyatomics can be achieved in the Agilent 4500 or 7500 ICP-MS systems through the use of the ShieldTorch™ and cooler plasma conditions. As a result, by combining hydride generation with cool plasma/ShieldTorch, it is possible to lower the background equivalent concentrations for all As and Se isotopes to low ppb to mid ppt levels in seawater samples.




Figure 1. Full-scan Mass Spectrum of Selenium (20 ppb) Showing Excellent Agreement with Expected Isotope Ratios.



Agilent Technologies
Innovating the HP Way

Table 1. Common Interferences on As and Se by Normal Plasma, Direct Nebulization ICP-MS

Selenium Isotopes	% Abundance	Major Interferent(s)	% Abundance of Interferent Mass(s)
74	0.89	Ge	35.94
76	9.36	ArAr	0.671
77	7.63	ArCl	24.13
78	23.78	ArAr	0.125
80	49.61	ArAr, BrH	99.202, 50.682
82	8.73	Kr, BrH	11.6, 49.303
Arsenic Isotope			
75	100	ArCl, CaCl	75.48, 43.45

Reaction Chemistry:

For optimum sensitivity, accuracy and precision, both As and Se must be pre-reduced to the most efficient oxidation state for hydride formation. This is achieved through the use of a pre-reduction step. In the case of Se, pre-reduction to the +IV state can be achieved by the use of HCl plus heat. Arsenic requires a stronger reducing environment, in this case a solution of KI plus ascorbic acid is used to reduce As to the desired +III state.

Standards and Reagents:

Tune solution:

20 ppb solution of Se or As pre-reduced as follows.

Pre-reductant Stock for As and Sb (KI + ascorbic acid)

Dissolve 5 grams each KI and ascorbic acid in 100 mL DI water in a polyethylene bottle. Cap and shake to dissolve solids.

Reductant (NaBH₄ solution)

Weigh 0.5 g high-purity NaBH₄ and 0.125 g NaOH into a 250 mL polyethylene bottle. Bring to volume (250 mL), cap and shake to dissolve solids. Prepare fresh daily.

Calibration standards:

While plasma matrix effects are all but eliminated by using hydride generation, the efficiency of the pre-reduction and reduction steps can be affected by matrix. Therefore, best results will be obtained using matrix-matched standards. In the case of seawater, calibration by method of standard additions gives good results. The standard addition calibration can then be converted to an external standard calibration for analysis of subsequent seawater samples. Replicate 10 mL aliquots of CASS 3 or NASS 5¹ were spiked with a multi-element calibration stock containing selenium and pre-reduced as described below. Spike levels were 0, 0.01, 0.05, 0.1, 0.5, 1.0 and 5 ppb.

Pre-reduction of samples and standards:

- Arsenic (Antimony and Bismuth)

10 mL of sample (seawater) is added to a 50 mL polypropylene centrifuge tube. 1 mL of the KI/ascorbic acid pre-reduction reagent is added with swirling. 3 mL of concentrated trace metal grade HCl is added with swirling. The tube is capped loosely and allowed to set for 15 minutes after which it is brought to a final volume of 25 mL with 18 MOhm deionized water.

- Selenium (and Tellurium)

10 mL of sample is added to a 50 mL polypropylene centrifuge tube. 10 mL of concentrated, trace metal grade HCl is slowly added with swirling. The tube is loosely capped and heated in a heat block or boiling water bath at 100 degrees C. for 10 minutes. After allowing to cool, the sample is brought to 25 mL final volume with 18 Mohm DI water.

¹ National Research Council, Canada

Tuning

Optimized tuning involves maximizing the analyte signal(s) while minimizing

Basically, a combination of forward power, sample gas flow (carrier plus makeup), and sample depth which minimizes m/z 78 and 80 in the blank and maximizes those masses in the tune solution (20 ppb Se, pre-reduced as described) is desired.

background may be due to trace Se in the reagents used for pre-reduction or hydride formation. Now aspirate the 20 ppb Se tuning solution. Set the acquisition masses at 78, 80 and 82. Set the displayed ion ratio to calculate the ratio of 82 to 80. The natural isotope ratio of Se82 to Se80 is 8.73/49.61 or 17.59%. Therefore as the displayed ratio approaches 17.6%, the background at m/z 80 due to ArAr is minimized. Try to maximize the signal at 78 while maintaining as close to 17.6% for 82/80 as possible.²




Figure 2. Tune Screens, 20 ppb Se Standard and Prep Blank

the interferences. Since the interferences are primarily due to argon-based polyatomics, the use of ShieldTorch with slightly reduced forward power to minimize the ionization of Ar is quite effective. The following conditions were set to allow the measurement of Se at m/z 78 or 80 and also work quite well for As.

As a first step, while aspirating a prep blank under hydride generating conditions, try to reduce the background at m/z = 80 to 10-20,000 counts per 0.1 sec. This is accomplished by cooling the plasma using a combination of RF power and carrier/makeup gas. See figure 2 for sample tune conditions. Some of the




Figure 3. Se spike in CASS 3 Showing Interferences at m/z 80 and 82 from BrH

² Note: This must be done on a clean Tune solution, not a sea water spike since BrH from the sea water can cause high background at both 80 and 82. Occasionally, krypton (m/z 82) in the argon supply can be sufficiently high to adversely affect the ratio as well.

ISIS Program

The ISIS program builder was used to create the ISIS program below. Typical values for ISIS parameters for hydride generation are shown. As a rule, sensitivity increases with sample

flow at the expense of sample consumption. The ratio of sample to reductant is important and should be optimized as well. Normal rinseout times are very fast due to the high sample flows utilized.

The screenshot displays the 'MPM Builder - hydride.MPU' application. It features three sequence editors and a 'Set Parameters' dialog box.

Sequence Parameter Table:

	Ena	Name	Type	Frac	Min	Max	Unit
<P1>	YES	Analysis Speed	NUM	2	-1.00	1.00	rps
<P2>	YES	Reductant Speed	NUM	2	-1.00	1.00	rps
<P3>	YES	Uptake Speed	NUM	2	-1.00	1.00	rps
<P4>	YES	Uptake Time	NUM	0	0.00	120.00	sec
<P5>	YES	Stabilization time	NUM	0	0.00	120.00	sec
<P6>	YES	Rinse Speed	NUM	2	-1.00	1.00	rps
<P7>	YES	Rinse Time	NUM	0	0.00	60.00	sec
<P8>	YES	Optional Rinse Vial	NUM	0	0.00	5.00	ALS Pos.
<P9>	YES	Optional rinse Time	NUM	0	0.00	120.00	sec

Sequence-1 "PreRun"

	Duration	Scan	ALS	Pump1	Pump2	Valve1	Valve2	AUX1	AUX2	AUX3
1	<P4>	---	---	<P3>	<P2>	LOAD	LOAD	OFF	OFF	OFF
2	<P5>	---	---	<P1>	<P2>	LOAD	LOAD	OFF	OFF	OFF

Sequence-2 "StartRun"

	Duration	Scan	ALS	Pump1	Pump2	Valve1	Valve2	AUX1	AUX2	AUX3
1	1	Start	---	<P1>	<P2>	LOAD	LOAD	OFF	OFF	OFF

Sequence-3 "PostRun"

	Duration	Scan	ALS	Pump1	Pump2	Valve1	Valve2	AUX1	AUX2	AUX3
1	<P7>	---	Rinse	<P6>	<P2>	LOAD	LOAD	OFF	OFF	OFF
2	<P9>	---	<P8>	<P6>	<P2>	LOAD	LOAD	OFF	OFF	OFF

Set Parameters Dialog:

Analysis Speed	0.30	rps
Reductant Speed	0.20	rps
Uptake Speed	0.30	rps
Uptake Time	45	sec
Stabilization time	0	sec
Rinse Speed	0.30	rps
Rinse Time	5	sec
Optional Rinse Vial	1	ALS Pos.
Optional rinse Time	30	sec

Buttons: OK, Cancel, Help

Figure 4. ISIS Program Builder and Method ISIS Parameters Showing Prerun, Startrun and Postrun Programs and Setpoints for ISIS Pumps




Figure 5. Selenium Standard Addition Calibration in DI Water at 0, 10, 50, 100 and 500 ppt.




Figure 6. Standard Addition Calibration in CASS 3 Standard Reference Seawater. Calibration Levels; 0, 10, 50, 100, and 500 ppt.

Analysis of Certified Reference Materials

Seawater certified reference materials CASS 3 and NASS 5 were analyzed for As, Se and Sb. Standard addition calibrations were prepared by spiking 10 aliquots of sample with a mixed calibration solution containing the elements of interest. Standard addition calibrations were prepared and then converted to external calibrations for subsequent sample analysis. 3 sigma MDLs were calculated from seven replicate analyses of the unspiked seawater samples using the converted external calibrations. Spike recoveries were also calculated for samples spiked at 0.05 and 2.5 ppb for both elements.




Figure 7. Arsenic in CASS 3 by Standard Addition




Figure 8. Antimony in CASS 3 by Standard Addition

Summary

The use of online, continuous-flow hydride generation coupled to the Agilent 4500 or 7500 ICP-MS offers a fast, sensitive, routine analytical technique for the analysis of the hydride forming elements such as As, Se and Sb in difficult matrices such as seawater. The process can be fully automated

for multiple samples using the Cetac ASX-500 autosampler and the Agilent Integrated Sample Introduction system (ISIS). 3-sigma detection limits are typically 10 – 30 ppt for these elements, which is below ambient levels for all three. However, slightly elevated background equivalent concentration for Se can make ambient-level Se analysis borderline at best.

The use of purified reagents may help to reduce the BEC for Se to levels closer to the calculated detection limit. When compared to direct nebulization ICP-MS analysis of 10X diluted seawater, detection limits are improved from 10 to 50 times with no long-term matrix effects on the ICP-MS interface or ion lenses.

Table 2. Results of Analysis of Certified Reference Seawater Materials

Sample	Element /Isotope	Measured Value	Certified Value	Spike Amount	Blank Measurement	% Recovery ⁽³⁾	MDL (4)
CASS 3	As/75	1.12 ppb	1.09	N/A	-	102	0.03
CASS 3	Se/78	0.682 ⁽¹⁾	0.042 ⁽²⁾	0.5	0.193	97.6	0.01
CASS 3	Sb/121	0.34	not certified	0	-	-	0.02
NASS 5	Sb/121	2.87	not certified	2.5	0.34	101	0.02
NASS 5	As/75	1.21 ppb	1.27	N/A	-	95	0.03

(1) raw measured concentration, not corrected for prep(reagent) blank

(2) total selenium is listed but not certified in CASS 3

(3) recovery calculated against certified value where available and against matrix spike recovery where certified value is not available.


(4) 3-sigma using seven replicates

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
 Agilent Technologies, Inc.
 Printed in Japan (03/00)
 5980-0243E



Indirect Determination of Fluoride Traces in Natural Waters by Ion Chromatography and ICP-MS Detection

Application Note

ICP-MS

Environmental

Maria Montes Bayon, University of Oviedo, Spain

Abstract

ICP-MS has been widely accepted as a powerful analytical technique for trace element determination in a wide variety of sample types. The technique is rapid, measures virtually all elements in a single acquisition and has limits of detection typically at or below the ng/L (ppt) level. Even initially problematic elements, such as K, Ca, Fe, As and Se, are now routinely measured using the power and flexibility of the Ar ICP to preferentially remove troublesome spectral overlaps.

However, there are some analytical challenges which cannot be overcome by plasma optimisation, most notably the analysis of elements which are not ionised in the Ar plasma. This Application Note presents a novel method for the indirect determination of one such element, fluorine, where the preliminary data indicates that the ICP-MS measurement is not

only possible, but offers significant advantages over traditional analytical methods.

4B	5B	6B	7B	0	
				2 4.003 He helium 24 581 54 403 -268.9	1
6 12.01 C carbon 11.256 13500 24.376 4918	7 14.01 N nitrogen 14.53 -209.9	8 16.00 O oxygen 13.614 -218.4	9 19.00 F fluorine 17.418 -219.6 -188.1	10 20.18 Ne neon 21.589 -248.7 31.07 -246.1	2
14 28.09 Si silicon 8.149 1414 16.34 2642	15 30.97 P phosphorus 10.484 44.1 19.72 279.8	16 32.07 S sulfur 10.357 112.8	17 35.45 Cl chlorine 13.01 -101	18 39.95 Ar argon 15.755 -189.2 185.9	3
32 72.61 Ge germanium 7.88 958.5 15.93 2691	33 74.92 As arsenic 9.81 18.63	34 78.96 Se selenium 9.75 220.2 21.5 684.9	35 79.90 Br bromine 11.84 -7.2 21.6 57.9	36 83.80 Kr krypton 13.996 -156.6 34.56 -153.4	4
50 118.7 Sn tin 7.342 232.0 14.628 2270	51 121.8 Sb antimony 8.639 630.7 16.5 1617	52 127.6 Te tellurium 9.01 449.8 18.6 989.8	53 126.9 I iodine 10.454 113.6 19.09 182.8	54 131.3 Xe xenon 12.127 113.9 21.2 -108.1	5

Fluorine first Ionisation Potential - 17.418 eV

Argon first Ionisation Potential - 15.755 eV



Agilent Technologies
Innovating the HP Way




Figure 1 Experimental Set-Up for Fluoride Determination

Table 1 Typical Operating Conditions

Instrument	HP 4500
Rf Power	1300 Watts
Nebuliser	Meinhard
Spray Chamber	Scott type, double pass, room temperature
Sampling depth	5.7 mm
Gas Flow Rates:	
Cool	15 L.min ⁻¹
Auxiliary	1 L.min ⁻¹
Carrier	1.17 L.min ⁻¹
Oxide level (CeO ⁺ /Ce ⁺)	<0.5 %
Doubly charged level (Ce ²⁺ /Ce ⁺)	<1%

Measurement of Fluoride

During the last decade, the majority of fluoride determinations have been performed using techniques such as potentiometry with fluoride Ion Selective Electrodes (ISE) , ion-chromatography with conductivity detection and, most recently, capillary ISEs has been the preferred technique, but is limited to determinations in the limited to determinations in the mg/L (ppm) range.

The chromatographic separation of Al-fluoride species was first described by Bertsch and Anderson, who

determined the stability constants of several AlF_x species. In acid aqueous solution, aluminium ions are present as [Al (H₂O)₆]³⁺ which can react with F⁻ to form the AlF₂⁺ complex.

Optimum PH for the complex formation seems to be between 2-4, therefore in the present work pH 2.6-3 was selected, where the complex AlF₂⁺ proved to be stable.

Samples and standard solutions were adjusted to pH=3 with nitric acid and spiked with Al³⁺ requiring at least a 5-fold weight excess of Al to fluoride to assure that only AlF₂⁺ was formed. The samples were

diluted by weight, transferred to 10ml polypropylene test tubes and immersed in a water bath at 50°C for 60 minutes, to ensure quantitative formation of the AlF₂⁺ complex. Under these conditions, several parameters were evaluated to obtain selective separation of the complex AlF₂⁺ in a 5 cm long ion exchange Dionex Ion Pac Column HPIC-CG2. HNO₃ was found to be an effective eluent for the separation of AlF₂⁺ from the excess of Al³⁺. Different molarities of nitric acid, from 0.15 M to 0.75 M, were tested and the conditions chosen for future studies were 0.45 M nitric acid at a flow rate of 0.5 mL/min. The AlF₂⁺ complex was measured indirectly by ICP-MS by collecting data for Al at mass 27.

Figure 1 shows the instrumental set-up of the IC-ICP-MS system. The exit tube from the column was connected directly to the concentric nebulizer of the ICP-MS, which can accept flow rates anywhere from 20uL/min to over 2mL/min.

ICP-MS operating conditions are summarised in Table 1.




Figure 2 Chromatogram Corresponding to 20 ng.g⁻¹ F⁻

Table 2 Analytical Characteristics

Analytical Characteristics	ICP-MS Detection
Detection Limit	0.1 ng.g ⁻¹
Precision	4 % ⁽¹⁾
Linear Range	up to 100 ⁽²⁾ ng.g ⁻¹
Regression coefficient (r) (n=7 points)	0.9993

(1) on 5 injections of 20 ng.g⁻¹ fluoride

(2) using 500 ng.g⁻¹ aluminium

The chromatogram obtained under these conditions for 20 ng/g F⁻ in the presence of 100 ng/g of Al is shown in Figure 2.

As can be observed, two aluminium containing peaks are detected. The first peak could be ascribed to the AlF²⁺ complex as its peak height/area was found to be proportional to the

concentration of fluoride in the sample.

Analytical Performance Characteristis

Analytical performance characteristics are summarised in Table 2. The linear dynamic range for fluoride determination depends on the

aluminium excess added to the sample. It was observed that, for a given aluminium concentration, the upper linear limit for fluoride determinations was about one fifth of the total aluminium concentration. Aluminium concentrations higher than 500 ng/g were not tested, to avoid contamination effects in the ICP-MS. In practice, it should be straightforward to dilute samples to a level of fluoride where Al addition would be at an acceptable level, as shown in this study. Alternatively, ISE could be used as a screening tool, after which the IC-ICP-MS method could be used to determine those fluoride levels which were found to be below the limit of detection for ISE.

The detection limit obtained by the IC-ICP-MS method was 0.1 ng/g, calculated as three times the standard deviation of the blank, divided by the slope of a linear calibration between 0-5 ng/g. As can be observed, the detection limit using ICP-MS detection is one of the lowest ever reported for the determination of fluoride.

Figure 3 shows a typical calibration curve obtained from 5 to 50 ng/g (ppb)

of fluoride and containing 200 ng/g aluminium in each standard solution. The linear calibration demonstrates that the peak area of the complex is proportional to the fluoride concentration. Determination of Fluoride in Fresh and Sea Water Samples.

Under the optimum separation conditions using HNO_3 for elution, the retention time for Al^{3+} is under 7 minutes, allowing a sampling rate of 6-7 samples per hour. To evaluate the use of the proposed ICP-MS method in routine operation, it was applied to the determination of fluoride in natural and drinking waters from a variety of sources and with different saline concentration.

At this time, no stable aqueous fluoride reference material was available, so it was decided to compare the proposed methodology with the fluoride ion selective electrode (FISE). Since many natural water samples contain fluoride levels below the limit of detection of FISE, a spike-recovery exercise was also undertaken.

In order to minimise aluminium addition to the samples and contamination of the ICP-MS, up to 200 fold dilution of some drinking and sea-water samples was necessary. The results obtained are summarised in Table 3.

Some of the water samples contained fluoride levels too low to be measured by FISE (at around 150 ng/g), so comparison between the FISE method and the IC-ICP-MS method was not possible. However, where FISE was able to measure the levels present, good agreement with the IC-ICP-MS results was obtained. In the other cases tested, the spike recovery exercise indicated that the IC-ICP-MS method gave good recoveries (within $100 \pm 10\%$), showing the applicability




Figure 3 Typical Calibration Curve of Fluoride

Table 3 Results Obtained for Fluoride in Water Samples Using ICP-MS

Water Sample (dilution factor)	Conc. found(n=3) ICP-MS(ng.g^{-1})	Conc. found FISE (ng.g^{-1})	Spiked amount (ng.g^{-1})	Recovery (%)
Fontecelta (200)	8050 ± 80	7700	4300	104
Font-Vella (10)	182 ± 2	-	205	97.8
Tap-water (10)	161 ± 1	-	210	90
*Sea-water(100)	1030 ± 60	1080	1080	97.5

of the proposed methodology to perform fluoride determination at extremely low levels in natural water samples.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.
Visit our website at
<http://www.agilent.com/chem/icpms>


Copyright © 2000
Agilent Technologies, Inc.
Printed in Japan (02/00)
5968-8232E



Water

Other
Applications

> [Return to Table of Contents](#)
> [Search entire document](#)



Time-of-Flight LC/MS Identification and Confirmation of a Kairomone in *Daphnia magna* Cultured Medium

Application

Natural Product Chemistry

Authors

Hideaki Uchida
Agilent Technologies Japan, Ltd.
Tokyo
Japan

Jerry A. Zweigenbaum
Agilent Technologies Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Takenori Kusumi and Takashi Ooi
The University of Tokushima
Tokushima
Japan

Abstract

***Daphnia* kairomones induce morphological change to green alga. An active compound (8-methylnonyl sulfate), which was originally isolated and determined from *Daphnia pulex* body, was identified from a cultured medium of *Daphnia magna* by liquid chromatography/time-of-flight mass spectrometry (LC/TOF-MS) with electrospray ionization after concentration by the Methylene Blue method.**

Introduction

A pheromone is a chemical substance that triggers a variety of behavioral responses in another member of the same species. On the other hand, a kairomone is a chemical substance released by an organism that affects other organisms in a food chain series. It was reported that a unicellular

green alga achieved morphological change into 2-, 4- and 8-colonies when the water was cultured with *Daphnia*. However, neither isolation nor elucidation of active compounds has been completed due to the very low concentration of the compounds in the cultured medium. A unique approach was tried: the active compounds were isolated from commercially available frozen *Daphnia pulex* body (10 kg) and the structure of the compounds determined with a combination of purification, chemical synthesis, and bioassay. The synthesized aliphatic sulfates undoubtedly showed activity to induce morphological changes of phytoplankton at an optimum concentration of low ppb (10^{-6} g/L). Because the *Daphnia* kairomones are anion surfactants, they are quantitatively detected with the Methylene Blue method [1]. The concentration of total anion surfactants in *Daphnia* cultured medium was determined at 8.0 ppb. However, this method quantified only the total amount of the surfactants and each active compound was not chemically identified.

The active compounds were isolated from *D. pulex*, but *D. magna* was used for the assay. The frozen *D. pulex* is commercially available; however, *D. magna* is larger in size than *D. pulex* and easy to assay albeit difficult to cultivate at kg-scale. It is possible for each species to release different compounds. Consequently, we report identification and confirmation of kairomones in *D. magna* cultured medium [2].

It is actually impossible to detect these aliphatic sulfates directly using HPLC with commonly used detectors such as ultraviolet absorption or fluorescence. As for LC/MS, electrospray ionization (ESI) in negative ion mode is best matched for these



Agilent Technologies

compounds because all target sulfates ($\text{R-OSO}_3^-\text{M}^+$) or amidosulfates ($\text{R-NHSO}_3^-\text{M}^+$) ionize well and can easily dissociate to R-OSO_3^- or R-NHSO_3^- in aqueous solution, respectively. LC/TOF-MS benefits from the increased identification capability of compounds in comparison to a quadrupole analyzer due to its accurate mass measurement capability.

Therefore, in this study we chose LC/TOF-MS with ESI to directly detect and identify the active compounds in the *D. magna* cultured medium. Furthermore, the orthogonal spray position of this LC/MS ion source resists ion suppression from the sample even though it contains significant matrix components.

Experimental

Compounds 1, 6, and 7 were commercially available from Sigma-Aldrich Japan K.K. (Tokyo, Japan), Kanto Chemical, Co., Inc. (Tokyo, Japan), and Tokyo Chemical Industry Co., Ltd. (Tokyo, Japan), respectively. Compounds 2, 3, and 5 were synthesized. Compound 4 was isolated from the cultured medium.

The instrument performed the internal mass calibration automatically and constantly, using the second electrospray nebulizer with an automated calibrant delivery system that introduced a low flow of a calibrating solution containing the internal reference mass compounds (m/z 112.9856 and 1033.9881). The instrument software constantly corrects the measured masses of all the spectra using the known masses as reference.

Five liters of *D. magna* cultured medium (250 adult bodies per liter dechlorinated tap water, 1 week) was concentrated to 100 mL and treated by the Methylene Blue method. Subsequently, the Methylene Blue reagent was removed by cation exchange resin (DOWEX 50WX8-100). The concentrated sample was dried and dissolved in 25 mL of Milli-Q water for LC/MS analysis. When treatment was complete, the cultured medium was concentrated to 200 times of the original volume. Authentic standards, shown in Table 1 (each at 100 ppb, except for 4, because it was isolated from the cultured medium and no authentic standard was obtained), and the concentrated cultured medium sample were analyzed by LC/TOF-MS with the ESI source under the same conditions.

LC/MS Method Details

LC Conditions

Instrument:	Agilent LC 1100
Column:	ZORBAX Eclipse XDB-C18 50 mm $\times$ 2.1 mm 3.5 μm (p/n 971700-902)
Column temp.:	40 $^\circ\text{C}$
Mobile phase:	A: 10 mM ammonium acetate aqueous solution B: acetonitrile
Gradient and flow rate:	30% B at 0 min (0.3 mL/min) 30% B at 3 min (0.3 mL/min) 95% B at 8 min (0.3 mL/min) 95% B at 8.1 min (0.5 mL/min) 95% B at 12 min (0.5 mL/min) 30% B at 12.1 min (0.5 mL/min) 30% B at 17 min (0.5 mL/min)
Injection volume:	10 μL

MS Conditions

Instrument:	Agilent 6210 TOF LC/MS
Source:	Negative ESI
Drying gas flow:	10 L/min
Nebulizer:	350 kPa
Drying gas temp.:	350 $^\circ\text{C}$
V_{cap} :	5000 V
Fragmentor:	250 V
Scan mode:	m/z 50-1100, 10,000 transients/scan, 0.89 scan/sec.
References mass:	m/z 112.9856 and 1033.9881

Results and Discussion

Six sulfates (1, 2, 3, 5, 6, and 7) and one amidosulfate (4) were separated by using the volatile buffered mobile phase (ammonium acetate and acetonitrile) for LC/MS. Thus even though 2 and 3, and 5 and 6 were two pairs of isomers they each could be distinguished chromatographically. Analysis time was substantially reduced to less than 10 min by using a short column (50 mm) packed with small particles (3.5 μm). Automatic continuous mass-axis correction with the two known reference compounds gives extremely accurate mass measurement. This provides fewer potential empirical formulas not only for the synthetic compounds but also for the unknown compounds in the *Daphnia* cultured medium.

To yield both the deprotonated molecule and the m/z 97 fragment (HOSO_3^-), in-source collision-induced dissociation (CID) was used. By setting the MS fragmentor to 250 V, familial fragments (m/z 97) in the mass spectra of all the aliphatic sulfates were observed together with each

deprotonated molecule. The extracted ion mass chromatogram of the m/z 97 fragment is a selective indicator of the targets, as shown in Figure 1. The measured mass error of the deprotonated molecule ($[M-H]^-$) in each standard compound is less than 0.4 mDa, as shown in Table 1.

Table 1. Measured Mass Accuracy of Authentic Standards

No.	$[M-H]^-$	Calcd. m/z	Measured m/z
1	$C_8H_{17}O_4S$	209.0853	209.0857
2	$C_9H_{19}O_4S$	223.1009	223.1011
3	$C_9H_{19}O_4S$	223.1009	223.1013
4	$C_{11}H_{24}NO_3S$	250.1482	250.1484
5	$C_{10}H_{21}O_4S$	237.1166	237.1167
6	$C_{10}H_{21}O_4S$	237.1166	237.1164
7	$C_{12}H_{25}O_4S$	265.1479	265.1481

D. magna cultured medium was concentrated by the Methylene Blue method, and subsequently the Methylene Blue reagent was removed with cation exchange resin. The method was modified to effect a 200-fold concentration of the Methylene Blue complex with anion in an organic layer. The concentrated cultured medium was analyzed by LC/TOF-MS with the ESI source under the same conditions.

The mass chromatogram of the m/z 97 fragment ion is a selective indicator of sulfate targets and is especially useful for identification of compounds containing sulfate in complex matrices as in the cultured medium (Figure 2). The retention time of the mass chromatogram of both m/z 97 and 237 in Figure 2 matches that of standard 5 in Figure 1. This strongly suggests that the cultured medium contains compound 5.




Figure 1. Structures and mass chromatograms for the $[M-H]^-$ ions of authentic standards and the familial fragment ion for sulfate.




Figure 2. Total ion chromatogram (TIC) and mass chromatogram of *Daphnia* cultured medium.

Using the mass spectral data described below, 5 was identified and confirmed in the *D. magna* cultured medium. Accurate mass measurement of the deprotonated molecule ($[M-H]^-$ in negative ion mode) can give both the molecular weight of the compound and its empirical formula. Low-level error has significant implications when trying to propose possible empirical formulas of unknowns. Actually, at 10 ppm accuracy, m/z 237.1169 (Figure 3) provides only three possible empirical formulas, with the elemental composition restricted to combinations of C_{0-20} , H_{0-45} , N_{0-5} , O_{0-5} , and S_{0-5} : $C_{10}H_{21}O_4S$ (error 0.3 mDa), $C_{11}H_{17}N_4S$ (error -1.0 mDa), and $C_{14}H_{13}S$ (error 2.3 mDa).

Accurate mass measurement of fragment ions also provides the atoms that those portions of the molecule contain (valuable structural information). At 10 ppm accuracy, m/z 96.9602 provides only one possible empirical formula with the same condition

described above: HO_4S (error 0.1 mDa). Accuracy of 20 ppm for m/z 96.9602 provides three possible empirical formulas with elemental composition restricted to the same combinations: HO_4S , C_4HOS (error -15 mDa) and HO_2S_2 (error 18 mDa).

The detected and confirmed 8-methylnonyl sulfate (5) is similar to one of the commonly used surfactants, sodium dodecyl sulfate (SDS, sodium salt of 7). All other active kairomone compounds described here also behave as surfactants due to both polar and nonpolar sites in the molecule. Large amounts of surfactants have been produced as detergents and partially released to the environment. Thus, it is a concern that environmentally released concentrations of surfactants acting as the kairomone would indirectly confuse the food chain in lakes and marshes and cause significant ecological disruption.




Figure 3. Mass spectrum of the peak at 5.1 min in the *Daphnia* cultured medium in Figure 2.

Conclusions

The kairomone is identified by the combination of LC/TOF-MS with ESI with sample preparation by the simple Methylene Blue method. The identification is confirmed by comparison of the retention time and mass spectrum of the synthetic standard compound with those of the actual sample. The mass error is 0.3 mDa between the actual sample result and the calculated m/z . The method needs no derivatization and shows low background due to using ESI in negative ion mode. Target compounds containing the SO_4 moiety were selectively screened by an MS instrument parameter (fragmentor voltage) adjustment. A fully automated introduction system of reference compounds for mass axis calibration gives very stable and reliable mass accuracy results.

Although the presence of other kairomone compounds may be assumed, this is the first direct chemical detection of the *Daphnia* kairomone from a cultured medium.

Reference

1. K. Aomura, N. Ashidate, T. Aisawa, M. Fujita, K. Goto, K. Hasebe, S. Hikime, A. Ikehata, S. Kawamura, M. Kimura, et al., In Mizu no Bunseki ed., The Japan Society for Analytical Chemistry: Hokkaido, Kagaku-Dojin, Kyoto (1981), pp 374-378
2. Hideaki Uchida, Ko Yasumoto, Akinori Nishigami, Jerry A. Zweigenbaum, Takenori Kusumi, and Takashi Ooi. "Time-of-Flight LC/MS Identification and Confirmation of a Kairomone in *Daphnia magna* Cultured Medium," *Bull. Chem. Soc. Jpn.* Vol. 81, No. 2, 298-300, (2008)

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
April 17, 2008
5989-8387EN



Agilent Technologies



Analysis of ionic tenside surfactants in wastewater by HPLC

Rainer Schuster

Environmental

Abstract

The detergents used for cleaning floors, worktop surfaces and laundry in the home and hygiene industry are the main source of the ionic species of surfactants known as tensides.

Sample preparation

Tensides can be extracted from either surface water or waste water by a liquid–solid technique. Narrow bore technology for lowest solvent consumption and highest sensitivity, with automated diode-array detection for evaluating peak purity and identity.

Separation

Figure 1 shows a normal flow rate elution on a 10 cm Hypersil ODS column with 2.1 mm internal diameter, 5 µm particles. A simple linear gradient and a constant oven temperature of 40 °C achieve good resolution.

- UV absorbance detection or
- Diode-array detection—for peak purity check and peak identity confirmation using UV absorbance spectra.




Figure 1
Separation of 10 µl injection of a Marlon A ionic tenside surfactant standard

Conditions

Column

250 x 2.1 mm Hypersil ODS C18, 5 µm

Mobile phase

A: 0.005 M KH_2PO_4

B: acetonitrile

Gradient

0 min 26% B

20 min 100% B

Flow rate

0.25 ml/min

Temperature

40 °C

Detection

222 nm (20 nm bandwidth)

reference 450 nm (100 nm bandwidth)



Agilent Technologies

Innovating the HP Way




Figure 2
Analysis of linear alkylbenzenesulfonates (LAS), alkylphenol polyethoxylates (APEO) and nonylphenol in waste water

References

1. Rainer Schuster, "Analysis of ionic tenside surfactants in wastewater by HPLC and diode-array detection," *Hewlett-Packard application note*, publication number 12-5091-1818E,

Conditions

Column

250 x 2.1 mm Hypersil
ODS C18, 5 μ m

Mobile phase

A: 0.005 M KH_2PO_4
B: acetonitrile

Gradient

0 min 26% B
20 min 100% B

Flow rate

0.25 ml/min

Temperature

40 $^{\circ}\text{C}$

Detection

222 nm (20 nm bandwidth)
reference 450 nm
(100 nm bandwidth)

Equipment

Agilent 1100 Series

- vacuum degasser
 - quaternary pump
 - autosampler
 - thermostatted column compartment
 - diode array detector
 - fluorescence detector
- Agilent ChemStation + software

Rainer Schuster is application chemist at Agilent Technologies, Waldbronn, Germany.

For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 10/97
Publication Number 5966-1877E



Agilent Technologies


Innovating the HP Way



Soil & Sediment

Volatiles Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)



Fast Analysis of Landfill Gas by Agilent Micro 3000 GC with Performance-Enhanced System

Application Note

Hydrocarbon Processing

Authors

Wenmin Liu
Agilent Technologies Co. Ltd.
412 Ying Lun Road
Waigaoqiao Free Trade Zone
Shanghai, 200131
China

Abstract

A fast and accurate solution is provided for landfill gas component analysis by the Agilent 3000 Micro GC configured with two performance-enhanced modules. The individual components are baseline separated in less than 30 seconds by a two-channel configured Micro GC. With this solution, landfill gas can be monitored and controlled easily.



Agilent Technologies

Introduction

Throughout the world, millions of tons of waste are deposited into landfills. That waste in landfills should be monitored for many years. The waste within the landfill will consist of a wide variety of substances, but a large proportion will be biodegradable, including animal and vegetable matter, paper, and wood. Landfill gas is a complex mixture of gases, but a few gases predominate. Generally, methane, carbon dioxide, and nitrogen are the main components that contribute more than 90 percent of landfill gas. Many other gases can be produced in trace amounts and the exact composition of the landfill gas will vary between different landfill sites, different parts of the same site, and over time. Clearly this gas has to be monitored and controlled. A level of 5 percent of methane in air is explosive. Some other components of landfill gas are dangerous to the health of people living nearby the landfill sites. Landfill operators are also legally required to monitor and control landfill gas on their site.

The Agilent 3000 Micro GC is a powerful tool for the fast analysis of gaseous analytes [1–3], and its robust construction and multiple channel configurations make analyzing complex samples quick and easy. The Agilent 3000 Micro GC with its newly developed performance-enhanced module is specially designed for the analysis of low-concentration components. In this application, an efficient solution is developed to analyze gas components in landfill gas by the Agilent 3000 Micro GC with performance-enhanced modules.

Experimental

Sample

The landfill gas standard was provided by Beijing AP BAIF Gas Industry Co. Ltd. (Beijing, China). The compositions and concentrations are shown in Table 1.

Table 1. Standard Compositions and Their Concentrations

Component	Concentration ($\mu\text{L/L}$)
CH_4	399.5
C_2H_6	174.5
CO_2	132.5
O_2	100
H_2S	254
N_2	Balance gas

Configurations and Analytical Conditions

The Agilent 3000 Micro GC configured with two performance-enhanced modules is used for the fast analysis of landfill gas. The PLOT U column channel (PLOT U, $8\text{ m} \times 0.32\text{ mm} \times 30\text{ }\mu\text{m}$) is responsible for the separation of CO_2 , C_2H_6 , and H_2S . The second channel is a molecular sieve (MS) column (PLOT-U, $3\text{ m} \times 0.32\text{ mm/MolSeive } 5\text{ \AA}$ PLOT, $10\text{ m} \times 0.32\text{ mm}$) for the separation of O_2 , N_2 , and CH_4 . The injectors used are the variable-volume type for PLOT U channel and backflush mode for MS channel; helium was used as the carrier gas. The analytical conditions are shown in Table 2.

Table 2. Analytical Conditions of Two-Channel Micro GC

Channel	Molecular sieve (PLOT-U, $3\text{ m} \times 0.32\text{ mm}/$ MolSeive $5\text{ \AA}$ PLOT, $10\text{ m} \times 0.32\text{ mm}$)	PLOT U ($8\text{ m} \times 0.32\text{ mm}$ $\times 30\text{ }\mu\text{m}$)
Sample inlet temp. ($^{\circ}\text{C}$)	60	60
Injector temp. ($^{\circ}\text{C}$)	80	80
Column temp. ($^{\circ}\text{C}$)	70	70
Inject time (ms)	100	100
Run time (s)	100	100
Column pressure (psi)	30	30

Results and Discussion

CO_2 , C_2H_6 , and H_2S were separated within 60 seconds. The analytical time for separation of O_2 , N_2 , and CH_4 was also less than 60 seconds. Figure 1A shows the chromatogram of channel A, and Figure 1B shows the chromatogram of channel B.




Figure 1. Chromatograms of landfill gas on PLOT U channel (A) and MS channel (B).

Table 3 shows the run-to-run repeatability by relative standard deviations (RSDs) of the peak height. The RSDs of separated components are all less than 1%, showing that the Micro GC is stable and reliable.

Table 3. Reproducibility of Two-Channel Micro GC Solution

Compound	Avg. R.T.	Avg. peak height	Peak height S. D.	R. S. D. (N = 10)
O ₂	0.443	193963.28	1671.26	0.86%
N ₂	0.553	1211399.24	6496.73	0.54%
CO ₂	0.447	1868.49	17.61	0.94%
CH ₄	0.807	1878.01	6.44	0.34%
H ₂ S	0.811	1336.20	18.35	1.37%

Conclusions

The Agilent 3000 Micro GC with performance-enhanced modules provides a fast and reliable method for the analysis of landfill gas samples. Six key components can be separated in less than

60 seconds with good repeatability, H₂S, the sulfur compound existing in landfill gas, can also be detected on such a two-module micro GC with the detection limit of 20 ppm (V/V).

References

1. M. Feeney, P. Larson, and B. Wilson, "Analysis of Fuel Cell Reformer Gases in Seconds Using the Agilent 3000 Micro Gas Chromatograph," Agilent Technologies publication 5988-5296 EN
2. M. Feeney and P. Larson, "Complete Analysis of Refinery Gases in Seconds Using the Agilent 3000 Micro Gas Chromatograph," Agilent Technologies publication 5988-6700EN

3. M. Feeney and C. K. Lo, " Micro GC Analysis of Natural Gas and LPG in Seconds Using the Agilent 3000 Natural Gas Analyzer," Agilent Technologies publication 5988-2420EN
4. Wenmin Liu, " Fast Analysis of Coal Mine Gas by the Agilent 3000 Micro GC," Agilent Technologies publication 5989-7432EN

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Published in the USA
September 18, 2008
5989-9249EN



Agilent Technologies



Ultra-Fast Total Petroleum Hydrocarbons (TPH) Analysis with Agilent Low Thermal Mass (LTM) GC and Simultaneous Dual-Tower Injection

Application Note

Environmental

Authors

Wei Luan
Agilent Technologies (Shanghai)
Co., Ltd.
412 Ying Lun Road
Shanghai 200131
China

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington DE 19808
USA

Abstract

This application note is targeted for ultra-high productivity of total petroleum hydrocarbons (TPH) analysis in environmental laboratories. Agilent's Low Thermal Mass (LTM) technology is employed here to perform ultra-fast gas chromatographic (GC) separations. The LTM technology uses a column module combining a fused silica capillary column with heating and temperature-sensing components wound around it, which can be heated and cooled very efficiently. In this application note, the speed of analysis for the hydrocarbon group eluting between C_{10} and C_{44} can be dramatically increased to about 13 times faster than a conventional method. In addition, the ultra-fast cooling function of an LTM module can reduce the total GC cycle time to 5.1 minutes. The simultaneous dual-tower injection from Agilent is used to further double productivity. The final result for TPH analysis productivity is 5.1 minutes per two samples.



Agilent Technologies

Introduction

Total petroleum hydrocarbons (TPH) is a term used to describe a large family of several hundred chemical compounds that originally came from crude oil. Many environmental laboratories in the world are analyzing the total amount of TPH at a site to evaluate the water or soil contamination by TPH, such as oil, gasoline, diesel fuel, etc.

The Agilent Low Thermal Mass (LTM) system (except for an external power supply) is built into a replacement GC oven door, which is mounted as an add-on to an Agilent 7890A GC. A version is also available for the Agilent 6890 GC. The key component of LTM system is the LTM column module combining a fused silica capillary column with heating and temperature-sensing components wound around it. The LTM system can heat and cool the column very efficiently for significantly shorter analytical cycle times as compared to conventional air bath GC oven techniques involving much higher thermal mass.

The GC method translation software from Agilent is a calculator used to scale a method between different column dimensions with equal or increased speed. In this application note, a 40-minute separation with a 30-meter column is translated into a 20-minute separation with a 15-meter column at first, without LTM technology. Then the method is further translated for LTM use with a 5-meter column within 3.1 minutes.

As a base for the LTM system, the Agilent 7890A can provide dual complete analysis channels. With a configuration of dual injection towers, single sample tray, dual split/splitless inlets, and dual detectors, the simultaneous TPH analysis can be accomplished to double lab productivity, in addition to the speed gains realized with LTM.

Experimental

Standard Preparation

The custom alkanes mix (cus-908) from Ultra Scientific (North Kingstown, Rhode Island, U.S.) contains n-alkanes from n-decane (C₁₀) to n-tetratetracontane (C₄₄) in hexane at the concentration listed in Table 1. Dilutions in dichloromethane are made up at 1.0, 5.0, 10.0, 50.0, and 100.0 µg/mL concentrations.

Table 1. Custom Alkanes Mix

Component	Concentration, mg/mL	Component	Concentration, mg/mL
n-decane	0.2	n-tetracosane	0.1
n-dodecane	0.1	n-hexacosane	0.1
n-tetradecane	0.2	n-octacosane	0.1
n-hexadecane	0.1	n-triacontane	0.1
n-octadecane	0.1	n-dotriacontane	0.1
n-eicosane	0.1	n-hexatriacontane	0.1
n-docosane	0.1	n-tetracontane	0.1
n-tricosane	0.2	n-tetratetracontane	0.1

Sample Preparation

Soil samples are mixed with sodium sulfate to remove excess moisture and then sonicated with 60-mL aliquots of dichloromethane, three times. Water samples are placed in a 2-L separate funnel. A 100-mL aliquot of dichloromethane is added and the mixture is shaken automatically for about 2 minutes. The liquid-liquid extraction is repeated two more times. For both matrices, the extract is concentrated on a steam bath to either 5 mL for a soil sample or 1 mL for a water sample. The extracts are not routinely treated with silica gel, unless specified.

Instrumentation and Conditions

Agilent 7890A GC with LTM system, consisting of:

G3440A	7890A Series GC system
#112	Split/splitless inlet with EPC (2)
#211	Capillary FID with EPC (2)
	Autoinjector modules (2)
	Autosampler tray module
G6579A	LTM system bundle for 2-channel LTM operation, for use with standard size LTM column modules (100–2000LTM DB-5 5 M × 0.32 mm id, 1.0 µm standard 5-inch LTM column module)

ChemStation 32-bit version B.04.01

Table 2. Gas Chromatograph Conditions

	Original 1X Method	2X Method	LTM Method
GC			
Agilent Technologies 7890A			
Inlet	EPC split/splitless	EPC split/splitless	EPC split/splitless
Mode	Constant pressure	Constant pressure	Ramp pressure
Injection type	Split	Split	Split
Injection volume (µL)	1.0	1.0	1.0
Inlet temp (°C)	300	300	300
Pressure, nominal (psig)	30	14.319	13.1 (0.1 min), 11.27 psi/min to 30 (1.5 min)
Liner	Helix liner, open ended, deactivated (p/n 5188-5396)	Helix liner, open ended, deactivated (p/n 5188-5396)	Helix liner, open ended, deactivated (p/n 5188-5396)
Split ratio	2:1	2:1	2:1
Gas saver	20 mL/min after 2 min	20 mL/min after 2 min	20 mL/min after 2 min
Gas type	Helium	Helium	Helium
Sample overlap	2 min after end of GC run	2 min after end of GC run	2 min after end of GC run
Oven	GC Oven	GC Oven	LTM module (p/n G6579A) with GC oven 300 °C for 3.1 min
Initial oven temp (°C)	40	40	40
Initial oven hold (min)	1	0.5	0.1
Ramp rate (°C/min)	10	20	200
Final temp (°C)	320	320	340
Final hold (min)	11	6.5	1.5
Run time (min)	40	21	3.1
Cooldown time (min)	5.4	5.4	2
Cycle time (min)	45.4	25.4	5
Column			
Type	DB-5 (p/n 123-5032)	DB-5 (p/n 123-5012)	DB-5 (p/n*)
Length (m)	30	15	5
Diameter (mm)	0.32	0.32	0.32
Film thickness (µm)	0.25	0.25	1.0
FID			
Temperature (°C)	300	300	300
H ₂ flow (mL/min)	30	30	30
Air flow (mL/min)	400	400	400
Makeup flow (mL/min)	25	25	25
Sampling rate (Hz)	50	50	50

*100–2000LTM DB-5 5M x 0.32 mm id, 1.0 µm standard 5-inch LTM column module

Results and Discussion

Ultra-Fast Separation of n-alkanes Mixture with LTM System and Scale-Up Using the GC Method Translator

The application is started with the analysis of a standard mixture of n-alkanes, containing n-C₁₀, n-C₁₂, up to n-C₄₄. Figure 1 compares the chromatogram of the standard mixture using three different methods in the same time scale. With the LTM system, the GC run time can be more than 10 times faster than conventional methods. In terms of cooling down, the classical GC oven such as 7890 fast oven will take about 5.4 minutes from 320 to 40 °C. Relatively, the LTM system has a much lower thermal mass, which can perform ultra-fast cooling. In this case, the LTM system will take about 2 minutes from 340 to 40 °C, for dual parallel LTM modules. In addition, sample overlap of the 7890 sample tray can prepare the

sample after the end of the last GC run parallel with GC oven cooldown. The resulting cycle time for LTM is 5.1 minutes, which means about nine times faster than the conventional method.

Resolution is also a concern with fast analysis. Figure 2 is the expanded view of Figure 1 with the nominal time scale, which demonstrates that all the peaks of n-alkanes are baseline separated, even with the nine-times-faster LTM method (speed calculated by total cycle time). The result is calculated by total amount of TPH, not by the individual peak amount; peak-grouping of ChemStation is employed here. The calibration is checked by injecting the standard mixture in different concentration levels, ranging from 1 to 100 µg/mL. The calibration curve of the LTM method is displayed in Figure 3, with average n-alkanes response factor by peak-grouping.




Figure 1. Comparison of conventional method and LTM method.




Figure 2. Expanded view of Figure 1, with the nominal time scale.




Figure 3. Calibration curve of LTM method after peak-grouping.

Simultaneous Dual-Channel Analysis with Agilent Dual-Tower Injection

Agilent 7890A and 6890 GCs make dual-channel analysis possible, with the configuration of a single sample tray and dual injection towers, inlets, columns, and detectors. Typically, a dual-channel configuration is used to identify target compounds in one GC run, using different retention time in columns of different polarity. The purpose here is to double lab productivity using dual identical channels at a much lower cost compared to two single-channel instruments. ChemStation can provide different choices for final data file generation. Figure 4 shows one option of detection signal setting for separating the dual-tower injection into two individual data files. Figure 5 is the chromatogram of two real samples with simultaneous dual-tower injection.




Figure 4. Signal setting for dual-tower injection to generate two individual data files.




Figure 5. Chromatogram of two real samples with simultaneous dual-tower injection.

Quantitative Analysis of TPH with Peak-Grouping and Peak-Summing

Peak-grouping is used to average each n-alkane response factor. With this average response factor, the nominal calibration curve can be used for quantitation of each peak, including unidentified peaks eluting between n-C₁₀ and n-C₄₄. In this case, the compound peak-grouping details and unidentified peak calibration settings can be seen in Figure 6.

Another requirement for TPH analysis is quantitation across the whole eluting time range between n-C₁₀ and n-C₄₄ to calculate all petroleum hydrocarbons not only n-alkanes. Baseline-holding and peak-summing in the ChemStation integration events table are necessary to meet this requirement; the related setting can be seen in Figure 7. For example, the integration result of real sample is shown in Figure 8.




Figure 6. Peak-grouping (left) and unidentified peak calibration setting (right) in ChemStation.

Time	Integration Events	Value
Initial	Slope Sensitivity	10
Initial	Peak Width	0.04
Initial	Area Reject	1
Initial	Height Reject	1
Initial	Shoulders	OFF
0.000	Integration	OFF
4.560	Area Sum	ON
4.560	Baseline Hold	ON
4.560	Integration	ON
39.100	Integration	OFF
39.100	Area Sum	OFF

Figure 7. Baseline-holding and peak-summing setting in the ChemStation integration events table.




Figure 8. Integration result of real sample after baseline-holding and peak-summing.

Real Sample Analysis

After calibration by peak-grouping and integration through peak-summing, the quantitation result can be reported as the total amount of TPH in a real sample. As a comparison of quantitation results with three different acquired methods, Table 3 demonstrates that the real sample analysis result by the ultra-fast LTM method is comparable with conventional methods.

Table 3. Comparison of Quantitation Result with Three Different Acquired Methods

	TPH Concentration ($\mu\text{g/mL}$)
Original method (30 m)	1097
2X method (15 m)	920
LTM method (5 m)	909

Conclusions

The low thermal mass of the Agilent LTM system can perform very efficient column heating and cooling, and is used here to develop an ultra-fast TPH analysis to meet the requirement for high lab productivity. Dual-tower injection is also used to further double the productivity with much less cost. The final solution with the LTM system and dual-tower injection can perform TPH analyses at a rate of 5.1 minutes per two samples. The total productivity increase is 18x compared to a conventional analysis on a single-channel system.

References

1. "Agilent Low Thermal Mass (LTM) System for Gas Chromatography," Agilent Technologies publication 5989-8711EN, June 2008
2. Wei Luan, Chuanhong Tu, and Michael Woodman, "Evaluation of Total Petroleum Hydrocarbon in Soil Using LC with Fraction Collector and GC/MS," Agilent Technologies publication 5989-6012EN, April 2007

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Published in the USA
November 18, 2008
5990-3201EN



Agilent Technologies



Improving GC-MS Method Robustness and Cycle Times Using Capillary Flow Technology and Backflushing

Application Note

Environmental

Author

Chris Sandy
Agilent Technologies, Inc.
UK and Ireland Sales Headquarters
710 Wharfedale Road
Winnersh Triangle
Wokingham, Berkshire, RG41 5TP
UK

Abstract

This application note demonstrates the customer benefits from using Capillary Flow Technology to provide backflushing of high-boiling materials in GC and GC/MS analyses. Benefits include reduction in chromatographic cycle times, a reduction in system column maintenance, and extended GC column life. If a GC/MS system is utilized, the author has experienced an increase in the number of samples analyzed before ion source maintenance is required.



Agilent Technologies

Introduction

A critical component of the GC/MS analysis of any sample that contains large amounts of matrix material is the sample preparation. Environmental samples such as soils and sediments require not only extraction, but may also require multiple cleanup steps in order to present as clean an extract as possible for injection in to the GC/MS system.

Any remaining matrix in the sample extract can have deleterious effects on the GC sample inlet, column, and the ion source of the mass spectrometer. Traditionally, these high-boiling matrix materials are removed from the capillary column by a long bake-out period after the analytes of interest have eluted. This long bake-out process causes thermal stress to the column and also drives the matrix material towards the ion source, where it will eventually affect system performance. Moreover, should any material remain in the column after the bake-out process, it can cause loss of chromatographic peak shape and retention time shifting of target analytes. This shifting of retention time is particularly troublesome if the mass spectrometer is being used in the selected ion monitoring (SIM) mode (as with a single quadrupole GC/MS) or in the multiple reaction monitoring (MRM) mode (as with a triple quadrupole GC/MS).

This paper demonstrates how high-boiling matrix materials can be removed from the column quickly and effectively – between sample injections – by using capillary flow technology and capillary column backflushing.

Figure 1 shows a schematic diagram of the GC/MS system used. The 15-m analytical column was connected to the EPC split/splitless inlet and a capillary flow technology two-way splitter (p/n G3180B or G1540 option number 889).




Figure 1. Schematic diagram of GC-MS system.

A short length of uncoated, deactivated fused silica (UDFS) capillary column is used as a restrictor between the splitter and the MS. Note carefully how the connections are made at the splitter. The X represents a port on the splitter plate that is closed off with a SilTite metal ferrule and stainless steel wire plug.

Backflushing in this example was accomplished during a post-run period by a combination of increasing oven temperature, reducing the inlet pressure of the analytical column, and increasing the pressure applied to the splitter plate.

Experimental

The full analytical conditions, both with and without post-run backflush set-points, are shown in Table 1.

Table 1. GC/MS Analysis Conditions

Gas chromatograph	Agilent 7890A
Columns	(1) 15.0 m × 0.25 µm id × 0.25 µm HP-5MS Ultra Inert (19091S-431SI) Inlet Front split/splitless, outlet 2-way Capillary Flow Device (2) 0.80 m × 0.15 mm id uncoated deactivated fused silica inlet two-way capillary flow device at 4.0 psig outlet vacuum
Carrier gas	Helium
Carrier gas mode	Constant pressure
Flow rate	17.18 psi
Injection port	EPC split/splitless
Autosampler	Agilent 7683A
Injection mode	Splitless, purge delay 0.5 min Purge flow 50.0 mL/min at 0.5 min
Injection volume	2.0 µL
Injection port liner	4 mm single-taper splitless liner (5181-3316)
Oven program °C (min)	70 (1) – 50 °C /min – 150 (0) 6 – 200 (0) – 16 – 280 (0) °C
Mass spectrometer	Agilent 5975C MSD
MS interface	280 °C
MS source	230 °C
MS quad 1	150 °C
Backflush conditions (1)	Post-run, 10 min, AUX 60 psig, oven 320 °C
Backflush conditions (2)	Post-run, 6 min, AUX 80 psig, oven 320 °C
Detection mode	El full scan; mass range 40:550 amu
El tune	Gain factor = 1

Results and Discussions

Experiment 1: No Backflushing Employed

In the first experiment, an extracted sediment sample was analyzed in full-scan mode to show the extent of the matrix problem. No backflushing was employed.

Before any sediment was injected, a system blank (no injection) followed by a 2- μ L solvent blank was made. In the absence of the actual hexane solvent used to prepare the

sediment extract, hexane that was not particularly clean was used. The TICs are shown overlaid in Figure 2, system blank in black, and solvent blank in gray. These chromatograms show that the system is free from high-boiling matrix material.

Following the blanks, a single injection of the sediment extract was made without backflushing; the TIC is shown in Figure 3. Note the very high abundance of the matrix and that when the analysis finishes, there is still a significant amount of matrix material to elute from the column.




Figure 2. System blank and solvent blank TICs.




Figure 3. Sediment extract TIC.

The sediment extract injection was followed by a series of hexane blank injections. The first seven hexane blank TICs are shown overlaid in Figure 4 with the solvent blank before the sediment was injected into the GC/MS system.

The original solvent blank TIC is shown in black, the eighth solvent blank TIC after the sediment injection is shown in gray.

Figure 5 shows that after the eighth solvent blank injection, the system has almost recovered to the level of background before the sediment sample was injected.




Figure 4. Successive solvent blank injections.




Figure 5. Eighth solvent blank and original solvent blank TICs

Experiment 2: Backflushing Employed

Backflushing was enabled during a post-run period by increasing column oven temperature, reducing the inlet pressure of the analytical column, and increasing the gas pressure applied to the splitter plate.

The 7890A instrument control software includes simple and easy-to-use screens to help set up post-run backflushing conditions. Figure 6 shows the configuration of columns and connections with the GC oven.

Figure 7 shows the actual backflushing conditions, namely the post-run oven temperature (320 °C), post-run inlet pres-

sure for the analytical column (1 psig), post-run pressure applied to the splitter device (60 psig), and post-run time (10 minutes). The figure also shows the number of column-volumes of carrier gas that will backflush the analytical column.

Note that using the backflushing conditions shown in Figure 7 (320 °C, column pressure 1 psig, and splitter pressure 60 psig for 10 minutes), that 59.4 column volumes of carrier gas was used to backflush the column during the post-run period. This backflush time may have been more than necessary. Alternate conditions were also investigated and are presented later.




Figure 6. Post-run backflushing screen number 1.

Summary of Backflush Calculations

Oven Temperature
320 °C

Detector	Maximum Flow	Allowable Pressure	Flow at Chosen Pressure
Vacuum	75	130.98	19.719

Backflush Pressure
60 psi

Inlet Pressure during Backflush
1 psi

Void Volumes
59.463

Backflush Flow to Inlet
7.6986 mL/min

Backflush Time
10 min

Void Time
0.16817 min

OK Cancel Help

Figure 7. Post-run backflushing screen number 2.

Before applying the backflush conditions to the method the user is presented with a convenient summary of the backflush conditions. See Figure 8.



Figure 8. Post-run backflushing screen number 3.

Another injection of the sediment including backflush was made followed by a blank injection of solvent. Figure 9 shows the overlaid TIC of the original solvent blank (black) overlaid on the solvent blank after the sediment injection (gray).

No evidence of any matrix material is indicated, demonstrating that all the high-boiling matrix material had been effectively removed by backflushing.




Figure 9. Original solvent blank TIC and solvent blank after sediment injection with post-run backflush (1).

Experiment 3: Backflushing Employed

In order to reduce cycle time for the method, the backflush conditions were modified by increasing the backflush pressure to 80 psig and holding for 6 minutes.

Note that using the backflushing conditions shown in Figure 10 (320 °C, column pressure 1 psig, and splitter pressure 80 psig for 6 minutes), that 46.6 column volumes of carrier gas was used to backflush the column during the post-run period.

Another injection of the sediment was made, followed by a blank injection of solvent. Figure 11 shows the overlaid TIC of the original solvent blank (black) overlaid on the solvent blank after the sediment injection (gray).

No evidence of any matrix material is indicated, demonstrating that all the high-boiling matrix material has been removed by backflushing with the more aggressive conditions as well. These conditions reduced the cycle time for this method 4 minutes compared to the backflushing conditions used in Experiment 1.




Figure 10. Post-run backflushing screen conditions number 2.




Figure 11. Original solvent blank TIC and solvent blank after sediment injection with post-run backflush (2).

Conclusions

Post-run backflushing was shown to effectively eliminate high-boiling sample matrix in a short amount of time. The major benefits of GC capillary column post-run backflushing include:

- Agilent's capillary flow technology and GC software enable easy and robust setup of GC backflushing.
- Compared to long bake-out periods with flow in the forward direction, a short period of backflushing can remove high-boiling matrix materials more effectively without contaminating the MS ion source.
- Chromatographic cycle time is reduced, columns stay clean, and the integrity of target analyte peak shapes and retention times are maintained.
- For this particular sediment extract the GC column was free of sample matrix after a backflush period of 6 minutes.
- Less system maintenance (ion source cleaning) is required.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Published in the USA
January 30, 2009
5990-3367EN



Agilent Technologies

Evaluation of Total Petroleum Hydrocarbon in Soil Using LC with Fraction Collector and GC/MS



Application

Environmental

Authors

Wei Luan and Chuanhong Tu
Agilent Technologies (Shanghai) Co., Ltd.
412 Ying Lun Road
Waigaoqiao Free Trade Zone
Shanghai 200131
P. R. China

Michael Woodman
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington DE 19808
USA

Abstract

Normal-phase liquid chromatography (NPLC) and capillary gas chromatography with mass spectrometry are employed to evaluate the total petroleum hydrocarbon (TPH) in the soil contaminated by crude oil. In this paper, paraffins and mono-aromatic and multi-aromatic compounds present in the sample were first separated by NPLC into different classes of compounds according to their individual polarities, and fractions were collected for subsequent analysis by GC/MS, separated by boiling point, and identified by their unique mass spectra.

Introduction

Pollution due to oil spills happens frequently all over the world. Positive identification of the source is a critical part of establishing liability for cleanup costs and environmental damages. Because the spill is subject to time-based alteration by weathering (dissolution or evaporation), chemical degradation (effects of sunlight, heat, air, and soil chemistry), and biological alteration (impact of microorganisms) it has become more and more important to map these effects. Scientists have developed diverse technologies to perform the comprehensive evaluation analysis of TPH in environmental matrices. DIN 38 409 H18 [1] is the official method using infrared spectrometry. Robert [2] introduced a comprehensive two-dimensional gas chromatography to track the weathering of an oil spill. A portable GC/MS method was presented to determine the concentration of TPH from unresolved signals in short test runs in the field.

Sjaak [3] introduced group-type characterization of mineral oil samples by two-dimensional comprehensively coupled LC x GC-ToF MS. The interface between LC and GC/MS consisted of a 100- μ L syringe, with two side entrances/exits in the upper part of the barrel, installed in an injection robot. A stop-flow mode of LC was adopted during the GC/MS analysis.

In this paper, we employed a fraction collector to replace the complex interface between HPLC and GC/MS and applied a combination of NPLC and GC/MS to evaluate the TPH in the soil contaminated by crude oil.



Agilent Technologies

Experimental

Instrumentation and Conditions

Agilent 1200 Series LC, consisting of:

G1379B	Micro vacuum degasser
G1312B	Binary pump SL
G1367C	High-performance autosampler SL
G1316B	Thermostatted column compartment SL with 6- or 10-port 2-position switching valve
G1315C	UV/VIS diode array detector SL
G1364C	Fraction collector (analytical scale)
ChemStation 32-bit version B.02.01-SR1	

Agilent 6890GC with 5975B MSD, consisting of:

G1540N	6890N network GC system with options: 201 MSD interface
G3243A	5975B inert MSD/DS perf turbo EI bundle
G3397A	Ion gauge/controller for use with 5975 MSD
G2913A	7683B autoinjector module
G2614A	7683 autosampler tray module
MSD Chemstation version D.03.00 with NIST 05 MS Library version 2.0d	

The LC and GC/MS operating conditions are listed in Table 1.

Sample Preparation

The crude oil sample was from the Daqing, China, oil field and contributed by Sinopec Shanghai Gao-qiao Petrochemical Corporation.

The sample was prepared by mixing a 1 g oil sample with a blank soil sample and depositing the mixture in a fume hood for 2 days. Next, 50 mL of hexanes was added and the sample was extracted in an ultrasonic water bath for 1 hour. The extract was filtered, and 10 mL of filtrate was pipetted and then evaporated under a nitrogen stream to less than 1 mL. The extract was then made up with hexanes to 1 mL, and the solution was injected into NPLC for analysis.

Operation of Column Switching Valve and Fraction Collector of NPLC

The crude oil sample was so complex that a column switching valve was employed to back-flush the analysis column in the NPLC system. To approximately evaluate the retention time of every group of compounds, a system calibration standard was used, which was composed of cyclohexane, o-xylene, dibenzothiophene and 9-methylanthracene, as generally outlined in ASTM Methods D6379 and D6591. The separation of the system calibration standard is shown in Figure 1. To minimize the total analysis time, the LC eluate of the first 3 min was sent to waste. Afterwards, fractions were collected every 0.5 min by the fraction collector. After collecting the fractions that contained the compounds of interest, the column was switched to backflushing mode for cleaning and the LC run was closed after the baseline stabilized.

Results and Discussion

The soil sample extract was separated into different groups by normal phase liquid chromatography according to their polarities, as displayed in Figure 2. A total of 23 fractions were collected, which were injected into the GC/MS system for subsequent separation according to their boiling point and identification according to their characteristic mass fragments. A total ion chromatogram (TIC) of typical paraffins and mono-aromatic, bi-aromatic, and tri-aromatic compounds is depicted, respectively, in Figure 3. Through the identification by mass spectra, the first group with a retention time range of 3.7 to 4.7 min in LC chromatography contained paraffins; the second group, with a retention time range of 4.7 to 6.2 min, contained mono-aromatic compounds; the third group, with a retention time range of 6.2 to 11.2 min, contained bi-aromatic compounds; and the fourth group, with a retention time range of 11.2 to 13.7 min, contained tri-aromatic compounds. No aromatic compounds eluted at the retention time range from 13.7 min to the end.

Table 1. LC and GC/MS Operating Conditions

LC		Agilent Technologies 1200SL		Inlet	EPC
Mobile phase		Hexanes		Injection type	Splitless
Flow rate		0.8 mL/min		Inlet temperature	250 °C
Wavelength		210 nm		Pressure	7.61 psi
Injection volume		100 µL		Purge flow	50.0 mL/min
Mode		Isocratic		Purge time	0.75 min
Column		Agilent ZORBAX NH ₂		Total flow	54.0 mL/min
		4.6 mm x 250 mm, 5 µm		Gas saver	On
Analysis time		30 min		Saver flow	20.0 mL/min
Column temperature		35 °C		Saver time	2.00 min
Column switching valve		Backflushing off		Gas type	Helium
Column switching timetable		Time	Column	Oven	
		15.00 min	Backflushing on	Initial temperature	50 °C
		30.00 min	Backflushing off	Initial time	1.00 min
Fraction trigger mode		Use timetable		Ramp rate	30.00 °C/min
				Final temperature	300 °C
Fraction collector timetable		Time	Trigger mode	Final hold	2.00 min
		3.70 min	Time-based	Total run time	11.33 min
		15.00 min	Off	Equilibration time	0.5 min
GC		Agilent Technologies 6890N		Column	
Autoinjector		7683 autoinjector and tray		Type	HP 5-ms
Sample washes		3		Length	30 m
Sample pumps		6		Diameter	0.25 mm
Injection volume		1 µL		Film thickness	0.25 µm
Syringe size		5 µL		Mode	Constant flow
Preinjection solvent A		0		Initial flow	1.0 mL/min
Preinjection solvent B		3		MSD	
Post-injection solvent A		0		Agilent Technologies 5975B inert	
Post-injection solvent B		3		Solvent delay	4 min
Viscosity delay		0 s		Tune file	Atune.U
Plunger speed		Fast		Mode	Scan
Preinjection dwell		0 min		Solvent delay	3.00 min
Post-injection dwell		0 min		EM voltage	Atune voltage
Sampling depth		Disable		Low mass	45.0 amu
				High mass	450.0 amu
				Threshold	150
				Sampling	2
				Scans	3.54
				Quad temperature	150 °C
				Source temperature	230 °C
				Transfer line temperature	280 °C




Figure 1. Chromatogram of standard solution.




Figure 2. Chromatogram of soil sample extract and factions collected in different vials.




Figure 3. Total ion chromatogram of typical fractions including paraffins and mono-, bi-, and tri-aromatic compounds.




Figure 3. Total ion chromatogram of typical fractions including paraffins and mono-, bi-, and tri-aromatic compounds. (continued)

	Vial Position	Time Slices
Paraffin	1-P1-A-01	3.7 to 4.2 min
Mono-aromatic compounds	1-P1-A-04	5.2 to 5.7 min
Bi-aromatic compounds	1-P1-B-04	9.7 to 10.2 min
Tri-aromatic compounds	1-P1-B-08	11.7 to 12.2 min

Conclusions

The separations by NPLC and GC are based on polarity and boiling point, respectively. Mass spectra could provide the information on the molecular structure; therefore, the combination of NPLC and GC/MS could be used to evaluate the complex matrix. In this work, an LC with a fraction collector performed the separation of classes of paraffins and mono-, bi-, and tri-aromatic compounds and collected time-based fractions into individual sample vials. The fractions were injected into the GC/MS for identification. A soil sample contaminated by crude oil was analyzed by this method and the results showed the detailed component information of every typical class, based on fractionation by polarity, to evaluate the total petroleum hydrocarbon in soil.

References

1. Deutsche Einheitsverfahren zur Wasser-, Abwasser- und Schlammuntersuchung, "Summarische Wirkungs- und Stoffkenngrößen, Bestimmung von Kohlenwasserstoffen (H18)," Deutsche Industrie Normen DIN, Beuth Verlag, Berlin 1981.
2. Robert K. Nelson, Tracking the Weathering of an Oil Spill with Comprehensive Two-Dimensional Gas Chromatography, *Environmental Forensics*, 7:33-44, 2006.
3. Sjaak de Koning, Group-type characterisation of mineral oil samples by two-dimensional comprehensive normal-phase liquid chromatography-gas chromatography with time-of-flight mass spectrometric detection, *Journal of Chromatography A*, 1058:217-221, 2004.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

The information contained in this publication is intended for research use only and is not to be followed as a diagnostic procedure.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
April 9, 2007
5989-6012EN



Agilent Technologies



Techniques for Optimizing the Analysis of Volatile Organic Compounds in Water Using Purge-and-Trap/GC/MS

Application

Environmental

Author

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA
(E-mail: phil_wylie@agilent.com)

Abstract

The analysis of volatile organic compounds in water is normally accomplished by purge-and-trap/gas chromatography/mass spectrometry. U.S. EPA Method 8260B with purge and trap sample introduction is widely used for the analysis of aqueous samples other than drinking water. This application note discusses problems that can arise and some easy solutions for them. These techniques have resulted in robust calibrations that meet Method 8260B calibration requirements over the range of 1–200 µg/L.

Introduction

U.S. EPA Method 8260B [1] is a general purpose method for the analysis of volatile organic compounds (VOCs) in matrices such as ground and surface water, sludges, soils and sediments, filter cakes, spent carbons, and spent catalysts. This method is only used for the analyses of target VOCs by gas chromatography with mass spectral

detection (GC/MS). It refers analysts to other U.S. EPA sample introduction methods that are appropriate for the matrix to be analyzed. This paper focuses on the analysis of VOCs in water using purge and trap (P&T) sample introduction according to U.S. EPA Method 5030C [2] coupled to GC/MS for separation and analysis (P&T/GC/MS). For simplicity, the combination of Methods 5030C with 8260B is referred to as just Method 8260B.

This P&T/GC/MS procedure is widely used in environmental laboratories for the analysis of VOCs in surface, ground, and wastewater samples. A similar method for the analysis of drinking water is described in EPA Method 524.2 [3]. Though well established, P&T/GC/MS methods can be a challenge to run successfully. There are numerous P&T, GC, and MS variables to optimize in order to obtain good recoveries for the target VOCs without undo disturbance from water and methanol that are inevitably transferred to the GC during trap desorption.

This application note describes techniques for optimizing Method 8260B using the Agilent 6890N GC and new 5973 inert mass selective detector (MSD) coupled to the new Teledyne Tekmar Velocity XPT P&T system. Included, in the paper, are suggestions for MSD tuning, sample preparation, instrument setpoints, and maintenance techniques that lead to a robust method for the analysis of VOCs in water. The discussion is applicable to most other P&T/GC/MS methods.



Agilent Technologies

Experimental

Chemical Standards, Reagents, and Vials

High purity B&J brand methanol was obtained from Honeywell Burdick & Jackson Co. (Muskegon, MI). Standard mixtures used for the preparation of calibration samples, spiking solutions, tune evaluation, and stability test samples were purchased from AccuStandard (New Haven, CT). These include the following: Part no. M-502-10X-Pak containing 60 VOC target analytes (54 liquids and 6 gases) at 2000 µg/mL each in methanol; Part no. M-8260A/B-IS/SS-10X-PAK containing p-bromofluorobenzene (BFB), chlorobenzene-d₅, dibromofluoromethane, 1,4-dichlorobenzene-d₄ (DCB-d₄), 1,2-dichloroethane-d₄, fluorobenzene (FBz), and toluene-d₈ at 2000 µg/mL each in methanol; and part no. M-524-FS-PAK containing BFB,

1,2-dichlorobenzene-d₄, and fluorobenzene (FBz) at 2000 µg/mL each in methanol.

VOC-free water was used for the preparation of standards and test samples. TraceClean 40-mL (nominal volume, actual volume is 43 mL) VOA vials (part no. 15900-022) were purchased from VWR Scientific (West Chester, PA).

Preparation of Calibration and Spiking Solutions

Secondary spiking solutions were prepared in methanol for each calibration level so that each 43-mL water sample could be spiked with 10 µL of the calibration solution (containing 60 VOCs) and 10 µL of the internal standard/surrogate mixture. Table 1 provides details on how the eight calibration standards were prepared.

Table 1. Procedure for Preparing Calibration Samples

A	B	C	D	E
Calibration level (µg/L)	Volume of 2000 µg/mL VOC Standard (µL)	Diluted to this volume in methanol (mL)	Results in this secondary standard concentration (µg/L)	Amount to spike into 43-mL vial (µL)
1	53.75	25.00	4.3	10.00
2	43.00	10.00	8.6	10.00
5	53.75	5.00	21.5	10.00
20	43.00	1.00	86	10.00
50	43.00	0.40	215	10.00
100	43.00	0.20	430	10.00
200	43.00	0.10	860	10.00
300	*	*	2000*	6.45**

Column A. Concentration of each analyte in the final aqueous calibration solution.

Column B. Volume of the 2000 µg/mL 60-component VOC standard solution which was diluted to the volume shown in column C.

Column C. Final volume of VOC solution after dilution in methanol.

Column D. Concentration of the calibration spiking solution prepared by diluting the amount of 2000 µg/mL standard in column B to the volume shown in column C.

Column E. Amount of the secondary standard solution (column D) added to 43 mL of water to prepare the calibration standard at the level shown in column A.

*The undiluted VOC standard (2000 µg/mL) was used for spiking.

**The 300 µg/L aqueous calibration standard was prepared by adding 6.45 µL of the 2000 µg/mL AccuStandard VOC solution and 3.55 µL of methanol to 43 mL of water in a VOA vial.

As discussed below, containers for storing the secondary standards (column C, Table 1) were chosen to minimize the headspace. Larger volumes were transferred to 2-mL screw top vials, while smaller volumes were transferred to crimp cap microvials of the appropriate size.

A solution of the internal standards (ISTDs) and surrogates was prepared at 215 ppm in methanol by diluting 43 μL of the 2000- $\mu\text{g}/\text{mL}$ AccuStandard solution to a volume of 400 μL . Each 43-mL water sample was spiked with 10 μL of this solution so that all samples and standards contained 50 $\mu\text{g}/\text{L}$ of each compound.

Preparation of Solutions for Repeatability Studies

Two kinds of spiked water samples were prepared for use in repeatability studies.

- System blanks consisted of clean water spiked with fluorobenzene, BFB, and 1,2-dichlorobenzene- d_4 at 10 $\mu\text{g}/\text{L}$ each.
- VOC spikes consisted of clean water with fluorobenzene, BFB, and 1,2-dichlorobenzene- d_4 at 10 $\mu\text{g}/\text{L}$ and the 60 VOC target compounds at 20 $\mu\text{g}/\text{L}$ each.

Replicate samples were prepared as follows.

- Secondary dilution standards containing fluorobenzene, BFB, and 1,2-dichlorobenzene- d_4 at 50.0 $\mu\text{g}/\text{mL}$ were prepared in 2-mL autosampler vials by diluting 25 μL of the 2000- $\mu\text{g}/\text{mL}$ AccuStandard solution with 975 μL of methanol.
- Secondary dilution standards of the 60-component VOC solution were prepared at 100 $\mu\text{g}/\text{mL}$ in 2-mL autosampler vials by diluting 50 μL of the 2000 $\mu\text{g}/\text{mL}$ AccuStandard solution with 950 μL of methanol.

System blanks were prepared by adding 100 μL of the 50.0 $\mu\text{g}/\text{mL}$ three component solution and 100- μL methanol to 500 mL of water in a 1.0-L screw-cap bottle. After inverting to mix thoroughly, this bottle was attached to the apparatus shown in Figure 1 and 11 VOA vials were filled by transferring the spiked water solution under nitrogen pressure.




Figure 1. Apparatus used to fill multiple VOA vials with the same spiked water solution.

- A) 1-L liquid chromatography solvent bottle
 B) Swagelok Tee with nothing connected to one fitting
 C) Finger used to cap fitting in order to pressurize the reservoir bottle
 D) VOA vial
 E) 1/8-inch PTFE tubing

VOA spiked samples were prepared by adding 100 μL of the 50.0- $\mu\text{g}/\text{mL}$ three component solution and 100 μL of the 100- $\mu\text{g}/\text{mL}$ 60-component VOC standard to 500 mL of water in a 1.0-L screw cap bottle. After inverting to mix thoroughly, this bottle was attached to the apparatus shown in Figure 1 and 11 VOA vials were filled by transferring the spiked water solution under nitrogen pressure.

Instrumentation and Analytical Conditions

The P&T instrumentation and setpoints are listed in Table 2. The following P&T options were not used: DryFlow trap, automatic ISTD addition, sample heating, dry purging, and sample cryofocusing. The method shown in Table 2 was derived using the wizard that is provided in the TekLink 2.2 P&T control software.

Table 2. Purge and Trap Instrumentation and Setpoints

P&T Instrument	Teledyne Tekmar Velocity XPT
Automatic sampler	Teledyne Tekmar Aquatek 70
Software control	Teledyne Tekmar VOC Teklink version 2.2
Trap	Vocarb 3000
P&T-GC interface	P&T transfer line spliced into the GC split/splitless inlet carrier gas line and GC carrier gas plumbed to the Velocity XPT
Sample size	5 mL
Valve oven temperature	150 °C
Transfer line temperature	150 °C
Sample mount temp	90 °C
Purge ready temp	45 °C
DryFlow standby temperature	175 °C
Standby flow	10 mL/min
Pressurize time	0.25 min
Fill I.S. time	0.00 (ISTDs added by hand)
Sample transfer time	0.25 min
Pre-purge time	0.00 min
Pre-purge flow	40 mL/min
Sample heater	Off (Samples not heated)
Sample preheat time	1.00 min
Preheat temperature	40 °C
Purge time	11.00 min
Purge temperature	0 °C (That is, less than the purge ready temp of 45 °C)
Purge flow	40 mL/min
Purge rinse time	0.25 min
Purge line time	0.25 min
Dry purge time	0.00 min (Dry purge not used)
Dry purge temp	40 °C
Dry purge flow	200 mL/min
GC start	Start of desorb
Desorb preheat temperature	245 °C
Desorb drain	On
Desorb time	1.00 min
Desorb temperature	250 °C
Desorb flow	200 mL/min
Bake rinse	On
Number of bake rinses	3
Bake drain time	0.50 min
Bake drain flow	400 mL/min
Bake time	3.00 min
Bake temperature	270 °C
Dry flow bake temperature	300 °C
Bake flow	400 mL/min
Focus temperature	Not used
Inject time	1.00 min
Inject temperature	180 °C
Standby temperature	100 °C

Table 3. GC/MS Instrumentation and Setpoints

Gas Chromatograph	Agilent 6890N
Inlet	Split/Splitless
Inlet liner	Single taper, deactivated (Agilent part no. 5181-3316)
Inlet temperature	250 °C
Split ratio	50:1
Column	20 m × 0.18 mm × 1.0 µm DB-VRX (Agilent part no. 121-1524)
Carrier gas	Helium at 1.0 mL/min constant flow
Oven temperature program	40 °C (3 min), 10 °C/min to 100 °C (0 min), 25 °C/min to 225 °C (3 min)
Mass Spectrometer	Agilent 5973 Inert MSD
Transfer line temperature	260 °C
Quad temperature	150 °C
Source temperature	230 °C
EM voltage	2035 volts
Scan range	35–260 <i>m/z</i>
Threshold	0
Samples	3
Solvent delay	0 min
Software	MSD Productivity ChemStation Software (Part no. G1701DA version D.01.00)

Results and Discussion

Section 1.3 of Method 8260B can be used to quantify most VOCs that have boiling points below 200 °C. It lists 123 compounds that can be determined by the method using various sample prep and sample introduction methods. Of these, seven are ISTDs or surrogates, nine are not recommended for P&T sample introduction, and three must be purged at 80 °C for efficient recovery. The remaining analytes vary considerably in their water solubility and volatility making this a challenging method to optimize. The intent of this application note is to share several techniques that one can use to optimize Method 8260B or any other P&T/GC/MSD method employed for water analysis.

For this study, the 60 VOCs listed in EPA Method 502.2 were analyzed along with three ISTDs and four surrogates (Table 4).

Table 4. Compound List with Average Response Factors (RF) and the RF %RSDs for Two Calibration Ranges: 1–300 and 1–200 µg/L

Type*	Compound	Retention time (min)	Minimum average response factor**	Maximum %RSD of calibration response factors***	Average RF 1–300 µg/L	RF %RSD 1–300 µg/L	Average RF 1–200 µg/L	RF %RSD 1–200 µg/L
T	Dichlorodifluoromethane	1.25	0.1	15	0.283	8.21	0.289	5.44
T,SPCC	Chloromethane	1.34		15	0.324	9.62	0.328	9.38
T,CCC	Vinyl chloride	1.42		30	0.220	2.47	0.220	2.66
T	Bromomethane	1.60		15	0.099	14.11	0.096	12.30
T	Ethyl chloride	1.67		15	0.152	5.57	0.154	4.27
T	Trichloromonofluoromethane	1.97	0.1	15	0.372	11.38	0.386	3.49
T,CCC	1,1-Dichloroethene	2.29		30	0.330	5.31	0.336	1.45
T	Methylene chloride	2.40		15	0.299	5.02	0.301	4.95
T	<i>trans</i> -1,2-Dichloro-ethene (E)	2.92		15	0.323	2.54	0.325	1.36
T,SPCC	1,1-Dichloroethane	3.14		15	0.444	4.93	0.446	5.22
T	<i>cis</i> -1,2-Dichloroethene (Z)	3.68		15	0.360	1.28	0.361	1.17
T	Bromochloromethane,	3.83		15	0.234	1.82	0.234	1.84
T,CCC	Chloroform	3.89		30	0.442	0.92	0.443	0.60
T	2,2-Dichloropropane	3.96		15	0.202	9.87	0.209	4.19
Sur	Dibromofluoromethane	4.01		15	0.248	0.83	0.248	0.89
Sur	1,2-Dichloroethane-d ₄	4.47	0.3	15	0.298	1.76	0.299	1.79
T	1,2-Dichloroethane	4.55		15	0.359	1.57	0.359	1.66
T	1,1,1-Trichloroethane	4.64		15	0.388	7.99	0.398	1.43
T	1,1-Dichloropropene	4.86		15	0.336	12.44	0.351	3.16
T	Carbon tetrachloride	5.01		15	0.309	13.88	0.322	7.66
T	Benzene	5.08		15	1.063	7.10	1.077	6.52
ISTD	Fluorobenzene	5.34		15		1.34		1.41
T	Dibromomethane	5.68		15	0.198	1.86	0.198	2.01
T,CCC	1,2-Dichloropropane	5.75		30	0.266	1.58	0.268	0.77
T	Trichloroethylene	5.81		15	0.288	6.79	0.295	2.14
T	Bromodichloromethane	5.85	0.1	15	0.334	5.47	0.331	5.60
T	1,3-Dichloropropene (Z)	6.64		15	0.383	5.49	0.381	5.74
T	1,3-Dichloropropene (E)	7.18		15	0.322	8.76	0.318	8.93
T	1,1,2-Trichloroethane	7.32		15	0.236	1.57	0.237	1.67
Sur	Toluene-d ₈	7.47		15	0.945	0.50	0.945	0.51
T,CCC	Toluene	7.55		30	1.098	7.47	1.126	2.07
T	1,3-Dichloropropane	7.62		15	0.428	1.28	0.428	1.20
T	Dibromochloromethane	7.86		15	0.254	12.10	0.249	11.88
T	1,2-Dibromoethane	8.15		15	0.244	1.88	0.244	2.03
T	Tetrachloroethylene	8.40		15	0.307	18.72	0.327	5.07
T	1,1,1,2-Tetrachloroethane	9.15	0.3	15	0.254	8.79	0.254	9.49
ISTD	Chlorobenzene-d ₅	9.19		15		0.98		0.81
T,SPCC	Chlorobenzene	9.22		15	0.981	5.00	0.997	2.14
T,CCC	Ethylbenzene	9.51		30	1.559	11.66	1.623	1.90
T,SPCC	Bromoform	9.72		15	0.246	14.57	0.242	15.08
T	m- & p-Xylene	9.73		15	2.510	11.97	2.614	2.75
T	Styrene	10.03		15	1.008	5.68	1.022	4.25
T,SPCC	1,1,2,2-Tetrachloroethane	10.08		15	0.395	3.41	0.394	3.46
T	o-Xylene	10.10		15	1.289	9.27	1.330	1.89
T	1,2,3-Trichloropropane	10.21		15	0.347	2.90	0.346	2.94
Sur	BFB	10.44	0.3	15	0.381	0.93	0.382	0.82
T	Isopropylbenzene	10.44		15	1.474	17.44	1.562	4.13
T	Bromobenzene	10.58		15	0.643	5.20	0.653	3.12
T	n-propylbenzene	10.82		15	1.840	17.38	1.950	3.60
T	2-Chlorotoluene	10.85		15	1.124	10.66	1.166	1.93
T	4-Chlorotoluene	10.92		15	1.184	10.23	1.224	3.75

Table 4. Compound List with Average Response Factors (RF) and the RF %RSDs for Two Calibration Ranges: 1–300 and 1–200 µg/L (Continued)

Type*	Compound	Retention time (min)	Minimum average response factor**	Maximum %RSD of calibration response factors***	Average RF 1–300 µg/L	RF %RSD 1–300 µg/L	Average RF 1–200 µg/L	RF %RSD 1–200 µg/L
T	1,3,5-Trimethylbenzene	11.08		15	1.275	14.63	1.340	3.02
T	Tertbutylbenzene	11.26		15	1.196	18.98	1.274	4.24
T	1,2,4-Trimethylbenzene	11.36		15	1.353	12.22	1.411	2.35
T	sec-Butylbenzene	11.43		15	1.729	21.91	1.858	5.67
T	1,3-Dichlorobenzene	11.44		15	1.529	10.75	1.579	5.61
T	1,4-Dichlorobenzene	11.49		15	1.597	9.97	1.643	5.99
ISTD	1,4-Dichlorobenzene-d ₄	11.47		15		1.09		1.17
T	p-Isopropyltoluene	11.58		15	2.587	19.00	2.757	3.52
T	1,2-Dichlorobenzene	11.73		15	1.485	6.33	1.516	2.74
T	Butylbenzene	11.87		15	2.355	20.68	2.522	4.81
T	1,2-Dibromo-3-chloropropane	12.06		15	0.186	13.90	0.180	11.56
T	1,2,4-Trichlorobenzene	12.95		15	1.211	12.42	1.250	8.76
T	Naphthalene	13.10		15	2.879	5.54	2.852	5.32
T	Hexachlorobutadiene	13.16		15	0.750	24.53	0.809	10.56
T	1,2,3-Trichlorobenzene	13.22		15	1.196	11.09	1.226	9.06
	Average %RSD of targets				9.07		4.60	
	Average %RSD of all compounds					8.22		4.23

*Compound designations as follows: T (target); SPCC (system performance check compound); CCC (calibration check compound); Surr (surrogate); ISTD (internal standard). Target compounds may also be designated as SPCCs or CCCs.

**The minimum average RF that must be met for the SPCCs.

***The maximum %RSD of the RFs. If any one or more of the CCC RF RSDs exceeds 30%, instrument maintenance is required. If the RF %RSD for any target compound exceeds 15%, other curve fits must be substituted for the average RF.

Method 8260B Requirements

Below is a summary of the most significant requirements of Method 8260B. If you are already very familiar with this method, you may want to skip this section.

ISTDs and surrogates: The ISTDs and surrogates listed in Table 4 are the recommended compounds for this method, although other compounds may be used instead.

Tuning requirements: Prior to running samples, the MSD must be adjusted so as to pass Method 8260B's BFB tuning specifications [1]. However, the method allows users to substitute CLP [4], Method 524.2 [3] or manufacturers' instructions for the specified BFB ion ratios. Table 5 lists the BFB tuning specifications for all three EPA methods. A scan range of 35–260 *m/z* is recommended.

Table 5. Criteria for BFB Tuning for Three Capillary GC/MS Volatiles Methods

Mass (<i>m/z</i>)	Relative abundance criteria		
	Method 524.2	Method 8260B*	CLP-SOW
50	15%–40% of 95	Same**	8%–40% of 95
75	30%–80% of 95	30%–60% of 95	30%–66 % of 95
95	Base Peak, 100%	Same	Same**
96	5%–9% of 95	Same	Same
173	<2% of 174	Same	Same
174	>50% of 95	Same	50%–120% of 95
175	5%–9% of 174	Same	4%–9% of 174
176	>95% but <101% of 174	Same	93%–101% of 174
177	5%–9% of 176	Same	Same

*Alternative tuning criteria may be used (for example, CLP or Method 524.2) including manufacturer's instructions provided that method performance is not adversely affected.

**"Same" implies that this requirement is the same as that shown for Method 524.2. Note, however, that alternative tuning criteria may be used for Method 8260B (see previous footnote).

System Performance Check Compounds (SPCCs): The SPCCs are used to check the performance of the system after calibration and before analysis of samples. These compounds are known to be sensitive to active sites and instrument contamination. They must meet a minimum RF that is specified in Table 4.

Calibration Requirements: As a minimum, Method 8260B requires a five-point calibration curve. In order to assume linearity of the calibration curve, the RF RSD of all target compounds must be less than or equal to 15%. Six analytes are designated as Calibration Check Compounds (CCCs) (Table 4). If the RF RSDs for any of these compounds exceeds 30%, it is indicative of instrument problems and repairs must be made. Compounds that exceed 15% RSD for their RFs can use alternative curve fitting methods as specified in EPA Method 8000B [5].

GC/MS Calibration Verification for Each 12-hour Shift: The P&T/GC/MSD performance must be re-evaluated every 12 hours. The most significant requirements are:

- The BFB tune must be rechecked and pass the original tuning requirements.
- A sample near the midpoint of the calibration curve must be analyzed using P&T sample introduction, demonstrating that:
 - Each SPCC meets its minimum RF.
 - The percent difference (between current and original response) must be less than 20% for each CCC.

- The retention time of each ISTD must not drift by more than 30 s.
- The ISTD areas must not change by more than a factor of 2 from the original mid-point calibration level (50% to 200%).
- A method blank must be run to show that there is no carryover or contamination of the system.

Calibration Results

Many laboratories employing Method 8260B generate five-point calibration curves between 5 and 200 µg/L. Knowing that laboratories often try to extend this range at both ends, an eight-point calibration was run at 1, 2, 5, 20, 50, 100, 200, and 300 µg/L. The signals for all analytes at 1 µg/L were sufficient to allow calibration at even lower levels. However, the lowest calibration level run for this work was 1 µg/L. Figure 2 shows a chromatogram of the targets, surrogates, and ISTDs at 50 µg/L each.




Figure 2. P&T/GC/MS analysis of a standard containing all of the compounds listed in Table 4, each at 50 µg/L in VOC-free water.

The average RF and %RSD of the RFs were calculated for each compound over the 1–300 µg/L and 1–200 µg/L ranges. As seen in Table 4, all five of the SPCCs exceeded their minimum RFs by a comfortable margin for both calibration ranges.

As mentioned above, the CCC RF RSDs must not exceed 30%. Table 4 shows that all six CCCs were significantly less than this for both calibration ranges. In fact, the average %RSD of the CCCs was only 4.90% for the 1–300 µg/L calibration and a remarkably small 1.58% in the narrower 1–200 µg/L range.

Only eight compounds exceeded the 15% RSD requirement in the 1–300 µg/L calibration range.

In all cases, the RF fell off significantly for the 300 µg/L standard, suggesting that the strong target ion response overloaded the MSD at that very high concentration.

In the 1–200 µg/L calibration range, the average RF could be used for all targets except, perhaps, bromoform which exceeded the 15% limit by 0.08%. If one justifies only two significant figures, even bromoform could use an average RF for calibrations. The average of the %RSDs for all targets was 8.9% for the 1–300 µg/L calibration and only 4.5% for the 1–200 µg/L range (Table 4). Figure 3 shows a plot of the RFs for each target compound over the 1–200 µg/L calibration range.




Figure 3. Plot of the RFs from a seven-level calibration for all of the target compounds listed in Table 4. Concentrations were at 1, 2, 5, 20, 50, 100, and 200 $\mu\text{g/L}$.

Figure 4 plots a distribution of the RF %RSD values for the 59 calibrated peaks (m- and p-Xylene were not resolved). It shows that most compounds have RFs over the 1–200 $\mu\text{g/L}$ calibration range with less than six percent RSD. More than 91% of the compounds have RSD values of 10% or less.




Figure 4. Distribution of the RF RSDs for the 59 calibrated peaks (m- and p-xylene were not resolved).

Response Stability

The longevity of any calibration depends upon having a consistent response for all compounds, even when running samples almost continuously over the course of several days, weeks, or even months. Some laboratories have observed a falloff in response over time that can jeopardize the calibration. Moreover, it has been observed that the recoveries for certain compounds may be dependent upon the presence or absence of other VOCs in the sample. A complete discussion of this problem and some simple solutions for it may be found in the “Optimization Techniques” section below.

In order to assess instrument stability over time, two types of samples were prepared. “System Blanks” contained only FBz, BFB, and 1,2-dichlorobenzene- d_4 (DCB- d_4) at 10 $\mu\text{g/L}$ in water. The first compound was used as the ISTD while the latter

two were chosen as surrogates. “Spiked” samples were the same as the system blanks but with the 60 target VOCs added at 20 $\mu\text{g/L}$ each. These samples were analyzed alternately, typically for 22 runs, but sometimes many more runs over several days.

Figure 5 is a plot of the normalized recoveries for FBz, BFB, and DCB- d_4 . It illustrates the two problems that can be observed when instrument parameters are not optimized. First, there is a gradual drop in response for all three compounds as illustrated by the sloping arrows. Superimposed upon this is a reduction in surrogate recovery in the absence of added VOCs. Because system blanks and spiked samples were alternated in the sequence, there was a “zigzag” appearance to the plot.




Figure 5. Normalized recoveries for FBz, BFB, and 1,2-DCB- d_4 . System blanks (containing only FBz, BFB, and DCB- d_4 at 10 $\mu\text{g/L}$ each) were analyzed alternately with system blanks spiked with an additional 60 VOCs at 20 $\mu\text{g/L}$ each. Arrows show a gradual loss of response over the course of the sequence. The zigzag pattern arises because the recovery of BFB and DCB- d_4 is higher in the presence of other VOCs.

The problems illustrated in Figure 5 can be avoided rather easily by not overloading the MSD's electron multiplier (EM) and by ensuring that there are no active sites in the sample flow path. Figure 6 shows normalized recovery plots for BFB and DCB-d₄ that are typical when the instrument parameters are set correctly. Once again, system blanks and spiked samples were alternated, but this time there was no drop in response over time. Surrogate recovery was independent of sample spiking. Simple solutions for resolving these problems are discussed below.




Figure 6. Normalized recovery for BFB (6A) and DCB-d₄ (6B) using the Agilent 6890N/5973 inert GC/MS coupled to the Velocity XPT P&T with optimized system parameters.

Optimization Techniques

MSD Tuning: Application Note 5988-4373EN [6] discusses three different ways to tune Agilent's 5973N MSD in order to meet BFB requirements. With the recent introduction of the 5973 inert MSD, these procedures still apply, though it is helpful to turn off the variable entrance lens setting when using the BFB autotune. The CLP Statement of Work specifications (Table 5) offers more latitude than the 8260B tuning requirements. Most importantly, ion 174 can be up to 120% of ion 95 (the reference ion). It is helpful to tune the MSD so as to produce a 174/95 ion ratio that is in the 90%–120% range because this improves the signal for bromoform (base peak = 173), which purges with poor efficiency. For this work, the “modified autotune” method was used and the 174/95 ratio was about 105%. It has been our experience that once the Agilent 5973 inert has been tuned to meet BFB requirements, the tune is stable for many weeks. It is impossible to say how long, because once tuned, it never failed to pass the BFB requirements.

MSD Parameter Optimization: When ISTD or surrogate responses fall off with repeated injections, overloading the Agilent 5973 MSD's high energy dynode (HED) EM may be the cause. The 5973 was designed to be significantly more sensitive than its predecessors and incorporates an HED in the EM. This reduces the noise and increases the signal, especially for ions of higher mass. However, this highly sensitive detector can be overloaded by continuous ion bombardment or by operating it at too high a voltage. The symptom is an unusually large loss of response over time.

Many GC/MS users erroneously believe that they can increase the sensitivity of their MSD by increasing the EM voltage. This can be done by raising the target value during tuning or by adding voltage to the tune value in the “MS SIM/Scan Parameters” window. However, in the electron impact mode, the noise increases at approximately the same rate as the signal. So, the true sensitivity (signal/noise) does not increase. The main consequence is to reduce the EM's lifetime. This can show up as a reduced response over time that might even be noticeable after several runs. (Note that these statements about signal/noise ratios do not necessarily apply to chemical ionization techniques.)

The solution to this “problem” is relatively simple. The easiest way is to reduce the EM voltage, which reduces the signal and noise, but not the signal/noise ratio. It may also be necessary to reduce the threshold value in the “Edit Scan Parameters” window in order to see the smaller ions. The default EM voltage values from an Autotune or BFB tune are usually correct, but these can be decreased somewhat if the above-mentioned symptoms occur.

It is easier to overload the EM in the selected ion monitoring (SIM) mode, because only a few ion fragments are monitored. During peak elution in the scan mode, there are “blank” spaces in all spectra where the signal is small or zero. With SIM, the signal is almost continuous and the ions monitored are usually the most abundant ones. Here again, the solution is relatively simple. One can reduce the EM voltage, decrease the SIM dwell time, and/or reduce the peak width by choosing the “High Resolution” option. The latter two values are set in the “Edit SIM Parameters” window. In any case, it is important to remember that both signal and noise are roughly proportional to the EM voltage and nothing is sacrificed by making small reductions in its value. Just remember to lower the threshold value or set it to 0 at the same time.

Reducing System Activity: When surrogate recoveries are higher in the presence of other analytes, as illustrated in Figure 5, active sites in the sample flow path are a likely cause. Surrogates can adsorb on these active sites, reducing their recovery. Surrogate recoveries improve when other analytes are present that compete for the active sites. To prevent such problems, one must use a highly inert P&T/GC/MS system and maintain its cleanliness by avoiding contamination from foaming samples. The Agilent 6890N/5973 inert GC/MS coupled to the Velocity XPT P&T showed no signs of sample adsorption. As seen in Figure 6, surrogate recoveries were highly stable with this system. If target or surrogate recoveries vary depending upon the presence of other analytes, it may be helpful to increase the temperature of the MSD source or upgrade an older 5973A or N with the new “Inert” source.

The P&T Method and Water Management: The VOC Teklink software used to control the new Teledyne Tekmar Velocity XPT concentrator and Aquatek 70 autosampler offers a “wizard” tool to help the user choose parameters for the method. Only minor modifications were made to the wizard-generated method. ISTDs were added manually to each sample so the “Fill I.S. Time” was set to 0.00 min. The bake time was increased to 3 minutes and the number of bake rinses was increased to three. The wizard chose all other parameters after the user provided information about the system configuration.

One of the primary concerns of P&T/GC/MS methods is the management of water that is inevitably purged along with the analytes. Since calibration, surrogate, and ISTD solutions are prepared in methanol, some of this solvent is also purged and retained by the trap. By starting the scan at 40 μ , methanol and water ions were not detected by the MSD. Nevertheless, transferring large amounts of water or methanol from the P&T to the GC/MS can result in poor reproducibility for those compounds that co-elute with them. Using the Velocity XPT with the Agilent 6890N/5973 inert system there were no problems that could be attributed to water. Because the P&T was configured with a Vocarb 3000 trap, the DryFlow trap was not required. Various dry purge times and flow rates were tried, but the only affect this had was to distort the peak shape of one or more early eluting peaks. Therefore, the dry purge option was not used. It is likely that some problems attributed to an excess of water actually result from overloading the MSD EM.

Standard preparation: The careful preparation of standards for calibration cannot be overemphasized. As with most laboratories, the initial dilutions were purchased as 2000 $\mu\text{g/mL}$ /component concentrates, which were stored without problem in a refrigerator. Experience in this laboratory showed that best results were obtained when observing the following guidelines:

- Prepare secondary dilutions used for sample spiking from freshly opened standards.

- Transfer secondary dilutions to appropriately sized glass containers so that there is little or no headspace in the vial. Store small quantities in microvials.
- Mininert vial closures were tried for sample storage but were prone to leakage and their use was discontinued. In addition, they were not available for microvials.
- It works well to prepare calibration standards by spiking methanolic solutions into pure water through the septum of the VOA vial. It works equally well to prepare standards in 50- or 100-mL volumetric flasks and pour the aqueous solutions into VOA vials.
- If several VOA vials of the same solution are being prepared at one time, do not prepare the solution in a single large volumetric flask. There will be some VOC loss by pouring repeatedly from the flask. Instead, spike vials individually or use the apparatus described in Figure 1 for sample transfer.
- When preparing calibration standards, transfer the same amount of methanolic solution to each VOC sample. This requires preparing secondary dilutions in methanol for each calibration level instead of spiking different amounts of a single standard.

Leaks: Leaks anywhere in the system can result in poor precision, loss of sample, and calibration failure. Leaks in the carrier gas flow path can easily be detected by the MSD as a high background of oxygen and nitrogen. To correct leaks, tighten or replace the offending fittings after finding the leaks using established techniques. A more difficult problem to detect results from leaks in the fittings that connect the purge vessel to the P&T instrument. Even the smallest leaks during the purge cycle can result in the loss of VOCs and cause poor precision. Leaks that a helium leak detector might miss, can still cause VOC loss. If all the RFs for a given calibration level seem to be low by a similar amount, or if the RF RSDs are all very similar (but too large), then P&T leaks are the likely cause. Tighten or replace the fittings associated with the purge vessel.

Conclusions

EPA Method 8260B with P&T sample introduction is one of the most widely used water analysis methods. There are numerous P&T, GC, and MS variables to optimize in order to obtain long-lasting linear calibration curves and good analytical results. This application note summarizes much of Agilent's experience in optimizing all facets of this VOC method. Most analysts know how to prepare calibration and check samples, tune the MSD, and set instrument parameters; and they find this method to be very rugged with infrequent need for retuning and recalibration. The suggestions in this paper are designed to help in case problems do arise or when an analyst runs this method for the first time. Though the focus was on Method 8260B, these techniques apply to almost any P&T/GC/MS method.

References

1. "Volatile Organic Compounds by Gas Chromatography/Mass Spectrometry (GC/MS)," U.S. Environmental Protection Agency, Office of Solid Waste, SW-846 Method 8260B, revision 2, December 1996
(<http://www.epa.gov/epaoswer/hazwaste/test/pdfs/8260b.pdf>).
2. "Purge-and-Trap for Aqueous Samples," U.S. Environmental Protection Agency, Office of Solid Waste, SW-846 Method 5030C, revision 3, May 2003
(<http://www.epa.gov/SW-846/pdfs/5030c.pdf>)
3. "Methods for the Determination of Organic Compounds in Drinking Water-Supplement III (EPA/600/R-95-131)," Method 524.2, revision 4.1, U.S. Environmental Protection Agency, Office of Research and Development, National Exposure Research Laboratory, Cincinnati, OH (1995).
4. "USEPA Contract Laboratory Program Statement of Work for Organics Analysis, Multi-Media, Multi-Concentration, OLM04.2," USEPA Contract Laboratory Program, Office of Emergency and Remedial Response
(<http://www.epa.gov/superfund/programs/clp/olm4.htm>).
5. "Determinative Chromatographic Separations," U.S. Environmental Protection Agency, Office of Solid Waste, SW-846 Method 8000B, revision 2, December 1996
(<http://www.epa.gov/epaoswer/hazwaste/test/pdfs/8000b.pdf>)
6. Philip L. Wylie, "BFB Tuning for Environmental Analysis: Three Ways to Succeed," Agilent Technologies publication 5988-4373EN
(<http://www.chem.agilent.com/temp/rad48994/00031636.pdf>)

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
February 25, 2004
5989-0603EN



Agilent Technologies



Optimized Analysis of Gasoline (BTEX) in Water and Soil Using GC/FID with Purge and Trap

Application Note
228-324

Author

**Imogene L. Chang PhD, and
Zhenghua Ji, PhD**
Agilent Technologies
Wilmington, DE 19808-1610

Abstract

Gas chromatography with purge and trap analysis using their HP-1 capillary column and the Agilent 5890 Series II gas chromatograph/flame ionization detector was done to determine gasoline components in contaminated water and soil in accordance with modified EPA Methods 8015/8020. Purge and trap and gas chromatograph parameters were optimized for accurate quantitation of gasoline range organics (aliphatics, aromatics, and oxygenates) and to increase analysis speed.

Key Words

- EPA Methods 8015/8020
- Gasoline
- BTEX
- Purge and Trap
- GROs
- GC/FID analysis
- LUST

Introduction

Modified EPA Methods 8015/8020 are used to determine gasoline and gasoline components in water and soil by capillary gas chromatography (GC) with a flame ionization

detector (FID) or photo-ionization detector (PID). The hydrocarbons in gasoline encompass a wide range, from butane to decane and benzene to naphthalene, and cover a boiling point range of 50°C to 281°C. For such complex mixtures, an efficient purge and trap (P and T) system is required to concentrate samples for high-resolution gas chromatography. Detection is achieved using an FID, and quantitation is based on FID response to a gasoline standard. Other light petroleum products that can be determined in the same manner include paint stripper, Stoddard solvent, mineral spirits, petroleum naphtha, and aviation jet fuels using the pattern recognition technique.

The analysis of gasoline components, e.g., gasoline range organics (GROs), and benzene, toluene, ethylbenzene, and xylenes (BTEX) in particular is of great importance because BTEX is frequently used as a marker in the identification of gasoline-type products. Subsequently, the analysis of BTEX is often used to determine the composition and the origin of such products including weathered fuels leaking from underground storage tanks (LUST), spills in pipe lines, and run-off from surface transportation.

For the analysis of gasoline with BTEX, the sample is introduced into a sparge tube on the P and T autosampler or purge vessel or the P and T unit. The P and T concentrates the volatiles in the

sample and transfers them onto the capillary column.

Parameters affecting the efficiency of P and T sample concentration include time and temperature for sample purge, dry purge, desorption of trapped volatile organics and trap baking. Most P and T system manufacturers recommend 11 minutes of purge or a total of 440 ml purge gas through the sample. Many laboratories use the manufacturer's set purge flow of 40 ml/min which corresponds to 11 minutes of purge time, to achieve a minimum of 440 ml purge gas through the sample. In this study a Vocab-3000 trap was used because it can provide higher trapping efficiency and allow for higher desorption and baking temperature.

A typical analysis can usually be completed in 35 to 40 minutes. In this application both P and T parameters and GC conditions were optimized for accurate quantitation and analysis speed.

Experimental

Samples were concentrated using an Agilent 7695A P and T system with a Vocab-3000 trap (part no. 5182-0775) and a 5-ml frit sparger (part no. 5182-0852). Using an HP-1 column (30 m x 0.53 mm x 5.0 µm, (part no. 19095Z-623), hydrocarbons were analyzed on an Agilent 5890 Series II GC with EPC and FID. Instrument requirements and optimal GC and P and T conditions are listed in **Table 1**.



Agilent Technologies
Innovating the HP Way

Working solutions were prepared from diluting commercial gasoline, LUST-modified GROs (part no. 5182-0860), and internal standard and surrogate (part no. 8500-6007) with GC-grade methanol (Burdick and Jackson). Concentrations of GROs, gasoline, and jet fuel standards are listed in **Table 2**.

Samples were prepared from spiking 5 ml of organic-free reagent water using a 5-ml sample syringe with a luer connector (part no. 9301-1185) with standard solutions using 5- μ l to 100- μ l fixed needle syringes (HP part nos. 9301-0810, 9301-0818, 9301-0059, 9301-0063, respectively).

Results and Discussion

To obtain accurate and reproducible results, complete sample purging, managing water adequately from the P and T system, and preventing carry-over from the trap are essential. Many environmental laboratories analyze gasoline with BTEX using long sample purge (11 to 15 minutes), dry purge (2 to 4 minutes), trap desorb (2 to 4 minutes), and trap bake (10 to 20 minutes) times. Therefore, a typical run usually takes 40 to 48 minutes including 3 to 5 minutes for trap cool-down.

Figure 1 shows a GC/FID analysis of a gasoline standard and a GC/PID chromatogram of a GROs standard using an OI 4460A P and T system with a BTX trap and DB-1 column (30 m x 0.53 mm x 5 μ m). GC and P and T conditions are listed in **Table 3**. Although the GC runs were completed in 27 minutes, the actual cycle time for each run was 37 to 40 minutes.

Table 1. Instrument Requirements and Optimized Conditions

A. Recommended Instrumentation

Gas chromatograph:	5890 Series II
Injection port:	Split/splitless inlet
Column:	HP-1, 30 m x 0.53 mm x 5.0 μ m (Part no. 19095Z-623)
Detector:	FID
Injection technique:	7695A P and T
Data system:	3365 ChemStation and HP Vectra 486/100MX

B. Experimental Conditions

GC Parameters

Inlet:	220°C, split injection (split ratio 5:1)
Carrier:	Helium, 10 ml/min, constant flow (6.5 psi at 40°C)
Oven parameters:	40°C (3 min) at 7°C/min to 125°C to 250°C (3 min) at 35°C/min
Detector:	FID, 300°C; nitrogen makeup gas, 25 ml/min; H ₂ , 30 ml/min; and air, 350 ml/min PID, 250°C

P and T Parameters

Line temperature:	200°C	Purge time:	11 min
Valve temperature:	200°C	Dry purge time:	1 min
Mount temperature:	40°C	Desorb time:	2 min
MCS line temperature:	100°C	Bake time:	5 min
Purge ready temperature:	30°C	BGB time:	2 min
MCS desorb temperature:	40°C		
Desorb preheat temperature:	245°C		
Desorb temperature:	250°C		
Bake temperature:	265°C		
MCS bake temperature:	300°C		




Figure 1. Typical chromatograms of gasoline and GROs standards using a DB-1 column under the GC and P and T conditions (Table 3) used in environmental testing laboratories (see Table 2 for peak identification).

Optimized GC Run Time

With the HP-1 column (30 m x 0.53 mm id x 5 μ m) and a faster oven temperature, the GC run time was initially reduced to 21 minutes for GROs and gasoline (see **Figure 2**). Good baseline separations and sharp symmetric peaks (**Figure 2B**) were obtained for all GROs, including surrogate (α,α,α -trifluorotoluene) and internal (4-bromofluorobenzene) standard. The oven temperature program used was 40°C (3 min) at 7°C/min to 125°C to 250°C (3 min) at 35°C/min and a constant carrier flow of 10 ml/min. Under these conditions (**Table 1**), both pentane and MtBE were clearly separated from the large solvent peak (menthanol).

Even though the last GROs component (naphthalene) eluted below 200°C at 17.8 minutes, the oven temperature was increased to 250°C to bake out the high-boiling material purged from the sample. As a result, no carryovers were found even with repeated injections of gasoline standard in the 23,000-ppb level.

GC run times were further lowered by using a thinner-film HP-1 column and/or faster oven temperature programs. **Table 4** shows the benefits of using various column thicknesses, temperature ramps, and carrier flows to achieve the optimal GC run time of 17 minutes. Analytes generally elute faster from a thin-film column (**Figure 4**). In **Figure 3**, the thick-film column retained hydrocarbons longer initially until the faster oven temperature ramp (15°C/min) sped up the elution of all GROs components from the column. To avoid potential coelution (peaks 4 and 5), a comparative smaller carrier flow (4.5 ml/min) was used instead of the optimal 10 ml/min carrier flow. Reducing the GC run time, however, would be counterproductive because the total run time is dependent on the P and T cycle.

Table 2. Analytes in Working Standards

Standards	Peak No.	Components	Concentration
GROS mix	1	MtBE	100 ppm each
	2	Benzene	
	3	Toluene	
	4	Ethylbenzene	
	5	m-/p-Xylene	
	6	o-Xylene	
	7	1,2,4-Trimethylbenzene	
	8	1,3,5-Trimethylbenzene	
	9	Naphthalene	
	10	α,α,α -Trifluorotoluene (SS)	
	11	4-Bromofluorobenzene (IS)	
Gasoline standard		Gasoline	500 ppm
Gasoline		Gasoline	2,500 ppm
Jet fuel		Aviation jet fuel	1,000 ppm




Figure 2. Chromatograms for gasoline and GROs standards using an HP-1 column under the optimal GC and P and T conditions listed in Table 1. (See Table 2 for peak identification.)





Figure 3. Chromatogram of GROs standards using a thick-film HP-1 (30 m x 0.53 mm x 5 μ m) column. (See Table 2 for peak identification and Table 4 for GC conditions.)

Table 3. Typical GC and P and T Conditions for Gasoline and BTEX Analysis

GC Parameters			
Injection:	Direct injection		
Carrier flow:	Initially 10 ml/min, constant pressure mode		
Oven temperature:	50°C (hold 3 min) to 125°C at 5°C/min to 240°C (5 min) at 45°C/min		
Detector:	PID (250°C) in series with FID (300°C)		
P and T Parameters			
Trap:	BTX trap		
Purge temperature:	Ambient	Purge time:	11 min
Dry purge temperature	22°C	Dry purge time:	2 min
Desorb preheat temperature	150°C	Desorb time:	4 min
Desorb temperature	180°C	Bake time:	15 min
Bake temperature:	200°C		

Figure 4. Chromatogram of GROs standards using a thin-film HP-1 (30 m x 0.53 mm x 3 µm) column. (See Table 2 for peak identification and Table 4 for GC conditions.)

Optimized P and T Cycle Time

Further optimization of the run was dependent on obtaining the most efficient parameters for the P and T cycle. Each aspect of the cycle was optimized as follows.

Sample Purge

Experimentation showed 11 minutes of purge time, or 440 ml of helium purge gas, to be the most efficient time for analyses of gasoline and GROs because shorter purge times (8 minutes or 320 ml of purge gas) were not sufficient to purge all GROs from the sample solution. **Figure 5** shows a comparative analysis of the same GROs standard shown in **Figure 2B** using 8 minutes of purge time instead of 11 minutes of purge time. The conditions for both analyses were the same and are shown in **Table 1**. By comparison, hydrocarbon recoveries (including aromatics) for the GC runs with 8 minutes of

sample purge were not as good particularly for the high-boiling fractions, such as trimethylbenzenes and naphthalene (compare peaks 7, 8, and 9 in **Figure 5** and **Figure 2B**). The naphthalene peak in **Figure 5** (8 minutes of purge) was remarkably


small, and area counts were lower than 1% of that recovered in **Figure 2B**. Based on this finding, 11 minutes is the optimal sample purge time for the determination of gasoline with BTEX.

Dry Purge

During sample purge, a larger amount of water is purged along with the volatile organics and is collected on the trap sorbent. Sorbent material in the Vocab-3000 trap is designed to minimize water trapping and reduce the release of excessive water onto the GC column during the thermal desorption process. A 1-minute dry purge of the Vocab trap was selected because the early-eluting peaks (such as pentane, MtBE, and benzene in **Figure 2**) were not skewed by water released from the trap onto the column.

Desorption

According to Klee¹, a fast and reproducible desorption temperature is the key to good chromatography using the P and T concentration technique. The higher the desorption temperature and desorption rate, the faster the volatile analytes can be moved to the GC column, and the narrower the peak widths of the early-eluting analytes. Therefore, a short desorption time is preferred. In addition,

Figure 5. Chromatogram of GROs standard using an 8-minute sample purge. (See Table 2 for peak identification and Table 1 for GC and P and T conditions.)

Doherty² reported that peak heights and peak areas of volatile organics, including those in the GROs mix, were virtually unchanged when the desorb time changed from 4 minutes to 1 minute. Several manufacturers of P and T systems also recommend a 1-minute desorb time for the routine analysis of volatile organics. However, experimentation (**Figure 2**) using a 2-minute desorb time at 250°C accommodated sharp initial peaks as well as good separation. This study applied a 2-minute desorption time at 250°C to all analyses.

Trap Baking

Three different bake times were evaluated for the Vocab-3000 trap (used a bake temperature of 265°C, recommended for the Vocab-3000 trap): 10, 8, and 5 minutes. At each bake time, the gasoline sample (1000-ppb concentration) was run using an 11-minute purge time followed by a run of reagent water with no sample purge. Chromatograms of these two runs were evaluated for carryover. In all three cases (bake times of 5, 8, and 10 minutes), no carryover was observed for any gasoline component. Therefore, a 5-minute bake time at 265°C was selected as an optimal bake time for the analysis of gasoline and GROs aromatics.

For samples containing 46,000 ppb of gasoline, no carry over from the trapped analytes was observed at the 5-minute bake time. This is based on the comparison of chromatograms of reagent water (0-minute purge) run immediately after each sample. However, carry over from the purge vessel was found. Repeated rinsing of the purge vessel with reagent water reduced the amount of carry over but did not eliminate it. Therefore, after a high level sample is run, it is advisable to remove and clean the purge vessel prior to the next run.

Heavier petroleum products, such as diesel and jet fuel (**Figure 6**), that often contain volatile components are also detectable by this method. Again, carry over is a problem. Carry

Table 4. GC Run Time of 17 Minutes

HP-1 Column Thickness	Oven Ramp	Carrier Flow Time
30 m x 0.53 mm x 5 µm	40°C (3 min) at 15°C/min to 250°C	4.5 ml/min (see Figure 3)
30 m x 0.53 mm x 3 µm	40°C (3 min) at 7°C/min to 95°C to 250°C (2 min) at 45°C/min	10 ml/min (see Figure 4)

over was observed in the reagent water (used an 11-minute purge) run immediately after the jet fuel sample.

Carry over ranged from 10 ppb to 60 ppb jet fuel and was high enough to cause a false-positive identification in subsequent runs.

As demonstrated by **Figure 7B** (a chromatogram of reagent water, 0-minute purge, run immediately after

a jet fuel sample), carry over from the Vocab trap was found to be negligible. Clearly the carry over was the result of contamination from the purge vessel (see **Figure 7A**). Although repeated rinsing reduced the amount of carry over, it did not eliminate it completely. Purge vessel carry over was eliminated completely when the purge vessel and the purge needle were removed and cleaned (see **Figure 7C**).

Figure 6. Chromatogram of 1,000-ppb aviation jet fuel standard. (See Table 1 for GC and P and T conditions.)





Figure 7. Chromatograms of reagent water following the analysis of the 1,000-ppb aviation jet fuel sample. (See Table 1 for GC and P and T conditions.) Note: The chromatograms were plotted on the same FID response scale.



Conclusion

Determination of optimized P and T parameters is critical in establishing optimized run times for the analysis of gasoline/BTEX. By reducing the P and T bake time to 5 minutes and selecting shorter dry purge (1 minute) and desorption times (2 minutes), the overall P and T cycle was shortened to 25-26 minutes. This is compatible with the run time of 21-22 minutes established for optimized GC conditions. When carry over from the purge vessel is controlled, this same application can be used successfully for the analysis of samples containing in excess of 46,000 ppb of gasoline and other volatile organics in light petroleum products.

Acknowledgment

The authors wish to thank Mr. Robert Remlinger at the Pace Laboratory in Petaluma, California for providing his GC/FID and GC/PID chromatograms.

Reference

1. Matthew S. Klee, *GC Inlets—An Introduction*, Hewlett-Packard Company, 1991, Part No. 5958-9468.
2. Linda Doherty, "The analysis of volatile organics in drinking water with an OI 4460A purge and trap and an HP GC/MS system," Hewlett-Packard Company, GC/MS Application Note, August 1991, Publication No. (23) 5091-2477E.

Copyright © 1995, 2000 Agilent Technologies
Printed in USA 04/00

Printed on recycled paper
Publication Number 5963-9968E

www.agilent.com




Agilent Technologies
Innovating the HP Way



Soil & Sediment

Semi-volatiles Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)



GC Analysis of Polybrominated Flame Retardants

Application

Environmental

Authors

Eberhardt Kuhn, Jason Ellis
Agilent Technologies, Inc.
91 Blue Ravine Rd,
Folsom, CA 95630
USA

Steve Wilbur
Agilent Technologies, Inc.
3380 146th Place SE
Suite 300
Bellevue, WA 98007
USA

Abstract

Polybrominated diphenyl ethers (PBDE) are used as flame retardants in such diverse products as textiles, circuit boards, and computer covers. Through the disposal of those products in landfills, PBDEs have found their way into the environment. Studies have shown that PBDEs have detrimental health effects.

Detection and quantitation of these compounds is complicated by their intrinsic properties: high boiling points and low thermal stability. This application note describes

development of suitable gas chromatography/mass spectrometry, gas chromatography micro electron capture detection, and gas chromatography inductively coupled plasma mass spectrometry methods to analyze PBDEs. The Agilent DB-XLB is the column of choice for this demanding analysis. The detection limit with micro electron capture detector was 100 ppt for most congeners.

Introduction

The presence of polybrominated diphenyl ethers (PBDE) throughout the environment has attracted the attention of scientists around the world. PBDEs are used as flame retardants in many commercial products, such as textiles and furniture, and in circuit boards in consumer electronics, such as TVs and computers. As more and more of these abundant consumer products find their way into landfills, PBDEs have been found in our drinking water supplies [1]. One alarming study predicts that the levels found in human breast milk of North American women appear to double every 2 to 5 years [2]. Exposure of personnel working with computers is also a concern [3]. While the toxicology of PBDE is still under investigation, research has established that it is persistent, bioaccumulative, and toxic. There is evidence that



Agilent Technologies

PBDE can cause neurotoxic effects similar to the now-banned polychlorinated biphenyls (PCB). As a result, California has just signed legislation banning the use of PBDEs [4]. Like PCBs, there are 209 PBDE congeners (Figure 1), and they are named in analogy to PCBs [5]. However, only seven congeners comprise about 95% of all detected peaks [6]. These major congeners are (by IUPAC number): 28, 47, 99, 100, 153, 154, and 209.




Figure 1. Structure of PBDE.

Until recently, the lack of available standards and individual congeners has made accurate quantitation difficult [7]. Now, practically all individual congeners are commercially available. For analysis by GC, several different stationary phases have been used. However, analysis times are generally quite long, and often not all critical congeners are sufficiently resolved. This study investigates two different columns and three detection modes. DB-XLB (Agilent Technologies, Folsom CA), a proprietary low-polarity stationary phase and DB-35ms (Agilent Technologies, Folsom CA), a mid-polarity phase, are both columns that have very low bleed and high thermal stability. DB-XLB has shown to be an excellent choice for detailed, high-resolution analysis of PCB congeners by GC/MS [8]. The structural similarities between PCBs and PBDEs suggest that DB-XLB should be an excellent choice for separation of PBDEs as well. DB-35ms has shown to be a suitable confirmatory column to DB-XLB [9]. The detection modes evaluated were mass selective detector (MSD), micro electron capture detector (μ ECD), and inductively coupled plasma mass spectrometry (ICP-MS). Method optimization efforts for speed, sensitivity, and resolution included different column dimensions, inlet conditions, detector settings, and temperature programs.

Results and Discussion

Baseline separation of all 14 critical congeners (Table 1) in a standard mixture including decabromodiphenylether (BDE-209) could be accomplished by DB-XLB in about 20 minutes with excellent peak shape and response of the decabromodiphenylether [10].

Table 1. PBDE Congeners in Test Mix EO-5103 Elution Order on DB-XLB

Peak	Congener (2.5 mg/mL)
1	2,2',4-TriBDE (BDE-17)
2	2,4,4'-TriBDE (BDE-28)
3	2,3',4',6-TetraBDE (BDE-71)
4	2,2',4,4'-TetraBDE (BDE-47)
5	2,3',4,4'-TetraBDE (BDE-66)
6	2,2',4,4',6-PentaBDE (BDE-100)
7	2,2',4,4',5-PentaBDE (BDE-99)
8	2,2',3,4,4'-PentaBDE (BDE-85)
9	2,2',4,4',5,6'-HexaBDE (BDE-154)
10	2,2',4,4',5,5'-HexaBDE (BDE-153)
11	2,2',3,4,4',5'-HexaBDE (BDE-138)
12	2,2',3,4,4',5',6-HeptaBDE (BDE-183)
13	2,3,3',4,4',5,6-HeptaBDE (BDE-190)
14	DecaBDE (BDE-209) (12.5 mg/mL)

A more demanding mixture (Table 2a,b) containing 39 of the most common and important congeners at very low concentration could be separated by DB-XLB in about 14 minutes (Figure 2a, b). This is much faster than analysis times typically reported with other columns. Although two of the tetra isomers are very close with this column, they were baseline resolved with DB-35ms. By contrast, there were two co-elutions with the DB-35ms, which were both baseline resolved on DB-XLB. This demonstrates that these two stationary phases are an excellent choice as a pair of confirmation columns. For baseline resolution of all congeners on a single column, as well as for separation of more complex mixtures, a column with more theoretical plates and/or a higher phase ratio may be necessary. Using


a DB-XLB, 30 m × 0.18 mm × 0.18 µm gave complete baseline separation of the tetra isomers, as did a DB-5ms, 60 m × 0.25 mm × 0.25 µm. However, the higher substituted isomers, in particular BDE-209, showed relatively low response. The lower phase ratio results in longer retention times for all congeners. This longer residence time on the column at high temperature may lead to on-column break down of these thermally labile compounds.

Table 2a. PBDE Congeners in Test Mix EO-5113 Elution Order on DB-XLB

2-MonoBDE (#1)	2',3,4-TriBDE (#33)	2,3,4,5,6-PentaBDE (#116)
3-MonoBDE (#2)	2,4,4'-TriBDE (#28)	2,3',4,4',5-PentaBDE (#118)
4-MonoBDE (#3)	3,3',4-TriBDE (#35)	
	3,4,4'-TriBDE (#37)	2,2',4,4',6,6'-HexaBDE(#155)
2,6-DiBDE (#10)		
2,4-DiBDE (#7)	2,4,4',6-TetraBDE (#75)	2,2',3,4,4'-PentaBDE (#85)
3,3'-DiBDE (#11)	2,2',4,5'-TetraBDE (#49)	3,3',4,4',5-PentaBDE (#126)
2,4'-DiBDE (#8)	2,3',4',6-TetraBDE (#71)	
3,4-DiBDE (#12)	2,2',4,4'-TetraBDE (#47)	2,2',4,4',5,6'-HexaBDE(#154)
3,4'-DiBDE (#13)	2,3',4,4'-TetraBDE (#66)	2,2',4,4',5,5'-HexaBDE(#153)
4,4'-DiBDE (#15)	3,3',4,4'-TetraBDE (#77)	2,2',3,4,4',5'-HexaBDE(#138)
		2,3,4,4',5,6-HexaBDE (#166)
2,4',6-TriBDE (#32)	2,2',4,4',6-PentaBDE (#100)	2,2',3,4,4',5',6-HeptaBDE (#183)
2,4,6-TriBDE (#30)	2,3',4,4',6-PentaBDE (#119)	2,2',3,4,4',5,6-HeptaBDE(#181)
2,2',4-TriBDE (#17)	2,2',4,4',5-PentaBDE (#99)	2,3,3',4,4',5,6-HeptaBDE (#190)
2,3',4-TriBDE (#25)		

Table 2b. PBDE Congeners in Test Mix EO-5113 Elution Order on DB-35ms

3-MonoBDE (#2)	2,4,4'-TriBDE (#28)	2,3',4,4',5-PentaBDE (#118)
2-MonoBDE (#1)	2',3,4-TriBDE (#33)	2,3,4,5,6-PentaBDE (#116)
4-MonoBDE (#3)	3,3',4-TriBDE (#35)	
	3,4,4'-TriBDE (#37)	2,2',4,4',6,6'-HexaBDE(#155)
2,6-DiBDE (#10)		
2,4-DiBDE (#7)	2,2',4,5'-TetraBDE (#49)	3,3',4,4',5-PentaBDE (#126)
3,3'-DiBDE (#11)	2,4,4',6-TetraBDE (#75)	2,2',3,4,4'-PentaBDE (#85)
2,4'-DiBDE (#8)	2,3',4',6-TetraBDE (#71)	
3,4-DiBDE (#12)	2,2',4,4'-TetraBDE (#47)	2,2',4,4',5,6'-HexaBDE(#154)
3,4'-DiBDE (#13)	2,3',4,4'-TetraBDE (#66)	2,2',4,4',5,5'-HexaBDE(#153)
4,4'-DiBDE (#15)	3,3',4,4'-TetraBDE (#77)	2,2',3,4,4',5'-HexaBDE(#138)
		2,3,4,4',5,6-HexaBDE (#166)
2,4',6-TriBDE (#32)	2,2',4,4',6-PentaBDE (#100)	2,2',3,4,4',5',6-HeptaBDE (#183)
2,4,6-TriBDE (#30)	2,3',4,4',6-PentaBDE (#119)	2,2',3,4,4',5,6-HeptaBDE(#181)
2,3',4-TriBDE (#25)	2,2',4,4',5-PentaBDE (#99)	2,3,3',4,4',5,6-HeptaBDE (#190)
2,2',4-TriBDE (#17)		




Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m $\times$ 0.25 mm id $\times$ 0.1 μ m (Agilent Technologies, part number 122-1231)
 Carrier gas: Helium at 38 cm/s at 100 $^{\circ}$ C (1.2 mL/min), constant flow mode
 Oven: 100 $^{\circ}$ C for 1 min; 100 $^{\circ}$ C to 340 $^{\circ}$ C at 20 $^{\circ}$ C/min, 340 $^{\circ}$ C for 12 min
 Injector: Cool-on-column, oven-track mode, 0.5 μ L
 Detector: Agilent 5973 MSD; transfer line at 325 $^{\circ}$ C, EI
 SIM: (Ions monitored: 231.8, 248.0, 327.9, 398.6, 400.5, 405.8, 845.7, 563.6, 643.5, 721.4, 799.3)

Note:

Mono-through octa-substituted homologs detected using selected ion monitoring (SIM) at the most intense of the M^{+} , $(M+2)^{+}$, $(M+4)^{+}$, $(M+6)^{+}$, or $(M+8)^{+}$ masses, with a data acquisition rate of approximately 3 cycles/second. Monitoring the molecular ion was not possible above octa-substituted PBDEs due to the limitations of the mass range of the Agilent 5973 instrument (maximum of m/z 800). Decabromodiphenylether was detected by monitoring significant fragments of high abundance: m/z 231.8, 398.6, 400.5, and 799.3.

Figure 2a. Gas chromatography/mass spectrometry (GC/MS) of PBDE congener mixture (EO-5113).




Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m $\times$ 0.25 mm id $\times$ 0.1 μ m (Agilent Technologies, part number 122-1231)
 Carrier gas: Helium at 38 cm/s at 100 $^{\circ}$ C (1.2 mL/min), constant flow mode
 Oven: 100 $^{\circ}$ C for 1 min; 100 $^{\circ}$ C to 340 $^{\circ}$ C at 20 $^{\circ}$ C/min, 340 $^{\circ}$ C for 12 min
 Injector: Cool-on-column, oven-track mode, 0.5 μ L
 Detector: Agilent 5973 MSD; transfer line at 325 $^{\circ}$ C, EI
 SIM: (Ions monitored: 231.8, 248.0, 327.9, 398.6, 400.5, 405.8, 845.7, 563.6, 643.5, 721.4, 799.3)

Note:

Mono-through octa-substituted homologs detected using SIM at the most intense of the M^+ , $(M+2)^+$, $(M+4)^+$, $(M+6)^+$, or $(M+8)^+$ masses, with a data acquisition rate of approximately 3 cycles/second. Monitoring the molecular ion was not possible above octa-substituted PBDEs due to the limitations of the mass range of the 5973 instrument (maximum of m/z 800). Decabromodiphenylether was detected by monitoring significant fragments of high abundance: m/z 231.8, 398.6, 400.5, and 799.3.

Figure 2b. GC/MS of PBDE congener mixture (EO-5113).

Figure 3 shows a chromatogram of a commercial flame retardant mixture. While commercial samples are typically classified as “penta”, “octa”, or “deca”, they contain other congeners as well. Again, the congeners in this mixture are well resolved, and the run time is very short (13 minutes).




Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m $\times$ 0.25 mm id $\times$ 0.1 μ m (Agilent Technologies, part number 122-1231)
 Carrier gas: Helium at 38 cm/s at 100 $^{\circ}$ C (1.2 mL/min), constant flow mode
 Oven: 100 $^{\circ}$ C for 1 min; 100 $^{\circ}$ C to 340 $^{\circ}$ C at 20 $^{\circ}$ C/min, 34 $^{\circ}$ C for 12 min
 Injector: Cool-on-column, oven-track mode, 0.5 μ L
 Detector: Agilent 5973 MSD; transfer line at 325 $^{\circ}$ C, EI
 SIM: (Ions monitored: 231.8, 248.0, 327.9, 398.6, 400.5, 405.8, 845.7, 563.6, 643.5, 721.4, 799.3)

Figure 3. Commercial flame retardant penta DE71-R.


Analysis times could be reduced even further by using hydrogen carrier gas and an Electron Capture Detector (ECD). This combination allows for faster flow rates, while improving sensitivity and lowering the detection limit. With the same column dimensions as above, run times of around 15 minutes are possible. With a custom-made column (DB-XLB, 15 m $\times$ 0.18 mm id $\times$ 0.07 μ m) the run time was less than 12 minutes (Figure 4), with no signs of degradation of the 209 congener. Break down of the higher congeners was, however, dependent on the run conditions. An inlet

temperature of 250 °C worked best, while the μ ECD gave best results at 300 °C. At higher detector temperature, degradation was noticeable, while lower ECD temperatures resulted in tailing peaks (likely due to cold trapping). As expected, sensitivity for PBDEs with a μ ECD is excellent (Figure 5). In the splitless injection mode, the detection limit under those run conditions for the tri and higher substituted PBDEs was around 100 ppt, with a signal-to-noise ratio of >20. The calibration curve for 2,2',4,4',6-PentaBDE (BDE-100) was linear from 1 ppm to 100 ppt.



Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 15 m $\times$ 0.18 mm id $\times$ 0.07 μ m (Agilent Technologies, custom column)
 Carrier gas: Hydrogen at 72 cm/s at 100 °C (4.0 mL/min), constant flow mode
 Oven: 100 °C for 0.5 min; 100 °C to 300 °C at 30 °C/min, 300 °C for 5 min
 Injector: 250 °C, split 20:1, 1 μ L
 Detector: ECD at 300 °C


Figure 4. GC- μ ECD of PBDE congener mixture (E0-5103).



Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m × 0.25 mm id × 0.1 μm (Agilent Technologies, part number 122-1231)
 Carrier gas: Hydrogen at 72 cm/s at 100 °C (4.0 mL/min), constant flow mode
 Oven: 100 °C for 1 min; 100 °C to 300 °C at 25 °C/min, 300 °C for 10 min
 Injector: 300 °C, splitless, 1 μL
 Detector: ECD at 300 °C

Figure 5. GC-μECD of PBDE mixture EO-5103 at 500 ppt.

The same sensitivity could be achieved with GC-ICP-MS. Figure 6 shows congener mixture EO-5103 diluted to 10 ppb. Calibration curves of individual congeners from 1 ppm to 1 ppb were linear ($R^2 = 1.000$), and the lower detection limit is calculated at 150 ppt. The system setup conditions for the ICP-MS, such as torch position, may not be fully optimized yet, so detection limits may be even lower.



Instrument: Agilent 6890 Gas Chromatograph with ALS and ChemStation Software
 Column: DB-XLB, 30 m × 0.25 mm id × 0.1 μm (Agilent Technologies, part number 122-1231)
 Carrier Gas: Helium at 36 cm/s at 100 °C (1.5 mL/min), constant flow mode
 Oven: 100 °C for 1 min; 100 °C to 300 °C at 20 °C/min, 320 °C for 13 min
 Injector: 320 °C, splitless, 1 μL
 Detector: Agilent 7500cs ICP-MS, monitoring Br at $m/z = 81$

Figure 6. GC-ICP-MS of PBDE mixture EO-5103 at 10 ppb.

Conclusions

DB-XLB is the column of choice for GC analysis of PBDEs. The high upper temperature limit and very low bleed characteristics of this column make it ideal for this class of large molecules. While the high upper temperature limit allows for fast run times - complete analyses, including BDE-209, can be run in about 20 minutes, the extremely low bleed at those temperatures increases sensitivity, thus providing lower detection limits. The DB-35ms is an excellent secondary column that has the same outstanding bleed and thermal properties as DB-XLB, yet a different selectivity required for a confirmation column. In general, short columns with a high phase ratio (thin film) yield better response for the higher congeners, since the shorter residence times on the column reduce the exposure to high temperatures, therefore reducing on-column break down.

Due to the high bromine content of PBDEs, sensitivity on an ECD is very high. With splitless injection, the lower detection limit that we achieved is approximately 100 ppt. This limit might be pushed even lower with a programmable temperature vaporization (PTV) inlet, where larger injection volumes are possible. However, in real samples, for example, marine wildlife, other halogenated compounds, like PCBs, may be present. Since an ECD cannot distinguish between halogens, it is impossible to determine if a PCB co-elutes with a PBDE, thus quantitation may not be accurate. GC/MS offers secondary confirmation of the identity of the eluted peak, but sensitivity is not as great. In SIM mode, the detection limit for PBDEs is estimated at about 10 ppb. GC-ICP-MS offers both - high sensitivity and ion selectivity. It can be tuned for Cl or Br. Thus, by monitoring for example m/z 81, only PBDE would be detected, and PCB would not interfere with quantitation.

Acknowledgements

Individual PBDE congeners were a generous gift from AccuStandard (New Haven, CT). Special thanks to Mehran Alaei and Ivy D'Sa of the Aquatic Ecosystem Protection Research Branch, National Water Research Institute, Burlington, Canada, for helpful discussions, sharing of data, and providing samples of industrial brominated flame retardants. Thanks also to Harry Prest and Emmett Soffey of Agilent Technologies and Robert Trengrove of Murdoch University for helpful discussions and providing data.

References

1. October 13, 2001, *Science News*, Vol. **160**, No. 15.
2. December 8, 2001, *Science News*, Vol. **160**, No. 22.
3. Andreas Sjödin et al, (1999) *Environmental Health Perspectives*, **107**:643-648.
4. August 4, 2003, *Chemical and Engineering News*, Vol. **81**, No. 31.
5. Karlheinz Ballschmitter et al, (1992) *J. High Res Chrom.*, **15**, 260-270.
6. Mehran Alaei of Environment Canada, personal communication
7. Andreas Sjödin et al, (1998) *Journal of Chromatography A*, **822**, 83-89.
8. J. W. Cochran and G. M. Frame, (1999) *Journal of Chromatography A*, **843**, 323-368.
9. Cameron George, (2001), *Separation Times* Vol. **14**, No. 1.
10. Eberhardt Kuhn et al, Pittcon 2003, 310-14P.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2003

Printed in the USA
September 11, 2003
5989-0094EN



Agilent Technologies



Determination of Polybrominated Diphenylethers (PBDE) in Sediment and Sewage Sludge

Application

Environmental

Authors

Sonia Wanner
Centre d'Analyse et de Recherche (CAR)
76 route du Rhin
F-67441 Illkirch
France

Isabelle Chanel
Agilent Technologies France
Parc Club du Moulin à Vent
33 rue du Docteur Levy
F-69693 Venissieux
France

Abstract

Generally used as flame retardants, polybrominated diphenylethers (PBDE) have become chemicals of significant environmental concern. While little toxicological information is available, PBDEs have been determined to be persistent and bio-accumulative substances, similar to well-known environmental contaminants such as polychlorinated biphenyls (PCBs). Therefore, environmental laboratories are asked to analyze polybrominated diphenylethers (flame retardants) in sediment and sewage sludge. This application note describes the successful separation of all PBDEs, including the most difficult, decabrominated diphenylether. Examples include standards as well as real samples of sewage sludge with quantitative data.

Introduction

With increasing frequency, environmental laboratories are asked to analyze PBDEs (flame retardants) in sediment and sewage sludge. See Figure 1.




Figure 1. Structure of PBDEs.

Brominated flame retardants (BFRs) are a group of chemicals added to many products, including computers, TVs, and household textiles, in order to reduce fire risk. Two substances, decabromodiphenyl ether (DecaBDE) and tetrabromobisphenol A (TBBP-A), account for about 50% of world use of brominated flame retardants. Two other polybrominated diphenyl ethers (PolyBDE) - octabromodiphenyl ether (OctaBDE) and pentabromodiphenyl ether (PentaBDE) - are used commercially, but in much smaller quantities than DecaBDE.

Heating (for example, during manufacture of plastics) and burning of materials containing PBDEs and other BFRs can produce polybrominated



Agilent Technologies

dibenzo-p-dioxins and dibenzofurans, which have similar toxicological effects to chlorinated dioxins. Research has shown that low-level exposure of young mice to PBDEs causes permanent disturbances in behavior, memory, and learning (Eriksson et al., 1998) [1]. PBDEs have also been shown to disrupt the thyroid hormone system in rats and mice; these systems are a crucial part of the development of the brain and body (Darnerud and Thuvander, 1998 [2]; Hallgren and Darnerud, 1998) [3].

The release of these organic pollutants can be revealed by analyses of sewage sludge produced by municipal waste-water treatment plants. Therefore, the European community has given a directive (2000/60/CE) [4] for water to analyze four PBDEs (BDE-99, BDE-100, BDE-205, BDE-209) and is now working on an ISO norm ISO/CD 22032 to analyze eight PBDEs (BDE-47, BDE-99, BDE-100, BDE-153, BDE-154, BDE-183, BDE-205, BDE-209).

This analysis starts with an extraction of brominated diphenyl ethers (BDEs) from the dried sample of sediment or sewage sludge by a solvent (for example, hexane or other solvents suitable to get high extraction rates). The extract is cleaned, with silica, for example, if necessary. After concentration, the BDEs are separated by capillary gas chromatography (GC) and detected with a suitable system. A calibration over the total procedure using an internal standard (ISTD) mix is used to calculate the concentration in the sample.

When analyzing PBDE with GC, a number of problems arise: [5]

- Adsorption to glass surfaces
- Discrimination of high molecular weight compounds

- Degradation of the heavier congeners
- Irreproducible results
- Disappearing peaks

This application note gives analysts the necessary tools to attempt low-level detection of PBDE by gas chromatography/mass spectrometry (GC/MS).

Materials and Methods

Samples

All sewage sludge and sediment samples were provided by municipal waste-water treatment plants. Ten grams of sediment or 1 g of sewage sludge is liquid extracted. The extract is cleaned on silica and the clean extract is concentrated in 1-mL hexane prior to GC analysis.

Standards and ISTDs

The project for the European norm 22032 (2000/60/CE) is requesting analysis of four PBDE (BDE-99, BDE-100, BDE-205 and BDE-209) and recommends TetraBDE (BDE-77) as ISTD. (See Table 1.) These standards were purchased commercially and were of the highest grade available. A test mixture of pentaBDE (BDE-99, BDE-100), octaBDE (BDE-205), and decaBDE (BDE-209) was used for the evaluation in order to obtain a GC analysis with little or no discrimination. BDE-77 was used as ISTD. Standard solutions containing 0.01; 0.05; 0.1; 0.2; 0.25; 0.5 ng/ μ L of pentaBDE, 0.5; 1; 2; 3; 4; ng/ μ L of decaBDE and octaBDE, and 0.2 ng/ μ L of ISTD were prepared in hexane.

Table 1. Selected BDEs

Name	Formula	Abbreviation	Molar mass g/mol
3,3',4,4'-tetraBDE	C ₁₂ H ₆ Br ₄ O	BDE-77	481.715
2,2',4,4',5-pentaBDE	C ₁₂ H ₅ Br ₅ O	BDE-99	564.6911
2,2',4,4',6-pentaBDE	C ₁₂ H ₅ Br ₅ O	BDE-100	564.6911
2,3,3',4,4',5,5',6-octaBDE	C ₁₂ H ₂ Br ₈ O	BDE-205	801.3804
DecaBDE	C ₁₂ Br ₁₀ O	BDE-209	959.1714

GC Conditions

The selection of column and injection parameters is of great importance for the GC analysis of PBDE, especially for the high molecular weight congeners. See Table 2.

The temperature of the GC is of great importance since some congeners decompose at temperatures just above 300 °C. Thermal degradation is a function of temperature and time; thus, by choosing a column with as little retention for the BDE congeners as possible and shortening the column to the minimum length required for the separation, thermal degradation can be minimized. In addition, pulsed injection allows shorter injection time and also helps to minimize risk of thermal degradation.

A pulsed splitless injection and a DB-1 30 m, 0.32 mm, thin film, 0.1 µm, really minimizes the time each PDBE stays in both the injector and in the column and avoids degradation.

Table 2. Optimized Run Conditions

Column:	DB-1
Part number:	123-1031
Length:	30 m
Diameter:	0.32 mm
Film thickness:	0.1 µm
Carrier:	Helium at 58 cm/s Flow rate 2.5 mL/min
Injector:	2 µL Pulsed splitless at 250 °C
Oven:	60 °C for 2 minutes 60 °C–200 °C at 10 °C/min 200 °C for 2 minutes 200 °C–300 °C at 20 °C/min 300 °C for 25 minutes
Detector	MS
Agilent 5973 inert MSD	
SIM mode	Group 1 / 3 min / <i>m/z</i> 486; 484; 326 Group 2 / 20 min / <i>m/z</i> 406; 564; 566 Group 3 / 24 min / <i>m/z</i> 642; 644; 562 Group 4 / 28 min / <i>m/z</i> 799; 797
Quad temperature	150 °C
Source temperature	230 °C
Transfer line temperature	300 °C

Results and Discussion

The chromatograms (Figures 2 and 3) show very good peak shapes for each PBDE and a high response for the most critical decaBDE (BDE-209) (see Figure 4) using the optimized run conditions listed in Table 2.




Figure 2. Total Ion Chromatogram (TIC) of a standard mixture at 2–20 ng/μL
1–2: pentaBDE
3–9: octaBDE
10: decaBDE




Figure 3. Selected Extracted Ion Chromatograms (EICs) of a standard mixture at 0.5–5 ng/μL.




Figure 4. EIC of BDE-209 in a standard mixture at 5 ng/μL.

In order to have a precise quantitation, five point calibration curves from 0.01 to 0.25 ng/μL for pentaBDE and from 0.5 to 4 ng/μL of octa and decaBDE were achieved with ISTD BDE-77 at 0.2 ng/μL. (See Figure 5.) For all components, the R^2 values range from 0.996 to 1, meeting the AFNOR requirements for valid quantitation (See Table 3).

Table 3. Calibration Curve Summary Using Optimized Analysis Conditions with GC/MS

Compound	Calibration range (ng/μL)	Target ion m/z	Qualifier ion m/z	R^2 value
BDE-77	<i>ISTD-0.2</i>	486.0	326.0	ISTD
BDE-99	<i>0.01-0.25</i>	405.8	563.6	1
BDE-100	<i>0.01-0.25</i>	405.8	563.6	1
BDE-205	<i>0.5-4</i>	641.6	643.6	0.990
BDE-209	<i>0.5-4</i>	799.4	797.4	0.996




Figure 5. Calibration curve for decaBDE (BDE-209) by GC/MS.

Concerning the limit of detection (LOD), the lower level at 1 µg/kg (10 µg/kg for sewage sludge\) for pentaBDE and 50 µg/kg (500 µg/kg for sewage sludge) for octaBDE and decaBDE in sediment, which is 10 pg/µL of pentaBDE or 0.5 ng/µL of octa and decaBDE in solution, is easily achieved. This is the case even for decaBDE because a very good signal-to-noise ratio was achieved, as shown in Figure 6.




Figure 6. EIC of BDE-209 in a standard mixture at 0.5 ng/µL, which is the required LOD 50 µg/kg of sediment.

Real sewage sludge samples were analyzed using the run conditions listed in Table 2. Figure 7 shows one example. The EICs of the different PDBE show that only one pentaBDE and the decaBDE are present in this sample, and they were quantified in a quantitation report showed on Table 4.




Figure 7. Overlaid EICs for BDE-77, 99, and 209 from sewage sludge.

Table 4. Quantitation Report of Real Sewage Sludge

ISTDs	RT	QIon	Response	Conc units	Dev(min)
BDE 77	19.43	486	823207	0.20 ng/μL	0.02
Target compounds					Qvalue
BDE 100	20.14	406	22687	0.0072 ng/μL	11
BDE 99	20.48	406	107372	0.0405 ng/μL	87
BDE 205	23.91	642	17336	0.3417 ng/μL	57
BDE 209	28.31	799	64526	5.2530 ng/μL	90

Summary

By combining the highly inert thin film DB-1 with the Agilent 6890 gas chromatograph and the Agilent 5973 inert MSD, laboratories can achieve accurate quantitation of PBDE in sediments and sewage sludge.

References

1. P. Eriksson, E. Jakobsson, and A. Fredriksson, Developmental neurotoxicity of brominated flame retardants, polybrominated diphenyl ethers and tetrabromo-bis-phenol A. (1998) *Organohalogen Compounds*, **35**: 375-377.
2. S. Hallgren and P.O. Darnerud, Effects of polybrominated diphenyl ethers (PBDEs), polychlorinated biphenyls, (PCBs) and chlorinated paraffins (CPs) on thyroid hormone levels and enzyme activities in rats. (1998) *Organohalogen Compounds*, **35**: 391-394.
3. P.O. Darnerud and A. Thuvander, Studies on immunological effects of polybrominated diphenyl ether (PBDE) and polychlorinated biphenyl (PCB) exposure in rats and mice. (1998) *Organohalogen Compounds*, **35**: 415-418.
4. European framework directive on water policy N° (2000/60/CE)
5. E. Kuhn, J. Ellis, and S. Wilbur, GC Analysis of Polybrominated Flame Retardants, Agilent Technologies publication 5989-0094EN www.agilent.com/chem

Acknowledgements

Dominique Eisenblaetter (CAR, Illkirch) and Bruno Schnepf (CARSO, Lyon) are acknowledged for supporting the partnership with Agilent Technologies France. Jean-Paul Chauve (Agilent Technologies France) and Eberhardt Kuhn (Agilent Technologies USA) are acknowledged for their technical support.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
June 4, 2004
5989-1110EN



Agilent Technologies



Fast USEPA 8270 Semivolatiles Analysis Using the 6890/5973 inert GC/MSD with Performance Electronics

Application

Environmental Analysis

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of semivolatiles using EPA Method 8270 presents challenges due to the simultaneous measurement of acids, bases, and neutrals over a wide concentration range. Due to productivity demands, laboratories want to run faster while maintaining linearity and sensitivity for even the most active compounds. The 6890/5973 inert GC/MSD system with Performance Electronics is designed to meet the criteria for fast analysis, while minimizing activity and maintaining linearity.

Introduction

USEPA Method 8270 for semivolatiles analysis is used to concurrently measure a mixture of acids, bases, and neutrals. Most laboratories analyze for 70–100 compounds with a chromatographic run time of 25–40 min. Laboratories want to reduce this run time for productivity increases. The calibration range required for the analysis varies

depending on a particular laboratory's statement of work (SOW). Historically, a range of 20–160 ng has been used. With the increased sensitivity of newer gas chromatograph/mass spectrometer (GC/MS) systems, laboratories are moving toward lower minimum detection limits (MDLs) and pushing the calibration range down to 1 ng.

The Agilent 6890/5973 *inert* GC/MSD (Gas Chromatograph/Mass Selective Detector) system with Performance Electronics was designed to meet the demand for faster runs and lower MDLs. Faster scan rates without loss of signal are now possible. This allows the use of smaller diameter columns, such as 0.18-mm id, resulting in shorter runs while maintaining sufficient data points across narrower chromatographic peaks.

The inert source allows for less material injected onto the column while maintaining mass spectrometer performance. Injection volume, therefore, can be matched to the 0.18-mm column. Performance comparisons using the inert source were published previously [1, 2].

This application note will demonstrate the use of the Agilent 6890/5973 *inert* with Performance Electronics for USEPA Method 8270. Smaller id columns with faster scan rates yield run times of 15 min while meeting Method 8270 criteria.



Agilent Technologies

Experimental

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized.

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet	EPC Split/Splitless		
Mode	Pulsed splitless, 0.5 µL injection		
Inlet temp	250 °C		
Pressure	21.48 psi		
Pulse pres	40.0 psi		
Pulse time	0.20 min		
Purge flow	50.0 mL/min		
Purge time	1.00 min		
Total flow	54.0 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet Liner	Agilent splitless, single taper, 4-mm id, p/n 5181-3316		
Oven	240 V		
Oven ramp	°C/min	Next °C	Hold min
Initial		55	1.00
Ramp 1	25	100	0.00
Ramp 2	30	280	0.00
Ramp 3	25	320	4.60
Total run time	15 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies DB-5.625, p/n 121-5622		
Length	20.0 m		
Diameter	0.18 mm		
Film thickness	0.36 µm		
Mode	Constant Flow = 1.0 mL/min		
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		

MSD	Agilent Technologies 5973 <i>inert</i> with Performance Electronics
Drawout lens	6-mm Large Aperture Drawout lens, p/n G2589-20045
Solvent delay	1.90 min
EM voltage	Run at DFTPP tune voltage - 153 V = 1012 V
Low mass	35 amu
High mass	500 amu
Threshold	10
Sampling	1
Scans/s	5.92
Quad temp	150 °C
Source temp	230 °C
Transfer line temp	280 °C
Emission current	DFTPP tune @ 25 µA

Calibration Standards were obtained from Accu-standard, New Haven, CT, (p/n M-8270-IS-WL-0.25x to 10x). They contain 74 target compounds at nine concentration levels with six ISTDs at 40 ppm.

Pulsed splitless injection was used to minimize residence times of analytes in the liner, thereby reducing loss of active compounds. The column flow rate alone, without using a pulsed injection, would take too long to sweep the 900-µL liner volume.

The inlet liner (p/n 5181-3316) is the most commonly used liner for Method 8270 analysis. It does not contain glass wool which would contribute to active compound degradation. Other liners can be used and a detailed discussion of these can be found in Reference 1.

The Agilent 6890 240 V oven was necessary for the 25 °C/min Ramp 3 used.

A 120 V oven will achieve 20 °C/min at higher temperatures and could be used, resulting in slightly longer run times.

The DB-5.625 column was recently introduced in the dimensions listed. A 0.5-µL injection volume is well suited to this column. The excellent resolution from this column allows a higher than normal initial temperature, 55 °C vs 40 °C. This higher temperature shortens cool-down time by more

than 5 min, resulting in productivity increases for the laboratory. Benzo[b]fluoranthene and benzo[k]fluoranthene met Method 8270 resolution requirements at the 80-ppm calibration level and lower, using the operating parameters in Table 1.

Previous work has shown improved linearity across a wide calibration range using a 6-mm drawout lens instead of the standard 3-mm lens [1]. Although not shown here, that comparison was repeated on this Performance Electronics system and is still valid. The 6-mm lens is also included in Agilent Kit p/n G2860A.

The 5973 *inert* was tuned using the automatic DF TPP target tune. The following steps were taken before executing DF TPP tune to insure that Method 8270 DF TPP criteria were met on injection.

1. Using the Tune Wizard, set the Mass 50 Target Abundance to 1.3% and the Emission Current to 25, as shown in Figures 1a–1f.
2. Edit the tuning macro as follows:
 - a Copy atune73.mac from the MSDChem\msexe folder.
 - b Paste the copy of atune73.mac into the MSDChem\msexe folder. The file name should be Copy of atune73.mac. This preserves an original copy of the file.
 - c Open atune73.mac in Notepad. Refer to Figures 2a–2h.
 - d Click Edit>Find and type samples in the Find What box.
 - e Click Find Next.
 - f Change the samples value from 3 to 1.
 - g Change the averages value from 3 to 6.
 - h Save the file and Close Notepad.




Figure 1a. Starting the Tune Wizard.




Figure 1b. Accept these masses.




Figure 1c. Set Mass 50 target to 1.3.



Figure 1d. Set Emission Current to 25.



Figure 1e. Accept Standard.




Figure 1f. Type in DFTPP.U if not present and click Select to save.




Figure 2a. Select File>Open in Notepad.




Figure 2b. Select atune.73.mac and click Open.




Figure 2c. Select Edit>Find.



Figure 2d. Type samples into the Find What box, then click Find Next.




Figure 2g. Select File>Save (do not use Save as).




Figure 2e. Results of Find samples.




Figure 2h. Select File>Exit to close Notepad.



Figure 2f. Change samples from 3 to 1 and averages from 3 to 6.

Previous work has shown improved linearity across a wide calibration range using a 25- μ A emission current instead of the 35- μ A default. The tuning macro was changed so that the sampling rate during tuning matched the sampling rate during data acquisition. The system was tuned at 2¹ and data were collected at 2¹. These changes resulted in reliably passing Method 8270 criteria on injection of DFTPP.

Remember that the tune macro changes are also reflected if an Autotune is done. The copy of atune73.mac contains the macro without the changes.

The sampling rate for data acquisition was changed from the usual 2² to 2¹, while preserving sufficient sensitivity. The resultant 5.92 scans/s typically yield 10 data points across the peaks that have a width of 1.8 s.

Results

The system was calibrated at nine levels: 1, 2, 5, 20, 50, 80, 120, 160, and 200-ppm. The TIC (Total Ion Chromatogram) for the 5-ppm level is shown in Figure 3. The peak shape is excellent and the

run time is less than 15 min. The benzo[b]fluoranthene and benzo[k]fluoranthene resolution can be seen at about 11.4 min. Each calibration level contained 74 compounds together with 6 ISTDs at 40 ppm.

The RRF (relative response factor) was calculated automatically for each compound by the GC/MSD ChemStation software. Linearity was determined by calculating the %RSD (percent relative standard deviation) of the RRFs across the calibration range for each compound. This is also done automatically by the software in conjunction with Excel.

USEPA Method 8270D specifies criteria for suitable RRFs and %RSD. Minimum system performance is determined by four active compounds, the SPCCs (system performance check compounds) and is measured by the average RRF.

Table 2 lists the Method 8270D SPCC criteria and the performance of the 5973 inert. The 5973 *inert* data easily exceeds the 8270D criteria, and are very good considering the low end of the calibration range. This performance margin allows more samples to be run before system maintenance is necessary.




Figure 3. TIC for 5 ppm Method 8270 Semivolatiles.

Table 2. SPCCs and Comparison of Average RRF

	8270D Criteria	1–200 ng 5973 <i>inert</i>
N-Nitroso-di-n-propyl amine	0.050	0.963
Hexachlorocyclopentadiene	0.050	0.216
2,4-Dinitrophenol	0.050	0.133
4-Nitrophenol	0.050	0.139

Linearity is shown in Table 3. Method 8270D specifies that this group of Calibration Check Compounds (CCCs) meet a 30% RSD criteria. The %RSD is calculated across the RRFs determined at each calibration level. All CCCs pass criteria using a calibration range of 2–200 ppm. Across a 1–200 ppm range, pentachlorophenol does not pass due to its known activity.

Table 3. CCC %RSD of RRFs from 1–200 ppm and 2–200 ppm

	1–200	2–200
Phenol	6	6
1,4-Dichlorobenzene	7	6
2-Nitrophenol	6	6
2,4-Dichlorophenol	5	4
Hexachlorobutadiene	6	4
4-Chloro-3-methylphenol	5	5
2,4,6-Trichlorophenol	12	10
Acenaphthene	11	10
Diphenylamine	8	8
Pentachlorophenol	36	24
Fluoranthene	8	7
Benzo[a]pyrene	3	3

The excellent system linearity shown here is due to many factors including tuning, the large aperture drawout, and the Performance Electronics. The new electronics allow using a scan rate of 2¹, while maximizing sensitivity. This improved signal/noise together with more data points across a peak yields easier and more reproducible peak integration.

Conclusions

The Agilent 6890/5973 *inert* with Performance Electronics shows improved sensitivity at faster scan rates. The faster scan rates allow using 0.18 mm id columns for faster runs and shorter cool-down times. Analysis of 74 analytes and 6 ISTDs can be accomplished in less than 15 min. EPA Method 8270D tune criteria can be routinely achieved. SPCC performance and CCC linearity can be met over a wider calibration range than that historically used. Productivity increases are possible through shorter runs, faster cool-down, easier peak integration, and use of a wider calibration range.

References

1. M. Szelewski, B. Wilson and P. Perkins, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270", Agilent Technologies, publication 5988-3072EN, www.agilent.com/chem.
2. M. Szelewski, "Fast Semivolatiles Analysis using the Agilent Technologies 6890/5973 *inert* GC/MSD", Agilent Technologies, publication 5989-0207EN, www.agilent.com/chem.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
August 4, 2004
5989-1510EN



Agilent Technologies



Addressing the Challenges of Analyzing Trace Perfluorooctanoic Acid (PFOA) and Perfluorooctane Sulfonate (PFOS) Using LC/QQQ

Application

Food, Environmental

Authors

Robert D. Voyksner
LCMS Limited
PO Box 27228
Raleigh, NC 27611-7228
USA

Chin-Kai Meng
Agilent Technologies
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

An approach to the difficult task of quantifying trace quantities of perfluorooctanoic acid (PFOA) and perfluorooctane sulfonate (PFOS) in complex matrix was developed using liquid chromatography and tandem mass spectrometry (LC/MS/MS). The technique uses isotopically labeled analytes for accurate quantitation (0.4 to 400 pg on column). It is important to recognize that if using the linear chain sample as standard for calibration, the quantitation results of real-world samples (branched and linear isomers mixed) will be off by as much as 40%.

Introduction

Perfluorooctanoic acid (PFOA) is an industrial surfactant and a necessary processing aid in the manufacture of fluoropolymers [1]. Fluoropolymers have many valuable properties, including fire resistance and the ability to repel oil, stains, grease

and water. One of the most common uses of PFOA is for processing polytetrafluoroethylene (PTFE), most widely known as Teflon®. PFOA is also a by-product from direct and indirect contact with food packaging (for example, microwave-popcorn bags, bags for muffins or french fries, pizza box liners, boxes for hamburgers, and sandwich wrappers), and in the fabrication of water- and stain-resistant clothes.

Perfluorooctanesulfonic acid (PFOS) is usually used as the sodium or potassium salt and is referred to as perfluorooctane sulfonate. See Figure 1.




Figure 1. Chemical structures for PFOA and PFOS. Note that both have C8 chains.



Agilent Technologies

Analytical Methodology for PFOA/PFOS

- LC/MS/MS is the preferred detection methodology due to its high sensitivity and specificity in complex matrices.
- Multiple reaction monitoring (MRM) is used to quantitate, using two or more product ions for confirmation.
- The detection limit is typically in the range 1 to 100 pg/mL (ppt), requiring high-sensitivity detection.
- On-column or off-line solid-phase extraction (SPE) and concentration are needed to achieve low-level detection (1 pg/mL).

Measuring PFOS and PFOA

Issue 1: *What transitions should be used to give the best accuracy when quantifying with a linear standard?*

Quantification of PFOS and PFOA is usually based on a linear standard, but actual samples show a series of branched isomers together with the linear isomer. The ratio of these isomers varies based upon biodegradation and industrial processes in their formation; therefore, it is unlikely that a standard can be formulated to mimic the actual sample. The relative intensities of the MRM transitions will vary based upon branching, making some transitions better than others. Branching impacts ionization efficiency and CID energy; therefore, it affects the accuracy of analytical measurement [2].

Issue 2: *Can isotopically labeled standards in matrix be used to measure nonlabeled PFOS and PFOA?*

Most biological and environmental matrices have background levels of PFOS and PFOA; although matrix-matched calibrations are providing good results, the accuracy can be enhanced. The method of standard additions is a protocol to address this issue, but it adds several additional injections to the analysis. Matrix may have varying amount of background. Standard addition is not practical in analyzing many different matrices. Solvent calibrations do not correct for matrix effects.

Experimental

Sample Prep

- All solvent standards were prepared in methanol.

- Plasma extracts were prepared by acetonitrile precipitation and centrifuging, with the upper layer taken and spiked with known concentrations of PFOA or PFOS.

LC

- Agilent 1200 Rapid Resolution LC system
- ZORBAX Eclipse Plus C18 Rapid Resolution HT column 2.1 cm × 50 mm, 1.8-μm particles (P/N 959741-902)
- 20-μL injection, 0.4 mL/min column flow
- 0 to 100% B in 10 min, A = water with 2 mM ammonium acetate; B = MeOH

MS/MS

- Agilent QQQ
- Negative-ion detection
- 3500 V_{cap}, drying gas 9.5 L/min at 350 °C, nebulizer 45 psi
- Fragmentor voltages, collision energy (CE), and ion transitions are experimentally determined

Multiple Reaction Monitoring (MRM)

Figure 2 displays a cross-section of the Agilent 6410 QQQ above a hypothetical sequence of spectra characteristic of ion transitions within the instrument.

The ions are generated in the source shown at the far left of the figure. The precursor ion of interest is then selected from this mixture and isolated through the Q1 quadrupole, which acts as a mass filter. This is similar to selected ion monitoring (SIM). After Q1, characteristic fragments that are specific to the structure of the precursor ion are generated in the collision cell (Q2, although not a quadrupole). By using the Q3 quadrupole, these fragments are then selected for measurement at the detector. This is a selective form of collision-induced dissociation (CID), known as tandem MS/MS. By setting Q3 to a specific fragment ion existing in the collision cell, the chemical or background noise is almost totally eliminated from the analyte signal, therefore, significantly increasing the signal-to-noise ratio. Ion 210 is called the precursor ion and ions 158 and 191 are product ions. Each transition (210→191 or 210→158) is a reaction for a particular target. Typically, the QQQ is used to monitor multiple analytes or mass transitions, therefore, the term MRM. The 158 could be considered the quantitation ion, because it is the




Figure 2. A cross-section of the Agilent 6410 QQQ above a sequence of spectra characteristic of ion transitions within the instrument for a hypothetical sample (*not* PFOA or PFOS). Note that the final spectrum is very clean, containing only the desired target ions. (HED = high-energy dynode electron multiplier)

most intense, and 191 could be used for confirmation by using the area ratio of the 191 qualifier to the 158 quantifier ion as a criterion for confirmation. With MRM, most chemical noise is eliminated in Q1, and again in Q3, allowing us to get ppt detection.

The fragmentor is the voltage at the exit end of the glass capillary where the pressure is about 1 mTorr. Fragmentor and collision energies need to be optimized. A fragmentor that is too small won't have enough force to push ions through the gas. A fragmentor that is too high can cause CID of precursor ions in the vacuum prior to mass analysis, thereby reducing sensitivity. The actual voltage used is compound-, mass-, and charge-dependent, and therefore needs to be optimized to get the best sensitivity. The CE in the collision cell needs to be optimized in order to generate the most intense product ions representative of each target compound. Collision cell voltage will depend on the bond strength, the molecular weight of the compound, and the path by which the ion is formed (directly from the precursor ion or through a series of sequential intermediates). Typically each product ion will exhibit a preferential collision energy that results in the best signal abundance.

The experimental operations required to arrive at optimal conditions are exemplified by the series of experiments shown in Figures 3 to 5.

Optimization of the fragmentor voltages for the $[M-H]^-$ ions of PFOA (m/z 413) and PFOS (m/z 499) are shown in Figure 3.

Note that there is little signal detected for PFOA at the optimal fragmentor voltage for PFOS (200 V). Ions 413 and 499 are called precursor ions. PFOA is relatively fragile; its precursor signal drops off at 160 V. PFOS shows that it is harder than PFOA to break apart; the best fragmentor voltage for PFOS is 200 V.

The appropriate collision energies for product ions m/z 369 $[M-CO_2H]^-$ and m/z 169 $[C_3F_7]^-$ are experimentally determined and used to quantify PFOA. See Figure 4.

In each case the collision energy producing the most intense peak for each ion is chosen for the analysis. PFOA takes little collision energy to break into ion m/z 369 (6 V for highest intensity).




Figure 3. Determination of optimal fragmentor voltage using sequential plots of signal intensity versus applied voltage.

To maximize the intensity of the ion at m/z 169, the collision energy needs to go to 16 V.

The QQQ software can switch collision energies very rapidly. So in a method, the optimal collision voltage can be selected for each ion transition.

In the same manner, the appropriate collision energies for PFOS product ions at m/z 169, 99, and 80 are experimentally determined and used for its quantitation. The optimal collision energies for the three ion transitions are 45, 50, and 70 V. See Figure 5.




Figure 4. Signal intensity as a function of collision energy for PFOA product ions m/z 369 $[M-CO_2H]^-$ and m/z 169 $[C_3F_7]^+$.

Notice the big difference in collision energy between PFOA (6 to 16 V) and PFOS (45 to 70 V). We have seen from fragmentor optimization that PFOA is relatively fragile compared to PFOS, in which the optimum fragmentor voltages are 120 and 200 V for PFOA and PFOS, respectively. The CE reinforces that aspect.

Example calibration curves for the specified product ions used to quantitate PFOA and PFOS are shown in Figure 6. The analyst can also sum the intensities of these MRM transitions to get a calibration curve.

These five ion transitions exhibit linear correlation coefficients > 0.998, and are good for quantitation over three orders of magnitude. Notice that the lowest amount on column is 0.4 pg.

Regarding issue 1: *What transitions should be used to give the best accuracy when quantifying with a linear standard?*

This is addressed using Figures 7 to 9.

Figure 7 exhibits chromatograms from these representative transitions for PFOA and PFOS for the linear standard and samples containing branches (10-min gradient).






Figure 5. Signal intensity as a function of collision energy for PFOS product ions at m/z 169, 99, and 80.

PFOA



PFOS



Concentration range 0.02 to 20 ng/mL (0.4 to 400 pg injected on column)

Figure 6. Calibration curves for the product ions used to measure PFOA and PFOS.

Real-world samples have been detected with branched isomers due to manufacturing processes, metabolism, and degradation processes. The top chromatogram of Figure 7 shows only linear chain compounds from a standard. The bottom chromatogram is an actual sample from the environment. It shows additional peaks (shoulders) in the chromatogram resulting from branched isomers.

We examine those peaks in greater detail in Figure 8.




Figure 7. MRM chromatograms for PFOA and PFOS for both linear and branched samples.

The relative abundances for each MRM transition are dependent on the branching locations and the specific mass transitions. Figure 8 shows a 10-minute run. The chromatography can separate the linear from the branched isomers. The branched sample is typically a C7 chain with a methyl side group (isooctyl isomer). The most interesting part of the analysis is that the ion ratios for the branched compounds are very different from the linear chain compounds [3, 4, 5]. For

linear PFOA, the ion at m/z 169 is about 30 to 40% of ion 369. The branched isomer shows that the ratio changed to 90 to 100%. For linear PFOS, the ion at m/z 99 is about 50% of ion 80 and is 500% of ion 169. The branched isomer shows that ion 99 is only 20 to 30% of ion 80, and 100% of ion 169. This is a cause of concern in terms of quantitation accuracy. This shows that CID stability is very different when the analyte is branched.




Figure 8. MRM chromatograms for PFOA and PFOS for both linear and branched samples.

Another variable in the analysis is the gradient time. Figure 9 compares the effect of a 3-min versus 10-min gradient.

In the fast gradient case (on the right), the branched isomers (dashed lines) are not resolved from the linear isomers (solid lines), resulting in a significant error in the measured value (most noticeable for PFOS).

The two chromatograms on the left are the same two that are shown in Figure 8. They are used here for comparison against the unresolved analytes shown on the right (3-min run). Although we would like to cut down on the analysis time, the branched and linear isomers need to be resolved in order to get accurate quantitation results.

Two samples of the same concentration. One sample is the pure linear isomer; the other sample has a mixture of branched isomers. If their MRM responses (ion ratios) are the same, they would show the same results as when the isomers are not resolved. This example shows that the responses are not the same when the isomers are not resolved. If you add the responses of the side chain analyte and the linear chain analyte of the same sample, the area of each ion transition is different from the pure linear chain analyte ion transition, as seen in the two chromatograms on the right, most apparent is for PFOS. If using the linear chain sample as standard for calibration, the results of real-world samples (branched and linear isomers mixed) will be off by as much as 40% (see Table 1). The quantitation falls apart.




Figure 9. Comparison of PFOA and PFOS MRM chromatograms produced using both 10- and 3-minute gradients. The 3-minute gradient chromatograms are on the right.

The effect of measurement accuracy (*not* ion ratios) of total PFOA and PFOS in branched samples against a linear standard for each MRM transition is shown in Table 1.

Table 1. Measurement Accuracy (Target Is 100%) as Function of Compound, Transition, and Run Time

Compound	MRM transition	Percent response (n = 8)	
		10-min run	3-min run
PFOA	413→369	105.9	108.2
	413→169	96.4	89.4
PFOS	499→169	102.5	112.2
	499→99	75.0	73.3
	499→80	59.3	61.1

The best MRM ions are in bold type. The best results for PFOA can be obtained by averaging the results for the two MRM ions together.

Ion ratios can cause quantitation failure. For PFOA, it does not matter if it's a 3-min run or a 10-min run: the ion 369 transition response is always higher and the ion 169 transition response is always lower. The errors are larger for the 3-min run. The variations are greater for PFOS. In literature, PFOS analysis monitors the ion 80 transition, but it exhibits a large variation. It can be as low as 60%, as seen in Table 1. 499 → 169 is a good transition for quantitation. It is much more accurate, but it is less sensitive compared to 499 → 80 transition.

Regarding issue 2: Can isotopically labeled standards in matrix be used to measure non-labeled PFOS and PFOA?

This is addressed using Figures 10 to 12.

Observations regarding the effect of different matrices on signal responses are shown in Figure 10. The taller trace represents the response of PFOA in methanol. The response is lower as the same amount of PFOA is added into a plasma extract.

The matrix effect (common using electrospray ionization) can lead to signal suppression or enhancement; therefore, matrix-matched calibrations are required for accurate quantitation. Due to varying background levels of PFOS and PFOA in matrix, it may not be feasible to use matrix-matched calibrations for quantitating PFOS or PFOA concentrations in study samples. Also, the method of standard additions is not a practical alternative for many matrices with varying levels of target analytes.

As a practical alternative, measuring PFOA using isotopically labeled matrix-matched standards was examined. Results are shown in Figures 11 and 12.

Figure 11 shows that isotopically labeled standards can provide a good linear calibration curve over the quantitation range of 0.02 to 20 ng/mL (0.4 to 400 pg on column). Excellent linear correlation coefficients (≥ 0.9994) were obtained.





Figure 10. PFOA responses in MeOH and plasma extract at the same concentrations.



Calibration in plasma from 0.02 to 20 ng/mL

Figure 11. Linear correlations for PFOA using two different isotopically labeled calibration standards.




Figure 12. Both isotopically labeled PFOA compounds show good correlation to the unlabeled PFOA. The same transitions for the labeled and native forms of the PFOA were used.

Table 2. Comparison of Different Matrix-Matched Calibrations for Measuring PFOA in Plasma

	Calibration standard	Matrix for calibration	Plasma sample response (Std Dev)
1	PFOA	MeOH	71 (± 33 %)
2	PFOA [1,2- ¹³ C]	Plasma	100.4 (± 3.1 %)
3	PFOA [1,2,3,4- ¹³ C]	Plasma	97.3 (± 5.1 %)

Matrix-matched calibrations using isotopically labeled PFOA work well.

For row 1, the calibration standard used MeOH as the solvent, and the plasma sample exhibited a 71% response due to matrix suppression. Therefore, we cannot use a calibration standard in MeOH to quantitate samples in matrix; the variation can be as large as 30%. Rows 2 and 3 show that if the calibration is done using an isotopically labeled compound in matrix, the actual plasma sample yields accurate results: 100 and 97%.

Conclusions

- The Agilent LC/QQQ is an excellent instrument for quantifying trace target compounds in complex mixtures.
- The best ion transitions for analysis need to be determined experimentally.
- Fragmentor voltages and collision energies require experimental determination and optimization.
- Using MRM in the QQQ helps achieve the lowest detection limits in complex matrices.
- Branched PFOA/PFOS can affect quantitation accuracy as much as 40% unless it is corrected.
- Matrix suppression can cause the quantitation to be off by as much as 30%. Isotopically labeled analytes work well for accurate quantitation in spite of varying background levels of PFOA/PFOS in matrices.

References

1. Perfluorooctanoic Acid (PFOA), USEPA, <http://www.epa.gov/oppt/pfoa/>
2. T. J. Wallington, M. D. Hurley, J. Xia, D. J. Wuebbles, S. Sillman, A. Ito, J. E. Penner, D. A. Ellis, J. Martin, S. A. Mabury, O. J. Nielsen, and M. P. Sulbaek Andersen, "Formation of C₇F₁₅COOH (PFOA) and Other Perfluorocarboxylic Acids

During the Atmospheric Oxidation of 8:2 Fluorotelomer Alcohol," *Environ. Sci. Technol.*, 40 (3), 924–930, 2006

3. Jonathan P. Benskin, Mahmoud Bataineh, and Jonathan W. Martin, "Simultaneous Characterization of Perfluoroalkyl Carboxylate, Sulfonate, and Sulfonamide Isomers by Liquid Chromatography-Tandem Mass Spectrometry," *Anal. Chem.*, 79 (17), 6455–6464, 2007
4. I. Langlois and M. Oehme, "Structural identification of isomers present in technical perfluorooctane sulfonate by tandem mass spectrometry," *Rapid Commun. Mass Spectrom.* 20, 844–850, 2006
5. Amila O. De Silva and Scott A. Mabury, "Isomer Distribution of Perfluorocarboxylates in Human Blood: Potential Correlation to Source," *Environ. Sci. Technol.* 40, 2903–2909, 2006

Acknowledgement

Partial support and the standards for this study were provided by the Environmental Lab of the 3M Company (St Paul, MN).

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
April 23, 2008
5989-7790EN



Agilent Technologies

Femtogram GC/MSD Detection Limits for Environmental Semivolatiles Using a Triple-Axis Detector



Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

The analysis of semivolatiles at very low levels presents challenges due to analyte activity, background contamination, and instrument sensitivity. Method requirements vary worldwide, with the least sensitive specifying 1- μ L injections and full-scan data acquisition. The lowest detection limits can be achieved using a programmable temperature vaporizing (PTV) inlet, trace ion detection (TID), and a triple-axis detector (TAD) with the MSD operating in SIM mode.

Introduction

Low-level semivolatiles analysis is used to concurrently measure a mixture of acids, bases, neutrals, and pesticides in drinking water or source water. Most laboratories analyze for > 100 compounds, with a chromatographic run time of 25 to 40 minutes. Sample extraction is accomplished using liquid-solid extraction (LSE) with C_{18} disks or cartridges. Liquid-liquid extraction with a solvent such as dichloromethane is an alternative technique. Extract injection is typically 1 μ L hot splitless with the MSD operating in full-scan mode, as specified in some commonly used methods such as USEPA Method 525.2 [1].

Sensitivity is an area where laboratories are seeking improved performance; it can be affected by sample preparation, extract volume injected, instrument tuning, signal acquisition, and overall system activity. Sensitivity is also a confusing term, with all of the following used interchangeably: maximum sensitivity, minimum sensitivity, best sensitivity, lowest detection limit, instrument detection limit (IDL), and method detection limit.

Previous publications have focused on activity/linearity, speed, productivity, and large-volume injection [2–5]. Sensitivity is a factor in all of these, and many times is a trade-off.

This application addresses the parameters that affect the IDL, that is, the “sensitivity” of the GC/MSD system. There are statistical ways to calculate the IDL, but these may not answer the questions, “How much can I actually see?” or “What is the lowest amount that will produce a peak I can integrate?”

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized. For the best sensitivity, parameters should be chosen that transfer the maximum amount of analyte onto the column. Furthermore, the entire system must be inert, as sensitivity is almost always lost on active analytes first.

Many analysts associate the use of PTV only with large-volume injection (LVI) in solvent vent mode [4]. LVI will allow lower levels of calibration, but



Agilent Technologies

Table1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 7890A or 6890N			Front Injector	
Inlet	EPC PTV			Sample washes	1
Mode	Splitless			Sample pumps	2
Temperature ramp	°C/min	Next °C	Hold min	Injection volume	2.0 µL
Initial		20	0.05	Syringe size	10 µL
Ramp 1	600	350	0.90	PreInj Solv A washes	0
Ramp 2	10	250	0.00	PreInj Solv B washes	1
Cryo	On			PostInj Solv A washes	3
Cryo use temperature	100 °C			PostInj Solv B washes	2
Cryo timeout	10.00 min (On)			Viscosity delay	0 seconds
Cryo fault	On			Plunger speed	Fast
Pressure	11.40 psi (On)			PreInjection dwell	0 minutes
Purge flow	30.0 mL/min			PostInjection dwell	0 minutes
Purge time	1.50 min			MSD	Agilent Technologies 5975C, Triple-Axis Detector
Total flow	34.4 mL/min			Drawout lens	3 mm standard aperture drawout lens
Gas saver	Off			Solvent delay	4 min
Gas type	Helium			Low mass	45 amu
PTV Liner	Agilent multi-baffle liner, no packing, p/n 5183-2037			High mass	450 amu
Oven	120V			Threshold	0
Oven ramp	°C/min	Next °C	Hold min	Sampling	2
Initial		40	2.50	Quad temp	180 °C
Ramp 1	50	110	0.00	Source temp	300 °C
Ramp 2	10	320	1.10	Transfer line temp	280 °C
Total run time	26 min			Tune type	Autotune
Equilibration time	0.5 min			EMV mode	Gain factor = 1
Oven max temperature	325 °C			MSD-SIM	
Column	Agilent Technologies HP 5 MSi, p/n 19091S-433i			AutoSIM was used to pick ions, groups and switching times	
Length	30.0 m			Number of groups	25
Diameter	0.25 mm			Compounds/group	Varied 1 to 22
Film thickness	0.25 µm			Ions/group	Varied 2 to 45
Mode	Constant flow			Dwell time, msec	Varied 5 to 50
Pressure	11.40 psi			Cycles/peak	Minimum 10
Nominal initial flow	1.4 mL/min			Calibration Standards	
Inlet	Front			Ultra Scientific, North Kingstown, RI. p/n DWK-5252. Four mixtures, co-diluted in dichloromethane, resulting in 108 compounds at 7 concentration levels: 10, 4, 1, 0.4, 0.1, 0.04, and 0.01 ppm. Each level spiked with 3 Internal Standards at 2 ppm and 4 surrogate standards at 2 ppm. Each level then diluted 1:100 in dichloromethane, resulting in 7 concentration levels: 100, 40, 10, 4, 1, 0.4, and 0.1 ppb (pg/µL) with IS/SS at 2 ppb.	
Outlet	MSD				
Outlet pressure	Vacuum				
RTL	System retention time locked to phenanthrene-d10 at 12.700 min				

method development is necessary to optimize recovery of compounds while eliminating the solvent. LVI also injects more matrix and may not improve Signal-to-Noise (S/N) due to chemical noise. The PTV has other operating modes; “cold” splitless mode was used here. Splitless injection into a cold inlet instead of a typical hot splitless inlet offers these advantages:

1. Solvent expansion is minimized; analytes do not travel outside the liner and contact metal surfaces, thereby minimizing degradation.
2. Analytes vaporize at the lowest temperature, also minimizing degradation.

3. Volatile solvent is transferred onto the column first; analyte peak shape is improved for injections of 2 to 5 µL.

Figure 1 shows the PTV temperature and flow programs together with the oven program. The PTV is held at 20 °C, a temperature below the boiling point of the solvent dichloromethane, 39.8 °C, during the fast injection period, 0.05 min. At the end of the injection period, the PTV is rapidly heated to 350 °C, transferring analytes onto the column. At the end of the splitless time, 1.5 min, the inlet is purged at 30 mL/min. The PTV is allowed to cool during the run.




Figure 1. PTV cold splitless temperature and flow programs.

The PTV program ramp can be adjusted and multiple ramps are possible. The PTV inlet liner (p/n 5183-2037) is multi-baffled and deactivated. It does not contain glass wool, which could contribute to active compound degradation. This liner has sufficient capacity to accommodate a 2- to 5- μ L injection volume at fast speed. A 2- μ L injection was used for all data presented here.

The oven program relationship to the PTV parameters is shown in Figure 1. The oven starts at 40 °C and is held there during the injection cycle and splitless transfer of analytes onto the column. The oven then programs rapidly to 110 °C, followed by a slower ramp for compound separation. There is an extra 1 min of oven hold time at 40 °C, which is between 1.5 and 2.5 min. This maintains the retention time locked (RTL) times for analytes while providing room for the injection to be scaled up to LVI, if desired. The 240V oven was used, but a 120V oven can also achieve the ramp rates found in Table 1.

The HP-5MSi column is designed for inertness and is well suited to this method. This is the latest version of the most popular column in environmental laboratories, the HP-5MS. The column was run in constant-flow mode at 1.4 mL/min to maintain peak shape and sensitivity.

The system was RTLocked to phenanthrene-d10 at 12.700 min. The primary benefit of RTL for this analysis is maintaining constant switching times for SIM groups. After clipping the column, a rerun and analysis of the locking standard is all that is needed to restore shifted peak times. Quantitation database and integration events times also do not have to be changed. Additional RTL applications detailing the numerous benefits of RTL are available at www.agilent.com/chem. It is almost impossible to use a method with this many SIM groups without RTL, in a productive laboratory.

The standard 3-mm drawout lens was used for best sensitivity. Previous work has shown improved linearity across a wide calibration range using the optional 6-mm lens [1]. Using the 6-mm lens will show a typical loss of 2 to 5x in the IDL.

The 5975C MSD was equipped with a Triple-Axis Detector (TAD) [6]. The TAD presents several advantages to the user, one of which is, "Although signal is enhanced, neutral noise is substantially reduced through the off-axis design." This increase in S/N for clean samples with minimal chemical noise can help reach a lower IDL. Trace ion detection (TID) was switched on during all data acquisition [7]. TID is a filtering routine to minimize noise and is selectable in the software.

Scan parameters are listed and data were collected in either scan mode or in SIM mode. None of the runs was made in synchronous SIM/scan mode. A sampling rate of 2 was used, as it is typical of most methods on a 250- μ m id column. This sampling rate, with a 45 to 450 mass range, resulted in at least 10 scans across each peak.

AutoSIM setup was used in combination with the scan quantitation database to pick ions, groups, and switching times. The SIM acquisition table from AutoSIM was used directly with only two modifications. Tebuthiuron (ion 156) and tricyclazole (ion 189) are known for poor peak shape. Their ions were manually added to the groups across which the peaks eluted. A target ion plus one qualifier ion were used for all internal (ISTDs) and surrogate standards (SSs). A target ion plus two qualifier ions were used for all other analytes, if they were present in sufficient abundance in the spectra. A minimum of 10 SIM data points were acquired across each peak.

A source temperature of 300 °C was used instead of the typical 230 to 250 °C range. This higher temperature has been used to minimize peak tailing, and therefore improve sensitivity for PAHs [5].

The compound list was taken from USEPA 525 and is typical of the analytes that laboratories worldwide are interested in analyzing at low levels. The USEPA 8270 list was not used, as it is targeted at higher concentrations of compounds in waste samples that contain high levels of matrix and are not comparable here. The best way to improve sensitivity for solids and waste samples is through extract cleanup. The standards were prepared in dichloromethane only for the single component analytes, except disulfoton sulfoxide and disulfoton sulfone, which were not included in the commercially available mixture. Standards were not prepared for multicomponent toxaphene or the Aroclors.

A typical calibration range for low-level semivolatiles is 0.1 to 10 ppm as defined in USEPA 525. Standards were made from 0.01 to 10 ppm, containing 2 ppm of ISTDs and SSs. A dilution of 1:100 of each of these yields a range of 0.1 to 100 ppb, with ISTDs and SSs at 20 ppb, for a lower working range. Atrazine and alachlor are present in two of the stock mixes, so their concentrations are twice that of other analytes. Pentachlorophenol is present at four times the other analyte concentrations, as described in USEPA 525.

Results

The standard solutions from 0.1 to 100 ppb were run in both SIM and scan modes. Data from the 0.1-ppb scan injections showed insufficient response or were too noisy to reproducibly integrate. The SIM data at 0.1 ppb were significantly improved compared to the scan data and could be routinely used. A listing of selected analytes with S/N measured from 1.0 ppb scan runs (2 pg) are shown in Table 2, together with data from 0.1- (0.2-pg) and 1.0-ppb SIM runs. Each value is an average of three acquisitions on one system, using peak-to-peak noise.

Table 2. Signal-to-Noise for Selected Analytes, SIM and Scan Modes

Compound	Ion	pg → RT	0.2	2.0	2.0
			SIM S/N	SIM S/N	Scan S/N
Hexachlorocyclopentadiene	237	7.960	6.3	77	7.5
Trifluralin	264	11.608	4.4	49	7.7
Simazine	201	12.274	1.0	16	2.4
Atrazine	200	12.385	3.1	30	13
Pentachlorophenol	266	12.492	2.4	20	3.7
Chlorothalonil	266	13.146	2.6	26	2.9
Aldrin	66	14.661	1.6	15	1.9
Heptachlor epoxide	353	15.429	6.2	49	3.4
4,4'-DDE	246	16.557	7.0	72	17
Carboxin	143	16.696	2.4	22	4.0
Endrin	263	17.003	2.3	22	4.1
4,4'-DDD	235	17.323	7.5	76	7.5
4,4'-DDT	235	18.000	5.9	60	5.9

There is excellent agreement between the SIM S/N values at the two levels for most compounds. This shows that the responses are real and that the entire system is inert. There is a slight loss of simazine and minimal interference for pentachlorophenol and heptachlor epoxide at the lowest level, 0.2 pg. At the 200 femtogram level, this is no surprise.

The scan S/N at 2.0 pg is lower than SIM, as expected, by 3- to 15-fold. The gains in S/N moving from scan to SIM are related to the dwell time versus the original sampling rate.

Extracted Ion Currents (EICs) from the 1.0-ppb level for both SIM and scan are shown in Figures 2a to 2d. It can clearly be seen that either the SIM or scan signals could be used for quantitation based on S/N and peak shape. Of particular note is the response and very good peak shape for pentachlorophenol, even at an 8-pg full scan.




Figure 2a. Atrazine – Extracted Ion 200, RT 12.350 min.




Figure 2b. Pentachlorophenol – Extracted Ion 266, RT 12.445 min.




Figure 2c. Aldrin – Extracted Ion 66, RT 14.616 min.




Figure 2d. 4,4'-DDT – Extracted Ion 235, RT 18.00 min.

Although linearity is not the focus of this application, it is a measure of inertness, reproducibility, and sensitivity. Linearity can be determined by the percent relative standard deviation (%RSD) of the relative response factor (RRF) for each compound across the calibration range. The %RSD and the

RRF calculations are done automatically by the GC/MSD ChemStation software in conjunction with Excel. There is no correct %RSD, as it is method dependent. The %RSDs of the RRFs for selected compounds are shown in Table 3.

Table 3. Linearity of Selected Analytes


Calibration range pg →	0.2–200 SIM %RSD	2–200 Scan %RSD
Compound		
Dichlorvos	1.9	7.0
Mevinphos	10.1	7.0
2,3-Dichlorobiphenyl	5.3	3.0
Atrazine	14.2	14.5
Pentachlorophenol	6.3	33.0
Anthracene	2.2	3.0
Chlorothalonil	7.6	25.0
Heptachlor epoxide	6.6	13.0
4,4'-DDE	4.5	9.0
4,4'-DDD	7.4	8.0
4,4'-DDT	4.0	5.9

At first glance some of the %RSD values appear high, such as pentachlorophenol (PCP) and chlorothalonil. These are calibrated, however, from 2 to 200 pg in scan mode, which is 50-fold lower than USEPA 525 mandates. The SIM data are calibrated from 0.2 to 200 pg, which is 500-fold

lower and a 10-fold wider range. This demonstrates both inertness and detectability at the femtogram level.

As an additional overall measure of system linearity, the average of all %RSDs was calculated at 8% for SIM data and 13% for scan data. Not all compounds were calibrated to the 0.1-ppb level, as they did not have a signal that could be reliably measured. The phthalates, easily detected at low levels, were excluded from these averages due to common laboratory contamination.

EICs at the 200-femtogram level, from SIM, are shown for six different compounds in Figures 3. All are easily seen and measured against noise. As an analyst's measure of sensitivity, the question from the introduction was "How much can I actually see?" The answer: very low picogram levels for most environmental semivolatiles in scan mode. The IDL using SIM is even lower, in the femtogram range.

**Figure 3. EICs at the 200 femtogram level.**

Conclusions

Traditional semivolatiles methods can be altered to achieve better instrument detection limits. There have been advancements in hardware, such as the Triple-Axis Detector (TAD), that improve sensitivity. Signal handling using Trace Ion Detection (TID) provides better S/N through lower noise. The PTV, used in “cold” splitless mode, maximizes the amount of sample on the column, while vaporizing analytes at the lowest possible temperature. Coupled with an inert column and source, the PTV provides an easy way to improve sensitivity. Methods that require only a target ion and a few qualifier ions for identification can often be changed to SIM from scan, improving S/N by 3- to 50-fold. Combining all of these hardware, software, and operating parameters can result in femtogram instrument detection limits (IDLs) and sensitivity you can use.

References

1. USEPA Method 525.2 is available from different sources listed on www.epa.gov/OGWDW/methods/where.html.
2. M. Szelewski, B. Wilson, and P. Perkins, “Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270,” Agilent Technologies, publication 5988-3072EN.
3. M. Szelewski, “Fast Semivolatiles Analysis Using the Agilent Technologies 6890/5973 inert GC/MSD,” Agilent Technologies, publication 5989-0207EN.
4. M. Szelewski, “Part-per-Trillion Calibration of Semivolatiles Using LVI-PTV-GC/MSD,” Agilent Technologies, publication 5989-6589EN.
5. M. Szelewski, “Synchronous SIM/Scan Low-Level PAH Analysis Using the Agilent Technologies 6890/5975 inert GC/MSD,” Agilent Technologies, publication 5989-4184EN.
6. H. Prest and J. Foote, “The Triple-Axis Detector: Attributes and Operating Advice,” Agilent Technologies, publication 5989-7655EN.
7. R. Roushall and H. Prest, “The 5975C Series MSDs: Method Optimization and Trace Ion Detection,” Agilent Technologies, publication 5989-6425EN.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
April 14, 2008
5989-8342EN



Agilent Technologies

Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W DB-5ms Ultra Inert Column



Application

Environmental

Author

Kenneth Lynam
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent Technologies Inc. has implemented new testing procedures to more effectively evaluate GC column inertness performance. The new testing procedure uses deliberately aggressive probes to thoroughly investigate column inertness quality. The value of using probes such as 1-propionic acid, 4-picoline, and trimethyl phosphate to establish a column inertness baseline is discussed. This baseline inertness profile is then extended to a real-world application example with challenging analytes in the semivolatile sample set. Inertness performance with analytes such as 2,4-dinitrophenol, benzoic acid, and benzidine clearly shows the advantage of using the Agilent J&W DB-5ms Ultra Inert columns for semivolatile analysis.

Introduction

Semivolatile analyses using methods similar to USEPA method 8270 [1] are important in environmental laboratories worldwide. A number of very

active analytes presents significant challenges for analysts, equipment providers, and column manufacturers in terms of inertness. Acidic compounds such as benzoic acid or 2,4-dinitrophenol and strong bases such as pyridine or benzidine are examples of active species found in the semivolatile sample set. These chemically charged species are particularly susceptible to adsorption onto active surfaces in the sample flow path, including the column itself. Both system and column inertness are critical for effective analysis of these active chemical species.

For many years Grob's mix [2] has been the standard mix to evaluate capillary GCs and columns. This mix consists of a series of alkanes, a substituted phenol (acidic component), an amine (basic component), an alcohol, and a diol. Virtually all capillary column manufacturers have used Grob's or a very similar test mix to evaluate column performance historically. These mixtures work well to evaluate column efficiency, system suitability against solute discrimination during injection, and potential solute absorption in the chromatographic flow path. Inertness evaluation based on single acidic and basic species in these mixes, though valuable, falls short of the rigorous requirements for inertness that applications on modern capillary GC columns require [3–4]. Modern GC applications demand a more comprehensive approach to properly investigate column inertness performance.



Agilent Technologies

Experimental

Baseline inertness testing of columns was on an Agilent 6890N GC equipped with a 7683B autosampler and an FID. Semivolatile application-specific chromatograms were generated using an Agilent 6890N GC/5975B MSD equipped with a 7683B autosampler.

Tables 1 and 2 list the chromatographic conditions used on each of the chromatographic systems. Table 3 lists flow path consumable supplies used in these experiments.

Table 1. Chromatographic Conditions 6890N/FID System

GC:	Agilent 6890N
Sampler :	Agilent 7683B, 0.5- μ L syringe (Agilent p/n 5188-5246), 0.02- μ L split injection, 1 ng each component on column
Carrier:	Hydrogen constant pressure 38 cm/s
Inlet:	Split/splitless; 250 °C, 1.4 mL/min column flow, split flow 900 mL/min, gas-saver flow 75 mL/min. on at 2.0 min
Inlet liner:	Deactivated single taper w/glass wool (Agilent p/n 5183-4647)
Column:	Agilent J&W DB-5ms Ultra Inert, 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 122-5532UI)
Oven:	65 °C isothermal
Detection:	FID at 325 °C, 450 mL/min air, 40 mL/min hydrogen, 45 mL/min nitrogen makeup

Table 2. Chromatographic Conditions 6890N/5975B MSD System

GC:	Agilent 6890N/5975B MSD
Sampler :	Agilent 7683B, 5.0- μ L syringe (Agilent p/n 5181-5246), 1.0- μ L splitless injection, 5 ng each component on column
Carrier:	Helium constant flow 30 cm/s
Inlet:	Split/splitless; 260 °C, 53.7 mL/min total flow, purge flow 50 mL/min on at 0.5 min, gas-saver flow 80 mL/min on at 3.0 min
Inlet liner:	Deactivated single taper w/glass wool (Agilent p/n 5183-4647)
Column:	Agilent J&W DB-5 ms Ultra Inert, 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 122-5532UI)
Oven:	40 °C (1 min) to 100 °C (15 °C/min), 10 °C to 210 °C (1 min), 5 °C/min. to 310 °C (8 min)
Detection:	MSD source at 300 °C, quadrupole at 180 °C, transfer line at 290 °C, scan range 50–550 AMU

The flow path supplies used in these experiments are listed in Table 3.

Table 3. Flow Path Supplies

Vials:	Amber screw cap (Agilent p/n 5182-0716)
Vial caps:	Blue screw cap (Agilent p/n 5282-0723)
Vial inserts:	100- μ L glass/polymer feet (Agilent p/n 5181-1270)
Syringe:	5 μ L (Agilent p/n 5181-1273)
Septum:	Advanced Green (Agilent p/n 5183-4759)
Inlet liners:	Deactivated single taper w/glass wool (Agilent p/n 5183-4647) for FID Deactivated single taper direct connect (Agilent p/n G1544-80730) for MSD
Ferrules:	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323)
20x magnifier:	20x magnifier loupe (Agilent p/n 430-1020)

Sample Preparation

Test probes for baseline inertness evaluation were purchased from Sigma Alrich (Milwaukee, WI 53201, USA). Dichloroethane used was Burdick and Jackson spectral grade purchased thorough VWR International (West Chester, PA 19380, USA). semivolatile standard (USEPA 8270) solutions were obtained either from Ultra Scientific (North Kingstown, RI 02852, USA) or AccuStandard (New Haven, CT 06513, USA).

Solutions were prepared using dichloroethane solvent and class A volumetric pipettes and flasks.

Results and Discussion

Baseline Inertness Profile for the Ultra Inert Columns

One means of quickly evaluating the suitability of a chromatographic system and the column component of that system is the deliberate injection of challenging analyte mixes on the system. Good sample recoveries and peak shapes quickly show that the injection system is functioning properly and establish a baseline inertness profile for the column. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species like those in the semivolatile sample set. The use of more demanding test mixes to certify column inertness performance is the approach taken for every column offered in the Ultra Inert series of capillary GC columns.

This application illustrates the implementation of more rigorous testing procedures to certify GC capillary column inertness. The baseline test mix selected for inertness contains 1-propionic acid, 4-picoline, trimethyl phosphate, and 1-heptanol. Key column evaluation criteria include efficiency of n-decane elution at a k' of 5, probe peak shapes, and peak height ratios of 4-picoline and trimethyl phosphate relative to closely eluting alkanes. The peak height ratio of active analytes, such as 4-picoline and trimethyl phosphate, relative to less active alkanes indicate the degree of surface activity for the reactive analyte. A higher ratio indicates better inertness. Testing with these aggressive probes provides more probative tools for evaluating inertness with problematic acidic and basic species. This testing procedure raises the bar for column inertness QC testing and sets a new industry standard for consistent column performance.

Figure 1 shows a baseline inertness chromatogram for an Ultra Inert DB-5ms column. Please note the peak shapes for trimethyl phosphate. This compound exhibits minor peak tailing in this example chromatogram and, for this analyte, represents

very good peak shape. The observable peak tailing for this analyte is what makes it an excellent tool for evaluating column inertness. On a lesser column this peak may not be seen at all.

Semivolatile Challenging Analytes

The evaluation of column performance went beyond the new baseline testing for inertness and looked at an abbreviated list of compounds specific to the USEPA Method 8270 sample set. The semivolatiles mix [5] contained N-nitrosodimethylamine, aniline, benzoic acid, 2,4-dinitrophenol, 4-nitrophenol, 2-methyl-4,6-dinitrophenol, pentachlorophenol, 4-aminobiphenyl, benzidine, 3,3'-dichlorobenzidine, benzo [b] fluoroanthene, benzo [k] fluoroanthene as well as recommended internal standards. These species were selected to range in polarity from basic to acidic species and from very early eluting nitrosamine to late eluting polynuclear aromatic hydrocarbons (PAHs). Figure 2 is a total ion chromatogram of the challenging analyte mix with a 5-ng on-column loading of each component.




Figure 1. Baseline inertness test chromatogram, 1 ng/component load on the Agilent J&W DB-5ms Ultra Inert column (Agilent p/n 122-5532UI), chromatographic conditions as in Table 1, flow path supplies as in Table 3.




Figure 2. Abbreviated semivolatile test chromatogram, 5 ng/component load on the Agilent J&W DB-5ms Ultra Inert column (Agilent p/n 122-5532UI), chromatographic conditions as in Table 2, flow path supplies as in Table 3.

One key assessment criterion for USEPA 8270 system suitability is the response factor for 2,4-dinitrophenol and its most closely eluting internal standard acenaphthene-d10. The minimum acceptable average response factor (over the entire concentration range) is 0.050 and the typical range is between 0.1 to 0.2. This response tends to decrease at lower concentrations and as the chromatographic system or the standard starts to deteriorate. In Figure 2, response factors for 2,4-dinitrophenol were greater than 0.1, and for 4-nitrophenol, they were greater than 0.2, each at a concentration of 5 µg/mL. These values are indicative of excellent column performance even at low standard concentration.

The recovery of benzidine is another key indicator of inertness performance for semivolatile analysis. This particular base is subject to thermal breakdown in the inlet and to oxidation from standing in solution. Injection temperatures above 260 °C caused benzidine recoveries to drop dramatically. It was necessary to balance benzidine recoveries with the elution of heavier PAHs when setting

injection port temperatures. An injection port temperature setting of 260 °C gave good recoveries for benzidine and was still hot enough for higher molecular weight PAHs to volatilize.

Semivolatile Large Mix

Figure 3 shows a 5-ng on-column loading of a broader range of semivolatile analytes. This large mixture was prepared by combining AccuStandard® semivolatile mixes 1, 2, 3, 4a, 4b, 5, and 6 all at a nominal concentration of 5 µg/mL. In total, 93 semivolatile compounds were included in this mix, ranging in boiling points from very low-boiling N-nitrosodimethylamine to high-boiling benzo (g,h,i) perylene. In addition, a wide diversity of analyte polarities was represented in this mix. The highlighted area in Figure 3 shows the elution and peak shape of highly basic benzidine and its response relative to the nearest eluting peak, flouranthene. Even in this large mix, benzidine gave good relative response and peak shape.

- 1 N-nitrosodimethylamine
- 2 2- Methyl pyridine
- 3 Benzidine
- 4 Fluoranthene
- 5 Benzo (g,h,i) perylene




Figure 3. Semivolatile (large mix) test chromatogram, 5 ng/component load on the Agilent J&W Ultra Inert DB-5ms column (Agilent p/n 122-5532UI), chromatographic conditions as in Table 2, flow path supplies as in Table 3. Several peaks of interest are labeled to indicate early- and late-eluting species. Benzidine (peak 3) and fluoranthene (peak 4) peaks are shown in the highlighted section.

Conclusions

Rigorous column inertness testing with aggressive probes ensures consistent and reliable column inertness performance for active analytes. Challenging probes such as 1-propionic acid, 4-picoline, and trimethyl phosphate are better predictive indicators of column behavior toward active analytes than traditional Grob style mixes used by many column manufacturers. Inertness testing with these aggressive probes produces columns with well-defined baselines for inertness performance.

Columns with well-defined inertness baselines provide a reliable platform for the analyst to begin analysis of semivolatiles. The Ultra Inert DB-5ms column used in this series of experiments demonstrates excellent inertness performance for some of the most difficult analytes in the semivolatile sample set, including N-nitrosodimethylamine, 2,4-dinitrophenol, 4-nitrophenol, and benzidine. The good recoveries and peak shapes observed for these difficult species, even with a 5-ng on-column loading, are indicative of successful semivolatile analyses on these new Ultra Inert DB-5ms columns.

References

1. US EPA Method 8270D, Revision 4, February 2007, "Semivolatile Organic Compounds by Gas Chromatography/Mass Spectrometry (GC/MS)"
2. K. Grob Jr., G. Grob, and K. Grob, "Comprehensive, Standardized Quality Test for Glass Capillary Columns," *Journal of Chromatography A*, Vol. 156, Issue 1, 21 August 1978, Pages 1–20
3. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenylmethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
4. Jim Luong, Ronda Gras, and Walter Jennings, "An Advanced Solventless Column Test for Capillary GC Columns," *J. Sep. Sci.*, 2007, 30, 2480–2492
5. Mike Szelewski and Bill Wilson, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270," Agilent Technologies publication 5988-3072EN

For More Information

For more information on our products and services,
visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
May 19, 2008
5989-8616EN



Agilent Technologies

Polybrominated Diphenyl Ether (PBDE) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column



Application

Environmental

Authors

Ken Lynam and Doris Smith
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Trace and ultra trace-level polybrominated diphenyl ether (PBDE) analyses are important tools for understanding food supply and environmental quality worldwide. In this application, trace-level PBDE analysis is demonstrated using electron impact single quadrupole scanning mass spectrometry. For these challenging separations, knowing that each GC column has been thoroughly tested for column inertness gives the analyst higher confidence in the accuracy of the results.

Agilent Technologies Inc. has implemented new testing procedures to more effectively evaluate GC column inertness performance. This new testing procedure employs deliberately aggressive probes to thoroughly investigate column inertness and quality. These extremely active probes, including 1-propionic acid, 4-picoline, and trimethyl phosphate, are used to verify each column's inertness performance.


Introduction

Polybrominated diphenyl ethers (PBDEs) are both persistent and increasingly common in the environment. These chemicals are typically used as flame retardants in textiles and electronic products such as televisions and computer equipment. There are

209 possible PBDE congeners that vary in the degree of bromination from mono to fully brominated decabromodiphenyl ether. Each of the individual congeners is assigned both an IUPAC name and bromodiphenyl ether (BDE) number, by convention. For example, fully brominated decabromodiphenyl ether is assigned the number BDE-209.

PBDEs as a class of molecules tend to undergo degradation on exposure to heat and light. BDE-209's long retention and susceptibility to thermal breakdown make it a particularly challenging analyte.

BDE-209 Structure



Unfortunately, these chemicals continue to find their way into food supplies and common house dust. [1–5] Similarities between PBDEs and polychlorinated biphenyl (PCBs) compounds include their tendency to persist in the environment and to bioaccumulate in adipose tissues.

The chief routes of human exposure to PBDEs appear to be ingestion of contaminated foods and inhalation of contaminated house dust. Measurable levels of PBDEs have been found in fish, meats,



Agilent Technologies

dairy products, eggs, and vegetables. Higher levels of PBDEs are found more often in fish than in other food sources. House dust studies in the U.S., Belgium, and Singapore have all shown appreciable levels of PBDEs. The need for reliable, sensitive, and robust analytical methods for the analysis of PBDEs is of global concern.

Long-term human toxicities for PBDEs are not well understood, even though a number of studies have found appreciable levels in breast milk and human adipose tissue. These studies suggest a link between long-term exposure of the mother to specific BDEs and neurological effects in the growing fetus. Human health concerns led to a ban on the use of penta-BDE and octa-BDE within the European Union in 2004.

This application highlights the value of using a 15-m Agilent J&W DB-5ms Ultra Inert capillary GC column for challenging PBDE analysis. Agilent Technologies Inc. has implemented new testing procedures to more effectively evaluate GC column inertness performance. This new testing procedure employs deliberately aggressive probes to thoroughly investigate column inertness and quality. These extremely active probes, including 1-propionic acid, 4-picoline, and trimethyl phosphate, are

used to verify each column's inertness performance. Capillary GC column activity as a potential source of result uncertainty has been all but eliminated with the Ultra Inert series of columns.

Experimental

An Agilent 6890N GC/5975B MSD equipped with a 7683B autosampler was used for this series of experiments. Table 1 lists the chromatographic conditions used for these analyses. Table 2 lists flow-path consumable supplies used in these experiments.

Sample Preparation

A seven-level eight-component BDE calibration curve set was purchased from AccuStandard (New Haven, CT). These solutions were transferred directly to amber glass autosampler vials and used as supplied. Concentration ranges were 0.5 to 250 ng/mL for BDEs -47, -100, -99, -154, -153, -183, and -205. BDE-209 concentration ranged from 2.5 to 1,000 ng/mL. The isooctane used was Burdick and Jackson Ultra Resi Grade purchased through VWR International (West Chester, PA, USA). Isooctane was used as a reagent blank and syringe wash solvent.

Table 1. Chromatographic Conditions

GC	Agilent 6890N/5973B MSD					
Sampler	Agilent 7683B, 5.0-μL syringe (Agilent p/n 5188-5246), 1.0-μL splitless injection, 5 ng each component on column					
Carrier	Helium 72 cm/s, constant flow					
Inlet	Pulsed splitless; 325 °C, 20 psi until 1.5 min, purge flow 50 mL/min at 2.0 min					
Inlet liner	Deactivated dual taper direct connect (Agilent p/n G1544-80700)					
Column	Agilent J&W DB-5ms Ultra Inert 15 m × 0.25 mm × 0.25 μm (Agilent p/n 122-5512UI)					
Oven	150 to 325 °C (17 °C/min), hold 5 min					
Detection	MSD source at 300 °C, quadrupole at 150 °C, transfer line at 300 °C, scan range 200–1000 amu					
SIM program						
	Time (min)	Group	PBDE bromination	[M]⁺	SIM ions [M–Br₂]⁺ [M–Br₂]⁺²	Confirmation ion
	3.00	1	3	405.8	246	247.9
			4	485.7	325.8	162.9
	5.75	2	5	536.6	403.8	565.7
			6	643.6	483.7	241.8
	8.00	3	7	721.5	561.6	563.6
	9.25	4	8	801.5	641.5	643.6
	11.50	5	10	959.3	799.4	399.7
						797

Table 2. Flow Path Supplies

Vials	Amber glass vials (Agilent p/n 5182-0716)
Vial caps	Blue screw cap (Agilent p/n 5282-0723)
Vial inserts	100 μ L glass/polymer feet (Agilent p/n 5181-1270)
Syringe	5 μ L (Agilent p/n 5181-1273)
Septum	Advanced Green (Agilent p/n 5183-4759)
Inlet liners	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Ferrules	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323)
20x magnifier	20x magnifier loupe (Agilent p/n 430-1020)

Results and Discussion

Baseline Inertness Profile for Ultra Inert Columns

The basic approach for inertness verification for the Agilent J&W Ultra Inert series of capillary GC columns is testing with highly active probes at low concentration and low temperature. [6] This is a new rigorous approach that establishes consistent baseline inertness profiles for each column in the Agilent J&W Ultra Inert GC column series. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species that tend to adsorb onto the column's active sites, particularly at trace levels, like the BDEs in this application example. A detailed

description of the test mix and additional application examples are available in references 7 through 9.

PBDE Analyses

PBDE-209 is a particularly challenging analyte due to its long retention and tendency to degrade with high-temperature exposure. High-temperature thermal stability is an issue for this class of compounds, but is more pronounced for BDE-209, as it is highly brominated and well retained. One key to successful BDE analysis is to limit the time that these compounds are exposed to high temperatures. A 15-m long column, as opposed to a typical 30-m long column was used in this case to limit residence time for BDE-209. [10,11] Fortunately, the BDEs resolve well, with symmetrical peak shapes, when using Agilent J&W DB-5ms phase, enabling successful separation on the shorter column. Figure 1 shows a total ion chromatogram of the eight BDEs investigated in this study.

In this application a seven-level eight-component BDE calibration curve set was evaluated over the concentration range of 0.5 to 250 ng/mL for BDEs -47, -100, -99, -154, -153, -183, and -205 and the range of 2.5 to 1,000 ng/mL BDE 209 on an Agilent J&W Ultra Inert DB-5ms 15 m $\times$ 0.25 mm $\times$ 0.25 μ m (p/n 122-5512UI) column. Sensitivity was excellent, even for the more challenging BDE-209 with a 0.025 ng on-column loading, yielding a 3.28 signal-to-noise level. The exploded view of the BDE-209 peak in Figure 2 illustrates the sensitivity observed for a 0.025-ng on-column loading of BDE-209.




Figure 1. Total ion chromatogram (SIM mode) of a 0.005-ng (BDEs -47, -100, -99, -154, -153, -183, -205, and -209) and 0.025-ng (BDE-209) on-column loading on an Agilent J&W DB-5ms Ultra Inert 15 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 122-5512UI).




Figure 2. Enlarged section of the total ion chromatogram (SIM mode) of a 0.025-ng BDE-209 on-column loading. The large peak in the figure is BDE-209, a particularly challenging BDE due to its long retention and thermal instability.

Linearity was excellent across the range studied, giving R^2 values of 0.997 or greater in all cases. Figure 3 indicates the correlation coefficients for each of the individual analytes and shows an example linear regression plot for BDE-209.




Figure 3. Correlation coefficients for the eight components over the 0.5 ng/mL to 1,000 ng/mL concentration range (BDE-209 2.5 to 1,000 ng/mL) used in this study. An example linear regression plot of particularly challenging BDE-209 is also shown.

Conclusions

This application successfully demonstrates the use of a 15-m Agilent J&W DB-5ms Ultra Inert capillary GC column for trace-level BDEs in a 15-minute analysis. Linearity was excellent for all eight BDEs studied, yielding 0.997 or greater R^2 values down to a 0.005 ng (0.025 ng for BDE-209) on-column loading of each component. One of the reasons for the excellent linearity and high R^2 values is the highly inert surface of the column. The lack of chemically active sites makes these columns an excellent choice for trace-level applications.

The Agilent 6890/5975B GC/MSD (SIM mode) equipped with an inert electron impact source had excellent sensitivity with even the most challenging BDE in this set, PBD-209. The signal-to-noise ratio for a 0.025-ng on-column loading of BDE-209 was greater than three to one with this system. This result shows clearly the power of using an Agilent J&W DB-5ms Ultra Inert column for trace-level BDE analysis. Lower limits of quantification are expected when using one of Agilent's latest GC/MS offerings, such as the 7890/5975C GC/MSD Triple-Axis Detector coupled with an Agilent J&W DB-5ms Ultra Inert GC capillary column.

References

1. Nerissa Wu, Thomas Herrmann, Olaf Paepke, Joel Tickner, Robert Hale, Ellen Harvey, Mark La Guardia, Michael D. McClean, and Thomas Webster, "Human Exposure to PBDEs: Associations of PBDE Body Burdens with Food Consumption and House Dust," *Environmental Science & Technology*, Volume 41, Number 5, 2007, pages 1584–1589
2. Stefan Voorspoels, Adrian Covaci, Hugo Neels, and Paul Schepens, "Dietary PBDE Intake: A Market-Basket Study in Belgium," *Environmental International*, Volume 33, Issue 1, January 2007, pages 93–97
3. Jing Tan, Si Min Cheng, Annamalai Loganath, Yap Seng Chong, and Jeffery Philip Obbard, "Polybrominated Diphenyl Ethers in House Dust in Singapore," *Chemosphere*, Volume 66, Issue 6, January 2007, pages 985–992
4. Souichi Ohta, Diasule Ishizuka, Hajime Nishinura, Teruyuki Nakoa, Osamu Azoasa, Yoshiko Shimaduzu, Fumie Ochiai, Takafumi Kida, Masatoshi Nishi, and Hideaki Miyata, "Comparison of Polybrominated Diphenyl Ethers in Fish, Vegetables, and Meats and Levels in Human Milk of Nursing Women in Japan," *Chemosphere*, Volume 46, Issue 5, February 2002, pages 689–696
5. Thomas A. McDonald, "Polybrominated Diphenylether Levels Among United States Residents: Daily Intake and Risk of Harm to the Developing Brain and Reproductive Organs," *Integrated Environmental Assessment and Management*, Volume 1, Number 4, 2005, pages 343–354
6. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenyltrimethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
7. "Agilent J&W Ultra Inert GC Columns: A New Tool to Battle Challenging Active Analytes," Agilent Technologies publication 5989-8665EN, June 2, 2008
8. Kenneth Lynam, "Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column," Agilent Technologies publication 5989-8616EN, May 19, 2008
9. Kenneth Lynam and Doris Smith, "Polycyclic Aromatic Hydrocarbon (PAH) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9181EN, July 24, 2008
10. Jonas Björklund, Petter Tollbäck, Christian Hiärne, Eva Dyremark, and Conny Östman, "Influence of the Injection Technique and the Column System on Gas Chromatographic Determination of Polybrominated Diphenyl Ethers," *Journal of Chromatography A*, 1041 (2004) 201–210
11. Chuanhong Tu and Harry Prest, "Determination of Polybrominated Diphenyl Ethers in Polymeric Materials Using the 6890 GC/5793N Inert MSD with Electron Impact Ionization," Agilent Technologies publication 5989-2850EN, April 5, 2005

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
August 27, 2008
5989-9571EN



Agilent Technologies



EPA Method 1694: Agilent's 6410A LC/MS/MS Solution for Pharmaceuticals and Personal Care Products in Water, Soil, Sediment, and Biosolids by HPLC/MS/MS

Application Note

Environmental

Authors

Imma Ferrer and E. Michael Thurman
Center for Environmental Mass
Spectrometry
University of Colorado
Civil, Environmental, and Architectural
Engineering
ECOT 441, 428 UCB
Boulder, CO 80309
USA

Jerry Zweigenbaum
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

An analytical methodology for screening and confirming the presence of 65 pharmaceuticals in water samples was developed using the Agilent G6410A Triple Quadrupole mass spectrometer (QQQ). The method was developed following the guidelines in EPA Method 1694. Four distinct chromatographic gradients and LC conditions were used according to the polarity and extraction of the different pharmaceuticals. Positive and negative ion electrospray were used with two multi-reaction monitoring (MRM) transitions (a quantifier and a qualifier ion for each compound), which adds extra confirmation in this methodology compared with the EPA method. Linearity of response of three orders of magnitude was demonstrated ($r^2 > 0.99$) for all the pharmaceuticals studied. The analytical performance of the method was evaluated for one wastewater sample collected from Boulder Creek, Colorado; positive identifications for carbamazepine and diphenhydramine were found for this sample using the methodology developed in this work.



Agilent Technologies

Introduction

The analytical challenge of measuring emerging contaminants in the environment has been a major research focus of scientists for the last 20 years. Pharmaceuticals and personal care products (PPCPs) are an important group of contaminants that have been targeted, especially in the last decade. In the area of PPCPs there are several methods addressing the analysis of these analytes, including EPA Method 1694 [1], which was recently published (December 2007). This EPA protocol uses solid-phase extraction (SPE) for water sample preparation [1]. The extracts are then analyzed directly by a

tandem mass spectrometer using a single transition for each compound. This application note describes the Agilent solution to this method, which is demonstrated with the Agilent model 6410A LC/MS QQQ. The Agilent initial implementation for EPA Method 1694 consists of 65 analytes (of 75 total analytes) and 17 labeled internal standards (of 20 total), which are a mixture of PPCPs that are analyzed each by a single MRM transition. (Note that the other compounds and internal standards could not be obtained at this time.) The method also uses Agilent C-18 and Hydrophilic Interaction Chromatography (HILIC) columns for all analytes. To provide additional confirmation, a second MRM transition was added for 60 of the 65 analytes analyzed. This gives an even greater assurance of correct identification than prescribed by the EPA. Table 1 shows the list of pharmaceuticals studied here.

Table 1. Analytes Studied in This Work

List of Group 1 Compounds EPA 1694: 46 Analytes

Acetaminophen	Codeine	Flumequine	Penicillin V	Sulfanilamide
Ampicillin	Cotinine	Fluoxetine	Roxithromycin	Thiabendazole
Azithromycin	Dehydronifedipine	Lincomycin	Sarafloxacin	Trimethoprim
Caffeine	Digoxigenin	Lomefloxacin	Sulfachloropyridazine	Tylosin
Carbadox	Diltiazem	Miconazole	Sulfadiazine	Virginiamycin
Carbamazepine	1,7-Dimethylxanthine	Norfloxacin	Sulfadimethoxine	Digoxin*
Cefotaxime	Diphenhydramine	Ofloxacin	Sulfamerazine	
Ciprofloxacin	Enrofloxacin	Oxacillin	Sulfamethazine	
Clarithromycin	Erythromycin	Oxolinic acid	Sulfamethizole	
Cloxacillin	Erythromycin anhydrate	Penicillin G	Sulfamethoxazole	

*Compound formed intractable Na adduct with current conditions.

List of Group 2, 3, and 4 Compounds: EPA 1694: 19 Analytes

Anhydrotetracycline (2)	Doxycycline (2)	Minocycline (2)	Triclocarban (3)
			Triclosan (3)
			Warfarin (3)
Chlorotetracycline (2)	4-Epianhydrotetracycline (2)	Tetracycline(2)	Albuterol (4)
		Meclocycline (2)	Cimetidine (4)
			Metformin (4)
Demeclocycline(2)	4-Epitetracycline(2)	Gemfibrozil (3)	Ranitidine (4)
		Ibuprofen (3)	
		Naproxen (3)	

List of Labeled Internal Standards

$^{13}\text{C}_2$ - ^{15}N -Acetaminophen	$^{13}\text{C}_2$ -Erythromycin	$^{13}\text{C}_6$ -Sulfamethazine	$^{13}\text{C}_3$ -Trimethoprim
$^{13}\text{C}_3$ -Atrazine	Fluoxetine- d_6	$^{13}\text{C}_6$ -Sulfamethoxazole	Warfarin- d_5
$^{13}\text{C}_3$ -Caffeine	Gemfibrozil- d_6	$^{13}\text{C}_6$ -2,4,5-Trichloro-phenoxycetic acid	Carbamazepine- d_{10} (Extra compound, not EPA list)
$^{13}\text{C}_3$ - ^{15}N -Ciprofloxacin	$^{13}\text{C}_3$ -Ibuprofen	$^{13}\text{C}_6$ -Triclocarban	
Cotinine- d_3	^{13}C -Naproxen- d_3	$^{13}\text{C}_{12}$ -Triclosan	

Experimental

Sample Preparation

Pharmaceutical analytical standards were purchased from Sigma, (St. Louis, MO). All stable isotope labeled compounds used as internal standards were obtained from Cambridge Isotope Laboratories (Andover, MA). Individual pharmaceutical stock solutions (approximately 1,000 µg/mL) were prepared in pure acetonitrile or methanol, depending on the solubility of each individual compound, and stored at -18 °C. From these solutions, working standard solutions were prepared by dilution with acetonitrile and water.

Water samples were collected from the wastewater treatment plant at the Boulder Creek outfall (Boulder, CO) and extracted as per the EPA method. Agilent has introduced a polymeric SPE sorbent with hydrophilic/lipophilic properties that may also be appropriate for this application. "Blank" wastewater extracts were used to prepare the matrix-matched standards for validation purposes. The wastewater extracts were spiked with the mix of pharmaceuticals at different concentrations (ranging from 0.1 to 500 ng/mL or ppb) and subsequently analyzed by LC/MS/MS.

LC/MS/MS Instrumentation

The analytes were subdivided in groups (according to EPA protocol for sample extraction) and LC conditions for the chromatographic separation of each group are as follows.

LC Conditions for Group 1-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	10% ACN and 90% H ₂ O with 0.1% HCOOH
Flow rate	0.2–0.3 mL/min
Gradient	t ₀ = 10% ACN, 0.2 mL/min t ₅ = 10% ACN, 0.2 mL/min t ₈ = 10% ACN, 0.3 mL/min t ₂₄ = 60% ACN, 0.3 mL/min t ₃₀ = 100% ACN
Injection volumes	15 µL

LC conditions for Group 2-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	10% ACN and 90% H ₂ O with 0.1% HCOOH
Flow rate	0.2 mL/min
Gradient	t ₀ = 10% ACN t ₁₀ = 10% ACN t ₃₀ = 100% ACN
Injection volumes	15 µL

LC conditions for Group 3-acidic extraction, negative electrospray ionization (ESI-) instrument conditions

Column	Agilent ZORBAX Eclipse Plus C18 2.1 × 100 mm, 3.5 µ (p/n 959793-902)
Column temperature	25 °C
Mobile phase	40% MeOH and 60% H ₂ O with 5 mM ammonium acetate, pH 5.5
Flow rate	0.2 mL/min
Gradient	t _{0.5} = 40% MeOH t ₇ = 100% MeOH
Injection volumes	15 µL

LC conditions for Group 4-acidic extraction, positive electrospray ionization (ESI+) instrument conditions

Column	Agilent ZORBAX HILIC Plus 2.1 × 100 mm, 3.5 µm (p/n 959793-901 custom order until November 1, 2008)
Column temperature	25 °C
Mobile phase	98% ACN and 2% H ₂ O with 10 mM ammonium acetate, pH 6.7
Flow rate	0.25 mL/min
Gradient	t ₀ = 98% ACN t ₅ = 70% ACN t ₁₂ = 70% ACN
Injection volumes	15 µL

The mass spectrometer conditions were general to all groups and are as follows.

MS Conditions

Mode	Positive and negative (depending on group) ESI using the Agilent G6410A Triple Quadrupole mass spectrometer
Nebulizer	40 psig
Drying gas flow	9 L/min
V capillary	4000 V
Drying gas temperature	300 °C
Fragmentor voltage	70–130 V
Collision energy	5–35 V
MRM	2 transitions for every compound as shown in Table 1
Dwell time	10 msec

Results and Discussion

Optimization of LC/MS/MS Conditions

The initial study consisted of two parts. First was to optimize the fragmentor voltage for each of the pharmaceuticals studied in order to produce the largest signal for the precursor ion. Typically the protonated molecule was used for the precursor ion. Each compound was analyzed separately using an automated procedure (MassHunter Optimizer software, Agilent Technologies, Santa Clara, CA) to check the fragmentor at each voltage. The data was then selected for optimal fragmentor signal and each compound was optimized again to determine automatically the collision energies for both the quantifying and qualifying ions. Optimal collision energies varied between 5 and 35 V. The MRM transitions and optimized energies used for this study are shown in Tables 2A to 2D.

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1 (The labeled standards are bold.)

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Acetaminophen	90	152 → 110 152 → 65	15 35
¹³C₂-¹⁵N-Acetaminophen	90	155 → 111 155 → 93	15 25
Ampicillin	70	350 → 160 350 → 106	10 15
¹³C₃-Atrazine	120	219 → 177 219 → 98	15 25
Azithromycin	130	749.5 → 591.4 749.5 → 158	30 35
Caffeine	110	195 → 138 195 → 110	15 25
¹³C₃-Caffeine	110	198 → 140 198 → 112	15 25
Carbadox	80	263 → 231 263 → 130	5 35
Carbamazepine	110	237 → 194 237 → 179	15 35
Carbamazepine-d₁₀	110	247 → 204 247 → 202	15 35
Cefotaxime	90	456 → 396 456 → 324	5 5
Ciprofloxacin	110	332 → 314 332 → 231	20 35
¹³C₃-¹⁵N-Ciprofloxacin	110	336 → 318 336 → 235	15 35

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1
(The labeled standards are bold.) continued

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Clarithromycin	110	748.5 → 158 748.5 → 590	25 15
Cloxacillin	90	436 → 160 436 → 277	15 15
Codeine	130	300 → 215 300 → 165	25 35
Cotinine	90	177 → 98 177 → 80	25 25
Cotinine-d₃	90	180 → 80 180 → 101	25 25
Dehydronifedipine	130	345 → 284 345 → 268	25 25
Digoxigenin	90	391 → 355 391 → 337	15 15
Digoxin	No response, Na adduct		
Diltiazem	130	415 → 178 415 → 150	25 25
1,7-Dimethylxanthine	90	181 → 124 181 → 99	15 15
Diphenhydramine	70	256 → 167 256 → 152	15 35
Enrofloxacin	130	360 → 316 360 → 342	15 15
Erythromycin	90	734.5 → 158 734.5 → 576	35 15
¹³C₂-Erythromycin	90	736.5 → 160 736.5 → 578	25 15
Erythromycin anhydrate	90	716.5 → 158 716.5 → 116	25 25
Flumequine	90	262 → 174 262 → 244	35 15
Fluoxetine	90	310 → 148	5
Fluoxetine-d₆	90	316 → 154	5
Lincomycin	110	407 → 126 407 → 359	25 15
Lomefloxacin	130	352 → 308 352 → 265	15 25
Miconazole	90	415 → 159 415 → 69	35 25
Norfloxacin	70	320 → 302 320 → 276	15 15
Ofloxacin	110	362 → 318 362 → 261	15 25

Table 2A. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 1 (The labeled standards are bold.) continued

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Oxacillin	70	402 → 160 402 → 243	15 5
Oxolinic acid	90	262 → 244 262 → 216	15 25
Penicillin G	90	335 → 160 335 → 176	5 5
Penicillin V	70	351 → 160 351 → 114	5 25
Roxithromycin	130	837.5 → 679 837.5 → 158	15 35
Sarafloxacin	130	386 → 299 386 → 368	25 25
Sulfachloropyridazine	90	285 → 156 285 → 92	10 25
Sulfadiazine	110	251 → 156 251 → 92	15 25
Sulfadimethoxine	80	311 → 156 311 → 92	20 35
Sulfamerazine	110	265 → 156 265 → 92	15 25
Sulfamethazine	90	279 → 156 279 → 186	15 15
¹³C₆-Sulfamethazine	90	285 → 186 285 → 162	25 25
Sulfamethizole	80	271 → 156 271 → 92	10 25
Sulfamethoxazole	110	254 → 156 254 → 92	15 25
¹³C₆-Sulfamethoxazole	110	260 → 162 260 → 98	15 25
Sulfanilamide	70	173 → 156 173 → 92	5 15
Thiabendazole	130	202 → 175 202 → 131	25 35
¹³C₆-2,4,5-Trichlorophenoxyacetic acid	110	259 → 201 259 → 165	5 25
Trimethoprim	110	291 → 230 291 → 261	25 25
¹³C₃-Trimethoprim	110	294 → 233 294 → 264	25 25
Tylosin	110	916.5 → 174 916.5 → 772	35 35
Virginiamycin	110	526 → 508 526 → 355	5 15

Table 2B. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 2

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Anhydrotetracycline	90	427 → 410 427 → 154	15 25
Chlorotetracycline	110	479 → 462 479 → 197	15 35
Demeclocycline	130	465 → 430 465 → 448	25 15
Doxycycline	110	445 → 428 445 → 154	15 25
4-Epianhydrotetracycline (EATC)	90	427 → 410 427 → 105	15 35
4-Epitetracycline (ETC)	110	445 → 410 445 → 427	15 5
Minocycline	90	458 → 441	15
Tetracycline (TC)	110	445 → 410 445 → 427	15 5

Table 2C. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 3

Compound	Fragmentor voltage	MRM transitions (<i>m/z</i>)	Collision energy (eV)
Gemfibrozil	100	249 → 121	5
Gemfibrozil-d₆	100	255 → 121	5
Ibuprofen	75	205 → 161	5
¹³C₃-Ibuprofen	75	208 → 163	5
Naproxen	75	229 → 169 229 → 170	25 5
¹³C-Naproxen-d₃	75	233 → 169 233 → 170	25 5
Triclocarban	100	313 → 160 313 → 126	10 25
¹³C₆-Triclocarban	90	319 → 160 319 → 132	5 25
Triclosan	75	287 → 35	5
¹³C₁₂-Triclosan	75	299 → 35	5
Warfarin	125	307 → 117 307 → 161	35 15
Warfarin-d₅	90	312 → 161 312 → 255	15 25

Table 2D. MRM Transitions and MS Operating Parameters Selected for the Analysis of the Pharmaceutical Compounds in Group 4

Compound	Fragmentor voltage	MRM transitions (m/z)	Collision energy (eV)
Albuterol (Salbutamol)	90	240 → 148	15
		240 → 166	5
Cimetidine	100	253 → 159	10
		253 → 95	25
Metformin	80	130 → 60	10
		130 → 71	25
Ranitidine	110	315 → 176	15
		315 → 130	25

Chromatographic separation was done independently for each group and a dwell time of 10 msec was used for every MRM transition. Figures 1A to 1D show the chromatograms corresponding to 100 ppb standard on column for all the pharmaceuticals studied. Extracted ion chromatograms are overlaid for each one of the target analytes according to their respective protonated molecule and product-ion MRM transitions.




Figure 1A. MRM extracted chromatogram for pharmaceuticals in Group 1. Three time segments were used in this chromatographic separation.




Figure 1B. MRM extracted chromatogram for pharmaceuticals in Group 2. Only one transition shown. See Table 2B for compound identification.




Figure 1C. MRM extracted chromatogram for pharmaceuticals in Group 3. Only one transition shown. See Table 2C for compound identification.




Figure 1D. MRM extracted chromatogram for pharmaceuticals in Group 4.

Application to Wastewater Samples

To confirm the suitability of the method for analysis of real samples, matrix-matched standards were analyzed in a wastewater matrix from an effluent site, at eight concentrations (0.1, 0.5, 1, 5, 10, 50, 100, and 500 ng/mL or ppb concentrations). Figure 2 shows an example standard curve for acetaminophen in the wastewater matrix. In general, all compounds gave linear results with excellent sensitivity over three orders of magnitude, with r^2 values of 0.99 or greater.




Figure 2. Calibration curve for acetaminophen in a wastewater matrix using a seven-point curve from 0.1 to 100 ng/mL (ppb) using a linear fit with no origin treatment.

Finally, a “blank” wastewater sample was analyzed and the presence of two pharmaceuticals, carbamazepine and diphenhydramine, could be confirmed with two MRM transitions. Figure 3 shows the ion ratios qualifying for these two compounds in a wastewater extract. As shown in Figure 3 in the two ion profiles, both pharmaceuticals were easily identified in this complex matrix due to the selectivity of the MRM transitions and instrument sensitivity.




Figure 3. MRM chromatograms of a wastewater sample for carbamazepine and diphenhydramine using two transitions.

Conclusions

The results of this study show that the Agilent 6410A Triple Quadrupole is a robust, sensitive, and reliable instrument for the study of pharmaceuticals in water samples, using high throughput methods. The Agilent 6410A Triple Quadrupole has been shown to be a successful instrument for the implementation of EPA Method 1694.

References

1. EPA Method 1694: Pharmaceuticals and personal care products in water, soil, sediment, and biosolids by HPLC/MS/MS, December 2007, EPA-821-R-08-002.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Printed in the USA
September 19, 2008
5989-9665EN



Agilent Technologies



Improving GC-MS Method Robustness and Cycle Times Using Capillary Flow Technology and Backflushing

Application Note

Environmental

Author

Chris Sandy
Agilent Technologies, Inc.
UK and Ireland Sales Headquarters
710 Wharfedale Road
Winnersh Triangle
Wokingham, Berkshire, RG41 5TP
UK

Abstract

This application note demonstrates the customer benefits from using Capillary Flow Technology to provide backflushing of high-boiling materials in GC and GC/MS analyses. Benefits include reduction in chromatographic cycle times, a reduction in system column maintenance, and extended GC column life. If a GC/MS system is utilized, the author has experienced an increase in the number of samples analyzed before ion source maintenance is required.



Agilent Technologies

Introduction

A critical component of the GC/MS analysis of any sample that contains large amounts of matrix material is the sample preparation. Environmental samples such as soils and sediments require not only extraction, but may also require multiple cleanup steps in order to present as clean an extract as possible for injection in to the GC/MS system.

Any remaining matrix in the sample extract can have deleterious effects on the GC sample inlet, column, and the ion source of the mass spectrometer. Traditionally, these high-boiling matrix materials are removed from the capillary column by a long bake-out period after the analytes of interest have eluted. This long bake-out process causes thermal stress to the column and also drives the matrix material towards the ion source, where it will eventually affect system performance. Moreover, should any material remain in the column after the bake-out process, it can cause loss of chromatographic peak shape and retention time shifting of target analytes. This shifting of retention time is particularly troublesome if the mass spectrometer is being used in the selected ion monitoring (SIM) mode (as with a single quadrupole GC/MS) or in the multiple reaction monitoring (MRM) mode (as with a triple quadrupole GC/MS).

This paper demonstrates how high-boiling matrix materials can be removed from the column quickly and effectively – between sample injections – by using capillary flow technology and capillary column backflushing.

Figure 1 shows a schematic diagram of the GC/MS system used. The 15-m analytical column was connected to the EPC split/splitless inlet and a capillary flow technology two-way splitter (p/n G3180B or G1540 option number 889).




Figure 1. Schematic diagram of GC-MS system.

A short length of uncoated, deactivated fused silica (UDFS) capillary column is used as a restrictor between the splitter and the MS. Note carefully how the connections are made at the splitter. The X represents a port on the splitter plate that is closed off with a SilTite metal ferrule and stainless steel wire plug.

Backflushing in this example was accomplished during a post-run period by a combination of increasing oven temperature, reducing the inlet pressure of the analytical column, and increasing the pressure applied to the splitter plate.

Experimental

The full analytical conditions, both with and without post-run backflush set-points, are shown in Table 1.

Table 1. GC/MS Analysis Conditions

Gas chromatograph	Agilent 7890A
Columns	(1) 15.0 m × 0.25 µm id × 0.25 µm HP-5MS Ultra Inert (19091S-431SI) Inlet Front split/splitless, outlet 2-way Capillary Flow Device (2) 0.80 m × 0.15 mm id uncoated deactivated fused silica inlet two-way capillary flow device at 4.0 psig outlet vacuum
Carrier gas	Helium
Carrier gas mode	Constant pressure
Flow rate	17.18 psi
Injection port	EPC split/splitless
Autosampler	Agilent 7683A
Injection mode	Splitless, purge delay 0.5 min Purge flow 50.0 mL/min at 0.5 min
Injection volume	2.0 µL
Injection port liner	4 mm single-taper splitless liner (5181-3316)
Oven program °C (min)	70 (1) – 50 °C /min – 150 (0) 6 – 200 (0) – 16 – 280 (0) °C
Mass spectrometer	Agilent 5975C MSD
MS interface	280 °C
MS source	230 °C
MS quad 1	150 °C
Backflush conditions (1)	Post-run, 10 min, AUX 60 psig, oven 320 °C
Backflush conditions (2)	Post-run, 6 min, AUX 80 psig, oven 320 °C
Detection mode	El full scan; mass range 40:550 amu
El tune	Gain factor = 1

Results and Discussions

Experiment 1: No Backflushing Employed

In the first experiment, an extracted sediment sample was analyzed in full-scan mode to show the extent of the matrix problem. No backflushing was employed.

Before any sediment was injected, a system blank (no injection) followed by a 2- μ L solvent blank was made. In the absence of the actual hexane solvent used to prepare the

sediment extract, hexane that was not particularly clean was used. The TICs are shown overlaid in Figure 2, system blank in black, and solvent blank in gray. These chromatograms show that the system is free from high-boiling matrix material.

Following the blanks, a single injection of the sediment extract was made without backflushing; the TIC is shown in Figure 3. Note the very high abundance of the matrix and that when the analysis finishes, there is still a significant amount of matrix material to elute from the column.




Figure 2. System blank and solvent blank TICs.




Figure 3. Sediment extract TIC.

The sediment extract injection was followed by a series of hexane blank injections. The first seven hexane blank TICs are shown overlaid in Figure 4 with the solvent blank before the sediment was injected into the GC/MS system.

The original solvent blank TIC is shown in black, the eighth solvent blank TIC after the sediment injection is shown in gray.

Figure 5 shows that after the eighth solvent blank injection, the system has almost recovered to the level of background before the sediment sample was injected.




Figure 4. Successive solvent blank injections.




Figure 5. Eighth solvent blank and original solvent blank TICs

Experiment 2: Backflushing Employed

Backflushing was enabled during a post-run period by increasing column oven temperature, reducing the inlet pressure of the analytical column, and increasing the gas pressure applied to the splitter plate.

The 7890A instrument control software includes simple and easy-to-use screens to help set up post-run backflushing conditions. Figure 6 shows the configuration of columns and connections with the GC oven.

Figure 7 shows the actual backflushing conditions, namely the post-run oven temperature (320 °C), post-run inlet pres-

sure for the analytical column (1 psig), post-run pressure applied to the splitter device (60 psig), and post-run time (10 minutes). The figure also shows the number of column-volumes of carrier gas that will backflush the analytical column.

Note that using the backflushing conditions shown in Figure 7 (320 °C, column pressure 1 psig, and splitter pressure 60 psig for 10 minutes), that 59.4 column volumes of carrier gas was used to backflush the column during the post-run period. This backflush time may have been more than necessary. Alternate conditions were also investigated and are presented later.




Figure 6. Post-run backflushing screen number 1.

Summary of Backflush Calculations

Oven Temperature
320 °C

Detector	Maximum Flow	Allowable Pressure	Flow at Chosen Pressure
Vacuum	75	130.98	19.719

Backflush Pressure
60 psi

Inlet Pressure during Backflush
1 psi

Void Volumes
59.463

Backflush Flow to Inlet
7.6986 mL/min

Backflush Time
10 min

Void Time
0.16817 min

OK Cancel Help

Figure 7. Post-run backflushing screen number 2.

Before applying the backflush conditions to the method the user is presented with a convenient summary of the backflush conditions. See Figure 8.



Figure 8. Post-run backflushing screen number 3.

Another injection of the sediment including backflush was made followed by a blank injection of solvent. Figure 9 shows the overlaid TIC of the original solvent blank (black) overlaid on the solvent blank after the sediment injection (gray).

No evidence of any matrix material is indicated, demonstrating that all the high-boiling matrix material had been effectively removed by backflushing.




Figure 9. Original solvent blank TIC and solvent blank after sediment injection with post-run backflush (1).

Experiment 3: Backflushing Employed

In order to reduce cycle time for the method, the backflush conditions were modified by increasing the backflush pressure to 80 psig and holding for 6 minutes.

Note that using the backflushing conditions shown in Figure 10 (320 °C, column pressure 1 psig, and splitter pressure 80 psig for 6 minutes), that 46.6 column volumes of carrier gas was used to backflush the column during the post-run period.

Another injection of the sediment was made, followed by a blank injection of solvent. Figure 11 shows the overlaid TIC of the original solvent blank (black) overlaid on the solvent blank after the sediment injection (gray).

No evidence of any matrix material is indicated, demonstrating that all the high-boiling matrix material has been removed by backflushing with the more aggressive conditions as well. These conditions reduced the cycle time for this method 4 minutes compared to the backflushing conditions used in Experiment 1.




Figure 10. Post-run backflushing screen conditions number 2.




Figure 11. Original solvent blank TIC and solvent blank after sediment injection with post-run backflush (2).

Conclusions

Post-run backflushing was shown to effectively eliminate high-boiling sample matrix in a short amount of time. The major benefits of GC capillary column post-run backflushing include:

- Agilent's capillary flow technology and GC software enable easy and robust setup of GC backflushing.
- Compared to long bake-out periods with flow in the forward direction, a short period of backflushing can remove high-boiling matrix materials more effectively without contaminating the MS ion source.
- Chromatographic cycle time is reduced, columns stay clean, and the integrity of target analyte peak shapes and retention times are maintained.
- For this particular sediment extract the GC column was free of sample matrix after a backflush period of 6 minutes.
- Less system maintenance (ion source cleaning) is required.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Published in the USA
January 30, 2009
5990-3367EN



Agilent Technologies



Semivolatile Organics Analysis Using an Agilent J&W HP-5ms Ultra Inert Capillary GC Column

Application Note

Environmental

Author

Doris Smith and Kenneth Lynam
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Trace-level semivolatile organics analyses using methods such as USEPA Method 8270 are important tools for assessing environmental contaminants worldwide. The wide-ranging chemical diversity of target semivolatiles can prove chromatographically challenging. This application note demonstrates the benefits of using an Agilent J&W HP-5ms Ultra Inert Capillary GC column with electron impact single quadrupole scanning mass spectrometry for trace-level semivolatiles analysis.

Agilent Technologies has implemented new testing procedures to more effectively evaluate GC column inertness performance. These new testing procedures employ deliberately aggressive probes to thoroughly investigate column inertness and quality. These aggressive probes, including 1-propionic acid, 4-picoline, and trimethyl phosphate, are used to verify each column's inertness performance.



Agilent Technologies

Introduction

USEPA Method 8270 [1] is a commonly used method for detecting semivolatile organic compounds in environmental samples by GC/MS. This method encompasses several classes of analytes, including amines, alcohols, polycyclic aromatic hydrocarbons, and phenols. The acidic and basic nature of many of the analytes makes minimizing any column or instrument activity critical to good chromatography and reliable results.

Minimizing activity in the GC column is essential in maximizing an analyte's response. Nitrophenols are among the most active compounds in semivolatiles series. 2,4-Dinitrophenol in particular is notorious for showing low response through adsorption onto active sites in the flow path during analysis. At low concentrations, the response factor (RF) for 2,4-dinitrophenol can fall below the minimum average RF of 0.050 required by USEPA 8270 due to interaction between the analyte and sample flow path. Capillary GC column activity as a potential source of result uncertainty has been effectively eliminated with the Ultra Inert series of columns.

A custom standard containing an abbreviated list of analytes specific to USEPA Method 8270 was analyzed to evaluate column performance. This semivolatiles "short mix" contained n-nitrosodimethylamine, aniline, benzoic acid, 2,4-dinitrophenol, 4-nitrophenol, 2-methyl-4,6-dinitrophenol, pentachlorophenol, 4-aminobiphenyl, benzidine, 3,3'-dichlorobenzidine, benzo[b]fluoranthene, and benzo[k]fluoranthene, along with the recommended internal standards. These target analytes were chosen based on their chemical activity, as well as their poor chromatographic behavior. The short mix is particularly useful for rapid evaluation of system performance for semivolatiles analysis. Challenging analytes from early-eluting nitrosoamines through late-eluting PAHs are represented in this mix and chromatographic performance can be assessed quickly.

A second "large mix" standard containing a broader selection of semivolatiles was also evaluated to show the Ultra Inert's performance when analyzing a more complex sample. This standard contained a variety of acidic, basic, and neutral groups, which ranged from very low-boiling components to high-boiling polycyclic aromatic hydrocarbons.

Experimental

An Agilent 6890N GC/5975B MSD equipped with a 7683B autosampler was used for this series of experiments. Table 1 lists the chromatographic conditions used for these analyses. Table 2 lists flow path consumable supplies used in these experiments.

Table 1. Chromatographic Conditions for EPA Method 8270 Calibration Standards

GC:	Agilent 6890N/5975B MSD
Sampler:	Agilent 7683B, 5.0- μ L syringe (Agilent p/n 5181-1273) 1.0 μ L splitless injection
Carrier:	Helium 30 cm/s, constant flow
Inlet:	Splitless; 260 °C, purge flow 50 mL/min at 0.5 min Gas saver 80 mL/min at 3 min
Inlet liner:	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Column:	Agilent HP-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 19091S-433UI)
Oven:	40 °C (1 min) to 100 °C (15 °C/min), 10 °C/min to 210 °C (1 min), 5 °C/min to 310 °C, hold 8 min
Detection:	MSD source at 300 °C, quadrupole at 180 °C, transfer line at 290 °C, scan range 45 to 450 amu

Table 2. Flow Path Supplies

Vials:	Amber screw top glass vials (Agilent p/n 5183-2072)
Vial caps:	Blue screw caps (Agilent p/n 5182-0723)
Vial inserts:	100 μ L glass/polymer feet (Agilent p/n 5181-8872)
Syringe:	5 μ L (Agilent p/n 5181-1273)
Septum:	Advanced Green (Agilent p/n 5183-4759)
Inlet liners:	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Ferrules:	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323)
20x magnifier:	20x magnifier loupe (Agilent p/n 430-1020)

Sample Preparation

A 12-component custom semivolatiles mix was purchased from Ultra Scientific (Kingston, RI) and used to prepare a seven-level calibration standard set. The stock semivolatiles solution as delivered had a nominal concentration of 2,000 μ g/mL. An internal standard mix as recommended by USEPA Method 8270 was purchased from AccuStandard (New Haven, CT). The internal/surrogate solution as delivered had a

nominal concentration of 4,000 µg/mL. The calibration standards were prepared with component and internal standard concentrations of 80, 40, 20, 10, 5, 2, and 1 µg/mL. All solutions were prepared in dichloromethane using class A volumetric pipettes and flasks. The dichloromethane used was Burdick and Jackson spectral grade purchased thorough VWR International (West Chester, PA). Dichloromethane was used as a reagent blank and syringe wash solvent.

The EPA 8270 Calibration Level 2 standard set was purchased from AccuStandard containing 83 semivolatile components and internal standards. The large mix calibration standard was prepared at an analyte concentration of 5 µg/mL.

Results and Discussion

Baseline Inertness Profile for Ultra Inert Columns

The basic approach for inertness verification for the Agilent J&W Ultra Inert series of capillary GC columns is testing with aggressive active probes at low concentration and low temperature. This is a rigorous approach that establishes consistent baseline inertness profiles for each column in the Agilent J&W Ultra Inert GC column series. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species that tend to adsorb onto active sites, particularly at trace level like the semivolatiles in this

application example. A more detailed description of the test mix and additional application examples can be found in references 2 through 7.

Semivolatiles Analysis (USEPA 8270)

In this application note a seven-level semivolatile calibration curve set was evaluated over the concentration range of 1 to 80 µg/mL on an Agilent J&W Ultra Inert HP-5ms 30 m × 0.25 mm × 0.25 µm (p/n 19091S-433UI). An example chromatogram of a 1-µL injection of the 1 µg/mL short mix calibration standard is shown in Figure 1. Scanning mode was used exclusively for this analysis.

Pentachlorophenol and benzidine are two components that are used to verify inlet and column inertness. Excessive peak tailing of these components would indicate column activity. Analysis of the short mix standard yielded sharp, symmetrical peak shapes for the problematic analytes as shown in Figure 2. Good separation was obtained in the analysis of the 5-ng on-column 8270 large mix standard for each of the semivolatiles, which is shown in Figure 3.

Semivolatile analysis by USEPA Method 8270 requires a minimum average RF of 0.050 for a system performance check compound such as 2,4-dinitrophenol. 2,4-Dinitrophenol is a highly active analyte that has proven to be one of the most challenging compounds, often yielding lower than expected




Figure 1. Total ion chromatogram (SCAN mode) of the 1-ng on-column EPA8270 short mix standard solution loading on an Agilent J&W HP-5ms Ultra Inert 30 m × 0.25 mm × 0.25 µm capillary GC column (p/n 19091S-433UI). Chromatographic conditions are listed in Table 1.




Figure 2. Enlarged section of the total ion chromatogram for a 1-μL injection of 1.0 μg/mL EPA 8270 short mix standard. The peaks of interest noted in the figure are two semivolatiles that are prone to peak tailing. Chromatographic conditions are listed in Table 1.




Figure 3. Total ion chromatogram (SCAN mode) of 5-ng on-column loading of EPA 8270 calibration (large mix) standard solution on an Agilent J&W HP-5ms Ultra Inert 30 m × 0.25 mm × 0.25 μm capillary GC column (p/n 19091S-433UI). Chromatographic conditions are listed in Table 1.

response factors at lower concentrations. In the analysis of the short mix calibration standard, the response for 2,4-dinitrophenol was greater than 0.1 at the 1-ng level. The average response was 0.15 over the concentration range studied. An example chromatogram for the signal-to-noise ratio for a 1-ng on-column loading of 2,4-dinitrophenol is shown in Figure 4. The signal-to-noise ratio for this difficult analyte was greater

than 16 to 1. This demonstrates the excellent performance of the HP-5ms Ultra Inert GC column.

Linearity was excellent across the range studied, giving R^2 values of 0.990 or greater for even the more difficult phenols. Figure 5 indicates the correlation coefficients for several of the more active analytes.




Figure 4. Enlarged section of the total ion chromatogram (scan mode) for a 1- μ L injection of 1 μ g/mL EPA Method 8270 short mix standard on an Agilent J&W HP-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 19091S-433UI). The peak in the figure is 2,4-dinitrophenol, one of the more demanding semivolatiles. This injection represents an on-column loading of 1 ng per component. Chromatographic conditions are listed in Table 1.




Figure 5. Correlation coefficients for some of the more challenging analytes in the EPA Method 8270 short mix standard over the 1 to 80 μ g/mL range of this study and an example linear regression plot for benzidine.

Conclusions

This application successfully demonstrates the use of an Agilent J&W HP-5ms Ultra Inert capillary GC column for low-level semivolatile organics. Linearity was excellent for all semivolatiles studied, yielding 0.99 or greater R^2 values down to a 1-ng column loading of each component. One of the reasons for excellent linearity and high R^2 values is the highly inert surface of the column. The lack of chemically active sites makes these columns an excellent choice for semivolatiles analyses.

This study was done using SCAN mode on an Agilent 6890N/5975B GC/MSD equipped with an inert electron impact source. The signal-to-noise ratio for a 1-ng on-column loading of 2,4-dinitrophenol was greater than 16 to 1 with this system. This result clearly shows the power of using an Agilent J&W HP-5ms Ultra Inert column for low-level semivolatile organics analysis. Lower limits of quantification are expected when using one of Agilent's latest GC/MS offerings, such as the 7890A/5975C GC/MSD Triple-Axis Detector coupled with an Agilent J&W HP-5ms Ultra Inert GC capillary column.

References

1. US EPA Method 8270D, Revision 4, February 2007, "Semivolatile Organic Compounds by Gas Chromatography/Mass Spectrometry (GC/MS)"
2. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenyltrimethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
3. "Agilent J&W Ultra Inert GC Columns: A New Tool to Battle Challenging Active Analytes," Agilent Technologies publication 5989-8685EN, May 29, 2008
4. Mike Szelewski and Bill Wilson, "Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270," Agilent Technologies publication 5988-3072EN, November 7, 2001
5. Kenneth Lynam, "Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column," Agilent Technologies publication 5989-8616EN, May 13, 2008
6. Kenneth Lynam and Doris Smith, "Polycyclic Aromatic Hydrocarbon (PAH) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9181EN, July 2008
7. Kenneth Lynam and Doris Smith, "Polybrominated Diphenyl Ether (PBDE) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9571EN, August 2008

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Published in the USA
January 20, 2009
5990-3416EN



Agilent Technologies



Fast Analysis of Polynuclear Aromatic Hydrocarbons Using Agilent Low Thermal Mass (LTM) GC/MS and Capillary Flow Technology QuickSwap for Backflush

Application Note

Environmental

Authors

Frank David
Research Institute for Chromatography
Pres. Kennedypark 26, B-8500 Kortrijk
Belgium

Matthew S. Klee
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Cycle time for GC-MS analysis of polynuclear aromatic hydrocarbons (PAHs) in soil and sediment samples was improved dramatically through the combined use of a narrow-bore (180- μm id) column installed in an LTM module and capillary column backflushing with QuickSwap. Improvements were achieved while maintaining resolution. Agilent Capillary Flow Technology enabled column backflushing to remove low-volatility material from the capillary column, reducing bakeout and maintenance time. The method resulted in increased sample throughput and lab productivity, while maintaining analytical performance.



Agilent Technologies

Introduction

The analysis of polycyclic (polynuclear) aromatic hydrocarbons (PAHs) by GC-MS is one of the most important applications in environmental analysis. In most reference methods, 16 target PAHs of particular toxicity and carcinogenicity are monitored, ranging from naphthalene (eluting first, MW = 128) to benzo(ghi)perylene (eluting last, MW = 276). Typically, PAH analyses are performed with a 30 m × 0.25 mm id × 0.25 µm 5% phenyldimethyl siloxane columns (for example, Agilent J&W HP-5MS or J&W DB-5MS) using a temperature program from 40–50 °C to 300–320 °C in 20 to 30 minutes of analysis time. The analysis of PAHs, therefore, covers the whole boiling point range of semivolatiles as typically covered in U.S. EPA Methods 525, 625, and 8270. These methods include compounds such as polychlorinated biphenyls (PCBs), phthalates, phenols, and most GC-amenable pesticides (for example, organochlorine, triazines, and organophosphorous). Any combination of these compounds is potentially present in PAH samples, in addition to hydrocarbon fuels and oils, complicating analysis of target PAHs. The use of mass spectrometers is required to facilitate reliable identification and quantitation.

Most labs are interested in maximizing lab efficiency and output. To this end, decreasing method analysis time and increasing sample throughput is often of interest. For this, columns of smaller diameter in combination with fast oven programming are an important option. However, a key challenge in PAH analysis is sufficient separation of key isomers (for example, benzo(b)fluoranthene and benzo(k)fluoranthene) since mass spectrometry is not able to differentiate them. Therefore, these isomers should be chromatographically separated, which requires columns of sufficient separation power and some careful choice in column flow and temperature ramp rates. Hence, it is important to use a tool like method translation software [1] to scale reference conditions appropriately.

Higher molecular-weight PAHs are potentially sensitive to cold spots and adsorption in the sample flow path. Problems with column connections, transfer line, source temperature, or activity in the inlet or column rapidly lead to peak tailing and loss of sensitivity. Although the compounds are considered apolar, PAH analysts find that frequent inlet, column, and source maintenance are needed when analyzing dirty samples (for example, sediment extract). A high source temperature (for example, ≥ 300 °C) and capillary column backflushing can greatly reduce the need for maintenance, thereby improving data quality and further increasing lab productivity.

In this application note, translation of a standard PAH method to a fast method using a 180-µm id column is demonstrated. To maximize sample throughput, fast column heating and cooling were further improved by using a low thermal mass (LTM) oven module. An Agilent Capillary Flow Technology QuickSwap capillary flow module was chosen for its ability to improve column replacement and system maintenance time, while providing the means to backflush the capillary column after the elution of the last PAH. As a result, low-volatility matrix compounds were efficiently removed, and maintenance interval greatly increased.

Experimental

Solutes and Sample

Tests were performed using a PAH standard mixture containing 16 PAHs in dichloromethane. The test mixture was obtained by dilution of a mixture in CH₂Cl₂/benzene (for example, Supelco, Bellefonte, PA, USA, cat no 48905, 2000 mg/mL) to 1 ng/µL (1 ppm) in dichloromethane.

A soil sample contaminated with mineral oil and PAHs was obtained from an environmental laboratory. 1 g of the soil was extracted in 20 mL dichloromethane (30 min ultrasonic treatment). This extract was filtered and analyzed directly as is typical in most high-volume environmental laboratories. The mineral oil concentration in the sample was approximately 5 g/kg. The concentrations of the PAHs were around 150 mg/kg for pyrene and fluoranthene and 5 to 10 mg/kg for the higher molecular-weight PAHs (for example, 9 mg/kg for benzo(a)pyrene). In the extract, the concentrations are 20 times lower (for example, 0.45 ng/µL for benzo(a)pyrene, assuming 100% extraction efficiency).

A sewage sludge sample (BCR-088, IRMM, Geel, Belgium) was also analyzed. 1 g of sludge was extracted in 20 mL of dichloromethane. The extract was filtered and analyzed directly. The sample contained concentrations of approximately 1 mg/kg of the higher molecular-weight PAHs (0.05 ng/µL benzo(a)pyrene in extract).

GC-MS Conditions

Analyses were performed on an Agilent 7890A GC – Agilent 5975C Series MSD system. The GC was equipped with an S/SI inlet, a QuickSwap device using a 17 cm × 110 µm id deactivated fused silica restrictor (G3185-60363), an AUX EPC module, and a LTM column module. The system configuration is diagrammed in Figure 1.




Figure 1. System configuration for fast GC analysis of PAHs using an LTM module and QuickSwap device for backflush.

Reference analyses were performed on a 30 m × 0.25 mm id × 0.25 µm Agilent J&W DB-5MS column, installed in the GC oven. For the fast method, a 20 m × 0.18 mm id × 0.18 µm J&W DB-5MS was used in LTM column format (p/n 121-5522LTM). Two pieces of 50 cm × 250 µm id deactivated fused silica tubing were used to connect the S/SI inlet to the column and from the column to the Quick-Swap device.

The final conditions for the 180-µm id column with backflushing are listed in Table 1.

Table 1. GC-MS Setpoints for Fast PAH Analysis Using a Low Thermal Mass Oven and QuickSwap Device for Backflush

Injection	1 µL, splitless mode, 280 °C
S/SI pressure program (He) (column inlet)	213 kPa (0.9 min), 60 kPa/min → 351 kPa, 7.5 kPa/min → 392 kPa (1.5 min), 600 kPa/min → 10 kPa (6 min)
AUX 1 (QuickSwap device, He) (column outlet)	28 kPa (10 min), 600 kPa/min → 250 kPa (6 min)
GC oven temperature	300 °C isothermal (17 min)
LTM oven program (translation of reference)	40 °C (0.9 min), 87 °C/min → 240 °C, 11 °C/min → 300 °C (8.35 min)
MS	SIM/Scan mode
Scan	50 to 300 <i>m/z</i> , samples = 2 ¹
SIM	See Table 2
Transfer line	280 °C
Solvent delay	2.70 min
MS temperatures	Source = 300 °C, Quad = 150 °C
Run table events	MS off at 10 min

Table 2. SIM Table

Group	Start time (min)	Ion (<i>m/z</i>)	Dwell time (msec)
1	2.70	128	50
2	3.00	152, 153, 154, 165, 166	25
3	3.65	178	50
4	4.20	202	50
5	5.00	228	50
6	6.50	252	50
7	8.50	276, 278	50

Results and Discussion

For reference, a mixture containing 16 PAHs at 1 ppm in dichloromethane was analyzed using the typical 30 m × 0.25 mm id × 0.25 µm J&W DB-5MS column. The column temperature was programmed from 40 °C (2 min) at 40 °C/min to 240 °C and then at 5 °C/min to 300 °C (11 min hold). A low initial temperature is typically applied when a low-boiling solvent such as dichloromethane is used in order to allow recondensation (solvent focusing) in the column. Higher initial temperatures can be used if higher-boiling solvents are used. With higher initial temperatures, both the run time and the cool-down time of the GC are reduced; however, method translations are only valid with the same starting temperature used in the reference method.

The reference chromatogram of the standard mixture is shown in Figure 2. The critical pair benzo(b)fluoranthene/ benzo(k)fluoranthene (peaks 11 and 12), eluted at 15 minutes, with sufficient resolution for quantification. The last solute, benzo(ghi)perylene, eluted at 19.7 minutes.

Next, the method was translated using GC Method Translation software [1] for the 20 m × 180 µm id × 0.18 µm column. Since separation power scales with length/diameter, the separation power of this column is very similar to that of the reference column. Through method translation, the inlet pressure and oven temperature program were scaled for the new column in fast analysis mode (one of the possible pre-sets in the software). The resulting conditions are listed in Table 1. The predicted speed gain was a factor 2.17.




Figure 2. Reference total ion chromatogram for conventional system configuration and method conditions. Peak identities are listed in Table 3.

The resulting chromatogram is shown in Figure 3. Comparing this chromatogram with the one in Figure 2, one can see that very similar resolution is obtained in about half of the retention time. Benzo(ghi)perylene elutes at 9.3 minutes, which corresponds well to the predicted retention time of 9.1 min-

utes (19.7/2.17). As expected, the resolution of benzo(b)fluoranthene and benzo(k)fluoranthene was similar to the separation obtained on the standard column. Resolution was maintained, while analysis time was reduced by a factor of 2.




Figure 3. Fast PAH method using 20 m × 0.18 mm id × 0.18 μm Agilent J&W DB-5MS LTM column and BF at 10 minutes. SIM chromatogram shown.

Using these conditions, a backflush can be initiated at 10 minutes. To accomplish backflush, inlet pressure was dropped to 10 kPa and outlet pressure (AUX 1, QuickSwap device) was raised to 250 kPa while the column temperature was maintained at 300 °C. These conditions resulted in efficient backflush of solutes in about 7 minutes. This time was found to be required (under the stated pressure conditions) for effective removal of sample contamination (mineral oil). During backflush, the mass spectrometer detector was switched off.

Retention time and peak area repeatability were tested by analyzing a series of six standard samples using the fast GC-MS (SIM/Scan) method in combination with backflushing. The results are given in Tables 3 and 4. The repeatability of retention times was excellent, with an average standard deviation of 0.001 minute (typically < 0.01% RSD). This confirms that the heating of the capillary column in the LTM oven is uniform. Also, the peak area repeatability was excellent (2% RSD on average) and similar to results obtained using splitless injection in combination with standard GC-MS conditions.

Table 3. Retention Time Repeatability of Target PAH Compounds Using the Fast Analysis Method

Order of elution	Compound name	Mean t_R (min)	σ	% RSD
1	Naphthalene	2.850	0.000	0.00
2	Acenaphthylene	3.280	0.000	0.00
3	Acenaphthene	3.326	0.000	0.00
4	Fluorene	3.481	0.000	0.00
5	Phenanthrene	3.825	0.000	0.01
6	Anthracene	3.846	0.000	0.00
7	Fluoranthene	4.429	0.001	0.01
8	Pyrene	4.583	0.001	0.01
9	Benz(a)anthracene	5.654	0.001	0.02
10	Chrysene	5.693	0.001	0.01
11	Benzo(b)fluoranthene	6.979	0.001	0.02
12	Benzo(k)fluoranthene	7.016	0.002	0.02
13	Benzo(a)pyrene	7.405	0.002	0.02
14	Indeno(123-cd)pyrene	8.910	0.002	0.02
15	Dibenz(ah)anthracene	8.968	0.002	0.02
16	Benzo(ghi)perylene	9.278	0.002	0.02
	Average		0.001	0.01

Table 4. Area Repeatability for Target PAHs

Order of elution	Compound name	Mean peak area	σ	% RSD
1	Naphthalene	2145022	45438.72	2.12
2	Acenaphthylene	2531734	57007.60	2.25
3	Acenaphthene	3410703	76081.85	2.23
4	Fluorene	3108369	66651.55	2.14
5	Phenanthrene	2341505	50290.78	2.15
6	Anthracene	2304885	46774.62	2.03
7	Fluoranthene	2598819	57961.99	2.23
8	Pyrene	2678698	58471.60	2.18
9	Benz(a)anthracene	2264966	58416.06	2.58
10	Chrysene	2597444	50507.12	1.94
11	Benzo(b)fluoranthene	2245073	50491.19	2.25
12	Benzo(k)fluoranthene	2954729	71902.33	2.43
13	Benzo(a)pyrene	2239967	57434.91	2.56
14	Indeno(123-cd)pyrene	1616395	56133.34	3.47
15	Dibenz(ah)anthracene	3065828	86273.62	2.81
16	Benzo(ghi)perylene	2511598	65387.08	2.60
	Average			2.37

Next, a real sample extract was analyzed with the fast method, applying backflushing at 10 minutes after elution of benzo(ghi)perylene. The chromatograms obtained in scan and SIM mode are shown in Figures 4 and 5. The chromatogram (Figure 4) shows the high background from mineral oil contamination of the sample. At 10 minutes, the drop in signal clearly signals the initiation of the backflush. Tests would later show that the mineral oil "hump" extends well after 24 minutes (ending temperature of 300 °C) when backflush is not used.

The SIM chromatogram in Figure 5 clearly shows the presence of PAHs in the sample (high concentration of phenanthrene through pyrene, lower concentrations of later-eluting PAHs; see inset).




Figure 4. Sample (soil extract) with fast method and backflush at 10 minutes. Scan TIC shown.




Figure 5. Sample (soil extract) with fast method and backflush at 10 minutes. SIM chromatogram shown with later portion expanded for better visibility.

A blank run was performed after the sample analysis with backflush. The resulting chromatogram in Figure 6 shows that no significant peaks were detected and that the background is flat, indicating that remaining mineral oil contamination was effectively removed with backflush.

One might question if the fast GC analysis (especially with temperature programming at 87 °C/min) in combination with SIM/Scan MS data acquisition mode results in enough data points per peak for accurate identification and quantification. The repeatability of peak areas, shown in Table 4, clearly demonstrates that the speed and repeatability of the Agilent 5975C Series MSD detection is excellent.

This is further illustrated in Figure 7, the AMDIS report for the detection of benzo(a)pyrene in the environmental sample. For this exercise, the scan data (as in Figure 3) were analyzed using AMDIS [2]. The upper window in Figure 7 shows overlaid TIC and extracted ion (m/z 252) chromatograms. The middle window confirms > 10 scans across the peak. The lower two windows show the raw spectrum and deconvolved spectrum, allowing unequivocal confirmation of the presence of benzo(a)pyrene in the sample. Even with the high background level, trace-level PAHs were reliably detected and confirmed.




Figure 6. Blank SIM/Scan run after sample extract analysis using backflush. Scan chromatogram shows clean baseline free of contamination.




Figure 7. AMDIS report on the detection of benzo(a)pyrene in soil extract in the presence of mineral oil.

An additional sequence of multiple runs without backflush was performed to illustrate the benefits of backflushing for elimination of sample carryover. Sample extract was analyzed with the LTM oven module programmed to 300 °C and held for 11 minutes (17 minutes total run time). An example TIC chromatogram is shown in Figure 8. It can be seen that the mineral oil envelope extends to 17 minutes (and beyond).




Figure 8. Soil extract analyzed without backflush. Scan chromatogram shows contribution of high mineral oil content in the extract.

Next, a blank run was performed. The chromatogram in Figure 9 shows that a significant portion of the mineral oil remained in the column even after the extended hold at the

higher temperature. Comparing the upper and lower chromatograms in Figure 9 (plotted with the same scale) clearly illustrates the efficacy of backflushing.




Figure 9. Blank run following the soil extract run without backflush (Figure 7). The upper TIC chromatogram shows high background carryover of matrix remaining on column after run. Bottom chromatogram is from Figure 6 (blank after method with backflush).

The standard mixture was then run after an analysis of sample extract without backflush. The resulting TIC chromatogram of the standard in Figure 10 shows several potential interferences from sample carryover in and among the PAH peaks. These contaminants are absent when backflushing is included in the method.

The extract of a sewage sludge was also analyzed. The sludge was contaminated with low-volatility plant material, phthalates, and linear alkyl sulphonates (LASs). A sequence was programmed wherein a 1-ppm PAH reference standard was analyzed first followed by 10 runs of the sewage sludge extract using backflush, one reference standard, another 10 runs of the sewage sludge extract without backflush, and a final reference standard. The chromatograms of the reference samples are overlaid in Figure 11. The two chromatograms of the references before and after the sample

analyses using backflush match perfectly and show a low baseline without ghost peaks. The last reference sample chromatogram (after 10 runs of sample without backflush) shows a significantly higher background, including ghost peaks.

From this test, it is clear that low-volatility material is not removed by the standard process of keeping the column at 300 °C for 7 minutes. By backflushing, this material is effectively removed. This improves not only the quality of the data, but also reduces or eliminates the need to trim the column due to accumulation of contaminants, a typical maintenance procedure for those running extracts without backflush. This demonstration should serve to assuage concerns about the use of LTM modules with dirty samples. This had been a concern in the past because the format does not accommodate column trimming.




Figure 10. GC-MS scan chromatogram of 1-ppm PAH standard after sample extract analysis with no backflush.




Figure 11. Standard analyses before and after analyzing sewage sludge extract with backflush and after analyzing sewage sludge extract without backflush.

A final review of improvements in analysis time revealed that the LTM column module provides an additional advantage of approximately 30% faster cooldown time compared to the conventional 7890A GC (even with fast cooling on). This further improves overall cycle time by one minute in addition to the savings from fast temperature ramp conditions and potential truncated run time from backflush.

Conclusions

A standard 25-minute method for the analysis of PAHs was translated to a fast GC-MS method using a narrow-bore column in an LTM column module. The resulting fast GC method decreased analysis time with elution of all PAHs within 10 minutes while maintaining resolution of critical isomers and method performance metrics.

The backflush capability afforded by using a Capillary Flow Technology QuickSwap capillary flow module resulted in efficient removal of high molecular-weight sample matrix and addresses prior concerns about column trimming with LTM columns. Faster run time, backflush, and faster cooldown combined in the new fast GC method with LTM significantly increase sample throughput and lab productivity while maintaining or improving data quality.

References

1. GC Method Translation Software available at <http://www.chem.agilent.com>.
2. AMDIS is an add-on to NIST Mass Spectral libraries. Information is available at <http://chemdata.nist.gov/mass-spc/amdis/>

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Printed in the USA
April 1, 2009
5990-3451EN



Agilent Technologies

Analysis of Semivolatiles Using High Efficiency Capillary GC Columns



Application Brief

Ken Lynam and Mike Szelewski

Introduction

U.S. EPA Method 8270 is broadly applicable for analysis of semi-volatiles using capillary gas chromatography with mass spectral detection. EPA 8270 is widely used in both contract analytical and government environmental laboratories. The method is capable of concurrently measuring a mixture of 70 to 100 acidic, basic, and neutral species. Shifting these important analyses from 0.25-mm id to 0.18-mm id or high efficiency GC columns is a viable means of obtaining faster results and improving laboratory productivity.

In this example, 77 compounds of interest and six internal standards are resolved on a 0.18-mm id high efficiency GC column using 7 minutes of analysis time. The same compounds and internal standards were also resolved using a 0.25-mm id column where 25 minutes of analysis time was required. Analysis speed using the high efficiency column was 8 minutes faster, resulting in a 32% reduction in analysis time.

Experimental

Method translation software available from Agilent Technologies translates chromatographic parameters from an existing method to the new column format with a few simple keystrokes [1].

Column dimensions, flow, and temperature parameters from an existing method are entered into a table along with the desired new column dimensions. The software then generates flow and temperature setpoints for the new translated method. Often these new setpoints yield a successfully translated method with the same separation and elution order with no additional method development. In this example, one-to-one phase-ratio correspondence was maintained between the 0.25-mm and 0.18-mm id column formats, enhancing the reliability of the software's predicted conditions. Keeping the phase ratio constant helps maintain peak elution order on the new column.

Instrument conditions are described in Table 1, and Figures 1 and 2.

Highlights

- 0.18-mm id, also known as high-efficiency GC columns, deliver faster results for U.S. EPA 8270 analyses.
- 32% reduction in analysis time when translating 0.25-mm id column method to the 0.18-mm id format.
- Resolution of 77 peaks of interest is maintained for the faster 0.18-mm id separation.
- DB-5.625 column: Agilent DB-5.625 column in 0.18-mm id provides faster sample analysis without loss of resolution.



Agilent Technologies

Table 1. Experimental Conditions

Column:	Figure 1. 30 m x 0.25 mm x 0.50 μ m DB-5.625 column, Agilent Technologies part number 122-5632 Figure 2. DB-5.625 20 m x 0.18 mm x 0.36 μ m column, Agilent Technologies part number 121-5622
Carrier:	He constant-flow mode 1.1 mL/min
Oven:	40 °C for 1.00 min, 25 °C/min to 320 °C 4.80 min hold
Injection:	Splitless 0.5 μ L injected at 300 °C, Quick-Swap pressure 5.0 psi during acquisition, 80.0 psi during backflush with inlet set to 1.0 psi during backflush
Detector:	Agilent Technologies 5975C Performance Turbo MSD equipped with a 6-mm large-aperture draw-out lens, Agilent Technologies part number G2589-20045




Figure 1. U. S. EPA Method 8270, 5 ng/mL System Performance Check Compounds Chromatogram using a 30-m x 0.25-mm x 0.50- μ m DB-5.625 column, Agilent Technologies part number 122-5632. Please refer to Table 1 for instrument conditions.




Figure 2. U.S. EPA Method 8270, 5 ng/mL System Performance Check Compounds Chromatogram using a 20-m x 0.18-mm x 0.36- μ m DB-5.625 column Agilent Technologies part number 121-5622. Please refer to Table 1 for instrument conditions.

Discussion of Results

Figures 1 and 2 depict the resolution of 77 compounds of interest along with six internal standards first on a 30 m x 0.25 mm x 0.5 μ m (Agilent part number 122-5632) standard-bore capillary column (Figure 1) and second on a 20 m x 0.18 mm x 0.36 μ m (Agilent part number 121-5622) high efficiency column (Figure 2). Peak resolution and quantification are comparable, and in both cases meet EPA 8270 criteria for System Performance Check Compounds (SPCCs) and Continuous Calibration Compounds (CCCs) over a calibration range from 1 to 200 ppm; 5 ppm SPCC chromatograms were selected for visualization purposes.

Significant improvement in analysis time was achieved by shifting the column used from a 0.25-mm id standard-bore capillary to a 0.18-mm id high efficiency GC column example; the 0.25-mm id column required 25 minutes of run time, and the 0.18-mm id column required 17 minutes. In this semi-volatile analysis example, 25 minutes of run time were required for the 0.25-mm id column, and 17 minutes were required on the 0.18-mm id column. Moving the analysis to a 0.18-mm id column yielded 8 minutes in time savings or 32% faster sample analysis.

Typical run time for EPA 8270 analysis using 0.25-mm id or standard-bore capillary columns is 25 minutes, excluding post-analysis bakeout and system cooldown time often required for dirty samples. When bakeout and subsequent system cooldown periods are accounted for, the overall cycle time climbs to 57 minutes. As shown above, a time saving of 8 minutes was achieved by using a high efficiency column. Further improvements in the cycle time for EPA 8270 analysis are achieved through the use of several advanced features on the Agilent 7890A GC. A QuickSwap device installed in a 7890A can be used to backflush heavy material matrix contaminants back out of the inlet, dramatically reducing matrix bakeout time [2]. Faster cooldown and thermal isolation features available on the 7890A GC also reduce system cycle times for dirty samples. The combination of a high efficiency column and the unique features of the 7890A reduce sample analysis time from 57 minutes to 24.3, a 32.7-minute time saving per sample run.

Conclusions

High efficiency GC columns provide a straightforward way to obtain faster results for EPA 8270 analysis without compromising resolution.

References

1. Method translation software: free download of method translation software available at <http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>.
2. Mike Szelewski, "Significant Cycle Time Reduction Using the Agilent 7890A/6975C GC/MSD for EPA Method 8270," Agilent Technologies publication 5989-6026EN

For More Information

For more information on our new line of high efficiency GC columns, please visit this link:
<http://www.chem.agilent.com/scripts/PDS.asp?lpage=60005>.

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
November 30, 2007
5989-7500EN



Agilent Technologies



Separation of Explosives in EPA 8330: Column Choices Optimize Speed, Resolution, and Solvent Use

Application

Environmental

Authors

John W. Henderson Jr. and William J. Long
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

ZORBAX Extend-C18 columns separate the explosive compounds in EPA method 8330, and the variety of column configurations available allows customized HPLC methods based on resolution, speed, and even solvent usage. For example, a fast method for the explosive-materials standard (EPA 8330) uses 1.8- μ m, short length columns. The method was then customized using two other Extend-C18 column configurations. Each column highlights a combination of resolution, speed, and/or solvent savings. The advantage is being able to choose which combination of resolution, speed, and solvent usage is needed by simple column substitution.

Introduction

The ZORBAX Rapid Resolution High Throughput (RRHT, 1.8 μ m) LC column line has over 120 column choices, including 11 bonded phases and silica, three column diameters, and six lengths. In addition, there are another 150+ Rapid Resolu-

tion (3.5 μ m) column choices, allowing customization of HPLC methods to meet the analyst's tailored objectives. Many ZORBAX column choices are available because the stationary phase chemistry (both silica support and bonded phase) between 5-, 3.5- and 1.8- μ m particles is uniform.

EPA 8330 explosives residues are typically analyzed by a 4.6 mm $\times$ 250 mm, 5 μ m C18 column [1] but can be improved by newer technology: smaller 1.8- μ m or 3.5- μ m ZORBAX particles and Extend-C18 bonded phase. Many different Extend-C18 columns can be chosen (the combination of column length, diameter, and particle size) to provide a satisfactory separation, and each separation exemplifies a newer column technology's benefit and supports the end user's choice of speed, resolution, and solvent usage.

High-efficiency 1.8- μ m particles in 100-mm length columns reduce analysis time and have about the same efficiency compared to 5- μ m particles in 250-mm columns. Therefore, they are helpful by saving time in method development or generating more data in a limited amount of time. But these columns will generate a higher back pressure that some people may not desire. It is still possible to obtain the same resolution but using a longer 3.5- μ m column. The end result is an analysis time still shorter than that achieved with a 250-mm, 5- μ m column.



Agilent Technologies

Experimental

The Agilent 1200 Rapid Resolution LC (RRLC) system:

- G1312B binary pump SL with mobile phase
A: 5 mM ammonium formate in water,
B: methanol
- G1376C automatic liquid sampler (ALS) SL
- G1316B Thermally Controlled Column (TCC) Compartment SL using the low-volume heat exchanger kit (PN G1316-80003)
- G1365C multiwavelength detector (MWD) at 254 nm, with a G1315-60024 micro flow cell (3-mm path, 2- μ L volume), response time setting of 0.5 s

ZORBAX columns:

- Rapid Resolution High Throughput (RRHT) Extend-C18, 4.6 mm $\times$ 100 mm, 1.8 μ m, PN 728975-902
- Rapid Resolution (RR) Extend-C18, 4.6 mm $\times$ 100 mm, 3.5 μ m, PN 764953-902
- Solvent Saver Plus Extend-C18, 3.0 mm $\times$ 100 mm, 3.5 μ m, PN 764953-302

The sample is a 1:1 mix of EPA 8330 Mix A (cat. no. 47283) and EPA 8830 Mix B (cat. no. 47284) from Sigma-Aldrich (Bellefonte, PA), diluted in methanol:water.

Results and Discussion

Selectivity, or the relative band spacing between two peaks, is different among C18 columns. In many cases the difference is small, so adjusting mobile phase organic strength can fine tune the retention to achieve comparable resolution between one C18 column and an alternative C18 column. Temperature may also influence selectivity, and small adjustments in temperature can fine tune the resolution.

For complex mixtures, fine tuning organic strength and temperature could be used to improve resolution and ultimately make a method more robust. Determining the combination of temperature, % organic, and what column (stationary phase) is best is frequently discovered by experimentation. This is time consuming at the very least and often daunting. Fortunately, research narrows the testing.

Consider an explosive residue standard of 14 nitroaromatic and nitramine compounds. Trace residues of these explosives were analyzed by time-of-flight LCMS by Kinghorn et al. using an Extend-C18, 4.6 mm $\times$ 250 mm, 5- μ m column and a methanol/water gradient at a temperature of 40 °C [2]. Additionally, EPA method 8330 describes an HPLC method for the 14 compounds using an isocratic methanol/water mobile phase and a C18 column. Temperature is not specified, but the method states, *"If column temperature control is not employed, special care must be taken to ensure that temperature shifts do not cause peak misidentification."* [1]

In both methods a lack of selectivity required a TOF detector or additional analysis by an orthogonal stationary phase to confirm peak identity.

We separated the 14 compounds with enough resolution to make the MS detector or secondary analysis by a different stationary phase redundant.

The above methods narrowed our method-development starting conditions to:

- Extend-C18 (from successful Kinghorn method)
- Isocratic mobile phase A: 5 mM ammonium formate, B: Methanol (so new method is similar to EPA 8330). The ammonium formate was selected based on recommendations from a pre-existing method. The difference between water and 5 mM ammonium formate was not investigated.
- 40 °C controlled temperature (to ensure constant selectivity)
- RRHT column configuration 4.6 mm $\times$ 100 mm, 1.8 μ m (for rapid analyses with efficiency comparable to the 4.6 mm $\times$ 250 mm, 5- μ m columns used in the Kinghorn and EPA methods)

The methanol composition of the mobile phase was lowered incrementally from 50 to 25% until all 14 were reasonably resolved. A critical pair (peaks 6 and 7) persisted as partially resolved. Further decreasing organic strength would result in excessive retention of peaks 12, 13, and 14. Temperature was then optimized. A one-degree temperature increase (41 °C) provided enough selectivity to resolve the critical pair. Figure 1 demonstrates temperature's selectivity effect on these compounds.




Figure 1. Temperature optimizes critical pair resolution.

Extend-C18 provides ample selectivity for the 14 nitroaromatics and nitramines identified in the EPA 8330 method; excellent resolution is obtained in a reasonable time. Figure 2 shows the separation using a RRHT 4.6 mm × 100 mm, 1.8 μm, Extend-C18. Resolution of all peaks is baseline or better ($R_s > 1.5$). High resolution makes it easier to quantify the analytes. For example, the EPA 8330 method warns, “2,4-DNT and 2,6-DNT elute at similar retention times ($R_s < 1.5$) and a large

concentration of one isomer may mask the other; therefore, if it is not apparent that both isomers are present, an isomeric mixture should be reported” [1]. When baseline resolution is obtained, retention times differ significantly, avoiding peak masking. If higher resolution is the most important objective, then the Extend-C18 4.6 mm × 100 mm, 1.8-μm column using the conditions in Figure 2 is an excellent choice.




Figure 2. EPA 8330 explosive standard high-resolution separation on Extend-C18.

Table 1 names the 14 explosives and their abbreviations used in the figures.

Table 1. EPA 8330 Explosives and Their Abbreviations

Name	Abbreviation
Cyclotetramethylene-tetranitramine	HMX
Cyclotrimethylene-trinitramine	RDX
1,3,5-trinitrobenzene	135TNB
1,3-dinitrobenzene	13DNB
Nitrobenzene	NB
2,4,6-trinitrophenyl-N-methylnitramine	tetryl
2,4,6-trinitrotoluene	TNT
2-amino-4,6-dinitrotoluene	2A DNT
4-amino-2,6-dinitrotoluene	4A DNT
2,4-dinitrotoluene	24 DNT
2,6-dinitrotoluene	26 DNT
2-nitrotoluene	2NT
4-nitrotoluene	4NT
3-nitrotoluene	3NT

If higher throughput is important, isocratic methods can be sped up by increasing flow rate. The 25% methanol mobile phase flowing 1.7 mL/min through the 4.6 mm × 100 mm, 1.8- μ m column generates a system pressure of about 500 bar, leaving

a small range to increase flow rate. An alternative is to substitute the 1.8- μ m column with a 3.5- μ m column. Pressure decreases substantially, allowing faster flow rates.

Figure 3 overlays two Extend-C18 chromatograms. The top chromatogram is a 4.6 mm × 100 mm column with 3.5- μ m particles at a 2.5 mL/min flow rate. Compared to Figure 2, the 32% increase in flow rate reduces analysis time by roughly 40%. The price for the considerable time savings is less resolution of closely neighboring peaks. Resolution is still sufficient, as a resolution factor (R_s) of 1.25 for equally sized peaks means 99.4% of peak area is not overlapped. If one peak is 1/32 as tall as the other, an R_s of 1.0 still means 99.2% of the peak areas do not overlap [3].

Figure 3's bottom chromatogram is a different column substitution, replacing the 4.6-mm-id column with the Solvent Saver 3.0-mm-id column. Flow rate was reduced from 2.5 to 1.1 mL/min. for equivalent mobile phase linear velocity. The outcome is similar retention and resolution, but only half of the solvent is consumed.

Table 2 summarizes the customization benefits.




Figure 3. Rapid resolution options for EPA 8330 explosive standard on Extend-C18.

Table 2. Column Dimensions Highlight Resolution, Speed, and Solvent Savings

	RRHT (4.6 mm id, 1.8 µm)	RR (4.6 mm id, 3.5 µm)	Solvent Saver Plus (3.0 mm id, 3.5 µm)
Resolution: Rs 7,6	2.3	1.3	1.3
Resolution: Rs 8,7	1.6	1.6	1.4
Resolution: Rs 9,8	2.3	1.5	1.6
Analysis time	26 min	16 min	16 min
Solvent consumption	44.2 mL/analysis	40 mL/analysis	17.6 mL/analysis

Table 2 suggests that another column configuration could be valuable for this analysis: Solvent Saver HT Extend-C18, 3.0 mm × 100 mm, 1.8-µm column (PN 728975-302). This would produce high resolution like the RRHT column and produce time and solvent savings from the smaller column diameter. The Solvent Saver HT Extend-C18 column was not evaluated in this work.

Conclusions

Highly efficient (1.8 µm) short columns (100 mm) are ideal for method development compared to 5-µm, 150-mm or 250-mm columns because shorter analysis time increases productivity and allows more analyses to be performed in a fixed time frame.

Selectivity is manipulated by changing stationary phase, mobile phase, and temperature.

An isocratic HPLC method for complex mixtures of explosive materials was quickly created from highly efficient 100-mm columns, Extend-C18's unique selectivity, and temperature optimization. The selectivity and column configurations make Extend-C18 a compelling choice for the analysis of explosive substances named in EPA method 8330. Extend-C18's selectivity provides ample resolution with negligible peak coelution; this may eliminate an additional analysis to confirm peak identity.

The ZORBAX column family, including Extend-C18, has consistent stationary-phase chemistry between 3.5- and 1.8-µm particles, enabling simple column substitution for method customization. The high-resolution 4.6 x 100, 1.8-µm configuration, however, requires flexibility to work at operating pressures above 400 bar. The chromatographer can choose benefits such as higher resolution, faster analysis time, or less solvent usage based on column dimensions.

References

1. EPA Method 8330, *Nitroaromatics and Nitramines by High Performance Liquid Chromatography (HPLC)*, revision 0, September 1994
2. R. Kinghorn, C. Milner, J. Zweigenbaum, "Analysis of Trace Residues of Explosive Materials by Time-of-Flight LC/MS," Agilent publication 5989-2449EN (2005)
3. L. R. Snyder, J. J. Kirkland, *Introduction to Modern Liquid Chromatography*, 2nd ed., pp. 38–42, 1979

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
November 21, 2007
5989-7632EN



Agilent Technologies



Synchronous SIM/Scan Low-Level PAH Analysis Using the Agilent Technologies 6890/5975 inert GC/MSD

Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of Polynuclear Aromatic Hydrocarbons (PAHs) presents challenges due to the tendency of the PAHs to adsorb on surfaces in the chromatographic system. Selected Ion Monitoring (SIM) analysis is needed for low-level analysis, while scan data are desired for confirmation. The 6890/5975 inert GC/MSD system is designed for improved PAH analysis using synchronous SIM/scan while maintaining linearity across a wide calibration range.

Introduction

PAHs are produced during combustion of organic material and are suspected carcinogens. The high amounts and widespread occurrence of these compounds in our environment requires reliable, sensitive, and very robust analytical methods.

PAHs tend to be adsorbed on any active or cold site in a GC/MSD system, such as inlets and ion sources. The 6890/5975 inert includes the inert source with high temperature filaments described previously [1]. Using the proper inlet liner also improves chromatographic peak shape and sensitivity.

Many laboratories calibrate for PAHs from 0.1 ppm to 10 ppm using SIM for low-level work. Historically, SIM has been necessary because of instrument sensitivity and loss of PAHs at the lower concentration levels. Full scan data is preferred for further confirmation of the compounds. The 5975 inert can acquire both SIM and scan data in a single run.

This application note will show the performance of the 6890/5975 inert for PAHs using a calibration range of 0.01 ppm–10.0 ppm in synchronous SIM/scan mode with linearity equal to that of many SIM only methods.

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized.



Agilent Technologies

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet	EPC Split/Splitless		
Mode	Pulsed Splitless, 1 µL injected		
Inlet temp	300 °C		
Pressure	13.00 psi		
Pulse pressure	40.0 psi		
Pulse time	0.20 min		
Purge flow	30.0 mL/min		
Purge time	0.75 min		
Total flow	34.6 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet Liner	Description	Agilent part number	
	Direct connect, dual-taper, 4-mm id	G1544-80700	
	or Splitless liner, single-taper, 4-mm id	5181-3316	
Oven 240 V			
Oven ramp	°C/min	Next °C	Hold min
Initial		55	1.00
Ramp 1	25	320	3.00
Total run time	14.60 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS	19091S-433	
Length	30.0 m		
Diameter	250 µm		
Film thickness	0.25 µm		
Mode	Constant Flow = 1.5 mL/min		
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
RTL	System Retention Time Locked to Triphenyl phosphate at 10.530 min		
MSD	Agilent Technologies 5975		
Drawout lens	6-mm ultra-large aperture	G2589-20045	
Solvent delay	4.00 min		
EM voltage	Run at Autotune voltage = 1294 V		
Low mass scan	45 amu		
High mass scan	450 amu		
SIM	12 groups, 3–6 ions/group, 10 ms dwell/ion		
Threshold	0		
Sampling	1		
Cycles/s	5.55 each, SIM and scan		
Quad temp	180 °C		
Source temp	300 °C		
Transfer line temp	280 °C		
Emission current	Autotune value = 34.6 µamp		

Calibration Standards

Calibration standards were diluted in dichloromethane from a stock mix of 16 PAHs. The 10 levels made were 10, 5, 2, 1, 0.5, 0.2, 0.1, 0.05, 0.02 and 0.01 ppm. The perylene-d12 internal standard and the three surrogate standards, 1,3-dimethyl-2-nitrobenzene, pyrene-d10 and triphenylphosphate, were added to each calibration level at 1.0 ppm.

The 6890 inlet temperature was set to 300 °C, instead of the typical 250 °C, to minimize compounds adsorbing on the liner surface. Pulsed injection was used to facilitate quantitative transfer of the heavier PAHs onto the column, minimizing inlet discrimination. Pulsed injection parameters are easily set in the ChemStation software and are automatically controlled by the EPC (Electronic Pneumatic Control) module.

The Direct Connect inlet liner allows for complete transfer of analytes onto the column. The column inlet end attaches to the liner and minimizes analyte exposure to the stainless steel annular volume in the inlet. The splitless liner, 5181-3316, yields better peak shapes for early eluters at the expense of lower amounts of analytes transferred to the column. Neither of these liners is well suited for split injections. Higher concentration samples requiring split injection would need a cyclosplitter-type liner, also suitable for splitless.

The 6890N 240V oven was necessary for the 25 °C/min ramp used up to the final temperature of 320 °C. A 120 V oven will achieve 20 °C/min at these higher temperatures and could be used, resulting in slightly longer run times.

The HP-5MS column is the most widely used column for environmental analysis. It has excellent lifetime and stability at elevated temperatures.

The system was Retention Time Locked to Triphenyl phosphate at 10.530 min. See the fundamentals of Retention Time Locking (RTL) for GC/MSD systems [2]. The primary benefit of RTL for the environmental laboratory is the ability to maintain retention times after clipping or changing the column. Quant database and integration events times do not have to be changed. For laboratories

performing PAH SIM analyses, reproducible retention times are a must so SIM group times remain constant. Additional RTL application notes are available at www.agilent.com/chem, detailing the numerous benefits of RTL.

The 5975 inert was tuned using Autotune. The automatic DFTPP target tune, as required by some government methods, can also be used. The ultra-large aperture drawout lens was used to maintain linearity across the wide calibration range of 0.01–10.0 ppm. Source temperature was set to 300 °C, which is now possible with the high temperature filaments. This higher source temperature in combination with the new source material produces better peak shapes for the PAHs.

Data were collected using the synchronous SIM/scan mode available with the 5975 inert. A quant database is first setup using full scan data. SIM ions and groups are then determined automatically using Generate AutoSIM Method. A checkbox in data acquisition is used to acquire SIM and scan data in the same run. For details of synchronous SIM/scan, see reference 3.

Results

The system was calibrated at 10 levels: 0.01, 0.02, 0.05, 0.1, 0.2, 0.5, 1.0, 2.0, 5.0, and 10.0 ppm using the SIM data from SIM/scan acquisition. The calibration table allows the user to choose either the SIM or scan data. The TIC (Total Ion Chromatogram) for the 0.2 ppm level is shown in Figure 1, both SIM and scan traces. Each calibration level contained 16 PAHs, perylene-d12 (ISTD) and the three surrogate standards, 1,3-dimethyl-2-nitrobenzene, pyrene-d10, and triphenyl phosphate.




Figure 1. Sixteen PAHs at 0.2 ppm each with surrogates and ISTD at 1.0 ppm each, using synchronous SIM/scan mode.

The RRF (relative response factor) was calculated automatically for each compound at each level by the GC/MSD ChemStation software. Linearity was determined by calculating the %RSD (percent relative standard deviation) of the RRFs across the calibration range for each compound. This is also done automatically by the software in conjunction with Excel.

Linearity is excellent with the average of all %RSDs = 6 %. This compares favorably with other methods that are SIM only or those that only calibrate down to 0.1 ppm.

There were 5.55 SIM cycles/s and 5.55 scans/s acquired throughout the run. This yields 11 SIM data points and 11 scan data points across a typical peak.

Full scan data are also available for further PAH confirmation using library searching. Figure 2 shows a full scan spectrum from benzo[ghi]perylene, together with its library match. Unknown peaks for which SIM data were not acquired can also be library searched. A more reliable, faster method for identifying all the peaks is the use of Deconvolution Reporting Software [4].




Figure 2. Spectrum from scan at 13.662 min with NIST05 Library match.

Conclusions

The 6890/5975 inert shows much improved response and peak shape for PAHs due to the inert source material and higher allowable source temperature. This improved response gives better linearity across the calibration range. Analysis of PAHs can be accomplished using synchronous SIM/scan data acquisition over a calibration range of 0.01 ppm to 10 ppm, while maintaining performance similar to SIM methods. Sensitivity of SIM is achieved while providing full scan data for confirmation of PAHs and identification of unknowns in a single run.

References

1. Mike Szelewski, "Full Scan Low Level Polynuclear Aromatic Hydrocarbon Analysis using the Agilent Technologies 6890/5973 inert Gas Chromatograph/Mass Selective Detector", Agilent Technologies, publication 5989-0264EN, www.agilent.com/chem.
2. K. Weiner, N. Mata and P. Wylie, "Retention Time Locking with the G1701BA MSD Productivity ChemStation", Agilent Technologies, publication 5968-3433E, www.agilent.com/chem.
3. Chin-Kai Meng, "Improving Productivity with Synchronous SIM/Scan", Agilent Technologies, publication 5989-3108EN, www.agilent.com/chem.
4. Philip L. Wylie, Michael J. Szelewski, Chin-Kai Meng, and Christopher P. Sandy, "Comprehensive Pesticide Screening by GC/MSD using Deconvolution Reporting Software", Agilent Technologies publication 5989-1157EN, www.agilent.com/chem.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
November 9, 2005
5989-4184EN



Agilent Technologies



Applying the 5975 inert MSD to the Higher Molecular Weight Polybrominated Diphenyl Ethers (PBDEs)

Application

Environmental, Component Testing

Author

Harry F. Prest
Agilent Technologies, Inc.
Santa Clara, CA
USA

This note presents the full scan spectra obtained for the PBDEs over the extended mass range of the 5975 inert MSD. The polymeric sample preparation and extraction protocols are cited elsewhere and supply two approaches to PBDE determinations [1].

Abstract

A previous application note presented results for analysis of the polybrominated diphenyl ethers (PBDEs) in polymers using the 5973N inert MSD [1]. Mass spectra were presented and interpreted for all of the important PBDEs. The new 5975 inert MSD provides many new features and improvements with expanded mass range to 1050 u being but one. This note presents the full spectra of the octa-, nona and decabrominated biphenyls ethers including ions that appear beyond the mass range of the previous 5973 MSD platform.

Introduction

PBDEs have become the “new PCBs” due to their widespread detection throughout the ecosystem. They have some structural and consequently mass spectral features in common with the polychlorinated biphenyls (PCBs) as well. The series of fragments formed by loss of chlorines ($M-nCl_2$) generates a number of intense ions useful in their determination. The PCBs also show relatively intense molecular ion clusters that assist in distinguishing the congeners. Similar attributes are expected and hoped for the PBDEs which show much more analytical difficulty than the PCBs.

Experimental

PBDE standards were acquired from Cambridge Isotope Laboratories (Andover, MA) and AccuStandard (New Haven, CT).

Instrumental Configuration and Conditions

The 6890 GC configuration and conditions are given in the previous application note [1]. The 5975 inert MSD system was operated in scan mode for acquisition of the PBDE spectra. The MSD scan operating parameters are cited in Table 1.

Table 1. 5975 inert MSD Configuration and Parameters

Mass spectrometer parameters	
Ionization mode	Electron impact
Ionization energy	70 eV
Tune parameters	Autotune
Electron multiplier voltage	Autotune + 400V
Scan mode	200–1000 u
Quadrupole temperature	150 °C
Inert source temperature	300 °C

Full conditions and parameters, as appropriate to the polymer analysis cited in reference 1, are available in the eMethod for this analysis (www.agilent.com/chem/emethods).



Agilent Technologies

Results

EI Spectra of the Higher Molecular Weight PBDEs

Figures 1, 2, and 3 present the full-scan spectra of an octa-, nona- and the decabromodiphenyl ether. Note that most intense ions in all cases are the $[M-Br_2]^+$ and the corresponding to $[M-Br_2]^{+2}$ ions. The relative abundance of the molecular ion clusters $[M]^+$ are under 30%. Figure 4 compares the

theoretical isotopic pattern to that experimentally obtained by the 5975 inert MSD. Agreement is good in both the abundance of the isotopes and the mass accuracy using the standard system Autotune. Mass accuracy agrees to within 0.2 m/z of the theoretical and experimental values. Table 2 presents the important ions for the PBDEs greater than the dibromodE. These ions are those most important to characterizing the technical mixtures used as additives to polymers.




Figure 1. Electron impact ionization spectrum of an octabromodiphenyl ether (PBDE-203) from 200 to 810 m/z .




Figure 2. Electron impact ionization spectrum of a nonabromodiphenyl ether (PBDE-208) from 200 to 890 m/z .




Figure 3. Electron impact ionization spectrum of the decabromodiphenyl ether (PBDE-209) from 200 to 1000 m/z .




Figure 4. Experimental spectrum of the decabromodiphenyl ether (PBDE-209) molecular ion cluster $[M]^+$ versus theory.

Table 2. Important Ions for the PB_nDEs ($n > 2$)

PBDE bromination	$[M]^+$	$[M-Br_2]^+$	$[M-Br_2]^{+2}$
3	405.8	246.0	123.0
4	485.7	325.9	162.9
5	563.6	403.8	201.9
6	643.5	483.7	241.9
7	721.5	561.6	(280.8 **)
8	801.4	641.5	320.8
9	879.3	719.4	359.7
10	959.2	799.3	399.7

**The 280.8 and 281.8 m/z ions can be compromised by column bleed interferences so these have not been used in acquisition although they provide a useful diagnostic for column degradation.

The user should note the ion source and quadrupole temperature settings in Table 1. Figure 5 presents SIM acquisitions of several higher molecular weight PBDEs at source temperatures of 300 °C and 230 °C. Notice the signal height roughly doubles on average for the PBDEs at the higher ion source temperature. The insert in the figure shows the improvement in the peak shape for the hexabrominated diphenyl ether. This peak sharpening accounts for the increase in signal height. Since these compounds elute at higher temperatures

among other high boiling components that belong to the matrix, heating the quadrupole is important for robust and low maintenance operation in samples.




Figure 5. Overlaid RIC SIM acquisitions of five PBDEs at ion source temperatures of 230 °C and 300 °C. Insert is expanded view of hexa-BDE overlays near baseline.

Conclusions

The new 5975 inert MSD has an expanded set of features including mass range. High mass accuracy under standard autotuning is obtained even at the high masses typical of the brominated diphenyl ethers. As users survey higher mass compounds, the heated quadrupole and high temperature capabilities of the 5975 inert MSD will become even more important to rugged and robust analyses in complicated samples.

More details on the other relevant instrumental parameters are available in the eMethod (www.agilent.com/chem/emethods).

Reference

1. C. Tu, and H. Prest, Determination of polybrominated diphenyl ethers in polymeric materials using the 6890 GC/5973N Inert MSD

with electron impact ionization. Agilent Technologies, publication 5989-2850EN, www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
June 13, 2005
5989-3142EN



Agilent Technologies



Determination of Polybrominated Diphenyl Ethers in Polymeric Materials Using the 6890 GC/5973N inert MSD with Electron Impact Ionization

Application

Environmental, Component Testing

Authors

Chuanhong Tu
Agilent Technologies, PuDong
Shanghai CHINA

Harry F. Prest
Agilent Technologies, Inc.
Santa Clara, CA
USA

Abstract

Due to their ubiquitous appearance in the ecosphere, various polybrominated diphenyl ether formulations have been banned. A major application of PBDEs is to impart fire retardancy to plastics used in electronics and electrical applications. This application note details an approach to determining the PBDEs present in the technical formulations in polymers. The instrumental analysis uses GC/MS with selected-ion monitoring (SIM) to determine tri-BDEs through the decaBDE in 15 minutes. Full scan spectra are presented for the PBDEs with interpretation and to provide an explanation of the choices in SIM ions. To insure correct identification of the PBDE isomers and allow rapid and convenient implementation in the laboratory, Retention Time Locking is applied to an internal standard. A sample preparation scheme referenced in this document provides two flexible and simple approaches to processing polymeric materials for this instrumental technique. PentaBDE, OctaBDE and DecaBDE technical formulations are characterized under the method and results for a typical high-impact polystyrene sample are also presented.

Introduction

Polybrominated diphenyl ethers (PBDEs) are a major issue in discussions of persistent organic contaminants. The detection of PBDEs in essentially all compartments of the ecosystem, including human serum and breast milk, has resulted in a ban of the manufacture and use of certain PBDE formulations by the European Union (EU). Some companies have made it a policy not to allow these compounds in their components and have insisted their suppliers comply. Because the PBDEs are added at percent concentrations (as w/w), the usage of these formulations has been prodigious. Global consumption in 2001 was estimated at 7500, 3790, 56100 metric tons, for the PentaBDE, OctaBDE and DecaBDE technical formulations, respectively.

PBDE analysis even at these relatively high concentrations is challenging in several respects. The PBDEs are a complicated class of compounds and their utility in suppressing combustion also makes them relatively fragile and subject to degradation in GC analysis. This was demonstrated by using shorter GC columns to improve PBDE responses, the most significant improvement being for the deca-BDE (BDE 209) [1]. The loss in congener resolution is less important in this application because the technical mixtures most frequently applied in polymers predominantly consist of isomers extending from the tri-BDEs to the deca-BDE and far less than the 209 possible congeners. Distinguishing congeners on the basis of their electron impact (EI) mass spectrum may be possible since there appears to be some differences in their spectra, however the most reliable index remains retention time (RT). For this reason, compound



Agilent Technologies

Retention Time Locking (RTL) is used to simplify identification and reproduction of the method in the user's laboratory.

Another complication is in sample preparation. There are several methods for extracting PBDEs from polymers each with advantages and disadvantages [2]. Of the many methods, the two approaches applied in processing samples for this application note are relatively inexpensive, simple, universal in application and in their acceptance, and allow for high sample throughput with minimal polymeric interferences. They are polymer dissolution and soxhlet extraction.

Experimental

Polymer samples were obtained from Agilent customers in the electrical and electronic component industries. Specific details of the polymer dissolution and soxhlet extraction methods are presented elsewhere [3]. In summary, the methods extract PBDEs from the sample via solvent, a dilution is made into toluene and PCB 209 is added to follow the dilution factor. Prior to injection, PCB 207 is added as an internal (injection) standard. Standards were made taking into account the potential percent concentration range of the PBDEs in polymeric samples and dilution factors used in the method.

PBDE standards were acquired from Cambridge Isotope Laboratories (Andover, MA) and AccuStandard (New Haven, CT). PCBs 209 and 207 were acquired from AccuStandard (New Haven, CT). Solutions were made in toluene of Burdick & Jackson solvent (VWR Scientific, San Francisco, CA).

Instrumental Configuration and Conditions

The 6890 GC and 5793N-inert MSD (mass selective detector) system configuration and conditions are given in Table 1. The GC is operated under constant flow conditions developed by applying RTL to lock the PCB 209 internal standard RT at 9.350 minutes. The 5793N inert MSD was equipped with the new Performance Electronics upgrade and allowed a single SIM group containing 24 ions to be used. The SIM ions are listed in Table 1 and were acquired with a dwell of 10-ms. This single SIM group method can be used to develop a preliminary method that can be further refined into multiple SIM groups by applying the AUTOSIM utility if the user wishes [4]. This is recommended for 5793-MSDs using standard electronics and targeting only congeners known to predominate in the particular technical mixture.

Table 1. GC and MSD Configuration and Parameters

Injection parameters

Injection mode	Pulsed splitless		
Injection volume	1 µL		
Injection port temperature	320 °C		
Pulse pressure and time	15.8 psi	1.80 min	
Purge flow and time	50.0 mL/min	2.00 min	
Gas saver flow and time	20.0 mL/min	3.00 min	

DB-5ms Column and oven parameters

GC column	DB-5ms (15 m × 0.25 mm id, 0.1 µm film) (p/n: 122-5511)		
Flow and mode	1.8 mL/min	Constant flow	
RTL parameters	9.350 min	RTL compound PCB 209	
Detector and outlet pressure	MSD	Vacuum	
Oven temperature	90 °C	1.00 min	
program	20 °C/min	340 °C	2.00 min
Oven equilibrium time	1.0 min		
Total program time	15.5 min		
MSD transfer line temp	320 °C		

Mass spectrometer parameters

Tune parameters	Autotune		
Electron multiplier voltage	Autotune + 400V		
Solvent delay	6.5 min		
Quadrupole temperature	150 °C		
Inert source temperature	300 °C		

Mass spectrometer SIM ions for single group

405.8	246.0	123.0
485.7	325.9	162.9
563.6	403.8	201.9
643.5	483.7	241.9
721.5	561.6	320.8
799.4	641.5	360.7
719.4	461.7	399.7
463.7	497.7	499.7

*Optional addition of m/z 280.8

Miscellaneous parts

Septa	5182-0739	BTO septa (400 °C)
Liner	5181-3315	Deactivated 4-mm id double taper
GC column ferrule	5181-3323	250 µm Vespel/Graphite
MSD interface ferrule	5062-3508	0.4-mm id preconditioned vespel/graphite

Results

Chromatography

After evaluating a series of columns the DB-5ms phase seems the best choice overall, which is consistent with the literature [1]. The literature shows that the shorter columns and thinner films are of benefit to improving the PBDE responses, especially deca-BDE (PBDE-209) [1] and this approach is applied here. The benefit appears in both response and also in shorter analysis times; elution of deca-BDE occurs in less than 15 minutes. The separation on the DB-5ms phase seems sufficient for characterizing PBDE additives in polymers since the desire is not so much the complete separation as it is the overall composition and contribution of the various isomers [5]. Nonetheless, the short analysis time makes RT reproducibility and accuracy more critical for correct assignments of the various PBDE isomers and this is greatly enhanced by applying RTL. A list of the Retention Time Locked elutions of the most prominent PBDEs is presented in Table 2. For reference, Figures 1, 2 and 3 present chromatograms of PentaBDE, OctaBDE, and DecaBDE technical mixtures with approximate elution windows of the various isomers.

Table 2. Prominent PBDE Congeners and their Locked RTs

Compound name	RTL RT (min)
PCB 207	8.69
PCB 209 (locking compound)	9.350
PBDE 17 (tri Br)	6.89
PBDE 28 (tri Br)	7.08
PBDE 71 (tetra Br)	7.97
PBDE 47 (tetra Br)	8.09
PBDE 66 (tetra Br)	8.25
PBDE 100 (penta Br)	8.82
PBDE 99 (penta Br)	9.06
PBDE 85 (penta Br)	9.43
PBDE 154 (hexa Br)	9.62
PBDE 153 (hexa Br)	9.93
PBDE 138 (hexa Br)	10.31
PBDE 183 (hepta Br)	10.73
? hepta PBDE	11.07
PBDE 190 (hepta Br)	11.23
PBDE 204 (octa)	11.62
PBDE 203 (octa)	11.78
? PBDE 196 (octa)	11.84
PBDE 205 (octa)	12.00
PBDE 208 (nona)	12.56
PBDE 207 (nona)	12.64
PBDE 209 (deca Br)	13.60

Note - tentative identification of PBDE 196 was based on reference [1]




Figure 1 Reconstructed ion chromatogram (RIC) for the GC/MS EI-SIM acquisition of a PentaBDE technical mixture (Cambridge Isotope Laboratories).




Figure 2 RIC for the GC/MS EI-SIM acquisition of a OctaBDE technical mixture (Cambridge Isotope Laboratories)




Figure 3 RIC for the GC/MS EI-SIM acquisition of a DecaBDE technical mixture (Cambridge Isotope Laboratories).

PBDE Spectral Interpretation

The EI ionization mass spectra of the PBDE congeners are rich in details and partially described in the literature [7]. Among the isomers the spectra are expected to be approximately identical in pattern and fragmentation pathway. Figure 4 presents a full scan spectrum of a hexabrominated-DE, PBDE-138, obtained at a source temperature of 300 °C. The spectrum shows the isotope cluster due to the molecular ion (643 m/z) and an intense cluster (484 m/z) consistent with the loss of Br₂. The mass assignment of the m/z 484 cluster is consistent with the result of $[M-Br_2]^+$, that is, $[C_{12}H_4OBr_4]^+$, and shows the tetrabrominated pattern (18 : 69 : 100 : 65 : 16). The next highest abundance isotope cluster appears around 242 m/z . Figure 4 shows this cluster and the cluster at m/z 484, $[M-Br_2]^+$. The isotope cluster patterns are similar, which suggests the same degree of

bromination, but the fragment mass assignments are half those of the 484 cluster and mass spacing is not 2 but 1 m/z unit. While it is possible this is due to overlapping fragments, the close correspondence in patterns lead the authors to propose that this isotope cluster is due to double-charged fragments; that is, $[M-Br_2]^{+2}$. Recently, this assignment was confirmed by high-resolution MS and the results will be published elsewhere [8]. This $[M-Br_2]^{+2}$ fragment is common among the PBDEs congeners and grows in relative abundance as the degree of bromination increases: approximately in 10% tetraBDEs; 15% in pentaBDEs; 20%–25% in hexaBDEs and heptaBDEs; 45% in octaBDEs; 60% in nonaBDEs; and > 80% in decaBDE. Figures 5, 6, 7, 8 and 9 show spectra for several PBDEs. We have also observed the same phenomena for the polybrominated biphenyls (PBBs). We also find the ratios vary within an isomeric series more than in PCBs.




Figure 4 Normalized EI mass spectrum of a hexabrominated-DE, PBDE-138, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 5 Sections of the normalized EI mass spectrum of the hexabrominated-DE, PBDE-138, for the $[M-Br_2]^+$ and proposed $[M-Br_2]^{+2}$ clusters.




Figure 6 Normalized EI mass spectrum of a pentabrominated-DE obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 7 Normalized EI mass spectrum of a heptabrominated-DE obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 8 Normalized EI mass spectrum of an octabrominated-DE, PDBE-203, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 9 Normalized EI mass spectrum of a nonabrominated-DE, PDBE-208, obtained in scan from 150–800 m/z at a source temperature of 300 °C.

In considering the EI spectrum of the decabromodiphenyl ether, PBDE-209, the same observations apply, Figure 10. Although the cluster of the molecular ion at 959 u, eludes the mass range limitation of the 5973N-MSD, the loss of Br₂ forms an intense isotope cluster at m/z 799, [M-Br₂]⁺ and the doubly charged fragment(s) for the [M-Br₂]⁺² at m/z 400 (399.6) as shown in Figure 11. Other data has shown that the intensity of the molecular ion cluster (959 u) is far less than that of the fragments at m/z 799 as is the trend for the PBDEs.




Figure 10 Normalized EI mass spectrum of the decabrominated-DE, PDBE-209, obtained in scan from 150–800 m/z at a source temperature of 300 °C.




Figure 11 Normalized EI mass spectrum of the decabrominated-DE, PDBE-209, obtained in scan from 150–800 m/z at a source temperature of 300 °C.

Therefore these ions (that is, $[M-Br_2]^+$, $[M-Br_2]^{+2}$ and $[M]^+$ where available), and compound RTs, identify and allow determination of the deca-BDE and other PBDEs to the ability of the 15-m column to separate the isomers, which appears quite effective and sufficient for characterizing additives. The monitored ions are given in Table 3 with the ions for the internal standards used in this analysis. Obviously, the bromines provide other ions displaced in mass by two units (except for the doubly-charged ions) that offer other additional ions for quantitation or confirmation.

Using the ions listed in Table 3 to identify the PBDE isomers, the regions in the chromatograms presented in Figures 1, 2 and 3 were labeled with the isomer elution windows. These ions and their ratios were also used to characterize PBDEs not available in the standards but found to occur within the samples and technical mixtures (for example, PBDE 196).

Results for Polymeric Samples

Extracting PBDEs from polymers requires that the entrained PBDEs permeate the polymer into the extracting medium. Apparently “melting” the polymer closes the transport corridors in the polymer and impedes extraction. However, “swelling” the polymer with a proper solvent, greatly improves the kinetics of extraction. Beyond deciding the proper solvent, the optimal time of the extraction must be experimentally determined for each plastic based on its consistency and response to the solvent. For the polymer dissolution and soxhlet extraction methods used here, solvent contact

times or the number of soxhlet cycles for near complete extraction was determined by serial extraction. Other concerns are described in the sample preparation protocols [3].

Figure 12 shows the chromatogram for an extracted HIPS (high-impact polystyrene) polymer sample supplied by an Agilent customer and Table 4 shows the results for replicate extractions and analysis. Note the chromatogram and its major components closely resembles the chromatogram for the OctaBDE technical mixture (Figure 2) and indicates the specificity of the selected ions and most importantly, the lack of polymeric interferences. The reproducibility of the component compositions is a testament to the reproducibility of the total method. A good portion of the variance is introduced by the high dilution factors used in the method to bring the polymer extract concentrations with the scale of the PBDE standards and therefore discriminates against the lower abundance components producing a higher degree of variation and absolute detection. A series of 25 replicate injections of an extracted sample showed negligible degradation in response or chromatography. The robust performance is largely due to the high MSD ion source and quadrupole operating temperatures of 300 °C and 150 °C, respectively. These high temperatures mitigate the effect of co-extracted polymeric residues on the ion source optics to render robust performance. The high operating temperature of the quadrupole provides a very long lifetime without cleaning or maintenance even when analyzing very dirty matrices such as these.

Table 3. Quantitation and Confirmation Ions for the PB_nDEs (n>2)

PBDE bromination	$[M]^+$	$[M-Br_2]^+$	$[M-Br_2]^{+2}$	Confirmation ion
3	405.8	246.0	123.0	403.8
4	485.7	325.9	162.9	483.7
5	563.6	403.8	201.9	561.6
6	643.5	483.7	241.9	641.5
7	721.5	561.6	(280.8 **)	563.6/719.4
8	799.4	641.5	320.8	643.5
9	—	719.4	360.7	721.5
10	—	799.4	399.7	—
PCB 207	463.7	461.7	—	—
PCB 209	497.7	499.7	—	—

**The 280.8 and 281.8 m/z ions can be compromised by column bleed interferences so these were not used in acquisition although they provide a useful diagnostic for column degradation.




Figure 12 RIC of the GC/MS SIM acquisition of an extracted HIPS polymer sample.

Table 4. Extraction Results for Replicate Analysis of a Polymer Sample for PBDE Composition Using the Two Extraction and Sample Preparation Protocols [3]

Soxhlet polymer extraction protocol results						
Sums	Replicate 1 (%)	Replicate 2 (%)	Replicate 3 (%)	Replicate 4 (%)	Replicate 5 (%)	SD
HexaBDEs	9.1	9.5	8.9	8.7	9.1	0.3
HeptaBDEs	53.3	52.5	51.7	53.1	53.1	0.7
OctaBDEs	29.5	29.5	30.7	29.5	29.8	0.5
NonaBDEs	8.0	8.4	8.6	8.7	8.1	0.3

Polymer Dissolution Extraction Protocol Results*				
Sums	Replicate 1 (%)	Replicate 2 (%)	Replicate 3 (%)	SD
HexaBDEs	9.9	10.0	9.7	0.2
HeptaBDEs	55.3	56.2	55.9	0.5
OctaBDEs	34.8	33.8	34.4	0.5

SD standard deviation

No tri-BDEs, tetraBDEs, pentaBDEs, or decaBDE were detected.

*A difference in analyte lists used to quantitate the soxhlet extracts slightly skews the results, specifically the addition of the nona-BDE analytes. Removing this group, the results agree within 3%.

Remarks

Figure 13 presents two overlaid reconstructed ion chromatograms of the SIM acquisitions of two splits of a single PBDE standard. One of the splits was contained in a clear vial and was exposed to laboratory light for about a week and the other split was stored in amber vial and in a freezer as a reference. The most impressive feature is the dramatic loss of the decaBDE and the possible appearance of another intense nonaBDE (around 11.8 minutes). Note the nonaBDEs in the standard showed no degradation while the octaBDEs and heptaBDEs showed varying degrees of loss in concentration. A number of small peaks appear in the baseline that suggest, on the basis of their fragments, ion ratios, and proximity to existing PBDEs in the standard, the presence of other BDE isomers. Assigning any identification in SIM without a standard reference compound to confirm RT and fragment ratios, or a full scan acquisition, must be considered highly speculative. However, the data does indicate a degradation of the decaBDE and some other PBDEs, and suggests possible isomerization of the some PBDEs under the influence of typical laboratory fluorescent lights. Time and resources do not allow us to pursue this matter,

but we provide these observations since there are implications in sample handling and standard preparation and storage.

Conclusions

The 5973N inert MSD equipped with performance electronics allows a single SIM group to survey for PBDE isomers important to characterizing the technical formulations of the PBDEs. Using a single group has the advantages of allowing many formulations to be studied without regard to the particular elution of the congeners (which would require careful maintenance of SIM windows), simplified setup and very rapid analysis. Implementing RTL allows specific congeners to be characterized and quantitated with high confidence. The intense fragmentation of the PBDEs and their universal propensity to form $[M-Br_2]^+$ and $[M-Br_2]^{+2}$ ions provides a unique fingerprint for each degree of bromination. The 15-m column used here provides rapid analysis and sufficient class separation. The method is universally applicable regardless of the sample preparation scheme as demonstrated here by replicate polymer analysis by two techniques, soxhlet extraction and polymer dissolution.




Figure 13. PBDE standard unexposed (green) and exposed to laboratory light. Delta (Δ) indicates change in response as Exposed-Unexposed (with negative signs indicating loss in response and positive an increased response).

References:

1. J. Bjorklund, et al., "Influence of the injection technique and the column system on gas chromatographic determination of polybrominated diphenyl ethers", (2004) *Journal of Chromatography A*, **1041**(1-2): p. 201-210.
2. A. M. Altwaiq, M. Wolf, and R. van Eldik, "Extraction of brominated flame retardants from polymeric waste material using different solvents and supercritical carbon dioxide", (2003) *Analytica Chimica Acta*, **491**(1): p. 111-123.
3. H. Prest. and C. Tu, "Sample Preparation Protocols for Polybrominated Diphenyl Ethers in Polymeric Materials for GC-MS analysis", (2005), available to Agilent customers by request through their Agilent sales agents. www.agilent.com/chem
4. H. Prest and D.W. Peterson, "New approaches to the development of GC-MS selected ion monitoring acquisition and quantitation methods", (2001), Agilent Technologies, publication 5988-4188EN www.agilent.com/chem
5. P. Korytar, et al., "Retention-time database of 126 polybrominated diphenyl ether congeners and two Bromkal technical mixtures on seven capillary gas chromatographic columns", (2005) *Journal of Chromatography A*, **1065**(2): p. 239-249.
6. V. Giarrocco, B. Quimby, and M. Klee, "Retention Time Locking: Concepts and Applications", (1998), Agilent Technologies, publication 5966-2469EN www.agilent.com/chem
7. S. Huber, and K. Ballschmiter, "Characterisation of five technical mixtures of brominated flame retardants", (2001) *Fresenius Journal of Analytical Chemistry*, **371**(6): p. 882-890.
8. Q. Zhang, et al., Rapid Communications in Mass Spectrometry, in preparation.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
April 5, 2005
5989-2850EN



Agilent Technologies



Full-Scan Low-Level Polynuclear Aromatic Hydrocarbon Analysis Using the Agilent Technologies 6890/5973 inert Gas Chromatograph/Mass Selective Detector

Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of polynuclear aromatic hydrocarbons presents challenges due to the tendency of the polynuclear aromatic hydrocarbons to adsorb on surfaces in the chromatographic system. This results in calibrations that are not linear and the need to run selected ion monitoring for low-level analysis. The Agilent Technologies 6890/5973 inert gas chromatograph/mass selective detector system is designed for improved polynuclear aromatic hydrocarbons analysis using full scan while maintaining linearity across a wide calibration range.

Introduction

Polynuclear aromatic hydrocarbons (PAHs) are produced during combustion of organic material and are suspected carcinogens. The high amounts and widespread occurrence of these compounds in our environment requires reliable, sensitive, and very robust analytical methods.

PAHs, especially the high molecular weight ones, tend to be adsorbed on any active or cold site in a gas chromatographic system. Additionally occurring inlet discrimination often further reduces the number of compounds with higher boiling points that are transferred onto the column. Therefore, typical PAH analyses on a gas chromatography (GC) or gas chromatography/mass selective detector (GC/MSD) system show decreasing response and sensitivity with increasing molecular weight.

The Agilent 6890/5973 inert GC/MSD system has features to overcome this negative trend, including a new uncoated solid-source material and higher temperature filaments. Using a direct-connect inlet liner also improves chromatographic peak shape and sensitivity.

Many laboratories calibrate for PAHs from 0.1 to 10 ppm using Selected Ion Monitoring (SIM) for low level work. Historically, SIM has been necessary because of instrument sensitivity considerations and loss of PAHs at the lower concentration levels, although full scan data is preferred for further confirmation of the compounds.

This application note will show the performance of the Agilent 6890/5973 inert for PAHs using a calibration range of 0.1 to 10.0 ppm in full scan mode with linearity equal to that of many SIM methods.



Agilent Technologies

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet	EPC split/splitless		
Mode	Pulsed splitless, 1 µL injected		
Inlet temperature	300 °C		
Pressure	12.64 psi		
Pulse pressure	30.0 psi		
Pulse time	0.30 min		
Purge flow	30.0 mL/min		
Purge time	1.0 min		
Total flow	34.6 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet liner	Direct Connect, deactivated, 4-mm id, Agilent part number G1544-80700		
Oven			
Oven ramp	°C/min	Next °C	Hold min
Initial		50	1.00
Ramp 1	25	200	0.00
Ramp 2	8	316	0.00
Total run time	21.50 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS part number 19091S-433		
Length	30.0 m		
Diameter	250 µm		
Film thickness	0.25 µm		
Mode	Constant flow		
Flow	1.5 mL/min		
Initial pressure	12.64 psi		
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
MSD	Agilent Technologies 5973 inert		
Drawout lens	6-mm ultralarge aperture, Agilent part number G2589-20045		
Solvent delay	3.00 min		
EM voltage	Run at DFTPP tune voltage = 1000 V		
Low mass	45 amu		
High mass	450 amu		
Threshold	0		
Sampling	2		
Scans/s	3.58		
Quad temp	180 °C		
Source temp	300 °C		
Transfer line temperature	280 °C		
Repeller voltage	DFTPP tune value		
Emission current	DFTPP tune value = 34.6 µamp		

Calibration standards

Calibration standards were diluted in dichloromethane from a stock mix of the 13 PAHs. The seven levels made were 10, 5, 2, 1, 0.5, 0.2 and 0.1 ppm. The perylene-d12 internal standard (ISTD) and the two surrogate standards, 1,3-dimethyl-2-nitrobenzene and triphenylphosphate, were added to each calibration level at 2.0 ppm.

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions that may have to be optimized.

The Agilent 6890 inlet temperature was set to 300 °C, instead of the typical 250 °C, to minimize compounds adsorbing on the liner surface. Pulsed injection was used to facilitate quantitative transfer of the heavier PAHs onto the column, minimizing inlet discrimination. Pulsed injection parameters are easily set in the ChemStation software and are automatically controlled by the electronic pneumatic control (EPC) module.

The Direct Connect inlet liner allows for complete transfer of analytes onto the column. The column inlet end attaches to the liner and minimizes analyte exposure to the stainless steel annular volume in the inlet.

The Agilent 5973 inert was tuned using the automatic DFTPP target tune, as required by some Government methods. The ultralarge aperture drawout lens was used to maintain linearity across the wide calibration range. Source temperature was set to 300 °C, which is now possible with the high temperature filaments. This higher source temperature in combination with the new source material produces better peak shapes for the PAHs.

Results

The system was calibrated at seven levels, 0.1, 0.2, 0.5, 1.0, 2.0, 5.0, and 10.0 ppm using full scan data acquisition. The total ion chromatogram (TIC) for the 0.2-ppm level is shown in Figure 1. Each calibration level contained 13 PAHs, perylene-d12 internal standard (ISTD) and the 2 surrogate standards, 1,3-dimethyl- 2-nitrobenzene and triphenylphosphate.

The relative response factor (RRF) was calculated automatically for each compound by the GC/MSD ChemStation software. Linearity was determined by calculating the percent relative standard deviation (%RSD) of the RRFs across the calibration range for each compound. This is also done automatically by the software in conjunction with Microsoft® Excel.

Linearity is shown in Table 2. The %RSD of the RRFs are shown for each of the PAHs. All RSDs are less than 5%. This level of performance is equal to that of most SIM methods for PAHs.




Figure 1. Thirteen PAHs at 0.2 ppm each with surrogates and ISTD at 2.0 ppm each.

As further proof of system inertness and sensitivity, a 0.01-ppm level spike was analyzed. This sample was quantitated against the seven level calibration curve using average response factor. The results are shown in Table 2. These results are excellent considering this is full scan data and the spike level was 10× lower than the lowest calibration point.

Table 2. %RSD of RRF from Seven Level Calibration and 0.01-ppm Spike Results

	%RSD	0.01 ppm Spike
Perylene-d12	3	—
1,3-dimethyl-2-nitrobenzene	1	2.100
Acenaphthylene	3	0.011
Fluorene	3	0.010
Phenanthrene	3	0.010
Anthracene	3	0.011
Pyrene	3	0.010
Triphenylphosphate	1	1.940
Chrysene	2	0.009
Benz[a]anthracene	3	0.010
Benzo[b]fluoranthene	2	0.009
Benzo[k]fluoranthene	4	0.010
Benzo[a]pyrene	2	0.010
Indeno(123-cd)pyrene	4	0.010
Dibenz(ah)anthracene	2	0.007
Benzo(ghi)perylene	3	0.011

Conclusions

The Agilent 6890/5973 inert shows much improved response and peak shape for PAHs due to the inert source material and higher allowable source temperature. This improved response gives better linearity across the calibration range. Analysis of PAHs can be accomplished using full scan data acquisition over a calibration range of 0.1 to 10 ppm, while maintaining performance similar to SIM methods.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Microsoft is a U.S. registered trademark of Microsoft Corporation.

© Agilent Technologies, Inc. 2003


Printed in the USA
November 11, 2003
5989-0264EN

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.



Agilent Technologies



Fast Semivolatiles Analysis using the Agilent Technologies 6890/5973 inert GC/MSD

Application

Environmental

Author

Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of semivolatiles presents challenges due to the simultaneous measurement of acids, bases, and neutrals over a wide concentration range. Due to productivity demands, laboratories want to run faster while maintaining linearity and sensitivity for even the most active compounds. The Agilent Technologies 6890/5973 inert gas chromatography/mass selective detector system is designed to meet the criteria for fast analysis, while minimizing activity and maintaining linearity.

Introduction

Semivolatiles analysis concurrently measures a mix of acids, bases, and neutrals. This mix presents a challenge for instrument design due to the interaction of the analytes with the instrument and consumables. Most laboratories analyze for 70–100 compounds with a chromatographic run time of

25–40 minutes. The calibration range required for the analysis varies dependent on a particular laboratory's statement of work. Historically a range of 20–160 ng was used. With the increased sensitivity of newer gas chromatography/mass spectrometry (GC/MS) systems, laboratories are moving toward lower minimum detection limits (MDLs) and pushing the calibration range down to 5 ng.

The Agilent 6890/5973 inert gas chromatograph/mass selective detector (GC/MSD) system was designed to meet the demand for these lower MDLs. A new uncoated solid source material has shown improved performance for the most active compounds, such as 2,4-dinitrophenol.

This inert source allows for less material injected onto the column while maintaining mass spectrometer performance. Split injections are possible where only splitless would suffice before. The ability to do split injections matches very well with smaller diameter columns such as 100 μm . These smaller columns provide for run times of 10 minutes or less.

This application note will show the performance of the Agilent 6890/5973 inert for semivolatiles using a 100- μm id column with a run time of 7.5 minutes and a calibration range of 5–200 ng.



Agilent Technologies

Instrument Operating Parameters

The recommended instrument operating parameters are listed in Table 1. These are starting conditions and may have to be optimized.

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet	150 psi EPC split/splitless		
Mode	Split, 1 µL injected		
Split ratio	10:1		
Inlet temp	250 °C		
Pressure	118 psi		
Split flow	22.8 mL/min		
Total flow	26.9 mL/min		
Gas saver	Off		
Inlet liner	Siltek™ Cyclosplitter, 4-mm id, Restek part number 20706-214.1		
Oven	240 V		
Oven ramp	°C/min	Next °C	Hold min
Initial		40	0.20
Ramp 1	45	320	1.58
Total run time	8.0 min		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS Custom		
Length	12.5 m		
Diameter	100 µm		
Film thickness	0.1 µm		
Mode	Ramped flow		
Flow	mL/min ²	mL/min	Hold min
Initial		2.3	0.10
Ramp 1	10	0.8	0.00
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
MSD	Agilent Technologies 5973 inert		
Solvent delay	0.95 min		
EM voltage	Run at DFTPP tune voltage = 1200 V		
Low mass	35 amu		
High mass	500 amu		
Threshold	0		
Sampling	1		
Scans/s	5.92		
Quad temp	150 °C		
Source temp	230 °C		
Transfer line temp	280 °C		
Repeller voltage	DFTPP tune value		
Emission current	DFTPP tune at 35 µamp, run at 25 µamp		

Calibration standards

Accustandard, New Haven, CT. Part number M-8270-IS-WL-0.25x to 10x, 77 compounds at eight concentration levels with six ISTDs at 40 ppm.

The Agilent 6890 with a 150 psi inlet (option) is necessary for both the initial high flow during injection and to maintain constant flow during the run. A 10:1 split is used to match the column capacity to the calibration concentration range. Higher splits can be used but splitting less or using splitless will cause peak overload and too much distortion for good integration.

The inlet liner was found to be of low activity, as it does not contain glass wool. Proper mixing for split injections is done by the internal liner geometry. This liner was also found to perform adequately for higher split ratios and for splitless.

The Agilent 6890 240 V oven was necessary for the 45 °C/min oven program ramp used.

The custom order HP-5MS column was obtained in a 20 m length and cut down to 12.5 m. The ramp flow allows for faster transfer of analytes onto the column to minimize exposure to the inlet liner. Ramp flows are easily set by the software and are accomplished with electronic pneumatic control (EPC).

The Agilent 5973 inert was tuned using the automatic DFTPP target tune, as required by some Government methods. After tuning, the emission current was manually set to 25 µamp. This was done to maximize linearity for easily ionized compounds. The sampling rate was changed from the default of 2 to 1, while preserving sufficient sensitivity. The resultant 5.92 scans/s yields a minimum of eight data points across the narrowest peaks.

Results

The system was calibrated at eight levels, 5, 10, 20, 50, 80, 120, 160, and 200 ppm. The total ion chromatogram (TIC) for the 5-ppm level is shown in Figure 1. Each calibration level contained 77 compounds together with six internal standards (ISTDs) at 40 ppm.

The relative response factor (RRF) was calculated automatically for each compound by the GC/MSD ChemStation software. Linearity was determined by calculating the percent relative standard deviation (%RSD) of the RRFs across the calibration range for each compound and was performed automatically by the software in conjunction with Microsoft® Excel.




Figure 1. Five ppm each 77 semivolatiles and six ISTDs at 40 ppm each.

There are published Government Methods, such as USEPA Method 8270D for Semivolatiles, that specify criteria for suitable RRFs and %RSD. In Method 8270D, minimum system performance of four active compounds, the system performance check compounds (SPCCs) is measured by the average RRF.

Table 2 lists the Method 8270D SPCC criteria, and performance of the Agilent 5973 inert together with an Agilent 5973 system. The Agilent 5973 inert data exceeds the 8270D criteria. The Agilent 5973 inert also shows exceptional results compared to the Agilent 5973. These results are superior because they were run 10:1 split, putting 10× less compound on column than those run on the Agilent 5973.

Table 2. SPCCs, Comparison of Average RRF

	8270D Criteria	Agilent 5973 inert	Agilent 5973
Calibration range, ppm		0.5–20	5–160
N-Nitroso-di-n-propyl amine	0.050	1.146	0.970
Hexachlorocyclopentadiene	0.050	0.284	0.253
2,4-Dinitrophenol	0.050	0.188	0.075
4-Nitrophenol	0.050	0.236	0.162

Linearity is shown in Table 3. The 77 compounds were grouped as indicated. The RSDs of the RRFs were averaged to show performance for entire compound classes, not just a few selected analytes. The linearity of the Agilent 5973 inert is significantly better than the Agilent 5973 across the same concentration range and across an extended range.

Table 3. Average RSDs of RRFs by Compound Class

	Agilent 5973 inert	Agilent 5973 inert	Agilent 5973
Calibration range, ppm	0.5–20	2–16	20–160
Miscellaneous base neutrals (19)	8	5	11
Acids (17 phenols, dinitrophenols)	8	5	11
Bases (12)	8	6	12
Phthalates, ethers (13)	9	6	12
PAHs (16)	7	5	8

Conclusions

The Agilent 6890/5973 inert shows improved response for active compounds such as nitrophenols at low levels. This improved response gives better linearity across the calibration range. Split injections are now possible while maintaining sufficient response and fast analysis can be done using 100- μ m columns. Analysis of 77 analytes and six ISTDs can be accomplished in less than 8 minutes over an extended calibration range of 0.5 ppm to 20 ppm.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Microsoft® is a U. S. registered trademark of Microsoft Corporation.
Siltek™ is a trademark of the Restek Corporation.

© Agilent Technologies, Inc. 2003

Printed in the USA
October 29, 2003
5989-0207EN




Agilent Technologies



Separation of Catechol and Various Metabolites

Application
Environmental
Robert Ricker

Carbazole is an environmental pollutant of some concern. Sensitive detection of carbazole and related metabolites provides a means of following its breakdown in various sources. The postulated pathway is: **carbazole** → **2,3-aminobiphenyl diol** → **anthranilic acid** → **catechol**. (The 2nd intermediate is not commercially available and was replaced with 2,3-dihydroxybiphenyl diol, to act as a related marker.)



Courtesy of Phillip Gibbs, Energy Biosystems Corp. The Woodlands, TX;
Rich Willson, University of Houston, Dept. Chemical Engineering, Houston, TX

Conditions:
ZORBAX 300 SB-C18 (4.6 x 150 mm) (Agilent P/N: 883995-902)
Mobile Phase: Gradient 5-60% in 20 min., Wash, 95%B for 2 min.
A) H₂O with 0.1% TFA to pH3 with TEA; **B)** ACN with 0.085% TFA
Injection 15µL, 250-500 µg/mL each, 1 mL/min, 65°C, Detect. UV (233 nm)

Highlights

- The resolution of peaks 1 and 2, not previously obtained, was achieved using the ZORBAX 300SB-C18 at low pH.
- The steric protecting groups of the ZORBAX SB-C18 stabilize the bonded phase, permitting stable and reproducible chromatography at pH ≤ 1.



Agilent Technologies

*Robert Ricker is an application chemist
based at Agilent Technologies, Wilmington,
Delaware.*

For more information on our products and
services, visit our website at:
www.agilent.com/chem

Copyright© 2002 Agilent Technologies, Inc.
All Rights Reserved. Reproduction,
adaptation or translation without prior
written permission is prohibited, except as
allowed under the copyright laws.


Agilent shall not be liable for errors
contained herein or for incidental or
consequential damages in connection with
the furnishing, performance, or use of this
material.

Information, descriptions, and specifications
in this publication are subject to change
without notice.

Printed in the USA
April 25, 2002
5988-6344EN



Agilent Technologies



Retention Time Locked GC-MS Analysis of Phenols

Application

Environmental

Author

Angelica Reese
Agilent Technologies, Inc.
91 Blue Ravine Road
Folsom, CA 95630
USA

Harry Prest
Agilent Technologies, Inc.
1601 California Ave
Palo Alto, CA 94304
USA

Abstract

Comprehensive retention time locking, gas chromatography-mass spectrometry methods for more than 50 phenols and their common internal standards are available. Retention time locking makes the phenol retention times on DB-XLB and DB-5ms columns universal and permanent. "Universal" means that any analyst using an Agilent 6890 Plus Gas Chromatograph and 5973N Mass Selective Detector can reproduce the retention times of every listed phenol. "Permanent" means that the phenol retention times will remain unchanged with typical column maintenance such as column trimming or replacement. This is particularly useful in making definitive assignments of phenol identity from among the many possible isomers that may be present in the samples but may not be on hand in the laboratory standards. A high resolution method and a more rapid "Fast Quant" method were developed for both columns. The high resolution programs have analysis times of

31 and 21 minutes while the "Fast Quant" method runtimes are reduced to 16 and 14 minutes for DB-XLB and DB-5ms columns, respectively. Both columns produce minimal column bleed resulting in improved mass spectral determinations. They also provide excellent separation of the phenols, the DB-XLB column achieving slightly better separation than the DB-5ms.

Introduction

Phenols are widely used compounds and their substituted derivatives are manufactured for use in plastics, drugs, dyes, preservatives, insecticides, fungicides, antiseptics, and disinfectants. They also occur as by-products of various industrial activities such as paper and pulp processing, coal gas liquification, and coke production. This multi-industry use has lead to widespread environmental contamination by phenolic compounds.

Use of chlorine as a bactericide in water treatment results in chlorinated species that rapidly react with phenol to form various substituted chlorophenols. As the degree of substitution increases, acidity, lipophilicity and tendency to bioaccumulate and become toxic to aquatic life increases. These chlorophenols are also added to provide or enhance anti-bacterial properties of various products. Recently, representatives of the German, Danish and Swedish environmental ministries have advised consumers against use of anti-bacterial soaps, many of which contain chlorophenols, in part because of their environmental effects.



Agilent Technologies

Nitrophenols tend to be among the most toxic of the phenols and their alkylated derivatives are commonly used as herbicides and pesticides. It is a startling and disturbing fact that 60 years ago 2,4-dinitrophenol was ingested to cause weight loss. Reputedly, it is becoming popular again despite well documented risks.

As a family, phenolic compounds exhibit a wide range of properties due to the numerous substitution derivatives possible, the most common of which are chlorinated, alkylated or nitro-group derivatives. Consequently, a variety of methods have been developed to test the presence of this important class of compounds in water, soil, sediment, and biota. Recently, a U.S. EPA method (528) has been promulgated that is dedicated to the analysis of 12 common phenols in drinking water. One of the limitations of this method and others is the lack of characterization of other phenol isomers that may be present and undetected or improperly identified.

This work details a gas chromatography-mass spectrometry (GC-MS) approach to the analysis of underivatized phenols. Retention time locking (RTL) is used to make this method universally applicable [1,2]. In other words, any laboratory analyzing samples for phenols can use this method to confidently identify phenolic compounds. This is important because many of the substituted phenols exist as multiple isomers, which exhibit very similar mass spectra and therefore require retention time information for confirmation. This retention time locking (RTL) method allows for the identification of phenols that might otherwise be undetected or possibly misidentified, simply because they are not present in the particular set of standards in use. Obviously, quantification requires standards, but estimating concentrations is possible using the response factors for related phenol isomers via standards on hand.

Experimental

Phenols were obtained from Ultra Scientific (North Kingstown, RI) and AccuStandard (New Haven, CT) as neat compounds and mixtures. Isotopically labeled phenols were acquired from Cambridge Isotope Laboratories (Andover, MA). Dilutions were made in acetone and in dichloromethane (Burdick and Jackson Grade, VWR Scientific).

The configuration and operating parameters of the Agilent 6890 Plus GC ("fast ramping" 220 V option), 7683 Automatic Liquid Sampler, and 5973N MSD with CI option used for acquiring the data are given in Table 1. The relatively recent EPA Method 528 for determination of phenols in drinking water via GC-MS suggests the DB-5ms column [3]. This column is widely used due to its versatility, robustness and low bleed. For similar reasons, the DB-XLB column is also very popular, particularly for the analysis of PCBs and other organochlorine compounds. Method parameters and compound elutions were explored for both columns under the criteria of resolution and total analysis time. This led to the development of two methods for both the DB-XLB and DB-5ms columns. The method details of the GC and MSD programs are given in Table 1.

Phenols are included in a number of U.S. EPA methods including 604, 1625, 1653, 528, 8270, 8041 and others. Each method utilizes different surrogates and internal standards. Method 528 uses 1,2-dimethyl-3-nitrobenzene and 2,3,4,5-tetrachlorophenol as internal standards and 2-chlorophenol-3,4,5,6-d₄, 2,4-dimethylphenol-3,5,6-d₃ and 2,4,6-tribromophenol as recovery surrogates. All these are included in this study. Isotopically labeled phenols, both deuterated and ¹³C-substituted, provide the most reliable recovery (surrogate) information and have also been included. A variety of internal standards have been applied in the various methods, such as pentafluorophenol, 2,5-dibromotoluene, and 2,2',5,5'-tetrabromobiphenyl. The tetrabromobiphenyl standard requires extending both the GC oven program slightly and the mass scan range beyond the mass range pertinent to the phenols if measuring the molecular ion(s) is desired (as an example, from 50 to 350 *m/z* to 50 to 476 *m/z*). However, the tetrabromobiphenyl method can be used with the "phenol" scan range if one assigns the intense 150 and 310 *m/z* fragments to identify the internal standard. (Technically, if the phenols alone were of interest, the scan range could be confined from 50 to 275 *m/z*, which has the advantage of more scans over the peak.)

The 2,4-dibromophenol was chosen as the locking compound because of its elution in the middle of the oven program, easily distinguished mass spectrum, and low cost.

Table 1. GC Injection, Oven and MSD Parameters for Both Fast Quant and High Resolution Methods Using the DB-XLB and DB-5ms Columns

Injection Parameters

Injection Mode	Pulsed splitless	
Inlet Temperature	200 °C	
Pulse Pressure and Time	25.0 psi	1.00 min
Purge Flow and Time	50.0 mL/min	0.25 min
Gas Saver Flow and Time	20.0 mL/min	3.00 min

DB-XLB Column and Oven Parameters: Fast Quant Method

GC column (P/N: 122-1232)	DB-XLB 30 m × 0.25 mm I.D., 0.25 µm	
Flow and Mode	1.2 mL/min	Constant Flow
Detector and Outlet Pressure	MSD	Vacuum
Oven Temperature Program	40 °C	2.00 min
40 °C/min	100 °C	0.20 min
2 °C/min	110 °C	0.00 min
30 °C/min	340 °C	0.00 min
Oven Equilibrium Time	0.50 min	
Total Program Time	16.37 min	
MSD Transfer Line Temp	320 °C	

DB-XLB Column and Oven Parameters: High Resolution Method

GC column (P/N: 122-1232)	DB-XLB 30 m × 0.25 mm I.D., 0.25 µm	
Flow and Mode	1.2 mL/min	Constant Flow
Detector and Outlet Pressure	MSD	Vacuum
Oven Temperature Program	40 °C	2.00 min
40 °C/min	100 °C	0.50 min
2 °C/min	140 °C	0.00 min
30 °C/min	340 °C	0.00 min
Oven Equilibrium Time	0.50 min	
Total Program Time	30.67 min	
MSD Transfer Line Temp	320 °C	

DB-5ms Column and Oven Parameters: Fast Quant Method

GC column (P/N: 122-5532)	DB-5 ms 30 m × 0.25 mm I.D., 0.25 µm	
Flow and Mode	1.2 mL/min	Constant Flow
Detector and Outlet Pressure	MSD	Vacuum
Oven Temperature Program	40 °C	2.00 min
40 °C/min	100 °C	0.20 min
2 °C/min	105 °C	0.00 min
30 °C/min	340 °C	0.00 min
Oven Equilibrium Time	0.50 min	
Total Program Time	14.03 min	
MSD Transfer Line Temp	320 °C	

DB-5ms Column and Oven Parameters: High Resolution Method

GC column (P/N: 122-5532)	DB-5 ms 30 m × 0.25 mm I.D., 0.25 µm	
Flow and Mode	1.2 mL/min	Constant Flow
Detector and Outlet Pressure	MSD	Vacuum
Oven Temperature Program	40 °C	2.00 min
40 °C/min	100 °C	0.50 min
2 °C/min	120 °C	0.00 min
30 °C/min	340 °C	0.00 min
Oven Equilibrium Time	0.50 min	
Total Program Time	21.33 min	
MSD Transfer Line Temp	320 °C	

Mass Spectrometer Parameters

Tune Parameters	Autotune
Electron Multiplier Voltage	Autotune +400 V
Solvent Delay	4.20 min
Scan Parameters	50 to 340 <i>m/z</i>
Quadrupole Temperature	150 °C
Source Temperature	230 °C

Miscellaneous Parts

Septa	5182-0739	BTO septa (400 °C)
Liner	5181-3315	deactivated 4 mm I.D. double taper
GC column ferrule	5181-3323	250 µm Vespel/graphite
MSD interface ferrule	5062-3508	0.4 mm I.D. preconditioned Vespel/graphite

Results and Discussion

Table 2 presents the locked retention times of the phenols using the DB-5ms and DB-XLB columns under the parameters presented in the experimental section. The absolute retention times of the phenols result as a consequence of locking the 2,4-dibromophenol elution time on both columns under all methods. The Fast Quant methods are intended for customers whose analyte list is a subset of the entire phenol list presented here. The High Resolution methods are given for customers with more extensive lists or concerns over possible coelutions or assignments of phenol identity. Both methods are intended for quantitative work.

Method 528 for phenols states that “Any capillary column that provides adequate resolution, capacity, accuracy, and precision can be used. Medium polarity, low bleed columns are recommended ...” Both the DB-XLB and DB-5ms columns meet these criteria. Bleed is extremely low from the DB-XLB

column making it well suited for many GC-MS analyses. The remarks concerning “adequate resolution” are apparently limited to the list of 17 compounds in the method and further qualified by “complete resolution is not necessary ... if

unique ions with adequate intensity are available for quantitation.” They do not cite potential failures among the many possible isomeric phenols that lack unique ions. Coelutions are difficult to avoid due to the many possible phenol isomers.

Table 2. Phenol names, CAS numbers, retention times and identifying ions under the acquisition methods are presented in Table 1. All compound absolute retention times are determined by locking the 2,4-dibromophenol retention time to the specified time under each method. On DB-XLB, dibromophenol is locked at 11.320 and 16.220 minutes in the "Fast Quant" and High Resolution methods, respectively. On DB-5ms, dibromophenol is locked at 8.950 and 13.850 minutes in the "Fast Quant" and High Resolution methods, respectively. Tetrabromobiphenyl is listed twice to emphasize the use of different identifying ions appropriate to different scanning ranges; entry #70 is for the scan range 50 to 340 m/z .

#	Compound Name	CAS #	Retention Times				Identifying Ions (m/z)
			DB-XLB	DB-5ms	DB-XLB High	DB-5ms High	
			Fast Quant (min)	Fast Quant (min)	Resolution (min)	Resolution (min)	
1	2-fluorophenol	367-12-4	4.345	4.135	4.370	4.125	112; 64; 92; 63
2	pentafluorophenol	771-61-9	5.205	4.940	5.360	4.940	183.9; 135.9; 116.9
3	d_5 -phenol		5.315	5.070	5.455	5.085	99; 71
4	phenol	108-95-2	5.350	5.085	5.490	5.100	94; 66; 65
5	2-chlorophenol-3,4,5,6- d_4		5.590	5.270	5.730	5.285	132; 133.9; 68; 96
6	2-chlorophenol	95-57-8	5.620	5.300	5.775	5.315	127.9; 129.9; 64
7	2-methylphenol (o-cresol)	95-48-7	6.405	6.025	6.605	6.050	108; 107; 79; 77
8	4-methylphenol (p-cresol)	106-44-5	6.775	6.320	7.005	6.370	107; 108; 77; 79
9	3-methylphenol (m-cresol)	108-39-4	6.815	6.345	7.045	6.375	108; 107; 79; 77
10	2-chloro-5-methylphenol	615-74-7	7.425	6.715	7.690	6.870	141.9; 107; 143.9; 77
11	2,6-dimethylphenol	576-26-1	.630	6.840	7.905	7.035	122; 107; 121; 77
12	2-ethylphenol (o-ethylphenol)	90-00-6	7.980	7.120	8.265	7.550	122; 107; 77
13	2,4-dimethylphenol-3,5,6- d_3		8.400	7.240	8.720	7.770	125; 124; 110; 109
14	2,4-dimethylphenol	105-67-9	8.425	7.255	8.740	7.795	122; 107; 121; 77
15	2,5-dimethylphenol	95-87-4	8.520	7.275	8.850	7.830	122; 107; 121; 77
16	2-nitrophenol- d_4		8.500	7.135	8.825	7.545	143; 69; 85; 113
17	2-nitrophenol	88-75-5	8.560	7.155	8.885	7.585	138.9; 64.95; 81.1; 108.9
18	4-ethylphenol (p-ethylphenol)	123-07-9	8.750	7.425	9.080	8.170	122; 107; 77
19	3-ethylphenol (m-ethylphenol)	620-17-7	8.825	7.440	9.170	8.205	122; 107; 77
20	3,5-dimethylphenol	108-68-9	9.030	7.445	9.410	8.270	122; 107; 77; 121
21	2,3-dimethylphenol	526-75-0	9.085	7.550	9.505	8.455	122; 107; 77; 121
22	2,4-dichlorophenol- d_3		9.060	7.505	9.475	8.305	164.9; 166.9; 66; 101
23	2,4-dichlorophenol	120-83-2	9.110	7.530	9.545	8.350	161.9; 163.9; 97.9; 63
24	2,5-dichlorophenol	583-78-8	9.155	7.550	9.610	8.410	161.9; 163.9; 63; 98.9
25	2,3-dichlorophenol	576-24-9	9.190	7.600	9.660	8.530	161.9; 163.9; 125.9; 63
26	2-isopropylphenol	88-69-7	9.340	7.740	9.900	8.980	136; 121; 103; 91
27	3-chlorophenol	108-43-0	9.360	7.710	9.935	8.910	127.9; 129.9; 65; 99.9
28	4-chlorophenol	106-48-9	9.400	7.715	10.020	8.915	127.9; 129.9; 65; 99.9
29	3,4-dimethylphenol	95-65-8	9.440	7.700	10.100	8.865	122; 107; 121; 77

Table 2. Continued

#	Compound Name	CAS #	Retention Times				Identifying Ions (<i>m/z</i>)
			DB-XLB Fast Quant (min)	DB-5ms Fast Quant (min)	DB-XLB High Resolution (min)	DB-5ms High Resolution (min)	
30	1,2-dimethyl-3-nitrobenzene	83-41-0	9.490	7.675	10.175	7.675	151; 134; 77; 106
31	2,6-dichlorophenol	87-65-0	9.700	7.850	10.585	9.215	161.9; 163.9; 63; 125.9
32	2-n-propylphenol	644-35-9	9.720	7.940	10.645	9.585	136; 107; 77
33	2,4,6-trimethylphenol	527-60-6	9.765	7.845	10.750	9.275	136; 121; 135; 91
34	4-chloro-2-methylphenol	1570-64-5	10.470	8.345	12.730	11.105	141.9; 107; 77; 143.9
35	2,3,5-trimethylphenol	697-82-5	10.535	8.375	12.980	11.215	136; 121; 91; 135
36	4-tertbutylphenol	98-54-4	10.615	8.515	13.300	11.905	150; 135; 107
37	4-chloro-3-methylphenol-d ₂	59-50-7	10.670	8.480	13.500	11.745	143.9; 109; 143.9; 79
38	4-chloro-3-methylphenol		10.670	8.480	13.500	11.740	141.9; 107; 77; 143.9
39	2,5-dibromotoluene	615-59-8	10.990	8.680	14.640	12.410	249.7; 251.8; 168.8; 170.9
40	2,3,5-trichlorophenol	933-78-8	11.180	8.845	15.605	13.340	195.8; 197.8; 159.8; 199.8
41	2,4-dibromophenol (lock compound)	615-58-7	11.320	8.950	16.220	13.850	251.7; 253.7; 249.7; 63
42	2,4,6-trichlorophenol-d ₂		11.390	8.960	16.760	14.075	197.9; 199.9; 201.8; 133.9
43	2,4,6-trichlorophenol	88-06-2	11.405	8.975	16.825	14.120	195.8; 197.8; 131.9; 199.8
44	2,4,5-trichlorophenol-d ₂		11.390	8.990	16.760	14.200	97.9; 199.9; 201.8; 133.9
45	2,4,5-trichlorophenol	95-95-4	11.405	9.005	16.825	14.250	195.8; 197.8; 131.9; 199.8
46	2,3,5,6-tetramethylphenol	527-35-5	11.400	9.000	16.950	14.375	150; 135; 91; 151
47	2,3,4-trichlorophenol	15950-66-0	11.465	9.075	17.105	14.510	195.8; 197.8; 159.8; 199.8
48	3,5-dichlorophenol	591-35-5	11.495	9.135	17.775	15.040	161.9; 163.9; 98.9; 63
49	2,3,6-trichlorophenol	933-75-5	11.625	9.180	18.125	14.900	195.8; 197.8; 159.8; 199.8
50	3,4-dichlorophenol	95-77-2	11.700	9.280	19.005	15.410	161.9; 163.9; 98.9; 63
51	3-nitrophenol	554-84-7	12.140	9.600	22.565	16.150	138.9; 65; 93; 81
52	1-naphthol	90-15-3	12.390	9.850	24.175	16.520	143.9; 114.9; 116; 89
53	4-nitrophenol-d ₄		12.450	9.865	24.920	16.625	143; 113; 69
54	4-nitrophenol	93951-79-2	12.470	9.875	24.960	16.640	138.9; 65; 109; 81
55	2,5-dinitrophenol	329-71-5	12.500	9.605	24.995	16.045	183.9; 63; 53
56	2,3,4,5-tetrachlorophenol	4901-51-3	12.655	10.040	25.320	16.790	231.8; 229.8; 233.8; 130.9
57	2,3,5,6-tetrachlorophenol	935-95-5	12.655	10.025	25.370	16.775	231.8; 229.8; 233.8; 130.9
58	2,3,4,6-tetrachlorophenol	58-90-2	12.710	10.065	25.550	16.845	231.8; 229.8; 233.8; 130.9
59	2,4-dinitrophenol-d ₃		12.710	9.800	25.745	16.420	186.9; 156.9; 110; 54
60	2,4-dinitrophenol	51-28-5	12.730	9.810	25.785	16.445	183.9; 153.9; 106.9; 91
61	3,4,5-trichlorophenol	609-19-8	12.910	10.315	26.285	17.305	195.8; 197.8; 199.8; 132.9
62	2,4,6-tribromophenol	118-79-6	13.155	10.485	26.650	17.450	329.7; 331.7; 327.6
63	2-methyl-4,6-dinitrophenol-d ₂		13.280	10.305	27.045	17.235	199.9; 123; 107; 170
64	2-methyl-4,6-dinitrophenol	534-52-1	13.290	10.310	27.055	17.245	197.9; 120.9; 104.95; 167.9
65	pentachlorophenol- ¹³ C ₆		13.660	10.930	27.595	18.045	271.8; 273.8; 269.8; 169.8
66	Pentachlorophenol	87-86-5	13.665	10.930	27.595	18.045	265.7; 267.7; 263.7; 164.8
67	Dinoseb	88-85-7	13.920	11.090	28.065	18.265	210.9; 239.95; 162.95; 146.9
68	2-cyclohexyl-4,6-dinitrophenol	131-89-5	15.620	12.380	29.625	19.660	230.95; 266; 184.95; 192.9
69	2,2',5,5'-tetrabromobiphenyl	59080-37-4	15.625	12.875	29.995	20.165	469.6; 388.7; 471.6; 390.7
70	2,2',5,5'-tetrabromobiphenyl (2)	59080-37-4	15.625	12.875	29.995	20.165	149.9; 309.8; 311.8; 307.8

The DB-XLB method results

Using the DB-XLB column, a single coelution is apparently unavoidable for reasonable oven programs. The 2,4,6-trichlorophenol and 2,4,5-trichlorophenol isomers completely coelute on the DB-XLB under both the Fast Quant and High Resolution methods. Closely eluting peaks in the DB-XLB High Resolution method are the meta and para cresols ($\approx 40\%$ resolved), the 2,5-dichlorophenol, 2,4-dichlorophenol and 2,3-dichlorophenol ($\approx 50\%$ resolved) the 2,3,4,5-tetrachlorophenol and 2,3,5,6-tetrachlorophenol ($> 50\%$ resolved). The DB-XLB Fast Quant Method oven program sacrifices resolution of the 2,3,4,5-tetrachlorophenol and 2,3,5,6-tetrachlorophenol. Additional close elutions occur between 3-chlorophenol and 4-chlorophenol, 3,4-dimethylphenol and 2,3-dimethylphenol, and 2-n-propylphenol and 2,4,6-trimethylphenol.

The DB-5ms method results

Using the DB-5ms High Resolution method, complete coelutions are apparently unavoidable for the 3-methylphenol and 4-methylphenol (meta- and para-cresol), and 3-chlorophenol and 4-chlorophenol for reasonable oven programs. Only partial resolution of 3-ethylphenol, 4-ethylphenol and 3,5-dimethylphenol, 2,4-dimethylphenol and 2,5-dimethylphenol, 2,4-dichlorophenol and 2,5-dichlorophenol, and 2,3,4,5-tetrachlorophenol and 2,3,5,6-tetrachlorophenol can be obtained. This last coelution is particularly troublesome in view of the critical role of the 2,3,4,5-tetrachlorophenol as an internal standard in Method 528. Shortening the oven program in the DB-XLB Fast Quant Method tightens the window between a few compounds such as 2,4,5-trichlorophenol and 2,3,4-trichlorophenol.

General Considerations

Regardless of which column and oven method are used, there are overlapping ions that can affect quantitation ratios, therefore, the user must

exercise caution. Table 2 also suggests ions for each of the phenols, although the exact ratios and choices depend on the choice of tuning criteria. This table shows that some confirming ion ratios must be affected by the presence of closely eluting phenols. For example, using the deuterated trichlorophenols as surrogates produces a 198 m/z fragment, which is common to the native trichlorophenols. There are similar concerns for other components such as the native and deuterated dichlorophenols.

Two noteworthy deviations from recommendations in Method 528 exist in these methods. The oven programs begin at 40 °C as opposed to the recommended 35 °C. The method states "...GC conditions may be modified, if all performance criteria...are met." Raising the initial temperature to 40 °C avoids the difficulties associated with trying to reach an oven equilibrium temperature of 35 °C when ambient laboratory temperatures are high and so greatly reduces the oven cycle time. This temperature of 40 °C was also demonstrated to work well with standards in dichloromethane as a concession to the continued use of dichloromethane solvent in methods like Method 528 (despite the mandate to reduce the use of chlorinated solvents).

Method 528 also suggests a constant head pressure of 12 to 15 psi. By using constant flow at 1.2 mL/min, the peak shape of the later eluting peaks is dramatically improved, resulting in increased sensitivity and reduced overall runtime. Method 528 contains a peak tailing factor (PTF) performance criteria that requires the acidic and poorly behaving phenols, the 2,4-dinitrophenol, 4-nitrophenol, pentachlorophenol, and 2-methyl-2,4-dinitrophenol, to demonstrate a tailing factor of less than 5 at a concentration of 5 to 10 $\mu\text{g/mL}$. Figures 1 through 4 show these factors for two of the difficult compounds, the 2,4-dinitrophenol and pentachlorophenol, using the Fast Quant methods for the DB-XLB and DB-5ms columns. Excellent PTFs are achieved for these compounds under these methods. PTFs were less than 1.5 which is much smaller than the required PTF of 5.




Figure 1. Peak tailing factor 2,4-dinitrophenol at 5 ng/ μ L on the DB-XLB column with the Fast Quant Method. The PTF is 0.81 (much smaller than the required 5) on a column that had over 100 injections.




Figure 2. Peak tailing factor for pentachlorophenol at 5 ng/ μ L on the DB-XLB column with the Fast Quant Method. The PTF is 1.41 (much smaller than the required 5) on a column that had over 100 injections.




Figure 3. Peak tailing factor for 2,4-dinitrophenol at 5 ng/μL on the DB-5ms column with the Fast Quant Method. The PTF is 1.37 (much smaller than the required 5) on a column that had over 100 injections.




Figure 4. Peak tailing factor for pentachlorophenol at 5 ng/μL on the DB-5ms column with the Fast Quant Method. The PTF is 1.11 (much smaller than the required 5) on a column that had over 100 injections.

"Active" Compounds

The phenols containing nitro-group substituents are well-known to be "active" or difficult compounds that are easily degraded or "lost" in the GC inlet, column, mass spectrometer or GC to MS connection. If the customer wishes to improve the response for these compounds, Agilent supplies liners that directly connect to the GC capillary column and improves the response of the nitro-phenols and related poorly performing compounds. These single and double taper direct connect liners (part numbers G1544-80730 and G1544-80700, respectively) have shown a large increase in 2,4-dinitrophenol response over the standard single taper liners. At the minimum, a double taper liner should be used for the phenols. Improvements in response and peak shape are also possible through pressure or flow programming at injection.

Similarly, the new "Ultra" source (part of applications kit G2860A) for the Agilent 5973 and 5973N MSD shows improvement in response and peak shape for the active phenols, especially the dinitro-series. The discussions in the recent Agilent 8270 application note are very pertinent to the analysis of phenols or other active compounds [4].

Conclusions

These methods are completely adaptable to any of the numerous methods requiring phenol quantification. All the phenols and their internal standards used in the U.S. EPA methods, including the recent 528 Method, are listed. A number of phenols not found in any method are also included to offer analysts an opportunity for more complete characterization of phenols and to avoid misidentification. It is apparent that without this precaution there may be mistakes in phenol identifications which will be misleading in environmental studies

and limit the usefulness of the data in toxicity assessments. The Fast Quant methods developed on both the DB-XLB and DB-5ms columns are particularly useful when surveying and quantitating a limited number of compounds. The significantly reduced runtimes of 16 minutes (DB-XLB) and 14 minutes (DB-5ms) are quite attractive for rapid, target compound analysis. Obviously, the longer, high-resolution methods provide the best separation. In general, better resolution for the phenols is achieved with the DB-XLB column as compared to the DB-5ms column. Both columns exhibit excellent low bleed characteristics, inertness and robustness, which makes them well-suited to these and related analyses.

References

1. Giarrocco, V., B. Quimby, and M. Klee, *Retention Time Locking: Concepts and Applications*, Agilent Technologies, 5966-2469E, <http://www.chem.agilent.com>
2. Agnew, D., et al., *Retention Time Locking with the G1701BA MSD Productivity ChemStation*, Agilent Technologies, (23)-5968-3433E, <http://www.chem.agilent.com>
3. Munch, J.W., *Determination of phenols in drinking water by solid phase extraction and capillary column gas chromatography/mass spectrometry*, U.S. Environmental Protection Agency, Cincinnati, OH.
4. Szelewski, M., W. Wilson and P. Perkins, *Improvements in the Agilent 6890/5973 GC/MSD System for use with USEPA Method 8270*, Agilent Technologies, 5988-3072EN, <http://www.chem.agilent.com>

For More Information

For more information on our products and services, you can visit our site on the World Wide Web at: <http://www.agilent.com/chem>.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2002

www.agilent.com/chem

Printed in the USA
April 3, 2002
5988-3934EN



Agilent Technologies



Solid-Phase Extraction and Gas Chromatography/Mass Spectrometry Analysis of Selected Phenols

Application

Environmental

Authors

Angelica A. Reese
Agilent Technologies, Inc.
91 Blue Ravine Road
Folsom, CA 95630
USA

Harry Prest
Agilent Technologies, Inc.
1601 California Ave
Palo Alto, CA 94304
USA

Abstract

Solid-phase extraction offers a simplified approach to the concentration of compounds present at trace levels in water. Polymeric resins, such as polystyrene-divinylbenzene, offer advantages over the commonly used octadecyl and similar silica-substrate solid-phase extraction adsorbents, especially for more polar compounds. Recently Agilent Technologies has expanded its offering of solid-phase extraction products to include a polystyrene-divinylbenzene solid-phase extraction material specifically for environmental applications, the AccuBond® ENV cartridge. Using the retention time locked gas chromatography/mass spectrometry analytical method previously described [1], this note makes an initial demonstration of the accuracy and precision that can be achieved for selected phenols at 10 ppb in water using this polystyrene-divinylbenzene solid-phase extraction material. The solid-phase extraction procedure is rapid, uses reduced drying times, and requires only two surrogates. The cartridge design has been optimized to provide increased recoveries for phenol, which

typically has low and irreproducible recoveries. Recoveries for phenol exceeded 70% and other phenols were greater than 90%. Precision was better than 5% and accuracy, as indicated by average absolute deviation as percent, was better than 8% for all phenols except 2-cyclohexyl-2,4-dinitrophenol. Sample delivery rate is high (20 to 25 mL/min) so a 1-liter sample can be extracted in less than an hour.

Introduction

Solid-phase extraction (SPE) has evolved to be a powerful tool for isolation and concentration of trace analytes in a variety of sample matrices. SPE has grown to replace liquid/liquid extraction due to the minimal use of solvent, the simplicity and flexibility of the approach, and the increased selectivity for analytes available. Beginning in and throughout the last decade, a large number of SPE applications were developed for compounds in matrices of environmental interest. The major focus of these applications was the collection and concentration of trace analytes from water. Most of the analytes were non-polar and strongly hydrophobic in nature such as polychlorinated biphenyls (PCBs), the organochlorine pesticides, polynuclear aromatic hydrocarbons (PAHs), for example, as these were relatively easy candidates for the technique and of widespread concern. More polar compounds like the phenols offer particular challenges.

SPE exploits the similarity in physicochemical properties of a class of analytes, their interaction with the SPE material, and their differences from the matrix. The phenols encompass a wide range in polarities and solubilities as shown in Table 1.



Agilent Technologies

The pKa values indicate that the dinitrophenol and the tetra- and penta-chloro phenols are fairly acidic and therefore are predominately dissociated in water at near-neutral pHs. Acid-base equilibrium considerations require that the water sample be acidified to at least 2 pH units below that of the lowest pKa value(s) to generate phenols primarily in their non-ionized form. Octanol-water partition constants (K_{ow}) and water solubilities of the undissociated compounds range over a factor of more than several thousand. The high aqueous solubilities and low K_{ow} s of phenol and the monosubstituted phenols make these the most difficult phenols to capture and retain.

Table 1. Physicochemical Properties of Some Phenols

Compound	$\log_{10} K_{ow}$	pKa	Solubility _(aq) g/L
Phenol	1.46	9.89	0.0884
4-chlorophenol	2.4	9.18	.027
4-methylphenol	1.96	10.26	.02
3-methylphenol	1.98	10	.022
4-nitrophenol	1.91	7.08	.013
2,4-dichlorophenol	3.2	7.68	.0045
2,4-dimethylphenol	2.35	10.6	.0088
2,4-dinitrophenol	1.67	4.09	.00034
2,4,6-trichlorophenol	3.69	7.42	.00043
2,3,4,6-tetrachlorophenol	4.45	5.38	.00018
Pentachlorophenol	5.05	4.92	0.000014

Polymeric resins were used early in the history of solid-phase extraction. These early materials needed extensive cleanup prior to use to avoid interferences obscuring analytes of interest. New generations of these polymers such as polystyrene-divinylbenzene (PS-DVB) have much lower backgrounds due to improvements in manufacturing processes. The use of PS-DVB polymers as an absorbent material has been demonstrated to provide improved recoveries for phenolic compounds as compared to the traditional and more commonly applied C18 material [2]. The details provided here ensure that analysts will observe less breakthrough of phenol, greatly improving overall recoveries.

The objective of this work was to develop a simple approach to SPE extraction and gas chromatography/mass spectrometry (GC/MS) analysis for selected phenols and perform a preliminary demonstration of accuracy and precision. A previous application note describes the retention-time locked GC/MS method in detail [1].

Experimental

The phenols were obtained from Ultra Scientific (North Kingstown, RI) and AccuStandard (New Haven, CT) as mixtures. Dilutions were made in acetone and in dichloromethane (Burdick and Jackson Grade, VWR Scientific, San Francisco, CA) for surrogates or spiking and standards, respectively. Sodium sulfate (analytical grade, VWR Scientific, San Francisco, CA) was kilned at 500 °C and stored in a desiccator.

Empty 6-mL cartridges and frits were obtained from Agilent Technologies Inc. (Wilmington, DE) for use as drying cartridges. AccuBond^{II} ENV PS-DVB cartridges containing 1000 milligrams of PS-DVB sorbent in a 6-mL cartridge were obtained from Agilent Technologies Inc. (Wilmington, DE). A summary of the equipment and consumables is given in Table 2.

Table 2. Equipment and Consumables Summary

Description	Part Number
Silanized amber vials	5183-4496
Vial crimp caps	5181-1210
AccuBond ^{II} ENV PS-DVB polymeric resin as 1000 mg / 6-mL cartridge, box of 30	188-3060
Empty SPE Cartridges Reservoirs, 6 mL, box of 50	700-4006
Frits for 6 mL cartridges reservoirs, 100/pk	700-4031
Stopcock valves, 10/pk	5185-5758
SPE Manifold, 10-port	5185-5754
SPE Manifold, 20-port	5185-7565

Spike and Recovery Experiments

For the initial demonstration of the accuracy and precision of the approach, 1.0 L of deionized RO water was spiked with 21 phenols at 10 pbb each. Deuterated phenol, 2,4-dibromophenol, and 2,4,6-tribromophenol were added at 10 ppb as recovery surrogates. Three “calibrators” were also made at that time by adding the spike and surrogates to a silanized vial containing some dichloromethane (DCM) as a keeper. The solution was mixed and the pH lowered to ≤ 2 with 5N HCl.

The PS-DVB SPE cartridge was conditioned by sequentially rinsing with 9 to 12 mL of DCM, 9 to 12 mL of methanol, and 9 to 12 mL of 0.05N HCl. At no time after the initial addition of DCM was the column allowed to run dry.

The 1-L water sample was then pulled through the SPE cartridge at a flow between 20 and 25 mL/min such that the sample was processed in less than 1 hour. The SPE cartridge was dried briefly by drawing clean laboratory air through the cartridge for about 2 minutes while tapping the cartridge body to dislodge bound water. The SPE cartridge was then eluted with 9 mL of DCM. The DCM eluant was dried using a cartridge filled with anhydrous sodium sulfate.

The dried DCM eluant was evaporated under dry, filtered nitrogen and transferred to a silanized amber vial. At this point, the volumes of the sample and the three calibrators were brought to approximately 0.9 mL and 100 μ L of a solution containing 2,5-dibromotoluene and 2,2',5,5'-tetrabromobiphenyl at 0.05 μ g/ μ L in DCM was added as internal (injection) standards. A solvent blank, the three calibrators and the sample were then

analyzed using an Agilent 6890 Plus GC and 5973N MSD according to operating parameters given in a previous note [1].

Results and Discussion

Corrected and uncorrected results of inter-day replicates for selected phenols are shown in Table 3. Phenol values were corrected to the deuterated phenol while all other compounds were corrected to 2,4-dibromophenol recoveries. With the exception of the 2-cyclohexyl-2,4-dinitrophenol, all RSD values and deviations are under 5% and 8%, respectively. The average RSD and absolute deviation for all the compounds are 4% and 6%, respectively. These indicate very good reproducibility and accuracy. An anomalously high value in the third trial seems to have inflated the deviation for 2-cyclohexyl-2,4-dinitrophenol.

Table 3. Spike and recovery results for accuracy and precision at 10 ppb using the AccuBond[®] ENV SPE cartridge. The average deviation is calculated as the relative average of the absolute deviations from 10 ppb and expressed as percentages. RSD represents the relative standard deviations.

Trial Number: Compound	Trial #1		Trial #2		Trial #3		RSD %	Average Deviation
	Uncorrected	Corrected	Uncorrected	Corrected	Uncorrected	Corrected		
Phenol	7.8	10.7	7.2	10.3	7.7	11.0	3%	7%
2-chlorophenol	9.8	9.3	9	8.9	10.3	9.3	3%	8%
2-methylphenol	9.9	9.4	9.1	9.0	10.5	9.5	3%	7%
3- & 4-methylphenol	9.8	9.3	9.2	9.1	10.4	9.4	2%	7%
2,4-dimethylphenol	9.9	9.4	9.4	9.3	10.5	9.5	1%	6%
2-nitrophenol	10.0	9.5	9.1	9.0	10.7	9.6	4%	6%
2,4-dichlorophenol	9.9	9.4	9.1	9.0	10.5	9.5	3%	7%
2,6-dichlorophenol	9.7	9.2	9.1	9.0	10.4	9.4	2%	8%
4-chloro-3-methylphenol	10.1	9.6	9.3	9.2	10.7	9.6	3%	5%
2,4-dibromophenol	10.5		10.1		11.1			
2,4,6-trichlorophenol	9.7	9.2	9.1	9.0	10.6	9.5	3%	7%
2,4,5-trichlorophenol	9.8	9.3	9.1	9.0	10.4	9.4	2%	8%
4-nitrophenol	10.0	9.5	9.8	9.7	11.5	10.4	4%	4%
2,3,4,5-tetrachlorophenol	9.7	9.2	9.3	9.2	10.7	9.6	3%	6%
2,3,5,6-tetrachlorophenol	9.9	9.4	9.1	9.0	10.4	9.4	2%	7%
2,3,4,6-tetrachlorophenol	9.8	9.3	9.3	9.2	10.6	9.5	2%	6%
2,4-dinitrophenol	10.6	10.1	9.8	9.7	11.9	10.7	5%	4%
2,4,6-tribromophenol	9.7	9.2	9.6	9.5	10.7	9.6	2%	5%
2-methyl-4,6-dinitrophenol	10.1	9.6	9.5	9.4	11.4	10.3	5%	4%
Pentachlorophenol	9.8	9.3	9.5	9.4	11.1	10.0	4%	4%
Dinoseb	10.2	9.7	9.4	9.3	11.5	10.4	5%	4%
2-cyclohexyl-4,6-dinitrophenol	11.2	10.7	10.6	10.5	14.4	13.0	12%	14%
2,2',5,5'-tetrabromobiphenyl	10.5	10.0	10.5	10.4	12.3	11.1	5%	5%

Typically, a 1-gram sorbent cartridge is considered an excessive use of material. However, work with 500-mg cartridges showed recoveries for phenol near and below 50%. Tandem cartridges revealed substantial phenol on the second cartridge. Increasing the polymer mass to 1 gram reduced breakthrough and consequently increased phenol recoveries. The methylphenols also demonstrated this behavior to a lesser degree and supported the change in sorbent bed mass.

Using a single surrogate to correct all the substituted phenols seems a tremendous simplification since the behavior and chemistries of the phenols differ widely. It is likely that this will become apparent at lower concentrations and most likely for the nitrophenols. Data does imply that the tetrabromobiphenyl (included in Table 3) may allow a better correction of the injection volume for the late eluters.

Conclusions

These preliminary results show that phenols can be extracted from aqueous samples accurately and precisely using AccuBond^{II} ENV PS-DVB polymeric resin. Coupled with a gas chromatographic analysis and retention time locking GC/MS [1], extraction, identification and quantitation of phenolic compounds can be done confidently, accurately and reproducibly. This method is a modification of U.S. EPA Method 528 [3]. The procedure here for the extraction of phenols from drinking water by polymeric SPE results in improved recoveries and greatly reduced drying times (2 minutes compared to 20 minutes), which increases sample throughput. The next steps in developing a full method

would be an exploration of detection limits which will require extraction of replicates at lower concentrations. It is expected that the behavior of the more "active" compounds may suggest an expanded suite of surrogates.

References

1. Reese, A. and H. Prest, *Retention Time Locked GC/MS Analysis of Phenols*, 5988-3934EN, www.agilent.com/chem
2. Rodriguez, Llompart and Cela, *Solid-phase extraction of phenols*, Journal of Chromatography A, 885 (2000) 291-304.
3. Munch, EPA Method 528, *Determination of Phenols in Drinking Water by Solid-Phase Extraction and Capillary Column Gas Chromatography/Mass Spectrometry (GC/MS)* Revision 1 (April 2000).

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
January 15, 2002
5988-5255EN





Improvements in the Agilent 6890/5973 GC/MSD System for Use with USEPA Method 8270

Application

Environmental

Author

Mike Szelewski
Bill Wilson, Ph.D.
Agilent Technologies
2850 Centerville Road
Wilmington, DE 19808
USA

Pat Perkins, Ph.D.
Agilent Technologies
1601 California Avenue
Palo Alto, CA 94304
USA

Abstract

Method 8270 presents challenges due to the simultaneous measurement of acids, bases and neutrals over a concentration range that varies from lab to lab. Laboratories want GC/MS instruments that are linear and inert over a wide concentration range. Changes have been made to the 6890/5973 GC/MSD system in the inlet, column, and source areas based on feedback from our customers. System performance has been improved by maximizing linearity and minimizing activity.

Introduction

USEPA Method 8270 (including versions A, B, C and D) is used to determine the concentration of semivolatile organic compounds in extracts prepared from many types of solid waste matrices, soils, air sampling media and water. The January 1998, revision 4, 8270D lists 240 possible analytes that can be measured. Most laboratories analyze for a significantly smaller number of compounds, usually 70 to 100.

Regardless of the number of analytes, there is usually a mix of acids, bases and neutrals that must be measured concurrently. This mix presents a challenge for instrument design due to the interaction of the analytes with the instrument and consumables.

The calibration range required for the analysis varies depending on a particular laboratory's statement of work. Method 8270 does not specify a calibration range, yet traditionally a range of 20 to 160 ng (nanograms) has been used as a carry-over from the USEPA Contract Lab Program (CLP). With the increased sensitivity of newer GC/MS systems, laboratories are moving toward lower minimum detection limits (MDLs) and pushing the 8270 calibration range down to 5 ng.



Agilent Technologies

The 6890/5973 GC/MSD (Gas Chromatograph/Mass Selective Detector) system was designed to meet demand for these lower MDLs. To further enhance performance, two main areas of improvement were identified in communications with users.

The first was improving the linearity of the GC/MSD system at the high end of the calibration range where roll off or flattening out of the calibration was observed. The relative response factors (RFs) were lower than they should have been at higher concentrations. This was seen for phthalates and for PAHs (Polyaromatic Hydrocarbons).

The second area for improvement was recovery at the low end of the calibration range for active compounds. The most active compounds, the nitrophenols, showed lower RFs at the low end of the calibration range than what was expected on some systems. The most active of these, 2,4-dinitrophenol, showed RFs below method requirements on some systems.

A study was undertaken to address the high end linearity and the low end activity. The primary goals of the study were to meet the following 8270 requirements:

1. Minimum Average RF of 0.050 for the System Performance Check Compounds (SPCCs) (Method 8270D, section 7.3.4.2)
2. Maximum Relative Standard Deviation (RSD) of 30% for the Calibration Check Compounds (Method 8270D, section 7.3.5.2)
3. Maximum Mean Relative Standard Deviation of 15% across all compounds (Method 8000B, section 7.5.1.2.1)

Additional study goals to ensure maximum productivity for the user were:

1. Minimize activity in the entire GC/MSD system to maximize RFs for active compounds—this gives the user a greater margin for system degradation when analyzing dirty samples.
2. Maximize linearity in the GC/MSD system at the high end without losing significant sensitivity at the low end—this improves overall RSDs.
3. Preserve method resolution requirements for benzo[b]fluoranthene and benzo[k]fluoranthene when using thinner film columns for shorter analysis times.

Experiments were done to meet the study goals by dividing the system into three main sections :

GC column, GC inlet, and MSD. Each of these areas is treated separately in a following section of this note.

Column

Column test system

To reduce the complexity of the chromatographic system and to provide the best possible sample introduction and detection, a COC/FID (Cool-On-Column/Flame Ionization Detector) system was used to test column performance. On-column injection eliminates any inlet activity while FID gives sensitive and essentially universal response for the analytes. The FID also provides directly comparable response information that can be used to validate analyte introduction between systems.

Test mix

To establish a test mix for evaluating the column and other components in the system, both anecdotal information and suggestions in the method were reviewed. Section 1.4 of 8270D points out the following compounds as potentially troublesome:

1.4.1 Benzidine may be subject to oxidative losses during solvent concentration and its chromatographic behavior is poor.

1.4.4 N-nitrosodimethylamine is difficult to separate from the solvent under the chromatographic conditions described.

1.4.6 Pentachlorophenol, 2,4-dinitrophenol, 4-nitrophenol, benzoic acid, 4,6-dinitro-2-methylphenol, 4-chloro-3-methylphenol, 2-nitroaniline, 3-nitroaniline, 4-chloroaniline, and benzyl alcohol are subject to erratic chromatographic behavior, especially if the GC system is contaminated with high boiling material.

Furthermore, the method cites several mixes of compounds for evaluating system performance. The DFTPP (decafluorotriphenylphosphine) mix adds 4,4'-DDT to the previously cited compounds. The system performance check compounds add N-nitroso-di-n-propylamine and hexachlorocyclopentadiene. Finally, the calibration check compounds add six more phenols as well as seven base/neutral compounds.

From anecdotal information, the phenols presented the greatest challenge. If the phenols cited are combined, the list is essentially all the phenols in EPA Method 604. While more test solute information was being collected, the phenols were run by COC/FID. Table 1 shows the RSD values for relative response factors from 5 to 160 ng on column. The last four compounds prove to be the most troublesome with 2,4-dinitrophenol being noticeably worse. Even so, the RSD values are all below 8%, indicating that COC/FID can be used to evaluate column performance. When done with unoptimized conditions/consumables in splitless sample

Table 1. Cool-on-column FID, RSD of RFs from 5 to 160 ng on column

Solute	RSD
Phenol	3.0
2-Chlorophenol	3.1
2-Nitrophenol	3.2
2,4-Dimethylphenol	3.3
2,4-Dichlorophenol	3.1
4-Chloro-3-methylphenol	3.2
2,4,6-Trichlorophenol	3.3
2,4-Dinitrophenol	6.9
4-Nitrophenol	3.8
4,6-Dinitro-2-methylphenol	4.3
Pentachlorophenol	4.5

introduction, the RSD values become unusable for these difficult compounds. With this information and the anecdotal performance data, a more comprehensive mix was devised.

The “short mix” is comprised of the four phenols from above, several bases, several neutral compounds, and the internal standards at 40 ng/μL. The compounds were selected so that they were easily resolved and unambiguously detected by COC/FID. Figure 1 shows a sample chromatogram of the short mix on a 0.5 μm column.

Column testing

8270D states that a 30 m × 0.25 mm × 1 μm silicone coated capillary column be used in the analysis. However, the method also makes provisions for split injections, allowing a thinner film to be used. Because of the obvious time pressure to perform environmental analyses, thinner film columns are widely used. From customer inputs, film thickness ranged from 0.25 to 1 μm; consequently, 0.25, 0.5, and 1 μm film thickness columns were evaluated. Each of the columns had already passed the Agilent 5MS column checkout and were used as received. In addition, columns from another supplier were also tested, yielding similar results to the Agilent columns.




Figure 1. COC-FID Chromatogram and identification of short mix compounds.

The instrument parameters followed the 8270 method operating conditions as closely as possible. The COC inlet was run in oven track mode, the column flow was constant at 1.3 mL/min, and the FID was set to 300 °C. The oven program followed the 8270 method except that the program rate (10 °C/min) was adjusted for the different film thickness to resolve the test compounds.

Numerous columns from each film thickness were tested. It is important to remember that all of these columns passed the standard column testing protocol. An arbitrary metric was set for pass/fail criteria. This value was 10% RSD for the 2,4-dinitrophenol RFs from 5 to 160 ng on column. Of all the columns tested, only a fraction gave results below this metric. Film thickness was not a factor since the same fraction of columns passed for each film thickness. Some of the columns were so active that the column alone could cause the system to fail the method qualifying criteria. For this reason, it is imperative that a stringent test protocol be utilized for evaluating columns and that only specifically tested columns be used for 8270D. A comparison of a column that passed and one that failed the arbitrary criteria is shown in Table 2.

Table 2. COC-FID Results on a "Pass" and a "Fail" 0.5 µm Column, 5 to 160 ng

Solute	"Pass"		"Fail"	
	RSD	Avg RF	RSD	Avg RF
N-Nitrosodimethylamine	0.78	0.54	0.30	0.52
Aniline	1.2	1.45	0.59	1.43
2,4- Dinitrophenol	7.5	0.33	21.	0.28
4-Nitrophenol	0.49	0.52	2.9	0.50
4,6-Dinitro-2-methylphenol	4.7	0.40	14.	0.37
4-Aminobiphenyl	1.0	0.94	3.3	1.02
Pentachlorophenol	5.0	0.34	15.	0.26
Benzidine	2.6	0.74	2.8	0.72
3,3'-Dichlorobenzidine	7.9	0.57	0.58	0.62

Column selection

Since all the film thicknesses studied can meet the method objectives, the column selection is typically based on other analysis needs. As in all chromatographic systems, there is a balance between speed of analysis, resolution, and column capacity. The 0.25 µm film thickness columns offer the fastest analysis possible but with a compromise in resolution and capacity. Conversely, the 1.0 µm columns provide the best capacity but at a cost of time. Using the Agilent method translation tool, the 0.5 µm film column is only a factor of two slower than the thin film column while providing a twofold increase in capacity. The 0.5 µm film

thickness column offers a good compromise between speed and capacity.

Inlet

There are many inlet related factors that affect 8270 performance. These include: split vs. splitless injection, syringes, injection volume, septa, inlet temperature, inlet seal, liners, using wool or not in the liner, and using a pulsed (flow programmed) vs a normal injection. Some of these parameters were studied to determine their contribution to low end activity and to high end linearity.

Split injection is allowed if the MSD has enough sensitivity. Split injections put less material on column, making it easier to meet resolution requirements on thinner film columns and at the same time improving peak shapes. However less material on column results in noticeable losses of active compounds due to column or MSD activity. High end linearity could be improved using split injections but the issue was solved as described in the source section of this note. Splitless injection is almost universally used and will be the focus of this inlet section.

A syringe experiment was not done as part of this study. Previous data show better reproducibility when using a 5 µL syringe in an ALS (Automatic Liquid Sampler). All injections were made using a 5 µL syringe with a tapered needle.

Injection volume was always 1 µL for the study. 8270 allows for 1 to 2 µL injection volumes, but previous data show worse reproducibility when using 2 µL injections. This is most likely due to expansion outside the liner and subsequent loss of analytes. Additionally, more residue is introduced with larger injection volume, negatively impacting instrument uptime.

Septa types were not studied and green septa were used. Inlet temperature was held at 250 °C. A new gold inlet seal was fitted with each liner, although changing the seal for a direct connect liner may not be necessary. Stainless steel (SS) seals were not used.

The inlet study focussed on liner types, carrier gas flow through the column during injection and the presence or absence of glass wool. The five different liner types that were used are described in Table 3. Two of the liners, the G1544-80700 and G1544-80730 are new designs. The column makes a direct connection into the liner bottom, similar to a capillary column connector.

Table 3. 2,4-Dinitrophenol Average RFs Using Various Inlet Liners, COC-FID

Splitless time Column flow		ng injected	0.2 min 1 mL/min		0.2 min 3 mL/min		0.75 min 1 mL/min		0.75 min 3 mL/min	
Part number	Liner		Avg RF	RSD	Avg RF	RSD	Avg RF	RSD	Avg RF	RSD
5062-3587	Single taper with glass wool	5	0.007	63	0.023	55	0.017	58	0.072	38
		160	0.122		0.198		0.187		0.228	
5181-3316	Single taper	5	0.092	37	0.136	21	0.105	33	0.125	22
		160	0.279		0.232		0.261		0.207	
5181-3315	Dual taper	5	0.203	14	0.215	11	0.201	15	0.216	12
		160	0.285		0.255		0.296		0.287	
G1544-80730	Single taper direct contact	5	0.287	5	0.269	7	0.272	6	0.229	9
		160	0.311		0.316		0.310		0.285	
G1544-80700	Dual taper direct contact	5	0.289	5	0.280	6	0.275	7	0.278	7
		160	0.331		0.330		0.327		0.328	
	COC	5	0.311	3	0.311	3	0.331	3	0.311	3
		160	0.331		0.331		0.331		0.331	

All liner experiments were performed using an FID to eliminate any affect an MSD would have on the results. RFs are not identical for MSD and FID due to inherent response differences. An approximate conversion is $RF_{fid} \times 0.7 = RF_{msd}$. Cool-on-column injection was done as a baseline for inlet performance.

The short mix was injected at the 5, 20, 80 and 160 ng levels, four replicates at each level. This series of 16 injections was made on each liner at each set of inlet conditions. There were four sets of inlet conditions. The splitless time was either 0.2 minute or 0.75 minute. The carrier flow through the column was either 1.0 mL/min or 3.0 mL/min held for the splitless time + 0.05 minute, then reduced to 1.2 mL/min. This is similar to a “pulsed splitless” injection, however flow programming gives the analyst control over the depressurization rate. The COC injections were made at a fixed column flow and the splitless time is not relevant.

Table 3 shows the results of these analyses. The average RFs for 2,4-dinitrophenol at the 5 ng and 160 ng levels are shown together with the RSD of all 16 RFs for each liner type/inlet conditions.

The 3587 liner shows the worst performance. 2,4-dinitrophenol has been eaten by the glass wool and low end activity is at its worst. Unfortunately most analysts use glass wool in the liner to prevent solids from contaminating the column.

The 3316 liner is the same as the 3587 but without the wool. Loss of 2,4-dinitrophenol can be attributed to contact with the gold inlet seal, the polyimide coating on the column outside and the stainless steel at both the top and bottom of the inlet. There could also be analyte contact with the stainless steel in the annular volume outside the liner.

The 3315 liner is the same as the 3316, but with a narrower opening at the top. This minimizes contact with the top of the inlet and there is an increase in 2,4-dinitrophenol response.

The new 80730 liner minimizes analyte contact with the polyimide on the column outside, the gold inlet seal and the inlet annular volume. Response for 2,4-dinitrophenol was significantly improved using this liner, even though it has a wide top similar to the 3316.

The new 80700 liner has the advantages of the 80730 and has a narrower top opening similar to the 3315. An additional increase is seen in 2,4-dinitrophenol response because analyte contact with inlet surfaces is minimized at both the top and bottom. Performance with this liner is nearly equal to that of COC and low end activity is minimized for the inlet only.

Figure 2 shows performance of the five liners and COC with one set of conditions that was used. The splitless time was 0.75 minute and the column flow was 3 mL/min during the injection. Each of the

bars shows the average RF for 2,4-dinitrophenol of the four replicate injections at each level. The order is 5 ng at the top increasing to 160 ng at the bottom. Above each bar is listed the average RF and RSD across all 16 injections. The 3587 liner with the wool shows the worst performance and the new 80700 liner with the direct connect bottom and narrow top shows the best performance. The COC data show column performance isolated from a hot splitless inlet. There is a slight drop-off in COC RFs comparing 5 ng to higher levels. Data for the other three sets of experimental conditions show similar trends and are not presented.




Figure 2. 2,4-Dinitrophenol RFs using five different liners.

Figure 3 shows performance of the 3587 liner at the four sets of experimental conditions. These data are shown as liners with wool are widely used. Comparing the first two bars shows the difference between a column flow of 1 mL/min and 3 mL/min during injection, both with a 0.2 minutes splitless time. Higher flow sweeps the inlet faster minimizing contact with the wool resulting in better 2,4-dinitrophenol performance. The higher column flow also means a higher inlet pressure. Previous work has shown that higher inlet pressures can keep the expanded solvent vapor contained in the liner. This holds true comparing the third and fourth bars with a 0.75 minute splitless time. The longer splitless time also results in a more complete transfer of 2,4-dinitrophenol onto the column at a fixed flow. In all cases performance suffers compared to COC.

In addition to 2,4-dinitrophenol, RFs and RSD were tracked for the other analytes in the short mix. Similar improvements were seen for the other active compounds although the liner effects were not as dramatic due to better performance of these

compounds initially. No adverse effects were seen for the neutral or basic compounds when the acidic compounds improved.

Another factor that was monitored was ISTD (internal standard) reproducibility. Using the new direct connect liners showed variability in ISTD areas on some test systems greater than that using the standard liners. These systems still met the -50%/+100% 8270 ISTD criteria. Using a column flow of 3 mL/min during the injection period minimized this ISTD variability.

The high end linearity issue is not caused by the inlet although inlet parameters can affect it. The low end activity issue is directly related to inlet activity, including liner, seal, wool and stainless steel. Activity can be minimized by using pressure programmed flow and optimized splitless time. The liner and the presence of wool have the largest affect on low end activity. The liner must be chosen based on sample type, allowing for a trade-off of activity vs dirtiness of extract.




Figure 3. 2,4-Dinitrophenol RFs using a 3587 liner.

Source

The position of the column in the ion source, ion source materials, dimensions of the ion source, and parameters used for operation all affect the response of the system in this method.

In general, the column should be positioned beyond the end of the interface but not too far into the ion source. If the column tip is positioned inside of the interface guide tube, compounds are exposed to the hot metal surface of the interface and may decompose. On the other hand, if a significant length of column is exposed inside the ion source, the polyimide coating of the column can take on a static charge due to the ions and electrons in the ion source, and this charge interferes with the ejection of ions from the ion source chamber. In practice, a 2 to 3 mm extension of the column out of the interface has been found to yield the best results. This position may be set by one of two methods:

- 1 Put the column nut and ferrule on the column; open the analyzer door; push the column through the interface until 2 to 3 mm is sticking out of the end; then tighten down on the column nut; or
- 2 Put the column nut and ferrule on the column; open the analyzer door; push the column through the interface until it is just beyond the end of the interface. Tighten the nut only finger tight. Hold the MSD analyzer door closed, and then slide the column in until it just bottoms out (stops). You have now hit the left side of the source. Mark the column with typewriter correction fluid in the oven next to the nut. You can release the MSD analyzer door. Back the column out 12.5 mm (the source i.d.). Tighten the column nut. There should be 2 to 3 mm of column visible at the MSD end of the transfer line. You have now positioned the column just inside the source.

Method 1 above has the advantage that you can see what is happening, but a disadvantage is that it is difficult to measure the 2 to 3 mm column length inside the vacuum manifold. Method 2 has a few more steps but gives reproducible results, if followed exactly.

The material used for the standard MSD ion source may decompose some analytes under some conditions, especially when the source temperature is high. The Ultra source (patent applied for) has been found to reduce low end activity under the conditions typically used for this method. Table 4 shows a comparison of RFs for 2,4-dinitrophenol using different source materials. It also shows that the new Ultra source can be abrasively cleaned with minimal loss in performance.

The high end linearity is a function of the density of ions produced in the ion source. Reducing the ion source pressure improves the high end linearity. Therefore, increasing the size of the holes in the ion source improves the high end linearity, attended by some loss in sensitivity. To improve high end linearity, the hole in the drawout lens is made 6 mm in diameter rather than the standard 3 mm diameter. The change in dimension allows for a better match between the instrument's linear working range and the requirements of the method.

Another way of improving the high end linearity is to alter the operating parameters used in the method. A combination of a lower emission current (20 μ A) and a high repeller setting (25 V) was determined to improve high end linearity so that the RSD of the analytes with strong response were single digit values. These analytes are the PAHs and phthalates. The emission current of 20 μ A is set by the analyst. The revised tuning macros automatically set the repeller voltage to 25 V.

Table 4. 2,4-Dinitrophenol Average RFs Using Various Ion Sources

ng Injected	COC-MSD Avg RFs of 2,4-dinitrophenol, n=4				
	5	20	80	160	Avg
Ultra source	0.121	0.185	0.229	0.244	0.194
Ultra source air baked at 150 °C	0.120	0.185	0.228	0.244	0.194
Ultra source cleaned with 400 grit SC paper	0.119	0.181	0.220	0.231	0.188
Ultra source cleaned with metal polish	0.107	0.169	0.209	0.221	0.177
Standard source B	0.036	0.073	0.132	0.152	0.098
Standard source A	0.025	0.036	0.063	0.086	0.052

Data

As a result of this study, the G2860A 8270 Semi-Volatiles Applications Kit has been developed. The kit provides modified and/or pretested components to improve system performance for USEPA Method 8270. The kit includes an Ultra source, specially tested column, inlet liners and tune macros. The data in Table 5 are an average result of four Ultra source/column combinations. These can be considered typical of a 6890/5973 system with the applications kit installed.

The data in Table 5 are from calibrations at 5, 10, 20, 50, 80, 120 and 160 ng. This extended range exceeds the typical range of 20 to 160 ng. The data meet the 8270 criteria listed in the Introduction section of this application note. The minimum average RF is well above the required 0.050 for all of the SPCCs. The RSDs for all the CCCs are significantly less than 30% required. The mean RSD of 7% across all compounds easily meets the minimum criteria of 15%.

Table 5. Typical results from a 6890/5973 GC/MSD System with the G2860A Applications Kit Installed, 5 to 160 ng, 1 µL Splitless Injection

	Avg RF	RSD		Avg RF	RSD
ISTDs					
1,4-Dichlorobenzene-d4		8	2-Chloronaphthalene	1.003	5
Naphthalene-d8		7	2-Nitroaniline	0.482	10
Acenaphthene-d10		7	Acenaphthylene	1.512	5
Phenanthrene-d10		8	Dimethylphthalate	1.187	4
Chrysene-d12		9	2,6-Dinitrotoluene	0.272	6
Perylene-d12		9	Acenaphthene (CCC)	0.958	5
Analytes					
Pyridine	1.436	6	3-Nitroaniline	0.265	8
N-Nitrosodimethylamine	0.799	6	2,4-Dinitrophenol (SPCC)	0.130	25
2-Fluorophenol	1.189	4	Dibenzofuran	1.421	4
Aniline	1.576	6	2,4-Dinitrotoluene	0.364	9
Phenol-d5	1.639	6	4-Nitrophenol (SPCC)	0.205	11
Phenol (CCC)	1.783	4	Fluorene	1.152	5
bis(2-chloroethyl) ether	1.280	5	4-Chlorophenyl-phenylether	0.566	6
2-Chlorophenol	1.293	4	Diethylphthalate	1.177	5
1,3-Dichlorobenzene	1.320	3	4-Nitroaniline	0.223	9
1,4-Dichlorobenzene (CCC)	1.371	3	4,6-Dinitro-2-methylphenol	0.135	16
1,2-Dichlorobenzene	1.275	3	Diphenylamine (CCC)	0.518	6
Benzyl alcohol	0.895	7	2,4,6-Tribromophenol	0.109	8
bis(2-chloroisopropyl)ether	2.273	9	Azobenzene	0.177	5
2-Methylphenol	1.356	7	4-Bromophenyl-phenylether	0.206	5
Hexachloroethane	0.615	3	Hexachlorobenzene	0.198	4
N-Nitroso-di-n-propylamine (SPCC)	1.508	5	Pentachlorophenol (CCC)	0.123	9
4-Methylphenol	1.243	7	Phenanthrene	1.064	4
Nitrobenzene-d5	0.489	3	Anthracene	1.017	4
Nitrobenzene	0.452	3	Carbazole	0.734	7
Isophorone	0.770	3	Di-n-butylphthalate	1.248	7
2-Nitrophenol (CCC)	0.188	7	Fluoranthene (CCC)	1.184	5
2,4-Dimethylphenol	0.309	8	Pyrene	1.344	5
bis(2-Chloroethoxy)methane	0.407	4	Benzidine	0.295	9
Benzoic acid	0.154	39	Terphenyl-d14	0.963	5
2,4-Dichlorophenol (CCC)	0.282	7	Butylbenzylphthalate	0.707	8
1,2,4-Trichlorobenzene	0.289	4	3,3'-Dichlorobenzidine	0.322	8
Naphthalene	0.919	4	Benzo[a]anthracene	1.213	5
4-Chloroaniline	0.340	9	Chrysene	1.168	3
Hexachlorobutadiene (CCC)	0.191	5	bis(2-Ethylhexyl)phthalate	0.906	4
4-Chloro-3-methylphenol (CCC)	0.341	6	Di-n-octylphthalate (CCC)	1.650	9
2-Methylnaphthalene	0.606	4	Benzo[b]fluoranthene	1.197	9
Hexachlorocyclopentadiene (SPCC)	0.267	11	Benzo[k]fluoranthene	1.108	8
2,4,6-Trichlorophenol (CCC)	0.370	8	Benzo[a]pyrene (CCC)	0.995	7
2,4,5-Trichlorophenol	0.368	6	Indeno[1,2,3-cd]pyrene	0.807	8
2-Fluorobiphenyl	1.222	4	Dibenz[a,h]anthracene	0.689	9
			Benzo[g,h,i]perylene	0.741	8
			Average of analyte RSDs		7

Continued

The additional study goals were also met. Method resolution requirements for benzo[b]fluoranthene and benzo[k]fluoranthene can be met when using thinner film columns depending on inlet parameters used. Linearity has been maximized at the high end without losing significant sensitivity at the low end. This improves overall RSDs. Activity in the entire GC/MSD system has been reduced thereby maximizing RFs for active compounds such as the nitrophenols. This gives the user a greater margin for system degradation when analyzing dirty samples.

These system improvements ensure maximum productivity for the analyst using an Agilent Technologies 6890/5973 GC/MSD for USEPA Method 8270.

Instrument Operating Parameters

Two sets of recommended instrument operating parameters are listed in Table 6 and Table 7. These are starting conditions and may have to be optimized.

The ramped flow and splitless times in Table 6 result in less material on column, better peak shape and resolution of benzo[b]fluoranthene and benzo[k]fluoranthene using a 0.5 μm column as provided in the G2860A 8270 Semi-Volatiles Applications Kit. However, less material on column may result in lower response factors for active compounds.

The ramped flow and splitless times in Table 7 result in more material on column, resulting in worse peak shape and benzo[b]fluoranthene and

benzo[k]fluoranthene are not resolved. However, more material on column may result in higher response factors for active compounds.

The 0.5 μm film thickness column is a compromise of speed versus resolution. A 1.0 μm film thickness column is recommended in 8270 for best resolution and best peak shape at higher analyte concentrations. Using a 1.0 μm film thickness column also results in the longest run times. A 0.25 μm film thickness column will give shorter run times, but capacity suffers and consequently so does peak shape. Some laboratories meet method resolution requirements using split injections on a 0.25 μm column.

Many users have had success keeping this method running by clipping the front end of the column on a regular basis, daily if needed. The first compounds to suffer degradation from not clipping the column are the phenols.

The 5181-3316 liner is also a compromise. The absence of wool helps to preserve active analytes but potentially subjects the column to degradation from dirty samples. Adding a wisp of wool will help protect the column but active analytes will decompose. The new direct connect liners are the best choice for clean samples or for minimizing inlet activity.

The method operating parameters given here should only be considered a good starting point. Optimization of the parameters by the analyst are dependent on the analytes and calibration ranges required by the individual laboratory's statement of work.

Table 6. Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet Liner	5181-3316, single taper, 4 mm i.d., deactivated		
Inlet	EPC Split/splitless		
Mode	Splitless, 1 µL		
Inlet temp	250 °C		
Pressure	9.24 psi		
Purge flow	30 mL/min		
Purge time	0.35 min		
Gas saver	Off		
Oven			
Oven ramp	°C/min	Next °C	Hold min
Initial		40	1.00
Ramp 1	15	100	0.00
Ramp 2	20	240	0.00
Ramp 3	10	310	6.00
Total run time	25 min		
Equilibration time	1.0 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS, 19091S-133, specially tested		
Length	30 m		
Diameter	0.250 mm		
Film thickness	0.5 µm		
Mode	Ramped flow		
Flow	mL/min	mL/min	Hold min
Initial		1.2	0.00
Ramp 1	99	2.0	0.35
Ramp 2	10	1.2	0.00
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
MSD	Agilent Technologies 5973 with Ultra Source		
Solvent delay	3.2 min		
EM voltage	DFTPP tune - 75 volts		
Low mass	35 amu		
High mass	500 amu		
Threshold	50		
Sampling	2		
Scans/sec	3.25		
Quad temp	150 °C		
Source temp	230 °C		
Transfer line temp	310 °C		
Repeller voltage	25 V as set by new tuning macro		
Emission current	20 µA set by the analyst		

Table 7. Alternate Gas Chromatograph and Mass Spectrometer Conditions

GC	Agilent Technologies 6890		
Inlet Liner	5181-3316, single taper, 4 mm i.d., deactivated		
Inlet	EPC Split/splitless		
Mode	Splitless, 1 µL		
Inlet temp	250 °C		
Pressure	23.14 psi		
Purge flow	30 mL/min		
Purge time	0.50 min		
Gas saver	Off		
Oven			
Oven ramp	°C/min	Next °C	Hold min
Initial		40	1.00
Ramp 1	15	100	0.00
Ramp 2	20	240	0.00
Ramp 3	10	310	6.00
Total run time	25 min		
Equilibration time	1.0 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP-5MS, 19091S-133, specially tested		
Length	30 m		
Diameter	0.250 mm		
Film thickness	0.5 µm		
Mode	Ramped flow		
Flow	mL/min	mL/min	Hold min
Initial		3.0	0.55
Ramp 1	10	1.2	0.00
Inlet	Front		
Outlet	MSD		
Outlet pressure	Vacuum		
MSD	Agilent Technologies 5973 with Ultra Source		
Solvent delay	3.2 min		
EM voltage	DFTPP tune - 200 volts		
Low mass	35 amu		
High mass	500 amu		
Threshold	50		
Sampling	2		
Scans/sec	3.25		
Quad temp	150 °C		
Source temp	230 °C		
Transfer line temp	310 °C		
Repeller voltage	25 V as set by new tuning macro		
Emission current	20 µA set by the analyst		

Conclusion

In this paper, we have demonstrated a process for examining the performance of various components on a complex analytical method composed of many compounds. The challenges of analyzing different classes of compounds in the shortest time while meeting the method requirements are difficult.

This study has led to the development of a 25-minute 8270D method suitable for an extended calibration range of 5 to 160 ng. The G2860A 8270 Semi-Volatiles Applications Kit provides the components necessary to convert an existing 6890/5973 to perform this analysis.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
November 7, 2001
5988-3072EN



Agilent Technologies



The Analysis of Dioxin Using a Benchtop Mass Spectrometer Application

6890/5973 Gas Chromatograph/Mass Selective Detector

Authors

Patrick D. Perkins
Agilent Technologies Company
Palo Alto, CA 94304
USA

Abstract

Currently the analysis of dioxins uses high resolution mass spectrometry, (HRMS); often considered a prohibitively expensive technique. To move to a more cost-effective approach, improvements in the analytical method (sample cleanup and chromatographic separation) as well as improvements in sensitivity of benchtop mass spectrometers were needed.^{1,2}

Compared to earlier generations of benchtop mass spectrometers, the 5973 mass selective detector offers measurably greater sensitivity for electron-impact-based detection due to a number of innovative enhancements.³

Analysis via the GC/MSD System

This work focused on determining the detection limit for 2,3,7,8-tetrachlorodibenzo-p-dioxin with a GC/MSD system configured as outlined in this note. The desired analytical goal was to detect 0.2 pg.

A submitted sample [5 pg/ μ L (ppb); 2,3,7,8-TCDD in 95/5 hexane/ether] was diluted by a factor of 100 with pure hexane. (The hexane was analyzed for response at the appropriate masses prior to use to verify its purity with respect to this analyte.)

For both concentrations, the mass ratio 319.9/321.9 was measured to confirm appropriate isotopic performance. Moreover, the response factors for $m/z = 321.9$ were determined for both levels and compared to verify linearity over a large concentration range.

Results

The mass ratio of 319.9/321.9 is 78%, correctly reflecting appropriate isotopic abundances. Comparing the response ratios of 0.05 pg and 5 pg injections (1 μ L each level), we observed that those were nearly equal: 24.6 and 23.0 ($2302.6 \div 100$).



Agilent Technologies

The signal/noise for the 0.05 pg injection is about 4:1 peak/peak, representing an approximate detection limit on the system used.

The conclusion is that the sensitivity of a 5973 MSD operating as an electron impact instrument is well-suited to trace analysis of dioxins, making it a cost-effective instrument for use in EPA Methods 625 and 613.⁴ For 2,3,7,8-TCDD, the detection limit with the 5973 is comparable to using HRMS. Note, however, that the ultimate method detection limits will depend on other factors — e.g., the sample matrix, type of sample cleanup used, etc. Additional sensitivity may be

possible by using large volume injection techniques.³ Future experiments will aim at evaluating the NCI (negative chemical ionization) performance of the 5973 for further gains in sensitivity and selectivity.

This will mean that a laboratory manager can choose configurations of both the chromatograph and the MSD to best match the needs of a laboratory workload. The work on the system described here demonstrated greatly enhanced sensitivity provided by cost-effective benchtop mass spectrometry.




Figure 1. The match of the spectrum for 5 pg 2,3,7,8-tetrachlorodibenzo-p-dioxin with the library search (lower panel). The match quality was 90%.





Figure 2. The TIC at m/z 321.9 for injection quantities of 5 pg (a.) and 0.05 pg (b.) in SIM mode.

6890 with 5973 MSD

Injection	• Pulsed splitless single taper liner with glass wool plug, P/N 5062-3587. • 250 °C • 1 µL injection volume • Viscosity delay, 1 sec • Sample washes, 3; post-injection solvent washes, 4
Column	HP-5MS: 30 m × 250 µm, 0.25 µm film (crosslinked 5% Ph Me Siloxane), P/N 19091S-433
Carrier	Helium, 37 cm/sec; vacuum compensation, on.
Temperature	Initial: 70 °C for 1.50 min
Program	Rate 1: 25.00 °C/min to 150 °C Rate 2: 10.00 °C/min to 280 °C Final: 280 °C for 0.00 min
Pressure	25.0 psi for 1.50 min; then
Program	1.0 mL/min constant flow rate
MSD	• Temperatures Transfer line = 300 °C Source = 230 °C Quadrupole = 106 °C • Tune = autotune • Emission current = 35 µamp • SIM mode, EMV = Autotune + 400 V • Solvent delay = 14.00 min • Dwell per ion = 125 msec • SIM Ions (<i>m/z</i>): 319.9, 321.9
Autosampler	7673B
ChemStation	G1701AA

References

1. P. R. Gardinali et al, Chemosphere 32 (1), pp. 1-11 (1996).
2. R. Malisch et al, Chemosphere 32 (1), pp. 31-44 (1996).
3. L. Doherty, "Enhancing Pesticide Analysis with a Highly Sensitive GC/MSD System," Application Note, Pub. No. (23) 5966-0370E (1997).
4. Code of Federal Regulations, Title 40, Vol. 13, Parts 136-149, Appendix A. Revised, July 1, 1997. U.S. Government Printing Office (via GPO Access; CITE: 40CFR136). Method 613 - 2,3,7,8-tetrachloro-dibenzo-p-dioxin by GC/MS (SIM). Method 625 - Base/Neutrals and Acids, Semivolatiles by GC/MS (SCAN).

For more information on our products and services, visit our worldwide website at <http://www.chem.agilent.com>.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright© 2001
Agilent Technologies, Inc.

Printed in the USA
April 2, 2001
(23) 5966-4294E



Agilent Technologies



A New Approach to the Analysis of Phthalate Esters by GC/MS

Application

Gas Chromatography/Mass Spectrometry
March 2001

Authors

Cameron George
Agilent Technologies, Inc.
91 Blue Ravine Road
Folsom, California 95630-4714
USA

Harry Prest
Agilent Technologies, Inc.
1601 California Avenue
Palo Alto, California 94304-1111
USA

Abstract

A new instrumental method for the determination of 29 phthalate esters, including six recently banned from baby toys by the European Union, using positive chemical ionization and retention-time locking is described. Positive chemical ionization provides a high degree of selective ionization for the phthalates, primarily producing spectra in which the protonated molecule ($M+1$) is the base peak. This provides easy discrimination among the phthalates on the basis of their molecular weight, while retention-time locking increases confidence in the identification of the various isomers.

In this approach, both pure compounds and technical mixtures are considered. Although this work focuses on the more commonly used 1,2-substituted esters, the 1,3-isomers and 1,4-isomers are also characterized.

The combination of positive chemical ionization and retention-time locking makes the method rugged, durable and applicable to a wide variety of matrices.

Introduction

The widespread use and manufacture of plastics have made the phthalate esters one of the most ubiquitous classes of compounds in our everyday environment. These “plasticizers” increase polymer flexibility due to their function as intermolecular “lubricants”. Because they are additives and not reagents, they are not chemically bound in the polymer and are available to leach from the matrix. Phthalates are also components of cosmetics, detergents, building products (flooring, sheeting, films), lubricating oils, PCB substitutes, carriers in pesticide formulations and solvents. Consequently, the potential for human exposure is very high. Toxicological studies have linked some of these compounds to liver and kidney damage, and to possible testicular or reproductive-tract birth defect problems, characterizing them as endocrine disruptors. Scientists at the U.S. Centers for Disease Control have, for the first time, documented human exposure to phthalates by determinations of the monoester metabolites in human urine [1]. Their work leads to the conclusion that “phthalate exposure is both higher and more common than previously suspected.”

Of particular concern were the significantly higher concentrations of the dibutyl phthalate metabolite in urine of women of childbearing age (20-40 years) than in other portions of the population.

The presence of phthalate esters in polyvinyl chloride (PVC) toys has generated the most



Agilent Technologies

controversy. While regulators in Greece have completely banned soft PVC toys, Austria, Denmark, Finland, France, Germany, Norway and Sweden have unilaterally banned phthalates in PVC toys for children under three years old. In December of 1999, the European Union (EU), concerned with a “serious and immediate risk” to children, placed an emergency ban on six of the phthalate esters in soft PVC toys and childcare products meant to be placed in the mouths of children under the age of three [2]. None of the six banned phthalates may exceed 0.1% by weight.

These heightened concerns suggest the need for an improved method of detecting and characterizing phthalate esters which is applicable to a wide variety of matrices. This application note describes such an analytical method.

Phthalate Structure and Mass Spectra

The three primary structures of phthalates are shown in Figure 1. Although there are three possible positions for the ester linkages, the most commonly used phthalates are based on the 1,2-benzenedicarboxylic acid structure (top). There are an infinite number of possible alkyl side chains, (R) and an infinite number of combinations of the side groups (R and R'). For example, the diisononyl phthalate consists of an array of compounds due to the isomeric branched-chain alkyl groups on both side chains.

For phthalate esters with saturated alkyl side chains (without oxygen), the most intense peak in the electron impact (EI) ionization mass spectrum at 70 eV is always at m/z 149 due to the rapid formation and stability of the ion shown in Figure 2. (The only exception is $R=R'=\text{CH}_3$ where the base peak is at m/z 163).






Figure 1. Phthalic ester (top) or the 1,2-benzenedicarboxylic acid ester, isophthalic ester (middle) or the 1,3-benzenedicarboxylic acid ester, and terephthalic ester (bottom) or the 1,4-benzenedicarboxylic acid ester. R and R' represent alkyl side chains which may be branched and contain oxygen.




Figure 2. The most abundant ion in the mass spectra of the phthalate esters with saturated alkyl side chains; m/z 149. The exception is for dimethyl phthalate where both R and R' are CH_3 and so the H on the oxygen is replaced by CH_3 and consequently m/z 163 becomes the base peak.

Invariably, the molecular ion is very weak or altogether absent; other fragments that provide information on the phthalate identity are also of very low abundance. As an example, consider the EI mass spectrum of dibutyl phthalate, one of the six banned by the EU, and bis(4-methyl-2-pentyl) phthalate in Figure 3. Identifying fragments have relative intensities of less than 10%. Gas chromatography provides some separation of the phthalates, but with the array of possible isomers and essentially a single identifying ion (i.e., m/z 149), distinguishing the individual phthalates of concern is difficult. More confident identification of the phthalates is possible using chemical ionization mass spectrometry in conjunction with retention-time locking (RTL).




Figure 3. Electron impact ionization mass spectra of di-n-butyl phthalate (upper panel) and bis(4-methyl-2-pentyl) phthalate (lower panel) from m/z 50 to 350 at 70 eV. Notice the lack of intense fragments and molecular ions. The molecular weights are 278 and 334 g/mole, respectively.

Retention-time locking allows compound retention times achieved on any one Agilent 6890 gas chromatograph (GC) to be replicated to within a few seconds on any other Agilent 6890 gas chromatograph (GC) applying the same GC method [3-5]. RTL is a powerful approach to compound identification. RTL allows the creation of compound acquisition methods and quantitation databases that can be reproduced in any laboratory, anywhere, because a compound can have a universally fixed and reproducible retention time. It is important that RTL be applied in conjunction with the appropriate detection scheme and sample preparation methods.

Chemical ionization provides a more selective form of ionization than electron impact [6]. By judicious choice of the reagent gases, the degree of compound fragmentation can be controlled to a certain extent. In positive chemical ionization, methane reagent gas usually provides more fragmentation than gases of higher proton affinity such as ammonia. Less fragmentation would be helpful in identifying the phthalates. Instead of all phthalates generating a single, similar ion, positive ionization can provide phthalate ester molecular weights.

Experimental

Phthalate esters were obtained from Ultra Scientific (North Kingstown, RI), AccuStandard (New Haven, CT), and ChemServices (West Chester, PA) as neat compounds and mixtures. Dilutions were made in isooctane (Burdick and Jackson Grade, VWR Scientific).

The configuration and operating parameters of the Agilent 6890Plus GC (standard 120V or "faster ramping" 220V), 7683 Automatic Liquid Sampler and 5973N MSD with CI option used for acquiring the data are given in the following tables. PCI reagent gas purities were 99.99% or higher.

Injection Parameters

Injection Mode	Pulsed Splitless	
Injection Port Temperature	300°C	
Pulse Pressure & Time	25.0 psi	1.00 min
Purge Flow & Time	20.0 mL/min	3.00 min
Gas Saver Flow & Time	20.0 mL/min	3.00 min

Oven Parameters

Temperature Program	80°C	1.00 min
50.00°C/min	200°C	0.00 min
15.00°C/min	350°C	2.00 min
Oven Equilibrium Time	0.25 min	
MSD Transfer Line Temp	325°C	

Column Parameters

GC column (122-5532)	DB-5MS 30 m; 0.25 mm i.d.; 0.25 µm film	
Initial Flow & Mode	1.2 mL/min	Constant Flow
Detector & Outlet Pressure	MSD	Vacuum

Mass Spectrometer Parameters

Tune Parameters	PCI Autotune (NH ₃)	
Electron Multiplier Voltage	Autotune + 400V	
Solvent Delay	4.00 min	
Scan Parameters	194 - 550 m/z	
Quadrupole Temperature	150°C	
Source Temperature	250°C	
Ammonia Gas Flow (MFC setting)	0.5 mL/min (10%)	

Miscellaneous Parts

Septa	5182-0739	BTO septa (400°C)
Liner	5062-3587	Deactivated 4 mm i.d. single taper
GC column ferrule	5181-3323	250 µm Vespel
MSD interface ferrule	5082-3508	0.4 mm i.d. graphitized Vespel

Results and Discussion

As expected using methane as the reagent gas, the PCI mass spectra of the phthalates show ions corresponding to the protonated molecule $[M+H]^+$ and adducts $[M+C_2H_5]^+$ and $[M+C_3H_5]^+$. Because of the relatively vigorous fragmentation produced by methane, the spectra of the dialkyl phthalate esters still resemble that produced in EI. In most cases, the fragment at m/z 149 is the base peak, however ions at m/z $M+1$, $M+29$ and $M+41$ are relatively intense with $[M+H]^+$ from 10% to 30% (Figure 5). The dialkyl phthalate spectra also show a fragment corresponding to loss of one of the alkyloxy side chains to produce an ion shown in Figure 4. This is the most intense fragment for the dimethyl and diethyl phthalates and for the dibutyl and dipentyl (diamyl) phthalates, about 75% of the 149 base peak. As the length of ester alkyl chain increases, the intensity of this fragment decreases. (Apparently, in the dialkyl isophthalates, loss of the alkyl side chain not accompanied by the oxygen may be a preferred route.)

Although positive chemical ionization with methane provides more information than EI on phthalate identity, the methane reagent is still rather unselective in ionization and will produce more chemical noise in the background, complicating identification in complex matrices.




Figure 4. One of the most intense fragments in the methane PCI spectra of the phthalate esters is formed by loss of one of the alkyloxy side groups.

Applying ammonia as the reagent gas in PCI to reduce chemical noise and enhance identification of the phthalates is a more useful approach. The relatively gentle ionization produces protonation of the dialkyl phthalates, with m/z $M+1$ the base peak in their spectra. When combined with retention-time locking, identification of phthalates becomes further simplified. Compare the spectra of the di-n-butyl phthalate acquired using methane versus ammonia as the reagent gas (Figure 5). The protonated molecule is the single dominant peak in the ammonia PCI mass spectrum of the di-n-butyl phthalate, and the adduct at m/z 296 ($[M+NH_4]^+$) is relatively small.





Figure 5. PCI methane (upper panel) and ammonia (lower panel) mass spectra of di-n-butyl phthalate. The PCI methane mass spectrum shows substantial fragmentation but relative to the EI spectrum in Figure 3, high abundance for the higher m/z ions such as the protonated molecule at m/z 279. The ion at m/z 205 is generated by loss of an oxybutyl fragment; a process described in Figure 4. The PCI-ammonia mass spectrum consists almost completely of the protonated molecule.

This implies an easy method for identification. Whereas the EI spectra of the phthalates most frequently result in a base peak at m/z 149, the dialkyl phthalate PCI-ammonia spectra have base peaks at $m/z = M+1$. All dialkyl phthalates molecular formulas can be expressed as



These phthalates have (nominal) molecular masses given by

$$M = 166 + (x + y) \cdot 14, \text{ or}$$

$$M = 166 + (w) \cdot 28,$$

where x and y are the side chain lengths, and the second formula applies to symmetrical side chains (i.e., $x = y = w$). For example, di-*n*-butyl phthalate has $x = y = 4$, and therefore a (nominal) molecular mass of 278 which produces m/z 279 as the base

peak. Interestingly, the PCI-ammonia spectra of the dialkyl isophthalates and terephthalates appear to have base peaks at m/z $M+18$ due to $[M+NH_4]^+$. Because of the greater steric access to the ester linkages, adduct formation may be preferred.

Table 1 gives the phthalate names, CAS numbers, molecular formula, nominal molecular mass, base peak in the PCI-ammonia spectrum and the RTL elution times. These retention times are "locked" relative to diphenyl phthalate, which has been chosen as the RTL locking compound and locked to elute at 9.450 min. Notice that the branched chain isomers elute prior to their straight chain forms on this column phase.

Table 1. Phthalate compound names, Chemical Abstracts Services numbers (CAS), molecular weights (M. Wt.), molecular formulas, nominal base peak in the PCI-ammonia spectrum and retention time (RT) in minutes. Retention times are locked relative to diphenyl phthalate (9.450 min). Retention time ranges are given for the isoalkyl phthalate technical mixtures. Phthalates banned by the EU are indicated by an asterisk*. Benzyl benzoate is included since it is used as a surrogate in U.S. Environmental Protection Agency Method 8061.

Name	CAS	M. Wt.	Molecular Formula	Base Peak	RT (min)
dimethyl phthalate	131-11-3	194	$C_8H_4O_4(CH_3)_2$	195	4.32
dimethyl isophthalate	1459-93-4	194	$C_8H_4O_4(CH_3)_2$	212	4.54
diethyl phthalate	84-66-2	222	$C_8H_4O_4(C_2H_5)_2$	223	4.81
diethyl terephthalate	636-09-9	222	$C_8H_4O_4(C_2H_5)_2$	240	5.06
benzyl benzoate	120-51-4	212	$C_{14}H_{12}O_2$	230	5.62
diisobutyl phthalate	84-69-5	278	$C_8H_4O_4(C_4H_9)_2$	279	5.95
di- <i>n</i> -butyl phthalate*	84-74-2	278	$C_8H_4O_4(C_4H_9)_2$	279	6.40
bis(2-methoxyethyl) phthalate	117-82-8	282	$C_8H_4O_4(C_2H_4OCH_3)_2$	283	6.57
diamyl phthalate	131-18-0	306	$C_8H_4O_4(C_5H_{11})_2$	307	6.94
bis(2-ethoxyethyl) phthalate	605-54-9	310	$C_8H_4O_4(C_2H_4OC_2H_5)_2$	311	7.13
butyl benzyl phthalate*	85-68-7	312	$C_8H_4O_4(C_4H_9)(CH_2C_6H_5)$	313	8.42
diphenyl phthalate	84-62-8	318	$C_8H_4O_4(C_6H_5)_2$	319	9.45
diphenyl isophthalate	744-45-6	318	$C_8H_4O_4(C_6H_5)_2$	319	10.30
dicyclohexyl phthalate	84-61-7	330	$C_8H_4O_4(C_6H_{11})_2$	331	9.32
bis(4-methyl-2-pentyl) phthalate	146-50-9	334	$C_8H_4O_4(CH_3C_5H_{10})_2$	335	6.93
diisohexyl phthalates	146-50-9	334	$C_8H_4O_4(C_6H_{13})_2$	335	7.55 - 8.28
dihexyl phthalate	84-75-3	334	$C_8H_4O_4(C_6H_{13})_2$	335	8.34
dibenzyl phthalate	523-31-9	346	$C_8H_4O_4(CH_2C_6H_5)_2$	347	10.51
hexyl-2-ethylhexyl phthalate	75673-16-4	362	$C_8H_4O_4(C_2H_5C_6H_{12})(C_6H_{13})$	363	8.84
bis(2- <i>n</i> -butoxyethyl) phthalate	117-83-9	366	$C_8H_4O_4(C_2H_4OC_4H_9)_2$	367	8.98
bis(2-ethylhexyl) phthalate*	117-81-7	390	$C_8H_4O_4(C_2H_5C_6H_{12})_2$	391	9.32
di- <i>n</i> -octyl phthalate*	117-84-0	390	$C_8H_4O_4(C_8H_{17})_2$	391	10.28
dioctyl isophthalate	137-89-3	390	$C_8H_4O_4(C_8H_{17})_2$	408	10.84
diisononyl phthalates*	28553-12-0	418	$C_8H_4O_4(CH_3C_8H_{17})_2$	419	9.40 - 11.10
dinonyl phthalate	84-76-4	418	$C_8H_4O_4(C_9H_{19})_2$	419	11.19
diisodecyl phthalates*	26761-40-0	446	$C_8H_4O_4(CH_3C_9H_{18})_2$	447	10.16 - 11.86
didecyl phthalate	84-77-5	446	$C_8H_4O_4(C_{10}H_{21})_2$	447	12.05
diundecyl phthalate	3648-20-2	474	$C_8H_4O_4(C_{11}H_{23})_2$	475	12.87
didodecyl phthalate	2432-90-8	502	$C_8H_4O_4(C_{12}H_{25})_2$	503	13.65
ditridecyl phthalate	119-06-2	530	$C_8H_4O_4(C_{13}H_{27})_2$	531	12.01 - 13.81

Technical formulations of the isoalkyl phthalates tended to contain substantial amounts of the straight chain isomer, which may convolute quantitation as well as peaks that may be construed as originating from nonequivalent side chains i.e., $x \neq y$ in equation 1). These impurities can be detected as $M \pm 14$ around the mass of the nominal isomer. For example, technical grade diisononyl phthalate contains compounds that generate ions at m/z 391 (minor), 405, 433, and 447 in addition to the nominal diisononyl phthalate compound at m/z 419. The “gentle” ionization of ammonia reagent gas, the elution times and the study of the

spectra of other pure isomers, such as the dinonyl phthalate, suggest that these fragments are not formed by the PCI process but are due to these different alkyl side chain impurities (Figure 6). To demonstrate the utility of the PCI-ammonia compared to conventional EI analysis, consider the chromatograms presented in Figure 7. The EI spectra of the phthalates produce m/z 149 as the base peak for all the phthalates present; distinguishing ions are minor constituents (<10% relative intensity), making identification complicated. However, by examining the appropriate PCI-ammonia ions, the various phthalates are easily distinguished.




Figure 6. PCI-Ammonia extracted ion chromatogram of technical diisononyl phthalate. The diisononyl appears as the major component at m/z 419 while ions at m/z 405, 433, and 447 indicate alkyl chains shorter by one CH_2 unit and longer by one and two CH_2 units respectively.




Figure 7. Chromatograms of dinonyl, diisononyl, didecyl, diisodecyl, diundecyl, didodecyl, ditridecyl phthalate esters in EI (upper panel), EI as an extracted ion chromatogram at m/z 149 (middle panel), and PCI-extracted ion chromatogram with ions selected for the individual phthalate classes as given in Table 1. The EI information is insufficient to identify coeluting phthalates. For example, the dinonyl and diundecyl phthalates are "buried under" the signals from the isodecyl and ditridecyl phthalates.

Conclusions

Applying GC - electron impact (EI) mass spectrometry to the determination of phthalates requires full chromatographic separation. The EI spectra of the phthalates are distinguished only by ions of very low intensity. In EI, the phthalates produce a single common ion (m/z 149) as the most intense spectral peak, regardless of the alkyl side chain substitution. Applying tandem mass spectrometry (i.e., EI/MS/MS) gains nothing, because there is a common parent ion, and therefore any daughter ions would also be non-unique. However, the combination of positive chemical ionization with retention-time locking allows even complex mixtures of phthalates to be characterized. Ammonia reagent gas produces the protonated molecule as the base peak, which immediately allows the phthalates to be distinguished on the basis of their substitution. PCI is also an advantage in complex matrices, where the non selective ionization of EI produces a high chemical background. This method should therefore be suitable for use in phthalate determinations in environmental media, plastics, cosmetics and many other matrices.

"Locking" the retention time enhances confidence in the characterization of the various phthalate isomers on the basis of their definitive retention time. This is especially helpful for determinations using selected ion monitoring (SIM), since SIM groups need not be edited after column maintenance [4]. The data in Table 1 facilitate the development of a SIM method. The extension of the method to phthalates which elute at higher temperatures ($>350^{\circ}\text{C}$) is also easily accomplished.

References

1. Blount, B.C., et al., Levels of seven urinary metabolites in a human reference population. *Environmental Health Perspectives*, 2000. 108 (10): p. 979-982.
2. *Official Journal of the European Communities, Decision 198/815/EC*. 1999, European Commission; European Union Scientific Committee on Toxicology, Ecotoxicology, and the Environment.
3. Giarrocco, V., B. Quimby, and M. Klee, *Retention Time Locking: Concepts and Applications*. 1998, Publication number (23) 5966-2469E, Agilent Technologies.
4. Prest, H. and P. Cormia, *Retention Time Locking: Advantages in GC/MS SIM Analysis*. 1999, Publication number (23) 5967-3797E, Agilent Technologies.
5. Prest, H. and K. Weiner, *Retention Time Locking: Creating Custom Retention Time Locked Screener Libraries*. 1999, Publication number (23) 5968-8657E, Agilent Technologies.
6. Harrison, A.G., *Chemical Ionization Mass Spectrometry*. Second ed. 1992: CRC Press.

For more information

For more information on our products and services, you can visit our site on the World Wide Web at: <http://www.agilent.com/chem>.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright © 2001
Agilent Technologies
All rights reserved. Reproduction and adaptation are prohibited.

Printed in the U.S.A.
March 7, 2001
5988-2244EN



Agilent Technologies



Analysis of Nitroaromatics and Nitro-Polycyclic Aromatic Hydrocarbons by Capillary Gas Chromatography with the Agilent 6890 Micro-ECD

Application

Gas Chromatography

March 1997

Authors

F. David
Research Institute for
Chromatography,
Kennedypark 20, B-8500
Kortrijk, Belgium

P. Sandra
University of Gent,
Krijgslaan 281, S4, B-9000
Gent, Belgium, Eindhoven
University of Technology,
The Netherlands

Matthew S. Klee
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A new electron capture detector (ECD) for the Agilent 6890 Series gas chromatograph (GC) allows very sensitive detection of nitroaromatic compounds at low picogram levels with a linear response over three orders of magnitude.

This application note describes the performance of the new 6890 Series Micro-ECD when analyzing two types of nitro-aromatic compounds—explosives and nitrated polycyclic aromatic hydrocarbons (nitro-PAHs).

Introduction

Electron capture detection is most often used for the sensitive and selective detection of halogenated compounds. However, other compound classes also have electron capturing properties and can, therefore, be detected at low levels using an electron capture detector (ECD). Compounds containing a nitro-function—particularly nitroaromatics—are strong electron-capturing molecules. The ECD provides a very sensitive tool for trace analysis of these solutes.

This application note demonstrates that the 6890 Series Micro-ECD provides an extremely sensitive alternative to the typical NPD or MS detection^{1,2} for nitro-PAHs and explosives.

Experimental

The analyses were performed on an 6890 Series GC. Injection was automated splitless using an Agilent 7673 automatic sampler. The instrument configuration and analytical conditions used for the analysis of the nitro-PAHs and explosives are summarized in table 1.

Results and Discussion

The sensitivity of the ECD depends on the makeup flow rate. The 6890 Micro-ECD optimized the argon/5% methane (Ar/CH₄) makeup gas flow rate for the analysis of nitro-PAHs. Nitrofluorene was used as test solute. The makeup flow rate was varied from 10 to 80 mL/min; at each setting, five runs were made.

Figure 1 shows the mean peak areas plotted versus the makeup flow rate. The optimum flow rate was obtained between 20 to 30 mL/min. At lower flow rates, the peak area decreased and the detector became less stable, shown in the increasing standard deviation on peak area. At higher flow




Agilent Technologies

Innovating the HP Way

Table 1. Instrumental Configuration and Analytical Conditions

Chromatographic System	
Gas chromatograph	6890 Series
Inlet	Split/splitless
Detector	Micro-ECD
Automatic sampler	7673 Series
Liner	Single taper deactivated (part number 5181-3316)
Data handling	ChemStation (DOS Series)
Column	30 m x 0.25 mm id x 0.25 μ m HP-5 MS (part number 19091S-433)
Experimental Conditions	
Inlet temperature	250 °C
Injection volume	1 μ L
Injection mode	Splitless
Purge time	0.75 min
Purge flow	50 mL/min
Carrier gas	Hydrogen
Head pressure	58 kPa at 50 °C
Carrier gas mode	Constant flow
Flow, velocity	1.4 mL/min, 40 cm/s
Oven temperature	50 °C, 1 min initial, 20 °C/min to 320 °C, 0.5 min hold
Detector temperature	320 °C
Detector gases	Argon/5% methane: 20 mL/min

**Figure 1. Peak area of 1-nitropyrene versus argon/5% methane makeup gas flow rate.**

rates, the detector was stable (exhibiting a small standard deviation), but sensitivity drastically decreased.

Nitrogen is an alternative makeup gas for electron capture detection. It can usually be used interchangeably with Ar/CH₄; similar results for the effect of makeup gas flow rate are expected.

Next, the linearity of the detector response was measured. Using nitropyrene as the test solute, standard solutions of 1, 10, 50, 100 and 1,000 ppb were analyzed. The calibration curve for this compound, as shown in figure 2, exhibits a very

good correlation coefficient ($r = 0.99996$).

Nitrated Polycyclic Aromatic Hydrocarbons

Nitro-PAHs are an important class of environmental pollutants.³ Polycyclic aromatic compounds are formed during incomplete combustion of organic material. In the presence of nitrogen oxides (NO_x), the neutral PAHs (such as naphthalene or pyrene) are converted into nitro-PAHs.³⁻⁵

The nitro-PAHs have much higher mutagenic and carcinogenic activity

than the neutral PAHs, but their extremely low concentration (measured as pg/m³) in environmental samples, particularly air particulates, makes them difficult to monitor. Very sensitive detection is needed.

Using the optimized GC conditions, a mixture of 11 nitro-PAHs, each having a concentration of 40 pg/mL (40 ppb), was analyzed. The chromatogram for this analysis is shown in figure 3. Good peak shapes were obtained for all compounds. The detection limit, which varied from 0.1 to 1 pg for the different PAHs, is at least one order of magnitude lower than that obtained by nitrogen-phosphorus detection (NPD), mass spectrometry (MS), or MS-MS.² It can, therefore, be concluded that the 6890 Micro-ECD offers greater sensitivity for the detection of these nitro-PAHs than other methods.

Explosives

Explosives can be present as residues at chemical waste sites or on materials close to an explosion. Sensitive and fast methods are needed for analyzing and monitoring these compounds for environmental remediation or forensic evidence.

Although explosives are often analyzed by high pressure liquid chromatography (EPA method 8330), capillary gas chromatography (CGC) can provide a good alternative for most solutes using NPD or MS. Some of the nitro-aromatics are included in the target compound lists of EPA methods 8090 and 8270 (CGC-MS).

Explosives such as TNT (2,4,6-trinitrotoluene) contain one or more nitro-functions. CGC-ECD can provide a very sensitive and fast screening method for detecting these compounds.

The chromatogram in figure 4 shows the results of a standard mixture of explosives using the analytical conditions in table 1. The concentration of the test solutes was 100 pg/mL




Figure 2. Calibration curve for 1-nitropyrene from 1 to 1,000 ppb

(100 ppb), except for 1,2-dinitrobenzene, which was present as an impurity. As the chromatogram shows, the different nitro-, dinitro-, trinitro-, and amino-nitro-compounds are well separated and elute with good peak shape.

The ECD response is dependent on the number of nitro-groups. For the mono-nitroaromatics, the detection limit is around 10 pg, while for the di- and tri-nitroaromatics the detection limit is below 1 pg. This example confirms that CGC-ECD can be used as a fast screening method for the analysis of this category of explosives.

Conclusion

The Agilent 6890 Series Micro-ECD allows very sensitive detection of nitroaromatic compounds. The detector was successfully used for the analysis of nitrated polycyclic aromatic hydrocarbons and explosives. Detection limits below 1 pg were obtained, and the detector was found to give a linear response over three orders of magnitude.




Figure 3. CGC-ECD analysis of nitrated polycyclic aromatic hydrocarbons (solute concentration: 40 ppb)




Figure 4. CGC-ECD analysis of explosives (solute concentration: 100 ppb)

References

1. L. Warzecha, *J High Resolution Chromatography* 19 (1996) p. 639.
2. A. Medvedovici, F. David, G. Desmet, and P. Sandra, *Journal of Microseparations*, 1997 (in press).
3. C. M. White (Ed.), "Nitrated Polycyclic Aromatic Hydrocarbons," Huthig Verlag, Heidelberg, 1985.
4. P. Ciccioli, A. Cecinato, E. Brancaleoni, R. Draisci, and A. Liberti, *Aerosol Science and Technology* 10 (1989) p. 296.
5. R. Atkinson, J. Arey, B. Zielinska, and J. M. Ashmann, *International Journal of Chem Kinetics* 22 (1990) p. 999.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5965-8015E



Agilent Technologies
Innovating the HP Way



An approach to the determination of N-nitrosodimethylamine at part-per-quadrillion levels using Positive Chemical Ionization and Large-Volume Injection

Harry F. Prest^a and Richard E. Herrmann^b

^a Senior Applications Chemist, Agilent Technologies, California Analytical Division, 1601 California Avenue, Palo Alto, CA 94304

^b Applications Chemist, APEX Technologies, Inc., 1095 Nimitzview Drive, Suite 100, Cincinnati, OH 45230

Introduction

N-nitrosodimethylamine (NDMA, Figure 1) is one of a series of nitroso compounds known to be carcinogenic. NDMA is found in nitrate-cured or smoked meats,¹ cheeses,² tobacco smoke,³ cooked foods and in beverages such as beer⁴ (both foreign and domestic⁵⁻⁷). The presence of NDMA in surface waters designated for use drinking water use is of particular concern and the U.S. Environmental Protection Agency (EPA) has promulgated a regulatory standard for these waters of 0.7 ng/l (700 ppq). When in 1998 NDMA was detected in California drinking water, the source was associated with the production and use of a rocket fuel component, unsymmetrical dimethylhydrazine. In response, the California Department of Health Services (DHS) announced an action level in drinking water of 2 ng/l (2 ppt). However, the best available methods in the literature provide *detection* limits on the order of 1–3 ng/l. EPA methods 625 and 1625 specify a detection limit for NDMA of 50 ppb—25,000 times the California DHS action level and 70,000 times the EPA regulatory standard. It follows that using existing methodologies, *any* detection of NDMA represents a violation.




Figure 1. N-nitrosodimethylamine, $(\text{CH}_3)_2\text{N}_2\text{O}$, 74 g/mole, CAS Registry No. 62-75-9

Determining NDMA at ppt or ppq concentrations in water is an analytical challenge. The extraction methods that have been applied, such as liquid-liquid or solid-phase extraction,⁸⁻¹⁰ produce concentration factors of 500 to 1000, but overall recoveries are generally low. The high polarity and volatility of NDMA contribute to lowered recoveries and extensive extract concentration by evaporation can lead to high losses.

To increase sensitivity and specificity, one prevalent detection scheme involves use of the chemiluminescent nitrogen detector. Electron impact mass spectrometry has also been used but the fragmentation pattern is not very favorable (Figure 2). While the molecular ion at 74 m/z may be a reliable quantitation ion, the confirming ions at 42 and 43 m/z are hardly unique and are easily compromised by fragments from interferences.




Figure 2. Electron impact ionization mass spectrum of NDMA

An approach to the determination of N-nitrosodimethylamine at part-per-quadrillion levels using Positive Chemical Ionization and Large-Volume Injection

One approach to overcoming the unfavorable electron impact (EI) ionization mass spectrum of NDMA is to apply positive chemical ionization (PCI). PCI can provide enhanced analyte selectivity and sensitivity. Utilizing large-volume injection (LVI) should lower the concentration of NDMA that can be detected in an extracted sample. This note describes the combined application of these two techniques as a possible approach to determining NDMA at ppt and ppq concentrations.

Experimental

NDMA standards were made by serial dilution in 1-ml of dichloromethane from a 100 ng/μl standard (Ultra Scientific, Kingstown, RI; part number NS-100). Dichloromethane was chosen as the solvent, because this solvent is used in both liquid-liquid and solid-phase extraction techniques.

Instrumental Section

The 6980 Plus GC / 5973 MSD with chemical ionization option was operated in the selected-ion-monitoring mode (SIM) with ammonia reagent gas. An HP-210 GC column 50%-trifluoropropyl-50%-methylsiloxane (30-m, .25 mm i.d., 0.5 μm film thickness, Part Number 19091C-733) was used with a 5-m, 0.32 mm i.d. uncoated retention gap (Part Number 19091-60600) joined by a press-fit connector (Part Number 5062-3555). A 100-μl syringe was used in the integrated automated liquid sampler 7683 injector for the 50-μl injections. GC oven conditions and mass selective detector settings are given in Tables 1 and 2.

Table 1. GC and Injector parameters

Oven Temperature Program	Temp	Time
Initial Temperature	45°C	3.00 min
Ramp 50°C / min	180°C	0.50 min
GC Oven Equilibrium Time		3.00 min
MSD Transfer Line		225°C
Inlet Mode		Split
Split Flow		50 ml / min
Gas Saver		Off
Column Flow (Helium carrier gas)		2.0 ml / min
Mode		Constant Flow
Outlet Pressure		Vacuum
Injection Volume		50 μl
Syringe Size		100 μl
Plunger Speed		Slow
Solvent Washes A, B	Methanol*	Dichloromethane

* A solvent that "wets" the glass bore improves syringe life.

Table 2. MSD parameters

Tune File *	PCINH3.U
Ammonia Reagent Gas Flow	10 %
EM Voltage	PCI CH ₄ AutoTune + 400V
MS Quadrupole Temp	106°C
MS Source Temp	250°C
Acquisition Mode	SIM
Solvent Delay	5.25 min
SIM Ions	Dwell
75.1 amu	80 msec
92.1 amu	80 msec

* PCI Autotune parameters were used for these experiments. Autotune provides high sensitivity over a large mass range, but even greater sensitivity for these low molecular weight ions can be achieved by manual adjustment of the tuning parameters.

Large-Volume Injections

The APEX ProSep™ 800 Series XT Plus Preseparation System Inlet (APEX Technologies, Cincinnati, OH) was used as the inlet for large-volume injections.^{11, 12} Injections were made into a fused-silica preseparation column packed with deactivated fused-silica wool in the top 3 to 7 cm of the column (available from APEX). The ProSep Precolumn Temperature Module and Flow Module parameters that were successful for this particular preseparation column are given in Tables 3 and 4. This is a very flexible device, and the parameters given can be further optimized to provide better performance for particular extracted matrices. For example, a higher final precolumn temperature than 180°C can be applied to remove high-boiling contaminants.

Table 3. ProSep Precolumn Temperature Program

	Target	Duration
Initial	45°C	0.05 min
250°C / min	180°C #	6.00 min

Higher bake-out temperatures are recommended for extracted samples.

Table 4. ProSep Precolumn Mode Program

	Mode	Duration
Initial	Split	0.05 min
1	Splitless	0.07 min*
2	GC Split **	2.50 min*

*These times should be appropriately optimized.

** It is recommended that ProSep Split be implemented instead of simply GC Split due to superior venting.

An approach to the determination of N-nitrosodimethylamine at part-per-quadrillion levels using Positive Chemical Ionization and Large-Volume Injection

Results

The application of PCI with ammonia reagent gas to NDMA produces a simplified mass spectrum consisting only of protonated NDMA, $[\text{NDMA}+\text{H}]^+$, and the ammonium adduct, $[\text{NDMA}+\text{NH}_4]^+$, which correspond to 75 m/z and 92 m/z, respectively. PCI provides a three-fold advantage over the EI approach. First, the relatively non-unique 74, 43, 42 m/z ions of the EI have been replaced by higher-mass ions. Second, PCI provides increased sensitivity for NDMA and a reduction in low-mass, “background” ions which enhances the signal-to-noise ratio. Third, by manipulating the ammonia gas flow, the abundances of the 92 m/z and 75 m/z ions can be controlled. As the ammonia flow into the source is increased, the abundance of the $[\text{NDMA}+\text{NH}_4]^+$ adduct also increases, allowing the ratio of 92 m/z to 75 m/z to be controlled by the analyst. For example, at 0.4 ml/min of ammonia—a relatively low flow setting of the reagent gas mass flow controller (8% of the total 5-ml/min provided by the controller)—the ratio of the protonated form to adduct is biased toward the protonated form: $[\text{NDMA}+\text{H}]^+ : [\text{NDMA}+\text{NH}_4]^+ = 4 : 3$. At higher flows, the situation reverses and $[\text{NDMA}+\text{NH}_4]^+$ predominates, e.g., at 0.9 ml/min ammonia (18% flow setting) $[\text{NDMA}+\text{H}]^+ : [\text{NDMA}+\text{NH}_4]^+ = 1 : 5$. It is therefore possible to produce an intense confirming ion for quantitative applications. A good compromise between signal intensities and ion abundances was achieved at a




Figure 3. Extracted ion chromatogram for NDMA at 40-fg/ μl using PCI-SIM with NH_3 reagent gas.

0.5 ml/min ammonia flow setting. Figure 3 shows the 75 m/z and 92 m/z SIM signals for a 40-fg/ μl standard for this flow. Under these conditions, $[\text{NDMA}+\text{H}]^+$ is 79% of $[\text{NDMA}+\text{NH}_4]^+$ according to the integrated signal areas.

Figure 4 shows the results of a linear regression of the response of the 92 m/z ion for 50- μl injections of NDMA standards from 20-fg/ μl to 4000-fg/ μl . The regression fit was very good, $r^2 = 0.999$, considering the propagation of error in the dilutions. The relative standard deviation in the response factors was less than 6% and could be improved by using a perdeuterated or ^{15}N -labeled NDMA surrogate.




Figure 4. Linear regression of response of the 92 m/z ion versus NDMA concentration from 20-fg/ μl to 4000 fg/ μl , $r^2 = 0.999$.

Table 5 shows the excellent degree of reproducibility in the ratio of 75 m/z confirming ion to 92 m/z target ion over a wide range of concentrations. The absolute value of the ratio was 0.79, with a relative standard deviation of < 3%. This high precision is important to the degree of confidence in confirming and quantitating NDMA.

Table 5. Reproducibilities of the ratio of the integrated areas of 75 m/z : 92 m/z and the response of the 92 m/z target ion for 5 injections at 5 concentrations.

Concentration as fg NDMA / μl	RSD Ratio 75 m/z / 92 m/z	RSD Response by 92 m/z area
20	2.9%	2.4%
40	2.2%	3.2%
200	0.7%	0.8%
2000	0.7%	1.7%
4000	0.3%	0.9%

Table 5 also shows the excellent reproducibility of the response of the 92 m/z ion for replicate 50- μl injections. Even at the 20-fg/ μl concentration, precision is better than 3%.

An approach to the determination of N-nitrosodimethylamine at part-per-quadrillion levels using Positive Chemical Ionization and Large-Volume Injection

Conclusions

Concentration and recovery factors for NDMA using present published methodologies suggest effective pre-concentration of NDMA in samples to be on the order of 500, e.g., 60–70% recovery of NDMA in extraction of a 1-liter water sample. This implies that the low 20-fg/μl NDMA standard corresponds to a sample concentration of 40 pg/l, or 40 parts-per-quadrillion. Alternatively, to quantitate NDMA at 0.5 ppt in water, which is 4 times lower than the California DHS limit and slightly lower than the EPA regulated limit, quantitating at 20 fg/μl is equivalent to requiring the extraction of *only* 80 ml of water even if recoveries are still only 50%. Extracting small volumes presents a significant simplification of the process and offers savings in solvent and related materials, and in processing time.

With NDMA eluting in about 5 1/2 minutes, the analysis is fast, and the run-to-run cycle time is short—less than 13 minutes between injections. The method may be further optimized for even more rapid analysis.

The 5973 MSD provides very stable ratios for the confirming ion that can be optimized for quantitative purposes as described. In contrast to EI, in which many possible interfering fragment ions are possible that may distort the ratio of the target and confirming ion(s), PCI with ammonia is unlikely to cause fragmentation-induced interferences because of the relatively “gentle” nature of ammonia reagent gas. Interferences could occur involving compounds with molecular weights of 74 or 91 g/mole eluting at the same retention time but that is unlikely scenario.

The high degree of reproducibility in the injections, even at very low NDMA concentrations, demonstrates the robustness of large-volume injections using the APEX ProSep with the 6890/5973 MSD. It should be emphasized that the reproducibility of 2.4% for the replicate 50-μl injections of the 20-fg/μl standard reported here was for the *absolute* response. Use of an internal standard should further lower the deviation in response and improve quantitation.

Using this approach it should now be possible to satisfy the 2 ppt action level for NDMA set by the State of California and the 700 ppq regulatory standard promulgated by the U.S. EPA.

References

1. Pensabene, J.W., W. Fiddler, and J.G. Phillips, Gas-chromatographic—chemiluminescence method for determination of volatile N-nitrosamines in minced fish-meat and surimi-meat frankfurters: collaborative study. *J-Assoc-Off-Anal-Chem.* Nov–Dec 1990; **73**(6): p. 947–952.
2. Dellisanti, A., G. Cerutti, and L. Airoidi, *Volatile N-nitrosamines in selected Italian cheeses.* *Bull-Environ-Contam-Toxicol.* Jul 1996; **57**(1): p. 16–21.
3. Mahanama, K.R.R. and J.M. Daisey, *Volatile N-nitrosamines in environmental tobacco smoke: sampling, analysis, emission factors and indoor air exposures.* *Environ-Sci-Technol.* May 1996; **30**(5): p. 1477–1484.
4. Markl, K.S. and R.A. Latimer, *Analytical methodology and determination of N-nitrosodimethylamine in beer, wort and malt.* *J-Am-Soc-Brew-Chem.* 1981; **39**(2): p. 59–64.
5. Gloria, M.B.A., J.F. Barbour, and R.A. Scanlan, *N-nitrosodimethylamine in Brazilian, U.S. domestic, and U.S. imported beers.* *Journal of Agricultural and Food Chemistry*, 1997; **45**: p. 814–816.
6. Izquierdo-Pulido, M., J.F. Barbour, and R.A. Scanlan, *N-nitrosodimethylamine in Spanish beers* *Food and Chemical Toxicology*, 1996; **34**: p. 297–299.
7. Stacchini, P. and M. Baldini, *Nitrosodimethylamine in the beer: Study on the presence in foreign and Italian beers.* *Rivista di Scienza dell’Alimentazione*, 1994; **23**: p. 187–192.
8. Jenkins, S.W.D., et al., *N-nitrosodimethylamine in drinking water using a rapid, solid-phase extraction method.* *Environmental Science and Pollution Research International*, 1995; **2**: p. 207–210.
9. Tomkins, B.A. and W.H. Griest, *Determination of N-nitrosodimethylamine at part-per-trillion concentrations in contaminated ground waters and drinking waters featuring carbon-based membrane extraction discs.* *Anal-Chem.* 1 Aug 1996; **68**(15): p. 2533–2540.

(references continued . . .)



10. Tomkins, B.A., W.H. Griest, and C.E. Higgins, *Determination of N-nitrosodimethylamine at part-per-trillion levels in drinking waters and contaminated groundwaters*. Anal-Chem. 1 Dec 1995; **67**(23): p. 4387-4395.
11. anon, *APEX ProSep Pre-column Separation Inlet (PSI)*, Agilent Technologies, Technology Note (23)-5968-4462E, www.hp.com/go/chemsupplies.
12. Prest, H.F., J.S. Hollis, and G. O'Neil, *The APEX ProSep 800 XT Plus Precolumn Separation Inlet: advantages of a chromatographic zone as GC inlet system*, Agilent Technologies, Application Note (23) 5968-5747E, www.hp.com/go/chemsupplies.

Acknowledgments

Harry Prest is very grateful to Dr. William Steeber of the California Department of Health Services, Los Angeles, CA and John M. Hughes of the Gas Phase Chemists Council for their review of the manuscript.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

Copyright © 1999
Agilent Technologies
All rights reserved. Reproduction and adaptation is prohibited.

Printed in the U.S.A. September 1999
(23) 5968-7799E


Revision 1.0 - December 1999



Soil & Sediment

Pesticides and Residues Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)



Contract Laboratory Program (CLP) Pesticide Analysis with 0.18 mm ID High-Efficiency GC Columns Utilizing Helium Carrier Gas

Application

Environmental

Authors

Ken Lynam and William Long
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, Delaware 19808
U.S.A.

Abstract

Contract Laboratory Program (CLP) pesticide analysis is demonstrated on high-efficiency GC columns (20 m × 0.18 mm id × 0.18 μm film thickness) with helium carrier gas. DB-17ms stationary phase is used for primary analysis and DB-XLB stationary phase for confirmation. Primary analysis and confirmation of 22 CLP pesticides in the protocol is achieved in an 11-minute analysis, a 35% reduction in analysis time versus 0.32 mm id columns.

Method translation software is successfully employed to translate an original set of conditions with hydrogen carrier gas to a new set of conditions using helium carrier gas. Elution order and degree of separation are shown to translate precisely from the original method to the new method through use of this software (available for free download) [1].

Introduction

The determination of organochlorine pesticides (OCPs) in environmental remediation samples are important, high-volume analyses in the competitive contract laboratory marketplace. A standard Contract Laboratory Program (CLP) pesticide method is used for these analyses. In many cases a lab will analyze large numbers of samples over the course of a given project, adding costs to both the lab and its

client. Here, 0.18 mm id high-efficiency GC columns are demonstrated as a means of enhancing laboratory productivity. These columns are fully compatible with standard gas chromatographs and helium carrier gas operation. The high efficiency these columns offer coupled with their full compatibility with existing GCs provide laboratories with a powerful tool for enhancing sample throughput. When analysis times for 30 m × 0.32 id and 20 m × 0.18 mm id columns were compared, a 17-minute analysis was reduced to only 11 minutes and with improved resolution [2].

Helium carrier gas was selected as a means to show the utility of 0.18 mm id columns in doing CLP pesticide analyses and to demonstrate the full compatibility of these columns with standard gas chromatographs. The operating gas pressures for these 20 m × 0.18 mm id columns range from 33 psi initially to 50 psi at the high point of the temperature program. The gas pressure range used with helium carrier gas with these 0.18 mm id columns was well within the operating range for standard chromatographs.

Experimental

This work was accomplished using an Agilent 6890N GC equipped with dual μECDs and a 7683B autosampler. A single split/splitless injection port was used for sample introduction at the head of a retention gap column connected through a Y-splitter with two analytical columns. Details of the chromatographic conditions are presented in Table 1.



Agilent Technologies

Table 1. Chromatographic Conditions

GC	Agilent 6890N
Sampler:	Agilent 7683B, 5 μ L syringe (Agilent p/n 5181-1273), 0.5 μ L injection
Inlet	Split/splitless; 250 °C pulsed splitless (35 psi for 0.5 min)
Inlet liner	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Carrier	Helium (constant flow, 49.5 cm/sec at 120 °C, purified through big universal trap Agilent p/n RMSH-2)
Retention gap	5 m $\times$ 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	
1	20 m $\times$ 0.18 mm $\times$ 0.18 μ m DB-17ms (Agilent p/n 121-4722)
2	20 m $\times$ 0.18 mm $\times$ 0.18 μ m DB-XLB (Agilent p/n 121-1222)
Oven	120 °C (0.49 min); 85 °C/min to 160 °C; 20 °C/min to 260 °C (0.20 min); 25 °C/min to 285 °C; 40 °C/min to 300 °C (3.5 min)
Detection	μ ECD 325 °C; nitrogen makeup; constant column + makeup flow 60 (mL/min)

The flow path supplies used in these experiments are listed in Table 2 below.

Table 2. Flow Path Supplies

		Agilent p/n
Vials	Amber screw cap	5182-0716
Vial caps	Blue screw cap	5282-0723
Vial inserts	100 μ L glass/polymer feet	5181-1270
Syringe	5 μ L	5181-1273
Septum	Advanced green	5183-4759
Inlet liner	Deactivated single taper direct connect	1544-80730
Ferrules	0.4 mm id short; 85/15 Vespel/graphite	5181-3323
Y-splitter	Quartz deactivated	5181-3398
Sealing resin	Polyimide sealing resin	500-1200
20x magnifier	20x magnifier loop	430-1020
Tubing cutter	Ceramic wafer column cutter	5181-8836

Sample Preparation

CLP pesticide standard solutions were purchased from AccuStandard, New Haven, CT 06513-USA. ULTRA RESI ANALYZED grade 2,2,4 trimethylpentane was purchased from J. T. Baker, Phillipsburg, NJ 08865-USA. CLP-023R-160X and CLP-024R-160X concentrates were diluted separately into two

100-mL volumetric flasks in 2,2,4 trimethylpentane and then combined in subsequent serial dilutions. Volumetric flasks and pipettes used were all class A. Standard concentration range for low-level target compounds in the protocol was from 1.6 to 40 ng/mL. On-column loading ranged from 0.4 to 10 pgs for low-level target compounds when a 0.5- μ L injection over both columns is considered.

Column Installation Tip on Using Y Splitters

Installation of the Y splitter was accomplished by coating the outside of the fused silica tubing to be inserted into the Y splitter with a thin film of polyimide sealing resin prior to cutting the tubing. The cut was then made through the coated section of tubing. The cut end was then checked with a 20x magnification loop to make sure that the cut was clean and that excess sealant had not diffused inside the column. Once a clean cut was obtained, the fused silica with the polyimide sealant on the outside only was inserted into the desired branch of the Y and held for approximately 45 seconds to seal. Good sealing was indicated by a thin ring of sealant at the point of contact. The process was done first with the analytical columns and then repeated for the trunk of the Y into the retention gap. This approach gave tight, reliable connections that have lasted without any difficulty for more than 2 months (to date) and hundreds of oven temperature program cycles.

Results and Discussion

The starting point for this application was a set of conditions for CLP pesticide analyses using hydrogen carrier gas and 0.18-mm high-efficiency columns developed by Wool and Decker [3]. Using hydrogen carrier and flow programming, they were able to achieve primary separation and confirmation analysis of CLP pesticides in a 7-minute analysis. The chromatographic parameters for the hydrogen carrier separation were input as initial setpoints in method translation software to convert the method to use with helium carrier. Helium carrier was selected for use in laboratories reluctant to work with hydrogen carrier due to site safety policy or individual preference. High-efficiency GC columns give the chromatographer the option to work with either helium or hydrogen carrier gases and still achieve faster analyses.

Wool and Decker [3] indicated in their paper that frequent trimming of the front of the column was necessary for use with heavy matrix samples due primarily to the lower sample capacity of 0.18-mm columns. In this work a 5-m 0.25-mm id retention gap and Y connector were installed ahead of the

analytical columns to help offset the diminished sample capacity relative to wider bore capillary columns. Use of a retention gap will also shield the analytical columns from deleterious matrix effects and extend the useful lives of the columns.

Agilent's method translation software simplifies conversion from established laboratory GC methods to parallel sets of conditions suitable for high-efficiency GC columns. Chromatographic conditions from the original method, along with the new column dimensions, are entered into a menu-driven table within the software. The software then generates a translated method table with all the new chromatographic setpoints for the translated method. The new translated method setpoints produced by the software are often all that is required to successfully translate a method.

Three primary modes of method translation are available in the method translation software: translate only, best efficiency, and fast analysis. The "translate only" mode produces a set of conditions that most closely resembles the original method in terms of relative position on the Van Deemter curve, degree of separation, and elution order. The "best efficiency" mode generates a set of conditions where column efficiency is prioritized. The "fast analysis" mode generates a set of conditions where analysis speed is prioritized. By using the various modes available a translated method specific to a particular application can be developed quickly with a few keystrokes and iterative passes through the software.

The software is very useful in porting methods from the use of one carrier gas to another. Translation from the original method using one carrier to a method using another carrier is accomplished by entering the original method setpoints, the new column dimensions, and the desired carrier. The software then generates the translated method setpoints for the new column and carrier. For additional information on Agilent's method translation software, please visit this link: <http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>.

Flow programming is not addressed in the method translation software, so minor adjustments to flow rate parameters may be required to achieve desired results. When translating flow-programmed methods, initial or intermediate flow rates can be entered into the original method parameters table to visualize the effect on the other parameters' output in the translated method table. The operator can then collect data at several different flow rates and select the best set of conditions for the application.

In this CLP pesticide example, the original method used a hydrogen carrier and flow programming. The initial flow parameters were entered into the method translation software, along with the new column dimensions, specifying helium as the carrier gas. Translate-only mode was selected in the software and produced the translated method setpoints that appear in Figure 1.

Original Method		Translated Method	
Column			
Length, m	20.00	☐ 20.00	
Internal Diameter, µm	180.0	☐ 180.0	
Film		☐ Unlock	
Thickness, µm	0.180	☒ 0.180	
Phase Ratio	250.0	☐ 250.0	
Carrier Gas	Hydrogen	Helium	
Enter one Setpoint			
Head Pressure, psi	25.756	37.597	
Flow Rate, mL/min	1.7943	1.4354	
Outlet Velocity, cm/sec	155.58	124.47	
Average Velocity, cm/sec	77.30	49.42	
Hold-up Time, min	0.431220	0.674472	
Outlet Pressure (absolute), psi	14.696	☐ 14.696	
Ambient Pressure (absolute), psi	14.696	☐ 14.696	
Oven Temperature 3-ramp Program			
	Ramp Rate	Final Temp.	Final Time
	°C/min	°C	min
Initial	120.00	0.490	
Ramp 1	59.400	160.00	0.000
Ramp 2	23.700	260.00	0.000
Ramp 3	35.600	300.00	1.690
	Ramp Rate	Final Temp.	Final Time
	°C/min	°C	min
	37.977	160.00	0.000
	15.152	260.00	0.000
	22.761	300.00	2.643

Figure 1. Method translation using translate-only mode.

Figure 2 shows the resulting CLP pesticide separations produced using translate-only mode in the method translation software on the DB-17ms column. Note that all 22 species are baseline resolved on the DB-17ms column where there is a partially separated triplet consisting of gamma chlordane, alpha chlordane, and endosulfan 1 on the DB-XLB column (Figure 3). This partially separated triplet was also observed in the original DB-XLB separation using hydrogen carrier.

Table 3 is a standard compound key for the numbered peaks in the chromatograms. Separation characteristics such as degree of separation and elution order were maintained exactly as they were in the original method using the new translated method with helium carrier. The original method

was successfully translated with no additional method development.

Unfortunately, the unresolved triplet on DB-XLB observed in the original method remained unresolved in the translated method. Additional method development attempts focused on resolving the partially separated triplet on the DB-XLB confirmation column and reduction of analysis time. Some success was achieved; however, the trailing two peaks in the triplet remained partially resolved on the DB-XLB confirmation column while analysis time was reduced to 11 minutes. The DB-17ms column resolved all of the species in the protocol throughout these experiments (Figure 4). Triplet resolution on the DB-XLB (Figure 5), though not ideal, is adequate for the purpose of peak confirmation of well-resolved species on the DB-17ms.




Figure 2. Translate-only separation (conditions as in Figure 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 0.4 pg/component loading for low-level target compounds.

Table 3. CLP Standard Compound List Key

1. Tetrachloro-m-xylene	12. 4,4' DDE
2. Alpha BHC	13. Dieldrin
3. Gamma BHC	14. Endrin
4. Beta BHC	15. 4,4' DDD
5. Delta BHC	16. Endosulfan II
6. Heptachlor	17. 4,4' DDT
7. Aldrin	18. Endrin aldehyde
8. Heptachlor epoxide	19. Endosulfan sulfate
9. Gamma chlordane	20. Methoxychlor
10. Alpha chlordane	21. Endrin ketone
11. Endosulfan I	22. Decachlorobiphenyl




Figure 3. Translate-only separation (conditions as in Figure 1) on 20 m × 0.18 mm × 0.18 μm DB-XLB (Agilent p/n 121-1222) with a 0.4 pg/component loading for low-level target compounds.




Figure 4. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 0.4 pg/component loading for low-level target compounds.




Figure 5. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-XLB (Agilent p/n 121-1222) with a 0.4 pg/component loading for low-level target compounds.

Detector Sensitivity and Linearity

The 0.5-μL injections were split between two columns for an on-column loading of 0.4 pg per component of the low-level target compounds. The data suggest that detection limits of at least an order of magnitude lower are possible. Sensitivity and linearity measurements conducted with these chemical species using μECD detection support this assertion [4]. Analyte

concentration range investigated here was from 1.6 – 40 ng/mL. This range meets the 16-fold low- to high-check standard criteria for the protocol and appears to cover only the middle of the dynamic range the detector is capable of fielding. Figure 3 shows the DB-17ms separation where low-level component loading was 0.4 pg. Figure 6 shows the same separation with a 10-pg loading for the same components.




Figure 6. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 10-pg/component loading for low-level target compounds.

Conclusions

Complete separation and confirmation of all 22 species in the CLP pesticide protocol were accomplished in an 11-minute analysis with helium carrier gas. These results demonstrate the utility of these 0.18-mm id high-efficiency GC columns for CLP pesticide analysis. Using a 0.5- μ L injection of pesticide standard solutions over a concentration range of 1.6 – 40 ng/mL gave excellent results. These results easily meet the 16x high/low dynamic range requirement for the protocol and suggest that expanding the range to both lower and higher concentrations is certainly possible with these 0.18-mm columns.

Full compatibility for use of these columns with standard GC equipment and helium carrier was also established by this successful separation. Operating pressure for use of these columns at the high point of the temperature program (300 °C) was 50 psi, well within the operation pressure range for standard GC equipment.

Method translation software successfully translated the original method using hydrogen carrier to the new method using helium carrier. Separation characteristics from the original method, such as elution order and degree of separation, were matched exactly in the translated method. This exercise served once again to validate the simplicity of

method translation using the software. Method development beyond the translated method setpoint only became necessary when improvements to the original separation were attempted.

References

1. To download Agilent Method Translation software, please visit this link: <http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>.
2. C. George, "Rapid Analysis of CLP Pesticides Using High-Temperature DB-35ms and DB-XLB Columns," Application Note 5988-4973EN, December 18, 2001
3. L. Wool and D. Decker, "Practical Fast Gas Chromatography for Contract Laboratory Program Pesticide Analysis," *Journal of Chromatographic Science*, Vol. 40 September 2002
4. I. L. Chang, M. S. Klee, and J. Murphy, "Validation Analysis of EPA CLP Target Organochlorine Pesticides with the Agilent 6890 Series GC and Micro-ECD," Application Note 5966-3742E, February 1998

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
January 16, 2008
5989-7818EN



Agilent Technologies



A Direct Column-Performance Comparison for Rapid Contract Laboratory Program (CLP) Pesticide Analysis

Application

Environmental

Authors

Ken Lynam and John W. Henderson, Jr.
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent J&W High Efficiency GC columns with internal diameter of 0.18 mm for Contract Laboratory Program (CPL) pesticide analyses gave superior results for CPL pesticide primary analysis and confirmation. Chromatograms depicting peak shape characteristics, peak resolution, and baseline stability for two sets of 0.18-mm id columns are presented in a head-to-head comparison. Complete primary and confirmatory analysis of the 20 pesticides in the protocol is accomplished in less than 6 minutes using hydrogen carrier gas and flow programming. Successful primary and confirmatory analyses were achievable only on Agilent J&W High Efficiency GC columns.

Introduction

The analyses of organochlorine pesticides (OCPs) in environmental remediation samples are important, high volume, analyses in the competitive contract laboratory marketplace. A standard Contract Laboratory Program (CLP) pesticide method is used for these analyses. In many cases a lab will analyze large numbers of samples over the course of a given project, accumulating costs to both the lab and its client. Use of Agilent J&W 0.18-mm id High Efficiency GC columns is a means of enhancing laboratory productivity [1-3].

Wool and Decker [3] reported their findings at the U.S. Environmental Protection Agency (Region VI, Houston, TX) laboratory and described the value of columns in the 20 m × 0.18 mm format for CLP pesticide analysis. Their suggestion to use a retention gap to protect the analytical columns from deleterious matrix effects and to help offset the lower sample capacity of these columns relative to wider bore columns was incorporated into this column comparison. Deactivated 5 m × 0.25 mm id retention gaps were used in this series of experiments on each column set used.

Columns with 0.18 mm id capable of doing CPL pesticide analysis are available from several leading column manufacturers. Agilent's suggested pair for CLP pesticide analysis in the 0.18 mm id format is a DB-17ms column for primary analysis and a DB-XLB column for confirmation. Vendor R's offering is a set of proprietary phase 0.18 mm id columns for both primary and confirmation analysis of CLP pesticides.

Experimental

The chromatograph used was an Agilent 6890N GC equipped with dual electron capture detectors (μ ECDs) and a 7683B autosampler. Sample introduction was done by a single split/splitless injection port at the head of a retention gap column connected through a Y-splitter with two analytical columns. Details of the initial chromatographic conditions appear in Table 1.



Agilent Technologies

Table 1. Chromatographic Conditions

GC :	Agilent 6890N
Sampler:	Agilent 7683B, 5 µL syringe (Agilent p/n 5181-1273), 0.5 µL injection
Carrier:	Hydrogen (flow programmed, 69 cm/s at 120 °C, ramped at 99 mL/min to 106 cm/s at 4.4 minutes, purified through a Big Universal Trap (Agilent p/n RMSH-2)
Inlet:	Split/splitless; 220 °C, pulsed splitless (35 psi for 0.5 min, purge flow of 40 mL/min on at 1 minute, gas saver flow 20 mL/min on 3 minutes
Inlet liner:	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Retention gap:	5 m × 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter:	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	1 20 m × 0.18 mm × 0.18 µm DB-17ms (Agilent p/n 121-4722)
	2 20 m × 0.18 mm × 0.18 µm DB-XLB (Agilent p/n 121-1222)
Oven:	120 °C (0.32 min); 120 °C/min to 160 °C; 30 °C/min to 258 °C (0.18 min); 38.81 °C/min to 300 °C (1.5 min)
Detection:	µECD 320 °C; nitrogen makeup; constant column + makeup flow (60 mL/min)

The flow path supplies used in these experiments are listed in Table 2.

Table 2. Flow Path Supplies

	Description	Agilent p/n
Vials:	Amber screw cap	5182-0716
Vial caps:	Blue screw cap	5282-0723
Vial inserts:	100 µL glass/polymer feet	5181-1270
Syringe:	5 µL	5181-1273
Septum:	Advanced green	5183-4759
Inlet liner:	Deactivated single taper direct connect	1544-80730
Ferrules:	0.4 mm id short; 85/15 Vespel/graphite	5181-3323
Y-splitter:	Quartz deactivated	5181-3398
Sealing resin:	Polyimide sealing resin	500-1200
20x magnifier:	20x magnifier loupe	430-1020
Tubing cutter:	Ceramic wafer column cutter	5181-8836

Both sets of columns used in this comparison were installed into the GC in the same manner. The same retention gap and inlet liner were used for both sets of columns. The chromatographic conditions (except for the columns) in Tables 1 and 2 were used to evaluate both the proprietary columns recommended by Vendor R and Agilent's columns. The primary analysis column from Agilent was a 20 m × 0.18 mm × 0.18 µm DB-17ms. The column from Vendor R was a 20 m × 0.18 mm × 0.18 µm with a proprietary stationary phase. The confirmatory analysis column from Agilent was a 20 m × 0.18 mm × 0.18 µm DB-XLB. The column from Vendor R was a 20 m × 0.18 mm × 0.14 µm with a proprietary stationary phase.

Sample Preparation

CLP pesticide standard solutions were purchased from AccuStandard (New Haven, CT 06513 USA). ULTRA RESI ANALYZED grade 2,2,4 trimethylpentane was purchased from J.T. Baker (Phillipsburg, NJ 08865 USA).

CLP-023R-160X and CLP-024R-160X concentrates were diluted first into 50-mL volumetric flasks in 2,2,4 trimethylpentane and then serially diluted. Volumetric flasks and pipettes used were all class A. The standard concentration range for low-level target compounds in the protocol was from 3.2 to 80 ng/mL. On-column loading ranged from 0.8 to 20 pg for low-level target compounds when a 0.5-µL injection over both columns is considered.

Column Installation Using Y Splitters

Installation of the Y splitter was accomplished by coating the outside of the fused silica tubing to be inserted into the Y splitter with a thin film of polyimide sealing resin prior to cutting the tubing. The cut was then made through the coated section of tubing. The cut end was then checked with a 20x magnification loupe to make sure that the cut was clean and that excess sealant had not diffused inside the column. Once a clean cut was obtained, the fused silica with the polyimide sealant on the outside only was inserted into the desired branch of the Y and held for approximately 45 seconds to seal. Good sealing was indicated by a thin ring of sealant at the point of contact. The process was done first with the analytical columns and then repeated for the trunk of the Y into the retention gap. This approach has given tight, reliable connections that have lasted without difficulty for over 2 months and through hundreds of oven temperature program cycles.

Method Translation Software/Path to Successful Conditions

The starting point for this comparison was the conversion of a successful set of separation conditions using helium carrier on Agilent's DB-17ms and DB-XLB 0.18 mm id columns [4] to a set of conditions using hydrogen carrier. The chromatographic parameters for the helium carrier separation were keyed into the translation table in the Agilent GC Method Translation software [5–6] to convert the method to use with hydrogen carrier. In the software, the "Translate Only" mode was used to convert the 11-minute helium carrier method to a 7.3-minute hydrogen carrier method using the same columns.

Method development effort beyond conversion from helium carrier to hydrogen carrier gas became necessary only when the goal of the analysis shifted to emphasize speed of analysis using flow programming. Flow programming is outside the scope of the Method Translation software. In this series of experiments, flow programming helped to elute highly retained peaks faster. Further temperature program modifications also increased the speed of analysis with minimal loss of resolution on the Agilent columns.

Results and Discussion

Successful separation of CLP pesticides using hydrogen carrier was demonstrated on Agilent's DB-17ms and DB-XLB 0.18-mm id columns using the conditions shown in Table 1. Vendor R's 0.18-mm ID columns were evaluated using the following conditions: the conditions shown in Table 1, the conditions obtained on Vendor R's Web site (to the extent practical), and with a set of conditions optimized specifically on Vendor R's columns for this analysis. The goal throughout these experiments was to show as fair and objective a comparison as possible.

To compare chromatograms, injections at a standard concentration of 3.2 ng/mL for low-level target species in the CLP protocol were selected. Using this concentration consistently provides a fixed point of reference and at the same time alleviates the potential for masking deleterious chromatographic effects often seen at higher concentrations. Inclusion of a Y scale in each chromatogram provides another fixed reference within each figure to facilitate comparison. Key aspects to

look for in the example chromatograms are peak resolution, indications of peak tailing, and temperature-dependent drift on the μ ECD.

An Agilent DB-17ms column was used as the primary analysis column in these experiments. An example chromatogram from an injection at a nominal concentration of 3.2 ng/mL for low target level pesticides is shown in the upper portion of Figure 1. This column resolved all the peaks of interest in less than 6 minutes, gave sharp symmetrical peaks, and had minimal background drift on the μ ECD. A compound label key for the numbered peaks in the chromatogram is located in Table 3.

An Agilent DB-XLB 20 m x 0.18 mm x 0.18 μ m column was used for confirmatory analysis on these experiments. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in the lower portion of Figure 1. This column resolved 20 of the peaks of interest in less than 6 minutes and gave near baseline resolution of peaks 10 and 11. Again, sharp symmetrical peaks and minimal temperature-dependent baseline drift were observed on the μ ECD. Although complete resolution of 20 of the 22 peaks of interest on the confirmatory columns is not ideal, the observed resolution is satisfactory for peak confirmation.

The peak identification table applies to Figure 1, depicting CPL pesticide separation on Agilent's column only. Elution order for these columns with their particular selectivity was established in previous work. To establish elution order on Vendor R's columns with different selectivity, injection of individual standards or mass spectral confirmation is required.

Table 3. CLP Standard Compound List Key

1. Tetrachloro-m-xylene	12. 4,4' DDE
2. Alpha BHC	13. Dieldrin
3. Gamma BHC	14. Endrin
4. Beta BHC	15. 4,4' DDD
5. Delta BHC	16. Endosulfan II
6. Heptachlor	17. 4,4' DDT
7. Aldrin	18. Endrin aldehyde
8. Heptachlor epoxide	19. Endosulfan sulfate
9. Gamma chlordane	20. Methoxychlor
10. Alpha chlordane	21. Endrin ketone
11. Endosulfan I	22. Decachlorobiphenyl




Figure 1. Chromatogram of 0.5- μ l injection of 3.2 ng/ml low-level target pesticide standard solution injected through a Y-splitter onto DB-17ms (Agilent p/n 121-4722) primary analysis column and a DB-XLB (Agilent p/n 121-1222) confirmatory analysis column, conditions as in Table 1.

The primary analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.18 μ m with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 2. This column gave resolution of 20 of the 22 peaks of interest, peak tailing for some species, and minimal temperature dependent baseline drift on the μ ECD. The arrows within the figure point to co-eluting and tailing peaks.

The confirmatory analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.14 μ m with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 2. This column yielded resolution of all 22 peaks of interest, indication of peak tailing for some species, and significant temperature-dependent baseline drift on the μ ECD. The arrows within the figure point to tailing peaks and highlight baseline drift, in this case over 100 Hz.

Vendor R's suggested separation conditions for their column pair were unsuccessful at producing results equivalent to those shown on their Web site. This appears to stem from an oversight on their part. Suggested conditions found in a figure caption on the Web site called for a 2-min hold 10° C above the maximum recommended temperature. A temperature of 330 °C was called for; however, the label on the column box listed the upper temperature program limit as 320 °C for the confirmation column. Vendor R's confirmation column demonstrated significant bleed even with a temperature program that reached only 300 °C, a full 20 °C below the upper limit.

A series of attempts to resolve the co-eluting pair of pesticides on Vendor R's primary analysis column gave improved but still incomplete resolution. It was necessary to substantially reduce flow rate and modify both temperature and flow programming parameters to achieve the results shown in Figure 3. The chromatographic conditions used for these injections appear in Table 4; the flow path supplies were the same as those listed in Table 2.




Figure 2. Chromatogram of 0.5 μL injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary analysis column and confirmatory columns, conditions as in Table 1. Figure 2. Chromatogram of 0.5 μL injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary analysis column and confirmatory columns, conditions as in Table 1.

The primary analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.18 μm with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 3. This column still gave resolution of 20 of the 22 peaks of interest, indication of peak tailing for some species, and minimal temperature-dependent baseline drift on the μECD . The arrows within the figure point to the unresolved peaks and tailing peaks.

The confirmatory analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.14 μm with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 3. This column yielded resolution of all 22 peaks of interest, indication of peak tailing for some species, and significant temperature-dependent baseline drift on the μECD . The arrows within the figure point to tailing peaks and highlight baseline drift.




Figure 3. Chromatogram of 0.5- μ L-injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary and confirmatory analysis columns, conditions as in Table 4.

Table 4. Chromatographic Conditions

GC:	Agilent 6890N
Sampler:	Agilent 7683B, 5 μ L syringe (Agilent p/n 5181-1273), 0.5 μ L injection
Carrier:	Hydrogen (flow programmed , 45 cm/s at 120 $^{\circ}$ C, ramped at 99 mL/min to 72 cm/s at 4.4 minutes, purified through a Big Universal Trap (Agilent p/n RMSH-2)
Inlet:	Split/splitless; 220 $^{\circ}$ C pulsed splitless (35 psi for 0.5 min, purge flow 40 mL/min on 1 minute, gas saver 20 mL/min at 3 minutes)
Inlet liner:	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Retention gap:	5 m $\times$ 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter:	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	1 20 m $\times$ 0.18 mm $\times$ 0.18 μ m primary analysis column 2 20 m $\times$ 0.18 mm $\times$ 0.14 μ m confirmatory analysis column
Oven:	120 $^{\circ}$ C (0.50 min); 60 $^{\circ}$ C/min to 160 $^{\circ}$ C; 30 $^{\circ}$ C/min to 260 $^{\circ}$ C; 40 $^{\circ}$ C/min to 300 $^{\circ}$ C (2.0 min)
Detection:	μ ECD 320 $^{\circ}$ C; nitrogen makeup; constant column + makeup flow 60 (mL/min)

Conclusions

Agilent's 0.18-mm id primary analysis column is superior to Vendor R's offering. All 22 peaks of interest were resolved on the DB-17ms primary analysis column in less than 6 minutes with sharp, symmetrical peaks and minimal baseline drift. Vendor R's primary analysis column resolved 20 of 22 peaks of interest and displayed evidence of peak tailing for some of the peaks of interest.

Agilent's 0.18-mm id confirmatory analysis column offering is superior to Vendor R's offering. Twenty of 22 peaks of interest were resolved on the DB-XLB, with the other two peaks being almost baseline resolved in less than 6 minutes, with sharp, symmetrical peaks and minimal temperature-dependent baseline drift. Resolution of 20 of 22 peaks is less than ideal but should serve well for peak confirmation. Vendor R's confirmatory column resolved all 22 peaks of interest but showed evidence of peak tailing and an unacceptable level of temperature-dependent baseline drift.

The DB-17ms and the DB-XLB columns used in these experiments gave very low bleed profiles on the μ ECDs. The stable baselines produced by both of these columns can lead to lower detection limits,

simpler integration and more reliable results over time. These columns also have the versatility of use with other analyses beyond CLP pesticides.

Reliable CLP pesticide primary and confirmation analyses are achievable using Agilent J&W high-efficiency GC columns in less than 6 minutes with standard gas chromatographic equipment.

References

1. I. L. Chang, M. S. Klee, and J. Murphy, "Validation Analysis of EPA CLP Target Organochlorine Pesticides with the Agilent 6890 Series GC and Micro-ECD," Agilent publication 5966-3742E, February 1998
2. C. George, "Rapid Analysis of CLP Pesticides Using High-Temperature DB-35ms and DB-XLB Columns," Agilent publication 5988-4973EN, December 18, 2001
3. L. Wool and D. Decker, "Practical Fast Gas Chromatography for Contract Laboratory Program Pesticide Analysis," *Journal of Chromatographic Science*, Vol. 40, September 2002
4. K. Lynam and W. Long, "Contract Laboratory Program (CLP) Pesticide Analysis with 0.18 mm ID High Efficiency GC Columns Utilizing Helium Carrier Gas," Agilent publication 5989-7818EN, January 7, 2008
5. To download Agilent Method Translation software please visit the link below:
<http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>
6. K. Lynam, "Agilent J&W High-Efficiency Capillary Columns: Productivity-Enhancing Tools for Fast GC Applications," Agilent publication 5989-7499-EN, November 7, 2007

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
February 26, 2008
5989-8031EN



Agilent Technologies



Organophosphorus Pesticides Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column

Application Note

Environmental

Authors

Doris Smith and Kenneth Lynam
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

Agilent Technologies Inc. has implemented new testing procedures to more effectively evaluate GC column inertness performance. This new testing procedure employs deliberately aggressive probes to thoroughly investigate and verify column inertness and quality. In challenging separations, knowing that the GC column has been thoroughly investigated for column inertness gives analysts higher confidence in the accuracy of their results.

Trace- and ultra trace-level pesticide analyses are important tools for accessing food supply and environmental quality worldwide. In this application note, trace-level organophosphorus pesticide analysis is demonstrated using electron impact single quadrupole scanning mass spectrometry. Agilent's J&W DB-5ms Ultra Inert capillary GC column provides excellent peak shape for even the most problematic pesticides.



Agilent Technologies

Introduction

Pesticides are commonly used in agricultural and residential applications throughout the world. Organophosphorus pesticides make up approximately 70 percent of the insecticides currently in use. Unfortunately, these highly toxic materials have three main routes of human exposure: inhalation, ingestion, and skin penetration. Sources of these exposures include consumption of foodstuff containing pesticide residues, aerosol inhalation, and dermal contact during pesticide application. [1]

Organophosphorus pesticides use the same mechanism of action as deadly nerve agents such as sarin, soman, and VX. These pesticides affect the nervous system of insects, mammals, and wildlife by inhibiting the enzyme cholinesterase, important in helping regulate nerve impulses. Inactivation of cholinesterase leads to the accumulation of the neurotransmitter acetylcholine in the central and peripheral nervous system, which leads to depressed motor function and respiratory depression. Human toxicities for this class of molecules have shown acute as well as chronic effects from pesticide poisoning. [2,3]

Organophosphorus pesticides tend to be difficult to quantify due to poor peak shape, as evidenced by broad, asymmetrical peaks. An EPA Method 525.2 standard containing organophosphorus pesticides along with a custom pesticide mix acquired from Ultra Scientific (North Kingstown, RI) were analyzed to highlight the value of using a 30-m Agilent J&W DB-5ms Ultra Inert capillary GC column for difficult pesticide analysis. Many pesticides are sensitive to chromatographic system activity and will readily breakdown. The Ultra Scientific custom mix contains several types of these pesticides, which are useful in quickly evaluating system performance with particularly challenging pesticide analytes. Capillary GC column activity as a potential source of result uncertainty has been virtually eliminated with the Ultra Inert series of columns. [4]

Experimental

An Agilent 6890N GC/5975B MSD equipped with a 7683B autosampler was used for this series of experiments. Table 1 lists the chromatographic conditions used for these analyses. Table 2 lists flow path consumable supplies used in these experiments.

Table 1A. Chromatographic Conditions for EPA Method 525.2 Calibration Standards

GC	Agilent 6890N/5975B MSD
Sampler	Agilent 7683B, 5.0- μ L syringe (Agilent p/n 5181-1273) 1.0- μ L splitless injection
Carrier	Helium 44 cm/s, constant flow
Inlet	Pulsed splitless; 250 °C, 40 psi until 0.75 min, purge flow 50 mL/min at 1.0 min
Inlet liner	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Column	Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 122-5532UI)
Oven	40 °C (1 min) to 110 °C (50 °C/min), 7 °C/min to 190 °C, 12 °C/min to 285 °C, hold 2 min.
Detection	MSD source at 250 °C, quadrupole at 150 °C, transfer line at 280 °C, EI mode, scan range 45–450 amu

Table 1B. Chromatographic Conditions for Ultra Scientific Calibration Standards

GC	Agilent 6890N/5975B MSD
Sampler	Agilent 7683B, 5.0- μ L syringe (Agilent p/n 5181-1273) 1.0- μ L splitless injection
Carrier	Helium 52 cm/s, constant flow
Inlet	Pulsed splitless; 250 °C, 40 psi until 0.75 min, purge flow 50 mL/min at 1.0 min
Inlet liner	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Column	Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m (Agilent p/n 122-5532UI)
Oven	75 °C to 175 °C (15 °C/min), 10 °C/min to 275 °C (1 min)
Detection	MSD source at 250 °C, quadrupole at 150 °C, transfer line at 280 °C, EI mode, scan range 45–450 amu

Table 2. Flow Path Supplies

Vials	Amber crimp-top glass vials (Agilent p/n 5183-4496)
Vial caps	Crimp caps with 11-mm septa (Agilent p/n 5181-1210)
Vial inserts	100- μ L glass/polymer feet (Agilent p/n 5181-8872)
Syringe	5 μ L (Agilent p/n 5181-1273)
Septum	Advanced Green (Agilent p/n 5183-4759)
Inlet liners	Deactivated dual taper direct connect (Agilent p/n G1544-80700)
Ferrules	0.4 mm id short; 85/15 Vespel/graphite (Agilent p/n 5181-3323)
20x magnifier	20x magnifier loupe (Agilent p/n 430-1020)

Sample Preparation

A six-component EPA Method 525.2 pesticide standard mix and internal/surrogate standard mix were purchased from Accu-Standard (New Haven, CT) and used to prepare a six-level calibration standard set. The stock pesticide solution as delivered had a nominal concentration of 1,000 µg/mL. The internal/surrogate solution as delivered had a nominal concentration of 500 µg/mL. The calibration standards were prepared with component concentrations of 10, 5, 2, 1, 0.5, and 0.1 µg/mL and a constant level of 5 µg/mL of internal/surrogate standard as per EPA Method 525.2. All solutions were prepared in acetone using class A volumetric pipettes and flasks. Acetone used was JT Baker Ultra Resi Grade purchased thorough VWR International (West Chester, PA). Acetone was used as a reagent blank and syringe wash solvent.

An 11-component pesticide standard mix was purchased from Ultra Scientific and used to prepare a seven-level calibration standard set. The stock pesticide solution as delivered had a nominal concentration of 1,000 µg/mL. The calibration standards were prepared with component concentrations of 10, 5, 2.5, 1, 0.5, 0.25, and 0.1 µg/mL. All solutions were prepared in 2,2,4-trimethylpentane using class A volumetric pipettes and flasks. The 2,2,4-trimethylpentane used was JT Baker Ultra Resi Grade purchased thorough VWR International (West Chester, PA). 2,2,4-Trimethylpentane was used as a reagent blank and syringe wash solvent.

Results and Discussion

Baseline Inertness Profile for Ultra Inert Columns

The basic approach for inertness verification for the Agilent J&W Ultra Inert series of capillary GC columns is testing with aggressive active probes at low concentration and low temperature. [5] This is a rigorous approach that establishes consistent baseline inertness profiles for each column in the Agilent J&W Ultra Inert GC column series. The baseline inertness profile then serves as a predictor for successful analysis of chemically active species that tend to adsorb onto active

sites, particularly at trace level, like the organophosphorus pesticides in this application example. A more detailed description of the test mix and additional application examples can be found in references 6 through 8.

Organophosphorus Pesticide Analysis

In this application note, a multilevel pesticide calibration curve set was evaluated over the concentration range of 0.1 to 10 µg/mL on an Agilent J&W Ultra Inert DB-5 ms 30 m × 0.25 mm × 0.25 µm (Agilent p/n 122-5532UI). Separate calibration curves were developed for both the EPA 525.2 organophosphorus and Ultra Scientific standards. The standard levels used for the 525.2 calibration were 0.1, 0.5, 1, 2, 5, and 10 µg/mL, while the Ultra Scientific calibration levels were 0.1, 0.25, 0.5, 1, 2.5, 5, and 10 µg/mL. The custom pesticide standard from Ultra Scientific was used to determine system performance by analyzing difficult pesticides, such as endrin and p,p'-DDT, which are prone to analyte breakdown.

No tailing was observed for any of the organophosphorus pesticide peaks across the range studied in either standard set. Sharp, symmetrical peak shapes were noted for all the organophosphorus pesticides analyzed. Good resolution was obtained for each of the pesticides investigated.

Linearity for the 525.2 standard components was excellent across the range studied, giving R^2 values of 0.997 or greater in all cases but fenamiphos, which had an R^2 value of 0.978. This value increases to 0.991 at the midlevel concentrations as suggested by EPA Method 525.2 Sec. 13.2.3.3. Figure 5 indicates the correlation coefficients for each of the individual pesticides and shows an example linear regression plot for disulfoton.

Linearity for the Ultra Scientific standard components was also quite good across the range studied. R^2 values of 0.990 or greater were obtained for the organophosphorus pesticides. Figure 6 indicates the correlation coefficients for each of the individual pesticides and shows an example linear regression plot for mevinphos.

- | | |
|-------------------------------------|-----------------------------|
| 1. 1,3-Dimethyl-2-nitrobenzene (SS) | 7. Ametryn |
| 2. Acenaphthene-d10 (IS) | 8. Fenamiphos |
| 3. Cycloate | 9. Tribufos (DEF) |
| 4. Prometron | 10. Triphenylphosphate (SS) |
| 5. Phenanthrene-d10 (IS) | 11. Chrysene-d12 (IS) |
| 6. Disulfoton | 12. Perylene-d12 (SS) |




Figure 1. Total ion chromatogram (scan mode) of the 1-ng on-column EPA Method 525.2 standard solution loading on an Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 122-5532UI). Chromatographic conditions are listed in Table 1A.




Figure 2. Enlarged section of the total ion chromatogram (scan mode) for a 1- μ L injection of 1.0 μ g/mL EPA Method 525.2 standard pesticide mix. The peaks noted in the figure are the three organophosphorus pesticides of interest. Chromatographic conditions are listed in Table 1A.




Figure 3. Total ion chromatogram (scan mode) of the 0.1-ng on-column Ultra Scientific standard solution loading on an Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 122-5532UI). Chromatographic conditions are listed in Table 1B.




Figure 4. Enlarged section of the total ion chromatogram (scan mode) for a 1- μ L injection of 0.1 μ g/mL Ultra Scientific standard pesticide mix on an Agilent J&W DB-5ms Ultra Inert 30 m $\times$ 0.25 mm $\times$ 0.25 μ m capillary GC column (p/n 122-5532UI). The peak in the figure is mevinphos, an organophosphorus pesticide of interest. This injection represents an on-column loading of 0.1 ng per component. Chromatographic conditions are listed in Table 1B.

Component	R ²
Cycloate	1.000
Prometon	0.999
Disulfoton	0.999
Ametryn	0.999
Fenamiphos	0.978
Tribufos (DEF)	0.997




Figure 5. Correlation coefficients for the EPA Method 525.2 pesticide components over the 0.1 to 10 µg/mL range of this study and an example linear regression plot for disulfoton.

Component	R ²
1,3-Dimethyl-2-nitrobenzene	0.999
Mevinphos	0.990
Pentachlorophenol	0.989
Terbufos	0.996
Bromacil	0.988
Aldrin	0.999
Carboxin	0.996
Endrin	0.998
p,p'-DDT	0.996
Triphenylphosphate	0.997
DEHP	0.996




Figure 6. Correlation coefficients for the Ultra Scientific pesticide components over the 0.1 to 10 µg/mL range of this study and an example linear regression plot for mevinphos.

Conclusions

This application successfully demonstrates the use of an Agilent J&W DB-5ms Ultra Inert capillary GC column for trace-level organophosphorus pesticides. Linearity was excellent for all organophosphorus pesticides studied, yielding 0.99 or greater R² values down to a 0.1-ng on-column loading of each component. One of the reasons for excellent linearity and high R² values is the highly inert surface of the column. The lack of chemically active sites makes these columns an excellent choice for trace-level applications.

This study was done using scan mode on an Agilent 6890/5975B GC/MSD equipped with an inert electron impact source. The signal-to-noise ratio for a 0.1-ng on-column loading of mevinphos was greater than 5 to 1 with this system. This result shows clearly the power of using an Agilent J&W DB-5ms Ultra Inert column for trace-level organophosphorus pesticides analysis. Lower limits of quantification are expected when using one of Agilent's latest GC/MS offerings, such as the 7890/5975C GC/MSD Triple-Axis Detector coupled with an Agilent J&W DB-5ms Ultra Inert GC capillary column.

References

1. J. Routt Reigart and James R. Roberts, *Recognition and Management of Pesticide Poisoning*, 5th Ed, 1999, pp 34–47 [Online] Available: www.epa.gov/oppfead1/safety/healthcare/handbook/handbook.htm
2. Kenneth D. Katz, et al, "Organophosphate Toxicity," [Online]. Available: www.emedicine.com/med/TOPIC1677.HTM (Article last updated May 30, 2008)
3. K. Steenland, "Chronic Neurological Effects of Organophosphate Pesticides," *BMJ*, May 25, 1996; 312(7042): 1312 – 1313.
4. J. W. Eichelberger, et al., US EPA Method 525.2 Revision 2.0, "Determination of Organic Compounds in Drinking Water by Liquid-Solid Extration and Capillary Column Gas Chromatography/Mass Spectrometry," National Exposure Research Laboratory, USEPA, Cincinnati, Ohio, 1995.
5. Mitch Hastings, Allen K. Vickers, and Cameron George, "Inertness Comparison of Sample of 5% Phenyl-dimethylpolysiloxane Columns," Poster Presentation, 54th Annual Pittsburg Conference, Orlando, FL, March 2003
6. "Agilent J&W Ultra Inert GC Columns: A New Tool to Battle Challenging Active Analytes," Agilent Technologies publication 5989-8685EN, May 29, 2008
7. Kenneth Lynam, "Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column," Agilent Technologies publication 5989-8616EN, May 13, 2008
8. Kenneth Lynam and Doris Smith "Polycyclic Aromatic Hydrocarbon (PAH) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column," Agilent Technologies publication 5989-9181EN, in press

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2008
Published in the USA
November 12, 2008
5989-9879EN



Agilent Technologies



A Direct Column-Performance Comparison for Rapid Contract Laboratory Program (CLP) Pesticide Analysis

Application

Environmental

Authors

Ken Lynam and John W. Henderson, Jr.
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent J&W High Efficiency GC columns with internal diameter of 0.18 mm for Contract Laboratory Program (CPL) pesticide analyses gave superior results for CPL pesticide primary analysis and confirmation. Chromatograms depicting peak shape characteristics, peak resolution, and baseline stability for two sets of 0.18-mm id columns are presented in a head-to-head comparison. Complete primary and confirmatory analysis of the 20 pesticides in the protocol is accomplished in less than 6 minutes using hydrogen carrier gas and flow programming. Successful primary and confirmatory analyses were achievable only on Agilent J&W High Efficiency GC columns.

Introduction

The analyses of organochlorine pesticides (OCPs) in environmental remediation samples are important, high volume, analyses in the competitive contract laboratory marketplace. A standard Contract Laboratory Program (CLP) pesticide method is used for these analyses. In many cases a lab will analyze large numbers of samples over the course of a given project, accumulating costs to both the lab and its client. Use of Agilent J&W 0.18-mm id High Efficiency GC columns is a means of enhancing laboratory productivity [1-3].

Wool and Decker [3] reported their findings at the U.S. Environmental Protection Agency (Region VI, Houston, TX) laboratory and described the value of columns in the 20 m × 0.18 mm format for CLP pesticide analysis. Their suggestion to use a retention gap to protect the analytical columns from deleterious matrix effects and to help offset the lower sample capacity of these columns relative to wider bore columns was incorporated into this column comparison. Deactivated 5 m × 0.25 mm id retention gaps were used in this series of experiments on each column set used.

Columns with 0.18 mm id capable of doing CPL pesticide analysis are available from several leading column manufacturers. Agilent's suggested pair for CLP pesticide analysis in the 0.18 mm id format is a DB-17ms column for primary analysis and a DB-XLB column for confirmation. Vendor R's offering is a set of proprietary phase 0.18 mm id columns for both primary and confirmation analysis of CLP pesticides.

Experimental

The chromatograph used was an Agilent 6890N GC equipped with dual electron capture detectors (μ ECDs) and a 7683B autosampler. Sample introduction was done by a single split/splitless injection port at the head of a retention gap column connected through a Y-splitter with two analytical columns. Details of the initial chromatographic conditions appear in Table 1.



Agilent Technologies

Table 1. Chromatographic Conditions

GC :	Agilent 6890N
Sampler:	Agilent 7683B, 5 µL syringe (Agilent p/n 5181-1273), 0.5 µL injection
Carrier:	Hydrogen (flow programmed, 69 cm/s at 120 °C, ramped at 99 mL/min to 106 cm/s at 4.4 minutes, purified through a Big Universal Trap (Agilent p/n RMSH-2)
Inlet:	Split/splitless; 220 °C, pulsed splitless (35 psi for 0.5 min, purge flow of 40 mL/min on at 1 minute, gas saver flow 20 mL/min on 3 minutes
Inlet liner:	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Retention gap:	5 m × 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter:	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	1 20 m × 0.18 mm × 0.18 µm DB-17ms (Agilent p/n 121-4722)
	2 20 m × 0.18 mm × 0.18 µm DB-XLB (Agilent p/n 121-1222)
Oven:	120 °C (0.32 min); 120 °C/min to 160 °C; 30 °C/min to 258 °C (0.18 min); 38.81 °C/min to 300 °C (1.5 min)
Detection:	µECD 320 °C; nitrogen makeup; constant column + makeup flow (60 mL/min)

The flow path supplies used in these experiments are listed in Table 2.

Table 2. Flow Path Supplies

	Description	Agilent p/n
Vials:	Amber screw cap	5182-0716
Vial caps:	Blue screw cap	5282-0723
Vial inserts:	100 µL glass/polymer feet	5181-1270
Syringe:	5 µL	5181-1273
Septum:	Advanced green	5183-4759
Inlet liner:	Deactivated single taper direct connect	1544-80730
Ferrules:	0.4 mm id short; 85/15 Vespel/graphite	5181-3323
Y-splitter:	Quartz deactivated	5181-3398
Sealing resin:	Polyimide sealing resin	500-1200
20x magnifier:	20x magnifier loupe	430-1020
Tubing cutter:	Ceramic wafer column cutter	5181-8836

Both sets of columns used in this comparison were installed into the GC in the same manner. The same retention gap and inlet liner were used for both sets of columns. The chromatographic conditions (except for the columns) in Tables 1 and 2 were used to evaluate both the proprietary columns recommended by Vendor R and Agilent's columns. The primary analysis column from Agilent was a 20 m × 0.18 mm × 0.18 µm DB-17ms. The column from Vendor R was a 20 m × 0.18 mm × 0.18 µm with a proprietary stationary phase. The confirmatory analysis column from Agilent was a 20 m × 0.18 mm × 0.18 µm DB-XLB. The column from Vendor R was a 20 m × 0.18 mm × 0.14 µm with a proprietary stationary phase.

Sample Preparation

CLP pesticide standard solutions were purchased from AccuStandard (New Haven, CT 06513 USA). ULTRA RESI ANALYZED grade 2,2,4 trimethylpentane was purchased from J.T. Baker (Phillipsburg, NJ 08865 USA).

CLP-023R-160X and CLP-024R-160X concentrates were diluted first into 50-mL volumetric flasks in 2,2,4 trimethylpentane and then serially diluted. Volumetric flasks and pipettes used were all class A. The standard concentration range for low-level target compounds in the protocol was from 3.2 to 80 ng/mL. On-column loading ranged from 0.8 to 20 pg for low-level target compounds when a 0.5-µL injection over both columns is considered.

Column Installation Using Y Splitters

Installation of the Y splitter was accomplished by coating the outside of the fused silica tubing to be inserted into the Y splitter with a thin film of polyimide sealing resin prior to cutting the tubing. The cut was then made through the coated section of tubing. The cut end was then checked with a 20x magnification loupe to make sure that the cut was clean and that excess sealant had not diffused inside the column. Once a clean cut was obtained, the fused silica with the polyimide sealant on the outside only was inserted into the desired branch of the Y and held for approximately 45 seconds to seal. Good sealing was indicated by a thin ring of sealant at the point of contact. The process was done first with the analytical columns and then repeated for the trunk of the Y into the retention gap. This approach has given tight, reliable connections that have lasted without difficulty for over 2 months and through hundreds of oven temperature program cycles.

Method Translation Software/Path to Successful Conditions

The starting point for this comparison was the conversion of a successful set of separation conditions using helium carrier on Agilent's DB-17ms and DB-XLB 0.18 mm id columns [4] to a set of conditions using hydrogen carrier. The chromatographic parameters for the helium carrier separation were keyed into the translation table in the Agilent GC Method Translation software [5–6] to convert the method to use with hydrogen carrier. In the software, the "Translate Only" mode was used to convert the 11-minute helium carrier method to a 7.3-minute hydrogen carrier method using the same columns.

Method development effort beyond conversion from helium carrier to hydrogen carrier gas became necessary only when the goal of the analysis shifted to emphasize speed of analysis using flow programming. Flow programming is outside the scope of the Method Translation software. In this series of experiments, flow programming helped to elute highly retained peaks faster. Further temperature program modifications also increased the speed of analysis with minimal loss of resolution on the Agilent columns.

Results and Discussion

Successful separation of CLP pesticides using hydrogen carrier was demonstrated on Agilent's DB-17ms and DB-XLB 0.18-mm id columns using the conditions shown in Table 1. Vendor R's 0.18-mm ID columns were evaluated using the following conditions: the conditions shown in Table 1, the conditions obtained on Vendor R's Web site (to the extent practical), and with a set of conditions optimized specifically on Vendor R's columns for this analysis. The goal throughout these experiments was to show as fair and objective a comparison as possible.

To compare chromatograms, injections at a standard concentration of 3.2 ng/mL for low-level target species in the CLP protocol were selected. Using this concentration consistently provides a fixed point of reference and at the same time alleviates the potential for masking deleterious chromatographic effects often seen at higher concentrations. Inclusion of a Y scale in each chromatogram provides another fixed reference within each figure to facilitate comparison. Key aspects to

look for in the example chromatograms are peak resolution, indications of peak tailing, and temperature-dependent drift on the μ ECD.

An Agilent DB-17ms column was used as the primary analysis column in these experiments. An example chromatogram from an injection at a nominal concentration of 3.2 ng/mL for low target level pesticides is shown in the upper portion of Figure 1. This column resolved all the peaks of interest in less than 6 minutes, gave sharp symmetrical peaks, and had minimal background drift on the μ ECD. A compound label key for the numbered peaks in the chromatogram is located in Table 3.

An Agilent DB-XLB 20 m x 0.18 mm x 0.18 μ m column was used for confirmatory analysis on these experiments. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in the lower portion of Figure 1. This column resolved 20 of the peaks of interest in less than 6 minutes and gave near baseline resolution of peaks 10 and 11. Again, sharp symmetrical peaks and minimal temperature-dependent baseline drift were observed on the μ ECD. Although complete resolution of 20 of the 22 peaks of interest on the confirmatory columns is not ideal, the observed resolution is satisfactory for peak confirmation.

The peak identification table applies to Figure 1, depicting CPL pesticide separation on Agilent's column only. Elution order for these columns with their particular selectivity was established in previous work. To establish elution order on Vendor R's columns with different selectivity, injection of individual standards or mass spectral confirmation is required.

Table 3. CLP Standard Compound List Key

1. Tetrachloro-m-xylene	12. 4,4' DDE
2. Alpha BHC	13. Dieldrin
3. Gamma BHC	14. Endrin
4. Beta BHC	15. 4,4' DDD
5. Delta BHC	16. Endosulfan II
6. Heptachlor	17. 4,4' DDT
7. Aldrin	18. Endrin aldehyde
8. Heptachlor epoxide	19. Endosulfan sulfate
9. Gamma chlordane	20. Methoxychlor
10. Alpha chlordane	21. Endrin ketone
11. Endosulfan I	22. Decachlorobiphenyl




Figure 1. Chromatogram of 0.5- μ l injection of 3.2 ng/ml low-level target pesticide standard solution injected through a Y-splitter onto DB-17ms (Agilent p/n 121-4722) primary analysis column and a DB-XLB (Agilent p/n 121-1222) confirmatory analysis column, conditions as in Table 1.

The primary analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.18 μ m with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 2. This column gave resolution of 20 of the 22 peaks of interest, peak tailing for some species, and minimal temperature dependent baseline drift on the μ ECD. The arrows within the figure point to co-eluting and tailing peaks.

The confirmatory analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.14 μ m with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 2. This column yielded resolution of all 22 peaks of interest, indication of peak tailing for some species, and significant temperature-dependent baseline drift on the μ ECD. The arrows within the figure point to tailing peaks and highlight baseline drift, in this case over 100 Hz.

Vendor R's suggested separation conditions for their column pair were unsuccessful at producing results equivalent to those shown on their Web site. This appears to stem from an oversight on their part. Suggested conditions found in a figure caption on the Web site called for a 2-min hold 10° C above the maximum recommended temperature. A temperature of 330 °C was called for; however, the label on the column box listed the upper temperature program limit as 320 °C for the confirmation column. Vendor R's confirmation column demonstrated significant bleed even with a temperature program that reached only 300 °C, a full 20 °C below the upper limit.

A series of attempts to resolve the co-eluting pair of pesticides on Vendor R's primary analysis column gave improved but still incomplete resolution. It was necessary to substantially reduce flow rate and modify both temperature and flow programming parameters to achieve the results shown in Figure 3. The chromatographic conditions used for these injections appear in Table 4; the flow path supplies were the same as those listed in Table 2.




Figure 2. Chromatogram of 0.5 μ L injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary analysis column and confirmatory columns, conditions as in Table 1. Figure 2. Chromatogram of 0.5 μ L injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary analysis column and confirmatory columns, conditions as in Table 1.

The primary analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.18 μ m with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 3. This column still gave resolution of 20 of the 22 peaks of interest, indication of peak tailing for some species, and minimal temperature-dependent baseline drift on the μ ECD. The arrows within the figure point to the unresolved peaks and tailing peaks.

The confirmatory analysis column from Vendor R was a 20 m $\times$ 0.18 mm $\times$ 0.14 μ m with a proprietary stationary phase. An injection at a nominal concentration of 3.2 ng/mL for low-level target pesticides is depicted in Figure 3. This column yielded resolution of all 22 peaks of interest, indication of peak tailing for some species, and significant temperature-dependent baseline drift on the μ ECD. The arrows within the figure point to tailing peaks and highlight baseline drift.




Figure 3. Chromatogram of 0.5- μ L-injection of 3.2 ng/mL low-level target pesticide standard solution injected through a Y-splitter onto Vendor R's primary and confirmatory analysis columns, conditions as in Table 4.

Table 4. Chromatographic Conditions

GC:	Agilent 6890N
Sampler:	Agilent 7683B, 5 μ L syringe (Agilent p/n 5181-1273), 0.5 μ L injection
Carrier:	Hydrogen (flow programmed , 45 cm/s at 120 $^{\circ}$ C, ramped at 99 mL/min to 72 cm/s at 4.4 minutes, purified through a Big Universal Trap (Agilent p/n RMSH-2)
Inlet:	Split/splitless; 220 $^{\circ}$ C pulsed splitless (35 psi for 0.5 min, purge flow 40 mL/min on 1 minute, gas saver 20 mL/min at 3 minutes)
Inlet liner:	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Retention gap:	5 m $\times$ 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter:	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	1 20 m $\times$ 0.18 mm $\times$ 0.18 μ m primary analysis column 2 20 m $\times$ 0.18 mm $\times$ 0.14 μ m confirmatory analysis column
Oven:	120 $^{\circ}$ C (0.50 min); 60 $^{\circ}$ C/min to 160 $^{\circ}$ C; 30 $^{\circ}$ C/min to 260 $^{\circ}$ C; 40 $^{\circ}$ C/min to 300 $^{\circ}$ C (2.0 min)
Detection:	μ ECD 320 $^{\circ}$ C; nitrogen makeup; constant column + makeup flow 60 (mL/min)

Conclusions

Agilent's 0.18-mm id primary analysis column is superior to Vendor R's offering. All 22 peaks of interest were resolved on the DB-17ms primary analysis column in less than 6 minutes with sharp, symmetrical peaks and minimal baseline drift. Vendor R's primary analysis column resolved 20 of 22 peaks of interest and displayed evidence of peak tailing for some of the peaks of interest.

Agilent's 0.18-mm id confirmatory analysis column offering is superior to Vendor R's offering. Twenty of 22 peaks of interest were resolved on the DB-XLB, with the other two peaks being almost baseline resolved in less than 6 minutes, with sharp, symmetrical peaks and minimal temperature-dependent baseline drift. Resolution of 20 of 22 peaks is less than ideal but should serve well for peak confirmation. Vendor R's confirmatory column resolved all 22 peaks of interest but showed evidence of peak tailing and an unacceptable level of temperature-dependent baseline drift.

The DB-17ms and the DB-XLB columns used in these experiments gave very low bleed profiles on the μ ECDs. The stable baselines produced by both of these columns can lead to lower detection limits,

simpler integration and more reliable results over time. These columns also have the versatility of use with other analyses beyond CLP pesticides.

Reliable CLP pesticide primary and confirmation analyses are achievable using Agilent J&W high-efficiency GC columns in less than 6 minutes with standard gas chromatographic equipment.

References

1. I. L. Chang, M. S. Klee, and J. Murphy, "Validation Analysis of EPA CLP Target Organochlorine Pesticides with the Agilent 6890 Series GC and Micro-ECD," Agilent publication 5966-3742E, February 1998
2. C. George, "Rapid Analysis of CLP Pesticides Using High-Temperature DB-35ms and DB-XLB Columns," Agilent publication 5988-4973EN, December 18, 2001
3. L. Wool and D. Decker, "Practical Fast Gas Chromatography for Contract Laboratory Program Pesticide Analysis," *Journal of Chromatographic Science*, Vol. 40, September 2002
4. K. Lynam and W. Long, "Contract Laboratory Program (CLP) Pesticide Analysis with 0.18 mm ID High Efficiency GC Columns Utilizing Helium Carrier Gas," Agilent publication 5989-7818EN, January 7, 2008
5. To download Agilent Method Translation software please visit the link below:
<http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>
6. K. Lynam, "Agilent J&W High-Efficiency Capillary Columns: Productivity-Enhancing Tools for Fast GC Applications," Agilent publication 5989-7499-EN, November 7, 2007

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
February 26, 2008
5989-8031EN



Agilent Technologies



Contract Laboratory Program (CLP) Pesticide Analysis with 0.18 mm ID High-Efficiency GC Columns Utilizing Helium Carrier Gas

Application

Environmental

Authors

Ken Lynam and William Long
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, Delaware 19808
U.S.A.

Abstract

Contract Laboratory Program (CLP) pesticide analysis is demonstrated on high-efficiency GC columns (20 m × 0.18 mm id × 0.18 μm film thickness) with helium carrier gas. DB-17ms stationary phase is used for primary analysis and DB-XLB stationary phase for confirmation. Primary analysis and confirmation of 22 CLP pesticides in the protocol is achieved in an 11-minute analysis, a 35% reduction in analysis time versus 0.32 mm id columns.

Method translation software is successfully employed to translate an original set of conditions with hydrogen carrier gas to a new set of conditions using helium carrier gas. Elution order and degree of separation are shown to translate precisely from the original method to the new method through use of this software (available for free download) [1].

Introduction

The determination of organochlorine pesticides (OCPs) in environmental remediation samples are important, high-volume analyses in the competitive contract laboratory marketplace. A standard Contract Laboratory Program (CLP) pesticide method is used for these analyses. In many cases a lab will analyze large numbers of samples over the course of a given project, adding costs to both the lab and its

client. Here, 0.18 mm id high-efficiency GC columns are demonstrated as a means of enhancing laboratory productivity. These columns are fully compatible with standard gas chromatographs and helium carrier gas operation. The high efficiency these columns offer coupled with their full compatibility with existing GCs provide laboratories with a powerful tool for enhancing sample throughput. When analysis times for 30 m × 0.32 id and 20 m × 0.18 mm id columns were compared, a 17-minute analysis was reduced to only 11 minutes and with improved resolution [2].

Helium carrier gas was selected as a means to show the utility of 0.18 mm id columns in doing CLP pesticide analyses and to demonstrate the full compatibility of these columns with standard gas chromatographs. The operating gas pressures for these 20 m × 0.18 mm id columns range from 33 psi initially to 50 psi at the high point of the temperature program. The gas pressure range used with helium carrier gas with these 0.18 mm id columns was well within the operating range for standard chromatographs.

Experimental

This work was accomplished using an Agilent 6890N GC equipped with dual μECDs and a 7683B autosampler. A single split/splitless injection port was used for sample introduction at the head of a retention gap column connected through a Y-splitter with two analytical columns. Details of the chromatographic conditions are presented in Table 1.



Agilent Technologies

Table 1. Chromatographic Conditions

GC	Agilent 6890N
Sampler:	Agilent 7683B, 5 µL syringe (Agilent p/n 5181-1273), 0.5 µL injection
Inlet	Split/splitless; 250 °C pulsed splitless (35 psi for 0.5 min)
Inlet liner	Deactivated single taper direct connect (Agilent p/n 1544-80730)
Carrier	Helium (constant flow, 49.5 cm/sec at 120 °C, purified through big universal trap Agilent p/n RMSH-2)
Retention gap	5 m × 0.25 mm id deactivated (Agilent p/n 160-2255-5)
Y-splitter	Quartz deactivated (Agilent p/n 5181-3398)
Columns:	
1	20 m × 0.18 mm × 0.18 µm DB-17ms (Agilent p/n 121-4722)
2	20 m × 0.18 mm × 0.18 µm DB-XXL (Agilent p/n 121-1222)
Oven	120 °C (0.49 min); 85 °C/min to 160 °C; 20 °C/min to 260 °C (0.20 min); 25 °C/min to 285 °C; 40 °C/min to 300 °C (3.5 min)
Detection	µECD 325 °C; nitrogen makeup; constant column + makeup flow 60 (mL/min)

The flow path supplies used in these experiments are listed in Table 2 below.

Table 2. Flow Path Supplies

		Agilent p/n
Vials	Amber screw cap	5182-0716
Vial caps	Blue screw cap	5282-0723
Vial inserts	100 µL glass/polymer feet	5181-1270
Syringe	5 µL	5181-1273
Septum	Advanced green	5183-4759
Inlet liner	Deactivated single taper direct connect	1544-80730
Ferrules	0.4 mm id short; 85/15 Vespel/graphite	5181-3323
Y-splitter	Quartz deactivated	5181-3398
Sealing resin	Polyimide sealing resin	500-1200
20x magnifier	20x magnifier loop	430-1020
Tubing cutter	Ceramic wafer column cutter	5181-8836

Sample Preparation

CLP pesticide standard solutions were purchased from AccuStandard, New Haven, CT 06513-USA. ULTRA RESI ANALYZED grade 2,2,4 trimethylpentane was purchased from J. T. Baker, Phillipsburg, NJ 08865-USA. CLP-023R-160X and CLP-024R-160X concentrates were diluted separately into two

100-mL volumetric flasks in 2,2,4 trimethylpentane and then combined in subsequent serial dilutions. Volumetric flasks and pipettes used were all class A. Standard concentration range for low-level target compounds in the protocol was from 1.6 to 40 ng/mL. On-column loading ranged from 0.4 to 10 pgs for low-level target compounds when a 0.5-µL injection over both columns is considered.

Column Installation Tip on Using Y Splitters

Installation of the Y splitter was accomplished by coating the outside of the fused silica tubing to be inserted into the Y splitter with a thin film of polyimide sealing resin prior to cutting the tubing. The cut was then made through the coated section of tubing. The cut end was then checked with a 20x magnification loop to make sure that the cut was clean and that excess sealant had not diffused inside the column. Once a clean cut was obtained, the fused silica with the polyimide sealant on the outside only was inserted into the desired branch of the Y and held for approximately 45 seconds to seal. Good sealing was indicated by a thin ring of sealant at the point of contact. The process was done first with the analytical columns and then repeated for the trunk of the Y into the retention gap. This approach gave tight, reliable connections that have lasted without any difficulty for more than 2 months (to date) and hundreds of oven temperature program cycles.

Results and Discussion

The starting point for this application was a set of conditions for CLP pesticide analyses using hydrogen carrier gas and 0.18-mm high-efficiency columns developed by Wool and Decker [3]. Using hydrogen carrier and flow programming, they were able to achieve primary separation and confirmation analysis of CLP pesticides in a 7-minute analysis. The chromatographic parameters for the hydrogen carrier separation were input as initial setpoints in method translation software to convert the method to use with helium carrier. Helium carrier was selected for use in laboratories reluctant to work with hydrogen carrier due to site safety policy or individual preference. High-efficiency GC columns give the chromatographer the option to work with either helium or hydrogen carrier gases and still achieve faster analyses.

Wool and Decker [3] indicated in their paper that frequent trimming of the front of the column was necessary for use with heavy matrix samples due primarily to the lower sample capacity of 0.18-mm columns. In this work a 5-m 0.25-mm id retention gap and Y connector were installed ahead of the

analytical columns to help offset the diminished sample capacity relative to wider bore capillary columns. Use of a retention gap will also shield the analytical columns from deleterious matrix affects and extend the useful lives of the columns.

Agilent's method translation software simplifies conversion from established laboratory GC methods to parallel sets of conditions suitable for high-efficiency GC columns. Chromatographic conditions from the original method, along with the new column dimensions, are entered into a menu-driven table within the software. The software then generates a translated method table with all the new chromatographic setpoints for the translated method. The new translated method setpoints produced by the software are often all that is required to successfully translate a method.

Three primary modes of method translation are available in the method translation software: translate only, best efficiency, and fast analysis. The "translate only" mode produces a set of conditions that most closely resembles the original method in terms of relative position on the Van Deemter curve, degree of separation, and elution order. The "best efficiency" mode generates a set of conditions where column efficiency is prioritized. The "fast analysis" mode generates a set of conditions where analysis speed is prioritized. By using the various modes available a translated method specific to a particular application can be developed quickly with a few keystrokes and iterative passes through the software.

The software is very useful in porting methods from the use of one carrier gas to another. Translation from the original method using one carrier to a method using another carrier is accomplished by entering the original method setpoints, the new column dimensions, and the desired carrier. The software then generates the translated method setpoints for the new column and carrier. For additional information on Agilent's method translation software, please visit this link: <http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>.

Flow programming is not addressed in the method translation software, so minor adjustments to flow rate parameters may be required to achieve desired results. When translating flow-programmed methods, initial or intermediate flow rates can be entered into the original method parameters table to visualize the effect on the other parameters' output in the translated method table. The operator can then collect data at several different flow rates and select the best set of conditions for the application.

In this CLP pesticide example, the original method used a hydrogen carrier and flow programming. The initial flow parameters were entered into the method translation software, along with the new column dimensions, specifying helium as the carrier gas. Translate-only mode was selected in the software and produced the translated method setpoints that appear in Figure 1.

		Original Method		Translated Method	
Column					
Length	m	20.00		20.00	
Internal Diameter	µm	180.0		180.0	
Film					
Thickness	µm	0.180		0.180	
Phase Ratio		250.0		250.0	
Carrier Gas					
Enter one Setpoint					
Head Pressure	psi	25.756		37.597	
Flow Rate	mL/min	1.7943		1.4354	
Outlet Velocity	cm/sec	155.58		124.47	
Average Velocity	cm/sec	77.30		49.42	
Hold-up Time	min	0.431220		0.674472	
Outlet Pressure (absolute)	psi	14.696		14.696	
Ambient Pressure (absolute)	psi	14.696		14.696	
Oven Temperature					
3-ramp Program					
		Ramp Rate	Final Temp.	Final Time	
		°C/min	°C	min	°C/min
Initial			120.00	0.490	120.00
Ramp 1		59.400	160.00	0.000	37.977
Ramp 2		23.700	260.00	0.000	15.152
Ramp 3		35.600	300.00	1.690	22.761
					300.00
					2.643

Figure 1. Method translation using translate-only mode.

Figure 2 shows the resulting CLP pesticide separations produced using translate-only mode in the method translation software on the DB-17ms column. Note that all 22 species are baseline resolved on the DB-17ms column where there is a partially separated triplet consisting of gamma chlordane, alpha chlordane, and endosulfan 1 on the DB-XLB column (Figure 3). This partially separated triplet was also observed in the original DB-XLB separation using hydrogen carrier.

Table 3 is a standard compound key for the numbered peaks in the chromatograms. Separation characteristics such as degree of separation and elution order were maintained exactly as they were in the original method using the new translated method with helium carrier. The original method

was successfully translated with no additional method development.

Unfortunately, the unresolved triplet on DB-XLB observed in the original method remained unresolved in the translated method. Additional method development attempts focused on resolving the partially separated triplet on the DB-XLB confirmation column and reduction of analysis time. Some success was achieved; however, the trailing two peaks in the triplet remained partially resolved on the DB-XLB confirmation column while analysis time was reduced to 11 minutes. The DB-17ms column resolved all of the species in the protocol throughout these experiments (Figure 4). Triplet resolution on the DB-XLB (Figure 5), though not ideal, is adequate for the purpose of peak confirmation of well-resolved species on the DB-17ms.




Figure 2. Translate-only separation (conditions as in Figure 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 0.4 pg/component loading for low-level target compounds.

Table 3. CLP Standard Compound List Key

1. Tetrachloro-m-xylene	12. 4,4' DDE
2. Alpha BHC	13. Dieldrin
3. Gamma BHC	14. Endrin
4. Beta BHC	15. 4,4' DDD
5. Delta BHC	16. Endosulfan II
6. Heptachlor	17. 4,4' DDT
7. Aldrin	18. Endrin aldehyde
8. Heptachlor epoxide	19. Endosulfan sulfate
9. Gamma chlordane	20. Methoxychlor
10. Alpha chlordane	21. Endrin ketone
11. Endosulfan I	22. Decachlorobiphenyl




Figure 3. Translate-only separation (conditions as in Figure 1) on 20 m × 0.18 mm × 0.18 μm DB-XLB (Agilent p/n 121-1222) with a 0.4 pg/component loading for low-level target compounds.




Figure 4. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 0.4 pg/component loading for low-level target compounds.




Figure 5. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-XLB (Agilent p/n 121-1222) with a 0.4 pg/component loading for low-level target compounds.

Detector Sensitivity and Linearity

The 0.5-μL injections were split between two columns for an on-column loading of 0.4 pg per component of the low-level target compounds. The data suggest that detection limits of at least an order of magnitude lower are possible. Sensitivity and linearity measurements conducted with these chemical species using μECD detection support this assertion [4]. Analyte

concentration range investigated here was from 1.6 – 40 ng/mL. This range meets the 16-fold low- to high-check standard criteria for the protocol and appears to cover only the middle of the dynamic range the detector is capable of fielding. Figure 3 shows the DB-17ms separation where low-level component loading was 0.4 pg. Figure 6 shows the same separation with a 10-pg loading for the same components.




Figure 6. Optimized separation (conditions as in Table 1) on 20 m × 0.18 mm × 0.18 μm DB-17ms (Agilent p/n 121-4722) with a 10-pg/component loading for low-level target compounds.

Conclusions

Complete separation and confirmation of all 22 species in the CLP pesticide protocol were accomplished in an 11-minute analysis with helium carrier gas. These results demonstrate the utility of these 0.18-mm id high-efficiency GC columns for CLP pesticide analysis. Using a 0.5- μ L injection of pesticide standard solutions over a concentration range of 1.6 – 40 ng/mL gave excellent results. These results easily meet the 16x high/low dynamic range requirement for the protocol and suggest that expanding the range to both lower and higher concentrations is certainly possible with these 0.18-mm columns.

Full compatibility for use of these columns with standard GC equipment and helium carrier was also established by this successful separation. Operating pressure for use of these columns at the high point of the temperature program (300 °C) was 50 psi, well within the operation pressure range for standard GC equipment.

Method translation software successfully translated the original method using hydrogen carrier to the new method using helium carrier. Separation characteristics from the original method, such as elution order and degree of separation, were matched exactly in the translated method. This exercise served once again to validate the simplicity of

method translation using the software. Method development beyond the translated method setpoint only became necessary when improvements to the original separation were attempted.

References

1. To download Agilent Method Translation software, please visit this link: <http://www.chem.agilent.com/cag/servsup/usersoft/files/GCTS.htm>.
2. C. George, "Rapid Analysis of CLP Pesticides Using High-Temperature DB-35ms and DB-XLB Columns," Application Note 5988-4973EN, December 18, 2001
3. L. Wool and D. Decker, "Practical Fast Gas Chromatography for Contract Laboratory Program Pesticide Analysis," *Journal of Chromatographic Science*, Vol. 40 September 2002
4. I. L. Chang, M. S. Klee, and J. Murphy, "Validation Analysis of EPA CLP Target Organochlorine Pesticides with the Agilent 6890 Series GC and Micro-ECD," Application Note 5966-3742E, February 1998

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
January 16, 2008
5989-7818EN



Agilent Technologies



Determination of Chlorinated Acid Herbicides in Soil by LC/MS/MS

Application Note

Environmental

Author

Chin-Kai Meng
Agilent Technologies
2850 Centerville Road
Wilmington, DE 19808-1601
USA

Abstract

Chlorinated acid herbicides were analyzed at the picogram level on column without any derivatization using liquid chromatography and tandem mass spectrometry (LC/MS/MS). Good linearity was observed for all the selected analytes, from low pg to low ng levels on column.

Introduction

Chlorinated acid herbicides are a popular class of broad-leaf weed killer in lawn and grain crops. Due to their widespread use, environmental contamination in water and soil from run-off is a serious concern.

Traditional analytical methods based on gas chromatography (GC) and/or mass spectrometry (MS) require derivatization of the analytes. Combining LC and electrospray ionization (ESI) in negative ion mode, these herbicides can be analyzed without derivatization. The multiple reaction monitoring (MRM) mode in MS/MS operation provides low pg detection limits.

This application note is based on standards and sample preparation procedures from the Montana Department of Agriculture in Bozeman, Montana.

Experimental

Standard and Sample Preparation

A stock solution of each analyte at 200 ppm is prepared in methanol. Intermediate mixed solutions for fortifying soil samples and making calibration standards are made by accurately mixing aliquots of each standard stock solution. The concentrations of each analyte in the intermediate solution used in this study are listed in Table 1.

Table 1. Acid Herbicide Mixed Intermediate Standards in Methanol

Clopyralid	5930 (pg/ μ L)	3,6-dichloro-2-pyridinecarboxylic acid
Picloram	1800	4-amino-3,5,6-trichloropicolinic acid
Dicamba	8200	3,6-dichloro-2-methoxybenzoic acid
2,4-D	1740	2,4-dichlorophenoxyacetic acid
MCPA	5480	2-methyl-4-chlorophenoxyacetic acid
Triclopyr	1240	[(3,5,6-trichloro-2-pyridinyl)oxy] acetic acid
2,4-DP	1410	2,4-dichlorophenoxypropionic acid or dichloroprop
MCPP	2710	2-(2-methyl-4-chlorophenoxy) propionic acid
2,4-DB	6900	2,4-dichlorophenoxybutyric acid



Agilent Technologies

Sample extraction and cleanup procedures are shown below.

Sample Extraction Procedure

1. Weigh 20 ± 0.1 g of soil.
2. Add 50 mL of 0.5N KOH in 10% KCl extracting solution to each sample. Mix thoroughly by shaking.
3. Place samples in boiling water bath for 15 minutes.
4. Place samples on horizontal shaker for 15 minutes.
5. Centrifuge samples at 1200 to 1500 rpm for 15 minutes.
6. Transfer a 3.0-mL aliquot into a 13-mL conical centrifuge tube and add 150 μ L of 12 N sulfuric acid.
7. Vortex and confirm the pH is <1.5 . If not, add additional acid solution.

Sample Cleanup Procedure

1. Add 2 mL of chloroform to the acidified extract.
2. Vortex 30 seconds and centrifuge at 3000 rpm for 2 minutes.
3. Remove the lower chloroform layer into another centrifuge tube. Repeat these three steps two more times.
4. Evaporate the chloroform extract to just dryness.
5. Immediately add 4.0 mL HPLC-grade water, vortex briefly, sonicate 5 minutes, and briefly vortex again. Fill autosampler vial.

See Reference 1 for more detailed information on sample preparation.

Instrumentation

LC:	1200 LC	
Column:	ZORBAX Extend-C18, RRHT, 2.1 mm $\times$ 100 mm, 1.8 μ m	
Column temperature:	60 $^{\circ}$ C	
Mobile phases:	A: 0.04% Glacial acetic acid in water B: Acetonitrile (ACN)	
Flow rate:	0.3 mL/min	
Injection volume:	1.0 μ L	
Gradient:	Time, min.	%B
	0	0
	1	40
	2	52
	3	60
	4	100
	8	100
	9	0
MS:	G6410A QQQ	
Ionization:	ESI (–)	
Mass range:	120 to 400 amu	
Capillary:	3500 V	
Nebulizer pressure:	40 psi	
Drying gas flow:	9 L/min	
Gas temperature:	200 $^{\circ}$ C	
Skimmer:	35 V	

MRM parameters are listed in Table 2.

Table 2. Method Parameters for MRM

Name	RT	MW	Quant	Qual	Frag V	Col cell	Dwell	Segment
Clopyralid	3.47	191	190 > 146	192 > 148	80	5	70	1
Picloram	3.69	240	239 > 195	241 > 197	80	5	70	1
Dicamba	4.31	220	219 > 175	219 > 145	60	0	150	2
2,4-D	5.02	220	219 > 161	221 > 163	80	15	25	3
MCPA	5.09	200	199 > 141	201 > 143	100	10	25	3
Triclopyr	5.26	255	254 > 196	256 > 198	80	10	25	3
2,4-DP	5.42	234	233 > 161	235 > 163	80	5	25	3
MCPP	5.46	214	213 > 141	215 > 143	100	10	25	3
2,4-DB	5.66	248	247 > 161	249 > 163	80	10	25	3

Due to the concentration differences for these analytes in the intermediate solution (Table 1), Dicamba's concentration was used as the "concentration level" shown in Table 3.

Table 3. Concentration Levels (8000 to 10 pg/ μ L) Used in This Study

Solution concentration level	8000	800	400	200	80	40	20	10
Clopyralid	5930	593	296.5	148.2	59.3	29.7	14.8	7.4
Picloram	1800	180	90	45	18	9.0	4.5	2.3
Dicamba	8200	820	410	205	82	41.0	20.5	10.3
2,4-D	1740	174	87	43.5	17.4	8.7	4.4	2.2
MCPA	5480	548	274	137	54.8	27.4	13.7	6.9
Triclopyr	1240	124	62	31	12.4	6.2	3.1	1.6
2,4-DP	1410	141	70.5	35.2	14.1	7.1	3.5	1.8
MCPP	2710	271	135.5	67.7	27.1	13.6	6.8	3.4
2,4-DB	6900	690	345	172.5	69	34.5	17.3	8.6

For example, concentration level 8000 is the intermediate solution, and concentration level 20 is a 1:400 dilution of the intermediate solution.

Results and Discussion

Figure 1 shows the overlaid chromatograms of all nine herbicides from the MRM analysis. The run time was less than 6 minutes. Using a 1.8- μ m particle size column, the peak widths of these analytes are in the range of 0.1 to 0.2 min. The narrower peak width helps to achieve a higher signal-to-noise ratio.

The MRM results of all nine herbicides at 1.6 to 10.3 pg on column are shown in Figure 2.

As shown in Table 3, the linearity range, incorporating 10, 20, 40, 80, 200, 400, 800, and 8000 pg on column, mimics the concentration of Dicamba.




Figure 1. Overlaid MRM results from the nine selected herbicides.




Figure 2. MRM results.

Therefore, the corresponding on column amounts for Triclopyr are: 1.6, 3.1, 6.2, 12.4, 31, 62, 124, and 1240 pg. The calibration model used was a linear model that included origin with no weighting. All analytes showed excellent linearity.

In the repeatability study, seven 1- μ L injections of the level 40 solution (Table 4) were analyzed to calculate the RSD. At this low concentration, all RSDs were <15%, with the majority in the single digits.

The matrix effect from three different matrices was evaluated. Water and soil extracts were spiked with the herbicide standards (50 μ L of the level 400 standard were added to 950 μ L of water, silt, clay, or sandy extracts). The resulting concentration of the analytes is equivalent to the level 20 solution (Table 3).

Table 5 shows the RSD of eight 1- μ L injections of the level 20 solutions, that is, <20 pg of each ana-

Table 4. Linearity (10 to 8000 pg/ μ L) and Repeatability

Compound	R ² (linear fit, include origin)	Repeatability, %RSD (n=7)	Amount on column
Clopyralid	0.9995	3.5	29.7 pg
Picloram	0.9991	13.1	9.0
Dicamba	0.9999	2.4	41.0
2,4-D	0.9998	6.5	8.7
MCPA	0.9999	2.2	27.4
Triclopyr	0.9993	11.9	6.2
2,4-DP	0.9998	4.5	7.1
MCPP	0.9999	5.0	13.6
2,4-DB	0.9973	8.4	34.5

lyte on column, in three different matrices. As expected, analytes with lower absolute responses showed higher RSD value.

Table 5. RSDs from Eight Injections of <20 pg of Each Analyte in Three Matrices

	Clay	Sandy	Silt	On column
Triclopyr	27	22	22	3.1 pg
MCP	6	5	7	6.8
MCPA	2	6	5	13.7
Clopyralid	14	15	13	14.8
2,4-DP	9	8	13	3.5
2,4-DB	9	3	9	17.3
2,4-D	11	14	13	4.4

The repeatabilities of responses in three matrices for all analytes were <15% except for Triclopyr, which was >20%.

The responses of ≤ 20 pg analytes among water and matrices are compared in Figure 3. The listed response for each matrix is the average of responses from eight injections. The RSDs for water and the three matrices are shown in Figure 3 and are comparable. In general, the variation of the responses among water and different matrices is less than 5% for all analytes except for 2,4-D, which has an RSD close to 10% due to the higher responses from the silt matrix. This shows that the method described in this application note is free from matrix interferences from clay, sand, and silt.

Conclusion

Using LC/MS/MS, chlorinated acid herbicides were analyzed at pg levels on column without any derivatization. At <40 pg on column, the repeatability of seven 1- μ L injections showed RSD <15%. Good linearity was observed for all analytes from low pg to low ng on column.




Figure 3. Analyte RSDs from water and soil extracts are comparable.

The RSDs of <20 pg analytes in the selected matrices were comparable to that in water (RSDs ~5%), except for 2,4-D, due to the higher response from the silt.

Acknowledgement

The author would like to thank Ms. Heidi Hickey and Ms. Angela Schaner from the Montana Department of Agriculture for valuable discussions, sample preparation procedures, and the samples used in this study.

Reference

1. "Determination of Chlorinated Acid Herbicides in Soils by Liquid Chromatography-Electrospray/Mass Spectrometry/Mass Spectrometry," by Angela Schaner and Laura Luckey, Revision 2, April 2, 2004. Montana Department of Agriculture, Laboratory Bureau, McCall Hall, Montana State University, Bozeman, MT 59717.

For More Information

For more information on our products and services, visit our website at www.agilent.com/chem

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
July 25, 2006
5989-5246EN



Agilent Technologies



Screening for 926 Pesticides and Endocrine Disruptors by GC/MS with Deconvolution Reporting Software and a New Pesticide Library

Application Note

Food and Environmental

Authors

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Rd.
Wilmington, DE 19808-1610
USA

endocrine disruptors in about two minutes per sample. Deconvolution helps identify pesticides that are buried in the chromatogram by co-extracted materials. The new database was compared to the smaller one for the DRS analysis of 17 surface water samples. With the new database, DRS found 99 pesticides, metabolites, fire retardants, and related contaminants that were not contained in the original RTL Pesticide and Endocrine Disruptor Library.

Abstract

An updated and greatly expanded collection of mass spectral libraries has been introduced, replacing Agilent's RTL Pesticide Library and DRS pesticide solution. The new library contains 926 pesticides, endocrine disruptors, and related compounds – 359 more than the original library. Included are all compounds specified for GC/MS analysis in the new Japanese "Positive List" regulations. All compounds have locked retention times that can be accurately reproduced using an Agilent GC/MS system with the ChemStation's Retention Time Locking software. The new Database can be used as a standard GC/MS library for compound identification or with Agilent's Screener software for identifications based upon retention time and mass spectral matching. The greatest benefit accrues when these libraries are used with Agilent's new version of Deconvolution Reporting Software (part number G1716AA version A.03.00). This solution allows one to screen GC/MS files for all 926 pesticides and

Introduction

Several years ago Agilent Technologies introduced Retention Time Locking (RTL) for gas chromatography (GC) and GC with mass spectral detection (GC/MS). RTL software makes it possible to reproduce retention times from run-to-run on any Agilent GC or GC/MS, in any laboratory in the world, so long as the same nominal method and GC column are used (1). Since any laboratory can reproduce retention times generated in another, it is possible to create mass spectral libraries that contain locked retention times. By locking their method to the published database, users can screen GC/MS files for all of the library's compounds. "Hits" are required to have the correct retention time as well as the correct spectrum, which eliminates many false positives and gives more confidence in compound identifications (2).



Agilent Technologies

More recently, Agilent introduced Deconvolution Reporting Software (DRS) that incorporates mass spectral deconvolution with conventional library searching and quantification. DRS results from a marriage of three different GC/MS software packages:

- 1) The Agilent GC/MS ChemStation,
- 2) The National Institute of Standards and Technology (NIST) Mass Spectral Search Program with the NIST '05 MS Library, and
- 3) The Automated Mass Spectral Deconvolution and Identification System (AMDIS) software, also from NIST.

The original DRS software was intended to be a comprehensive solution for pesticide analysis and, therefore, included the mass spectra (in AMDIS format) and locked retention times for 567 pesticides and suspected endocrine disruptors (3).

Recently, Agilent introduced an updated and greatly expanded Pesticide and Endocrine Disruptor Database (part number G1672AA) that now contains 926 entries. This represents the addition of 359 new compounds to the original library. At the same time, Agilent introduced a new version of the DRS software (part number G1716AA version A.03.00) that can be used with any Agilent-provided or user-developed DRS library.

Pesticide and Endocrine Disruptor Database Contents

The G1672AA Pesticide and Endocrine Disruptor Database contains virtually all GC-able pesticides, including those introduced very recently. In addition, the database includes numerous metabolites, more endocrine disruptors, important PCBs and PAHs, certain dyes (for example, Sudan Red), synthetic musk compounds, and several organophosphorus fire retardants.

This new database includes:

- A conventional mass spectral library for use with Agilent GC/MS ChemStations

- A screener database for use with Agilent's powerful screener software that is integrated into the GC/MS ChemStation
- Locked Retention Times for all 926 compounds that any Agilent 5975 or 5973 GC/MS user can reproduce in their laboratory
- Files for use with Agilent's G1716AA (A.03.00) Deconvolution Reporting Software
- An e-method that can be loaded into Agilent's G1701DA (version D.02.00 SP1 or higher) with instrument parameters for acquiring GC/MS files and analyzing the data with DRS. These parameters are listed in Table 1.
- Example files
- Application notes

On November 29, 2005, the Japanese Government published a "Positive List" system for the regulation of pesticides, feed additives, and veterinary drugs. Maximum Residue Limits (MRL) have been set for 758 chemicals while 65 others have been exempted from regulation. Fifteen substances must have no detectable residues. Other agricultural chemicals not mentioned have a uniform MRL of 0.01 ppm (4). This new regulation is scheduled to take effect on May 29, 2006.

Of the pesticides in the Japanese Positive List, 265 are to be analyzed by GC/MS. The new G1672AA Pesticide library contains mass spectra and locked retention times for all of these compounds. Thus, a laboratory could screen for all 265 "positive list" compounds and several hundred more pesticides in just 1–3 minutes after the GC/MS run.

Experimental

Table 1 lists the instrumentation, software, and analytical parameters used by Agilent for pesticide analysis. Depending upon the desired injection volume, a PTV inlet or split/splitless inlet can be used.

Table 1. Instrumentation and Conditions of Analysis

Gas Chromatograph	Agilent 6890N
Automatic Sampler	Agilent 7683 Injector and AutoSampler
Inlet	Agilent PTV operated in the solvent vent mode or Split/Splitless
Column	Agilent 30 m × 0.25 mm × 0.25 µm HP-5MSi (part number 19091S-433i)
Carrier gas	Helium in the constant pressure mode
Retention time locking	Chlorpyrifos-methyl locked to 16.596 min (nominal column head pressure = 17.1 psi)
Oven temperature program	70 °C (2 min), 25 °C/min to 150 °C (0 min), 3 °C /min to 200 °C (0 min), 8 °C /min to 280 °C (10–15 min)
PTV inlet parameters	Temp program: 40 °C (0.25 min), 1600 °C/min to 250 °C (2 min); Vent time: 0.2 min; Vent flow: 200 mL/min; Vent pressure: 0.0 psi; Purge flow: 60.0 mL/min; Purge time: 2.00 min
Injection volume	15 µL (using a 50-µL syringe)
Mass Selective Detector	Agilent 5975 inert
Tune file	Atune.u
Mode	Scan (or SIM with SIM DRS library)
Scan range	50–550 u
Source, quad, transfer line temperatures	230, 150, and 280 °C, respectively
Solvent delay	4.00 min
Multiplier voltage	Autotune voltage
Software	
GC/MSD ChemStation	Agilent part number G1701DA (version D02.00 sp1 or higher)
Deconvolution Reporting Software	Agilent part number G1716AA (version A.03.00) Deconvolution Reporting Software
Library searching software	NIST MS Search (version 2.0d or greater) (comes with NIST '05 mass spectral library – Agilent part number G1033A)
Deconvolution software	Automated Mass Spectral Deconvolution and Identification Software (AMDIS_32 version 2.62 or greater; comes with NIST '05 mass spectral library – Agilent part number G1033A)
MS Libraries	NIST '05 mass spectral library (Agilent part number G1033A) Agilent RTL Pesticide and Endocrine Disruptor Libraries in Agilent and NIST formats (part number G1672AA)

Results and Discussion

DRS, which has been described in preceding papers (3,5,6), can be summarized as follows:

Three separate, but complimentary, data analysis steps are combined into the DRS. First, the GC/MS ChemStation software performs a normal quantitative analysis for target pesticides using a target ion and up to three qualifiers. An amount is reported for all calibrated compounds that are detected. For other compounds in the database, an estimate of their concentration can be reported based upon an average pesticide response factor

that is supplied with the DRS software. The DRS then sends the data file to AMDIS, which deconvolutes the spectra and searches the Agilent RTL Pesticide Library using the deconvoluted full spectra. A filter can be set in AMDIS, which requires the analyte's retention time to fall within a user-specified time window. Because RTL is used to reproduce the RTL database retention times with high precision, this window can be quite small – typically 10–20 seconds. Finally, the deconvoluted spectra for all of the targets found by AMDIS are searched against the 147,000-compound NIST mass spectral library for confirmation; for this step, there is no retention time requirement.

This approach was rapidly adopted by many laboratories because of its ability to identify pesticides in complex chromatograms containing high levels of co-extracted interferences. Indeed, the solution proved to be so useful that users began to create their own DRS libraries (7). Therefore, the DRS was unbundled from the pesticide database so that it could be used with any agilent-provided or user-created database.

The original 567-compound RTL Pesticide Library (G1049A) included pesticides, a few metabolites, and most of the GC-amenable endocrine disruptors that were known at the time. The new version of the library includes many more pesticides, endocrine disruptors, and metabolites. This update also contains important compounds from other classes of contaminants that have been found in food and water supplies. Included are eighteen polychlorinated biphenyls (PCBs), four polybrominated biphenyls (PBBs), several polynuclear aromatic hydrocarbons (PAHs), several organophosphorus fire retardants, three important toxaphene congeners, and three Sudan dyes.

Advantages of Deconvolution

Figure 1 shows a screen from AMDIS that illustrates the power of this deconvolution software. The white trace in Figure 1A is the total ion chromatogram while the other three are extracted ions of a deconvoluted peak (a “component” in AMDIS terminology). Note that the TIC and extracted ions are not scaled to each other and this component is actually obscured by co-eluting compounds. Figure 1B juxtaposes the deconvoluted component spectrum (white) with the complete “undeconvoluted” spectrum (black). Clearly, this component is buried under co-eluting peaks that would ordinarily obscure the analyte. Figure 1C shows that the deconvoluted peak (white spectrum) is a good library match for norflurazon (black spectrum). The locked retention time for norflurazon in the RTL Pesticide Database is 26.933 min, which is just 2.3 seconds away from its observed RT in this chromatogram. Confidence in peak identifications is greatly enhanced by the combination of spectral deconvolution and locked retention time filtering.




Figure 1. AMDIS screen showing the identification of norflurazon.

- A) The total ion and extracted ion chromatograms where norflurazon elutes.
- B) The deconvoluted component spectrum (white) juxtaposed with the spectrum at 26.972 min (black).
- C) The deconvoluted component matched to the library spectrum of norflurazon.

Surface Water Analysis - Revisiting an Earlier Study

In an earlier study, a comparison was made between Agilent's DRS and conventional pesticide analysis (3). The California Department of Food and Agriculture (CDFA) provided data files for 17 surface water extracts that had been analyzed in their laboratory. Since the GC/MS chromatograms were locked to the Agilent pesticide method, it was possible to analyze these data files using DRS without having to re-run the samples. The original DRS analysis was made using the 567-compound RTL Pesticide Database. For comparison, these same data files were re-analyzed using the new 926-compound RTL Pesticide Database. The chromatogram (Figure 2) and the DRS report (Figure 3) from one of these samples are shown below.

Excluding phthalates, seven new compounds (shown with bold type in Figure 3) were identified using the 926-compound database: 4-chlorophenyl isocyanate (a phenylurea herbicide metabolite); 3,4-dichlorophenyl isocyanate (diuron metabolite); tris(2-chloroethyl) phosphate (a fire retardant); caffeine (a stimulant); Cyprodinil (a fungicide); desmethyl-norflurazon (a metabolite of norflurazon, an herbicide); and tris(2-butoxyethyl) phosphate (a fire retardant). Although caffeine is not generally considered to be dangerous, it is included in the database because it has been found frequently in sewage effluent and in numerous waterways together with a various pharmaceuticals and pesticides (8).




Figure 2. Chromatogram of a surface water extract that was analyzed by DRS using the new RTL Pesticide and Endocrine Disrupter Database. The results of this analysis are shown in Figure 3.

MSD Deconvolution Report

Sample Name: E02-557

Data File: C:\MSDCHEM\1\DATA\CDFA surface water data\E02-557.d

Date/Time: 11:24 AM Tuesday, Apr 4 2006

The NIST library was searched for the components that were found in the AMDIS target library.

RT	Cas #	Compound name	Agilent ChemStation amount (ng)	AMDIS match	RT Diff (sec.)	NIST reverse match	Hit number
4.4689	106445	4-Methylphenol		62	3.2		
4.4689	0000	3-Carbobenzyloxy-4-ketoproline				48	1
4.8840	104121	4-Chlorophenyl isocyanate		84	-1.8	86	2
6.3879	102363	Diuron Metabolite [3,4-Dichlorophenyl isocyanate]		99	3.1	95	1
6.8357	759944	EPTC		84	2.0	85	1
7.6988	95761	3,4-Dichloroaniline		93	2.1	89	2
7.9342	131113	Dimethylphthalate		67	1.7	84	2
8.1112	25013165	Butylated hydroxyanisole		63	-7.7		
8.1112	0000	7-Methoxy-2,2,4,8-tetramethyltricyclo [5.3.1.0(4,11)]undecane				62	1
8.941	29878317	Tolyltriazole [1H-Benzotriazole, 4-meth-]	1.29				
9.7903	134623	N,N-Diethyl-m-toluamide		85	2.2	84	2
10.0019	84662	Diethyl phthalate		98	2.6	92	1
10.7109	119619	Benzophenone		86	2.6	88	2
10.9684	126738	Tributyl phosphate		96	3.0	90	1
11.6491	1582098	Trifluralin		83	0.7	74	1
12.9326	122349	Simazine		88	1.4	86	2
13.4309	115968	Tris(2-chloroethyl) phosphate		79	1.0	78	1
13.7478	1517222	Phenanthrene-d10		95	1.3	83	1
15.4048	58082	Caffeine		80	1.6	74	1
15.9474	84695	Diisobutyl phthalate		90	3.2	88	4
16.5988	5598130	Chlorpyrifos Methyl		97	0.4	90	1
17.3653	7287196	Prometryn		90	1.5	84	1
18.4213	84742	Di-n-butylphthalate		99	0.4	94	1
18.9214	51218452	Metolachlor		90	0.7	87	1
20.5633	121552612	Cyprodinil		69	-0.1		
20.5633	76470252	9,9-Dimethoxy-9-sila-9, 10-dihydroanthracene				70	1
26.4247	23576241	Norflurazon, Desmethyl-		87	-4.5	69	2
26.9700	27314132	Norflurazon		87	1.5	79	1
26.9992	85687	Butyl benzyl phthalate		94	-0.5	94	1
27.3984	51235042	Hexazinone		89	0.8	83	1
28.0127	78513	Tris(2-butoxyethyl) phosphate		75	3.3	83	1
29.6537	117817	Bis(2-ethylhexyl)phthalate		98	0.3	90	3
33.9298	84764	Di-n-nonyl phthalate		65	-1.9		
33.9298	0000	Phthalic acid, 3,4-dichlorophenyl propyl ester				71	1
13.739		Phenanthrene-d10	10				

Figure 3. DRS report from the analysis of a surface water sample. The compounds shown in bold type were found by the new RTL Pesticide Database but not the original one because these compounds were not included.

For this sample, the ChemStation identified only tolyltriazole at 8.941 min, but AMDIS did not confirm this assignment, nor could it be confirmed manually. Butylated hydroxyanisole was tentatively identified by AMDIS with a low match value, but the retention time is off by -7.7 seconds which is considerably more than most other hits. This compound is not in the NIST library so it could not be confirmed. The ChemStation method used for this analysis required that all three qualifier ions fall within $\pm 20\%$ (relative) which is a rigorous requirement for such a complex sample. This explains why so few compounds were found by the ChemStation.

Cyprodinil (20.563 min) was identified by AMDIS but the NIST library search failed to confirm its presence. The next line shows that the best NIST library match is an anthracene derivative that is nothing like cyprodinil. This result was obtained when AMDIS was configured to “use uncertain peaks” as shown in Figure 4. When this feature is

turned off in DRS Compound Identification Configuration, the best NIST library hit for this spectrum is, indeed, cyprodinil. When a compound's identity is ambiguous, as with cyprodinil, it may be useful to perform the DRS search both ways and compare the results.

In the comparison described earlier (3), DRS was able to identify all 37 pesticides found by the CDFA chemist. However, DRS completed the task for all 17 samples in about 20 minutes compared to ~8 hours for the manual procedure (Table 2). Moreover, DRS identified one false positive in the CDFA report and found 34 additional pesticides and related compounds.

Using the new 926-compound Database, it took 32 minutes to analyze all of the samples and DRS was able to find an additional 99 pesticides, metabolites, fire retardants, and related compounds (Table 2).




Figure 4. DRS configuration screen for the method called **Tri_Pest**. When the box labeled “Use Uncertain Peaks” is checked, AMDIS will use uncertain peaks for library searches. When unchecked, AMDIS ignores uncertain mass spectral peaks. Sometimes, this can affect the quality of a library match.

Table 2. Comparison of the Results Obtained by Screening 17 Surface Water Extracts Using Traditional Methods (CDFA) and Using DRS With Two Different Databases – the G1049A With 567 Compounds and the G1672AA With 926 Entries

	CDFA	Agilent DRS (Original G1049A database)	Agilent DRS (G1672 AA database)
Targets found (not counting ISTD)	37	Same 37 +34 more	Same 37 +99 more
False positives	1	0	0
Processing time	~8 hrs (ChemStation only)	20 minutes	32 min

Handling Stereoisomers

Many pesticides have multiple stereoisomers with virtually identical mass spectra. For example, cyfluthrin has four diastereomers arising from its three chiral centers. It is very difficult and sometimes impossible to determine the elution order of these isomers and most analysts report them as a sum of the isomer amounts. Agilent's G1049A RTL Pesticide database arbitrarily assigned each isomer a Roman numeral with I for the earliest eluting isomer, II for the next, and so on. The same Chemical Abstracts Service number (CAS #) was assigned to all of the isomers. Generally, it was a CAS # for the compound with "unstated stereochemistry." This caused some incompatibility with AMDIS as explained below.

AMDIS software differentiates among compounds using a "chemical identification number." The easiest and most consistent approach is to use each compound's CAS #. The default setting for AMDIS is to allow each CAS # to be used only once when analyzing a GC/MS data file. While this seems logical, it requires that each database entry have a different CAS #. It is possible to allow multiple hits per compound by checking the box in AMDIS found in the drop down menu under Analyze/Settings/Identif. However, this allows multiple peaks to be assigned the same compound name.

In the new RTL Pesticide Database (G1672AA), the Roman numeral designations remain and the first isomer in the series is given its genuine CAS #. Subsequent isomers in the series are given unique, but fictitious "CAS #s" generated by Agilent. The compound's real CAS # appears in braces after the compound name. For example, the cyfluthrin isomers are entered into the database as shown in Table 3.

Table 3. Method for Listing Compounds with Multiple Stereoisomers in the New G1672AA RTL Pesticide Database

RT	Compound name*	CAS #**
32.218	Cyfluthrin I	68359-37-5
32.359	Cyfluthrin II {CAS # 68359-37-5}	999028-03-4
32.477	Cyfluthrin III {CAS # 68359-37-5}	999029-03-7
32.536	Cyfluthrin IV {CAS # 68359-37-5}	999030-03-4

* In a series, the earliest eluting isomer is identified with "I" and is assigned its legitimate CAS #. Subsequent isomers are assigned unique, but fictitious CAS #s (see footnote **). Their actual CAS # is put in braces behind the compound name.

** Cyfluthrin I has been given its genuine CAS #. Cyfluthrin II-IV have been given unique numbers that can be distinguished from actual CAS numbers because they all have six digits before the first hyphen (9 total) and all begin with the series 999.

Figure 5 shows how permethrin was identified in a spinach sample using both databases with AMDIS configured to allow one hit per compound. Using the older 567-compound database (G1049A) only one permethrin isomer was identified because its CAS # could be used only once. With the new format used in the 926-compound RTL Pesticide Database (G1672AA), both isomers of permethrin were identified. Not surprisingly, the NIST library search found no hits with the same fictitious CAS # assigned to permethrin II. So, the software printed the best match on the following line. This compound, a cyclopropanecarboxylic acid derivative, is a permethrin isomer.

So long as the NIST library search is turned on in DRS, it will always print another line after reporting a compound with a fictitious CAS #. Note that these fictitious CAS #s always contain 9 digits and begin with 999.

A)

RT	Cas #	Compound name	Agilent	AMDIS match	RT Diff (sec.)	NIST	Hit number
			ChemStation amount (ng)			reverse match	
31.6158	52645531	Permethrin II		88	3.9	91	3

B)

RT	Cas #	Compound name	Agilent	AMDIS match	RT Diff (sec.)	NIST	Hit number
			ChemStation amount (ng)			reverse match	
31.4127	52645531	Permethrin I		78	2.6	81	3
31.6088	999046036	Permethrin II {CAS # 52645-53-1}		65	3.5		
31.6088	51877748	Cyclopropanecarboxylic acid, 3-(2,2-dichlorovinyl)-2,2-dimethyl-, (3-phenoxyphenyl)methyl ester, (1R-trans)-				95	1

Figure 5. A) A single isomer of permethrin was identified by DRS using the G1049A 567-compound database when AMDIS was not allowed to use multiple hits per compound. B) Two permethrin isomers are identified by DRS with the G1672AA 926-compound database under the same circumstances.

Conclusions

The new G1672AA RTL Pesticide and Endocrine Disruptor library contains substantially more target analytes than its predecessor. With the addition of 359 new compounds, it is the most comprehensive library of its type available today. Many new pesticides, metabolites, and endocrine disruptors were added along with important PCBs, PBBs, PAHs, synthetic musk compounds, Sudan dyes, and organophosphorus fire retardants. The database contains all of the analytes specified for GC/MS analysis in the new Japanese “Positive List” regulations.

When combined with the complete DRS solution, one can screen GC/MS data files for all 926 compounds in about two minutes per sample. This is the fastest, most comprehensive, most accurate, and least tedious method for screening food and environmental samples for these compounds.

References

1. V. Giarocco, B. Quimby, and M. Klee, “Retention Time Locking: Concepts and Applications,” Agilent Technologies, publication 5966-2469E, www.agilent.com/chem
2. H. Prest, P. Wylie, K. Weiner, and D. Agnew, “Efficient Screening for Pesticides and Endocrine Disruptors Using the 6890/5973 GC/MSD System,” Agilent Technologies, publication 5968-4884E, www.agilent.com/chem
3. P. L. Wylie, M. J. Szelewski, C.-K. Meng, C. P. Sandy, “Comprehensive Pesticide Screening by GC/MSD using Deconvolution Reporting Software,” Agilent Technologies, publication 5989-1157EN, www.agilent.com/chem
4. “Introduction of the Positive List System for Agricultural Chemical Residues in Foods Department of Food Safety, Ministry of Health, Labour and Welfare” <http://www.mhlw.go.jp/english/topics/food-safety/positivelist060228/introduction.html>
5. C. P. Sandy, “A Blind Study of Pesticide Residues in Spiked and Unspiked Fruit Extracts using Deconvolution Reporting Software,” Agilent Technologies, publication 5989-1564EN, www.agilent.com/chem
6. C. Lesueur and M. Gartner, “Routine Identification and Quantification of Pesticide Multi-residues in Fruit and Vegetable Samples with Full Scan, SIM, and Deconvolution Reporting Software,” 2005 *Ernährung/Nutrition*, **29** (11) 466–471
7. X. Ping, C.-K. Meng, and M. Szelewski, “Building Agilent GC/MSD Deconvolution Reporting Libraries for any Application,” Agilent Technologies, publication 5989-2249EN, www.agilent.com/chem
8. “Large-scale studies of the occurrence and distribution of new contaminants in the environment – Reconnaissance studies,” *USGS, Contaminant Occurrence Studies*, http://toxics.usgs.gov/topics/reconnaissance_studies.html

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Acknowledgments

The author wishes to thank Dr. G. Kempe of the Landesuntersuchungsanstalt Sachsen, Institut, Chemnitz, Germany for his help in acquiring much of the data for this library update. The author also thanks Dr. Mark Lee and Mr. Steve Siegel of the California Department of Food and Agriculture for providing the surface water extract data files.

Appendix A

Lists of Compounds in Databases

1,2,4-Trichlorobenzene	2,6-Dimethylaniline	Acetochlor
1,2-Dibromo-3-chloropropane	2-[3-Chlorophenoxy]propionamide	Acifluorfen methyl ester
1,3,5-Tribromobenzene	2-Chlorophenol	Aclonifen
1,3-Dichlorobenzene	2-Ethyl-1,3-hexanediol	Acrinathrin
17 α -Ethinylestradiol	2-ethyl-6-methylaniline	Alachlor
1-naphthalenol	2-Hydroxyestradiol	Aldrin
2-(1-naphthyl)acetamide	2-Methyl-4,6-dinitrophenol	Allidochlor
2-(2-Butoxyethoxy)ethyl thiocyanate	2-Methylphenol	Ametryn
2-(Octylthio)ethanol	2-Nitrophenol	Amidithion
2,3,4,5-Tetrachloronitrobenzene	2-Phenoxypropionic acid	Aminocarb
2,3,4,5-Tetrachlorophenol	3,4,5-Trimethacarb	Amitraz
2,3,4,6-Tetrachlorophenol	3,4-Dichloroaniline	Amitraz metabolite [Methanimidamide, N-(2,4-dimethylphenyl)-N'-methyl-]
2,3,5,6-Tetrachlorophenol	3,5-Dichloroaniline	Ancymidol
2,3,5,6-Tetrachloro-p-terphenyl	3-Aminophenol	Anilazine
2,3,5-Trichlorophenol	3-Chloro-4-fluoroaniline	Aniline
2,3,5-Trimethacarb	3-Chloro-4-methoxyaniline	Anilofos
2,3,6-Trichloroanisole	3-Chloroaniline	Anthracene
2,3,7,8-Tetrachlorodibenzofuran	3-Hydroxycarbofuran	Aramite I
2,3,7,8-Tetrachlorodibenzo-p-dioxin	3-Indolylacetoneitrile	Aramite II {CAS # 140-57-8}
2,4,5,6-Tetrachloro-m-xylene	3-Trifluormethylaniline	Atraton
2,4,5-T methyl ester	4,4'-Dichlorobenzophenone	Atrazine
2,4,5-Trichloroaniline	4,4'-Oxydianiline	Atrazine-desethyl
2,4,5-Trichlorophenol	4,6-Dinitro-o-cresol (DNOC)	Azaconazole
2,4,5-Trichloro-p-terphenyl	4-Aminodiphenyl	Azamethiphos
2,4,5-Trimethylaniline	4-Bromoaniline	Azibenzolar-S-methyl
2,4,6-Tribromoanisole	4-Chloro-2-methylaniline	Azinphos-ethyl
2,4,6-Tribromophenol	4-Chloro-3-methylphenol	Azinphos-methyl
2,4,6-Trichloroanisole	4-Chloroaniline	Aziprotryn metabolite [2-Amino-4-isopropylamino-6-methylthio-1,3,5-triazine]
2,4,6-Trichlorophenol	4-Chlorophenyl isocyanate	Aziprotryne
2,4-D methyl ester	4-Isopropylaniline	Azobenzene
2,4-D sec-butyl ester	4-Methylphenol	Azoxybenzene
2,4-DB methyl ester	4-Nitrophenol	Azoxystrobin
2,4'-Dichlorobenzophenone (2,4'-Dicofol decomposition product)	4-Nonylphenol	Barban
2,4-Dichlorophenol	5,7-Dihydroxy-4'-methoxyisoflavone	Beflubutamid
2,4-Dichlorophenyl benzenesulfonate	9,10-Anthraquinone	Benalaxyl
2,4-Dimethylaniline	Acenaphthene	Benazolin-ethyl
2,4-Dimethylphenol	Acenaphthylene	Bendiocarb
2,6-Dichlorobenzamide	Acephate	Benfluralin
2,6-Dichlorobenzonitrile	Acequinocyl	
	acetamiprid	

Benfuracarb	Bromophos-ethyl	Chlordimeform
Benfuresate	Bromopropylate	Chlorethoxyfos
Benodanil	Bromoxynil	Chlorfenapyr
Benoxacor	Bromoxynil octanoic acid ester	Chlorfenethol
Bentazone	Bromuconazole I	Chlorfenprop-methyl
Bentazone methyl derivative	Bromuconazole II {CAS # 116255-48-2}	Chlorfenson
Benthiocarb	Bufencarb	Chlorfenvinphos
Benzene, 1,3- <i>bis</i> (bromomethyl)-	Bupirimate	Chlorfenvinphos, <i>cis</i> -
Benzenesulfonamide	Buprofezin	Chlorfenvinphos, <i>trans</i> -
Benzidine	Butachlor	Chlorflurecol-methyl ester
Benzo(a)anthracene	Butafenacil	Chlormefos
Benzo(a)pyrene	Butamifos	Chlornitrofen
Benzo[b]fluoranthene	Butoxycarboxim	Chlorobenzilate
Benzo[g,h,i]perylene	Butralin	Chloroneb
Benzo[k]fluoranthene	Butyl benzyl phthalate	Chloropropylate
Benzophenone	Butylate	Chlorothalonil
Benzoximate metabolite	Butylated hydroxyanisole	Chlorotoluron
Benzoylprop ethyl	Cadusafos	Chlorpropham
Benzyl benzoate	Cafenstrole	Chlorpyrifos
b-Estradiol	Caffeine	Chlorpyrifos Methyl
BHC alpha isomer	Captafol	Chlorthal-dimethyl
BHC beta isomer	Captan	Chlorthiamid
BHC delta isomer	Carbaryl	Chlorthion
BHC epsilon isomer	Carbetamide	Chlorthiophos
Bifenazate metabolite (5-Phenyl-o-anisidine)	Carbofuran	Chlorthiophos sulfone
Bifenox	Carbofuran-3-keto	Chlorthiophos sulfoxide
Bifenthrin	Carbofuran-7-phenol	Chlozolate
Binapacryl	Carbophenothion	Chrysene
Bioallethrin	Carbosulfan	Cinerin I
Bioallethrin S-cyclopentenyl isomer	Carboxin	Cinerin II
Bioresmethrin	Carfentrazone-ethyl	Cinidon-ethyl
Biphenyl	Carpropamid	cis-Chlordane
<i>Bis</i> (2,3,3,3-tetrachloropropyl) ether	Carvone	Clodinafop-propargyl
<i>Bis</i> (2-butoxyethyl) phthalate	Cashmeran	Clomazone
<i>Bis</i> (2-ethylhexyl)phthalate	Cekafix	Cloquintocet-mexyl
Bisphenol A	Celestolide	Coumaphos
Bitertanol I	Chinomethionat	Crimidine
Bitertanol II {CAS # 55179-31-2}	Chloramben methyl ester	Crotoxyphos
Boscalid (Nicobifen)	Chloranocryl	Crufomate
Bromacil	Chlorbenside	Cyanazine
Bromfenvinphos-(E)	Chlorbenside sulfone	Cyanofenphos
Bromfenvinphos-(Z)	Chlorbicyclen	Cyanophos
Bromobutide	Chlorbromuron	Cyclafuramid
Bromocyclen	Chlorbufam	Cycloate
Bromophos	Chlordecone	Cyclopentadecanone
	Chlordene, <i>trans</i> -	Cycluron

Cyflufenamid	Dichlofluanid metabolite (DMSA)	Dinocap I
Cyfluthrin I	Dichlone	Dinocap II {CAS # 39300-45-3}
Cyfluthrin II {CAS # 68359-37-5}	Dichlormid	Dinocap III {CAS # 39300-45-3}
Cyfluthrin III {CAS # 68359-37-5}	Dichlorophen	Dinocap IV {CAS # 39300-45-3}
Cyfluthrin IV {CAS # 68359-37-5}	Dichlorprop	Di-n-octyl phthalate
Cyhalofop-butyl	Dichlorprop methyl ester	Dinoseb
Cyhalothrin I (lambda)	Dichlorvos	Dinoseb acetate
Cyhalothrin (Gamma)	Diclobutrazol	Dinoseb methyl ether
Cymiazole	Diclocymet I	Dinoterb
Cymoxanil	Diclocymet II {CAS # 139920-32-4}	Dinoterb acetate
Cypermethrin I	Diclofop methyl	Di-n-propyl phthalate
Cypermethrin II {CAS # 52315-07-8}	Dicloran	Diofenolan I
Cypermethrin III {CAS # 52315-07-8}	Dicrotophos	Diofenolan II {CAS # 63837-33-2}
Cypermethrin IV {CAS # 52315-07-8}	Dicyclohexyl phthalate	Dioxabenzofos
Cyphenothrin <i>cis</i> -	Dicyclopentadiene	Dioxacarb
Cyphenothrin <i>trans</i> - {CAS # 39515-40-7}	Dieldrin	Dioxathion
Cyprazine	Diethyl ethyl	Diphacinone
Cyproconazole	Diethofencarb	Diphenamid
Cyprodinil	Diethyl dithiobis(thionoformate) (EXD)	Diphenyl phthalate
Cyprofuram	Diethyl phthalate	Diphenylamine
Cyromazine	Diethylene glycol	Dipropetryn
d-(<i>cis-trans</i>)-Phenothrin-I	Diethylstilbestrol	Dipropyl isocinchomeronate
d-(<i>cis-trans</i>)-Phenothrin-II {CAS # 260002-80-2}	Difenoconazol I	Disulfoton
Dazomet	Difenoconazol II {CAS # 119446-68-3}	Disulfoton sulfone
DDMU [1-Chloro-2,2-bis(4'-chlorophenyl)]	Difenoxuron	Ditalimfos
Decachlorobiphenyl	Diflufenican	Dithiopyr
Deltamethrin	Diisobutyl phthalate	Diuron
Demephion	Dimefox	Diuron Metabolite [3,4-Dichlorophenyl isocyanate]
Demeton-S	Dimepiperate	Dodemorph I
Demeton-S-methylsulfon	Dimethachlor	Dodemorph II {CAS # 1593-77-7}
Desbromo-bromobutide	Dimethametryn	Drazoxolon
Desmedipham	Dimethenamid	Edifenphos
Desmetryn	Dimethipin	Empenthrin I
Dialifos	Dimethoate	Empenthrin II {CAS # 54406-48-3}
Di-allate I	Dimethomorph-(E)	Empenthrin III {CAS # 54406-48-3}
Di-allate II {CAS # 2303-16-4}	Dimethomorph-(Z) {CAS # 110488-70-5}	Empenthrin IV {CAS # 54406-48-3}
Diamyl phthalate	Dimethylphthalate	Empenthrin V {CAS # 54406-48-3}
Diazinon	Dimethylvinphos(z)	Endosulfan (alpha isomer)
Diazinon-oxon	Dimetilan	Endosulfan (beta isomer)
Dibenz[a,h]anthracene	Dimoxystrobin	Endosulfan ether
Dicamba	Di-n-butylphthalate	Endosulfan lactone
Dicamba methyl ester	Di-n-hexyl phthalate	Endosulfan sulfate
Dicapthon	Diniconazole	Endrin
Dichlofenthion	Dinitramine	Endrin aldehyde
Dichlofluanid	Di-n-nonyl phthalate	Endrin ketone
	Dinobuton	

EPN	Fenoprop methyl ester	Fluoxastrobin <i>cis</i> -
Epoxiconazole	Fenothiocarb	Fluquinconazole
EPTC	Fenoxanil	Flurenol-butyl ester
Erbon	Fenoxaprop-ethyl	Flurenol-methylester
Esfenvalerate	Fenoxycarb	Fluridone
Esprocarb	Fenpiclonil	Flurochloridone I
Etaconazole	Fenpropathrin	Flurochloridone II {CAS # 61213-25-0}
Ethalfuralin	Fenpropidin	Flurochloridone, deschloro-
Ethidimuron	Fenson	Fluroxypyr-1-methylheptyl ester
Ethiofencarb	Fensulfothion	Flurprimidol
Ethiolate	Fensulfothion-oxon	Flurtamone
Ethion	Fensulfothion-oxon -sulfone	Flusilazole
Ethofenprox	fensulfothion-sulfone	Fluthiacet-methyl
Ethofumesate	Fenthion	Flutolanil
Ethofumesate, 2-Keto	Fenthion sulfoxide	Flutriafol
Ethoprophos	Fenthion-sulfone	Fluvalinate-tau-I
Ethoxyfen-ethyl	Fenuron	Fluvalinate-tau-II {CAS # 102851-06-9}
Ethoxyquin	Fenvalerate I	Folpet
Ethylenethiourea	Fenvalerate II {CAS # 51630-58-1}	Fonofos
Etoxazole	Fepropimorph	Formothion
Etridiazole	Fipronil	Fosthiazate I
Etridiazole, deschloro- (5-ethoxy-3-dichloromethyl-1,2,4-thiadiazole)	Fipronil, desulfinyl-	Fosthiazate II {CAS # 98886-44-3}
Etrimfos	Fipronil-sulfide	Fuberidazole
Eugenol	Fipronil-sulfone	Furalaxyl
Exaltolide [15-Pentadecanolide]	Flamprop-isopropyl	Furathiocarb
Famoxadon	Flamprop-methyl	Furilazole
Famphur	Fluacrypyrim	Furmecyclox
Fenamidone	Fluazifop-p-butyl	Halfenprox
Fenamiphos sulfoxide	Fluazinam	Haloxypop-methyl
Fenamiphos-sulfone	Fluazolate	Heptachlor
Fenarimol	Flubenzimine	Heptachlor epoxide isomer A
Fenazaflor	Fluchloralin	Heptachlor exo-epoxide isomer B
Fenazaflor metabolite	Flucythrinate I	Heptenophos
Fenazaquin	Flucythrinate II {CAS # 70124-77-5}	Hexabromobenzene
Fenbuconazole	Fludioxonil	Hexachlorobenzene
Fenchlorazole-ethyl	Flufenacet	Hexachlorophene
Fenchlorphos	Flumetralin	Hexaconazole
Fenchlorphos-oxon	Flumiclorac-pentyl	Hexazinone
Fencloirim	Flumioxazin	Hexestrol
Fenfuram	Fluometuron	Hydroprene
Fenhexamid	Fluoranthene	Imazalil
Fenitrothion	Fluorene	Imazamethabenz-methyl I
Fenitrothion-oxon	Fluorodifen	Imazamethabenz-methyl II {CAS # 81405-85-8}
Fenobucarb	Fluoroglycofen-ethyl	Imibenconazole
Fenoprop	Fluoroimide	Imibenconazole-desbenzyl
	Fluotrimazole	

Indeno[1,2,3-cd]pyrene	Mecoprop methyl ester	Monocrotophos
Indoxacarb and Dioxacarb decomposition product [Phenol, 2-(1,3-dioxolan-2-yl)-]	Mefenacet	Monolinuron
Ioxynil	Mefenpyr-diethyl	Musk amberette
Ioxynil octanoate	Mefluidide	Musk Ketone
Ipconazole	Menazon	Musk Moskene
Iprobenfos	Mepanipirim	Musk Tibetene (Moschustibeten)
Iprodione	Mephosfolan	Musk xylene
Iprovalicarb I	Mepronil	Myclobutanil
Iprovalicarb II {CAS # 140923-25-7}	Metalaxyl	N,N-Diethyl-m-toluamide
Irgarol	Metamitron	N-1-Naphthylacetamide
Isazophos	Metasystox thiol	Naled
Isobenzan	Metazachlor	Naphthalene
Isobornyl thiocynoacetate	Metconazole I	Naphthalic anhydride
Isocarbamide	Metconazole II {CAS # 125116-23-6}	Naproanilide
Isocarbophos	Methabenzthiazuron [decomposition product]	Napropamide
Isodrin	Methacrifos	Nicotine
Isufenphos	Methamidophos	Nitralin
Isufenphos-oxon	Methfuroxam	Nitrapyrin
Isomethiozin	Methidathion	Nitrofen
Isoprocarb	Methiocarb	Nitrothal-isopropyl
Isopropalin	Methiocarb sulfone	N-Methyl-N-1-naphthyl acetamide
Isoprothiolane	Methiocarb sulfoxide	Nonachlor, <i>cis</i> -
Isoproturon	Methomyl	Nonachlor, <i>trans</i> -
Isoxaben	Methoprene I	Norflurazon
Isxadifen-ethyl	Methoprene II {CAS # 40596-69-8}	Norflurazon, desmethyl-
Isxaflutole	Methoprotryne	Nuarimol
Isoxathion	Methoxychlor	o,p'-DDD
Jasmolin I	Methoxychlor olefin	o,p'-DDE
Jasmolin II	Methyl (2-naphthoxy)acetate	o,p'-DDT
Jodfenphos	Methyl paraoxon	Octachlorostyrene
Kinoprene	Methyl parathion	o-Dianisidine
Kresoxim-methyl	Methyl-1-naphthalene acetate	o-Dichlorobenzene
Lactofen	Methyldymron	Ofurace
Lenacil	Metobromuron	Omethoate
Leptophos	Metolachlor	o-Phenylphenol
Leptophos oxon	Metolcarb	Orbencarb
Lindane	Metominostrobin (E)	<i>ortho</i> -Aminoazotoluene
Linuron	Metominostrobin (Z) {CAS # 133408-50-1}	Oryzalin
Malathion	Metrafenone	Oxabetrinil
Malathion-o-analog	Metribuzin	Oxadiazon
MCPA methyl ester	Mevinphos	Oxadixyl
MCPA-butoxyethyl ester	Mirex	Oxamyl
MCPB methyl ester	Molinate	Oxycarboxin
m-Cresol	Monalide	Oxychlordane
Mecarbam		Oxydemeton-methyl
		Oxyfluorfen

p,p'-DDD	Phenanthrene	Promecarb
p,p'-DDE	Phenanthrene-d10	Promecarb artifact [5-isopropyl-3-methylphenol]
p,p'-DDM [<i>bis</i> (4-chlorophenyl)methane]	Phenakpton	Prometon
p,p'-DDT	Phenol	Prometryn
p,p'-Dibromobenzophenone	Phenothiazine	Propachlor
p,p'-Dicofol	Phenothrin I	Propamocarb
Paclobutrazol	Phenothrin II	Propanil
Paraoxon	Phenoxyacetic acid	Propaphos
Parathion	Phenthoate	Propargite
PBB 52 Tetrabrombiphenyl	Phorate	Propargite metabolite [Cyclohexanol, 2-(4-tert-butylphenoxy)]
PBB 101	Phorate sulfone	Propazine
PBB 15	Phorate sulfoxide	Propetamphos
PBB 169 Hexabrombiphenyl	Phorate-oxon	Propham
PCB 101	Phosalone	Propiconazole-I
PCB 105	Phosfolan	Propiconazole-II {CAS # 60207-90-1}
PCB 110	Phosmet	Propisochlor
PCB 118	Phosphamidon I	Propoxur
PCB 126	Phosphamidon II {CAS # 13171-21-6}	Propyzamide
PCB 127	Phthalide	Prosulfocarb
PCB 131	Phthalimide	Prothioconazole-desthio
PCB 136	Picloram methyl ester	Prothiofos
PCB 138	Picolinafen	Prothoate
PCB 153	Picoxystrobin	Pyracarbolid
PCB 169	Pindone	Pyraclofos
PCB 170	Piperalin	Pyraflufen-ethyl
PCB 180	Piperonyl butoxide	Pyrazon
PCB 30	Piperophos	Pyrazophos
PCB 31	Pirimicarb	Pyrazoxyfen
PCB 49	Pirimiphos-ethyl	Pyrene
PCB 77	Pirimiphos-methyl	Pyrethrin I
PCB 81	Plifenat	Pyrethrin II
p-Dichlorobenzene	p-Nitrotoluene	Pyributicarb
Pebulate	Potasan	Pyridaben
Penconazole	Prallethrin, <i>cis</i> -	Pyridaphenthion
Pendimethalin	Prallethrin, <i>trans</i> - {CAS # 23031-36-9}	Pyridate
Pentachloroaniline	Pretilachlor	Pyridinitril
Pentachloroanisole	Probenazole	PyrifenoX I
Pentachlorobenzene	Prochloraz	PyrifenoX II {CAS # 88283-41-4}
Pentachloronitrobenzene	Procymidone	Pyriftalid
Pentachlorophenol	Prodiamine	Pyrimethanil
Pentanochlor	Profenofos	Pyrimidifen
Permethrin I	Profenofos metabolite (4-Bromo-2-chlorophenol)	Pyriminobac-methyl (E)
Permethrin II {CAS # 52645-53-1}	Profluralin	Pyriminobac-methyl (Z) {CAS # 136191-64-5}
Perthane	Prohydrojasmon I	
Phantolide	Prohydrojasmon II {CAS # 158474-72-7}	
Phenamiphos		

Pyriproxyfen	Tecnazene	Triadimenol
Pyroquilon	Tefluthrin, <i>cis</i> -	Tri-allate
Quinalphos	Temephos	Triamiphos
Quinoclamine	Terbacil	Triapenthenol
Quinoxifen	Terbucarb	Triazamate
Quintozene metabolite (pentachlorophenyl methyl sulfide)	Terbufos	Triazophos
Quizalofop-ethyl	Terbufos-oxon-sulfone	Tributyl phosphate
Rabenzazole	Terbufos-sulfone	Tributyl phosphorotrithioite
Resmethrin	Terbumeton	Trichlamide
Resmethrine I	Terbuthylazine	Trichlorfon
Resmethrine II {CAS # 10453-86-8}	Terbuthylazine-desethyl	Trichloronate
Rotenone	Terbutryne	Triclopyr methyl ester
S,S,S-Tributylphosphorotrithioate	Tetrachlorvinphos	Triclosan
Schradan	Tetraconazole	Triclosan-methyl
Sebuthylazine	Tetradifon	Tricresylphosphate, <i>meta</i> -
Sebuthylazine-desethyl	Tetraethylpyrophosphate (TEPP)	Tricresylphosphate, <i>ortho</i> -
Secbumeton	Tetrahydrophthalimide, <i>cis</i> -1,2,3,6-	Tricresylphosphate, <i>para</i>
Silafluofen	Tetramethrin I	Tricyclazole
Silthiopham	Tetramethrin II {CAS # 7696-12-0}	Tridemorph, 4-tridecyl-
Simazine	Tetrapropyl thiodiphosphate	Tridiphane
Simeconazole	Tetrasul	Trietazine
Simetryn	Thenylchlor	Triethylphosphate
Spirodiclofen	Theobromine	Trifenmorph
Spiromesifen	Thiabendazole	Trifloxystrobin
Spiroxamine I	Thiazopyr	Triflumizole
Spiroxamine II {CAS # 118134-30-8}	Thifluzamide	Trifluralin
Spiroxamine metabolite (4-tert-butylcyclohexanone)	Thiofanox	Triphenyl phosphate
Sudan I	Thiometon	Tris(2-butoxyethyl) phosphate
Sudan II	Thionazin	Tris(2-chloroethyl) phosphate
Sudan Red	Thymol	Tris(2-ethylhexyl) phosphate
Sulfallate	Tiocarbazil I	Triticonazole
Sulfanilamide	Tiocarbazil II {CAS # 36756-79-3}	Tryclopyrbutoxyethyl
Sulfentrazone	Tolclofos-methyl	Tycor (SMY 1500)
Sulfotep	Tolfenpyrad	Uniconazole-P
Sulfur (S8)	Tolyfluanid	Vamidothion
Sulprofos	Tolyfluanid metabolite (DMST)	Vernolate
Swep	Tolyltriazole [1H-Benzotriazole, 4-methyl-]	Vinclozolin
Tamoxifen	Tolyltriazole [1H-Benzotriazole, 5-methyl-]	XMC (3,4-Dimethylphenyl N-methylcarbama
TCMTB	Tonalide	XMC (3,5-Dimethylphenyl N-methylcarbama
Tebuconazole	Toxaphene Parlar 26	Zoxamide
Tebufenpyrad	Toxaphene Parlar 50	Zoxamide decomposition product
Tebupirimifos	Toxaphene Parlar 62	
Tebutam	<i>trans</i> -Chlordane	
Tebuthiuron	Transfluthrin	
	Traseolide	
	Triadimefon	

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
April 18, 2006
5989-5076EN



Agilent Technologies



Identifying Pesticides with Full Scan, SIM, μ ECD, and FPD from a Single Injection Application

Food Safety, Environmental

Authors

Chin-Kai Meng and Bruce Quimby
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

In this application note, a gas chromatography/mass spectrometry (GC/MS) system capable of providing up to four signals from a single injection is described. When a three-way micro-fluidic splitter is added to the end of the column, two additional signals from GC detectors can be acquired together with the MS data from a single injection. This multi-signal configuration provides: full-scan data for library searching, selective ion monitoring (SIM) data for trace analysis, micro-electron capture detector and flame photometric detector data for excellent selectivity and sensitivity from complex matrices. A combination of element selective detectors, SIM/Scan, and deconvolution reporting software makes a very powerful pesticide analysis system. Examples for trace-level compound quantitation/confirmation or for screening are discussed.

Introduction

Many laboratories in the world are analyzing pesticide residue levels in both foods and the environment to protect human health. The process usually involves homogenizing the sample, extracting the pesticides, and analyzing the target compounds with a Gas Chromatograph (GC) or a Liquid

Chromatograph (LC) depending on the nature of the compounds. For GC amenable compounds, the traditional detectors are NPD (Nitrogen Phosphorus Detector), μ ECD (micro-Electron Capture Detector), and FPD (Flame Photometric Detector) for their excellent sensitivity and selectivity. However, even with dual-column confirmation analysis, these GC detectors cannot be used to verify the identity of the compounds with high confidence.

Full scan mass spectral data and library searching are typically used for final compound verification. However, full-scan analysis has a worse (higher) detection limit (DL) compared to selective detectors on a GC. To improve the DL, the technique selective ion monitoring (SIM) is often used. With SIM, the MS monitors only a few characteristic ions for each target compound within the retention time (RT) range that the target elutes from the column. By monitoring only a few specific ions, the signal-to-noise ratio (S/N) improves significantly. The ions monitored are time programmed in groups corresponding to the RTs of the targets. SIM analyses with closely eluting targets require precise alignment of chromatographic RTs with the time programming of SIM groups. The Retention Time Locking (RTL) technique can be applied to eliminate the need to adjust SIM group time-windows after column maintenance or replacement.

In this application note, a GC/MS system capable of providing up to four signals from a single injection is described. The benefits of the multi-signal detection include:

- Confirmatory information – Full-scan data for library search capability




Agilent Technologies

- Maximum sensitivity – SIM data enables trace analysis
- Excellent selectivity – μ ECD and FPD detect trace-level hetero-compounds from complex matrices

Experimental

A recent technical note describes “Synchronous SIM/Scan”, which takes advantages of the Performance Electronics in the 5975 inert MSD to get both SIM and full-scan signals in a single run without sacrificing performance [1]. The SIM method can be easily developed automatically using the ChemStation’s AutoSIM tool [2]. By simply selecting a checkbox in the method, the SIM and full-scan data can be acquired together. The trade-off is giving up some cycles per second but gaining an additional signal (full-scan data or SIM data) for the whole analysis. With properly chosen acquisition parameters, for example, increasing the scan speed, the decrease of cycles per second is usually not significant and does not affect peak quantitation or the quality of results (for example, S/N).



At the end of the column, effluent flow is split three ways according to the length and diameter of the capillary tubing (restrictor) used.

Figure 1. A schematic of the multi-signal configuration.
Note: the EPC flow adds to the column flow into the splitter.

Besides the SIM/Scan data, the ChemStation software can simultaneously acquire up to two additional GC detector signals, for example, FPD (in phosphorus- or sulfur- mode) and NPD (nitrogen-phosphorus detector) signals or both P- and S- signals from a dual-wavelength FPD (DFPD). See Figure 1.

Figure 1 is a schematic for multi-signal detection. At the end of the column, a three-way micro-fluidic splitter was used to split the column effluent to different detectors [3]. For this study, an FPD and a μ ECD were installed. Notice on the figure that an Auxiliary Electronic Pneumatics Control (Aux EPC) gas channel was connected to the splitter to maintain the pressure at the end of the column so that the split ratios/flows are kept constant throughout a run. Figure 2 shows a close-up view of the micro-fluidic splitter installed in the GC oven.




Figure 2. A close-up view of the micro-fluidic three-way splitter in the 6890 GC oven.

The size of the micro-fluidic plate is 1.25 inches (3.2 cm) wide and 2.5 inches (6.4 cm) tall. The device was designed to eliminate the common problems of large thermal mass, excess dead volume, and leaky connection due to oven temperature cycling etc. The splitter's flow paths and connection points are laid out and etched onto a thin, stainless steel plate using photolithography and chem-milling technologies. The plate is diffusion bonded, mounted with column connectors, and surface deactivated, resulting in an integrated and compact micro-fluidic splitter. Metal ferrules are used at the connectors that are leak-free after temperature cycling and will not absorb solvents or sample matrix, improving sensitivity for trace analysis applications.

Deactivated capillary tubing between the splitter and each detector was used as a flow restrictor. Aux EPC pressure and the restrictor dimensions were determined using a spreadsheet-like calculator program to achieve the proper split ratio among all detectors. The three-way splitter can easily turn into a two-way splitter when a connector is capped.

Other advantages of a splitter include back-flushing [3] and quick-swapping. The Aux EPC flow can be run-time programmed to a higher pressure, while at the same time the inlet pressure is lowered to near ambient. This causes the column flow to reverse direction, back-flushing the less volatile materials out of the split vent of the inlet. The Aux EPC on the splitter also allows column changing and inlet maintenance without cooling and venting the MSD. The splitter's flow paths and connection points were designed in such a way

that when the column fitting is removed, the helium gas from the Aux EPC purges the fitting, preventing air from entering the splitter/MSD. See Table 1 for hardware details and settings.

Table 1. Gas Chromatograph, Mass Spectrometer, and Three-Way Splitter Operating Parameters

GC	Agilent Technologies 6890		
Inlet	EPC Split/Splitless		
Mode	Splitless, 1.0 µL injected (7683 ALS)		
Inlet temp	280 °C		
Pressure	~27 psi (chlorpyrifos methyl RT locked to 16.596 min)		
Purge flow	50.0 mL/min		
Purge time	0.75 min		
Total flow	55.3 mL/min		
Gas saver	Off		
Gas type	Helium		
Inlet liner	Siltek Cyclosplitter, 4-mm id, Restek p/n 20706-214.1		
Oven			
Oven ramp	°C/min	Final (°C)	Hold (min)
Initial		70	2.00
Ramp 1	25	150	0.00
Ramp 2	3	200	0.00
Ramp 3	8	280	15
Total run time	46.87 min (last standard elutes around 35 min)		
Equilibration time	0.5 min		
Oven max temp	325 °C		
Column	Agilent Technologies HP 5-ms, p/n 19091S-433		
Length	30.0 m		
Diameter	0.25 mm		
Film thickness	0.25 µm		
Mode	Constant pressure		
Nominal initial flow	2.5 mL/min		
Outlet	Unspecified		
Outlet pressure	3.8 psi (Aux EPC pressure to splitter)		
Front detector (FPD)			
Phosphorus mode			
Hydrogen flow:	75.0 mL/min	Sulfur mode	Hydrogen flow: 50.0 mL/min
Oxidizer flow:	100.0 mL/min	Oxidizer flow:	60.0 mL/min
Temperature:	250 °C		
Oxidizer gas type:	Air		
Mode:	Constant makeup flow		
Makeup flow:	60.0 mL/min		
Makeup gas type:	Nitrogen		
Lit offset:	2.00		
Data rate:	5 Hz		

Table 1. Gas Chromatograph, Mass Spectrometer, and Three-Way Splitter Operating Parameters (Continued)**Back detector (μECD)**

Temperature:	300 °C
Mode:	Constant makeup flow
Makeup flow:	60.0 mL/min
Makeup gas type:	Nitrogen
Date rate:	5 Hz

Thermal AUX 2

Use:	MSD Transfer line heater
Initial temp:	280 °C

Pressure AUX 5

Gas type:	Helium
Initial pressure:	3.80 psi
Initial time:	0.00 min (this value will follow oven ramp)

MSD Agilent Technologies 5975 inert MSD

Tune file	Atune.U
Mode	Scan
Solvent delay	3.00 min
EM voltage	Atune voltage
Low mass	45 amu
High mass	555 amu
Threshold	100
Sampling	2
A/D Samples	4
Scans/s	2.89
Quad temp	150 °C
Source temp	230 °C

Three-way splitter Agilent 6890N Option 890, when installed on the GC during factory assembly

Split ratio	10:10:1 MSD:FPD:μECD
MSD restrictor	1.444 m × 0.18-mm id Deactivated fused silica tubing
FPD restrictor	0.532 m × 0.18-mm id Deactivated fused silica tubing
μECD restrictor	0.507 m × 0.10-mm id Deactivated fused silica tubing
Flow to MSD (at 280 °C)	1.53 mL/min
Flow to FPD (at 280 °C)	1.53 mL/min
Flow to μECD (at 280 °C)	0.153 mL/min
Makeup flow (at 280 °C)	1.38 mL/min

Software Used in this Application Note

GC/MSD ChemStation	G1701DA
Deconvolution Reporting Software (DRS)	G1716AA
NIST Library	G1033A
AMDIS (included for free with the NIST library CD)	

Results and Discussion

Figure 3 shows four signals that were simultaneously acquired from a single injection of a pesticide mixture. Due to the high sensitivity of the μ ECD, the split ratios for the three detectors was set to MSD:FPD: μ ECD = 10:10:1. This split ratio distributes the sample of a 1- μ L splitless injection of a 1-ppm (1000 pg/ μ L) sample to the different detectors as labeled in Figure 3.




Figure 3. Signals acquired simultaneously from a 1- μ L splitless injection of 1-ppm standard. The split ratios were MSD:FPD: μ ECD = 10:10:1.

Figure 4 shows the signals when the pesticide standard was diluted 100-fold in a produce matrix. The total ion chromatogram (TIC) from full scan was not shown due to the lack of sensitivity. The FPD(P) and μ ECD were able to detect all the pesticides spiked in this extract. For trace-level target compound analysis, the SIM signal can be used for quantitation and the GC signals used for further confirmation.




Figure 4. Data of a produce extract spiked at 10 ppb. FPD and μ ECD were able to detect the respective standards spiked into the extract.

Another application for this multi-signal system is for screening. In screening, no target list is available for the analysis; therefore, SIM acquisition or MS/MS is not possible. Figure 5 shows three signals (no SIM) from a produce extract.




Figure 5. Full-scan, FPD(P), and μ ECD data for extract 13-10927.

The Deconvolution Reporting Software (DRS) [3, 4] found several pesticides in the TIC as shown in Figure 6.

MSD Deconvolution Report
Sample Name: 13-10927
Data File: C:\MSDCHEM\1\DATA\051905-spike-4sig\13-10927-2^2.40ms-Q.D
Date/Time: 09:06:39 AM Wednesday, May 25 2005

The NIST library was searched for the components that were found in the AMDIS target library.

R.T.	Cas #	Compound Name	Agilent ChemStation Amount (ng)	AMDIS Match	R.T. Diff sec.	NIST Reverse Match	Hit Num.
8.7747	90437	o-Phenylphenol		81	-0.1	84	2
9.962	84662	Diethyl phthalate	0.09	85	0.9	82	1
10.3407	114261	Propoxur		80	-0.7		
10.3407	6280962	Phenol, 2-propoxy-				88	1
10.6840	119619	Benzophenone		61	1.0	64	2
16.6138	5598130	Chlorpyrifos Methyl		71	0.3	70	2
18.4548	84742	Di-n-butylphthalate		88	1.6	92	1
21.0934	148798	Thiabendazole		79	8.8	80	2
24.6063	41394052	Metamitron		62	9.5		
24.6063	2009247	7H-Furo[3,2-g][1]benzopyran-7-one, 9-hydroxy-				86	1

Done My Computer

Figure 6. Report for extract 13-10927 generated from DRS.

The possible pesticides in the sample were benzophenone, chlorpyrifos methyl, and thiabendazole. Propoxur and metamitron were not confirmed by both AMDIS and NIST; therefore, they were most likely false positives.

Due to the complexity of the sample matrix and other interferences, it is sometimes difficult to get a high library match factor from peaks in the TIC, even after background subtraction. Therefore, element selective detectors would be very useful in providing the supporting information for compound confirmation. The multi-signal system was retention time locked, therefore, from the RT and the aligned peaks from the FPD(P) and the μ ECD responses, chlorpyrifos methyl ($C_7H_7Cl_3NO_3PS$) was confirmed.

It usually takes less than 3 minutes to turn off the FPD photomultiplier, swap the P-filter with the S-filter, and turn the photomultiplier back on. After the swap, adjust the detector gas flows to optimize the response in either P- or S- mode. A new injection of the same extract was made in FPD(S) mode. The FPD(S) result is shown with previously acquired signals in Figure 7. Two major peaks were seen on the FPD(S) chromatogram. From the peak RTs, they supported the presence of chlorpyrifos methyl and thiabendazole ($C_{10}H_7N_3S$) respectively. Note that the full-scan TIC barely showed a peak for either compound, which made it impossible for traditional data analysis to identify both compounds. The FPD(S) mode is very selective, but it is not as sensitive as the FPD(P) mode. Although the μ ECD is very sensitive, it is not as selective as the FPD. A combination of GC detectors, SIM/Scan, and DRS makes a very powerful pesticide analysis system.

Conclusion

The Synchronous SIM/Scan provides users with library searchable full-scan spectra as well as trace level SIM data in a single analysis. When a three-way micro-fluidic splitter is added to the end of the column, two additional signals from element selective detectors can be acquired together with the MS data from a single injection. This configuration makes it very attractive for the analysis of trace-level pesticide residues in foods or environmental samples.

This multi-signal configuration provides: full-scan data for library searching, SIM data for trace analysis, μ ECD and FPD data for excellent selectivity and sensitivity from complex matrices. In this application note, examples of μ ECD signal and FPD signal (P- or S- mode) were acquired together with the SIM/Scan data from a single injection for trace-level compound quantitation/confirmation, or for screening.




Figure 7. Full-scan, FPD(S), and FPD(P) data for extract 13-10927.

References

1. Chin-Kai Meng, "Improving Productivity with Synchronous SIM/Scan", Agilent Technologies, publication 5989-3108, www.agilent.com/chem
2. Harry Prest and David W. Peterson, "New Approaches to the Development of GC/MS Selected Ion Monitoring Acquisition and Quantitation Methods", Agilent Technologies, publication 5988-4188, www.agilent.com/chem
3. Michael J. Szelewski and Bruce Quimby, "New Tools for Rapid Pesticide Analysis in High Matrix Samples" Agilent Technologies, publication 5989-1716, www.agilent.com/chem
4. Philip L. Wylie, Michael J. Szelewski, Chin-Kai Meng, and Christopher P. Sandy, "Comprehensive Pesticide Screening by GC/MSD Using Deconvolution Reporting Software" Agilent Technologies, publication 5989-1157, www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
July 6, 2005
5989-3299EN



Agilent Technologies



Comprehensive Pesticide Screening by GC/MSD using Deconvolution Reporting Software Application

Food Safety

Author

Philip L. Wylie, Michael J. Szelewski, and Chin-Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Christopher P. Sandy
Agilent Technologies, Inc.
Block A, CSC Eskdale Road
Winnersh Triangle Estate
Wokingham, Berk RG41 5DZ
United Kingdom

Introduction

According to The Pesticide Manual, more than 700 pesticides are currently approved for use around the world [1]. About 600 more were used in the past, but are either banned or no longer marketed. In spite of their discontinuance, some of these still persist in the environment where they may bioaccumulate in the flora and fauna. Many pesticides or their degradation products can be found at trace levels in food and beverages; in soil, water, and air; in aquatic and terrestrial flora and fauna; and in human blood, adipose tissue, and breast milk. The World Health Organization has classified pesticides into five groups based upon their acute toxicity to humans [2]. The categories range from “Acutely Hazardous” to those that are “Unlikely to Present Acute Hazard in Normal Use.” Certain pesticides are classified as persistent organic pollutants (POPs), carcinogens, teratogens, or endocrine disrupters. It is now common to analyze for

pesticides in food and environmental samples to track their distribution in the environment and to ensure a safe food supply.

Current analytical methods target only a subset of the possible compounds. Whether for food or environmental samples, analyses are often complicated by the presence of co-extracted natural products. Food or tissue extracts can be exceedingly complex matrices that require several stages of sample cleanup prior to analysis [3]. Even then, it can be difficult to detect trace levels of contaminants in the presence of the remaining matrix.

For efficiency, multiresidue methods (MRMs) must be used to analyze for most pesticides. Traditionally, these methods have relied upon gas chromatography (GC) with a constellation of element-selective detectors to locate pesticides in the midst of a variable matrix [4, 5, 6]. GC with mass spectral detection (GC/MS) has been widely used for confirmation of hits. Liquid chromatography (LC) has been used for those compounds that are not amenable to GC [2]. Today, more and more pesticide laboratories are relying upon LC with mass spectral detection (LC/MS) and GC/MS as their primary analytical tools [7, 8]. Still, most MRMs are target compound methods that look for a small subset of the possible pesticides. Any compound not on the target list is likely to be missed by these MRMs.

Using the techniques of retention time locking (RTL) [9, 10, 11] and spectral deconvolution [12], a method has been developed to screen for 567 pesticides and suspected endocrine disrupters in a single GC/MS analysis. Spectral deconvolution



Agilent Technologies

helps to identify pesticides even when they are buried under co-eluting matrix compounds. RTL helps to eliminate false positives and gives greater confidence in the results. Users can easily add compounds to the method if they wish.

Experimental

Table 1 lists the instrumentation, software, and analytical parameters used by Agilent for pesticide analysis. Depending upon the desired injection volume, a PTV inlet or split/splitless inlet can be used.

Samples

Vegetable extracts were obtained from Dr. Mark Lee and Stephen Siegel at The California Department of Food and Agriculture (CDFA; Sacramento, CA USA) and from Dr. J.G.J. Mol at TNO Nutrition and Food Research (Zeist, The Netherlands). Seventeen data files from the GC/MS analysis of surface water samples were also contributed by CDFA and were processed in this laboratory using the Deconvolution Reporting Software (DRS). GC/MS data files (locked to the Agilent Pesticide Method) for 17 crop extracts were supplied by NRM Laboratories, Berkshire, UK.

Table 1. Instrumentation and Conditions of Analysis

Gas chromatograph	Agilent 6890N
Automatic sampler	Agilent 7683
Inlet	Agilent PTV operated in the solvent vent mode
Column	Agilent 30 m × 0.25 mm × 0.25 µm HP-5MS (p/n 19091S-433)
Carrier gas	Helium in the constant pressure mode
RTL	Chlorpyrifos-methyl locked to 16.596 min (nominal column head pressure = 17.1 psi)
Oven temperature program	70 °C (2 min), 25 °C/min to 150 °C (0 min), 3 °C /min to 200 °C (0 min), 8 °C /min to 280 °C (10–15 min)
PTV inlet parameters	Temp program: 40 °C (0.25 min), 1600 °C/min to 250 °C (2 min); Vent time: 0.2 min; Vent flow: 200 mL/min; Vent pressure: 0.0 psi; Purge flow: 60.0 mL/min; Purge time: 2.00 min
Injection volume	15 µL (using a 50-µL syringe)
Mass Selective Detector (MSD)	Agilent 5973 inert
Scan range	50–550 amu
Source, quad, transfer line temperatures	230, 150, and 280 °C, respectively
Solvent delay	4.00 min
Multiplier voltage	Autotune voltage
Software	
GC/MSD ChemStation	Agilent p/n G1701DA (Version D01.00 sp1)
Deconvolution Reporting Software (DRS)	Agilent p/n G1716AA
Library searching software	NIST MS Search (version 2.0) (included with NIST '02 mass spectral library, Agilent p/n G1033A)
Deconvolution software	Automated Mass Spectral Deconvolution and Identification Software (AMDIS) (included with NIST '02 mass spectral library, Agilent p/n G1033A)
MS Libraries	NIST '02 mass spectral library (Agilent p/n G1033A); Agilent RTL Pesticide Library (p/n G1049A)

Results and Discussion

RTL and RTL Databases

RTL is a technique developed by Agilent that allows users to match analyte retention times (RTs) on any Agilent 6890 GC, in any laboratory in the world, so long as the same nominal GC method and capillary column are used [13]. Using RTL, Agilent has developed several retention-time-locked databases for GC and GC/MS that include the locked retention time, compound name, CAS number, molecular formula, molecular weight, and mass spectrum (GC/MS databases only) for each entry [14]. The Agilent RTL Pesticide Library contains this information for almost all GC-amenable pesticides, as well as several endocrine disruptors - 567 compounds in all. For use with the DRS discussed below, this library was converted into the NIST format [15]. Separate Automated Mass Spectral Deconvolution and Identification Software (AMDIS) libraries for the RTs and compound information were created from the original RTL Pesticide Library. Users can easily augment these libraries with newer pesticides or other compounds of interest [15].


Basics of Deconvolution

In GC/MS, deconvolution is a mathematical technique that “separates” overlapping mass spectra into “cleaned” spectra of the individual components. Figure 1 is a simplified illustration of this process. Here, the total ion chromatogram (TIC) and apex spectrum are shown. As is often the case, the peak is composed of multiple overlapping components and the apex spectrum is actually a composite of these constituents. A mass spectral library search would give a poor match, at best, and certainly would not identify all of the individual components that make up the composite “spectrum.”

The deconvolution process finds ions whose individual abundances rise and fall together within the spectrum. In this case, it first corrects for the spectral skew that is inherent in quadrupole mass spectra and determines a more accurate apex RT of each chromatographic peak. As illustrated in Figure 1, deconvolution produces “clean” spectra for each overlapping component. These individual spectra can be library searched with a high expectation for a good match.

The AMDIS that is incorporated into the Agilent DRS is supplied by the National Institute of Science and Technology (NIST) [12].

TIC and spectrum



Deconvoluted peaks and spectra




Figure 1. An illustration of mass spectral deconvolution process.

DRS

Agilent's DRS results from the combination of three different GC/MS software packages: 1) the Agilent GC/MS ChemStation, 2) the NIST Mass Spectral Search Program with the NIST '02 MS Library, and 3) the AMDIS software, also from NIST. Included in the DRS, are mass spectral and locked RT libraries for 567 pesticides and suspected endocrine disrupters.

Three separate, but complimentary, data analysis steps are combined into the DRS. First, the GC/MS ChemStation software performs a normal quantitative analysis for target pesticides using a target ion and up to three qualifiers. An amount is reported for all calibrated compounds that are detected. For other compounds in the database, an estimate of their concentration can be reported based upon an average pesticide response factor

(RF) that is supplied with the DRS software. The DRS then sends the data file to AMDIS, which deconvolutes the spectra and searches the Agilent RTL Pesticide Library (in AMDIS format) using the deconvoluted full spectra. A filter can be set in AMDIS, which requires the analyte's RT to fall within a user-specified time window. Because RTL is used to reproduce the RTL database RTs with high precision, this window can be quite small - typically 20 seconds or less. Finally, the deconvoluted spectra for all of the targets found by AMDIS are searched against the 147,000-compound NIST mass spectral library for confirmation; for this step, there is no RT requirement.

Once the appropriate method is loaded, the DRS report can be generated with a single mouse click as shown in Figure 2. The software can run automatically after each analysis or at a later time on a single file or a batch of files.




Figure 2. ChemStation pull down menu showing options for running the DRS on single or multiple files.

Pesticides in an Herbal Mix

Figure 3 shows a TIC from the extract of an herbal mix. Figure 4 shows the MSD Deconvolution Report for this sample, which is produced in html format so it can easily be emailed or copied into a spreadsheet. This sample was chosen because herbs are among the most difficult vegetable products to analyze. Their extracts contain a large number of natural products that interfere with pesticide analysis.




Figure 3. TIC of an herbal mix.

Document - Microsoft Internet Explorer provided by Agilent Technologies, Inc.

File Edit View Favorites Tools Help

Address: C:\MSDCHEM\1\DATA\Hans Mol Data Feb 04 samples\Mar03_X4\MOL_4A.D\MOL_4A.htm

MSD Deconvolution Report
 Sample Name: Herbal Mix Control
 Data File: C:\MSDCHEM\1\DATA\Hans Mol Data Feb 04 samples\Mar03_X4\MOL_4A.D
 Date/Time: 02:03:11 PM Tuesday, Apr 27 2004

The NIST library was searched for the components that were found in the AMDIS target library.

R.T.	Cas #	Compound Name	Agilent ChemStation Amount (ng)	AMDIS Match	R.T. Diff sec.	Reverse Match	Hit Num
13.038	1610180	Prometon		84	2.5	71	1
18.468	84742	Di-n-butylphthalate	1.7	90	2.5	84	1
23.654	38727558	Diethyl ethyl		69	3.2	73	1
24.079	72559	p,p'-DDE		64	3.3	55	1
27.436	51235042	Hexazinone		61	3.3	80	1
29.681	117817	Bis(2-ethylhexyl)phthalate	0.62	92	2.7	88	3
29.770	21609905	Leptophos		87	3.0	71	1
29.864	2365655	Mirex	0.06	63	2.4	86	2
34.344	51630581	Fenvalerate I		70	5.3	83	2
34.779	102851069	Fluvalinate-tau-I		63	4.6		
34.779	69409945	Fluvalinate				71	1
13.766		Phenanthrene-d10	10				

Done My Computer

Figure 4. MSD Deconvolution Report generated for the herbal mix extract shown in Figure 3.

The DRS report in Figure 4 lists the RT, CAS number, and compound name for each hit. Phenanthrene- d_{10} , listed at the bottom of the report, is the internal standard (ISTD) used by the ChemStation to estimate the quantity of each compound that it found. Since an average pesticide response factor was used for all 567 target compounds, the amounts listed in column 4 are only estimates. Experience has shown that most estimates reported using an average pesticide response factor fall within a factor of 10 of their actual values. True quantitation requires calibration with pesticide standards in the normal way, but this is not practical for all of the pesticides in the database. A laboratory would normally generate calibration curves for their target set of pesticides and use the average RF for the remaining compounds in the database. In this way, when a new compound is detected, the lab can immediately get a rough estimate of its concentration and decide if it should be added to the calibration list.

Column 5 in the report shows the match factor obtained through AMDIS deconvolution and RTL Pesticide Library searching using the deconvoluted full spectra. In this case, several more targets were identified by AMDIS than were found by the ChemStation software (for example, Prometon and p,p'-DDE), which is typical for complex samples. When locked RTs are available, it is a significant advantage to set a RT requirement in the AMDIS software. In this case, hits that did not fall within ± 10 seconds of the database RT were eliminated. Column 6 shows the RT difference (in seconds) between the compound's library RT and its actual value in the chromatogram.

Figure 4 shows that the software identified two phthalates (suspected endocrine disruptors) in addition to the pesticides. Phthalates are ubiquitous in the environment and are extremely difficult to remove from the background. In this case, no attempt was made to determine if the phthalates were actually extracted from the sample or were introduced in the laboratory.

The last two columns in the DRS report show the results from searching all of the AMDIS hits against the NIST 147,000-compound mass spectral library. When the NIST library search finds a compound in the top 100 matches (a user-settable value) that agrees with the AMDIS results, its match factor is listed in column seven. The hit number is shown in the last column, with "1" being the best match (highest match factor) in the NIST database. Occasionally, the NIST library search does not find the AMDIS hit among the top

100 spectral matches. In this case, the next line in the report shows the best library match for that spectrum. This is evident for fluvalinate-tau-I (Figure 4), which eluted at 34.779 min. The next line shows the best NIST library match for that spectrum - fluvalinate. In this case, no compound with the same CAS number as fluvalinate-tau-I is contained in the NIST mass spectral library. In fact, fluvalinate-tau-I is the D isomer, while fluvalinate is the DL isomer mixture.

Blind Comparison Between DRS and Traditional Data Review

Many comparisons have shown that the DRS is much better than conventional methods at identifying target compounds in complex samples, such as food and environmental extracts. Two such studies are described here. In the first case, 17 unspiked crop samples were analyzed by NRM Laboratories in Berkshire, UK using Agilent's RT-locked pesticide method. The data files, but not their list of pesticide hits, were sent to Agilent for analysis using the new DRS. Table 2 shows a comparison of the results from the two laboratories. Using manual data review, NRM identified 28 pesticides in the 17 samples, four of which were below their lowest calibration level. Using the same data files, the DRS identified 33 pesticides.

Agilent's automated method did not identify azoxystrobin in the spring onion sample because it is not included in the RTL pesticide library. While it can be found in the NIST library, it has a molecular ion at 403 amu and method used at NRM only scanned to 400 amu. The DRS method confirmed all four pesticides that were below the NRM calibration range and found five more (terbacil, pyrimethanil, methiocarb, pyridaben, and propamocarb) that were not included in their method.

The agreement between the manual and automated methods was excellent. However, the DRS looks for many more pesticides and was able to find several that were missed by the manual method. In addition, manual data review took a chemist about 7 hours for the 17 samples while the DRS finished the task in 50 minutes of unattended computer time.

Table 2. A Comparison of the Pesticides Found in 17 Unspiked Crop Samples Using Conventional Data Review and Agilent's DRS. Pesticides that Were Found by Only One Method Are Underlined

Sample	Agilent DRS results*	NRM Manual Analysis**
Coriander	Propyzamide Chlorthal-dimethyl p,p'-DDE	Propyzamide Chlorthal-dimethyl p,p'-DDE
Rosemary	<u>Terbacil</u> Pirimicarb Chlorthal-dimethyl	Not found*** Pirimicarb Chlorthal-dimethyl
Spring Onion	Propyzamide <u>Pyrimethanil</u> Pirimicarb Metalaxyl Iprodione Not in DRS library†	Propyzamide Not found*** Pirimicarb Metalaxyl Iprodione <u>Azoxystrobin</u>
Chives	<u>Methiocarb</u> Iprodione	Not found*** Iprodione
Cherry Tomato	Procymidone <u>Pyridaben</u>	Procymidone Not found***
Courgette	<u>Propamocarb</u>	Not found***
Aubergine	Procymidone Buprofezin Endosulfan sulfate Iprodione	Procymidone Buprofezin Endosulfan sulfate Iprodione
Flat Leaf Parsley	Chlorthal-dimethyl	Chlorthal-dimethyl
Lambs Lettuce	Iprodione	Iprodione†††
Cos Lettuce	Dimethoate Metalaxyl Procymidone Terbuconazole Omethoate††	Dimethoate Metalaxyl Procymidone Terbuconazole††† Omethoate
Fine Endive	Procymidone lamda-Cyhalothrin	Procymidone lamda-Cyhalothrin
Red Potato	Chloroprotham Pirimicarb	Chloroprotham Pirimicarb†††
Fine Endive	Pirimicarb	Pirimicarb†††

* Pesticides found by re-analyzing NRM datafiles using Agilent's DRS software.

** Pesticides found by NRM using target compound analysis and manual verification.

*** This compound was not in the NRM target compound list.

† This compound is not included in the Agilent RTL Pesticide Library or the DRS software.

†† Found by the Agilent ChemStation but not found by AMDIS or NIST library searching after deconvolution. After careful review of this hit, omethoate was judged not to be in the sample.

††† Compound was detected but was below the calibration range.

Analysis of Surface Water Samples: In another study, the CDFA analyzed 17 surface water extracts for pesticides. TICs for two typical samples are shown in Figure 5. The CDFA used RTL and RTL database searching but without the benefit of spectral deconvolution. The same data files were then analyzed using the DRS for comparison.

Table 3 shows the results from the CDFA manual analysis of the 17 samples compared to results using the DRS. The CDFA found 38 pesticide hits in the 17 samples, some of which were for the same pesticide in multiple samples. It took a skilled analyst about 8 hours to review the results, eliminate false positives, and verify all of the hits. The DRS found 37 of the compounds seen by the CDFA and identified one CDFA hit as a false positive. In addition, 34 more pesticides were

found for a total of 71 hits in the 17 samples. The process was fully automated and took about 20 minutes of unattended computer time to process all of the data files.

Table 3. A Comparison of Results from the Analysis of 17 Surface Water Samples by GC/MS. The CDFA Used RTL and RTL Database Searching, but No Deconvolution. Agilent's DRS Was Used to Analyze the Same Data Files

	CDFA	DRS
Number of pesticide hits	37	Same 37 + 34 additional
Number of false positives	1	0
Time required for analysis	~ 8 hours	20 minutes




Figure 5. TICs of typical surface water extracts provided by the CDFA.

Conclusions

Agilent's new DRS solution for pesticide analysis offers laboratories a number of real benefits.

- **Ease of use:** This software solution is very simple to use and takes no more skill than is needed to operate the 6890N/5973 inert GC/MS system. There is no need for the user to learn about the intricacies of deconvolution or to master a new software package.
- **Automation:** The deconvolution report can be generated automatically after each run or a batch of samples can be processed all at once.
- **Time savings:** Data review is reduced from hours to minutes.
- **Quality:** It produces results with the fewest false positives and false negatives.
- **Reproducibility:** Results are not dependent upon the skill or experience of the operator.
- **Accuracy:** Comparisons such as those discussed in this application note show that the DRS finds pesticides with greater accuracy than manual methods of data analysis. It is particularly useful for relatively complex samples where co-eluting matrix components might obscure traces of target pesticides.
- **Comprehensive:** This method screens for almost all GC-amenable pesticides as well as several suspected endocrine disrupters in a single GC/MS run. With 567 compounds in the method, it is the most comprehensive pesticide-screening tool available. Users can add more compounds to the method as needed.
- **Produces quantitative, semi-quantitative, and qualitative results:** All calibrated compounds can be quantified. The concentrations of any other compounds can be estimated using an average pesticide response factor provided with the software.

Use of the DRS is not limited to pesticide analysis. Other target compound mass spectral libraries can be converted into the AMDIS format and used with this software. For example, one could use existing libraries for forensic drugs, flavors and fragrances, organic pollutants, etc. Users can even generate their own libraries and use them with the DRS. While not required, it is a big advantage to have an RTL library with locked RTs for each entry, as this will give the fewest false positives.

Acknowledgements

The authors wish to thank Dr. Mark Lee and Stephen Siegel of the California Department of Food and Agriculture, Dr. J.G.J. Mol of TNO Research, The Netherlands, and the management and staff at NRM Laboratories, UK, for their contribution of samples and data.

References

1. C.D.S Tomlin, editor. The Pesticide Manual, 13th edition, British Crop Protection Council, Surry, UK (2003).
2. http://www.who.int/pcs/docs/Classif_Pestic_2000-02.pdf
3. J. Cook, M.P. Beckett, B. Reliford, W. Hammock, and M. Engel (1999) *J. AOAC Int.*, **82** (6), 1419-1435.
4. M.A. Luke, J.E. Froberg, and H.T. Masumoto, (1975) *J. Assoc. Off. Anal. Chem.* **58**, 1020-1026.
5. M. Luke, J. Froberg, G. Doose, and H. Masumoto, (1981) *J. Assoc. Off. Anal. Chem.* **64**, 1187-1195.
6. B. McMahon and N. Hardin (1994) Pesticide Analytical Manual, Vol. 1, 3rd Ed., U.S. Food and Drug Administration, Washington, DC.
7. J. Fillion, R. Hindle, M. Lacroux, and J. Selwyn (1995) *J. AOAC Int.* **78**, 1252-1266.
8. J. Fillion, F. Sauvé, and J. Selwyn (2000) *JAOAC Int.*, **83**, 698-712.
9. P. Wylie and B. Quimby, "A Method Used to Screen for 567 Pesticides and Suspected Endocrine Disrupters," Agilent Technologies, publication 5967-5860E www.agilent.com/chem.
10. H. Prest, P. Wylie, K. Weiner, and D. Agnew, "Efficient Screening for Pesticides and Endocrine Disrupters Using the 6890/5973 GC/MSD System," Agilent Technologies, publication 5968-4884E www.agilent.com/chem.
11. K. Weiner and H. Prest, "Retention Time Locking: Creating Custom Retention Time Locked Screener Libraries," Agilent Technologies, publication 5968-8657E www.agilent.com/chem.
12. National Institute of Standards and Technology, AMDIS Literature and Downloads website: http://www.amdis.net/What_is_AMDIS/AMDIS_Literature_and_Downloads/amdis_literature_and_downloads.html.

13. V. Giarocco, B. Quimby and M. Klee, "Retention Time Locking: Concepts and Applications," Agilent Technologies, publication 5966-2469E www.agilent.com/chem.
14. <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#RTL>.
15. M. Szelewski and C.K. Meng, "Building and Editing RTL Screener Databases and Libraries," Agilent Technologies, publication 5989-0916EN www.agilent.com/chem.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
May 19, 2004
5989-1157EN




Agilent Technologies



Effect of Column Temperature on Separation of Herbicides

Application
Agrichemical
Robert D. Ricker

Herbicides are a group of molecules that selectively control plant growth through a variety of mechanisms. The large differences in molecular structure of herbicides result in a wide range of retention times and, therefore, long runtimes when performing HPLC separations in isocratic mode. HPLC analysis of these molecules may be used as a means of determining their presence as contaminants in soil, groundwater, and wastewater and may also be used as a means of monitoring their uptake and metabolism in target and non-target plant species.



Conditions:
Column: ZORBAX SB-C18, 4.6 x 150 mm, Agilent Part No. 883975-902
Mobile Phase: MeOH : pH 6.0 NaOAc buffer (48:52)
Flow: 1.5 mL / min.

Highlights

- Higher temperatures provide capability for rapid, high efficiency reversed-phase separations.
- Agilent ZORBAX SB-C18 columns are uniquely stable at temperatures of even 90°C.
- Higher temperatures reduce mobile-phase viscosity and decrease column back pressure.



Agilent Technologies

*Robert Ricker is an application chemist
based at Agilent Technologies, Wilmington,
Delaware.*

For more information on our products and
services, visit our website at:
www.agilent.com/chem

Copyright© 2002 Agilent Technologies, Inc.
All Rights Reserved. Reproduction,
adaptation or translation without prior
written permission is prohibited, except as
allowed under the copyright laws.


Agilent shall not be liable for errors
contained herein or for incidental or
consequential damages in connection with
the furnishing, performance, or use of this
material.

Information, descriptions, and specifications
in this publication are subject to change
without notice.

Printed in the USA
April 25, 2002
5988-6284EN



Agilent Technologies



Rapid Analysis of CLP Pesticides Using High-Temperature DB-35ms and DB-XLB Columns

Application

Environmental

Author

Cameron George
Agilent Technologies, Inc.
91 Blue Ravine Road
Folsom, CA 95630-4714
USA

Abstract

Arylene-phase column pairs (primary and confirmation) permit high oven temperature for rapid analysis of CLP chlorinated pesticides. The columns are also suitable for phenoxy acids, haloacetic acids, polychlorinated biphenyls and Environmental Protection Agency Method 508.1 pesticides.

Introduction

Accurate identification and confirmation of trace level chlorinated pesticides are difficult tasks facing environmental laboratories. The chromatographic system, including the analytical columns, must be optimized. The gas chromatography (GC) columns must possess the selectivity, inertness and

thermal stability needed to achieve optimum resolution and sensitivity in the shortest possible time. These needs are realized with Agilent Technologies' J&W Brand DB-35ms (primary) and DB-XLB (confirmation) columns.

The excellent selectivity of high phenyl content phases for chlorinated pesticides is well documented. However, these phases typically suffer from poor thermal stability resulting in high bleed and excessively long analysis times.

DB-35ms uses arylene-phase technology to provide improved thermal stability through a "stiffening" of the polymer backbone. The result is increased sensitivity and an upper temperature limit of 360°C. The column bleed contribution to background noise is reduced, giving a much improved signal-to-noise ratio and increased usable sensitivity compared to standard 35%-phenyl phases. The high thermal limit translates into shorter analysis times, increased column lifetime and the ability to periodically bake the column at a high temperature to remove semivolatile contaminants.

DB-XLB uses a proprietary second-generation arylene technology giving it the same 360°C upper temperature limit and the lowest bleed of any phase available.



Agilent Technologies

Experimental

The columns and related inlet parts are described in Table 1.

Table 1. Columns and Related Parts

Phase/Description	id (mm)	Film (μm)	Length (m)	Part Number
DB-35ms	0.32	0.25	30	123-3832
DB-XLB	0.32	0.50	30	123-1236
Quartz deactivated splitter	-	-	-	5181-3398
Deactivated fused silica guard column	0.53	-	5	160-2535-5

This is a small sampling of the many DB columns and dimensions available.

Results and Discussion

Simple window diagramming identified the exact film thickness necessary to allow DB-XLB to give optimum confirmation power when run using the primary column temperature program. Figure 1 shows the optimized primary and confirmation chromatograms for the DB-35ms/DB-XLB column pair.

Because these columns are designed for enhanced thermal resistance, it is not necessary to bake them excessively upon installation to reduce bleed to acceptable levels. A simple 1 to 2 hour conditioning period is typically more than adequate. Conditioning columns overnight is a common requirement with cyanopropyl- and trifluoropropyl-containing CLP pesticide columns. This practice can result in increased column activity and decreased column life time, but is not required with DB-35ms/DB-XLB. In short, you are ready sooner after column installation.

Environmental laboratories are also interested in other gas chromatography/electron capture detector (GC/ECD) methods with the same dual column

pair used for the chlorinated pesticides. These methods include phenoxy acid herbicides (EPA Method 8151A), haloacetic acids (EPA Method 552.2), PCBs (EPA Method 8082) and EPA Method 508.1 pesticides. This column pair provides baseline resolution of all 8151A analytes on both columns in just over 16 minutes. In addition, DB-35ms and DB-XLB provide the best confirmation and the fewest coelutions of any dual column pair commercially available for 508.1 pesticides.

Conclusions

The DB-35ms and DB-XLB column pair perform rapid, high-resolution separations of CLP pesticides. The high temperature limit and low column bleed make these columns attractive for analyses of similar semivolatile sample mixtures.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Column: DB-35ms
30 m × 0.32 mm id, 0.25 µm
P/N: 123-3832

Column: DB-XLB
30 m × 0.32 mm id, 0.50 µm
P/N: 123-1236

Carrier: Helium at 45 cm/sec
(EPC in constant flow mode)

Oven: 110 °C for 0.5 min
110-320 °C at 15 °/min
320 °C for 2 min

Injector: Splitless, 250 °C
30 sec purge activation time
50 pg per component

Detector: Micro ECD, 350 °C
Nitrogen makeup gas
(column + makeup flow =
30 mL/min constant flow)

1. Tetrachloro-m-xylene (SS)
2. α-BHC
3. γ-BHC
4. β-BHC
5. Heptachlor
6. δ-BHC
7. Aldrin
8. Heptachlor epoxide
9. γ-Chlordane
10. α-Chlordane
11. Endosulfan I
12. 4,4'-DDE
13. Dieldrin
14. Endrin
15. 4,4'-DDD
16. Endosulfan II
17. 4,4'-DDT
18. Endrin aldehyde
19. Endosulfan sulfate
20. Methoxychlor
21. Endrin ketone
22. Decachlorobiphenyl (SS)

SS-Surrogate Standard




Figure 1. CLP Pesticides

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
December 18 2001
5988-4973EN



Agilent Technologies



A Complete Solution for Chlorinated Pesticides and Herbicides Using DB-35ms and DB-XLB Columns

Application

Environmental

Author

Cameron George
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

DB-35ms (primary) and DB-XLB (confirmation) columns, used with inert inlet components and hydrogen carrier gas, perform CLP pesticide analyses in less than 15 minutes total cycle time. Phenoxy acids can be analyzed with the same configuration.

Introduction

Obtaining high quality data in the shortest possible time is a desire of all analytical testing laboratories. To achieve this goal, all aspects of the chromatographic system must be optimized. The GC columns must possess the selectivity, inertness and thermal stability needed to achieve optimum resolution and sensitivity in the least amount of time. For the analysis of CLP pesticides and phenoxy acid herbicides, these needs are met with DB-35ms (primary) and DB-XLB (confirmation) columns.

In another Application Note[1], DB-35ms and DB-XLB show excellent selectivity and inertness for CLP pesticides, achieving one hundred percent

confirmation in less than 16 minutes. However, there is always the desire for a faster analysis. This note reports the result of changing to hydrogen carrier gas and increasing the oven ramp rate.

Experimental

Table 1 describes the columns and related inlet parts.

Table 1. Columns and Related Parts

Phase/Description	id (mm)	Film (µm)	Length (m)	Part number
DB-35ms	0.32	0.25	30	123-3832
DB-XLB	0.32	0.50	30	123-1236
Quartz deactivated splitter	-	-	-	5181-3398
Deactivated fused silica guard column	0.53	-	5	160-2535-5

This is a small sampling of the many DB columns and dimensions available.

Results and Discussion


To reduce analysis time without a significant loss in resolution, the carrier gas was changed to hydrogen. Using hydrogen carrier gas with a linear velocity of 65 cm/sec, and increasing the oven ramp rate from 15 °C/min to 25 °C/min, reduces analysis time to less than 10 minutes. Considering a typical cool-down time of 4 to 5 minutes, the total instrument cycle-time is now less than 15 minutes.




Agilent Technologies

Results and Discussion

Figure 1 shows the excellent resolution and confirmation available for CLP pesticides using DB-35ms/DB-XLB with hydrogen carrier gas and a properly scaled temperature program.



Columns: DB-35ms
30 m × 0.32 mm I.D., 0.25 μm
Part No.: 123-3832
DB-XLB
30 m × 0.32 mm I.D., 0.50 μm
Part No.: 123-1236
Carrier: Hydrogen at 65 cm/sec
(EPC in constant flow mode)
Oven: 110 °C for 0.5 min
110-320 °C at 25 °C/min
320 °C for 2 min
Injector: Splitless, 250 °C
30 sec purge activation time
50 pg per component
Detector: μECD, 350 °C
Nitrogen makeup gas (column +
makeup flow = 30 mL/min constant
flow)



1. Tetrachlorom-xylene (SS)
2. α-BHC
3. γ-BHC
4. β-BHC
5. Heptachlor
6. δ-BHC
7. Aldrin
8. Heptachlor epoxide
9. γ-Chlordane
10. α-Chlordane
11. Endosulfan I
12. 4,4'-DDE
13. Dieldrin
14. Endrin
15. 4,4'-DDD
16. Endosulfan II
17. 4,4'-DDT
18. Endrin aldehyde
19. Endosulfan sulfate
20. Methoxychlor
21. Endrin ketone
22. Decachlorobiphenyl


Figure 1 Analysis of CLP pesticides using DB-35ms and DB-XLB columns.

DB-XLB and DB-35ms have flexibility for a range of GC/ECD methods, a result of their ideal selectivity, inertness and the robustness of low bleed phases. Phenoxy acid herbicides (EPA Method 8151A) are nicely resolved with these columns. All twenty common herbicides are resolved in slightly

over 16 minutes, as shown in Figure 2. The analysis can be optimized for faster analysis. To obtain chromatograms and analysis conditions for additional GC/ECD methods, go to Agilent's Technical Support at www.agilent.com/chem

Columns: DB-35ms 30m × 0.32 mm I.D., 0.25 µm Part No.: 123-3832	Injector: Splitless, 250 °C 30 sec purge activation time 50 pg per component	7. MCPA
DB-XLB 30m × 0.32 mm I.D., 0.50 µm Part No.: 123-1236	Detector: µECD, 350 °C Nitrogen makeup gas (column + makeup flow = 30 mL/min constant flow)	8. 4,4', Dibromooctafluorobi-phenyl (IS)
Carrier: Helium at 45 cm/sec (EPC in constant flow mode)		9. Dichloroprop
Oven: 50 °C for 0.5 min 50-100 °C at 25 °C/min 100-320 °C at 12 °C/min 320 °C for 2 min		10. 2,4-D
	1. Dalapon	11. Pentachlorophenol
	2. 3,5-Dichlorobenzoic acid	12. 2,4,5-T,P
	3. 4-Nitrophenol	13. 2,4,5-T
	4. Methyl-2,4-dichlorophenyl-acetate (SS)	14. Chloramben
	5. Dicamba	15. Dinoseb
	6. MCPP	16. 2,4-DB
		17. Bentazone
		18. DCPA
		19. Picloram
		20. Acifluorfen

DB-35ms



DB-XLB




Figure 2. EPA 8151A phenoxy acid herbicides.

Conclusions

DB-XLB and DB-35ms columns, when used with inert inlet components, hydrogen carrier gas and an appropriate carrier velocity, yield these benefits:

- Short analysis times for better productivity
- Excellent thermal stability with 360 °C upper temperature limit
- Confirmation for CLP pesticides and phenoxy acid herbicide

Reference

1. "Rapid Analysis of CLP Pesticides Using High-Temperature DB-35ms and DB-XLB Columns," Application Note 5988-4973EN, Nov 26, 2001.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
December 17, 2001
5988-4971EN



Agilent Technologies



Identification and Quantitation of Pesticides in the Parts-per-Trillion Range Using Retention Time Locking and GC/MS Application

Environmental, Food

Author

C. Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The typical pesticide quantitation limit for a mass spectrometer in the Scan mode is in the sub-ppm range. By using a selected ion monitoring method, a lab can lower the target compound quantitation limit to the low parts-per-billion (pg/ μ L) range using a retention time locked gas chromatography/mass spectrometry method. By adding large volume injection capability to the method, target compounds at parts-per-trillion can be quantified.

A specially developed 567-compound retention time locking pesticide mass spectral library can automatically screen an acquired sample's data file for all 567 compounds in seconds. The library can also be applied for rapid screening of samples acquired in selected ion monitoring method. Using the compound library information, a selected ion monitoring method for 80 target compounds was created in less than 2 hours without running any analyses.

Introduction

Most pesticides are typically analyzed on a gas chromatograph (GC) with element-selective detectors (ESDs). Although these ESDs provide low ppb

detection limits and are easy to operate, the data do not provide sufficient information to confirm a compound's presence with confidence. Due to the universal nature of mass spectrometric detection, a mass spectrometer (MS) provides additional information and increased confidence in the assignment of compound identity. With recent advances in GC/MS hardware and software and the decrease in cost of ownership, more and more laboratories are routinely analyzing pesticide residue samples with MS detection.

To match the GC/ESD detection limits and/or to eliminate sample concentration steps, a user must lower the MS detection limit by 2 to 3 orders of magnitude. This application note, discusses the following approaches.

- Run the MS in single ion monitoring (SIM) mode
- Make large volume injections (LVIs)
- Use higher electron multiplier voltage (EMV)

For compound identification, a specially developed 567-compound retention time locking (RTL) [1] pesticide library could perform the entire 567-compound screening in seconds using Scan data. A subset of the library could be screened in seconds from SIM data.

Experimental

A pesticide standard mixture was used to compare the lowest detection limits of splitless injection and LVI under Scan and SIM modes.



Agilent Technologies

System Configuration for Screening and Quantitation:

- 6890 GC with a programmable temperature vaporizer (PTV) [2,3] inlet
- 5973 Mass Selective Detector (MSD)
- 7683 Automatic Liquid Sampler (ALS) tray and autoinjector
- HP-5MS capillary column (30 m × 0.25 mm × 0.25 μm), P/N 19091S-433
- G1701BA version B.00.00 MSD ChemStation software or higher
- G1049A MSD RTL Pesticide Database/Library

Table 1. GC Method Parameters

Oven	70(2)/25/150(0)/3/200(0)/8/280(10) = 41.87 min
Inlet	PTV
Inlet pressure	17.30 psi (locked to methyl chlorpyrifos at 16.593 min), constant pressure mode

Table 2. Injection Parameters

Injection mode	Solvent vent	Splitless
Injection volume (syringe)	25 μL (50-μL syringe, P/N 5183-0318)	1 μL (10-μL syringe, P/N 9301-0713)
Injection speed	Inject @ 100 μL/min Draw @ 300 μL/min Dispense @ 4500 μL/min	Fast
Inlet temp	40(0.35)/600/320 (3)/50/200 (Hold until end)	280 °C
Vent	Vent time = 0.29 min Vent flow = 150 mL/min Vent pressure = 0.00 psi	
Purge	60 mL/min @ 2 min	60 mL/min @ 2 min
Liner	Deactivated, Multi Baffled (P/N 5183-2037)	Deactivated, Multi Baffled (P/N 5183-2037)
Inlet cooling	Liquid CO ₂	None

Table 3. MS Method Parameters

Solvent delay	3 min
Tune file	Atune.u
Transfer line	280 °C
MS Quad	150 °C
MS source	230 °C
Threshold	150
Sample #	2
Scan range	35 to 500 amu (in Scan mode)
Forty (40) SIM groups (in SIM mode)	

Table 4. Pesticide Screening Parameters for the SIM Method

Extraction window	±0.100 minute
Qualifier mode	Absolute
Qualifier %	30
Zero qualifiers	Included
Subtraction mode	Average start/stop
Screen database	Rtlpest.SCD

Results and Discussion

RTL [1] was used to:

1. Expedite data comparison in overlay format
2. Achieve lower target compound detection limit
3. Allow rapid pesticide screening using the RTL pesticide database/library
4. Help to differentiate isomers by their retention time (RT) differences
5. Eliminate the tedious SIM method RT updating process after column maintenance
6. Simplify the editing of the SIM ion groups

A mixture from the California Department of Food and Agriculture (CDFA) of 80 pesticides at 5000 pg/μL each was used as the stock solution for this study. The mixture contained carbamate, organochlorine, organophosphorus, and organonitrogen pesticides. Figure 1 is an offset overlay of three total ion chromatograms (TIC) with 50, 100, and 500 pg of each of the pesticides injected. These TICs were obtained in the Scan mode from 1-μL splitless injections. For many of these pesticides the quantitation limit in the Scan mode is about 500 pg on column.




Figure 1. Total ion chromatograms from 1- μ L splitless injections of 80 pesticides with 50, 100, and 500 pg of each compound injected.

SIM Mode

To lower the detection limit, a SIM method was created. Instead of the traditional way of making a SIM method, a user can use the information in the RTL Pesticide Database to build a SIM method

without running an analysis. Here are the steps for editing SIM ion group parameters:

1. List the MSD RTL Pesticide Database from the ChemStation (Figure 2 is a partial listing) and paste the complete listing into a spreadsheet.

Scdlist.txt - Notepad

File Edit Search Help

SCD Compound List Report

Screen Database : C:\DATABASE\RTLPEST.SCD
Total SCD Cpnds : 567

Cpd#	Compound Name	Tion	Exp_RT	Q1	Q2	Q3
1	Diethylene glycol	45	3.39	75	76	44
2	Aniline	93	3.55	66	65	92
3	p-Dichlorobenzene	146	3.88	148	111	75
4	Dicyclopentadiene	66	4.00	132	67	65
5	Dimefox	44	4.01	110	154	42
6	o-Dichlorobenzene	146	4.09	148	111	75
7	2-Methylphenol	108	4.25	107	77	79
8	4-Methylphenol	107	4.42	108	77	79
9	m-Cresol	108	4.42	107	79	77
10	1,2-Dibromo-3-chloropropane	157	4.53	155	75	159
11	2,4-Dimethylaniline	121	5.19	120	106	77
12	2,6-Dimethylaniline	121	5.20	106	120	77
13	2,4-Dichlorophenol	162	5.19	164	63	98
14	1,2,4-Trichlorobenzene	180	5.29	182	184	145
15	Ethiolate	100	5.41	72	161	44
16	3-Chloroaniline	127	5.45	129	65	92
17	4-Chloroaniline	127	5.48	129	65	92
18	2-Ethyl-1,3-hexanediol	56	5.51	55	73	57
19	p-Nitrotoluene	91	5.57	137	65	107
20	Methamidophos	94	5.66	95	141	47
21	Dichlorvos	109	5.83	185	79	187
22	Allidochlor	41	6.18	56	138	132
23	2,3,5-Trichlorophenol	196	6.63	198	200	160
24	2,6-Dichlorobenzonitrile	171	6.75	173	136	100

Figure 2. A partial listing of the pesticide screener database. The listing includes the compound number, compound name, target ion, expected retention time, and three qualifier ions.

- In the spreadsheet, delete the rows of the compounds not needed in the method.
- Separate target compounds into groups (see the added "Group #" column on Figure 3) using these criteria:
 - One to three compounds in each group, and
 - The RTs of the adjacent compounds in adjacent groups are at least 0.2 minute apart. For example, compounds 42 and 51 are more than 0.2 minute apart, so they are in different groups. Compounds 51 and 55 are less than 0.2 minute apart, so they are in the same group.
- Use the average RT of the adjacent compounds in adjacent groups as the SIM group RT (see the added "Group RT" column on Figure 3). For example, the average retention time of compound 42 (7.91 min, in group 2) and compound 51 (8.78 min, in group 3) is 8.35 minute which is used as the starting retention time of group 3. When all the group numbers and respective starting retention times are determined, make a hardcopy of the spreadsheet for easy entry into the "MS SIM/Scan Parameters" in the next step.
- Enter the target ion and qualifier ion(s) (Q1, Q2, and/or Q3) of all compounds into the respective ChemStation SIM group (Figure 4). Notice that all the information for building the SIM groups came from Figure 3.

#	Compound Name	MSD_RT	T	Q1	Group #	Group RT
24	2,6-Dichlorobenzonitrile	6.75	171	173	1	3.00
35	Mevinphos	7.60	127	192		
42	Propham	7.91	93	179	2	7.75
51	o-Phenylphenol	8.78	170	169	3	8.35
55	Pentachlorobenzene	8.95	250	252		
76	Propoxur	10.35	110	152	4	9.60
82	Diphenylamine	10.52	169	168		
92	Chlorpropham	11.05	127	213	5	10.76
98	Ethalfuralin	11.28	276	316		
102	Bendiocarb	11.54	151	126	6	11.41
103	Trifluralin	11.64	306	264		
104	Benfluralin	11.73	292	264		
111	Phorate	11.96	75	121	7	
113	BHC alpha isomer	12.09	181	219		
117	Hexachlorobenzene	12.38	284	286		
120	Dicloran	12.56	206	176		
122	Demeton-S	12.63	88	60		
124	Dimethoate	12.68	87	93		
129	Simazine	12.91	201	186		

Figure 3. A spreadsheet of target compounds separated into different SIM groups with RTs of the adjacent compounds in adjacent groups at least 0.2 minute apart. The starting retention time of each group was determined by calculating the average RT of the adjacent compounds in adjacent groups.

The number of qualifier ions used in a SIM method depends on the number of analytes of interest. For a method monitoring 20 to 30 compounds, all three qualifier ions should be used in the SIM method. As the list of target compounds grows, fewer qualifier ions should be used in the method to maintain a reasonable and comparable ion dwell time and sampling rate.

In general, 10 scans (cycles) per peak are recommended for quantitation purposes. For example, if an analyte peak is 6 seconds wide, about 1.7 cycles per second should be maintained for that SIM ion group. Once the number of cycles per second is determined, the dwell time of the ions can be varied to meet that. As the dwell time is entered for each ion, the ChemStation automatically shows the number of cycles per second. In Figure 4, Group 6 has 3.03 cycles per second.




Figure 4. A screen capture of the MSD ChemStation showing the MS and SIM parameters. The SIM parameters (group ID, group retention time, and ions) were all derived from Figure 3.

Figure 5 shows two chromatograms obtained from 1-μL splitless injections at 50 pg/μL using both Scan and SIM modes. The Scan mode has significantly higher baseline noise than the SIM mode. Some of the compounds, especially the late eluters, were not detected in the Scan mode. When the Scan method was changed to a SIM method at this concentration, the signal-to-noise ratio (S/N) increased by a factor of 100. It is worth pointing out that a SIM method does not record background ions from the sample matrix, therefore minimizing the baseline noise and improving the S/N.




Figure 5. Chromatograms of 1- μ L splitless injections at 50 pg/ μ L from Scan and SIM modes.

In a SIM method, the retention times of the ion groups normally need updating after column maintenance. By using RTL, a user can not only eliminate the tedious RT updating process [4] but also decrease the detection limit. With reproducible known RTs of target compounds, the start and end time of each ion group can be determined optimally. By narrowing the time windows of an ion group to monitor only one or two compounds at a time, the MS can monitor fewer ions in each window, allowing more sampling time for the target ions.

Ideally, a SIM method will have the maximum number of ion groups and the minimum number of ions in each group. In this way, each ion group can get more scans per unit time resulting in better peak shape and more accurate quantitation.

LVI

To decrease the detection limit further, a user can put more sample on column using the LVI technique. The typical “solvent-vent” approach is to inject the sample slowly into a PTV inlet at a temperature just below the solvent boiling point and let solvent evaporate before ramping up the inlet temperature to move the compounds onto the capillary column. Figure 6 compares a 1- μ L splitless injection with a 25- μ L solvent-vent injection. Both injections resulted in 50 pg per compound on column. Note that the solvent-vent ion chromatogram is plotted upside down for ease of comparison with the splitless ion chromatogram. It is obvious from the figure that the two techniques provide very similar results. This demonstrates that the solvent-vent technique is a viable approach for sample introduction.




Figure 6. SIM results of 50 pg on column using either a 1-µL splitless or a 25-µL solvent-vent injection.

Higher EMV

It is known that the signal increases with higher EMV on the MS. In Figure 7, the upper signal, after 10-fold magnification, is a 25-µL LVI of 0.5 pg/µL at tune voltage. The bottom signal is the same injection with the electron multiplier set to tune +400 V. Adding 400 V to the EMV increases

the signal by 10X, which makes the integration more accurate. However, the baseline noise also increases by 10X, so the S/N stays the same.

Although increasing the EMV does help to bring small peaks over the detection threshold, it shortens the life of the multiplier. In general, the EMV should be kept at the tune voltage.




Figure 7. SIM results of 12.5 pg on column using either EMV at Tune voltage or Tune +400 V.

LVI in Combination with SIM Methods

Combining LVI and SIM, Figures 8 and 9 show quantifiable peaks of three compounds at as low as 5 pg on column. In Figure 8, ion chromatograms of endosulfan sulfate and p,p'-DDT at 0.2 and 500 pg/ μ L are shown. The top chromatogram was from a 25- μ L solvent-vent SIM method and the bottom chromatogram was from a 1- μ L splitless Scan method. By using LVI and SIM, it is interesting to see that similar S/N ratios were achieved

even with a 2500-fold decrease (from 500 to 0.2 pg/ μ L) in sample concentration.

By increasing the injection volume to 100 μ L, samples at concentration as low as 0.05 pg/ μ L can also be quantified as shown in Figure 9. The top portion shows the chlorthal-dimethyl extracted ion chromatograms (EIC) of mass 299 and 301 from a 100- μ L full Scan run. The bottom portion shows the same ions from a 100- μ L SIM run. The SIM method shows better peak shape and lower baseline noise.




Figure 8. Ion chromatograms of endosulfan sulfate and p,p'-DDT at 0.2 and 500 pg/ μ L. The top chromatogram was from a 25- μ L solvent-vent SIM method and the bottom chromatogram was from a 1- μ L splitless Scan method.




Figure 9. Ion chromatograms of 100-μL chlorthal-dimethyl injected at 0.05 pg/μL. The top portion was from a full Scan run and the bottom portion was from a SIM run.

Target Compound Screening

Combining RTL and the G1049A MSD RTL Pesticide Database/Library, a user can screen for 567 pesticides and suspected endocrine disruptors from any Scan run [5]. A user can screen a subset of the library with improved sensitivity using a SIM method. The MSD ChemStation can generate a

567-compound screening report automatically in less than 30 seconds. Figure 10 is a report of the 0.5 pg/μL sample (25 μL injected in SIM mode) that lists the “probable hits” (marked with an x) and “possible hits” (marked with a ?). All target compounds at this 12.5 pg on column level were found by the software.

MultiVu - [C:\SYS_X\DATA\80MIX\0403SIM\0_5PG2.D\scrntemp.txt]

File Edit Search Window

Screen Report (Not Reviewed)

Data File : C:\SYS_X\DATA\80MIX\0403SIM\0_5PG2.D Vial: 16
 Acq On : 3 Apr 2001 10:26 Operator: 40 SIMgrps, 40gr
 Sample : CDFA 80 mix 10000:1 Inst : GC/MS Ins
 Misc : CDFA 80 mix = 5 ng/ μ L Multiplr: 1.00
 Sample Amount: 0.00

MS Integration Params: events.e

Screen File: Rtlpest.RES Extraction Window: +/- 0.100 min
 Screen Database: Rtlpest.SCD Qualifier Mode : Absolute
 Qualifier % : 30
 Zero qualifiers : Included
 Subtraction Mode : Sub Average Start/Stc

Compound	Status	ExpRT	Delta	Target m/z	Resp.	Qualifiers Out of Range	XCR
16 3-Chloroaniline	?	5.453	+0.034	127	11386	129	0.92
17 4-Chloroaniline	?	5.478	+0.009	127	17984	129	0.92
24 2,6-Dichlorobenzonitrile	x	6.752	-0.031	171	171652		0.97
35 Mevinphos	x	7.595	-0.035	127	101291		0.96
42 Protham	?	7.908	-0.039	93	107866	119,137	0.76
51 o-Phenylphenol	?	8.782	-0.038	170	204523	141	0.94
55 Pentachlorobenzene	?	8.947	-0.048	250	121353	248	0.85
76 Propoxur	x	10.353	-0.050	110	212997		0.99
82 Diphenylamine	x	10.516	-0.056	169	257621		0.94
92 Chlorprotham	?	11.045	-0.034	127	81328	153,154	0.75
102 Bendiocarb	?	11.540	-0.040	151	94050	166	0.85
103 Trifluralin	x	11.637	-0.011	306	41880		0.93
104 Benfluralin	x	11.725	-0.013	292	62933		0.96
111 Phorate	?	11.962	-0.042	75	63143	121,260	0.88
113 BHC alpha isomer	?	12.084	-0.045	181	46666	219,183,217	0.60
117 Hexachlorobenzene	?	12.377	-0.055	284	91832	282,288	0.00

Figure 10. Typical report from the GC/MS pesticide screener showing probable "hits" (marked with an x) and possible hits (marked with a ?). Other information includes the library retention time followed by the RT difference in this chromatogram, the target ion, its abundance, out of range qualifier(s), and a cross correlation value with the library spectrum.

Conclusions

Using the information (compound names, retention times, and ion masses) in the RTL pesticide database, a SIM method of 80 target compounds can be created in less than 2 hours without running any analyses. The examples show that both LVI and SIM are effective techniques to decrease the quantitation limit of target compounds from sub-ppm to ppt.

Any lab can decrease the quantitation limit by a factor of 100 without any hardware modification. Lowering the quantitation limit from 500 pg down to 5 pg on column can be done using a SIM method and RTL. By adding LVI to the system, target compounds in femtogram/ μ L can be quantified.

Acknowledgement

The author would like to acknowledge Alex Chung and Mark Lee at CDFA for providing the pesticide mixture used in this study.

References

1. Vince Giarrocco, Bruce Quimby, and Matthew S. Klee, *Retention Time Locking: Concepts and Applications*, Agilent Technologies Application note, 5966-2469E, printed March 2000, www.agilent.com/chem
2. Bill Wilson, Philip L. Wylie, and Matthew S. Klee, *Large Volume Injection for Gas Chromatography Using a PTV Inlet*, Agilent Technologies Application note, 5965-7770E, printed February 2000, www.agilent.com/chem

3. Philip L. Wylie, *Trace Level Pesticide Analysis by GC/MS Using Large-Volume Injection*, Agilent Technologies Application note, 5966-1214E, printed April 2000, www.agilent.com/chem
4. Prest, H. and P. Cormia, *Retention Time Locking: Advantages in GC/MS SIM Analysis*, Agilent Technologies Application Note, 5968-3797E, printed December 1999, www.agilent.com/chem
5. Harry Prest, Philip L. Wylie, Ken Weiner, and Doug Agnew, *Efficient Screening for Pesticides and Endocrine Disrupters Using the 6890/5973 GC/MSD System*, Agilent Technologies Application note, 5968-4884E, printed December 1999, www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2001

Printed in the USA
November 14, 2001
5988-4392EN



Agilent Technologies



Analysis of Simazine, Thiobencarb, and Thiuram by Liquid Chromatography/Mass Spectrometry Application

Environmental

Author

Hiroki Kumagai

Abstract

A liquid chromatography/mass spectrometry method using electrospray ionization in positive ion mode was successfully applied to the sensitive and simultaneous determination of the pesticides Simazine, Thiobencarb, and Thiuram.

Background

In recent years, the potential contamination of water supplies by runoff of many kinds of pesticides from golf courses and agricultural fields has become a societal problem. Many governments have established guidelines for pesticide use and water quality standards to limit such contamination. In Japan, the concentration limits in drinking water for the pesticides Simazine, Thiobencarb, and Thiuram are 3, 20, and 6 ppb, respectively.

Typically, gas chromatography-mass spectrometry (GC/MS) is used to determine Simazine and Thiobencarb in drinking water, while Thiuram is determined by high-performance liquid chromatography (HPLC) with ultraviolet (UV) detection. However, the Thiuram method used to date has problems with both selectivity and sensitivity. A better method of analysis is needed for this chemical. Such a method is described below.

Method

- Instrument: Agilent 1100 Liquid Chromatograph/Mass Spectrometer (LC/MS) with electrospray ionization (ESI) positive ion mode
Drying gas: N₂ (8 L/min, 350 °C)
Nebulizer: N₂ 40 psi
Fragmentor: 40 V (Thiuram), 70 V
Mass range: 100–500 amu

• LC Conditions:

Mobile phase A: CH₃OH/30 mM CH₃COONH₄ (50/50)

Mobile phase B: CH₃OH

Gradient: 0 % to 100 % B in 20 min

Flow rate: 0.2 mL/min

Oven temperature: 40 °C

Injection volume: 50 µL

- Column: Inertsil ODS3, 3.1 mm id × 250 mm long × 5 µm

Sample Analysis

All three pesticides were determined simultaneously using the Agilent 1100 LC/MS. The following figures illustrate both the sensitivity and applicability of this method.




Figure 1. Total ion chromatogram of target pesticides, each at 5 ng.



Agilent Technologies




Figure 2. Mass spectra of target pesticides.




Figure 3. SIM chromatograms of target pesticides.

Conclusion

The LC/MS method described above is suitable for the simultaneous determination of the pesticides Simazine, Thiuram, and Thiobencarb. The peaks are well separated with detection limits of 0.02, 2.5, and 1 ppb, respectively, approximately 1/10 of the Japanese concentration limits.

Hiroki Kumagai is an application chemist at Agilent/Yokogawa Analytical Systems, Tokyo, Japan.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright© 2001
© Agilent Technologies, Inc.

www.agilent.com/chem


Printed in the USA
October 18, 2001
5988-4233EN



Agilent Technologies

The Analysis of Organophosphate Pesticides by LC/MS

Application



LC-MS

Authors

Paul Zavitsanos
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Paul Yang
MOE
Ontario Canada

Lorna Grey
MOE
Ontario Canada

Abstract

Organophosphate pesticides were readily analyzed using liquid chromatography-mass spectrometry with electrospray ion source. Sensitivity and selectivity were significantly better than using a diode-array UV detector.

Overview

Liquid chromatography-mass spectrometry (LC-MS) is rapidly becoming a routine technique for efficient trace analysis of polar pesticides in various types of samples. In comparison to existing methodologies, such as gas chromatography-mass spectrometry (GC-MS) and ultraviolet (UV) detection, LC-MS considerably simplifies cleanup procedures, reducing both time of analysis and method development time.¹

LC-MS with an electrospray ion (ESI) source avoids the thermal degradation of labile pesticides encountered with GC and eliminates the need for preliminary derivatization to increase compound volatility.

Additionally, LC-MS provides unequivocal identification of each pesticide, even if the pesticide was not completely resolved from neighboring eluants. Traditional UV detection cannot provide the required specificity because many of the pesticides within the same class exhibit similar UV spectra.

Sample case

A mixture of organophosphate pesticides and an internal standard were analyzed using an Agilent 1100 LC/MS with an ESI source (Table 1).

Table 1. Mixture of Organophosphate Pesticides

Elution order	Compound	[M+H] ⁺	Concentration µg/mL
1	Mevinphos isomer 1	225	0.2
2	Dimethoate	230	0.5
3	Mevinphos isomer 2	225	0.5
4	Dichlorvos	221	0.5
5	Azinphos methyl	318	0.05
6	Parathion methyl	264	0.2
7	Malathion	331	0.5
8	Diazinon	305	0.2
9	Triphenyl orthophosphate*	327	1.0
10	Parathion ethyl	292	0.1
11	Phorate	261	0.1
12	Reldan	322	0.5
13	Ronnel	321	0.1
14	Terbuphos	289	0.2
15	Dursban	350	0.1
16	Ethion	385	0.2
17	Temephos	467	0.1

* Internal standard



Agilent Technologies

Method summary

- Column 2.1 mm id × 5 cm long, filled with 3.5 μm particles, C18 chemistry
- 20 mM ammonium acetate vs. acetonitrile mobile phase gradient
 - 5 % to 95 % acetonitrile in 4 minutes
 - Hold 2 minutes
- Splitless 400 $\mu\text{L}/\text{min}$ flow
- 3 μL injection volume
- Scan data 120 to 600 m/z
- SIM data as per Table 1. 95 msec dwell/ion in two groups

Results

Simultaneous UV (220 nm) and MS detector outputs are compared in Figure 1. The MS plot is a composite of all the individual extracted ion chromatograms. Each was obtained at the $[\text{M}+\text{H}]^+$ value given in Table 1, and are separated and stacked in Figure 2 for easy comparison.




Figure 1. Comparison of UV and MS chromatograms.




Figure 2. Stacked normalized extracted ion chromatograms for compounds 1 through 17.

Figures 3 through 6 show the resulting normalized mass ion spectra for each compound included in Table 1.




Figure 3. Stacked normalized ion mass spectra for compounds 1 through 4.




Figure 4. Stacked normalized ion mass spectra for compounds 5 through 8.




Figure 5. Stacked normalized ion mass spectra for compounds 9 through 12.




Figure 6. Stacked normalized ion mass spectra for compounds 13 through 17.

Conclusions

When determining organophosphate pesticides using LC-MS with an ESI source:

- All the tested organophosphate pesticides ionized well and gave definite $[M+H]^+$ ions
- Sensitivity and selectivity are significantly better than using diode-array UV detector
- Overall chromatography and analysis is simple and straightforward
- Positive identification and quantification are performed using integrated software

For more information, contact your local Agilent sales representative, or visit www.agilent.com.

Reference

1. Elbert Hogendoorn and Peit van Zoonen, *Journal of Chromatography A*, 892 (2000) 435-453.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright© 2001
© Agilent Technologies, Inc.

Printed in the USA
September 13, 2001
5988-3774EN



Fast Screening of Pesticides and Endocrine Disruptors Using the Agilent 6890/5973N GC/MSD System, Part II



Application

Gas Chromatography
May 2000

Authors

C. Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, Delaware 19808-1610
USA

Michael J. Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent Technologies' new, fast GC/MSD method can significantly speed up the screening of pesticides. Agilent's GC Method Translation software (available free from the Agilent Technologies Web site, <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#mxlator>) was used in developing the new method based on the standard 42-min method. A 15 m × 0.25 mm × 0.25 μm Agilent HP-5MS column was used to increase analysis speed up to fourfold. The time savings were implemented in increments (down to 10.5 minutes) to verify the predictability of scaling and the effect of scaling on the signal-to-noise ratio.

Key Words

RTL, pesticide, environmental, screening, fast GC, method translation, 5973, 6890, MTL

Introduction

Analysts want faster analyses to improve laboratory productivity. Often, when speeding up GC methods, an analyst will trade resolution for increased analysis speed. This loss of resolution can complicate peak identification, even with a mass selective detector (MSD).

Agilent Technologies has developed new techniques to solve the peak identification problem based on Agilent's retention time locking (RTL) and a new mass spectral library that contains the locked retention times and characteristic ions

for 567 of the most common pesticides and endocrine disruptors of concern worldwide. A GC/MSD method was developed based on the standard 42-min method¹ to screen for all 567 of the most common analytes. A specific combination of column stationary phase, carrier gas flow rate, and oven temperature programming is required to lock all the compounds to an expected retention timetable². Compound identification based only on spectral searching alone is difficult when analyzing extracts containing significant sample matrix content because of overlapping peaks and noisy baselines.

The new screening tool, integrated within Agilent's ChemStation for MSD, searches for all 567 compounds. It first checks and integrates four characteristic ions within the expected time window and then prints a report showing "hits" and "possible hits" (ratios of characteristic ions that do not match the expected values in the library within specified limits).

In Part I of the MSD fast screening application brief³, a 10 m × 0.1 mm × 0.1 μm Agilent HP-5 column was used to increase analysis speed up to fourfold. In this application brief, a 15 m × 0.25 mm × 0.25 μm Agilent HP-5MS column was used. The faster methods were scaled exactly as predicted by using a combination of Agilent's method translation (MTL) and RTL software. Because scaling was exact, these faster methods can be used with precisely-scaled pesticide libraries, making the screening process even more powerful and adaptable to individual needs.



Agilent Technologies

Innovating the HP Way

Experimental

The GC method translation software tool was used to find operating conditions for the faster methods. Figure 1 is a screen capture of MTL software data entry showing the original conditions and the new chromatographic conditions for a fourfold speed gain. The column flow rate, which is helpful to avoid exceeding MSD pumping capacity⁴, also is found in the table. In this study, a turbo pump was used, which could handle the 3.8 mL/min carrier flow. The program also determined the required column head pressure and corresponding oven ramp. The Agilent 6890 GC fast oven option (220/240V in the U.S.) was required for the faster oven ramp used in this study.

General chromatographic conditions are listed in table 1. The standard used was a mixture of 26 pesticides at 10 ppm. A 15 m × 0.25 mm × 0.25 µm Agilent HP-5MS column (part number 19091S-431) was used. The head pressure determined by the method translation software (18 psi) was used as the starting point for retention time locking. The column head pressure required to lock retention times of the compounds to the library (the original retention time divided by 4) was determined using the automated RTL process integrated within the Agilent ChemStation for MSD.

GC Method Translation - 15M-4X.MXD

Criterion: ☐ Translate Only ☐ Best Efficiency ☐ Fast Analysis ☒ None Speed gain: 4.00000

		Original Method	Translated Method																																				
Column Length,	m	30.00	☐ 15.00																																				
Internal Diameter,	µm	250.0	☐ 250.0																																				
Film Thickness,	µm	0.250	☐ Unlock																																				
Phase Ratio		250.0	☐ 0.250																																				
			☒ 250.0																																				
Carrier Gas		Helium	Helium																																				
Enter one Setpoint			☒ Unlock																																				
Head Pressure,	psi	18.000	☐ 18.000																																				
Flow Rate,	mL/min	1.9015	☐ 3.8030																																				
Outlet Velocity,	cm/sec	Very large	Very large																																				
Average Velocity,	cm/sec	50.30	☐ 100.60																																				
Hold-up Time,	min	0.994049	☐ 0.248512																																				
Outlet Pressure (absolute),	psi	0.000	☒ 0.000																																				
Ambient Pressure (absolute),	psi	14.696	☒ 14.696																																				
Oven Temperature	3-ramp Program																																						
		<table border="1"> <thead> <tr> <th>Ramp Rate</th> <th>Final Temp.</th> <th>Final Time</th> </tr> <tr> <th>°C/min</th> <th>°C</th> <th>min</th> </tr> </thead> <tbody> <tr> <td></td> <td>70.00</td> <td>2.000</td> </tr> <tr> <td>25.000</td> <td>150.00</td> <td>0.000</td> </tr> <tr> <td>3.000</td> <td>200.00</td> <td>0.000</td> </tr> <tr> <td>8.000</td> <td>280.00</td> <td>10.000</td> </tr> </tbody> </table>	Ramp Rate	Final Temp.	Final Time	°C/min	°C	min		70.00	2.000	25.000	150.00	0.000	3.000	200.00	0.000	8.000	280.00	10.000	<table border="1"> <thead> <tr> <th>Ramp Rate</th> <th>Final Temp.</th> <th>Final Time</th> </tr> <tr> <th>°C/min</th> <th>°C</th> <th>min</th> </tr> </thead> <tbody> <tr> <td></td> <td>70.00</td> <td>0.500</td> </tr> <tr> <td>100.000</td> <td>150.00</td> <td>0.000</td> </tr> <tr> <td>12.000</td> <td>200.00</td> <td>0.000</td> </tr> <tr> <td>32.000</td> <td>280.00</td> <td>2.500</td> </tr> </tbody> </table>	Ramp Rate	Final Temp.	Final Time	°C/min	°C	min		70.00	0.500	100.000	150.00	0.000	12.000	200.00	0.000	32.000	280.00	2.500
Ramp Rate	Final Temp.	Final Time																																					
°C/min	°C	min																																					
	70.00	2.000																																					
25.000	150.00	0.000																																					
3.000	200.00	0.000																																					
8.000	280.00	10.000																																					
Ramp Rate	Final Temp.	Final Time																																					
°C/min	°C	min																																					
	70.00	0.500																																					
100.000	150.00	0.000																																					
12.000	200.00	0.000																																					
32.000	280.00	2.500																																					
Sample Information	Liquid		☐ Unlock																																				
Injected Volume,	µL	1.0	☒ 1.0																																				
Split Ratio		0.00	☐ 0.41																																				
Effective on-Column Volume,	µL	1.0	0.71																																				
Nominal Column Capacity,	µL	0.017	0.012																																				

Figure 1. Screen capture showing the method translation (MTL) software data entry used in a 4X speed gain translation.

This process (first translate the method then lock the retention times) was repeated for the 2.5X time reductions.

Figure 2 shows the results of the shortened analysis times. The three chromatograms look extremely similar, except that the time axis is scaled proportionally. Because MTL followed by RTL scales methods very precisely, scaled screening libraries for corresponding time reductions can be obtained by dividing the retention times in the library by the speed gain (which does not have to be an integer). Using the same injection method (1- μ L splitless), the peak heights of the faster runs were twice those from the original

Table 1 Chromatographic Conditions

Speed	Onefold	Two and a half fold	Fourfold
GC	110 V	220/240 V	
Column	30 m × 0.25 mm × 0.25 μm HP-5MS (P/N 19091S-433)	15 m × 0.25 mm × 0.25 μm HP-5MS (P/N 19091S-431)	
Injection mode	Splitless	Splitless	
Column head pressure	18.0 psi	5.74 psi	18.0 psi
Column flow (mL/min)	1.9	1.49	3.8
Inlet control mode	Constant pressure	Constant pressure	
Carrier gas	Helium	Helium	
Injector Temp.	250 °C	250 °C	
Oven Temp.	70 (2 min)	70 (0.8 min)	70 (0.5 min)
Ramp 1	25 °C/min	62.5	100
	150 (0 min)	150 (0 min)	150 (0 min)
Ramp 2	3 °C/min	7.5	12
	200 (0 min)	200 (0 min)	200 (0 min)
Ramp 3	8 °C/min	20	32
	280 (10 min)	280 (4 min)	280 (2.5 min)
Oven equilibration	2 min	2 min	
Injection volume	1 μL	1 μL	
Liner	5183-4647	5183-4647	
MS Conditions (Turbo pump)			
Solvent delay	3 min	1.44 min	0.9 min
Tune file	Atune.u	Atune.u	
Low mass	35 amu	35 amu	
High mass	500 amu	450 amu	
Threshold	150	250	
Sampling	2	2	1
Scans/sec	3.15	3.50	6.54
Quad Temp.	150 °C	150 °C	
Source Temp.	230 °C	230 °C	
Transfer line Temp.	280 °C	280 °C	
Acquisition mode	Scan (EI)	Scan (EI)	

analysis. A faster oven ramp and the shorter column made the peaks narrower and higher, so an improvement in the signal-to-noise ratio is realized with the faster methods.

Conclusion

The highly accurate and reproducible pressure and temperature control of the Agilent 6890 GC allows precise scaling of the standard 42-min GC/MSD pesticide method. Run time was shortened to 10.5 minutes using a fast oven ramp rate and a 15-meter, 250-micron column. The combination of MTL and RTL facilitated scaling and yielded exact scaling. RTL libraries can be scaled accurately to correspond to the faster analyses.

References

1. B. D. Quimby, L.M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking," Application Note 228-401, Agilent publication number 5967-5820E, May 1998.
2. H. Prest, P. L. Wylie, K. Weiner, and D. Agnew, "Efficient Screening for Pesticides and Endocrine Disruptors Using the HP 6890/5973 GC/MSD System," Agilent publication number 5968-4884E, April 1999.
3. C. K. Meng and M. Szelewski, "Fast Screening of Pesticide and Endocrine Disruptors Using the Agilent 6890/5973N GC/MSD System," Agilent publication number 5968-9220, January 2000.
4. H. Prest, "GC Column Selection and Pumping Considerations for Electron and Chemical Ionization MSD operation," Agilent publication number 5968-7958E, November 1999.




Figure 2. The TICs of the 2.5X and 4X speedups. The standard analysis (1X) was 42 minutes long.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright ©2000
Agilent Technologies, Inc.

Printed in the USA 5/00
5980-1057E



Agilent Technologies
Innovating the HP Way

Fast Screening of PCB Congeners Using the Agilent 6890/5973N GC/MSD System



Application

Gas Chromatography

May 2000

Authors

C. Kai Meng
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Michael J. Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Agilent Technologies' fast GC/MSD method can significantly speed up the screening of PCB congeners. Agilent's GC method translation software (available free from the Agilent Technologies Web site, <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#mxlator>) was used in developing the new method based on a standard 42-min method. A 15-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS column was used to increase analysis speed up to four-fold. The time savings were implemented in increments (down to 10.5 minutes) to verify the predictability of scaling and the affect of scaling on the signal-to-noise ratio.

Key Words

RTL, PCB, polychlorinated biphenyls, congeners, environmental, screening, fast GC, method translation, 5973, 6890, MTL

Introduction

Polychlorinated biphenyls (PCBs) are a group of 209 individual compounds (known as congeners) with varying harmful effects. Chronic (long term) exposure to some PCB formulations by inhalation in humans results in respiratory tract symptoms, gastrointestinal effects, mild liver effects, and effects on the skin and eyes such as chloracne, skin rashes, and eye irritation.

PCBs are no longer produced in the United States and are no longer used in the manufacture of new products. Smaller amounts of PCBs may be released to the air from disposal sites containing transformers, capacitors, and other PCB wastes, incineration of PCB-containing wastes, and improper disposal of the compounds to open areas. Today, PCBs are still detected in water and soil due to the environmental recycling of the compound. PCBs have been detected in foods and they bio-accumulate through the

food chain, with some of the highest concentrations found in fish.

The analysis of PCBs normally is accomplished using GC with an electron-capture detector (ECD). Because of the drastically different toxicity of the different congeners, it is of great interest to identify the individual congeners using a mass spectrometer (MS).

Agilent Technologies has developed techniques to solve the peak identification problem based on Agilent's retention time locking (RTL) and a mass spectral library that contains the locked retention times and characteristic ions for all 209 PCB congeners. A GC/MSD method was developed based on a standard 42-min method¹ to screen for all congeners. A specific combination of column stationary phase, carrier-gas flow rate, and oven temperature programming is required to lock all the compounds to an expected retention timetable². Compound identification based only on spectral searching alone is difficult when the isomers have the same mass spectra.

The screening tool, integrated within Agilent's ChemStation for MSD software, searches for all 209 congeners by first checking and integrating the



Agilent Technologies

Innovating the HP Way

expected target ion within the expected time window. If the target ion is found, the software will then search and integrate the three qualifier ions within the expected time window. Last, the software will print out a report showing "hits" and "possible hits" (ratios of characteristic ions that do not match the expected values in the library within specified limits).

In order to improve laboratory productivity, we scaled the method for four-fold speed-up. While a 30-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS column is used for standard speed, a 15-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS column is used for the four-fold speed. These faster methods were able to be scaled exactly as predicted by using a combination of Agilent's method translation (MTL) and RTL software.

Often, when speeding up GC methods, an analyst trades resolution for increased analysis speed. This loss of resolution can complicate peak identification, even with a mass selective detector (MSD). However, because scaling was exact, the faster methods can be used with precisely scaled congener libraries, making the screening process even more powerful and adaptable to individual needs.

Experimental

The GC method translation software tool was used to find operating conditions for the faster methods. Figure 1 is a screen capture of the MTL software data entry showing the original conditions and the new chromatographic conditions for a four-fold speed gain. The column flow rate, which is helpful to avoid exceeding MSD pumping capacity³, also is found in the table. In this study, a turbo pump that could handle the 3.8 mL/min carrier flow was used. The program also determined the required column head pressure and corresponding oven ramp. The Agilent 6890 GC fast oven option (220/240V in the U.S.) was required

GC Method Translation - 15M-4X.MXD

Criterion: ☐ Translate Only ☐ Best Efficiency ☐ Fast Analysis ☒ None Speed gain: 4.00000

		Original Method	Translated Method	
Column				
Length,	m	30.00	☐ 15.00	
Internal Diameter,	μ m	250.0	☐ 250.0	
Film				
Thickness,	μ m	0.250	☐ 0.250	
Phase Ratio		250.0	☒ 250.0	
Carrier Gas				
Enter one Setpoint		Helium	Helium	
Head Pressure,	psi	18	☐ 18.000	
Flow Rate,	mL/min	1.9015	☐ 3.8030	
Outlet Velocity,	cm/sec	Very large	Very large	
Average Velocity,	cm/sec	50.30	☐ 100.60	
Hold-up Time,	min	0.994049	☐ 0.248512	
Outlet Pressure (absolute),	psi	0.000	☒ 0.000	
Ambient Pressure (absolute),	psi	14.696	☒ 14.696	
Oven Temperature 3-ramp Program				
	Initial	Ramp Rate	Final Temp.	Final Time
		$^{\circ}$ C/min	$^{\circ}$ C	min
	Ramp 1	25.000	150.00	0.000
	Ramp 2	3.000	200.00	0.000
	Ramp 3	8.000	280.00	10.000
		100.000	150.00	0.500
		12.000	200.00	0.000
		32.000	280.00	2.500
Sample Information Liquid				
Injected Volume,	μ L	1.0	☐ 1.0	
Split Ratio		0.00	☐ 0.41	
Effective on-Column Volume,	μ L	1.0	0.71	
Nominal Column Capacity,	μ L	0.017	0.012	

Figure 1. Screen capture showing the method translation (MTL) software data entry used in a 4X speed-gain translation.

for the faster oven ramp used in this study.

General chromatographic conditions are listed in Table 1. The RTL standard used was a mixture of pesticides and PCB congeners at 10 ppm. A 15-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS column (part number 19091S-431) was used. The head pressure determined by the method translation software (18 psi) was used as the starting point for retention time locking. The column head pressure required to lock retention times of the compounds to the library (the original retention time divided by four) was determined using the automated RTL process integrated within the Agilent ChemStation for MSD.

A very important modification to the

MS method is changing the default values of "Use mass range from" to **-0.50 to +0.50** amu (the default values are -0.3 to +0.7). The changes can be made from the "Extracted Ion Chromatograms..." dialog box selected from the "Chromatogram" on the menu bar.

Figure 2 shows the results of the shortened analysis times. The two chromatograms look extremely similar, except that the time axis is scaled proportionally. It is interesting to note that the last peak in the 4X analysis came out *before the first peak of the 1X analysis*. Because MTL followed by RTL scales methods very precisely, scaled screening libraries for corresponding time

reductions can be obtained by dividing the retention times in the library by the speed gain (which does not have to be an integer).

Conclusion

The highly accurate and reproducible pressure and temperature control of the Agilent 6890 GC allows precise scaling of a standard 42-min GC/MSD method. The run time was shortened to 10.5 minutes using a fast oven ramp rate and a 15-meter 250-micron column. The combination of MTL and RTL facilitated scaling and yielded exact scaling. RTL libraries can be scaled accurately to correspond to the faster analyses. The GC/MSD conditions used are the same as the fast pesticide method⁴, which allows for screening pesticides and PCB congeners in a single analysis.

References

1. B. D. Quimby, L.M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking," Application Note 228-401, Agilent publication number 5967-5820E, May 1998.
2. H. Prest, P. L. Wylie, K. Weiner, and D. Agnew, "Efficient Screening for Pesticides and Endocrine Disruptors Using the HP 6890/5973 GC/MSD System," Agilent publication number 5968-4884E, April 1999.
3. H. Prest, "GC Column Selection and Pumping Considerations for Electron and Chemical Ionization MSD operation," Agilent publication number 5968-7958E, November 1999.
4. C. Kai Meng and Michael Szelewski, "Fast Screening of Pesticides and Endocrine Disruptors Using the Agilent 6890/5973N GC/MSD System, Part II", Agilent publication number 5980-1057E, May 2000.

Table 1. Chromatographic Conditions

Speed	Standard	Four-fold
GC	110 V	220/240 V
Column	30-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS (part number 19091S-433)	15-m $\times$ 0.25-mm $\times$ 0.25- μ m Agilent HP-5MS (part number 19091S-431)
Injection mode	Splitless	Splitless
Column head pressure	18.0 psi	18.0 psi
Column flow (mL/min)	1.9	3.8
Inlet control mode	Constant pressure	Constant pressure
Carrier gas	Helium	Helium
Injector Temperature	250 °C	250 °C
Oven Temperature	70 (2 min)	70 (0.5 min)
Ramp 1	25 °C/min	100
	150 (0 min)	150 (0 min)
Ramp 2	3 °C/min	12
	200 (0 min)	200 (0 min)
Ramp 3	8 °C/min	32
	280 (10 min)	280 (2.5 min)
Oven equilibration	2 min	2 min
Injection volume	1 μ L	1 μ L
Liner	5183-4647	5183-4647

MS Conditions (Turbo pump)		
Solvent delay	3 min	0.9 min
Tune file	Atune.u	Atune.u
Low mass	50 amu	50 amu
High mass	550 amu	550 amu
Threshold	200	200
Sampling	3	1
Scans/sec	1.52	5.56
Quad Temperature	150 °C	150 °C
Source Temperature	230 °C	230 °C
Transfer line Temperature	280 °C	280 °C
Acquisition mode	Scan (EI)	Scan (EI)




Figure 2. The TICs of the standard speed and fast (4X) analyses. The standard analysis (1X) was 42 minutes long.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 5/2000
5980-1472E



Agilent Technologies
Innovating the HP Way



Validation Analysis of EPA CLP Target Organochlorine Pesticides with the Agilent 6890 Series GC and Micro-ECD

Application

Gas Chromatography

February 1998

Authors

Imogene L. Chang and
Matthew S. Klee
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Joseph Murphy
Roy F. Weston Company
Lionville Laboratory
Exton, PA 19341
USA

Abstract

Generating environmental data for organochlorine pesticides in various matrices can be time-consuming for laboratories and engineering firms. To keep a gas chromatograph/electron capture detector (GC/ECD) system operating within control limits, precious analytical time must be spent on tasks such as recalibration, reinjection of samples, detector cleaning, and reintegration of chromatographic peaks. These tasks take time away from running billable samples and adversely affect laboratory throughput.

The Agilent 6890 Series Micro-ECD used in this study shows improved performance in several key areas:

increased linear working range (greater than 4 orders of magnitude for some components), increased sensitivity (organochlorine pesticides at sub-ppb levels), increased stability, and increased resistance to contamination.

Introduction

Organochlorine pesticides (OCPs) and polychlorinated biphenyls (PCBs) are found worldwide in the environment. Because many of these pesticides are suspected to be carcinogenic and/or endocrine hormone disrupters^{1,2}, determination of their presence in water, air, soil, and food is required by governmental agencies such as the U.S. EPA, the FDA, and the World Health Organization.

The U.S. EPA provides several comprehensive guidelines^{3,4} and regulations^{5,6} for analysis of OCPs and PCBs by gas chromatography with electron capture detectors (GC/ECD). These include EPA method 8081 for wastewater/solid wastes, EPA methods 505 and 508 for drinking water/water supplies, EPA method 608 for municipal and industrial discharges, and the Contract Laboratory Program (CLP) method for waste/clean-up sites. Most contract laboratories competing for the large number of potential CLP

samples find that competition is strong and profit margins very low compared with other environmental methods.

CLP methods have very specific performance criteria that can be very time-consuming for laboratories to meet consistently. To keep a GC/ECD system operating within control limits, precious analytical time must be spent on tasks such as recalibration, reinjection of samples, detector cleaning, reintegration of chromatographic peaks, etc. Spending too much time with any of these tasks takes time away from running billable samples, and adversely affects the throughput and profitability of the laboratory.

In this study, the 6890 Series Micro-ECD greatly reduced the time required to meet CLP quality control criteria for CLP analysis of OCPs and PCBs. Validated results show four key improvements: increased linear working range (greater than 4 orders of magnitude), increased sensitivity (detecting OCPs at sub-ppb level), more stable calibration, and increased resistance to contamination (more robust, fast detector recovery and reduced maintenance).



Agilent Technologies

Innovating the HP Way

Experimental

Water and soil samples were extracted after spiking with surrogates tetrachloro-m-xylene (TCX) and decachlorobiphenyl (DBC). Extracts of OCPs were analyzed in accordance with EPA CLP method OLM03.1⁶. Typically, a 1-L volume of water sample was extracted with methylene chloride by liquid-liquid extraction or a 30-g aliquot of soil/sediment sample extracted with 1:1 acetone/methylene chloride by sonication. These extracts were concentrated and solvent-exchanged into a 10-mL volume of hexane.

Working standards for checking linearity and CLP QA/QC criteria were prepared from certified standards (available commercially) in hexane, as described in the CLP method⁵.

All analyses were performed using a 6890 Series GC with an automatic liquid sampler, a single split/splitless inlet, a pair of primary and confirmatory columns, and two 6890 Micro-ECDs. Instrument conditions are listed in table 1.

A sample extract or working standard (1 μ L) was injected into the 6890 Series GC in the splitless mode. A guard column (equivalent to a 5-m retention gap, part no. 19095-60610) was used. It was connected to a "Y" glass butt connector that split the sample equally between the pair of columns.

Column A (an equivalent of the Agilent HP-608 column) was used as the primary analytical column, and column B (an equivalent of the Agilent HP-1701 column) was used as the confirmatory column, in accordance with the CLP method.

In the case of poor chromatography or a failing control limit for inlet degradation, routine maintenance was performed. This involved changing the inlet septum, installing a new inlet liner, and clipping a short piece of the retention gap. Columns were routinely conditioned to remove late-eluting column contaminants. When CLP criteria could not be met after routine maintenance, columns were replaced with new columns of the same type.

Results and Discussion

Sensitivity

Figures 1 and 2 show chromatograms of CLP target organochlorine pesticides on column A using the GC conditions listed in table 1. All 20 OCPs in the midpoint calibration standards (mix A and mix B) were baseline resolved with both the primary analytical column (column A) and the confirmation column (column B, shown in figure 3). The amount of individual OCPs in the midpoint calibration standard was 20–40 pg on-column (methoxychlor was 200 pg). Table 2 lists the concentration of midpoint calibration standards, peak identification, and the Contract Required Quantitation Limits (CRQLs)⁶ for all CLP target OCPs.

Table 1. Experimental Conditions

Sampler	Agilent 7673, 10- μ L syringe, 1- μ L injection
Inlet	Split/splitless; 200 °C, pulsed splitless mode (28 psi for 1 min)
Carrier	Helium, 16.8 psi (150 °C); 3.5 mL/min constant flow (each column)
Column	(1) 30 m, 0.53 mm id, 0.8- μ m film DB-608, an equivalent of Agilent HP-608 (part no. 19095S-023) (2) 30 m, 0.53 mm id, 1.0- μ m film RTX-1701, an equivalent of Agilent HP PAS-1701 (part no. 19095S-123)
Oven	150 °C (0.5 min); 5 °C/min to 280 °C (5–15 min).
Detector	330 °C; makeup gas: nitrogen, constant column and makeup flow (60 mL/min)

Figures 1 and 2 also show good responses for dilute OCPs (0.25–0.5 pg on-column, 1/20th of the concentration of those for CRQLs). Quantitation at this level was easy with the micro-ECD; most OCPs exhibited a signal-to-noise ratio greater than 10 (see the lower chromatograms in figures 1 and 2). These results, confirmed by column B and the second micro-ECD (see figure 3), show that the 6890 Series Micro-ECD can easily detect low levels of OCPs (lower than 1/20 of those required by CLP). This is in good agreement with Chang⁷, who reported detection of OCPs as low as 0.050 pg on-column. However, detection of this low level is not necessary because the CRQLs⁵ range from 5 to 10 pg (methoxychlor at 50 pg) on-column (see table 2).




Figure 1. Pesticides in CLP calibration mix A on the primary column (A). 20 pg/μL (upper chromatogram) and 0.25 ng/μL (lower chromatogram) for methoxychlor (peak 9).




Figure 2. Pesticides in CLP calibration mix B on the primary column (A).

To ensure reliable results, three-point initial calibrations were routinely performed in accordance with CLP requirements using standards of 5, 20, and 80 pg/μL for lindane. Table 2 lists typical response factors and percent relative standard deviation (% RSD) for all CLP target OCPs. Typical % RSDs ranged from 2 percent for beta-BHC to 14 percent for endrin aldehyde, easily meeting the CLP criterion of 20.0 percent or less over the CLP calibration range.

Micro-ECD Linearity

Although classical electron capture detectors can provide sensitive detection, they are notorious for nonlinear response toward OCPs. For example, linearity is problematic for isomers of BHCs, particularly at the high concentration level. On the other hand, linearity as well as low response is problematic for methoxychlor, particularly at the low concentration level. These problems were not encountered using the 6890 Series GC system with micro-ECDs.




Figure 3. Pesticides on the confirmatory column (B). 20 to 40 pg/μL each, 200 pg/μL for methoxychlor.

Table 2. CLP Target Organochlorine Pesticides and Responses

	Peak	Pesticides	Mid-Level Standard pg/μL (4X)	CRQLs (on column) pg	Response Factors*	
					Average (peak height)	% Relative Standard Deviation
Mix A	1	alpha-BHC	20	5	23052	10.90
	2	gamma-BHC(lindane)	20	5	21729	6.51
	3	Heptachlor	20	5	17661	3.40
	4	Endosulfan I	20	5	15536	2.68
	5	Dieldrin	40	10	16204	4.83
	6	Endrin	40	10	10515	4.54
	7	4,4'-DDD	40	10	14334	5.06
	8	4,4'-DDT	40	10	12418	7.65
	9	Methoxychlor	200	50	4652	5.55
	21	TCX	20	50	16567	2.13
Mix B	22	DCB	40	10	5752	14.73
	10	beta-BHC	20	5	16190	2.40
	11	delta-BHC	20	5	10586	5.40
	12	Aldrin	20	5	20609	11.58
	13	Heptachlor epoxide	20	5	16482	7.01
	14	alpha-Chlordane	20	5	15929	5.20
	15	gamma-Chlordane	20	5	16527	5.69
	16	4,4'-DDE	40	10	15913	5.29
	17	Endosulfan II	40	10	16791	9.52
	18	Endrin aldehyde	40	10	8453	14.20
	19	Endosulfan sulfate	40	10	8926	5.59
	20	Endrin ketone	40	10	2144	3.39
	21	TCX	20	5	10114	3.01
	22	DCB	40	10	5667	14.97

* Typical three-point calibration from column A (concentrations: 1X, 4X, and 16X)

Linearity of the micro-ECD was determined by analyzing a series of dilutions of OCPs at concentrations ranging from 0.1 pg/μL to 3.2 ng/μL for lindane (see the 15-level calibration in table 3). For most OCPs, correlation coefficients were better than 0.99 over a concentration range greater than 5 orders of magnitude (0.1 to 3.2 pg/μL for lindane).

Table 3. Linearity Study

Pesticides		15-Point Calibration		10-Point Calibration			
		Concentration pg/μL	Correlation Coefficients	Concentration pg/μL	Response Factors		Correlation Coefficients
					Average	% Relative Standard Deviation	
Mix A	alpha-BHC	0.1 to 32,000	0.995	1 to 1,600	52,557	19.3	0.998
	Lindane	0.1 to 32,000	0.997	1 to 1,600	46,635	17.3	0.997
	Heptachlor	0.1 to 32,000	0.997	1 to 1,600	35,712	18.0	0.997
	EndosulfanI	0.1 to 32,000	0.997	1 to 1,600	31,858	13.9	0.998
	Dieldrin	0.2 to 64,000	0.995	2 to 3,200	35,718	19.0	0.995
	Endrin	0.2 to 64,000	0.992	2 to 3,200	24,849	19.5	0.996
	4,4'-DDD	0.2 to 64,000	0.995	2 to 3,200	33,903	17.3	0.996
	4,4'-DDT	0.2 to 64,000	0.992	2 to 1,600	20,618	18.2	0.993
	Methoxychlor	1 to 320,000	0.990	10 to 4,000	8,199	16.1	0.998
	TCX	0.1 to 32,000	0.997	1 to 1,600	72,423	10.8	0.998
DCB	0.2 to 64,000	0.996	2 to 3,200	23,956	17.2	0.998	
Mix B	beta-BHC	0.1 to 32,000	0.995	1 to 1,600	21,388	11.6	0.998
	delta-BHC	0.1 to 32,000	0.993	1 to 1,600	47,532	17.0	0.997
	Aldrin	0.1 to 32,000	0.994	1 to 1,600	35,851	14.3	0.997
	Heptachlor epoxide	0.1 to 32,000	0.994	1 to 1,600	36,234	11.9	0.998
	alpha-Chlordane	0.1 to 32,000	0.995	1 to 1,600	34,958	12.2	0.997
	gamma-Chlordane	0.1 to 32,000	0.995	1 to 1,600	35,250	11.3	0.997
	4,4'-DDE	0.2 to 64,000	0.989	2 to 3,200	40,065	18.6	0.996
	Endosulfan II	0.2 to 64,000	0.991	2 to 1,600	24,212	16.4	0.997
	Endrin aldehyde	0.2 to 64,000	0.990	2 to 3,200	18,628	16.6	0.995
	Endosulfan sulfate	0.2 to 64,000	0.992	2 to 3,200	27,644	14.7	0.996
	Endrin ketone	0.2 to 64,000	0.990	2 to 3,200	20,803	13.6	0.996

For a smaller concentration range (3 orders of magnitude), correlation improved and % RSDs of calibration factors for most OCPs were within 20 percent as required by CLP (see the 10-point calibration in table 3). Figure 4 shows a linear curve for lindane (1 to 1,600 pg/ μ L), typical of most OCPs in this concentration range. Figure 4 also shows the linear curve for methoxychlor (10 to 4000 pg/ μ L), a pesticide that typically responds poorly to classical ECD. This concentration range, typically from 1 to 1,600 or from 2 to 3,200 pg/ μ L for most OCPs, represents a 100-fold improvement over that required by CLP (CLP specifies 5 to 80 pg/ μ L for lindane). This wider linearity range allows more analyses for samples without requiring rework (dilution/concentration and re-analysis). If dilution of samples is required, the higher linearity of the detector results in more accurate estimations of correct dilution factors to bring sample concentrations within the CLP range.

Calibration Stability and System Robustness

The 6890 Series GC system with 6890 Micro-ECDs was regularly calibrated in accordance with CLP requirements. Analyses of blanks, continuous calibration using the midlevel standards, and performance evaluation mix were performed for each 12 hours of operation or every 10 to 20 samples. If results of these analyses failed to meet CLP breakdown, retention time, and response criteria, routine maintenance (such as changing inlet septum and liner or clipping a few inches off the guard column) was performed. If necessary, the instrument was recalibrated (using a three-point initial calibration). No cleaning or baking of the micro-ECD was required, even though a wide variety of samples was analyzed, including some dirty soil extracts⁸.




Figure 4. Linear calibration curves for lindane and methoxychlor over extended ranges.

At a minimum, CLP requires that system stability be monitored by analyzing midpoint calibration standards every 12 hours. In this study, system (or calibration) stability was based on verification of the calibration factors and retention times of target OCPs to match those from the initial calibration run within specific limits. The difference in calibration response (RPD—relative percent difference) between the later midpoint calibration run and the initial calibration run must be less than ± 25 percent (upper and lower RPD control limits).

Figure 5 is a continuous calibration verification (CCV) control chart of RPD for lindane and methoxychlor on column A over a 6 month period, typical of most OCPs on both column A and column B.

Throughout this study, the system was within RPD control limits and other calibration verification criteria for several days at a time without per-

forming any re-calibration. When any OCP failed to meet CLP calibration verification criteria (that is, when an OCP was outside the RPD control limits of the CCV), nonintrusive system maintenance was conducted and a new initial calibration was performed. These steps were also done when the instrument was switched for 1 or 2 weeks to analyze a different type of sample, requiring a different GC method. When the instrument was switched back to the original CLP analysis of OCPs and PCBs, the instrument still met calibration verification criteria (within the RPD control limits). This represents a significant improvement over previous designs that usually required full recalibration after switching between methods and indicates that using the micro-ECD saved time and improved laboratory productivity.

Over a period of 6 months, the 6890 Series GC/dual micro-ECD system was in continuous operation

and performed several different methods. For example, the system was used for 2 to 3 weeks to analyze pesticides and aroclors by the CLP method and solid waste method (EPA method 8081). The system was then switched to a drinking water method⁸ for a few weeks and later returned to the CLP method for OCPs. In other instances, the system was switched to analyze herbicides (EPA method 8150), then to drinking water (EPA method 504), and back again to the CLP method or method 8081 for OCPs and aroclors. In each case, the stabilization of the micro-ECDs was fast, requiring only a few injections of hexane blanks prior to running the CCV calibration standards.

Throughout this study (which included continuous operations over 6 months), even though routine column and inlet maintenance was needed (columns were replaced once during the course of the study), no micro-ECD maintenance was needed.

Conclusion

The improved performance of the Agilent 6890 Series GC/dual micro-ECD system met all CLP criteria for the analysis of OCPs over a period of 6 months. System validation was performed throughout this period for a wide variety of samples and analyses of different EPA methods. The 6890

Series GC with micro-ECDs easily met and maintained CLP criteria during the study. In addition, the micro-ECD showed improved sensitivity, greater dynamic and linear operating ranges, and more stable response. Moreover, it required minimal maintenance, and showed rapid recovery after switching between methods. Use of the Agilent 6890 Micro-ECD has a high potential to save time, improve quality of data, and increase laboratory productivity.




Figure 5. CCV control chart demonstrating stability of response and performance during the study.

References

1. U.S. Environmental Protection Agency, *Special Report on Environmental Endocrine Disruption: An Effects Assessment and Analysis, Risk Assessment Forum*, EPA/630/R-96/012, February 1997.
2. Colborn, T., Dumanoski, D., and Myers, J. P., *Our Stolen Future*, Penguin Books UAA Inc., New York, NY, 1996.
3. U.S. Environmental Protection Agency, *Methods for the Determination of Organic Compounds in Drinking Water*, Methods 505 and 508, rev 2.0, 1991.
4. U.S. Environmental Protection Agency SW-836, "Organochlorine Pesticides and PCBs as Aroclors by Gas Chromatography: Capillary Column Technique," Method 8081, *Test Methods for Evaluating Solid Wastes, Physical and Chemical Methods*, third edition, 1994.
5. U.S. Environmental Protection Agency, *Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater*, Method 608, EPA-600/4-82-059, 1982.
6. U.S. Environmental Protection Agency, "Statement of Work for Organic Analysis," *Contract Laboratory Program*, OLM03.1, August 1994.
7. Channel, I., and Chang, I. L., "Analysis of Organochlorine Pesticides and PCB Congeners with the Agilent 6890 Micro-ECD," Agilent Technology, Application Note 228-384, Publication No. (23) 5965-8556E, June 1997.
8. Chang, I. L., and Murphy, J., "Analysis of EDB and DBCP in Water with the 6890 Series Gas Chromatograph and 6890 Micro-Electron Capture Detector, EPA Method 504," Agilent Technology, Application Note 228-385, Publication No. (23) 5966-0495E, August 1997.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 4/2000
5966-3742E



Agilent Technologies

Innovating the HP Way



Fast Dual-Column GC/ECD Analysis of Chlorinated Pesticides—EPA Methods 608 and 8080

Application Note
228-305

Author

Imogene L. Chang, Ph.D.
Agilent Technologies
Wilmington, DE 19808-1610

Abstract

Dual-column analysis with HP-35 and HP PAS-1701 columns was used to analyze chlorinated pesticides targeted in EPA Methods 608 and 8080 for wastewater and solid wastes. GC parameters were optimized using the Agilent 5890 Series II gas chromatograph (GC) with electronic pressure control (EPC), a dual injector, and a dual electron capture detector (ECD) system. The analysis of 18 pesticides was completed in 12 minutes.

Introduction

Currently, many testing laboratories use dual-column/dual-ECD GC systems to analyze the chlorinated pesticides specified in EPA Methods 608 and 8080^{1,2}. For this application, EPC was used with an HP-35 column (35% phenyl, 65% methyl polysiloxane phase) as the primary column and the HP PAS-1701 column for confirmation.

The unique selectivity of the HP-35 column for this set of chlorinated pesticides permitted focus on the optimization of oven temperature for the HP PAS-1701 column. Individual EPC ports for each injector permitted individual regulation of column flow for both the HP-35 and the HP PAS-1701.

Experimental

EPA Method 608 and 8080 targeted pesticides were separated using 30 m x 0.53 mm x 1.0 μ m HP-35 and HP PAS-1701 columns (part no. 19095G-123 and 19094U-023, respectively). Analyses were performed on an HP 5890 Series II GC with EPC, dual split/splitless inlets, and dual ECDs. An Agilent 7673 automatic liquid sampler was used to process the simultaneous splitless injections. A deactivated single-tapered glass liner with a small plug of glass wool (part no. 5181-3316) and a Merlin

Microseal septum (part no. 5181-8816) were used with each split/splitless inlet. Instrumentation and GC conditions are listed in **Table 1**.

A test mix containing 18 pesticides (50 ppb per component) and two surrogates was prepared from the dilution of certified standard mixes with pesticide-grade hexane (Burdick & Jackson). Pesticides in the test mix are listed in **Table 2**.

Table 1. Experimental Conditions

Instrument Requirement	
Gas Chromatograph	Agilent Technologies 5890 Series II with EPC
Injection Ports	Dual split/splitless inlets
Column	HP-35, 30 m x 0.53 mm x 1.0 μ m (Part no. 19095G-123) HP PAS-1701, 30 m x 0.53 mm x 1.0 μ m (Part no. 19095S-123)
Detector	Dual ECD
Sample Introduction	7673 automatic sampler with dual injectors
Data Collection	3365 ChemStation and HP Vectra 486/33T PC
Experimental Conditions	
Injection	Splitless 1 μ l, purge delay, 0.75 min, inlet temperature of 250°C
Carrier gas	(A) HP-35, pressure program: 8.6 psi (1 min) at 0.5 psi/min to 12 psi and at 3.0 psi/min to 25 psi (0 min) (B) HP-1701, helium, 10 ml/min constant flow
Oven	160°C (1 min) to 280°C at 10°C/min and to 300°C (2 min) at 25°C/min
Detector	ECD (300°C), 120 ml/min N ₂ makeup, 6 ml/min anode purge



Agilent Technologies
Innovating the HP Way

Results and Discussion

In a dual-column/dual-ECD system, samples introduced in a single injection can be split between two columns using a Y-connector and detected by different ECDs. However, when using a Y-connector without EPC, the split sample flow to each column cannot be optimized, and equal and consistent sample splits cannot be presumed. The only variable that can be optimized, in dual-column ECD analysis using a Y-connector is the oven temperature program, which can be optimally balanced for the two dissimilar columns. Using dual-column GC/ECD without EPC, it would typically require 45 to 60 minutes to obtain baseline separations for EPA Method 608 and 8080 targeted pesticides (see **Figure 1**).

A typical run from an environmental testing laboratory for a test mix containing 18 targeted pesticides and two surrogates is shown in **Figure 1. A**

Table 2. Chlorinated Pesticides.

Peak No.	Pesticides
1	Tetrachloro-m-xylene (SS1)
2	alpha-BHC
3	Lindane
4	beta-BHC
5	Heptachlor
6	delta-BHC
7	Aldrin
8	Heptachlor epoxide
9	Endosulfan I
10	4,4'-DDE
11	Dieldrin
12	Endrin
13	4,4'-DDD
14	Endosulfan II
15	4,4'-DDT
16	Endrin aldehyde
17	Endosulfan sulfate
18	Methoxychlor
19	Endrin ketone
20	Decachlorobiphenyl (SS2)

Yconnector was used to split samples for both columns, DB-608 and DB-1701, and good baseline separations were obtained for most analytes. This dual-column run was completed in 45 to 53 minutes using the following oven temperature program: 150°C (1 minute) to 260°C (18.34 minute) at 3°C/minute, then to 275°C (5 minutes) at 25°C/minute. Clearly this oven temperature program was optimized to separate critical pairs, such as DDE/dieldrin, DDD/endosulfan II, endosulfan sulfate/methoxychlor, and methoxychlor/endrin ketone for both columns.

Figure 2 shows chromatograms of the same pesticide test mix using the HP-35 and HP PAS-1701 columns and EPC. The oven program, 160°C (1 minute) to 280°C at 10°C/minute and to 300°C (2 minutes) at 25°C/minute, was optimized to separate the critical pairs, endosulfan




Figure 1. Typical chromatograms of a pesticides standard mix using DB-608 and DB-1701 columns under GC conditions used in environmental testing laboratories. (See Table 2 for peak identification.)




Figure 2. Chromatograms of a pesticides standard mix using HP-35 and HP PAS-1701 columns under the GC conditions listed in Table 1. (See Table 2 for peak identification.)

II/DDT and methoxychlor/endosulfan sulfate, for the HP PAS-1701 column. In this run, EPC provided a constant 10 ml/minute helium flow to the HP PAS-1701 column throughout the entire run.

For the HP-35 column, the following pressure program was used: 8.6 psi (hold 1 minute) at 0.5 psi/minute to 12 psi and at 3.0 psi/minute to 25 psi (hold for constant flow for the remainder of the run). This pressure program actually provided a 10 ml/minute constant flow to elute most of the pesticides and an increased flow (up to 20 ml/minute) near the end of the run to elute the last analyte, surrogate decachlorobiphenyl and other high-boiling materials from the column.

GC parameters optimized for dual-column/dual-injector/dual-ECD analysis of chlorinated pesticides reduced analysis time to less than

12 minutes. In addition to speed, all EPA Methods 608 and 8080 targeted pesticides and surrogates were well resolved with good sharp peaks for accurate quantitation.

Conclusion

The use of EPC permitted individual column flow control to each ECD. The unique selectivity of the HP-35 column for chlorinated pesticides permitted focus on the optimization of oven temperature for the HP PAS-1701 column. Run time was 11.5 minutes with good baseline separations for all 20 target pesticides and surrogates. The result was a reduction in sample turnaround time from 54 to 11.5 minutes for a 400% increase in productivity. This is more than a twofold improvement in productivity when compared with conventional methods currently used at many environmental testing laboratories with DB-608 and DB-1701 columns.

Acknowledgement


The author wishes to thank Ms. Joann Faulkner and her colleagues at the Pace Laboratory in Petaluma, California, for providing chromatograms and pesticide standards.

References

1. USEPA SW-846 "Test methods for Evaluating Solid Wastes," Methods 8000 and 8080, September 1986.
2. USEPA "Methods for Organic Chemical Analysis of Municipal and Industrial Wastewater," Method 608, 1982.
3. I. L. Chang, "The Analysis of Chlorinated Pesticides and PCBs Using the HP-608 Capillary Column," Agilent Application Note 228-236, Publication No. 5091-7567E.



Trace Level Pesticide Analysis by GC/MS Using Large-Volume Injection



Application

Gas Chromatography

September 1997

Author

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Large-volume injection (LVI) using the Agilent programmable temperature vaporizing (PTV) inlet can improve gas chromatography system detection limits by one to two orders of magnitude over standard methods that call for 1- or 2- μ L injections. An Agilent 6890 Series gas chromatograph (GC), configured with a PTV inlet, a 6890 Series automatic liquid sampler (ALS), and an Agilent 5973 mass selective detector (MSD), was used for the analysis of pesticides in standards and several food extracts. By making 100- μ L injections, several pesticides could be identified by scanning gas chromatography/mass spectrometry (GC/MS) at the 100 ppt (100 ng/L) level. The PTV inlet tolerated dirty food extracts very well; more than 1,500 μ L of such samples

were injected into a single PTV liner. This application note includes recommendations for doing LVI using the PTV/6890/5973 GC/MSD system.

Introduction

More than 700 pesticides are registered for use in the world¹, and many more continue to persist in the environment, even though they are no longer being applied. For the protection of human health and the environment, pesticide residues are routinely monitored in food, water, soil, and tissue samples. "Acceptable" residue limits have been set for various foods and environmental samples by agencies such as the United States Environmental Protection Agency (U.S. EPA), the Codex Alimentarius Commission², and many other governmental organizations around the world. A great many methods have been developed to screen for pesticides in food³⁻⁷ and the environment⁸⁻¹⁰ to ensure that risks associated with pesticide use are minimized.

Recently, concern has increased that certain pesticides and other synthetic chemicals may be acting as pseudo hormones which disrupt the normal function of the endocrine system in wildlife and humans. Birth defects, behavioral changes, breast cancer, lowered sperm counts, and reduced intelligence are among the many disorders that have been blamed on these "endocrine disrupting" compounds, though much research must be done to verify these assertions. In 1996, Colborn, Domanoski, and Myers¹¹ brought these issues into the public spotlight with the publication of their book *Our Stolen Future*. Recently, the United States Congress passed legislation calling for increased testing of suspected endocrine disrupters and monitoring their levels in food¹² and water¹³ supplies. Because the endocrine system can be exquisitely sensitive to extremely low hormone concentrations, there is a need to measure concentrations of suspected endocrine disrupters (many of which are pesticides) at very low levels. Initiatives such as the Pesticide Data Program, developed by the United States Department of Agriculture¹⁴, seek to



Agilent Technologies

Innovating the HP Way

determine the lowest measurable pesticide levels in various foods to develop a total exposure model. Clearly, there is pressure to push pesticide detection limits to even lower levels than are routinely achieved today. Most residue measurements are made by gas chromatography using a variety of element-selective or mass spectral detectors (GC/MS). Therefore, to achieve lower detection limits, it is necessary to improve the detection limits of these GC methods.

In GC, there are primarily four ways to improve method detection limits: 1) increase the concentration of analytes in a sample, usually by reducing the volume of an extract; 2) increase the sensitivity of the detector; 3) increase the selectivity of the detector to reduce chemical background "noise" or 4) increase the volume of sample injected. Because GC/MS can be highly selective and extremely sensitive, it is often the method of choice for pesticide analysis and/or confirmation. However, for the reasons discussed above, there are occasions when even greater sensitivity is required. This application note describes a method for increasing GC/MS system detection limits by making large-volume injections (LVI) using Agilent's new programmable temperature vaporizing (PTV) inlet. Because this LVI technique is detector-independent, it is applicable to other GC configurations that may be used for pesticide residue analysis.

Experimental

Pesticide Standard Solution

Stock solutions of 14 pesticides were prepared at 1 mg/mL by adding 10 mg each of trifluralin, hexachlorobenzene, pentachloronitrobenzene, dichloran, chlorothalonil, chlorpyrifosmethyl, chlorpyrifos, endosulfan

I, p,p'-DDE, propargite, iprodione, methoxychlor, and fenvalerate (mix of isomers I and II) to individual 20 mL vials and diluting with 10.0 mL of acetone. Permethrin was obtained as a mixture of permethrin I and permethrin II comprising 32 percent and 27 percent of the sample, respectively, so 16.95 mg of this mixture was diluted with 10 mL of acetone giving a solution in which the combined permethrins represented 1 mg/mL. A stock mixture was prepared by adding 4 mL of the permethrin and fenvalerate solutions and 1 mL of each of the other stock solutions to a 100-mL volumetric flask and diluting to volume with acetone. The resultant solution contained 40 ng/ μ L each of the combined permethrin and fen-

valerate isomers and 10 ng/ μ L each of the other 12. This sample was diluted further with acetone to prepare standards that were analyzed by LVI. All these pesticides were obtained in neat form from Chem Service (West Chester, PA USA).

Extracts

Fruit and vegetable extracts were obtained from the Florida Department of Agriculture and Consumer Services (Tallahassee, FL USA). Commodities were extracted using a version of the Luke procedure¹⁵⁻¹⁷ that gave a final sample representing 1.75 g of the commodity per mL of extract.

Table 1. Instrumentation and Conditions Used for Pesticide Samples

GC/MS System	
Gas chromatograph	6890 Series GC
Automatic liquid sampler	6890 Series ALS
Mass spectral detector	5973 Series MSD
Programmable temperature vaporizing inlet	PTV with CO ₂ cooling
Computer for data acquisition and analysis	HP Vectra XU 6/200
Software	G1701AA Version A.03.00 running Microsoft® Windows™ 95
Column	30 m x 0.25 mm x 0.25 μ m Agilent HP-5MS
Instrumental Conditions	
GC Parameters	
Carrier gas	Helium
Inlet liner	Prototype deactivated borosilicate with fritted glass on interior walls (part no. 5183-2041)
Syringe size	50 μ L
Injection volume	100 μ L (Inject 10 μ L 10 times)
Injection delay	12 sec
Inlet temperature program	40 °C (4.2 min), 200 °C/min to 320 °C (2 min)
Vent flow	400 mL/min Vent pressure 0.0 psi for 4.00 min
Purge flow to split vent	50.0 mL/min at 6.50 min
Column head pressure	0 psi (4 min) then 17.3 psi (constant pressure)
Oven temperature program	50 °C (6.13 min), 30 °C/min to 150 °C (2 min), 3 °C/min to 205 °C (0 min), 10 °C/min to 250 °C (20 min)
MSD Parameters	
Acquisition mode	Scan (35-550 amu)
Temperatures	Transfer line = 280 °C, MS quad = 150 °C, MS source = 230 °C

Instrumentation

Table 1 lists the instrumentation and chromatographic conditions used for LVI and GC/MS analysis of pesticide samples.

Brief PTV Tutorial

Before focusing on the PTV/GC/MS analysis of pesticides, it is important to understand how the PTV inlet operates in the solvent vent mode for large-volume injections.

The PTV Inlet

The PTV inlet has the same basic functions as the split/splitless inlet except that it is temperature programmable from -60 °C (using CO₂ cooling) or -160 °C (using liquid N₂ cooling) to 450 °C at rates up to 720 °C/min. However, the PTV's design has been optimized for its main uses—LVI and cold split/splitless injection. Although hot split and splitless injections may be made with or without a pressure pulse, care must be taken not to exceed the small internal volume of the PTV inlet. In practice, it is best to choose the Agilent split/splitless inlet for hot injections and the PTV inlet for LVI and cold split/splitless techniques.

Most GC pesticide methods call for injecting 1–2 µL; splitless injection is used because it is compatible with dirty extracts of food, soil, or water. Pulsed splitless injection allows one to make injections of up to 5 µL using standard equipment¹⁸. Enormous gains in system sensitivity can be realized by using the PTV inlet in the "solvent vent" mode, which is compatible with injections of 5–1,000 µL. These large injections may be made manually or automatically using either a standard 6890 Series ALS in the multiple injection mode or by using a controlled speed injector available from Gerstel¹⁹. Because the injection process may take several minutes,

manual injections are usually impractical and good precision may be hard to achieve.

The 6890 Series ALS is designed to make one or more injections of up to 25 µL into the PTV inlet. After the desired number of injections has been made, the inlet is heated and the chromatography begins. Though the system controls allow up to 99 injections, a reasonable upper limit is about 10, making 250 µL the typical injection volume limit for this system. For even larger injections, the controlled speed injector¹⁹ should be used. For all of the analyses described below, 100 µL were injected by making 10 sequential injections of 10 µL each.

How the PTV Works in the Solvent Vent Mode

Figure 1 shows a diagram of the PTV inlet. For large-volume injections, three steps are required. These are: 1) injection and solvent elimination; 2) splitless sample transfer to the GC column; and 3) chromatographic separation and, if desired, a simultaneous inlet bake-out step. The steps are described more completely below.

Injection and Solvent Elimination (Step 1)

During injection, the column head pressure is set to 0 psi to eliminate or, in the case of GC/MS, reduce the flow through the column. When mass spectral detection is used, there is still






Figure 1. The PTV inlet shown with the septumless head. The inlet is also available with a septum head that may be equipped with a standard septum or a Merlin Microseal. (Figure reproduced with permission of Gerstel GMBH.)

some flow because the column outlet is under vacuum. At the same time, a steady stream of carrier gas passes through the inlet and out through the split vent. This flow is typically between 100 and 500 mL/min. The sample is injected into the cool liner where it remains as a liquid, dispersed over the liner walls or any packing material that may be in the liner. The steady flow of carrier gas through the liner causes the solvent (and any volatile fraction of the sample) to evaporate and be swept with the carrier gas out through the split vent. This is analogous to "blowing down" a sample with a stream of inert gas, except that this takes place inside the PTV inlet. When most of the solvent has evaporated, the next injection is made and the evaporation process repeats, accumulating more sample in the inlet. To recover an analyte completely, its boiling point should be at least 100 °C greater than that of the solvent; most pesticides fall into this category.



A Sample is injected too rapidly



B Solvent evaporates completely between injections

Figure 2. Chromatograms A and B illustrate the result of poor timing of multiple injections.

The timing of these multiple injections can be important. If the sample is introduced too rapidly, the liner may become flooded and liquid will be forced out through the split vent. Chromatographically, this shows up as reduced area counts for all analytes (see figure 2A). If there is too much time between injections, all of the solvent may evaporate and more of the volatile analyte fraction may be lost too. This results in poor recovery of volatiles but 100 percent recovery of the less volatile compounds (see figure 2B). Set-points such as inlet temperature, vent flow, and injection delay times can affect recovery of volatiles. Note that for 100 percent recovery, an analyte should have a boiling point at least 100 °C greater than the solvent. One can adjust the delay between injections by entering the desired value in the ChemStation software. Some experimentation is usually necessary when setting this delay for a new method. It will be dependent upon such factors as the solvent type, injection volume, vent flow, and inlet temperature.

Splitless Sample Transfer to the GC Column (Step 2)

Once the desired number of injections has been made, the column head pressure is restored and the vent flow is turned off. At this point, the inlet temperature is programmed up to a value that is sufficient to transfer all of the desired analytes to the GC column. This step is similar to

a splitless injection, except that instead of flash vaporization, the sample is transferred as the inlet temperature is programmed up. For the most gentle treatment of labile analytes, slow ramp rates may be used. This allows analytes to be flushed into the column at the minimum temperature needed for volatilization. When sample decomposition is not a problem, the inlet may be heated as fast as 720 °C/min.

Chromatographic Separation (Step 3)

During sample transfer, the oven temperature is usually held between 30 °C below and 20 °C above the solvent's atmospheric boiling point, depending on whether the solvent effect is needed to focus the more volatile fraction of the analytes. Again, some experimentation is necessary to optimize peak shapes. After the sample has been transferred in step 2, the oven temperature is programmed up and chromatography begins.

After the inlet has reached its maximum temperature and sufficient time has elapsed to transfer the sample to the column, a purge flow of 30-50 mL/min is restored to the split vent. If desired, one can set a very large split flow for a few minutes and bake out the inlet at a higher temperature to remove nonvolatile impurities. To conserve carrier gas, gas saver should be turned on at the end of this bake-out step.

Entering PTV Inlet Parameters into the Agilent ChemStation

When preparing the PTV portion of a GC method, one should first decide on the sample size and how many injections are required. In this work, ten 10- μ L injections were made for a total of 100 μ L. When entering parameters into the ChemStation screen, the Injector icon is first selected (figure 3) under the "GC edit parameters" menu. Next, the Configure button is pressed to enter the syringe size and enable multiple injections. From the main injector screen, the injection volume (10 μ L) and number of injections are entered¹⁰. For this work, a 12-second delay was chosen between injections to allow for solvent evaporation.

The estimated total injection time is listed on the Inlets screen (figure 4). This is helpful when setting the inlet and oven parameters. First, the vent flow rate (400 mL/min for these analyses) is chosen, which sets the vent pressure to 0 psi until the injection sequence is done and solvent from the last injection has largely evaporated (4.00 min in figure 4). This is done by entering these values in the following fields:

Vent Flow 400 mL/min
Vent pressure 0.0 psi until
4.00 min

Next, the purge flow and elapsed time are set by entering values in the following field:

Purge Flow to Split Vent
50.0 mL/min @ 6.50 min

Note that as an aid in setting up the method, the "estimated total injection time" is shown just above the previous data entry fields.

In this example, the normal column head pressure was restored and the vent flow was turned off at 4.00 min. This prepares the inlet for the splitless transfer of the sample to the column. The vent flow remained off until it was set to 50 mL/min at 6.5 min. Thus, there is a 2.5-min period for inlet temperature

programming and splitless sample transfer to the column. In this example, the inlet was held at 40 °C for 4.2 min, enough time to make 10 injections, turn off the purge flow, and restore the column head pressure; the PTV was then programmed to 320 °C at 200 °C/min (figure 4).




Figure 3. The injector screen from Agilent GC and GC/MS ChemStation software showing the setpoints available for multiple injections. To configure the sampler for multiple injections, set the syringe size, and choose slow injection, click on the Configure button.




Figure 4. The inlets screen from Agilent GC and GC/MS ChemStation software showing the setpoints available for operation of the PTV inlet in the solvent vent mode.

Although not done for these analyses, the inlet could be baked out by setting the "purge flow to split vent" to a large value (perhaps 500 mL/min) at the end of the splitless time (6.50 min) and at the same time, program the inlet to a higher temperature. After the bake-out period, the inlet temperature is programmed downward and gas saver is turned on.

Normally, the GC oven is held at its starting temperature until the splitless injection is complete (6.50 min in this case) at which time oven temperature programming is begun. For this work, the oven temperature program was begun at 6.13 min so that the pesticide retention times would match a retention time data base that was in use. Figure 5 diagrams the PTV and GC oven setpoints used for this work.

PTV Inlet Liner Considerations

The correct liner choice is critical to the success of any pesticide analysis by PTV injection. The liner must be thoroughly deactivated or many labile pesticides may decompose or adsorb in the inlet. In general, any liner containing glass wool will be unsatisfactory for the analysis of labile pesticides, whether or not the glass wool is deactivated. At this time, two PTV liners are suggested for pesticide analysis:

- Part no. 5183-2037 is a deactivated, open multibaffled liner with no internal packing that may be used for single or multiple injections of 5 μ L or less. This liner gives very good recovery for pesticides, even extremely difficult ones such as acephate and methamidophos.

- Part no. 5183-2041 is a deactivated liner with an internal coating of sintered glass to give it more surface area and is, therefore, suitable for single or multiple 25- μ L injections. This liner gives better than 70 percent recovery for most pesticides, although tests have shown that acephate and methamidophos cannot be analyzed using this liner, and that recoveries of guthion are often less than 50 percent. A prototype version of this liner was used for all of the work described in this application note.






Figure 5. Illustration of the GC and sampler setpoints used for 100- μ L injections of pesticide samples. Note that normally, the GC oven hold period would have been at least 6.5 min for this method. A value of 6.13 min pesticide retention times to a data base.

Results and Discussion

When compared to a typical 2- μ L splitless injection, 100- μ L PTV injections can often result in a 50-fold improvement in system detection limits. Selective detectors such as the MSD can help the analyst to realize the full measure of this sensitivity improvement by excluding background that may be introduced from solvent impurities, vial cap extract, and indigenous compounds coextracted with the analytes. In this application, it was possible to see most of the pesticides in the 14-component mixture at 100 ppt in the scan mode (400 ppt for the isomer mixes of permethrin and fenvalerate). Figure 6 shows extracted ion chromatograms for trifluralin and hexachlorobenzene (HCB) at 100 ppt. Library searching gave a match quality of 93 for the HCB peak. Fenvalerate isomers I and II were found in the solution in a ratio of about 78:22. Figure 7 shows extracted ion chromatograms for fenvalerate I at a concentration of 311 ppt.



A Extracted ion current chromatograms of trifluralin



B Extracted ion current chromatogram of HCB with its mass spectrum and library match

Figure 6. Scanning GC/MS results for a pesticide standard containing Trifluralin and Hexachlorobenzene at 100 ppt. (Ten 10- μ L injections were made using the PTV inlet.)




Figure 7. Extracted ion current chromatograms of Fenvalerate I at a concentration of 311 ppt in a pesticide standard. (Ten 10- μ L injections were made using the PTV inlet.)

Analysis of a bell pepper extract revealed several pesticide residues. As seen in figure 8, chlorpyrifos and the endosulfans were easily detected. The Florida Department of Agriculture determined the concentration of chlorpyrifos, alpha-endosulfan, beta-endosulfan, and endosulfan sulfate to be 0.210, 0.011, 0.018, and 0.013 ppm, respectively. It is important to note that these compounds could be detected with very high selectivity by extracting high mass ions that are characteristic of these pesticides but not of the matrix. Using LVI, there is ample signal from these less abundant ions for good quantitation. With normal injection volumes, selectivity may have to be compromised and the most abundant ions extracted in a pesticide spectrum to gain sensitivity.

Phosmet, captan, and propoxur were all easily detected in a pear sample. The total ion current chromatogram (TIC) is shown in figure 9 along with spectrum obtained for captan juxtaposed with the library spectrum. Figure 10 shows the propoxur peak along with 2,4,6-tribromoanisole and 2,4,6-tribromophenol, two other compounds that were surprising to find in a pear sample. Though the origin of these brominated compounds is not known, a recent paper by Hoffmann and Sponholz 20 suggests that tribromophenol is used to treat storage pallets for the prevention of fire and mold growth, and that the anisole is formed from the phenol microbiologically. Perhaps these pears were shipped in containers that had been similarly treated.




Figure 8. GC/MS Analysis of a bell pepper extract. (Ten 10- μ L injections were made using the PTV inlet.) Using LVI, there was sufficient signal to use high mass ions with smaller abundances to achieve greater selectivity.




Figure 9. TIC of a pear extract resulting from a 100- μ L Injection (10 x 10 μ L). Captan was easily detected, and its spectrum gave a library match quality of 96.




Figure 10. TIC of a pear extract resulting from a 100- μ L Injection (10 x 10 μ L). Propoxur and two brominated phenolics were easily identified.

A single sintered glass coated liner of the type described above (part no. 5183-2041) was used for about ten 50- and ten 100- μ L injections (ca. 1,500 μ L total) of vegetable extracts before it was replaced. All of the extracts were rather dirty, and an inlet bake-out step was not used. Although the liner looked somewhat discolored for about 2 cm where injections were made, it still performed well at the time it was replaced.

Conclusion

Using the PTV inlet in the solvent vent mode, it is relatively simple to increase system detection limits by one or two orders of magnitude. When combined with the Agilent 6890 Series automatic liquid sampler,

multiple injections of up to 25 μ L each into the inlet can be made, allowing the solvent to vent while pesticides and other less volatile analytes accumulate. After the desired sample volume has been introduced (typically 5-250 μ L), the solvent vent is closed and the sample is transferred to the column in a temperature-programmed splitless injection. By making 100- μ L injections into a PTV-equipped Agilent 6890 Series GC coupled to the Agilent 5973 MSD, it was possible to see several pesticides at the 100 ng/L level (100 ppt) in the scan mode. With such low detection limits, less abundant ions can be used to identify and quantitate pesticides at low ppb levels, thereby gaining in selectivity as well.

When performing LVI, there are several parameters to adjust and some method development time is usually required. However, the method described herein worked well and can be duplicated for the PTV/GC/MS analysis of pesticides in food.

Acknowledgment

The author wishes to thank Ms. Joanne Cook of the Florida Department of Agriculture and Consumer Services for supplying the food extracts used in these experiments and Dr. Bill Wilson (Agilent Technologies) for supplying liner deactivation test results.

References

1. Tomlin, Clive, ed (1994), *The Pesticide Manual, Tenth Edition*, British Crop Protection Council, Surry, UK.
2. Miller, R. W., *This is Codex Alimentarius*, Secretariat of the Joint FAO/WHO Food Standards Programme, Food and Agriculture Organization of the United Nations, Rome.
3. McMahon, B. M. and Hardin, N. F. eds. (1994), *Pesticide Analytical Manual, Vol I, Third Edition*, U.S. Food and Drug Administration, Washington, DC.
4. Lee, S. M., Papathakis, M. L., Feng, H.-M. C., Hunter, G. G., and Carr, J. E. (1991), *Fresenius' A. Anal Chem* 339, 376-383.
5. Fillion, J., Hindle, R., Lacroix, M., and Selwyn, J. (1995), *J AOAC Int* 78, 1252-1266.
6. Working Group on Development and Improvement of Residue-analytical Methods (1996), *Analytical Methods for Pesticide Residues in Food-stuffs*, General Inspectorate for Health Protection, Ministry of Public Health, Welfare & Sport, The Netherlands.
7. Luke, M. A., Froberg, J. E., Doose, G. M., Masumoto, H. T. (1981), *J Assoc Off Anal Chem* 64, 1187-1195.
8. Stan, H. J., ed. (1995), *Analysis of Pesticides in Ground and Surface Water II*, Springer-Verlag, Berlin, Germany.
9. Wagner, R. E., Kotas, W., and Yogis, G. A., eds. (1994), *Guide to Environmental Analytical Methods, 2nd Edition* Genium, Schenectady, NY.
10. U.S. Environmental Protection Agency, *Test Methods for Evaluating Solid Waste, SW-846, Draft Method 8085: Pesticides by GC/AED*.
11. Colborn, T., Dumanoski, D., and Myers, J. P. (1996), *Our Stolen Future*, Penguin, New York, NY.
12. *Food Quality Protection Act of 1996*, Public Law 104-170, Congressional Record pp. H8127-H8141.
13. *Safe Drinking Water Act Amendments of 1996*, Public Law 104-182, Congressional Record pp. H9680-H9700.
14. *Pesticide Data Program Annual Summary Calendar Year 1994*, U.S. Department of Agriculture, Agricultural Marketing Service, Washington, DC.
15. Luke, M. A., Froberg, J. E., Doose, G. M., and Masumoto, H. T. (1981), *J Assoc Off Anal Chem* 64, 1187-1195.
16. Luke, M. A., and Doose, G. M. (1983), *Bull Environ Contamin Toxicol* 30, 110-116.
17. Sawyer, L. D. (1985), *J Assoc Off Anal Chem* 68, 64-71.
18. Wylie, P. L., Phillips, R. J., Klein, K. J., Thompson, M. Q., and Hermann, B. W. (1991), *J High Resol Chromatog* 14, 649-655.
19. The controlled speed injector is available from Gerstel US, 1510 Caton Center Dr., Baltimore, MD 21227 USA.
20. Hoffmann, A. and Sponholz, W. (March 1997), *American Laboratory*, 22-23.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Microsoft is a U.S. registered trademark and Windows™ is a U.S. trademark of Microsoft Corporation.

HP® is a registered trademark of Hewlett-Packard Company.

Copyright © 2000
Agilent Technologies, Inc.


Printed in the USA 4/2000
5966-1214E



Agilent Technologies

Innovating the HP Way

A Method Used to Screen for 567 Pesticides and Suspected Endocrine Disrupters



Application

Gas Chromatography

May 1998

Authors

Philip L. Wylie and
Bruce D. Quimby
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A gas chromatographic (GC) method has been developed that can be used to screen for 567 pesticides and suspected endocrine disrupters. In principle, it can be used to screen for any GC-amenable pesticide, metabolite, or endocrine disrupter. The method relies on a technique called retention time locking (RTL). RTL is a procedure that allows the chromatographer to reproduce analyte retention times independent of GC system, column length, or detector so long as columns with the same stationary phase, nominal phase ratio, and diameter are used. Because RTL increases retention time precision and predictability, raw retention times can be used as a more reliable indicator of compound identity. The chromatographer first locks the GC method so that all retention times match those listed in a 567-compound pesticide and

endocrine disrupter retention time table. After analyzing a sample by GC with atomic emission detection (GC-AED), the analyst enters a peak's retention time and known elemental content (presence or absence of heteroatoms) into a dialog box. If element-selective detectors are used, detector response can be entered in addition to or in place of GC-AED data. The software then searches the pesticide table for those compounds that elute at the correct retention time and have the right elemental content or detector response. Most often, the software finds just one compound that meets these criteria, and rarely does it find more than three. Confirmation is performed by GC with mass spectral detection (GC-MS) or by calculation of elemental ratios using GC-AED data. With retention time locking, pesticides have the same retention time on all GC systems; this makes GC-MS confirmation much easier because the analyte's retention time is already known.

Key Words

Pesticides, endocrine disrupters, gas chromatography, retention time locking, RTL

Introduction

*The Pesticide Manual*¹ lists 759 compounds and biological agents that are used currently as active ingredients in various pesticide formulations. Many compounds, though no longer used, still persist in the environment. For the protection of human health and the environment, acceptable limits in food and water have been set by governmental bureaus such as the United States Environmental Protection Agency (USEPA) and the Codex Alimentarius Commission.² Numerous methods have been developed to screen for pesticide contamination in food³⁻⁷ and the environment⁸⁻¹⁰ to ensure that these standards are met.

Certain pesticides and other synthetic chemicals have been suspected of behaving as pseudo hormones, disrupting normal functions of the endocrine system in wildlife and humans. Maladies such as birth defects, behavioral changes, breast cancer, lowered sperm counts, and reduced intelligence have been blamed on exposure to endocrine disrupters.¹¹ The 1996 publication of *Our Stolen Future*, a book by Colborn,



Agilent Technologies
Innovating the HP Way

Dumanoski, and Myers,¹¹ brought these concerns to the attention of the public. Recently passed legislation in the U.S. calls for more testing of suspected endocrine disrupters and monitoring of them in food¹² and water¹³ supplies. To facilitate more research into the endocrine disrupter issue, methods are needed to detect suspected compounds at trace levels.

Because so many pesticides are in use, it is usually impractical to screen for large numbers of them individually and, therefore, multiresidue methods are preferred. Most laboratories that analyze for pesticides in food or the environment screen for only a few dozen compounds because it is often very difficult to screen for more. Recently however, methods have been developed using gas chromatography with mass spectral detection (GC-MS), that can screen for more than 200⁵ or even 300⁶ pesticide residues.

Still, there is no universal method to analyze for all GC-amenable pesticides. While GC-MS methods are gaining in popularity, there are still some limitations. When methods employ selected ion monitoring (SIM) or tandem mass spectrometry (MS-MS), method development is more tedious and any shift in GC retention times requires that individual analyte retention time windows be shifted accordingly. These methods are only capable of detecting compounds on the target list; there are still hundreds of pesticides, metabolites, and suspected endocrine disrupters that could be missed. On the other hand, methods based on scanning GC-MS alone may require more sample cleanup to avoid interferences from co-extracted indigenous compounds. Typically, these methods do not screen for many pesticide metabo-

lites, endocrine disrupters, or other environmental contaminants. A method that could be used to screen for endocrine disrupters and almost all of the volatile pesticides and metabolites would offer a better means of monitoring the food supply and the environment.

This paper describes a universal method that, in principle, could be used to screen for any pesticide, metabolite, or endocrine disrupter that can elute from a gas chromatograph. The screening procedure relies on a new gas chromatographic technique called retention time locking (RTL)¹⁴⁻¹⁶ with database searching based on retention time and elemental content or detector response. This technique is used to narrow an analyte's identity to a few possibilities. Confirmation is performed by GC-MS or by calculation of a compound's elemental ratio using GC with atomic emission detection (GC-AED).

Experimental

Standards and Extracts

Pesticide standards used to develop the retention time table were obtained from Chem Service (West Chester, PA, USA), Promochem Ltd (Welwyn Garden City, Hertfordshire, England), Dr. Ehrenstorfer (Augsburg, Germany), Hayashi Pure Chemical Industries, Ltd (Osaka, Japan), Wako Pure Chemical Industries, Ltd (Osaka, Japan), and GL Sciences Inc (Tokyo, Japan).

Fruit and vegetable extracts were obtained from the Florida Department of Agriculture and Consumer Services (Tallahassee, FL, USA). Samples were extracted with acetonitrile followed by solid-phase extraction (SPE) using a C-18 cartridge. Extracts

intended for analysis by halogen-selective detectors were also subjected to floracil SPE.

Pesticide Retention Time Table

The table containing GC and GC-MS retention times for 567 pesticides, metabolites, and suspected endocrine disrupters was obtained from Agilent Technologies, Wilmington, DE, USA (G2081AA).

Instrumentation

Table 1 lists the instrumentation and chromatographic conditions used for GC-AED screening and GC-MS confirmation.

Software for Method Translation

Software for use in translating the normal GC method to one that runs three times faster was obtained from Agilent Technologies, Wilmington, DE, USA.¹⁷

Results and Discussion

Retention Time Locking

Key to the development of this method is a new concept in gas chromatography called retention time locking (RTL).¹⁴⁻¹⁶ Agilent RTL software allows the chromatographer to match analyte retention times from run to run, independent of the GC system, detector, or manufacturing variations in column dimensions. The only requirement is that the columns used have the same stationary phase and the same nominal diameter and phase ratio. For example, with RTL it is possible to match analyte retention times on a GC-AED and a GC-MS even though the MS operates under vacuum and the AED operates at 1.5 psi above ambient pressure. The

procedure also compensates for differences in GC column length resulting from variations in manufacturing or from column cutting required during routine maintenance.

RTL is accomplished by adjusting the GC column head pressure until a given analyte, such as an internal standard, has the desired retention time. When this is done, all other analytes in the chromatogram will have the correct retention times as well. Software has been developed that can be used to determine the column head pressure that will lock the retention times correctly after one or two “scouting” runs.

With RTL, it is possible to measure pesticide retention times using a given GC method, and then reproduce those retention times in subsequent runs on the same or different instruments. With this increased retention time precision and predictability, retention times become a far more useful indicator of analyte identity. For many years, relative retention times^{3,6} or retention indices^{18,19} have been used to identify compounds. These techniques were developed to compensate for the fact that retention times were not predictable from day to day, column to column, or instrument to instrument. With the increased retention time precision of the Agilent 6890 GC and RTL, it seemed that raw retention times could be used for compound identification instead of retention indices. The chromatographer could simply scan a table of pesticide retention times, eliminating all possibilities but those with close elution times under the same locked GC conditions.

Table 1. Instrumentation and Conditions of Analysis

Agilent GC-AED System	
Gas chromatograph	6890
Automatic sampler	6890 Series automatic sampler
Atomic emission detector	G2350A atomic emission detector
Computer for data acquisition and analysis	HP Vectra XM Series 4 5/150
Software	G2360AA GC-AED software running on Microsoft® Windows™ 3.11
Column	30 m × 0.25 mm × 0.25 µm HP-5MS (part no. 19091S-433)
GC inlet	Split/splitless, 250 °C or 260 °C
Inlet liner	Single-tapered deactivated (part no. 5181-3316) with 2-cm deactivated glass wool plug centered ~ 3 cm from the top
Injection volumes	3–5 µL splitless when running method at 3× speed; 2–3 µL splitless at 1× speed
Inlet pressure (splitless)*	87.5 psi constant pressure for method at 3× speed; 27.6 psi constant pressure for 1× speed
Inlet pressure program (pulsed splitless)*	60 psi (2.01 min), 10 psi/min to 27.9 psi (hold)
Oven temperature program	70 °C (2 min), 25 °C/min to 150 °C (0 min), 3 °C/min to 200 °C (0 min), 8 °C/min to 280 °C (10 min)
AED transfer line temperature	290 °C
AED cavity temperature	320 °C
AED elements and wavelengths (nm)	Group 1: Cl 479, Br 478 Group 2: C 193, S 181, N 174 Group 3: P 178 Group 4: F 690 (optional)
Agilent GC-MS System	
Gas chromatograph	6890
Automatic sampler	6890 Series automatic sampler
Mass selective detector	5973 MSD
Computer for data acquisition and analysis	HP Vectra XU 6/200
Software	G1701AA Version A.03.00 running on Microsoft® Windows® 95
Column	30 m × 0.25 mm × 0.25 µm HP-5MS (part no. 19091S-433)
Inlet	Split/splitless, 250 °C
Inlet liner	Single-tapered deactivated with small amount of glass wool at the bottom (part no. 5062-3587)
Injection volume	2 µL
Inlet pressure*	15.5 psi (constant pressure)
Oven temperature program	Same as GC-AED
MSD parameters	
Acquisition mode	Scan (35–550 amu)
EM voltage	200 rel
Solvent delay	3.20 min
Threshold	150
Scans/sec	2.86
Temperatures	Transfer line = 280 °C, MS quad = 150 °C, MS source = 230 °C

*The column head pressures shown are typical values. Exact values were determined as part of the retention time locking procedure.

Pesticides almost always contain heteroatoms and often have several in a single molecule. The most frequently encountered heteroatoms are O, P, S, N, Cl, Br, and F. GC with atomic emission detection (GC-AED) has been shown to be a useful tool for pesticide screening because it is selective for all of the elements found in these compounds.^{20–22} Thus, GC-AED screening provides valuable information about the elemental content of an unknown molecule. By including this elemental information along with the retention time, it should be possible to narrow pesticide “hits” to just a few possibilities.

To implement this screening procedure, a table of pesticide and endocrine disrupters retention times had to be created using a suitable method under locked conditions.

GC Method for Pesticide Screening

First, a GC method was needed that could elute hundreds of pesticides and endocrine disrupters in a reasonable time with adequate separation. However, the goal was not to separate every possible analyte in a single GC run. Because the intention was to build a table of locked retention times using this method, it had to reproduce these retention times under a variety of conditions. For example, the method needed to accommodate a variety of injection techniques including splitless, pulsed splitless,^{23,24} cold splitless using a PTV inlet, and on-column injection which is occasionally used for the more labile pesticides.

The method also needed to perform well with samples dissolved in common solvents such as acetone and methylene chloride. Because a retention gap (or guard column) is sometimes added to protect the analytical column, the method had to be

tested to see if it could still be locked with a retention gap installed.

The column chosen for the method was a 30 m × 0.25 mm × 0.25 μm HP-5MS because the same column could be used with any GC-detector combination. In particular, this column was chosen for its low bleed at high temperatures and because its optimum column flow is compatible with GC-MS. The 5% phenyl methyl silicone phase in this column has been widely used for pesticides.

Method translation software^{17,25,26} can be used to increase the speed of a method while retaining the same relative retention times. This can be done by translating the method to a column having the same phase ratio but a smaller id or by increasing the flow rate and oven temperature program while using the same column. The final goal was to design a method that could run at three times the normal speed on the 30-m × 0.25-mm × 0.25-μm HP-5MS column or be translated to a 100-μm id column.

After several weeks of method development, the GC oven temperature program shown in figure 1a was chosen because it met all of the development criteria. Chlorpyrifos-methyl (C₇H₇Cl₃NO₃PS) was chosen as the locking standard. It is an ideal choice because chlorpyrifos-methyl elutes near the middle of the chromatogram (16.596 minutes), has good peak shape, and can be seen by most element-selective detectors. Because GC-AED requires three runs to generate element-selective chromatograms for C, Br, Cl, N, S, and P, the method was translated to run three times faster using software for method translation.^{17,25,26} The faster oven temperature program used by this method requires 6890 GC systems that are configured for fast oven tem-

perature ramping. The method translation software can be used to speed up the method by any desired factor; even 120-V 6890 GCs can run the method two times faster. However, the original method must be used for GC-MS because of the restriction in flow rates into the MSD. Figure 1b lists the threefold (3×) faster GC method.

Pesticide Retention Time Table

Once developed, this method was employed to create a table of locked retention times for the 567 pesticides, metabolites, and suspected endocrine disrupters. Increasing international food trade requires the analysis of pesticides that may be used in the supplying country but not in the recipient country. The goal was to create a table that included pesticides used around the world so pesticide standards were obtained from sources in Europe, Japan, and the USA.

A list of suspected endocrine disrupters was compiled from various lists published on the World Wide Web.^{27–31} Many of these compounds are, in fact, pesticides. Most of the GC-amenable endocrine disrupters were analyzed and their retention times appear in the table. However, the 209 polychlorinated biphenyl congeners were not included because their inclusion might actually complicate the identification of organochlorine pesticides.

Standards, diluted to 10 ppm in acetone, were first analyzed by GC-MS using the oven temperature program shown in figure 1a and instrumental conditions listed in table 1. Compound identities were verified by matching their spectra to library entries,³² by comparison with a published spectral compendium,³³ or by matching spectra to a list of charac-

teristic ions.⁶ When reference spectral information was not available, the pesticides were verified by spectral interpretation. Samples were then analyzed on two different 6890 GC-FID instruments under the same locked conditions (chlorpyrifos-methyl retention time = 16.596 minutes). The GC-MS retention time and the average of the two GC-FID retention times were tabulated for each compound along with its molecular formula, molecular weight, and CAS number. In addition to these fields, there are four user-definable columns in table 2 that can be used to add such things as mass spectral information, internal catalog numbers, or comments. Table 2 lists a small portion of the database. It must be noted that all retention time values were created using constant column head pressure. This is because GC-MS retention times are very close to those obtained with other detectors when constant pressure is used. In this mode, GC-MS and GC-FID retention times match within ± 0.1 minute except for three compounds that elute at the very end of the chromatogram. Even in this case, the differences are no more than 0.2 minute. The discrepancy between GC-MS and GC-FID retention times is larger in the constant flow mode.

Pesticide Screening Method

Figure 2 diagrams the pesticide screening method. First, RTL was used to match GC-AED and GC-MS analyte retention times to those listed in the pesticide table. Software for RTL¹⁴⁻¹⁶ was used to determine the




Figure 1. a) GC oven temperature program for the Agilent pesticide method at normal speed. When using this method, chlorpyrifos-methyl must be locked to 16.596 minutes. This method is used by GC-MS and can be used by any other GC system. b) GC oven temperature program for the Agilent pesticide method translated to run three times faster. This method may be used with 6890 GCs configured with any detector except an MSD so long as the GC is configured for fast oven temperature ramping. Chlorpyrifos-methyl must be locked to 5.532 minutes.

Table 2. Small Portion of the Pesticide and Endocrine Disrupter Retention Time Table That Contains 567 Entries. The retention times shown here are for the pesticide method run at normal speed as shown in figure 1a. Chlorpyrifos-methyl was locked to 16.596 minutes (± 0.015 minute for the collection of the tabulated retention time values. The table includes four additional columns for user-defined information.

FID RT	Name	CAS No.	Molecular Formula	MW	MSD RT
16.542	Acetochlor	34256-82-1	C:14,H:20,Cl:1,N:1,O:2,	269.77	16.542
16.549	Fuberidazole	3878-19-1	C:12,H:8,N:2,O:1,	196.21	16.549
16.583	Methyl parathion	298-00-0	C:8,H:10,N:1,O:5,P:1,S:1,	263.20	16.594
16.596	Chlorpyrifos methyl	5598-13-0	C:7,H:7,Cl:3,N:1,O:3,P:1,S:1,	322.53	16.593
16.637	Vinclozolin	50471-44-8	C:12,H:9,Cl:2,N:1,O:3,	286.11	16.630
16.650	Plifenat	21757-82-4	C:10,H:7,Cl:5,O:2,	336.43	16.641
16.689	Terbucarb	001918-11-2	C:17,H:27,N:1,O:2,	277.41	16.686
16.730	Chloranocryl	2164-09-2	C:10,H:9,Cl:2,N:1,O:1,	230.09	16.736
16.752	3-Hydroxycarbofuran	16655-82-6	C:12,H:15,N:1,O:4,	237.26	16.741
16.773	Heptachlor	76-44-8	C:10,H:5,Cl:7,	373.32	16.796
16.800	Carbaryl	63-25-2	C:12,H:11,N:1,O:2,	201.22	16.806

column head pressure needed to produce a retention time of 16.596 minutes for chlorpyrifos-methyl. When analyzing samples by GC-AED, the method was usually run at 3× speed and chlorpyrifos-methyl was locked to 5.532 minutes.

Figure 3 shows the RTL software screen that is used to develop the retention time calibration. To accomplish this for the pesticide method, one should install the 30 m × 0.25 mm × 0.25 µm HP-5MS column (part no. 19091S-433) and set the column head pressure to one of the appropriate nominal values as shown below, making sure to use the constant pressure mode.

- 26 psi for atmospheric pressure detectors run at normal speed (eg, NPD, FPD)
- 16 psi for GC-MSD operated at normal speed
- 27.5 psi for GC-AED operated at normal speed
- 88 psi for GC-AED operated at 3× speed

To prepare a calibration table similar to the one shown in figure 3, the chromatographer must make five analyses of chlorpyrifos-methyl at the following column head pressures: the nominal pressure, the nominal pressure + 20%, the nominal pressure + 10%, the nominal pressure – 10%, and the nominal pressure – 20%. Because of the first run affect, it is usually wise to make one or two blank runs before performing the five calibration runs. The five pressures and the chlorpyrifos-methyl retention times are entered into the table provided by the RTL software. This calibration table stays with the method and can be used to lock, or re-lock, the GC




Figure 2. Diagram of the screening method that uses retention time locking and retention time table searching to identify pesticides and suspected endocrine disrupters.

	Pressure	Ret Time
Run 1	22.08	17.831
Run 2	24.84	17.006
Run 3	27.6	16.302
Run 4	30.36	15.683
Run 5	33.12	15.145

Pressure Units:

Desired Ret Time:

Min relock pressure:

Max relock pressure:

Column:

Compound Name:

Buttons: OK, Cancel, Print, Help

Figure 3. RTL software screen showing typical retention time locking calibration data for the pesticide method run at normal speed using a GC detector that operates at atmospheric pressure.

method as long as that method is used. That is, the five calibration runs only need to be made once for a given method.

The software screen for locking the GC method is shown in figure 4. To lock the method, one enters the retention time of chlorpyrifos-methyl and clicks on the “Calc new pressure” button. The RTL software calculates the pressure needed to lock the chlorpyrifos-methyl peak at the desired retention time. By clicking on the “Update current 6890 Method” button, this value is entered automatically into the method.

One can use Agilent’s software for method translation¹⁷ to convert the method to other speeds (eg, 1.9×) and determine the nominal column head pressure required. If this is done, the pesticide table must be exported to a spreadsheet program where the analyte retention times can be divided by the appropriate factor (1.9 in this case). This new table can then be imported back into the ChemStation for use with the new method.

After locking the method to the table, GC-AED element-selective chromatograms were obtained for C, Cl, Br, N, S, P, and sometimes F. From the GC-AED chromatograms, it was usually possible to determine which heteroatoms were present or absent in the suspected pesticide peak. RTL software was then used to search the database by retention time and elemental content. Figure 5 shows the RTL software screen used for retention time table searching. One can enter the elements known to be present or not present in the GC-AED peak of interest. Up to six other element-selective detectors can be configured for use in the search algorithm. When the presence or absence of a heteroatom is uncertain,

(Re)Lock current method

Retention time:
Enter current retention time of:
chlorpyrifos-methyl
16.581 Minutes
Then select button 'Update Method' to calculate a new pressure and enter it in the method.

Method Information:
Current Method: RLPESCHK.
Column: 1
Pressure used: 26.39 psi
Desired RT: 16.596 Minutes
Calc new pressure: 26.33 psi

Update current HP6890 Method Print Done Help

Figure 4. RTL software screen used to calculate the column head pressure needed to lock or re-lock a method. In this case, the chlorpyrifos-methyl retention time was 16.581 minutes and the pressure needed to re-lock the method was calculated to be 26.33 psi. By clicking on the “Update current 6890 Method,” button, the new pressure is entered automatically into the GC method.

Search Retention Time Table

Load Table... HPPSTRC5.RTT : HP Pesticide RT Table Release Candidate 5

Search RT, minutes: 16.638
Search Window, minutes: 0.2

Compound contains these elements:
☐ Br ☐ Cl ☐ F ☒ N ☐ O ☒ P ☒ S
☐ ☐ ☐ ☐ ☐ ☐ ☐

Does not contain these elements:
☒ Br ☒ Cl ☐ F ☐ N ☐ O ☐ P ☐ S
☐ ☐ ☐ ☐ ☐ ☐ ☐

Compound detected with:
 NPD ☐
 FPD (P) ☐
 FPD (S) ☐
 ELCD ☐

Not detected with:
 NPD ☐
 FPD (P) ☐
 FPD (S) ☐
 ELCD ☐

Search Cancel Help

Figure 5. RTL software screen used to search a retention time table on the basis of retention time and known elemental content. In this case, the software will search the Agilent pesticide table at 16.638 ± 0.1 minutes for compounds that contain N, P, and S but do not contain Br or Cl. If element-selective detectors (such as the NPD) are used, this information can be provided to the search routine. Up to six different element-selective detectors can be configured as shown for NPD, FPD (P), FPD (S), and ELCD.

nothing is added to the search routine for that element.

One must choose a search time window wide enough to include the correct analyte, but narrow enough to eliminate as many extraneous “hits”

as possible. Experience has shown that the normal speed method requires a search window of 0.2 to 0.3 minute. The 3× speed method can use a search window of 0.1 minute. If the heteroatom content is known for a peak, retention time table searching

with these search windows most often finds just one pesticide and rarely finds more than three possibilities.

Confirmation is usually done by GC-MS under locked conditions so that all GC-MS retention times match the values listed in the pesticide retention time table. This was found to be of enormous benefit. Prior to GC-MS confirmation, the analyst already knows which pesticides to look for and their expected retention times. Alternatively, when there is adequate signal to quantitate the analyte in multiple AED element-selective chromatograms, it is often possible to confirm a pesticide's identity simply by calculating its heteroatom ratio. GC-AED software for element ratioing facilitates this procedure.

Analysis of a Green Onion Extract

Numerous samples of fruit and vegetable extracts have been analyzed using this methodology. The results for a green onion extract illustrate the versatility and potential of this method.

Green onion extracts are usually very dirty and contain a large number of co-extracted sulfur compounds that can obscure sulfur-containing pesticides. The onion chromatograms shown in figure 6 were run under locked conditions at 2× speed in Tallahassee, Florida, by the Department of Food and Agriculture using a 5890 SERIES II/5921A GC-AED system. Retention time searching indicated that folpet was present in the sample, but it could not be confirmed at the time. The same sample was sent to the Agilent Technologies Little Falls Site in Wilmington, DE, where it was analyzed by scanning GC-MS using an 6890/5973 system. As shown in figure 7, folpet was

easily confirmed at the expected retention time. In addition, the pesticides trichlorophenol, chlorothalonil, propoxur, and prochloraz were identified. Searching the CI peak at about 6 minutes gave no pesticide hits. However, GC-MS suggested the presence of a trichloronaphthalene isomer at the corresponding retention time in the GC-MS chromatogram (about 12 minutes because the GC-MS was operated at normal speed). Though not a pesticide, trichloronaphthalene is considered to be a hazardous compound that should not be in food.

The same green onion sample was then analyzed by the newer model GC-AED system (6890/G2350A) at 3× speed (figure 8). Several more pesticides were identified by searching the pesticide/ endocrine disrupter table using a 0.1-minute retention time window. Table 3 lists the pesticide hits that were obtained for each retention time search using the available GC-AED data. Sulfur was not included in any of the searches

because onion extracts have such a high sulfur background.

Confirmation by GC-MS was much easier because the GC-MS retention time for each pesticide hit was printed out with the RT search report. Thus, the retention times and probable identities of each pesticide were already known before the GC-MS analysis was run. As is shown in figure 7 for folpet, one can simply extract the ions characteristic for each pesticide hit and look in the extracted ion chromatogram at the expected retention time.

Quantitative Analysis

The Agilent pesticide screening method is a qualitative tool to identify any of the 567 pesticides and endocrine disrupters listed in the retention time table. This, of course, is the first step in any pesticide screening method. Quantitative analysis can be performed in one of two ways.




Figure 6. CI- and N-selective chromatograms of a green onion extract from an 5890/5921A GC-AED system. The analysis was performed at 2× speed under locked conditions in Tallahassee, Florida, by the Department of Agriculture and Consumer Services. In addition to folpet, trichlorophenol, propoxur, and prochloraz were identified by retention time table searching and confirmed by GC-MS at their expected retention times. There were no hits for the CI peak at about 6 minutes, which was identified by GC-MS as a trichloronaphthalene isomer.

The traditional method is to inject standards into the GC, GC-AED, or GC-MS system to determine response factors from which quantitative results are calculated by the ChemStation software. However, because the GC-AED elemental response is almost independent of molecular structure, compound-independent calibration (CIC) can be used to quantitate all of the pesticides and endocrine disrupters that are found. For example, one could spike chlorpyrifos-methyl ($C_7H_7Cl_3NO_3PS$) at a known concentration into each pesticide extract and obtain element-specific calibration curves for Cl, N, P, and S. These curves could then be used to calibrate for any other compound containing one or more of these elements. Because the GC-AED is quite stable, external standard CIC often works just as well. The GC-AED software facilitates CIC. Unfortunately, this procedure determines the amount of a compound that reaches the AED and does not compensate for losses due to decomposition or adsorption in the inlet or column.

Conclusions

Most screening procedures in use today are capable of finding only a fraction of the pesticides that are registered around the world. This new method has the capability of screening for virtually any volatile pesticide, metabolite, or endocrine disrupter. Although confirmation is usually required, GC-MS analysis is made much easier and more reliable because the pesticide's retention time and probable identity are already known.




Figure 7. Confirmation of folpet in a green onion extract. The tabulated GC-MS retention time is 21.594 minutes, and folpet was detected in this sample at 21.637 minutes by simply extracting its characteristic ions.




Figure 8. Element-selective chromatograms obtained for the same green onion extract shown in figure 6. These chromatograms were obtained at 3× speed using an 6890/G2350A GC-AED system.

While GC-AED is an ideal tool for element-selective pesticide screening,^{20–22} many laboratories rely on a combination of other selective detectors. It is still possible to apply this method if each GC system runs the Agilent pesticide method under the same locked conditions. Any combination of GC-AED and/or element-selective detector response data can be entered into the RTL searching software.

When combined with RTL and retention time searching, GC-AED and GC-MS provide the most comprehensive and reliable screening method available for pesticides, metabolites, and suspected endocrine disrupters. Unlike most target compound methods in use today, this procedure has a good chance of finding and identifying unexpected or unknown pesticides, even in complex food extracts. RTL software makes it easy to add more compounds to the method, simply by determining their retention times under the same locked conditions.

Retention time locking with database searching could easily be applied to similar types of analyses. For example, one might use the procedure to identify polychlorinated biphenyls, polynuclear aromatics, drugs of abuse, or flavor and fragrance compounds.

Acknowledgments

The authors wish to thank the following people for their contributions to the development of this method: Joanne Cook and Marc Engel (Florida Department of Agriculture and Consumer Services) for supplying a green onion chromatogram, for contributing fruit and vegetable extracts, and for

Table 3. Green onion pesticide "hits" obtained by searching the 567-compound pesticide/endocrine disrupter RT table using a 0.1-minute RT window and element-selective GC-AED data. Compounds confirmed by GC-MS are shown for comparison. The GC/MS (figure 7) and GC-AED (figure 8) chromatograms were obtained at normal and 3X speeds, respectively. Sulfur peaks were not used to narrow the search because of the high background of sulfur-containing compounds in the onion extract.

GC-AED RT	RT Search Hits	Confirmed by GC-MS
1.933	Dichlorvos	Dichlorvos
2.281	2,4,6-Trichlorophenol 2,4,5-Trichlorophenol	2,4,5-Trichlorophenol
3.440	Fenobucarb Propoxur 4,6-Dinitro-o-cresol	Propoxur
3.854	No pesticide hits	Trichloronaphthalene isomer
4.955	Terbacil Chlorothalonil	Chlorothalonil
5.538	Chlorpyrifos-methyl	Chlorpyrifos-methyl
7.232	Folpet Chlorbenside	Folpet
9.965	Mirex	Mirex
10.588	Prochloraz	Prochloraz

beta testing the method; Matthew Klee and Leonid Blumberg for many useful discussions; and James Green and Takeshi Otsuka for their help in developing the retention time table.

References

1. C. Tomlin (Ed.), *The Pesticide Manual*, Eleventh Edition, British Crop Protection Council, Farnham, Surrey, UK, 1997.
2. R. W. Miller, *This is Codex Alimentarius*, Secretariat of the Joint FAO/WHO Food Standards Programme, Food and Agriculture Organization of the United Nations, Rome.
3. B. M. McMahon and N. F. Hardin (Eds.), *Pesticide Analytical Manual*, Vol. I, Third Edition, U.S. Food and Drug Administration, Washington, D.C., 1994.
4. S. M. Lee, M. L. Papathakis, H.-M. C. Feng, G. G. Hunter, and J. E. Carr, *Fresenius' J Anal Chem* **339**, 376–383, 1991.
5. J. Fillion, R. Hindle, M. Lacroix, and J. Selwyn, *J AOAC Int* **78**, 1252–1266, 1995.
6. Working Group on Development and Improvement of Residue-analytical Methods, *Analytical Methods for Pesticide Residues in Foodstuffs*, General Inspectorate for Health Protection, Ministry of Public Health, Welfare and Sport, The Netherlands, 1996.
7. M. A. Luke, J. E. Froberg, G. M. Doose, and H. T. Masumoto, *J Assoc Off Anal Chem* **64**, 1187–1195, 1981.
8. H.-J. Stan (Ed.), *Analysis of Pesticides in Ground and Surface Water II*, Springer-Verlag, Berlin, Germany, 1995.
9. R. E. Wagner, W. Kotas, and G. A. Yogis (Eds.), *Guide to Environmental Analytical Methods*, 2nd Edition Genium, Schenectady, NY, 1994.
10. U.S. Environmental Protection Agency, *Test Methods for Evaluating Solid Waste*, SW-846, Draft Method 8085: Pesticides by GC-AED.

11. T. Colborn, D. Dumanoski, and J. P. Myers, *Our Stolen Future* Penguin, New York, NY, 1996.
12. Food Quality Protection Act of 1996, Public Law 104-170, Congressional Record, pp. H8127–H8141.
13. Safe Drinking Water Act Amendments of 1996, Public Law 104-182, Congressional Record pp. H9680–H9700.
14. V. Giarrocco, B. Quimby, and M. Klee, Retention Time Locking: Concepts and Applications, Application Note 228-392, Publication (23) 5966-2469E, December 1997.
15. P. L. Wylie and B. D. Quimby, Abstracts of the 1st European Pesticide Residue Workshop, Alkmaar, The Netherlands, Paper # O-023, June 10–12, 1996.
16. M. Klee and T. Sullivan, Environ. Testing and Analysis, pp. 16–17 and 44–45, March/April 1998.
17. Hewlett Packard Company, *Software for Method Translation*, Available on the World Wide Web at: <http://www.chem.agilent.com/cag/servsup/usersoft/main.html>.
18. M. L. Lee, F. J. Yang, and K. D. Bartle, *Open Tubular Column Gas Chromatography, Theory and Practice*, Wiley, New York, NY, pp. 217–218, 1984.
19. C. Bicchì, A. D'Amato, and A. Binello, *J High Resol Chromatogr* **19**, 80–84, 1996.
20. S. M. Lee and P. L. Wylie, *J Agric Food Chem* **39**, 2192–2199, 1991.
21. P. L. Wylie and R. Oguchi, *J Chrom* **517**, 131–142, 1990.
22. N. L. Olson, R. Carrell, R. K. Cummings, and R. Rieck, *LC-GC* **12**, 142–154, 1994.
23. P. L. Wylie and K. Uchiyama, *J AOAC Int* **79**, 571–577, 1996.
24. P. L. Wylie, K. L. Klein, M. Q. Thompson, and B. W. Hermann, *J High Resol Chromatogr* **15**, 571–577, 1992.
25. W. D. Snyder and L. M. Blumberg, *Proceedings of the Fourteenth International Symposium on Capillary Chromatography*, Baltimore, MD, pp. 28–38, May 25–29, 1992.
26. B. D. Quimby, L. M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking," Application Note 228-401, Publication 5967-5820E, April 1998.
27. <http://www.nij.gov/hse/environ/edsub/substancesnew.html>.
28. <http://www.wwfcanada.org/hormone-disruptors>.
29. <http://www.epa.gov/opptintr/opptendo/index.htm>.
30. <http://www.osf-facts.org/basics.chemlist.html>.
31. <http://www.mst.dk/liste.htm>.
32. Hewlett-Packard Company. Mass Spectral Libraries: HP Pest library, Wiley 275 library, NBS75K Library, Palo Alto, CA.
33. Pesticide Reference Spectra, Vol. 1–4, Spectral Service GmbH, Köln, Germany and Riedel-de Haën AG, Seelze, Germany, 1992.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Microsoft® and Windows NT® are U.S. registered trademarks. HP® is a registered trademark of Hewlett-Packard Company.


Copyright ©2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5967-5860E



Agilent Technologies
Innovating the HP Way

Analysis of Sulfur and Phosphorus Compounds with a Flame Photometric Detector on the Agilent 6890 Series Gas Chromatograph



Application

Gas Chromatography

February 1997

Authors

William H. Wilson
Matthew S. Klee
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A gas chromatograph (GC) with a flame photometric detector (FPD) is frequently employed in analyzing complex samples for specific compounds. The wavelength filter of the FPD can be set to select for many elements, but it is most commonly used to detect sulfur and phosphorus. This application note discusses the uses of the FPD in gas chromatography, demonstrates the linearity and method detection limits (MDL) of the 6890 Series GC with an FPD, and gives examples of analyses of organophosphorus pesticides using the 6890 GC with an FPD.

Key Words

Gas chromatography, flame photometric detector, FPD, sulfur analysis, phosphate analysis, pesticides, organophosphorus pesticides, EPA method 1618, EPA method 622.

Introduction

The flame photometric detector is one of the most widely used selective detectors in gas chromatography. The FPD consists of a reducing flame that produces chemiluminescent species. These species emit characteristic light that is optically filtered for the desired wavelength; the wavelength selection determines which compound is detected. The filtered light is measured by a photomultiplier and transduced into a signal. A second photomultiplier can be added, which allows simultaneous detection of a second signal.

FPD filters can be selected for many different compounds, but the most common uses are for the selective detection of sulfur and phosphorus compounds in complex mixtures. The selectivity of classical FPDs is typically (as a ratio by weight to carbon) 10^5 for sulfur and 10^6 for phosphorus. The FPD operates over a dynamic range of 1×10^3 for sulfur and 1×10^4 for phosphorus.¹

Gas chromatography with an FPD can be used to detect sulfur compounds in crude oil and sulfur contaminants in natural gas.

In food analysis it is used to detect off-flavors resulting from the libera-

tion of volatile sulfur compounds. It is also used to simultaneously detect sulfur and phosphorus in chemical warfare agents. In the environmental area, the FPD is used for detection of organophosphorus pesticides and herbicides. Several EPA methods for pesticide detection, including EPA methods 1618² and 622³, specify the use of an FPD.

A schematic of a single FPD for the 6890 Series GC is shown in figure 1. A dual wavelength version is available that has a second photomultiplier mounted perpendicular to the first for simultaneous detection of a second wavelength. The 6890 GC is available with either a single or dual FPD.

The sensitivity of any FPD is affected by detector temperature, flame chemistry, and filter wavelength.

- **Detector temperature.** To protect the photomultiplier, the maximum temperature limit for the 6890 FPD is 250 °C. Photomultiplier tube (PMT) noise increases with setpoint temperature, so the detector temperature should be as low as possible. Generally, the temperature should be set about 25 °C above the highest temperature reached in the oven program. To prevent water condensation and clouding of the window, the minimum operating temperature is 120 °C.⁴



Agilent Technologies
Innovating the HP Way

- **Flame chemistry.** FPD sensitivity is highly dependent on detector gas flows. On the 6890 GC, the gas flows are electronically controlled. This allows rapid and precise optimization of flow rates. Sulfur and phosphorus modes have different optimum flow requirements, so the ability to easily set and reset flows increases the quality of results and saves time.
- **Filter wavelength.** For the FPD, filters of specific wavelength are physically installed in the detector. A 394-nm filter is used for sulfur detection, and 526-nm filter for phosphorus detection.




Figure 1. Single photomultiplier tube FPD for 6890 Series GC

Experimental

All experiments were performed on a 6890 Series GC with electronic pneumatics control (EPC) and an Agilent 7673 automatic liquid sampler (ALS). An Agilent 1707A ChemStation was used for instrument control and data acquisition. Chromatography conditions are shown with the individual chromatograms in figures 2, 3, and 4.

Table 1. MDL and Linearity over 10² Range Sulfur Mix on the FPD

Peak Number	Compound Name	MDL pgS/sec n = 11	Linearity r ² n = 15
1	2,5-dimethylthiophene	26.22	0.9986
2	sec-butylsulfide	20.10	0.9983
3	1,4-butanedithiol	22.27	0.9972
4	dodecanethiol	16.90	0.9985
5	octyl sulfide	16.14	0.9979

Results and Discussion

Linearity and MDL

In sulfur mode, the response of the FPD is proportional to analyte concentration squared. The calculated MDL and r² values from linearity experiments for a single photomultiplier in sulfur mode are listed in table 1, and the chromatogram for a 20–40 ppb sample from the experiment is shown in figure 2. The square of the concentration was used to calculate regression statistics. When using a ChemStation for data analysis, a quadratic calibration fit is used for sulfur.




Figure 2. 1 µL of 1.5 ppm sulfur standard, FPD in sulfur mode (The peaks are identified in table 1.)

The response of the FPD is linear in phosphorus mode. Table 2 shows the r^2 values for an organo-phosphorus pesticide mixture and the MDL calculated from the study. Figure 3 shows the chromatogram. A standard linear curve fit is used for phosphorus when using a ChemStation for data analysis.

Analysis of EPA Method 1618

Figure 4 shows the chromatogram obtained from the analysis of organophosphorus pesticides according to EPA method 1618. The injected concentration of each compound was 1–2 ppm.

Table 2. MDL and Linearity over 10^3 Range for Organophosphorus Pesticides on the FPD

Peak Number	Compound Name	MDL pgPesticide/sec n = 11	Linearity r^2 n = 15
1	phorate	1.85	0.9996
2	demeton	1.13	> 0.9998
3	disulfoton	1.31	> 0.9999
4	diazinon	1.74	> 0.9999
5	malathion	1.74	> 0.9999
6	fenthion	1.75	> 0.9999
7	parathion	1.84	> 0.9999
8	trichloronate	2.27	> 0.9999
9	tokuthion	2.51	> 0.9999
10	fensulfothion	—	> 0.9999
11	ethion	1.29	> 0.9999
12	sulprofos	2.36	> 0.9999
13	guthion	1.24	> 0.9999
14	coumaphos	2.08	> 0.9999




Figure 3. 1 μ L Splitless injection of 20–40 ppb organophosphorus pesticide standard, FPD in phosphorus mode (The peaks are identified in table 2.)




Figure 4. Analysis of organophosphorus pesticides according to EPA method 1618, 1 μ L on-column injection of 1–2 ppm standard, FPD in phosphorus mode (The peaks are identified in table 2.)

Conclusions

The Agilent 6890 Series GC with an FPD can be used for the sensitive, and selective measurement of sulfur- and phosphorus-containing compounds in complex mixtures. The electronic pneumatics control on the Agilent 6890 GC ensures rapid and accurate gas flow control, provides for easier method setup and documentation, and simplifies optimization.

3. EPA Method 622, *USEPA Method 622: The Determination of Organophosphorus Pesticides in Municipal and Industrial Wastewater*, USEPA Report #600/4-82-008, NTIS #82-156027.
4. *Operating Manual, Flame Photometric Detector*, Agilent Technologies, Part Number G1535-90100.

References

1. *Detectors for Gas Chromatography*, Agilent Technologies, Part Number 5958-9433E, 1991.
2. EPA Method 1618, *USEPA Method 1618: Organo-halide Pesticides, Organo-phosphorus Pesticides, and Phenoxy-Acid Herbicides by Wide-Bore Capillary Column Gas Chromatography with Selective Detectors*, Revision A, 1989, Office of Water Regulations and Standards.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5965-7442E



Agilent Technologies
Innovating the HP Way

Analysis of Organochlorine Pesticides and PCB Congeners with the Agilent 6890 Micro-ECD



Application

Gas Chromatography

June 1997

Authors

Isabelle Chanel
Agilent Technologies, Inc.
European Marketing Group
76337 Waldbron
Germany

Imogene Chang
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A new electron capture detector (ECD) for the Agilent 6890 Series gas chromatograph (GC) was used to analyze polychlorinated biphenyl congeners and organochlorine pesticides. The linearity of the 6890 Micro-ECD in the calibration range of 2 to 400 ppb was evaluated. The micro-ECD easily meets the linearity requirements of U.S. EPA contract laboratory programs for pesticides. Its limit of detection for these compounds goes down to less than 50 ppt. The micro-ECD also exhibits good reproducibility.

Key Words

Organochlorine pesticides, PCB congeners, 6890 GC, micro-ECD; pesticide analysis, ECD.

Introduction

The electron capture detector (ECD) is the detector of choice in many Contract Laboratory Programs (CLP)¹ and EPA methods for pesticide analysis because of its sensitivity and selectivity for halogenated compounds. However, there are drawbacks to the ECD design. The ECD is inherently nonlinear², with a limited linear range. The limited linear range means that dilution and reanalysis are frequently required for samples that are outside the calibration range.

Also, the typical ECD is designed to be compatible with both packed and capillary columns. This results in a flow cell that is larger than that required for capillary columns alone, which reduces detector sensitivity.

To address these problems, a new ECD was developed for the 6890 Series gas chromatograph (GC). The 6890 Micro-ECD has a smaller flow cell optimized for capillary columns and was redesigned to improve the linear operating range.

This application note examines the linearity, reproducibility, and limit of detection of the new ECD with mixtures of polychlorobiphenyl (PCB) congeners and organochlorine pesticides (OCPs).

Experimental

All experiments were performed on an 6890 Series GC with electronic pneumatics control (EPC) and the 6890 Micro-ECD. Table 1 shows the experimental conditions for PCB congeners and OCPs.

Table 1. Experimental Conditions for PCB Congener and OCP Analysis.

System Conditions	PCB Congener Analysis	OCP Analysis
Oven	80 °C (2 min); 30 °C/min to 200 °C; 10 °C/min to 320 °C (5 min).	80 °C (2 min); 25 °C/min to 190 °C; 5 °C/min to 280 °C; 25 °C/min to 300 °C (2 min).
Inlet	Split/splitless; 300 °C	Split/splitless; 250 °C
Carrier	Helium, 16.8 psi (80 °C); 1.3-mL/min constant flow	Helium, 23.9 psi (80 °C); 2.2-mL/min constant flow
Sampler	Agilent 7673, 10- μ L syringe, 1- μ L splitless injection	7673, 10- μ L syringe, 1- μ L splitless injection
Column	30-m, 250- μ m id, 0.25- μ m film HP-5MS (part no. 19091S-433)	30-m, 250- μ m id, 0.25- μ m film HP-5MS (part no. 19091S-433)
Detector	330 °C; makeup gas: nitrogen, constant column and makeup flow	330 °C; makeup gas: nitrogen, constant column and makeup flow



Agilent Technologies
Innovating the HP Way

The solutions were prepared by making appropriate dilutions of a stock solution with isooctane. For PCB congeners, the stock solution was an EPA PCB congener calibration check solution (from Ultra Scientific Company, part number RPC-EPA-1). For OCPs, the solution was an OCP calibration check solution (part number 8500-5876).

Results and Discussion

Linearity and Response Factors

A series of dilutions of the PCB mixture from 2 ppb to 200 ppb and of the OCP mixture from 2 ppb to 400 ppb was injected into the 6890 Micro-ECD system. The linearity was determined by calculating the correlation coefficient from the resulting calibration curve.

Figures 1 and 2 present typical chromatograms of OCPs and PCBs at 20 or 40 ppb and 50 ppb, respectively. Figure 3 is a calibration curve of decachlorobiphenyl, typical of other PCB congeners. Figure 4 shows the calibration curve of 4, 4' DDE, typical of OCPs. The correlation coefficient,




Figure 1. Typical chromatogram of OCPs at 20 or 40 ppb.
See table 1 for conditions. See table 5 for peak identification.




Figure 2. Typical chromatogram of PCB congeners at 50 ppb.
See table 1 for conditions. See table 4 for peak identification.




Figure 3. Typical linearity of PCB congener analysis: decachlorobiphenyl from 2-200 ppb.




Figure 4. Typical linearity of OCP analysis: 4,4' DDE from 4 to 400 ppb.

average response factors, and percent relative standard deviation (%RSD) for the response factors for each analyte are shown in tables 2 and 3.

All correlation coefficients were at least 0.9996. In these experiments, the 6890 Micro-ECD is linear over this range. The typical range required by CLP methods is 5-80 ppb¹, so the 6890 Micro-ECD exceeds the range by almost twofold.

In addition, the CLP method requires the percent RSD of the response factors for most components to be less than 20 percent for a three-point calibration curve (5 to 80 ppb). As shown in tables 2 and 3, the percent RSD of the response factors ranged from 0.55 percent to 12.5 percent for the PCB congeners and from 2.8 percent to 10 percent for the OCPs over a concentration range of two orders of magnitude (2 to 400 ppb). Furthermore, the average response factor of each analyte was so consistent and reproducible that the internal standard technique can be used to quantify all OCPs and PCB congeners.

Table 2. PCB Congener Analysis: Linearity of the 6890 Micro-ECD 2 ppb to 200 ppb.
See table 1 for conditions.

Peak	Name	Average Response Factor	%RSD of Response Factor	Correlation (%)
1	2,4-Dichlorobiphenyl	2e-2	12.5	99.97
2	2,2',5-Trichlorobiphenyl	2e-2	11.1	99.97
3	2,4,4'-Trichlorobiphenyl	8.5e-3	7.5	99.99
4	2,2',5,5'-Tetrachlorobiphenyl	1.3e-2	10.2	99.97
5	2,2',3,5-Tetrachlorobiphenyl	1e-2	9.4	99.98
6	2,3,4,4'-Tetrachlorobiphenyl	8e-3	6.7	99.99
7	2,2',4,5,5'-Pentachlorobiphenyl	9e-3	8.8	99.98
8	3,3',4,4'-Tetrachlorobiphenyl	1.2e-2	12.6	99.97
9	2,3,4,4',5-Pentachlorobiphenyl	8e-3	5.5	99.99
10	2,2',4,4',5,5'-Hexachlorobiphenyl	8e-3	8.1	99.98
11	2,3,3',4,4'-Pentachlorobiphenyl	6e-3	1.9	99.99
12	2,2',3,4,4',5-Hexachlorobiphenyl	6.5e-3	3.8	99.99
13	3,3',4,4',5-Pentachlorobiphenyl	9e-3	6.5	99.99
14	2,2',3,4,5,5',6-Heptachlorobiphenyl	8e-3	5.7	99.99
15	2,2',3,3',4,4'-Hexachlorobiphenyl	5.6e-3	1.8	99.99
16	2,2',3,4,4',5,5'-Heptachlorobiphenyl	5.8e-3	1.0	99.99
17	2,2',3,3',4,4',5-Heptachlorobiphenyl	5.8e-3	0.57	99.99
18	2,2',3,3',4,4',5,6-Octachlorobiphenyl	6e-3	0.78	99.99
19	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	8e-3	3.1	99.96
20	Decachlorobiphenyl	1e-2	9.5	99.98

Table 3. OCP Analysis: Linearity of the 6890 Micro-ECD 2 or 4 ppb to 200 or 400 ppb.
See table 1 for conditions.

Peak	Name	Average Response Factor	% RSD of Response Factor	Correlation (%)
1	2,4,5,6-Tetra-m-xylene	4.2e-3	5.3	99.97
2	beta-BHC	1.1e-2	7.1	99.99
3	delta-BHC	6.4e-3	4.7	99.99
4	Aldrin	4.7e-3	9.5	99.97
5	Heptachlor epoxide	4.7e-3	5.4	99.99
6	gamma-Chlordane	6.6e-3	6.6	99.99
7	alpha-Chlordane	5e-3	4.3	99.98
8	4,4' DDE	5e-3	2.8	99.99
9	Endosulfan II	2.9e-3	4.4	99.98
10	Endrin aldehyde	4.5e-3	5.9	99.94
11	Endosulfan sulfate	5.1e-3	5.3	99.97
12	Endrin ketone	4.7e-3	9.0	99.89
13	Decachlorobiphenyl	3.7e-3	9.9	99.96

Reproducibility

The reproducibility of the 6890 Micro-ECD was established by analyzing each mixture using identical conditions five times. Each analyte in the PCB congener mixture was injected at a concentration of 50 ppb, and the analytes in the OCP mixture were 20 or 40 ppb. The results are shown in tables 4 and 5. The highest %RSD for any analyte is 3.69 percent for aldrin, which is well below the CLP maximum allowable RSD of 15 percent.¹

Table 4. PCB Congener Analysis: Reproducibility of the 6890 Micro-ECD 50 ppb; N=5.
See table 1 for conditions.

Peak	Name	Average	RSD
		Area	(%)
1	2,4-Dichlorobiphenyl	2229	1.26
2	2,2',5-Trichlorobiphenyl	2547	1.29
3	2,4,4'-Trichlorobiphenyl	5687	1.41
4	2,2',5,5'-Tetrachlorobiphenyl	3721	1.43
5	2,2',3,5-Tetrachlorobiphenyl	4941	1.46
6	2,3,4,4'-Tetrachlorobiphenyl	5943	1.40
7	2,2',4,5,5'-Pentachlorobiphenyl	5089	1.47
8	3,3',4,4'-Tetrachlorobiphenyl	3822	1.72
9	2,3,4,4',5-Pentachlorobiphenyl	6203	1.62
10	2,2',4,4',5,5'-Hexachlorobiphenyl	6189	1.44
11	2,3,3',4,4'-Pentachlorobiphenyl	8375	1.68
12	2,2',3,4,4',5-Hexachlorobiphenyl	7538	1.56
13	3,3',4,4',5-Pentachlorobiphenyl	5092	2.02
14	2,2',3,4,5,5',6-Heptachlorobiphenyl	6224	1.69
15	2,2',3,3',4,4',5-Hexachlorobiphenyl	8921	1.67
16	2,2',3,4,4',5,5'-Heptachlorobiphenyl	8527	1.82
17	2,2',3,3',4,4',5-Heptachlorobiphenyl	8625	1.91
18	2,2',3,3',4,4',5,6-Octachlorobiphenyl	8338	2.13
19	2,2',3,3',4,4',5,5',6-Nonachlorobiphenyl	6097	2.55
20	Decachlorobiphenyl	4622	2.85

Table 5. OCP Analysis: Reproducibility of the 6890 Micro-ECD; N=5.
See table 1 for conditions.

Peak	Name	Concentration	Average	RSD
		(ppb)	Area	(%)
1	2,4,5,6-Tetra-m-xylene	20	4785	0.7
2	beta-BHC	20	1802	0.81
3	delta-BHC	20	3251	1.50
4	Aldrin	20	402	3.69
5	Heptachlor epoxide	20	4316	1.58
6	gamma-Chlordane	20	2958	1.23
7	alpha-Chlordane	20	4219	1.06
8	4,4' DDE	40	4103	1.76
9	Endosulfan II	40	7176	1.27
10	Endrin aldehyde	40	4719	0.85
11	Endosulfan sulfate	40	4040	3.04
12	Endrin ketone	40	4386	2.52
13	Decachlorobiphenyl	40	5369	0.85

Detection Limit

To establish the lower limit of detection for the 6890 Micro-ECD with PCBs and OCPs, 1- μ L injections were made at gradually decreasing concentrations. Figures 5 and 6 show chromatograms with analyte concentrations of 50 to 100 ppt.

All the analyte peaks for both the PCB congener and OCP mixtures are still easy to quantitate, and in fact smaller concentrations can be reliably analyzed. Aldrin, which has the lowest response of the OCPs, still exhibits an adequate signal-to-noise ratio at the 50 ppt level under these analysis conditions.

Conclusion

The Agilent 6890 Micro-ECD response was linear over the concentration range of 2 to 200 ppb, produced reproducible results, and exhibited excellent sensitivity for mixtures of PCB congeners and OCPs.

References

1. U.S. EPA Contract Laboratory Program, "Statement of Work for Organic Analysis," OLM03.1, August 1994.
2. R. Buffington and M.K. Wilson, eds., *Detectors for Gas Chromatography*, Agilent Technologies, Inc., Part Number 5958-9433, 1987.




Figure 5. PCB congener mixture at 50 ppt each.

See table 1 for conditions. See table 4 for peak identification.




Figure 6. OCP Mixture at 50 to 100 ppt.

See table 1 for conditions. See table 5 for peak identification.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Copyright © 2000
Agilent Technologies, Inc.

Printed in the USA 3/2000
5965-8556E



Agilent Technologies
Innovating the HP Way

Fast Screening of Pesticide and Endocrine Disruptors Using the Agilent 6890/5973N GC/MSD System, Part I



Application

Gas Chromatography
January 2000

Authors

C. Kai Meng
Agilent Technologies
2850 Centerville Road
Wilmington, Delaware 19808-1610
USA

Michael Szelewski
Agilent Technologies
2850 Centerville Road
Wilmington, Delaware 19808-1610
USA

Abstract

Agilent Technologies' new, fast GC/MSD method can significantly speed up the screening of pesticides. Agilent's GC method translation software (available free from the Agilent Technologies Web site, <http://www.chem.agilent.com/cag/servsup/usersoft/main.html#mxlator>) was used in developing the new method based on the standard 42-min method. A 10 m x 0.1 mm x 0.1 μ m HP-5 column was used to increase analysis speed up to fourfold. The time savings were implemented in increments (down to 10.5 minutes) to verify the predictability of scaling and the effect of scaling on the signal-to-noise ratio.

Key Words

RTL, pesticide, environmental, screening, fast GC, method translation, 5973, 6890, MTL

Introduction

Analysts want faster analyses to improve laboratory productivity. Often, when speeding up GC methods, an analyst will trade resolution for increased analysis speed. This loss of resolution can complicate peak identification, even with a mass selective detector (MSD).

Agilent Technologies has developed new techniques to solve the peak identification problem based on Agilent's retention time locking (RTL) software and a new mass spectral library that contains the locked

retention times and characteristic ions for 567 of the most common pesticides and endocrine disruptors of concern worldwide. A GC/MSD method was developed based on the standard 42-min method¹ to screen for all 567 of the most common analytes. A specific combination of column stationary phase, carrier gas flow rate, and oven temperature programming is required to lock all the compounds to an expected retention timetable². Compound identification based only on spectral searching alone is difficult when analyzing extracts containing significant sample matrix content because of overlapping peaks and noisy baselines.

The new screening tool, integrated within Agilent's ChemStation for MSD, searches for all 567 compounds by first checking and integrating four characteristic ions within the expected time window, and second by printing out a report showing "hits" and "possible hits" (ratios of characteristic ions that do not match the expected values in the library within specified limits).

In one application, the analysis time of the standard pesticide method was reduced by one half, two-thirds, and three-fourths. The faster methods were scaled exactly as predicted by using a combination of Agilent's method translation (MTL) and RTL software. Because scaling was exact, these faster methods can be used with precisely-scaled pesticide libraries, making the screening process even more powerful and adaptable to individual needs.



Agilent Technologies
Innovating the HP Way

Experimental

The GC method translation software tool was used to find operating conditions for the faster methods. Figure 1 is a screen capture of MTL software data entry showing the original conditions and the new chromatographic conditions for a twofold speed gain. The column flow rate, which is helpful to avoid exceeding MSD pumping capacity³, is also found in the table. A 16:1 split ratio was suggested in the table as a proportional scaling from the original column to the smaller i.d. column with corresponding lower capacity. The program also determined the required column head pressure and corresponding oven ramp. The Agilent 6890 GC fast oven option (220/240V in the U.S.) was required for the faster oven ramp used in this study.

GC Method Translation - RTL2X.MXD

Criterion: ☐ Translate Only ☐ Best Efficiency ☐ Fast Analysis ☒ None Speed gain: 2.00000

		Original Method	Translated Method																																				
Column Length,	m	30.00	☐ 10.00																																				
Internal Diameter,	µm	250.0	☐ 100.0																																				
Film Thickness,	µm	0.250	☐ Unlock																																				
Phase Ratio		250.0	☐ 0.100																																				
			☒ 250.0																																				
Carrier Gas		Helium	Helium																																				
Enter one Setpoint			☒ Unlock																																				
Head Pressure,	psi	18.000	☐ 30.715																																				
Flow Rate,	mLn/min	1.9015	☐ 0.2817																																				
Outlet Velocity,	cm/sec	Very large	Very large																																				
Average Velocity,	cm/sec	50.30	☐ 33.53																																				
Hold-up Time,	min	0.994049	☐ 0.497025																																				
Outlet Pressure (absolute),	psi	0.000	☒ 0.000																																				
Ambient Pressure (absolute),	psi	14.696	☒ 14.696																																				
Oven Temperature	3-ramp Program																																						
		<table><thead><tr><th>Ramp Rate</th><th>Final Temp.</th><th>Final Time</th></tr><tr><th>°C/min</th><th>°C</th><th>min</th></tr></thead><tbody><tr><td></td><td>70.00</td><td>2.000</td></tr><tr><td>25.000</td><td>150.00</td><td>0.000</td></tr><tr><td>3.000</td><td>200.00</td><td>0.000</td></tr><tr><td>8.000</td><td>280.00</td><td>10.000</td></tr></tbody></table>	Ramp Rate	Final Temp.	Final Time	°C/min	°C	min		70.00	2.000	25.000	150.00	0.000	3.000	200.00	0.000	8.000	280.00	10.000	<table><thead><tr><th>Ramp Rate</th><th>Final Temp.</th><th>Final Time</th></tr><tr><th>°C/min</th><th>°C</th><th>min</th></tr></thead><tbody><tr><td></td><td>70.00</td><td>1.000</td></tr><tr><td>50.000</td><td>150.00</td><td>0.000</td></tr><tr><td>6.000</td><td>200.00</td><td>0.000</td></tr><tr><td>16.000</td><td>280.00</td><td>5.000</td></tr></tbody></table>	Ramp Rate	Final Temp.	Final Time	°C/min	°C	min		70.00	1.000	50.000	150.00	0.000	6.000	200.00	0.000	16.000	280.00	5.000
Ramp Rate	Final Temp.	Final Time																																					
°C/min	°C	min																																					
	70.00	2.000																																					
25.000	150.00	0.000																																					
3.000	200.00	0.000																																					
8.000	280.00	10.000																																					
Ramp Rate	Final Temp.	Final Time																																					
°C/min	°C	min																																					
	70.00	1.000																																					
50.000	150.00	0.000																																					
6.000	200.00	0.000																																					
16.000	280.00	5.000																																					
Sample Information	Liquid		☐ Unlock																																				
Injected Volume,	µL	1.0	☒ 1.0																																				
Split Ratio		0.00	☐ 16																																				
Effective on-Column Volume,	µL	1.0	0.058																																				
Nominal Column Capacity,	µL	0.017	0.00099																																				

Figure 1. Screen capture showing the method translation (MTL) software data entry used in a twofold speed gain translation.

General chromatographic conditions are listed in table 1. The standard used was a mixture of 26 pesticides at 10 ppm. A 10 m x 0.1 mm x 0.1 µm HP-5 column (part number 19091J-141) was used. The head pressure determined by the method translation software (30.72 psi) was used as the starting point for retention time locking. The column head pressure required to lock retention times of the compounds to the library (the original retention time divided by 2) was determined using the automated RTL process integrated within the Agilent ChemStation for MSD. This process (first translate the method then lock the retention times) was repeated for the threefold and fourfold time reductions.

Table 1. Chromatographic Conditions

Speed	Onefold (1X)	Twofold (2X)	Threefold (3X)	Fourfold (4X)
GC	110 V	220/240 V		
Column	30 m x 0.25 mm x 0.25 µm HP5-MS (P/N 19091S-433)	10 m x 0.1 mm x 0.1 µm HP-5 (P/N 19091J-141)		
Injection mode	Splitless	16:1 split		
Column head pressure	18.0 psi	36.55 psi	63.17 psi	90.0 psi
Column flow (mL/min)	1.5	0.4	0.8	1.5
Inlet control mode	Constant pressure	Constant pressure		
Carrier gas	Helium	Helium		
Injector temperature	250 °C	250 °C		
Oven temperature	70 (2 min)	70 (1 min)	70 (0.67 min)	70 (0.5 min)
Ramp 1	25 °C/min	50	75	100
	150 (0 min)	150 (0 min)	150 (0 min)	150 (0 min)
Ramp 2	3 °C/min	6	9	12
	200 (0 min)	200 (0 min)	200 (0 min)	200 (0 min)
Ramp 3	8 °C/min	16	24	32
	280 (10 min)	280 (5 min)	280 (3.33 min)	280 (2.5 min)
Oven equilibration	2 min	2 min		
Injection volume	1 µL	1 µL		
Liner	5183-4647	5183-4647		
MS Conditions				
Solvent delay	3 min	1.8 min	1.2 min	0.9 min
Tune file	Atune.u	Atune.u		
Low mass	35 amu	35 amu		
High mass	500 amu	450 amu		
Threshold	150	250		
Sampling	2	2	1	1
Scans/sec	3.15	3.50	6.54	6.54
Quad temperature	150 °C	150 °C		
Source temperature	230 °C	230 °C		
Transfer line temperature	280 °C	280 °C		
Acquisition mode	Scan (EI)	Scan (EI)		

Figure 2 shows the results of the shortened analysis times. The three chromatograms look extremely similar, except that the time axis is scaled proportionally. Because MTL followed by RTL scales methods very precisely, scaled screening libraries for corresponding time reductions can be obtained by dividing the retention times in the library by the speed gain (which does not have to be an integer). The peak heights from all the methods are very similar. Although the sample was split 16:1 for the smaller column, the small column i.d. and faster oven ramp combination made the peaks narrower and higher, so there was minimal loss in the signal to noise ratio.

Conclusion

The highly accurate and reproducible pressure and temperature control of the Agilent 6890 GC allows precise scaling of the standard 42-min GC/MSD pesticide method. Run time was shortened to 10.5 minutes using a fast oven ramp rate and a 10-meter 100-micron column. The combination of MTL and RTL facilitated scaling and yielded exact scaling. RTL libraries can accurately be scaled to correspond to the faster analyses.

References

1. B. D. Quimby, L.M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking," Application Note 228-401, Agilent publication number 5967-5820E, May 1998.
2. H. Prest, P. L. Wylie, K. Weiner, and D. Agnew, "Efficient Screening for Pesticides and Endocrine Disruptors Using the HP 6890/ 5973 GC/MSD System," Agilent publication number 5968-4884E, April 1999.
3. H. Prest, "GC Column Selection and Pumping Considerations for Electron and Chemical Ionization MSD operation," Agilent publication Number 5968-7958E, November 1999.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright © 2000
Agilent Technologies

Printed in USA 2/00
5968-9220E




Figure 2. Three TICs of the 2X, 3X, and 4X speedups. The standard analysis (1X) was 42 minutes long. The two vertical lines on the figure are used as references to show the similarity of the TICs.



Agilent Technologies
Innovating the HP Way



LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Eric Grosjean and Daniel Grosjean,
DGA, Inc., Ventura, CA

Peter G. Green, Environmental Analysis Center,
Environmental Engineering Science, California
Institute of Technology, Pasadena, CA

John M. Hughes, Agilent Technologies,
Pleasanton, CA

Abstract

A simple and sensitive LC/MS method has been developed for the analysis of carbonyl compounds derivatized with (2,4-dinitrophenyl)hydrazine (DNPH) using the Agilent 1100 LC/MSD system. Detection is carried out simultaneously with the diode-array detector and the LC/MSD using negative ion atmospheric pressure chemical ionization (APCI).¹ The method was applied to 78 carbonyls including 1-alkanals (from formaldehyde to octadecanal), saturated and unsaturated aliphatic aldehydes and ketones, aromatic carbonyls (including hydroxy- and/or methoxy-substituted compounds), aliphatic dicarbonyls, and aliphatic carbonyl esters.

Introduction

The ability to identify carbonyls and to measure their concentrations at levels of parts per billion (ppb) or lower in complex mixtures is important in many areas, including biomedical research and environmental chemistry—especially air pollution. A well-established method utilizing UV detection of the DNPHs of both simple and multifunctional carbonyl compounds^{2,3} has been extended to include simultaneous MS detection using APCI in negative ion mode. Concentration of the compounds

of interest from ambient air samples and subsequent derivatization is simplified by the use of C18 SPE cartridges impregnated with the derivatizing reagent. The combined methodology has been applied to several studies involving air pollution phenomena.¹

Experimental

The system included an Agilent 1100 Series binary pump, vacuum degasser, autosampler, thermostatted column compartment, diode-array detector, and an LC/MSD. The LC/MSD was used with the APCI source. Complete system control and data evaluation were carried out using the Agilent ChemStation for LC/MS.

Sample Collection and Preparation

Carbonyl-DNPH standards were synthesized in our laboratory as described previously.^{2,3} Carbonyls were purchased from commercial suppliers (Aldrich Chemical Co., Lancaster Synthesis, Wiley Organics, Fluka Chemical Corp.) or were prepared as described in previous work.^{2,3}

Air samples were collected by drawing air at 1 liter/minute through C18 Sep-Pak cartridges (Waters Corporation) impregnated with (2,4-dinitrophenyl)hydrazine/phosphoric acid.⁴ Collected carbonyl compounds were derivatized to (2,4-dinitrophenyl)hydrazones on the cartridge, and were then eluted with 2 mL of acetonitrile. The eluate was analyzed directly by LC/MS. The sample can be concentrated for the analysis of the higher molecular weight carbonyls, which are present at lower levels in ambient air.

Results and Discussion

DNPH derivatives are used to analyze carbonyl compounds by liquid chromatography to maximize detection of small, polar molecules, many of which cannot be analyzed using gas chromatography. The original LC/UV method for the analysis of DNPH derivatives of carbonyls was first improved by the use of a diode-array detector and HP particle beam LC/MS interface to provide positive identification of about 40 carbonyls at ppb levels in laboratory studies of air pollution chemistry⁵ and in urban air.⁶ The mass spectrometer provided extra dimensions of information to the already-rich data of the diode-array LC method, allowing the quantitation of coeluting analytes and the identification of unknowns for which standards were not initially available. However, the particle beam interface could not provide the detection limits necessary for measurement of carbonyls in ambient air, due to the significant percentage of water in the LC gradient required for the separation of the more complex mixtures.

To overcome this limitation, API-LC/MS was evaluated for this application. Both electrospray (ESI) and APCI in positive ion and negative ion modes were evaluated. APCI negative ion detection was found to provide the most sensitive and specific information about these compounds, giving 1–2 orders of magnitude better sensitivity than either ESI positive or negative ion or APCI positive ion detection.

Parameters for the acquisition of mass spectral data were automatically optimized by carrying out multiple injections of a standard mixture of 13 carbonyl-DNPH derivatives, using the system's Flow Injection Analysis Series capability. A fragmentor setting was chosen to obtain maximum $[M-H]^-$ for all 13 compounds present in the test mixture. Further optimization of the fragmentor voltage for specific compounds could be carried out to obtain distinct fragments, as the fragmentor voltage is time-programmable during acquisition. Those compounds which required a high percentage of acetonitrile for elution (eluting after 33 minutes) were found to have much better response with a corona current of 10 μ A versus 4 μ A for the smaller, early-eluting analytes. The scan range can be lowered

to 50 amu if significant fragment ions below 125 amu are generated by in-source collision-induced dissociation (CID); the chemical noise, especially in the TIC, is lower when starting the scan at 125 amu.

Mobile phases containing acetonitrile often do not give optimal response in APCI compared to methanol/water eluents, and acetonitrile seems to form carbon on the corona needle more quickly than methanol. However, for this analysis, adequate separation of carbonyls in a reasonable analysis time could not be achieved using methanol/water instead of acetonitrile/water, even trying a variety of columns. Nonetheless, maintenance of the APCI spray chamber after extended use with high flow rates of acetonitrile/water only required cleaning of the corona needle and spray shield with mild abrasive cloth and solvent.

Early work with this method was carried out using a similar column but with dimensions of 4.6 mm i.d. $\times$ 150 cm at a flow rate of 1.4 mL/min, with results comparable to those obtained on the 3mm i.d. column. An additional gradient has also been developed utilizing THF as a mobile phase modifier. This gradient method is capable of better separation of C3 and C4 carbonyl compounds which co-elute using the acetonitrile/water gradient.

Tables 1–6 (shown on pages 9–14) list the first 78 carbonyl compounds that have been analyzed with this method, along with chromatographic and spectral details. The method has been used for more than 140 carbonyl compounds, including several with molecular weights of approximately 650 Da.

Figure 1 shows the 360 nm and MS total ion chromatograms of a mixture of the DNPH derivatives of 13 carbonyls. The amount injected per component is 60 ng (as carbonyl). The UV chromatogram is labeled with the identity of the peaks and the MS chromatogram with the mass of the base peak in the spectrum ($[M-H]^-$ anion).

Figure 2 shows extracted ion chromatograms from the data in Figure 1, illustrating how the specificity of the MS detector can help with coelution, sometimes even allowing quantitation of coeluting peaks.

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones




Figure 1. Liquid chromatography analysis of a mixture of the DNPH derivatives of 13 carbonyls by ultraviolet absorption at 360 nm (diode array detector, top) and by atmospheric pressure negative chemical ionization mass spectrometry (total ion current, bottom): C1, formaldehyde; C2, acetaldehyde; C3K, acetone; ACR, acrolein; C3, propanal; CR, crotonaldehyde; MEK, 2-butanone; MTH, methacrolein; C4, butanal; BZ, benzaldehyde; C5, pentanal; TOL, *m*-tolualdehyde; C6, hexanal.

Chromatographic Conditions

Column: Nucleosil 100-5 C18 HD 5 μ m,
3 $\times$ 250 mm
Guard column: Phenomenex Security Guard C18,
3 mm i.d. $\times$ 4 mm
Mobile phase: A = water
B = acetonitrile
Gradient: Start with 49% B
at 26 min 49% B
at 40 min 100% B
Post-time: 5 minutes
Flow rate: 1.0 ml/min
Column temp: 38°C
Injection vol: 20 μ l
Diode-array
detector: Signal: 360, 40; 385, 40; 430, 40 nm
Reference: 540, 40 nm

MS Conditions

Source: APCI
Ionization mode: Negative
Vcap: 1500 V
Corona current: 10 μ A
Nebulizer: 60 psig
Drying gas flow: 4 l/min
Drying gas temp: 350°C
Vaporizer temp: 500°C
Scan: 125–600 amu,
Threshold: 150 counts
Gain: 5
Step size: 0.1 amu
Peak width: 0.1 min
Time filter: On
Fragmentor: 50 V

LC/DAD/MS Analysis of Carbonyl
(2,4-Dinitrophenyl)hydrazones




Figure 2. Extracted ion chromatograms for the region of Figure 1 containing acrolein (m/z 235), acetone and propanal (m/z 237), crotonaldehyde and methacrolein (m/z 249), and MEK (2-butanone) and butanal (m/z 251).

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Figure 3 shows mass spectra of two carbonyl DNPHs from the data in Figure 1: formaldehyde DNPH and hexanal DNPH. Using conditions optimized for best detection of the $[M-H]^-$ ion, these spectra show little fragmentation even with the high vaporizer temperature (500°C) found to be optimal for the method.

Figure 4a shows the MS total ion chromatogram of a sample taken from a study of the reaction of the unsaturated ketone 4-hexen-3-one with ozone in a laboratory smog chamber. The LC/MS analysis allows the identification of unreacted 4-hexen-3-one,

and of the carbonyl reaction products acetaldehyde, 2-oxobutanal, formaldehyde, glyoxal, and cyclohexanone (the latter a product of oxidation of cyclohexane, added to scavenge any OH radical which may form as a side product of the ozone-unsaturated ketone reaction). Figure 4b shows the mass spectra of the DNPH derivatives of cyclohexanone and of the dicarbonyl compound 2-oxobutanal. The spectra contain the ion m/z 182, which is characteristic of many carbonyl DNPHs and can be used to help locate and identify carbonyl DNPHs in complex mixtures.




Figure 3. Atmospheric pressure negative chemical ionization mass spectra of analytes in Figure 1: (top) formaldehyde DNPH, (bottom) hexanal DNPH.




Figure 4a. Atmospheric pressure negative chemical ionization mass spectrometry analysis of the carbonyl products of the reaction of ppb levels of ozone with 4-hexen-3-one in the presence of cyclohexane: (a) total ion current chromatogram with DNPH derivatives of unreacted 4-hexen-3-one (three peaks due to syn/anti isomers of DNPH) and of the reaction products formaldehyde (C1), acetaldehyde (C2), cyclohexanone, glyoxal, and 2-oxobutanal.




Figure 4b. Atmospheric pressure negative chemical ionization mass spectra of DNPHs of cyclohexanone and 2-oxobutanal.

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Figure 5a shows the UV and MS chromatograms from the LC/MS analysis of an ambient air sample collected during early morning peak traffic in Porto Alegre, Brazil, where the mixture of vehicle fuels is unique in the world.⁷ The MS data is shown using the base peak chromatogram (BPC), a very useful tool for helping to filter noise from the MS data. The BPC reconstructs an MS chromatogram using only the most intense ion (the base peak) from each spectrum, rather than adding up the abundances of all ions in each spectrum as does the total ion chromatogram (TIC).

Figure 5b shows an expanded view of the region of the UV and MS chromatograms, in which the C6 to C18 straight-chain alkanals elute. In Figure 5c, the extracted ion chromatograms for specific compounds show the distinctive masses of the $[M-H]^-$ ions, which confirm and/or identify the peaks detected with the UV detector.




Figure 5a. LC/MS analysis of an ambient air sample collected in Porto Alegre, Brazil, during early morning peak traffic: (top) UV 360 nm chromatogram; (bottom) APCI negative ion base peak chromatogram (BPC).

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones




Figure 5b. Expanded region from C6 to C18 alkanals of the analysis in Figure 5b: (top) UV 360 nm chromatogram; (bottom) APCI negative ion base peak chromatogram (BPC).




Figure 5c. Extracted ion chromatograms of the $[M-H]^-$ ion for 1-alkanal DNPH derivatives in Brazil air sample. Each EIC is labeled with the carbon number of the 1-alkanal DNPH derivative and the observed mass of the M-H ion.

Summary and Conclusions

This note describes the straightforward addition of API mass spectrometry to a well-established LC method for carbonyl analysis. The resulting APCI-LC/MS method is robust and sensitive, with application not only to simple aldehydes and ketones, but also to hydroxy carbonyls, dicarbonyls, carbonyl esters and keto acids as well. This development has improved a long-standing technique in environmental research, and is applicable to many other fields in which carbonyl-containing compounds are important but difficult to analyze with adequate selectivity, sensitivity, and/or confidence in identification.

Acknowledgments

The authors would like to thank **Christine Miller** of Agilent Technologies for review and helpful comments.

References

1. Grosjean, E., Grosjean, D., Green, Peter G., Anal. Chem. 1999, 71, 1851–1861.
2. Druzik, C. M., Grosjean, D., Van Neste, A., Parmar, S. S., Int. J. Environ. Anal. Chem. 1990, 38, 495–512.
3. Grosjean, E., Grosjean, D., Int. J. Environ. Anal. Chem. 1995, 61, 47–64.
4. Grosjean, E., Grosjean, D., Int. J. Environ. Anal. Chem. 1995, 61, 343–360.
5. Grosjean, E., Grosjean, D. J., Atmos. Chem. 1997, 27, 271–289.
6. Grosjean, E., Grosjean, D., Fraser, M. P., Cass, G. R., Environ. Sci. Technol. 1996, 30, 2687–2703.
7. Grosjean, E., Grosjean, D., Gunawardena, R., Rasmussen, R. A., Environ. Sci. Technol. 1998, 32, 736–742.

Authors

Eric Grosjean is a research chemist at DGA, Inc., and **Daniel Grosjean** is president of DGA, Inc., Ventura, CA.

Peter Green is a senior scientist at the Environmental Analysis Center, Environmental Engineering Science, California Institute of Technology, Pasadena, CA.

John Hughes is a senior applications consultant at Agilent Technologies, Pleasanton, CA.

Table 1. Summary of Data for the DNPH Derivatives of 1-Alkanals.

Carbonyl	Carbonyl-DNPH			
	RRT ^a	UVmax ^b	MW ^c	BP ^{de}
formaldehyde	1.00	355	210	209
acetaldehyde	1.40	364	224	223
propanal	2.30	365	238	237
butanal	3.65	366	252	251
pentanal	5.98	367	266	265
hexanal	7.92	366	280	279
heptanal	8.54	366	294	293
octanal	8.96	365	308	307
nonanal	9.28	363	322	321
decanal	9.52	362	336	335
undecanal	9.74	362	350	349
dodecanal	9.92	361	364	363
tridecanal	10.09	361	378	377
tetradecanal	10.24	361	392	391
pentadecanal	10.43	361	406	405
hexadecanal	10.62	361	420	419
heptadecanal	10.85	360	434	433
octadecanal	11.12	360	448	447

^a RRT = retention time of carbonyl-DNPH relative to that of formaldehyde-DNPH (4.08 ± 0.02 min).

^b UV max = wavelength of maximum absorption, nm, from 200–600 nm absorption spectrum recorded with diode array detector.

^c MW = molecular weight of carbonyl-DNPH.

^d BP = base peak (most abundant ion), *m/z*, in atmospheric pressure negative chemical ionization mass spectrum.

^e No ions other than BP and ¹³C contribution to BP (see text) were present in the spectra of the DNPH derivatives of 1-alkanals.

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Table 2. Summary of Data for the DNPH Derivatives of Other Saturated Aliphatic Carbonyls.^a

Carbonyl	Carbonyl-DNPH				
	RRT	UV max	MW	BP	Other Ions ^b
ALDEHYDES					
2-methylpropanal	3.69	363	252	251	none
3-methylbutanal	5.51	363	266	265	none
2-methylbutanal	5.70	363	266	265	263 (1)
2,2-dimethylpropanal	5.66	364	266	265	none
cyclohexylmethanal	8.09	366	292	291	none
KETONES					
acetone	2.01	368	238	237	none
acetone- <i>d</i> ₆	1.98	367	244	243	237–242 ^c
2-butanone	3.44	369	252	251	none
2-pentanone	5.51	371	266	265	none
3-pentanone	5.51	370	266	265	263 (2)
3-methyl-2-butanone	5.52	370	266	265	263 (2)
3,3-dimethyl-2-butanone	7.78	370	280	279	263 (1)
2,4-dimethyl-3-pentanone	8.27	370	294	293	277 (8)
cyclohexanone	5.36	373	278	277	275 (23)
2-methylcyclohexanone	7.94	371	292	291	289 (25)
nopinone ^d	8.30	372	318	317	315 (5)

^a RRT, UV max, MW, and BP are defined in footnotes *a–d* of Table 1.

^b *m/z*; Not including ¹³C contribution to BP; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

^c Abundances relative to that of BP = 3% (*m/z* = 237), 4% (238), 6% (239), 13% (240), 24% (241), and 44% (242).

^d 6,6-Dimethylbicyclo [3.1.1] heptan-2-one.

LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones

Table 3. Summary of Data for the DNPH Derivatives of Unsaturated Aliphatic Carbonyls.^a

Carbonyl	Carbonyl-DNPH				
	RRT	UV max	MW	BP	Other Ions ^b
ALDEHYDES					
acrolein	2.01	380	236	235	none
crotonaldehyde ^c	3.08	382	250	249	none
methacrolein	3.44	381	250	249	none
2-ethylacrolein	5.55	379	264	263	none
<i>trans</i> -2-hexenal	7.60	382	278	277	275 (7)
2-methyl-2-pentenal	7.67	384	278	277	275 (3)
<i>cis</i> -4-heptenal	7.78 ^d	365	292	291	289 (7)
	7.95 ^e (2%)	366	292	291	289 (7)
<i>trans</i> -2-decenal	9.41	381	334	333	331 (6)
<i>trans</i> -2-undecenal	9.64	380	348	347	345 (5)
KETONES					
methyl vinyl ketone	2.68 ^e (13%)	368	250	249	none
	2.87 ^e (3%)	372	250	249	none
	3.06 ^d	379	250	249	none
1-penten-3-one	4.76 ^d	378	264	263	247 (8)
	4.99 ^e (12%)	376	264	263	247 (9)
3-penten-2-one	4.43 ^e (3%)	382	264	263	none
	4.83 ^d	384	264	263	none
4-methyl-3-penten-2-one	6.94	386	278	277	263 (3)
4-hexen-3-one ^c	7.12 ^e (4%)	385	278	277	none
	7.38 ^e (35%)	357	278	277	none
	7.72 ^d	357	278	277	none
6-methyl-5-hepten-2-one ^f	8.27	368	306	305	289 (4)
4-acetyl-1-methylcyclohexene	8.64	369	318	317	301 (4)

^a RRT, UV max, MW, and BP are defined in footnotes a–d of Table 1.

^b *m/z*; not including ¹³C contribution to base peak; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

^c Predominantly the *trans* isomer.

^d Largest peak.

^e Smaller peak; percent of largest peak (peak height basis at 360 nm) given in parentheses.

^f Two coeluting peaks.

Table 4. Summary of Data for the DNPH Derivatives of Aromatic Carbonyls.^a

Carbonyl	Carbonyl-DNPH				
	RRT	UV max	MW	BP	Other Ions ^b
benzaldehyde	4.75	384	286	285	none
<i>o</i> -tolualdehyde	7.13	386	300	299	none
<i>m</i> -tolualdehyde	7.29	385	300	299	none
<i>p</i> -tolualdehyde	7.35	388	300	299	none
acetophenone	6.77	382	300	299	none
2,5-dimethylbenzaldehyde	8.15	389	314	313	none
2-hydroxybenzaldehyde (salicylaldehyde)	2.97	391	302	301	none
4-methoxybenzaldehyde (<i>p</i> -anisaldehyde)	4.98	398	316	315	none
3,4-dimethoxybenzaldehyde	3.07	398	346	345	none
4-hydroxy-3-methoxybenzaldehyde (vanillin)	1.75	402	332	331	329 (2), 315 (1)
4-hydroxy-3-methoxyacetophenone (acetovanillone)	2.37	393	346	345	343 (5), 329 (45), 313 (4), 298 (2)
3,5-dimethoxy-4-hydroxybenzaldehyde (syringaldehyde)	1.54	436	362	361	360 (40), 359 (1), 345 (1)
4-hydroxy-3-methoxycinnamaldehyde (coniferyl aldehyde)	2.67	415	358	357	356 (12), 355 (22), 325 (5), 310 (10)

^a RRT, UV max, MW, and BP are defined in footnotes *a–d* of Table 1.

^b *m/z*; not including ¹³C contribution to BP; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

Table 5. Summary of Data for the DNPH Derivatives of Dicarbonyls.^a

Carbonyl	Carbonyl-DNPH					
	RRT	UV max	MW (mono)	MW (di)	BP	Other Ions ^b
glyoxal	6.09	415	238	418	417	237 (14), 238 (16)
methylglyoxal	7.90	432	252	432	431	251 (14), 249 (17)
2-oxobutanal ^c	8.31	410	266	446	445	263 (12)
2,3-butanedione	1.50 ^e (1%)	362	266		265	none
	1.79 ^e (2%)	369	266		265	none
	8.31 ^d	403		446	445	265 (7), 263 (48)
succinic dialdehyde	0.81 ^e (5%)	360	266		265	
	1.55 ^{d,f}	338 ^f			247 ^f	
	6.42 ^e (12%)	368		446	445	263 (80)
glutaraldehyde	7.34	368	280	460	459	279 (10)
2,3-pentanedione	8.72	402	280	460	459	443 (8), 279 (15)
2,4-pentanedione	1.03	310	280	460	262	302 (14), 232 (6), 360 (7), 279 (0.1), 288 (5)
3,4-hexanedione	8.89	400	294	474	473	293 (5), 291 (12)
pinonaldehyde ^g	3.73 ^e (9%)	368	348		347	none
	9.07 ^d	368		528	527	345 (16)

^a RRT, UV max, and BP are defined in footnotes *a–d* of Table 1. MW (mono) and MW (di) are the molecular weights of the mono-DNPH derivative and di-DNPH derivative, respectively.

^b *m/z*; not including ¹³C contribution to BP; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

^c Prepared by reaction of ozone with 1-penten-3-one, 2-ethylacrolein, and 4-hexen-3-one.

^d Largest peak.

^e Smaller peak; percent of largest peak (peak height basis at 360 nm) is given in parentheses.

^f This compound is not the mono-DNPH derivative; see text.

^g (2,2-Dimethyl-3-acetylcyclobutyl) ethanal, prepared by reaction of ozone with pinene.

**LC/DAD/MS Analysis of Carbonyl
(2,4-Dinitrophenyl)hydrazones****Table 6. Summary of Data for the DNPH Derivatives of Other Carbonyls.^a**

Carbonyl	Carbonyl-DNPH				
	RRT	UV max	MW	BP	Other Ions ^b
methyl glyoxylate ^c	0.89 ^f (60%)	355	268	267	none
	1.72 ^e	357	268	267	none
ethyl glyoxylate	1.24 ^f (65%)	356	282	281	none
	2.71 ^e	359	282	281	none
2-oxoethyl acetate ^d	1.14 ^e	360	282	281	249 (18)
	1.22 ^f (13%)	356	282	281	249 (16)
methoxyacetone	1.59 ^e	363	268	267	none
	2.25 ^f (30%)	370	268	267	none
2-furaldehyde	2.14 ^e	392	276	275	none
	3.00 ^f (25%)	383	276	275	none

^a RRT, UV max, MW, and BP are defined in footnotes *a–d* of Table 1.

^b *m/z*; not including ¹³C contribution to base peak; see text. The percent abundance of the ion relative to that of BP is given in parentheses.

^c Prepared by reaction of ozone with methyl acrylate and with methyl *trans*-3-methoxyacrylate (MTMA).

^d Prepared by reaction of ozone with MTMA and with *trans*-2-hexenyl acetate.

^e Largest peak.

^f Smaller peak; percent of largest peak (peak height basis at 360 nm) is given in parentheses.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

Copyright © 2000

Agilent Technologies

All rights reserved.

Reproduction and adaptation is prohibited.

Printed in the U.S.A. January 2000

(23) 5968-8850E



Analysis of Bendiocarb and Metabolite by HPLC

Rainer Schuster

Environmental

Abstract

The bendiocarb insecticide can be extracted from soil either with Soxhlet equipment or by ultrasonic treatment in solution and from water by either a liquid–solid or a liquid–liquid technique.

Separation

Figure 1 shows the separation on a 2.1 mm internal diameter Hypersil ODS column. A constant oven temperature of 40 °C is important here.

- UV-visible detection
- Diode-array detection—for simultaneous multiple wave-lengths and peak identity confirmation by spectra.




Figure 1
Separation of a 20 µl injection containing aldicarb, bendiocarb and metabolite monitored at 212 nm

Conditions

Column

100 x 2.1-mm Hypersil ODS C18, 5 µm

Mobile phase

Water–acetonitrile
(65:35 isocratic mixture)

Flow rate

0.36 ml/min

Temperature

40 °C

Detection

212 nm (16 nm bandwidth)
reference 450 nm (100 nm bandwidth)

Diode array detector performance

Detection limit 4 µg/l
(without sample enrichment)



Agilent Technologies

Innovating the HP Way

Sample preparation


Narrow-bore technology for
lowest solvent consumption and highest sensitivity.

Equipment

Agilent 1100 Series

- binary pump
- autosampler
- thermostatted column compartment
- diode array detector

Agilent ChemStation +
software



Rainer Schuster is application
chemist at Agilent
Technologies, Waldbronn,
Germany.

For more information on our
products and services, visit
our worldwide website at
<http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 10/97
Publication Number 5966-1876E



Agilent Technologies

Innovating the HP Way



Analysis of Paraquat and Diquat by HPLC

Rainer Schuster

Environmental

Abstract

The paraquat and diquat herbicides can be extracted from soil either with Soxhlet equipment or by ultrasonic treatment in solution and from water by either a liquid–solid or a liquid–liquid technique.

Separation

Figure 1 shows the separation on a 2.1-mm internal diameter Hypersil ODS column.

- UV-visible detection
- Diode-array detection—for simultaneous multiple wavelengths and peak identity confirmation by spectra.




Figure 1
Separation of 10 µl injection of a paraquat and diquat standard

Conditions

Column

100 x 2.1 mm Hypersil ODS C18, 5 µm

Mobile phase

Hexane sulfonic acid
0.35 % triethylamine
pH 2.5 (H₃PO₄)

Flow rate

0.4 ml/min

Detection

256 nm (10 nm bandwidth),
310 nm (10 nm bandwidth)
reference 450 nm (100 nm bandwidth)

Diode array detector performance

Detection limit 4 µg/l
1 ng (absolute) with enrichment factor
of 100



Agilent Technologies

Innovating the HP Way

Sample preparation


Narrow-bore technology for lowest solvent consumption and highest sensitivity.

Equipment

Agilent 1100 Series

- binary pump
- autosampler
- thermostatted column compartment
- diode array detector

Agilent ChemStation + software



Rainer Schuster is application chemist at Agilent Technologies, Waldbronn, Germany.

For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 10/97
Publication Number 5966-1875E



Agilent Technologies

Innovating the HP Way




Soil & Sediment

Inorganics Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)

Direct Analysis of Undiluted Soil Digests Using the Agilent High Matrix Introduction Accessory with the 7500cx ICP-MS



Application

Environmental

Authors

Steve Wilbur
Agilent Technologies
Bellevue WA
USA

Wim Proper
Eurofins Analytico
Barneveld
Netherlands

Noriyuki Yamada and Naoki Sugiyama
Agilent Technologies
Hachioji
Japan

Abstract

Agilent has developed the High Matrix Introduction (HMI) accessory for ICP-MS as an alternative to conventional dilution. The HMI modifies the sample introduction system of the Agilent 7500 Octopole Reaction System (ORS) ICP-MS, making it possible to directly measure sample solutions with total dissolved solids (TDS) exceeding 1%. In collaboration with the Eurofins Analytico laboratory in the Netherlands, a 7500cx/HMI was used to directly measure high TDS soil extracts in compliance with Dutch regulatory guidelines. The results show that the HMI is a suitable replacement for conventional autodilution, allowing Analytico to use a single 7500cx/HMI ICP-MS in place of several instruments, including conventional ICP-MS, ICP-OES and a dedicated mercury analyzer.

Introduction

The determination of trace elements in high-matrix samples has always been a difficult analytical challenge. While inductively coupled plasma mass spectrometry (ICP-MS) has unsurpassed detection capability for trace metals, the potential for salt accumulation on the MS interface has always required that dissolved solids levels be limited. Furthermore, extremely corrosive or acidic samples can damage conventional ICP-MS interface components, including the sampler and skimmer cones, requiring the use of platinum or other expensive components. Compared to ICP-Optical Emission Spectroscopy (ICP-OES) or other non-MS-based techniques, this has been considered an inherent limitation of ICP-MS. To compensate for this limitation, samples with total dissolved solids (TDS) levels higher than 0.1 to 0.2%, depending on the matrix, typically require dilution before measurement by ICP-MS, relying on ICP-MS's high sensitivity to compensate for the sensitivity loss due to dilution. However, conventional sample dilution has a number of other disadvantages, including reduced productivity, introduction of contaminants, dilution factor errors, and increased waste volume. As a superior alternative to conventional dilution, Agilent has developed a simple, novel modification to the sample introduction system of the Agilent 7500 ICP-MS with Octopole Reaction System (ORS) that can significantly improve the



Agilent Technologies

tolerance to high-matrix samples. The Agilent High Matrix Introduction (HMI)¹ accessory reduces sample matrix load on the plasma, making it possible to directly measure sample solutions with TDS exceeding 1%. As a result, samples previously measurable only by ICP-OES can now be measured directly by ICP-MS, using a 7500 ORS fitted with HMI. In this work, an Agilent 7500cx/HMI was used to test the system's ability to directly measure high TDS soil extracts in aqua regia and meet Dutch regulatory guidelines for reporting limits and data quality.

Direct Analysis of Aqua Regia Digests of Soils Using HMI-ICP-MS

This work was done in collaboration with the Eurofins Analytico laboratory (Analytico Milieu) in the Netherlands. Analytico has been part of the Eurofins group since 2001. Eurofins is a bio-analytical company with approximately 50 laboratories distributed over France, Germany, the UK, Denmark, Norway, Switzerland, and the United States. One of three divisions within Analytico, Analytico Milieu's expertise extends to the analysis of soil, sludge, groundwater, wastewater, air, building materials and residual matter, and, additionally, method development, validation, logistics, project management, and data management.

In this collaboration, an Agilent 7500cx equipped with the HMI was used to generate performance data to be used for compliance with the Dutch regulation pertaining to contaminated soils (AS3000). Due to the high TDS levels and high acid concentrations of digested soils, dilution is necessary prior to analysis by ICP-MS. Analytico currently uses the Agilent Integrated Sample Introduction System (ISIS) to perform online dilutions to meet these requirements. However, the limitations of conventional dilutions prompted Analytico to evaluate the potential of HMI as a faster, simpler, less expensive replacement for conventional autodilution that would also eliminate the maintenance issues associated with a conventional autodilutor.

Instrumentation

An Agilent 7500cx ICP-MS with the second peripump option for high sample throughput was equipped with the HMI. A Burgener MiraMist nebulizer was used. Instrument tune parameters,

including HMI settings, are listed in Table 1. The plasma was optimized in ultra robust mode with 1/12 aerosol dilution. This is the maximum dilution factor that can be set with HMI and is approximately equivalent to diluting the sample x12 conventionally. All analytes except selenium were acquired in helium collision mode, thus eliminating the need for no-gas mode and the associated time required for mode switching. Selenium was acquired in hydrogen reaction mode due to the low detection limits required.

Table 1. Instrument Tune Conditions (Values relating to HMI are shaded.)

RF power (W)	1600
Carrier gas (L/min)	0.28
HMI dilution gas (L/min)	0.67
Aerosol dilution factor	1/12
Sample uptake rate (mL/min)	0.17
ISTD uptake rate (mL/min)	0.17
Total nebulizer flow (mL/min)	0.34
Extract 1 (V)	0
Extract 2 (V)	-160
He flow (He mode)	4.0 mL/min
KED (He mode)	2 volts
H ₂ flow (H ₂ mode)	4.0 mL/min
KED (H ₂ mode)	2 volts

Sample Preparation

Actual soil samples received from Analytico's customers were prepared by adding 1 gram of soil to 8 mL of aqua regia prior to microwave digestion. Digested samples were then diluted to 50 mL final volume in ultra pure (18.2 MΩ) water. The final acid concentration is 4% HNO₃ and 12% HCl.

Calculation of Method Detection Limits (MDLs)

Since the HMI is effectively applying a dilution, the effects on detection limits are of critical importance. While ICP-MS possesses high sensitivity, the requirement for ultra trace detection limits in high TDS samples can still be challenging. Analytico has required MDLs for most analytes (based on a 1-g soil sample diluted to a final volume of 50 mL; see Table 2), which must be met in order for them to meet their reporting limits and satisfy Dutch regulatory requirements.

¹ HMI theory and performance are discussed in detail in Agilent Product Overview: Performance Characteristics of the Agilent High Matrix Sample Introduction (HMI) Accessory for 7500 Series ICP-MS, 5989-7737EN.

Table 2. Analytico 3-Sigma Required Detection Limits for Soils

Analyte	Soil dry wt (mg/kg)	After 50x dilution (µg/L)
Cd	0.17	3.4
Cr	15	300
Cu	5	100
Ni	3	60
Pb	13	260
Zn	17	340
Hg	0.05	1
As	4	80
Ag	1	20
Se	10	200
Sb	1	20
Sn	6	120
Ba	15	300
Co	1	20
Mo	1.5	30
V	1	20
Be	0.1	2
Te	10	200
Tl	3	60

MDLs were calculated as 3-sigma of 10 replicates of a low-level (between one to three times the required MDL) spiked sand sample measured consecutively and also measured on 10 different days over a 30-day period² (Table 3). For all regulated elements, the calculated MDLs exceeded the Dutch regulatory requirements by nearly an order of magnitude or better. So with the HMI operating at maximum effective dilution, the system has ample sensitivity for the application.

Analysis of Certified Reference Materials

Two certified reference materials (BCR-144R Domestic Sewage Sludge, IRMM, Belgium, and

Table 3. Calculated Method Detection Limits (mg/kg) According to the Requirements of Dutch Regulation AS3000

MDL(1) = 3σ of 10 replicates taken on the same day

MDL(2) = 3σ of 10 replicates taken on different days¹

Analyte - isotope	ORS mode	MDL (1) (mg/kg)	MDL (2) (mg/kg)	Dutch required MDL (mg/kg)
Be 9	He	0.042	0.046	0.1
V 51	He	0.255	0.481	1
Cr 52	He	2.300	4.517	15
Co 59	He	0.147	0.348	1
Ni 60	He	0.770	0.922	3
Cu 63	He	0.502	1.303	5
Zn 66	He	1.704	3.104	17
As 75	He	0.549	1.079	4
Se 78	H ₂	0.832	2.041	10
Se 78	He	1.064	1.991	10
Mo 95	He	0.195	0.413	1.5
Ag 107	He	0.278	0.701	1
Cd 114	He	0.058	0.066	0.17
Sn 118	He	0.589	1.353	6
Sb 121	He	0.333	0.401	1
Te 125	He	1.217	2.112	10
Ba 135	He	3.041	6.227	15
Hg 201	He	0.014	0.025	0.05
Tl 203	He	0.285	0.546	3
Pb 208	He	1.197	2.844	13

FeNeLab River Clay, FeNeLab, Netherlands) were analyzed in replicate as part of the validation procedure. The CRMs were prepared in the same manner as standard soil samples and measured on 10 different days during a 30-day time period. Table 4 shows the results of replicate (n = 10) analyses of both CRMs in mg/kg. Recoveries ranged from 87 to 108%, well within the regulatory requirement of 80 to 110%.

² MDLs calculated from 10 different days are for information only.

Table 4. Results of Replicate (n = 10) Analyses of Two Certified Reference Soil Samples (FeNeLab and BCR-144R)

Analyte	ORS Mode	FeNeLab River Clay			BCR-144R Sewage Sludge		
		Measured mg/kg (ave, n = 10)	Certified mg/kg	Rec. % (ave)	Measured mg/kg (ave, n = 10)	Certified mg/kg	Rec. % (ave)
Be 9	He	1.6			0.2		
V 51	He	59.6			13.9		
Cr 52	He	191.9	187	103	88.8	90	99
Co 59	He	19.8	18.7	106	13.6	13.3	102
Ni 60	He	55.7	52.9	105	40.7	44.9	91
Cu 63	He	153.9	156	99	270.0	300	90
Zn 66	He	1031.6	970	106	825.1	919	90
As 75	He	44.7	44	102	3.2		
Se 78	H ₂	2.0			1.7		
Se 78	He	2.4			1.5		
Mo 95	He	1.3			6.9		
Ag 107	He	2.9			8.2		
Cd 114	He	8.5	8.07	105	1.7	1.84	90
Sn 118	He	0.02			36.0	40.8	88
Sb 121	He	1.6			2.8	3.05	92
Te 125	He	0.3			0.1		
Ba 135	He	828.3	817	101	319.2	367	87
Hg 201	He	4.1	3.83	107	3.2	3.11	102
Tl 203	He	1.1			0.1	0.14	
Pb 208	He	297.0	274	108	94.9	96	99

Determination of Precision and Accuracy at High and Low Concentrations

In addition to analysis of replicate CRMs, both low-level and high-level spiked samples were analyzed in replicate (n = 10; 10 different days during 30-day time period) in order to determine both accuracy and precision over a wide range of concentrations (Table 5).

Table 5. Results of Replicate (n = 10) Measurements Taken on 10 Nonconsecutive Days During a 30-Day Period of Both Low-Level and High-Level Spikes of Soil Samples

Analyte	ORS mode	Low-level spike conc. mg/kg	Measured mg/kg (ave, n = 10)	RSD (%)	Rec. % (ave)	High-level spike conc. mg/kg	Measured mg/kg (ave, n = 10)	RSD (%)	Rec. % (ave)
Be 9	He	1	0.8	3.5	81	800	773.9	3.6	97
V 51	He	50	50.9	4.0	102	800	771.4	2.5	96
Cr 52	He	150	149.6	4.0	100	1100	1062.7	2.5	97
Co 59	He	10	10.4	4.1	104	800	766.3	2.0	96
Ni 60	He	25	25.3	5.3	101	1100	1074.1	3.1	98
Cu 63	He	40	40.0	6.2	100	1100	1058.5	2.5	96
Zn 66	He	150	151.6	4.2	101	1100	1094.3	4.7	99
As 75	He	40	39.0	5.0	97	400	395.5	2.8	99
Se 78	H ₂	100	102.7	3.7	103	1300	1336.0	2.2	103
Mo 95	He	13	12.2	5.0	93	1300	1235.3	3.3	95
Ag 107	He	8	8.3	4.6	103	40	40.8	4.2	102
Cd 114	He	1.2	1.1	7.1	94	1100	1062.8	2.9	97
Sn 118	He	40	41.7	4.0	104	1300	1262.6	3.2	97
Sb 121	He	10	9.7	5.9	97	1300	1188.0	2.4	91
Te 125	He	80	82.1	4.2	103	750	807.4	2.4	108
Ba 135	He	120	121.1	4.5	101	1100	1102.2	5.6	100
Hg 201	He	0.4	0.4	4.4	106	13	13.5	4.3	104
Tl 203	He	23	24.0	4.6	104	40	41.3	3.4	103
Pb 208	He	100	101.9	4.7	102	800	778.1	4.0	97

Sample Analysis

In order to test the long-term robustness of the HMI-equipped system, a 23-hour sequence consisting of an initial calibration and 235 soil samples was analyzed. Absolute drift was measured by monitoring the recovery of the five internal standards (⁶Li, Ge, Rh, In, Ir) in both gas modes (He and H₂) over the course of the sequence. Normalized recoveries (relative to the method

blank) are shown in Figure 1. Overall downward drift over 23 hours was approximately 20%, which is easily corrected by internal standards and not sufficient to have a detrimental effect on method accuracy or sensitivity. By comparison, a similar system without HMI, running these samples directly would suffer severe loss of sensitivity (> 80%) due to cone clogging before the sequence was completed.





Figure 1. Normalized internal standard recovery in digested soil samples for the duration of the 23-hour sequence. Numbers next to each ISTD in the caption denote the ORS gas mode (#2 = H₂, #3 = He).

$\pm 10\%$. Ten percent control limits are shown in red, indicating that all CCV recoveries were well within the prescribed limits for the entire sequence. This excellent calibration stability not only ensures the most accurate sample results, but also eliminates time wasted in unnecessary recalibrations should a CCV fail during the sequence.



Productivity

The operation of the HMI accessory does not adversely affect productivity in any way, since the HMI conditions are constant throughout operation and do not require any additional execution or stabilization time. Therefore, a given method run with HMI would take the same amount of time per sample as one run without HMI. HMI is also fully compatible with Agilent's time-saving pre-emptive and intelligent rinse functions, which minimize time wasted during both sample uptake and rinse-out. Furthermore, since HMI permits the direct analysis of undiluted samples of many types, the extra time associated with either manual or autodilution is saved, which considerably shortens the total time (prep plus analysis) required per sample. The improved stability as a result of HMI use can also minimize the need for recalibrations and sample reruns, further reducing the average run-to-run time. In this work, the average run time for a sample in a 23-hour, 235-sample sequence of undiluted soil digestates was 5.9 minutes, including acquisition in both H₂ and He modes.

Conclusions

Based on Analytico's evaluation, when compared with conventional autodilution for high TDS, high acid digests of soil and sludge samples, Agilent's

HMI interface provided a number of significant advantages.

- **Speed** – HMI does not require liquid dilution of sample and stabilization of diluted sample. It also permits the use of Agilent's pre-emptive rinse function, which allows rinsing of the sample tubing to begin before acquisition has finished.
- **Low maintenance** – There is no tubing to replace and no moving parts to maintain.
- **Simple** – There are no critical timing issues or plumbing common to continuous flow autodilutors.
- **Flexibility** – Since hardware changes or reconfigurations are not required after installation of HMI, the system can be switched between conventional mode and HMI mode on the fly.

These advantages have allowed Analytico to use a single 7500cx ICP-MS fitted with HMI to replace several instruments required for the analysis of these sample types, including conventional ICP-MS, ICP-OES, and a dedicated mercury analyzer.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
February 27, 2008
5989-7929EN



Agilent Technologies



High-Speed Environmental Analysis Using the Agilent 7500cx with Integrated Sample Introduction System – Discrete Sampling (ISIS–DS)

Application Note

Environmental

Authors

Steve Wilbur
Agilent Technologies, Inc.
3380 146th Place SE, Suite 300,
Bellevue Washington, 98007
USA

Takeo Kuwabara and Tetsushi Sakai
Agilent Technologies
Tokyo Analytical Division
9-1 Takakura-cho, Hachioji
Tokyo 192-0033
Japan

Abstract

Agilent has further improved the sample throughput capabilities of its 7500cx ICP-MS with Octopole Reaction System (ORS) using a newly configured Integrated Sample Introduction System–Discrete Sampling (ISIS-DS) accessory, and helium collision mode. Employing this new methodology, a complete suite of 30 or more elements can be analyzed in compliance with USEPA criteria (spectrum mode, three replicates, and sub-ppb MDLs) in approximately 75 seconds, sample to sample, with excellent removal of polyatomic interferences. Performance data showing stability, interference control, accuracy, precision, and washout are presented. The new system is applicable to labs requiring extremely high sample throughput and with its low sample consumption of ~2.2 mL/sample, for applications where sample volume is limited.



Agilent Technologies

Introduction

The Agilent Integrated Sample Introduction System (ISIS) has always permitted the highest sample throughput, using either high-speed uptake with constant flow nebulization or discrete sampling using a six-port valve and sample loop with time-resolved acquisition. In keeping with Agilent's continual focus on product enhancement, ISIS Discrete Sampling (ISIS-DS) has been reconfigured to further improve productivity. The resulting enhanced ISIS-DS sampling mode takes advantage of the ability of the 7500cx ICP-MS to analyze environmental samples using a single collision cell mode (He mode). This new mode of operation permits USEPA-compliant analysis (spectrum mode, three replicates, and sub-ppb MDLs) of a complete suite of 30 or more elements in approximately 75 seconds, sample to sample.

ISIS Configuration

Figure 1 shows the ISIS configuration used. It is a typical discrete sampling configuration with a couple of important modifications. Pump 1 (P1) is the large ISIS sample uptake peristaltic pump. Pump 2 (P2) is the standard 7500 nebulizer pump.

The ISIS uptake pump (P1), which is located downstream of the valve, draws the sample from the autosampler into the sample loop. As a result, the sample loaded in the sample loop is never exposed to peristaltic pump tubing, thereby eliminating a common source of contamination and carryover. This high-speed, high-capacity peristaltic pump is capable of rinsing and filling the sample loop in approximately 10 seconds when using the Cetac ASX-520 autosampler with the wide-bore 0.8 mm id probe. The other modification is the addition of the tee joint between the valve and nebulizer to allow the use of online internal standard addition. By minimizing both the length and diameter of the tubing between the valve and nebulizer, the time from rotation of the valve (sample injection) to the realization of a constant analyte signal is less than 15 seconds. A 300- μ L loop is sufficient to allow more than 30 seconds of continuous spectrum mode acquisition. Larger loop sizes can be used to achieve any duration of acquisition required. After acquisition has completed, the valve returns to the load position, flushing any remaining sample to waste and rinsing the nebulizer and spray chamber with clean rinse solution. At this point, approximately 15 seconds is required for the signal to return to baseline in preparation for the next analysis (Figure 2).




Figure 1. ISIS-DS sampling with online internal standard configuration. Valve in "load" position on left and in "inject" position on right.




Figure 2. Analyte and internal standard profile during discrete sampling analysis (log scale for signal intensity). Time 0 – autosampler probe enters the sample and loop is loaded. Inject at 10 seconds, 15 seconds acquisition delay, 30 seconds acquisition, 10 seconds rinse, 10 seconds overhead. Total time is approximately 75 seconds.

Experimental

A sequence of 216 samples was analyzed in 4 hours 29 minutes using the new ISIS-DS sampling configuration depicted in Figure 1 and the acquisition conditions listed in Table 1. The 7500cx was operated in a single cell mode (He collision mode) resulting in both excellent removal of polyatomic interferences and very fast acquisitions since no cell gas switching or stabilization was required¹. The sequence consisted of a single initial calibration at 0.1, 1, 10, and 100 ppb for all elements, followed by repeated (n = 26) analyses of a block of samples consisting of:

- 50 ppb calibration check (CCV)
- NIST 1643e water
- CCB (blank)
- USEPA Interference Check Solution – A (ICS-A)
- Blank
- USEPA ICS-AB (spiked with all analytes at 100 ppb to monitor carryover)
- Blank
- Blank

¹ This is a key benefit over reaction cell ICP-MS instruments that have to operate in multiple cell modes to cover all analytes. While it is possible to use multiple cell modes with discrete sampling, the resulting acquisition time is significantly lengthened, minimizing the benefits in terms of both run time and matrix exposure. If multiple cell modes are employed using the Agilent Octopole Reaction System, the small cell volume and very rapid gas switching reduce the cost in time and matrix exposure.




Figure 4. CCV recoveries (50 ppb) for entire sequence. USEPA limits for CCV recoveries in both Method 200.8 and 6020 are $\pm 10\%$ (shown in red).

Accuracy

Long-term accuracy and precision were also determined through repeated analysis of NIST 1643e Certified Reference Water ($n = 26$). Results are tabulated in Table 2, showing recoveries within $\pm 10\%$ or better of certified values and relative standard deviations near 1% for most elements. Be and Se had higher %RSDs due to the short integration times used

and slightly lower count rates for these elements in He mode. Longer integration times can be used if higher counts or better precision are required for these elements. When ultimate DLs for Se are required (low ppt), H_2 mode is recommended. Due to the fast switching time of the ORS, Se can be measured in H_2 mode with only ~30 seconds added to the sample to sample run time.

Table 2. Precision (%RSD) and Mean Recovery of NIST 1643e Water for 26 Separate Analyses

Mass/ element	Mean measured value (µg/L)	RSD (%)	Certified value (µg/L)	Mean recovery (%)
9 Be	13.8	2.5	14.0	101.0
23 Na	22689.2	2.0	20740.0	109.4
24 Mg	7300.3	2.1	8037.0	90.8
27 Al	142.3	3.3	141.8	100.4
39 K	1837.8	1.1	2034.0	90.4
43 Ca	32170.1	0.7	32300.0	99.6
51 V	37.8	1.1	37.9	99.8
53 Cr	19.2	1.7	20.4	93.9
55 Mn	38.0	0.9	39.0	97.6
56 Fe	98.1	3.9	98.1	100.0
59 Co	28.8	0.7	27.1	106.4
60 Ni	59.2	0.8	62.4	94.9
63 Cu	23.2	0.8	22.8	101.9
66 Zn	70.0	0.5	78.5	89.2
75 As	54.3	0.9	60.5	89.8
78 Se	10.0	3.4	12.0	83.2
95 Mo	121.7	1.1	121.4	100.3
107 Ag	1.1	1.4	1.1	101.1
111 Cd	6.2	0.8	6.6	94.3
121 Sb	59.5	0.9	58.3	102.0
205 Tl	7.4	0.8	7.4	100.0
208 Pb	19.6	0.9	19.6	99.7

Washout

Washout is always a concern in high sample throughput applications, particularly when analyzing high-matrix, variable samples. In order to evaluate the washout for each element, two sequential blank samples were measured immediately after each spiked ICS-AB sample. The spiked ICS-AB contained 100 ppb of all calibrated elements, plus very high concentrations of Na, Mg, Al, K, and Fe. Memory effects were determined by measuring the blank immediately following the ICS-AB. Any subsequent carryover was measured in the sec-

Table 3. Washout Performance (Mean value of 26 ICS-AB spikes [100 ppb], each immediately followed by two consecutive blanks. Percent reduction calculated as $1 - ([\text{mean Blank}] / [\text{mean ICS-AB}])$ in percentage.)

Mass/ element	ICS-AB spike Mean	Blank 1 Mean	Percent reduction Mean	Blank 2 Mean	Percent reduction Mean
9 Be	94.9315	0.0199	99.979	0.0097	99.990
23 Na	96707.6923	19.6032	99.980	13.5090	99.986
24 Mg	79238.8462	14.2332	99.982	9.8046	99.988
27 Al	75758.0769	11.7913	99.984	7.8004	99.990
39 K	82694.2308	17.6441	99.979	13.2657	99.984
43 Ca	9092.8462	1.4105	99.984	0.9697	99.989
53 Cr	95.7327	0.0419	99.956	0.0441	99.954
55 Mn	94.8977	0.0132	99.986	0.0069	99.993
56 Fe	77021.9231	12.5122	99.984	8.0837	99.990
57 Fe	75266.5385	12.0863	99.984	7.7304	99.990
59 Co	106.8577	0.0140	99.987	0.0092	99.991
60 Ni	101.3692	-0.0161	100.016	-0.0129	100.013
63 Cu	98.5700	0.0163	99.984	0.0043	99.996
66 Zn	99.9350	0.0055	99.994	0.0011	99.999
75 As	95.8615	0.0290	99.970	0.0171	99.982
78 Se	94.0162	0.0841	99.911	0.0428	99.955
95 Mo	1862.3077	1.4281	99.923	0.6278	99.966
107 Ag	96.8769	0.0181	99.981	0.0098	99.990
111 Cd	104.0538	0.0134	99.987	0.0084	99.992
121 Sb	109.1346	0.2629	99.759	0.1077	99.901
205 Tl	93.4731	0.0339	99.964	0.0131	99.986
208 Pb	92.4704	-0.0175	100.019	-0.0241	100.026

ond blank (Table 2). In all cases, greater than 3 orders of magnitude reduction (> 99.9%) was achieved before the first blank, even for the high-concentration matrix elements. The second blank showed nearly no additional reduction, indicating that essentially complete washout was achieved during the configured sample uptake and rinse-out steps of the analysis. Even "sticky" elements, such as Mo, Sb, and Tl, demonstrated the same high degree of washout. This level of washout is comparable to or better than standard peristaltic pumped systems using much longer rinse times.

Conclusions

The results of this simple experiment illustrate that discrete sampling in spectrum mode (as opposed to time-resolved mode) using the Agilent Integrated Sample Introduction System can achieve extremely high sample throughput for typical environmental analyses using USEPA criteria. These data highlight that this novel method, using ISIS, easily exceeds the demanding USEPA requirements for stability, interference control, accuracy, precision, and washout.

The ISIS-DS system offers several advantages over other discrete sampling systems: Full integration into the ICP-MS mainframe, fully integrated software, compatibility with the industry standard ASX 520 autosampler, no vacuum pump and associated pump valve to wear and replace, very low sample consumption (~2.2 mL/sample), and the flexibility to use the ISIS for other supported sample-introduction tasks, such as constant-flow nebulization, autodilution, or hydride generation.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

www.agilent.com/chem

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc., 2009
Printed in the USA
March 11, 2009
5990-3678EN



Agilent Technologies

Direct Analysis of Undiluted Soil Digests Using the Agilent High Matrix Introduction Accessory with the 7500cx ICP-MS



Application

Environmental

Authors

Steve Wilbur
Agilent Technologies
Bellevue WA
USA

Wim Proper
Eurofins Analytico
Barneveld
Netherlands

Noriyuki Yamada and Naoki Sugiyama
Agilent Technologies
Hachioji
Japan

Abstract

Agilent has developed the High Matrix Introduction (HMI) accessory for ICP-MS as an alternative to conventional dilution. The HMI modifies the sample introduction system of the Agilent 7500 Octopole Reaction System (ORS) ICP-MS, making it possible to directly measure sample solutions with total dissolved solids (TDS) exceeding 1%. In collaboration with the Eurofins Analytico laboratory in the Netherlands, a 7500cx/HMI was used to directly measure high TDS soil extracts in compliance with Dutch regulatory guidelines. The results show that the HMI is a suitable replacement for conventional autodilution, allowing Analytico to use a single 7500cx/HMI ICP-MS in place of several instruments, including conventional ICP-MS, ICP-OES and a dedicated mercury analyzer.

Introduction

The determination of trace elements in high-matrix samples has always been a difficult analytical challenge. While inductively coupled plasma mass spectrometry (ICP-MS) has unsurpassed detection capability for trace metals, the potential for salt accumulation on the MS interface has always required that dissolved solids levels be limited. Furthermore, extremely corrosive or acidic samples can damage conventional ICP-MS interface components, including the sampler and skimmer cones, requiring the use of platinum or other expensive components. Compared to ICP-Optical Emission Spectroscopy (ICP-OES) or other non-MS-based techniques, this has been considered an inherent limitation of ICP-MS. To compensate for this limitation, samples with total dissolved solids (TDS) levels higher than 0.1 to 0.2%, depending on the matrix, typically require dilution before measurement by ICP-MS, relying on ICP-MS's high sensitivity to compensate for the sensitivity loss due to dilution. However, conventional sample dilution has a number of other disadvantages, including reduced productivity, introduction of contaminants, dilution factor errors, and increased waste volume. As a superior alternative to conventional dilution, Agilent has developed a simple, novel modification to the sample introduction system of the Agilent 7500 ICP-MS with Octopole Reaction System (ORS) that can significantly improve the



Agilent Technologies

tolerance to high-matrix samples. The Agilent High Matrix Introduction (HMI)¹ accessory reduces sample matrix load on the plasma, making it possible to directly measure sample solutions with TDS exceeding 1%. As a result, samples previously measurable only by ICP-OES can now be measured directly by ICP-MS, using a 7500 ORS fitted with HMI. In this work, an Agilent 7500cx/HMI was used to test the system's ability to directly measure high TDS soil extracts in aqua regia and meet Dutch regulatory guidelines for reporting limits and data quality.

Direct Analysis of Aqua Regia Digests of Soils Using HMI-ICP-MS

This work was done in collaboration with the Eurofins Analytico laboratory (Analytico Milieu) in the Netherlands. Analytico has been part of the Eurofins group since 2001. Eurofins is a bio-analytical company with approximately 50 laboratories distributed over France, Germany, the UK, Denmark, Norway, Switzerland, and the United States. One of three divisions within Analytico, Analytico Milieu's expertise extends to the analysis of soil, sludge, groundwater, wastewater, air, building materials and residual matter, and, additionally, method development, validation, logistics, project management, and data management.

In this collaboration, an Agilent 7500cx equipped with the HMI was used to generate performance data to be used for compliance with the Dutch regulation pertaining to contaminated soils (AS3000). Due to the high TDS levels and high acid concentrations of digested soils, dilution is necessary prior to analysis by ICP-MS. Analytico currently uses the Agilent Integrated Sample Introduction System (ISIS) to perform online dilutions to meet these requirements. However, the limitations of conventional dilutions prompted Analytico to evaluate the potential of HMI as a faster, simpler, less expensive replacement for conventional autodilution that would also eliminate the maintenance issues associated with a conventional autodilutor.

Instrumentation

An Agilent 7500cx ICP-MS with the second peripump option for high sample throughput was equipped with the HMI. A Burgener MiraMist nebulizer was used. Instrument tune parameters,

including HMI settings, are listed in Table 1. The plasma was optimized in ultra robust mode with 1/12 aerosol dilution. This is the maximum dilution factor that can be set with HMI and is approximately equivalent to diluting the sample x12 conventionally. All analytes except selenium were acquired in helium collision mode, thus eliminating the need for no-gas mode and the associated time required for mode switching. Selenium was acquired in hydrogen reaction mode due to the low detection limits required.

Table 1. Instrument Tune Conditions (Values relating to HMI are shaded.)

RF power (W)	1600
Carrier gas (L/min)	0.28
HMI dilution gas (L/min)	0.67
Aerosol dilution factor	1/12
Sample uptake rate (mL/min)	0.17
ISTD uptake rate (mL/min)	0.17
Total nebulizer flow (mL/min)	0.34
Extract 1 (V)	0
Extract 2 (V)	-160
He flow (He mode)	4.0 mL/min
KED (He mode)	2 volts
H ₂ flow (H ₂ mode)	4.0 mL/min
KED (H ₂ mode)	2 volts

Sample Preparation

Actual soil samples received from Analytico's customers were prepared by adding 1 gram of soil to 8 mL of aqua regia prior to microwave digestion. Digested samples were then diluted to 50 mL final volume in ultra pure (18.2 MΩ) water. The final acid concentration is 4% HNO₃ and 12% HCl.

Calculation of Method Detection Limits (MDLs)

Since the HMI is effectively applying a dilution, the effects on detection limits are of critical importance. While ICP-MS possesses high sensitivity, the requirement for ultra trace detection limits in high TDS samples can still be challenging. Analytico has required MDLs for most analytes (based on a 1-g soil sample diluted to a final volume of 50 mL; see Table 2), which must be met in order for them to meet their reporting limits and satisfy Dutch regulatory requirements.

¹ HMI theory and performance are discussed in detail in Agilent Product Overview: Performance Characteristics of the Agilent High Matrix Sample Introduction (HMI) Accessory for 7500 Series ICP-MS, 5989-7737EN.

Table 2. Analytico 3-Sigma Required Detection Limits for Soils

Analyte	Soil dry wt (mg/kg)	After 50x dilution (µg/L)
Cd	0.17	3.4
Cr	15	300
Cu	5	100
Ni	3	60
Pb	13	260
Zn	17	340
Hg	0.05	1
As	4	80
Ag	1	20
Se	10	200
Sb	1	20
Sn	6	120
Ba	15	300
Co	1	20
Mo	1.5	30
V	1	20
Be	0.1	2
Te	10	200
Tl	3	60

MDLs were calculated as 3-sigma of 10 replicates of a low-level (between one to three times the required MDL) spiked sand sample measured consecutively and also measured on 10 different days over a 30-day period² (Table 3). For all regulated elements, the calculated MDLs exceeded the Dutch regulatory requirements by nearly an order of magnitude or better. So with the HMI operating at maximum effective dilution, the system has ample sensitivity for the application.

Analysis of Certified Reference Materials

Two certified reference materials (BCR-144R Domestic Sewage Sludge, IRMM, Belgium, and

Table 3. Calculated Method Detection Limits (mg/kg) According to the Requirements of Dutch Regulation AS3000

MDL(1) = 3σ of 10 replicates taken on the same day

MDL(2) = 3σ of 10 replicates taken on different days¹

Analyte - isotope	ORS mode	MDL (1) (mg/kg)	MDL (2) (mg/kg)	Dutch required MDL (mg/kg)
Be 9	He	0.042	0.046	0.1
V 51	He	0.255	0.481	1
Cr 52	He	2.300	4.517	15
Co 59	He	0.147	0.348	1
Ni 60	He	0.770	0.922	3
Cu 63	He	0.502	1.303	5
Zn 66	He	1.704	3.104	17
As 75	He	0.549	1.079	4
Se 78	H ₂	0.832	2.041	10
Se 78	He	1.064	1.991	10
Mo 95	He	0.195	0.413	1.5
Ag 107	He	0.278	0.701	1
Cd 114	He	0.058	0.066	0.17
Sn 118	He	0.589	1.353	6
Sb 121	He	0.333	0.401	1
Te 125	He	1.217	2.112	10
Ba 135	He	3.041	6.227	15
Hg 201	He	0.014	0.025	0.05
Tl 203	He	0.285	0.546	3
Pb 208	He	1.197	2.844	13

FeNeLab River Clay, FeNeLab, Netherlands) were analyzed in replicate as part of the validation procedure. The CRMs were prepared in the same manner as standard soil samples and measured on 10 different days during a 30-day time period. Table 4 shows the results of replicate (n = 10) analyses of both CRMs in mg/kg. Recoveries ranged from 87 to 108%, well within the regulatory requirement of 80 to 110%.

² MDLs calculated from 10 different days are for information only.

Table 4. Results of Replicate (n = 10) Analyses of Two Certified Reference Soil Samples (FeNeLab and BCR-144R)

Analyte	ORS Mode	FeNeLab River Clay			BCR-144R Sewage Sludge		
		Measured mg/kg (ave, n = 10)	Certified mg/kg	Rec. % (ave)	Measured mg/kg (ave, n = 10)	Certified mg/kg	Rec. % (ave)
Be 9	He	1.6			0.2		
V 51	He	59.6			13.9		
Cr 52	He	191.9	187	103	88.8	90	99
Co 59	He	19.8	18.7	106	13.6	13.3	102
Ni 60	He	55.7	52.9	105	40.7	44.9	91
Cu 63	He	153.9	156	99	270.0	300	90
Zn 66	He	1031.6	970	106	825.1	919	90
As 75	He	44.7	44	102	3.2		
Se 78	H ₂	2.0			1.7		
Se 78	He	2.4			1.5		
Mo 95	He	1.3			6.9		
Ag 107	He	2.9			8.2		
Cd 114	He	8.5	8.07	105	1.7	1.84	90
Sn 118	He	0.02			36.0	40.8	88
Sb 121	He	1.6			2.8	3.05	92
Te 125	He	0.3			0.1		
Ba 135	He	828.3	817	101	319.2	367	87
Hg 201	He	4.1	3.83	107	3.2	3.11	102
Tl 203	He	1.1			0.1	0.14	
Pb 208	He	297.0	274	108	94.9	96	99

Determination of Precision and Accuracy at High and Low Concentrations

In addition to analysis of replicate CRMs, both low-level and high-level spiked samples were analyzed in replicate (n = 10; 10 different days during 30-day time period) in order to determine both accuracy and precision over a wide range of concentrations (Table 5).

Table 5. Results of Replicate (n = 10) Measurements Taken on 10 Nonconsecutive Days During a 30-Day Period of Both Low-Level and High-Level Spikes of Soil Samples

Analyte	ORS mode	Low-level spike conc. mg/kg	Measured mg/kg (ave, n = 10)	RSD (%)	Rec. % (ave)	High-level spike conc. mg/kg	Measured mg/kg (ave, n = 10)	RSD (%)	Rec. % (ave)
Be 9	He	1	0.8	3.5	81	800	773.9	3.6	97
V 51	He	50	50.9	4.0	102	800	771.4	2.5	96
Cr 52	He	150	149.6	4.0	100	1100	1062.7	2.5	97
Co 59	He	10	10.4	4.1	104	800	766.3	2.0	96
Ni 60	He	25	25.3	5.3	101	1100	1074.1	3.1	98
Cu 63	He	40	40.0	6.2	100	1100	1058.5	2.5	96
Zn 66	He	150	151.6	4.2	101	1100	1094.3	4.7	99
As 75	He	40	39.0	5.0	97	400	395.5	2.8	99
Se 78	H ₂	100	102.7	3.7	103	1300	1336.0	2.2	103
Mo 95	He	13	12.2	5.0	93	1300	1235.3	3.3	95
Ag 107	He	8	8.3	4.6	103	40	40.8	4.2	102
Cd 114	He	1.2	1.1	7.1	94	1100	1062.8	2.9	97
Sn 118	He	40	41.7	4.0	104	1300	1262.6	3.2	97
Sb 121	He	10	9.7	5.9	97	1300	1188.0	2.4	91
Te 125	He	80	82.1	4.2	103	750	807.4	2.4	108
Ba 135	He	120	121.1	4.5	101	1100	1102.2	5.6	100
Hg 201	He	0.4	0.4	4.4	106	13	13.5	4.3	104
Tl 203	He	23	24.0	4.6	104	40	41.3	3.4	103
Pb 208	He	100	101.9	4.7	102	800	778.1	4.0	97

Sample Analysis

In order to test the long-term robustness of the HMI-equipped system, a 23-hour sequence consisting of an initial calibration and 235 soil samples was analyzed. Absolute drift was measured by monitoring the recovery of the five internal standards (⁶Li, Ge, Rh, In, Ir) in both gas modes (He and H₂) over the course of the sequence. Normalized recoveries (relative to the method

blank) are shown in Figure 1. Overall downward drift over 23 hours was approximately 20%, which is easily corrected by internal standards and not sufficient to have a detrimental effect on method accuracy or sensitivity. By comparison, a similar system without HMI, running these samples directly would suffer severe loss of sensitivity (> 80%) due to cone clogging before the sequence was completed.





Figure 1. Normalized internal standard recovery in digested soil samples for the duration of the 23-hour sequence. Numbers next to each ISTD in the caption denote the ORS gas mode (#2 = H₂, #3 = He).

$\pm 10\%$. Ten percent control limits are shown in red, indicating that all CCV recoveries were well within the prescribed limits for the entire sequence. This excellent calibration stability not only ensures the most accurate sample results, but also eliminates time wasted in unnecessary recalibrations should a CCV fail during the sequence.



Productivity

The operation of the HMI accessory does not adversely affect productivity in any way, since the HMI conditions are constant throughout operation and do not require any additional execution or stabilization time. Therefore, a given method run with HMI would take the same amount of time per sample as one run without HMI. HMI is also fully compatible with Agilent's time-saving pre-emptive and intelligent rinse functions, which minimize time wasted during both sample uptake and rinse-out. Furthermore, since HMI permits the direct analysis of undiluted samples of many types, the extra time associated with either manual or autodilution is saved, which considerably shortens the total time (prep plus analysis) required per sample. The improved stability as a result of HMI use can also minimize the need for recalibrations and sample reruns, further reducing the average run-to-run time. In this work, the average run time for a sample in a 23-hour, 235-sample sequence of undiluted soil digestates was 5.9 minutes, including acquisition in both H₂ and He modes.

Conclusions

Based on Analytico's evaluation, when compared with conventional autodilution for high TDS, high acid digests of soil and sludge samples, Agilent's

HMI interface provided a number of significant advantages.

- **Speed** – HMI does not require liquid dilution of sample and stabilization of diluted sample. It also permits the use of Agilent's pre-emptive rinse function, which allows rinsing of the sample tubing to begin before acquisition has finished.
- **Low maintenance** – There is no tubing to replace and no moving parts to maintain.
- **Simple** – There are no critical timing issues or plumbing common to continuous flow autodilutors.
- **Flexibility** – Since hardware changes or reconfigurations are not required after installation of HMI, the system can be switched between conventional mode and HMI mode on the fly.

These advantages have allowed Analytico to use a single 7500cx ICP-MS fitted with HMI to replace several instruments required for the analysis of these sample types, including conventional ICP-MS, ICP-OES, and a dedicated mercury analyzer.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
February 27, 2008
5989-7929EN



Agilent Technologies



Rapid Analysis of High-Matrix Environmental Samples Using the Agilent 7500cx ICP-MS

Application

Environmental

Author

Steven Wilbur
Agilent Technologies, Inc.
3380 146th Place, SE, Suite 300
Bellevue, WA 98007
USA

Abstract

The new Agilent 7500cx with Octopole Reaction System (ORS) is capable of analyzing most typical environmental samples using only one mode of analysis: helium mode. For the first time, it is possible to analyze an entire environmental suite of elements, including Hg and the major elements such as Na, K, Ca, Mg, Al, and Fe, in less than 2.5 minutes per sample, under conditions that remove or reduce practically all matrix-based interferences.

Introduction

Contract analytical laboratories, particularly those focused on the analysis of environmental samples, face challenges that are significantly different from those of research institutes in government and academia. The samples are typically more numerous, unknown and highly variable in composition, and generally require rapid turnaround. Despite these challenges, the environmental laboratory must ensure that the data produced is of high quality and is supported by extensive analytical quality control (AQC) in order to remain productive and profitable. The recent great improvement in productivity (and, consequently, profitability) of the metals section in contract environmental labs is largely due to the increasing use of ICP-MS, with its rapid multi-element capability, wide elemental cov-

erage and dynamic range, low detection limits, and ease of use. With the advent of collision/reaction cell (CRC) ICP-MS, the ability of the technique to eliminate or significantly reduce the effects of polyatomic interferences in complex matrices has further improved its usability for many applications. However, until recently, the improved accuracy delivered by CRC ICP-MS came at a significant cost to productivity. Typical CRC ICP-MS systems must use reactive cell gases to specifically target known interferences, which requires time-consuming, matrix-specific method development. Furthermore, multiple cell conditions are necessary depending on the matrix and analyte list, which can add minutes to each sample analysis.

Agilent pioneered the use of helium (collision) mode coupled with kinetic energy discrimination (KED) on the 7500c instrument, allowing most polyatomic interferences to be removed using a single set of cell conditions. Subsequent advances in instrument design and in the understanding of the collision mechanisms involved have resulted in the 7500cx, an ICP-MS capable of analyzing typical environmental samples using only helium mode. By eliminating the need for both hydrogen (reaction) mode¹ and no-gas mode, sample throughput is significantly improved and routine operation is greatly simplified. Coupled with improvements in uptake and rinse-out speed through various hardware and software innovations, it is now possible to analyze an entire environmental suite of elements, including Hg and the major elements such as Na, K, Ca, Mg, Al, and Fe, in less than 2.5 min-

¹ Trace level selenium analysis (i.e., below 0.2 ng/mL) requires the use of hydrogen mode to eliminate the Ar₂⁺ interferences on the preferred isotopes at mass 78 and 80.



Agilent Technologies

utes per sample, under conditions that remove or reduce all matrix-based interferences. This application documents the performance of the 7500cx for the high-throughput analysis of long sequences of typical high-matrix environmental samples.

Instrumentation

A standard Agilent 7500cx ICP-MS with a glass concentric nebulizer was used for all analyses. The instrument was tuned for standard robust plasma conditions (Table 1) and the ORS was operated in helium mode only. This means that all elements were measured under identical helium mode collision conditions and no mode switching was necessary. Furthermore, the helium mode conditions used are generic and do not have to be set up or modified for specific sample matrices. Method parameters are shown in Table 1.

Table 1. Instrument Tune and Acquisition Conditions Used

Instrument	7500cx
Sampler	Ni (standard)
Skimmer	Ni (standard)
Nebulizer	MicroMist (standard)
Plasma torch	Quartz, 2.5 mm (standard)
Integration Time	
Li, Be, As, ⁷⁸ Se, ¹¹¹ Cd	0.3 sec x 1 point
All other	0.1 sec x 1 point
Tune Parameters	
RF power	1550 W
Sample depth	8.5 mm
Carrier gas	0.80 L/min
Makeup gas	0.23 L/min
Extract 1	0V
Extract 2	-120 V
Energy discrimination	2 V
Reaction gas	He 5.0 mL/min
CeO/Ce	0.52%
Ce ⁺⁺ /Ce	2.06%

Sensitivity in Helium Mode

Real sensitivity, as determined by practical limits of detection (LOD), is a function of signal to background (high signal, low background) and the precision of the background measurement. The greatest analytical benefit in using helium mode will be realized for analytes that suffer from polyatomic ion overlaps (essentially every isotope of every element from mass 45 to 82). However, it is important to assess the possible degradation in performance for elements that do not suffer from polyatomic interference where helium mode is used for all analytes. Poorer signal to noise for

noninterfered elements is a possibility, as any ICP-MS operating with the cell pressurized (in collision or reaction mode) will suffer some loss of signal for low-mass elements when compared with no-gas mode. This signal loss occurs as a result of collisions between analyte ions and gas molecules in the cell. However, in most cases, the reduction in background more than compensates for the loss of signal, so real detection limits for noninterfered elements are not significantly impacted. In order to measure actual sensitivity under helium conditions, signal-to-background ratios and 3 sigma instrument detection limits (IDLs) were determined in helium mode for all commonly measured elements². For nearly all elements, IDLs are in the low- to sub-ppt range. More important for environmental applications are the background equivalent concentrations (BECs) and IDLs for those elements that typically suffer from interferences in high-matrix samples. Table 2 compares the BECs, IDLs, and equivalent concentration of interferences for several critical elements in no-gas and helium mode in USEPA Interference Check Solution (ICS-A³ - see Table 3 for composition). Note the significant reduction in all three measurements for all isotopes, showing that helium mode is capable of simultaneously removing interferences on multiple elements (and even multiple isotopes) in complex matrices.

Interference Removal in Helium Mode

USEPA Method 6020 specifies an interference check sample (ICS-A) designed specifically to monitor the effect of polyatomic interferences resulting from high concentrations of common matrix components. Traditionally, these interferences have been compensated for through the use of mathematical correction equations. However, experienced ICP-MS users know that in the case of multiple interferences on a single analyte or interferences from uncommon matrix components, mathematical correction is unreliable. Additionally, many polyatomic interferences cannot be corrected mathematically because of the lack of a free mass at which to monitor the interferent. A common example is the interference from ⁴⁰Ar²³Na on ⁶³Cu. This is a significant interference in saline matrices, but because Na is monoisotopic (at mass 23), it is not possible to derive a mathematical cor-

² Performance characteristics of the Agilent 7500cx ICP-MS. Agilent application note 5989-6663EN.

³ ICS-A is the USEPA-specified "Interference Check Solution" designed to alert the user to the possibility of isobaric, doubly charged, polyatomic and memory interferences in high-matrix samples. ICS-AB is the same high-matrix solution spiked with 100 to 200 ppb of each analyte element in order to measure the effects of high matrix on analyte recovery. In this work, the target analytes were spiked much lower (20 ppb, ICS-AB Modified) in order to test the effectiveness of interference removal at trace analyte levels.

Table 2. Comparison of No-Gas Mode and Helium Mode on BEC, IDL, and Measured Concentration in ICS-A Solution (Note the much higher measured concentration values obtained in no-gas mode due to polyatomic interferences. Se 77 and 78 values do not agree in no-gas mode, and V gives a negative concentration reading.)

	No Gas Mode			Helium Mode		
	BEC (ppt)	IDL (ppt)	Measured conc (ppb)	BEC (ppt)	IDL (ppt)	Measured conc (ppb)
⁵¹ V	1461	143	-1.35	107	45	0.13
⁷⁵ As	1945	186	3.23	120	149	0.70
⁷⁷ Se	9973	540	12.31	401	204	0.50
⁷⁸ Se	9738	313	3.84	342	162	0.43

rection based on the abundance of a second ArNa polyatomic ion. This has typically led ICP-MS users to select the alternative (and much lower abundance) Cu isotope at mass 65. However, ⁶⁵Cu suffers from a much higher level of S-based interferences (S₂ and SO₂) than ⁶³Cu as well as a significant ²⁵Mg⁴⁰Ar interference, so switching to ⁶⁵Cu to avoid the ArNa overlap can result in compromised data quality in many sample types.

Cr is another example of an element that commonly suffers from polyatomic interferences (⁴⁰Ar¹²C, ³⁵Cl¹⁶OH, ³⁶Ar¹⁶O, and ³⁸Ar¹⁴N on ⁵²Cr, and ³⁷Cl¹⁶O, ⁴⁰Ar¹³C, and ³⁶Ar¹⁶OH on ⁵³Cr), which cannot be reliably corrected mathematically due to the lack of a free reference mass. For these reasons, helium mode, with its ability to remove all polyatomic interferences regardless of sample matrix composition, is vastly more reliable and more widely applicable than the use of mathematical corrections⁴.

Figure 1 shows overlaid spectra for USEPA ICS-A, measured from mass 73 to 82 in no-gas, helium, and hydrogen modes. The spectra have been normalized on the bromine peak at *m/z* 79 to compensate for differences in sensitivity between modes. The differences in spectral complexity are clear, with almost every mass showing some level of interference in no-gas mode, while helium mode has reduced all of these interferences to background levels.

Table 3. Composition of ICS-A and ICS-AB (modified)³ (ICS-AB was prepared by spiking ICS-A with a 20-ppb standard containing all analyte elements of interest.)

Component	ICS-A concentration (mg/L)	ICS-AB concentration (mg/L)
Al	100.0	100.0
Ca	300.0	300.0
Fe	250.0	250.0
Mg	100.0	100.0
Na	250.0	250.0
P	100.0	100.0
K	100.0	100.0
S	100.0	100.0
C	200.0	200.0
Cl	2000.0	2000.0
Mo	2.0	2.0
Ti	2.0	2.0
As	0.0	0.02
Cd	0.0	0.02
Cr	0.0	0.02
Co	0.0	0.02
Cu	0.0	0.02
Mn	0.0	0.02
Hg	0.0	0.02
Ni	0.0	0.02
Se	0.0	0.02
Ag	0.0	0.02
V	0.0	0.02
Zn	0.0	0.02

⁴ Note that because helium mode works only on polyatomic interferences, it is not capable of removing elemental isobaric interferences (e.g., ⁴⁰Ar on ⁴⁰Ca) or doubly charged interferences. Fortunately, these types of interferences are rare, and simple methods are available to avoid them, such as choosing an alternative analyte isotope.




Figure 1. Overlaid spectra of ICS-A obtained in no-gas, hydrogen, and helium modes over the range from mass 73 to 82 to show interferences on As and Se. Spectra normalized on Br signal at m/z 79. Note that while H_2 mode is effective for the removal of the Ar_2^+ overlap at mass 80 (main isotope of Se) in simple matrices, it is not effective for several other interferences at this mass in ICS-A ($ArCa$, Ca_2 , S_2O , SO_3 , etc.). Ar_2^+ is completely removed by H_2 mode at m/z 78, which is therefore the preferred isotope.

Experimental

A 12-hour, 300-sample sequence, representing a typical environmental batch, was analyzed after a single initial calibration consisting of a blank and standards at 1, 10, 50, and 100 ppb (Figure 2). The sequence consisted of repeated blocks of 10 samples, including NIST 1640 standard reference water, ICS-A, ICS-AB, and two commercially available high total dissolved solids (TDS) mineral water samples. After each block, blank check and calibration check samples (USEPA sample types continuing calibration blank [CCB] and continuing calibration verification [CCV]) were automatically inserted to check for memory effects and calibration accuracy. No recalibrations were performed during the 12-hour run.




Figure 2. Schematic of analytical sequence. 300 sample analyses were performed, including an initial calibration and 22 repeated analyses of a block of samples containing 10 samples followed by 2 CCV samples and a CCB.

Long-Term Stability

Analysis of CCV Samples

As a check on calibration stability for all analyte elements, a CCV standard (50 ppb for all analytes except Hg – 1 ppb) was analyzed repeatedly throughout the sequence. USEPA Methods 200.8 and 6020 require that the measured CCV values fall within $\pm 10\%$ of the true value in order to report samples. Figure 3 shows the results of 25 measurements of the CCV sample over the 12-hour sequence, indicating no failures throughout the run, despite the fact that no recalibrations were performed after the initial calibration.

Analysis of High-Matrix Samples

In order to simulate difficult, high-matrix sample types, ICS-A and ICS-AB were each analyzed twice

in each 10-sample block (giving a total of 48 replicate analyses of each), in addition to the two high-TDS mineral water samples. ICS-A and ICS-AB were selected because they are well characterized and were specifically designed by the USEPA to challenge the ICP-MS's ability to handle high-matrix samples in terms of controlling interferences, managing ionization suppression, eliminating memory effects, and maintaining long-term stability. Long-term precision and accuracy for trace-level measurement in high-matrix samples can be determined by examining the results of repeated analysis of ICS-AB. Recoveries ranged from 97 to 104% with %RSDs ranging from less than 1% to approximately 5% over the 12-hour sequence (Figure 4).




Figure 3. Measured values of 50 ppb CCV samples ($n = 25$) over the course of the sequence. USEPA criteria are $\pm 10\%$ (i.e., 45 to 55 ppb).




Figure 4. Spike recovery (20 ppb, 1 ppb Hg) for ICS-AB over 12 hours (n = 44).

Analysis of Certified Reference Material

NIST 1640 certified reference water was analyzed repeatedly (n = 44) as part of the sequence. Results are shown in Table 4.

Table 4. Results of Repeated Analysis of NIST 1640 (n = 44) Over a 12-Hour Sequence

Element	Mean (n = 44)	RSD (%)	Certified value (µg/L)	Recovery (%)
⁹ Be	32.36	4.72	34.94	92.6
²⁷ Al	48.62	3.90	52.00	93.5
⁴² Ca	6652.25	2.59	7045	94.4
⁵¹ V	12.66	1.40	12.99	97.4
⁵² Cr	36.14	3.19	38.60	93.6
⁵⁵ Mn	114.96	3.87	121.50	94.6
⁵⁹ Co	19.64	2.27	20.28	96.8
⁶⁰ Ni	26.76	2.86	27.40	97.7
⁶³ Cu	84.95	2.16	85.20	99.7
⁶⁶ Zn	52.64	2.66	53.20	99.0
⁷⁵ As	25.28	1.52	26.67	94.8
⁷⁸ Se	20.69	4.61	21.96	94.2
⁸⁸ Sr	118.03	1.31	124.20	95.0
¹⁰⁷ Ag	7.15	1.67	7.62	93.8
¹¹¹ Cd	21.31	1.26	22.79	93.5
¹²¹ Sb	13.48	1.68	13.79	97.7
¹³⁷ Ba	140.78	1.03	148.00	95.1
²⁰⁰ Hg	0.10	12.23	—	—
²⁰² Hg	0.10	9.83	—	—
²⁰⁴ Pb	26.98	3.62	27.86	96.9
²⁰⁵ Tl	0.01	54.91	—	—
²⁰⁶ Pb	25.04	1.06	27.86	89.9
²⁰⁷ Pb	26.94	1.11	27.86	96.7
²⁰⁸ Pb	26.17	0.86	27.86	94.0
²³² Th	0.05	45.36	—	—
²³⁸ U	0.73	2.90	—	—

Average Analysis Time

One of the major goals of using a single ORS mode is to improve productivity. To ensure that this end was met:

- Integration times were kept short, typically 0.1 second per point.
- A single point per mass was used.
- Intelligent and pre-emptive rinse functions were employed (minimizes wasted time in uptake and rinseout and ensures that carryover could not occur).

Figure 5 graphically shows the time savings possible. In a conventional CRC system, after sample uptake and initial stabilization, acquisition occurs in the first of several CRC modes, followed by cell evacuation, repressurization, and restabilization (top). The process continues until all necessary modes have been completed (typically 3). In the 7500cx helium mode (bottom), initial uptake and stabilization are the same. After that, helium mode acquisition can begin immediately, since no cell evacuation or repressurization is necessary, followed by rinse. Pre-emptive rinsing begins up to 60 seconds before acquisition has finished, and intelligent rinse monitors rinseout, ensuring complete washout without any wasted time. The total acquisition time for all analytes and internal standards was 9.7 seconds per replicate. Three replicates were acquired according to USEPA methods,

resulting in a total acquisition time of 29.2 seconds. Overall, the average run-to-run time based on 300 runs beginning at 4:44 p.m. and ending at 5:04 a.m. the following morning was 2.46 minutes per run. As the data in Table 4 illustrate, despite the short acquisition time, precision was not compromised and all data returned excellent %RSDs over the 12-hour period.

Conclusions

Since helium mode is universal, all interferences are removed without prior sample knowledge. Tuning is simplified and problems associated with reactive cell processes such as the creation of new interferences or loss of analyte or internal standard are avoided. Stability is not compromised since cell conditions are static and run times are

markedly improved through the elimination of multiple cell conditions along with the associated stabilization times.

For many applications, particularly commercial analysis of high-matrix environmental samples, the use of helium mode offers significant benefits in productivity, data reliability, and ease of use.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.




Figure 5. Typical multimode CRC operation (top), and 7500cx using helium mode and pre-emptive rinse software (bottom).

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
September 20, 2007
5989-7297EN



Agilent Technologies



Faster, Simpler, More Accurate Semiquantitative Analysis Using the Agilent 7500cx ICP-MS

Application

Author

Steven Wilbur
Agilent Technologies, Inc.
Bellevue, WA
USA

Abstract

The new Agilent 7500cx allows the user to achieve the full potential of ICP-MS for semiquantitative elemental screening of a wide range of sample types. Complex, unknown samples can be analyzed with better speed, accuracy, and data integrity than ever before, since all matrix interferences are removed in the Octopole Reaction System (ORS) using helium collision mode. Results are presented for three different certified reference materials.

Introduction

Semiquantitative elemental analysis (semiquant) by ICP-MS is a powerful tool for quick screening of unknown samples for a wide range of trace elements. The ability to perform accurate semiquant is a strength of ICP-MS that is not shared by other elemental analysis techniques. It is based on the fact that the relative response of any element can be estimated from the response of any other element under a given set of conditions. These relative responses are determined by the unique

properties of each element as well as the instrument and operating conditions, and can be stored in a semiquant response factor database. The use of internal standards or other calibration elements allows the database to be updated as needed to reflect the specific acquisition and matrix conditions. In practice, however, spectral interferences have limited the usefulness of semiquant for a number of elements in many common matrices.

Collision/Reaction Cell ICP-MS and Semiquant

In most collision/reaction cell (CRC) instruments, specific information about the matrix and target analytes is required in order to set up the correct collision/reaction chemistry to eliminate the interferences. Additionally, the conditions required to eliminate one interference in one matrix are generally not effective for all analytes in all matrices. For this reason, multiple sets of collision/reaction conditions are typically used. However, accurate semiquant response factors cannot be determined for elements acquired under different CRC conditions. As a result, it has not previously been possible to use CRC technology to reduce interferences in semiquant in the same way as in full quantification. However, the unique ability of Agilent's Octopole Reaction System (ORS) to eliminate polyatomic interferences using carefully controlled kinetic energy discrimination (KED) in helium collision mode permits all elements to be acquired under a single, universal set of CRC conditions.



Agilent Technologies

KED eliminates the transmission of the larger polyatomic ions from the collision cell to the quadrupole by placing an energy barrier between the collision cell and quadrupole. Since polyatomic ions are always larger than atomic (analyte) ions of the same mass (Figure 1), they undergo more energy-reducing collisions with the helium cell gas

than do the smaller atomic ions. As a result, the polyatomic ions have insufficient residual energy to cross the energy barrier at the cell exit, and so are excluded from the ion beam. Figure 2 depicts the effects of KED on ion energy. Only the high-energy atomic ions exceed the stopping potential




Figure 1. Graphic representation of the relative diameter of an atomic ion (Cu) compared with the polyatomic ions that can interfere. Most elemental ions are smaller than 150-picometer radius, while most polyatomic ions are larger.





Figure 2. Diagrammatic representation of Kinetic Energy Discrimination after energy-reducing collisions within the Octopole Reaction System cell.

and are transmitted. Since helium is a nonreactive gas, no new interferences are formed in the cell and no analyte signal is lost by reaction, as occurs with any reactive cell gas.

The use of helium collision mode with semiquant conveys all the advantages normally associated with the use of CRC technology in full quant. It also solves the previously critical limitations of semiquant due to unresolved interferences. The advantages include:

- Semiquant is simple, fast, accurate, and interference-free for all analytes in any matrix.
- Helium collision mode allows the use of HCl, H₂SO₄, or other acids in digestion without danger of chlorine- or sulfur-based interferences on elements such as As, Cr, Se, V, Zn, etc.
- Improved stability for elements like Ag, Hg, Sb, Sn, and the Pt group due to the ability to add HCl to samples and standards.
- Ability to select the most abundant isotope for the best sensitivity, or multiple isotopes for absolute data confidence.
- Freedom to use any internal standards.

Table 1. Tune Conditions Used for NIST 1640 Semiquant Analysis in Helium Collision Mode

RF power	1550 W
Sample depth	8.0 mm
Carrier gas flow rate	0.90 L/min
Makeup gas flow rate	0.23 L/min
Sample flow rate	0.4 mL/min
Spray chamber temperature	2 °C
Helium flow rate	5 mL/min
KED	2V

Table 2. Semiquant Acquisition Parameters for NIST 1640

Total run time	170 seconds
Acquisition mode	Spectrum - peak hopping
Number of masses	250
Integration time[sec] masses 2 - 260	0.1 sec/point
Number of points per mass	1
Acquisition time	50.9 [sec]
Number of replicates	1
Uptake time	20 sec
Stabilization time	60 sec
Post acquisition rinse	30 sec
Preemptive rinse	On (time = 30 sec)

Experimental

The 7500cx ICP-MS was tuned for the same typical robust plasma conditions that are used in routine quantitative analysis (Table 1). No special tuning is required. Semiquant acquisition parameters are listed in Table 2.

A single calibration standard containing 200 ppb of Ag, Al, As, Ba, Be, Bi, Ca, Cd, Co, Cr, Cs, Cu, Fe, Ga, K, Li, Mg, Mn, Na, Ni, Pb, Rb, Se, Sr, Th, Tl, U, V, and Zn made up in 1% HNO₃/0.5% HCl was used to update the semiquant response factor database for a range of elements across the mass range. Non-calibrated elements are updated by interpolating between calibrated isotopes, which the ChemStation does automatically. Any number of calibration elements may be used, but increasing the number of calibration elements will improve semiquantitative accuracy. Internal standardization was applied using a typical suite of internal standard elements distributed across the mass range.

Results and Discussion

Tables 3 and 4 show the results of a semiquantitative screen of three standard reference materials, NIST 1640 water, LGC 6010 hard drinking water,

Table 3. Results of Helium Collision Mode Semiquant Analysis NIST 1640 Standard Reference Water

Element	NIST 1640 certified value	SQ conc.	Unit	Recovery (%)
9 Be	34.94	33.42	µg/L	95.6
11 B	301.1	335.83	µg/L	111.5
23 Na	29.35	22.25	mg/L	75.8
24 Mg	5.819	4.24	mg/L	72.9
27 Al	52	48.92	µg/L	94.1
39 K	994	919.17	µg/L	92.5
42 Ca	7.045	5.81	µg/L	82.4
51 V	12.99	12.83	µg/L	98.8
52 Cr	38.6	36.58	µg/L	94.8
55 Mn	121.5	121.67	µg/L	100.1
56 Fe	34.3	30.92	µg/L	90.1
59 Co	20.28	19.75	µg/L	97.4
60 Ni	27.4	25.83	µg/L	94.3
63 Cu	85.2	81.17	µg/L	95.3
66 Zn	53.2	51.83	µg/L	97.4
75 As	26.67	27.75	µg/L	104.0
78 Se	21.96	24.08	µg/L	109.7
88 Sr	124.2	122.50	µg/L	98.6
95 Mo	46.75	46.17	µg/L	98.8
107 Ag	7.62	7.31	µg/L	95.9
111 Cd	22.79	21.50	µg/L	94.3
121 Sb	13.79	12.83	µg/L	93.1
137 Ba	148	139.17	µg/L	94.0
208 Pb	27.89	23.5	µg/L	84.3

Table 3 has been simplified to show only those elements with some reference values, although many other elements were determined in each reference material.

Table 4. Results of Helium Collision Mode Semiquant Analysis of LGC 6010 Hard Drinking Water and LGC 6177 Landfill Leachate Standard Reference Materials

Element	LGC 6010 hard drinking water			LGC 6177 landfill leachate		
	LGC certified value (µg/L)	SQ conc. (µg/L)	Recovery (%)	LGC certified value (µg/L)	SQ conc. (µg/L)	Recovery (%)
10 B	N/A	83	N/A	9,800	6,700	68.4
23 Na	21,900	20,000	91.3	1,750,000	1,500,000	85.7
24 Mg	4,200	3,700	88.1	73,500	62,000	84.4
27 Al	208	160	76.9	N/A	110	N/A
31 P	N/A	670	N/A	11,500	12,000	104.3
39 K	5,100	5,100	100.0	780,000	810,000	103.8
44 Ca	83,200	73,000	87.7	74,800	77,000	102.9
52 Cr	48	51	106.3	180	160	88.9
55 Mn	48	45	93.8	140	130	92.9
56 Fe	236	240	101.7	3,800	3,300	86.8
60 Ni	48	42	87.5	210	170	81.0
66 Zn	542	540	99.6	260	250	96.2
75 As	55	49	89.1	N/A	86	N/A
78 Se	9.5	13	136.8	N/A	< 16.00	N/A
107 Ag	6.2	4.3	69.4	N/A	1.8	N/A
121 Sb	11.9	13	109.2	N/A	5	N/A
137 Ba	116	110	94.8	N/A	770	N/A
208 Pb	95	92	96.8	N/A	17	N/A

Table 4 has been simplified to show only those elements with some reference values, although many other elements were determined in each reference material.

and LGC 6177 landfill leachate. No attempt was made to matrix-match; tune conditions used were as shown in Table 1; and all elements were acquired in helium collision mode. In all cases, for every certified element, the semiquantitative result was within $\pm 40\%$ of the certified concentration, from as low as 7 ppb for Ag in NIST 1640 to over 1700 ppm for Na in the LGC 6177 landfill leachate.

Conclusions

Semiquant has always been a powerful tool available to the ICP-MS analyst for quickly estimating the concentration of unknown, uncalibrated elements in a variety of simple matrices. However, in complex matrices, polyatomic interferences could render the results for many elements useless. Collision/reaction cell technology, which requires more than one set of conditions for all masses, cannot be used since it would result in deviation from the standard relative response tables upon which semiquant is based. Helium collision mode coupled with kinetic energy discrimination in the Agilent 7500cx can overcome these limitations. By effectively removing polyatomic interferences, rapid, accurate, semiquantitative screening of a wide

range of sample types for most analyte elements is possible. In this work, a full mass range, 250 isotope semiquant screen was performed in less than 3 minutes total sample-to-sample time with accuracy comparable to full quantification, for most elements, when measuring three different certified reference materials.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
May 4, 2007
5989-6662EN



Agilent Technologies



Unmatched Removal of Spectral Interferences in ICP-MS Using the Agilent Octopole Reaction System with Helium Collision Mode

Application

Metals Analysis

Authors

Ed McCurdy, Glenn Woods and Don Potter
Agilent Technologies
Lakeside Business Park
Cheadle Royal, Cheshire
UK

Abstract

Many routine laboratories have adopted ICP-MS as their primary technique for metals analysis due to its simple operation as a multi-element analyzer. However, despite its higher performance for the targeted removal of specific interferences, collision/reaction cell (CRC) ICP-MS remains relatively understudied in terms of its multi-element capability. This work demonstrates that the Agilent 7500ce ICP-MS can be operated with a single set of He cell gas conditions, to provide effective interference removal for a range of elements in a challenging and complex sample matrix.

Introduction

ICP-MS is an immensely powerful multi-element analytical technique, but it does suffer from some well-documented spectral interferences, which can be especially problematic when complex and variable samples are analyzed. Most interferences in ICP-MS arise due to an overlap from a molecular (or polyatomic) ion at the same nominal mass as the analyte of interest. Commonly reported interferences can be broadly divided into two groups: those derived from the plasma and aqueous solution

(plasma-based), such as ^{40}Ar , $^{40}\text{Ar}^{16}\text{O}$, and $^{40}\text{Ar}^{38}\text{Ar}$, and those derived from sample matrix components (matrix-based), such as $^{35}\text{Cl}^{16}\text{O}$, and $^{32}\text{S}^{34}\text{S}$. Plasma-based polyatomic ions are both predictable and reasonably constant, regardless of sample matrix, whereas matrix-based polyatomic ions are less predictable and vary with sample matrix components and their relative concentrations.

Recent advances in CRC technology have led to dramatic improvements in the analysis of interfered elements which previously proved difficult or impossible to measure at required levels in certain sample matrices. In a CRC ICP-MS, the cell is typically pressurized with a reactive gas that reacts with the interference (referred to as reaction mode). Attenuation of the interfering species occurs by one of several different processes depending on the gas and the interference. However, in practice, “reaction mode-only” CRCs limit the system to the removal of single interfering ions from single analytes [1–8], using highly reactive gases and specific measurement conditions. Some instruments use “simpler” or less reactive cell gas such as H_2 , but its use is limited mainly to plasma-based interferences, as it reacts slowly or not at all with matrix-based interferences which are much more difficult to remove.

Helium (He) Collision Mode

The development of the Agilent Octopole Reaction System (ORS) introduced a new and much more powerful mode of CRC operation – He collision mode – which uses an inert collision gas to remove all polyatomic species based on their size rather



Agilent Technologies

than their relative reactivity with a reaction gas. Since all polyatomics are larger than analyte ions of the same mass, their larger cross-section means that they suffer more collisions with the cell gas and so lose more energy as they progress through the pressurized region. On arrival at the cell exit, the large cross section polyatomic species all have distinctly lower ion energy (due to collisions with the He cell gas) than the analyte ions and so can be prevented from leaving the cell using a stopping voltage, allowing only the analytes to pass through to the analyzer. This separation process is known as kinetic energy discrimination (KED), and this simple yet extremely effective approach offers a number of significant analytical advantages over reaction mode.

Advantages of He Collision Mode:

- In contrast with a reactive cell gas, He is inert - so does not react with the sample matrix - no new interferences are formed in the cell
- As He is inert, it does not react with and cause signal loss for analyte or internal standard ions
- ALL interferences (plasma-based AND matrix-based) are removed or attenuated so multi-element screening or semiquant analysis can be combined with effective interference removal
- Since He collision mode is not interference-specific, multiple interferences can be removed from the same analyte (or different analytes) simultaneously [9, 10]
- No prior knowledge of the sample matrix is required, and no method development is required, in contrast to the extensive, analyte- and matrix-specific method development which is required for any reactive mode of interference removal [11]
- He collision mode can be applied to every sample, every matrix, and the same setup (gas flow rate) is used for every application
- No cell voltages to set up or optimize
- NO interference correction equations are used

Why Can't Other CRC-ICP-MS Use He Collision Mode?

To work properly, He collision mode requires efficient analyte/interference separation by KED, which requires two conditions to be met: first, the energy of all the ions entering the cell must be very tightly controlled. Agilent's unique ShieldTorch

interface insures a very narrow ion energy spread of 1 eV: its physically grounded shield plate provides better control of initial ion energy than electrically grounded plasma designs (such as balanced, center-tapped or interlaced coils). Second, in the cell, polyatomic species must experience a sufficiently high number of collisions to differentiate them from the analyte ions at the cell exit. In the Agilent ORS this is achieved by the use of an octopole ion guide – the only implementation of an octopole cell in ICP-MS. There are two key benefits to the use of an octopole cell:

- Octopoles have a small internal diameter. As a result, the cell entrance and exit apertures are small – so the cell operates at relatively higher pressure compared to quadrupole or hexapole cells which increases ion/gas collisions.
- Octopoles also have better focusing efficiency than hexapole and quadrupole ion guides. The ion beam is tightly focused, which insures good ion transmission and high sensitivity at its higher cell operating pressure.

Only the Agilent ORS combines the ShieldTorch interface with an octopole cell and so only the Agilent ORS can effectively use He collision mode.

Testing He Collision Mode – a Worst Case Scenario

A synthetic sample matrix was prepared to give rise to multiple interferences across a range of common analytes and test the ability of He collision mode to remove all overlapping polyatomic species. A standard solution was prepared, containing 1% HNO₃, 1% HCl and 1% H₂SO₄ (all UpA UltraPure Reagents, Romil, Cambridge, UK), 1% Butan-1-ol (SpS Super Purity, Romil, Cambridge, UK) and 100 mg/L (ppm) each of Na and Ca (both prepared from 10,000 mg/L Spex CertiPrep Assurance single element standards), to simulate a very complex natural sample matrix. Table 1 summarizes the potential polyatomic species in this sample matrix, illustrating that practically every element in the mid-mass region (from 50 to 80 amu) suffers from multiple interferences. This makes the accurate determination of these elements in complex sample matrices extremely challenging for conventional ICP-MS, as the complex nature of the multiple interferences means mathematical corrections will be unreliable. This also illustrates why reactive cell gases are unsuitable for the multi-element analysis of complex samples; no single reaction gas can be effective for a range of

polyatomic ions, each of which will have different reactivity with any given reactive cell gas. However, every interference shown in Table 1 is a polyatomic ion and can therefore be attenuated effectively using a single set of He collision mode conditions. Two sets of spectra were acquired to show the ability of the He collision mode to remove multiple interferences; one in no-gas mode and the second with He added to the cell. No data correction or background subtraction was applied. Finally, a 5-ppb multi-element spike was added to

the matrix and spectra acquired to confirm the recovery of all analytes and check for correct isotopic fit.

Instrumentation

An Agilent 7500ce ICP-MS was optimized using the typical tuning conditions for high and variable sample matrices (plasma conditions optimized as usual for ~0.8% CeO/Ce). No attempt was made to optimize any parameter for the targeted removal of any specific interference. 5.5 mL/min He gas (only) was added to the cell for the collision mode measurements.

Table 1. Principal Polyatomic Interferences from an Aqueous Matrix Containing N, S, Cl, C, Na, and Ca

Isotope	Principal interfering species
⁵¹ V	³⁵ Cl ¹⁶ O, ³⁷ Cl ¹⁴ N
⁵² Cr	³⁶ Ar ¹⁶ O, ⁴⁰ Ar ¹² C, ³⁵ Cl ¹⁶ OH, ³⁷ Cl ¹⁴ NH
⁵³ Cr	³⁶ Ar ¹⁶ OH, ⁴⁰ Ar ¹³ C, ³⁷ Cl ¹⁶ O, ³⁵ Cl ¹⁸ O, ⁴⁰ Ar ¹² CH
⁵⁴ Fe	⁴⁰ Ar ¹⁴ N, ⁴⁰ Ca ¹⁴ N
⁵⁵ Mn	³⁷ Cl ¹⁸ O, ²³ Na ³² S
⁵⁶ Fe	⁴⁰ Ar ¹⁶ O, ⁴⁰ Ca ¹⁶ O
⁵⁷ Fe	⁴⁰ Ar ¹⁶ OH, ⁴⁰ Ca ¹⁶ OH
⁵⁸ Ni	⁴⁰ Ar ¹⁸ O, ⁴⁰ Ca ¹⁸ O, ²³ Na ³⁵ Cl
⁵⁹ Co	⁴⁰ Ar ¹⁸ OH, ⁴³ Ca ¹⁶ O
⁶⁰ Ni	⁴⁴ Ca ¹⁶ O, ²³ Na ³⁷ Cl
⁶¹ Ni	⁴⁴ Ca ¹⁶ OH, ³⁸ Ar ²³ Na, ²³ Na ³⁷ ClH
⁶³ Cu	⁴⁰ Ar ²³ Na, ¹² C ¹⁶ O ³⁵ Cl, ¹² C ¹⁴ N ³⁷ Cl
⁶⁴ Zn	³² S ¹⁶ O ₂ , ³² S ₂ , ³⁶ Ar ¹² C ¹⁶ O, ³⁸ Ar ¹² C ¹⁴ N, ⁴⁸ Ca ¹⁶ O
⁶⁵ Cu	³² S ¹⁶ O ₂ H, ³² S ₂ H, ¹⁴ N ¹⁶ O ³⁵ Cl, ⁴⁸ Ca ¹⁶ OH
⁶⁶ Zn	³⁴ S ¹⁶ O ₂ , ³² S ³⁴ S, ³³ S ₂ , ⁴⁸ Ca ¹⁸ O
⁶⁷ Zn	³² S ³⁴ SH, ³³ S ₂ H, ⁴⁸ Ca ¹⁸ OH, ¹⁴ N ¹⁶ O ³⁷ Cl, ¹⁶ O ₂ ³⁵ Cl
⁶⁸ Zn	³² S ¹⁸ O ₂ , ³⁴ S ₂
⁶⁹ Ga	³² S ¹⁸ O ₂ H, ³⁴ S ₂ H, ¹⁶ O ₂ ³⁷ Cl
⁷⁰ Zn	³⁴ S ¹⁸ O ₂ , ³⁵ Cl ₂
⁷¹ Ga	³⁴ S ¹⁸ O ₂ H
⁷² Ge	⁴⁰ Ar ³² S, ³⁵ Cl ³⁷ Cl, ⁴⁰ Ar ¹⁶ O ₂
⁷³ Ge	⁴⁰ Ar ³³ S, ³⁵ Cl ³⁷ ClH, ⁴⁰ Ar ¹⁶ O ₂ H
⁷⁴ Ge	⁴⁰ Ar ³⁴ S, ³⁷ Cl ₂
⁷⁵ As	⁴⁰ Ar ³⁴ SH, ⁴⁰ Ar ³⁵ Cl, ⁴⁰ Ca ³⁵ Cl
⁷⁷ Se	⁴⁰ Ar ³⁷ Cl, ⁴⁰ Ca ³⁷ Cl
⁷⁸ Se	⁴⁰ Ar ³⁸ Ar
⁸⁰ Se	⁴⁰ Ar ₂ , ⁴⁰ Ca ₂ , ⁴⁰ Ar ⁴⁰ Ca

Comparison of Spectra

The background spectrum obtained in no-gas mode is shown in Figure 1a, together with the same spectrum (same mass range and intensity scale) under He collision mode conditions, in Figure 1b. From Figure 1a, it is clear that the normal background components of the argon plasma gas and aqueous sample solution (Ar, O, H), together with the additional components of the synthetic sample matrix (HNO₃, HCl, H₂SO₄, butanol, Ca and Na), lead to the formation of several high intensity background peaks in the no-gas mode spectrum, notably ⁴⁰Ar¹⁶O⁺ and ⁴⁰Ar₂⁺ from the plasma, but also ⁴⁰Ar¹²C⁺, ³²S₂⁺, ³⁵Cl¹⁶O⁺, etc, from the matrix. These high intensity background peaks show why several interfered elements (⁵⁶Fe, ⁷⁸Se and ⁸⁰Se, ⁵²Cr in a carbon matrix, ⁶⁴Zn in a sulfur matrix) have traditionally been considered as difficult elements for ICP-MS.

When helium is added to the cell (He collision mode conditions) all of these high intensity background peaks are removed from the spectrum, (Figure 1b – same sample, same intensity scale as Figure 1a) demonstrating the effectiveness and the universal applicability of He collision mode. Figures 2a and 2b are the same two spectra as in Figure 1, but with the vertical scale expanded 100x. Many more, lower intensity, matrix-derived polyatomic species are now observed. These interferences, though present at lower levels than the plasma-based polyatomic ions, have the potential to cause more serious errors in routine sample analysis, as their presence and intensity is dependent on matrix composition, which, in routine laboratories, may be variable and unknown. At this expanded scale, it is clear that the use of He collision mode has reduced the background

species to very low levels, including the high intensity plasma-based species ArO^+ and Ar_2^+ . The only peaks clearly visible in He collision mode (Figure 2b) on this scale are Fe and Zn (the peak template confirms the Zn isotopic pattern at m/z 64, 66, and 68), due to trace level contamination present in the matrix components. By contrast, in no-gas mode (Figure 2a), almost every isotope of every element in this mass region has an overlap from at least one matrix-derived polyatomic interference.




Figure 1. High intensity interfering polyatomic ions from complex matrix sample (see text for composition) in (a) no-gas mode and (b) He collision gas mode, on same intensity scale (2.0E7).




Figure 3. Complex matrix sample in He collision mode, (a) spiked at 5 ppb with V, Cr, Fe, Mn, Ni, Co, Cu, Zn, Ge, As, and Se and (b) unspiked. Intensity scale is 5.0E4 (5.0E3 for inset spectra).

Conclusions

The ability to remove ALL polyatomic interferences under a single set of conditions means that He mode is effectively universal – being suitable for any isotope of any element in any sample matrix. The use of He collision mode provides a unique new mode of operation, in which ALL the isotopes of each analyte become accessible. This, in turn, means that major isotopes that could not previously be used due to interferences (for example: ^{52}Cr in a carbon matrix, ^{56}Fe in any aqueous sample, ^{63}Cu in a sodium matrix, and ^{64}Zn in a sulfate matrix) - now become available. This is a great advantage to the analyst since, if desired, results can be verified by measuring many elements at both the preferred isotope AND at a second,

“qualifier” isotope. Since both isotopes are free from polyatomic interference when measured using He collision mode, the use of two independent measurements gives a valuable confirmation of the reported result.

A further benefit of this powerful mode of analysis concerns sample preparation. In normal (non-CRC) ICP-MS, the choice of dilution media was limited mostly to nitric acid. Hydrochloric and sulfuric acid could not be used because of the problems of chloride or sulfur-based matrix interferences. Analysts can now choose the most appropriate digestion technique for the sample, secure in the knowledge that any new polyatomic interferences will be removed under the existing, standard He mode conditions.

The use of He collision mode on the 7500ce was demonstrated to provide effective removal of all polyatomic interferences under a single set of conditions, thereby enabling accurate multi-element analysis in complex and unknown samples. The use of an inert cell gas insures that there is no loss of analyte signal by reaction and that no new interfering species are generated, in contrast to the use of a reactive cell gas.

Since no analytes are lost by reaction and no new interferences are formed, uninterfered elements (and internal standards) can be measured under the same conditions as potentially interfered elements, and the use of a single set of cell conditions for all analytes allows multi-element analysis of transient signals (such as those derived from chromatography or laser ablation sample introduction), as well as semiquantitative screening analysis.

He collision mode is suitable for all analytes that suffer from polyatomic ion interferences and the cell conditions do not need to be set up specifically for each analyte, so the same cell conditions can be applied to new analyte suites, without requiring method development. Furthermore, since the He mode conditions are not set up specifically for the removal of individual interferences, identical cell conditions can be used for highly variable or completely unknown sample matrices, which greatly simplifies operation in a routine laboratory. The ORS enables ICP-MS to be used for the trace multi-element measurement of the most complex, real world sample matrices with no method development and with complete confidence.

References

1. G. K. Koyanagi, V. I. Baranov, S. D. Tanner and D. K. Bohme, (2000), *J. Anal. Atom. Spectrom.*, **15**, 1207.
2. P. R. D. Mason, K. Kaspers and M. J. van Bergen, (1999), *J. Anal. Atom. Spectrom.*, **14**, 1067.
3. J. M. Marchante Gayon, I. Feldmann, C. Thomas and N. Jakubowski, (2000), *J. Anal. Atom. Spectrom.*, **16**, 457.
4. E. H. Larsen, J. Sloth, M. Hansen and S. Moesgaard, (2003), *J. Anal. Atom. Spectrom.*, **18**, 310.
5. H-T. Liu and S-J. Jiang, (2003), *Anal. Bioanal. Chem.*, **375**, 306.
6. D. R. Bandura, S. D. Tanner, V. I. Baranov, G. K. Koyanagi, V. V. Lavrov and D. K. Bohme, in *Plasma Source Mass Spectrometry: The New Millennium*, eds. G. Holland and S. D. Tanner, The Royal Society of Chemistry, Cambridge, 2001, p. 130.
7. C. C. Chery, K. DeCremer, R. Cornelis, F. Vanhaecke and L. Moens, (2003), *J. Anal. Atom. Spectrom.*, **18**, 1113.
8. F. Vanhaecke, L. Balcaen, I. Deconinck, I. De Schrijver, C. M. Almeida and L. Moens, (2003), *J. Anal. Atom. Spectrom.*, **18**, 1060.
9. N. Yamada, J. Takahashi and K. Sakata, (2002), *J. Anal. Atom. Spectrom.*, **17**, 1213.
10. E. McCurdy and G. Woods, (2004), *J. Anal. Atom. Spectrom.*, **19**, 607.
11. J. W. Olesik and D. R. Jones, (2006), *J. Anal. Atom. Spectrom.*, **21**, 141.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
March 23, 2006
5989-4905EN



Agilent Technologies



A Comparison of the Relative Cost and Productivity of Traditional Metals Analysis Techniques Versus ICP-MS in High Throughput Commercial Laboratories

Application

Author

Steve Wilbur
Agilent Technologies, Inc.
3380 146th Pl SE Suite 300
Bellevue, WA 98007 USA

Abstract

A financial model was developed to help the metals laboratory using graphite furnace atomic absorption and inductively coupled plasma optical emission spectroscopy calculate the potential savings by switching to inductively coupled plasma mass spectrometry. Results based on several typical laboratory examples are presented.

Introduction

The past 5 years have seen significant growth in the use of inductively coupled plasma mass spectrometry (ICP-MS) for the analysis of trace metals in many applications in the environmental, semiconductor, geological, and health sciences industries. This growth is driven by three factors. First is the need for increasingly lower limits of detection for many metals in many applications. Second is the significantly improved performance, reliability, and ease of use of modern ICP-MS instruments. And third is economics.

Traditionally, most elemental analysis has been performed by either atomic absorption (AA) or optical emission spectroscopy (OES). Generally, the ultratrace (sub-ppb) elements were measured by graphite furnace atomic absorption (GFAA), a highly sensitive single-element technique. The trace and minor (ppb to ppm) elements were measured

by inductively coupled plasma optical emission spectroscopy (ICP-OES), which is less sensitive but capable of simultaneous multi-element analysis.

As the need for sub-ppb detection limits extends to more elements in more samples, ICP-OES becomes less useful and the reliance on GFAA increases. However, GFAA, while sensitive, is slow, expensive to operate, and has limited dynamic range. Because GFAA is much slower than ICP-OES, many routine labs have a dedicated GFAA instrument for each analyte that is required to be measured by GFAA - multiple GFAAs working with one ICP-OES. Furthermore, the analysis of mercury will add the need for a third technique, either cold vapor AA or atomic fluorescence. However, in the interest of simplicity, a separate mercury analyzer was not considered in the examples used. Each of these techniques may require separate sample handling and preparation, as well as separate analysis, data processing and archival, significantly increasing the cost per sample.

The subject of this application note is to evaluate the productivity and cost effectiveness of ICP-MS as a routine, highly sensitive, multi-element technique where a single ICP-MS instrument has the potential to replace an ICP-OES, multiple GFAAs, and a mercury analyzer for most routine elemental analyses. The analytical applicability of ICP-MS to many types of samples is already well established. More recently, the introduction of the Octopole Reaction System on the 7500 Series ICP-MS instruments from Agilent has removed the final performance barriers that have prevented ICP-MS being proposed as a complete replacement for GFAA and ICP-OES.



Agilent Technologies

Methods

To facilitate this study, a spreadsheet-based sample cost comparison model was developed in Excel. This tool allows the user to provide detailed parameters related to numbers and types of samples, as well as associated costs of sample preparation, instrumentation, and analysis. Output is simply cost of analysis per sample. Also reported are the total time required for sample analysis per month, the number of analysts required, and the number of instruments. The model compares the results for GFAA, ICP-OES, and ICP-MS. While it will allow almost any values to be entered for most parameters, the results presented here are based on values obtained from several commercial laboratories doing these analyses. No model can exactly predict the results for all situations and still be simple enough to be useful. Therefore, in the interest of simplicity, a number of assumptions were made in the design of the model and in the example data entered. We feel that the assumptions are realistic and do not impart significant bias on the results. The tool is easy to use and can allow a laboratory to quickly and simply evaluate the cost effectiveness of the three techniques based on laboratory-specific information.

Assumptions

- GFAA system costs US\$30K
- ICP-OES system costs US\$100K
- ICP-MS system costs US\$180K
- Cost of funds (finance) is 6%
- General facilities costs, such as laboratory space, utilities etc., are ignored since they are difficult to estimate and do not significantly affect the results in most cases.

- An instrument operator can keep a modern, automated GFAA, ICP-OES, or ICP-MS running for two shifts (16 hours) per day. When analysis times exceed 16 hours per day for any technique, additional instrumentation and operators will be required. Instruments are added in increments of one; operators are added in fractions since it is assumed that they can be shared with other tasks in the laboratory and cost calculations are based only on the portion of time the operator spends on the specific analysis.
- GFAA is a single element technique. Instruments with multiple lamps still perform a single analysis at a time. Typical analysis time is 90 seconds per element and each element requires two replicate analyses (burns).
- ICP-OES and ICP-MS are multi-element techniques and the number of elements does not significantly effect the analysis time. This is not strictly true, but the assumption is reasonable for the sake of simplicity.
- GFAA will use pressurized argon and the consumption is 40 hours of use per cylinder (\$100).
- GFAA graphite tubes and platforms cost \$50 per set and last for 100 burns.
- ICP-MS and ICP-OES will use liquid argon and the typical consumption is 3 weeks of use per dewar (\$250).
- ICP-MS detectors last typically for 3 years and the cost per year is amortized based on 3-year lifetime.

Results

Several typical laboratory scenarios were evaluated by varying the current instrument complement of the laboratory, and by varying the current and anticipated number of samples to be analyzed per month. Also examined was the effect of the number of elements that must be analyzed by GFAA (in the case of laboratories without ICP-MS) to meet required DLs.

Scenario 1

Laboratory currently has one GFAA plus one ICP-OES, which are paid for. ICP-MS must be purchased and amortized over 3 years. See Table 1.

Table 1. Scenario 1

Samples/ month	GFAA elements	# GFAA required	Cost/sample GFAA + ICP-OES	# ICP-MS required	Cost/ sample ICP-MS	Savings/ month
400	8	1	\$41	1	\$30	\$4,536
1000	8	2	\$33	1	\$15	\$18,196
5000	8	9	\$31	2	\$9	\$112,968

Scenario 2

Laboratory currently has two GFAA plus one ICP-OES, which are paid for. ICP-MS must be purchased and amortized over 3 years. See Table 2.

Table 2. Scenario 2

Samples/ month	GFAA elements	# GFAA required	Cost/sample GFAA + ICP-OES	# ICP-MS required	Cost/ sample ICP-MS	Savings/ month
400	8	1	\$41	1	\$30	\$4,536
1000	8	2	\$32	1	\$15	\$17,283
5000	8	9	\$31	2	\$9	\$112,055

Scenario 3

Laboratory currently has no instrumentation and must decide on purchasing GFAA plus ICP-OES versus ICP-MS. See Table 3.

Table 3. Scenario 3

Samples/ month	GFAA elements	# GFAA required	Cost/sample GFAA + ICP-OES	# ICP-MS required	Cost/ sample ICP-MS	Savings/ month
400	8	1	\$51	1	\$30	\$8,491
1000	8	2	\$37	1	\$15	\$22,151
5000	8	9	\$32	2	\$9	\$116,923

Scenario 4

Comparison of costs per sample as a function of number of GFAA elements. (All instruments must be purchased.) See Table 4.

Table 4. Scenario 4

Samples/ month	GFAA elements	# GFAA required	Cost/sample GFAA + ICP-OES	# ICP-MS required	Cost/ sample ICP-MS	Savings/ month
1000	2	1	\$24	1	\$14	\$9,601
1000	4	1	\$28	1	\$14	\$12,751
1000	8	2	\$38	1	\$14	\$22,151
1000	10	3	\$42	1	\$14	\$27,490

Discussion

In all cases, even when the laboratory already owns two graphite furnaces and one ICP-OES (a common configuration) and must purchase the ICP-MS, the cost per sample is lower for ICP-MS. This is mainly due to the high cost of consumables for GFAA plus the fact that GFAA and ICP-OES requires two separate sample prep steps. Additionally, as the number of samples increases from a conservative number of 400 per month to 1000 and 5000 per month, the differential becomes much greater. This is caused by rapidly increasing labor costs for GFAA, as well as the much higher sample capacity of ICP-MS, lower consumables costs, and requirements for only a single sample prep.

Return on Investment for ICP-MS

A simple return on investment (ROI) can be calculated from the above tables. In this case, the cost per month of the new ICP-MS system is approximately US \$5500.00 (assuming purchase price of US\$180K financed for 3 years at 6%). Figure 1 shows the payback times for a laboratory that already owns two GFAAs and one ICP-OES as a function of the sample load. The y-axis represents the accumulated monthly savings of using ICP-MS versus GFAA + ICP-OES for three different sample loads compared to the unpaid balance on the ICP-MS instrument. As can be seen, the accumulated savings of ICP-MS is equal to the payoff amount after just 4 months when analyzing 2000 samples per month. Even when analyzing as few as 400 samples per month, the accumulated savings is sufficient to pay off the ICP-MS instrument in around 20 months. In this case, eight furnace elements are assumed. Other assumptions are as above.




Figure 1. Cumulative return on investment of ICP-MS purchase for three sample levels plotted against the monthly unpaid balance on the ICP-MS. In this case, it is assumed that the accumulated revenue will be used to pay off the loan when the balance equals the residual loan amount. At that point, the net monthly revenue is increased by the loan amount. In this example, laboratories running 2000 samples per month will be able to pay off the ICP-MS in about 4 months, 1000 sample laboratories in about 8 months, and 400 sample laboratories in about 20 months. At the end of 36 months (the original loan period), net revenue exceeds \$200K for the 400 sample lab, \$750K for the 1000 sample lab, and \$1.7 million for the 2000 sample lab.

Conclusions

For almost any metals laboratory, analyzing at least 100 samples per week (400 per month) and using a combination of GFAA and ICP-OES for the analysis, converting to ICP-MS will save money. Depending on the number of samples, the payback for the ICP-MS can be as short as a few months. The cost advantages are not reduced significantly, even if the laboratory already owns its GFAA and ICP-OES instruments. They are also not significantly affected by the number of GFAA elements. As Scenario 4 shows, for the laboratory analyzing at least 1000 samples per month with only two elements by GFAA, the cost savings of switching to ICP-MS is approximately \$10,000 per month. Add to this the increased confidence in results obtained by ICP-MS, the ability to analyze all analyte elements at GFAA (or better) DLs, and the robustness and simplicity of operation of modern ICP-MS instruments, and the choice becomes simple. The productivity of ICP-MS in a high-volume laboratory can quickly pay off the purchase price and increase laboratory profitability significantly.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2005

Printed in the USA
January 17, 2005
5989-1585EN



Agilent Technologies



Speciation of Organic Compounds, Using a Newly Developed, Experimental GC-ICP-MS Interface

Application Note

ICP-MS

Environmental

Michiko Yamanaka* and O.F.X. Donard**

* Agilent Technologies, Tokyo Analytical Division, Tokyo, Japan

** Laboratoire de Chimie Analytique Bioinorganique & Environment, University of Pau, Pau, France

Introduction

Tin has been an important metal for thousands of years, having been used in the formulation of alloys such as bronze, in mirrors and in the production of glass. More recently, organotin compounds have been used as industrial materials such as stabilizers in polymers. The trialkylated forms are efficient biocides and fungicides and their properties have been used in many applications. For example, triphenyltin (TPHT) has been used as a pesticide and tributyltin (TBT) was used extensively both as a wood preservative and as the active component in marine anti-fouling paints, applied to the hulls of sailing vessels. While organotin compounds degrade rapidly under photolytic conditions, some trialkyltin compounds are persistent once introduced in the environment (e.g. TBT). Despite of the fact that TBT has been banned from use on small boats for over a decade, it is still commonly used on the hulls of large ships, to prevent the growth of marine organisms. In 1989, TBT was banned in all states of the USA on vessels of 25 meters or less in length. Despite a general reduction in the use of organotin compounds, they can accumulate in sediments over many

years and can be ingested and absorbed by marine organisms, leading to accumulation in the marine

food chain and ultimately presenting a potential threat both to the environment and later to human consumption.

Recent studies provide strong evidence that many organotin compounds can act as endocrine disruptors, even at very low concentrations. Endocrine disruptors interfere with the action of many hormones, and can be very damaging to the development of animal embryos. As a consequence, there is an increasing demand for a new analytical method for these compounds, which is fast, sensitive and offers high chromatographic resolution.

Capillary Gas Chromatography (GC) offers fast and high-resolution speciation, and is well suited for organotin compounds. Measurement limits using currently available GC detectors (FPD, MS and AED) are good, but the need for determination of organotins at ever-lower levels of concentration has fuelled the investigation of alternative detection systems. Further the presence of sulfur compounds in many of the samples requires a highly selective and sensitive detector.

Inductively Coupled Plasma Mass Spectrometry (ICP-MS) offers ultra trace detection limits and high selectivity for most elements. The principles of ICP-MS are summarized in Figure 1. Samples are introduced into a high temperature argon plasma, where they are decomposed, atomized

and ionized. The resultant ions are transported, through a sampling interface, into a mass spectrometer for measurement. The high temperature in the ICP source means that all forms of an element are decomposed into individual atoms, so ICP-MS results represent total element levels. However, in combination with an on-line separation technique, such as Liquid Chromatography (LC), Ion Chromatography (IC) or Capillary Electrophoresis (CE), ICP-MS is increasingly being used as a sensitive and highly specific detector in a wide variety of speciation applications.

Combining the separation capabilities of a GC with the selectivity and sensitivity of ICP-MS could offer benefits in the measurement of ultra-trace levels of organically bound metals. In this paper, we describe some initial investigations into the coupling of GC to ICP-MS, for the analysis of organotin compounds.



Agilent Technologies
Innovating the HP Way




Figure 1. Schematic of an ICP-MS

The interface is not yet commercially available, but it shows some promise. We have used the GC-ICP-MS device to separate and quantify organotin compounds – monobutyltin (MBT), dibutyltin (DBT), tributyltin (TBT), monophenyltin (MPhT), diphenyltin (DPhT), and triphenyltin (TPhT) - in marine environmental samples of oyster tissue and sediment, collected from the same locality.

Instrumentation

The GC used in these studies was a model 5890, and the ICP-MS was a 4500, both from Agilent Technologies.

The general principal of combining GC with ICP-MS is simple. The end of the capillary GC column is fastened to the base of the ICP torch, so that separated species are carried directly into the plasma by a heated Ar flow.

Using a heated transfer line to connect the GC to the ICP-MS prevents material condensing within the interface and so enables the analysis of high boiling point compounds. Figure 2 is a schematic that describes the interface used during these experiments. Xenon was added to the argon make-up gas as a means of optimizing the ICP-MS operating conditions. The Xe:Ar gas mixture

was preheated by passing it through a stainless steel coil mounted within the GC oven.

Initial evaluations of the interface were undertaken at the laboratory of O.F.X. Donard at the University of Pau in France. Figure 3 is a chromatogram of a GC-ICP-MS separation of a 1µL injection of a standard, which contained a mixture of organotin species. Each peak in Figure 3 represents the equivalent of 5 pg tin.






Figure 2. Schematic of the GC-ICP-MS and Interface




Figure 3. GC-ICP-MS Chromatogram of a 1uL Injection of a 5ppb Organotin Mixed Standard

Table 1 GC-ICP-MS Acquisition Conditions

GC	
Injection mode	Splitless
Injection volume	1uL
Inlet temp	290° C
Column	Non-polar capillary – HP-1 (30m,0.32mm, 0.25um)
Carrier gas	He – 1.0mL/min
Oven program	70°C (1 min):ramp to 190°C (30°C/min): ramp to 270°C (15°C/min)
Interface temperature	250° C
ICP-MS	
RF power	1300W
Sampling depth	8mm
Carrier gas flow	0.8L/min
Oxygen gas flow	0.02L/min (added to auxiliary gas)

Ethylation using sodium tetraethylborate (NaBEt_4) was chosen as the derivatization method for this work. The reaction between the organotin compound and the NaBEt_4 is in aqueous conditions, which makes it much more suitable for environmental and biological samples than a normal Grignard reagent.


As the chromatogram illustrates, the peak shapes obtained are excellent, suggesting little or no broadening caused by the interface.

Initial results

Preliminary studies on organotin content of oysters and sediments were done in collaboration with the University of Pau . We have taken here samples from the Bay of Arcachon since it is one of the most productive areas for oyster farming. Despite of the fact that organotin concentrations have declined in the water and the sediment of the bay, organotin compounds can be found in oysters, due to bioaccumulation. In general there is an increasing concern

about the occurrence of organotin in shellfish worldwide, particularly as many species are used for human consumption. Samples of oysters and sediment were collected and analysed using the GC with ICP-MS detection.

Some care had to be exercised in the preparation of the oyster tissue, to prevent any potential decomposition of the analyte. The sample preparation method is summarized in Figure 4. Tripropyl tin (TPrT) was added to each sample as an internal standard.

**Figure 4. Sample Preparation Steps for the Oyster Tissue**





Figure 5. Sample Preparation Steps for the Sediment

A similar procedure was used for the preparation of sediment samples (Figure 5), except that acetic acid was used instead of Tetramethyl ammonium hydroxide (TMAH).

Figure 6 is a typical GC-ICP-MS chromatogram from one of the oyster extracts, illustrating excellent separation and peak shape. As the data show, there are substantial and measurable amounts of a variety of organotin compounds in the sample.



upper 118m/z, lower 120m/z
obtained simultaneously note different vertical scale

1 Sn (inorganic), 2 MBT(0.2pg), 3 TPrT (IS, 2.5pg),
4 DBT(1.8pg), 5 TBT(4.0pg), 6 TPhT(0.3pg)
other peaks are not identified

Figure 6. GC-ICP-MS Chromatogram from the Analysis of One of the Oyster Tissue Samples

Table 2. Results Summary from the Analysis of Oyster Samples across Arachon Bay, Plus Analysis of a Sediment Sample

Area	water(%)	concentration / ng/g (Dry)					
		MBT	DBT	TBT	MPhT	DPhT	TPhT
Area1	85	8.3	13	28	0.3	N.D.	N.D.
Area2	81	0.8	9.5	21	N.D.	N.D.	1.6
Area3	85	3.7	15	46	1.3	N.D.	N.D.
Area4	81	1.1	12	42	N.D.	N.D.	N.D.
Area5	86	0.7	11	51	N.D.	N.D.	2.1
Area6	83	1.8	13	39	N.D.	N.D.	N.D.
Area7	81	0.5	5.3	16	N.D.	N.D.	1.6
Area8	82	1.7	18	54	N.D.	N.D.	N.D.
Area9	83	2.4	20	141	N.D.	N.D.	N.D.
sediment	36	6.0	5	7	3.0	N.D.	2.0

Table 2 summarizes data from oysters sampled in and around Arachon Bay, as well as a sediment sample. Tributyltin (TBT) is the single largest component in each case, although there are several other species present at significant levels. Monobutyltin (MBT) and Dibutyltin (DBT) are breakdown products of TBT. Although the use of TBT in marine antifouling paints has been discontinued in France, the organotin compound still exists in the sediment where the oysters develop. Of particular interest is Area 9, which is a part of the Bay where oyster production has been poor. This also coincides with the largest level of TBT.

The exceptional resolution of the chromatographic separation allows an anticipation of the formation of metabolite products from organotin compounds (e.g. methylation of butyltin compounds) opening the way to new understanding of environmental and biometabolic pathways for these contaminants after further identification.

Summary

These preliminary results suggest that GC-ICP-MS offers a highly sensitive and selective method for the determination of organometallic compounds in environmental matrices. The exceptional chromatographic separation capability of the CGC,


coupled to the sensitivity, selectivity and multielemental capability of the ICP-MS detector, certainly makes this combination a very promising tool for environmental studies. The interface used in these studies is not yet commercially available and will require some further refinement and characterization. The robustness of the heating system will require some refinement to ensure long-term reliability. Future applications work is under way evaluating the potential of this interface for the simultaneous determination of other organometals such as tin, lead and mercury compounds.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2003
 Agilent Technologies, Inc.
 Printed in Japan (07/03)
 5980-0336E



Improving the Analysis of Organotin Compounds Using Retention Time Locked Methods and Retention Time Databases

Application

Environmental

Authors

Frank David
Research Institute for Chromatography
Pres. Kennedypark 20, B-8500
Kortrijk, Belgium

Pat Sandra
University of Gent
Krijgslaan 281 S4, B-9000
Gent, Belgium

Philip L. Wylie
Agilent Technologies
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The analysis of organotin compounds is becoming increasingly important in both environmental analysis and in food and consumer product analysis. This application note describes a retention time locked (RTL) gas chromatography/mass spectrometry (GC/MS) method for the analysis of derivatized organotin compounds. Three retention time locked libraries are made available, corresponding to three different derivatization methods. The retention time databases allow easy peak location and identification of the target solutes based on mass spectra and retention times.

Introduction

For many years, organometal speciation has been an important topic in environmental analysis, primarily due to increasing awareness of the toxicological effects of many organometal compounds. Within the class of organometalics, organotin compounds are probably the most widely spread in the environment due to their use as additives in polymers and in antifouling paints. Organotin compounds degrade in the environment into more polar metabolites [1]. Tributyltin, one of the most frequently used organotin additives (as tributyltin chloride or tributyltin oxide), for instance, degrades into dibutyltin and monobutyltin species. Consequently, a large diversity of organotin compounds can be detected in various environmental samples [2]. More recently, organotin contamination of diapers and printed T-shirts was reported and numerous analyses were performed on different consumer products, including all types of absorbent hygiene products.

Different methods were used for the extraction and analysis of organotin compounds in environmental, food, and consumer product matrices. Since the organotin compounds with less than four alkyl groups are very polar, they cannot be analyzed directly by GC and must be derivatized into tetraalkyltin compounds prior to analysis. Initially, most methods were based on extraction with



Agilent Technologies

tropolone (a complexing agent) and n-hexane, followed by Grignard derivatization and determination with GC-flame photometric detection (FPD) [3–9]. Recently, in-situ ethylation with sodium tetraethylborate (NaBEt_4) [10–13] has largely replaced Grignard derivatization. At the same time, mass selective detectors (MSD) and atomic emission detectors (AED) have replaced the FPD as the preferred GC detector for organotin compounds [11,13].

A few years ago, solid phase micro extraction (SPME) in combination with capillary gas chromatography-inductively coupled plasma mass spectrometry (CGC-ICP-MS) was used for the determination of volatile and semi-volatile organometal compounds, resulting in excellent sensitivity and selectivity [14,15]. SPME was performed in the headspace or directly in the aqueous sample using a 100 mm polydimethylsiloxane (PDMS) coated fiber. Using NaBEt_4 , organotin compounds could be derivatized in-situ and simultaneously extracted into the PDMS phase.

More recently, stir bar sorptive extraction (SBSE) using a magnetic stir bar coated with a 0.5–1 mm PDMS layer was developed [16]. After extraction, the solutes were thermally desorbed online to GC/MS, GC-AED or GC-ICP-MS. SBSE in combination with CGC-ICP-MS was applied for the determination of organotins in environmental samples after in-situ derivatization with NaBEt_4 , resulting in unsurpassed sensitivity with detection limits reaching the ppq (pg/L) level [17].

For standard applications such as the determination of organotin compounds in sediments, or soils, and in extracts or leachates of consumer products, these extremely high sensitivities are not required. For these applications, sufficient sensitivity is obtained using mass spectrometric detection. In comparison to AED or ICP-MS, where specific tin-chromatograms are obtained, the chromatograms obtained by mass spectroscopy are far more complex, even when using the selected ion monitoring (SIM) mode. Several ions per solute need to be monitored, and the derivatized sample extracts often contain many co-extracted solutes

or by-products of the derivatization reaction. Therefore, data interpretation is more demanding requiring the use of extracted ion chromatograms, retention time matching, and calculation of the relative abundances of target and qualifier ions. In this respect, the use of retention time locked methods offers several advantages. If a selected ion method is used, the switching times between groups of monitored ions are fixed and do not need to be adjusted after column maintenance or column change, since the retention times of all solutes can be relocked. Moreover, quantification databases do not need to be updated for variations in retention times. Finally, a retention time locked database can be used, allowing easy peak allocation. Solute detection and confirmation are far more reliable using the results screener option [18,19], which combines the power of spectral matching with locked retention time matching.

In this application note, a GC/MS method is described for the analysis of organotin compounds in environmental, food, or consumer product extracts. Since derivatization by Grignard reaction and derivatization using NaBEt_4 are both easy and convenient, three types of derivatives are considered: methyl-derivatives using methylmagnesium bromide, pentyl- derivatives using pentylmagnesium bromide (both Grignard reagents), and ethyl-derivatives using NaBEt_4 . The most important organotin compounds are listed in Table 1 together with typical ions for the mass spectra of all three derivatives. Tin has several isotopes and the mass spectra are characterized by typical isotope clusters. The relative abundances of the tin isotopes are Sn-116 (14.24%), Sn-117 (7.57%), Sn-118 (24.01%), Sn-119 (8.59%), Sn-120 (32.97%), Sn-122 (4.71%), and Sn-124 (5.98%). For the organotin compounds listed in Table 1, mass spectral libraries and retention-time-locked screener libraries were created for all three types of derivatives. After selecting the appropriate derivitization method, a library and screener database can be selected, allowing fast data interpretation. Sample extraction and clean-up are beyond the scope of this application note.

Experimental

Samples

The organotin compounds listed in Table 1 were purchased from Dr Ehrenstorfer, Augsburg, Germany (<http://www.analytical-standards.com>). For analysis, the standards were dissolved in methanol at a 1000 ppm (1mg/mL) concentration. These solutions were further diluted, depending on the derivatization method used. For creation of the databases, approximately 10 µg of compound was derivatized, resulting in a final concentration of 10 ppm.

Derivatization method 1: The sample extract is concentrated to 1 mL in an apolar solvent (typically hexane) in a reaction tube. To this solution, 0.5 mL methylmagnesiumbromide Grignard reagent (1.4 M in 75/25 toluene/THF, Sigma-Aldrich cat no 28,223-5) is added. The solution is vortexed for 10 s and allowed to stand at room temperature for 15 min. This procedure should be performed in a fume hood, since toxic vapors evolving from the reaction and the solvents are

flammable. The reaction is stopped and the excess reagent is removed by adding 2 mL of a saturated ammoniumchloride solution in water or 2 mL 0.25 mol/L aqueous sulphuric acid. The mixture is vortexed for 10 s and the two phases are allowed to separate. The clear upper layer (apolar hexane phase) is transferred to an autosampler vial for analysis. The resulting organotin compounds are the methyl-derivatives.

Derivatization method 2: The sample extract is concentrated to 1 mL in an apolar solvent (typically hexane) in a reaction tube. To this solution, 0.5 mL pentylmagnesiumbromide Grignard reagent (2 M in diethylether, Sigma-Aldrich cat no 29,099-8) is added. The remaining steps in this procedure are identical to those used in derivitization method 1. The resulting organotin compounds are the pentyl-derivatives.

Derivatization method 3: The sample extract is concentrated to 1 mL in a polar solvent (typically ethanol) in a reaction tube. To this solution, 1 mL acetate buffer (82 g/L sodium acetate in water, adjusted to pH 4.5 with acetic acid) and 50 µL

Table 1: Organotin Compounds and Characteristic Ions for the Three Derivatization Products

Organotin solute Reagent	Abbreviation	Derivatization 1 Methyl- magnesium bromide Methyl-	Derivatization 2 Pentyl- magnesium bromide Pentyl-	Derivatization 1 Sodium tetraethylborate Ethyl-
Derivatives				
Triethyltin	TET	193, 191, 165, 163	179, 177, 249, 247	207, 205, 179, 177
Tetraethyltin	TeET	207, 205, 179, 177	207, 205, 179, 177	207, 205, 179, 177
Tripropyltin	TPT	179, 177, 221, 219	277, 275, 165, 163	235, 2331, 249, 247
Tetrapropyltin	TePT	249, 247, 207, 205	249, 247, 207, 205	249, 247, 207, 205
Monobutyltin	MBT	165, 163, 151, 149	319, 317, 193, 191	235, 233, 179, 177
Dibutyltin	DBT	151, 149, 207, 205	319, 317, 179, 177	263, 261, 207, 205
Tributyltin	TBT	193, 191, 249, 247	305, 303, 179, 177	291, 289, 207, 205
Tetrabutyltin	TeBT	291, 289, 179, 177	291, 289, 179, 177	291, 289, 179, 177
Monophenyltin	MPhT	227, 225, 223, 197	339, 337, 197, 195	255, 253, 197, 195
Diphenyltin	DPhT	289, 287, 285, 197	345, 343, 197, 195	303, 301, 197, 195
Triphenyltin	TPhT	351, 349, 347, 197	351, 349, 347, 197	351, 349, 347, 197
Tetraphenyltin	TePhT	351, 349, 347, 197	351, 349, 347, 197	351, 349, 347, 197
Tricyclohexyltin (Cyhexatin)	TCT	301, 299, 219, 217	357, 355, 205, 203	315, 313, 233, 231
Monooctyltin	MOT	165, 163, 263, 261	375, 373, 193, 191	291, 289, 179, 177
Diocetyl tin	DOT	263, 261, 151, 149	417, 415, 375, 373	375, 373, 263, 261

derivatization reagent are added. The derivatization reagent is prepared by dissolving 2 g NaBEt₄ (Sigma-Aldrich cat no 48,148-3) in 10 mL ethanol. This solution should be freshly prepared. The sample is shaken and allowed to react for 30 min. After addition of 5 mL water, the derivatized compounds are extracted in 1 mL hexane. The mixture is vortexed for 10 s and the two phases are allowed to separate. The clear upper layer (apolar hexane phase) is transferred to an autosampler vial for analysis. The resulting organotin compounds are the ethyl-derivatives.

These derivatization methods can be adapted to the type of sample analyzed. For example, derivatization method 3 is often applied to aqueous samples directly, combining *in-situ* derivatization and simultaneous extraction. This method is also used for sediment samples. Typically 1 g sample (dry weight) is extracted with 10 mL acetate buffer, 7 mL methanol and 10 mL hexane. Four mL of a 5% NaBEt₄ solution is added while stirring. The derivatized organotin compounds are simultaneously extracted into the hexane layer.

Analytical Conditions

All analyses were performed on an Agilent 6890-5973N GC-MSD system. Automated splitless injection was performed using an Agilent 7683 automatic liquid sampler. The instrumental configuration and analytical conditions are summarized in Table 2. The retention time of tetrabutyltin (used as the locking standard) was locked at 16.000 min. To duplicate this method, the initial column head pressure can be set to the pressures indicated in Table 2 (nominal pressure). Then the retention time locking (RTL) calibration runs can be performed automatically (at -20%, -10%, +10% and +20% of the nominal pressure) [18]. The retention time versus head pressure curve is then calculated and stored in the method. Agilent's RTL software uses this curve to set the column head pressure so that retention time of the locking standard (tetrabutyltin) is 16.000 min.

Table 2. Instrumentation and Conditions of Analysis

Instrumentation	
Chromatographic system	Agilent 6890 GC
Inlet	Split/Splitless
Detector	Agilent 5973 N MSD
Automatic sampler	Agilent 7683
Liner	Splitless liner (part number 5062-3587)
Column	30 m × 0.25 mm id × 0.25 µm HP-5MS (Agilent part number 19091S-433)
Experimental conditions	
Inlet temperature	280 °C
Injection volume	1 µL
Injection mode	Splitless, purge time: 1 min, purge flow: 50 mL/min.
Carrier gas	Helium
Head pressure	Tetrabutyltin is retention time locked at 16.000 min (pressure around 45 kPa at 50 °C, 34 cm/s at 50 °C)
Oven temperature	50 °C, 1 min, 10 °C/min to 300 °C, 4 min.
Transfer line temperature	300 °C
Detector	Scan (40–550 amu), threshold 100, MS quad 150 °C, MS source 230 °C. Solvent delay: 4 min SIM mode: 50 ms dwell time per ion, ions listed in Table 3

Results and Discussion

A typical chromatogram, for an organotin standard mixture, derivatized using method 3 (ethyl-derivatives with NaBEt_4), is shown in Figure 1. The compounds elute according to their boiling point, and the elution sequence can be predicted by calculating the total number of carbon atoms after

derivatization. With this derivatization, the elution sequence of the butyltin compounds is MBT (10 C atoms) < DBT (12 C atoms) < TBT (14 C atoms) < TeBT (16 C atoms). The spectrum obtained for tributyltin (as tributylethyltin) is shown in Figure 2. The typical ion clusters, resulting from the different tin isotopes, are clearly detected.




Figure 1. GC/MS chromatogram for the analysis of an organotin standard mixture after derivatization with NaBEt_4 (ethyl-derivatives).




Figure 2. Mass spectrum of tributyltin after derivatization with NaBEt_4 (ethyl-derivative).

The analysis of a coastal sediment sample is shown in Figure 3. In this case, derivatization method 2 (Grignard reaction with pentylmagnesium bromide) was applied and a complex chromatogram was obtained. Using the extracted ion chromatogram at m/e 179 the butyltin compounds were easily detected (Figure 4). Tetrabutyltin, eluting at 16.000 min, was added as internal standard. In this case, pentyl- derivatives are analyzed. Therefore the elution order is reversed since the derivatization adds a C5-group for every free valency. The elution sequence is now TeBT (16 C atoms = unchanged) < TBT (17 C atoms) < DBT (18 C atoms) < MBT (19 C atoms). The mass spectrum obtained for the pentyl derivative of tributyltin is shown in Figure 5.




Figure 3. GC/MS chromatogram for the analysis of a coastal sediment sample after derivatization with pentylmagnesium bromide (pentyl-derivatives).




Figure 4. Extracted ion chromatogram showing the presence of butyltin compounds in the coastal sediment sample extract (shown in Figure 3) after derivatization with pentylmagnesium bromide (pentyl-derivatives).




Figure 5. Mass spectrum of tributyltin after derivatization with pentylmagnesium bromide (pentyl-derivative).

Using the Agilent results screener and the appropriate screener library, the files can be screened for the presence of all compounds listed in the screener database. Figure 6 shows a typical result, with the identification of pentyltricyclohexyltin at 24.908 min. The target ions for this compound are extracted and overlaid in the top window. For easy comparison, the apex mass spectrum is displayed. Though not shown in Figure 6, the Agilent RTL Screener Software can display the library and apex spectra together for easy spectral comparison. In addition, the relative abundances of the

target ion and qualifiers are measured and compared to the library data. What distinguishes the Agilent screener methods from conventional GC/MS techniques is the comparison of a peak's locked retention time to values stored with the RTL database. In this case, the locked retention time of pentyltributyltin is within 0.002 min (0.12 s) of the database value. The Agilent results screener compares locked retention times and spectral information for fast peak allocation and more reliable identification.




Figure 6. Screener result for the detection of tricyclohexyl tin in a sample extract after derivatization with pentylmagnesium bromide (pentyl-derivative).

For added specificity and sensitivity, SIM methods were developed for all three alkyl derivatives of the target tin compounds. Table 3 lists the SIM ions and target compounds in each group. Note that the start time for each SIM group is also listed. Normally, this timing could not be published with confidence, because of retention time differences

between instruments. However, RTL allows analysts to duplicate locked methods directly and reproduce all analyte retention times within a few thousandths of a minute. Thus, it is possible to apply this method directly, including the SIM group timing, after locking tetrabutyltin to the method-specified retention time of 16.000 minutes.

Table 3. SIM Groups and Timing for Methyl, Pentyl, and Ethyl Derivatives of the Target Tin Compounds Listed in Table 1. The GC/MS Method Shown in Table 2 was used with the Retention Time of Tetrabutyltin Locked to 16.000 Minutes.

	Start time (min)	Solutes	Ions
Derivatization 1			
1	5.00	TET, MBT	193, 191, 165, 163, 151, 149
2	6.50	TeET	207, 205, 179, 177
3	8.00	MPhT, DBT, TPT	227, 225, 223, 151, 149, 207, 205, 179, 177, 221, 219
4	10.50	MOT, TePT	165, 163, 263, 261, 249, 247, 207, 205
5	12.50	TBT, TeBT	193, 191, 249, 247, 291, 289, 179, 177
6	16.40	DPhT, DOT	289, 287, 285, 197, 263, 261, 151, 149
7	21.00	TCT, TPhT	301, 299, 219, 217, 351, 349, 347, 197
8	25.00	TePhT	351, 349, 347, 197
Derivatization 2			
1	5.00	TeET	207, 205, 179, 177
2	9.00	TET, TePT	179, 177, 249, 247, 207, 205
3	13.50	TPT, TeBT	277, 275, 165, 163, 291, 289, 179, 177
4	16.50	TBT, DBT, MBT	305, 303, 179, 177, 319, 317, 193, 191
5	20.00	MPhT, MOT, DPhT	339, 337, 197, 195, 375, 373, 193, 191
6	22.80	DPhT, TCT	345, 343, 275, 273, 357, 355, 205, 203
7	24.00	DOT, TPhT	417, 415, 375, 373, 351, 349, 347, 197
8	26.00	TePhT	351, 349, 347, 197
Derivatization 3			
1	5.00	TeET (=TET)	207, 205, 179, 177
2	8.50	MBT, TPT	235, 233, 179, 177, 249, 247
3	11.40	TePT, DBT	249, 247, 207, 205, 263, 261, 207, 205
4	13.00	MPhT, TBT	255, 253, 197, 195, 291, 289
5	14.80	MOT, TeBT	291, 289, 179, 177, 291, 289
6	17.00	DPhT, DOT	303, 301, 197, 195, 375, 373, 263, 261
7	22.00	TPhT, TCT	351, 349, 347, 197, 315, 313, 233, 231
8	25.00	TePhT	351, 349, 347, 197

Conclusion

A GC/MS method is presented for the analysis of organotin compounds in extracts of environmental, food, or consumer product samples. Three different derivatization methods are described. For each derivatization method, mass spectral and retention time-locked screener databases were created. By itself, RTL is a valuable tool for maintaining GC and GC/MS methods and for comparing results among different laboratories. It also allows analysts to duplicate methods exactly, including SIM group timing and peak timing in quantitative methods.

When combining RTL with locked mass spectral database searching, peak identifications become far more convenient and reliable. While many compounds can have similar spectra, they usually do not have similar spectra and identical retention times. Agilent's ability to reproduce retention times for a given method on any 6890 GC makes it possible to differentiate closely-related compounds and to screen for large numbers of analytes in a matter of seconds. This rapid GC/MS screening technique is now available for a wide variety of important tin compounds.

The three organotin databases are available for free from the Life Sciences and Chemical Analysis portion of the Agilent web site (www.agilent.com).

References

1. P. J. Graig, (1986) *Organometallics in the environment; Principles and Reactions*, 133.
2. Harino H., M. Fukushima, Y. Yamamoto, S. Kawai, N. Miyazaki, (1998) *Archives of Toxicology*, **35**, 558.
3. A. M. Caricchia, S. Chiavarini, C. Creminini, R. Morabito, and R. Scerbo, (1994) *Anal. Chim. Acta*, **286**, 329.
4. K. Fent and J. Hunn, (1991) *J. Environ. Sci. Technol.*, **25**, 956.
5. J. L. Gomez-Ariza, E. Morales, and M. Ruiz-Benitez, (1992) *Analyst*, **117**, 641.
6. H. Harino, M. Fukushima, and M. Tanaka, (1992) *Anal. Chim. Acta*, **264**, 91.
7. M. D. Müller, (1987) *Anal. Chem.*, **59**, 617.

8. M. Nagase and K. Hasabe, (1993) *Anal. Sci.*, **9**, 517.
9. H. H. Van de Broek, G. B. M. Hermes, and C. E. Goewie, (1988) *Analyst*, **113**, 1237.
10. N. Følsvik and E. M. Brevik, (1999) *J. High Resolut. Chromatogr.*, **22**, 177.
11. M. Ceulemans, C. Witte, R. Lobinski, and F. C. Adams, (1994) *Appl. Organomet. Chem.*, **8**, 451.
12. Y. Morcillo and C. Porte, (1998) *Trends Anal. Chem.*, **17**, 109.
13. J. S. Lobinska, M. Ceulemans, R. Lobinski, and F. C. Adams, (1993) *Anal. Chim. Acta*, **278**, 99.
14. L. Moens, T. De Smaele, R. Dams, P. van den Broek, and P. Sandra, (1997) *Anal. Chem.*, **69**, 1604.
15. J. Vercauteren, A. De Meester, T. De Smaele, F. Vanhaecke, L. Moens, R. Dams, and P. Sandra, (2000) *J. Anal. At. Spectrom.*, **15**, 651.
16. E. Baltussen, P. Sandra, F. David, and C. Cramers, (1999) *J. Microcolumn Sep.*, **11**, 737.
17. J. Vercauteren, C. Pérèz, C. Devos, P. Sandra, F. Vanhaecke and L. Moens, (2001) *Anal. Chem.*, **73**, 1509.
18. V. Giarrocco, B. Quimby and M. Klee, Retention Time Locking: Concepts and Applications, Agilent Technologies, publication 5966-2469E www.agilent.com/chem
19. K.R. Weiner and H.F. Prest, Retention Time Locking: Creating Custom Retention Time Locked Screener Libraries, Agilent Technologies, publication 5968-8657E www.agilent.com/chem

For More Information

For more information on our products and services, visit our web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2003

Printed in the USA
April 21, 2003
5988-9256EN



Agilent Technologies



Meeting Worldwide Regulatory Requirements for the Analysis of Trace Metals in Drinking Water Using the Agilent 7500c ICP-MS

Application

Environmental

Authors

Steven Wilbur, Emmett Soffey
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The Agilent 7500c ICP-MS can be used to meet the regulatory requirements for trace metals in drinking water around the world. Elements previously relegated to other techniques, such as GFAA or ICP-OES due to very high or low concentrations or the presence of interferences, can now be measured in a single analysis.

Introduction

Virtually all developed countries have adopted programs and regulations to monitor and maintain the quality of public water systems. In the US, water quality is regulated by the United States Environmental Protection Agency (USEPA) as mandated by the *Safe Drinking Water Act of 1974*. In the European Union, drinking water is regulated by the *Council Directive 98/83/EC of 3, November, 1998 on the Quality of Water Intended for Human Consumption*. In Japan, quality of drinking water is regulated by the *Japan Water Supply Act*, dating from 1957, and most recently updated in 2001. Most of the rest of the world's developed countries have adopted drinking water quality standards based on World Health Organization (WHO) Standards, *Guidelines for Drinking Water Quality*, 1996, 1998, or on the USEPA standards. While

these guidelines, as they pertain to trace metals, vary somewhat in their lists of regulated metals and concentrations, they are fundamentally similar. They all require accurate, precise measurement of multiple toxic metals in drinking waters at the lowest practical limits of quantification. This application note will demonstrate that the sensitivity, accuracy, and precision requirements for the analysis of trace metals in drinking water worldwide can be met by a single, robust technique using the Agilent 7500c ICP-MS system with Octopole Reaction System (ORS) technology.

US Regulations

In the US, the quality of public drinking water is safeguarded by the provisions of the Safe Drinking Water Act of 1974.

The Safe Drinking Water Act (SDWA) was originally passed by Congress to protect public health by regulating the nation's public drinking water supply. The law, amended in 1986 and 1996, requires many actions to protect drinking water and its sources in rivers, lakes, reservoirs, springs, and ground water wells (SDWA does not regulate private wells, which serve fewer than 25 individuals). SDWA authorizes the USEPA to set primary national health-based standards for drinking water to protect against both naturally-occurring and man-made contaminants that may be found in drinking water. These primary national drinking water standards include maximum contaminant level goals (MCLGs), levels below which there is no known or expected health risk. From these MCLG values, EPA determines maximum contaminant levels (MCLs), which are



Agilent Technologies

enforceable levels that may not be exceeded. The MCLs are set as closely as possible to the MCLGs and are based on best available current technology and economic feasibility. These limits are reviewed and updated periodically as new information becomes available and technology improves.

Japanese Regulations

Drinking water quality in Japan is regulated by the Japan Water Supply Act, which was first promulgated in 1957 with the Quality Standard for Drinking Water set the following year. This standard currently regulates the drinking water quality of more than 97% of the population. The Quality Standard sets maximum allowable concentrations (MAC) for 17 metals. It also requires that quantification limits be set at 1/10 of the MAC to assure accurate measurements at trace levels. Because of this, in 2001 the Drinking Water Test Method was revised and expanded to include the use of ICP-MS for 14 of the 17 metals. The approval of the use of ICP-MS has eliminated the need for costly and time

consuming preconcentration, which was required to meet the required detection limits using ICP-OES.

European Union Regulations

Currently, water quality in the European Union (EU) is regulated by Council Directive 80/778/EEC. This directive applies to all waters intended for human consumption, except natural mineral waters or waters which are medicinal products. As of December 2003, Directive 80/778/EEC will be repealed and replaced by Council Directive 98/83/EC *Directive on the Quality of Water Intended for Human Consumption*, which came into force on December 25, 1998. The standards are based largely on recommendations by the WHO¹. Member states of the European Community, while they must comply fully, are permitted to implement regulation and enforcement locally. As a result, no single regulation exists for the analysis of trace metals in water throughout Europe.

¹World Health Organization Guidelines and International Standards for Drinking-Water Quality, 1998

Table 1. Drinking Water Standards for Trace Metal Content from WHO Recommendations, EU Regulations, Japan Drinking Water Regulations and USEPA.

Analyte	WHO Standard (mg/L)	EC Directive 98/83/EC (mg/L)	Japan Drinking Water Standard (mg/L)	USEPA Primary MCL (mg/L)	Agilent 7500c MDLs*** (mg/L)
Aluminum (Al)		0.2	0.2	0.02-0.2*	0.000054
Antimony (Sb)	0.005**	.005	0.002	0.006	0.000035
Arsenic (As)	0.01**	.01	0.01	0.01	0.000052
Barium (Ba)	0.7			2	0.000027
Beryllium (Be)				0.004	0.000028
Boron (B)	0.5**	1	1.0		
Cadmium (Cd)	0.003	0.005	0.01	0.005	0.000025
Chromium (Cr)	0.05**	0.05		0.1	0.000019
Copper (Cu)	2**	2	1.0	1.3	0.000023
Iron (Fe)		0.2	0.3	0.3*	0.00125
Lead (Pb)	0.01	.01	0.05	0.015	0.000017
Manganese (Mn)	0.5**	.05	0.05	0.05*	0.000020
Mercury (Hg)	0.001	0.001	0.0005	0.002	0.000005
Molybdenum(Mo)	0.07				0.000030
Nickel (Ni)	0.02**	0.02	0.01		0.000024
Selenium (Se)	0.01	0.01	0.01	0.05	0.000047
Silver (Ag)				0.01*	0.000027
Sodium (Na)		200	200		0.0276
Thallium (Tl)				0.002	0.000021
Uranium (U)	0.002**		0.002	0.030	0.000015
Zinc (Zn)				5.0*	0.000101

*Secondary Standard, **Provisional Guideline Value, ***MDLs Calculated as Three Sigma of 10 Replicates of Low Standard, as Described in this Work. MDLs Reported in mg/L to Match Regulatory Requirements.

Table 1 includes the trace metals that are regulated by various worldwide regulatory and advisory agencies. ICP-MS is the only analytical technique capable of meeting all the required detection limits for all the regulated trace metals. Therefore, while not mandated as the only acceptable technique for most regulations, ICP-MS is becoming the instrument of choice for trace metals analysis in water worldwide.

While the details of QA/QC criteria and reporting requirements vary significantly from jurisdiction to jurisdiction, Table 1 shows that the actual detection limit requirements are very similar. In addition, the fundamental goals of the QA/QC requirements in all jurisdictions are the same. This is to insure that the reported values for all samples meet commonly accepted guidelines for accuracy and precision. Typically, these guidelines are met through the analysis of periodic QC samples inserted into the sample queue. Such QC samples should include: a check on the accuracy of the initial instrument calibration; a control sample of known concentration similar to that of the analytes in a similar matrix; a sample designed to test the ability of the system to eliminate interferences as false positives; a sample designed to detect sample carryover or memory problems; and periodic calibration check samples to check for instrument drift. If samples are to be analyzed outside the calibration range of the analytical method, then a linear range check sample must also be analyzed. It is outside the scope of this application note to detail the specific QA/QC requirements for each regulation where they exist at all. Instead, a general QA/QC protocol will be outlined which will demonstrate the ability of the Agilent 7500c to meet generally accepted guidelines while easily meeting the required reporting limits for drinking water monitoring worldwide. Simple modifications to this procedure can be implemented to insure strict compliance with detailed local requirements.

Advantages to the Use of the ORS for Drinking Water Analysis

Generally, drinking water is not considered a particularly difficult matrix for analysis by ICP-MS. There are, however, a few significant challenges.

These challenges are due to the very low desired reporting limits for several elements (Table 1), as well as the possibly high concentrations for others, such as Ca and Na. This combination of very low and very high analyte concentrations presents a challenge that no other analytical technique can overcome. In order to measure all elements simultaneously, the ICP-MS must be able to accurately measure mercury at 0.05 ppb or less and Na or Ca as high as 1000s of ppm. In addition, the ICP-MS must be able to eliminate common interferences on Fe, As, Se, Cu, V, and other elements which originate in the plasma and interface region. If unmanaged, these interferences make trace level analysis of the above elements difficult or impossible in many water samples.

The ORS serves two purposes. First, it uses collision/reaction cell technology to virtually eliminate polyatomic interferences on most elements. This allows the analyst to select the most abundant isotope of each analyte for analysis and avoid the use of mathematical correction factors. The result is sub-ppb detection limits for virtually all elements of interest. Second, it allows the analyst to use passive collisions in the ORS to reduce the ion current for high concentration, low-mass elements such as Na and Ca. In this way, the dynamic range for these elements is shifted to allow accurate, linear measurement at levels previously impossible by ICP-MS. It is this ability to simultaneously improve the sensitivity for ultra-trace analytes and extend the dynamic range upward for matrix analytes that is unique to the ORS system.

Instrument Conditions

Table 2 shows the instrument conditions used for typical water analysis. Listed are the preferred isotope, the tune mode (normal, hydrogen reaction, or helium collision), integration time, calibration range, and approximate detection limit based on normal commercial laboratory conditions. RF power is typically set high, 1400–1500 W, to maximize decomposition of the matrix. Other tune conditions such as ion optics, quadrupole, and detector parameters are set according to standard instrument tune guidelines. No special tuning is required.

Table 2. Elements of Interest with Appropriate Isotopes, ORS Acquisition Mode, Integration Time, Calibration Range and Measured MDLs for Each Isotope

Analyte	Isotope	ORS mode	Integration time (s)	Calibration range (ppb)	~MDL (ppb)
Aluminum (Al)	27	Normal	0.1	0.5–100	0.054
Antimony (Sb)	121	Normal	0.1	0.5–100	0.035
Arsenic (As)	75	Helium	0.5	0.5–100	0.052
Barium (Ba)	137	Normal	0.1	0.5–100	0.027
Beryllium (Be)	9	Normal	0.1	0.5–100	0.028
Boron (B)	10	Normal	0.1	0.5–100	
Cadmium (Cd)	111	Normal	0.1	0.5–100	0.025
Calcium (Ca)	40	Hydrogen	0.1	50–200,000	2.02
Chromium (Cr)	52	Helium	0.5	0.5–100	0.019
Copper (Cu)	63	Helium	0.5	0.5–100	0.023
Iron (Fe)	56	Hydrogen	0.1	50–200,000	1.25
Lead (Pb)	Sum of isotopes 206, 207, 208	Normal	0.1	0.5–100	0.017
Manganese (Mn)	55	Normal	0.1	0.5–100	0.020
Mercury (Hg)	202	Normal	1.0	0.05–1.0	0.005
Molybdenum (Mo)	95	Normal	0.1	0.5–100	0.030
Nickel (Ni)	60	Helium	0.5	0.5–100	0.024
Potassium (K)	39	Helium	0.5	50–200,000	3.02
Selenium (Se)	78	Hydrogen	0.5	0.5–100	0.047
Silver (Ag)	107	Normal	0.1	0.5–100	0.027
Sodium (Na)	23	Hydrogen	0.1	50–200,000	27.6
Thallium (Tl)	205	Normal	0.1	0.5–100	0.021
Uranium (U)	238	Normal	0.1	0.5–100	0.015
Vanadium (V)	51	Helium	0.5	0.5–100	0.034
Zinc (Zn)	66	Normal	0.1	0.5–100	0.101
Useful Internal Standards					
6Li	6	Normal	0.1	50	
Sc	45	All	0.1	50	
Ge	70,72,74	All	0.1	50	
Y	89	Normal	0.1	50	
In	115	Normal	0.1	50	
Tb	159	Normal	0.1	50	
Pt	195	Normal	0.1	50	
Bi	209	Normal	0.1	50	




Figure 1. Summary of general water analysis protocol.

Figure 1 depicts the general flow of sample analysis and QA/QC that would be performed to meet the daily requirements of most drinking water regulations. Specific QA/QC details vary from jurisdiction to jurisdiction and are not outlined here. In addition to the daily requirements, less frequent, periodic QA/QC documentation must be performed to ensure ongoing accuracy and precision. Such periodic requirements include: verification of method detection limits, dynamic range,

management of interferences (both isobaric and memory effects), as well as general instrument condition and performance. Specific examples of these requirements are found in USEPA Method 200.8 and the UK Drinking Water Inspectorate publication, “NS-30.”

Interference Correction

Because the ORS is capable of efficiently removing polyatomic interferences and most isobaric

elemental interferences in unknown, complex matrices, the use of mathematical interference correction is all but eliminated. The elements which typically require interference correction in water, Ca, V, Fe, As, Se, Mo, and Cd can all be analyzed without the need for mathematical correction. This simplifies the analysis and improves confidence in the results. In this work, only Li-6, In-115, and Pb are corrected (see Table 3). The Li-6 correction is used to correct the abundance of the Li-6 internal standard in the presence of high concentrations of Li-7 in some samples. The In-115 correction is used to correct an internal standard, In, in the presence of high concentrations of tin. Neither of these cases is common and normally these can be ignored. The Pb correction is used to normalize the lead response in the case of varying lead isotope ratios and is not an interference correction.

Table 3. Typical Mathematical Corrections Used for Water Matrices with the Agilent 7500c ORS System

Mass	Equation
6	$(6)^*1 - (7)^*0.082$
115	$(115)^*1 - (118)^*0.014$
208	$(208)^*1 + (206)^*1 + (207)^*1$

Experiment

The following data and results were all obtained from a single sequence of 44 analyses of standards, blanks, QC samples, unknown groundwater samples, and seawater samples. All calibrations are based on a single set of standards prepared in 1% nitric acid/0.5% hydrochloric acid. No attempt at matrix matching beyond simple acidification was made. The instrument and conditions were like those of a typical commercial environmental laboratory. "Clean room" conditions or ultra-high purity reagents were not employed. The Agilent 7500c ICP-MS with ORS and Integrated Sample Introduction System (ISIS), configured for autodilution, was used.

Quality Control

Quality control in this experiment consisted of four components:

- Verification of tune performance for each ORS mode
- Initial Calibration linearity check
- Verification of accuracy of initial calibration using NIST 1640 standard reference water
- Periodic verification of calibration accuracy through measurement of continuing calibration verification (CCV) samples

Autodilution

The Agilent 7500c was configured with an ISIS for rapid sample uptake and autodilution. ISIS uses flowing stream autodilution rather than discrete sample dilution. This greatly enhances the throughput and minimizes the possibility of contamination compared with other types of autodiluters. In the ISIS autodiluter, the sample stream is mixed with a flowing stream of diluent in an entirely closed system. Dilution factor is controlled by high precision peristaltic pumps that are automatically and periodically monitored for accuracy throughout the run. Autodilution is invoked automatically by the intelligent sequencing software whenever the system encounters a user-definable out-of-range condition, such as an analyte outside the calibration range or an internal standard outside predefined bounds. Autodilution was invoked in a number of the samples in this work. An excellent check on both the linearity of the instrument and the accuracy of the autodilution can be obtained by comparing the results for diluted and undiluted samples. If the results match well, both the instrument linearity and autodilution accuracy are in control. Tables 5 and 7 show excellent examples of this.

Results

QC results are depicted in Tables 4 (CCV results) and 5 (NIST 1640 results). Examples of calibration linearity are depicted in Figures 2, 3, and 4, which are representative. Calibration "R" values of .9998 or greater are considered linear.

Table 4. Recovery of Periodic Calibration Check Standard in a Sequence of Water Samples Including Drinking Waters, Ground Waters, and Seawaters. Calibration Checks were Run After 30 and 43 Real Samples in this Experiment

	CCV		%	%	
	Actual value	CCV 50/5000/0.5	Recovery	CCV 50/5000/0.5	Recovery
Total DF:		1		1	
File:		031_CCV.D#		044_CCV.D#	
Be/9 [#1]	50	50.62	101.2	50.01	100.0
Na/23 [#2]	5000	4933.00	98.7	4838.00	96.8
Mg/24 [#1]	5000	4700.00	94.0	4802.00	96.0
Al/27 [#1]	50	47.09	94.2	46.84	93.7
K/39 [#3]	5000	5260.00	105.2	5076.00	101.5
Ca/40 [#2]	5000	5053.00	101.1	5063.00	101.3
V/51 [#3]	50	51.52	103.0	50.84	101.7
Cr/52 [#3]	50	51.43	102.9	50.78	101.6
Mn/55 [#1]	50	49.92	99.8	50.89	101.8
Fe/56 [#2]	5000	5067.00	101.3	5068.00	101.4
Co/59 [#1]	50	49.88	99.8	50.16	100.3
Ni/60 [#3]	50	51.99	104.0	51.36	102.7
Cu/63 [#3]	50	52.64	105.3	51.74	103.5
Zn/66 [#1]	50	49.27	98.5	49.44	98.9
As/75 [#3]	50	51.63	103.3	51.58	103.2
Se/78 [#2]	50	50.90	101.8	50.61	101.2
Se/80 [#2]	50	51.45	102.9	51.10	102.2
Mo/95 [#1]	50	49.44	98.9	48.11	96.2
Ag/107 [#1]	50	48.73	97.5	47.02	94.0
Cd/111 [#1]	50	49.34	98.7	48.40	96.8
Sb/121 [#1]	50	47.71	95.4	47.03	94.1
Ba/137 [#1]	50	50.35	100.7	49.19	98.4
Hg/202 [#1]	0.5	0.49	98.3	0.47	94.8
Tl/205 [#1]	50	49.68	99.4	50.46	100.9
Pb/208 [#1]	50	49.41	98.8	49.25	98.5
Th/232 [#1]	50	48.54	97.1	49.09	98.2
U/238 [#1]	50	49.46	98.9	49.84	99.7

Values in brackets after element mass are tune mode, 1= normal, 2 = hydrogen, 3 = helium.

Table 5. Analysis of Certified Reference Water NIST 1640 as a Calibration Check. Sample was Measured Neat and Autodiluted 1/20 (actual measured DF = 21.72), since Na Value Exceeded Upper Calibration Limit. Note that Even in the Undiluted Sample, the Recovery for Na is 101.2%

	Certified value (ppb)	NIST 1640 1	% Recovery undiluted	NIST 1640 21.72	% Recovery diluted
Total DF:					
Be/9 [#1]	34.94	35.750	102.3	34.860	99.77
Na/23 [#2]	29350	29690.000	101.2	29140.000	99.28
Mg/24 [#1]	5819	5893.000	101.3	6154.000	105.76
Al/27 [#1]	52	49.180	94.6	69.290	133.25
K/39 [#3]	994	947.900	95.4	858.800	86.40
Ca/40 [#2]	7045	7328.000	104.0	7488.000	106.29
V/51 [#3]	12.99	13.030	100.3	12.930	99.54
Cr/52 [#3]	38.6	37.470	97.1	38.540	99.84
Mn/55 [#1]	121.5	119.500	98.4	120.100	98.85
Fe/56 [#2]	34.3	35.840	104.5	31.820	92.77
Co/59 [#1]	20.28	19.400	95.7	20.010	98.67
Ni/60 [#3]	27.4	26.920	98.2	28.000	102.19
Cu/63 [#3]	85.2	86.450	101.5	92.350	108.39
Cu/65 [#3]	85.2	86.350	101.3	91.340	107.21
Zn/66 [#1]	53.2	55.380	104.1	55.560	104.44
As/75 [#3]	26.67	26.910	100.9	28.080	105.29
Se/78 [#2]	21.96	21.990	100.1	20.930	95.31
Mo/95 [#1]	46.75	45.310	96.9	43.280	92.58
Ag/107 [#1]	7.62	7.210	94.6	7.497	98.39
Cd/111 [#1]	22.79	22.560	99.0	22.420	98.38
Sb/121 [#1]	13.79	13.090	94.9	12.590	91.30
Ba/137 [#1]	148	143.900	97.2	142.100	96.01
Hg/202 [#1]		0.017		0.019	
Tl/205 [#1]		0.009		-0.042	
Pb/208 [#1]	27.89	26.690	95.7	26.370	94.55
Th/232 [#1]		0.011		-0.429	
U/238 [#1]		0.725		0.698	

Values in brackets after element mass are tune mode, 1= normal, 2 = hydrogen, 3 = helium.

Table 6. Replicate Analyses of Low Standard After Sequence of 33 High Level Samples, Standards, and Blanks for MDL Calculations. Three Sigma MDL are Calculated in ppb

	MDL rep 01	MDL rep 02	MDL rep 03	MDL rep 04	MDL rep 05	MDL rep 06	MDL rep 07	MDL rep 08	MDL rep 09	MDL rep 10	3 Σ MDL
Be/9 [#1]	0.50	0.50	0.49	0.49	0.50	0.47	0.49	0.49	0.50	0.49	0.028
Na/23 [#2]	53.45	47.78	43.96	39.85	40.52	36.48	34.69	30.58	30.17	22.08	27.617
Mg/24 [#1]	49.82	49.13	49.75	48.94	48.83	48.92	49.32	48.84	48.24	48.41	1.530
Al/27 [#1]	0.30	0.26	0.25	0.25	0.25	0.23	0.24	0.24	0.25	0.26	0.054
K/39 [#3]	56.28	55.34	55.09	53.35	55.02	55.15	53.73	53.25	54.17	53.70	3.023
Ca/40 [#2]	52.33	51.76	51.55	51.81	52.32	51.86	51.28	51.33	53.42	51.15	2.023
V/51 [#3]	0.51	0.53	0.53	0.53	0.54	0.51	0.53	0.50	0.52	0.52	0.034
Cr/52 [#3]	0.52	0.52	0.51	0.51	0.50	0.51	0.52	0.51	0.51	0.51	0.019
Mn/55 [#1]	0.49	0.49	0.49	0.47	0.48	0.48	0.49	0.48	0.48	0.47	0.020
Fe/56 [#2]	53.84	53.69	53.43	53.46	53.97	53.18	53.10	52.91	53.17	52.65	1.251
Co/59 [#1]	0.48	0.48	0.49	0.48	0.48	0.48	0.49	0.49	0.48	0.47	0.016
Ni/60 [#3]	0.50	0.49	0.49	0.48	0.50	0.48	0.48	0.49	0.48	0.49	0.024
Cu/63 [#3]	0.48	0.48	0.46	0.47	0.46	0.48	0.48	0.47	0.46	0.47	0.023
Zn/66 [#1]	0.50	0.45	0.43	0.43	0.43	0.42	0.42	0.46	0.44	0.42	0.074
As/75 [#3]	0.50	0.53	0.53	0.49	0.54	0.54	0.54	0.53	0.52	0.52	0.052
Se/78 [#2]	0.52	0.51	0.53	0.52	0.49	0.52	0.52	0.51	0.48	0.51	0.047
Se/80 [#2]	0.58	0.62	0.56	0.56	0.55	0.57	0.58	0.55	0.54	0.57	0.066
Mo /95 [#1]	0.47	0.46	0.46	0.46	0.45	0.46	0.48	0.44	0.47	0.45	0.030
Ag/107 [#1]	0.45	0.47	0.46	0.44	0.46	0.46	0.46	0.45	0.44	0.45	0.027
Cd/111 [#1]	0.45	0.43	0.44	0.44	0.44	0.44	0.44	0.44	0.45	0.43	0.025
Sb/121 [#1]	0.46	0.45	0.44	0.45	0.43	0.44	0.46	0.45	0.43	0.45	0.035
Ba/137 [#1]	0.49	0.47	0.47	0.49	0.48	0.47	0.47	0.47	0.46	0.48	0.027
Hg/202 [#1]	0.04	0.04	0.04	0.05	0.04	0.04	0.04	0.04	0.04	0.04	0.005
Tl/205 [#1]	0.40	0.42	0.42	0.43	0.42	0.42	0.42	0.42	0.41	0.41	0.021
Pb/208 [#1]	0.46	0.46	0.46	0.45	0.46	0.45	0.45	0.45	0.45	0.45	0.017
Th/232 [#1]	0.29	0.34	0.34	0.34	0.34	0.34	0.34	0.34	0.34	0.34	0.050
U/238 [#1]	0.43	0.44	0.44	0.43	0.43	0.43	0.44	0.44	0.43	0.43	0.015

Values in brackets after element mass are tune mode, 1= normal, 2 = hydrogen, 3 = helium.

Detection Limits

The method detection limits reported in Table 6 were generated at the end of a sequence of 33 real world samples, standards, and blanks. Column one lists the isotope and ORS acquisition mode, #1 = Normal Mode, #2 = Hydrogen Mode, #3 = Helium Mode. Actual method detection limits will vary depending on instrument and laboratory conditions. These detection limits should be achievable with normal levels of laboratory cleanliness, using trace metal grade acids and ASTM type 1 water. The instrument used for this work was equipped with the ISIS, which typically improves DLs somewhat by increasing sample introduction precision and minimizing carryover.

Dynamic Range

One of the advantages of using the ORS is its ability to reduce interferences on certain trace level analytes and simultaneously attenuate the signal on high concentration or matrix elements. In this work, calibrations were generated from a low of 50 ppt for Hg to a high of 200 ppm for the mineral elements, Na, K, Ca, Mg, and Fe. Sample calibration curves follow. Additionally, while Na was calibrated only as high as 200 ppm, which is the highest regulated concentration in any of the elements in the worldwide drinking water regulations (see Table 1), it yields linear response at much higher concentrations.

Table 7. A Series on Analyses on Three High Dissolved Solids Ground Water Samples. Each Sample was Analyzed Undiluted and Automatically Autodiluted. Elements which were Undetected were Removed for Simplicity.

	Water 1	Water 1	Water 2	Water 2	Water 3	Water 3
Total DF:	1	21.72	1	21.72	1	21.72
File:	014SMPL.D	015SMPL.D	016SMPL.D	017SMPL.D	018SMPL.D	019SMPL.D
Na/23 [#2]	489100.000	492500.000	330500.000	324100.000	563700.000	554000.000
Na/23 [#3]	480300.000	505800.000	337200.000	342800.000	563000.000	571800.000
Mg 24 [#1]	559.000	599.900	511.700	534.800	3099.000	3407.000
K/39 [#3]	1564.000	1365.000	794.000	721.400	2513.000	2333.000
Ca/40 [#2]	8708.000	8760.000	2337.000	2255.000	13350.000	13400.000
Mo/95 [#1]	0.776	0.773	1.482	1.535	49.070	49.180
Ba/137 [#1]	17.070	16.990	29.250	28.800	5.263	5.154
U/238 [#1]	0.043	0.037	0.036	0.034	0.115	0.103

Values in brackets after element mass are tune mode, 1 = normal, 2 = hydrogen, 3 = helium.

Table 7 shows the results of the analysis of three brackish ground water samples. Each sample was analyzed directly and then autodiluted. Both sets of results show both the dynamic range of the Agilent 7500c and the accuracy of the autodilution. The autodilution factor of 21.72 is the result of the system automatically calibrating the dilution

factor at the beginning of the sequence and periodically, as needed. Note that for the uranium result, where the undiluted concentration is only 30–40 ppt, the autodiluted result agrees very well. This translates to accurate measurement of uranium in the diluted samples of $\sim 35/21.7 = 1.6$ ppt.

Table 8. Results of Analysis of a 1/10 "Synthetic Seawater" Blank (High Purity 0.3% NaCl) Plus a Spike at 5 ppb for Trace Elements and 500 ppb for Matrix Elements.

	1/10 Synth Sea H₂O	Spike 1/10 Synth Sea H₂O + 5 ppb	% Recovery 5/500 ppb spike
File:	020SMPL.D#	021SMPL.D#	
Be/9 [#1]	0.000	4.591	91.8
Na/23 [#1]	over range	over range	N/A
Na/23 [#2]	1233000.000	1215000.000	N/A
Na/23 [#3]	1193000.000	1193000.000	N/A
Mg/24 [#1]	2.382	477.000	94.9
I/27 [#1]	-0.409	4.250	93.2
K/39 [#1]	13.730	491.500	95.6
K/39 [#2]	8.195	548.600	108.1
K/39 [#3]	16.510	597.400	116.2
Ca/40 [#2]	6.740	532.600	105.2
V/51 [#3]	0.031	5.426	107.9
Cr/52 [#3]	0.045	5.287	104.8
Mn/55 [#1]	-0.003	4.497	90.0
Fe/56 [#2]	-0.258	508.600	101.8
Co/59 [#1]	0.122	4.569	89.0
Ni/60 [#1]	0.024	4.318	85.9
Ni/60 [#3]	-0.040	4.801	96.8
Cu/63 [#3]	-0.117	4.691	96.2
Cu/65 [#3]	-0.117	4.564	93.6
Zn/66 [#1]	0.025	4.520	89.9
Zn/67 [#1]	0.007	4.714	94.1
As/75 [#3]	0.011	5.027	100.3
Se/78 [#2]	0.006	4.366	87.2
Se/80 [#2]	0.143	4.620	89.5
Mo/95 [#1]	0.043	5.040	99.9
Ag/107 [#1]	-0.010	4.254	85.3
Cd/111 [#1]	0.033	4.545	90.2
Sb/121 [#1]	0.034	4.598	91.3
Ba/137 [#1]	0.010	4.789	95.6
Hg/202 [#1]	0.017	0.020	N/A
Tl/205 [#1]	-0.003	4.883	97.7
Pb/208 [#1]	0.175	5.066	97.8
U/238 [#1]	0.000	4.968	99.4

Values in brackets after element mass are tune mode, 1 = normal, 2 = hydrogen, 3 = helium.

Table 8 shows the results of the analysis of a 0.3% 3000 ppm NaCl or 1180.5 ppm Na, both unspiked and spiked with trace elements and other matrix elements. Recoveries are reported in column 4. Note that in this case, for demonstration purposes, Na was acquired in all three ORS modes (normal, hydrogen, and helium). As expected, in the normal mode, the sodium signal was over range and the detector was protected from excessive signal. However, sodium was measurable in both hydrogen

and helium modes at 1233 and 1193 ppm respectively, yielding recoveries of 104% and 101% respectively without further dilution or any other manipulation of instrument conditions. Under identical conditions, in the same run at the same time, Arsenic in the spike was also measured using He collision mode at 5.03 ppb to give 100.3% recovery.

1180.5 ppm sodium




Figure 2. Calibration curve for Na in Helium collision mode showing linearity from 50 ppb to 1180 ppm (0.3% NaCl).




Figure 3. Arsenic calibration acquired in helium collision mode (same as Na in Figure 2) from 0.5 to 100 ppb.




Figure 4. Mercury calibration acquired in normal (no gas) mode from 0.05–1 ppb.

The calibration curves in Figures 2–4 were all acquired from the same mixes of standard elements in dilute nitric/hydrochloric acid. That means that the low standard contained 50 ppt of mercury, 500 ppt of the other trace elements and 50 ppb of the mineral elements (Na, K, Ca, Mg, and Fe), and so on through the levels. In the sodium curve, the actual calibration was performed up to 200 ppm (level 7 in Figure 2); the 1180.5 ppm level was the 1/10 “synthetic seawater” NaCl solution.

Conclusions

While the specific details for drinking water monitoring vary from country to country around the world, the overall requirements, both from a reporting limit and quality control standpoint, are

very similar. Currently, of the many available techniques for monitoring trace metals in water, only ICP-MS has the sensitivity and elemental coverage to meet all worldwide requirements. In addition, the use of collision/reaction cell technology in the form of the Agilent 7500c ORS allows the user both to easily meet the strictest ultra-trace reporting limits and to measure mineral or matrix elements at 1000s of ppm simultaneously, without fear of false positives from polyatomic interferences or out-of-range elements.

For More Information

For more information on our products and services, visit our web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2003

Printed in the USA
February 19, 2003
5988-8902EN



Agilent Technologies



A Comparison of GC-ICP-MS and HPLC-ICP-MS for the Analysis of Organotin Compounds

Application

Environmental

Author

Raimund Wahlen
LGC Limited, Queens Road
Teddington, Middlesex
TW11 0LY, United Kingdom

Abstract

An inductively coupled plasma mass spectrometer (ICP-MS) was used as a detector for gas chromatography (GC) and high performance liquid chromatography (HPLC) analysis of organotin compounds. ICP-MS is a highly sensitive detector with detection limits in the pg–ng range, as well as enabling calibration by isotope dilution mass spectrometry (IDMS). Calibrating using isotopically labeled organotin species reduces measurement uncertainties and leads to greater precision compared to external calibration methods. This application note details the relative merits of the two techniques for the analysis of organotin compounds.

Introduction

The toxic effects of organotin compounds in the environment have been well documented [1] and have led to extensive research into analytical methodologies for their determination in a variety of matrices. The widespread use of organotin compounds has resulted in their detection in most marine and fresh-water sediments as well as in open-ocean waters [2]. In recent years, the focus of research in organotin analysis has begun to include matrices with human health implications, such as seafood [3], manufactured products (PVC pipes used for drinking water distribution [4]), and human blood samples [5].

Organotin analysis has traditionally been performed by chromatographic separation (gas chromatography (GC) or high performance liquid chromatography (HPLC)) coupled to a variety of detectors. GC separations enable the analysis of many different groups of organotin compounds (for example, butyl-, phenyl-, octyl-, and propyl) in a single analysis after derivatization [6]. However, derivatization is time-consuming and yields may vary between species and in terms of efficiency depending on matrix components. GC-ICP-MS has the potential to facilitate simultaneous multi-elemental speciation analysis, because species of Se [7], Pb [8], Hg [9], and Sn [10] have volatile forms and could be analyzed in a single analysis. Organotin separations by HPLC offer the advantage that derivatization is not required, which eliminates a potential source of uncertainty in the final result and can reduce analysis time significantly. However, the range of compounds that can be analyzed in a single run are limited compared to GC. The use of ICP-MS as a detector enables calibration by isotope dilution mass spectrometry as well as providing very low limits of detection (pg–ng range). In conjunction with isotopically labeled organotin species, this approach offers many advantages from an analytical point of view including reduced measurement uncertainties and greater precision compared to external calibration methods.

Experimental

Reagents and Standards

Acetonitrile (UpSTM ultra-purity solvent grade) was obtained from Romil (Cambridge, UK). Glacial



Agilent Technologies

acetic acid (TraceSelect) and anhydrous sodium acetate (Microselect $\geq 99.5\%$ NT) were obtained from Fluka (Gillingham, Dorset, UK). Triethylamine, methanol and hexane were used as HPLC grade. Deionized water was obtained from a water purification unit at $>18\text{M}\Omega$ (Elga, Marlow, UK). Sodium tetra-ethylborate (NaBEt_4) was obtained from Aldrich (Gillingham, Dorset, UK).

Tributyltinchloride (TBTCl), Dibutyltinchloride (DBTCl_2), Triphenyltinchloride (TPhTCl) and Diphenyltinchloride (DPhTCl₂) were obtained from Aldrich and purified according to the procedure described by Sutton et al [11]. The ^{117}Sn isotopically enriched TBTCl was synthesized according to the procedure described in the same paper. Monobutyltinchloride (MBTCl_3) and Tetrabutyltinchloride (TeBTCl) were obtained from Aldrich, and Dioctyltin (DOT), Tripropyltin (TPrT), and Tetrapropyltin (TePrT) were obtained from Alfa Aesar (Johnson Matthey, Karlsruhe, Germany).

Instrumentation

Accelerated solvent extraction was carried out using a Dionex ASE 200 system. An Agilent 7500i ICP-MS was used for time-resolved analysis of ^{120}Sn , ^{118}Sn , and ^{117}Sn . The ShieldTorch system was used, and a second roughing pump was added in-line to increase sensitivity.

An Agilent Technologies (Palo Alto, California, USA) 1100 HPLC system was used for HPLC separations. All stainless steel parts of the HPLC system that come into contact with the sample were replaced by polyether ether ketone (PEEK) components. A 100-cm length piece of PEEK tubing was used to connect the analytical column to the $100\text{-}\mu\text{L min}^{-1}$

PFA MicroFlow nebulizer of the ICP-MS. Optimization of the ICP-MS conditions was achieved prior to HPLC analysis by adjusting the torch position and tuning for reduced oxide and doubly charged ion formation with a standard tuning solution containing 10 ng g^{-1} of ^7Li , ^{89}Y , ^{140}Ce , and ^{205}Tl in 2% HNO_3 . After this preliminary optimization, the HPLC system was coupled to the nebulizer and a final optimization was carried out using ^{103}Rh added to the HPLC mobile phase. To reduce the solvent loading on the plasma, the double-pass spray-chamber was Peltier-cooled to -5°C . Oxygen (0.1 L min^{-1}) was mixed into the make-up gas and added post-nebulization to convert organic carbon to CO_2 in the plasma and avoid a carbon build-up on the cones. The final optimization was important because the nebulizer gas and make-up gas flows had to be adjusted to ensure plasma stability with the organic mobile phase conditions. HPLC separations were performed using a C-18 ACE column ($3\text{-}\mu\text{m}$ particle size, $2.1\text{ mm} \times 15\text{ cm}$) with a mobile phase of $65:23:12:0.05\%$ v/v/v/v acetonitrile/water/ acetic acid/TEA. The flow rate was 0.2 mL min^{-1} , and $20\text{ }\mu\text{L}$ of sample blends and mass-bias blends were injected. See Table 1.

GC separations were performed on an Agilent 6890 GC. The Agilent G3158A GC interface [12] was used to couple the GC to the ICP-MS. The GC method was used as described by Rajendran et al [6]. The analytical column was connected to a length of deactivated fused silica, which was inserted along the ICP transfer line and injector. After installation of the interface, the torch position and the ion lenses were tuned using a 100-ppm xenon in oxygen mixture, which was added to the ICP-MS carrier gas at 5% volume via a T-piece. The isotope monitored for this adjustment was ^{131}Xe .

Table 1. ICP-MS Parameters Used

	HPLC-ICP-MS Platinum	GC-ICP-MS Platinum
Interface cones		
Plasma gas flow	$14.5\text{--}14.9\text{ L min}^{-1}$	$14.5\text{--}14.9\text{ L min}^{-1}$
Carrier gas flow	$0.65\text{--}0.75\text{ L min}^{-1}$	$0.80\text{--}0.85\text{ L min}^{-1}$
Make-up gas flow	$0.15\text{--}0.25\text{ L min}^{-1}$	Not used
RF power	$1350\text{--}1550\text{ W}$	$1100\text{--}1200\text{ W}$
Sampling depth	$4\text{--}7\text{ mm}$	$6.5\text{--}7.5\text{ mm}$
Integration time per mass	300 ms	100 ms
Isotopes monitored	^{120}Sn ^{117}Sn ^{103}Rh	^{120}Sn ^{118}Sn ^{117}Sn
Other parameters	ICP torch injector diameter: 1.5 mm Peltier cooled spray chamber at -5°C 5% O_2 added post-nebulization ShieldTorch fitted	5% N_2 or O_2 added to enhance sensitivity ShieldTorch fitted

Extraction of Organotin Compounds

The ASE extraction cells were fitted with PTFE liners and filter papers and filled with dispersing agent. The sediment and the isotopically enriched spike were added and left to equilibrate overnight. Each cell was extracted using five 5-minute cycles at 100 °C and 1500 psi after a 2-minute preheat and 5-minute heat cycle. 0.5 M sodium acetate/ 1.0 M acetic acid in methanol was used as the extraction solvent [13]. A calibrated solution (mass-bias blend) was prepared by adding the appropriate amounts of both ^{120}Sn TBTCI and ^{117}Sn TBTCI into an ASE cell filled and extracting under the same conditions as the samples. Digestion blanks were prepared by extracting ASE cells filled with hydromatrix and PTFE liners. After the extraction, each cell was flushed for 100 seconds with 60% of the volume and purged with N_2 . Prior to analysis, the extracts were diluted two- to five-fold in ultrapure water for HPLC-ICP-MS analysis. For GC-ICP-MS analysis, 5 mL of sample-, blank-, and mass-bias blend solutions were derivatized with 1 mL of 5% NaBEt_4 and shaken for 10 minutes with 2 mL of hexane. An aliquot of the hexane fraction was then injected for analysis.

Isotope Dilution Mass Spectrometry (IDMS) Methodology

The method used for IDMS consisted of analyzing a blend of the sample together with a mass-bias calibration blend. Each sample blend was injected four times and bracketed by injections of the mass-bias calibration blend. The mass-bias calibration blend was prepared to match the concentration and isotope amount ratio in the sample by mixing the same amount of spike added to the sample with a primary standard of the analyte of interest [14], [15]. The estimation of the standard uncertainties for the measured isotope amount ratios was different to the one described in [14] as they were calculated as peak area ratios and not spectral measurement intensities. The chromatographic peaks were integrated manually using the RTE integrator of the Agilent ICP-MS chromatographic software. The mass fraction obtained from the measurement of each sample blend injection was then calculated according to:

$$w'_X = w_Z \cdot \frac{m_Y}{m_X} \cdot \frac{m_{Zc}}{m_{Yc}} \cdot \frac{R_Y - R'_B \cdot \frac{R_{Bc}}{R'_{Bc}}}{R'_B \cdot \frac{R_{Bc}}{R'_{Bc}} - R_Z} \cdot \frac{R_{Bc} - R_Z}{R_Y - R_{Bc}}$$

R'_B	Measured isotope amount ratio of sample blend (X+Y)
R'_{Bc}	Measured isotope amount ratio of calibration blend (Bc=Z+Y)
R_{Bc}	Gravimetric value of the isotope amount ratio of calibration blend (Bc=Z+Y)
R_Z	Isotope amount ratio of Primary standard Z (IUPAC value)
R_Y	Isotope amount ratio of spike Y (value from certificate)
w'_X	Mass fraction of Sn in sample X obtained from the measurement of one aliquot
w_Z	Mass fraction of Sn in primary standard Z
m_Y	Mass of spike Y added to the sample X to prepare the blend B (=X+Y)
m_X	Mass of sample X added to the spike Y to prepare the blend B (=X+Y)
m_{Zc}	Mass of primary standard solution Z added to the spike Y to make calibration blend Bc (=Y+ Z)
m_{Yc}	Mass of spike Y added to the spike Y primary standard solution Z to make calibration blend Bc (=Y+ Z)

The representative isotopic composition of Sn taken from IUPAC was used to calculate the isotope amount ratios of the primary standard. For the spike TBTCI, the isotopic composition was obtained from the certificate supplied with the ^{117}Sn enriched material from AEA Technology plc (UK). For the measured isotope amount ratio of the calibration blend (R'_{Bc}), the average of the two ratios measured before and after each sample blend isotope amount ratio (R'_B) were taken. A mass fraction was calculated for each sample blend injection and the average of the bracketing mass-bias calibration blend injections. The average of the four mass fractions was then reported as the mass fraction obtained for the blend analyzed. The final mass fraction was recalculated back to the original sample and corrected for moisture content.

Results and Discussion

General Comparison

Analysis of mixed organotin standard solutions showed that the GC method could separate a greater number (10–12) of compounds in a single run compared to HPLC-ICP-MS (5–6). The injection-to-injection time was ~40% shorter for HPLC-ICP-MS, due to the temperature profile used for GC separations. Because of the cost of the derivatizing agent, the reagent cost per sample is approximately double for GC sample preparation.

Sensitivity Enhancement of GC-ICP-MS by Using Additional Gases

Figure 1 and Table 2 illustrate the effect of adding different additional gases on the signal response

for a range of organotin compounds. Adding 5% O₂ results in an increase in the measured peak area ranging from 9-fold (DBT and MPhT) to 12-fold (MBT). The addition of N₂ results in a further increase compared to analysis without addition of an optional gas. Response factors range from 105 (DBT and TPhT) to 136 for MBT and 150 for TeBT. This translates to a reduction of the method detection limit (3s) for TBT from 0.4 ng mL⁻¹ (no gas) to 0.03 ng mL⁻¹ (with 5% O₂ added) to 0.006 ng mL⁻¹ (with 5% N₂ added). The table below summarizes detection limits based on analysis of a calibration standard for MBT, DBT, and TBT.

Detection limits (ng mL⁻¹ as Sn) by GC-ICP-MS

	No gas added	5% N ₂ added
MBT	0.7	0.01
DBT	0.5	0.008
TBT	0.4	0.006




Figure 1. Sensitivity increase on a 20 ng mL⁻¹ mixed standard by using a) no additional gas, b) 5% O₂, and c) 5% N₂.

Table 2. Effect of Different Additional Gases on Sensitivity of Organotin Compounds by GC-ICP-MS

Compound	Retention time (min)	a) No gas added (peak area)	b) 5% O ₂ added (peak area)	Response factor compared to a)	c) 5% N ₂ added (peak area)	Response factor compared to a)	Response factor compared to b)
MBT	5.57	2274	27029	12	309702	136	12
DBT	6.38	3247	29238	9	340436	105	12
MPhT	6.84	2026	18173	9	215182	106	12
TBT	7.02	3490	33132	10	399868	115	12
TeBT	7.54	3717	34225	9	558916	150	16
DPhT	8.46	3181	29665	9	338057	106	11
TPhT	9.81	4287	41119	10	450803	105	11

Comparison of HPLC-ICP-MS and GC-ICP-MS for Analysis of TBT in Sediment

Table 3 shows the comparative data obtained by analysis of the same sediment extracts by both methodologies. There is no statistically significant difference between the two data sets. This confirms that the chromatographic separation and the different sample pretreatment (dilution/derivatization) used has no influence on the analytical result obtained. The chromatography for both methods appears in Figure 2 and Figure 3. The isotope amount ratio measurement precision, measured for 15 injections over a 6–8 hour period, is good for both methods (1.6% for HPLC-ICP-MS and 1.7% for GC-ICP-MS). The uncertainty estimates provided by HPLC-ICP-MS tend to be larger than for GC

separations. This is a result of broader peaks (50–60s by HPLC, compared to 4–6s by GC) and greater baseline noise.

Detection limits for sediment analysis are estimated by peak height measurements (3s) as 3 pg TBT as Sn for HPLC-ICP-MS and 0.03 pg TBT as Sn for GC-ICP-MS with 5% O₂ addition. This demonstrates the superior sensitivity of GC-ICP-MS even without sample preconcentration.

The accuracy of the analytical procedure was evaluated by measuring extractions of the certified reference sediment PACS-2 (NRC, Canada). The mean mass fraction obtained by the HPLC-ICP-MS analysis of four extracts was 864 ±35 ng g⁻¹ TBT as Sn compared to a certified value of 980 ±130 ng g⁻¹ TBT as Sn.

Table 3. TBT Data for Sediment Extracts

Sample	HPLC-ICP-MS (ng/g as Sn) n = 4	Standard uncertainty k = 1 (ng/g as Sn)	GC-ICP-MS (ng/g as Sn) n = 4	Standard uncertainty k = 1 (ng/g as Sn)
1	827	19	853	12
2	805	38	846	13
3	845	9	838	8
Mean	826	22	846	11
Expanded uncertainty (k = 2)	±87		±39	




Figure 2. HPLC-ICP-MS chromatogram.




Figure 3. GC-ICP-MS chromatogram.

Conclusions

Both HPLC-ICP-MS and GC-ICP-MS offer advantages for organotin speciation analysis. While there is no statistical difference in the results obtained, HPLC-ICP-MS can be used for cheaper and faster determinations of large sample batches, while the superior sensitivity and the greater number of analytes separated make GC-ICP-MS an ideal tool for monitoring studies at the ultratrace level.

References

1. S. Nicklin and M. W. Robson, (1988) *Applied Organometallic Chemistry*, **2**, 487–508.
2. H. Tao, R. B. Rajendran, C. R. Quetel, T. Nakazato, M. Tominaga, and A. Miyazaki, (1999) *Anal. Chem.*, **71**, 4208–4215.
3. J. C. Keithly, R. D. Cardwell, and D. G. Henderson, (1999) *Hum. Ecol. Risk Assess.*, **5**, No. 2, 337–354.
4. A. Sadiki, and D. T. Williams, (1996) *Chemosphere*, **32**, 12, 2389–2398.
5. S. Takahashi, H. Mukai, S. Tanabe, K. Sakayama, T. Miyazaki, and H. Masuno, (1999) *Environmental Pollution*, **106**, 213–218.
6. R. B. Rajendran, H. Tao, T. Nakazato, and A. Miyazaki, (2000) *Analyst*, **125**, 1757–1763.
7. J. L. Gomez-Ariza, J. A. Pozas, I. Giraldez, and E. J. Morales, (1998) *J. Chromatogr. A.*, **823** (1–2): 259–277.
8. I. A. Leal-Granadillo, J. I. Garcia-Alonso, and A. Sanz-Medel, (2000) *Anal-Chim-Acta.*, **423** (1): 21–29.
9. J. P. Snell, I. I. Stewart, R. E. Sturgeon, and W. J. Frech, (2000) *J. Anal. At. Spectrom.*, **15** (12): 1540–1545.
10. J. R. Encinar, P. R. Gonzalez, J. I. Garcia Alonso, and A. Sanz-Medel, (2002) *Anal. Chem.*, **74**, 270–281.
11. P. G. Sutton, C. F. Harrington, B. Fairman, E. H. Evans, L. Ebdon, and T. Catterick, (2000) *Applied Organometallic Chemistry* **14**, 1–10.
12. Agilent Technical Note “GC-ICP-MS Interface” publication 5988-3071EN.
13. C. G. Arnold, M. Berg, S. R. Müller, U. Dommann, and R. P. Schwarzenbach, (1998) *Anal. Chem.*, **70**, 3094–3101.
14. T. Catterick, B. Fairman, and C. J. Harrington, (1998) *J. Anal. At. Spectrom.* **13**, 1109.
15. *Guidelines for achieving high accuracy in isotope dilution mass spectrometry*, edited by M. Sargent, C. Harrington, and T. Harte RSC London, 2002.

Acknowledgments

The work described in this application note was supported under contract with the Department of Trade and Industry (UK) as part of the National Measurement System Valid Analytical Measurement (VAM) program.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
August 7, 2002
5988-6697EN



Agilent Technologies



Analysis of Rare Earth Elements in Geological Samples by Laser Ablation - Inductively Coupled Plasma Mass Spectrometry (LA-ICP-MS)

Geological

Authors

Helene Brätz & Reiner Klemm
Mineralogisches Institut,
Universität Würzburg,
Am Hubland,
97074 Würzburg,
Germany

Abstract

The unique, coherent chemical properties of the rare earth elements (REE) make them highly suitable for geological studies into the history of rocks. Prior to the advent of reliable laser ablation inductively coupled plasma mass spectrometry (LA-ICP-MS) methods, the steps required to prepare the rock samples for REE analysis were both time consuming and costly. Now, the same fusion beads prepared for X-ray-fluorescence (XRF) analysis, used for the determination of major and certain trace elements, can also be used for LA-ICP-MS analysis, without additional sample preparation. Data published in the literature [1] for geostandards: BE-N (Basalt), MRG-1 (Gabbro) and MAG-1 (Marine Mud), compares well to the results obtained by LA-ICP-MS.

Introduction

The rare earth elements (REE) belong to the inner transition metals and play an important part in understanding the geological history of rocks. In most cases, the REE content of a geological sample reflects the pristine composition of the rock formation and can, therefore, yield reliable information concerning magmatic processes and the reconstruction of palaeo-tectonic settings. This is because REE are amongst the most immobile elements during diagenesis, metamorphism, hydrothermal alteration and weathering.

In the past, the determination of REE in geological samples was a time consuming and expensive task: sample digestion and separation of the REE via ion exchange was required prior to analysis by ICP-AES or ICP-MS. More recently, the methodology has developed whereby REE can be determined in the same whole-rock fusion glass beads which are used for X-ray fluorescence (XRF) analyses, by laser ablation inductively coupled plasma mass spectrometry (LA-ICP-MS), with two key advantages:

1. Only one chemical sample preparation procedure is necessary, thereby reducing the use of expensive supra pure chemicals.
2. The bulk chemistry and certain trace elements of a rock sample can be determined by XRF prior to analysis of the same fusion bead by LA-ICP-MS.



Agilent Technologies

Sample preparation

0.6 g very finely (<40µm) ground geological sample (international geostandards BE-N, MRG-1, MAG-1) was added to 3.6 g Spectromelt A12 (66:34 mixture of di-lithiumtetraborate and lithiummetaborate, Merck). Just before melting, 1.1 g NH₄NO₃ was added as an oxidant and merged once again. Fusing was carried out in a Pt-crucible at 1100°C. A different preparation method is described by Becker & Dietze [2]. The bulk chemistry and certain trace elements, as well as the homogeneity of the

glass targets, were determined using X-ray-fluorescence (PHILIPS PW1480; Brätz & Klemm, in prep). No further sample preparation is required for additional analysis of the REE in the whole-rock glass target by LA-ICP-MS. At most, the surface of the glass targets can be wiped with alcohol. The measurements were undertaken at the Mineralogisches Institut of the Universität Würzburg by means of a 266 nm Nd:YAG Laser (New Wave Research Inc., Merchantek Products) connected to an Agilent 7500i ICP-MS. Table 1 displays the instrument operating parameters of the LA-ICP-MS, which was tuned for maximum sensitivity.

Table 1. Laser ablation and ICP-MS operating parameters

Laser ablation adjustment

Merchantek 266 LUV
Wavelength: 266 nm
Pulse duration: 6 ns
Repetition frequency: 20 Hz
Laser energy: 70% (=1.9 mJ)
Ablation pattern: line, 50 µm spot Ø
Scan speed: 20 µm/sec.
Laser warm-up: 10 sec.
On delay: 0 sec.

ICP-MS adjustment

Agilent 7500i
Plasma power: 1390 W
Carrier Gas (Ar): 1.27 L/min.
Plasma Gas (Ar): 14.9 L/min.
Auxiliary Gas (Ar): 0.9 L/min.
Acquisition Mode: Time Resolved Analysis
Integration time: Si 0.01 sec.; REE 0.15 sec.
Background: 10 sec.
Acquisition time: 40 sec.


Results

Quantification of the REE was undertaken using the GLITTER software [3, 4]. The REE in the glass standard reference material NIST612 were used as calibration standards, and ²⁹Si as the internal standard. Each prepared geostandard (BE-N, MRG-1, MAG-1) was analysed several times on different days, the relative standard deviation differs from 2 to 14% (the majority from 3 to 8%), and, in agreement with the XRF-measurements of major and certain trace elements, the LA-ICP-MS data highlight an almost homogeneous REE distribution in the glass targets. The mean concentration values for the geostandards, see Table 2, generally show excellent agreement when compared to data from the literature [1]. A graphical representation of the LA-ICP-MS results in comparison to the reference values is shown in Figure 1.

It is important to note that the data presented in this application note has been corrected solely by subtracting the instrument background counts from the counts for each of the elements investigated. While there is the potential for oxide overlaps on the REE - although at much lower levels than would be seen with solution nebulization - the results were in good agreement with the reference values, even when no interference correction was applied. The low level of oxide interferences on the Agilent 7500i is due to the high efficiency of the plasma, which decomposes matrix components efficiently, and thus permits difficult applications to be run without over reliance on correction equations [5].

Table 2. Results for REE concentrations [ppm] in lithium borate glasses from this study and comparison data from the literature [1] (underlined data are proposed values, other values are recommended, except those in parentheses which are informative values). LA-ICP-MS results for BE-N are the mean values of at large 53 measured patterns at six days, for MRG-1 the mean values of 44 measured patterns at five days and for MAG-1 the mean values of 20 measured patterns at two days.

Element	BE-N (Basalt)			MRG-1 (Gabbro)			MAG-1 (Marine Mud)		
	LA-ICP-MS			LA-ICP-MS			LA-ICP-MS		
	[1]	mean	%RSD	[1]	mean	%RSD	[1]	Mean	%RSD
¹³⁹ La	82	88	3.3	9.8	11	7.1	43	44	5.7
¹⁴⁰ Ce	152	168	3.1	<u>26</u>	30	9.1	88	81	11.1
¹⁴¹ Pr	17.5	18.3	3.1	<u>3.4</u>	4.0	6.4	<u>9.3</u>	9.0	8.9
¹⁴⁶ Nd	67	70	3.4	19.2	21	5.1	38	40	3.8
¹⁴⁷ Sm	12.2	12.4	3.7	4.5	5.2	8.0	7.5	8.1	3.1
¹⁵³ Eu	3.6	3.9	3.9	1.39	1.60	8.1	1.55	1.45	10.3
¹⁵⁷ Gd	9.7	9.3	2.7	<u>4</u>	4.8	11.6	5.8	6.7	4.5
¹⁵⁹ Tb	1.3	1.2	6.4	0.51	0.58	6.8	0.96	0.86	9.9
¹⁶³ Dy	6.4	6.4	4.0	<u>2.9</u>	3.3	6.6	5.2	5.4	3.7
¹⁶⁵ Ho	1.1	1.1	3.4	0.49	0.53	6.2	1.02	0.89	7.3
¹⁶⁶ Er	2.5	2.5	4.9	<u>1.12</u>	1.3	11.3	<u>3</u>	3.1	3.2
¹⁶⁹ Tm	0.34	0.31	3.5	<u>0.11</u>	0.15	7.9	0.43	0.37	6.8
¹⁷² Yb	1.8	1.9	3.6	(0.6)	1.0	14.2	2.6	2.9	1.7
¹⁷⁵ Lu	0.24	0.25	3.8	<u>0.12</u>	0.11	8.9	0.40	0.33	9.1







Figure 1. LA-ICP-MS results for REE in comparison to reference values of the international geostandards BE-N, MRG-1 and MAG-1 [1].

Conclusions

The samples prepared for XRF-analysis for the determination of major and certain trace elements (Brätz & Klemm, in prep.) can be used readily for LA-ICP-MS analysis, without additional sample preparation. This way of analysing the REE is fast and relatively inexpensive in comparison to conventional REE-analysis methods. The measured values for the REE in international geostandards are in good agreement with data available in the literature [1]. A disadvantage of the Li borate fusion method of sample preparation is the very high Li-content in the glasses [2], which causes Li contamination of the glassware as well as interface and requires careful cleaning of both the laser ablation and ICP-MS systems in order to permit the subsequent measurement of these elements at trace levels.

References

1. Compilation of Working Values and Sample Description for 383 Geostandards. – Geostandards Newsletter, Vol 18, Special Issue, July 1994.
2. Becker J.S. & Dietze H.J. (1999): Determination of trace elements in geological samples by laser ablation

inductively coupled plasma mass spectrometry. – Fresenius J Anal Chem 365: 429-434.

3. GLITTER Version 3.0, On-line Interactive Data Reduction for the LA-ICPMS, Macquarie Research Ltd., 2000. <http://www.es.mq.edu.au/GEMOC>
4. Griffin W.L., van Achterbergh E., Ryan C.G., Jackson S.E., Pearson N.J. & Sharma A. (2000): Agilent Technologies ICP-MS Journal 2000 Issue 7, p 4.
5. McCurdy E.J., Wilbur S., Woods G.D. & Potter D. (2001) in Plasma Source Mass Spectrometry: The New Millennium (eds G. Holland and S. D. Tanner) The Royal Society of Chemistry, Cambridge, 45-60.

Acknowledgement

We would like to thank Ed McCurdy from Agilent Technologies for his constructive comments to a former version of this application note.

For More Information


For more information on Agilent Technologies' products and services, visit our Web site at www.agilent.com/chem/icpms.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

**Copyright © 2002
Agilent Technologies, Inc.
Printed 6/2002
Publication number: 5988-6305EN**





Automated Real-Time Determination of Bromate in Drinking Water Using LC-ICP-MS and EPA Method 321.8 Application

ICP-MS

Author

Jason A. Day, Anne Vonderheide, Joseph A. Caruso
University of Cincinnati
Cincinnati, OH 45220
USA

Thomas J. Gludenis, Jr.,
Agilent Technologies Inc.,
2850 Centerville Rd,
Wilmington, DE 19808
USA

Abstract

The suitability of coupling an HPLC to an ICP-MS for the fully automated, routine analysis of bromate in drinking water as per the proposed EPA Method 321.8 was investigated. The necessity to monitor the carcinogen bromate in ozonated drinking waters at single ppb levels has led the USEPA to investigate HPLC-ICP-MS as an alternative technique to the ion chromatography with conductivity detection method currently specified. During this investigation, a series of rigorous performance checks were used to assess the implementation of the proposed method including the determination of bromate in a series of EPA disinfection byproduct (DBP) standards.

Introduction

Ozonation is a common method used for the disinfection of drinking waters. In waters containing bromide (Br^-), such as those found in coastal regions subject to salt-water intrusion, a disinfection byproduct (DPB) of the ozonation process is the bromate ion (BrO_3^-). The bromate ion, produced by the oxidation of bromide, is very carcinogenic, with an estimated lifetime cancer risk of 1:10,000

for a concentration of 5 ppb.¹ The current method specified by the USEPA for the determination of bromate in drinking water uses ion chromatography (IC) with conductivity detection. One disadvantage of this method is the need for a tedious and time consuming sample pretreatment step.

The need for sample pretreatment arises from the potential for co-elution of chloride and bromide ions present in the sample, potentially resulting in false positive results. In order to prevent this from occurring, chloride present in the sample is precipitated out of solution using silver cartridges with subsequent pre-concentration of the bromate ions. This time consuming and lengthy clean-up procedure and pre-concentration step can result in pre-concentration of sulfate ions present in the water. Sulfate can subsequently displace the bromate ions on the resonating column resulting in false negatives.

For these reasons, ICP-MS has been investigated as an alternative, ion selective detector for this analysis. ICP-MS provides the resolution necessary to separate the bromate and chloride ion, thereby eliminating the need for a matrix elimination step. Furthermore, ICP-MS has been used successfully for the analysis of bromate in water samples containing concentrations of chloride in excess of 5000 ppb - much higher than the typical content of ozonated drinking water - without the need for sample pretreatment.²

This study will investigate the suitability of ion chromatography coupled to ICP mass spectrometry (ICP-MS) as an automated, real-time measurement approach, to determine low levels of bromate in ozonated drinking water samples, using the proposed EPA Method 321.8.³



Agilent Technologies

Instrumentation

The Agilent Technologies 1100 Series HPLC system, coupled to a 7500 Series ICP mass spectrometer using the real-time Plasma Chromatographic software was used for this study. This system was specifically designed for the rigors of automated trace element speciation work, mainly in response to laboratory demands, particularly in the environmental, clinical and food application areas, that need to carry out routine elemental speciation. Its design takes advantage of Agilent's expertise in chromatography and its recognized leadership position in ICP-MS.

During the past few years, the potential of ICP-MS as a detector for elemental speciation studies has been realized.⁴ When coupled to a chromatographic separation device, ICP-MS offers unmatched detection capability for laboratories interested in quantifying different species, forms, oxidation states or biomolecules associated with trace elements.^{2,5} Traditional approaches of coupling ICP-MS to chromatography devices are cumbersome, labor intensive and not readily automated. In fact, the majority of ICP-MS chromatography data handling software packages were designed specifically for liquid and gas chromatography (LC, GC) applications and required modification for use with ICP-MS. Some approaches even analyzed the chromatographic spectral peaks "post-run", meaning the data had to be imported into another software package after the analysis was completed, for quantitation purposes. It was clear that there was a real demand for a fully automated system, designed specifically for trace element speciation analysis. Agilent Technologies answered that demand with a fully integrated package for trace element speciation, comprising an 1100 Series HPLC system, coupled to a 7500 Series ICP mass spectrometer, using the Agilent ChemStation and real-time Plasma Chromatographic software.⁶

Methodology

ICP-MS Conditions

The ICP-MS instrumental conditions were optimized to give maximum signal at m/z 79, the most sensitive mass for Br. Because bromine is not completely ionized in argon ICP, sampling depth,

nebulizer flow, RF power and ion lens voltages have to be optimized very carefully to guarantee the most efficient sampling of bromide ions. Operating conditions for the 7500 are shown in Table 1. These conditions gave an instrument response of 110,000 cps for a 100 ppb bromate standard, with a background of 1,800 cps (partially due to trace levels of bromide in the 18 M Ω deionized water).

Table 1: Optimized Operating Conditions for ⁷⁹Br Using the Agilent 7500 ICP-MS

Parameter	Optimized conditions
Nebulizer	Meinhard concentric - glass
Nebulizer flow rate	1.05 L/min
Spray chamber	Scott double pass - glass
Spray chamber temperature	2 °C
Sample flow rate	1 mL/min
RF power	1200 W
Sampling depth	Optimized for max signal at ⁷⁹ Br
Ion lens voltages	Optimized for max signal at ⁷⁹ Br

Chromatographic Conditions

See Table 2 for the chromatographic conditions for the separation. The column eluent was passed via a short length of PEEK tubing to a six-port Rheodyne injector equipped with a 100 μ L (or 500 μ L depending on the measurement) PEEK loop. A post column injection was performed at the beginning of each run (for internal standard purposes, specified in the proposed EPA Method) at the exact time the data acquisition began on the ICP-MS. See Figure 1 for a schematic of the HPLC instrumentation coupled to the ICP-MS.

Table 2: Chromatographic Conditions for the Bromate Study

Parameter	Specification
Eluent mobile phase	25 mM Ammonium nitrate, 5 mM Nitric acid (~pH 2.7) in 18 M Ω Deionized water
Injection volumes	100 μ L, 500 μ L loops
Post-column injector	Used for internal standardization
Pump flow rate	1 mL/min
Column	Dionex CarboPac PA-100 (94 $\times$ 250 mm) - with guard




Figure 1: A schematic of the 1100 HPLC instrumentation coupled to the 7500 ICP-MS used for the bromate study.

Sample Preparation

The blank was 18 MΩ deionized water adjusted to pH 10 with NaOH. Standards were prepared daily from a USEPA 1 mg/mL bromate stock solution.

Demonstration of Instrument and Method Performance

As a way of maintaining data quality, the EPA uses performance checks to monitor the instrument and also ensure that the methodology is working correctly. Some of the more important performance checks for this proposed EPA method 321.8 include the measurement of:

- Abundance Sensitivity of ICP Mass Spectrometer
- Method Detection Limit
- Chromatographic Interferences
- Laboratory Fortified Blank
- Laboratory Fortified Matrix
- DBP Performance Sample

These measurements were used to assess the performance of the integrated system used for this study.

Abundance Sensitivity

A large argon dimer, $^{40}\text{Ar}^{40}\text{Ar}^+$ at mass 80 adjacent to the bromate ion $^{79}\text{Br}^+$ at mass 79, has the potential to bias results in the determination of bromate by ICP-MS. It is therefore critical that the abundance sensitivity, which is a measure of the instrument's ability to separate a trace peak from a major one,⁷ is optimized to allow for maximum rejection of the ions at mass 80. The very high operating vacuum of the 7500, and the high frequency of its quadrupole, combined with optimization of the rod-bias voltages, ensures that it achieves clean separation of both peaks, even at a mass of 79.5 amu, where the tail of the $^{40}\text{Ar}^{40}\text{Ar}^+$ might interfere with the Br^+ at mass 79. The excellent abundance sensitivity of the quadrupole's hyperbolic rods is demonstrated in Figure 2, which shows a spectral scan of 2% HNO_3 . The effect of the large signal at mass 80 is shown to have minimal affect on the small bromine signal at mass 79.




Figure 2: Mass spectrum showing clean separation of $^{79}\text{Br}^+$ from the argon dimer $^{40}\text{Ar}^{40}\text{Ar}^+$.

Method Detection Limit (MDL)

Two method detection limits were performed - one using a 500 μL loop, as specified in the method, and another using a 100 μL loop. A blank and three calibration standards (1, 5, and 25 ppb bromate) were used for both method detection limit tests.

Seven individually prepared bromate standards of 1 ppb (for the 100 μL loop) and 0.5 ppb (for the 500 μL loop) were then analyzed to determine the method detection limit (MDL). From this, an MDL was calculated for each loop by multiplying the standard deviation of the seven replicate results by 3.14, as indicated in the EPA method. Individual MDL replicate concentrations and statistics for both loops are shown in Table 3.

Table 3: Method Detection Limit Data for a 100 μL and 500 μL Loops

Replicate #	100 μL Loop Concentration (ppb)	500 μL Loop Concentration (ppb)
MDL-1	1.1	0.46
MDL-2	0.98	0.39
MDL-3	0.77	0.35
MDL-4	0.77	0.46
MDL-5	0.97	0.45
MDL-6	0.83	0.48
MDL-7	0.90	0.41
Mean	0.90	0.42
SD	0.131	0.044
RSD (%)	14.6	10.5
MDL	0.41	0.14

Chromatographic Interferences

To show that other halogenated compounds do not elute at similar retention times as bromate, a haloacetic acid standard (HAA) standard solution, provided by the EPA, was analyzed. The stock solution was diluted 1:100 yielding final concentrations of six different halogenated compounds reported in Table 4.

Table 4: Concentrations of Six Haloacetic Acid Compounds that Could Potentially Interfere with the Determination of Bromate

Compound	Concentration (ppb)
Monochloroacetic acid	15
Dichloroacetic acid	15
Trichloroacetic acid	5
Monobromoacetic acid	10
Dibromoacetic acid	5
Bromochloroacetic acid	10

A chromatogram containing the haloacetic acid mixture and a 10 ppb bromate standard is shown in Figure 3. The retention time for bromate is 3.5 minutes. The bromine-containing HAA standards elute at 2.5 minutes, 5.9 minutes and 7.1 minutes indicating no chromatographic interference with bromate. Average bromate recovery ($n = 2$) for this standard spiked with 10 ppb bromate was 102%.




Figure 3: A chromatogram containing haloacetic acid mixture and a 10 ppb bromate standard.

Laboratory Fortified Blank

Ten replicates of a laboratory-fortified blank (LFB) were analyzed at a concentration of 5 ppb, which was approximately ten times the MDL. The LFB samples consisted of 18 MΩ deionized water adjusted to pH 10 with NaOH and spiked with 5 ppb bromate standard. The average for the replicates was 4.7 ppb (8.9% RSD) with a 93% recovery.

Laboratory Fortified Matrices

Four fresh samples supplied by the EPA, taken from ozonation utilities in the U.S., were analyzed using this methodology. Each sample was adjusted to pH 10 with NaOH, and analyzed twice, unfortified and fortified with 10 ppb bromate. The results for all four samples are shown in Table 5. The recovery results for these matrices are all within the EPA guidelines of 70-130% for this method.

Table 5: Bromate Results from Ozonation Utilities

Sample ID	Concentration of bromate in unfortified sample (ppb)	Concentration of bromate in fortified sample (ppb)	% Recovery
A	2.0	12	102%
B	2.7	12	89%
C	4.0	16	118%
D	8.9	18	100%

USEPA DBP Performance Evaluation Check

An EPA check ampule (USEPA ICR PE ampule for inorganic DBPs - Study 9), whose concentration was not known at the time of analysis, was also analyzed as a blind check sample. The ampule was prepared in duplicate by diluting 1:100 and analyzing immediately. Results are shown in Table 6. Once again, the recoveries are both within the recommended guidelines.

Table 6: Recovery of Inorganic DBPs in EPA Check Ampules

Sample	Concentration in original ampule (ppb)	% Recovery (917 ppb true value)
Ampule 1	1120	120
Ampule 2	1040	113

Conclusion

The ability to measure bromate in ozonated drinking waters at sub-ppb levels is essential to understanding its risk assessment as a carcinogen. Once USEPA Method 321.8 is validated for use, ICP-MS detection coupled to HPLC will become an approved method for achieving this. It has been shown that the instrumentation used in this study surpasses all the performance criteria specified in

the methodology, achieving a method detection limit of 0.14 ppb, with a 500 μ L loop and 0.41 ppb with a much smaller injection volume (100 μ L). Furthermore, this has been implemented in an automated fashion with real time data analysis using the Agilent 1100 LC and 7500 Series ICP-MS demonstrating that the technique is well suited for use as a routine analytical tool.

References

1. WHO, *Guidelines for Drinking Water Quality*, 2nd Edition, Vol. 1, Recommendations of the World Health Organization, 1993
2. J. T. Creed, M. L. Magnuson, J. D. Pfaff, C. A. Brockhoff, *Journal of Analytical Chromatography*. 753, 261-267, 1996.
3. Determination of bromate in drinking waters by ion chromatography inductively coupled plasma - mass spectrometry. *USEPA Method 321.8*
4. M. Yamanaka. Specific determination of bromate and iodate in ozonized water by ion chromatography with two detection methods: Post-column derivatization and ICP-MS. *Journal of Analytical Chromatography*, 779, 259-265, 1997
5. J. T. Creed, M. L. Magnuson, C. A. Brockhoff, *Environmental Science and Technology*. 31, 2059-2063, 1997.
6. Technical Features of the ICP-MS Plasma Chromatographic Software: *Agilent Technologies Application Note* 5968-5943EN, Feb 2001
7. Practical Benefits of Abundance Sensitivity in ICP-MS: *Agilent Technologies Application Note* 5964-9024EN, Feb 2001


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Copyright© 2001
Agilent Technologies, Inc.

Printed in the USA
June 22, 2001
5988-3161EN





The Determination of As in Samples Containing High Concentrations of Chloride by ICP-MS

Technical Note

Michiko Yamanaka

Introduction

One of the main advantages of ICP-MS over ICP-AES is its relative freedom from spectral interferences. There are, however, a few cases where spectral overlap is a problem. One example is the determination of As in samples containing high (%) levels of chloride. The polyatomic ion $^{40}\text{Ar}^{35}\text{Cl}$ interferes with ^{75}As , and in addition $^{40}\text{Ar}^{37}\text{Cl}$ interferes with ^{77}Se . The interference of ArCl on Se is not a problem since a different Se isotope can be selected. As, however is monoisotopic, so no alternate isotope is available. One method to overcome such polyatomic overlaps is to resolve the interference using high resolution. In this case, however, a resolving power of >7500 is required to effectively separate As and ArCl. At this resolution, ion transmission is only $\sim 1\%$ of the transmission at unit mass resolution and so detection limits are compromised.

The 4500 ICP-MS offers the precise, routine determination of As




Fig. 1
Isotopic patterns of As, Se and ArCl

even in very high concentrations of chloride by the use of mathematical correction. Elemental (interference correction) equations resident in the 4500 ICP-MS ChemStation software correct for the interferences on both As and Se simultaneously. Most importantly, the inherent ion signal sta-

bility of the 4500 ICP-MS allows for very precise correction, making it possible for the 4500 ICP-MS to determine As at the ppb and sub-ppb level even in 5% HCl. This technical note examines the effect of increasing Cl concentration on the observed As signal, and determines the ability of the 4500 ICP-



Agilent Technologies

Innovating the HP Way

MS to measure As in HCl. The derivation and use of elemental equations is also explained.

Elemental equations

In samples containing chloride, the ion signal measured at mass 75 is the sum of ^{75}As and $^{40}\text{Ar}^{35}\text{Cl}$. This is shown in Fig. 1, which depicts the elemental ratios of As, Se and ArCl. This diagram is for graphical representation only; the intensities of the bars are arbitrary and do not relate to concentration values of each individual species. Also, Ar_2 species have been omitted for clarity. The ratio of the ArCl species at masses 75 and 77 is the same as the ratio of the Cl isotopes at masses 35 and 37. Therefore, the signal intensity of ArCl at mass 75 can be derived from the ArCl signal at mass 77. However, Se also has an isotope at mass 77, so the presence of Se will increase the observed signal at mass 77. Thus the contribution of Se to the total signal intensity at mass 77 must also be calculated using an alternate Se isotope. For Se correction, mass 82 is normally chosen, since the 78 and 80 isotopes suffer interference from Ar_2 . In practice, this correction is simply and automatically performed by the ChemStation software using elemental equations. In this example, the equation given in EPA method 200.8 (trace metals in drinking water and wastewater by ICP-MS) was used and is shown in Fig. 2.

Influence of Cl Concentration on As Signal

To study the effectiveness of using elemental equations to correct for Cl interference, a series of 1 $\mu\text{g/l}$ (ppb) As solutions were spiked with Cl at 0, 100, 200, 500 and

$$\begin{aligned} &\text{As signal intensity (mass 75)} \\ &= 1.000 * (^{75}\text{C}) - 3.127[(^{77}\text{C}) - (0.815) * (^{82}\text{C})] \\ &= 1.000 * (^{75}\text{C}) - 3.127 * (^{77}\text{C}) + 2.549 * (^{82}\text{C}) \end{aligned}$$

($^{\text{M}}\text{C}$): ICP-MS signal (counts) at mass M

Fig. 2
Elemental equation for As




Fig. 3
Influence of Cl on As signal

1000 mg/l (ppm). The solutions were measured for As, both with and without the use interference correction. A plot of observed As concentration vs. added Cl is shown in Fig. 3. Without correction, the observed As signal increased with added Cl, as expected. At 1000 mg/l Cl, the apparent increase in As was approx. 1 $\mu\text{g/l}$. Using interference correction, however, no increase in As concentration was reported, demonstrating the effectiveness of interference correction. The 4500 ICP-MS generates a very stable ion signal from both elemental and polyatomic ions, allowing precise, reproducible correction for ArCl. Ion signal stability (typically <1%RSD over 2 hours) is due mainly to the mechanical and electronics design of the 4500 ICP-MS, but also partly

due to the precise temperature control of the spray chamber ($\pm 0.1^\circ\text{C}$), enabling a very stable sample aerosol to be generated.

Determination of As in Cl Matrix

To study the effectiveness of applying interference correction to the quantitative determination of As in a chloride matrix, a series of standard solutions in a 5% HCl matrix were prepared. The As concentrations were 0, 1, 5, 10, 50, 100 and 200 $\mu\text{g/l}$. The standards were measured using the 4500 ICP-MS - the operating parameters used are given at the bottom of this page. No internal standards were used. Calibration plots for As were constructed, both with and without interference correction selected. The data was




Fig. 4-1
As calibration plots in 5% HCl without interference correction




Fig. 4-1
As calibration plots in 5% HCl with interference correction

not blank subtracted. The plots shown in Fig. 4-1 were generated without applying interference correction. Although the correlation was good, the high background due to ArCl can be seen. The scale is expanded on the right to show the low concentration points. Below 10 $\mu\text{g/l}$, the calibration plot becomes essentially flat. In contrast, when interference correction is applied (Fig. 4-2), excellent correlation and linearity were obtained, even at the 1 $\mu\text{g/l}$ level. Clearly, the combination of interference correction and good ion signal stability (elemental and polyatomic) allow the 4500 ICP-MS to precisely determine As even in a chloride matrix. The ability to detect As at sub-ppb levels in the presence of chloride is particularly important to the study of toxic metals in foods, biomedical, environmental and clinical applications. In addition, the demonstrated ability of interference correction to compensate for polyatomic overlap at low ion concentrations can be applied to other classic ICP-MS interferences. Other interferences will be studied in future Agilent Technical Notes.

Operating conditions

RF power	: 1.3 kW
Sampling depth	: 8 mm
Plasma gas	: 16 l/min.
Auxiliary gas	: 1.0 l/min.
Carrier gas	: 1.15 l/min.
Nebulizer	: Concentric type

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5963-9561E



Agilent Technologies

Innovating the HP Way



Determination of Mercury in Drinking Water Samples by ICP-MS Using EPA Method 200.8

Application Note Environmental



Abstract

The quantitative determination of mercury in drinking water samples, simultaneously with 20 other elements (as described in the EPA Method 200.8) is presented. To avoid the Hg memory effects normally experienced with conventional nebulizer/spray chamber sample introduction systems, gold was added off-line to all standards and samples to act as a complexing agent. The addition of gold and the design of the 4500 ICP-MS assure fast washout time and allow the determination of all elements, including mercury, in drinking water by a single ICP-MS run.



Introduction

EPA Method 200.8¹ describes the multi-element determination of trace metals waters and wastes by inductively coupled plasma-mass spectrometry (ICP-MS). This method provides procedures for determination of dissolved elements in ground waters, surface waters and drinking water. It may also be used for the determination of total recoverable element concentrations in these waters as well as waste waters, sludges and solid waste samples. EPA Method 200.8 is applicable to 21 elements, including mercury, enabling all required elements to be analyzed by a single technique - ICP-MS. This application note describes the additional sample preparation necessary for the successful determination of mercury.

As stated in the method, samples may be analyzed directly by pneumatic nebulization without acid digestion if the samples have been properly preserved with acid and have turbidity of < 1 NTU at the time of analysis. This total recoverable determination procedure is referred to as *direct analysis* (section 1.4 - EPA Method 200.8).

For the *direct analysis* of water samples which do not require digestion/extraction prior to analysis, and for which turbidity is < 1 NTU, the combined concentrations of inorganic and organo-mercury species in solution can be determined provided gold is added off-line to both samples and standards alike (section 1.6 - EPA Method 200.8)¹.

System Design

The 4500 ICP-MS was developed with the routine user in mind: innovative hardware and software design has resulted in the automation of routine tasks such as the optimization of ion lenses, plasma conditions, and adjustment of the ICP torch position. By making optimization independent of the operator, performance becomes more consistent, even in a multi-user environment.

A programmable computer-controlled peristaltic pump system allows for a selection of the optimum rinse time to accommodate both high sample throughput and effective elimination of memory effects. An example of a peristaltic pump program is shown in Figure 1.

The pump speed and time both before acquisition (sample uptake) and after acquisition (rinse) can be set by the user. Pumping the sample into the system at high speed reduces sample uptake time, and a stabilization time allows the system to stabilize at the normal acquisition uptake rate prior to the commencement of data acquisition. The system can also be programmed to rinse longer after standards than samples, minimizing total rinse time. A second optional rinse following acquisition is also available, enabling the use of two different rinse solutions for special applications.

Memory Interferences

Memory interferences, commonly referred to as *memory effects* arise when analyte signal is enhanced due to contribution

Peristaltic Pump Program

Before Acquisition

Uptake Speed: 0.50 rps

Uptake Time: 45 sec

Stabilization Time: 5 sec

After Acquisition (Rinse Port)

Rinse Speed: 0.50 rps

Rinse Time(Sample): 5 sec

Rinse Time(STD): 5 sec

After Acquisition (Optional Rinse)

Rinse Vial: 2

Rinse Speed: 0.50 rps

Rinse Time: 15 sec

OK Cancel Help

Figure 1.
Peristaltic Pump Program

from a previous high concentration sample. Memory effects can result from the adsorption/desorption of the analyte anywhere in the sample introduction system: Peristaltic pump tubing, nebulizer, spray chamber, torch or interface.

In acidic solution, mercury has a tendency to be retained on the glassware, particularly on the injector tip of the torch and in the spray chamber. As a result, the analyst has to program long washout times, and the aspiration of a sample containing very high levels of mercury will require the sample introduction system to be dismantled and thoroughly cleaned. The off-line addition of gold to the sample solution dramatically reduces washout times, since gold complexes with mercury presumably forming an amalgam, allowing it to be washed effectively from the system. The addition of gold to both standards and samples enables determination of mercury in the same analysis as for the other 20

elements in the EPA Method 200.8, allowing all elements to be measured in a single run by ICP-MS alone.

Instrumentation

The instrument used for this work was a 4500 ICP-MS fitted with a Babington-type nebulizer, glass spray chamber and quartz one-piece torch. An ASX-500 autosampler (CETAC Technologies Inc., Omaha, NE), was also fitted.

Reagents, Standards and Labware

The importance of good quality of reagents used was discussed in the Agilent Application Note (publication No. 5964-4277E)². For this work, a Milli-Q SP point-of-use deionized water system (Millipore, Bedford, MA) was used to prepare all standards.

Plasma gas flow rate	15.0 L/min	
Aux. gas flow rate	1.0 L/min	
Carrier gas flow rate	1.17 L/min	
RF Power	1300 W	
Nebulizer	PEEK, Babington - type	
Spray chamber	Glass, double pass	
Spray chamber temp	1 deg C	
ICP torch injector	Quartz, 2.5 mm	
Sample uptake rate	0.4 mL/min	
Sampler cone	Nickel	
Skimmer cone	Nickel	
Sampling depth	6.4 mm	
Acquisition parameters	Quantitative	Monitoring
Points/mass	3	6
Integration time/mass	0.99 sec	0.6 sec
Total acquisition time/replicate	36 sec	139 sec
Replicates	3	1
Total acquisition time/sample	109 sec	139 sec

Table 1.
4500 ICP-MS Operating Parameters

Fresh mercury standards were prepared daily from a 10 mg/L (ppm) stock solution. Gold was added off-line to all standards and

samples at the level of 100 mg/L (ppb), along with the internal standard (Tb at 50 µg/L). Both standards were prepared from




Figure 2.
Monitoring of the Mercury Washout Time

1,000 mg/L stock solutions (Inorganic Ventures, Lakewood, NJ). All standards and samples were acidified with 1% (v/v) ultrapure nitric acid (Optima Grade - Fisher Scientific, Pittsburgh, PA)

Experimental

To study the effect of gold addition on mercury washout, a 5 µg/L Hg solution was spiked with 100µg/L Au and aspirated by the 4500 ICP-MS. The washout of the mercury signal with a gold wash solution was measured by monitoring the signal in time resolved mode. Two mercury isotopes were monitored, plus bismuth for the purpose of background monitoring. Figure 2 shows the washout characteristics observed for a 5 ppb mercury standard solution. For ²⁰²Hg, the signal counts measured at readings signal counts 30 seconds apart are shown. Two orders of magnitude washout for mercury was achieved in less than one minute, demonstrating much better washout than in acidic solution without the addition of gold. Operating parameters for both the washout study and routine quantitative analysis are given in Table 1.

A graphical representation of the acquisition method printed from the Agilent ChemStation software is shown in Figure 3. This method was applied for all 21 elements listed in EPA Method 200.8, including Mercury. A mercury calibration containing standards at 0, 2 and 5 ppb Hg was constructed and is shown in Figure 4. Terbium (mass 159) was used as the internal standard (IS). As can be seen, an excellent fit was obtained, and from the slope of the curve, detection limits in the low ng/L range can be estimated.

Spectrum Acquisition Parameters

☐ Set every Mass

Integration time
per Point: 0.33 [sec]
(330.00 [msec])
per Mass: 0.99 [sec]

Acquisition Time
Acquisition: 36.35890 [sec]
Repetition: 3
Total Time: 109 [sec]

Masses: 20 40 60 80 100 120 140 160 180 200 220 240 260

Periodic Table Mass Scale

Peak Pattern: TRA (1) Full Quant (3) Semi Quant (6) Maximum (20)

OK Cancel Help Check Parameter Enter

Figure 3. Acquisition Parameters for Quantitative Determination of 21 Elements (including Mercury) by ICP-MS According to EPA Method 200.8




Figure 4. Mercury Calibration Curve (Tb used as internal standard)

EPA Method 200.8 (section 7.4.1) specifies the maximum concentration of the calibration standard to be 5 ppb.

Conclusions

The determination of mercury has been shown to be easily incorporated into the standard multi-elemental analysis protocol of water samples using ICP-MS. Mercury carry-over was readily eliminated by the off-line addition of gold. This procedure allowed the analysis of mercury in the same run as the other analytes, enabling the measurement of all required elements by a single instrument. The addition of gold to the samples at the time of collection will minimize losses of mercury in sampling vessels.

References

- ¹ EPA Method 200.8 EMMC version. Revision 5.4. EMSL Cincinnati OH 45268 - May 1994
- ² Analysis of Drinking Water and Waste Water by ICP-MS Using EPA Method 200.8. Agilent Application Note (publication No5964-4277E), December 1997

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5965-5383E



Agilent Technologies

Innovating the HP Way



Meeting UK Drinking Water Inspectorate Requirements for Trace Metals Analysis Using the 4500 ICP-MS

Application Note Environmental

Glenn D. Woods
Ed McCurdy

Abstract

Inductively Coupled Plasma Mass Spectrometry (ICP-MS) has gained wide acceptance for the determination of many trace elements, but is less frequently used for the determination of higher levels of elements, due to its perceived limitations in dynamic range and matrix tolerance.

Several applications require the measurement of trace and minor elements in the same sample, which generally means that laboratories must employ multiple techniques to perform a complete analysis. One such application is the measurement of inorganic components in drinking water, where the analyte concentrations that must be measured range from sub-ug/L (ppb) to 100's of mg/L (ppm). Traditionally, this analysis would have been carried out using a combination of Inductively Coupled Plasma Optical Emission Spectrometry (ICP-OES), Graphite Furnace Atomic Absorption Spectrometry (GFAAS) and hydride and fluorescence techniques specifically for As, Se, Sb and Hg.

This paper discusses the validation of the 4500 ICP-MS for this analysis, allowing all of the controlled elements to be measured in a single run, using a single technique. Results are presented from the performance testing of the 4500 ICP-MS for the analysis of 26 trace and minor elements in Drinking Water, using the validation and quality control criteria defined in the NS-30 "A Manual on Analytical Quality Control for The Water Industry" by the UK Water Authority.



Agilent Technologies
Innovating the HP Way

Introduction

Inductively coupled plasma mass spectrometry (ICP-MS) has been used for the determination of many trace and minor elements in various samples from diverse fields including environmental, geological, metallurgical, semiconductor, petrochemical and biomedical. One of the principal benefits which has led to the widespread use of ICP-MS has been its wide elemental coverage and excellent detection limits for a range of elements which are impossible to measure by a single alternative technique. In particular, for the measurement of trace elements at ug/L and ng/L levels, ICP-MS has often been able to replace Inductively Coupled Plasma Optical Emission Spectrometry (ICP-OES), Graphite Furnace Atomic Absorption Spectrometry (GFAAS), hydride generation and fluorescence techniques, allowing all important toxic trace elements to be measured in a single analysis.

Typically, however, ICP-MS has been perceived as inappropriate for the determination of higher levels of analytes, due to limited matrix tolerance and excessive sensitivity, which limits the upper calibration level. Although most ICP-MS instruments have the capability to measure over a wide dynamic range (8 orders of magnitude), this usually requires regular and time consuming cross calibration across two detector modes and still allows measurement only up to a few 10's mg/L.

(1) Drinking Water Quality

In the United Kingdom, drinking water quality is monitored by the Drinking Water Inspectorate (DWI), using the Water Supply (Water Quality) Regulations of

1989. These regulations list a total of 56 parameters, including colour, turbidity, organic compounds, anions and inorganic elements, which must be monitored in drinking water supplies. The list includes 21 inorganic elements, ranging from Ca (maximum concentration or Prescribed Concentration Value (PCV) of 250 mg/l) to Hg (PCV of 1 ug/L). The regulation requires that the detection limit (calculated from $4.65 \times$ the standard deviation of the blank) for each determinand must be less than one tenth of the PCV, so the detection limit of Hg, for example, must be less than 0.1 ug/L.

Under the Drinking Water Regulations, each laboratory is required to performance test the analytical systems for each parameter before that analytical system can be used for routine analysis of compliance samples. The design of the performance testing and calculation of the performance characteristics should be in accordance with the guidance given in the publication "NS-30", a manual on analytical quality control in the Water Industry.

(2) Requirements for Acquisition of Performance Testing Data

Taking into account the DWI requirements and NS-30 guidelines, the following protocol for performance testing is typical for metals analysis:

- 1) The calibration range should be such that all results fall within the range.
- 2) The calibration must have at least 3 points plus blank, to demonstrate a straight line.

3) Samples and standards must be prepared fresh, before each batch.

4) A maximum of 2 batches can be analysed on any one day, provided the instrument is switched to overnight conditions between batches.

5) Samples must be analyzed in random order.

6) Samples must be analysed in replicate, in at least 5 batches. In practice, analysis of duplicate samples in 11 batches satisfies the DWI condition on degrees of freedom.

7) A batch of samples must consist of the following: Blank, Standards (typically at concentrations appropriate to the PCV and the levels found in representative samples) and Samples of the type to be measured routinely.

(3) Requirements for Statistical Validation

After acquiring the concentration data, the results must satisfy the following QC criteria:

- 1) The maximum tolerable error of individual results should not exceed 1/10 of the PCV or 20% of the result, whichever is the greater.
- 2) The maximum tolerable standard deviation of individual results should not exceed 1/40 of the PCV or 5% of the result, whichever is the greater.
- 3) The maximum tolerable systematic error (or bias) of individual results should not exceed 1/20 of the PCV or 10% of the result, whichever is the greater.

4) The estimates of total standard deviation must not be significantly greater at the 95% confidence level than the specified maximum tolerable total standard deviation at the relevant concentration.

5) The recovery of an added spike should not be significantly less than 95%, or significantly greater than 105%.

6) The limit of detection must be lower than 1/10 of the PCV.

The performance testing protocol described in NS-30 validates not only an analytical instrument, but also the entire laboratory protocol. If any aspect of sample or calibration standard preparation is not reproducible, then the error will be observed in the between batch variation. For this reason, it is essential that sample and standard preparation techniques are well developed and carried out reproducibly.

In a large analyte suite, there may be several issues that must be addressed regarding element stability, compatibility and cross-contamination, in addition to straightforward issues of the selection of appropriate glass/plasticware to avoid element leaching or adsorption. As Hg was one of the required analytes, Au was added to the standards and samples at 100 ug/L final concentration to stabilize Hg. In the absence of Au, the Hg signal is found to be unstable and exhibits extended washout times. The internal standard (IS) mixture, which contained Be, Sc, Y, In, Tb and Tl, was added to the standards and samples automatically by means of the on-line IS addition system.

The 4500 ICP-MS was validated for the 21 controlled elements (B, Na, Mg, Al, P, K, Ca, Cr, Fe, Mn, Ni, Cu, Zn, As, Se, Ag, Cd, Sb, Ba, Hg and Pb) in drinking water, according to the NS-30 protocol. At the same time, the 4500 ICP-MS was also validated for a further 5 elements (Li, V, Co, Sr and Sn). Whilst NS-30 lists 21 inorganic components which must be monitored, additional elements may also be measured, provided that the NS-30 protocol has been followed and validation requirements have been met. Thus, each lab can extend the validated elemental range of the technique to meet their own needs and also their customer's specific requirements.

Instrumentation

The ICP-MS instrument used was a standard Hewlett-Packard 4500 ICP-MS, in conjunction with a Cetac ASX-500 random access autosampler. The 4500 ICP-MS was configured with the standard sample introduction system, which consists of a Agilent High Solids nebuliser, quartz spray chamber, quartz one-piece torch and Ni sample and skimmer cones. The standard 4500 ICP-MS sample introduction system is ideally suited to the analysis of high-matrix environmental samples, as discussed below:

• Low Sample Uptake Rate

The sample uptake rate of the 4500 ICP-MS is only 0.1 to 0.4mL/min, compared to between 0.8mL/min and 2.5mL/min, which is typical for conventional ICP-MS or ICP-OES instrumentation. This lower solution flow rate means that matrix loading on the plasma is minimised. In turn, this means that the plasma can dry,

decompose, dissociate, atomise and ionise the sample analytes and matrix more efficiently, resulting in reduced spectral interferences and reduced sample matrix effects.

The matrix tolerance capabilities of the Babington-type nebuliser are well known, but commercially available versions of these nebulisers tend to require very high solution flow rates and can be prone to pulsing and poor washout. The Agilent High Solids nebuliser is a modified Babington-type design, manufactured for the 4500 ICP-MS. It features a wide, square section groove cut into an angled front face and optimised to produce a stable aerosol at low sample uptake rates. The design of the groove ensures that no sample solution is trapped on the nebuliser face, which in turn prevents spiking during washout due to sample re-nebulisation.

• Low Polyatomic Ion Formation

Some of the most troublesome interferences in ICP-MS are caused by the overlap of polyatomic ions formed from combinations of oxygen with the argon carrier gas or matrix ions. If the sample introduction area, in particular the spray chamber, is maintained at a constant low temperature (0-2 °C), the water vapour loading in the sample aerosol can be reduced and so the cooling effect of the aerosol on the plasma is reduced. This results in a higher plasma temperature and gives more efficient breakdown of oxide species.

The normal method for monitoring the likely impact of oxide overlaps in the ICP-MS spectrum is by measuring cerium. Of all elements,

cerium has one of the highest metal-oxide (MO) bond strengths. The CeO/Ce ratio can therefore be used as a “worst-case” indicator of the likely interference problems an ICP-MS instrument will suffer in real sample analyses, where high levels of elements such as S, Cl, Al, Mg, Ca, etc. (all of which will form oxide species at much lower levels than Ce) might be encountered.

On the 4500 ICP-MS, the typical CeO/Ce ratio is <0.5%, partly due to the use of a cooled spray chamber, but also as a result of the use of a wide bore injector (2.5mm diameter) in the plasma torch. The wide injector diameter ensures that the sample aerosol is relatively diffuse in the central channel of the torch and so the plasma energy can decompose the sample matrix more efficiently, breaking up any refractory oxide species. Furthermore, the wide torch injector reduces gas velocity through the central channel giving a longer sample residence time in the plasma, which also assists matrix oxide decomposition.

• Linear Calibration

In order to determine high and low level elements in the same run, an ICP-MS instrument should have a wide dynamic range. Most ICP-MS instruments achieve this using a detector that can be operated in both pulse-count and analog mode for the measurement of low intensity and high intensity signals respectively. The 4500 ICP-MS has the capability to construct a single linear calibration line for all elements, from ng/L to 100's mg/L levels, without regular adjustment of detector or tuning parameters. The cross-calibration of the 2 detector modes is achieved using

a single solution, analysed once, and the calibration is stable over long periods of analysis.

Standard and Sample Preparation

Calibration stock standards were obtained from BDH and a series of working stock solutions was prepared, each stock containing compatible groups of the analytes. Ca, Na, Mg, K, Al, Fe, Cu and Zn were prepared from 10,000 mg/L stock solutions while the other elements were prepared from 1,000 mg/L single element stocks. Calibration standard solutions were prepared at concentrations appropriate to the levels normally found in the sample types to be tested. Hg and Se were prepared in a separate stock from the other elements. In order to analyze Ag, all samples and calibration standards were prepared in 1% v/v HNO₃ and 0.5% v/v HCl solution.

Two tap waters, one river derived and the other borehole derived, were analyzed as samples and two Blanks, two Analytical Quality Control (AQC) solutions and two Spiked solutions were prepared. Two vials were prepared for each blank, sample, spike and AQC. All the standard and sample solutions were freshly prepared for each batch.

The Internal Standard solution, which contained Be, Sc, Y, In, Tb and Tl, was added to the samples and standards by means of the on-line IS addition system of the 4500 ICP-MS. After on-line dilution in the sample stream, the final concentration of the internal standards was approximately 0.1mg/L, with the exception of Be, which was 10x higher to compensate for its low degree of ionisation.

Automatic setup of the pulse count/analog (P/A) factor of the detector was carried out using a tuning solution which contained Ca, B, P, Fe, Ba, Na, Mg, Al, K, Cu Zn and Sr at concentrations between 0.1mg/L and 100mg/L.

The appropriate concentration for each element was selected, to give an acceptable count-rate in both detector modes.

Experimental

(1) Instrumental Conditions

After turning on the plasma and allowing 15 minutes for the system to warm up, the instrument was tuned by using 3 of the elements present in the internal standard solution (Be, Sc and Tl).

The instrument was tuned by monitoring mass 9, 45 and 205, to give a sensitivity of around 200,000, 200,000 and 300,000 counts per second, respectively. This represents at least a factor of 10 lower sensitivity than can be achieved when the instrument is tuned for maximum sensitivity. i.e. the system was “detuned”. With a system tuned for maximum sensitivity, the higher level analytes such as Na and K would be “over-range”, i.e. above the maximum measurable concentration of the instrument.

For the successful analysis of environmental samples by ICP-MS, several sample introduction and plasma parameters must be considered, namely RF power, carrier gas flow, sample uptake rate and sampling depth. Higher plasma temperature and longer residence time of the analytes are critical parameters in order to decompose heavy matrices effectively and to minimize oxide formation. Table 1 shows the parameters used for routine

Parameter	Setting
Forward power	1350W
Peri-pump speed (analysis)	0.1 rps
Peri-pump speed (uptake/rinse)	0.3 rps
Sampling depth	8.5 mm
Carrier gas flow	1.25 L/min
Rinse time	30 sec
Acquisition Time	73 sec
Number of repeats	3

Table 1
4500 ICP-MS Operating Conditions for the Analysis of High Matrix Samples

1. Blank 1	13. Tap water A + Spike (L) 1
2. Blank 2	14. Tap water A + Spike (L) Hg/Se 1
3. AQC (L) 1	15. Tap water A + Spike (L) 2
4. AQC (L) Hg/Se 1	16. Tap water A + Spike (L) Hg/Se 2
5. AQC (L) 2	17. Tap water B 1
6. AQC (L) Hg/Se 2	18. Tap water B 2
7. AQC (H) 1	19. Tap water B + Spike (H) 1
8. AQC (H) Hg/Se 1	20. Tap water B + Spike (H) Hg/Se 1
9. AQC (H) 2	21. Tap water B + Spike (H) 2
10. AQC (H) Hg/Se 2	22. Tap water B + Spike (H) Hg/Se 2
11. Tap water A 1	23. Drift
12. Tap water A 2	24. Drift Hg/Se

polyatomics. Although HNO₃ and HCl were intentionally added to all samples in order to stabilise the solutions and allow the analysis of Ag, interference correction worked well and excellent results were obtained for all of these elements.

analysis of environmental samples using the 4500 ICP-MS.

(2) Sample Analysis

Each analytical batch consisted of the blanks, samples, spikes and AQC's shown below. Following analysis of the calibration standards, the sample batch was analysed in random order. A different random order was used for each batch, ensuring that no bias was introduced by running the test solutions in a constant order. Drift check solutions, which do not form part of the validation sequence, were analyzed at the end of each batch.

The analysis of Hg and Se was separated from the other elements for two reasons:

1) Following successful validation of the method, the mixed calibration standards should be stable for a week. However, Hg would not be expected to be stable over this period, so the Hg standards would need to be prepared fresh daily.

2) The Ca standard solution contained a small amount of Se. This contamination introduced a bias into the Se calibration at low level, so Se was calibrated using a standard mix that contained no Ca.

With regard to Fe, As and V, which are considered difficult elements to analyse by ICP-MS due to polyatomic overlaps from ArN, ArCl and ClO respectively, an interference correction equation was used to correct for background contributions from these

Results and Discussion

(1) Calibration Curves

Figures 1 shows the calibration curves of some of the major elements, determined at concentrations up to 300mg/L. Figure 2 shows calibrations for some of the trace elements, calibrated at low ug/L levels. Linear calibrations were obtained in all cases.




Figure 1
Calibrations for Selected Major Elements




Figure 2
Calibrations for Selected Trace Elements

(2) NS-30 Performance Testing Results

Once quantitative results had been obtained from all of the batches, the statistical processing defined in NS-30 was carried out. Tables 2 and 3 show the calculated results of one high and one low concentration element found in the tap water samples (Na and Hg respectively)

Na (23) IS – Sc	Blank	AQC(L)	AQC(H)	Sample 1	Spike 1	Sample 2	Spike 2
Mean (mg/L)	-0.7005	53.0727	123.1818	34.0273	155.954	44.0409	95.8818
M1	6.0556	16.3264	32.9273	8.1404	67.2455	9.9548	19.7033
M0	0.0002	2.6527	13.0909	0.7782	10.5909	1.4223	5.8182
F value	26122.086	6.1546	2.5153	10.4607	6.3494	6.9992	3.3865
Significant	p=0.001	p=0.01	NS	p=0.001	p=0.01	p=0.01	p=0.05
Sw	0.0152	1.6287	3.6181	0.8821	3.2544	1.1926	2.4121
Sb	1.7400	2.6147	3.1493	1.9186	5.3223	2.0655	2.6349
St	1.7401	3.0805	4.7968	2.1117	6.2384	2.3851	3.5722
F 0.05	1.8307	1.7202	1.6228	1.7522	1.7202	1.7202	1.6435
Calc. F	0.2153	0.6748	0.6065	0.3171	0.6401	0.4045	0.5552
Degree F	10	13	17	12	13	13	16
Bias OK?		Pass	Pass				
SD OK ?		Pass	Pass	Pass	Pass	Pass	Pass
Recovery		107.55	103.24		101.61		103.68
95% Conf. Limits		2.83	1.55		2.48		2.79
Recovery OK ?					Pass		Pass
Limit of Detection	0.077 mg/L						
LOD OK?	Pass						

Table 2
NS-30 Performance Test Results for Na

Hg (202) IS – Au	Blank	AQC(L)	AQC(H)	Sample 1	Spike 1	Sample 2	Spike 2
Mean (mg/L)	-0.0011	0.2121	1.0650	0.0105	1.0623	0.0138	0.2295
M1	0.0001	0.0004	0.0011	0.0001	0.0012	0.0002	0.0004
M0	0.0002	0.0003	0.0006	0.0001	0.0009	0.0002	0.0007
F value	1.2233	1.4911	1.8473	2.3750	1.4631	1.2303	1.8405
Significant	NS	NS	NS	NS	NS	NS	NS
Sw	0.0127	0.0163	0.0244	0.0077	0.0292	0.0134	0.0260
Sb	0.0000	0.0081	0.0159	0.0064	0.0140	0.0045	0.0000
St	0.0127	0.0182	0.0291	0.0100	0.0324	0.0141	0.0260
F 0.05	1.5558	1.5705	1.5865	1.6228	1.5705	1.5558	1.5705
Calc. F	0.2562	0.5278	0.2990	0.1589	0.3711	0.3194	1.0840
Degree F	21	20	19	17	20	21	20
Bias OK?		Pass	Pass				
SD OK ?		Pass	Pass	Pass	Pass	Pass	Pass
Recovery		106.61	106.61		105.18		107.841
95% Conf. Limits		3.57	1.23		1.07		3.4205
Recovery OK ?					Pass		Pass
Limit of Detection	0.064 ug/L						
LOD OK?	Pass						

Table 3
NS-30 Performance Test Results for Hg

Tables 4 and 5 show the summary results of all elements. In every case, all of the statistical analysis indicated that the 4500 ICP-MS gave acceptable results under the requirements of the protocol defined in NS-30.

Elements	PCV	Units	LOD	AQC	Recovery	Spike	Recovery	95% SD
Li		ug/L	0.328	40	102.52	40	100.00	2.48
B	2000	ug/L	99.453	400	104.41	400	91.34	4.50
Na	150	mg/L	0.077	50	106.15	50	103.68	2.79
Mg	50	mg/L	0.064	10	102.77	10	105.42	2.43
Al	200	ug/L	1.562	200	102.34	200	100.68	2.06
P	2200	ug/L	4.524	500	97.07	500	98.34	3.44
K	12	mg/L	0.021	6	104.97	6	98.91	1.56
Ca	250	mg/L	0.338	100	103.32	100	97.73	2.70
V		ug/L	0.606	10	101.09	10	100.10	2.74
Cr	50	ug/L	1.332	10	104.09	10	98.46	3.64
Fe	200	ug/L	14.692	200	98.84	200	98.94	2.90
Mn	50	ug/L	0.900	50	100.45	50	101.69	2.40
Co		ug/L	0.052	10	102.36	10	105.24	1.02
Ni	50	ug/L	0.869	10	108.91	10	105.58	2.05
Cu	3000	ug/L	1.173	500	101.78	500	100.60	0.71
Zn	5000	ug/L	2.632	500	107.12	500	102.08	1.34
As	50	ug/L	1.067	10	93.13	10	98.51	2.49
Se	10	ug/L	0.837	2	102.77	2	108.95	5.96
Sr		ug/L	1.062	120	104.47	120	90.34	3.29
Ag	10	ug/L	0.055	3	102.47	3	100.17	2.09
Cd	5	ug/L	0.130	1	105.91	1	104.59	3.29
Sn		ug/L	0.107	10	102.86	10	103.53	1.88
Sb	10	ug/L	0.032	2	100.73	2	101.46	1.20
Ba	1000	ug/L	1.029	200	101.93	200	101.03	1.15
Hg	1	ug/L	0.064	0.2	106.05	0.2	107.84	3.42
Pb	50	ug/L	0.130	50	100.52	50	100.00	1.23

Table 4
NS-30 Performance Test Summary Results For All Elements Low AQC & Spike

Elements	PCV	Units	AQC	Recovery	Spike	Recovery	95% SD
Li		ug/L	180	101.14	180	100.15	2.02
B	2000	ug/L	2000	97.77	2000	97.40	1.85
Na	150	mg/L	120	102.65	120	101.61	2.48
Mg	50	mg/L	50	103.95	50	103.80	2.38
Al	200	ug/L	1800	99.81	1800	100.53	1.41
P	2200	ug/L	2200	98.74	2200	103.53	1.70
K	12	mg/L	12	103.97	12	101.31	1.26
Ca	250	mg/L	250	100.96	250	93.62	1.20
V		ug/L	50	98.84	50	97.70	2.26
Cr	50	ug/L	50	99.78	50	96.95	2.36
Fe	200	ug/L	1600	97.78	1600	95.99	2.94
Mn	50	ug/L	120	99.13	120	99.78	1.88
Co		ug/L	50	98.87	50	98.52	0.92
Ni	50	ug/L	50	101.14	50	98.76	1.45
Cu	3000	ug/L	3000	99.73	3000	98.17	0.90
Zn	5000	ug/L	5000	100.72	5000	98.47	1.36
As	50	ug/L	50	93.36	50	96.84	2.38
Se	10	ug/L	10	100.73	10	105.16	3.71
Sr		ug/L	600	100.48	600	94.38	0.76
Ag	10	ug/L	10	103.91	10	99.38	1.63
Cd	5	ug/L	5	103.58	5	102.52	1.71
Sn		ug/L	50	102.88	50	103.04	2.11
Sb	10	ug/L	10	100.50	10	100.65	0.61
Ba	1000	ug/L	1000	100.23	1000	98.48	1.08
Hg	1	ug/L	1	106.50	1	105.18	1.07
Pb	50	ug/L	90	99.70	90	100.26	1.12

Table 4
NS-30 Performance Test Summary Results For All Elements High AQC & Spike

Conclusions

The 4500 ICP-MS was applied to the analysis of drinking water, following the methodology defined in NS-30. Linear calibrations were obtained for trace elements at low and sub-ug/L levels, in the same acquisition as the major elements at 100's mg/L.

All QC criteria were met, and the system was validated for 21 NS-30 elements plus an additional 5 elements. Operating in a reduced sensitivity mode allowed for the measurement of high concentration elements, such as Na and Ca, while the wide dynamic range of the instrument still allowed detection limit criteria for trace elements such as Hg to be met.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5968-7602E



Agilent Technologies

Innovating the HP Way



The Determination of Selenium by ICP-MS, Using the ShieldTorch

Application Note

Ed McCurdy
Glenn Woods



Selenium is an element of considerable interest in environmental and biomedical applications. Several instances of selenium deficiency and toxicity in agricultural livestock have been reported, whilst there is increasing interest in Se as it relates to human physiology.

Se is an essential trace element in humans, but there is a narrow range between Se deficiency and Se toxicity. An excess of Se leads to seleniosis, whilst deficiency has been implicated in coronary heart disease, arthritis, cirrhosis and cancer. Se is available in several forms as a dietary supplement, many of which are derived from yeasts.

The determination of Se by ICP-MS has been one of the most enduring challenges for the technique, due to a combination of factors.



Agilent Technologies
Innovating the HP Way

Firstly, Se is typically present at relatively low levels in natural (uncontaminated) biological materials and the total concentrations present may comprise several different forms of Se, which can have an impact on certain methods of analysis.

Secondly, whilst the Ar plasma is probably the most capable source yet devised for atomic spectrometry, it does suffer from certain limitations with respect to the ionisation environment and the background spectrum. In the case of Se, these two factors conspire to give a low analyte signal level and a relatively high blank signal.

Se has a high first ionisation potential, which means that a smaller proportion of the Se atoms in the plasma are converted into ions. The signal for Se is around 10% of the signal which would be obtained for a fully ionised element, so the signal to noise is about 10x poorer than it could be. Furthermore, all of the Se isotopes are potentially overlapped by polyatomic interferences from plasma or matrix-based peaks, which restricts the choice of Se isotopes which can be used for quantitation. The available Se isotopes and their respective potential overlaps are shown in Table 1.

Clearly, many of these potential interferences are Ar-based, which makes them difficult to avoid in an Ar plasma. Several techniques have been suggested to alleviate the problems associated with these overlaps, each of which has its own advantages and limitations.

The various techniques which have been used are discussed in the following paper, together with

Se Isotopic Mass	Isotopic Abundance (%)	Potential Overlap(s)
74	0.89	$^{36}\text{Ar}^{38}\text{Ar}$
76	9.36	$^{38}\text{Ar}^{38}\text{Ar}$ and $^{36}\text{Ar}^{40}\text{Ar}$
77	7.63	$^{40}\text{Ar}^{37}\text{Cl}$
78	23.78	$^{38}\text{Ar}^{40}\text{Ar}$
80	49.61	$^{40}\text{Ar}^{40}\text{Ar}$
82	8.73	^{82}Kr and $^{81}\text{Br}^1\text{H}$

Table 1.
Selenium Isotopic Abundances and Potential Interferences

a novel approach which relies on the selective ionisation of the analyte in a plasma environment which is optimised for the reduction of the Ar-based polyatomic ions.

Hydride generation can be used for Se measurements, either utilising a stand-alone hydride generation instrument, or using a hydride generation accessory as the sample introduction method for ICP-MS. The transport efficiency of hydride generation is certainly improved over the use of a conventional spraychamber, but there are several chemical limitations to the technique, most notably that all of the Se must be converted to a form which will form hydrides. In addition, with hydride generation-ICP-MS, the main problem of Ar_2 overlaps on 4 of the Se isotopes is not addressed.

Alternative plasmas have been used, particularly He-based microwave induced plasmas (MIP). This solution offers the dual benefit of a more highly ionising plasma environment (as He has a higher ionisation potential than Ar), together with the removal of the Ar-based polyatomic species. However, these systems are expensive to run, and are not widely available or established as commercial instrumentation.

In common with most polyatomic interferences, the Ar-based overlaps on the Se isotopes can be separated from the analyte peak through the use of a high-resolution magnetic sector mass spectrometer. In addition to offering a very expensive and non-routine solution to the problem, high-resolution mass spectrometers do not address the fundamental problem of the presence of the interfering peak. In order to separate a polyatomic from an adjacent analyte peak, a theoretical resolution is normally calculated, based on equal heights for the 2 peaks and separation only to the 10% valley definition. However, in the case of a trace analyte (such as Se) adjacent to a major interference (such as Ar_2), these calculations are not appropriate. A much higher resolution setting will typically be required and the transmission and sensitivity will therefore be severely compromised. Typically, operation at resolutions of several thousand (as needed even for the separation of equal height peaks) will result in a reduction in transmission of around 95%, i.e. only around 5% of the original signal remains.

Techniques have been investigated for the removal of various polyatomic species using selective collisions with a gas which is introduced into the mass




Figure 1.
Schematic of Shield Torch System on the 4500 ICP-MS Series

Forward Power	1000 W
Sampling Depth	13 mm
Carrier Gas Flow	1.2 L/min
Blend Gas Flow	0.8 L/min
Ion Lens Tuning	Typical Cool Plasma Settings
Acquisition Time	21 seconds/repeat
Number of Repeats	3 (10 for LOD blank)

Table 2.
4500 ICP-MS Operating Conditions for Se Analysis

spectrometer vacuum chamber. These techniques have not, as yet, proved robust in their ability to decompose specific polyatomics without the introduction of numerous additional cluster ions, which can result in an increase in the overall complexity of the spectrum. Furthermore, collision cells have been shown to be highly susceptible to contamination from matrix components, resulting in poor tolerance to natural samples. Whilst an individual poly-atomic ion can be attenuated, albeit

usually with severe attenuation of the analyte signal, it has been demonstrated that different optimum conditions are required for each poly-atomic ion, so the technique is appropriate only on a single-element batch processing basis.

A simple and elegant solution to the problem of Se analysis has been developed by Agilent Technologies application staff, working with the ShieldTorch System on the 4500 ICP-MS.

The ShieldTorch system comprises a grounded metal plate which lies between the plasma RF load coil and the plasma torch, as shown in Figure 1. This has the effect of removing the capacitive coupling between the coil and the plasma, so the plasma is held at the same potential (ground) as the mass spectrometer interface.

Combined with changes to the operating parameters of the plasma (gas flows and sampling depth), which reduce the temperature of the central channel of the plasma, this leads to a background spectrum which is virtually free from Ar-based peaks. Since Se has a relatively high first ionisation potential, it might be expected that reducing the plasma temperature would dramatically reduce the Se signal. However, it is straightforward to optimise the 4500 ICP-MS to give minimal Ar₂ signal whilst retaining good sensitivity for Se. The principal operating parameters are outlined in Table 2.

Under these conditions, the Ar₂ background is much reduced, as shown in Figure 2, whilst Se can be measured at the low ppb level, also shown in the same Figure. From these spectra, it is clear that the Se isotopic pattern matched the theoretical isotopic abundance, indicating that the Ar₂ polyatomics have been effectively removed. This analytical methodology was applied to the measurement of Se in HCl. With the robustness of the higher-power Cool Plasma of the 4500 ICP-MS, this change in matrix did not require any further optimisation or re-tuning of the plasma parameters or ion lenses.

For the quantitative measurement of low concentrations of analytes,




Figure 2.
Selenium Isotopic Pattern in 10ppb Standard and Blank (inset)

Isotope	Dwell time/point (s)	Dwell time/mass (s)
76	2.0	6.0
77	2.0	6.0
78	0.4	1.2
80	0.2	0.6
82	2.0	6.0

Table 3.
Integration Times Used for Selenium Analysis

it is normal to concentrate the integration time on the peaks of interest. For this reason, a peak jumping acquisition was used, where the quadrupole settles only at the top of each set mass. This ensures that the best signal to noise is achieved, although the spectral information is much more limited. The integration times used for the Se isotopes in this study are shown in Table 3. Different integration times were used, in approximately inverse proportion to the isotopic abundance of the individual isotopes, so approximately equal counts (in raw counts) were collected for each.

The calibrations obtained for the Se isotopes at mass 76, 78, 80 and 82, measured in a matrix of 4% HCl, are shown in Figures 3 to 6. In each case, the calibration was in the range from 0ppb to 5ppb. The linearity for each calibration was 1.000.

No blank subtraction was used, no interference correction was required and no internal standard was added.

In HCl, a further possible polyatomic peak might be encountered, due to the formation of $^{40}\text{Ar}^{37}\text{Cl}$, which would overlap the

Se isotope at mass 77. Whilst there are 4 Se isotopes which are free from interference (as shown in Figures 3 to 6), it would be useful if a further isotope could be measured as well. A greater number of available isotopes increases the possibility of carrying out stable isotope tracer analyses in biological systems, as well as extending the possibility of conducting isotope dilution analysis to improve the accuracy of measurements at ultra-trace levels.

The fit of the Se isotopic template to the spectrum for 10ppb Se in 4% HCl is shown in Figure 7. Inset in this spectrum is the spectrum for the blank 4% HCl, on the same intensity scale. The residual ArCl peak at mass 77 is equivalent to about 3ppb, suggesting that the ^{77}Se isotope might be analytically useful at the sub-10ppb level, in addition to the other 4 Se isotopes shown in Figures 3 to 6.




Figure 3.
Calibration for Selenium 76




Figure 4.
Calibration for Selenium 78

The calibration for Se at mass 77 is shown in Figure 8. As with all of the other calibrations shown in Figures 3 to 6, this calibration was generated using the method of standard additions, so the intercept on the y-axis indicates the contribution from the ArCl background. Even in the presence of this background, an acceptable calibration was obtained at the sub-5ppb level.

The 4% HCl Blank was repeated 10 times and the detection limit for each Se isotope was calculated based on the multi-point calibration in 4% HCl. The 3 sigma detection limits calculated are shown in Table 4. Note that these are conservative detection limits, as they are based on the analysis of a matrix blank (4% HCl) analysed as a real sample, immediately following the analysis of the calibration standards. Detection limits a factor of 2-5 lower than these values have been obtained under optimum analytical conditions. Also shown in Table 4 are the background equivalent concentrations for each of the Se isotopes, indicating that backgrounds well below 100ppt were achieved for the 3 Se isotopes.

To be useful in real analysis, it must be demonstrated that good precision can be obtained at analytically useful concentrations. The calibration graphs show the good precision obtained on each calibration standard and Table 4 shows the actual precision obtained at the 1ppb level.

The analysis of Se is of increasing interest in human nutrition and toxicology. The ability to measure trace Se concentrations without resorting to separate analytical techniques is beneficial. The




Figure 5.
Calibration for Selenium 80




Figure 6.
Calibration for Selenium 82

Shield Torch System of the 4500 ICP-MS allows operation of the ICP-MS under optimum conditions for Se analysis, without the limitations in matrix tolerance

associated with collision or reaction cells. The possibility of mass spectrometric determination of multiple Se isotopes, allowing stable isotope tracers to be used,

is an exciting development in the growing applications for higher power cool plasma analysis using the ShieldTorch System on the 4500 ICP-MS.




Figure 7.
Selenium Isotopic Pattern in 4% HCl Blank (inset) and 10ppb Standard




Figure 8.
Calibration for ^{77}Se in 4% HCl

Se Isotope	BEC (ppt)	3s LOD (ppt)	Precision at 1ppb (%)
76 Se	172.8	38.04	2.61
77 Se	2880	81.12	2.47
78 Se	89.5	49.14	5.24
80 Se	29.6	59.82	4.97
82 Se	31.1	59.7	2.35

Table 4.
Summary of Detection Limit Data for Selected Se Isotopes

Ed McCurdy is a Sales Specialist and Glenn Woods is an Application Chemist both at Agilent Technologies, Inc. Manchester, UK

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5968-7598E



Agilent Technologies

Innovating the HP Way



Specific Determination of Bromate and Iodate in Ozonized Water by Ion Chromatography with Two Detection Methods : Postcolumn Derivatization and ICP-MS Detection

Submitted to : Journal of Chromatography A, 789, 259-265 (1997)

Application Note Environmental

Michiko Yamanaka

Abstract

A specific determination for bromate, iodate and other halogen anions in drinking water by direct injection using ion chromatography (IC) with either inductively coupled plasma mass spectrometry (ICP/MS), or the postcolumn derivatization is described. The advantages of ICP/MS as an element selective detector was evaluated for bromate and iodate by considering the comparison with the postcolumn derivatization. Samples were directly injected into the IC column, and halogen anions were separated. The eluates were directly introduced into ICP/MS and detected at 79 and 127 amu. The detection limit ($S/N = 3$) for bromate and iodate with injection of 0.5 mL were 0.45 $\mu\text{g Br/L}$ and 0.034 $\mu\text{g I/L}$, respectively. The IC combined with ICP/MS was applied to the simultaneous determination of bromate, bromide and other halogen anions in raw and ozonized water. Good agreement was obtained for the determined values by IC-ICP/MS and postcolumn derivatization. Furthermore, several bromine species different from bromate or bromide were detected by IC-ICP/MS.



Agilent Technologies
Innovating the HP Way

Introduction

Bromate can be formed by the oxidation of bromide ions during ozonation and possibly by other oxidants in water treatment [1-4]. Bromate has been estimated as a potential carcinogen, and has been classified in Group 2B by the International Agency of Research on Cancer (IARC). The concentration of bromate in drinking water associated with an excess lifetime cancer risk of 10^{-5} corresponds to 3 µg/L [5]. The World Health Organization (WHO) recommended the provisional guideline value of 25 µg/L which is associated with an excess lifetime cancer risk of 7×10^{-5} , because of limitation in available analytical and treatment methods [5].

Ion chromatography (IC) with a pretreatment method [6] or an on-line preconcentration method [7-8] has been reported for the determination of trace bromate. However, the peak of bromate at the detection limit level will often vanish in that of chloride which is always present in water at a level of three orders of magnitude higher. The authors have developed a sensitive and selective ion chromatographic determination method of bromate with postcolumn conversion into tribromide by hydrobromic acid [9]. Sub-µg/L of bromate in water was determined by using the developed postcolumn derivatization. Furthermore, other disinfectant by-products such as chlorite and iodate were also detected with similar detection limits.

On the other hand, inductively coupled plasma mass spectrometry (ICP/MS) combined with liquid chromatography or IC (LC-ICP/MS or IC-ICP/MS) is an effective

technique for the speciation study of metallic and organometallic species because of its element selectivity and sensitivity. The combined technique has been also applied to the determination of halogen species, especially, iodine that can be sensitively detected by ICP/MS [10-14].

In the present work, the specific determination of bromate, iodate and other halogen species in drinking water by direct injection using IC with ICP/MS and the postcolumn derivatization is described. The advantages of ICP/MS as an element selective detector was evaluated for bromate and iodate by considering the comparison with the postcolumn derivatization. Furthermore, the IC-ICP/MS system was applied to the simultaneous determination of halogen anions in raw and ozonized water.

Experimental

Reagents

All reagents used were purchased from Wako Pure Chemical Industries (Osaka, Japan). Stock solutions (1000 mg/L as elements) for each anion were prepared by dissolving with pure water and stored in refrigerator. Analytical solutions were prepared by diluting the stock solution to the required concentration just before use. Pure water was obtained from Milli-Q system (Nihon Millipore, Tokyo, Japan).

Instrument

Ion chromatograph used in this experiment was Model IC7000S (Yokogawa Analytical Systems Inc., Japan) equipped with a UV/VIS detector, and ICP/MS was Model 4500 (Agilent Technologies, Inc. USA). Excelpak ICS-A23 and ICS-A13 (7.6 mm x 4.6 mm i.d.

each, Yokogawa Analytical Systems Inc.) were chosen as separation columns. ICS-A23 and ICS-A13 were packed with hydrophilic and semi-hydrophilic anion exchange resin with 0.05 mequiv./g of dry, respectively.

IC-ICP/MS

Ion chromatograph and ICP/MS were connected by 500 mm x 0.3 mm i.d. of ETFE tube. Ammonium carbonate was chosen as a mobile phase. Ammonium salt was used to prevent a salt deposition and clogging at sampling orifice of ICP/MS caused by sodium in a mobile phase. The operating conditions of ICP/MS are described in Table 1.

Postcolumn derivatization

Two Excelpak ICS-A13 columns in series were chosen to separate the halogen species according to the previous paper [9]. The operating conditions of the postcolumn derivatization are described in Table 2.

Results and Discussion

Separation of halogen anion

First of all, the separation of halogen anions using ICS-A13 as the separation column according to previous paper [9] was examined to establish appropriate separation conditions. The chromatography behaviour of iodide on anion-exchange resins has been described [15]. In this experiment, however, the peak of iodide showed a broad and tailing shape, while bromate, bromide and iodate showed good peak shapes. It was also noted that the retention time was long (more than 30 min) and depended on its concentration. It was not drastically improved in spite of a series of change of mobile phase.

RF power	1300 W
RF reflected power	<1 W
Plasma gas	16.0 L/min
Auxiliary gas	1.00 L/min
Carrier gas flow	1.06 L/min
Sampling depth	7.5 mm
Mass	79 amu (Br), 127 amu (I)
Integration time	0.5 sec
Number of scans	1

Table 1
Operational conditions of ICP-MS.

Ion Chromatography	
column	Excellpak ICS-A13 x 2
mobile phase	5×10^{-3} mol/L Na_2CO_3 / 1×10^{-3} mol/L NaHCO_3 , 1.0 mL/min
column temp.	40 °C
injection volume	0.1 mL
Reagent preparation	
reagent	5 mg/L NaNO_2 in 0.5 mol/L NaBr, 1.0 mL/min
preparation reagent	0.75 mol/L H_2SO_4 , 1.0 mL/min
cation hollow fiber	5 m
Postcolumn derivatization	
reaction coil	3 m x 0.5 mm i.d.
reaction temp.	40 °C
detection	UV-268 nm

Table 2
Operating conditions of postcolumn derivatization




Fig. 1
Chromatograms of halogen anion standards by IC-ICP/MS. Peaks: BrO_3^- (10 $\mu\text{g/L}$), Br^- (10 $\mu\text{g/L}$), IO_3^- (1 $\mu\text{g/L}$), and I^- (2 $\mu\text{g/L}$).
Experimental conditions: column, Excellpak ICS-A23; mobile phase, 0.03 mol/L $(\text{NH}_4)_2\text{CO}_3$; flow rate, 1.0 mL/min; column temperature, 40 °C; injection volume, 0.5 mL.


Therefore, ICS-A23 was used on behalf of ICS-A13 because of increase of hydrophilicity of packing materials. The use of the ICS-A23 with 0.03 mol/L ammonium carbonate solution (pH 9.2) made it possible to improve peak shape and retention time of iodide. Fig. 1 shows the chromatograms of halogen anion standards by direct injection with a 0.5 mL sample. Four halogen anions were completely separated within 8 minutes. The analytical time will be reduced by increasing the concentration or pH of mobile phase. For the purpose of this work, that is the simultaneous separation of many halogen species, these separation conditions were a compromise between the number of determinants and analytical time.

Evaluation of IC-ICP/MS

The linearity, detection limits and repeatability for bromate and iodate were determined. The linear range of bromate and iodate was more than 3 orders of magnitude, from 0.5×10^{-3} to 1 mg/L and from 0.1×10^{-3} to 1 mg/L, respectively. Equally, good linearity for bromide and iodide was also obtained. The detection limits ($n = 3$) for bromate, bromide, iodate and iodide were 0.45 $\mu\text{g/L}$, 0.44 $\mu\text{g/L}$, 0.034 $\mu\text{g/L}$ and 0.051 $\mu\text{g/L}$, respectively. The repeatability ($n = 6$) for 1.0 $\mu\text{g/L}$ of bromate, 1.0 $\mu\text{g/L}$ of bromide, 0.1 $\mu\text{g/L}$ of iodate and 0.2 $\mu\text{g/L}$ of iodide was 8.1 %, 8.0 %, 6.2 % and 6.8 %, respectively.

In the standard method for water quality, the quantitative limit is determined by the sample concentration which gives 10 % of relative standard deviation (RSD) [16]. The quantitative limits of this method were obtained from the

a) BrO_3^-



b) IO_3^-




Fig. 2
Relationships between the RSD and sample concentration for bromate a) and iodate b). Experimental conditions are same as those given in Fig. 1.

RSD values which were calculated for each set of 10 measurements of bromate and iodate solutions at various concentrations.

Fig. 2 shows the relationships between the RSD and the sample concentration. The concentrations of bromate and iodate at 10 % of RSD were 0.42 µg/L and 0.051 µg/L, respectively. Fig. 2 also shows the signal stability in the concentrations which give sufficient sensitivity for bromate and iodate.

In both species, RSDs were saturated around 1% even in high concentrations. The saturated RSD is considered to be affected by ICP-MS stability.

Interference by coexistent substance


The interference from coexistent substances such as chloride, sulfate and nitrate has been reported by Creed and others[14]. They reported that bromate can be determined in a chloride matrix with 5-6 orders of magnitude higher. However, a retention time shift for bromate in 1000 mg/L of chloride matrix was observed. So, the interference from coexistent substances such as fluoride, chloride, nitrite, phosphate and sulfate was examined. Mixed anion standard solutions ranging in concentration from 5 to 50 mg/L of anions were injected. Peaks of these anions were not observed on the chromatogram. The retention time

shift for halogen anions in the concentration below 50 mg/L of anions matrix was not observed. However, one peak was observed at void volume in chromatogram of 79 amu. This peak was recognized to be a polyatomic ion ($^{40}\text{Ar}^{39}\text{K}^+$) formed by combination of potassium in sample solution with argon as the plasma gas, because it appeared at the retention time of potassium that was observed in 39 amu. Conclusively, this peak due to potassium will be neglected on the determination of bromate because it is eluted at the void volume of the anion exchange column and completely separated from that of bromate under these separation conditions.

Application to the determination of halogen anions in the water

The presented method was applied to the determination of halogen anions in several water samples. The chromatograms of the ozonized water by using IC-ICP/MS and the postcolumn derivatization were shown in Fig. 3. The determined concentrations of halogen anions in raw (river) and ozonized water are listed in Table 3. The concentrations of halogen anions determined by both method were relatively in agreement. However, some iodate values obtained using ICP-MS were slightly higher than that of postcolumn derivatization. The disagreement could be due to lack of precision in such low concentration. Furthermore, there could be interference from other iodine-containing species coeluting with iodate, because ICP-MS would detect any species containing iodine, and it would give positive error in the iodate values. Bromate values by ICP-MS were a little lower than that of postcolumn method. The reason is

a) ICP/MS



b) postcolumn derivatization




Fig. 3

Chromatograms of ozonized water (sample B) using IC-ICP/MS a) and postcolumn derivatization b). Peaks: a) BrO_3^- (13.0 $\mu\text{g/L}$), Br^- (17.8 $\mu\text{g/L}$), IO_3^- (3.57 $\mu\text{g/L}$), and I^- (3.56 $\mu\text{g/L}$) b) IO_3^- (4.13 $\mu\text{g/L}$), BrO_3^- (15.7 $\mu\text{g/L}$) Experimental conditions are same as those given in Fig. 1 and Table 2. Unit of the concentrations is $\mu\text{g/L}$ as species.

samples	determined concentrations [$\mu\text{g/L}$ as species]					
	IC-ICP-MS				postcolumn	
	BrO_3^-	Br^-	IO_3^-	I^-	BrO_3^-	IO_3^-
A. raw water	0.26	28.9	0.44	0.63	0.29	0.09
B. ozonized sample A	13.0	17.8	3.57	3.56	15.7	4.13
C. raw water	1.64	59.1	1.26	2.97	1.65	0.60
D. ozonized sample C	1.88	38.5	5.66	0.14	2.31	4.98
E. ozonized water	1.87	5.73	5.45	0.05	1.85	4.77

Table 3

Comparison of determined concentrations of halogen anions in raw and ozonized water. Experimental conditions are same as those given in Fig. 1 and Table 2.

not clear because bromate values in this postcolumn reaction procedure doesn't suffer from interference from other oxidants [9].

Bromate and iodate with the concentration of $\mu\text{g/L}$ level were detected even in the raw water. Probably, the contamination of river water with trace bromate was caused by a waste water. On the other hand, the existence of iodate in mineral water has been also reported [17]. The concentrations of bromate and iodate in the ozonized water were rather increased than those in the corresponding raw water, while that of bromide was decreased by ozonation. Apparently, bromate and iodate will be formed during ozonation for the water treatment. However, the material balances of bromine and iodine were absolutely incompatible. These results suggest the halo-oxyacids are produced by oxidation of the corresponding halides, but that they are not always produced by the same mechanism.

Sample E gave a distinctive chromatogram at 79 amu (Fig. 4). Several unidentified species different from bromate or bromide were detected. These species are estimated as bromine compounds because no interferences from other elements are observed at 79 amu. The existence of other bromine species suggests that these species could lead to bromate during ozonation. It can also explain that the sum of bromate and bromide was not constant for ozonized water and its raw water (sample D and C) in Table 3. Furthermore, a large unidentified peak with a broad peak shape was also detected at the retention time of about 40 minutes in the chromatograms of ICP/MS at 127 amu. Heumann




Fig. 4
Chromatograms of ozonized water (sample E). Peaks: BrO_3^- (1.87 $\mu\text{g/L}$), Br^- (5.73 $\mu\text{g/L}$), IO_3^- (5.45 $\mu\text{g/L}$), and I^- (0.05 $\mu\text{g/L}$). Experimental conditions are same as those given in Fig. 1. Unit of the concentrations is $\mu\text{g/L}$ as species.

et al. reported that organoiodide exists in river water, because the peaks with exactly the same retention time were obtained in both chromatograms of ICP/MS and UV detector at 254 nm [13].

Therefore, the detection of these unidentified peaks by a simultaneous detection using ICP/MS and UV detector was examined. No peaks in the chromatogram of UV at 254 nm were observed at the retention times of these unidentified peaks in the chromatogram of ICP/MS. Furthermore, the retention behaviors of the unidentified peaks were evaluated by adding ethanol to the mobile phase. The retention times were drastically decreased as the concentration of ethanol increased. Clearly, these species were retained by their hydrophobicity, not ionicity. The elucidation of the unidentified peaks detected at 79 amu will be very difficult because of their lower amounts. The unidentified peak detected at 127 amu might be based on inorganic iodine

rather than organoiodine but its chemical structure is not still determined. These unidentified peaks might be concerned in the production mechanism of the halo-oxyacids by the ozonation. A further detailed examination would be necessary to elucidate these unidentified peaks.

Conclusions

A specific determination for bromate, iodate and other halogen anions in drinking water by direct injection using IC with ICP/MS and the postcolumn derivatization is presented. Bromate and iodate in ozonized water were determined at the $\mu\text{g/L}$ level without any interference from other anions. The sensitivity of the ICP/MS detector for halogens was also very high similar to that of metals and greater than that of other detectors for halogens. The proposed method will be effective for the simultaneous determination of halogen anions.

References

1. M. S. Siddiqui, G. L. Amy, and R. G. Rice, *J. AWWA*, **87** (1995) 59.
2. J. C. Kruithof, and J. C. Schippers, *Water Supply*, **11** (1992) 121.
3. J. C. Kruithof and R. T. Meijers, *Water Supply*, **13** (1995) 93.
4. J. C. Kruithof and R. T. Meijers, *Water Supply*, **13** (1995) 117.
5. WHO, "Guidelines for Drinking-water Quality", 2nd Ed., vol. 1. Recommendations, the World Health Organization, Geneva, 1993.
6. F. Sacher, A. Matschi, and H.-J. Brauch, *Acta Hydrochim. Hydrobiol.*, **23** (1995) 26.
7. R. J. Joyce, and H. S. Dhillon, *J. Chromatogr. A*, **671** (1994) 165.
8. H. Weinberg, *J. Chromatogr. A*, **671** (1994) 141.
9. Y. Inoue, T. Sakai, H. Kumagai and Y. Hamaoka, *Anal. Chim. Acta*, in press.
10. V. V. Salov, J. Yoshinaga, Y. Shibata and M. Morita, *Anal. Chem.*, **64** (1992) 2425.
11. K. Takatera and T. Watanabe, *Anal. Chem.*, **65** (1993) 759.
12. D. T. Heitkemper, L. A. Kaine, D. S. Jackson and K. A. Wolink, *J. Chromatogr. A*, **671** (1994) 101.
13. K. G. Heumann, L. Rottmann and J. Vogl, *J. Anal. At. Spectrom.*, **9** (1994) 1351.
14. J. T. Creed, M. L. Magnuson, J. D. Pfaff and C. Brockhoff, *J. Chromatogr. A*, **753** (1996) 261.
15. K. Ito, E. Shoto and H. Sunahara, *J. Chromatogr. A*, **549** (1991) 265.
16. "Standard Methods for the Examination of Water", Japanese Water Supply Society, (1993) 38.
17. K. G. Heumann, and H. Seewald, *Fresenius' Z. Anal. Chem.*, **320** (1985) 493.

Michiko Yamanaka is an Application Chemist
at Yokogawa Analytical Systems, Inc. Tokyo,
Japan

Agilent Technologies shall not be liable for
errors contained herein or for incidental or
consequential damages in connection with the
furnishing, performance or use of this material.

Information, descriptions and specifications in
this publication are subject to change without
notice.


Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
Agilent Technologies, Inc.
Printed 4/2000
Publication number 5968-3049E



Agilent Technologies

Innovating the HP Way



The Determination of Trace Elements in Soils and Sediments by ICP-MS

Application Note Environmental

Concerns regarding “safe” levels of contaminants in the environment, particularly heavy metals, continue to grow. The requirement for analysis of more elements at ever decreasing concentrations is exposing the limitations of currently used analytical techniques. Further improvements in sensitivity and elemental coverage are required. While GFAAS (Graphite Furnace Atomic Absorption Spectrometry) and ICP-OES (Inductively Coupled Plasma Optical Emission Spectrometry) are still the most commonly used techniques in environmental elemental analysis, ICP-MS is the only technique that offers the improvements in sensitivity that will be demanded in the near future. The 4500 ICP-MS benchtop ICP-MS offers high throughput multielement analysis at the sub ug/ml (ppb) level with the robustness and ease of operation required for true routine use. In this application brief, the analysis of two typical environmental solids - lake sediment and soil - is described. The




Fig. 1.
Qualitative spectrum of SL-1 (Lake sediment)

samples analyzed were standard reference materials - IAEA (International Atomic Energy Agency) SL-1 (lake sediment), and IAEA SOIL-7 (soil).

Sample Preparation

0.1g of each sample was digested with 1ml of pure water, 0.3ml of hydrofluoric acid (38%) and 0.7ml of nitric acid (68%) using microwave digester for 1 hour. After digestion the sample was diluted to 100ml with deionized water.



Agilent Technologies
Innovating the HP Way

Procedure

An internal standard mix containing Be, In and Bi was added to each sample. The sample solutions were quantified by external standardization, by measuring them against multi-element standards.

Operating conditions

RF power : 1.3 kW
Sampling depth : 8 mm
Plasma gas : 16 l/min.
Auxiliary gas : 1.0 l/min.
Carrier gas : 1.15 l/min.
Nebulizer : Babington type

Results

Lake sediment

Fig.1 demonstrates the qualitative spectrum of SL-1. A large number of elements, ranging from Li at low mass to U at high mass can be clearly observed, even though the total analysis time was only 100 sec.

The quantitative results and the certified values are given in Table 1. The major constituents in this sample are shown in Table 2. After digestion, Fe, Mn, Mg, K and Al were present in solution at levels ranging from a few mg/l(ppm) to 100s of mg/l(ppm), giving rise to the possibility of interference due to spectral overlap. The 4500 ICP-MS's excellent abundance sensitivity and low levels of polyatomic species ensured that the analyte values obtained were in good agreement with certified values.

Soil

Fig.2 shows the qualitative spectrum obtained from SOIL-7. The presence of over 20 elements can be clearly observed, although the




Fig. 2.
Qualitative spectrum of SOIL-7

Element	m/z	Certified	Measurement
V	51	170±15	169
Cr	52	104±9	115
Mn	55	3400±160	3520
Co	59	19.8±1.5	20.2
Ni	60	44.9±8.0	49.6
Cu	65	30±5.0	32.0
Zn	66	223±10	222
As	75	27.5±2.9	29.6
Se	82	*2.9	1.10
Cd	114	0.26±0.05	0.38
Sb	121	1.31±0.12	1.20
Pb	208	37.7±7.4	40.7
Units: mg/kg			

Table 1.
Quantitative values: SL-1
* Not certified - information only

elemental composition is quite different to SL-1, even from visual inspection of the qualitative spectra.

Quantitative results and the certified values are given in Table 3 and again very good agreement was obtained. The main components of this sample are also given in Table 4. As can be seen, the sam-

Element	Content
Fe	6.7
Mn	0.34
Ti	0.52
Na	0.17
Al	8.9
Ca	0.25
K	1.5
Mg	2.9
S	1.2
Units: %	

Table 2.
Main constituents of SL-1

ple matrix contains Ca at over 20%, which can affect the determination of Co and Ni, due to interference from CaO. Nevertheless, the 4500 ICP-MS values for Co and Ni agree well with the values supplied, which demonstrates the applicability of this technique to real life sample matrices, even where analytes are present at trace levels in the sample digest.

Element	m/z	Certified Conc.	Confidence interval	Measurement
V	51	66	59-73	67.3
Cr	52	60	49-74	60.7
Mn	55	631	604-650	629
Co	59	8.9	8.4-10.1	8.60
Ni	60	*26	*21-37	24.1
Cu	65	11	9-13	9.85
Zn	66	104	101-113	104.4
As	75	13.4	12.5-14.2	13.8
Se	82	*0.4	*0.2-0.8	3.11
Cd	114	*1.3	*1.1-2.7	1.20
Sb	121	1.7	1.4-1.8	1.60
Pb	208	60	55-71	61.7
Units: mg/kg				

Table 3.
Results of SOIL-7
*** Not certified - information only**

Component	Content
Al ₂ O ₃	8.9
CaO	22.9
Fe ₂ O ₃	3.7
K ₂ O	2.9
MgO	1.9
Na ₂ O	0.6
SO ₃	0.3
SiO ₂	38.5
TiO ₂	0.5
Loss on ignition (900°C)	20.5
Units: %	

Table 4.
Matrix components of SOIL-7

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.


Visit our website at
<http://www.agilent.com/chem/icpms>
Copyright © 2000

Agilent Technologies, Inc.
Printed 4/2000
Publication number 5963-7138E



Agilent Technologies

Innovating the HP Way



Analysis of Arsenic, Selenium and Antimony in Seawater by Continuous-Flow Hydride ICP-MS with ISIS

Application Note

ICP-MS

Environmental

Steve Wilbur

Analysis of arsenic and selenium in seawater at trace levels presents a number of challenges. While ICP-MS is generally considered to be a highly sensitive, interference free technique for analysis of trace metals in environmental samples, matrix effects can result in unacceptably high detection limits for these two elements. These matrix effects are based on two phenomena; 1) ionization suppression in the plasma of high ionization energy elements such as As (9.81 eV) and Se (9.75 eV) in the presence of a significant excess of easily ionizable elements such as Na (5.14 eV) and 2) spectral interferences by argon based polyatomic species such as ArCl and ArAr. For example, ArCl interferes

with the only isotope of arsenic and all the significant selenium isotopes suffer from polyatomic interferences of Ar, Cl, or Br. Optimum sensitivity therefore requires some mechanism for separating the analyte from the matrix and reducing or eliminating the argon based polyatomic species. Since arsenic, selenium and a number of other elements (Sb, Te, Bi, Ge, Sn, Pb) are known to form gaseous hydrides under specific reducing conditions, these elements can be removed from the matrix (for example the Na and Ca) and analyzed as gasses

in a flowing stream of argon. Reduction or elimination of argon polyatomics can be achieved in the Agilent 4500 or 7500 ICP-MS systems through the use of the ShieldTorch™ and cooler plasma conditions. As a result, by combining hydride generation with cool plasma/ShieldTorch, it is possible to lower the background equivalent concentrations for all As and Se isotopes to low ppb to mid ppt levels in seawater samples.




Figure 1. Full-scan Mass Spectrum of Selenium (20 ppb) Showing Excellent Agreement with Expected Isotope Ratios.



Agilent Technologies
Innovating the HP Way

Table 1. Common Interferences on As and Se by Normal Plasma, Direct Nebulization ICP-MS

Selenium Isotopes	% Abundance	Major Interferent(s)	% Abundance of Interferent Mass(s)
74	0.89	Ge	35.94
76	9.36	ArAr	0.671
77	7.63	ArCl	24.13
78	23.78	ArAr	0.125
80	49.61	ArAr, BrH	99.202, 50.682
82	8.73	Kr, BrH	11.6, 49.303
Arsenic Isotope			
75	100	ArCl, CaCl	75.48, 43.45

Reaction Chemistry:

For optimum sensitivity, accuracy and precision, both As and Se must be pre-reduced to the most efficient oxidation state for hydride formation. This is achieved through the use of a pre-reduction step. In the case of Se, pre-reduction to the +IV state can be achieved by the use of HCl plus heat. Arsenic requires a stronger reducing environment, in this case a solution of KI plus ascorbic acid is used to reduce As to the desired +III state.

Standards and Reagents:

Tune solution:

20 ppb solution of Se or As pre-reduced as follows.

Pre-reductant Stock for As and Sb (KI + ascorbic acid)

Dissolve 5 grams each KI and ascorbic acid in 100 mL DI water in a polyethylene bottle. Cap and shake to dissolve solids.

Reductant (NaBH₄ solution)

Weigh 0.5 g high-purity NaBH₄ and 0.125 g NaOH into a 250 mL polyethylene bottle. Bring to volume (250 mL), cap and shake to dissolve solids. Prepare fresh daily.

Calibration standards:

While plasma matrix effects are all but eliminated by using hydride generation, the efficiency of the pre-reduction and reduction steps can be affected by matrix. Therefore, best results will be obtained using matrix-matched standards. In the case of seawater, calibration by method of standard additions gives good results. The standard addition calibration can then be converted to an external standard calibration for analysis of subsequent seawater samples. Replicate 10 mL aliquots of CASS 3 or NASS 5¹ were spiked with a multi-element calibration stock containing selenium and pre-reduced as described below. Spike levels were 0, 0.01, 0.05, 0.1, 0.5, 1.0 and 5 ppb.

Pre-reduction of samples and standards:

- Arsenic (Antimony and Bismuth)

10 mL of sample (seawater) is added to a 50 mL polypropylene centrifuge tube. 1 mL of the KI/ascorbic acid pre-reduction reagent is added with swirling. 3 mL of concentrated trace metal grade HCl is added with swirling. The tube is capped loosely and allowed to set for 15 minutes after which it is brought to a final volume of 25 mL with 18 MOhm deionized water.

- Selenium (and Tellurium)

10 mL of sample is added to a 50 mL polypropylene centrifuge tube. 10 mL of concentrated, trace metal grade HCl is slowly added with swirling. The tube is loosely capped and heated in a heat block or boiling water bath at 100 degrees C. for 10 minutes. After allowing to cool, the sample is brought to 25 mL final volume with 18 Mohm DI water.

¹ National Research Council, Canada

Tuning

Optimized tuning involves maximizing the analyte signal(s) while minimizing

Basically, a combination of forward power, sample gas flow (carrier plus makeup), and sample depth which minimizes m/z 78 and 80 in the blank and maximizes those masses in the tune solution (20 ppb Se, pre-reduced as described) is desired.

background may be due to trace Se in the reagents used for pre-reduction or hydride formation. Now aspirate the 20 ppb Se tuning solution. Set the acquisition masses at 78, 80 and 82. Set the displayed ion ratio to calculate the ratio of 82 to 80. The natural isotope ratio of Se82 to Se80 is 8.73/49.61 or 17.59%. Therefore as the displayed ratio approaches 17.6%, the background at m/z 80 due to ArAr is minimized. Try to maximize the signal at 78 while maintaining as close to 17.6% for 82/80 as possible.²




Figure 2. Tune Screens, 20 ppb Se Standard and Prep Blank

the interferences. Since the interferences are primarily due to argon-based polyatomics, the use of ShieldTorch with slightly reduced forward power to minimize the ionization of Ar is quite effective. The following conditions were set to allow the measurement of Se at m/z 78 or 80 and also work quite well for As.

As a first step, while aspirating a prep blank under hydride generating conditions, try to reduce the background at m/z = 80 to 10-20,000 counts per 0.1 sec. This is accomplished by cooling the plasma using a combination of RF power and carrier/makeup gas. See figure 2 for sample tune conditions. Some of the




Figure 3. Se spike in CASS 3 Showing Interferences at m/z 80 and 82 from BrH

² Note: This must be done on a clean Tune solution, not a sea water spike since BrH from the sea water can cause high background at both 80 and 82. Occasionally, krypton (m/z 82) in the argon supply can be sufficiently high to adversely affect the ratio as well.

ISIS Program

The ISIS program builder was used to create the ISIS program below.

Typical values for ISIS parameters for hydride generation are shown. As a rule, sensitivity increases with sample

flow at the expense of sample consumption. The ratio of sample to reductant is important and should be optimized as well. Normal rinseout times are very fast due to the high sample flows utilized.

The screenshot displays the 'MPM Builder - hydride.MPU' application window. It features a menu bar (File, Edit, Sequence, Settings, Window) and a 'Sequence Parameter' table. Below this are three sequence editors: 'Sequence-1 "PreRun"', 'Sequence-2 "StartRun"', and 'Sequence-3 "PostRun"'. Each sequence editor has a table with columns for Duration, Scan, ALS, Pump1, Pump2, Valve1, Valve2, AUX1, AUX2, and AUX3. To the right, a 'Set Parameters' dialog box is open, showing input fields for various parameters with their units.

Ena	Name	Type	Frac	Min	Max	Unit
<P1>	Analysis Speed	NUM	2	-1.00	1.00	rps
<P2>	Reductant Speed	NUM	2	-1.00	1.00	rps
<P3>	Uptake Speed	NUM	2	-1.00	1.00	rps
<P4>	Uptake Time	NUM	0	0.00	120.00	sec
<P5>	Stabilization time	NUM	0	0.00	120.00	sec
<P6>	Rinse Speed	NUM	2	-1.00	1.00	rps
<P7>	Rinse Time	NUM	0	0.00	60.00	sec
<P8>	Optional Rinse Vial	NUM	0	0.00	5.00	ALS Pos.
<P9>	Optional rinse Time	NUM	0	0.00	120.00	sec

Duration	Scan	ALS	Pump1	Pump2	Valve1	Valve2	AUX1	AUX2	AUX3
1	<P4>	---	<P3>	<P2>	LOAD	LOAD	OFF	OFF	OFF
2	<P5>	---	<P1>	<P2>	LOAD	LOAD	OFF	OFF	OFF

Duration	Scan	ALS	Pump1	Pump2	Valve1	Valve2	AUX1	AUX2	AUX3
1	<P7>	---	<P6>	<P2>	LOAD	LOAD	OFF	OFF	OFF
2	<P9>	---	<P6>	<P2>	LOAD	LOAD	OFF	OFF	OFF

Parameter	Value	Unit
Analysis Speed	0.30	rps
Reductant Speed	0.20	rps
Uptake Speed	0.30	rps
Uptake Time	45	sec
Stabilization time	0	sec
Rinse Speed	0.30	rps
Rinse Time	5	sec
Optional Rinse Vial	1	ALS Pos.
Optional rinse Time	30	sec

Figure 4. ISIS Program Builder and Method ISIS Parameters Showing Prerun, Startrun and Postrun Programs and Setpoints for ISIS Pumps




Figure 5. Selenium Standard Addition Calibration in DI Water at 0, 10, 50, 100 and 500 ppt.




Figure 6. Standard Addition Calibration in CASS 3 Standard Reference Seawater. Calibration Levels; 0, 10, 50, 100, and 500 ppt.

Analysis of Certified Reference Materials

Seawater certified reference materials CASS 3 and NASS 5 were analyzed for As, Se and Sb. Standard addition calibrations were prepared by spiking 10 aliquots of sample with a mixed calibration solution containing the elements of interest. Standard addition calibrations were prepared and then converted to external calibrations for subsequent sample analysis. 3 sigma MDLs were calculated from seven replicate analyses of the unspiked seawater samples using the converted external calibrations. Spike recoveries were also calculated for samples spiked at 0.05 and 2.5 ppb for both elements.




Figure 7. Arsenic in CASS 3 by Standard Addition




Figure 8. Antimony in CASS 3 by Standard Addition

Summary

The use of online, continuous-flow hydride generation coupled to the Agilent 4500 or 7500 ICP-MS offers a fast, sensitive, routine analytical technique for the analysis of the hydride forming elements such as As, Se and Sb in difficult matrices such as seawater. The process can be fully automated

for multiple samples using the Cetac ASX-500 autosampler and the Agilent Integrated Sample Introduction system (ISIS). 3-sigma detection limits are typically 10 – 30 ppt for these elements, which is below ambient levels for all three. However, slightly elevated background equivalent concentration for Se can make ambient-level Se analysis borderline at best.

The use of purified reagents may help to reduce the BEC for Se to levels closer to the calculated detection limit. When compared to direct nebulization ICP-MS analysis of 10X diluted seawater, detection limits are improved from 10 to 50 times with no long-term matrix effects on the ICP-MS interface or ion lenses.

Table 2. Results of Analysis of Certified Reference Seawater Materials

Sample	Element /Isotope	Measured Value	Certified Value	Spike Amount	Blank Measurement	% Recovery ⁽³⁾	MDL (4)
CASS 3	As/75	1.12 ppb	1.09	N/A	-	102	0.03
CASS 3	Se/78	0.682 ⁽¹⁾	0.042 ⁽²⁾	0.5	0.193	97.6	0.01
CASS 3	Sb/121	0.34	not certified	0	-	-	0.02
NASS 5	Sb/121	2.87	not certified	2.5	0.34	101	0.02
NASS 5	As/75	1.21 ppb	1.27	N/A	-	95	0.03

(1) raw measured concentration, not corrected for prep(reagent) blank

(2) total selenium is listed but not certified in CASS 3

(3) recovery calculated against certified value where available and against matrix spike recovery where certified value is not available.


(4) 3-sigma using seven replicates

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.

Visit our website at
<http://www.agilent.com/chem/icpms>

Copyright © 2000
 Agilent Technologies, Inc.
 Printed in Japan (03/00)
 5980-0243E



New ASTM Standard: Recommended operating conditions for the Agilent Capillary Electrophoresis system

Maria Serwe

Environmental

Abstract

ASTM Subcommittee D19.05 on Inorganic Constituents in Water approved a new standard test method for determination of dissolved inorganic anions in aqueous matrices using capillary ion electrophoresis and chromate electrolyte¹. The Agilent Capillary Electrophoresis system provided equivalent performance during the inter-laboratory study preceding approval (c/w sect. 17.6 in test method). This document (reference B1.16 in test method) describes equivalent method parameters specific for the Agilent system equipped with DAD detection and computer control through Agilent ChemStation.




Figure 1
Analysis of waste water from a municipal waste treatment plant

Method Entries

Lift offset	4 mm
Cassette temp.	25° C
Preconditioning	
flush 1.1 min from flush buffer vial into waste vial	
Electric	on
Polarity	negative
Voltage	system limit
Current	0.00 µA
Power	system limit
Low current limit	0.00 µA
Time table	
0.3 min, current = 14.00 µA	
Injection	
by pressure, 50 mbar x 6.2 sec (37 nl)	
UV-detection	
Signal = 470/50 nm, reference = 275/10 nm, response time = 0.2 sec (PW > 0.01 min)	
Integration	
peak top type = center of gravity	
Calibration	
calculate with corrected areas	



Agilent Technologies

Innovating the HP Way

Method parameters

The parameters described here are supplementary to the test method (see also reference 2).

Capillary

Standard bare fused silica capillary ($L = 64.5$ cm, $l = 56$ cm, $75\text{ }\mu\text{m}$ id), fitted with a blue alignment interface. A new capillary is prepared by flushing 0.5 N NaOH for 5 min, water for 1 min and run buffer for 3 min (at 1 bar). If the current on a new capillary must be tested (c/w sect. 11.4), a voltage of 18.5 kV should be applied. If the system is idle overnight, leave the capillary in buffer. For long-term storage flush the capillary with water followed by air.

Vials


2-mL glass vials with polyurethane caps are used as buffer or waste container. 1-mL capped polypropylene vials are used as sample container. The buffer vials (inlet, outlet and flush buffer vial) are filled to 1 mL, the waste vial is filled with 0.6 mL buffer. For best migration time stability the run buffer vials should be replaced after 10 runs. It is not recommended to use the replenishment system with the Waters IonSelect™ High Mobility Anion Electrolyte.

Sample preparation

The waste water samples were diluted (1:20) and filtered through a $0.45\text{ }\mu\text{m}$ filter prior to injection.

Equipment

- Agilent Capillary Electrophoresis system
- Agilent ChemStation



References

1. D6508-00 (2000)
2. M. Serwe and J. Krol, "Determination of Dissolved Inorganic Anions in Aqueous Matrices Using Capillary Ion Electrophoresis and Chromate Electrolyte" Poster presentation at HPCE 2000 in Saarbrücken, Germany.

Maria Serwe is an application chemist at Agilent Technologies, Waldbronn, Germany.


For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 2000 Agilent Technologies
Released 03/2000
Publication Number 5968-8660E



Agilent Technologies

Innovating the HP Way



Indirect Determination of Fluoride Traces in Natural Waters by Ion Chromatography and ICP-MS Detection

Application Note

ICP-MS

Environmental

Maria Montes Bayon, University of Oviedo, Spain

Abstract

ICP-MS has been widely accepted as a powerful analytical technique for trace element determination in a wide variety of sample types. The technique is rapid, measures virtually all elements in a single acquisition and has limits of detection typically at or below the ng/L (ppt) level. Even initially problematic elements, such as K, Ca, Fe, As and Se, are now routinely measured using the power and flexibility of the Ar ICP to preferentially remove troublesome spectral overlaps.

However, there are some analytical challenges which cannot be overcome by plasma optimisation, most notably the analysis of elements which are not ionised in the Ar plasma. This Application Note presents a novel method for the indirect determination of one such element, fluorine, where the preliminary data indicates that the ICP-MS measurement is not

4B	5B	6B	7B	0	
				2 4.003 He helium 24 581 54 403 -268.9	1
6 12.01 C carbon 11 256 24 376 4918	7 14.01 N nitrogen 14 53 -209.9	8 16.00 O oxygen 13 614 -218.4	9 19.00 F fluorine 17 418 -219.6 188.1	10 20.18 Ne neon 21 589 -248.7 31 07 -246.1	2
14 28.09 Si silicon 8 149 1414 16 34 2642	15 30.97 P phosphorus 10 484 44.1 19 72 279.8	16 32.06 S sulfur 10 357 112.8	17 35.45 Cl chlorine 13 01 -101	18 39.95 Ar argon 15 755 -189.2 185.9	3
32 72.61 Ge germanium 7 88 958.5 15 93 2691	33 74.92 As arsenic 9 81 18 63	34 78.96 Se selenium 9 75 220.2 21 5 684.9	35 79.90 Br bromine 11 84 -7.2 21 6 87.9	36 83.80 Kr krypton 13 996 -156.6 24 56 -153.4	4
50 118.7 Sn tin 7 342 232.0 14 628 2270	51 121.8 Sb antimony 8 639 630.7 16 5 1617	52 127.6 Te tellurium 9 01 449.8 18 6 989.8	53 126.9 I iodine 10 454 113.6 19 09 182.8	54 131.3 Xe xenon 12 127 111.9 21 2 -108.1	5

Fluorine first Ionisation
Potential - 17.418 eV

Argon first Ionisation
Potential - 15.755 eV

only possible, but offers significant advantages over traditional analytical methods.



Agilent Technologies
Innovating the HP Way




Figure 1 Experimental Set-Up for Fluoride Determination

Table 1 Typical Operating Conditions

Instrument	HP 4500
Rf Power	1300 Watts
Nebuliser	Meinhard
Spray Chamber	Scott type, double pass, room temperature
Sampling depth	5.7 mm
Gas Flow Rates:	
Cool	15 L.min ⁻¹
Auxiliary	1 L.min ⁻¹
Carrier	1.17 L.min ⁻¹
Oxide level (CeO ⁺ /Ce ⁺)	<0.5 %
Doubly charged level (Ce ²⁺ /Ce ⁺)	<1%

Measurement of Fluoride

During the last decade, the majority of fluoride determinations have been performed using techniques such as potentiometry with fluoride Ion Selective Electrodes (ISE) , ion-chromatography with conductivity detection and, most recently, capillary ISEs has been the preferred technique, but is limited to determinations in the limited to determinations in the mg/L (ppm) range.

The chromatographic separation of Al-fluoride species was first described by Bertsch and Anderson, who

determined the stability constants of several AlF_x species. In acid aqueous solution, aluminium ions are present as [Al (H₂O)₆]³⁺ which can react with F⁻ to form the AlF₂⁺ complex.

Optimum PH for the complex formation seems to be between 2-4, therefore in the present work pH 2.6-3 was selected, where the complex AlF₂⁺ proved to be stable.

Samples and standard solutions were adjusted to pH=3 with nitric acid and spiked with Al³⁺ requiring at least a 5-fold weight excess of Al to fluoride to assure that only AlF₂⁺ was formed. The samples were

diluted by weight, transferred to 10ml polypropylene test tubes and immersed in a water bath at 50°C for 60 minutes, to ensure quantitative formation of the AlF₂⁺ complex. Under these conditions, several parameters were evaluated to obtain selective separation of the complex AlF₂⁺ in a 5 cm long ion exchange Dionex Ion Pac Column HPIC-CG2. HNO₃ was found to be an effective eluent for the separation of AlF₂⁺ from the excess of Al³⁺. Different molarities of nitric acid, from 0.15 M to 0.75 M, were tested and the conditions chosen for future studies were 0.45 M nitric acid at a flow rate of 0.5 mL/min. The AlF₂⁺ complex was measured indirectly by ICP-MS by collecting data for Al at mass 27.

Figure 1 shows the instrumental set-up of the IC-ICP-MS system. The exit tube from the column was connected directly to the concentric nebulizer of the ICP-MS, which can accept flow rates anywhere from 20uL/min to over 2mL/min.

ICP-MS operating conditions are summarised in Table 1.




Figure 2 Chromatogram Corresponding to 20 ng.g⁻¹ F⁻

Table 2 Analytical Characteristics

Analytical Characteristics	ICP-MS Detection
Detection Limit	0.1 ng.g ⁻¹
Precision	4 % ⁽¹⁾
Linear Range	up to 100 ⁽²⁾ ng.g ⁻¹
Regression coefficient (r) (n=7 points)	0.9993

(1) on 5 injections of 20 ng.g⁻¹ fluoride

(2) using 500 ng.g⁻¹ aluminium

The chromatogram obtained under these conditions for 20 ng/g F⁻ in the presence of 100 ng/g of Al is shown in Figure 2.

As can be observed, two aluminium containing peaks are detected. The first peak could be ascribed to the AlF²⁺ complex as its peak height/area was found to be proportional to the

concentration of fluoride in the sample.

Analytical Performance Characteristis

Analytical performance characteristics are summarised in Table 2. The linear dynamic range for fluoride determination depends on the

aluminium excess added to the sample. It was observed that, for a given aluminium concentration, the upper linear limit for fluoride determinations was about one fifth of the total aluminium concentration. Aluminium concentrations higher than 500 ng/g were not tested, to avoid contamination effects in the ICP-MS. In practice, it should be straightforward to dilute samples to a level of fluoride where Al addition would be at an acceptable level, as shown in this study. Alternatively, ISE could be used as a screening tool, after which the IC-ICP-MS method could be used to determine those fluoride levels which were found to be below the limit of detection for ISE.

The detection limit obtained by the IC-ICP-MS method was 0.1 ng/g, calculated as three times the standard deviation of the blank, divided by the slope of a linear calibration between 0-5 ng/g. As can be observed, the detection limit using ICP-MS detection is one of the lowest ever reported for the determination of fluoride.

Figure 3 shows a typical calibration curve obtained from 5 to 50 ng/g (ppb)

of fluoride and containing 200 ng/g aluminium in each standard solution. The linear calibration demonstrates that the peak area of the complex is proportional to the fluoride concentration. Determination of Fluoride in Fresh and Sea Water Samples.

Under the optimum separation conditions using HNO_3 for elution, the retention time for Al^{3+} is under 7 minutes, allowing a sampling rate of 6-7 samples per hour. To evaluate the use of the proposed ICP-MS method in routine operation, it was applied to the determination of fluoride in natural and drinking waters from a variety of sources and with different saline concentration.

At this time, no stable aqueous fluoride reference material was available, so it was decided to compare the proposed methodology with the fluoride ion selective electrode (FISE). Since many natural water samples contain fluoride levels below the limit of detection of FISE, a spike-recovery exercise was also undertaken.

In order to minimise aluminium addition to the samples and contamination of the ICP-MS, up to 200 fold dilution of some drinking and sea-water samples was necessary. The results obtained are summarised in Table 3.

Some of the water samples contained fluoride levels too low to be measured by FISE (at around 150 ng/g), so comparison between the FISE method and the IC-ICP-MS method was not possible. However, where FISE was able to measure the levels present, good agreement with the IC-ICP-MS results was obtained. In the other cases tested, the spike recovery exercise indicated that the IC-ICP-MS method gave good recoveries (within $100 \pm 10\%$), showing the applicability




Figure 3 Typical Calibration Curve of Fluoride

Table 3 Results Obtained for Fluoride in Water Samples Using ICP-MS

Water Sample (dilution factor)	Conc. found(n=3) ICP-MS(ng.g^{-1})	Conc. found FISE (ng.g^{-1})	Spiked amount (ng.g^{-1})	Recovery (%)
Fontecelta (200)	8050 ± 80	7700	4300	104
Font-Vella (10)	182 ± 2	-	205	97.8
Tap-water (10)	161 ± 1	-	210	90
*Sea-water(100)	1030 ± 60	1080	1080	97.5

of the proposed methodology to perform fluoride determination at extremely low levels in natural water samples.

Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

Information, descriptions and specifications in this publication are subject to change without notice.
Visit our website at
<http://www.agilent.com/chem/icpms>


Copyright © 2000
Agilent Technologies, Inc.
Printed in Japan (02/00)
5968-8232E



Soil & Sediment


Other
Applications

> [Return to Table of Contents](#)
> [Search entire document](#)



Reversed-Phase Separation 15 Explosives from Soil Extract

Application
Environmental
Robert Ricker



Highlights

- *Medium-bore columns reduce both the amount of sample required and generation of mobile-phase waste. This medium-sized bore does not require a special low-volume chromatograph but does require that the system contain minimal dead volume.*
- *Isocratic operation has the advantage of quick turn-around between injections since re-equilibration is not required.*

Courtesy of Ursula Hechler, Lab Dr. Wessling, Altenberge, Germany, Terra. Tech. 1, 27-28 (1995)

Conditions:
ZORBAX SB-C18 (3 x 250 mm) (Agilent P/N: 880975-302)
Mobile Phase: Methanol:Water (50:50) (v/v)
Injection volume 10µl, 0.3 mL/min, Ambient, Detect. UV (230 nm)



Agilent Technologies

*Robert Ricker is an application chemist
based at Agilent Technologies, Wilmington,
Delaware.*

For more information on our products and
services, visit our website at:
www.agilent.com/chem

Copyright© 2002 Agilent Technologies, Inc.
All Rights Reserved. Reproduction,
adaptation or translation without prior
written permission is prohibited, except as
allowed under the copyright laws.


Agilent shall not be liable for errors
contained herein or for incidental or
consequential damages in connection with
the furnishing, performance, or use of this
material.

Information, descriptions, and specifications
in this publication are subject to change
without notice.

Printed in the USA
April 25, 2002
5988-6342EN





Agilent Technologies



Qualitative and Quantitative Analysis of Explosives and Related Compounds Using Polar and Nonpolar HPLC Columns

Application
Environmental
Robert Ricker



Courtesy of Th. Renner, Hess. Landesanstalt f. Umwelt, Dez. III/2, P.O. Box 3209, 65022 Wiesbaden, Germany

Conditions:
ZORBAX® SB-C18, SB-CN (2.1 x 150 mm) (Agilent P/N: 883700.905, 883700.922)
Mobile Phase: A: ACN + 5% H₂O + 5 mM CF₃COONH₄
B: H₂O + 5% ACN + 5 mM CF₃COONH₄
pH 2.7 (CF₃COOH)
Inject: 10 µL of 19 nitromethanes in ACN:H₂O (20:80), 5mM CF₃COONH₄;
0.23mL/min, 18°C, Detect. UV(210, 240, 360 nm)



Agilent Technologies

Gradient Shapes

ZORBAX[®] SB-C18 (2.1x150 mm) (P/N:883700.922)
Sample: 0.5ng / µL

Time [min]	Flow [mL/min]	% A [%]	% B [%]
0	0.23	20	80
2	0.23	20	80
10	0.23	30	70
20	0.23	35	65
25	0.23	40	60
35	0.23	70	30
40	0.23	70	30
42	0.23	20	80
45	0.23	20	80

ZORBAX[®] SB-CN (2.1x150 mm) (P/N:883700.905)
Sample: 5ng / µL

Time [min]	Flow [mL/min]	% A [%]	% B [%]
0	0.23	20	80
1	0.23	20	80
15	0.23	30	70
30	0.23	80	20
35	0.23	80	20
37	0.23	20	80
40	0.23	20	80

Robert Ricker is an application chemist
based at Agilent Technologies, Wilmington,
Delaware.

For more information on our products and
services, visit our website at:
www.agilent.com/chem

Table 1 - List of Analytes

	Compound	Rt [min] on Zorbax SB-C18	Rt [min] on Zorbax SB-CN	Quantitation on Zorbax SB
1	picric acid	11.02	16.82	CN (360 nm)
2	4-amino-2-nitrotoluene	11.31	7.57	C18 (240 nm)
3	2-amino-6-nitrotoluene	13.72	10.00	C18 (240 nm)
4	RDX	15.42	14.13	C18 (210 nm)
5	2-amino-4-nitrotoluene	15.92	11.02	C18 (240 nm)
6	HMX	17.76	20.37	C18 (210 nm)
7	1,3-dinitrobenzene	19.41	13.40	CN (240 nm)
8	1,3,5-trinitrobenzene	19.87	14.90	CN (240 nm)
9	2-amino-4,6-dinitrotoluene	24.79	20.98	C18 (240 nm)
10	2,4-dinitrotoluene	25.52	21.55	C18 (240 nm)
11	4-amino-2,6-dinitrotoluene	27.37	19.90	CN (240 nm)
12	2-nitrotoluene	27.41	18.13	CN (240 nm)
13	2,6-dinitrotoluene	27.84	20.87	C18 (240 nm)
14	4-nitrotoluene	28.47	17.39	C18 (240 nm)
15	3-nitrotoluene	29.46	17.43	C18 (240 nm)
16	2,4,6-trinitrotoluene	30.59	23.85	CN (240 nm)
17	tetryl	32.22	26.30	CN (240 nm)
18	diphenylamine	42.59	27.32	CN (210 nm)
19	hexyl	45.78	34.45	CN (360 nm)

Copyright© 2002 Agilent Technologies, Inc.
All Rights Reserved. Reproduction,
adaptation or translation without prior
written permission is prohibited, except as
allowed under the copyright laws.

Agilent shall not be liable for errors
contained herein or for incidental or
consequential damages in connection with
the furnishing, performance, or use of this
material.

Information, descriptions, and specifications
in this publication are subject to change
without notice.

Printed in the USA
April 25, 2002
5988-6345EN



Agilent Technologies



Analysis of ionic tenside surfactants in wastewater by HPLC

Rainer Schuster

Environmental

Abstract

The detergents used for cleaning floors, worktop surfaces and laundry in the home and hygiene industry are the main source of the ionic species of surfactants known as tensides.

Sample preparation

Tensides can be extracted from either surface water or waste water by a liquid–solid technique. Narrow bore technology for lowest solvent consumption and highest sensitivity, with automated diode-array detection for evaluating peak purity and identity.

Separation

Figure 1 shows a normal flow rate elution on a 10 cm Hypersil ODS column with 2.1 mm internal diameter, 5 µm particles. A simple linear gradient and a constant oven temperature of 40 °C achieve good resolution.

- UV absorbance detection or
- Diode-array detection—for peak purity check and peak identity confirmation using UV absorbance spectra.




Figure 1
Separation of 10 µl injection of a Marlon A ionic tenside surfactant standard

Conditions

Column

250 x 2.1 mm Hypersil ODS C18, 5 µm

Mobile phase

A: 0.005 M KH_2PO_4

B: acetonitrile

Gradient

0 min 26% B

20 min 100% B

Flow rate

0.25 ml/min

Temperature

40 °C

Detection

222 nm (20 nm bandwidth)

reference 450 nm (100 nm bandwidth)



Agilent Technologies

Innovating the HP Way




Figure 2
Analysis of linear alkylbenzenesulfonates (LAS), alkylphenol polyethoxylates (APEO) and nonylphenol in waste water

References

1. Rainer Schuster, "Analysis of ionic tenside surfactants in wastewater by HPLC and diode-array detection," *Hewlett-Packard application note*, publication number 12-5091-1818E,

Conditions

Column

250 x 2.1 mm Hypersil
ODS C18, 5 μ m

Mobile phase

A: 0.005 M KH_2PO_4
B: acetonitrile

Gradient

0 min 26% B
20 min 100% B

Flow rate

0.25 ml/min

Temperature

40 $^{\circ}\text{C}$

Detection

222 nm (20 nm bandwidth)
reference 450 nm
(100 nm bandwidth)

Equipment

Agilent 1100 Series

- vacuum degasser
 - quaternary pump
 - autosampler
 - thermostatted column compartment
 - diode array detector
 - fluorescence detector
- Agilent ChemStation + software

Rainer Schuster is application chemist at Agilent Technologies, Waldbronn, Germany.


For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 10/97
Publication Number 5966-1877E



Agilent Technologies

Innovating the HP Way



HPLC Analysis of Explosive Constituents in Soil Samples


Application Note

Environmental

Rainer Schuster and
Angelika Gratzfeld-Huesgen



An HPLC method for detecting traces of explosive constituents at low nanogram levels in soil samples is described. The analytes were extracted from soil with acetonitrile in an ultrasonic bath. Analysis was performed using a newly-designed base-deactivated Hypersil column. Compounds were identified and confirmed by spectral library search and by retention time tagging. The detection limit from a 2-g sample in 10 ml ACN extracted was 8 to 20 mg/kg at an injection volume of 10 μ l. The retention time precision was better than 0.5 % RSD and the quantitative precision was between 0.5 and 2.5 %. Linearity was better than 2.5 % over the range from 2 to 500 ng/ μ l.



Agilent Technologies
Innovating the HP Way

Introduction

Armed forces all over the world have been disposing of expired munitions in appreciable quantities for the last century. Most of this disposal involves direct combustion, such as detonation or incineration, which partially removes some of the toxic constituents. However, a significant proportion of dumped explosives contaminates soil and/or ground-water.

The most widely found explosives are trinitrotoluene (TNT), its corresponding metabolites and hexogen. The most commonly used explosives are listed in table 1. Over time, explosive residues and their transformation products have accumulated in large areas of soil formerly occupied by settling lagoons. Concern about the environmental fate of these residues is now intensified because

recent studies of the toxicity of TNT have shown liver damage and anaemia among chronically exposed munitions workers.¹ In addition, TNT has been found to be mutagenic.²

The metabolism of TNT in bacteria, animal and plant systems has been examined in a number of investigations. According to McCormick,¹ TNT is reduced by bacteria to 2-amino-4,6-dinitrotoluene (2-AMDNT) and 4-amino-2,6-dinitro- toluene (4-AMDNT); a metabolism that occurs also in plants and animals. This universal metabolism of TNT by bacteria, animals and plants to the AMDNT isomers is significant, as both metabolites show severe toxicity and mutagenicity. Other metabolites found are dinitrotoluenes, and both di- and trinitrobenzenes.

Accurate assessment of environmental and health risks demands analytical methods that provide for an acceptable mass balance. Due to the limited thermal stability of explosives residues, like octogen, hexogen, tetryl, nitropenta and aminometabolites, a method utilizing high-performance liquid chromatography (HPLC) has been developed. The US Environmental Protection Agency (EPA) has published a draft method for the analysis of 12 explosives in soil using HPLC and UV-Visible detection.³

In this Application Note we describe the analysis of the 12 EPA-listed explosives plus 7 other commonly used explosives and metabolites (table 1) using a newly-developed base-deactivated Hyperasil reversed phase column. For peak confirmation we used a diode-array detector on-line coupled to the HPLC column.

A special software program for the Agilent Technologies HPLC ^{3D}ChemStation (DOS Series) quantified the explosives residues and automatically identified them as present when retention times and spectral identification matched the specified match threshold values.

Listed in EPA 8330 ³		
2,4,6-Trinitrophenol	2,4,6-TNP	
Octogen (RMX)		x
Hexogen (HMX)		x
1,3,5-Trinitrobenzene	1,3,5-TNB	x
2-Amino-6-Nitrotoluene	2-A-6-NT	
1,2-Dinitrobenzene	1,2-DNB	
1,3-Dinitrobenzene	1,3-DNB	x
2-Amino-4-Nitrotoluene	2-A-4-NT	
Nitrobenzene	NB	x
Tetryl		x
2,4,6-Trinitrotoluene	TNT	x
2-Amino-4,6-Dinitrotoluene	2-A-4,6-DNT	
4-Amino-2,6-Dinitrotoluene	4-A-2,6-DNT	
2,4-Dinitrotoluene	2,4-DNT	x
2,6-Dinitrotoluene	2,6-DNT	x
2-Nitrotoluene	2-NT	x
4-Nitrotoluene	4-NT	x
3-Nitrotoluene	3-NT	x
Nitropenta		

Table 1
19 commonly-used explosives analyzed in this study together with the 12 explosives listed in EPA draft method 8303³

Experimental

Soil samples were prepared according to EPA Draft Method No. 8330.³ A 2-g sample was placed in a 15-ml glass vial and 10 ml of acetonitrile was added. The vial was capped with a Teflon-lined cap, vortex swirled for one minute, and then placed in an ultrasonic bath for 18 hours. When tetryl was being analyzed, the ultrasonic bath was kept at, or below, room temperature.

After sonication, the sample was allowed to settle for 30 minutes; 5 ml of supernatant was removed and combined with 5 ml of calcium chloride solution (5 g/l). The mixture was shaken and then left to stand for 15 minutes. The supernatant was placed in a syringe and filtered through a 0.5- μ m filter. The first 2 to 3 ml were discarded and the remainder was retained for analysis.

Chromatography

For the chromatographic separation we used an HP 1090 Series M liquid chromatograph with DR 5 binary solvent delivery system, variable-volume autoinjector, temperature-controlled column compartment and solvent-preheating device.

For instrument control and data evaluation we used an HPLC ^{3D}ChemStation (DOS Series) from Agilent Technologies. A Hypersil BDS column from Agilent Technologies was used for all experiments. The column contained 3- μ m particles, and had a 4-mm inner diameter and a length of 100 mm. The mobile phase was a gradient system water-methanol (HPLC) from Baker (Gross-Gerau, Germany) at a flow rate of 0.72 ml per min. The column compartment temperature was 38 °C.

A UV-Visible diode-array detector was used for dual wavelength detection and on-line spectral acquisition. The detection wavelengths were 214 nm with a bandwidth of 10 nm, and 235 nm with a 40-nm bandwidth. The complete chromatographic conditions are listed with figure 1.

Detection and compound confirmation

Due to possible interferences from the soil matrix it is mandatory to identify compounds of interest not only by retention time, but also by a further confirmation step.

With diode-array based detection, several wavelengths can be selected and peak spectra can be acquired automatically. This enables an individual library to be compiled for each class of compound. The confirmation used the dedicated spectral library for explosives with retention-time tagging. A software routine developed for this task searched every peak within each chromatogram for the best match to library spectra within a given retention time range, expressed as a percentage.

In addition, for each peak, a purity check — an overlaid baseline corrected for up- and downslope spectra — was performed. After each search a chromatogram is plotted and a customized report is printed. The report contains all the data: retention times, analysis, library and calibration table, amounts, library purity data and peak names.

The method is fully automatic. Data acquisition and data evaluation, including quantification and qualitative identification are performed automatically.

Method validation

For method validation such as precision, linearity, and sensitivity, we used the system suitability software employed by the HPLC ^{3D}ChemStation.

Results and discussion

We were able to separate the common explosives and metabolites. Figure 1 shows a chromatogram of a standard at about 10 to 20 ng/injected amount.

Several soil samples were analyzed for these explosive constituents. One soil sample was analyzed for tear gas.

Gradient	26 % B, to 40 % B at 10 min, to 55 % B at 20 min, to 70 % B at 30 min, to 26 % B at 31 min
Oven temperature	38°C
Detection wavelengths	214 nm for nitropenta 235 nm for other nitro-compounds




Figure 1
Chromatogram of standard sample

Figure 2 shows the chromatogram of a soil sample. The major explosive constituent 2,2',4,4',6,6'-hexanitrodiphenylamine (2,2',4,4',6,6'-HNDA) at 20.2 min was identified by spectral library search and retention time comparison with a standard.

After spectral search without any retention time-window (throughout the whole library) the strong tailing peak at 5.7 min was indicated to be a metabolite of the major constituent 2,2',4,4',6,6'-HNDA.

In addition, large amounts of 2,4,6-TNT and the corresponding metabolites 2,4-DNT, 3,4-DNT and 1,3,5-DNB could be identified. Amounts were in the µg to mg/g-range (for example, 3.2 mg TNT/g soil, 1.9 mg 2,4-DNT/g soil), figure 2.




Figure 2
Soil sample after extraction with acetonitrile and ultrasonic extraction




Figure 3a
Soil sample from Huenxe (N. Germany) extracted according to EPA Draft Method No. 8330³

In figure 3 a soil analysis with rather high levels for 1,3-dinitrobenzene and TNT, 240 mg/kg of soil for 1,3-DNT, and 14 mg/kg soil for TNT, is shown. After the chromatographic run a report was generated with compound names, retention time of sample and standards, and with purity and identity match factors. TNT and 1,3-DNT have been positively confirmed by retention times and UV spectra.

The following peaks at 12.07, 18.9 and 21.1 min all show similar spectra. They are not found in the library, however, the spectral characteristics indicated them to be nitrometabolites.

Report							
Quantification method:	ESTD		calibrated by		Area response		
Sample Info:	PROJECT: EXPLOSIVES						
Misc. Info:	SAMPLE: HUENXE 40 mg/CH ₃ CN .2 ml						
Method File Name:	EXPLO.M		Wavelength from:		205 to 400 nm		
Library File Name:	UMW:EXPLO.L		Library Threshold:		950		
Reference Spectrum:	Apex		Peak Purity Threshold:		950		
Time Window from:	8.0 & to 5.0 %		Smooth Factor:		5		
Dilution Factor: 1.0	Sample amount: 0.0		Resp.Fact.uncal.peaks:		None		
Name	Amount	Peak-Ret.	Cal.-Ret.	Lib.-Ret	Purity	Library	Res.
	[mg/kg]	[min]	[min]	[min]	Matchfactor		
1,3 Dinitrobenzene	239.52	A 7.372	7.402	7.377	1000	1000	0.9
2,4,6-Trinitrotoluene	13.65	A 10.789	10.829	10.782	1000	1000	4.7
...?-Amino-4,6-dinti	-----	A 10.789	-----	11.211	1000	961	4.7
	=====						
	253.17						
	=====						
Not identified peaks							
Hexogen ?	1.21	A 4.520	4.249	4.288	965	496	3.1
2-nitrotoluene ?	5.08	A 14.055	14.308	14.483	987	821	1.2

Figure 3b
Automatically-printed report accompanying chromatogram in figure 3a

A critical “non-explosive” compound — often carelessly disposed of — is chloracetophenone, the major constituent of tear gas. The analysis of this compound in soil can be performed under the same conditions as for explosives, figure 4.




Figure 4
Analysis of chloracetophenone in soil

Figure 5 shows the separation of explosive constituents in a soil sample that are often described as critical: 2,4,6-TNT, 2A-2,6-DNT and 4-A-2,6-DNT.

Concentrations were in the low ng-range for each compound: 50 ng TNT; 15 ng 2-A-4,6-DNT; and 15 ng 4-A-2,6-DNT.

All three compounds were identified by retention times and UV spectra. In figure 5 the sample spectrum of 2,4,6-TNT is overlaid with the library spectrum.




Figure 5
Shows the determination of TNT and the aminometabolites 4-amino-2,6-dinitrotoluene (4-A-2,6-DNT) and 2-amino-4,6-dinitrotoluene (2-A-4,6-DNT) in soil samples.

Selectivity and recovery

Surprisingly, most of the analyzed real life soil samples did not show many interferences from other compounds; most of them showed a purity factor of 1000 and identification via library search was close

to 1000, indicating efficient sample preparation.

Recovery rates for a spiked soil sample (10 mg/kg) for these compounds have been found to be between 85 and 100 % according to an interlaboratory comparison⁴.

Linearity and repeatability

The linearity for 2,4,6-TNT was checked and found to be better than 2.5 % within the range from 2 to 500 ng/μl.

The repeatability for all compounds was better than 0.2 % for retention time and between 1 and 3.5 % for peak area, except for nitropenta, which was 7 %, due to its instability. The calculation was based on 8 runs with injected amounts of 8 to 20 ng absolute. Figure 6 shows parts of print-outs from a system suitability report as generated by the HPLC ChemStation.


	%RSD	
	RT	Peak area
2,4,6-Trinitrophenol	0.37	2.18
Octogen (RMX)	0.04	2.38
Hexogen (HMX)	0.09	1.14
1,3,5-Trinitrobenzene	0.09	1.86
2-Amino-6-Nitrotoluene	0.12	1.99
1,2-Dinitrobenzene	0.13	1.23
1,3-Dinitrobenzene	0.10	1.00
2-Amino-4-Nitrotoluene	0.13	2.74
Nitrobenzene	0.11	0.77
Tetryl	0.14	3.36*
2,4,6-Trinitrotoluene	0.11	1.52
2-Amino-4,6-Dinitrotoluene	0.14	2.68
4-Amino-2,6-Dinitrotoluene	0.14	1.46
2,4-Dinitrotoluene	0.11	3.69
2,6-Dinitrotoluene	0.10	2.15
2-Nitrotoluene	0.08	2.13
4-Nitrotoluene	0.08	2.44
3-Nitrotoluene	0.09	2.44
Nitropenta	0.06	6.91*

* due to instability of these compounds

Table 2
Precision of retention times and peak areas

Compound (signal No. 1): 1,3-DNB

Run #	measRet Time [min]
1	7.8670
2	7.8573
3	7.8539
4	7.8552
5	7.8540
6	7.8586
7	7.8586
8	7.8567
Mean:	7.8577
S.D.:	0.0042
RSD [%]:	0.0537



Run #	Area []
1	57.8521
2	58.2713
3	58.2464
4	58.4260
5	58.7530
6	58.8206
7	58.5031
8	57.9159
Mean:	58.2841
S.D.:	0.4798
RSD [%]:	0.8232




Figure 6
Repeatability for 1,3-DNB for retention time and peak area

Sensitivity

The detection limit for all explosive constituents and metabolites was 1 ng to 3 ng/μl except for nitropenta, which was 8 ng/μl. Peak spectra acquired at these low levels still matched standard spectra at higher concentrations.

Conclusion

We have shown that the commonly used explosive constituents and their metabolites (nitroaromatics and nitramines) can be covered by one comprehensive method including sample preparation and HPLC. An automated spectral library search can positively confirm explosive constituents at levels as low as 1 to 3 ng/μl.


References

- 1
N.G. McCormick, F.E. Feeherry and H.S. Levenson, *Appl. Environ. Microbiol.*, **1976**, *31*, 949
- 2
J.V. Dilley, C.A. Tyson and G.W. Newell, Mammalian Toxicity Evaluation of TNT Wastewaters. Contract No. DAMD17-76-C-6050. Vol. III. Stanford Research Institute, Menlo Park, CA. 1978.
- 3
U.S. Environmental Protection Agency. "EPA Method 8330, Nitroaromatics and nitramines by high performance liquid chromatography (HPLC)."
- 4
St. Hastenteuffel, M. Schmidt, R. Wagner, *Labor Praxis*, **1992**, *9*, 888-894 "Rüstungsaltslasten".

For the latest information and services visit our world wide web site:
<http://www.agilent.com/chem>

Copyright © 1993 Agilent Technologies
All Rights Reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

Publication Number 5091-7626E



Agilent Technologies
Innovating the HP Way




Air

Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)

Rapid Separation and Identification of Carbonyl Compounds by HPLC



Application

Environmental

Authors

William J. Long and John W. Henderson, Jr.
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

A fast HPLC method for the analysis of DNPH derivatized carbonyls found in air samples is demonstrated. A 1.8- μ m StableBond C18 separated a standard of the major 13 DNPH derivatized carbonyls. An air sample was analyzed in under 10 minutes and found to contain several carbonyls.

Introduction

Carbonyl compounds are important constituents in urban and global atmospheres. In urban atmospheres, these compounds frequently initiate photo-

chemical smog and sustain reactions leading to ozone formation. Outdoor sources include motor vehicle exhaust and other forms of incomplete hydrocarbon combustion. Indoor sources, such as aldehydes found in insulation, tobacco smoke, furniture, and particle board, also contribute to the overall environmental concerns. Measurement of low-level atmospheric carbonyl compounds requires techniques that are sensitive and free of interferences. Unfortunately, many known carbonyl compounds in air samples (for example, formaldehyde and acetone) have no chromophores and are not detected by the UV detector. Thus, for low-molecular-weight aldehydes and ketones in air and water, HPLC methods have been developed for the in-situ derivatization of carbonyls using 2,4-dinitrophenyl-hydrazine (DNPH) (Figure 1).

Official Methods for Carbonyl Compounds

There are several official regulatory agency methods for DNPH-derivatized carbonyls based on the sample matrix (see Table 1).




Figure 1. Chemical reaction for derivatizing of carbonyls from air or water samples.



Agilent Technologies

Table 1. Methods for Analysis of DNPH-Derivatized Carbonyls

Method Number	Matrix
EPA TO-11	Ambient air
EPA 8315A	Liquid, solid, and gas samples
ASTM D5197	Ambient air
NIOSH 2016 and 2532	Ambient indoor air
EPA 554	Drinking water

EPA = U.S. Environmental Protection Agency

ASTM = American Society for Testing Materials

NIOSH = National Institute for Occupational Safety and Health

These methods are all variations of the general approach discussed in the experimental section. In some cases, for toxic air samples, an ozone scrubber must be installed prior to the DNPH cartridge since ozone interferes with the carbonyl-DNPH reaction.

Experimental


The carbonyl-containing air sample is passed through a silica gel cartridge that has been coated with DNPH or impinged into an acidified DNPH solution. For water samples, the reaction occurs directly by the addition of DNPH to the water, buffered at pH 3. Carbonyl compounds are rapidly

derivatized to hydrazones under these conditions. These colored hydrazones are then eluted from the trapping cartridge using acetonitrile; or for water samples, extracted from solution with methylene chloride. These extracts are then concentrated, reconstituted in a suitable solvent, and injected into a reversed-phase column for separation and quantitation.

Once the derivatized hydrazones are collected and extracted (or eluted), reversed-phase HPLC is the preferred method to analyze these compounds [1-5]. Since the hydrophobicities of the hydrazones vary widely, gradient conditions are required to elute them in a reasonable time.

Results and Discussion

Figure 2 depicts the separation of the major DNPH-derivatized carbonyl standards that are on the list of important environmental toxins. This is a commercially available standard solution (3- μ g/mL) purchased from Sigma (St. Louis, MO). The Stable-Bond C18 1.8 μ m 4.6 mm $\times$ 150 mm column (pn 829975-902) showed excellent resolution,

**Figure 2. Commercial DNPH standard and analysis conditions.**

including partial separation of peaks 8 and 9 of the standard. The separation of 2-butanone-2,4-DNPH and butyraldehyde-2,4-DNPH is noteworthy since this pair is unresolved on a number of reversed-phase columns. The high surface coverage of the C18 phase is partially responsible for the good selectivity. The initial portion of the chromatogram is isocratic, allowing easy transfer of the method to any instrument as well as potential scaling to smaller diameter columns used with mass spectroscopic detection. Higher flow-rate analyses are easily accomplished using the Agilent 1200 System; however, the maximum pressure measured throughout these gradients was approximately 370 bar.

The 60% acetonitrile initial mobile phase composition eluted these nonpolar compounds in a reasonable time. A higher aqueous mobile phase composition results in a loss of resolution of peaks 3 and 4 (acrolein-DNPH and benzaldehyde-DNPH). A higher organic composition compromises the resolution of other peaks, most readily seen in the 7-8-9 group (crotonaldehyde-DNPH, formaldehyde-DNPH, and hexaldehyde-DNPH). A wavelength of 360 nm was used. This wavelength avoids detecting extraneous peaks that usually have stronger absorbance at lower UV wavelengths. Finally, formic acid was added at 0.1 % concentration to both the water and acetonitrile. This will improve the ionization of the analytes when using MS detection, add greater stability to the column, and prevent secondary interactions, while not complicating the mobile phase preparation.

Analysis of Carbonyl Compounds in Ambient Air Samples

Outdoor air was collected on DNPH-coated traps and run through the extraction procedure. This extract was kindly provided by Vermont's Department of Environmental Conservation's (DEC) Environmental Laboratory, Waterbury, VT, USA. The extracts were directly injected into the Agilent StableBond SB-C18 column. A blank extract was also run. The blank was prepared using a collection cartridge with a DNPH loading; however, this cartridge was not carried through the entire sampling process.

Figure 3 shows the HPLC results of an actual air-sample collected near Burlington, Vermont. In this sample, small amounts of formaldehyde, acetaldehyde, and acetone were found. Some unknown peaks were observed that were also present in the blank. One compound eluted about 5.5 minutes and was attributed to unreacted DNPH; the others were unidentified.

Conclusions

Using DNPH collection and HPLC analysis, small amounts of carbonyl-containing compounds in air can be separated and measured in a short time. The Agilent StableBond SB-C18 column gave excellent selectivity and provided a fast separation of the EPA list of carbonyl compounds in about 8 minutes.




Figure 3. Burlington site top (sample) bottom (field blank) SB-C18 4.6 mm × 150 mm × 1.8 μm.

References

1. Robert Ricker, "Separation of DNPH-Derivatized Aldehydes from Ambient Air Samples," Agilent Technologies, Publication No. 5988-6346EN (2002).
2. Noriko Shimoi and Hiroki Kumagai, "Analysis of Formaldehyde and Acetaldehyde in Air by HPLC Using DNPH Cartridge," Agilent Technologies, Publication No. 5965-9796E (1997).
3. Hiroki Kumagai, "HPLC Analysis of Formaldehyde in Indoor Air," Agilent Technologies, Publication No. 5867-5598E (1998).
4. Paul Kirschmer, "Aldehydes in Air," Hewlett Packard (now Agilent Technologies), Publication No. 12-5952-1551 (1990).
5. E. Grosjean, D. Grosjean, P.G. Green and J.M. Hughes, "LC.DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl)hydrazones," Agilent Technologies, Publication No. 5986-8850E (2000).

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
April 30, 2008
5989-7483EN



Agilent Technologies



High-Throughput Semiquantitative Screening of Ambient Air Samples by ORS-ICP-MS and Integrated Sample Introduction System (ISIS)

Application

Environmental

Author

Neal Julien
Midwest Research Institute (MRI)
Florida Division
Palm Bay, FL
USA

Abstract

A new method has been developed to analyze large numbers of air samples for trace metal content. To aid sample throughput, an Agilent Integrated Sample Introduction System (ISIS) was used with an Agilent 7500c Octopole Reaction System-ICP-MS operating in semiquantitative analysis mode. Using this methodology, 2,500 samples were analyzed for dissolved and extractable elemental composition in approximately 2 weeks. Instrument stability and reliability was demonstrated by good recoveries for the NIST 1643e water CRM. Data handling made use of macros to download and export sample results in a format easily imported by statistical analysis software.

Introduction

ICP-MS is unique in its ability to rapidly determine the approximate elemental composition of unknown samples using a process called “semiquantitative analysis” or “semiquant.” In semiquant, the mass spectrometer is rapidly scanned over the entire mass range, thereby detecting the response for every possible element or isotope. From these responses, semiquant can estimate the relative concentration of each element based on a table of known relative responses for all isotopes. If the concentration of a single or a few components is known, for example, an added internal standard(s), then the concentrations of the remaining

elements can be determined.

Traditionally, a limitation of semiquant has been the possibility of uncorrected polyatomic interferences leading to false positive results. While the advent of collision reaction cell (CRC) technology has significantly reduced this problem in quantitative ICP-MS, in most cases, it has not benefited semiquant in the same way. This is because semiquant must be performed with all elements acquired under identical conditions so that response factors can be interpolated across the mass range. Reactive CRC processes create new interferences and therefore cannot be used for all elements simultaneously. However, helium (He) collision mode does not create any new interferences and can be used to reduce virtually all polyatomic interferences using a process called kinetic energy discrimination. Semiquant analysis using He mode only is much less prone to interferences than traditional semiquant and can be used even in complex, unknown matrices. For these reasons, it is particularly useful in surveys where nothing is known about the possible composition of the samples, and therefore calibration for every possible element would be expensive and time consuming.

Since absolute quantitative accuracy and precision are not expected, semiquant can rely on fewer replicates and shorter integration times than quantitative analysis. In this work, the entire mass range is scanned in about 40 seconds. However, in order to take full advantage of the rapid acquisition, equally rapid sample handling is required. By using the Agilent Integrated Sample Introduction System (ISIS) in a segmented flow configuration, sample uptake and rinseout were reduced to about 20 seconds each. The result was a complete, fully automated semiquant survey of unknown samples



Agilent Technologies

in 1 minute per sample.

Midwest Research Institute (MRI)

MRI is an independent, not-for-profit research organization headquartered in Kansas City, Missouri, with laboratory facilities in Palm Bay, Florida, and Rockville, Maryland. MRI also manages the National Renewable Energy Laboratory in Golden, Colorado. The Institute performs research in energy, engineering, life sciences, national security, and defense.

Brevard Teaching and Research Laboratory (BTRL) was one of the earliest laboratories in Florida to acquire ICP-MS and has been using the technique for trace element analysis since 1991. The company was purchased by MRI in 1996 and recently acquired an Agilent 7500c to support research in bioanalytical and forensic applications.

Project Description

MRI was recently contracted to analyze 2,500 air samples collected using a SpinCon Advanced Air Sampler (Sceptor Industries, Kansas City, MO) for elemental composition. The SpinCon is a wet-concentrator air sampler designed to collect particulate matter and other airborne molecular material directly into a collection solution. The composition of the solution can be optimized to maximize recovery of specific analytes. The volume available for elemental analysis was approximately 5 mL; no information about sample composition was provided. After preliminary discussions with the client, it was determined that semiquantitative analysis would be sufficient, provided a measure of data quality could be defined and sample turnaround requirements could be satisfied. Finally, a turnaround time of 1 month was required to meet project scheduling demands.

Experimental

Materials and Methods

An Agilent 7500c ICP-MS with Octopole Reaction System (ORS) and ISIS was configured with an in-house design for rapid sample throughput (see Table 1 for operating parameters). A customized ISIS program was developed using Agilent's multi-pump module (MPM) builder software¹ to control

the ISIS valve and pumps for this application. The system was operated in a so-called "stream selection" mode to maximize sample throughput.

Calibration and check solutions were prepared from National Institute of Standards and Technology (NIST) traceable material. The instrument was calibrated before each use with a 29-component multi-element standard prepared from stock solutions obtained from SPEX Certiprep, Inc. (Metuchen, NJ).

NIST standard reference material 1643e, Trace Elements in Water, was diluted 10-fold with 1% nitric

Table 1. Instrumental Parameters for Agilent 7500c ORS ICP-MS

Parameter	Value
RF power	1500 W
Plasma gas flow	15.0 L/min
Auxiliary gas flow	1.0 L/min
Makeup gas flow	0.30 L/min
Helium (ORS) gas flow	2.0 mL/min
Sampling depth	6.0 mm
Spray chamber temperature	7 °C
Number of isotopes acquired	196
Integration time per isotope	100 ms

Sample Preparation

Air samples were collected using the SpinCon air sampler at a rate of 450 L/min directly into a 10-mL volume of a proprietary collection solution. A 5-mL aliquot was shipped to MRI (FL) and stored at 4 °C until processed.

Samples were prepared for dissolved and extractable element analysis in a final matrix of 1% nitric acid by volume. For dissolved element analyses, the sample was mixed thoroughly and a 200-μL aliquot removed then centrifuged at 1,000 rpm for 10 minutes. A 100-μL aliquot of the supernatant was removed and diluted to 1,000 μL with 1% nitric acid directly into an autosampler tube. For extractable element analysis, a 200-μL aliquot of sample was mixed with the processing reagents and shaken at room temperature for 10 minutes to simulate field processing. The sample was then diluted to a final volume of 2,000 μL with 1% nitric acid, centrifuged at 1,000 rpm for 10 minutes, and a 1,000-μL aliquot transferred to an autosampler tube. With this procedure, each sample produced two fractions for analysis, resulting in a total of 5,000 individual analyses.


¹ Available from Agilent by special request. The MPM builder allows the user to develop sophisticated, custom ISIS applications and integrate them into routine, automated ICP-MS analysis.

ISIS Programming

In the standard high-throughput ISIS application (Figure 1), the ISIS peristaltic pump (P1) is used to rapidly deliver the sample or rinse solution to the nebulizer peristaltic pump (P0), which operates at a fixed speed. The advantages of this constant flow approach are that the plasma is never disturbed by changes in the sample loading rate and stabilization delays are minimized, since less time is wasted waiting for the pump tubing to stretch and relax, as occurs when the pump speed is changed. A drawback is that at constant flow, approximately 35 seconds are required to move the sample from mixing tee 1 to the nebulizer and allow for signal stabilization. An additional 10 seconds are required to transfer the sample from the autosampler tube to mixing tee 1. With this configuration a stable signal profile is obtained approximately 45 seconds after the autosampler probe enters a sample.

Another consideration when using the standard ISIS configuration is the time penalty incurred to flush the sample still in the pump tubing when the analysis is complete, which is in addition to the normal rinse period. The rinse time required for this application was evaluated with a 1,000- $\mu\text{g/L}$ cobalt standard. Using a cyclonic spray chamber with an internal volume of 50 mL, the rinse time to reduce the signal by three orders of magnitude ($< 1 \mu\text{g/L}$) was approximately 40 seconds.

Given the constraints of the project, higher throughput was needed. Using standard high-throughput conditions with 40-second read time, the total time required for a single sample is approximately 120 seconds (rinse in/stabilize, 40 seconds; data acquisition, 40 seconds; and rinse out, 40 seconds). Using the CETAC ASX-510 autosampler, a fully loaded tray of 270 samples (three racks with 90 samples each) with calibration and QC checks every 20 samples requires approximately 10 hours, which is longer than the standard 8-hour shift.



P1 - feeds sample or rinse to mixing tee 1

P0 - feeds sample and internal standard to mixing tee 2 and drains spray chamber

Figure 1. Configuration for standard high-throughput application.

Based on previous designs of segmented and continuous flow techniques used at MRI in the past, a customized application (Figure 2) was developed which significantly reduced the time required to rinse the sample in and out of the ICP-MS system. This approach, termed stream-selection, reduces the overall cycle time by eliminating the delay associated with the nebulizer pump, with one major difference from the standard high-throughput approach: a switching valve is required. Like the standard high-throughput application, liquid handling may be performed using one ISIS pump in combination with the on-board nebulizer pump. The preferred configuration does away with the standard nebulizer pump entirely and uses two ISIS pumps for liquid handling.

In this configuration, the sample and rinse streams are independent and the ISIS valve selects which stream goes to the nebulizer. In addition, the flow rate of the sample stream is not coupled to the nebulizer and can be adjusted without disturbing the plasma. With this design, one ISIS pump (Figure 2, P1) is used to feed rinse solution to the nebulizer and add the internal standard. The other ISIS pump (Figure 2, P2) is used to manage the sample. During the load step, the sample is transferred at the maximum uptake rate to the valve. The pump is then slowed to the analysis speed and after a short delay (3 to 5 seconds) to allow the tubing to relax, the sample flow is switched online to the internal standard mixing tee and nebulizer. This arrangement maintains the advantages of constant-flow nebulization, with two additional benefits: the transfer time of the sample to the spray chamber is minimal since there is no pump between the valve and the nebulizer, and rinsing of the spray chamber can begin immediately upon completion of data acquisition by switching the valve back to the load position.

Using this system, a stable signal can be attained in approximately 20 seconds after the autosampler probe enters a sample, and rinse out from 1,000 µg/L to < 1 µg/L can still be accomplished within ~20 seconds of the completion of data acquisition. With a 40-second read time, the total time required for a single sample is reduced from approximately 120 seconds to approximately 70 seconds (rinse in/stabilize, 20 seconds; data acquisition, 40 seconds; and rinse out, 10 seconds). Note that the programmed rinse time is only 10 seconds. Since rinsing of the spray chamber continues to occur during the 20-second load step

for the following sample, the effective rinse time is actually 30 seconds. In certain circumstances (for example, samples of similar matrix composition with moderate analyte levels), the programmed rinse time could be eliminated altogether, reducing the cycle time even further. Using the CETAC ASX-510 autosampler, a fully loaded tray of 270 samples (three racks with 90 samples each) with calibration and QC checks every 20 samples requires approximately 6 hours, an improvement of approximately 40%. More significantly, the analysis can be completed in a single shift, with time available for a second run to be prepared and set up for after-hours analysis. A typical work day using this configuration is shown in Table 2, and a total of 540 samples can be processed daily.

Table 2. Typical Work Schedule with the Stream Selection Application


Time	Activity
8:00 - 8:30 a.m.	Instrument maintenance - check cones, pump tubing, and torch. Replace if necessary
8:30 - 9:15 a.m.	Plasma ignition and warm-up, load samples, setup software, download results from previous run
9:15 - 9:30 a.m.	Tuning and performance check
9:30 a.m.	Start run #1 (270 samples)
10 a.m. - 2:30 p.m.	Sample preparation for second run
3:30 p.m.	First run complete
3:30 - 4:00 p.m.	Instrument maintenance - check cones, pump tubing, and torch
4:00 - 4:30 p.m.	Plasma ignition and warm-up, load samples, set up software
4:30 - 4:45 p.m.	Tuning and performance check
4:45 p.m.	Start run #2 (270 samples)
10:45 p.m.	Run complete, instrument to standby

Results and Discussion

SRM Results

NIST 1643e was read 72 times over the course of the study. A control chart for six elements, selected to cover the full range of concentrations and shown with target recovery limits of $\pm 30\%$, is presented in Figure 3. Actual recoveries and %RSDs are presented in Table 3. Note that measured concentrations were actually 10 times lower than the certificate value and these results are corrected for dilution.

2A - Sample Load



2B - Sample Inject




Figure 2. Configuration for stream selection application.




Figure 3. Long-term stability of six representative elements in NIST 1643e (diluted 10x) covering the range of concentrations.

Table 3. Recovery of Certified Concentrations in NIST 1643e, n = 72

Element	Expected (mg/L)	Actual (mg/L)	%RSD (n = 72)	Recovery (%)
Be	0.014	0.014	19	98.5
Na	20.74	22.09	11	107
Mg	8.037	8.867	8.5	110
Al	0.142	0.148	25	105
K	2.034	2.246	11	110
Ca	32.30	32.54	10	100
V	0.038	0.039	8.9	103
Cr	0.020	0.021	11	106
Mn	0.039	0.041	8.4	105
Fe	0.098	0.104	9.0	106
Co	0.027	0.027	7.7	101
Ni	0.062	0.063	10	101
Cu	0.023	0.022	15	94.1
Zn	0.079	0.079	12	101
As	0.060	0.064	12	106
Rb	0.014	0.013	16	92.2
Sr	0.323	0.312	6.4	96.6
Mo	0.121	0.118	7.7	97.4
Ag	0.001	0.001	22	81.4
Cd	0.007	0.007	12	99.3
Sb	0.058	0.056	10	96.3
Ba	0.544	0.516	15	94.9
Tl	0.007	0.007	25	94.5
Pb	0.020	0.018	19	88.6

Sample Results

Samples were analyzed without incident for the duration of the project. Using this approach, 2,500 samples were analyzed for dissolved and soluble element composition (a total of 5,000 analyses) in approximately 10 days. Analytical results were exported to a dedicated database using post-run macros for statistical analysis.

As expected, the elemental distribution in most samples was dominated by the mineral elements, with Na, K, Ca, and Mg accounting for > 98% of the total elemental composition. Elements typically associated with urban airborne particulates, such as aluminum, iron, and zinc, were found in moderate (> 0.5 mg/L) to high (> 1 mg/L) concentrations in all samples. This was expected since sampling took place primarily in urban areas.

In all cases, measured concentrations were higher in the extractable analysis compared to the dissolved analysis. This was expected since particulate matter in the sample was expected to release loosely bound elemental components to the extracting solvent. Several samples were found to contain levels of toxic metals at least 10 times higher than the average value, but no conclusions can be made since site-specific information was not provided.

Conclusions

It has been demonstrated that with careful selection of the collection fluid, samples collected by the SpinCon advanced air sampler are directly compatible with trace element analysis. By using semiquant analysis in He-only mode, with custom ISIS programming to maximize throughput, it was possible to analyze 2,500 samples for dissolved and extractable elemental composition in approximately 2 weeks, meeting the project turnaround time requirements. This ISIS program could also be used to improve throughput in quantitative applications with similar results. The performance of the Agilent 7500c system was stable and reliable for the duration of the project as demonstrated by good recoveries for the NIST 1643e water CRM. The use of macros to download and export sample results significantly reduced the time spent preparing analysis reports and produced data in a format easily imported by our statistical analysis software.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

The information contained in this publication is intended for research use only and is not to be followed as a diagnostic procedure.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
January 30, 2007
5989-6123EN



Agilent Technologies



Screening for 171 Volatile Organic Air Pollutants Using GC/MS with Deconvolution Reporting Software and a New Indoor Air Toxics Library

Application

Environmental

Author

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Rd.
Wilmington, DE 19808-1610
USA

Matthew Bates and Elizabeth Woolfenden
Markes International
Gwaun Elai Medi Science Campus
Llantrisant
RCT, CF72 8XL
UK

Abstract

A retention-time-locked mass spectral database was created specifically for indoor air analysis by thermal desorption/gas chromatography/mass spectroscopy (TD/GC/MS). This Indoor Air Toxics Database contains locked retention times and mass spectra for 171 volatile and semivolatile organic compounds that are targets in various indoor air methods. In combination with Agilent's Deconvolution Reporting Software (DRS), it is possible to identify any of these compounds in just 2 to 3 minutes after a TD/GC/MS analysis. A key feature of DRS is the ability to deconvolute overlapping mass spectra so that unresolved GC peaks can be identified reliably. Agilent's DRS generates a report that combines results from three data analysis programs – the Agilent ChemStation, the Automated Mass Spectral Deconvolution and Identification System, and the National Institute of Standards and Technology MS Search Program. Air samples from an office building and a carpet warehouse were collected on Tenax TA-packed TD tubes and were analyzed by TD/GC/MS. Using the Indoor Air Toxics Database, DRS was able to identify more than 80 compounds in the office air and 102 in the carpet store air. Data analysis was automated and required about 3 minutes per sample to complete.

Introduction

At sea-level and 15 °C, air is 99.9997147% nitrogen, oxygen, argon, carbon dioxide, neon, methane, helium, krypton, hydrogen, and xenon [1]. The remaining constituents are mostly organic chemicals that can number into the thousands. Some of these are either irritating or toxic to people who are exposed to them. Indoor air usually contains more volatile and semivolatile organic compounds (VOCs and SVOCs) than outdoor air. For example, the USEPA's "Total Exposure Assessment Methodology studies found levels of about a dozen common organic pollutants to be 2 to 5 times higher inside homes than outside, regardless of whether the homes were located in rural or highly industrial areas" [2].

Sources for VOCs in homes and offices include building materials such as plywood, particle board, and paints; furnishings such as carpets, furniture, and office machines; stored fuels, solvents, aerosol sprays, cleaning products and household chemicals; heating and cooling systems; manufacturing processes; and even dry-cleaned clothing. Since most people in industrialized countries spend 80% to 90% of their time in a home, school, office building, or a vehicle, indoor air pollution is a major concern.

This application discusses a new method for the analysis of 171 naturally occurring and anthropogenic VOCs and SVOCs that are found in air. The focus is primarily on toxic compounds found in indoor air that may contribute to sick-building syndrome or cause untoward health affects.

This new method makes it possible to screen GC/MS chromatograms for all 171 toxic VOCs in 2 to 3 minutes after data acquisition. The method



Agilent Technologies

uses Agilent's Deconvolution Reporting Software (DRS) [3–9] together with a mass spectral database that contains the locked retention times (RTs) for each of the 171 analytes.

While the method can accommodate any means for VOC sample introduction, it was designed for use with the Markes International UNITY™ Thermal Desorber. Air samples are conveniently collected on TD tubes that may be packed with one or more sorbents. In UNITY, these tubes are heated under a reverse flow of carrier gas to sweep the trapped volatiles into a sorbent-packed cold trap. The concentrated sample is then transferred to the GC column by heating the cold trap rapidly under a reverse flow of helium.

Experimental

Table 1 lists the instrumentation, software, and analytical parameters used by Agilent for air analysis with DRS and the new Indoor Air Toxics Library.

Table 1. Instrumentation and Conditions of Analysis

Thermal desorption system	Markes UNITY with a Markes Ultra™ autosampler
Prepurge time	1.0 min
Primary desorb	280 °C for 5.0 min
Trap low temp	–10 °C
Trap desorb	300 °C for 3.0 min
Trap	General purpose hydrophobic
Flow path temp	140 °C
Nominal carrier gas pressure	30.9 psi
Desorb flow	20 mL/min
Split ratio	Varies from 50:1 to splitless depending upon the sample
Sample tube	3.5-inch × 0.25-inch deactivated stainless steel packed with Tenax TA
Sample pump	SKC Pocket Pump 210-1002 (SKC, Inc. Eighty Four, PA USA)
Software for pump control	SKC DataTrac software for Pocket Pump Ver. 2.07
Pump flow rate	200 mL/min
Gas chromatograph	Agilent 6890N
Column	Agilent 60 m × 0.25 mm × 1.4 µm DB-VRX (p/n 122-1564)
Carrier gas	Helium in the constant pressure mode

Retention time locking	Toluene locked to 12.468 min or Toluene-d8 locked to 12.366 min (nominal column head pressure = 30.91 psi)
Oven temperature program	45 °C (3 min), 10 °C/min to 190 °C (0 min), 20 °C/min to 250 °C (8 min)
Mass selective detector	Agilent 5975 inert
Tune file	Atune.u
Mode	Scan
Scan range	33 to 300 u
Source, quad, transfer line temperatures	230, 150, and 260 °C, respectively
Solvent delay	0.00 min
Multiplier voltage	Autotune voltage
Software	
GC/MSD ChemStation	Agilent p/n G1701DA (Ver. D02.00 sp1 or higher)
DRS	Agilent p/n G1716AA (Ver. A.03.00) DRS
Library searching software	NIST MS Search (Ver. 2.0d or greater) (comes with NIST '05 mass spectral library — Agilent p/n G1033A)
Deconvolution software	Automated Mass Spectral Deconvolution and Identification Software (AMDIS_32 Version 2.62; comes with NIST'05 mass spectral library — Agilent p/n G1033A)
MS libraries	NIST'05 Mass Spectral Library (Agilent p/n G1033A) and Agilent Indoor Air Toxics Libraries in Agilent and NIST formats (p/n G1673AA)
DRS setpoints	
Minimum match factor	60
RI window	10 (seconds)
Component width	12
Adjacent peak subtraction	one
Resolution	High
Sensitivity	High
Shape requirements	High
Use uncertain peaks?	Yes and no. Samples were analyzed under both conditions

Sample Collection

Indoor air samples were collected on Tenax® TA-packed TD tubes by active sampling using the SKC pocket pump. Six- or twelve-liter air samples were collected by pumping at 200 mL/min for either 30 minutes or 1 hour. Tenax TA is classified as a weak sorbent and is not very effective at trapping compounds that are less volatile than n-heptane. As seen in Figure 1, many of the more volatile compounds were identified by this procedure even though they were not trapped quantitatively.

Results and Discussion

Figure 1 shows a GC/MS chromatogram for a sample of air collected inside of an office building. While there are only about a dozen major peaks in the chromatogram, there are numerous minor ones. It is usually easy to identify the larger peaks with conventional GC/MS analysis, especially

when they are well separated chromatographically. However, the toxicity of airborne chemicals varies over many orders of magnitude, and some of the smaller peaks may be far more significant than the larger ones. As seen in the inset, many peaks are poorly resolved while others may be completely obscured by much larger overlapping analytes. It is a tedious process to identify all of the important analytes in such chromatograms. DRS is designed to simplify this process while producing far more accurate peak identifications.

DRS

Agilent's DRS combines the results from three complimentary GC/MS data analysis packages. First, the GC/MS ChemStation software performs a normal quantitative analysis for all calibrated compounds using a target ion and up to three qualifiers. An amount is reported for all calibrated compounds that are detected.




Figure 1. TD/GC/MS chromatogram of an air sample collected in an office building. The inset shows that many peaks are poorly resolved and could be difficult to identify with normal GC/MS data analysis.

Then, DRS sends the data file to a spectral deconvolution package developed by the National Institute for Standards and Technology (NIST). This software, called Automated Mass Spectral Deconvolution and Identification System (AMDIS), deconvolutes the spectra of overlapping chromatographic peaks [10]. While a thorough discussion of deconvolution is beyond the scope of this paper, the basic principles are illustrated in Figure 2.

The chromatographic peak shown in black looks Gaussian, but it is actually the result of at least three compounds that were only partially resolved. The spectrum at the apex of this peak is composed of ions from all three compounds, some of which are common to two or three of the overlapping analytes. AMDIS deconvolutes the chromatogram and pulls out “cleaned spectra” from the overlapping peaks. In most cases, AMDIS is very successful at isolating a compound’s spectrum from column bleed, other analytes, and co-extracted interferences, even when interference abundances are far greater than the target analyte.

Using the deconvoluted full spectrum, AMDIS searches each peak against Agilent’s RTL Indoor Air Toxics Library and reports a hit if the match quality exceeds a user-settable threshold. As a further requirement for compound identification, the user can require the analyte’s RT to fall within a specified time window. Because retention time locking (RTL) is used to reproduce the database RTs with high precision, this window can be quite small – typically 10 to 20 seconds.

As a confirmation step, the deconvoluted spectra of all AMDIS hits are searched against the 163,000-compound NIST mass spectral library; for this step, there is no RT requirement. More details about DRS can be found in earlier publications [3–9].

Figure 3 shows the report generated by DRS for the office air sample shown in Figure 1. Each identified compound is reported with its RT, CAS #, and compound name. If the sample contains an internal standard and if the compound has been calibrated, an amount is reported in the fourth column. The amounts are calculated by the ChemStation software when it identifies a compound. As shown in Figure 3, values of “0” are reported when the ChemStation finds the compound but there is no internal standard and/or calibration table. For this example, a minimum match factor of 60 was required by AMDIS but only one match value was less than 70 and only six more were less than 80. Column 6 reports the difference (in seconds) between each analyte’s RT in the current chromatogram and the Indoor Air Toxics RTL Database. For this analysis, AMDIS was configured so that peaks had to elute within 10 seconds of their database RT to be identified as a hit. It is straightforward to match the database RTs using RTL, so most of the differences were well under the 10-second requirement.




Figure 2. An illustration showing how AMDIS deconvolution software can extract “clean” spectra from unresolved chromatographic peaks. The deconvoluted spectra can be searched against normal mass spectral libraries with a high probability of finding a good match.

MSD Deconvolution Report

Sample Name: Sample 1

Data File: C:\Documents and Settings\lfs-wyllie\My Documents\My GC_MS Data\Thermal Desorption Data

August 05\Aug 11_05\Little Falls Office Air 12 L near Sheila.D

Date/Time: 02:36 PM Thursday, Jun 15 2006

The NIST library was searched for the components that were found in the AMDIS target library.

R.T.	Cas #	Compound Name	Agilent ChemStation Amount (ng)	AMDIS Match	R.T. Diff sec.	NIST Reverse Match	Hit Num.
3.8545	75070	Acetaldehyde	0	100	3.6	97	1
4.3465	74839	Bromomethane		87	3.1	97	1
5.1977	75694	Trichlorofluoromethane	0	82	4.6	63	1
5.2307	67630	2-Propanol		95	4.8	92	1
5.3256	67641	Acetone		94	4.4	89	1
5.8065	109875	Dimethoxymethane		80	4.5	86	1
5.8447	75650	tert-Butanol		97	3.8	90	1
5.9033	107131	Acrylonitrile		72	4.8	96	1
6.0007	75092	Dichloromethane	0	100	3.8	93	1
6.2969	75150	Carbon disulphide		99	3.9	95	1
6.4849	71238	1-Propanol		97	5.3	88	1
6.8607	107835	2-Methylpentane		99	2.4	95	1
6.9439	1634044	Methyl tert-butylether	0	92	2.2	93	1
7.227	96140	3-Methylpentane	0	100	3.2	94	1
7.6239	110543	n-Hexane		97	3.0	87	1
7.6543	78933	2-Butanone (MEK)		95	4.0	92	1
8.056	141786	Ethyl acetate	0	98	3.0	95	1
8.0896	67663	Chloroform		96	3.0	93	1
8.472	96377	Methylcyclopentane	0	92	2.8	87	1
8.5039	109999	Tetrahydrofuran (THF)	0	100	2.9	96	1
8.9263	107062	1,2-Dichloroethane		96	2.5	91	1
9.0558	71556	1,1,1-Trichloroethane	0	97	1.8	91	1
9.1309	71363	1-Butanol	0	100	2.9	90	1
9.3141	108214	Isopropyl acetate		99	2.1	95	1
9.3658	563804	3-Methyl-2-butanone		82	2.4	91	1
9.4254	110827	Cyclohexane		73	1.8	66	5
9.4332	591764	2-Methylhexane		93	2.3	83	1
9.5361	56235	Tetrachloromethane	0	98	1.9	96	1
9.5869	71432	Benzene	0	98	2.1	94	1
9.6552	107982	1-Methoxy-2-propanol		76	2.8	87	1
9.6749	589344	3-Methylhexane	0	100	1.0	94	1
10.1401	540841	2,2,4-Trimethylpentane	0	97	1.2	94	1
10.2925	142825	n-Heptane		96	1.4	93	1
10.4336	79016	Trichloroethene	0	98	1.4	94	1
10.5149	75274	Bromodichloromethane		80	2.2	81	5
10.6556	123911	1,4-Dioxane		81	2.3	89	3
10.677	109604	Propyl acetate	0	97	1.9	94	1
10.6903	80626	Methyl methacrylate	0	97	1.0	87	1
11.1379	108872	Methylcyclohexane	0	99	0.9	94	1
11.5350	108101	4-Methyl-2-pentanone (MIBK)	0	99	1.3	92	1
11.8726	71410	1-Pentanol	0	100	1.2	94	1
12.2704	589811	3-Methylheptane		97	0.6	94	1
12.4818	108883	Toluene		99	0.8	94	1

Figure 3. DRS report for a sample of air collected inside of an office building. A TD/GC/MS chromatogram of this sample is shown in Figure 1. In about 3 minutes, nearly 90 compounds were identified in this sample using DRS and Agilent's Indoor Air Toxics Database.

12.6892	111660	1-Octene		89	0.6	80	1
12.7378	68122	N,N-Dimethylformamide		71	7.3	93	1
12.9064	111659	n-Octane		100	0.9	95	1
12.9954	66251	n-Hexanal		99	1.3	90	1
13.2226	123864	n-Butyl acetate	0	98	-0.1	95	1
13.5330	127184	Tetrachloroethene	0	94	-0.1	92	1
14.4034	111273	1-Hexanol		94	-0.2	83	3
14.5296	108907	Chlorobenzene		86	0.1	92	1
14.6878	2216333	3-Methyloctane	0	98	-0.7	93	1
14.8209	100414	Ethylbenzene	0	99	-0.0	96	1
14.9607	108930	Cyclohexanol		61	-7.2		
14.9607	53771883	Cyclopentane, 1-methyl-3-(1-methylethyl)-				74	1
15.1076	108383	m-Xylene	0	100	0.3	95	1
15.109	106423	p-Xylene	0	100	-0.9	96	1
15.297	111842	n-Nonane	0	80	-0.1	83	1
15.6080	100425	Styrene	0	100	-0.2	96	1
15.6329	108941	Cyclohexanone	0	93	0.1	84	1
15.7194	95476	o-Xylene	0	99	-0.1	95	1
16.2615	98828	Isopropylbenzene (cumene)	0	99	-1.2	86	4
16.5140	80568	alpha-Pinene		99	-1.1	93	1
16.8949	108952	Phenol		83	0.2	86	2
16.9587	103651	n-Propylbenzene		82	-0.0	81	1
16.9629	79925	Camphene	0	98	-1.2	85	1
17.1163	620144	m-Ethyltoluene	0	99	-1.3	96	2
17.3947	108678	1,3,5-Trimethylbenzene		93	-0.7	87	4
17.5571	98839	alpha-Methylstyrene (2-propenyl benzene)		73	-0.9	69	5
17.5620	127913	beta-Pinene	0	99	-1.1	94	1
17.6099	611143	o-Ethyltoluene		76	-1.0	75	4
17.7008	124130	n-Octanal		95	1.2	89	1
17.9831	95636	1,2,4-Trimethylbenzene	0	97	-1.4	93	3
18.018	104767	2-Ethyl-1-hexanol	0	96	-1.0	94	1
18.1096	13466789	delta-3-Carene	0	98	-1.4	94	1
18.3657	541731	1,3-Dichlorobenzene	0	98	6.6	94	1
18.3666	106467	p-Dichlorobenzene	0	99	-0.9	91	3
18.4226	99876	p-Isopropyltoluene (p-Cymene)		89	1.0	91	1
18.4556	5989275	Limonene	0	98	-1.5	93	1
18.6311	526738	1,2,3-Trimethylbenzene		82	-1.2	79	2
19.1411	95136	Indene		81	-1.1	94	4
19.3949	98862	Acetophenone	0	99	-1.2	94	1
19.5943	124196	n-Nonanal	0	97	1.0	95	1
21.202	112312	n-Decanal	0	100	0.4	94	1
21.7534	91203	Naphthalene		94	-2.3	89	1
21.8340	87683	Hexachlorobutadiene		82	-1.2	56	3
23.8346	629594	n-Tetradecane	0	96	-3.6	90	1
25.3658	629629	n-Pentadecane	0	80	-4.3	92	1
26.1682	128370	2,6-di-t-Butyl-4-methylphenol (BHT)		98	-4.7	88	2
27.1476	544763	n-Hexadecane		99	-5.4	91	1

Figure 3. Continued

As a further check on a peak's identity, the deconvoluted spectrum of each hit is searched against the NIST'05 mass spectral library, which contains more than 163,000 compounds. If the compound identified by AMDIS (using the Indoor Air Toxics Library) is among the top 100 NIST'05 library hits, its match factor and hit number are reported in columns 7 and 8, respectively. For the office air sample, the first NIST library match corresponded with the AMDIS results most of the time; in all cases the best hit was among the top 5.

Isomers and compounds with similar structures can have virtually identical mass spectra. So it is not expected that the first NIST library hit will always be the best match for the deconvoluted spectrum. When searching the Indoor Air Toxics Library, DRS takes advantage of RT filtering, which helps to eliminate isomers and other compounds with similar structures and mass spectra. There is no RT requirement for the NIST'05 library search, so structural isomers might have equal or even

slightly better NIST library matches than the true compound. If the NIST hit number in column 8 is large (perhaps greater than 5 or 10), it is wise to look at the AMDIS match value and RT difference. If the match value is low or the RT difference is high, manual peak evaluation is recommended. For most samples, no manual re-evaluation of the results is needed. An exception is discussed below.

Analysis of Air from a Carpet Store

Figure 4 shows a chromatogram obtained for an air sample that was collected inside a carpet warehouse. The warehouse had rolls of new carpet stacked floor to ceiling along each wall. A 12-L air sample was collected on a Tenax tube over a 1-hour period from random places inside the warehouse. Analysis was performed using the Markes UNITY Thermal Desorber in the splitless mode.




Figure 4. TD/GC/MS chromatogram of a 12-L air sample collected in a carpet store using a Tenax TA TD tube. Figure 5 shows the DRS report for this sample.

MSD Deconvolution Report

Sample Name: Sample 1

Data File: C:\Documents and Settings\lfs-wylie\My Documents\My GC_MS Data\Thermal Desorption Data

August 05\Aug 12_05\Carpet store 12 L splitless.D

Date/Time: 01:32 PM Friday, Jun 16 2006

The NIST library was searched for the components that were found in the AMDIS target library.

R.T.	Cas #	Compound Name	Agilent ChemStation Amount (ng)	AMDIS Match	R.T. Diff sec.	Reverse Match	Hit Num.
3.8527	75070	Acetaldehyde	0	94	3.5	97	1
4.3398	74839	Bromomethane		74	2.7	92	1
5.1975	75694	Trichlorofluoromethane		75	4.6	82	2
5.2367	67630	2-Propanol	0	100	5.1	96	1
5.3270	67641	Acetone		97	4.5	91	1
5.4380	110009	Furan		64	3.1	96	15
5.7943	109875	Dimethoxymethane		100	3.7	94	1
5.8426	75650	tert-Butanol	0	99	3.6	92	1
5.8901	107131	Acrylonitrile		71	4.0	93	1
5.9976	75092	Dichloromethane		89	3.6	82	1
6.2886	75150	Carbon disulphide		99	3.4	95	1
6.4757	71238	1-Propanol	0	99	4.7	92	1
6.8530	107835	2-Methylpentane	0	100	1.9	95	1
6.9453	1634044	Methyl tert-butylether		92	2.3	96	1
7.2185	96140	3-Methylpentane	0	100	2.5	96	1
7.2754	108054	Vinyl acetate		87	3.3	93	2
7.4955	123728	n-Butanal		65	2.3	65	7
7.6153	110543	n-Hexane		89	2.5	79	2
7.6392	78933	2-Butanone (MEK)		87	3.1	90	1
8.0532	141786	Ethyl acetate	0	100	2.7	96	1
8.090	67663	Chloroform	0	96	3.0	92	1
8.1464	96333	Methyl acrylate	0	98	3.1	96	1
8.468	96377	Methylcyclopentane	0	90	3.0	84	1
8.5105	109999	Tetrahydrofuran (THF)		85	3.3	91	1
8.9170	107062	1,2-Dichloroethane		82	1.9	91	1
9.052	71556	1,1,1-Trichloroethane	0	93	1.6	74	1
9.1277	71363	1-Butanol	0	100	2.7	90	1
9.3090	108214	Isopropyl acetate		99	1.8	95	1
9.3634	563804	3-Methyl-2-butanone		68	2.2	62	78
9.4194	591764	2-Methylhexane		93	1.5	84	1
9.4233	110827	Cyclohexane		89	1.7	75	1
9.5320	56235	Tetrachloromethane	0	99	1.7	96	1
9.5854	71432	Benzene	0	100	2.0	95	1
9.6547	107982	1-Methoxy-2-propanol	0	81	2.7	88	1
9.6705	589344	3-Methylhexane	0	100	0.8	94	1
10.1347	540841	2,2,4-Trimethylpentane		81	0.9	94	1
10.2907	142825	n-Heptane		85	1.3	86	1
10.384	78875	1,2-Dichloropropane	0				
10.4263	79016	Trichloroethene	0	100	0.9	95	1
10.6464	123911	1,4-Dioxane		93	1.7	94	1
10.6681	109604	Propyl acetate	0	98	1.0	97	1
10.6875	80626	Methyl methacrylate		84	0.8	84	1
11.140	108872	Methylcyclohexane	0	98	1.0	94	1
11.5293	108101	4-Methyl-2-pentanone (MIBK)	0	100	1.0	92	1
11.7420	624920	Dimethyldisulphide		70	1.5	88	1
11.8714	71410	1-Pentanol	0	98	1.2	92	1
11.8873	107926	Butyric acid		67	5.3	88	2
12.2602	589811	3-Methylheptane		89	0.0	91	1
12.4812	108883	Toluene		99	0.8	94	1
12.6712	111660	1-Octene		84	-0.5	82	7
12.9043	111659	n-Octane		92	0.7		

Figure 5. DRS report for a sample of air collected inside a carpet store. A TD/GC/MS chromatogram of this sample is shown in Figure 4. In about 3 minutes, more than 100 compounds were identified in this sample using DRS and Agilent's Indoor Air Toxics Database.

12.9043	691372	1-Pentene, 4-methyl-				80	1
12.9861	66251	n-Hexanal		99	0.8	91	1
13.2195	123864	n-Butyl acetate	0	99	-0.3	96	1
13.5377	127184	Tetrachloroethene	0	99	0.2	97	1
14.4028	111273	1-Hexanol		84	-0.2	81	6
14.5265	108907	Chlorobenzene		94	-0.1	89	1
14.6812	2216333	3-Methyloctane		96	-1.1	81	1
14.8181	100414	Ethylbenzene	0	98	-0.2	95	1
15.0870	108930	Cyclohexanol		68	0.4	76	2
15.0958	108383	m-Xylene	0	100	-0.4	95	3
15.103	106423	p-Xylene	0				
15.2896	111842	n-Nonane		100	-0.6	95	1
15.4525	111762	2-Butoxyethanol		98	0.6	89	1
15.6036	100425	Styrene	0	100	-0.4	95	1
15.6243	108941	Cyclohexanone	0	97	-0.4	94	1
15.7114	95476	o-Xylene	0	99	-0.6	96	1
16.2610	98828	Isopropylbenzene (cumene)	0	98	-1.3	88	4
16.5167	80568	alpha-Pinene	0	99	-0.9	95	1
16.7452	871830	2-Methylnonane	0	84	-1.1	80	1
16.9015	108952	Phenol	0	98	0.6	92	2
16.9413	103651	n-Propylbenzene		94	-1.1	89	1
17.0899	95498	2-Chlorotoluene	0	94	0.5	82	1
17.1177	620144	m-Ethyltoluene		93	-1.2	91	3
17.3867	108678	1,3,5-Trimethylbenzene	0	98	-1.2	94	1
17.4708	124185	n-Decane	0	96	-1.3	88	1
17.4711	872059	1-Decene		72	8.5	69	78
17.5598	127913	beta-Pinene	0	86	-1.2	79	2
17.6038	611143	o-Ethyltoluene	0	97	-1.4	93	1
17.6819	124130	n-Octanal		83	0.1	77	2
17.9868	95636	1,2,4-Trimethylbenzene	0	97	-1.2	92	2
18.0191	104767	2-Ethyl-1-hexanol		95	-0.9	90	1
18.0434	622979	p-Methylstyrene		72	-1.1	88	11
18.0456	611154	o-Methylstyrene		83	3.5	78	14
18.1146	13466789	delta-3-Carene	0	90	-1.1	90	1
18.1525	135988	sec-Butylbenzene		79	0.6	89	5
18.2952	99876	p-Isopropyltoluene (p-Cymene)		93	-6.6	89	6
18.3438	106467	p-Dichlorobenzene		65	-2.2		
18.3438	55030176	Carbonic acid, ethyl 3-(1-methylethoxy)phenyl ester				67	1
18.3616	541731	1,3-Dichlorobenzene		96	6.4	95	1
18.4515	5989275	Limonene		80	-1.7	78	1
18.6270	526738	1,2,3-Trimethylbenzene		98	-1.4	94	2
18.7574	111875	1-Octanol		76	-1.7	72	18
18.8820	95501	1,2-Dichlorobenzene		76	0.8	94	2
19.0131	104518	n-Butylbenzene		77	-1.4	72	13
19.1341	95136	Indene	0	81	-1.5	91	3
19.3458	1120214	n-Undecane		81	-1.5	81	1
19.3937	98862	Acetophenone		97	-1.3	92	1
19.5892	124196	n-Nonanal		84	0.7	63	1
20.8036	112345	2-(2-Butoxyethoxy)ethanol		82	-2.2	82	2
20.9162	112403	n-Dodecane	0	98	-2.6	87	6
21.1871	112312	n-Decanal		86	-0.5	64	1
21.760	91203	Naphthalene	0	99	-1.8	96	1
21.818	87683	Hexachlorobutadiene	0				
22.3957	629505	n-Tridecane	0	93	-2.0	61	42
23.8389	629594	n-Tetradecane		95	-3.3	91	1
25.3715	629629	n-Pentadecane	0	97	-4.0	92	1
25.4035	475207	Longifolene		86	-3.6	83	8
26.1677	128370	2,6-di-t-Butyl-4-methylphenol (BHT)		92	-4.8	81	6
27.1364	544763	n-Hexadecane	0	98	-6.1	91	1

Figure 5. Continued

Reviewing the Results

Agilent's DRS software identified 108 compounds in the carpet store air sample. For most compounds, the AMDIS match quality was high (>80) and the RT difference was small (<5 seconds). Furthermore, most compounds had an excellent match to the NIST'05 spectral library and were the top hit or at least among the top five. These compounds have been identified with very high confidence.

As mentioned earlier, it is a good idea to review compounds that have a large deviation from the database RT, have a borderline match to the Indoor Air Toxics Library, or are not among the top 5 to 10 hits in the NIST library search. Table 2 lists 11 compounds (of the 108 reported) where further evaluation was helpful.

Three compounds (1,2-dichloropropane, p-xylene, and hexachlorobutadiene) were found by the ChemStation but not by AMDIS (Table 1). Experience has shown that AMDIS rarely, if ever, fails to corroborate the presence of a compound identified by the ChemStation when it is actually present. Therefore, these compounds could be eliminated easily as false positives. While p-xylene might be present, it is impossible to distinguish it from m-xylene, which was also reported. These isomers are normally reported together.

AMDIS occasionally finds ions that may or may not belong to the spectrum for a peak it has found. So, AMDIS can be configured to search the NIST'05 library with or without these "uncertain" peaks included. The inclusion or exclusion of uncertain

peaks can sometimes mean the difference between a good NIST'05 library match and a poor one. Therefore, it is a good idea to run DRS in both configurations if any of the NIST library confirmations are ambiguous. The new version of DRS software (G1716 Ver. A.03.00) allows the user to choose this setting in the Compound Identification Configuration screen shown in Figure 6, which can be reached from the DRS drop-down menu item.

Table 2 shows some examples where the inclusion of uncertain peaks makes a difference in the NIST'05 library search. For example, dimethyldisulfide was not found among the top 100 hits when uncertain peaks were included (columns 6 and 7 in Table 2). However, when those spectral peaks were excluded, dimethyldisulfide was the best spectral match (columns 8 and 9 in Table 2).




Figure 6. Compound Identification Configuration window in the DRS software. Users can edit these setpoints under Method Association Settings. One of the choices is whether or not to use uncertain peaks when searching the NIST'05 mass spectral library.

Table 2. Compounds with Ambiguous Identifications Using DRS Software with Initial AMDIS Setpoints That Included Uncertain Peaks. The data file was re-analyzed with uncertain peaks excluded. The last column shows the final assessment after analyzing the data with and without the uncertain peaks included for the NIST library search.

RT (min)	Name	Found by Chem-Station	AMDIS match	RT dif (s)	NIST match using uncertain peaks	Hit number using uncertain peaks	NIST match not using uncertain peaks	Hit number not using uncertain peaks	Presence confirmed
10.384	1,2-Dichloropropane	Yes	None	None	None	None	None	None	No
11.742	Dimethyldisulfide	No	70	1.5	None	None	88	1	Yes
11.887	Butyric acid	No	67	5.3	62	6	88	2	Yes
15.103	p-Xylene	Yes	None	None	None	None	None	None	#
16.745	2-Methylnonane	Yes	84	-1.1	70	80	80	1	Yes
17.471	1-Decene	No	72	8.5	74	34	69	78	No
18.115	delta-3Carene	Yes	90	-1.1	85	8	90	1	Yes
18.757	1-Octanol	No	76	-1.7	72	75	72	18	No
19.013	n-Butylbenzene	No	77	-1.4	73	9	72	13	No
21.818	Hexachlorobutadiene	Yes	None	None	None	None	None	None	No
22.396	n-Tridecane	Yes	93	-2.0	84	9	61	42	Yes

m-Xylene was identified at 15.096 min. p-Xylene may be present but spectral and RT similarity makes it impossible to differentiate between it and m-xylene.

The only really ambiguous hits were those that had a relatively low AMDIS target library match and poor NIST'05 library matches with and without uncertain peaks included. For this sample, manual review was only needed for 1-decene, 1-octanol, n-butyl benzene, and n-tridecane. Of the four, only n-tridecane could be confirmed.

Of the 108 target VOCs reported, six were eliminated using these data review procedures. The AMDIS settings (Figure 6) for this analysis were chosen to be quite sensitive to small peaks obscured by high background. The minimum match factor was set to 60 (Figure 7A), while the resolution, sensitivity, and shape requirements were all set to 'high' (Figure 7B). These settings can identify more peaks, but as seen in Table 2, can sometimes report a few false positives. However, false positives are usually easy to spot by looking at the DRS report. They typically have a lower AMDIS target library match value with a larger than usual RT deviation and have a lower NIST'05 library match and hit number. Because DRS runs in 2 or 3 minutes, it is easy to change any of the AMDIS settings and re-analyze the data file.

DRS was able to identify numerous halogenated compounds, nonhalogenated solvents, aromatics, and monomers in the carpet store air. Many of these compounds undoubtedly evolved from the carpet and would be at their highest concentrations when the carpet is new. However, carpet also adsorbs VOCs and may evolve them at a later time.

Quantitative Analysis

It is impossible to quantify a compound that is not first identified by the method. DRS helps by making reliable identifications. As usual, quantitative analysis requires that the target compounds be calibrated using standards. As seen in Figures 3 and 5, AMDIS often finds analytes that were missed by the ChemStation. These compounds can be quantified (if calibrated) using the QEdit feature of the Agilent ChemStation.




Figure 7. Two windows from the AMDIS software showing the deconvolution setpoints used for these analyses. These windows are accessed within the AMDIS software under the "Analyze/Settings" drop-down menu item.

Under **View**, choose **QEdit Quant Result**, which opens this software tool (Figure 8). Compounds marked with an 'X' in the Quick Edit list were found by the ChemStation. Cyclohexane was found by DRS but failed to meet the ChemStation's ion ratio requirements. By double-clicking on cyclohexane in the Quick Edit window, QEdit extracts cyclohexane's target and qualifier ions and highlights its expected RT with a dashed line. The user can integrate the peak using the mouse (hold down the right button and draw in the baseline) and save it to the integration report.

Rather than calibrate for all compounds, some methods allow certain target concentrations to be estimated. Such compounds are given toluene's response factor and are reported as "toluene equivalents."

Conclusions

Most indoor air contains a wide variety of volatile and semivolatile organic compounds, many of which may be irritating or even toxic to inhabitants. Most of these compounds are emitted from building materials, carpet and furnishings, cleaning products, stored solvents, and other materials. It is convenient to collect indoor air samples on TD tubes for analysis by TD/GC/MS. However, such samples can produce extremely complex chromatograms with dozens or even hundreds of unresolved peaks.

Agilent's Deconvolution Reporting Software and new Indoor Air Toxics Database can identify up to 171 target compounds in about 3 minutes following routine TD/GC/MS analysis. The method deconvolutes the spectra of overlapping peaks, creating




Figure 8. In this QEdit window, the user can verify integrations and integrate peaks that were initially missed by the ChemStation but identified by AMDIS as part of the DRS software.

“cleaned” spectra that can be searched against the Indoor Air Toxics Database and the NIST’05 Mass Spectral Library. This automated process is faster and more accurate than traditional GC/MS methods.

References

1. <http://www.physlink.com/reference/AirComposition.cfm>
2. <http://www.epa.gov/iaq/voc.html>
3. Philip L. Wylie, “Screening for 926 Pesticides and Endocrine Disruptors by GC/MS with Deconvolution Reporting Software and a New Pesticide Library,” Agilent Technologies, Publication 5989-5076EN, www.agilent.com/chem
4. Bruce Quimby, “Screening for Hazardous Chemicals in Homeland Security and Environmental Samples Using a GC/MS/ECD/FPD with a 731 Compound DRS Database,” Agilent Technologies, Publication 5989-4834EN, www.agilent.com/chem
5. Mike Szelewski and Bruce Quimby, “New Tools for Rapid Pesticide Analysis in High-Matrix Samples,” Agilent Technologies, Publication 5989-1716EN, www.agilent.com/chem
6. Chris Sandy, “A Blind Study of Pesticide Residues in Spiked and Unspiked Fruit Extracts Using Deconvolution Reporting Software,” Agilent Technologies, Publication 5989-1654EN, www.agilent.com/chem
7. Philip Wylie, Michael Szelewski, Chin-Kai Meng, and Christopher Sandy, “Comprehensive Pesticide Screening by GC/MSD Using Deconvolution Reporting Software,” Agilent Technologies, Publication 5989-1157EN, www.agilent.com/chem
8. Xiaofei Ping, Chin-Kai Meng, and Michael Szelewski, “Building Agilent GC/MSD Deconvolution Reporting Libraries for Any Application,” Agilent Technologies, Publication 5989-2249EN, www.agilent.com/chem
9. C. Lesueur and M. Gartner, “Routine Identification and Quantification of Pesticide Multi-residues in Fruit and Vegetable Samples with Full Scan, SIM, and Deconvolution Reporting Software,” *Ernahrung/Nutrition* 29 (11), 466-471 (2005)
10. National Institute of Standards and Technology, AMDIS Literature and Downloads Web site: http://www.amdis.net/What_is_AMDIS/AMDIS_Literature_and_Downloads/amdis_literature_and_downloads.html

Appendix 1

Appendix 1 lists all of the compounds in the RTL Indoor Air Toxics Database

1,1,1,2-Tetrachloroethane

1,1,1-Trichloroethane

1,1,2,2-Tetrachloroethane

1,1,2-Trichloroethane

1,1-Dichloroethane

1,1-Dichloroethene

1,1-Dichloropropene

1,1-Dimethoxyethane

1,2,3-Trichlorobenzene

1,2,3-Trichloropropane

1,2,3-Trimethylbenzene

1,2,4-Trichlorobenzene

1,2,4-Trimethylbenzene

1,2-Dibromo-3-chloropropane

1,2-Dibromoethane

1,2-Dichlorobenzene

1,2-Dichloroethane

1,2-Dichloroethene (cis)

1,2-Dichloroethene (trans)

1,2-Dichloropropane

1,3,5-Trimethylbenzene

1,3-Butadiene

1,3-Dichlorobenzene

1,3-Dichloropropane

1,3-Diisopropylbenzene

1,4-Dioxane

1-Butanol

1-Decene

1-Hexanol

1-Methoxy-2-propanol

1-Octanol

1-Octene

1-Pentanol

1-Propanol

2-(2-Butoxyethoxy)ethanol

2,2,4-Trimethylpentane

2,2-Dichloropropane

2,6-di-t-Butyl-4-methylphenol (BHT)

2-Butanone (MEK)

2-Butoxyethanol

2-Butoxyethyl acetate

2-Chlorotoluene

2-Ethoxyethanol

2-Ethoxyethyl acetate

2-Ethyl-1-hexanol

2-Ethylhexyl acetate

2-Methoxyethanol

2-Methoxyethyl acetate

2-Methyl-2-propanethiol

2-Methylhexane

2-Methylnonane

2-Methylpentane

2-Propanol

3-Methyl-2-butanone

3-Methylheptane

3-Methylhexane

3-Methyloctane

3-Methylpentane

4-Chlorotoluene

4-Methyl-2-pentanone (MIBK)

Acetaldehyde

Acetic acid

Acetone

Acetophenone

Acrylonitrile

alpha-Cedrene

alpha-Methylstyrene (2-propenyl benzene)

alpha-Pinene

Aniline

Benzene

beta-Pinene

Bromobenzene

Bromochloromethane

Bromodichloromethane

Bromoform

Bromomethane

Butyl acetate

Butyric acid

Camphene

Caprolactam

Carbon disulphide

Chlorobenzene

Chloroethane

cis-1,3-Dichloropropene

Cyclohexane

Cyclohexanol

Cyclohexanone

delta-3-Carene

Dibromochloromethane

Dibromomethane

Dichlorodifluoromethane

Dichloromethane

Diethyl disulfide

Dimethoxymethane

Dimethyl sulphide

Dimethyldisulphide

Dimethylphthalate

Epichlorohydrin

Ethanethiol

Ethyl acetate

Ethyl acrylate

Ethyl tert-butyl disulfide

Ethylbenzene

Ethynylbenzene (Phenylacetylene)

Furan

Hexachlorobutadiene

Indene

Isopropyl acetate

Isopropylbenzene (cumene)

Limonene

Longifolene

Methanethiol

Methyl acrylate

Methyl ethyl disulfide

Methyl methacrylate

Methyl tert-butyl disulfide

Methylchloride

Methylcyclohexane

Methylcyclopentane

Methyl-t-butylether	Tetrachloromethane
m-Ethyltoluene	Tetrahydrofuran (THF)
m-Xylene	Tetrahydrothiophene
N,N-Dimethylformamide	Toluene
Naphthalene	Toluene-d8
n-Butanal	trans-1,3-Dichloropropene
n-Butyl acrylate	Trichloroethene
n-Butylbenzene	Trichlorofluoromethane
n-Decanal	Trichloromethane
n-Decane	Vinyl acetate
n-Dodecane	Vinylchloride (chloroethene)
n-Heptane	
n-Hexadecane	
n-Hexanal	
n-Hexane	
n-Nonanal	
n-Nonane	
n-Octanal	
n-Octane	
n-Pentadecane	
n-Propylbenzene	
n-Tetradecane	
n-Tridecane	
n-Undecane	
o-Ethyltoluene	
o-Methystyrene	
o-Xylene	
p-Dichlorobenzene	
Phenol	
p-Isopropyltoluene (p-Cymene)	
p-Methylstyrene	
Propyl acetate	
Propylene glycol	
Propylene oxide	
p-Xylene	
Pyridine	
sec-Butylbenzene	
Styrene	
tert-Butanol	
tert-Butylbenzene	
Tetrachloroethene	

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
August 3, 2006
5989-5435EN



Agilent Technologies



Round-the-Clock, Online and Cryogen-Free Monitoring of Hydrocarbons in Ambient Air Using Thermal Desorption-Gas Chromatography

An application of the UNITY™-Air Server thermal desorber system

Technical Overview

Background

The presence of volatile hydrocarbons in urban atmospheres is believed to contribute to the formation of ground level ozone, one of the main constituents of urban smog. The compounds of interest range in volatility from ethyne (acetylene) to trimethylbenzene and are generally referred to as 'ozone precursors'.

Vehicle emissions are thought to be the main source of these compounds. Recent European and US regulations^{1,2} require round-the-clock monitoring of target species in all major urban centers to establish and monitor the link between periods of high traffic density and high pollution levels. Key compounds include: benzene, toluene, xylene, and 1,3-butadiene. Continuous real-time monitoring provides an insight into emission episodes from local industry and can be used to monitor the effect of weather conditions such as wind direction, precipitation, and temperature inversion.

Introduction

The UNITY™-Air Server is a new, cost-effective thermal desorber for round-the-clock speciated measurement of multiple trace-level volatile organic compounds (VOCs) in air or pure gases. It combines automated, controlled-flow sampling with cryogen-free concentration technology. The

system can be coupled to an Agilent gas chromatograph (GC) or a gas chromatograph/mass spectrometer (GC/MS), and is designed for unattended operation in remote field locations.

In summary, sample air is pulled through an optionally incorporated permeable membrane dryer directly onto an electrically-cooled, sorbent-packed focusing trap at a controlled flow rate. No liquid cryogen is required. The membrane dryer selectively eliminates water and other low molecular weight polar components, reducing the risk of interference from unknown species. It facilitates the use of flame ionization detection (FID) rather than MS detection.

To avoid contamination, sampling flows are controlled by an electronic mass flow controller and pump located downstream of the focusing trap. All sampling parameters are selected by the user and monitored by UNITY-Air Server software as an integral part of the analytical method. After sample collection, the flow path is purged with carrier gas to prevent carryover and to eliminate oxygen from the focusing trap. The trap then heats rapidly, at rates approaching 100 °C/s, to inject retained analytes into the capillary column as a highly concentrated band of vapor. This transfer may be performed splitless for maximum sensitivity. Once the trap has desorbed, it recools, re-equilibrates to the trapping temperature, and begins collection of the next sample while analysis of the previous sample is ongoing.

¹Council Directive 96/62/EC: On ambient air quality assessment and management, and its "daughter" directive - 2000/69/EC relating to limit values for benzene and carbon monoxide in ambient air.

²1990 US Clean Air Act Amendment



Agilent Technologies

MARKES
International
LIMITED

The UNITY-Air Server also offers automatic interchange between three sample channels (typically sample, reference, and blank) for remote system calibration/validation as per user requirements. Six or eight channel options are also available.

This application note describes validation of the system for online monitoring of the 27 ozone precursors specified by European regulators, plus 1,2,4-trimethylbenzene, 1,3,5-trimethylbenzene, and isoprene. Table 1 in the Appendix shows the full list of 30 compounds.

Operation of the system for compliance with the 56-component US EPA ozone precursor list is also demonstrated. Table 2 in the Appendix shows the list of 56 compounds. Key factors taken into account when developing this method included the need for a system that could operate round-the-clock unattended, hence the requirement for cryogen-free operation. The system should allow hourly sample collection with as much of the hour as possible dedicated to sampling. Finally, detection limits should be below 0.5 ppb - ideally 0.1 ppb.

Defining the Ideal Cold Trap

Initial tests were carried out using the 30-component ppb-level certified gas standard described above

(National Physical Laboratory, Teddington, UK). Individual concentrations are listed in Table 1 in the Appendix. Two types of ozone precursor focusing traps were tested:

Trap 1 - Three-bed trap: porous polymer sorbent (5 mm), graphitized carbon black (8 mm), and carbon molecular sieve (-45 mm).

Trap 2 - Four-bed trap: porous polymer sorbent (5 mm), graphitized carbon black (8 mm), carbon molecular sieve 1 (15 mm), and carbon molecular sieve 2 (30 mm).

Trap 1 is the stronger of the two, retaining the highly volatile compounds to a greater extent than trap 2. However, the strength of the sorbents in trap 1 caused slight broadening of early eluting peaks under the splitless conditions used for optimum sensitivity (sub ppb). Figure 1 shows a chromatogram of a splitless injection using the four-bed trap specifically designed for this application.

Breakthrough Tests

All the C2 hydrocarbons are highly volatile species. Ethyne (acetylene) has a boiling point of -89°C and is the most difficult to trap. To retain it quantitatively without liquid cryogen requires careful selection of the cold trap sorbent(s) and focusing temperature.




Figure 1. Chromatogram showing a splitless injection of 150 mL of calibration standard.

Breakthrough volume experiments were performed on the selected cold trap using the ppb-level certified gas standard generated by the National Physical Laboratory, Teddington, UK. Steadily increasing volumes of the gas standard were introduced and a graph of detector response versus sampled volume traced. Breakthrough occurs when the data deviates from a linear relationship, that is, when the species of interest are no longer quantitatively retained. Data from the low volumes of standard introduced were also used to estimate detection limits.

Analytical conditions used for determining the breakthrough volumes:

Column: J&W GasPro, 30 m × 0.32 mm
 GC Program: 40 °C (hold 5 min)
 Ramp 1: 5 °C/min to 90 °C
 Ramp 2: 20 °C/min to 260 °C
 Hold (10 min)
 Prepurge time: 2 min
 Sampling rate: 10 mL/min
 Sampling time: Various
 Purge time: 1 min
 Cold trap: Ozone precursor trap
 Cold trap low: -15 °C
 Cold trap high: 300 °C
 Cold trap hold: 5 min
 Transfer line: 100 °C

of calibration gas for acetylene and propane. Propane is a less volatile component that has a breakthrough volume of many liters on the cold trap used in these experiments.

Figure 2 shows that there is good reproducibility and negligible breakthrough for acetylene, even up at 600 mL of sampled gas. Field sampling volumes of 450 mL (45 min sampling at 10 mL/min) may therefore be used.

Detection/Quantitation Limits

Signal-to-noise ratios for the 150 mL volume of standard using the GC-FID are in the order of 300:1 for the light hydrocarbons at ~6 ppb. For compounds from n-butane upwards, which are at ~2 ppb concentration level, signal-to-noise ratio is 150:1. Assuming a minimum detection signal-to-noise ratio of 3:1 and a minimum quantifiable signal of double that, approximate detection/quantitation limits for 450 mL air samples were calculated as follows:

Hydrocarbons	Detection ppb	Quantification ppb
C2 to C3	0.05	0.1
C4+	0.03	0.06

Figure 2 shows peak area versus sampled volume




Figure 2. Peak area vs. volume sampled for acetylene and propane.

Reproducibility of Peak Area and Retention Time

Figure 3 shows four repeat analyses of the ozone precursor calibration standard on a J&W 30 m $\times$ 0.32 mm GasPro column. Although some coelution of C5 hydrocarbons was observed, excellent retention time (<1% RSD) and peak area (<2% RSD) precision were found across the analyte range for sequence of 12 analyses.




Figure 3. Repeat analyses of 200 mL gas standard run before 5-day field monitoring study.

Suburban Air Monitoring

Analyzer performance for an unattended field operation was evaluated during a 5-day trial at one of Europe's leading centers for standardization in environmental monitoring. Figure 4 shows a sequence of ambient air profiles running from before dawn through the height of the rush hour in a suburban environment. These data were collected at the end of the trial and show that good

analytical performance was maintained. No user intervention was required during the 5-day trial. Detection limits in this relatively clean environment were also satisfactory.

Figure 5 describes a two-column configuration suitable for GC-FID detection and quantitation of low molecular weight hydrocarbons.




Figure 4. A series of suburban air profiles from 06:30 to 10:30 on 24th January 2000.




Figure 5. Schematic representation of the two-column ozone precursor analytical system.

Figures 6 and 7 show chromatograms obtained using the 30- and 56-component calibration gas standards respectively, using the described two-column GC system. Peak identifications are

given in Tables 1 and 2 in the Appendix. This configuration makes it possible to separate all of the components in these two standard mixtures.




Figure 6. Thirty-component calibration gas injection on two-column analytical system.




Figure 7. Fifty six-component calibration gas injection on two-column analytical system.

Figures 8 and 9 show linearity plots for five selected compounds.




Figure 8. Detector response vs. sampled volume for ethene, propane, and 1,3-butadiene.




Figure 9. Detector response vs. sampled volume for heptane and toluene.

Appendix

Table 1. Details of ppb-Level 30-Component Gas Standard

Compound	Concentration (mole fraction by ppb)	Uncertainty (mole fraction by ppb)
Ethane (1)	5.94	±0.15
Ethene (2)	9.31	±0.20
Ethyne (7)	7.75	±0.20
Propane (3)	2.25	±0.05
Propene (4)	5.86	±0.15
Propyne (15)	2.53	±0.05
n-Butane (6)	2.27	±0.05
<i>iso</i> -Butane (5)	2.63	±0.05
<i>iso</i> -Butene (10)	2.49	±0.05
1-Butene (9)	2.91	±0.05
<i>trans</i> -2-Butene (8)	1.94	±0.05
<i>cis</i> -2-butene (11)	2.08	±0.05
1,3-Butadiene (14)	4.66	±0.10
n-Pentane (13)	2.32	±0.05
i-Pentane (12)	1.04	±0.02
<i>trans</i> -2-Pentene (16)	3.54	±0.10
<i>cis</i> -2-Pentene (17)	1.35	±0.03
Isoprene (20)	1.61	±0.04
2-Methylpentane (18)	2.78	±0.05
3-Methylpentane (19)	3.18	±0.05
Cyclohexane (23)	2.92	±0.05
n-hexane (21)	1.55	±0.04
Benzene (22)	3.00	±0.05
n-Heptane (24)	2.43	±0.05
Toluene (25)	2.82	±0.05
Ethylbenzene (26)	1.55	±0.04
o-Xylene (28)	0.88	±0.02
m-Xylene (27)	1.23	±0.03
1,2,4-Trimethylbenzene (30)	0.99	±0.02
1,3,5-Trimethylbenzene (29)	0.81	±0.02

Table 2. Details of ppb-Level 56-Component Gas Standard

Peak number	Compound
1	Ethane
2	Ethylene
3	Propane
4	Propylene
5	<i>iso</i> -Butane
6	n-Butane
7	Acetylene
8	<i>trans</i> -2-Butene
9	1-Butene
10	<i>cis</i> -2-Butene
11	Cyclopentane
12	Isopentane
13	n-Pentane
14	<i>trans</i> -2-Pentene
15	1-Pentene
16	<i>cis</i> -2-pentene
17	2,2-Dimethylbutane
18	2,3-Dimethylbutane
19	2-Methylpentane
20	3-Methylpentane
21	Isoprene
22	2-Methyl-1-Pentene
23	Hexane
24	Methylcyclopentane
25	2,4-Dimethylpentane
26	Benzene
27	Cyclohexane
28	2-Methylhexane
29	2,3-Dimethylpentane
30	3-Methylhexane
31	2,2,4-Trimethylpentane
32	n-Heptane
33	Methylcyclohexane
34	2,3,4-Trimethylpentane
35	Toluene
36	2-Methylheptane
37	3-Methylheptane
38	n-Octane
39	Ethylbenzene
40	m/p-Xylene
41	Styrene
42	o-Xylene
43	n-Nonane
44	Isopropylbenzene
45	n-Propylbenzene
46	m-Ethyltoluene
47	p-Ethyltoluene
48	1,3,5-Trimethylbenzene
49	o-Ethyltoluene
50	1,2,4-Trimethylbenzene
51	n-Decane
52	1,2,3-Trimethylbenzene
53	m-Diethylbenzene
54	p-Diethylbenzene
55	n-Undecane
56	n-Dodecane

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

UNITY™, UNITYe, and Air Server are trademarks of Markes International Ltd., UK.


© Agilent Technologies, Inc. 2003

Printed in the USA
April 24, 2003
5988-9254EN



Agilent Technologies

MARKES
International
L I M I T E D



Application of SecureTD™ for Re-collection and Repeat Analysis of Desorbed Samples

Overcoming the one-shot limitation of thermal desorption

Technical Overview

Introduction

Thermal desorption (TD) has a number of very significant advantages versus conventional solvent extraction methods. These include:

- Increased sensitivity
 - Detection limits enhanced by a factor of 10^3 to 10^4 .
 - Higher sample recovery. A 95% or better desorption efficiency for all volatile organic compounds (VOCs), including polar compounds, vs. 30% to 80% for most solvent extraction methods.
- Cost savings
 - No manual sample preparation required, thus reducing time and cost per analysis.
 - Reusable TD tubes (100 to 200 times).
- No solvent required
 - No masking of peaks of interest by the solvent.
 - No introduction of artifacts/impurities from the solvent.
 - Improved laboratory working environment (with elimination of a health hazard). Carbon disulfide (CS_2), the most commonly used extraction solvent, is very toxic.
 - No solvent disposal costs or expensive air extraction equipment required.

However, once a sample has been thermally desorbed (that is, heated in a flow of carrier gas), no sample remains for repeat analysis. In contrast to this, CS_2 extracts from charcoal tubes can be injected many times, as long as they are kept refrigerated. In some cases this can be a significant consideration, overriding the many other advantages of TD. Markes International TD systems, including UNITY™ (single tube thermal desorber) and ULTRA-UNITY™ (100-tube automated thermal desorber), are the only thermal desorbers with SecureTD™. SecureTD is designed to overcome the one-shot limitation of conventional TD by using quantitative re-collection for repeat analysis.

SecureTD: Split Re-collection for Repeat Analysis

UNITY, The Markes International platform thermal desorber, was specifically designed to overcome the one-shot limitation of conventional analytical TD by harnessing the idea of split re-collection pioneered by Dr Jan Kristensson [1]. Using any of Markes International TD systems, samples may be split as they are transferred from the primary sample tube to the focusing trap and/or during subsequent transfer from the focusing trap to the analyzer. The split flow is directed to either a tube filled with charcoal (to scrub the effluent stream), or to a conditioned sorbent tube for sample re-collection.



Agilent Technologies

MARKES
International
LIMITED

The same conditioned sorbent tube is used to collect the flow whether splitting on the inlet to the trap (primary desorption), outlet to the trap (secondary desorption), or both (see Figures 1 and 2).




Figure 1. Re-collection during primary (tube) desorption.




Figure 2. Re-collection during secondary (trap) desorption.

TD offers such a large enhancement in sensitivity versus solvent extraction that it is invariably possible to redirect a portion of the sample for re-collection without compromising method detection limits. The short length of the UNITY flow path leading to the split re-collection tube is constructed of inert Silcosteel™ tubing, heated to prevent analyte condensation or degradation. A steep temperature gradient inside the re-collection tube ensures quantitative trapping of target analytes over the relatively short re-collection period without condensation or breakthrough. UNITY control software allows exchange of the split re-collection tube in between samples without interrupting gas flow to the analyzer.

An automated ULTRA-UNITY system may use manual SecureTD for method development/validation or re-collection of critical samples. If automatic re-collection is required for every sample, then the SecureTD function may be automated using an AutoSecure™ system. See Figure 3.



Figure 3. AutoSecure system.

Laboratory Test of Re-collection Performance

The performance of SecureTD was tested with a high loading ($\sim 1 \mu\text{g}$) of toluene. To prepare the standard, $1 \mu\text{L}$ of a 0.1% (v/v) toluene standard in methanol was introduced to a conditioned Tenax TA tube in stream of pure nitrogen via the standard loading rig (C-CSLR).

Analytical conditions:

Tenax tube

Tube desorb: 280 °C for 5 min

Flow path: 120 °C

Cold trap packed with Tenax and Carboxpack

Cold trap low: -10 °C,

Cold trap high: 300 °C for 2 min

Helium carrier gas: 14 psi (giving a column flow of 1.5 mL/min)

Desorb flow: 15 mL/min, Split flow: 40 mL/min giving a split ratio of 99:1

GC column: 30 m $\times$ 0.32 mm $\times$ 1 mm film methyl silicone

The sample was re-collected and re-analyzed four times.

Recovery data are presented in Table 1. Figure 4 shows a chromatogram from a recovered sample and a bar chart for the toluene recoveries over the four re-collection and reanalysis steps.

Table 1. Analysis of Toluene Using Re-collection with a 98.9 : 1 Split Ratio

Analysis number	Area counts	Data point as a % of previous	Data point as % of original
1	643952		100.0
2	638144	99.1	99.1
3	630494	98.8	97.9
4	623338	98.9	96.8
5	616320	98.9	95.7




Figure 4. Chromatogram and bar chart of relative peak area % on subsequent "saved" samples.

SecureTD performance was also tested with a low concentration (approximately 170 ng/μL) benzene, toluene, o-xylene (BTX) solution. Two μL of the solution was introduced onto a conditioned Tenax tube, as above, and analyzed under similar conditions - this time using a split ratio of 21:1. Six re-collection, repeat-analyses were carried out and showed good correlation between the expected and observed decay. See Figure 5.

SecureTD: Why Re-Collect?

There are a number of situations where re-collection of a portion of the sample is advantageous.

- Method development/validation
- Erroneous GC parameters, for example, co-elution, detector problems, premature completion of the GC run, etc.
- Incorrect split conditions, including too little or too much sample passed onto column
- Identification of unknowns
- Troubleshooting
- Sample archiving - for critical one-off samples or samples taken for regulatory compliance
- Unique samples, for example, re-collection from online/headspace samples




Figure 5. Re-collection and re-analyses of BTX solution.

Method Validation - Validation of Quantitative Recovery of High Boiling Compounds

A solution of the following phthalates (high boiling plasticizer compounds) was analyzed with re-collection:

DEP Diethyl phthalate
DMPP Dimethyl propyl phthalate
DBP Dibutyl phthalate
DEHP Diethyl hexyl phthalate
DOP Dioctyl phthalate
DNP Dinonyl phthalate

Figure 6 shows how SecureTD re-collection was used to validate the quantitative recovery of high boiling compounds such as dioctyl and dinonyl phthalate. No bias was observed throughout the sequence of primary and repeat analyses. Blanks run between each of the repeat analyses demonstrated no carryover.




Figure 6. Re-collection of high boiling compounds.

Erroneous GC Parameters - Evaluation of Repeat Analysis for Labile, High Boiling Analytes

To test the repeat analysis capability for other demanding applications, a Tenax TA tube was loaded with low μg levels of a series of labile, high boiling organic amines. See Table 2. The loaded tube was prepared in the South Wales laboratory of Solutia UK Ltd. using direct injection of a liquid standard. A blank tube was also analyzed. Split effluent from the sample was re-collected on a conditioned Tenax TA tube and re-analyzed. During the first analysis of the standard, the GC run finished prematurely, half-way through elution of 4A. Its relative concentration, however, was determined from analysis of the re-collected sample. Relevant chromatograms are shown in Figures 7 to 9.

Analytical conditions were set as follows:

Tube desorb: 320 °C for 10 min
 Flowpath: 200 °C
 Cold trap packed with Tenax TA
 Cold trap low: -10 °C,
 Cold trap high: 300 °C for 5 min
 Helium carrier gas at 15 psig giving a column flow of ~1.5 mL/min
 Desorb flow: 15 mL/min, split flow (inlet and outlet) 47 mL/min giving an overall split ratio of ~130:1
 GC column: 30 m $\times$ 0.25 mm $\times$ 0.25 mm film methyl silicone
 GC oven: 50 °C for 2 min, 30 °C/min to 250 °C for 3.5 min, 15 °C/min to 280 °C for 0 min (run 1) or 1 min (subsequent analyses)

Table 2. Repeat Analysis of Amines

Compound name	Abbr	Peak area Run 1	Peak area Repeat analysis
Para-nitrochlorobenzene	PNCB	3225	3583
Formaninlide	FAN	4177	4352
N-isopropyl, N'-phenyl paraphenylenediamine	1PPD	4729	4950
4-Nitrodipheylamine	4N	3104	3274
4-Aminodiphenylamine	4A	4967*	5283

*Extrapolated from rpt analysis




Figure 7. Chromatogram showing the first desorption of a liquid standard of a series of labile, high boiling amines.




Figure 8. Chromatogram of blank tube desorbed after liquid standard - showing no system carryover.




Figure 9. Chromatogram of re-collected split sample.

Troubleshooting

A solution of high molecular weight hydrocarbons (C28, C32, C36, and C40) was loaded onto pre-conditioned sorbent tubes packed with quartz wool and Tenax TA, then analyzed.

Each compound was nominally present at a similar concentration; however, the C36 and C40 peak were much smaller than expected. It was unclear at first whether this was an instrumentation problem or an issue with the sample solution. The sample was re-collected and reanalyzed three times and no bias, that is, no loss of n-C36 or n-C40, was observed. This showed that higher boiling components were in fact at a lower concentration than the more volatile species, and it was later determined that the high boilers were dropping out of solution before they could be loaded onto the primary sorbent tube. See Figure 10.




Figure 10. Stacked chromatograms of successively re-collected high molecular weight hydrocarbons.

Summary

This work illustrates the significant benefits of SecureTD, both for overcoming the one-shot limitation of traditional TD, and as a powerful tool for method development and validation. This innovation should allow TD, with all its inherent advantages of cost, sensitivity, and safety, to be used for all relevant environmental health and safety applications.

Acknowledgement

The evaluation entitled Erroneous GC Parameters was carried out in collaboration with Solutia UK Ltd. and Flexsys Ltd. We gratefully acknowledge their contribution to the work.

Reference

1. J. Kristensson, Thermal desorption: A multi-shot technique, Stockholm Sweden: University of Stockholm; 1987.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

UNITY™, ULTRA-UNITY™, AutoSecure™, SecureTD™ are trademarks of Markes International Ltd. UK.

Tenax™ is a registered trademark of Buchem bv. Netherlands.

Carbopack B™ is a registered trademark of Supelco Inc. USA.

SilicoSteel® is a registered trademark of the Restek Corporation.

© Agilent Technologies, Inc. 2003


Printed in the USA
April 24, 2003
5988-9253EN



Agilent Technologies

MARKES
International
LIMITED

Optimizing Analytical Performance and Extending the Application Range of Thermal Desorption for Monitoring Air Indoors and Inside Vehicle Cabins



Technical Overview

Introduction

Thermal desorption (TD) is a readily automated gas extraction technology based on standard gas chromatography parameters. It provides an efficient, high-sensitivity alternative to conventional solvent extraction. The process of TD involves the extraction of volatile or semivolatile organic compounds from a sorbent or material by heating the sample in a flow of inert gas. The extracted analytes are then transferred in the flow of carrier gas to the analyzer [typically a gas chromatograph (GC) or a gas chromatograph/mass spectrometer (GC/MS)] as a small, discreet, and concentrated volume of vapor. The thermal desorber becomes a multipurpose, standalone GC injector. Concentration factors as high as 10^5 to 10^6 can be achieved using modern systems with analytes collected from tens to hundreds of liters of air being delivered to the analyzer in as little as 200 μL of gas.

Though inherently simple, many factors contribute to the performance and efficiency of the TD process, which determines the ultimate sensitivity and reliability of a TD-based analytical method. These factors include retention efficiency (during sampling/focusing), desorption efficiency, artifacts, band broadening, and analyte/system stability. This overview describes optimization of all of these parameters during the development and validation of TD procedures. Examples of optimum method performance in terms of precision, linearity, and sensitivity are presented. A novel approach to overcoming the traditional one-shot limitation of TD is also described.

Analytical TD — The Process

Analytical TD is a gas-phase introduction technique for vapor-phase analytical systems such as GC and GC/MS. It combines many pre-analytical procedures including sample preparation/collection, selective concentration, analyte extraction, and injection into one labor-saving automated operation. It is used for the measurement of trace volatile organic compounds (VOCs); however, the range of sample types and applications is very diverse:

- Air can be sampled and analyzed online on a semicontinuous basis for real-time studies. Examples include diurnal variation of indoor air pollution, real-time tracer gas studies, etc.
- Building materials and furniture are large contributors to indoor air pollution. The volatile content of solid or liquid samples such as paints or textiles can be measured by weighing the material into empty sampling tubes for extraction and quantitative analysis by direct TD-GC/MS.
- In other cases, vapor phase samples can be collected offline into containers (canisters, bags, etc.) or sorbent tubes. Relevant applications for collection in sorbent tubes include exhaust from materials emission tests, indoor air pollution profiling, studies of building ventilation using tracer gases, and the characterization of odors.



Agilent Technologies

MARKES
International
LIMITED

Regardless of the primary sampling device used, volatiles are ultimately swept by the carrier gas into a secondary focusing device inside the thermal desorber where target analytes are selectively retained. Once all the compounds of interest have been transferred to the focusing device and all unwanted volatiles (water, for example) have been swept to vent, the focusing device is thermally desorbed by rapid heating in a reverse flow of inert gas. This process 'injects' target compounds into the analyzer in a tiny, concentrated 'slug' of vapor.

Sampling Options

Containers – Canisters and Bags

Containers, such as passivated canisters or Tedlar™ bags, are the best air sampling option for ultravolatile chemicals such as C2 hydrocarbons. Though expensive, evacuated canisters provide the simplest of all air sampling options with 'grab' sample collection via release of a single valve. However, Tedlar bags offer limited storage stability (<24 hours) for many common VOCs [1]. Canisters are similarly prone to poor recovery of less volatile or more polar species [2] when used for higher concentration atmospheres. Many polar or less volatile species tend to stick to the internal walls of containers and cannot be quantitatively recovered. Humidity can also cause problems. If liquid water condenses inside the container, organic compounds, particularly the more polar species, will partition between the aqueous and vapor phases, giving unreproducible results. While Tedlar bags are typically used only once, canisters can be reused indefinitely. However, they require stringent cleaning by repeated evacuation and purging between uses.

Vapor Sampling onto Sorbent Tubes

While no single sampling method suits all indoor applications, TD sample tubes may provide the most versatile option. Used either empty for desorbing volatiles from materials (see below), or packed with sorbent for retaining vapor-phase organics, they are compatible with all but the most volatile species (for example, acetylene, ethylene, and some freons). Typically, a known volume of air is pulled through the tube at around 50 mL/min using a standard pump. Alternatively, industry-standard steel or coated steel tubes, which have a well-defined, fixed-air gap between the end of the

tube and the sorbent sampling surface, can also be used as diffusive (passive) samplers. In this mode, tubes are simply left open at the sampling end, allowing analytes to migrate from the air to the sorbent at a rate controlled by the diffusion gradient according to Fick's first law.

Many of the limiting factors dictating the performance of sorbent tube based air sampling methods (pumped or diffusive) relate to sorbent selection and preparation.

Optimizing Analytical Performance for Sorbent Tube-Based Methods

Sorbent Selection

Sorbent strength – Analytical sensitivity and precision are largely determined by sampling efficiency, desorption efficiency, and the level of interferences (see section on artifacts below). The sorbent(s) selected must be sufficiently strong enough to retain target analytes during sampling/concentration, but weak enough to release them efficiently during the TD phase.

Concentration enhancement potential – Depending on the retentive strength (breakthrough volume) of the sorbent tube selected for the analytes in question, as much as 100–200 L of air can be pumped through a sorbent tube during sampling. During primary (tube) desorption the compounds of interest can be eluted in as little as 100–200 mL of carrier gas and transferred to the focusing trap. Using new, state-of-the-art, fast desorption traps, analytes can subsequently be desorbed from the trap and transferred to the analyzer, splitless, in as little as 200 µL of gas. This produces an overall concentration enhancement of 10^6 . Exceptional detection limits can be achieved, even with a conventional Flame Ionization Detector (FID) (Figure 1).

A wide range of sorbents is now commercially available. These can be classified generally as weak, medium, or strong. Less volatile analytes should be trapped on weaker sorbents, while more volatile analytes should be trapped on stronger sorbents. If a wide volatility range of compounds is being monitored, it is often necessary to pack the tube with more than one sorbent material and to arrange them in order of increasing strength, starting from the sampling end. At ambient




Figure 1. Thirty pg of benzene from a sorbent tube. Equivalent to 10 ppt in 1 L of air.

temperatures, sorbents can be used to retain quantitatively compounds as volatile as vinyl chloride monomer (VCM) and propane. Electrically-cooled sorbent focusing traps can concentrate the most volatile freons and components as volatile as acetylene without additional cooling from liquid cryogen.

Other key considerations when selecting sorbents include:

- **Inertness** – Some sorbents are contaminated by chemically active materials, such as trace metals, from the production process. This is especially true of carbon blacks, many of which derive originally from natural charcoals.
- **Hydrophobicity** – Most common weak and medium strength sorbents are very hydrophobic; their sorbent strength is not compromised even when sampling at high (>90%) humidity. However, most strong sorbents are comprised of some sort of carbonized molecular sieve, and their sorbent strength can be reduced at very high humidity by as much as a factor of 10. If a large amount of water is retained on the tube, this can adversely affect the analysis; however, most modern desorption systems incorporate one or more methods for selectively eliminating water.
- **Artifacts** – Sorbents vary significantly with respect to inherent artifact levels. Some porous polymers, such as the Chromosorb Century series and Poropaks, have relatively high artifacts, with several peaks at 5–10 ng levels. Tenax TA™ is better with minimum levels between 0.1 and 1 ng for well-conditioned materials. Both carbon blacks and carbonized molecular sieves are excellent with respect to inherent artifacts, between 0.01 and 0.1 ng, if well conditioned. However, the carbonized molecular sieves require extended conditioning at steadily increasing temperatures, and when new, can continue to show a high background of inorganic gases for several days.
- **Temperature stability** – Most sorbents, including Tenax TA, are stable up to 350 °C, and many of the carbon sorbents can be taken much higher. Care must be taken with most of the other porous polymers, Chromosorbs and Poropaks, which typically have temperature limits at or below 225 °C. This means that they cannot be packed into mixed-bed tubes with more stable sorbents. If this is done, it is not possible to adequately condition the higher temperature materials without overheating the polymers.

- **Mechanical strength** – Carbon blacks are extremely friable and prone to the formation of fines. Care should be taken not to over compress these sorbents during tube packing and to avoid sharp knocks to the tubes once they are packed. As the carbon packing ages, the formation of fines may increase tube impedance beyond the limit of some pumps. Most other sorbents are mechanically strong, though Tenax TA can have a high percentage of fines when new and may require sieving before use. Generally speaking, recommended mesh sizes for sorbents in standard 4–5 mm bore sampling tubes range from 30–80 mesh. A selection of the most common sorbents and their associated characteristics is presented in Table 1.

Pumped Monitoring/Active Sampling Through Sorbent Tubes

Pumped monitoring is the most versatile sampling option for the compatibility of packed tubes with both single and multibed sorbents. It is specified by a number of international standard methods relating to indoor air. These include prENV 13419 and ISO DIS 16000 for testing emissions from building materials and US EPA Method TO-17, ISO 16017 Pt. 1, and ASTM D6196-97 for general monitoring of VOCs in indoor air. Industry standard

¼-inch od by 3.5-inch long tubes can be sampled efficiently at rates ranging from 10 to 200 mL/min, with the optimum being 50 mL/min [3].

‘Universal’ tubes – There is no such thing as a universal tube. However, perhaps the most useful combination of sorbents that can be packed into a single tube for pumped monitoring of uncharacterized atmospheres is Tenax TA backed up by Carbopack B™ (Carbograph 1™), in turn backed up by Spherocharb™ (Unicarb™) or Carboxen 1000™. The main limitation of this sorbent combination is that the middle strength carbon black sorbent is not completely inert and may cause degradation of labile analytes such as nitrogen, sulphur-containing compounds, and some monoterpenes. The ultimate ‘train’ of tubes for monitoring uncharacterized areas consists of three inert Silcosteel tubes connected together in series using inert, nonemitting fittings. The front tube is packed with Tenax TA, the middle one is packed with Chromosorb 106™, and the back one is packed with Unicarb. Whenever using these or any multisorbent combination of tubes, sampling must always take place through the weaker sorbent first. Higher boiling analytes are thus retained by and desorbed from the weak sorbent without coming into contact with the stronger sorbents.

Table 1. Key Features of the Most Common Sorbents

Sorbent	Strength	Features
Tenax TA	Weak	Inert, hydrophobic, individual artifacts below 1 ng, max temperature: 350 °C, sieve to remove fines
Carbograph 1	Weak-Medium	Not inert, hydrophobic, individual artifacts below 0.1 ng, max temperature: >400 °C, prone to fines formation
Chromosorb 106	Medium	Inert, hydrophobic, individual artifacts up to 10 ng, max temperature: 225 °C, precondition to shrink before use
Unicarb/Spherocharb	Strong	Inert, not hydrophobic, individual artifacts below 0.1 ng, max temperature: >350 °C, condition slowly - increasing the temperature stepwise, purge thoroughly to remove O ₂ before heating
Carboxen 1000	Ultrastrong	Inert, not hydrophobic, individual artifacts below 0.1 ng, max temperature: >350 °C, condition slowly - increasing the temperature stepwise, purge thoroughly to remove O ₂ before heating

Diffusive sampling

Axial samplers – Single-bed, ¼-inch od, 5 mm id stainless steel or Silcosteel sorbent tubes with a 15-mm air gap between the surface of the sorbent and the sampling surface are used as standard for pumped monitoring (see above). However, these tubes were designed as long ago as 1979 [4] to be used as axial format diffusive samplers. The uptake rate of many common solvents is already well validated for these tubes. Diffusive sampling eliminates the expense and relative complexity of sampling pumps and facilitates large-scale air monitoring campaigns at affordable cost. The diffusive sampling rate is a constant function of atmospheric concentration, as predicted by Fick's law, provided the concentration at the surface of the sampler remains at zero (Figure 2).




Figure 2. Illustration of diffusive sampling on axial sorbent tubes.

For use as diffusive samplers, the tubes are capped with special diffusion caps at the sampling end and kept sealed at the nonsampling end. The diffusion caps simply have a gauze surface to stop macroparticles from entering the tube and to mask the sorptive surface.

Typical sampling rates on axial diffusive tubes are quoted at around 2 ng/ppm/min (2 pg/ppb/min), which is equivalent to a pumped flow of between 0.5 and 1 mL/min. Standard sorbent tubes may be used in diffusive mode for both short term monitoring (1–8 hours) in high concentration areas and long term (3 days to 4 weeks) monitoring of 'typical' indoor and ambient air.

Radial diffusive samplers – New radial diffusive samplers consist of a sorbent sampling cartridge housed in a porous polymer body; this allows sampling along and around the whole cylindrical surface of the sampler (Figure 3). These devices sample at a rate equivalent to 50–100 mL/min, but saturate quickly. They can only be used for short term 0.5 to 6-hour air monitoring and at ambient/indoor (low ppb) levels. They are a useful complement to the axial diffusive tubes. After sampling, the sorbent cartridge is simply slipped from its porous polymer housing and placed into an empty 'carrier' tube for analysis by TD-GC/MS. The sampling cartridge is an impedance fit inside the middle of the carrier tube to ensure gas passes through the body of the cartridge during desorption. The cartridge may be reused as many times as a standard sorbent tube.

Diffusive sampling is specified by a number of international standard methods relating to indoor air. These include prEN 13528 and ISO 16017 Pt. 2 for general monitoring of VOCs in indoor air and the Dutch standard for ventilation testing using perfluorocarbon tracer gases [5].




Figure 3. Radial diffusive samplers.

Conditioning and Storage of Sorbent Tubes

To clean them before use, sorbents invariably require stringent conditioning at high temperatures in a flow of inert gas. Many of the porous polymer-type sorbents also require preconditioning in bulk before they are used to pack tubes. This is because as much as 10%–15% of sorbent mass may be lost during the first conditioning cycle. It is rare for any form of solvent washing to be required, but conditions used for tube cleaning should be more stringent (in terms of flow and temperature) than those to be used subsequently for analytical TD.

Conditioned and sampled tubes should be stored using long-term ¼-inch screw caps fitted with combined PTFE ferrules. Tubes capped and stored in this way are reported to be stable for up to 27 months [6], provided the compounds concerned are not chemically active.

Desorption and Analysis

Advice on optimizing and validating the TD and GC/MS analysis process has been described in the literature [7] and is outlined in many of the international standard methods listed above for pumped and diffusive sampling. In summary, analytical desorption temperatures should be kept below those used for tube conditioning with a carrier gas flow of 20–30 mL/min. All air (O₂) should be purged from the tubes before heat is applied, and system flow paths should be kept short, inert, and uniformly heated. TD methods should readily facilitate better than 95% recovery in a single desorption.

The linearity of TD-GC/MS methods should be the same as those achieved using GC/MS with conventional liquid inlets. The precision of TD methods is typically limited to 1%–2% by the manual introduction of standards to sorbent tubes during calibration. However, this is insignificant relative to the overall variability of the complete sampling and analysis procedure for indoor or ambient air. Most standard methods quote this at 15%–30%.

As demanded by international standard methods, TD instrumentation should feature automatic leak testing and tubes that are sealed before and after analysis to maintain data integrity.

SecureTD™ Repeat Analysis for TD

Given its enormous advantages over solvent extraction of adsorbents (in terms of sensitivity, reusable tubes, reproducibility, and environmental acceptability), it is sometimes surprising that TD has not universally replaced solvent extraction for all air monitoring applications. The reason that solvent extraction is still used, especially for some industrial applications, is that more than one analysis can be carried out on each extracted sample. TD, on the other hand, has traditionally been a one-shot technique; once a sample has been thermally desorbed (heated in a flow of inert gas), it is gone. No sample remains for repeat analysis. The latest commercial TD technology overcomes this limitation by offering quantitative re-collection of the split effluent for repeat analysis. In all but the lowest (ppt) level applications, a split can be used. In some cases, when

determining the solvent content of coatings or adhesives for example, a large split is often necessary for optimum analytical performance. The latest commercial TD apparatus facilitates quantitative split re-collection for repeat analysis. In these systems, the normal charcoal filter is designed to be the same size as a standard sorbent tube and is easily interchanged. The flowpath leading up to the split point is also uniformly heated and inert. For sample re-collection, the charcoal tube is simply replaced with a conditioned sorbent tube. A steep temperature gradient along the first portion of the re-collection tube ensures good retention efficiency.

The re-collected sample can be archived for analysis by a third party lab or re-analyzed immediately under the same or different analytical conditions as required. Excellent precision can be obtained (Figure 4).




Figure 4. Re-collection and repeat analysis of desorbed toluene.

The Field and Laboratory Emissions Chamber (FLEC)

The FLEC (Figure 5) is a specialized piece of sampling apparatus for testing VOC emissions from construction products and other materials used indoors. It is a simple, portable materials emissions chamber that is shaped like the mouth of a trumpet. It is placed onto the surface of a planar material and air is passed uniformly over the surface. Exhaust gases are collected onto one or two sorbent tubes and then analyzed using standard TD-GC/MS techniques.



Figure 5. Field and laboratory emission cell (FLEC) for emission testing.

The FLEC complies with Section 2 of the new European standard for testing VOC emissions - prENV 13419. FLEC applications include emissions testing from applied wall coverings, floor coverings, adhesives, sealant materials, paints, and coatings.

Breath Sampling as a Tool for Investigating Biological Exposure

The Bio-VOC Breath Sampler (Figure 6) is a disposable device that collects a 100-mL sample of end-tidal air and transfers it to a sorbent tube [8]. Several breath samples from the same individual can be loaded onto the same sample tube if required. Analysis is typically done by conventional TD-GC/MS.



Figure 6. Monitoring biological exposure via alveolar air collected using the Bio-VOC breath sampler.

Indoor air-related applications for the Bio-VOC Breath sampler include chronic personal exposure monitoring, particularly for individuals living near local emission sources (for example, above a dry cleaning shop).

Direct Desorption

Direct TD provides a convenient and high-sensitivity alternative to purge and trap or solvent extraction for some relatively homogeneous materials. Samples such as powders, film, fibers, granules, resin, or even droplets of liquid can be weighed directly into empty tubes or special PTFE tube inserts.

The sample is then heated in a stream of inert carrier gas that strips volatiles from the sample and transfers them to the focusing trap. In this mode, TD becomes a dynamic headspace procedure.

It is used for complete and quantitative extraction of residual volatiles to determine the solvent or volatile content of a sample. Examples of building materials suitable for this approach include printed polymers/papers, carpet, water based paint, wood varnish, adhesives, etc.

For many quality control and trouble-shooting applications, direct TD eliminates hours of conventional sample preparation. In many cases, a 3-way separation can be achieved. Solids are left in the sample tube and prevented from contaminating the analytical system, and unwanted interferents such as water or ethanol may be eliminated during the focusing process. This leaves only the target organics to be collected in the focusing trap and transferred to the analyzer.

Samples may be weighed directly into empty tubes supported by two glass wool plugs or placed into inert tube inserts such as PTFE liners to prevent contamination of the inner surface of the tube. If complete, quantitative extraction is required, samples should have a relatively high surface area to mass ratio. Examples of such samples include powder, granules, liquid droplets, or fibers. Resins should be smeared inside PTFE inserts or onto glass fiber 'boats' to prevent contamination of the inside of the tube. Similarly, liquids (emulsions, solutions, etc.) can be introduced as droplets on glass wool plugs inside PTFE liners. It is important to make sure the sample does not block the sample

tube; this will stop the gas flow and prevent complete TD. In addition, make sure that the sample is not taken above its decomposition temperature. An example of paint analysis by direct TD-GC/MS is shown in Figure 8.

Summary of Applications for TD in Indoor Air Monitoring

TD methods provide a high sensitivity and robust analytical option for a wide range of indoor air monitoring and related applications. A summary of some key applications is given below, along with useful references. Factors affecting method

optimization were described and many key applications relating to indoor air were referenced. A summary of these and other relevant TD applications is listed below with key references:

- Testing VOC emissions from building materials and furnishings [9, 10]
- Indoor air profiling [11]
- Ventilation testing [5]
- VOC content of materials [12]
- Identifying indoor mold/fungal contamination via VOC profiling [13]
- Biological exposure testing [14]
- Real-time air profiling for diurnal variation studies [15]




Figure 8. Direct desorption of volatile and semi-volatile organics from paint.

References

1. ASTM; D6399-99a. Standard guide for selecting instruments and methods for measuring air quality in aircraft cabins.
2. Coutant, R.W., and McClenny, W.A. Competitive adsorption effects and the stability of VOC and PVOC in canisters. Proceedings of 1991 USEPA/AWMA International Symposium: Measurement of Toxic and Related Air Pollutants 1991; Vol 1: 382-388.
3. Brown, R.H., and Purnell, C.J. Collection and analysis of trace organic vapor pollutants in ambient atmospheres. The performance of a Tenax-GC adsorbent tube. (1979) *J. of Chrom.* **178**, 79-90.
4. Brown, R.H., Charlton, J., and Saunders, K.J. The development of an improved diffusive sampler. (1981) *Am. Ind. Hyg. Assoc. J.* **42**, 865-869.
5. HJTh Bloemen et al. Ventilation rate and exchange of air in dwellings. Netherlands Nat'l Inst. for Public Health and Environmental Hygiene, with RIVM. 1992 Report.
6. Lindquist, F., and Bakkeren, H. Stability of chlorinated hydrocarbons on Tenax. CEC commissioned report from TNO, the Netherlands, Rpt. No. R90/268, 1990.
7. Woolfenden, E.A. Monitoring VOCs in air using sorbent tubes followed by thermal desorption capillary GC analysis: Summary of data and practical guidelines. (1997) *Journal of Air & Waste Mngmnt Assoc.* **47**, 20-36.
8. Wilson, H.K., and Monster, A.C. New technologies in the use of exhaled breath analysis for biological monitoring. (1999) *Occup Environ. Med.* **56**, 753-757.
9. Wolkoff, P. An emission cell for measurement of volatile organic compounds emitted from building materials for indoor use - the field and laboratory emission cell FLEC. (1996) *Gefahrstoffe-Reinhaltung der Luft* **56**, 151-157.
10. Jensen, B., Wolkoff, P., Wilkins, C.K., and Clausen, P.A. Characterization of linoleum. Part 1. Measurement of VOC by use of FLEC (1995) *Indoor Air* **5**, 38-43.
11. Brown, V.M., Crump, D.R., Gardiner, D., and Yu, C.W.F. Long term diffusive sampling of volatile organic compounds in indoor air. (1993) *Environmental Technology* **14**, 771-777.
12. Monitoring materials and processes for trace level VOCs. Markes International Ltd. Thermal Desorption Technical Support Note 9.
13. Bjurman, J. and Kristensson, J. Volatile production by aspergillus versicolor as a possible cause of odor in houses affected by fungi. (1992) *Mycopathologia*, **118**, 173-178.
14. Wilson, H.K. Breath analysis. Physiological basis and sampling techniques. Scand. J. Work. (1985) *Env. Health*, **12**, 174-192.
15. US EPA, Office of Air Quality Planning and Standards Enhanced ozone monitoring network design and siting criteria guidance document EPA - 450/4-91-033, 1991.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

Tedlar™ is a trademark of E.I. Du Pont de Nemours Co, USA
Tenax TA™ is a registered trademark of Buchem bv, Netherlands
Chromosorb™ is a registered trademark of Manville Corporation, USA
Poropak™ is a registered trademark of Waters Associates Inc. USA
Carbograph™ is a registered trademark of LARA s.r.l., Italy
UniCarb™, UNITY™, and SecureTD™ are trademarks of Markes International Ltd.
FLEC™ is a registered trademark of CHEMATEC, Denmark
Carboxen 1000™ is a registered trademark of Sigma-Aldrich, USA
Carbopack B™ is a registered trademark of Sigma-Aldrich, USA
Spherocarb™ is a registered trademark of Phase Separations, Ltd., UK
Silcosteel® is a registered trademark of the Restek Corporation.


© Agilent Technologies, Inc. 2003

Printed in the USA
April 21, 2003
5988-9255EN



Agilent Technologies

MARKES
International
LIMITED



The Benefits of Setting Up a UNITYe-Based Thermal Desorber Using an Agilent 6890 GC's Electronic Pneumatic Control

Technical Overview

Introduction

Electronic Pneumatic Control (EPC) offers numerous advantages for gas chromatographic (GC) methods including: electronic control of all gas flows and pressures, maintenance of constant flow or pressure throughout a run, flow or pressure programming, and independent regulation of column and split flows. With EPC, flow rates may be stored and recalled with each individual GC method. GCs equipped with EPC allow reproducible results that are independent of operator, laboratory environment, or column.

The precise control of the Agilent GC column flows has allowed the development of Retention Time Locking (RTL) software. RTL allows one to match retention times between different Agilent 6890 systems independent of the inlet or detector. This has substantial cost and time saving benefits and leads to more accurate peak identification.

Though desirable for enhanced analytical performance, it has previously proved difficult and expensive to incorporate EPC into method-compliant thermal desorption (TD) systems. This is because of the many valve and carrier gas flow path changes that occur during the analytical sequence (for example, stop-flow leak testing, dry-purging, prepurging, tube desorption, and backflush trap desorption). However, after a collaborative development program between Agilent Technologies, Inc. and Markes International, Ltd., backpressure regulated EPC has now been successfully and cost-effectively incorporated into the UNITY™ TD

platform. This development significantly improves analysis using coupled thermal desorption-gas chromatography (TD-GC), particularly for complex sets of target analytes.

Implementation of EPC with UNITY - UNITYe

Back-pressure regulated EPC control is implemented on UNITY using the standard EPC module supplied with the 6890 GC split/splitless (S/S) inlet (Figure 1). Some modifications are incorporated on a standard UNITY system to make it an EPC-compatible UNITYe. The most important modification involves inserting a tee into the carrier gas bypass line, close to the connection point with the fused silica transfer line. The tee is connected to a convenient bulkhead fitting on Unity, allowing easy connection to the septum purge port of the Agilent split/splitless EPC module. This provides accurate monitoring and closed-loop control of column head pressure, regardless of the stage of TD operation and the required flow. Use of a low-volume, 3-way valve on each of the two gas connection lines (not shown in Figure 1) would allow the EPC module to be connected interchangeably between the UNITYe and the split/splitless GC inlet. Once configured, a UNITYe-based TD system coupled to a 6890 GC or gas chromatograph/mass spectrometer (GC/MS) offers all the performance enhancements associated with electronic pressure and flow control on standard Agilent 6890 liquid injection systems.



Agilent Technologies

MARKES
International
LIMITED




Figure 1. Schematic of UNITYe showing primary desorption step.

Stable Retention Times with Different Split Flow Settings

Using conventional pressure pneumatics, the column flow and, therefore, analyte retention times shift every time the TD split flow is adjusted. This shift makes it difficult to calculate split ratios exactly and prevents the same data processing method and compound list being used for both

high and low concentration applications. With EPC, carrier gas pressure at the head of the column is continuously monitored and maintained. Retention times remain steady despite split flow changes (Figure 2). EPC control of the GC and TD flows is extremely stable over time. For example, there was no change in the retention times for the benzene, toluene, and xylene peaks over the 15-hour sequence shown in Figure 3.




Figure 2. Retention times stable to two decimal places under significantly different split flows.




Figure 3. Retention time stability for 30 TD/GC/MS analyses of benzene, toluene and xylene over a 15-hour period.

Retention Time Locking (RTL) and Compound Databases

RTL allows retention times to be fixed; they can be re-established precisely after column maintenance or replacement. This means that calibration tables, developed in data handling software to identify and quantify peaks, never need to be adjusted. It also allows methods to be transferred and chromatograms to be reproduced on any other UNITYe-Agilent 6890 TD/GC (or TD/GC/MS) system using the same method and configured with a column of the same nominal dimensions.

In fact, RTL has rendered retention times so stable that it is now possible to create searchable databases (libraries) of component retention times.

RTL databases for use on GC/MS systems include the full spectrum for each compound, its locked retention time, and a table of key ions for use by the ChemStation screener software. The Agilent screener software searches for every compound in the RTL database in a fully automated post-run data processing operation (Figure 4).

A user-generated RTL mass spectral database was used to screen the laboratory air sample shown in Figure 1a. Figure 1b gives the initial report generated by the RTL screener software with numerous target compounds identified. Figure 1c shows the extracted ion chromatogram for m/z 91 which is common to several of the identified peaks. Agilent's results screener software makes it convenient to confirm peak identities.

Electronic Read-Out of Total System Flow

Another practical benefit of EPC with UNITYe-based thermal desorbers is the ability to monitor carrier gas flow through the system in real-time. Total gas flow [column flow plus cold trap flow, when applicable, plus split flow] is displayed when

accessed via the convenient keyboard and display unit on the 6890 GC or via ChemStation PC software. This eliminates the need for flow meters and provides a convenient confirmation of long-term system stability and leak-tight gas supply connections into the system.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

UNITY™ and UNITYe are trademarks of Markes International Ltd., UK.

© Agilent Technologies, Inc. 2003

Printed in the USA
March 31, 2003
5988-9252EN

4a



4b

Cpd#	Compound Name	Status	EXpRt	Delta	Target m/z	Qualifiers	Out of Range	XCR
14	MTBE methyl-t-butyl-ether	?	1.702	-0.021	73	114	57, 41, 43	
34	Chloropicrin	?	3.888	0.004	117	84	119, 82, 47	
37	Tetrachloroethene	?	4.247	0.014	166	1018	164, 131	0.6
40	Ethylbenzene	x	4.821	0.005	91	47633		0.99
41	m-Xylene	x	4.902	0.001	91	397628		0.99
42	p-Xylene	x	4.904	-0.001	91	397628		0.99
44	Styrene	x	5.11	-0.005	104	9886		0.97
45	o-Xylene	x	5.129	-0.005	91	41866		0.99
48	Isopropylbenzene	x	5.404	-0.010	105	2085		0.91
50	2-Chlorotoluene	?	5.626	-0.001	91	4338	126, 89	0.84
51	n-Propylbenzene	x	5.639	-0.014	91	4338		0.97
53	1,3,5-Trimethylbenzene	x	5.746	-0.015	105	5157		0.94
55	1,2,4-Trimethylbenzene	x	5.928	-0.014	105	17919		0.99
56	1,3-Dichlorobenzene	?	6.021	-0.017	146	194	111, 75	0.62
59	p-Isopropyltoluene	x	6.127	-0.014	119	5234		0.67
61	n-Butylbenzene	x	6.32	-0.015	91	2638		0.60
63	1,2,4-Trichlorobenzene	?	6.981	-0.024	180	534	182, 184	0.61

4c




Figure 4. Use of RTL database searching to identify compounds in a 6-L sample of laboratory air. a) Total ion chromatogram (TIC) from TD/GC/MS analysis. b) RTL database search report generated during post-run data analysis. Compounds marked with an "X" are likely hits; compounds marked with a "?" require further review. c) Extracted ion chromatogram of m/z 91 showing ethylbenzene, one of the compounds identified by RTL database searching.



Agilent Technologies

MARKES
International
LIMITED



HPLC Analysis of Formaldehyde in Indoor Air

Hiroki Kumagai

Environmental

Abstract

It was recently discovered that some volatile organic compounds cause the sick building syndrome. Formaldehyde is such a typical compound. It was analyzed by HPLC using 2,4-dinitrophenylhydrazine (DNPH) as the derivatization reagent. The silica gel cartridge, which was impregnated with DNPH (DNPH cartridge) is commonly used for sampling and concentrating aldehydes in air.

In this Application Brief we describe HPLC analysis of formaldehyde in houses using the DNPH cartridge.

Analyzed compounds

Formaldehyde and acetaldehyde of indoor air were analyzed as DNPH derivatives.




Figure 1
Chromatogram of formaldehyde and acetaldehyde
(standard)

Conditions

Column:

250 x 4.6 mm
ZORBAX Eclipse XDB-C18
(Agilent part number 990967-902)

Mobile phase:

CH₃CN/H₂O = 45/55

Column compartment:

40 °C

Injection vol:

25 µl

Detector:

diode-array detector
wavelength 365/16 nm
reference: off



Agilent Technologies

Innovating the HP Way

Sample preparation

Indoor air of newly built houses was taken as sample. Sampling was performed by sucking air through DNPH cartridges with the pump. An ozone scrubber was inserted before the DNPH cartridge. The actual sampling volume was 5 - 20 l.




Figure 2
Chromatogram of formaldehyde and acetaldehyde (DNPH derivative) of indoor air of newly-built house A.




Figure 3
Chromatogram of formaldehyde and acetaldehyde (DNPH derivative) of indoor air of newly-built house B.

Equipment

Agilent 1100 Series

- vacuum degasser
- quaternary pump
- autosampler
- thermostatted column compartment
- diode array detector, Agilent ChemStation + software

HPLC method performance

Limit of detection:
formaldehyde 0.25 $\mu\text{g}/\text{m}^3$,
acetaldehyde 0.35 $\mu\text{g}/\text{m}^3$
(calculated from 3 s of blank values)

Repeatability:
of RT over 6 runs
<0.1 %
of areas over 6 runs
<0.5 %

Hiroki Kumagai is application chemist at Yokogawa Analytical Systems Inc., Tokyo, Japan

For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 1998 Agilent Technologies
Released 04/98
Publication Number 5967-5598E



Agilent Technologies

Innovating the HP Way



Analysis of Formaldehyde and Acetaldehyde in Air by HPLC using DNPH Cartridge

Noriko Shimoi and
Hiroki Kumagai

Environment

Abstract

The monitoring of aldehydes, especially formaldehyde and acetaldehyde, is important for the monitoring of air pollution and acid rain problems. These aldehydes are analyzed by HPLC using 2,4-dinitrophenylhydrazine (DNPH) as the derivatization reagent. The cartridge of silica gel that was impregnated with DNPH (DNPH cartridge) is commonly used for the sampling and concentrating of aldehydes in air.


This application brief describes the analysis of formaldehyde and acetaldehyde in the air using DNPH cartridge.

Analyzed Compounds

Formaldehyde and acetaldehyde in air as DNPH derivatives.

Sample

Air of some location in Japan.



Conditions

Column

250 mm ~ 4.6 mm i.d. Inertsil ODS 80A

Mobile Phase

CH₃CN/H₂O = 50/50

Temperature

40 °C

Injection vol

25 µl

Diode array detector

A—365/8 nm, reference off

Figure 1
Chromatogram of DNPH derivatives of formaldehyde and acetaldehyde



Agilent Technologies

Innovating the HP Way

Sample Preparation

Sampling was performed by sucking air through the DNPH cartridge (ozone scrubber was inserted before DNPH cartridge) with a pump. Sampling time was 24 hours at a flow rate of 0.1 l/min. The actual sampling volume was measured by the flow meter.

Method performance

Limit of Detection: formaldehyde 0.25 $\mu\text{g}/\text{m}^3$, acetaldehyde 0.35 $\mu\text{g}/\text{m}^3$ (calculated from 3σ of blank values)

Repeatability of RT over 6 runs < 0.1 %

Repeatability of area over 6 runs < 0.5 %




Figure 2
Chromatogram of aldehydes in the air of city A (Japan)





Figure 3
Chromatogram of aldehydes in the air of city B (Japan)

Equipment

Agilent 1100 Series

- degasser
 - binary pump
 - autosampler
 - thermostatted column compartment
 - diode array detector
- Agilent ChemStation + software



The authors are application chemists at Yokogawa Analytical Systems Inc.

For more information on our products and services, visit our worldwide website at <http://www.agilent.com/chem>

© Copyright 1997 Agilent Technologies
Released 06/97
Publication Number 5965-9796E



Agilent Technologies


Innovating the HP Way



Material Analysis

Applications

- > [Return to Table of Contents](#)
- > [Search entire document](#)



Use of the Agilent 7020 ZetaProbe to control suspension stability

Application Note



Abstract

Some industrial processes require flocculated suspensions while others require the particles to be well dispersed. It can be a challenge to control these processes, because subtle changes in chemical composition can change the degree of aggregation. In this application note, we show how the fast and accurate zeta potential measurements from the Agilent 7020 ZetaProbe can be used for controlling the stability of a colloid.



Agilent Technologies

Properties of aggregated and dispersed suspensions are critical to performance

Colloidal particles are in a state of constant motion, and they collide with one another many millions of times per second. If there is no repulsion between them, the collisions will result in particles sticking together, forming doublets that quickly develop into triplets and larger groups. Soon, the entire suspension may become a single large aggregate. Alternately, the aggregates (or flocs as they are called) may settle rapidly to form a loose deposit, entrapping a large amount of the suspension medium.

When a suspension is highly dispersed, with strong repulsive forces preventing aggregation, it behaves in many ways like a simple liquid. For example:

1. It will usually have a low viscosity that is independent of shear rate, so it will flow easily and will not 'gel'.
2. It may be difficult to filter, either because the particles are so small that they pass straight through the filter, or because they enter the filter and clog the pores.
3. If the particles are not very dense, it may take a long time for them to settle. When they do settle, they will tend to form a dense deposit that may be very difficult to redisperse. (This is called 'caking').

The opposite is true of an unstable (aggregated) suspension. Such a suspension has the following properties:

1. It will almost always show unusual flow characteristics, with a much higher viscosity than the solvent. This viscosity will depend on how fast the suspension is sheared.
2. It will often behave like a solid if the shearing forces are too small to break down the structure.
3. The aggregates will settle rapidly, but they will form a very loose open network structure that will entrap a lot of water. This structure can be easily broken up by shaking the suspension.
4. The same sort of process may occur in filtration. The solid can easily be separated from the bulk of the suspension medium, but it may be difficult to dewater the remaining filter cake.

In most of the critical operations involved in handling colloidal suspensions, the state of aggregation or dispersion determines how the system will respond. For example, if the aim is to filter out the particles or to produce a slurry that is easily redispersed by shaking the container, an aggregated state is required. But if the aim is to produce a colloid that is easy to pump around, then a disperse state is needed. And a stable colloid is preferred in the colloidal processing of ceramics, for such a slurry produces a stronger ceramic [1].

Zeta potential often controls the state of aggregation

A suspension is stable if the repulsive force between the particles is strong enough to overcome the van der Waals attraction, so to control the aggregation, it is necessary to control the repulsive force.

There are a number of ways to increase this force. One can use a nonionic surfactant or a neutral polymer that adsorbs onto the particles to create a steric barrier to coagulation. Alternatively, one can use electric charge to provide the repulsive force. Aggregation in this case is usually controlled by:

1. Adjusting the solution pH
2. Adding an ionic surfactant
3. Adding a charged polymer, or
4. Adding a highly adsorbable ion, like polyphosphate.

Whenever a charge is present on the particle surfaces, it will contribute to repulsion, and may be the dominant cause of the repulsion. In all such cases, the zeta potential (the electrostatic potential near the surface of the particle) must be controlled in order to control the aggregation process.

Small changes in pH or in the concentration of highly adsorbable ions may influence the effective surface charge and, hence, the state of aggregation. Thus, a small change in the level of impurities in a batch component or a change in the composition of a recirculating water stream may cause a significant shift in zeta potential. In a poorly controlled situation, such changes can lead to different behavior on different days. In cases where a formulation must be made up fresh (as in the preparation of agricultural sprays), there may be problems with the formulation when using water supplies with varying salt composition.

Most process controllers are aware of the importance of maintaining control over the pH in oxide systems or systems involving proteins or weak organic acids, but *many do not realize that it is the zeta potential that must be controlled.*

pH can be used as a substitute control if nothing better is available, but it can sometimes be quite misleading, for the zeta usually depends on other parameters in addition to the pH. The pH is also a troublesome quantity to measure in a colloidal suspension, for the pH probes are rather delicate and are difficult to maintain.

Agilent 7020 ZetaProbe helps to pinpoint conditions for stable dispersions

In the case of electrostatically stabilized suspensions, the zeta potential provides a measure of the repulsive force between the particles. A zeta potential of at least 25 mV (positive or negative) is normally required to achieve a reasonably stable dispersion.

In Figure 1, we show Agilent 7020 ZetaProbe measurements of zeta as a function of pH for alumina, titania, and silica particles. The suspension of silica particles will be stable above pH 4, the alumina will be stable below pH 8, and the titania will be stable at about 2 pH units away from the isoelectric point of 6. From these titration curves, it is easy to determine the required pH range to make either stable or aggregated suspensions. Note that these curves depend on other factors, such as the concentration and type of the suspending electrolyte. Thus, there is no general rule for the pH range required for stability; the zeta curve for each suspension must be measured individually.




Figure 1. These titration curves show zeta potential versus pH for three metal oxides, and illustrate how the ZetaProbe can be used to determine the pH range where the zeta potential is large enough to produce stable suspensions.

Another use of zeta is in monitoring required levels of dispersant. Usually the dispersant is added until the particle surfaces are completely covered, and this occurs when the zeta potential levels off as a function of added dose. This is illustrated in Figure 2 for the case of a polyelectrolyte dispersant, Darvan C, added to an alumina suspension. In this example, the zeta potential has leveled off after about 2.5 mL of polyelectrolyte, so there would be no point in adding more Darvan C than this.

Even in the case when nonionic components are used for controlling dispersion, the zeta is usually reduced as these molecules adsorb, and so zeta measurements can be used to monitor the amount required for surface coverage. Reference [1] contains a number of excellent examples of the use of zeta for controlling levels of both ionic and nonionic dispersants.

ZetaProbe provides significant advantages over other methods

Since it is the zeta potential that actually determines the state of aggregation or dispersion in many systems, it is obvious that a direct and continuous measure of zeta potential would be the ideal way of controlling those industrial process streams. The problem in the past has been the difficulty of obtaining reliable measurements of the zeta potential of the particles in a suspension. Nearly all the other devices for measuring zeta rely on the traditional optical methods for observing the particle motion in an applied electric field. They can only be used effectively on very dilute suspensions. The dilution process takes time and it often changes the zeta potential.

This problem has been solved with the advent of the ZetaProbe. This device can be inserted into a colloidal suspension and within a few seconds can give a reading of the zeta potential that is both reproducible and reliable. No longer is it necessary to dilute the sample before measurement. The ZetaProbe can measure zeta in suspensions of almost any concentration greater than about 0.5% solids. Results are routinely obtained on emulsions up to 60% by volume.




Figure 2. ZetaProbe measurement of zeta potential helps to determine the optimum dispersant dose.

Since the particles or droplets in a concentrated suspension have a large surface area, the relative effect of contamination is minimized, and the resulting ZetaProbe measurement is very robust. With other techniques that require sample dilution, contaminants are spread across a smaller particle surface area, which can lead to large errors in the measurement of zeta potential.

The ZetaProbe delivers consistent, dependable results that indicate true changes in colloids rather than instrument artifacts. With the optical procedures, one makes measurements on a small number of individual particles and seeks some sort of average value of zeta. Even with the light scattering methods, the number of particles that are sampled is relatively small. In the ZetaProbe, the measurement averages the effects of many billions of particles. Results on the same colloid are remarkably consistent from sample to sample, batch to batch, and day to day. Thus, any variations in the measured zeta indicate a real physical change in the colloid and not an instrument artifact.

Unlike other electroacoustic devices, with ZetaProbe there is no need to estimate the particle size by some additional measurement and hope you have the right particle size to make a sensible zeta calculation. The ZetaProbe is able to make an adequate estimate of the effective size and handles the entire calculation. This estimate is made using our patented multifrequency electroacoustic technique. The other electroacoustic devices cannot make such measurements because it would violate our patent and for this reason, they cannot estimate particle size.

With the ZetaProbe, the metal electrodes through which the field is applied are resistant to chemicals and abrasives, and the only other materials that come in contact with the suspension are highly chemically resistant polymers. Maintenance is minimal, the measurement time is around thirty seconds, and the results are extremely reliable.

Accessories help to customize the ZetaProbe for the application at hand. For example, the suspension can be stirred continuously and quite vigorously during the measurement, or it can be pumped in a flow loop to allow on-line simulation studies.

The ZetaProbe comes with computer-controlled syringes to allow titration with reagents like acids and bases, or with surfactant or dispersant solutions. This is one of the great strengths of the device. A reproducible and reliable plot of the zeta potential as a function of pH or additive dose can readily be obtained in a matter of minutes (limited essentially by the speed of equilibration of the particle surface with the bulk solution). This capability speeds process optimization.

Conclusion: a rapid, robust instrument to control particle aggregation

Many industrial processes require that colloidal particles be either aggregated or dispersed, but control of these processes is challenging because the degree of aggregation can be affected by small changes in chemistry of the dispersed system. Zeta potential can be used for controlling aggregation, for it provides a measure of the interparticle electrostatic repulsive force and the degree of adsorption of polymeric dispersant on the particle surface. The Agilent 7020 ZetaProbe provides reliable, reproducible measurements of zeta potential in undiluted colloidal suspensions. Because it requires no sample dilution and delivers repeatable readings in seconds, it is the ideal instrument for direct and continuous measurement of zeta potential in industrial process streams.

Reference

1. Greenwood, R. (2003) "Review of the measurement of zeta potentials in concentrated aqueous suspensions using electroacoustics," *Advances in Colloid and Interface Science* **106**, 55-81.

Learn more:

www.agilent.com/chem/particleanalyzers

Buy online:

www.agilent.com/chem/store

Find an Agilent customer center in your country:

www.agilent.com/chem/contactus

U.S. and Canada

1-800-227-9770

agilent_inquiries@agilent.com

Europe

info_agilent@agilent.com

Asia Pacific

adinquiry_aplsca@agilent.com

This item is intended for Research Use Only.
Not for use in diagnostic procedures.


Information, descriptions and specifications in this publication are subject to change without notice. Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

All rights reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

© Agilent Technologies, Inc. 2008
Printed in the U.S.A. August 26, 2008
5989-8123EN




Agilent Technologies



Basics of Zeta Potential

Application Note



Abstract

This Application Note describes the nature of the electrostatic potential near the surface of a particle, called the zeta potential. It explains how the zeta potential is determined by measuring the velocity of the particles in an electric field. It also explains how the charge on the particle surface affects properties of suspensions and emulsions.



Agilent Technologies

Introduction

The particles in a colloidal suspension or emulsion usually carry an electrical charge. The charge is more often negative than positive and it may arise in a number of ways.

Sometimes the surface of the particles contains chemical groups that can ionize to produce a charged surface. Sometimes the surface adsorbs ions of one sign in preference to ions of the opposite sign. In other cases, chemical compounds are added deliberately to adsorb on the particle surface and generate charge.

However it may happen, the amount of charge on the particle surface is an important particle characteristic because it determines many of the properties of the suspension or emulsion.

Charge distribution

Although the particles are electrically charged, the colloid as a whole is electrically neutral, because the charge on the surface of each particle is counterbalanced by charges (ions) of opposite sign in the surrounding solution.

The charges on the particle surface are normally considered to be attached rather firmly to it and to remain there (though they may exchange with charges of similar type in the solution). The surrounding (balancing) charge, by contrast, is much more loosely associated with the particle.

Because of the thermal motions of the solvent molecules and ions, this countercharge is spread in a *diffuse layer* that stretches out for some distance (on the order of nanometers) from the particle surface (Figure 1).

The oppositely charged ions (called *counter-ions*) tend to congregate around the particle and very few negatively charged ions (*co-ions*) can get close to the surface because of the repulsion from the charges on the particle. Farther away from the particle, the co-ions suffer less repulsion and eventually, at distances of at most a few tens of nanometers, the numbers of cationic and anionic charges are evenly balanced.




Figure 1. Distribution of charge around a negatively charged particle

Measuring the charge

There are various ways to measure the particle charge, and the different methods do not always measure the same quantity. Most of the commercial devices for determining zeta apply an electric field to the suspension and measure how fast the particles move as a result. This process is called *electrophoresis*. The bigger the charge they carry, the faster the particles will move. This is how the Agilent 7020 ZetaProbe works too, but it measures particle motion in MHz electric fields, while the standard products use DC or slowly varying electric fields. And the ZetaProbe determines the particle motion by measuring the sound waves that the particles emit as they shake back and forth, while the other zeta devices use optical techniques which are limited to very dilute suspensions.

In electrophoresis measurements, one does not usually observe all of the particle charge. The electric field pulls the particle in one direction, but it also pulls the counterions in the opposite direction. Some of the counterions will move with the particle (those within the dotted circle in Figure 1, for example) so the measured charge will be a *net* charge.

The electrostatic potential near the particle surface is shown in Figure 2. It changes very quickly (and linearly) from its value at the surface through the first layer of counterions and then changes more or less exponentially through the diffuse layer. The junction between the bound charges and the diffuse layer is again marked by the broken line. That surface, which separates the bound charge from the diffuse charge around the particle, marks where the solution and the particle move in opposite directions when an external field is applied. It is called the *surface of shear* or the *slip surface*.

The voltage difference between that surface and the liquid beyond the double layer is called the *zeta potential*. It is this potential that determines how fast the particles move in an applied electric field.




Figure 2. Electrostatic potential near a negatively charged spherical particle

The particle velocity is proportional to the strength of the applied field. By dividing the velocity by the field strength, we obtain a quantity that is a particle property, independent of field strength. This ratio of velocity to field strength is called the electrophoretic mobility in the case of a DC field, and the dynamic mobility in the AC field case. Zeta is calculated from the measured mobility using an appropriate theoretical formula.

Charge affects properties

At first it would seem to be a distinct disadvantage of this method that it only measures a part of the potential on the particle. But in fact that turns out to be an advantage.

When the charge is measured in this way, it reflects more realistically what one particle “sees” as it approaches another particle, and that is what determines the properties of the suspension. If the

repulsion between approaching particles is large enough, they will bounce away from one another, and that will keep the particles in a state of *dispersion*.

If the repulsive force is not strong enough, the particles will come together and may stick in a permanent doublet. Then other particles may come along and be caught in the growing aggregate. The suspension is then unstable and the aggregates will quickly settle out from the surrounding medium.

If one is relying on the electric charge alone to keep the system in a disperse state, then the zeta potential will usually need to be kept above 25 mV in magnitude.

Generally speaking, the higher the absolute value of the zeta potential, the more stable the system will be. That means it will be better able to withstand additions of salt (which might otherwise destabilize it). It will also usually show a lower viscosity.

On the other hand, if one wants to separate the particles and remove them from the surrounding fluid, it will be advantageous to reduce the magnitude of the zeta potential.

Aside from its application to suspension stability, the zeta potential is also widely used as a monitor of surface chemistry. Since zeta is a surface property, it is very sensitive to any coating or adsorbed material on the surface. Thus, it is used to detect the presence of any surface contamination, to check coating consistency, and to monitor adsorption of polymeric dispersants.

Conclusion: importance of zeta potential

Particles in a colloidal suspension or emulsion usually carry an electrical charge, which affects the degree of dispersion or aggregation. The zeta potential is the electrostatic potential near the surface of a particle, and is determined by measuring the velocity of the particles in an applied electric field. When the absolute value of the zeta potential is greater, the system is more stable and the particles are more likely to remain dispersed and less likely to aggregate. The value of zeta is also very sensitive to surface chemistry, so it is an ideal indicator for detecting contamination or monitoring adsorption on the particle surface.

Learn more:

www.agilent.com/chem/particleanalyzers

Buy online:

www.agilent.com/chem/store

Find an Agilent customer center in your country:

www.agilent.com/chem/contactus

U.S. and Canada

1-800-227-9770

agilent_inquiries@agilent.com

Europe

info_agilent@agilent.com

Asia Pacific

adinquiry_aplsc@agilent.com

This item is intended for Research Use Only.
Not for use in diagnostic procedures.


Information, descriptions and specifications in this publication are subject to change without notice. Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

All rights reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

© Agilent Technologies, Inc. 2008
Printed in the U.S.A. March 28, 2008
5989-8124EN



Agilent Technologies



Definitive Quality Control of Titania Coatings with the Agilent 7020 ZetaProbe

Application Note

Abstract

Commercial titania particles are nearly always coated with a substance such as silica or alumina to prevent breakdown under sunlight. The Agilent 7020 ZetaProbe is ideal for monitoring the type and the integrity of this surface coating, and for this reason, it is used in the quality control (QC) labs of titania manufacturers and their customers to detect any batch-to-batch variability.



Agilent Technologies

The importance of coatings for titania

Titania (TiO_2) is a white pigment and an important industrial material, widely used in the paint, ink, paper, synthetic fiber, and even cosmetic industries.

It is used as a coating, a reflecting agent, or as a scatterer/absorber of light.

In its pure form, titania suffers from the drawback that it is *photoactive*, so when it is acted on by light, it can release an electron from its surface and that electron may cause chemical damage to the surrounding material over time. Thus, for example, a paint that is made using uncoated titania particles will crack and deteriorate under prolonged exposure to sunlight. For this reason, the titania particles are usually covered with a thin layer of some other oxide, like silica, alumina, or zirconia, or some combination of these materials.

Titration using the ZetaProbe reveals surface coating

The ZetaProbe has proved to be a vital QC tool for controlling the surface coating in the titania manufacturing process. The QC is usually done by carrying out a pH titration on a sample from the process stream to determine the curve of zeta against pH.

Two sample ZetaProbe titration curves are shown in Figure 1. The first is for an uncoated titania, while the second is for a silica-coated titania. Clearly, the curves are strongly influenced by the type of coating. In practice, attention is usually focused on the *isoelectric point* (IEP), which is the pH at which zeta is zero. For the uncoated titania particles, the IEP is 6.2, but for the silica-coated particles it is below pH 2, which is typical of a pure silica particle. For alumina-coated particles on the other hand, the IEP is up around 9.




Figure 1. ZetaProbe titration curve for uncoated titania shows an IEP of 6.2, while that of silica-coated titania shows an IEP of less than 2, allowing one to easily distinguish the two surfaces.

Thus, the IEP provides a clear indication of the type and the integrity of the coating on the titania particles. If the coverage is patchy or if it is too thin, the IEP will be shifted. For each batch of titania, the IEP is measured and compared to the standard value for that coating grade.

The ZetaProbe is ideal for this application, because it has been designed for easy and accurate IEP determination. Its computer-controlled burettes and rapid measurement processes allow the IEP to be determined to better than 0.1 pH units in under half an hour. This is critical for the QC labs where throughput is vital.

The various optical devices for measuring zeta are inherently slower and far less accurate than the ZetaProbe because they require sample dilution, which is both time-consuming and which introduces errors due to changes in the supernatant or contamination of particle surface by trace surface-active materials. The ZetaProbe does not require sample dilution because it uses our patented electroacoustic technique, which can be applied to concentrated suspensions.

Electroacoustic measurement provides insight into the coating process

The titration curve for the silica-coated titania in Figure 1 has the same form as for a pure silica particle. Clearly in this case the coating is thick enough to completely mask the underlying titania, but how thick does the coating have to be for complete coverage, and what happens with thinner layers?




Figure 2. Electrostatic potential near a negatively charged spherical particle

An answer to the second question is provided by the data in the Figure 2, which shows the electroacoustic zeta curves for titania particles during an alumina deposition process. In this experiment, progressively larger quantities of aluminum (as aluminum chloride or nitrate) were added to the titania colloidal solution. After each addition (at low pH), the pH was raised, causing the Al^{3+} ion to hydrolyze and become adsorbed on the particle surface as the oxide or hydroxide. The initial titania was uncoated and had its natural IEP at about pH 5. When coating was complete, the IEP had shifted up to pH 9.1, a value characteristic of the alumina-covered surface.

Djedjev et al recently carried out a detailed study of silica coating on titania using a combination of electroacoustic, dielectric response, and transmission electron microscopy (TEM) measurements of the coating layer [1]. They found that the IEP drops to the limiting silica value when the coating is around one nm thick. Further increases in the coating layer do not alter the titration curve any more. From the dielectric measurements, they determined that the dielectric constant of the coating is around 20, higher than the value for pure silica. The authors take this to be an indication of hydrolysis within the silica layer.

Conclusion

The Agilent 7020 ZetaProbe is an excellent tool for quality control of surface coating in the titania manufacturing process. The isoelectric point – the pH at which the zeta potential is zero – differs depending on the type and integrity of the surface coating. The ZetaProbe enables very easy, rapid, and accurate determination of a plot of zeta potential versus pH, so it is an ideal instrument to assess the quality of the coating process. The ZetaProbe does not require sample dilution, so it saves time and avoids the errors that are inherent in optical measurement of zeta potential.

Reference

1. Djerdjev, A. M.; Beattie, J. K.; and O'Brien, R.W. (2005) "Coating of Silica on Titania Pigment Particles Examined by Electroacoustics and Dielectric Response." *Chemistry of Materials* **17 (15)** 3844-9.

Learn more:

www.agilent.com/chem/particleanalyzers

Buy online:

www.agilent.com/chem/store

Find an Agilent customer center in your country:

www.agilent.com/chem/contactus

U.S. and Canada

1-800-227-9770

agilent_inquiries@agilent.com

Europe

info_agilent@agilent.com

Asia Pacific

adinquiry_aplsca@agilent.com

This item is intended for Research Use Only.
Not for use in diagnostic procedures.


Information, descriptions and specifications in this publication are subject to change without notice. Agilent Technologies shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance or use of this material.

All rights reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

© Agilent Technologies, Inc. 2008
Printed in the U.S.A. March 28, 2008
5989-8122EN



Agilent Technologies



Using the Agilent 7500cx ICP-MS with High Matrix Introduction Accessory for the Analysis of Metals in High Tech Manufacturing

Application

Environmental

Authors

Keiki Katagiri, Masahiro Kanou, and Taichi Yamamoto
Nihon Environmental Services Co., Ltd.
Tokyo, Japan

Yasuyuki Shikamori and Tetsushi Sakai
Agilent Technologies
Tokyo, Japan

Abstract

A new method has been developed using an Agilent 7500cx fitted with a High Matrix Introduction (HMI) accessory for the direct analysis of trace contaminants in high-purity metals and electronic devices. Samples were prepared using reagents with varying chemical compositions and concentrations in accordance with environmental directives governing hazardous material content in manufactured goods, for example, Restriction of Hazardous Substances (RoHS) and End of Life, Vehicles (ELV). Despite the high matrix composition of the samples, the HMI is designed to analyze these sample types directly, with excellent accuracy and long-term stability, avoiding the need to dilute.

Introduction

Accurate measurement of the metals content of manufactured goods is necessary for several reasons, including process control, product quality assurance, and compliance with environmental regulations. In many cases, such as high-purity metals, the sensitivity required may be extremely high. In other cases, complex and variable matrices make interference-free analysis difficult. Traditionally, analysis of very high matrix samples by ICP-MS required sample dilution in order to avoid the common problems of

spectral interferences, matrix suppression, and poor long-term stability. This paper will discuss the advantages of using the Agilent High Matrix Introduction (HMI) accessory with the Agilent 7500cx ICP-MS for both the analysis of high-purity metals and electronic and automotive devices regulated under the Restriction of Hazardous Substances (RoHS), End of Life, Vehicles (ELV), and other recent environmental directives governing hazardous material content in manufactured goods. While these applications differ significantly in many ways, both require accurate and precise measurements in samples containing both high acid and matrix concentrations in excess of 1,000 ppm.

Details on the theory and operation of the HMI accessory are covered in Agilent publication "Performance Characteristics of the Agilent High Matrix Introduction System," 5989-7737EN.

Experimental

Analysis of Trace Contaminants in High-Purity Metals

High-purity metals analysis is challenging due to the very low detection limits required in the presence of a very high matrix concentration. Additionally, the use of aggressive acid mixes can be damaging to the ICP-MS interface. In this work, three high-purity metal certified reference materials (CRMs) (JSAC 0121¹ aluminum, NIST 398² copper, and JSS003-5³ iron) were analyzed using an Agilent 7500cx fitted with the HMI accessory. Instrument conditions are shown in Table 1. Samples were prepared by gently dissolving 1 gram of sample into 100 mL of 20% aquaregia or 10% nitric acid and analyzed directly.

¹ JSAC - The Japan Society for Analytical Chemistry

² National Institutes of Science and Technology, USA

³ Japan Iron and Steel Federation



Agilent Technologies

Note that even when analyzing 20% aquaregia, nickel sampling and skimmer cones were used. Recoveries of certified values are shown in Tables 2 through 4. Long-term stability was tested by repeatedly (n = 150) analyzing a 1% Cu solution in 10% nitric acid and monitoring internal standard recovery (see Figure 1).

Table 1. ICP-MS and HMI Parameters Used for High-Purity Metals Analysis

Parameter	Setting
Sampling cone	Ni
Skimmer cone	Ni
Nebulizer	MicroMist
Plasma conditions	Ultra robust
Aerosol reduction level	High
Helium gas flow rate	5 (mL/min)
Kinetic energy discrimination (KED)	3 (V)

Table 2. Recovery of Certified Values for JSAC 0121 (High-Purity Aluminum)

Element	m/z	Cell gas	Certified value	Result	
			mg/kg	mg/kg	Recovery (%)
Mg	24	He	2.82 ± 0.13	2.841	101
Ti	47	He	1.96 ± 0.07	2.073	106
Cr	52	He	1.13 ± 0.06	1.098	97
Mn	55	He	1.73 ± 0.06	1.730	100
Fe	56	He	9.4 ± 0.3	10.016	107
Cu	63	He	3.48 ± 0.11	3.738	107
Zn	68	He	2.03 ± 0.13	2.117	104
Zr	90	He	2.02 ± 0.13	2.000	99

Table 3. Recovery of Certified Values for NIST 398 (Unalloyed Copper)

Element	m/z	Cell gas	Certified value	Result	
			mg/kg	mg/kg	Recovery (%)
Fe	56	He	11.4 ± 0.5	11.52	101
Ni	60	He	7.0 ± 0.1	7.04	101
Zn	68	He	24 ± 1	24.18	101
As	75	He	25.0 ± 3	27.62	110
Se	78	He	17.5 ± 0.8	17.33	99
Ag	107	He	20.1 ± 0.2	19.75	98
Sn	118	He	4.8 ± 0.6	5.46	114
Sb	121	He	7.5 ± 0.1	7.25	97
Te	125	He	10.1 ± 0.2	10.12	100
Pb	208	He	9.9 ± 0.6	10.15	103
Bi	209	He	2.0 ± 0.3	2.09	105

Table 4. Recovery of Certified Values for JSS003-5 (High-Purity Iron)

Element	m/z	Cell gas	Certified value	Result	
			mg/kg	mg/kg	Recovery (%)
Al	27	He	78 ± 6	78.6	101
Cr	52	He	0.1	0.12	115
Mn	55	He	27 ± 1	26.6	99
Co	59	He	2.2 ± 0.2	2.25	102
Ni	60	He	0.4 ± 0.1	0.35	88
Cu	63	He	15.4 ± 0.5	15.3	99
Mo	95	He	0.7 ± 0.1	0.75	107
Sn	118	He	4.9 ± 0.2	4.92	100
W	182	He	0.4 ± 0.2	0.36	90




Figure 1. Internal standard signal stability over 150-sample sequence – 1% copper solution in 10% nitric acid.

Discussion

Using the HMI accessory with the Agilent 7500cx permits simple, direct analysis of high TDS, high acid metal digests directly, without prior dilution. Results for three standard reference high-purity metals showed excellent agreement with certified values. Long-term stability was excellent as evidenced by stable internal standard recoveries over a 150-sample sequence of 1% Cu solutions.

RoHS and ELV Directives

The RoHS directive (2002/95/EC) was enacted by the European Commission in July 2006. Similar restrictions have also been enacted in China according to a Chinese version of the RoHS directive and in the State of California, United States. In Japan, J-Moss is the Japanese version of the RoHS directive. The ELV directive (2000/53/EC) was enacted in July 2003. These directives restrict the use of certain hazardous chemical substances (see Table 5 for thresholds for each targeted substance) in electronic and electrical products (RoHS) and in automobile components (ELV) to ensure the health of users and prevent environmental pollution when these components are disposed of. The International Electric Standardization Conference (IEC) has been studying techniques for measuring hazardous chemical substances in electronic and electrical products since June 2005 under the standard number IEC62321. This standard is expected to propose X-ray fluorescence analysis as a screening technique, and ICP-MS as a precision analysis technique.

Table 5. RoHS/ELV Directive Targeted Substances and Thresholds

Target substance	RoHS directive (mg/kg)	ELV directive (mg/kg)
Cd	100	100
Pb	1000	1000
Hg	1000	1000
Cr ₆ ⁺	1000	1000
PBBs [*]	1000	—
PBDEs ^{**}	1000	—

* Polybrominated biphenyl flame retardants

**Polybrominated diphenyl ether flame retardants. Deca BDE is not currently regulated under RoHS

Experimental

Analysis of Regulated Metals According to RoHS and ELV Directives

Many of the materials regulated by the RoHS/ELV directives are composed of inorganic materials,

including metals and ceramics, combined with polymer resins and other additives such as inorganic fillers. Consequently, solutions made from these materials contain high concentrations of various elements from the principal substances. Furthermore, electronic devices or similar components that are difficult to digest require the use of techniques and reagents resulting in sample solutions with complex compositions. These matrix components are a common cause of interferences in ICP-MS. Additionally, ICP-MS sensitivity tends to drop when continuously measuring large numbers of high matrix samples, limiting the number of samples that can be measured and requiring frequent maintenance of the sample introduction system and MS interface.

In this paper, the Agilent 7500cx/HMI was used to analyze various samples considered difficult to analyze for elements targeted by the RoHS/ELV directives.

Methodology

Samples were prepared according to U.S. Environmental Protection Agency (EPA) test method 3052, which can prepare cadmium, lead, mercury, and total chrome at the same time. In this method, a specified amount of the sample is placed inside a sealable Teflon-coated container with HF or a mixture of other acids. The contents are digested by heating with microwave radiation. The amount of initial sample material and final volume were adjusted to keep the maximum concentration of the matrix solution within 1,000 mg/L (or 100 mg/L where possible). Table 6 shows the target analyte masses and their related internal standards, while Table 7 shows the relevant instrument parameters.

Table 6. Analyte Masses and Internal Standard Elements Used

Measured element	<i>m/z</i>	Internal standard element
Cr	52	⁷¹ Ga
	53	
Cd	106	¹¹⁵ In
	110	
	111	
	114	
	116	
Hg	201	²⁰⁵ Tl
	202	
Pb	206	²⁰⁵ Tl
	208	

Table 7. ICP-MS Parameters with HMI Installed for RoHS Analysis

Parameter	Value
Sampling cone	Nickel
Skimmer cone	Nickel
Nebulizer	Mira Mist
Plasma conditions	Ultra robust
Aerosol reduction level	Medium
Helium gas flow rate	4 (mL/min)
Kinetic energy discrimination (KED)	2V

Results and Discussion

To evaluate the sensitivity in the matrix, 100 high matrix samples consisting of various digested polymers, alloys, and glass samples, as well as alkaline fusion samples, were measured consecutively. Blank Checks (CCBs) were included after every five samples to monitor variations in sensitivity and background. Figure 2 shows the variation in sensitivity of the internal standard elements in the CCB samples. The measurements without the HMI varied significantly with an overall loss of sensitivity. Furthermore, increasing memory effects from common matrix components made it difficult to continue measuring, resulting in the need to clean the sample introduction system. However, with the HMI attached, measuring sensitivity did not drop from the beginning of the analysis to the end. The internal standard elements used remained stable with %CV values for Ga (3.6%), In (3.4%), and Tl (2.2%).

Effects of Digestion Reagents on High Matrix Concentrations

Matrix interference can result from using a combination of acids as a digestion reagent or when the concentration of acid differs significantly compared to the standard solution. Three commonly used digestion solvents, HNO_3 , $\text{HNO}_3 + \text{HF}$, and alkali fusion using sodium carbonate were evaluated to test the effectiveness of the HMI at reducing matrix interferences. Alkali fusion was tested because it is required for the dissolution of otherwise insoluble, high melting-point materials such as ceramics. We measured the blanks for each extraction solvent and compared the signals of the internal standard elements. The internal standard reference signal was based on an extraction solvent using only dilute HNO_3 . Figure 3 shows the effect of the various extraction solvents compared to nitric acid. Without HMI (Figure 3, left) installed, there is a significant matrix effect depending on the extraction solvent used. When HMI was employed (Figure 3, right), suppression was eliminated and the relative effects of the various extraction solvents were minimized, even when using alkali fusion. The fact that HMI was effective in minimizing matrix effects from various, complex digestion reagents means it is possible to measure a wider range of difficult-to-digest materials.




Figure 2. ISTD signal stability over 100 samples without HMI (left) and with HMI (right).




Figure 3. ISTD signal suppression by extract solvent without HMI (left) and with HMI (right).

Conclusions

The Agilent HMI accessory for the 7500 ICP-MS with Octopole Reaction System (ORS) has been shown to be a simple, reliable technique for the direct measurement of high TDS samples as diverse as high-purity metals and electrical and electronic devices and components. HMI allows the direct analysis of both high dissolved solids samples and high acid concentrations using standard nickel interface cones with excellent accuracy and long-term stability. The RoHS/ELV directives target a multitude of materials that require the use of a variety of digestion reagents and procedures.

In this study, using the HMI with the Agilent 7500cx ICP-MS made it possible to measure high matrix samples prepared using reagents with varying chemical compositions and concentrations

continuously over many hours. Compared to ICP-MS analysis without using HMI, the sample introduction system and interface required only a minimum of maintenance, demonstrating that the 7500cx with HMI is effective at meeting the requirements for analyzing hazardous substances targeted by the RoHS/ELV directives. Furthermore, by eliminating the need for extra sample handling and the potential of contaminated diluent, HMI greatly reduces the possibility of false positives while significantly simplifying and streamlining the analytical process.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
March 18, 2008
5989-8095EN



Agilent Technologies



RoHS/ELV Directives - Measurement of Heavy Metals Using ICP-MS

Application

Environmental

Authors

Taichi Yamamoto, Yuki Arai, Tomohiro Seki
Nihon Environmental Services Co., Ltd.
Tokyo
Japan

Abstract

This application note describes a robust analytical method for the determination of heavy metals and substances regulated by the EU Restriction of Hazardous Substances/End of Life Vehicles (RoHS/ELV) directives. Based on the experience of Nihon Environmental Services Co., Ltd in Japan using an Agilent Technologies 7500c ORS (Octopole Reaction System) collision/reaction cell ICP-MS, this note summarizes:

- **An overview and validation of ICP-MS methodology for RoHS applications**
- **Benefits of ICP-MS methodology to the analysis of trace elements in high matrix samples and limitations of EDXRF (Energy Dispersive X-Ray Fluorescence) for the measurement of lead in flame resistant plastics**
- **Advantages of ICP-MS for RoHS applications.**

Introduction

The European Union (EU) RoHS directive (Restriction of the use of certain Hazardous Substances, Directive 2002/95/EC effective July 2006) aims at

effectively eliminating the use of hazardous chemical materials used in electric/electronic products. The EU End of Life Vehicles (ELV) Directive 2000/53/EC covers the use of certain substances in the manufacture of new vehicles and automotive components. In China and Japan, the respective equivalents of the RoHS directive will be enforced at the same time as in the EU. The Japanese version is currently being prepared by the Ministry of Economy, Trade and Industry.

Table 1 shows the substances/metals that are regulated by the RoHS/ELV directives along with their thresholds. The RoHS directive restricts the use of three heavy metals: cadmium (Cd), lead (Pb), mercury (Hg), plus hexavalent chromium (Cr⁶⁺) and two brominated flame retardants. The ELV directive only targets the metals stated above. In accordance with these directives, careful control is required during the manufacture of sub components to prevent the above substances entering into the process. Polymeric resin materials are particularly susceptible to contamination. Nevertheless, other than British Standard/European Standard BS EN1122:2001: Plastics – Determination of Cadmium - Wet Decomposition Method [1], a standard method for analyzing metal impurities in resins does not exist. A National Standardization Technical Committee (TC111) working group 3 organized in the International Electrotechnical Commission (IEC) was set the task of developing standard RoHS analysis methods.



Agilent Technologies

Table 1. Substances Restricted by the RoHS/ELV Directives and Their Thresholds

Restricted substance	RoHS directive/ mg/kg	ELV directive/ mg/kg
Cd	100	100
Pb	1000	1000
Hg	1000	1000
Cr ⁶⁺	1000	1000
PBBs*	1000	—
PBDEs**	1000	—

* Polybrominated biphenyls

** Polybrominated diphenyl ethers

Methodology

Table 2 summarizes the methods of analysis that are performed at Nihon Environmental Services, along with the minimum quantitative detection limits. Official analysis methods for hexavalent chromium include EPA3060A/7196A, (alkaline digestion of hexavalent chromium, colorimetric method), plus JIS H 8625 (hexavalent chromium by a diphenylcarbazine colorimetric method), ISO3856/5 (determination of hexavalent chromium content of the pigment portion of liquid paint or paint in powder form, diphenylcarbazine spectrophotometric method) and DIN53314

(determination of content of chromium (VI) in leather by colorimetric analyses using diphenyl carbazine). None of these, however, have been sufficiently validated for a wide variety of materials. For this reason, it has become general practice at Nihon Environmental Services to measure the total concentration first, and then measure the concentration of the hexavalent form only if the total concentration exceeds the Cr⁶⁺ minimum quantitation limit. Nihon Environmental Services uses US EPA SW-846 Method 3052 (microwave assisted acid digestion of siliceous and organically based matrices, hereafter “EPA3052”) [2]. This screening method specifies the simultaneous pre-treatment procedures for cadmium, lead, mercury, and total chromium.

Nihon Environmental Services Co., Ltd uses an Agilent 7500c equipped with an ORS collision/reaction cell to analyze cadmium, lead and chromium, see Table 3 for operating conditions. Quantitative determination of mercury is also possible provided that the memory effect (the element’s adsorption to the container) and the volatility of the material are taken into account. The instrument was calibrated using a mixed standard solution (SPEX, Metuchen NJ, USA). Table 4 shows the analytical isotopes and internal standards monitored.

Table 2. Minimum Quantitative Detection Limits and Methods of Analysis

Restricted substance	Minimum Level of Quantitation mg/kg	Analysis method	
		Sample preparation	Quantitative Analysis (Technique)
Cd	1	In accordance with the US EPA SW-846 Method 3052 Acid decomposition method with microwave oven	ICP-MS method, see Table 3 for operating parameters
Pb	10		
Hg	1		
Cr	1		
Cr ⁶⁺	10	In accordance with the US EPA SW-846 Method 3060A Hot alkali extraction method	In accordance with the US EPA SW-846 Method 7196A, using Diphenylcarbazine absorption spectroscopy
PBBs	10	Solvent extraction method	GC/MS
PBDE	10	Solvent extraction method	GC/MS

Table 3. ICP-MS Operating Parameters, Agilent 7500c ICP-MS

Nebulizer type	Babington
RF power	1600 W
Sampling depth	8.5 mm
Carrier gas flow rate	1.2 L/min
Makeup gas flow rate	0 L/min
Spray chamber temp	2 °C
Peristaltic pump speed	0.1 rps
Reaction gas	H ₂ (3.5 mL/min)

Table 4. Isotopes Used for Measurements by ICP-MS

Measured element	<i>m/z</i>	Internal Standard (<i>m/z</i>)
Cr	52	Ga (71,69) or Y (89)
	53*	
Cd	106	In (115*) or Y (89) or Te (125)
	111*	
	112	
Hg	200	Tl (205)
	202*	
Pb	207	Tl (205)
	208*	

* Isotope that is used primarily for quantitative determination.

Validation of Methodology

Analysis of Standard Reference Materials

A standard polyethylene substance CBR-680 supplied by the Community Bureau of Reference (CBR) was prepared for analysis by ICP-MS according to the procedures detailed in methods EN1122 and EPA3052. The certified value for cadmium in the standard is 140.8 mg/kg. The measured values were subjected to Grubbs' test for outliers to confirm that no samples were to be

rejected. The results were then tested at the 5% significance level to check if there was a difference between the averages calculated by the two methods. The average resulting from the EN1122 method was 143.2 mg/kg (CV: 3.2%, recovery: 101%) and the average from the EPA3052 method was 138.0 mg/kg (CV: 2.4%, recovery 98%). No significant difference was observed between the results.

Results of a Proficiency Test

To test the validity of their ICP-MS methodology the lab took part in the proficiency test in 2004 (IIS04P02): "Cadmium and Lead in Plastics" that was administered by the Institute for Interlaboratory Studies (IIS), in the Netherlands. At present, this is the only international proficiency test that is based on the ISO/IEC Guide 43. According to the report, this test attracted the participation of 56 analytical institutions from 20 countries around the world, with a large number of participants from Japan, Hong Kong, China and other areas in Asia [3]. Three participating labs used ICP-MS, 17 used atomic absorption spectroscopy and 33 used ICP-OES.

Three samples were used in the test. Cadmium was the target metal for #0454 and #0455, while lead was the target for #0456. All samples were polyvinyl chloride (PVC) moldings. Samples #0454 and #0456 contained over 10 times the regulated value of Cd and Pb respectively, while Sample #455 had only a moderate concentration of Cd. The results that Nihon Environmental Services obtained were close to the average for both the EN1122 and EPA Method 3052, as shown in the example histograms for Cd and Pb in Figures 1 and 2. The calculated z-scores were within a range of ± 1 .





Figure 1. Histograms of results for Cd in sample #0454 and #0455.




Figure 2. Histogram of results for Pb in sample #0456.

High-Concentration Matrix Samples

The materials covered by the RoHS/ELV directives include various metals and ceramics, as well as polymers. Some resin products contain a large amount of inorganic components as a result of additives such as metal fillers. While resins and other organic components can be decomposed using microwave digestion, their inorganic constituents often remain in high concentrations. It is difficult for some types of analytical instrumentation to measure trace elements in the presence of such high concentration matrices. To overcome this problem, pretreatment methods such as solvent extraction and ion exchange are proposed. Nihon Environmental Services, however, prefers direct quantitative determination and uses ICP-MS with minimum sample pretreatment. By making use of the relative freedom from spectral interferences provided by the 7500c ICP-MS, complicated sample pretreatment procedures are simplified, and the risk of introducing contaminants is minimized. Turnaround time is also improved.

Managing Interferences in ICP-MS

Spectral interferences caused by overlaps of poly-atomic species on elements of interest (cadmium, lead, chromium, and mercury) were overcome by operating the 7500c ORS collision/reaction cell in helium mode (4.5 mL/min flow rate). Physical interferences were corrected through the use of appropriately selected internal standards. Internal standards were selected with similar ionization potential and a similar mass-to-charge ratio to the analytes being measured. Note that the internal standards recommended by the USEPA are not always the most suitable for all matrices.

Limitations of EDXRF for Measurement of Lead in Flame Resistant Plastics

EDXRF spectroscopy can provide quick, low cost analyses. For this reason, this instrument is widely used for screening tests in the electronic, electric appliance and automobile industries, where the number of parts and components used extends from several hundreds to several tens of thousands. Modern EDXRF instruments have improved significantly in sensitivity and are currently capable of measuring at ppm levels under optimized conditions. However, their application is limited because of interferences on key analytes.




Figure 3. EDXRF spectra of brominated flame retardant containing plastics A (top) and B (bottom).

Figure 3 shows an example of the measurement of lead contained in two flame resistant plastic samples (A and B) using an EDXRF spectrometer. The presence of the prominent peaks associated with bromine suggests that both samples A and B contain brominated flame retardants. EDXRF results also showed less than 10 mg/kg of lead for sample A and 70 mg/kg of lead for sample B. However, analysis by ICP-MS showed less than 10 mg/kg for both samples. The difference in the results for lead in Sample B can be accounted for as follows: Table 5 shows how the wavelength of the lead peak $L_{\alpha 1}$ is close to K_{α} of arsenic, and the $L_{\beta 1}$ and $L_{\beta 2}$ of lead are close to K_{α} and $K_{\beta 1}$ of bromine. This means that it is difficult to determine lead in a sample

which contains arsenic and bromine. Brominated compounds are generally added as a flame retardant and antimony trioxide (SbO_3) is sometimes used to enhance performance. Arsenic compounds are not intentionally added to plastics, however it can occur as a contaminant in the antimony compound. The ICP-MS results for Sample B showed arsenic was present at the 50-ppm level. The comparison demonstrates that ICP-MS provides more reliable results for the determination of heavy metals and other elements such as arsenic, in flame-resistant materials.

Table 5. EDXRF Wavelengths for Quantitative Analysis and Interference Identification

Elements	Spectrum	keV
Pb	$L_{\alpha 1}$	10.552
	$L_{\beta 1}$	12.614
	$L_{\beta 2}$	12.623
As	K_{α}	10.532
	$K_{\beta 1}$	11.727
Br	K_{α}	11.909
	$K_{\beta 1}$	13.292

Advantages of ICP-MS

A major advantage of ICP-MS for RoHS applications is its multi-element capability which enables it to determine a full suite of elements including mercury. This eliminates the need for a peripheral technique such as cold vapor atomic absorption (CVAA) for ICP-optical emission spectroscopy (OES). Antimony (Sb) and arsenic (As) are not currently listed in RoHS/ELV, but these elements are listed along with beryllium (Be) and selenium (Se) in the Green Procurement Guidelines issued by JIG (Joint Industry Guideline) [4] prepared jointly by the industry groups in Japan, the United States and the EU. ICP-MS allows the determination and quantification of all elements specified in current directives and guidelines as well as impurity elements which provide valuable information on the content of the sample.

Another advantage of the technique is its sensitivity. The RoHS/ELV maximum allowable concentration is 100 ppm (Cd) and 1000 ppm (Pb, Cr, Hg). Some manufacturers set specific requirements at, for example, 1/100 or 1/1000 of the RoHS/WEE

threshold which requires determination at lower than the 1–10 ppm level. Because ICP-MS is significantly more sensitive than ICP-OES or AAS, only 1/10–1/100 of the sample amount is required for ICP-MS. This reduces the time required for sample preparation and allows small sample volumes to be analyzed. This is an advantage if the sample itself is very small or the sample is a high value part, such as a noble metal. Further benefits of the simplified sample preparation procedure arise from the reduced volume of acid that is required to digest the sample and that needs to be disposed of at the end of the analysis.

ICP-MS also provides the possibility of employing isotope dilution mass spectrometry (IDMS) as a high caliber reference calibration technique for more accurate quantitative analysis. IDMS involves spiking samples before the dissolution process, which allows accurate calculation of sample preparation recovery.

Conclusions

The ICP-MS method developed at Nihon Environmental Services Co., Ltd. using the 7500c ORS is capable of measuring the four metals regulated by the RoHS/ELV directives efficiently, as well as the 10 heavy metals specified in the guidelines currently prepared jointly by the industries concerned in Japan, the United States and the EU.

To assure the quality of the data acquired according to the RoHS/ELV directives, it is desirable to have reliable third parties perform the same measurements to ensure that the results will be commercially acceptable worldwide. Nihon Environmental Services is ISO9001 accredited and conducts method development according to ISO management. The company also obtained laboratory accreditation (ISO/IEC17025) from the Japan Accreditation Board for Conformity Assessment (JAB) for the measurement of cadmium according to the EN1122 method, which employs ICP-MS as the determination method. IEC TC111 will also include ICP-MS. This experience provides further confidence in the ICP-MS method as applied to the RoHS/ELV directives.

References

1. BSEN1122:2001 “Plastics - Determination of cadmium - Wet decomposition method” (Japanese Standards Association)
2. US EPA SW-846 Method 3052,
<http://www.epa.gov/SW-846/pdfs/3052.pdf>
3. Results Proficiency Test Cadmium and Lead in Plastics October 2004. For more information contact: masahiko_endo@agilent.com
4. Guideline for Standardization of Material Declaration by Japan Electronics and Information Technology Association (JEITA JGPSSI),
<http://home.jeita.or.jp/eps/green2.htm>

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem/icpms.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
January 30, 2006
5989-3574EN



Agilent Technologies



Analysis of Electroceramics by Laser Ablation ICP-MS

Application

Semiconductor

Author

Masahiro Oishi and Keiichi Fukuda
Materials Analysis Center
Technology Group
TDK Corporation,
Japan

Abstract

TDK is one of the leading electronic component manufacturers supporting the advance of cell phones, personal computers, and car electronics. As the electroceramic chip parts used in these devices become smaller, thinner, and lighter, new analytical methodology is needed to meet the demand for faster, more sensitive methods of quantitative analysis of solid materials. In addition, environmental regulations are expected to become increasingly stringent, which will impact on the need for reliable methods for the trace analysis of solids. To meet these challenges, researchers at TDK have developed a method based on laser ablation inductively coupled plasma mass spectrometry which offers simultaneous quantitative analysis of major and minor elements with high sensitivity, spatial resolution of 10 μm , robustness, and rapid analysis. The results are based on a new normalization method which can compensate for the sample introduction rate differences between samples or between different sites. The technique is applicable to the simultaneous analysis of major, minor, and trace elements in electroceramics as well as other sample types in other industry sectors.

Introduction

All ceramics, including electroceramics, can be defined as polycrystalline nonmetallic materials. By using precisely controlled compositions and additives, their unique electrical (dielectric, piezoelectric), optical, and magnetic properties can be optimized for use in many key technologies such as communications, electronics, and automation. For example, dielectric materials are used in chip capacitors, whereas magnetic materials are used in transformer coils using ferrite, chip beads, and other components.

Currently, there is a drive to make electroceramics lighter and more compact, and to achieve thinner packages, higher compositeness, and lower levels of power consumption [1]. For instance, ceramic capacitors are one form of electroceramics that are in high demand. They were initially comprised of a single layer, but with developments in multilayering and chip technology, larger capacity and more compact capacitors are now widely used. The ability to make multilayer ceramic chip capacitors smaller, lighter, and thinner has contributed greatly to the propagation of mobile devices such as cellular telephones. As these materials continue to become smaller and thinner, there is an increased need to conduct composition analysis at lower limits of detection (LOD).

Furthermore, the need for fast, high-sensitivity analysis is not restricted to the production and processing industry. Electroceramics are used



Agilent Technologies

primarily in electrical and electronic devices, and in recent years, environment-related regulations pertaining to electrical and electronic devices have grown increasingly stringent worldwide. Two new environmental regulations that will take effect in the European Union (EU) in 2006 are the directive on Waste Electrical and Electronic Equipment (WEEE) and Restriction on the Use of Certain Hazardous Substances (RoHS). The WEEE directive is associated with the disposal of waste electrical and electronic equipment; while RoHS, restricts the use of certain hazardous substances present in electrical and electronic equipment. The proposal for the RoHS directive will prohibit the use of mercury, cadmium, lead, hexavalent chromium, and other toxic substances from electrical and electronic equipment. Also, in Japan there are pressures on the electronics industry to eliminate lead and to restrict the use of other toxic substances.

In this application note, laser ablation inductively coupled plasma mass spectrometry (LA-ICP-MS) was used to analyze electroceramics. A method was developed that enables rapid, convenient, and highly sensitive compositional analysis. Further details were described in a previous report [2].

Inorganic Analysis of Electroceramics

The techniques generally used for the inorganic analysis of electroceramics are X-ray fluorescence (XRF), inductively coupled plasma atomic emission spectroscopy (ICP-AES), or inductively coupled plasma mass spectrometry (ICP-MS). Inorganic analysis of micro portions is generally performed using an electron probe micro-analyzer (EPMA) or an energy dispersive X-ray analyzer attached to a scanning electron microscope.

The XRF enables convenient analysis of major elements and minor components. XRF measurement targets include bulk, particle, and thin film samples. The technique is extremely effective in characterizing unknown samples; however, conducting high-sensitivity analysis requires a larger measurement diameter and is relatively slow. When measurements are required at lower LODs than is possible via XRF analysis, the sample is usually dissolved using acid, or fused with alkali and then dissolved and analyzed using ICP-AES or ICP-MS. Drawbacks associated with these methods include: the additional time required for sample dissolution, the risk of sample contamination during sample preparation, and the fact that “local” analysis of solids is not possible. In many cases, microfield analysis, EPMA, which has an element

mapping function, is used. However, EPMA requires some sample preparation, and because the sample chamber is contained within a vacuum, time is required before measurements can be performed. In addition, analysis cannot be performed at a sufficiently high level of sensitivity, with typical detection limits (DL) at ppm levels.

Thus, conventional methods of analysis have fallen short of the mark with regard to speed, convenience, sensitivity, dynamic range, and microfield analysis. In contrast, LA-ICP-MS enables local analysis of solid samples while maintaining the high sensitivity of ICP-MS. ICP-MS also offers a wide linear dynamic range. For example, the working analytical range of the Agilent 7500 ICP-MS extends to nine orders with very high sensitivity. In addition, the detection circuit used in the 7500 Series ICP-MS means acquisition speed is not compromised when analyzing higher concentration elements and ensures that transient signals from a laser ablation pulse can be measured over such a wide dynamic range. This is a key advantage in the determination of trace and major elements in inclusions, where the analyte signal is very short-lived, and analyte concentrations vary widely.

This report summarizes investigations into the possibility of applying a new LA-ICP-MS method to compositional and impurities analysis of electroceramics.

Analysis Using Laser Ablation ICP-MS

Evaluation of LA-ICP-MS

LA-ICP-MS is widely used to determine inorganic elements in solid samples. A laser is used to irradiate the solid sample and to generate microparticles. The particles are carried on a steady gas stream to the ICP-MS, where the sample is ionized and measured. Thus, solid samples can be analyzed directly without preprocessing, and element analysis can be performed at a high level of sensitivity. LA-ICP-MS is often used as a means of qualitative analysis, although it is also used in quantitative analysis. Typical applications include the determination of trace elements in iron [3] and the characterization of geological samples [4, 5, 6]. At the same time, however, the elements involved in these analyses are trace components, and few studies have been conducted on assays that included everything from principal to trace components.

Advantages of the technique include:

- Measurement speed: There is no need to draw the sample chamber into a vacuum, so sample measurements can be carried out rapidly.
- High sensitivity and wide dynamic range: Gases and micro-particles generated by laser ablation are introduced directly into the ICP-MS for measurement, enabling high-sensitivity analysis. Moreover, the ICP-MS has a wide dynamic range, enabling a broad spectrum of analysis ranging from principal component elements to impurity elements.
- Local analysis is possible: The laser beam is narrow and a charged coupled device (CCD) camera can be attached, enabling local analysis of specific subsections of the sample.
- Changing the analysis field: The area being analyzed can be modified by changing the diameter of the laser beam.
- Analyzing a wide range of samples: Almost any sample can be fused and ablated using the fourth higher harmonic (266 nm) or fifth higher harmonic (213 nm) of an Nd:YAG laser, or using an excimer laser (193 nm).
- Measuring samples of various shapes: Bulk, particle, thin film and other types of samples can be measured. However, a smoother sample field, that has no bumps or projections, achieves more stable results.

Some disadvantages include:

- Problems with stability: The efficiency with which samples can be introduced varies for each sample, so analysis values are sometimes not stable.
- Quantitative analysis is difficult: Quantitative analysis of solutions by ICP-MS is carried out using a method of calibration that uses external standards or standard addition. However, in the case of LA-ICP-MS, internal standards are difficult to add to solid materials. The internal standardization can be used if there are principal component elements for which the concentrations are already known, but then the method cannot be applied in all types of analysis.

Semiquantitative Analysis

Because quantitative analysis using external standards is difficult via LA-ICP-MS, generally the concentration conversion coefficient is calculated separately for each element being measured, and semiquantitative analysis is performed. In this case, either National Institute of Science and

Technology (NIST) 611, 612, 613, or 614 glass, which contains multi-elements, or a manufactured standard that is similar to the material being tested, is used for calculating the concentration conversion coefficient (k). If NIST glass is used, the concentration conversion coefficients of the various elements contained in the NIST glass are calculated ahead of time. Then the actual test sample is analyzed and the semiquantitative values for the actual test sample are determined from the data obtained using the concentration conversion coefficients. However, when NIST glass is used, the sample introduction efficiency is different for the material being measured, in many cases. This increases the error in the semiquantitative values. When a standard sample that is similar to the material being tested is used as the standard sample, there are also problems such as the sample introduction efficiency being different depending on the location being analyzed.

Given these challenges with the semiquantitative analysis of electroceramics, we developed a method in which the semiquantitative values are standardized in order to suppress fluctuation of the sample introduction efficiency. Moreover, in order to reduce the error of the semiquantitative values, a solid reference sample was used that was similar to the material being measured. To carry out standardization, however, it was necessary to measure all of the elements and determine the semiquantitative values. In other words, it was necessary to calculate the concentration conversion coefficients (k) for all of the elements. Because the solid reference sample contained only some of the components of the electroceramic, it was not possible to calculate the concentration conversion coefficients (k) for all of the elements. In this case, a concentration conversion coefficient (k-aqua) was calculated by measuring the SPEX multi-element standard solution (XSTC-1, 7, 8, 13). This value was then corrected to take account of the element being present in the solid rather than in solution, to give a k-aqua* value. The k-aqua* values were used as the concentration conversion coefficient (k) for the calculations.

The procedure for semiquantitative analysis of the electroceramic test sample is described below:

1. Using pneumatic nebulization, aqueous standards containing SPEX XSTC-1,7,8,13 were measured over the entire mass range (m/z 2 to 260 amu).
2. Semiquantitative factors (SF) were calculated for the elements in the aqueous standard.
3. Using LA-ICP-MS a solid standard was measured across the entire mass range (m/z = 2–260).

4. For those elements where the concentration is known, semiquantitative factors (SF) were calculated in the solid standard.
5. For those elements that occur in both the aqueous and solid standard and for which SF values were calculated, the coefficient (k) was generated.
6. The k coefficient can be used to convert SF values obtained using the aqueous standard into those useful for solid standards (SF obtained by pneumatic nebulization ICP-MS) $\times$ (coefficient (k)). This way, SF values of elements that are not in the solid standard could be generated.
7. The concentration conversion values for all elements were converted to the equivalent oxide.
8. Using the sum of the oxide conversion values of the detected elements, standardization was performed, and the standardized semiquantitative values were determined. For an example of semiquant factor calculations see Table 2.

Oxide conversion was carried out at this time because electroceramics are primarily oxides.

Table 2. Semiquant (SQ) Factor Calculation

Case 1

	SQ Factor of LA	SQ Factor of nebulizer	
Fe	100	200	
Co	?	1000	
Ni	2000	4000	
Coefficient (k) of Fe is 100/200			= 0.5
Coefficient (k) of Ni is 2000/4000			= 0.5
Coefficient (k) of Fe and Ni is same			
Co SQ factor is 1000 $\times$ 0.5			= 500

Case 2

	SQ Factor of LA	SQ Factor of nebulizer	
Fe	100	200	
Co	?	1000	
Ni	3000	4000	
Cu	?	2000	
Zn	4000	4000	
Coefficient (k) of Fe is 100/200			= 0.5
Coefficient (k) of Ni is 3000/4000			= 0.75
Coefficient (k) of Zn is 4000/4000			= 1.0
Co SQ factor is 1000 $\times$ ((0.5 + 0.75)/2)			= 625
Cu SQ factor is 2000 $\times$ ((0.75 + 1.0)/2)			= 1750

Using the above method results in the following advantages:

- Elements not contained in the solid reference sample can be measured.
- Standardization processing makes it possible to correct the sample introduction efficiency between samples, or for each of the measurements, thus minimizing disparities and offset from the true values.

Using this method of analysis, we investigated the possibilities of semiquantitative analysis of an area measuring several mm² on a ferrite bulk sample. In addition, we attempted analysis of a spot on a barium titanium oxide (BaTiO₃) disk, to determine whether we could apply this method of analysis to local analysis of an area measuring several tens of μm^2 .

Semiquantitative Analysis of Ferrite Bulk Samples

Ferrite is a typical magnetic material for electroceramics, and is used for a wide range of components, from bulk-shaped parts such as transformer coils and deflecting yoke coils to chip-shaped parts such as chip beads. Two types of ferrite samples with different compositions were used. The samples were manufactured in-house and measured 2.0 cm in length, 1.0 cm in width, and 0.5 cm in height. For a solid reference sample, we used a nickel-copper-zinc (NiCuZn) ferrite sample, and calculated the concentration conversion coefficient. Table 1 shows the measurement conditions used in the test. A 100- μm beam diameter at 2 mJ output energy and repetition rate of 10 Hz was used. The measurement was carried out over the entire mass range ($m/z = 2 \sim 260$), and the integration time for the various masses was set at 0.05 s, with measurements being performed three times. To compare the analysis values, the same sample was analyzed using XRF. The results measured using the LA-ICP-MS for the two types of ferrite samples are shown in Figures 1 and 2 respectively.

There was excellent agreement between the principal composition and the reference values

Table 1. Laser Ablation and ICP-MS Conditions**Laser ablation**

New Wave Research LUV266X

Wavelength: 266 nm

Pulse frequency: 10 Hz

Laser energy: 2 mJ for Ferrite

Ablation pattern: Raster, 100- μ m spot diameter for Ferrite,Scan speed: 50 μ m/s for Ferrite

Laser warm-up: 10 s

ICP-MS

Agilent 7500s



RF power: 1200 W

Carrier gas: 1.15 L/min

Plasma gas: 16.0 L/min

Number of masses: $m/z = 2$ to 260

Integration time: 0.05 s

**Figure 1. Comparison of results of semiquantitative analysis using LA-ICP-MS and XRF analysis conducted on ferrite sample A.****Figure 2. Comparison of results of semiquantitative analysis using LA-ICP-MS and XRF analysis conducted on ferrite sample B.**

obtained via XRF, with variations of only several percent. Even for the trace components, the difference from the reference value was within 10%. The disparity among the three measurements was approximately 5% to 10% for the bulk elements, and approximately 20% for the trace elements. Using this analysis method, it was possible to suppress the fluctuation in the sample introduction efficiency that is peculiar to LA-ICP-MS. Table 3 shows the analysis values for all of the elements detected with the LA-ICP-MS measurement of ferrite sample A.

Table 3. A Comparison of the Principal Components and Trace Element Concentrations (wt %) of Ferrite Sample A with the Concentrations Obtained from XRF (The % RSD for the LA-ICP-MS Indicates the RSD for the Three Measurements)

Elements	XRF	LA-ICP-MS	
	Reference value	Mean	%RSD
MgO	0.27	0.26	11.0
Al ₂ O ₃	0.16	0.16	9.7
SiO ₂	0.076	0.076	10.1
Cr ₂ O ₃	0.030	0.031	4.1
MnO	0.30	0.28	0.8
Fe ₂ O ₃	66.0	66.0	0.5
CoO	*	0.004	3.1
NiO	13.8	13.6	2.8
CuO	4.2	4.1	0.8
ZnO	15.1	15.5	2.3
Y ₂ O ₃	*	0.00004	18.9
ZrO ₂	*	0.001	20.8
Nb ₂ O ₅	*	0.003	6.5
MoO ₃	*	0.004	8.6
In ₂ O ₃	*	0.00004	8.1
SnO ₂	*	0.004	14.7
Sb ₂ O ₃	*	0.0002	17.0
BaO	*	0.001	15.6
WO ₃	*	0.0004	4.1
Bi ₂ O ₃	*	0.0001	11.7

* Not detectable

Trace components, such as V₂O₅, Y₂O₃, ZrO₂, MoO₃, Sb₂O₃, BaO, WO₃, and Bi₂O₃, which could not be detected with XRF, could be measured using the LA-ICP-MS. Heavy elements could also be measured and have sub-ppm DLs. Although not included in our samples, the technique offers good DLs for cadmium, lead, mercury and other elements which will be targeted by the RoHS directive, so the proposed method will be effective in the analysis of toxic metals.

The time required for analysis was 40 seconds per measurement, and the total time for the three repetitions, including the time spent changing the samples, was approximately 5 minutes. Moreover, no sample preparation was carried out when the measurements were taken. In our opinion, this semi-quantitative LA-ICP-MS method satisfies the requirements for electroceramics analysis in terms of speed, convenience, and high sensitivity.

Semiquantitative Analysis of Spots on a BaTiO₃ disk

Next, we investigated whether the technique could be applied to feature (local) analysis of a dielectric material. A 1-cm diameter BaTiO₃ disk, manufactured in-house, was used. BaTiO₃ is a major component of chip capacitors. Depending on the elements added to BaTiO₃, the baking conditions, and other parameters, black spots sometimes appear on the surface during manufacture. The LA-ICP-MS quantitative technique described above was used to characterize both these spots and normal areas on the BaTiO₃ disk. The following laser conditions were used in this measurement: beam diameter of 10 μm at 10 Hz and 0.02 mJ. In addition, for comparison purposes, we analyzed the entire disk using XRF. The results are shown in Figure 3.




Figure 3. A comparison of results obtained using the LA-ICP-MS for semiquantitative analysis of areas of the BaTiO₃ disk with no spots and areas with spots, compared with the results obtained using XRF analysis.

The calculated semiquantitative values for the normal areas of the BaTiO₃ disk using LA-ICP-MS were approximately equal to the results for the disk as a whole, as obtained using XRF. Analysis of the black spots (an area of several micrometers) on the BaTiO₃ disk indicated significant disparities in the amounts of MgO, MnO and Y₂O₃. Figure 3 illustrates the analysis of the spots compared to the normal areas of the BaTiO₃ disk. It is thought that the spots on the BaTiO₃ disk were caused by aggregation of

MgO, MnO, and Y₂O₃. Figures 4 and 5 show a CCD image of the BaTiO₃ disk before and after LA-ICP-MS analysis, and, as the photographs illustrate, there was very little damage to the sample with the laser diameter set at 10 μ m.

As described above, our analyses indicate that the LA-ICP-MS method of semiquantitative analysis is effective as a means of local analysis of areas measuring several tens of micrometers in diameter.



Figure 4. CCD image of the BaTiO₃ disk prior to laser irradiation.



Figure 5. CCD image of the BaTiO₃ disk after laser irradiation showing minimal damage (laser diameter was 10 μ m).

Conclusions

Not only are electroceramics becoming smaller and more heavily layered, but the boards themselves are becoming more hybridized as capacitors and magnetic elements begin to share space on the same board. To keep apace with these developments, methodology for the trace analysis of impurities will continue to evolve. In addition, environmental regulations are expected to become increasingly stringent, which will impact on the need for reliable methods for the trace analysis of solids. Therefore, the demand for newer, faster, and more convenient methods of semiquantitative analysis, such as the LA-ICP-MS technique discussed in this application note, will continue to grow.

Using concentration conversion coefficients obtained from an aqueous standard and solid reference samples and by measuring all of the elements, we found that LA-ICP-MS provides an effective technique for rapid semiquantitative analysis. The technique can be applied to measurements across a wide dynamic range from bulk to trace components of materials. Furthermore, this method is not limited to electroceramics and can be applied to various other materials and substances.

References

- 1 TDK Product Hotline Magazine, **34**, (2000).
2. M. Oishi and K. Fukuda, (2003) *J. Mass Spectrom. Soc. Jpn.*, **51**, 220.
3. A. J. Campbell and M. Humayun, (1999) *Analytical Chemistry*, **71**, 939 .
4. M. D. Norman, N. J. Pearson, A. Sharma, W. L. Griffin, (1996) *Geostandard Newsletter*, **20**, 247.
5. J. S. Becker, H. J. Dietze, *Fresenius J. Anal. Chem.*, **365**, 429 (1999).
6. H. Bratz and R. Klemm, "Analysis of Rare Earth Elements in Geological Samples by Laser Ablation ICP-MS", Agilent Technologies, publication 5988-6305EN, www.agilent.com/chem/icpms.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem/icpms.

For more information about semiconductor measurement capabilities, go to www.agilent.com/chem/semicon.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
April 8, 2004
5989-0321EN






Productivity Tools

Applications

- > Return to Table of Contents
- > Search entire document



Integrated Second Peristaltic Pump for Improved Sample Throughput and Reduced Matrix Effects

Technical Overview

Introduction

As a simpler, less expensive alternative to Agilent's Integrated Sample Introduction System (ISIS), the Second Peripump Option permits both rapid sample uptake and constant flow nebulization for improved throughput and matrix tolerance and is fully compatible with all the most recent hardware and software improvements on the 7500 Series ICP-MS.

Uncoupling Sample Uptake from Sample Nebulization

With the introduction of its ISIS in 1999, Agilent pioneered the use of constant flow nebulization in ICP-MS. By uncoupling the sample uptake rate (using a separate, high-capacity peristaltic pump) from the nebulizer flow rate (using a small, close-coupled peristaltic pump), very high sample throughput could be achieved without the concurrent overloading of the sample introduction system and plasma. Total matrix load on the plasma could be reduced by a factor of 5x or more over a conventional single pump system with the added benefit of significantly higher sample throughput. While ISIS supported many other functions, including autodilution and matrix elimination, for many users, constant flow nebulization was the primary advantage.

Second Peristaltic Pump Option

Based on the input of dozens of ISIS users, Agilent decided to introduce a simplified, more economical solution for rapid sample uptake and constant flow nebulization: a computer-controlled second peristaltic pump that is fully compatible with recent software and hardware enhancements to improve matrix tolerance and productivity.

The second peristaltic pump option works seamlessly with both Pre-emptive and Intelligent Rinse functions, as well as with the new High Matrix Sample Introduction (HMI) accessory. The result is simple, fully integrated, high sample throughput for even the most difficult samples, with no danger of plasma overloading or sample carryover.




Figure 1. Schematic of the second peristaltic pump arrangement.



Figure 2. The second peristaltic pump option allows completely independent control of both the sample uptake pump (left) and the nebulizer pump (right) and fully supports all intelligent and pre-emptive rinse functions.

Operation of the second peristaltic pump is simple and fully controlled by the ChemStation software. The second peristaltic pump is used to rapidly pull the sample to the Tee shown on Figure 1. After the sample reaches the Tee, the nebulizer pump transports it to the nebulizer at a constant flow, without the need to alter the pump speed. This constant flow eliminates extended stabilization time and the introduction of excessive sample into the plasma, interface, and mass spectrometer.

The ChemStation pre-emptive rinse feature will move the autosampler probe to the rinse station to begin cleaning the probe and sample line while the nebulizer pump delivers the remaining sample to complete the analysis. In addition, Intelligent Rinse will ensure that rinse time is sufficient by monitoring up to 10 predefined element signals, but avoid excessive rinse times when they are not needed (for example, after a blank). A significant advantage to this system is that high throughput is accomplished without the need to use a six-port valve or additional vacuum pumps.

Ordering Information

Order Agilent product number G3146B to add a second three-channel peristaltic pump integrated into the mainframe. ISIS tubing kit G3138-65006 is recommended with G3146B. It is preconfigured for easy set up. Please note that G3146B is not compatible with G3148B (ISIS).

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
April 30, 2008
5989-8543EN



Agilent Technologies

Eliminate the Dilution Step from ICP-MS Sample Prep with the Agilent High Matrix Introduction System

Introduction

Agilent has developed the High Matrix Introduction (HMI) accessory for ICP-MS as an alternative to conventional dilution. The HMI modifies the sample introduction system of the Agilent 7500 Octopole Reaction System (ORS) ICP-MS, making it possible to directly measure sample solutions with total dissolved solids (TDS) exceeding 1%.

Analytical Challenges

Analysts at TestAmerica Savannah labs in the USA tested the HMI for the analysis of soil and Toxicity Characteristic Leaching Procedure (TCLP) samples. For ICP-MS analysis in the Savannah Labs, these types of samples are typically diluted by a factor of 1:5 for liquids and 1:10 for soils. The dilution steps reduce the matrix effects contributed by both the acids used in the preparation and the samples themselves. There are several disadvantages associated with this practice:

- Possibility of introducing contamination from the pipette tips or the diluent
- Chance of "human" error of simply preparing an inaccurate dilution
- Sample prep time and cost of reagents
- Increased waste disposal volume

HMI Methodology

With the HMI unit installed on the 7500ce, TestAmerica analysts are now able to introduce most typical environmental samples to the ICP-MS directly, without a dilution step, and thus eliminate the disadvantages associated with conventional dilution.

High Acid Matrices

A significant hurdle to running undiluted environmental samples is related to the final acid concentration specified in USEPA method 3050B for soils and wastes using the "hot-plate" procedure, which includes 10% HCl. Method 3010A for liquids specifies a final concentration of 5% HCl. Prior to using the HMI, matrix matching during the dilution step was used to reduce and normalize the acid concentration in standards and both types of samples. Not only does the HMI eliminate the matrix effects from varying acid concentrations, it also removes the need for expensive platinum cones when analyzing high acid concentrations. TestAmerica now uses 5% HNO₃ /5% HCl for standards and blanks with all sample types run using HMI.

The HMI was set-up for typical "ultra-robust" analysis. Table 1 shows comparison Method Detection Limit (MDL) data (mg/kg) for soils with and without the HMI. With the HMI, the digestates were analyzed directly (undiluted); without the HMI, the digestates were diluted 1/10. The results highlight an improvement in MDLs for the majority of elements when the HMI is used.

Element (Mass)	HMI	w/o HMI
	MDL	MDL (1/10 dil.)
	mg/kg	mg/kg
Al (27)	4.1	5.8
Sb (121)	0.026	0.031
As (75)	0.03	0.15
Ba (137)	0.053	0.17
Be (9)	0.021	0.018
B (11)	0.33	1.3
Cd (111)	0.029	0.031
Ca (40)	5.7	8.4
Cr (52)	0.031	0.13
Co (59)	0.0064	0.0094
Cu (63)	0.078	0.14
Fe (56)	1.7	4.6
Pb (208)	0.055	0.03
Mg (24)	1.3	1.9
Mn (55)	0.037	0.11
Mo (95)	0.036	0.058
Ni (60)	0.024	0.036
K (39)	3.8	6.5
Se (78)	0.13	0.044
Ag (107)	0.005	0.0071
Na (23)	1.8	15
Sr (88)	0.051	0.066
Tl (205)	0.026	0.015
Sn (118)	0.105	0.24
Ti (47)	0.17	0.12
V (51)	0.041	0.096
Zn (66)	0.84	0.64

Table 1. Comparison of MDL for a suite of elements using HMI and normal dilution.

Conclusions

The addition of the High Matrix Introduction system to the Agilent 7500ce ICP-MS allows the analysis of soils without the complications of a dilution step and with slightly improved Method Detection Limits (MDL). This ensures that soils analyzed according to USEPA methodologies can now be done so with significantly improved productivity and reduced costs.


Acknowledgements

Cliff Eaton & Ernie Walton, TestAmerica Inc. Savannah, Ga., USA

More Information www.agilent.com/chem/hmi



Retention Time Locking with the MSD Productivity ChemStation



Technical Overview

Introduction

A retention time is the fundamental qualitative measurement of chromatography. Most peak identification is performed by comparing the retention time of the unknown peak to that of a standard. It is much easier to identify peaks and validate methods if there is no variation in the retention time of each analyte.

However, shifts in retention time occur frequently. Routine maintenance procedures such as column trimming alter retention times. In a multi-instrument laboratory running duplicate methods, the retention times for each instrument will differ from each other, even when run under nominally identical conditions. These differences in retention times mean that each instrument must have a separate calibration and integration event table, making it time-consuming to transfer methods from one instrument to another. Differences in retention time also complicate comparison of data between instruments over time.

What Is Retention Time Locking?

Retention time locking (RTL) allows a close match of retention times on one Agilent Technologies GC/MSD or GC system to those on another like system with the same nominal column. By making an adjustment to the inlet pressure, the retention times on one system can be closely matched to those on another system using the same nominal column. The ability to very closely match retention times from one system to another can greatly reduce the time it takes to develop and transfer methods. “RTLocked” methods can also compensate for degradations in chromatographic perfor-

mance. The ability to correct for degrading chromatographic performance, optimize lab resources, and still provide the correct answer saves time, money, and results in significant productivity gains.

Using GC/MS, it is also possible to screen samples for the presence of target compounds using a mass spectral database of RTL spectra. The RTL mass spectral database provides additional confirmatory information in spite of changes to the chromatographic system. One such database is the G1672AA Pesticide RTL Library. This database allows for quick and easy screening of pesticide samples.

When Should I Lock My Methods?

Locking or relocking your methods should be done whenever you make any changes to the chromatographic system or move methods from one system to another (GC or GC/MS). To establish and maintain a locked method, RTL should be performed whenever:

- The column is changed or trimmed
- The method is installed on a new instrument
- A detector of different outlet pressure is used (GC vs. MS)
- System performance is validated
- Troubleshooting chromatographic problems

How Does It Work?

The process of RTL is to determine what adjustment in inlet pressure is necessary to achieve the



Agilent Technologies

desired match in retention times. To lock a given method for the first time or for the reasons above, you must first develop a Retention Time vs. Pressure (RT vs. P) calibration curve. Using an established method, multiple (five) injections of the standard are used to calculate the retention times at predefined inlet pressures. The use of an automatic sampler simplifies this process. The RT vs. P calibration data for each of the five injections are saved and used to correct locked methods.

The five defined pressures are:

- Target pressure -20%
- Target pressure -10%
- Target pressure (nominal method pressure)
- Target pressure +10%
- Target pressure +20%

Even when using columns with the same part number (same id, stationary phase type, phase ratio, and same nominal length), separate and different locking calibration curves may be needed. Other examples of when separate locking calibration curves are required include:

- Systems with different column outlet pressures (MSD/vacuum, FID/atmospheric)
- Columns differing from the “nominal” length by more than 15% (for example, due to trimming)
- Systems where the predicted locking pressure falls outside the range of the current calibration

Selecting the Standard Compound for RTLocking

A specific compound (usually one found in the normal method calibration standard) must be

chosen and then used for both developing the locking calibration and locking all future systems. The compound, or target peak, should be easily identifiable, symmetrical, and should elute in the most critical part of the chromatogram. Compounds that are very polar or subject to degradation should be avoided.

Once the target compound has been chosen and all other chromatographic parameters of the method have been determined, the five calibration runs are performed. The resulting RT vs. P calibration curve data are saved. The software is then used to select and integrate the peak used for locking.

Creating an RTL Method

The following is an overview of the actual steps taken to acquire the RT vs. P calibration curve data, selecting the compound/peak to use and locking the method.

Acquiring the RTLock Data

From **Instrument Control**, select the **Instrument** menu and

Acquire RTLock Calibration

Data.... Agilent Technologies GCs are the only ones supported. See Figure 1.

If you are using an automatic sampler, the five sample injections will be made automatically. This example illustrates how RTL works on a GC/MS system. Upon completion of the five-sample analysis, Data Analysis will begin and display the nominal MS total ion chromatogram (TIC). If the system was configured as a stand-alone GC, all five chromatograms will be displayed. From these displays, you will select the compound that will be used for RTLocking of the method.

Selecting the RTLock Compound

Use the mouse to select the compound or peak that you would like used for locking. For GC-only mode, you must select one peak from each of the five chromatograms for RTLocking. Once you have made your selection, you will be asked to allow the software to automatically find the remaining peaks. You may choose to zoom the display for better visibility. See Figure 2.




Figure 1. From instrument control, you select the mode of data acquisition for RTL.




Figure 2. From this panel, the user selects the peak used for RTL. In this example the second peak has been selected. The spectrum of the selected compound is also displayed and is used to confirm the RTL compound.




Figure 3. When the RT vs. P calibration curve equation is calculated, the correlation coefficient is determined for the RTLocked compound in each of the five calibration samples. The resulting coefficient is displayed at each peak. The "nominal," or no change to pressure calibration sample, has a correlation of 1.

Calculating the RTLock Curve and Saving a Method

Once the RTLock compound has been selected, the new RT vs. P curve for each compound will be displayed. To select a new compound and calculate new RT vs. P curves, reset the nominal MSTIC from the **RTLock** menu item. Select a new compound as the RTL compound and from the **RTLock** menu item, select **Calculate New Curve from Selected Peaks**. This will generate new RT vs. P calibration curves. The new RT vs. P calibration curve equation will be displayed on the screen along with the correlation coefficient. Select **Yes** to either create a new, or update an existing, RT vs. P calibration file. See Figure 3.

Next, you can enter the name and retention time of the RTLock compound. See Figure 4 and Figure 5.




Figure 4. Enter or confirm the name of the RTLock compound.




Figure 5. Enter or confirm the retention time of the RTLock compound.

View Current RTLock Method Set-points and Report

RT Pressure (psi)

17.345	12.86
16.940	14.24
16.567	15.82
16.214	17.40
15.895	18.98

OK

- Method name
- Calibration date
- Instrument name
- Operator name
- Status of method (on or off)

- RTLock compound name
- Tabular retention time/pressure calibration table
- Maximum deviation
- RTLock curve equation and correlation coefficient data
- Locked retention time information (file name, acquisition date, instrument name, and operator name)
- Report date




Figure 8. Example RTLock Report

Running an RTLock Method

Once the RTL method is created, you can analyze and process new samples. This requires that you unlock and relock the methods without editing the quantitation calibration data. The following example demonstrates how retention times might change when column maintenance is performed or a method is moved to a new GC/MS system. See Figure 9. Once the method is RTLocked, new samples are analyzed and retention times corrected. See Figure 10.

Unlocking and Relocking a Method

Once a method is locked you may unlock or relock it using the same or different compounds or after additional maintenance. To define a new compound for RTLocking, select **RTLock Setup** from the **View** menu in **Data Analysis**. See Figure 11. The nominal RTLock sample that represents the method you are working on will be displayed. Once again, use the mouse to identify a new RTLock compound.




Figure 9. Overlay of an RTLocked data file (labeled Locked) and the resulting data file after clipping one meter off the column (labeled After Cut).




Figure 10. Offset overlay of RTLocked data file and the RTCorrected datafile show peaks overlapped and corrected for column maintenance.




Figure 11. To define a new compound for RTLocking, select RTLock Setup from the View menu in data analysis.

After selecting the compound to RTLock, from the **RTLock** menu item, select **Calculate New Curve** from **Selected Peaks**. This will generate a new RT vs. P calibration curve. The new RT vs. P calibration curve equation will be displayed on the screen along with the correlation coefficient. Select **Yes** to create a new or update an existing RTLock calibration. See Figure 12. From the RTLock menu you can also:

- View current setpoints
- Calculate the RT vs. P curve
- Restore the original chromatograms
- Report the RTLock calibration
- Unlock the method
- Relock the method

Summary

RTLocking provides an easy and flexible tool that can be used to reduce the time and complexity often associated with routine chromatographic maintenance. It allows methods to be transferred between like GC/MS systems without time-intensive edits to the quant database and reacquisition of standards. It also simplifies the process for executing routine chromatographic maintenance. RTLocking can minimize mistakes and provide a productivity improvement for most applications by reducing the time and setpoint changes required to update a method.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.




Figure 12. RTLock view and menu choices.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2008

Printed in the USA
May 5, 2008
5989-8574EN



Agilent Technologies

Case Study for Agilent Lab Monitor and Diagnostic Software



Application

HPI, Environmental, Food Safety

Author

Chunxiao Wang
Agilent Technologies (Shanghai) Co. Ltd.
412 Ying Lun Road
Waigaoqiao Free Trade Zone
Shanghai 200131
China

Abstract

Agilent Lab Monitor & Diagnostic (LMD) software can monitor in real time all the Agilent GCs and LCs in your lab. It automatically tracks supply usage, monitors chromatographic quality, and notifies you of maintenance needs before a problem occurs by keeping track of injections, hours of operation, and other parameters that you specify. Two case studies are given demonstrating some of the features and benefits of this software.

Introduction

Agilent Lab Monitor & Diagnostic (LMD) software is an innovative tool to help you manage your lab to ensure performance, productivity, and reliability. LMD software can monitor in real time a single Agilent GC or LC or all the Agilent GCs and LCs in your lab. It automatically tracks supply usage, monitors chromatographic quality, and notifies you of maintenance needs before a problem occurs by keeping track of injections, hours of operation, and other parameters that you specify. LMD software “knows” when it's time to replace consumables or perform basic upkeep. It provides full diagnostic

capabilities with an extended list of tests and calibration procedures and automates basic diagnostic routines that help verify proper instrument performance. The software is coupled with an extensive suite of user information Help functions that provide quick, easy access to maintenance information, such as manuals and videos, so that you can get the information you need right when you need it.

LMD provides the following features and benefits:

- Increases your lab's uptime by alerting you to problems before they happen
- Provides intuitive help with diagnostic capabilities and easy-to-follow repair procedures in case of a problem
- Enhances diagnostics and troubleshooting functionality with searchable, complete user information capability
- Keeps your systems in top condition and helps with routine troubleshooting
- Maximizes column and consumables utilization by optimizing replacement schedules
- Helps you meet regulatory requirements by keeping all maintenance, event, and run logs in a single, easily accessible location
- Provides a link to the optional, Web-enabled Remote Advisor to back up your internal service and support resources

The following two case studies demonstrate some of the features and benefits of the Agilent LMD software.



Agilent Technologies

Configuration for Case Studies

- One PC with LMD monitors two Agilent 7890A GCs
- Agilent LMD software (A.01.03, Advanced)
- Firmware (A.01.06)
- ChemStation (B.03.02)

The first case study demonstrates the feature/benefit of right advice/alert by tracking resource counters before results go bad.

Problem

Oxygen is an enemy to most capillary GC columns, especially polar columns. In this study, a polar column is used for analyzing trace oxygenates. The baseline is getting worse after 400 runs because of

septum leakage, which may impact quantitative analysis for trace-level analysis (see Figure 1, upper chromatogram).

Tracking Resource Counters and Giving Alarm Before Results Go Bad

Because LMD is configured to track the GC's inlet septum, it reminds the user to change the septum when the limit has been reached, before the GC baseline goes bad. After the septum is changed, the expected baseline is obtained. Figure 1 shows the baseline of the polar column after 400 runs (top) and after the septum has been changed (bottom).

LMD can track not only the inlet septum, but also other GC resources, like the inlet o-ring, oxygen traps, inlet gold seal, and so on. As Figure 2 shows, LMD gives real-time indicators and alerts of preventive maintenance needs.




Figure 1. Baseline chromatograms on polar column after 400 runs and after the inlet septum has been replaced.




Figure 2. LMD real-time indicators and alerts of preventive maintenance needs.




Figure 3. Alert email for when the front inlet septum limit has been reached.

Four alert actions are available: Set Not Ready, Set Service Due, Email, and Text Message. For example, when the email alert action is selected, LMD will send an alert email to the users you specify. Figure 3 shows an example email alert informing a user that the front inlet septum's limit has been reached.

An email alert is configured in only three steps:

1. Manage the users (see Figure 4)
2. Manage the alerts (see Figure 5)
3. Configure the maintenance indicators




Figure 4. Procedure for managing users.





Figure 5. Procedure for managing alerts.



Procedure

1. Edit parameters and click the icon that allows for selection of diagnostic counters.
2. Select the counters that you want to use within LMD.

Figure 6A. Procedure for configuring maintenance indicators. Set up the resource counter within ChemStation/Workstation.




Figure 6B. Procedure for configuring maintenance indicators. Set up the same counter within LMD.

In this example, a warning email will be sent at 350 injections on the front inlet liner. At 400 injections the GC will be set to "Not Ready," thus stopping the sequence, and an email will be sent to the distribution list that was set up in the previous procedure (see Figure 4).

For the 7890A GC, the resource counters must first be enabled from ChemStation before they will count within LMD (see Figure 6A). Next, the same counters are set up within LMD maintenance indicators (see Figure 6B).

The next case study demonstrates how LMD can provide intuitive help and easy-to-follow procedures in case there is a problem with diagnostic capabilities. It also illustrates how the complete, searchable user information enhances the diagnostic and troubleshooting functionality of LMD.

Problem

The trace level peak was lost or its response reduced on the 7890A GC with FID and capillary column. In this scenario, the response of ethylbenzene is reduced and m-oxylenes is lost, as shown in Figure 8.

Designing Diagnostics and Tests to Solve Specific Problems

This problem may be caused by inlet leakage. The diagnostic tests of the LMD software simplify complex troubleshooting tests for the user by automatically performing specific troubleshooting-related tasks. For example, the inlet leak and inlet decay tests help the user with quick diagnostics, and the FID checkout test helps verify proper performance with convenient guidance. The problem can be fixed efficiently with the intuitive help of LMD.

When an LMD test is running the GC Remote light comes on, indicating control of the GC. At this time, the ChemStation must be closed to run the LMD tests.

1. Run SS inlet 7890A leak check. Result: Failed. The procedures and result are shown in Figure 8.

2. Run SS inlet 7890A pressure decay test to confirm a leakage. Result: Failed. The above tests indicate that there is leakage in the inlet system. The procedures and result are shown in Figure 9.
3. Solve the inlet leak problem by tightening the column fittings, base gold seal fitting, split vent trap housing, septum nut, and the latch to the SSL inlet. Result: These actions don't work.
4. Replace the inlet septum and the liner O-ring. User document search capability makes it easy to find instructions on how to change the consumables, including the inlet septum and liner O-ring. Also, detailed consumable information, including part number, helps you select the right part (see Figure 10).
5. Run the SS inlet pressure decay and leak check tests. Result: Passed. See Figure 11.
6. Run the FID checkout test to confirm that the GC system is operating properly. Before the detector checkout test can run, you have to install the appropriate consumable parts; that is, an evaluation column, HP-5 30 m x 0.32 mm x 0.25 μm (p/n 19091J-413); an FID performance evaluation (checkout) sample (p/n 5188-5372) is also needed. The software will prompt you when you are required to perform a task or answer a question. When the FID detector checkout test is finished, restore the instrument to normal operating conditions. Result: Passed. See Figure 12.
7. Run trace-level aromatic sample. The expected result is obtained as shown in Figure 13 after diagnostics and troubleshooting.
8. The GC system is fixed.




Figure 7. Trace level peak lost or response reduced on 7890GC with FID and capillary column.




Figure 8. Procedure and result for SS inlet leak check test.




Figure 9. Procedure and result for SS inlet pressure decay test.

The screenshot shows a search interface with a search bar containing 'inlet liner' and a 'Go!' button. Below the search bar, there are two main sections of results. The first section, titled 'Maintaining your GC', lists several items, including '100. To Change the Liner and O-Ring on the Split/Splitless Inlet'. The second section, titled 'Replacement O-ring', lists several items, including 'Replacement O-ring (See Consumables and Parts for the Split/Splitless Inlet)'. A table titled 'Table 6 Other consumables and parts for the split/splitless inlet' is also visible, listing various parts and their part numbers. A photograph of the inlet assembly is shown at the bottom right, with a callout indicating 'ROUTE TUBING BY CHANNELS, AVOID SHADED AREAS'.

Procedure

User document search capability gives the instructions:

1. Type "inlet liner," then click **Go for** searching.
2. Select **Maintaining your GC>100.....**, then you can get the instructions.
3. Instructions on how to change the inlet septum and liner O-ring
4. Click **Replacement O-ring** for detailed information on consumables and parts for SS inlet, including part number.

Figure 10. Searchable, complete user information capability allows for enhanced diagnostics and troubleshooting functionality.




Figure 11. The result passed both inlet leak check and pressure decay test after troubleshooting.




Figure 12. The result has passed FID checkout test.




Figure 13. Expected result for trace-level aromatic sample is obtained after troubleshooting with intuitive help from LMD.

Conclusions

Agilent Lab Monitor & Diagnostic (LMD) software is a new tool to help ensure the productivity, performance, and reliability of instruments in the lab. LMD monitors multiple instruments in the lab continuously in real time and detects maintenance needs and instrument problems before a problem occurs. These case studies demonstrated the benefits of Agilent LMD software for customers.

- **Right advice before results go bad**

Real-time instrument monitoring tracks the number of runs or the life of GC resources, such as inlet septa, liners, and o-rings. Then, when the user-specified limit has been reached, LMD generates an Alert Action, for example, it sends an alert email to specified user(s).

- **Intuitive help in case of a problem**

- Diagnostics and tests will help you solve problems and verify proper performance.

- Easy-to-use system tests, including an inlet leak test and inlet decay test, will help you do quick diagnostics.
- A detector checkout test will provide convenient guidance to help you verify proper performance.

- **Extensive user document search capability**

LMD offers easy-to-find and easy-to-use instructions on how to change the consumables, including the inlet septum and liner O-ring, and detailed consumable information, including part numbers, to help you select the right parts.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
May 15, 2008
5989-8613EN



Agilent Technologies



Capillary Flow Technology for GC/MS: A Simple Tee Configuration for Analysis at Trace Concentrations with Rapid Backflushing for Matrix Elimination

Application

Environmental, Drug Testing, and Forensics

Author

Harry Prest
Agilent Technologies Inc.
5301 Stevens Creek Blvd.
Santa Clara, CA 95051
USA

Abstract

Capillary Flow Technology devices offer the potential to enhance GC/MSD operation and robustness. In operation, they can allow rapid service of the GC column and inlet, including liner and septum, without venting or subjecting the MSD to air. In terms of robustness, late eluting compounds can be removed from the column by "backflushing," which forces components to retreat through the column into the injection port before they damage the MSD source or compromise the next analysis. This leads to higher analytical integrity as both the column phase and the MSD can be protected. This application describes a simple arrangement for Capillary Flow Technology devices that provides ventless maintenance features with highly accelerated backflushing and minimal losses in the MSD signal. This solution supports GC analysis in constant flow mode with pressure pulsed injections and is recommended for all MSD users (in both electron impact or chemical ionization modes), including those with diffusion pump systems.

Introduction

The introduction of Electronic Pressure Control (EPC) was a major advance for GC and especially GC/MS analysis. EPC allowed development of the constant flow mode of analysis, which generates

chromatographic peaks of consistent width (time) and allows optimization of MS cycle times to meet either qualitative or quantitative requirements. Also, splitless injections gained pressure pulsing or ramped flow modes, which lowered the analytes' residence time in the hot injection port and confined the expansion of the injection solvent (avoiding overfilling of the liner). The power of this approach led to continued evolution of EPC technology with the present state of the art represented in the new 7890A GC.

The recent addition of Capillary Flow Technology (CFT) devices has reinvigorated and recast Deans switching and other pressure control approaches to GC analysis. One such CFT device, the Quick-Swap [1–3], provides two important capabilities to GC/MS:

- 1) The ability to service and/or replace the entire analytical column or the injection port liner and septum without venting the MSD (yet still retaining high vacuum integrity)
- 2) The ability to remove from the column late-eluting, highly retained components that elute after the target compounds of analytical interest by reversing the carrier flow direction through the column in what is called "backflushing." With the oven temperature elevated and the flow reversed, these very high boiling interferences can be pushed off the column into the split vent and thereby prevent degradation of the column phase or the detector.

A schematic representation of the arrangement that makes this possible is shown in Figure 1.



Agilent Technologies




Figure 1. Schematic of QuickSwap arrangement.

Every new approach has a downside and for QuickSwap it is the additional makeup flow required to purge the QuickSwap device during analysis which dilutes the signal in the GC/MSD. This is not an issue for many users since the sensitivity of the MSD is usually more than adequate. However, analysis at trace concentrations has more stringent requirements and maintaining a signal closely comparable to that of a single continuous column is essential.

Another CFT configuration for GC/MSD applications designed specifically for trace GC/MS analysis where customers do not wish to surrender signal is possible using the QuickSwap or any of several other CFT devices. In this alternate configuration, the CFT device is located in the middle of the analytical column, essentially splitting the column in half. For example, a 15-m column precedes and follows a CFT tee. Schematically this arrangement is illustrated in Figure 2. The auxiliary EPC device adds just enough pressure (flow) to match the flow (pressure) from the first column, so there is little flow addition and therefore less “dilution” and loss in the GC/MSD signal. Backflushing is similarly simple; the pressure or flow is dropped in the first column section while the second section column flow is increased.

Advantages of this pressure controlled tee (PCT) approach are similar to those of QuickSwap, such as:

- Service of injection port liner and septum without venting the MSD
- Column cutback or replacement of the “front” or first column without venting the MSD

But additional advantages of the PCT arrangement over QuickSwap are:

- Minimal or no signal loss (in EI- or CI-MS) is obtained because of the very small additional “makeup” gas flow.
- Constant flow mode and pressure pulsed injections are straightforward.
- This configuration is suitable for diffusion pumped systems and allows backflushing in diffusion pumped systems.
- Backflushing is more rapid and can be initiated earlier.

This application details some configurations and provides an example of backflushing.

cages to avoid the extra cage.) Using a Vespel/graphite ferrule, one end was connected to the back injection port and the other end to the lowest connection of the CFT device with a SilTite ferrule and nut. The other two CFT tee connections were sealed with CFT blanking plugs and the back injection port was pressure tested as described in the 7890A *Advanced User Guide* (part number G3430-90015).

One of the 15-m columns was then hung on the cage carrying the 1-m column and installed with one end through the MSD transfer line. Since this column (column #2) can be expected to have a rather long life as it will be protected by the upstream column, a SilTite ferrule is recommended for the transfer-line seal. These ferrules do not develop leaks as the transfer-line temperature is cycled; however, the Vespel/graphite ferrules can shrink and develop leaks. (Note that if the surface of the transfer line is very worn it may fail to seal well, in which case the Restek *Agilent interface cleaner* [P/N 113450] can be used to resurface the sealing surface if very carefully employed). The

other end of this GC column was connected to the uppermost connection on the CFT tee with the SilTite ferrule.

The “upstream” 15-m GC column (column #1) was hung on the other 15-m column cage and installed in the front split/splitless injection port with a Vespel/graphite ferrule, liner, and BTO septum, as usual. The other end was connected to the CFT tee middle post and, after temporarily removing the other connected columns, blanked off and pressure tested as above.

All connections were then re-established to the CFT tee with the 1-m column in the lower position; the front, first column (#1) connected in the middle position; and the rear, second or MSD column (#2) in the uppermost connection. Helium was supplied to both the front and back ports, and a helium leak detector was used to check for any leaks.

A picture of the arrangement is shown in Figure 3.




Figure 3. Picture of the installed pressure controlled tee arrangement for the GC/MSD.

GC Configuration

The GC can be configured in several ways. However, for instructional purposes and those of these experiments, the GC was configured as follows:

Column #1:	30 m × 0.25 mm id × 0.25 µm column
Inlet:	Front injection port: pulsed splitless mode, split flow 15 mL/min
Outlet:	MSD (vacuum)
Mode:	Constant flow
Column #2:	15 m × 0.25 mm id × 0.25 µm column
Inlet:	Back injection port: split mode, split flow 15-mL/min
Outlet:	MSD (vacuum)
Mode:	Constant flow

The flows were set to 1.2-mL/min, all zones were left cold, and the MSD power was turned on. With the MSD and GC zones still “cold,” the MSD background was checked to be sure m/z 28 was decreasing, indicating that the system was tight. Only after there was confidence that there was no leak were other zones brought up to temperature.

Operating with Pressure Pulsed-Splitless Injection

Figures 4A and 4B show screen captures of the 7890A GC configuration for a standard pressure-pulsed splitless injection with constant flow mode operation; they show the front and back injection port parameters. Remember, the arrangement is set up such that the front port, into which the sample will be injected, is configured as if a 30-m column were installed into the MSD. Typical pressure-pulse conditions are set for these parameters: a 25 psi pulse for 0.5 minutes; split flow on at 0.75 minutes at 50-mL/min; with gas saver on at 2 minutes at 15-mL/min. The general rules apply for pressure-pulsed splitless injections: given a particular liner, inlet temperature, injection volume, and solvent, the expansion of the solvent is confined to a fraction of the interior volume (< 0.75) of the liner by the pressure applied.

Figure 4B shows that the back injection port is in split mode, at 120 °C (to remove water background), with split flow and gas saver set at 15-mL/min flow.




Figure 4A (upper panel). Typical pressure-pulsed splitless injection parameters for constant flow: front injection port.




Figure 4B (lower panel). Typical pressure-pulsed splitless injection parameters for constant flow: back injection port (not used for injection but for column control).

Figures 5A and 5B show the constant flow mode settings for the two columns. The front column flow is the typical 1.20 mL/min, but the back

column flow is slightly higher at 1.25 mL/min to prevent any backflow. Essentially the additional flow is equivalent to an extra meter of column length.




Figure 5A (upper panel). Typical pressure-pulsed splitless injection parameters for constant flow: First column section (configured as a 30-m column).




Figure 5B (lower panel). Typical pressure-pulsed splitless injection parameters for constant flow: Second column section (configured as a 15-m column).

Results and Discussion

Figure 6 shows the results for pressure-pulsed splitless injections of octafluoronaphthalene (OFN) at 1-pg/ μ L acquired in selected ion monitoring (SIM) with the two 15-m column and CFT tee configuration and the standard 30-m continuous

column configuration. Both peak height and area remain the same, indicating that there is no loss in signal. This is as expected since no signal dilution is taking place. There is a slight degradation in S/N for the CFT tee results as the background noise is raised by about 35% due to the additional flow controller. The important point is that the signal is preserved at trace levels.




Figure 6. Reconstructed total ion chromatogram (RTIC) of three replicate SIM acquisitions of octafluoronaphthalene using pulsed splitless injection with CFT tee (left profiles) and with a standard 30-m continuous column configuration (right profiles).

Chromatographic Character

Beyond preserving signal, the CFT device should exhibit reasonable chromatographic performance. One indication of chromatographic integrity is the peak shape profiles of the fatty acid methyl esters (FAMES). The result for GC/MS analysis of a FAMES standard acquired using a metabolomics method is shown in Figure 7 and suggests very little degradation of chromatography using this PCT. This can be expected as the path is deactivated and the path length in the channels in the

PCT relative to the linear velocity suggests a relatively rapid transit through the device.

Another common chromatographic test used in organochlorine pesticide analysis (as in USEPA method 8081) examines degradation of 4,4'-DDT and Endrin. This degradation test was developed to indicate the degree of activity of the injection port by examining the amounts of DDD and DDE products of DDT and the ketone and aldehyde products of Endrin. The situation is complicated here as the degradation products can be generated in both the injection port and the CFT tee. How-




Figure 7. Reconstructed total ion chromatogram (RTIC) of a multicomponent FAMES standard using pulsed splitless injection with CFT tee (upper) and the reconstructed extracted ion chromatogram (REIC) for m/z 74. The enlarged panel is for octadecanoic methyl ester.

ever, because those products formed in the injection port and those formed at the CFT device will have different retention times due to differing lengths of column, the degradation contributions from the two origins should be discernable. By analyzing these known breakdown products in the PCT and then injecting the DDT and Endrin agents themselves, an estimate of the activity contributed by the CFT device can be calculated. The upper panel of Figure 8 presents the reconstructed total ion current (RTIC) for the selected ion monitoring (SIM) signals of the four breakdown products. These were acquired in SIM-scan mode with a single SIM group composed of one or two major ions for each compound so there was no time

selection for the compounds' appearance. On the basis of summed areas, the total breakdown for Endrin is less than 13% with the CFT device contributing less than 10% of the total breakdown area or less than 1.2% to the area total. The DDT breakdown is less than 4% for the system; however, the CFT device contributes about 46% of the total observed breakdown and is about double the breakdown generated by the port. It is possible some DDD breakdown is "hidden" under the DDT peak. On the basis of the DDT to DDE contribution from the CFT tee, however, it is likely to increase the breakdown perhaps less than about another 2%. A better study would use on-column injection




Figure 8. CFT tee activity. A: the REIC of a GC-MS SIM acquisition using pulsed splitless injection with the PCT configuration of the expected degradation products of DDT and Endrin at 0.2 ng on column : 4,4'-DDE (DDE), 4,4'-DDD (DDD), Endrin aldehyde (EA), and ketone (EK). B: REIC for an injection of 2.0 ng of 4,4'-DDT and Endrin identifying degradation products. Those with an asterisk (*) are attributed to the injection port and due to the CFT device activity such as; from Endrin (5 as ketone) and from 4,4'-DDT (6 as DDE). Note 7 is tentatively identified as DDMU, source unknown.

of all components, but the verdict is likely the same: the CFT device has some activity but is comparable to that of other elements (for example, in the inlet and liner). It is worth noting that this CFT device has a very long path compared to others (see the *Alternative Configurations* section) and that air intrusion in any part of the system will be a major issue in considering activity problems.

Adding Backflush

Figures 9A, 9B, and 9C show the GC parameters for adding backflush. They are quite simple. The oven temperature can remain the same as the temperature at the end of the oven program or can be raised to the isothermal or programmed temperature limits in Post Run for backflushing. Raising the column temperature during Post Run helps condition the column and removes some column bleed but is not necessary. The front column (column #1) flow is dropped to 0.3 mL/min and the back column (column #2) flow is raised to 4 mL/min.

To quickly estimate the duration of the Post-Run time parameter, notice that the back column (column #2) in Figure 9C cites the column Holdup Time at a given flow. At the 1.25-mL/min shown, the Holdup Time is roughly 0.4 minutes. When the

column #2 flow is raised to 4 mL/min, the Holdup Time for back flow through column #1 will be less than this (actually around 0.26 min). But estimating that every 0.4 minute the front 15-m column section would be flushed at least once is very conservative and an adequate approximation. Five to 10 column volumes will flush this front 15-m section in less than 2 to 4 minutes, which is relatively rapid. Choose a time in this range (for example, 3 minutes) and test the effectiveness of the backflush method by injecting a sample and follow this with a solvent blank injected under the non-backflush GC/MSD method. There should be no sign of carryover. Extend this Post-Run time if there is carryover or further raise the Post-Run temperature or both. This is a very conservative approach.

Column or Inlet Servicing and Maintenance

To change the liner, septum, cutback the column, or replace the front 15-m column, simply cool the inlet(s) and increase the flow on the back column (column #2) to 4 mL/min and set the front injection port pressure to OFF. It is worth saving this method (such as SERVICE-Front.M). When the head of the column is removed from the injection port, one can confirm that the carrier is flowing back up the column by immersing the tip in liquid.

	Rate °C/min	Value °C	Hold Time min	Run Time min
► (Initial)		45	2.25	2.25
Ramp 1	40	275	0	8
*				

Post Run: 300 °C

Figure 9A (upper panel). Adding backflushing in Post Run: oven parameters.

GC Edit Parameters

Oven Temperature: 151.0 °C

	Description
1	Agilent 190915-433: 325 °C: 30 m x 250 µm x 0.25 µm In: Front SS Inlet He Out: Vacuum
2	Agilent 190913-431: 325 °C: 15 m x 250 µm x 0.25 µm In: Back SS Inlet He Out: Vacuum
	Aux Pressure 1 N2
	Aux Pressure 2 N2
	Aux Pressure 3 N2
	PCM A-1 N2
	PCM A-2 N2

Control Mode ☒ On

☒ Flow ☐ Pressure

Average Velocity

Holdup Time

1.2 mL/min
9.4667 psi
39.824 cm/sec
1.2555 min

(Initial): 0 min
He @ 45 °C Oven
Out: Vacuum
30 m x 250 µm x 0.25 µm

	Rate mL/min per min	Value mL/min	Hold Time min	Run Time min
► (Initial)		1.2	0	8
*				

Final value will be extended by GC run time.

Post Run: 0.3 mL/min

Apply OK Cancel Help

Figure 9B (middle panel). Adding backflushing in Post Run: front column (column #1) parameters.

GC Edit Parameters

Oven Temperature: 45.0 °C

	Description
1	Agilent 190915-433: 325 °C: 30 m x 250 µm x 0.25 µm In: Front SS Inlet He Out: Vacuum
2	Agilent 190913-431: 325 °C: 15 m x 250 µm x 0.25 µm In: Back SS Inlet He Out: Vacuum
	Aux Pressure 1 N2
	Aux Pressure 2 N2
	Aux Pressure 3 N2
	PCM A-1 N2
	PCM A-2 N2

Control Mode ☒ On

☒ Flow ☐ Pressure

Average Velocity

Holdup Time

1.25 mL/min
2.7419 psi
57.48 cm/sec
0.43493 min

(Initial): 0 min
He @ 45 °C Oven
Out: Vacuum
15 m x 250 µm x 0.25 µm

	Rate mL/min per min	Value mL/min	Hold Time min	Run Time min
► (Initial)		1.25	0	8
*				

Final value will be extended by GC run time.

Post Run: 4 mL/min

Apply OK Cancel Help

Figure 9C (lower panel). Adding backflushing in Post Run: back column (column #2) parameters.

This backflow also prevents fines from the column cutting from entering the column. Make the necessary service and reattach and reload the analytical method.

If a completely new 15-m column (#1) is installed, it can be conditioned *in situ* by setting up the backflow condition with the oven at the conditioning column temperature.

Advanced Techniques: Concurrent Backflushing

If the fastest possible total analytical time is the highest priority, one will realize that backflush can begin earlier than the elution of the last component. In other words, backflushing can occur

during the analytical acquisition, thereby increasing productivity. After the last compound of interest has passed the CFT tee and entered the back 15-m column, the pressure or flow through the earlier 15-m column can be dropped and compounds will cease moving forward and actually begin to retreat. When the last compound elutes, then the flow in the back column can be raised to complete backflushing. This is demonstrated in Figure 10.

The calculations are also very simple. To calculate when the flow (pressure) in the front column (column #1) is to be reduced, simply subtract the Holdup Time (Figure 9C) from the last compound's




Figure 10. Example of backflushing with flow or pressure control. Upper panel: RTIC of original six-component standard. The third peak is considered the last analyte and the fourth peak the beginning of the late-eluting interferences. Middle panel: RTIC of the same standard with backflushing beginning at 10.1 min (a), where the first 15-m column (column #1) flow is dropped and at (b) where column #2 flow is increased to 4 mL/min. Note that the last analyte is retained but the late eluters never enter the MSD. Lower panel: solvent blank run without backflush after the backflush method which shows no carryover.

elution time. After this last compound has eluted, go into Post Run and set the second 15-m column (#2) flow to 4-mL/min (or the pumping system maximum) with the front column (#1) pressure remaining low and the oven at the final programmed temperature. This can best be accomplished in ramped flow mode or in pressure programming. Do this for two to three column volumes and test with a sample followed by a solvent blank to see if this is sufficient. Experimentation with particular samples will enable setting these requirements more efficiently.

Conclusions

Alternative Configurations

The CFT is very rich and allows many possible arrangements; these are only a few suggestions or alternatives. The CFT tee used here can be replaced by a purged two-way splitter with one channel plugged (G3180-61500) or even the QuickSwap itself can be moved back from the MSD interface and suspended in the oven.

However, the best CFT tee device appears to be the new Purged Ultimate Union (G3186-60580), Figure 11. As the name describes, this is essentially a union with a gas purging line, making it a very low dead volume tee. It occupies very little space and can be suspended from the column cage, the oven wall, or through the upper GC wall. Preliminary tests of this Purged Ultimate Union using DDT and Endrin have shown very little breakdown. Chromatographic behavior is also very good.

Similarly, the carrier control need not be the back injection port split/splitless module; a Pressure Control Module (PCM) or EPC module can be used. Of the two, the Pressure Control Module may be more convenient.

Most importantly, the CFT tee position itself does not need to be exactly in the middle. The best arrangements can be considered on the basis of selection against components and the rapidity of backflushing. In other words, rapid backflushing suggests a shorter upstream column #1. So another arrangement is at the two-thirds mark or a 10-m column, then the CFT tee, and then a 20-m column to create a 30-m analytical column. Here




Figure 11. Purged Ultimate Union.

backflushing would be nearly 10 times faster than the arrangement with QuickSwap and more than twice as fast as the 15-m column for the same pressure. This would be the best arrangement for the MSD with a diffusion pump. Also, in terms of analytical time, this approach would provide even higher efficiency since 10 column volumes could be flushed in about 2 minutes. If backflushing begins before the analytical run ends (as shown in Advance Techniques and in Figure 10), then in many cases the Post-Run time would be very short or entirely unnecessary, yet still provide sufficient backflushing. This would further reduce total cycle times.

The joined columns need not match in many aspects. For example, a 0.32-mm id may be the first column and a 0.25-mm id the second column. In this situation it will be better to have the columns configured and described as they actually exist in the 7890A. For example, column #1 inlet is the splitless port and the outlet is the PCM module A; column #2 inlet is the PCM module A and the outlet is the MSD. Considerations of capacity, resolution, robustness, etc., can be entertained in several innovative ways to enhance productivity and data quality.

This solution can also be implemented on the Agilent 6890 GC. Of course, the PCT tee configuration is not confined to the Agilent GC/MS detector, but is suitable for other detection schemes as well.

Future software releases will contain a key command that will allow more functionality and greater ease of use: it will allow the user to apply the IGNORE READY = TRUE condition to the EPC device controlling the CFT tee. This will prevent the pressure pulse or other flow conditions from producing a "not ready" condition for the instrument.

References

1. The 5975C Series GC/MSD, Agilent Technologies publication 5989-7827EN
2. Frank David and Matthew S. Klee, "Analysis of Suspected Flavor and Fragrance Allergens in Cosmetics Using the 7890A GC with Column Backflush," Agilent Technologies publication 5989-6460EN
3. Frank David and Matthew S. Klee, "GC/MS Analysis of PCBs in Waste Oil Using the Backflush Capability of Agilent QuickSwap Accessory," Agilent Technologies publication 5989-7601EN

(These references are available in the Literature Library at www.chem.agilent.com.)

Acknowledgements

The author is very grateful to Bruce Quimby, Wes Norman, and Matthew Klee for several informative and encouraging discussions. Also, a special thanks to Wes Norman for providing superb CFT devices tailored to the needs of the GC/MSD and an advance example of the Purged Ultimate Union.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2008

Printed in the USA
June 24, 2008
5989-8664EN



Agilent Technologies



Reliable Transfer of Existing Agilent 6890/5973 GC/MSD Methods to the New 7890/5975 GC/MSD

Application

Gas Chromatography/Mass Spectroscopy

Authors

Russell Kinghorn and Courtney Milner
BST International
Melbourne
Australia

Matthew S. Klee (Agilent Contact)
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The performance of the Agilent Technologies' new series of instruments, the 7890 Series GC and 5975 Series MSD, is compared to that of the previous versions, the 6890 Series GC and the 5973 Series MSD. Performance is shown to be fully equivalent in test comparisons using a 16-component polynuclear aromatic hydrocarbon (PAH) sample. Excellent reproducibility and calibration characteristics were obtained. These results indicate that one can migrate a method currently running on a 6890/5973 system to a 7890/5975 system with high confidence that the performance will be equivalent or better.

Introduction

Agilent Technologies recently introduced new gas chromatograph and mass spectrometer platforms, the 7890 Series GC and the 5975 Series MSD, containing improved software, firmware, and hardware over the prior series, the 6890 GC and the 5973 MSD.

It was necessary to validate instrument performance of the 7890 Series GC for methods previously created and run on 6890 Series instrument to ensure equivalence. It was also desirable to demonstrate the ease of method transfer from existing 6890 GC methods using the prior ChemStation software to new 7890A GC methods using the new ChemStation software.

Table 1. System Configurations Compared

6890 System configuration	7890A System configuration
Agilent 6890A GC	Production prototype 7890 Series GC
S/SI inlet	S/SI inlet
ALS + tray	7683 ALS + tray
Agilent 5973N MSD	Agilent 5975B MSD
Diffusion pump	Standard turbo
Inert E.I. source	Inert E.I. source
ChemStation 1701 DA version D.00.01	ChemStation 1701DA version D.03.00



Agilent Technologies

The method conditions used for this comparison were similar and are summarized in Table 2.

Table 2. Semivolatiles Method Conditions

Column	HP-5 MS, 25 m x 250 μ m id (p/n 19091S-433)
Carrier gas	He, constant pressure mode, nominal 13 psig
RTL	Anthracene @ 8.300 min
Split/splitless inlet	300 °C, pulsed splitless: 25 psig for 0.3 min, 30 mL/min purge @ 0.75 min
Oven	55 °C (1 min) $\rightarrow$ 320 °C (3 min) @ 25 °C/min; total time 14.60 min
Sample	1- μ L injection of PAHs in 0.32 to 10 ppm concentration range
MSD	Scan 45 to 400 u Samples = 2 ² Autotune EM offset +200 V Source = 230 °C Quad = 150 °C Transfer line = 280 °C

Experimental

Our goals were to determine the performance metrics on a current 6890 GC for a typical retention time locked method, to transfer method conditions to a new 7890A GC and relock, and to determine the 7890A performance metrics and compare them to those of the 6890. The system configurations used are shown in Table 1.

Results and Discussion

The test sample contained 16 different polynuclear aromatic hydrocarbons (PAHs), covering a wide range of physical properties. Total ion chromatograms (TICs), derived from each of the Agilent systems are compared in Figure 1. The comparison reveals a very high level of reproducibility.

More detailed comparisons for selected PAHs are shown in Figures 2 and 3.

We note from the TICs shown in Figures 1 to 3 that the performance of both systems is nearly identical. The reproducibility data for all 16 PAHs are shown in Table 3, along with the delta RT, illustrating the ability to move methods between systems without the need for method redevelopment.




Figure 1. Overlays of TICs of the same sample of PAHs are virtually indistinguishable. Inset shows the TICs in separated format.




Figure 2. System TICs for acenaphthylene, acenaphthene, and fluorene are compared.




Figure 3. System TICs for benzo[b]fluoranthene, benzo[k]fluoranthene, and benzo[a]pyrene are compared.

Table 3. Comparison of Performance Metrics

Solute	6890/5973				7890/5975				ΔRT
	Avg RT (min)	SD	RSD	Calibration linearity, r^2	Avg RT (min)	SD	RSD	Calibration linearity, r^2	
Naphthalene	5.103	0.005	0.098	0.992	5.103	0.005	0.098	0.995	0.000
Acenaphthylene	6.650	0.000	0.000	0.998	6.649	0.003	0.050	0.998	0.001
Acenaphthene	6.830	0.000	0.000	0.993	6.830	0.000	0.000	0.995	0.000
Fluorene	7.320	0.000	0.000	0.997	7.320	0.000	0.000	0.998	0.000
Phenanthrene	8.256	0.005	0.064	0.999	8.251	0.003	0.040	0.999	0.004
Anthracene	8.300	0.000	0.000	0.999	8.300	0.000	0.000	0.998	0.000
Fluoranthene	9.430	0.000	0.000	0.997	9.430	0.000	0.000	0.995	0.000
Pyrene	9.650	0.000	0.000	0.997	9.650	0.000	0.000	0.996	0.000
Chrysene	10.830	0.000	0.000	0.991	10.830	0.000	0.000	0.992	0.000
Benz[a]anthracene	10.870	0.000	0.000	0.995	10.870	0.000	0.000	0.994	0.000
Benz[b]fluoranthene	11.848	0.010	0.082	0.999	11.849	0.011	0.089	0.997	-0.001
Benz[k]fluoranthene	11.862	0.004	0.037	0.997	11.862	0.004	0.037	0.999	0.000
Benzo[a]pyrene	12.151	0.003	0.027	0.999	12.150	0.000	0.000	0.999	0.001
Indeno[1,2,3-cd]pyrene	13.412	0.008	0.062	0.998	13.412	0.004	0.033	0.995	0.000
Dibenz[a,h]anthracene	13.404	0.005	0.039	0.994	13.396	0.005	0.039	0.996	0.009
Benzo[ghi]perylene	13.732	0.004	0.032	0.993	13.729	0.008	0.057	0.995	0.003

Figure 4 shows that the response characteristics for all PAH components are similar on both the 6890/5873 and 7890/5975C systems.




Figure 4. PAH calibration plots over the 0.32-10 ppm concentration range using both the 6890/5973 (upper) and 7890A/5975C (lower) GC/MSD systems.

Conclusions

System equivalence is demonstrated. The new Agilent 7890 Series GC and 5975 Series MSD system easily reproduced method characteristics of the prior Agilent 6890 Series GC and 5973 Series MSD systems, using a 16-component PAH sample and retention time locking. This demon-

strates that methods can be confidently migrated to the new systems without loss in performance, allowing rapid and trouble free implementation of the new platforms.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
April 4, 2007
5989-6569EN



Agilent Technologies



Direct Injection of Fish Oil for the GC-ECD Analysis of PCBs: Results Using a Deans Switch With Backflushing

Application

Environmental and Pharmaceutical

Author

Philip L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
USA

Abstract

A Deans switch, employing Agilent's Capillary Flow Technology, was configured on an Agilent 7890A gas chromatograph (GC) equipped with dual electron capture detectors (ECDs). A method was developed for the analysis of fish oil for polychlorinated biphenyl (PCB) contamination. The Deans switch was used to heart cut 7 indicator PCBs (IUPAC congeners 28, 52, 101, 118, 138, 153, and 180) from the primary DB-XLB column onto a DB-200 column for further separation. Fish oil from a supplement capsule was simply diluted 1:10 in isooctane and injected directly. In a separate experiment, the fish oil was analyzed by GC with a flame ionization detector (GC/FID) without backflushing. From these analyses, it was estimated that about two-thirds of the fish oil components would remain on the column after the 17.4-minute GC/ECD run. To prevent carryover, contamination, and retention time shifts, the Deans switch was used to backflush the primary column at the end of each run. Evidence shows that backflushing removed the fish oil residue, which otherwise would quickly degrade the chromatography.

Introduction

Fish oils contain high levels of eicosapentanoic acid (EPA) and docosahexanoic acid (DHA), omega-3 fatty acids that are thought to have

beneficial health affects. In addition to eating fish, many people take fish oil as a supplement to their daily diet. However, fish, especially those high on the aquatic food chain, can bioaccumulate fat-soluble pollutants. Among these are polychlorinated dibenzodioxins (PCDDs), polychlorinated dibenzofurans (PCDFs), and polychlorinated biphenyls (PCBs). Therefore, fish oil used in supplements undergoes a variety of analyses, including tests for halogenated pollutants.

One of the quality assurance tests is to analyze fish oil for PCB contamination. This is complicated by the fact that fish oil is a very complex mixture containing high-boiling fatty acids and triglycerides of fatty acids; chain lengths are mostly between 14 and 22 carbons. They also contain varying amounts of phospholipids, glycerol ethers, wax esters, and fatty alcohols. PCB analysis is complex by itself, with 209 possible congeners. Of these, 140 to 150 have been observed in commercial PCB mixtures called Aroclors. PCB analysis usually focuses on the 12 planar, dioxin-like PCBs and/or on seven indicator PCBs (IUPAC Numbers 28, 52, 101, 118, 138, 153, and 180).

To obtain sufficient sensitivity and selectivity for these compounds, analysts have traditionally employed very expensive techniques such as high-resolution mass spectrometry (HR/MS) or HR/MS/MS. Analysis of the fish oil generally follows a series of extraction and cleanup steps. This paper focuses on the analysis of the seven indicator PCBs in fish oil using an Agilent 7890A GC configured with a Deans switch, two columns of differing selectivity, and dual electron capture



Agilent Technologies

detectors (ECDs). Fish oil from a commercially available supplement was simply diluted 10:1 in isooctane and injected into the GC. No cleanup steps were employed.

Experimental

The fish oil supplement was obtained from a local grocery store. According to the bottle's label, each gelatin capsule contains 1.0 g of fish oil of which 180 mg is EPA and 120 mg is DHA. Oil was removed from a capsule and diluted with isooctane (pesticide grade from Sigma-Aldrich, Milwaukee, WI, USA) to make a 10% solution. This solution was spiked with various Aroclors (Supelco, Bellefonte, PA, USA) or with individual PCB congeners (AccuStandard, New Haven, CT, USA).

Table 1 lists the instrumentation and experimental conditions for the analysis.

Table 1. Instrumentation and Experimental Conditions

Instrumentation and Software	
Gas chromatograph	Agilent 7890A
Automatic sampler	Agilent 7683B Series injector and tray
Primary column	J&W 30-m × 0.18-mm × 0.18-μm DB-XLB (P/N 121-1232)
Primary column connections	Split/splitless inlet to Deans switch
Secondary column	J&W 30-m × 0.25-mm × 0.50-μm DB-200 (P/N 122-2033)
Secondary column connections	Deans switch to back ECD
Restrictor	76.8-cm × 0.100-mm deactivated fused silica tubing
Restrictor connections	Deans switch to front ECD
Inlet liner	Agilent deactivated single taper with glass wool (P/N 5062-3587)
Auxiliary pressure control device	Agilent 7890A Pneumatic Control Module (PCM) Option # 309
Deans switch calculator software	Agilent Technologies Deans Switch Calculator (Rev. A.01.01)
Software for data acquisition and analysis	Agilent GC ChemStation (Rev. B.03.01)

Instrumental Conditions for Analysis

Inlet	Split/splitless at 330 °C
Oven temperature program	80 °C (1 min), 50 °C/min to 200 °C (0 min), 10 °C/min to 290 °C (5 min)
Detectors	Dual ECD at 340 °C
ECD make-up gas	N ₂ at 60 mL/min
Inlet pressure	H ₂ at 41.040 psig (constant pressure mode)
PCM pressure to Deans switch	H ₂ at 20.610 psig (constant pressure mode)

Post-Run Backflush Conditions

Post-run duration	2.4 min
Inlet pressure	H ₂ at 0 psig
PCM pressure	H ₂ at 80 psig
Oven temperature during backflush	290 °C for 2.4 min

Results and Discussion

Without backflushing, the high-boiling components of fish oil can be retained by the GC column, causing severe carryover problems from one run to the next. After a few injections, so much of the fish oil residue builds up on the column that it causes PCB retention times to shift by a minute or more. Such dramatic retention time shifts would prevent the use of the Deans switch, where heart cuts are just a few seconds wide.

Deans Switch—Heart Cutting

The Deans switch is one of Agilent's new devices that employ Capillary Flow Technology. These devices have extremely low dead volumes, are inert, and do not leak, even with large cycles in oven temperature. Columns are easy to install into the Deans switch, which is mounted on the side of the oven wall (Figure 1).




Figure 1. Photograph of the Deans switch installed on the side of the 7890A GC oven. The column and restrictor connections are indicated by an * in Figure 2a.

As shown in Figure 2a, the 30-m $\times$ 0.18-mm $\times$ 0.18- μ m DB-XLB column is connected between the split/splitless inlet and the Deans switch. A short length of deactivated fused silica tubing (76.8 cm $\times$ 0.100 mm) connects the Deans switch to the front ECD. The secondary column (30-m $\times$ 0.25-mm $\times$ 0.5- μ m DB-200) was chosen because it is more polar than the DB-XLB column and has a different selectivity for PCBs. It has an upper temperature limit of 300 °C, which is high enough to elute the PCBs of interest.

Figure 2a shows the Deans switch in the “normal” mode with the solenoid valve in the off position.

In this mode, the effluent from the primary DB-XLB column is directed through the restrictor to the front ECD. When the solenoid valve is switched, the effluent is directed through the secondary DB-200 column to the back ECD (Figure 2b). The retention times for the seven indicator PCBs were initially determined with the valve in the *off* position. Using the timed events table in the ChemStation, the valve was switched to *on* just before each PCB peak and *off* immediately after. This produced seven heart cuts that were directed through the DB-200 column to the back ECD.




Figure 2a. Deans switch in the “no cut” position. The effluent from the DB-XLB column goes directly to the front ECD through the short restrictor. The intersections marked with an * are column and restrictor connections to the Deans switch plate (Figure 1).




Figure 2b. Deans switch in the “cut” position. The effluent from the DB-XLB column goes to the DB-200 column and then to the back ECD.

In some Deans switch systems, the second column is placed in a separate GC oven or cryogenic cooling is used to trap the heart cut components at the head of the second column. In this case, both columns were mounted inside of the 7890A oven and cooling was not used to focus compounds at the head of the DB-200 column.

Figure 3a shows the chromatogram for a fish oil sample spiked with Aroclor 1260. PCBs 28, 52, 101,

118, 138, 153, and 180 were cut out of the primary chromatogram (Figure 3b) and sent to the second column (Figure 3c). The purpose of the DB-200 column is to resolve the target PCBs from other PCBs and matrix components that co-elute with them on the DB-XLB column. Six of the 7 PCBs appear to be well resolved on the DB-200 column. PCB 118 is only partially resolved by this method.




Figure 3a. GC/ECD chromatogram of Aroclor 1260 spiked into fish oil. This is the effluent from the primary DB-XLB column with seven heart cuts.




Figure 3b. Enlargement of the chromatogram in Figure 3a showing where heart cuts were made for the seven target PCBs.




Figure 3c. GC/ECD chromatogram from the DB-200 column. The peaks in this chromatogram were heart cut from the DB-XLB column. Except for congener 118, the target PCBs were separated from co-eluting interferences by the DB-200 column.

Deans Switch–Backflushing

Data collection with the Deans switch system ended at 17.4 min with the oven at 290 °C. While it was assumed that a lot of the fish oil components remained on the column at this point, it was impossible to tell because the ECD responds poorly to these compounds. The fish oil does contribute some small peaks (both positive and negative) to the chromatogram, but it is impossible to see the full contribution of the fish oil. So a sample of the fish oil was analyzed on an identical DB-XLB column using a flame ionization detector (FID) with no Deans switch installed. The temperature was held at 290 °C for an extra 25 minutes to determine if high boiling compounds were still eluting.

Figure 4 shows that a great deal of the fish oil continued to elute after 17.4 minutes (arrow in figure). When a blank run was made with a final oven temperature of 310 °C, much more of the fish oil eluted from the column (Figure 4, middle chromatogram). A second blank run (Figure 4, top chromatogram) showed that fish oil components were still eluting from the column. In actuality, only about a third of the fish oil comes off the column under the Deans switch conditions. This is why other fish oil methods begin with a solvent extraction followed by solid phase extraction for sample cleanup.




Figure 4. GC/FID chromatogram from a 1 μ L splitless injection of 10% fish oil using a 30-m $\times$ 0.18-mm $\times$ 0.18 μ m DB-XLB column. The arrow indicates where the GC/ECD method ends and the post-run backflush begins. In this case, there was no back-flushing so the oven was held at 290 $^{\circ}$ C for an extra 25 min. The run was repeated two more times without injection but with the oven held at 310 $^{\circ}$ C for 30 minutes at the end of the run. Residue from the fish oil injection continued to elute, even during a second bakeout step.

The 7890A has been designed to make column backflushing a routine process. It has been shown empirically that backflushing should continue for about five times the holdup time. In this case the column was held at 290 $^{\circ}$ C during the post run backflush. At the same time, the inlet pressure was dropped to 0 psig while the PCM pressure was increased to 80 psig. Using Agilent's GC Pressure/Flow Calculator software, the H₂ flow rate backwards through the column was 3.81 mL/min and the holdup time was 0.466 min. Backflushing was, therefore, continued for 2.4 minutes, which is slightly more than five times the calculated holdup value. Figure 5 shows the Deans switch in the backflush mode.




Figure 5. Deans switch in the “backflush” mode. The inlet pressure is dropped to 0 (or 1) psig while the PCM pressure is raised to 80 psig. This causes the carrier gas to flow backwards through the DB-XLB column. The reverse flow sweeps high-boiling fish oil components off the head of the column and out the split vent.

As mentioned earlier, just a few injections of fish oil can cause dramatic shifts in PCB retention times. Backflushing forces the remaining fish oil components backwards through the primary column and out through the split vent. This prevents fish oil buildup on the column, thus eliminating carryover and retention time shifts. Figure 6a compares the first and last chromatograms in a six-run sequence. One- μL splitless injections were made of 10% fish oil spiked with Aroclor 1260. This sequence was run after many previous injections of fish oil using this method, and it is clear that the retention times did not shift.

Figure 6b shows the seven PCBs that were heart cut from the two analyses shown in Figure 6a. Figure 6b shows no differences in the first and last heart cut chromatograms, providing further proof that there were not even subtle shifts in the PCB retention times. Each heart cut was just 4 to 5 seconds wide, so very small RT shifts in the first column would dramatically alter the results in the second.




Figure 6a. First (top) and sixth (inverted) injections of 10% fish oil spiked with Aroclor 1260. Seven Deans switch cuts were made from this DB-XLB column in order to isolate PCBs 28, 52, 101, 118, 138, 153, and 180. The DB-XLB column was back-flushed after each run, preventing build-up of fish oil residue. The comparison shows that there was no shift in retention times caused by fish oil accumulation.




Figure 6b. Chromatogram of the seven PCB congeners and interferences that were cut from the DB-XLB column to the DB-200. The first chromatogram (top) and sixth (inverted) are identical, providing further proof of retention time stability. Any retention time shift on the primary column would severely alter the appearance of the secondary chromatogram.

Conclusions

This paper demonstrates that it is possible to analyze PCBs in fish oil without performing laborious sample cleanup prior to GC injection. A Deans switch was used to cut seven target PCBs (28, 52, 101, 118, 138, 153, and 180) from a DB-XLB column for further separation on a DB-200 column. This produced nearly baseline separation of the target PCBs. Only congener 118 was not well separated from co-eluting PCBs. Further refinement of the oven temperature program would be needed to isolate this congener.

It has been estimated that about two-thirds of the fish oil remained on the primary GC column at the end of the run. By setting the Deans switch to the backflush mode for just 2.4 minutes at the end of each run, this material was swept backwards through the column and out the split vent. There was no evidence for retention time shifts or carryover from run to run.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

The information contained in this publication is intended for research use only and is not to be followed as a diagnostic procedure.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2007

Printed in the USA
January 5, 2007
5989-6095EN



Agilent Technologies

Improving Productivity and Extending Column Life with Backflush

Application Brief

Chin-Kai Meng

All Industries

A previous application note [1] has shown that multiple GC signals and MS signals can be acquired from a single sample injection. When a 3-way splitter is connected to the end of a column, column effluent can be directed proportionally to two GC detectors as well as the MSD. This multi-signal configuration provides full-scan data for library searching, SIM data for quantitation, and element selective detector data for excellent selectivity and sensitivity from complex matrices.

The system used in this study consists of a 7683ALS, a 7890A GC with split/splitless inlet, 3-way splitter, μ ECD, dual flame photometric detector (DFPD), and a 5975C MSD. Figure 1 shows four chromatograms from a single injection of a milk extract. The synchronous SIM/scan feature of the 5975C MSD provides data useful for both screening (full scan data) and quantitation (SIM data). DFPD provides both P and S signals without the need to switch light filters.

Noticeably in the full scan TIC in Figure 1, a significant number of matrix peaks were observed after 32 minutes. It is not uncommon to add a “bake-out” oven ramp to clean the column after analyzing complex samples. The bake-out period is used to quickly push the late eluters out of the column to be ready for the next injection. Therefore, it is common to use a higher oven temperature than required for the analysis and an extended bake-out period at the end of a normal

Highlights

- Backflush – a simple technique to remove high boilers from the column faster and at a lower column temperature to cut down analysis time and increase column lifetime.
- The milk extract example shows that a 7-minute 280 °C backflush cleaned the column as well as a 33-minute 320 °C bake-out. The cycle time was reduced by more than 30%.
- Using backflush, excess column bleed and heavy residues will not be introduced into the MSD, thus reducing ion source contamination.




Figure 1. Four chromatograms collected simultaneously from a single injection of a milk extract.



Agilent Technologies

over program to clean out the column, which adds to the cycle time and shortens the column lifetime. Adding the bake-out period to the milk extract analysis, additional matrix peaks were observed even up to 72 minutes, while target compounds already eluted before 42 minutes. This means that 30 minutes were lost in productivity for each injection.

Backflush [2] is a simple technique to drastically decrease the cycle time by reversing the column flow to push the late eluters out of the inlet end of the column. Late eluters stay near the front of the column until the oven temperature is high enough to move them through the column. When the column flow is reversed before the late eluters start to move down the column, these late eluters will take less time and at a lower oven temperature to exit the inlet end of the column.

There are many benefits in using backflush:

- Cycle time is reduced (no bake-out period, cooling down from a lower oven temperature)
- Column bleed is reduced (no high-temperature bake-out needed), resulting longer column life
- Ghost peaks are eliminated (no high boilers carryover into subsequent runs)
- Contamination that goes into the detector is minimized, which is especially valuable for the MSD (less ion source cleaning)

Figure 2 shows three total ion chromatograms from the Agilent 7890A GC/5975C MSD. The top chromatogram is a milk extract analysis with all the target compounds eluted before 42 minutes (over program goes to 280 °C). However, an additional 33-minute bake-out period at 320 °C was needed to move the high boilers out of the column. This bake-out period was almost as long as the required time to elute all target compounds. The middle chromatogram is the same milk extract analysis stopped at 42 minutes with a 7-minute backflush post-run at 280 °C added to the analysis. The bottom chromatogram is a blank run after the backflushing was completed. The blank run shows that the column was very clean after backflushing. The example shows that a 7-minute backflush cleaned the column as well as a 33-minute bake-out.

The milk extract example in Figure 2 illustrates the backflush technique in reducing cycle time and column bleed. The cycle time was reduced by more than 30% and the column was kept at 280 °C, without going to the bake-out temperature




Figure 2. Three total ion chromatograms comparing the results with and without backflush.

of 320 °C. A column effluent splitter or QuickSwap is required to do the backflush.

References

1. Chin-Kai Meng and Bruce Quimby, "Identifying Pesticides with Full Scan, SIM, μ ECD, and FPD from a Single Injection," Agilent Application Note, 5989-3299EN, July 2005.
2. Matthew Klee, "Simplified Backflush Using Agilent 6890 GC Post Run Command," Agilent Application Note, 5989-5111EN, June 2006.

Acknowledgement

Milk extract is courtesy of Dr. Steven Lehotay from USDA Agricultural Research Service in Wyndmoor, Pennsylvania, USA.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
December 26, 2006
5989-6018EN



Agilent Technologies



Using RTL and 3-Way Splitter to Identify Unknown in Strawberry Extract

Application Brief

Chin-Kai Meng

Food Safety and Environmental

Fruit and vegetable extracts are usually very complex to analyze. It is common to use the very selective GC detectors, for example NPD, μ ECD, and FPD, to look for trace pesticide residues in the extracts. Mass spectrometry is most often used to confirm the hits from GC detectors. A previous application note [1] describes a GC/MS system with a three-way splitter added to the end of the column. The column effluent could be split three ways to two GC detectors and the MSD. The splitter system is therefore capable of providing up to four signals (two GC signals, SIM, and full-scan chromatograms) from a single injection. The combination of element selective detectors, SIM/scan, and Deconvolution Reporting Software (DRS) makes a very powerful pesticide analysis system [2]. The trade-off is the decrease of analyte concentration in any detector due to the flow splitting at the end of the column.

The system used for this study consists of an Agilent 7890A GC with split/splitless inlet, a three-way splitter, μ ECD, dual flame photometric detector (DFPD), and 5975C MSD. Figure 1 shows chromatograms from 2 separate injections (each injection provides two GC signals) of the same strawberry extract without any hardware or filter changes. All of the target compounds were found and confirmed by DRS, GC, and MS signals except the unknown peak at about 41 minutes. The peak shows responses from μ ECD, DFPD(S) and DFPD(P). However, no peak was observed in the MS full-scan signal. This makes it difficult to confirm the unknown peak using the full-scan TIC.

Since the analysis was retention time locked, it is therefore possible to find potential matches by examining the RTL pesticide database (part number G1672AA). The unknown compound, containing electron-capturing atoms (for example, Cl or O), P, and S atoms, would have a target retention time inside the

Highlights

Splitter—an inert, easy-to-use capillary flow technology that splits column effluent to multiple detectors (for example, MSD, DFPD, and μ ECD). The splitter configuration provides a comprehensive screening and quantitative system.

By combining RTL, element-selective detector chromatograms, and the RTL pesticide database, a trace level pesticide residue was identified without the full-scan mass spectrum.



Agilent Technologies




Figure 1. Unknown compound detected by GC signals not found in strawberry extract TIC.

Table 1. Compound List Extracted from the RTLPest3.tab File

Name	CAS	Mol form	Mol wt	R.T.	Target Ion	Q1	Q2	Q3
Fluthiacet-methyl	117337196	C ₁₅ H ₁₅ ClFN ₃ O ₃ S ₂	403.9	39.10	403	56	405	232
Benzo[g,h,i]perylene	191242	C ₂₂ H ₁₂	276.3	39.13	276	277	138	275
Temephos	3383968	C ₁₆ H ₂₀ O ₆ P ₂ S ₃	466.5	40.74	466	125	93	109
PBB 169 hexabrombiphenyl	60044260	C ₁₂ H ₄ Br ₆	627.6	40.93	308	468	148	154
Rotenone	83794	C ₂₃ H ₂₂ O ₆	394.4	41.70	192	191	394	177

41 ± 0.5-minute window (that is, 40.5 to 41.5 min) in the database, if it is included in the database. Table 1 is a portion of the RTLPest3.tab file¹ opened in Microsoft Excel. The compound temephos at locked retention time 40.74 min meets all the criteria for the unknown peak. To further confirm peak identity, extracted ion chromatograms (EICs) of the four major ions of temephos were plotted. Figure 2 shows EICs of target ion and three qualifiers (ions 466, 125, 93, and 109 from Table 1) of temephos. Although the ion intensities were weak, the noticeable presence of all four ions at 40.9 min helped to confirm that the unknown peak was temephos.

1. The RTLPest3.tab file is created in the C:\Database directory while executing the Tools\List Screen Database... command (in MSD Enhanced Data Analysis software) and selecting the RTLPest3.scd from the C:\Database directory.




Figure 2. EICs of target ion 466 (temephos) and three qualifier ions.

References

1. Chin-Kai Meng and Bruce Quimby, "Identifying Pesticides with Full Scan, SIM, μ ECD, and FPD from a Single Injection," Application Note, 5989-3299, July 2005.
2. Mike Szelewski and Bruce Quimby, "New Tools for Rapid Pesticide Analysis in High Matrix Samples," Application Note, 5989-1716, October 2004.

Acknowledgement

Strawberry extract is courtesy of Dr. Steven Lehotay from USDA Agricultural Research Service in Wyndmoor, Pennsylvania, USA.

For More Information


For more information on our products and services, visit our Web site at www.agilent.com/chem.

Copyright © 2006 Agilent Technologies
All Rights Reserved. Reproduction, adaptation, or translation without prior written permission is prohibited, except as allowed under the copyright laws.

Printed in the USA
December 13, 2006
5989-6007EN



Agilent Technologies



Fast and Ultra-fast Analysis with the Agilent 1200 Series Rapid Resolution LC System Compared to a Conventional Agilent 1100 Series LC System Using Sub 2- μ m Particle Columns

Application Note

A. G. Huesgen

Abstract

Due to an increasing workload in many analytical laboratories, a need to develop analytical methods faster has arisen. Furthermore, developing faster methods for standard columns is critical. Faster method development for faster LC methods is a requirement that can be met with state-of-the-art LC equipment. Even though conventional LC equipment can also provide fast methods, better performance and time savings can be obtained on specially designed LC systems with wider pressure and temperature ranges and lower delay volume - predominantly with 2.1-mm ID columns, where typically lower flow rates are used than on 4.6-mm ID columns. This Application Note shows that shorter run times, shorter equilibration times, and consequently shorter cycle times and more sample throughput are obtained using the Agilent 1200 Series Rapid Resolution LC (RRLC) system.



Agilent Technologies

Introduction

Due to an increasing workload in many analytical laboratories, a need to develop analytical methods faster has arisen. Furthermore, developing faster methods for standard columns is critical. Increasingly more applications are carried out using LC/MS systems, therefore there is also a demand to use narrow-bore columns for full compatibility with most MS engines. Narrow-bore columns with an internal diameter of 2.1 mm and lower have high demands in respect to low delay volumes and dispersion volumes before and after the column. In the following experiment an example is given, showing how fast methods can be developed on an LC system taking advantage of higher pressure and temperature limits of state-of-the-art equipment. In addition, speed and performance comparisons are made between a conventional Agilent 1100 Series LC system and an Agilent 1200 Series Rapid Resolution LC system, using 4.6-mm ID columns and 2.-mm ID columns packed with 1.8- μ m particles.

Experimental

An Agilent 1200 Series RRLC system was used with the following modules:

- Agilent 1200 Series binary pump SL with vacuum degasser for applications using 1.8- μ m particle columns up to 150-mm length and with internal diameters from 2.1 to 4.6 mm
- Agilent 1200 Series high-performance autosampler SL for highest area precision
- Agilent 1200 Series thermostatted column compartment SL with wide temperature range from 10 degrees below ambient up to 100 °C
- Agilent 1200 Series diode-array detector SL for 80-Hz operation, including new data protection tool
- ZORBAX SB C-18 columns with different internal diameters and 50-mm length, packed with 1.8- μ m particles
- Low dispersion kit for optimized conditions for 2.1-mm ID columns (Agilent part number G1316-68744)

An Agilent 1100 Series LC system was used with the following modules:

- Agilent 1100 Series binary pump with vacuum degasser
- Agilent 1100 Series well-plate autosampler
- Agilent 1100 Series thermostatted column compartment
- Agilent 1100 Series diode-array detector B
- Low dispersion kit for optimized conditions for 2.1-mm ID columns (Agilent part number 5065-9947)

Results and discussion

In the past the Agilent 1100 Series LC system was frequently used for fast and ultra-fast analysis¹. The instrument is very well suited specifically for the analysis of compounds using short 4.6-mm ID column packed with 1.8- μ m particles, and run times below one minute. Cycle times below two minutes were achieved. The Agilent 1200 Series RRLC system is a newly developed LC system with a wider pressure and temperature range, lower system delay volumes and improved noise for the DAD system. Due to these advancements, speed and performance have improved compared to an Agilent 1100 Series LC system, especially for columns with an internal diameter of 2.1 mm.

Experiments using a 4.6-mm ID column

Both instruments were set up in a standard configuration with mixers and 0.17-mm ID flow capillaries installed. Typically the same parameters can be used to optimize an LC method for speed and resolution. These parameters are flow rate, column temperature, gradient profile and other instrument-specific parameters such as switching the autosampler delay volume out of the flow path after the sample has reached the top of the column (ADVR=automatic delay volume reduction). Gradient changes can therefore reach the column much faster. A typical example of how a fast method can be developed is given in figure 1. The objective is to achieve fast cycle times and a minimum resolution of 2 for all peaks.




Figure 1
Method development of an ultra fast LC method.

Chromatographic conditions:

Test sample:	Set of 9 compounds; 100 ng/μL each; dissolved in water/ACN (65/35) 1. Acetanilide, 2. Acetophenone, 3: Propiophenone, 4. Butyrophenone, 5. Benzophenone, 6.Valerophenone, 7. Hexanophenone, 8. Heptanophenone, 9. Octanophenone
Column:	50 x 4.6 mm ZORBAX SB C-18, 1.8 μm for 600 bar operation
Pump:	Solvent A: H ₂ O + Solvent B: ACN Gradient: 35 to 95 % B using different profiles
Autosampler:	Injection volume: 1 μL Wash 5 sec for needle exterior flush out factor 20
Thermostatted column compartment:	Temperature: different temperatures
Diode array detector	B and diode-array detector SL:
	Signal: 245/10 nm Ref 450/100 nm

Optimization of all of the above-mentioned parameters on both systems resulted in the chromatograms shown in figure 2. The pressure limit of 400 bar on the Agilent 1100 Series LC system restricts the maximum possible flow. 5 mL/min flow was not possible, even though the column temperature was set to 80 °C, which is the upper limit for the 1100 Series column compartment. The Agilent 1200 Series RRLC system can be operated with up to 600 bar and up to 100 °C. Applying a flow rate of 5 mL/min can be done without reaching the 600 bar pressure limit at elevated temperatures. In addition, due to design changes, the noise level of the Agilent 1200 Series DAD SL has significantly improved compared to the Agilent 1100 Series DAD B.

The performance for both systems is shown in table 1.

Resolution and noise have improved with the Agilent 1200 Series RRLC system, whereas run and cycle times are comparable. The noise level of the 1200 Series RRLC system can be further reduced using the post column cooling device². The device adapts the temperature of the column effluent to the temperature of the optical unit. This further reduces the noise level, especially if high flow rates and high temperatures are used. Another possibility to reduce cycle time is to enable the overlapped injection features, which is possible with both systems.




Figure 2
Standard Agilent 1200 Series RRLC system vs. Agilent 1100 Series LC system: analysis of phenone mix on 4.6-mm ID column packed with 1.8- μ m particles.

Chromatographic conditions:

Test sample:	Set of 9 compounds, 100 ng/ μ L each, dissolved in water/ACN (65/35) 1. Acetanilide, 2. Acetophenone, 3. Propiophenone, 4. Butyrophenone, 5. Benzophenone, 6. Valerophenone, 7. Hexanophenone, 8. Heptanophenone, 9. Octanophenone
Column:	50 x 4.6 mm ZORBAX SB C-18, 1.8 μ m for 600 bar operation
Pump:	Solvent A: H ₂ O, Solvent B: ACN Gradient: 35 to 95 % B in 0.3 min
Autosampler:	Injection volume: 1 μ L Wash 5 sec for needle exterior, flush-out factor 20
Thermostatted column Compartment:	Temperature: 80 °C
Detector DAD B and DAD SL:	Signal: 245/10 nm Ref 450/100 nm

Parameter	Standard 1100 Series 80 °C 4.8 mL/min	Standard 1200 Series 80 °C 5 mL/min
Flow rate	4.8 mL/min	5 mL/min
Run time	0.60 min	0.60 min
Cycle time	1 min 37 sec	1 min 37 sec
Rs Peak 5	2.22	2.30
PW1/2 peak 9	0.00378 min	0.00375 min
PW1/2 peak 1	0.00458 min	0.00486 min
Noise PtoP	6.2021 mAU	0.7930 mAU
Backpressure	376 bar	448 bar
Injection volume	1 μ L	1 μ L
DAD data rate	20 Hz, path 10 mm	80 Hz, path 10 mm

Table 1
Performance comparison for 4.6-mm ID column.

Furthermore, column switching valves can be installed in the ovens, which provides even higher sample throughput using 2 columns for analysis. A sample is analyzed on the first column, while the second column is regenerated using a second pump. If the analysis on the first column is completed, the next injection can be immediately performed on the previously equilibrated second column.

Experiments using 2.1-mm ID column

Columns with an internal diameter of 2.1 mm and lower have high demands regarding low delay volumes and dispersion volumes before and after the column. Using columns with an internal diameter of 2.1 mm, the Agilent 1100 Series binary LC system must be optimized without using a mixer or only a mixer with a significantly smaller volume and capillaries with smaller IDs for all flow connections. Nevertheless, cycle times below 2 minutes could barely be achieved using columns packed with 1.8 μm particles and 50 mm length. This was mainly due to the pressure limitation of 400 bar for the Agilent 1100 Series LC system. In addition, the delay volume of the 1100 Series LC system is a drawback for fast run and equilibration times. With the introduction of the Agilent 1200 Series RRLC system this gap was closed. Now using narrow bore columns packed with 1.8- μm particles, run times below 0.5 min are possible, with higher flow rates and

elevated temperatures. Both systems are compared using the same column and optimized instrument configurations. To allow for optimized conditions for both systems, the following set-ups were used:

Configuration of the Agilent 1100 Series LC system:

- The mixer was replaced by a short capillary with an internal diameter of 0.12 mm (Agilent part number G1312-67301)
- Seat and seat capillary were replaced by 0.12-mm ID parts (well-plate seat, Agilent part number G1367-87104, and seat capillary, Agilent part number G1313-87103)
- The capillary from the injector to the column compartment was replaced with a 0.12-mm ID capillary (Agilent part number 01090-87610)
- The 0.17-mm ID capillary from the column compartment to the column was exchanged with a capillary with an internal diameter of 0.12 mm (Agilent part number G1316-87303)
- The column was connected to the detector using the detector inlet capillary.
- A 1.7- μL cell with a path length of 6 mm was used as the detector cell.

Configuration of the Agilent 1200 Series RRLC system:

- The low delay volume configuration for the pump was set up with a 120- μL delay volume (mixer and damper were moved out of the flow path).
- Two flow capillaries were replaced with 0.12-mm ID capillaries, all included in the Agilent 1200 Series low dispersion kit (Agilent part number G1316-68744).
- The seat capillary was also replaced with a 0.12-mm ID capillary (included in kit Agilent part number G1316-68744)
- The DAD SL 2 μL flow cell with a 3-mm path length was used. The inlet capillary was directly connected to the column outlet.

The same 2.1 x 50 mm column was used for both systems. The flow rate was set so that the back-pressure was close to the limit of each system. Automated delay volume reduction (ADVR) was selected in the injector setup screen for both systems. The injection volume was set to 1 μL for the Agilent 1100 Series LC system, and to 2 μL for the Agilent 1200 Series RRLC system to compensate for the lower path length of the 1200 Series 2- μL flow cell.

In figure 3 an overlay of the chromatograms obtained from both systems is shown. In table 2 the performance for both system is recorded.

The chromatograms in figure 3 clearly demonstrate the advantages of the Agilent 1200 Series RRLC system, using 2.1-mm ID columns, packed with 1.8- μ m particles. Faster run times and cycle times are possible, due to the fact that higher flow rates can be obtained with the Agilent 1200 Series RRLC system. Table 2 indicates that the cycle time for the Agilent 1200 Series RRLC system is only half that of the Agilent 1100 Series LC system. In addition, the resolution of the 5th peak and also peak width at half height is significantly improved at higher flow rates.




Figure 3
Analysis performed with a 2.1-mm ID column with the optimized Agilent 1200 Series RRLC system and the optimized Agilent 1100 Series LC system using automated delay volume reduction for both systems.

Chromatographic conditions:

Test sample: Set of 9 compounds, 100 ng/ μ L each, dissolved in water/ACN (65/35)
1. Acetanilide, 2. Acetophenone, 3. Propiophenone, 4. Butyrophenone,
5. Benzophenone, 6. Valerophenone, 7. Hexanophenone, 8. Heptanophenone,
9. Octanophenone

Column: 50 x 2.1 mm ZORBAX SB C-18, 1.8 μ m for 600 bar operation

Pump: Solvent A: H₂O, Solvent B: ACN
Gradient: 35 to 95 % B in 0.3 min

Autosampler: Injection volume: 1 and 2 μ L
Wash 5 sec for needle exterior, flush out factor 20

Thermostatted column compartment:
Temperature: 80 and 95 $^{\circ}$ C

Detector DAD B and DAD SL:
Signal: 245/10 nm Ref 450/100 nm

Parameter	1100 Series, optimized, no mixer, ADVR, 80 $^{\circ}$ C	1200 Series, optimized, low delay volume configuration, ADVR, 95 $^{\circ}$ C
Flow rate	1.2 mL/min	2.2 mL/min
Run time	0.65 min	0.38 min
Cycle time	2 min 33 sec	1 min 16 sec
Rs Peak 5	1.86	2.15
PW1/2 peak 9	0.00556 min	0.00328 min
PW1/2 peak 1	0.00729 min	0.0049 min
Noise PtoP	0.1 mAU	0.2 mAU
Backpressure	370 bar	570 bar
Injection volume	1 μ L	2 μ L
DAD data rate	20 Hz, path 6 mm	80 Hz, path 3 mm

Table 2
Performance comparison using a 2.-mm ID column.

Conclusions

Faster method development for faster LC methods is a requirement that can be met with state-of-the-art LC equipment. Even though conventional LC equipment can also provide fast methods, better performance and time savings can be obtained on specially designed LC systems with wider pressure and temperature ranges. Predominantly with 2.1-mm ID columns, where typically lower flow rates are used than on 4.6-mm ID columns, an LC system like the Agilent 1200 Series RRLC system provides significantly lower delay volumes. Shorter run times and shorter equilibration times, and consequently shorter cycle times and more sample throughput are obtained.

References

1. Anabel Fandino, "Ultra-fast liquid chromatography using the Agilent 1100 Series HPLC system and 1.8- μ m ZORBAX SB C18 Rapid Resolution HT columns", *Agilent Application Note, publication number 5989-1603EN*, **2004**.
2. A.G.Hüsken, "Agilent 1200 Series column compartment SL with temperature control up to 100 °C and post-column cooling for lowest baseline noise", *Agilent Application Note, publication number 5989-5034EN*, **2006**.

*Angelika Gratzfeld-Huesgen is
Application Chemist at Agilent
Technologies, Waldbronn.
Germany.*


www.agilent.com/chem/1200rr

© Agilent Technologies, 2006

Published October 1, 2006
Publication Number 5989-5672EN



Agilent Technologies



Improving the Effectiveness of Method Translation for Fast and High Resolution Separations

Application

Author

Michael Woodman
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The increased availability of sub-2-micron (STM) columns and increased demand for methods friendly to mass spectrometers has led to strong trend toward conversion of existing HPLC methods to smaller diameter and smaller particle size columns. While the conversion is a simple mathematical exercise requiring the scaling flow rates, gradient times and injection volumes, many users observe less than perfect results. Here we look closely at the problem and propose calculations that improve the speed and/or resolution in a more predictable and beneficial way.

Introduction

Methods developed on older columns packed with large 5- or 10- μm particles are often good candidates for modernization by replacing these columns with smaller dimension columns packed with smaller particle sizes. The potential benefits include reduced analysis time and solvent consumption, improved sensitivity and greater compatibility with mass spectrometer ionization sources.

Simplistically, a column of 250-mm length and containing 5- μm particles can be replaced by a 150-mm length column packed with 3- μm particles. If the ratio of length to particle size is equal, the two columns are considered to have equal resolving power. Solvent consumption is reduced by L_1/L_2 , here about 1.6-fold reduction in solvent usage per analysis. If an equal mass of analyte can then be successfully injected, the sensitivity should also increase by 1.6-fold due to reduced dilution of the peak as it travels through a smaller column of equal efficiency.

LC/MS (Liquid Chromatography/Mass Spectrometry) ionization sources, especially the electrospray ionization mode, have demonstrated greater sensitivity at lower flow rates than typically used in normal LC/UV (UltraViolet UV/VIS optical detection) methods, so it may also be advantageous to reduce the internal diameter of a column to allow timely analysis at lower flow rates. The relationship of flow rate between different column diameters is shown in Equation 1.

$$\text{Flow}_{\text{col. 1}} \times \left[\frac{\text{Diam. column 2}}{\text{Diam. column 1}} \right]^2 = \text{Flow}_{\text{col. 2}} \quad (\text{eq. 1})$$

The combined effect of reduced length and diameter contributes to a reduction in solvent consumption and, again assuming the same analyte mass can be injected on the smaller column, a proportional increase in peak response. We normally scale the injection mass to the size of the column,



Agilent Technologies

though, and a proportional injection volume would be calculated from the ratio of the void volumes of the two columns, multiplied by the injection volume on the original column.

$$\text{Inj. vol.}_{\text{col. 1}} \times \left[\frac{\text{Volume}_{\text{column2}}}{\text{Volume}_{\text{column1}}} \right] = \text{Inj. vol.}_{\text{col. 2}} \quad (\text{eq. 2})$$

For isocratic separations, the above conditions will normally result in a successful conversion of the method with little or no change in overall resolution. If one wishes to improve the outcome of the method conversion, though, there are several other parameters that should be considered. The first of these parameters is the column efficiency relative to flow rate, or more correctly efficiency to linear velocity, as commonly defined by van Deemter [1] and others, and the second is the often overlooked effect of extracolumn dispersion on the observed or empirical efficiency of the column.

Van Deemter observed and mathematically expressed the relationship of column efficiency to a variety of parameters, but we are most interested here in his observations that there is an optimum linear velocity for any given particle size, in a well-packed HPLC column, and that the optimum linear velocity increases as the particle size decreases. Graphically, this is often represented in van Deemter plots as shown in Figure 1, a modified version of the original plot [2].

In Figure 1 we observe that the linear velocity at which 5- μm materials are most efficient, under the conditions used by the authors, is about 1 mm/sec. For 3.5- μm materials the optimum linear velocity is about 1.7 mm/sec and has a less distinct opti-

um value, suggesting that 3.5- μm materials would give a more consistent column efficiency over a wider flow range. For the 1.8- μm materials, the minimum plate height, or maximum efficiency, is a broad range beginning at about 2 mm/sec and continuing past the range of the presented data. The practical application of this information is that a reduction in particle size, as discussed earlier, can often be further optimized by increasing the linear velocity which results in a further reduction in analysis time. This increase in elution speed will decrease absolute peak width and may require the user to increase data acquisition rates and reduce signal filtering parameters to ensure that the chromatographic separation is accurately recorded in the acquisition data file.

The second important consideration is the often overlooked effect of extracolumn dispersion on the observed or empirical efficiency of the column. As column volume is reduced, peak elution volumes are proportionately reduced. If smaller particle sizes are also employed there is a further reduction in the expected peak volume. The liquid chromatograph, and particularly the areas where the analytes will traverse, is a collection of various connecting capillaries and fittings which will cause a measurable amount of bandspreading. From the injector to the detector flow cell, the cumulative dispersion that occurs degrades the column performance and results in observed efficiencies that can be far below the values that would be estimated by purely theoretical means. It is fairly typical to see a measured dispersion of 20 to 100 μL in an HPLC system. This has a disproportionate effect on the smallest columns and smallest particle sizes, both of which are expected to yield the smallest




Figure 1. van Deemter plot with various flow rates and particle sizes.

possible peak volumes. Care must be taken by the user to minimize the extracolumn volume and to reduce, where practical, the number of connecting fittings and the volume of injection valves and detector flow cells.

For gradient elution separations, where the mobile phase composition increases through the initial part of the analysis until the analytes of interest have been eluted from the column, successful method conversion to smaller columns requires that the gradient slope be preserved. While many publications have referred to gradient slope in terms of % change per minute, it is more useful to express it as % change per column volume. In this way, the change in column volume during method conversion can be used to accurately render the new gradient condition. If we think of each line of a gradient table as a segment, we can express the gradient by the following equation:

$$\% \text{ Gradient slope} = \left[\frac{(\text{End}\% - \text{Start}\%)}{\#\text{Column volumes}} \right] \quad (\text{eq. 3})$$

Note that the use of % change per column volume rather than % change per minute frees the user to control gradient slope by altering gradient time and/or gradient flow rate. A large value for gradient slope yields very fast gradients with minimal resolution, while lower gradient slopes produce higher resolution at the expense of increased solvent consumption and somewhat reduced sensitivity. Longer analysis time may also result unless the gradient slope is reduced by increasing the flow rate, within acceptable operating pressure ranges, rather than by increasing the gradient time.

Resolution increases with shallow gradients because the effective capacity factor, k^* , is increased. Much like in isocratic separations, where the capacity term is called k' , a higher value directly increases resolution. The effect is quite dramatic up to a k value of about 5 to 10, after which little improvement is observed. In the subsequent examples, we will see the results associated with the calculations discussed above.

Experimental Conditions

System

Agilent 1200 Series Rapid Resolution LC consisting of:
 G1379B micro degasser
 G1312B binary pump SL
 G1367C autosampler SL, with thermostatic temperature control
 G1316B Thermostatted column compartment SL
 G1315C UV/VIS diode array detector SL, flow cell as indicated in individual chromatograms
 ChemStation 32-bit version B.02.01

Columns

Agilent ZORBAX SB-C18, 4.6 mm × 250 mm, 5 μm
 Agilent ZORBAX SB-C18, 3.0 mm × 150 mm, 3.5 μm

Mobile phase conditions

Organic solvent: Acetonitrile
 Aqueous solvent: 25 mM phosphoric acid in Milli-Q water

Gradient Conditions

Gradient slope: 7.8% or 2.3% per column volume, as indicated. See individual chromatograms for flow rate and time

Sample


Standard mixture of chlorinated phenoxy acid herbicides,
 100 μg/mL in methanol

Results

The separation was initially performed on a standard 4.6 × 250 mm, 5-μm ZORBAX SB-C18 column thermostatted to 25 °C (Figure 2) using conditions referenced in US EPA Method 555. The method was then scaled in flow and time for exact translation to a 3.0 × 150 mm, 3.5-μm column (Figure 3). Solvent consumption is reduced from 60 mL to 15.5 mL per analysis.

The separation was then re-optimized for faster separation with the identical slope, 7.8%, by increasing the flow rate from 0.43 to 1.42 mL/min, and proportionately reducing the gradient time (Figure 4). Finally, increased resolution is demonstrated by keeping the original times used in Figure 3 with the increased flow rate (Figure 5). This yields a gradient with identical time but a reduced slope of 2.3%. The increased resolution of peaks 4 and 5 is readily apparent.

The conditions in Figure 4, 7.8% slope at increased linear velocity on 3.0 × 150 mm, 3.5-μm material, yield a separation with comparable resolution to the original 4.6 × 250 mm method, but with only a 12-minute total analysis time. This is excellent for



Conditions

EPA Method 555 with ZORBAX SB-C18 columns and fast DAD detector

ZORBAX SB-C18 4.6 mm × 250 mm, 5 μm

Column temp: 25 °C

Gradient: 10% to 90% ACN vs. 25 mM H₃PO₄

Gradient slope: 7.8% ACN/column volume


Analysis flow rate: 1 mL/min

Group A Compounds

Total analysis time: 60 min

Detection: UV 230 nm, 10-mm 13-μL flow cell, filter 2 seconds (default)

Figure 2. Gradient separation of herbicides on 4.6 250 mm 5-μm ZORBAX SB-C18.



Conditions:

EPA Method 555 with ZORBAX SB-C18 columns and fast DAD detector

ZORBAX SB-C18 3.0 mm × 150 mm, 3.5 μm

Column temp: 25 °C

Gradient: 25 mM H₃PO₄/ACN, 0% to 90% ACN in 18 minutes

Gradient slope: 7.8% ACN/column volume

Analysis flow rate: 0.43 mL/min

Detection: UV 230 nm, 3-mm 2-μL flow cell, filter 0.2 seconds

Total analysis time: 36 min.

Figure 3. Gradient separation of herbicides on 3.0 150 mm, 3.5-μm ZORBAX SB-C18.




Figure 4. High speed gradient separation of herbicides on 3.0 150 mm, 3.5-μm ZORBAX SB-C18.




Figure 5. Reduced slope gradient separation of herbicides on 3.0 150 mm, 3.5-μm ZORBAX SB-C18.

high throughput screening and quantitation of a large number of samples. Figure 5, with the gradient slope reduced to 2.3%, results in a high-resolution separation with a calculated R value of 3.3 vs. the standard 3.0×150 mm separation value of 1.9, for the critical pair seen in Figure 5 at 7.5 to 8 minutes.

In Table 1 the column has been replaced with a low dead volume connecting union in a system fitted with 0.12-mm id capillary tubing at all points of sample contact. A 1- μ L injection of dilute actone

Table 1. Volumetric Measurements of Various Flow Cells

Flow cell	Elution volume (μ L)	Half height width (μ L)	5 Sigma width (μ L)
New SL 2 μ L 3 mm	11	5	12
Micro 6 mm 1.7 μ L (n = 2)	14	6	18
Semi-micro 6 mm 5 μ L (n = 2)	13	6.5	18.5
Standard 10 mm 13 μ L	26	11	26
New SL 10 mm 13 μ L	27	11	25

is made to determine the bandspreading contribution of the system, with various flow cells. Multiple flow cells were tested, and the average result reported, where possible. The elution volume summarizes the total volume of all tubing in the system. While the absolute volume from the 2- μ L to the 13- μ L flow cells is 11 μ L, we observe an increase of 15 to 16 μ L because of the larger diameter inlet tubing integral to the larger volume flow cells.

Conclusion

Careful analysis of the existing gradient conditions, coupled with an awareness of the need to accurately calculate new flow and gradient conditions can lead to an easy and reliable conversion of existing methods to new faster or higher resolution conditions. In addition, awareness of extracolumn dispersion, especially with small and high resolution columns, will ensure good column efficiency which is critical to a successful translation of the method.

References

1. J. J. van Deemter, F. J. Zuiderweg, A. Klinkenberg, Chemical Engineering Science 1956, 5, 271–289
2. The Influence of Sub-Two Micron Particles on HPLC Performance, Agilent Technologies, application note 5989-9251EN, May 2003

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
August 9, 2006
5989-5177EN




Agilent Technologies



Agilent 1200 Series Rapid Resolution LC system and the Agilent 6210 TOF MS – Highest data content with highest throughput

Application Note

Michael Frank



Abstract

Fast and unambiguous determination of purity and identity of compounds derived from screening libraries is a common task for many analytical labs in the pharmaceutical industry. The method of choice to determine the identity of compounds is mass spectrometry, preferably with accurate mass. As yet, data quality was usually compromised by gaining higher throughput. This Application Note demonstrates how a daily throughput of far more than 1000 samples can be achieved together with full spectral data acquisition and accurate mass information with close to FT-MS mass accuracy.



Agilent Technologies

Introduction

In the quest to achieve highest throughput in LC/MS analyses, the quality of the data is often compromised. There are certain approaches to increase the throughput of LC/MS systems. One approach is to do flow injection analysis. This probably delivers the highest possible throughput, however since no chromatographic separation occurs, the probability to lose compounds by the ion suppression effect during the ionization process is high. Orthogonal detection methods like UV detection do not succeed at all in flow injection analysis as all compound signals are overlaid. Approaches to achieve at least minimal chromatographic separation by using very short columns with 5 μm particles and ballistic gradients are an improvement in view of data quality, however, not state-of-the-art. Some manufacturers have established parallel working instrumentation with a shared mass spectrometer and shared UV detector. Obviously, this also compromises data quality as the full acquisition rate of each instrument has to be shared on each LC channel¹.

With the introduction of an LC/MS system which facilitates the use of columns with sub two micron particles it is now possible to achieve short analyses times as well as high chromatographic resolution. Furthermore the system is able to acquire full UV spectral data and mass spectral data with accurate masses.

Experimental

The Agilent 1200 Series Rapid Resolution LC system is set up for alternating column regeneration (ACR)² using 2.1-mm id columns. The pumps are in the low delay volume configuration with an internal volume of only ca. 120 μL . All other modules are optimized for lowest delay volumes by using the low delay volume capillary kit (G1316-68744) and the alternating column regeneration kit (G1316-68721). Consequently, from the injection valve on only capillaries of 0.12 mm id are used. In the thermostatted column compartment the newly introduced low dispersion heat exchangers consisting of 1.6 μL internal volume have been used as well as the high pressure rated 2-position/10-port valve.

The instrument set-up is shown in figure 1:

- Two Agilent 1200 Series binary pumps SL with the new Agilent 1200 Series micro vacuum degasser placed between the two pumps eliminates the need for long tubing to the pumps.

- Agilent 1200 Series high performance autosampler SL.
- An Agilent 1200 Series thermostatted column compartment SL, equipped with a high pressure, 2-position/10-port valve, facilitating alternating column regeneration.
- An Agilent 1200 Series diode-array detector SL allowing a data acquisition rate of 80 Hz and equipped with a 500 nano liter flow cell with 0.12-mm id connecting capillaries.
- Agilent 6210 Time-of-Flight mass spectrometer allowing a maximum data acquisition rate of 40 Hz and equipped with a dual ESI source for parallel ionization of the analyte and a reference mixture.
- Two ZORBAX SB C18, 2.1 mm id x 50 mm, 1.8 μm columns
- As mobile phase gradient grade water with 0.1 % trifluoro acetic acid and acetonitrile with 0.08 % trifluoro acetic acid was used. No additional filtering of the solvents was made.




Figure 1
Agilent 1200 Series Rapid Resolution LC system with Agilent 6210 TOF-MS with low delay volume for high speed applications using 2.1-mm id columns with lengths ranging from 20 to 50 mm.

Instrument control and data acquisition was done by the Agilent TOF-software A02.01 running on a Hewlett-Packard xw 4300 workstation with an Intel dual core Pentium™ D840 CPU at 3.2 GHz.

Results and discussion

By applying elevated temperatures the viscosity of the solvent can be reduced which allows higher flow rates and therefore shorter gradient times. A maximum temperature of 80 °C was applied, which allowed a flow rate of 1.8 mL/min without hitting the pressure limit of the pump. This results in a linear velocity of approximately 11 mm/s for the 2.1 mm x 50 mm column (1.8 µm). With the help of the regeneration pump and the 2-position/10-port valve in the column compartment cycle times could be reduced significantly because one column is flushed with high organic content solvent and then re-equilibrated again with the starting composition of the gradient while on the second column the separation of a sample occurs. After this sequence the 10-port valve is switched and both columns are exchanged in the flow path. Details of alternating column regeneration and the correct setting of time points are described in another Application Note². Despite the high flow rate (1.8 mL/min), the column effluent was not split prior to reaching the mass spectrometer. The standard ESI source specifies a maximum flow rate of up to 1 mL/min, however even these higher flows are tolerated if the drying gas temperature and flow rate are set to maximum and little condensation occurs. Condensation of water is practically eliminated when using ACR because equilibration is done on the column which

Data File	Sample Type	Inj Vol (µl)	Capillary	Fragmentor	Skimmer
opt_4000_215_60.wiff	Unknown	1	4000	210	60
opt_4000_215_60.wiff	Unknown	1	3000	210	60
opt_4000_215_60.wiff	Unknown	1	2000	210	60
opt_4000_215_60.wiff	Unknown	1	4000	180	60
opt_4000_215_60.wiff	Unknown	1	3000	180	60
opt_4000_215_60.wiff	Unknown	1	2000	180	60
opt_4000_215_60.wiff	Unknown	1	4000	150	60
opt_4000_215_60.wiff	Unknown	1	3000	150	60
opt_4000_215_60.wiff	Unknown	1	2000	150	60
opt_4000_215_60.wiff	Unknown	1	4000	210	40
opt_4000_215_60.wiff	Unknown	1	3000	210	40

Figure 2
Feature of the TOF software to modify the MS parameter from run to run.

Method:			
Solvent:		A = water (0.1% TFA), B = ACN (0.08% TFA)	
Temperature:		80 °C	
Flow:		1.8 mL/min	
Gradient:		0.00 min 5%B	Regeneration: 0.00 min 5%B
		0.50 min 90%B	0.01 min 95%B
		0.51 min 5%B	0.20 min 95%B
		0.65 min 5%B	0.21 min 5%B
			0.65 min 5%B
Stoptime:		0.65 min	no limit
Posttime:		off	off
DAD:		Wavelength: 210 nm (8), ref. off	
		Peak width: >0.0025 min (0.05s responsetime), 80 Hz	
		Spectra: no	
		Slit: 8 nm	
		Balance: pre-run	
MS:		Scan range: 100-1000 m/z	
		Acquisition rate: 5, 20, 30 and 40 cycles/s	
		Data type: profile data	
		Capillary voltage: 3000 V	
		Fragmentor: 180 V	
		Skimmer: 40V	
		Gas temperature: 350 °C	
		Gas flow: 13 L/min	
Injection volume:		1 µL	
Injector:		Overlapped injection, Automatic delay volume reduction, Sample flush out factor = 10	
Valve position:		Next position	

Table 1
LC/MS method used for the data shown in figures 3-5. The method was also used to achieve the values in table 2.

is not connected to the detector. Generally the use of an Agilent multi mode source with a specified flow rate up to 2 mL/min even with pure water is recommended. The chromatographic conditions in table 1 were used to achieve gradient times of 0.5 min. Under these conditions, the peak capacity for the MS detection is in the range of >40 in 39 s. With the use of a 5-µm particle size column of the same dimension the peak capacity would only be half!

The detector of the Agilent 6210 TOF MS would be saturated if the compound concentrations used here to give also significant UV signals would be injected into the MS without special settings. Saturation of the MS detector would produce incorrect results in mass determination. The solution is to intentionally desensitize the TOF MS. This can be done quite easily by applying the functionality of the TOF software to alter the MS parameters from one run to the other,

simply by adding one or more “MS-parameter” columns to the worklist (figure 2). Select “add columns” from the worklist and then chose “MS-parameter” and the desired parameter. As the reference mixture is also affected by these settings, the concentration of the reference mixture was increased. Only the capillary voltage, the fragmentor voltage and the skimmer voltage were varied. The optimal conditions determined by this approach can be found in the method parameters in table 1.

In figure 3 the total ion chromatogram and the UV chromatogram achieved with conditions above (80 Hz DAD, 30 Hz TOF data acquisition rate) is shown for a five-component sample (58 ng/μL atenolol, 85 ng/μL primidon, 62 ng/μL metoprolol, 125 ng/μL verapamil and 75 ng/μL beclomethasone-dipropionat). The peaks of the total ion chromatogram are inherently broader than the peaks of the UV chromatogram because of additional extra column volume from the flow cell and also from connecting the capillary between the UV detector and ESI interface. But as can be seen in figure 3, the additional peak broadening of the MS peaks is only minor. The peak widths at half height of the MS peaks obtained under the highest data acquisition rate (40 Hz) are shown in figure 4 with values from as little as 0.34 to 0.42 s. The chromatograms shown in figure 5 were produced under the same chromatographic conditions, but with different data acquisition rates of the time-of-flight MS. The peak form and resolution are improved by having high data acquisition




Figure 3
Comparison of corresponding peaks in the UV (red trace) and the MS detection (black trace).




Figure 4
MS total ion chromatogram of highest speed LC-TOF-MS analysis (40 Hz TOF data acquisition rate).

rates in the MS which shows clearly in figure 5. The effect is nicely demonstrated on the little side peak next to the primidon peak – with 40-Hz data acquisition rate it is obvious that an additional compound shows up but with 5 Hz data acquisition rate this could not be differentiated from tailing of the primidon! The advantage, especially if MS quantization is necessary, is clear.

By applying the chromatographic conditions of table 1 and 80 Hz signal data acquisition of one wavelength and 30 Hz TOF centroid data, a cycle time of 49 s was achieved. The achievable cycle time is not only dependent on the used run time (that is the gradient time plus additional flush and re-equilibration times, or in Agilent terminology the stop time plus post time) but also very much dependent on the instrument overhead time. This is usually caused by communication between the data system and the individual LC/MS modules as well as the data system writing data to the hard disc and initiating certain processes. The overhead time caused by the data system can be significant if the computer's performance is not sufficient to handle the data amount or if other software programs or processes are consuming the power available. To decrease the cycle time it might be worth decreasing the amount of data acquired.

Table 2 shows the cycle times and the possible daily throughput depending on the DAD and MS settings. Since the MS data are constantly written to the hard disc during data acquisition, whereas the UV data are buffered and added to the data file after the stop time of




Figure 5
Total ion chromatograms recorded with varying data acquisition rates – dependence of the MS peak shape and resolution on the data acquisition rate.

DAD (80 Hz)		TOF (100 – 1000 Da)		Cycletime	Throughput	
Type	Wavelength	Centroide	Profile	Data rate [Hz]	[s]	[Samples/day]
spectral	190-900 (1)		x	20	62	1394
spectral	190-900 (1)	x		20	62	1394
spectral	190-400 (2)		x	20	59	1464
spectral	190-400 (2)		x	40	59	1464
spectral	190-400 (2)		x	30	58	1490
signal	210/254		x	20	50	1728
signal	210	x		30	49	1763

Table 2
Dependence of the cycle time on the DAD and MS data acquisition settings, method stop-time was 0.65 min (39 s), pre-run balance was applied (ca. 2 s). The number in brackets for the DAD wavelength range stands for the scan width in nm.

the method, the cycle time depends more on the UV data amount than on the MS data amount. The cycle time was calculated from the time stamp each file gets assigned from the WindowsXP™ operating system after closing the file following data acquisition.

If using a TOF MS the attention is certainly focused on the accurate mass. The question may arise if the possibility to obtain low mass accuracy errors might suffer from these high speed conditions. Figure 6

shows the achieved mass accuracy errors of the analysis of 140 members of a chemical library used in a screening campaign by a pharmaceutical company. The shown error-values have been extracted from an automated empirical formula confirmation report and involved no manual interference. Sixteen of the compounds could not be ionized under positive ESI conditions and two compounds showed large mass errors of 11 and 15 ppm, probably caused by co-eluting isobaric impu-

rities. The cycle time was 90 s and was determined by a required injector program which allowed an on-line dilution of the samples directly prior to the analysis. Chromatographic conditions applied a 5-100 % water-acetonitrile (0.1 % TFA) gradient in 0.7 min at a flow rate of 1.5 mL/min and 60 °C column temperature. UV data acquisition to determine purity was done in the wavelength range of 210 to 500 nm with an acquisition rate of 80 Hz. The MS data acquisition rate was at 8 Hz to reduce the file size. The scan range was 120 – 1200 Da, capillary voltage 4000 V and the fragmentor voltage at 215 V. No ACR was applied and the flow to the MS was splitted in a 1:7.5 ratio.

More compelling is the histogram of the mass errors of these samples as shown in figure 7. More than 91 % of the ionizable compounds (outliers included) have a mass accuracy error in the range of ± 2.0 ppm. Excluding the outliers even 93 % of the analyzed samples lie in-between the ± 2.0 ppm range. In the ± 1.0 ppm range which is FT-MS-like mass accuracy 71 % of the samples can be found (72 % excluding the outliers).




Figure 6
Mass accuracy errors of the analyses of a set of chemical library members under fast-LC conditions.




Figure 7
Histogram of the mass accuracy errors of the analyses of a set of chemical library members under fast LC conditions. The given populations of the ± 1.0 ppm and ± 2.0 ppm range include the outliers.

Conclusion

The Agilent 1200 Series Rapid Resolution LC system together with the Agilent 6210 Time-of-Flight mass spectrometer allows acquisition of a wealth of data to unambiguously determine the purity and identity of compounds in samples as they are typical for the high throughput analytical departments of pharmaceutical companies. In the time range of one minute high chromatographic resolution, full spectral diode-array data from 190-900 nm wavelength in a band width of 1 nm at an 80 Hz acquisition rate plus full MS spectral data from 100-1000 m/z with high acquisition rate and with an accurate mass with a mass error below ± 2.0 ppm for more than 91 % of the samples could be acquired.

Using features like alternating column regeneration, overlapped injection, high temperatures, high flow rates together with highest data acquisition rates and most importantly stable and easy-to-use accurate mass, this system outperforms other high throughput LC/MS techniques used as yet in throughput and/or data quality. The linear velocities achieved were in the range of 11 mm/s and cycle times were as fast as 49 s for a run time of 41 s. Due to the columns with particle sizes of 1.8 μm , the UV peak capacities were still in the range of fifty and even the MS peak capacities were in the range of forty for a gradient time of 39 s.

References

1.

Jeremy R. Kenseth, Shelly J. Coldiron, "High-throughput characterization and quality control of small-molecule combinatorial libraries", *Curr. Opin. Chem. Biol.* 8; 418-423; **2004**.

Jill Hochlowski, Xueheng Cheng, "Current Application of Mass Spectrometry to Combinatorial Chemistry", *Anal. Chem.* 74, 2679-2690; **2002**.

2.

Udo Huber, "High throughput HPLC – Alternating column regeneration with the Agilent 1100 Series valve solutions" *Agilent Application Note, Publication number 5988-7831EN*; **2002**.

Most of the data herein was presented as a poster, titled "Non-multiplexed DAD-ToF Analysis of 1400 Samples/day" by Michael G. Frank, Edgar Naegele (Agilent Technologies, Waldbronn, Germany), Doug McIntyre (Agilent Technologies, Santa Clara, USA), Thilo A. Fligge, Stefan Buehler, Markus Christ (Boehringer-Ingelheim, Biberach, Germany), CO-1152, at the Pittcon conference 2006 in Orlando, Florida, USA.

Michael Frank is Application Chemist at Agilent Technologies, Waldbronn, Germany.

www.agilent.com/chem/1200rr


The information in this publication is subject to change without notice.

Copyright © 2006 Agilent Technologies, Inc.
All Rights Reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

Published April 1, 2006
Publication Number 5989-4505EN



Agilent Technologies



Achieving fastest analyses with the Agilent 1200 Series Rapid Resolution LC system and 2.1-mm id columns

Application Note

Michael Frank



Abstract

The need to increase the daily throughputs of LC systems is a constant desire. Now, with the Agilent 1200 Series Rapid Resolution LC system highest throughputs are possible, and in combination with the Agilent ZORBAX RRHT columns and the increased pressure and temperature range of the LC system, excellent chromatographic resolution can be achieved even at run times below one minute.

This Application Note describes the correct set-up of the instrument which is the key for optimal results with narrow bore columns, such as a 2.1 mm x 50 mm column packed with sub two micron particles. Peak capacities in the range of fifty in analysis times as short as 24 seconds and peak widths as narrow as 200 milliseconds are shown. The well-balanced use of all possible module options to achieve shortest cycle times with throughputs far beyond 1500 samples per day is described.



Agilent Technologies

Introduction

Particularly analytical service laboratories in the pharmaceutical industry, responsible for analyzing chemical libraries¹ or performing MS based quantifications of certain ADME-properties and drug metabolism studies of drug candidates² are faced with the challenge to increase their throughput, but also to maintain a high chromatographic resolution. In 2003 Agilent Technologies introduced sub two micron particles in their RRHT column series. Because of the small particle size, the chromatographic resolution obtainable with these columns is superior to standard particle sizes such as 3.5 μm or even 5 μm . Due to a unique silica manufacturing process, Agilent ZORBAX RRHT columns show a significantly reduced backpressure, if compared to similar column dimensions of other manufacturers. Excellent chromatographic results are achieved in a very short analysis time with the Agilent 1200 Series Rapid Resolution LC system, which facilitates an increased pressure range and flow rates from 0.05 up to 5 mL/min using column diameters ranging from 2.1-mm id up to 4.6-mm id. This Application Note will focus on 2.1-mm id columns only. Not only are the run times of the analyses important for high throughput, but also the overhead time. The Agilent 1200 Series Rapid Resolution LC system can be optimized to achieve highest throughputs with exceptionally good overall system performance.

Experimental

An important issue when dealing with narrow bore columns, especially in gradient mode where smallest peak widths can be achieved, is to have small extra column volumes. This also includes any volumes in front of the sampling device, because any volume after the solvent mixing point will increase the time for the gradient composition to reach the column. This results in an increased run time. The Agilent 1200 Series Rapid Resolution LC system can be reconfigured within a few minutes to provide appropriate system volumes for different column ids. Here, the pumps are set-up in the low delay volume configuration with an internal volume of approximately 120 μL . All other modules are optimized for lowest delay volumes by using the low delay volume capillary kit (G1316-68744). Consequently, only capillaries of 0.12 mm id are used beyond the injection valve. In the Agilent 1200 Series thermostatted column compartment SL the newly introduced low dispersion

heat exchangers with 1.6 μL internal volume were used. In some experiments, the Agilent 1200 Series Rapid Resolution LC is set up for alternating column regeneration to achieve highest throughput using the ACR-capillary kit (G1316-68721) and 2.1-mm id columns³. The high pressure rated 2-position/10-port valve in the thermostatted column compartment was only placed into the flow path if alternating column regeneration was used indeed.

The instrument set-up is as follows (figure 1):

- Agilent 1200 Series binary pump SL with the new Agilent 1200 Series micro vacuum degasser
- Agilent 1200 Series high performance autosampler SL
- Agilent 1200 Series thermostatted column compartment SL, equipped with a high pressure, 2-position/10-port valve, facilitating alternating column regeneration
- Agilent 1200 Series diode-array detector SL with a 2- μL /3-mm cell
- ZORBAX SB C18, 2.1 mm id x 50 mm, 1.8 μm




Figure 1
System setup with low delay volume for high speed applications using 2.1-mm id columns with lengths from 20 to 50 mm.

The Agilent 1200 Series binary pump SL is designed to fulfill the demands for high throughput, highest performance, optimum resolution and low-pump ripple. The pump hardware is significantly different from the standard binary pump. In the Agilent 1200 Series binary pump SL the pressure transducer is separate from the damper which has been modified to have a lower delay volume (pressure dependent ranging from 80–280 μL). In this study the pumps were used in the low delay volume configuration without the mixer and damper in the flow path. In contrast to the standard binary pump the pump heads of the binary pump SL have an additional damping coil (500 μL volume each) to allow damping in the low delay volume configuration. This does not add to the gradient delay volume because it is before the mixing point. Anyway, pressure ripples are also strongly suppressed by the Electronic Damping Control (EDC). The pressure range of the pump and all other modules is increased to 600 bar.

Only one sample, the so-called “phenone-mix”, was used in the course of this study to keep variations low. The sample consists of nine compounds: acetanilid, acetophenone, propiophenone, butyrophenone, benzophenone, valerophenone, hexanophenone, heptanophenone and octanophenone. Unless otherwise stated, the concentration was 0.1 $\mu\text{g}/\mu\text{L}$ for each compound except butyrophenone which was 0.2 $\mu\text{g}/\mu\text{L}$. The solvent was water-acetonitril 2:1.

Results and discussion

The most frequently sold particle size in chromatographic columns today is 5 μm . Of course, fast and ultra fast LC is also possible with columns packed with particles of these larger diameters – the reduced




Figure 2
Van Deemter curves of columns packed with 1.8 μm , 3.5 μm and 5.0 μm particles.

back pressure is even beneficial to allow higher flow rates. However, resolution will be sacrificed because conditions are usually far on the right side of the van-Deemter-optimum. Here, the big advantage of the RRHT columns with particles of less than 2 μm diameter is proven. The van Deemter optimum is shifted further to the right and the curve is much flatter at the onset because the “resistance of mass transfer” term is diminished (figure 2). In figure 3 the analysis on a 2.1-mm id column with 1.8- μm particles is compared to the linear scaled analysis on the same stationary phase but on 5 μm particles packed in a 4.6-mm id-column. The gain in resolution is obvious – from $R_s = 2.1$ up to $R_s = 3.5$ for the critical pair which matches the theoretically expected value of a 1.66 fold increase in resolution. Also note that there is a saving in solvent consumption of 8.6 mL in the “standard” HPLC analysis and only 1.8 mL in the ultra fast HPLC analysis.

For gradient separation the dependencies of the capacity factor can be expressed as:

$$k^* = 0.87 \cdot tg \cdot \frac{F}{V_m \cdot \Delta\%B \cdot S}$$

(tg = gradient time, F = flow rate, V_m = column void volume, $\Delta\%B$ = gradient steepness, S = solvent and solute dependent factor)

If the product of the gradient time and flow rate, the so-called gradient volume, is kept constant together with all other parameters, the gradient time might be decreased while the flow rate is increased. Thus, the capacity factors of two compounds will stay constant and if no large alteration of the plate height occurs, the resolution will not change significantly, either. The final point is the big advantage of the sub two micron particles – the van-Deemter curve is nearly flat on the right side of the minimum (figure 2) and flow rates can be increased with only little increase in plate heights. However, the equation is an empirical one and deviations may occur especially under extreme conditions.

With a two-step approach, highest gradient speeds with virtually no loss or only little loss in resolution can be achieved. In the first step, start from a medium temperature and begin to increase the flow rate up to the pressure maximum. Subsequently the temperature should be increased to lower the viscosity of the solvent and then the flow rate is increased again. It may be worthwhile to check the resolution with two identical gradients but with different temperatures to see the influence of the temperature change on the resolution which may be very compound dependent. In figure 4 the result of this approach is shown. A nearly 7-fold increase in separation speed could be achieved with still base-line separation of the critical pair before meeting the pressure and temperature limit (the maximum temperature is a function of flow, temperature, number of controlled Peltier elements and of the heat capacity of the solvent used).




Figure 3
Analysis with 1.8- μ m particle column vs. 5.0 μ m particle column.

Conditions: 4.6-mm id column used on standard Agilent 1200 system		
Solvent:	A = Water, B = ACN	
Temperature:	40 °C	
Column:	2.1 mm x 50 mm, 1.8 μm	4.6 mm x 50 mm, 5.0 μm
Flow:	1.0 mL/min	4.8 mL/min (scaled from 2.1 mm col.)
Gradient:	0.00 min 35 %B	0.00 min 35 %B
	0.90 min 95 %B	0.90 min 95 %B
	1.10 min 95 %B	1.10 min 95 %B
	1.11 min 35 % B	1.11 min 35 % B
	1.15 min	1.15 min
Stoptime:	0.70 min	0.70 min
Wavelength:	245 nm (8), ref. 450 nm (100)	245 nm (8), ref. 450 nm (80)
Peakwidth:	>0.0025 min (0.05 s res.time), 80 Hz	>0.01 min (>0.2 s), 20 Hz
Injection volume:	1 μ L	5 μ L (not scaled)

Conditions:	
Solvent:	A = water, B = ACN
Temp.:	40 °C, 80 °C, 95 °C
Flow:	0.35, 0.70, 1.20, 2.00, 2.40 mL/min
Gradient:	0.00 min 35 %B
	2.60 min 95 %B
	3.20 min 95 %B
	3.21 min 35 %B
	<i>Time values for F = 0.35 mL/min.</i>
	<i>For all other flow rates times are scaled so that (tg x F) = 0.90 mL</i>
Stop time:	3.20 min
Post time:	2.00 min
Wavelength:	245 nm (8), Ref. 450 nm (100)
Peak width:	>0.0025 min (0.05 s response time), 80 Hz




Figure 4
Increasing separation speed by increasing temperature and flow rate while decreasing gradient time.

The last chromatogram is enlarged in figure 5 and reveals the details of this separation. The first peak is eluted after only five seconds and peaks with a width at half height of less than 200 ms are achievable. Within twenty-four seconds nine compounds are separated with a peak capacity in the range of fifty.

Retention time precision at highest analysis speed

High analysis speed is meaningless without precision. One basic performance criteria for HPLC pumps is the precision of gradient formation measured by the precision of retention times of repeated gradients. However, the stability of the column temperature must also be taken into consideration, because temperature fluctuations will also influence the retention times of a given sample. In table 1 and figure 6 the results from the 10-fold repeated analysis of a standard sample are listed and since the deviation between individual runs is so small, the octanophenone peak is enlarged in a separate window. This sample contains compounds that are both not retained and refer to isocratically eluted compounds found at the starting conditions of the gradient, as well as highly unpolar and strongly retained compounds. The analyses

Conditions:

Solvent: A = Water, B = ACN
 Temp.: 40 °C, 80 °C
 Flow: 0.35 mL/min, 1.20 mL/min, 2.0 mL/min
 Gradient:
 0.00 min 35%B
 2.60 min 95%B
 3.20 min 95%B
 3.21 min 35%B
*Time values for F = 0.35 mL/min.
 For all other flow rates times are scaled so that (time x flow) = 0.90 mL*
 Stop time: 3.20 min
 Post time: 2.00 min
 Injection vol.: 1.0 µL




Figure 5
Separation of a nine compound mixture under ultra fast conditions.




Figure 6
Overlaid chromatograms of the repeated analysis of a 9 compound mixture under various conditions.

were done at high and low flow rates as well as with high and low temperatures as in the examples shown earlier. In all cases the mean retention time precision is below 0.3 % RSD, which was the specification of the Agilent 1100 Series LC system. Of course, the results are also in line with the specifications for the new Agilent 1200 Series Rapid Resolution LC system which is < 0.07 % RSD or < 0.02 min SD, whichever is met first. At these high gradient speeds, the SD criteria are always met. The RSD criteria are also met for both fast-LC gradients of 2.6 min duration (0.35 mL/min flow rate). Even at ultra-fast gradient speeds, the retention time precisions are still below or only slightly higher than 0.1% RSD (table 1).

Improving the cycle-time

Not only is the gradient speed important when dealing with high-throughput analysis but furthermore the over all cycle time of the entire system, which is the time between two consecutive analyses. A good method to measure the cycle time is by using the time stamp the data file is assigned by the operating system of the computer. Clearly, optimizing the cycle time has some drawbacks. For example, extensive needle cleaning procedures are in contradiction with a high sampling speed. Table 2 gives an overview of important parameters influencing the cycle time. Using 1.8- μ m particle size columns together with an optimized HPLC system very short run times can be achieved without sacrificing chromatographic resolution. Combining short run times together with low overhead times will result in a high daily throughput. In figure 7 the cycle time and daily throughput is shown for two

	0.35 mL/min, 40°C		0.35 mL/min, 80°C		1.20 mL/min, 40°C		2.00 mL/min, 80°C	
	SD	% RSD	SD	% RSD	SD	% RSD	SD	% RSD
Average	0.00107	0.067	0.00084	0.070	0.00048	0.098	0.00031	0.134

Table 1
Standard deviations (mAU) and %RSD (n=10) of the retention times under different chromatographic conditions in temperature and flow.

Module	Parameter	Effect on cycle time	Other effects
Autosampler	Pump	Low delay volume setting	Reduced retention times, run time can be shortened, reduced cycle time
			Increased pressure ripple, slightly increased mixing noise if modifiers such as TFA are used.
	Automatic Delay Volume Reduction (ADVR) – activated	Reduced delay volume, reduced retention times, run time can be shortened, reduced cycle time	Increased carry-over
	ADVR activated and Overlapped Injection (OI)	Enables parallel sampling, thus reduces the cycle time independently of the below listed settings (as long as the overall sampling speed does not exceed the gradient and post time)	Increased carry-over
	no OI – Needle Wash	Increased sampling time with increasing wash time	Reduced carry-over with longer needle wash time
Column compartment	no OI – Equilibration time	Increased sampling time with increased equilibration time	Better injection precision with longer equilibration time
	no OI – Draw/Eject speed	Low speed causes increased sampling time	Low speed results in better injection precision
	Alternating column regeneration	Saves column wash-out and equilibration time, reduces cycle time enormously	Additional hardware required, slightly increased extra column volume, slightly different retention times between columns possible
	Detector	Pre-run and/or post-run balance	Increased cycle time
		Spectral data acquisition with high data rate, small band width and broad wavelength range large data files	Depending on computer power and additional processes running might increase cycle time because of writing speed
Software			Baseline drifts possible if not applied
			Reduced information content if no spectral data acquired or with lower resolution
	Data analysis with acquisition	Increased cycle time, depending on computer power and number of peaks	Data analysis has to be done offline is no set
	Save method with data	Slightly increased cycle time	Information is missing if method is not saved
	Execution of pre-run or post-run macros	Increased cycle time, depending on macro	Depending on macro
System	LC controlled over local network between computer and LC (and MS) only	Faster data and method transfer between computer and LC because of reduced net work traffic reduced cycle time	Additional hardware might be necessary (use independent acquisition computer)
	Number of detectors	More detectors produce a higher data amount and lower the data transfer speed, resulting in higher cycle times	More detectors higher information content

Table 2
Influence of various parameters on the overall cycle time.

different methods – both giving virtually the same resolution. The first method (0.45 min gradient) utilizes alternating column regeneration and high temperatures to allow high flow rates and speed optimized settings. A cycle time of 49 s could be achieved, resulting in a theoretical daily throughput of more than 1700 samples per day. The second method (0.90 min gradient) does not use high temperatures or alternating column regeneration and the time saving of some simple and often forgotten method options are shown. By optimizing these parameters the real cycle time gets as close to 8 s to the run time (stop time plus post time) and allows a daily throughput of more than 700 samples per day. By sub-optimal method set up this can easily drop to below 500 samples per day if options like automatic delay volume reduction, overlapped injection or offline data-analysis are not used.

Conclusion

The Agilent 1200 Series Rapid Resolution LC system is a powerful tool to achieve highest chromatographic resolutions and also highest throughputs. The extended pressure range allows the usage of columns packed with stationary phases with particles sizes below 2 µm, for example, Agilent RRHT columns with particle sizes of 1.8 µm. These columns not only allow an increase in linear flow rates with virtually no loss in resolution but also have an inherently higher resolution compared to 3.5 µm or even 5.0 µm particle sizes. The possibility to switch the pump into its low delay volume configuration allows the use of the entire bandwidth of today's widely used column ids – from 4.6 mm




Figure 7
Cycle time and daily throughput optimization.

Chromatographic conditions:

Alternating Column Regeneration Method

Solvent: A = Water, B = ACN
 Temp.: 80 °C
 Flow: 2.0 mL/min
 ADVR: Yes
 Gradient:

Gradient-Pump

0.00 min 35 %B
 0.45 min 95 %B
 0.46 min 35 %B
 0.57 min 35 %B

Regeneration-Pump

0.00 min 35 %B
 0.01 min 95 %B
 0.11 min 95 %B
 0.12 min 35 %B

Stoptime: 0.57 min
 Posttime: off
 Wavelength: 245 nm (8), ref. 450 nm (100)
 Peak width: > 0.0025 min (0.05 s response time), 80 Hz
 Spectra: none
 Injection volume: 1.0 µL
 Injector: Overlapped injection, 2 s needle wash, sample flush-out factor = 10, draw/eject speed = 100 µL/min

Valve: next position

No Alternating Column Regeneration Method

Solvent: A = Water, B = ACN
 Temp.: 40 °C
 Flow: 1.0 mL/min
 ADVR: Yes
 Gradient:

0.00 min 35 %B
 0.90 min 95 %B
 1.10 min 95 %B
 1.11 min 35 %B

No

0.00 min 35 %B
 0.90 min 95 %B
 1.10 min 95 %B
 1.11 min 35 %B

Stoptime: 1.15 min

1.40 min (add. 300 µL extra column volume, increased retention times)
 0.70 min

Posttime: 0.70 min
 Wavelength: 245 nm (8), ref. 450 nm (100)
 Peak width: > 0.0025 min (0.05 s response time), 80 Hz
 Spectra: all, 190-500 nm, BW = 1 nm
 Injection volume: 1.0 µL
 Injector: See figure 7, 2 s equilibration time

down to 2.1 mm and even 1.0 mm. As illustrated above, the system has uncompromised performance

characteristics even at highest gradient speeds.

References

1.

Jeremy R. Kenseth, Shelly J. Coldiron, "High-throughput characterization and quality control of small-molecule combinatorial libraries", *Curr. Opin. Chem. Biol.* 8; 418-423; **2004**.

Jill Hochlowski, Xueheng Cheng, "Current Application of Mass Spectrometry to Combinatorial Chemistry", *Anal. Chem.* 74, 2679-2690; **2002**.

2.

R. Kostianen, et al., "Liquid chromatography/atmospheric pressure ionization-mass spectrometry in drug metabolism studies", *J. Mass Spectrom.*, 38, 357-372; **2003**.

Garry Siuzdak, et al., "The application of mass spectrometry in pharmacokinetics studies", *Spectroscopy* 17 681-691; **2003**.

3.

Udo Huber, "High throughput HPLC – Alternating column regeneration with the Agilent 1100 Series valve solutions" *Agilent Application Note, Publication number 5988-7831EN*; **2002**.

Michael Frank is Application Chemist at Agilent Technologies, Waldbronn, Germany.

www.agilent.com/chem/1200rr


The information in this publication is subject to change without notice.

Copyright © 2006 Agilent Technologies, Inc.
All Rights Reserved. Reproduction, adaptation or translation without prior written permission is prohibited, except as allowed under the copyright laws.

Published March 1, 2006
Publication Number 5989-4502EN



Agilent Technologies



Screening for Hazardous Chemicals in Homeland Security and Environmental Samples Using a GC/MS/ECD/FPD with a 731 Compound DRS Database

Application Note

Homeland Security, Environmental

Authors

Bruce Quimby
Mike Szelewski
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808
UASA

Abstract

Response to homeland security or environmental incidents involving hazardous chemicals requires first, the rapid and accurate identification of the chemical agent(s) involved and second, the quantitative measurement of that agent in large numbers of samples to aid in managing the response. Given the unknown nature of the analytes and the complexity of matrices that could be encountered, developing analytical methods for this analysis is challenging. The approach described in this work uses a gas chromatography/mass spectrometry (GC/MS) system with a micro-fluidic splitter added to the end of the column. The splitter divides the column effluent between the MS and either a dual-wavelength flame photometric detector (DFPD) or a micro electron-capture detector (μ ECD) and a single-wavelength FPD. This approach allows the simultaneous collection of MS and two channels of selective GC detector data from a single injection. This multisignal configuration provides: full-scan MS data for library searching, selective ion monitoring (SIM) data for trace analysis, μ ECD and FPD data for excellent selectivity and sensitivity in complex matrices. The systems use retention time locking (RTL) to produce retention times (RTs) that precisely match those in a 731 compound database of hazardous chemicals. Deconvolution Reporting Software (DRS) is used to provide fast and accurate

interpretation of the MS data, especially in samples with high matrix contamination. The combination of selective GC detectors, SIM/Scan, and deconvolution makes a very powerful hazardous chemical analysis system that shows significant progress toward the above goals.

Introduction

In recent years, there has been increasing concern over the release of hazardous chemicals through either accidental or intentional acts. Both the homeland security and environmental communities recognize the need for preparing analytical laboratories that can respond quickly to such incidents. The terms toxic industrial chemicals/toxic industrial materials (TIC/TIM) are used in homeland security to refer to hazardous chemicals, while the environmental community uses different terminology like hazardous materials. In either case, the challenge is to develop laboratory methods with the capability of identifying any hazardous chemical(s) involved in an incident and to be able to measure its concentration in collected samples.

There are several significant challenges to face when developing methods for this analysis. The methods must be able to:

- Rapidly and accurately identify the specific toxic agents involved
- Measure concentration correctly at high levels of agent at the epicenter (high dynamic range)
- Measure concentration correctly at low levels of agent at perimeters and during decontamination (low detection limits)



Agilent Technologies

- Be highly selective over matrix interferences (wood smoke, fuels, burning tires, etc.) to minimize both false positives and false negatives
- Identify as many toxic agents as possible
- Handle large numbers of samples

It is clear that there is no single analytical technique that can be used for detecting all possible hazardous chemicals. However, one technique that is widely applicable for the identification and measurement of broad classes of hazardous chemicals is GC/MS. GC/MS is widely used in laboratories worldwide for the analysis of thousands of different chemicals.

GC/MS methods are typically developed to analyze between 10 and 100 individual compounds. A target compound is deemed to be present if the target ion and two or three qualifier ions, with specific abundance ratios, fall within a defined RT window. The identity of the target may be further confirmed by comparison of the scan at the apex of the peak with a library reference spectrum.

Matrix interferences are usually minimized by optimizing a combination of the sample preparation, GC, and MS parameters. Since most methods only deal with at most a few matrix types, the ions chosen for identification purposes can be selected such that they are minimized in the matrix. With the limited number of targets addressed by the method, recalibration of response factors, RTs, and qualifier ion abundance ratios can be accomplished with the injection of a few calibration mixtures.

General screening methods for very large numbers of targets in widely varying and complex matrices offer a new set of challenges for the method developer. When screening for hundreds of targets, several factors must be addressed:

- Use of sample preparation to reduce matrix interferences is now significantly limited because rigorous cleanup steps may unintentionally remove targets. This reduced level of cleanup can result in significantly higher levels of matrix interferences to contend with.
- Recalibration of response factors, RTs, and qualifier abundance ratios is difficult or impossible because of the large number of targets.
- The methods may be deployed in laboratories without access to standards for all of the targets.

- The time required for data review of hundreds of targets in complex matrices can become unmanageably large.
- Even with a very large database of targets, it is possible that hazardous chemicals not in the target list could be present in a sample.

Recently, several techniques have become available to help address the above set of challenges. RTL produces RTs that precisely match from instrument-to-instrument and to those in a database [1]. This eliminates the need for recalibration of the individual RTs and timed events. The introduction of reliable and inert microfluidic splitters allows for the simultaneous collection of mass spectral data and, for example, phosphorus, sulfur, and/or electron capture data [2]. The selective detector chromatograms can highlight suspect compounds even if they are not in the MS target list. They can also offer an alternative means for quantitation of target analytes.

The introduction of the synchronous SIM/Scan feature allows for the simultaneous acquisition of both full scan and SIM data from the same injection [2, 3]. The scan data can be used for screening the full list of targets in the database while the SIM data looks for a high priority subset of compounds down to very low levels.

One of the most significant tools developed for dealing with complex matrices is Agilent's Deconvolution Reporting Software (DRS) [4]. It uses advanced computational techniques to extract the spectra of targets from those of overlapped interference peaks. It then compares the extracted spectrum with a library to determine if the target is present. Any hits are confirmed by searching against the main NIST MS reference library. This process is automated and provides significant time savings in data interpretation. Since it deals with the entire spectrum instead of just four ions, DRS can often correctly identify a target in the presence of interferences where the typical approach would fail. The use of DRS substantially reduces the number of both false positives and false negatives.

This application note describes the combination of the above techniques with a database of 731 hazardous chemicals, the Agilent Hazardous Chemical DBL (HCD), to be used for screening purposes. The compounds were chosen because of their significance in environmental or food safety analysis. The reasoning is that if the materials are manufactured in significant quantities and are toxic, they would be likely to appear in an

environmental method. The pesticides are included because many exhibit toxicity.

The list is comprised of:

- Chlorinated Dioxins and Furans: EPA 8280A, 10 compounds
- Polychlorinated biphenyls: EPA 8082, 19 compounds
- Volatiles: EPA 502/524, 60 compounds
- Semivolatiles: EPA 8270C Appendix IX, 140 compounds
- Pesticides: Agilent RTL Pesticide Database (adapted), 567 compounds
- Total: 796 compounds, with 65 compounds in two groups, or 731 individual compounds

The names of all the compounds in the database are listed in Appendix A at the end of this note.

The above list by no means contains all of the hazardous chemicals that could be encountered. However, it does screen for a large number of known hazards and with the addition of selective detection can highlight other nontarget compounds that may be of interest.

The chromatographic conditions chosen for development of the database are general in nature and are compatible with the analysis of other types of compounds beyond those in the table. For example, laboratories with access to calibration standards for chemical warfare agents (CWA) can add CWA data to the tables and screen for them as well.

The RTs for compounds in the database were collected with the column outlet pressure at 3.8 psig using a microfluidic splitter. This was done to assure that the RTs observed during sample analysis would closely match those in the database when a microfluidic splitter or QuickSwap is used.

The chromatographic conditions for the database were chosen to be compatible with the method translation technique. Constant pressure mode was used in the GC inlet so that method translation can be used to precisely time scale the methods for faster operation [5]. Provided with the Agilent Hazardous Chemicals DBL are the files to run the analysis precisely threefold (3X) and sevenfold (7X) faster than the primary database (1X). Also, each of the three-speed variations of the database are provided in two forms: one with the entire set of 731 compounds and one with the 36 aromatic hydrocarbons removed. The latter is provided for use with samples known to contain fuels

and where the fuel components are not of interest. In the examples shown below the database with hydrocarbons removed was used, since fuels were used as prototype matrices.

System Configuration

The system configurations used are shown in Figure 1A and 1B.




Figure 1. System configurations. A). GC/MS/ECD/FPD system used for 1X and 3X screening analyses. B). GC/MS/DFPD system used for 7X screening analyses.

Key components are:

Fast Oven

The primary 1X method only requires the 120V oven. With the 6890N 240V oven (option 002), the screening analysis method can be run precisely three times faster (14.33 min) using a 15-m HP-5MS column. If the 240V GC is further equipped with SP1 2310-0236 (puts MSD interface in back of oven under rear injection port) and

using the G2646-60500 oven-insert accessory, the speed can be increased to seven times faster (6.14 min) with a 5-m HP-5MS column. Note that use of the oven insert prevents use of the front inlet and detector positions. Only one detector is available for splitting. The DFPD is a good choice for this configuration, as it uses only one detector position but generates two signals.

μECD

The 6890N Option 231 is a μECD. The signal from the electron capture detector (ECD) is collected, stored, and processed by the MS ChemStation simultaneously with the MS data. ECDs are selective in nature and exhibit very sensitive response to halogenated compounds, with detection limits below 1 pg for polyhalogenates. They also respond to several other functional groups like nitro compounds. They do, however, also respond to some fairly low-priority compounds, like phthalate esters. The ECD data can be used in several ways. Nontarget halogenated or nitro compounds are highlighted. The presence of an electrophore at the RT of an identified compound can be used to support confirmation of identity. The response on the ECD can be used for quantitative analysis, but only after calibration with a standard, as the response factors are compound dependent and can vary significantly with compound class.

Single FPD

The 6890N Option 240 is a single FPD. It is used to selectively detect either sulfur or phosphorus. The detector is usually run in the phosphorus mode to highlight such compounds as organophosphorus pesticides and nerve agents. In the phosphorus mode, the detector is highly selective ($>10^6$) with a very low (~ 0.050 pg) detection limits for phosphorus. The ability of the FPD to uncover nontarget organophosphorus compounds like new pesticides or designer nerve agents is especially helpful. The presence of phosphorus at the RT of an identified compound can be used to support confirmation of identity. Because the response per unit weight of phosphorus is relatively consistent from compound to compound, the FPD can be used for semi-quantitative analysis in situations where no calibration standard is available for an identified analyte.

Dual FPD

The 6890N Option 241 is a DFPD with two optical detection channels that measures sulfur and phosphorus simultaneously. The DFPD sulfur response is also selective ($>10^4$) and sensitive (detection limits <10 pg), although not as much as phosphorus.

The sulfur signal is also quadratic with respect to the amount of sulfur injected. It is often used to detect sulfur-mustard agents and for confirmation of sulfur-containing pesticides. The response per unit weight of sulfur is relatively consistent from compound to compound, but varies more than that of the phosphorus signal.

Microfluidic Splitter

The 6890N Option 890 (3-way splitter) or Option 889 (2-way splitter) uses diffusion-bonded plate technology combined with metal column ferrules to make an inert, easy-to-use, leak free, high-temperature column-effluent splitter. The splitter uses Auxiliary EPC for constant pressure makeup (6890N Option 301). The Auxiliary EPC makeup can be pressure programmed at the end of the run to higher pressure, while at the same time the inlet pressure is lowered to near ambient. This causes the flow in the column to reverse direction, back-flushing heavy materials out the split vent of the inlet. Backflushing can greatly reduce analysis times for samples that contain high-boiling matrix components [6]. The Aux EPC also allows column changing and maintenance without venting the MSD. When the column fitting is removed from the splitter, helium from the makeup supply purges the fitting, preventing air from entering the MSD. If the column is attached to the splitter but removed from the inlet, helium flows backwards through the column and out the inlet end. Inlet maintenance or column headtrimming can be done without cooling and venting the MSD to prevent sucking air into a hot source.

MSD System

The 5975 inert MSD with performance turbo (G3243A) or 5973N inert MSD with performance electronics and performance turbo (G2579A), EI (electron impact ionization mode) MSD is used. These configurations provide faster full scan rates while maintaining sensitivity. The scan rates are compatible with the narrower peaks generated by fast chromatography. The performance turbo pump is required to handle the higher flows associated with the screening method.

Synchronous SIM/Scan

The D.02.00 (or higher) revision of the Agilent MSD ChemStation is used because it supplies the synchronous SIM/Scan feature. SIM/Scan operates by collecting SIM data every other cycle and scan data on alternate cycles throughout the entire chromatogram. The signal-to-noise performance of the collected SIM and scan data is virtually identical to that obtained with SIM-only and scan-only

methods. As with conventional SIM methods, not all 731 targets can be monitored in a single run due to the required time separation between SIM groups. In general, the acquisition of SIM data is set up to collect high-priority targets at very low levels. Examples would be the chlorinated dioxins and CWAs.

DRS Software (G1716AA)

Spectral deconvolution of the MS data enables identification of analytes in the presence of overlapped matrix peaks [4]. This significantly reduces chromatographic resolution requirements, which allows detection of targets in higher levels of matrix or can be used with fast chromatography to shorten analysis times. DRS uses the AMDIS deconvolution program from NIST, originally developed for trace chemical-weapons detection in complex samples. DRS presents the analyst with three distinct levels of compound identification:

- ChemStation, based on RT and four-ion agreement
- AMDIS, based on “cleaned spectra” full-ion matching and locked RT
- NIST05 search using a 163000 compound library

Hazardous Chemical DBL (G1671AA)

This supplies the mass spectral library, method, and DRS files for the 731 compound-screening method.

Instrument Operating Parameters

The instrument operating parameters used (unless noted otherwise) are listed in Table 1. These are starting conditions and may have to be optimized.

The split/splitless injection port was used for all work described here. It was chosen for its flexibility, allowing splitless injections for clean samples and split injections for dirty or high-concentration samples. It is also compatible with column backflushing. For all cases (except ambient headspace), the inlet liner used was the 4-mm id Siltek Cyclosplitter (Restek, part number 20706-214.1). This inlet liner was found to be of low activity, as it does not contain glass wool. Proper mixing for split injections is done by the internal liner geometry. Except as noted, split injections with a split ratio of 10:1 were used. For high matrix samples, this roughly matches the amount of matrix injected with the column capacity. If excess amounts of matrix are injected, the RTs of targets can shift. Split injection is also the easiest and most reliable way of screening samples for analytes ranging in

volatility from gases to large polynuclear aromatic hydrocarbons (PAHs). Splitless injections are usually incompatible with the lowest boiling volatiles due to problems with the solvent. For low matrix samples where semivolatiles are of interest, splitless injections can be used.

For ambient headspace analysis [7], the conditions are listed separately at the bottom of Table 1. The liner used for ambient headspace was 1-mm id straight through (no glass wool) and Siltek coated (Restek, part number 20973-214.5). The auto injector parameters are critical in ambient headspace and are listed in Table 1. The volatiles samples run by ambient headspace were prepared as described in Reference 7.

While the targets in the table cover a very broad range of boiling points, it is usually not practical to screen for all of them in one run. This is because an analysis for semivolatile compounds would be done with a solvent that would occlude the lowest boiling volatiles in the table. Conversely, a method for injecting the lowest boiling compounds would usually not be suitable for the highest boiling. The MSD solvent delays listed in Table 1 are based on isooctane as the solvent in a semivolatiles analysis. If a lower boiling solvent is used, it may be possible to reduce these delays accordingly.

Some of the target compounds were found to have sufficiently high boiling points to require higher inlet and detector temperatures. These were the higher molecular weight PAHs, the polychlorinated dioxins, and the polychlorinated furans. For these compounds the inlet temperature, MS source, and transfer line were also raised to 300 °C. Without this increase in temperature, the compounds would exhibit tailing and in some cases reduction in signal. The trade-off with temperature is that the performance of some thermally labile compounds is degraded at the higher temperatures.

The MSD data acquisition sampling rates listed in Table 1 are for scan mode only. For volatiles analysis, the scan rate is increased one step. It is also increased one step when SIM/Scan is used. In SIM/Scan mode the SIM dwell time was set to 40 milliseconds for each ion monitored.

The microfluidic splitter parameters are chosen to provide the desired flow ratio between detectors while meeting the flow requirements of the detectors used. A primary consideration is to make sure that the flow to the MSD does not exceed ~4 mL/min while collecting analyte data. It was also desired to split the effluent equally between the DFPD and MSD in the 2-way split configuration. In the 3-way configuration, the split to the μ ECD was reduced

Table 1. Gas Chromatograph and Mass Spectrometer Conditions

	Original 1X Method	3X Method	7X Method
GC			
Agilent Technologies 6890N			
7683 Autoinjector and Tray			
Inlet	EPC Split/Splitless	EPC Split/Splitless	EPC Split/Splitless
Mode	Constant pressure	Constant pressure	Constant pressure
Injection type	Split	Split	Split
Injection volume (uL)	1.0	1.0	1.0
Inlet temp (°C)	250	250	250
Pressure, nominal (psig)	31.17	23.96	8.84
RT Locking compound	Tripropyl phosphate	Tripropyl phosphate	Tripropyl phosphate
RT Locking time (min)	12.874	4.291	1.839
Split ratio	10:1	10:1	10:1
Gas saver	Off	Off	Off
Gas type	Helium	Helium	Helium
Oven			
Voltage (VAC)	120 or 240	240	240 (and pillow)
Initial oven temp (°C)	40	40	40
Initial oven hold (min)	2	0.667	0.286
Ramp rate (°C/min)	10	30	70
Final temp (°C)	300	300	300
Final hold (min)	15	5	2.143
Total run time (min)	43.00	14.33	6.14
Equilibration time (min)	0.5	0.5	0.5
Column			
Type	HP 5-MS inert	HP 5-MS	HP 5-MS
Agilent part number	19091S-433i	19091S-431	Custom
Length (m)	30	15	5
Diameter (mm)	0.25	0.25	0.25
Film thickness (um)	0.25	0.25	0.25
Outlet pressure (AUX EPC, psig)	3.8	3.8	3.8
FPD or DFPD			
Type	Single, Phosphorus	Single, Phosphorus	Dual, S and P
Temperature (°C)	250	250	250
Hydrogen flow (mL/min)	75	75	75
Air flow (mL/min)	100	100	100
Mode: Constant makeup flow			
Nitrogen makeup flow (mL/min)	60	60	60
Data rate (Hz)	5	10	10
μECD			
Temperature (°C)	300	300	N/A
Nitrogen makeup flow (mL/min)	60	60	N/A
Mode: Constant makeup flow			
Data rate (Hz)	5	10	N/A
AUX EPC Pressure			
Pressure (psig)	3.8	3.8	3.8
Gas type	Helium	Helium	Helium

Table 1. Gas Chromatograph and Mass Spectrometer Conditions (Continued)**MSD**

Agilent Technologies	5975 inert MSD	5975 inert MSD	5973 inert with Performance Electronics
Tune file	Atune.U	Atune.U	Atune.U
Mode	Scan	Scan	Scan
Solvent delay (min)	2.20	0.82	0.40
EM voltage	Atune voltage	Atune voltage	Atune voltage
Low mass (amu)	35	35	35
High mass (amu)	565	565	565
Threshold	0	0	0
Sampling	1	1	0
Scans/s	5.23	5.23	9.46
Quad temp (°C)	150	150	150
Source temp (°C)	230	230	230
Transfer line temp (°C)	280	280	280

Splitter

Type	3 way	3 way	2 way
6890N option number	890	890	889
Flow ratio	1:1:0.1 MSD:FPD:ECD	1:1:0.1 MSD:FPD:ECD	1:1 MSD:DFPD
[Deactivated fused silica tubing]			
MSD restrictor length (m)	1.44	1.44	1.44
MSD restrictor id (mm)	0.18	0.18	0.18
FPD/DFPD restrictor length (m)	0.53	0.53	0.53
FPD/DFPD restrictor id (mm)	0.18	0.18	0.18
ECD restrictor length (m)	0.51	0.51	N/A
ECD restrictor id (mm)	0.10	0.10	N/A

Ambient Headspace

Inlet	EPC Split/Splitless
Mode	Constant pressure
Injection type	Split
Inlet temp (°C)	200
Pressure, nominal (psig)	31.17
RT locking compound	Tripropyl phosphate
RT locking time (min)	12.874
Split ratio	1:1
Gas saver	Off
Gas type	Helium

Autoinjector

Sample washes	0
Sample pumps	3
Injection volume (µL)	50
Syringe size (µL)	100
PreInj Solvent A washes	0
PreInj Solvent B washes	0
PostInj Solvent A washes	1
PostInj Solvent B washes	3
Viscosity delay (s)	5
Plunger speed	Fast
Pre-injection dwell (min)	0
Post-injection dwell (min)	0
Sampling depth (mm) [critical!]	20

to 1/10th that going to the MSD and FPD because of the extreme sensitivity of the detector. The lengths and diameters of the detector restrictors were calculated using the spreadsheet calculator included with the splitter.

The peak recognition windows used in the Agilent ChemStation were set to ± 0.2 min and in AMDIS to 12 s. these values were found to be sufficiently wide enough to compensate for some RT drift yet narrow enough to minimize the number of false positives. The minimum match factors setting in AMDIS was set to 45. This value seemed to give the least number of false positives and false negatives.

Results

Volatiles

To evaluate the HCD method for volatiles analysis, headspace injection was chosen. Headspace injections are usually done with an automated heated sampler specifically designed for the purpose. Ambient headspace [7] is a variant of the technique that uses a gastight syringe in the liquid autosampler and injects the headspace from a 2-mL vial. It is unheated, and is thus limited to compounds that are volatile at room temperature. Ambient headspace works well for the analysis of

relatively non-polar volatiles in water. It is convenient for labs that need to screen samples for volatiles but do not have a dedicated headspace sampler. The conversion from liquid sampling to ambient headspace simply requires changing the inlet liner and the autosampler syringe.

Figure 2 shows the chromatograms from a run using the system in Figure 1A. A mixture of 14 halogenated volatiles was spiked into water at 2 ppm. Fifty microliters of the approximately 1 mL of headspace in the vial was injected. With the exception of peaks 3 and 4, which coelute, the compounds are well separated. The ECD chromatogram is inverted for comparison with the MS total ion chromatogram from the full-scan data. All of the volatiles respond on the ECD, although the response to compounds 1, 2, and 8 is significantly lower than for the rest of the compounds. In general with an ECD the response to a compound increases dramatically with the number of halogens in the molecule. Since none of the compounds contain phosphorus, there is no response on the FPD.

Figure 3 shows the DRS report for the sample. For each compound identified, the RT, Chemical Abstracts number (CAS#), and compound name are listed. A line is generated in the report if a compound is found by either the Agilent ChemStation, AMDIS, or both.




Figure 2. Ambient headspace analysis of volatile organics in water, spiked at 2 ppm per component.

MSD Deconvolution Report

Sample Name: 2 ppmVOA MIX 3 Only

Data File: C:\msdchem\1\DATA\042205AMHS_SimScan\2ppmMIX 3_Only_simscan.D

Date/Time: 05:13:03 PM Friday, Dec 9 2005

The NIST library was searched for the components that were found in the AMDIS target library.

R.T.	Cas #	Compound Name	Agilent ChemStation Amount (ng)	AMDIS Match	R.T. Diff sec.	NIST Reverse Match	Hit Num.
1.497	107062	1,2-Dichloroethane	2.27	97	0.6	94	1
1.540	563586	1,1-Dichloropropylene	7.6	100	0.5	96	1
1.867	78875	1,2-Dichloropropane	4.92	95	0.7	90	1
1.871	79016	Trichloroethylene	7.58	99	0.6	91	1
2.330	10061015	cis-1,3-Dichloropropylene	4.39	98	1.0	92	2
2.677	10061026	trans-1,3-Dichloropropylene	3.3	97	1.5	94	1
2.758	79005	1,1,2-Trichloroethane	2.82	99	1.7	92	1
2.961	142289	1,3-Dichloropropane	3.39	98	1.5	92	1
3.273	106934	1,2-Dibromoethane	2.6	91	1.5	76	4
4.032	630206	1,1,1,2-Tetrachloroethane	5.15	100	1.9	94	1
5.187	79345	1,1,2,2-Tetrachloroethane	2.38	99	2.3	89	1
5.322	96184	1,2,3-Trichloropropane	1.89	98	2.5	94	1
6.323	76017	pentachloroethane	0.08	63	2.0	76	1
8.232	96128	3-Chloro-1,2-dibromopropane	1.62	93	1.6	87	1
10.439	87683	hexachlorobutadiene	16.46	94	0.9	95	1

Figure 3. DRS report for the analysis in Figure 2.

The report shows that a compound has been determined as present by the Agilent ChemStation if a value appears in the Agilent ChemStation Amount column. This means the identification criteria set in the DATA ANALYSIS section of the method have been met. Typically the criteria are that the target ion is present and all three qualifier ions are present in ratios that fall within the percent uncertainty values for that compound.

The Agilent ChemStation Amount listed is a very rough approximation of the amount of the compound, in nanograms, reaching the MS. This is based on the response factor originally observed when the HCD table data was collected. Since valid quantitation requires recent recalibration of response factors on the specific instrument used for analysis, the numbers in this column should never be used to report concentrations of identified analytes. The error in these values can easily be a factor of 10 or higher. The purpose of the listed values is to give an approximate amount that can be used to guide standard preparation for quantitative calibration of the compound, if needed.

The match value listed under the AMDIS column is the degree to which the extracted (deconvolved) spectrum of the peak at that RT matched the spectrum in the HCD AMDIS target library. The higher this number, the better the spectra agree. The

column "R.T. Diff sec." lists the difference in seconds between the observed RT and that in the AMDIS target library. The lower this number, the better the RTs agree.

The NIST column lists the reverse-match quality of the extracted spectrum compared with the NIST05 main library spectrum with the same CAS#. The entry "Hit Num." is the number of the hit in the NIST search results that has the same CAS# as the identified compound. The higher the reverse-match value and the lower the hit number, the better the extracted spectrum matches with NIST05. The NIST column serves as a second opinion on the identity of the extracted spectrum.

The analysis in Figure 2 is of course an easy one, but serves to demonstrate how the system works. All 14 spiked compounds were found by both the Agilent ChemStation and AMDIS. The certainty of identification is very high because:

- The target ion and three qualifier ions are present in appropriate ratios and at the appropriate time as determined by the Agilent ChemStation
- The deconvolved spectrum and the RT at which it appears closely matches the data in the AMDIS target library.


- The extracted spectrum of the identified compound also matches the spectrum with the same CAS # in the NIST05 library.
- The compounds all have a significant response on the ECD, as expected from their halogen content.

To challenge the system in a more realistic way, the effect of matrix and dilution of the analytes was studied. Additional samples were prepared that contained: the same 2-ppm mixture of analytes plus 100 ppm of pump gasoline; 100 ppb of analytes only; and 100 ppb of analytes plus 100 ppm of pump gasoline.

Figure 4 shows the chromatograms from the 100 ppb of analytes with 100 ppm of gasoline. The complexity of the TIC chromatogram illustrates the severe matrix challenge presented by the thousand-fold excess of gasoline. In the ECD chromatogram, interference peaks are now apparent. However, with the exception of peaks 1, 2, 8, and 12, all of the analytes peaks are still visible above the matrix interferences.

Table 2 summarizes the results from the matrix and dilution experiments. In the sample that was 2 ppm of analytes with 100 ppm of gasoline, the Agilent ChemStation (column labeled Quant) found all but two of the compounds. Those two compounds had qualifier ions out of range due to interferences from the matrix. AMDIS successfully found all 14 compounds. Also, with the exception of compound 8, all of the analytes were clearly visible above the matrix responses on the ECD chromatogram.

In the sample that contained 100 ppb of analytes but without gasoline, quant found 7 of the 14 analytes. Using full-scan data, the signal to noise ratio for most of the analytes at the 100-ppb level is very low. This results in difficulties with finding the qualifier ions in ratios that fall within the specified uncertainty range in the quant calibration table. AMDIS found 11 of the 14 compounds. Peak 3 was not found due to a severe overlap with the coeluting peak number 4. Peaks 9 and 13 were missed by AMDIS because the signal to noise ratio was too low.



Peak identities

- 1) 1,2-Dichloroethane
- 2) 1,1-Dichloropropylene
- 3) 1,2-Dichloropropane
- 4) Trichloroethylene

- 5) *cis*-1,3-Dichloropropylene
- 6) *trans*-1,3-Dichloropropylene
- 7) 1,1,2-Trichloroethane
- 8) 1,3-Dichloropropane
- 9) 1,2-Dibromoethane

- 10) 1,1,1,2-Tetrachloroethane
- 11) 1,1,2,2-Tetrachloroethane
- 12) 1,2,3-Trichloropropane
- 13) 3-Chloro-1,2-dibromopropane
- 14) Hexachlorobutadiene

Figure 4. Ambient headspace analysis of volatile organics in water. Analytes at 100 ppb plus pump gasoline at 100 ppm.

Table 2. Effect of Matrix and Concentration on DRS Results

RT (min)	Compound	Peak Number	2 ppm STD only		2 ppm STD with 100 ppm gasoline		100 ppb STD only		100 ppb STD with 100 ppm gasoline	
			Quant (ng)	AMDIS (match)	Quant (ng)	AMDIS (match)	Quant (ng)	AMDIS (match)	Quant (ng)	AMDIS (match)
1.491	1,2-Dichloroethane	1	2.27	97	2.47	93		73		65
1.536	1,1-Dichloropropylene	2	7.60	100	7.34	98	0.37	89		85
1.793	1,2-Dichloropropane	3	4.92	95	5.59	64	0.21	Overlap		Overlap
1.863	Trichloroethylene	4	7.58	99	7.71	97	0.40	90	0.30	82
2.317	<i>cis</i> -1,3-Dichloropropylene	5	4.39	98	4.81	98	0.21	88	0.23	74
2.658	<i>trans</i> -1,3-Dichloropropylene	6	3.30	97		84		53		Overlap
2.735	1,1,2-Trichloroethane	7	2.82	99	3.05	96	0.12	72		Overlap
2.938	1,3-Dichloropropane	8	3.39	98	3.50	97		66	0.22	46
3.250	1,2-Dibromoethane	9	2.60	91		95		S/N		66
4.003	1,1,1,2-Tetrachloroethane	10	5.15	100	5.32	99		89	0.31	88
5.151	1,1,2,2-Tetrachloroethane	11	2.38	99	2.41	98		48	0.19	53
5.283	1,2,3-Trichloropropane	12	1.89	98	1.85	98	0.07	79	0.14	75
8.208	3-Chloro-1,2-dibromopropane	13	1.62	93	2.40	90		S/N		59
10.435	Hexachlorobutadiene	14	16.46	94	3.54	89	0.65	75	0.36	52
	Total Found		14	14	12	14	7	10	7	11

With 100 ppm of gasoline added to the 100-ppb sample, quant again found 7 of the 14 compounds and AMDIS again found 11 of the 14. Curiously, in both cases some of the compounds missed in the absence of matrix were now found. It is possible that the presence of matrix enhances the concentration of some of the analytes in the headspace. The compounds missed in quant were again the result of low signal to noise and/or interference. In AMDIS the three missed peaks were due to severe interferences from the gasoline. As indicated above, the ECD response from 10 of the 14 compounds was still visible above the peaks due to interferences.

SIM/Scan

The quant data in Table 2 was generated using full scan mode. Peak 13 was missed in quant due to low signal to noise ratio. SIM/Scan mode can be

used to collect SIM data simultaneously with the scan data. The 100 ppb plus 100-ppm gasoline sample was run in SIM/Scan mode with SIM groups for each of the 14 analytes. Figure 5 compares the target and qualifier extracted ion chromatograms in both modes with the ECD response for peak 13.

The signal-to-noise (peak to peak) for the target ion increases from 34 in full scan mode to 433 in SIM mode. The peaks lost in quant due to low signal-to-noise were all recovered in SIM mode. This example demonstrates the power of SIM/Scan when looking for high-priority targets at low levels. If necessary, the ECD could also be used for quantitation, as it has a high signal to noise ratio and is free from interference.




Figure 5. Target and qualifier extracted ion chromatograms for peak 13 (3-Chloro-1,2-dibromopropane) in Figure 4. SIM, scan, and ECD data collected simultaneously.

AMDIS

Figure 6 illustrates the ability of AMDIS to clean the interference ions from the spectrum of an analyte. The raw spectrum at the top of Figure 6 was taken at the apex of peak 13 in the 100 ppb plus 100-ppm gasoline sample. When searched against the NIST05 library using the NIST search program, the actual compound (3-Chloro-1,2-dibromopropane) was the 70th hit in the search results. Using manual subtraction of nearby spectra in the Agilent ChemStation data analysis program improved the quality of the spectrum so that it was now the second hit when searched in NIST. This is a tedious process, however, when dealing with a large number of analytes. The spectrum as deconvolved by AMDIS is shown in Figure 6 above the

NIST05 library spectrum. When this spectrum is searched, it is the first hit in the results. The automated deconvolution provided by AMDIS saves an enormous amount of time in the data review process.

Fast Methods

When a retention time locked database is constructed, the RTs are (or at least should be) collected under the highest resolution conditions expected for the application. If the database is collected under constant pressure mode, method translation can then be used to adjust the speed of the method to meet the needs of different situations.




Figure 6. Comparison of raw, manually subtracted, AMDIS deconvoluted, and NIST05 reference spectra for peak 13 (3-Chloro-1,2-dibromopropane) in Figure 4.

The 3X method uses RTs in its database that are simply the RTs from the 1X method divided by exactly 3. The 7X method likewise uses RTs that are 1/7 of those in the original database. The quality of RTs matching between the two new faster methods and the new divided databases is demonstrated in Figure 7. Three different mixtures containing 13 chlorinated hydrocarbons and 36 pesticides were run with the two methods. The RTs were compared to those in the two new databases. The graph at the top of Figure 7 plots the database RT on the x-axis versus the difference of the measured RT from the database on the y axis.

If the RT matching were perfect, the plot would be a straight horizontal line at zero height on the y axis. The maximum deviation from the table values for the 3X method was -0.047 min. The plot

indicates that a peak recognition window of ± 0.1 min should be sufficient. The maximum deviation in the 7X plot at the bottom of Figure 8 is $+0.032$ min indicating that the same peak recognition window could be used here as well. In general the RTs in scaled methods agree very well with the predicted RTs.

The conditions for the two higher-speed methods were chosen to increase speed while maintaining the same column capacity. The capacity is important for both the dynamic range of quantitative measurements and for minimizing analyte RT shifts in samples with high levels of matrix. In gas chromatography, the well-known triangle of speed, resolution, and capacity dictates that if the capacity is to be maintained and the speed is to be increased, then the resolution will decrease.





Figure 7. Difference between scaled HCD table and experimental retention times for 50 compound test set. Y axis is table value minus experimental, X axis is table RT. Top plot is 3X, bottom is 7X.

Figure 8 shows three sets of chromatograms using the HCD database at three different speeds. The sample consists of nine organophosphorus pesticides (identified in the caption to Figure 8) at 50 ppm and a matrix consisting of an equal volume mixture of gasoline, kerosene, and diesel fuel spiked at 50,000 ppm total mixture. The 1X and 3X data were collected on the three-way splitter instrument and the 7X was collected on the DFPD instrument. All nine compounds also contained sulfur as can be seen in the DFPD sulfur chromatogram at the bottom of Figure 8. Note that the sulfur tails somewhat compared to the phosphorus.



Peak identities

- 1) O,O,O-triethyl phosphorothioate
- 2) Thionazin
- 3) Sulfotepp
- 4) Phorate


- 5) Dimethoate
- 6) Disulfoton
- 7) Methyl parathion
- 8) Parathion
- 9) Famphur

Figure 8. Comparison of 1X, 3X, and 7X chromatograms. 1X and 3X were run on GC/MS/ECD/FPD system, 7X on GC/MS/DFPD.

Figure 9 expands the RT region of the phosphorous chromatogram containing peaks 3, 4, and 5 from Figure 8. The decrease in resolution with increasing speed is clearly evident.

If only the standard target and three qualifier ion approach is used, the loss in resolution causes a significant problems. With the 1X method, all nine of the analytes are identified and eight false positives are reported. With the 3X method, all analytes are again found but now with 25 false positives. With the significantly decreased resolution of the 7X method, only seven of the nine analytes are identified and 48 false positives are reported.

The situation is much different when using the approach described here. Even in the worst situation, the 7X method, AMDIS finds all nine analytes with high-quality matches and only three false positives. The DRS report for the 7X analysis is shown in Table 3. To simplify the table, the 48 false positives that only appear in the quant column are not shown. The analyte compounds are shown in bold. All show close RT and high-quality spectral matches to both the AMDIS target library and to the NIST05 library.



Peak identities

- 3) Sulfotepp
- 4) Phorate
- 5) Dimethoate

Figure 9. Comparison of FPD phosphorus chromatograms from 1X, 3X, and 7X runs in Figure 8.

Table 3. DRS Report for 7x Analysis of 50 ppm Pesticides In 50,000 ppm Gasoline/Kerosine/Diesel Matrix

RT	Cas #	Compound name	Agilent ChemStation amount (ng)	AMDIS match	RT Diff (sec.)	NIST reverse match	Hit number
0.973	98862	Acetophenone		71	-9.5	74	50
1.380	126681	O,O,O-triethyl phosphorothioate	13.92	69	0.7	71	1
1.520	94597	Safrole		46	-7.6		
1.520	52417502	Benzeneacetaldehyde, à,2,5-trimethyl-				74	1
2.113	132649	Dibenzofuran	0.35	64	0.6	80	3
2.138	90437	o-Phenylphenol		55	2.3		
2.138	2131411	Naphthalene, 1,4,5-trimethyl-				85	1
2.275	297972	Thionazin	89.2	91	0.5	85	1
2.417	3689245	Sulfotepp		88	0.5	83	1
2.427	298022	Phorate	23.31	90	0.6	85	1
2.485	60515	Dimethoate	27.34	84	0.7	85	1
2.619	298044	Disulfoton	22.7	92	0.6	88	1
2.748	298000	Methyl parathion	25.12	92	0.6	82	1
2.901	56382	Parathion (ethyl)		91	0.7	85	1
3.360	52857	Famphur		93	0.8	85	1
(48 quant-only hits not shown)							

The peak at 0.973 minutes is a reasonable spectral match to acetophenone, but the large time difference and being the 50th hit in the NIST search results suggests that this is not the compound. The peak at 1.520 min is a poor spectral match with a large time difference. The absence of a NIST reverse search and hit entry means that the listed compound was not in the top 100 hits in the NIST search. The next compound listed at 1.520 min is the top entry from the NIST search. It is quite clear that safrole is not present.

The peak at 2.113 min, dibenzofuran, was not one of the analytes added to the sample. However, it probably is present in the diesel fuel matrix. Its presence is supported by both reasonably good spectral matches and close time matching with a database.

The last extraneous peak at 2.138 min is also questionable. The time match is somewhat poor and the NIST reverse search suggests the identification is not correct.

All nine analytes are detected with the FPD on both the phosphorus and sulfur chromatograms. All analytes except peak 1 are detected selectively on the ECD as well.

These results suggest that while the loss of resolution in going to 7X is unacceptable when using only conventional screening approaches, with the method discussed here, it is a viable option. By using the DRS report combined with the selective detector data, the number of false positives and false negatives are significantly reduced. For those situations where speed is a critical factor, for example in response to homeland security incidents, the fastest method may be the one of choice.

For many laboratories, the 3X method would be an attractive choice. It has higher resolution than the 7X and higher speed than the 1X and still allows the use of two GC detectors in parallel with the MSD. It also only requires a 240V oven, not the repositioning of the MSD to the back position.

Conclusions

The systems described here offer several advantages when screening samples for the presence of hazardous chemicals. The advantages derive from a combination of techniques that result in both faster and more accurate screening results.

- Retention time locked target database of 731 hazardous chemicals for screening with MS
- Microfluidic splitter - using selective detection simultaneous with MS data for added confirmation, finding non-target suspect compounds, and alternate quantitation
- SIM/Scan - Acquire SIM data on high priority targets simultaneously with scan data. Saves time by eliminating need to run samples in both modes.
- DRS - automated deconvolution dramatically increases accuracy of target identification, even in the most challenging matrices. The reduction of data interpretation from hours to minutes is especially useful for response to hazardous chemical incidents.
- Fast chromatography using shorter columns, faster ovens, and backflushing to greatly reduce run times.

This combination of techniques offers a viable solution to the hazardous chemicals challenge.

References

1. Retention time locking (RTL), Vince Giarrocco, Bruce Quimby, and Matthew Klee, "Retention Time Locking: Concepts and Applications", Agilent Technologies, publication 5966-2469E www.agilent.com/chem
2. Chin Kai-Meng and Bruce Quimby, "Identifying Pesticides with Full Scan, SIM, μ ECD, and FPD from a Single Injection", Agilent Technologies, publication 5989-3299EN www.agilent.com/chem

3. Chin-Kai Meng, "Improving Productivity with Synchronous SIM/Scan", Agilent Technologies, publication 5989-3108EN www.agilent.com/chem
4. Philip Wylie, Michael Szelewski, Chin-Kai Meng, Christopher Sandy, "Comprehensive Pesticide Screening by GC/MSD using Deconvolution Reporting Software", Agilent Technologies, publication 5989-1157EN www.agilent.com/chem
5. B. D. Quimby, L. M. Blumberg, M. S. Klee, and P. L. Wylie, "Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking", Agilent Technologies, publication 5967-5820E www.agilent.com/chem
6. Michael J. Szelewski and Bruce Quimby, "New Tools for Rapid Pesticide Analysis in High Matrix Samples", Agilent Technologies, publication 5989-1716EN www.agilent.com/chem
7. Michael J. Szelewski and Bruce D. Quimby, "Ambient Headspace GC and GC-MSD Analysis of Nonpolar Volatiles in Water", Agilent Technologies, publication 5968-9455E www.agilent.com/chem

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Appendix A

Lists of Compounds in Databases

Volatiles:

EPA 502/524, 60 compounds

1,1,1,2-Tetrachloroethane
1,1,1-Trichloroethane
1,1,2,2-Tetrachloroethane
1,1,2-Trichloroethane
1,1-Dichloroethane
1,1-Dichloroethylene
1,1-Dichloropropylene
1,2,3-trichlorobenzene
1,2,3-Trichloropropane
1,2,4-trichlorobenzene
1,2,4-trimethylbenzene
1,2-Dibromoethane
1,2-dichlorobenzene
1,2-Dichloroethane
1,2-Dichloropropane
1,3,5-trimethylbenzene
1,3-dichlorobenzene
1,3-Dichloropropane
1,4-dichlorobenzene
2,2-Dichloropropane
2-chlorotoluene
3-Chloro-1,2-dibromopropane
4-chlorotoluene
Benzene
Bromobenzene
Bromochloromethane
Bromodichloromethane
Bromoform
Bromomethane
Carbon Tetrachloride
Chlorobenzene
Chlorodibromomethane
Chloroethane
Chloroform
Chloromethane
cis-1,2-Dichloroethylene
cis-1,3-Dichloropropylene
Dibromomethane
Dichlorodifluoromethane
Ethylbenzene
Hexachlorobutadiene
Isopropylbenzene
Methylene Chloride
m-xylene
Naphthalene
n-butylbenzene
n-propylbenzene

o-Xylene
p-isopropyltoluene
p-xylene
Styrene
tert-butylbenzene
Tetrachloroethylene
Toluene
trans-1,2-Dichloroethylene
trans-1,3-Dichloropropylene
Trichloroethylene
Trichlorofluoromethane
Vinyl chloride

Semivolatiles:

EPA 8270C Appendix IX,
140 compounds
1,2,4,5-tetrachlorobenzene
1,2,4-trichlorobenzene
1,2-dichlorobenzene
1,3,5-trinitrobenzene
1,3-dichlorobenzene
1,4-dichlorobenzene
1,4-naphthoquinone
1-naphthylamine
2,3,4,6-tetrachlorophenol
2,4,5-trichlorophenol
2,4,6-trichlorophenol
2,4-dichlorophenol
2,4-dimethylphenol
2,4-dinitrophenol
2,4-dinitrotoluene
2,6-dichlorophenol
2,6-dinitrotoluene
2-acetylaminofluorene
2-chloronaphthalene
2-chlorophenol
2-methyl-4,6-dinitrophenol
2-methylnaphthalene
2-naphthylamine
2-nitroaniline
2-nitrophenol
2-picoline
3,3'-dichlorobenzidine
3,3'-dimethylbenzidine
3-methylcholanthrene
3-nitroaniline

4,4'-DDD
4,4'-DDE
4,4'-DDT
4-aminobiphenyl
4-bromophenyl phenyl ether
4-chloro-3-methylphenol
4-chloroaniline
4-chlorophenyl phenyl ether
4-nitroaniline
4-nitrophenol
4-nitroquinoline-1-oxide
5-nitro-*o*-toluidine
7,12-dimethylbenz[a]anthracene
a,a-dimethylphenethylamine
Acenaphthene
Acenaphthylene
Acetone
Acetophenone
Aldrin
Alpha-BHC (alpha-HCH)
Aniline
Anthracene
Aramite (total)
Benz[a]anthracene
Benzene
Benzo[a]pyrene
Benzo[b]fluoranthene
Benzo[ghi]perylene
Benzo[k]fluoranthene
Benzyl alcohol
Beta-BHC (beta-HCH)
Bis(2-chloroethoxy)methane
Bis(2-chloroethyl) ether
Bis(2-chloroisopropyl) ether
Bis(2-ethylhexyl)phthalate
Butyl benzyl phthalate
Chlorobenzilate
Chrysene
Delta-BHC (delta-HCH)
Diallate (total)
Dibenz[a,h]anthracene
Dibenzofuran
Dieldrin
Diethyl phthalate
Dimethoate
Dimethyl phthalate
Di-*n*-butyl phthalate

Di-n-octyl phthalate
 Dinoseb
 Diphenylamine
 Disulfoton
 Endosulfan I
 Endosulfan II
 Endosulfan sulfate
 Endrin
 Endrin aldehyde
 Ethyl methanesulfonate
 Famphur
 Fluoranthene
 Fluorene
 Gamma-BHC (lindane)
 Heptachlor
 Heptachlor epoxide -isomer B
 Hexachlorobenzene
 Hexachlorobutadiene
 Hexachlorocyclopentadiene
 Hexachloroethane
 Hexachlorophene
 Hexachloropropene
 Indeno[1,2,3-cd]pyrene
 Isodrin
 Isophorone
 Isosafrole
 Kepone
 m-cresol (3-methylphenol)
 m-dinitrobenzene
 Methapyrilene
 Methoxychlor
 Methyl methanesulfonate
 Methyl parathion
 Naphthalene
 Nitrobenzene
 N-nitrosodiethylamine
 N-nitrosodimethylamine
 N-nitrosodi-n-butylamine
 N-nitrosodi-n-propylamine
 N-nitrosodiphenylamine
 N-nitrosomethylethylamine
 N-nitrosomorpholine
 (4-nitrosomorpholine)
 N-nitrosopiperidine
 (1-nitrosopiperidine)
 N-nitrosopyrrolidine (1-nitrosopyrrolidine)
 O,O,O-triethyl phosphorothioate
 o-cresol (2-methylphenol)
 o-toluidine
 p-(dimethylamino)azobenzene
 Parathion (ethyl)
 p-cresol (4-methylphenol)
 Pentachlorobenzene
 Pentachloroethane
 Pentachloronitrobenzene
 Pentachlorophenol
 Phenacetin

Phenanthrene
 Phenol
 Phorate
 p-phenylenediamine
 Pronamide
 Pyrene
 Pyridine
 Safrole
 Sulfotepp
 Thionazin

Chlorinated Dioxins and Furans:

EPA 8282, 19 compounds

2,3,7,8-Tetrachlorodibenzo-p-dioxin
 1,2,3,7,8-Pentachlorodibenzo-p-dioxin
 1,2,3,4,7,8-Hexachlorodibenzo-p-dioxin
 1,2,3,4,6,7,8-Heptachlorodibenzo-p-dioxin
 Octachlorodibenzo-p-dioxin
 2,3,7,8-Tetrachlorodibenzofuran
 1,2,3,7,8-Pentachlorodibenzofuran
 1,2,3,4,7,8-Hexachlorodibenzofuran
 1,2,3,4,6,7,8-Heptachlorodibenzofuran
 Octachlorodibenzofuran

Polychlorinatedbiphenyls:

EPA 8082, 19 compounds

2-chlorobiphenyl
 2,3-dichlorobiphenyl
 2,2',5-trichlorobiphenyl
 2,4',5-trichlorobiphenyl
 2,2',5,5'-tetrachlorobiphenyl
 2,2',3,5'-tetrachlorobiphenyl
 2,3',4,4'-tetrachlorobiphenyl
 2,2',4,5,5'-pentachlorobiphenyl
 2,2',3,4,5'-pentachlorobiphenyl
 2,3,3',4',6-pentachlorobiphenyl
 2,2',3,5,5',6-hexachlorobiphenyl
 2,2',4,4',5,5'-hexachlorobiphenyl
 2,2',3,4,5,5'-hexachlorobiphenyl
 2,2',3,4,4',5'-hexachlorobiphenyl
 2,2',3,4',5,5',6-heptachlorobiphenyl
 2,2',3,4,4',5',6-heptachlorobiphenyl
 2,2',3,4,4',5,5'-heptachlorobiphenyl
 2,2',3,3',4,4',5-heptachlorobiphenyl
 2,2',3,3',4,4',5,5',6-nonachlorobiphenyl

Pesticides:

Agilent RTL pesticide database (adapted), 567 compounds

1,2,4-Trichlorobenzene
 1,2-Dibromo-3-chloropropane
 17a-Ethynylestradiol
 2-(1-naphthyl)acetamide
 2-(2-Butoxyethoxy)ethyl thiocyanate
 2-(Octylthio)ethanol

2,3,4,5-Tetrachlorophenol
 2,3,4,6-Tetrachlorophenol
 2,3,5,6-Tetrachlorophenol
 2,3,5-Trichlorophenol
 2,3,5-Trimethacarb
 2,3,5-Trimethylphenyl methyl carbamate (Trimethacarb)
 2,3,7,8-Tetrachlorodibenzofuran
 2,3,7,8-Tetrachlorodibenzo-p-dioxin
 2,4,5-T methyl ester
 2,4,5-Trichlorophenol
 2,4,6-Trichlorophenol
 2,4-D methyl ester
 2,4-D sec-butyl ester
 2,4-DB methyl ester
 2,4-Dichlorophenol
 2,4-Dichlorophenyl benzenesulfonate
 2,4-Dimethylaniline
 2,6-Dichlorobenzonitrile
 2,6-Dimethylaniline
 2-[3-Chlorophenoxy]propionamide
 2-Ethyl-1,3-hexanediol
 2-Hydroxyestradiol
 2-Methylphenol
 2-Phenoxypropionic acid
 3,4,5-Trimethacarb
 3,4-Dichloroaniline
 3,5-Dichloroaniline
 3-Chloroaniline
 3-Hydroxycarbofuran
 4,4'-Dichlorobenzophenone
 4,6-Dinitro-o-cresol (DNOC)
 4-Chloroaniline
 4-Methylphenol
 5,7-Dihydroxy-4'-methoxyisoflavone
 9,10-Anthraquinone
 Acephate
 Acetochlor
 Acifluorfen methyl ester
 Alachlor
 Aldrin
 Allidochlor
 Ametryn
 Amidithion
 Aminocarb
 Amitraz
 Ancymidol
 Anilazine
 Aniline
 Atraton
 Atrazine
 Azaconazole
 Azamethiphos
 Azinphos-ethyl
 Azinphos-methyl Aziprotryne
 Azobenzene
 Barban

Benalaxyl	Chlorbufam	Demeton-S
Benazolin-ethyl	Chlordecone	Demeton-S-methylsulfon
Bendiocarb	Chlordimeform	Desbromo-bromobutide
Benfluralin	Chlorfenethol	Desmedipham
Benfuresate	Chlorfenprop-methyl	Desmetryn
Benodanil	Chlorfenson	Dialifos
Bentazone	Chlorfenvinphos	Di-allate I
Bentazone methyl derivative	Chlorflurecol-methyl ester	Di-allate II
Benthiocarb	Chlormefos	Diamyl phthalate
Benzo(a)pyrene	Chlornitrofen	Diazinon
Benzophenone	Chlorobenzilate	Dibrom (naled)
Benzoylprop ethyl	Chloroneb	Dicamba
b-Estradiol	Chloropropylate	Dicamba methyl ester
BHC alpha isomer	Chlorothalonil	Dicapthon
BHC beta isomer	Chlorotoluron	Dichlofenthion
BHC delta isomer	Chlorpropham	Dichlofluanid
Bifenox	Chlorpyrifos	Dichlone
Bifenthrin	Chlorpyrifos Methyl	Dichlormid
Binapacryl	Chlorthal-dimethyl	Dichlorophen
Bioallethrin	Chlorthiamid	Dichlorprop
Bioallethrin S-cyclopentenyl isomer	Chlorthion	Dichlorprop methyl ester
Bioresmethrin	Chlorthiophos	Dichlorvos
Biphenyl	Chlorthiophos sulfone	Diclobutrazol
Bis(2-ethylhexyl)phthalate	Chlorthiophos sulfoxide	Diclofop methyl
Bisphenol A	Chlozoline	Dicloran
Bitertanol I	cis-Chlordane	Dicrotophos
Bitertanol II	Clomazone	Dicyclohexyl phthalate
Bromacil	Coumaphos	Dicyclopentadiene
Bromobutide	Crimidine	Dieldrin
Bromocyclen	Crotoxyphos	Diethatyl ethyl
Bromophos	Crufomate	Diethofencarb
Bromophos-ethyl	Cyanazine	Diethyl dithiobis(thionoformate) (EXD)
Bromopropylate	Cyanofenphos	Diethyl phthalate
Bromoxynil	Cyanophos	Diethylene glycol
Bromoxynil octanoic acid ester	Cycloate	Diethylstilbestrol
Buprofezin	Cycluron	Difenoconazol I
Butachlor	Cyfluthrin I	Difenoconazol II
Butamifos	Cyfluthrin II	Diiflufenican
Butoxycarboxim	Cyfluthrin III	Dimefox
Butralin	Cyfluthrin IV	Dimethachlor
Butyl benzyl phthalate	Cyhalothrin I (lambda)	Dimethametryn
Butylate	Cymoxanil	Dimethipin
Butylated hydroxyanisole	Cypermethrin I	Dimethoate
Captafol	Cypermethrin II	Dimethylphthalate
Captan	Cypermethrin III	Dimethylvinphos(z)
Carbaryl	Cypermethrin IV	Dimetilan
Carbetamide	Cyprazine	Di-n-butylphthalate
Carbofuran	Cyprofuram	Diniconazole
Carbofuran-3-keto	Cyromazine	Dinitramine
Carbophenothion	d-(cis-trans)-Phenothrin-I	Dinobuton
Carbosulfan	d-(cis-trans)-Phenothrin-II	Dinocap I
Carboxin	Dazomet	Dinocap II
Chinomethionat	Decachlorobiphenyl	Dinocap III
Chloramben methyl ester	Deltamethrin	Dinocap IV
Chloranocryl	Demephion	
Chlorbenside		
Chlorbromuron		

Dinoseb	Fenpropathrin	Isofenphos
Dinoseb acetate	Fenson	Isomethiozin
Dinoseb methyl ether	Fensulfothion	Isoprocab
Dinoterb	Fenthion	Isopropalin
Dinoterb acetate	Fenthion sulfoxide	Isoprothiolane
Di-n-propyl phthalate	Fenuron	Isoproturon
Dioxacarb	Fenvalerate I	Isoxaben
Dioxathion	Fenvalerate II	Isoxathion
Dioxydemeton-S-methyl	Fepropimorph	Jodfenphos
Diphacinone	Flamprop-isopropyl	Kinoprene
Diphenamid	Flamprop-methyl	Lenacil
Diphenylamine	Fluazifop-p-butyl	Leptophos
Dipropetryn	Flubenzimine	Leptophos oxon
Disulfoton	Fluchloralin	Lindane
Ditalimfos	Flucythrinate I	Linuron
Dithiopyr	Flucythrinate II	Malathion
Diuron	Flumetralin	Malathion-o-analog
Dodemorph I	Fluometuron	MCPA methyl ester
Dodemorph II	Fluorodifen	MCPB methyl ester
Drazoxolon	Fluotrimazole	m-Cresol
Edifenphos	Flurenol-butyl ester	Mecarbam
Endosulfan (alpha isomer)	Flurenol-methylester	Mecoprop methyl ester
Endosulfan (beta isomer)	Fluridone	Mefenacet
Endosulfan ether	Flurochloridone I	Mefluidide
Endosulfan lactone	Flurochloridone II	Menazon
Endosulfan sulfate	Fluroxypr-1-methylheptyl ester	Mephosfolan
Endrin	Flusilazole	Mepronil
Endrin aldehyde	Flutolanil	Metalaxyl
Endrin ketone	Flutriafol	Metamitron
EPN	Fluvalinate-tau-I	Metasystox thiol
Epoxiconazole	Fluvalinate-tau-II	Metazachlor
EPTC	Folpet	Methacrifos
Erbon	Fonofos	Methamidophos
Esfenvalerate	Formothion	Methfuroxam
Esprocarb	Fuberidazole	Methidathion
Etaconazole	Furalaxyl	Methiocarb
Ethalfuralin	Furathiocarb	Methiocarb sulfone
Ethiofencarb	Furmecyclox	Methiocarb sulfoxide
Ethiolate	Heptachlor	Methomyl
Ethion	Heptachlor epoxide	Methoprene I
Ethofumesate	Heptachlor exo-epoxide isomer B	Methoprene II
Ethoprophos	Heptenophos	Methoprotryne
Ethoxyquin	Hexabromobenzene	Methoxychlor
Ethylenethiourea	Hexachlorobenzene	Methyl paraoxon
Etridiazole	Hexachlorophene	Methyl parathion
Etrimfos	Hexaconazole	Methyl-1-naphthalene acetate
Famphur	Hexazinone	Methyldymron
Fenarimol	Hexestrol	Metobromuron
Fenazaflor	Imazalil	Metolachlor
Fenbuconazole	Ioxynil	Metolcarb
Fenchlorphos	Iprobenfos	Metribuzin
Fenfuram	Iprodione	Mevinphos
Fenitrothion	Isazophos	Mirex
Fenobucarb	Isobenzan	Molinate
Fenoprop	Isobornyl thiocynoacetate	Monalide
Fenoprop methyl ester	Isocarbamide	Monocrotophos
Fenoxycarb	Isodrin	Monolinuron

Myclobutanil	Phosphamidon II	Sulfur (S8)
N,N-Diethyl-m-toluamide	Phthalide	Sulprofos
N-1-Naphthylacetamide	Picloram methyl ester	Swep
Naphthalic anhydride	Pindone	Tamoxifen
Napropamide	Piperalin	TCMTB
Nicotine	Piperonyl butoxide	Tebuconazole
Nitralin	Piperophos	Tebutam
Nitrapyrin	Pirimicarb	Tecnazene
Nitrofen	Pirimiphos-ethyl	Temephos
Nitrothal-isopropyl	Pirimiphos-methyl	Terbacil
N-Methyl-N-1-naphthyl acetamide	Plifenat	Terbucarb
Norflurazon	p-Nitrotoluene	Terbufos
Nuarimol	Pretilachlor	Terbumeton
o,p'-DDD	Probenazole	Terbuthylazine
o,p'-DDE	Prochloraz	Terbutryne
o,p'-DDT	Procymidone	Tetrachlorvinphos
Octachlorostyrene	Profenofos	Tetradifon
o-Dichlorobenzene	Profluralin	Tetraethylpyrophosphate (TEPP)
Omethoate	Promecarb	Tetramethrin I
o-Phenylphenol	Prometon	Tetramethrin II
Oryzalin	Prometryn	Tetrapropyl thiodiphosphate
Oxabetrinil	Propachlor	Tetrasul
Oxadiazon	Propamocarb	Thenylchlor
Oxadixyl	Propanil	Thiabendazole
Oxamyl	Propargite	Thiofanox
Oxycarboxin	Propazine	Thiometon
Oxychlordane	Propetamphos	Thionazin
Oxydemeton-methyl	Propham	Tiocarbazil I
Oxyfluorfen	Propiconazole-I	Tiocarbazil II
p,p'-DDD	Propiconazole-II	Tolclofos-methyl
p,p'-DDE	Propoxur	Tolylfluanid
p,p'-DDT	Propyzamide	trans-Chlordane
Paclobutrazol	Prothiofos	Triadimefon
Paraoxon	Prothoate	Triadimenol
Parathion	Pyracarbolid	Tri-allate
p-Dichlorobenzene	Pyrazon	Triamiphos
Pebulate	Pyrazophos	Triazophos
Penconazole	Pyrazoxyfen	Tributyl phosphate
Pendimethalin	Pyributicarb	Tributyl phosphorotrithioite
Pentachloroaniline	Pyridaben	Trichlorfon
Pentachloroanisolet	Pyridaphenthion	Trichloronate
Pentachlorobenzene	Pyridate	Triclopyr methyl ester
Pentachloronitrobenzene	Pyridinitril	Tricyclazole
Pentachlorophenol	PyrifenoX I	Tridiphane
Pentachloro	PyrifenoX II	Trietazine
Permethrin I	Pyrimethanil	Triflumizole
Permethrin II	Pyroquilon	Trifluralin
Perthane	Quinalphos	Tryclopypyrbutoxyethyl
Phenamiphos	Quinoclamine	Tycor (SMY 1500)
Phenakapton	Quizalofop-ethyl	Uniconazole-P
Phenoxyacetic acid	Resmethrin	Vamidothion
Phenthoate	S,S,S-Tributylphosphorotrithioate	Vernolate
Phorate	Sebuthylazine	Vinclozolin
Phosalone	Secbumeton	
Phosfolan	Simazine	
Phosmet	Simetryn	
Phosphamidon I	Sulfotep	

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2006

Printed in the USA
February 9, 2006
5989-4834EN



Agilent Technologies



RoHS/ELV Directives - Measurement of Heavy Metals Using ICP-MS

Application

Environmental

Authors

Taichi Yamamoto, Yuki Arai, Tomohiro Seki
Nihon Environmental Services Co., Ltd.
Tokyo
Japan

Abstract

This application note describes a robust analytical method for the determination of heavy metals and substances regulated by the EU Restriction of Hazardous Substances/End of Life Vehicles (RoHS/ELV) directives. Based on the experience of Nihon Environmental Services Co., Ltd in Japan using an Agilent Technologies 7500c ORS (Octopole Reaction System) collision/reaction cell ICP-MS, this note summarizes:

- **An overview and validation of ICP-MS methodology for RoHS applications**
- **Benefits of ICP-MS methodology to the analysis of trace elements in high matrix samples and limitations of EDXRF (Energy Dispersive X-Ray Fluorescence) for the measurement of lead in flame resistant plastics**
- **Advantages of ICP-MS for RoHS applications.**

Introduction

The European Union (EU) RoHS directive (Restriction of the use of certain Hazardous Substances, Directive 2002/95/EC effective July 2006) aims at

effectively eliminating the use of hazardous chemical materials used in electric/electronic products. The EU End of Life Vehicles (ELV) Directive 2000/53/EC covers the use of certain substances in the manufacture of new vehicles and automotive components. In China and Japan, the respective equivalents of the RoHS directive will be enforced at the same time as in the EU. The Japanese version is currently being prepared by the Ministry of Economy, Trade and Industry.

Table 1 shows the substances/metals that are regulated by the RoHS/ELV directives along with their thresholds. The RoHS directive restricts the use of three heavy metals: cadmium (Cd), lead (Pb), mercury (Hg), plus hexavalent chromium (Cr⁶⁺) and two brominated flame retardants. The ELV directive only targets the metals stated above. In accordance with these directives, careful control is required during the manufacture of sub components to prevent the above substances entering into the process. Polymeric resin materials are particularly susceptible to contamination. Nevertheless, other than British Standard/European Standard BS EN1122:2001: Plastics – Determination of Cadmium - Wet Decomposition Method [1], a standard method for analyzing metal impurities in resins does not exist. A National Standardization Technical Committee (TC111) working group 3 organized in the International Electrotechnical Commission (IEC) was set the task of developing standard RoHS analysis methods.



Agilent Technologies

Table 1. Substances Restricted by the RoHS/ELV Directives and Their Thresholds

Restricted substance	RoHS directive/ mg/kg	ELV directive/ mg/kg
Cd	100	100
Pb	1000	1000
Hg	1000	1000
Cr ⁶⁺	1000	1000
PBBs*	1000	—
PBDEs**	1000	—

* Polybrominated biphenyls

** Polybrominated diphenyl ethers

Methodology

Table 2 summarizes the methods of analysis that are performed at Nihon Environmental Services, along with the minimum quantitative detection limits. Official analysis methods for hexavalent chromium include EPA3060A/7196A, (alkaline digestion of hexavalent chromium, colorimetric method), plus JIS H 8625 (hexavalent chromium by a diphenylcarbazine colorimetric method), ISO3856/5 (determination of hexavalent chromium content of the pigment portion of liquid paint or paint in powder form, diphenylcarbazine spectrophotometric method) and DIN53314

(determination of content of chromium (VI) in leather by colorimetric analyses using diphenyl carbazine). None of these, however, have been sufficiently validated for a wide variety of materials. For this reason, it has become general practice at Nihon Environmental Services to measure the total concentration first, and then measure the concentration of the hexavalent form only if the total concentration exceeds the Cr⁶⁺ minimum quantitation limit. Nihon Environmental Services uses US EPA SW-846 Method 3052 (microwave assisted acid digestion of siliceous and organically based matrices, hereafter “EPA3052”) [2]. This screening method specifies the simultaneous pre-treatment procedures for cadmium, lead, mercury, and total chromium.

Nihon Environmental Services Co., Ltd uses an Agilent 7500c equipped with an ORS collision/reaction cell to analyze cadmium, lead and chromium, see Table 3 for operating conditions. Quantitative determination of mercury is also possible provided that the memory effect (the element’s adsorption to the container) and the volatility of the material are taken into account. The instrument was calibrated using a mixed standard solution (SPEX, Metuchen NJ, USA). Table 4 shows the analytical isotopes and internal standards monitored.

Table 2. Minimum Quantitative Detection Limits and Methods of Analysis

Restricted substance	Minimum Level of Quantitation mg/kg	Analysis method	
		Sample preparation	Quantitative Analysis (Technique)
Cd	1	In accordance with the US EPA SW-846 Method 3052 Acid decomposition method with microwave oven	ICP-MS method, see Table 3 for operating parameters
Pb	10		
Hg	1		
Cr	1		
Cr ⁶⁺	10	In accordance with the US EPA SW-846 Method 3060A Hot alkali extraction method	In accordance with the US EPA SW-846 Method 7196A, using Diphenylcarbazine absorption spectroscopy
PBBs	10	Solvent extraction method	GC/MS
PBDE	10	Solvent extraction method	GC/MS

Table 3. ICP-MS Operating Parameters, Agilent 7500c ICP-MS

Nebulizer type	Babington
RF power	1600 W
Sampling depth	8.5 mm
Carrier gas flow rate	1.2 L/min
Makeup gas flow rate	0 L/min
Spray chamber temp	2 °C
Peristaltic pump speed	0.1 rps
Reaction gas	H ₂ (3.5 mL/min)

Table 4. Isotopes Used for Measurements by ICP-MS

Measured element	<i>m/z</i>	Internal Standard (<i>m/z</i>)
Cr	52 53*	Ga (71,69) or Y (89)
Cd	106 111* 112	In (115*) or Y (89) or Te (125)
Hg	200 202*	Tl (205)
Pb	207 208*	Tl (205)

* Isotope that is used primarily for quantitative determination.

Validation of Methodology

Analysis of Standard Reference Materials

A standard polyethylene substance CBR-680 supplied by the Community Bureau of Reference (CBR) was prepared for analysis by ICP-MS according to the procedures detailed in methods EN1122 and EPA3052. The certified value for cadmium in the standard is 140.8 mg/kg. The measured values were subjected to Grubbs' test for outliers to confirm that no samples were to be

rejected. The results were then tested at the 5% significance level to check if there was a difference between the averages calculated by the two methods. The average resulting from the EN1122 method was 143.2 mg/kg (CV: 3.2%, recovery: 101%) and the average from the EPA3052 method was 138.0 mg/kg (CV: 2.4%, recovery 98%). No significant difference was observed between the results.

Results of a Proficiency Test

To test the validity of their ICP-MS methodology the lab took part in the proficiency test in 2004 (IIS04P02): "Cadmium and Lead in Plastics" that was administered by the Institute for Interlaboratory Studies (IIS), in the Netherlands. At present, this is the only international proficiency test that is based on the ISO/IEC Guide 43. According to the report, this test attracted the participation of 56 analytical institutions from 20 countries around the world, with a large number of participants from Japan, Hong Kong, China and other areas in Asia [3]. Three participating labs used ICP-MS, 17 used atomic absorption spectroscopy and 33 used ICP-OES.

Three samples were used in the test. Cadmium was the target metal for #0454 and #0455, while lead was the target for #0456. All samples were polyvinyl chloride (PVC) moldings. Samples #0454 and #0456 contained over 10 times the regulated value of Cd and Pb respectively, while Sample #455 had only a moderate concentration of Cd. The results that Nihon Environmental Services obtained were close to the average for both the EN1122 and EPA Method 3052, as shown in the example histograms for Cd and Pb in Figures 1 and 2. The calculated z-scores were within a range of ± 1 .





Figure 1. Histograms of results for Cd in sample #0454 and #0455.




Figure 2. Histogram of results for Pb in sample #0456.

High-Concentration Matrix Samples

The materials covered by the RoHS/ELV directives include various metals and ceramics, as well as polymers. Some resin products contain a large amount of inorganic components as a result of additives such as metal fillers. While resins and other organic components can be decomposed using microwave digestion, their inorganic constituents often remain in high concentrations. It is difficult for some types of analytical instrumentation to measure trace elements in the presence of such high concentration matrices. To overcome this problem, pretreatment methods such as solvent extraction and ion exchange are proposed. Nihon Environmental Services, however, prefers direct quantitative determination and uses ICP-MS with minimum sample pretreatment. By making use of the relative freedom from spectral interferences provided by the 7500c ICP-MS, complicated sample pretreatment procedures are simplified, and the risk of introducing contaminants is minimized. Turnaround time is also improved.

Managing Interferences in ICP-MS

Spectral interferences caused by overlaps of poly-atomic species on elements of interest (cadmium, lead, chromium, and mercury) were overcome by operating the 7500c ORS collision/reaction cell in helium mode (4.5 mL/min flow rate). Physical interferences were corrected through the use of appropriately selected internal standards. Internal standards were selected with similar ionization potential and a similar mass-to-charge ratio to the analytes being measured. Note that the internal standards recommended by the USEPA are not always the most suitable for all matrices.

Limitations of EDXRF for Measurement of Lead in Flame Resistant Plastics

EDXRF spectroscopy can provide quick, low cost analyses. For this reason, this instrument is widely used for screening tests in the electronic, electric appliance and automobile industries, where the number of parts and components used extends from several hundreds to several tens of thousands. Modern EDXRF instruments have improved significantly in sensitivity and are currently capable of measuring at ppm levels under optimized conditions. However, their application is limited because of interferences on key analytes.




Figure 3. EDXRF spectra of brominated flame retardant containing plastics A (top) and B (bottom).

Figure 3 shows an example of the measurement of lead contained in two flame resistant plastic samples (A and B) using an EDXRF spectrometer. The presence of the prominent peaks associated with bromine suggests that both samples A and B contain brominated flame retardants. EDXRF results also showed less than 10 mg/kg of lead for sample A and 70 mg/kg of lead for sample B. However, analysis by ICP-MS showed less than 10 mg/kg for both samples. The difference in the results for lead in Sample B can be accounted for as follows: Table 5 shows how the wavelength of the lead peak $L_{\alpha 1}$ is close to K_{α} of arsenic, and the $L_{\beta 1}$ and $L_{\beta 2}$ of lead are close to K_{α} and $K_{\beta 1}$ of bromine. This means that it is difficult to determine lead in a sample

which contains arsenic and bromine. Brominated compounds are generally added as a flame retardant and antimony trioxide (SbO_3) is sometimes used to enhance performance. Arsenic compounds are not intentionally added to plastics, however it can occur as a contaminant in the antimony compound. The ICP-MS results for Sample B showed arsenic was present at the 50-ppm level. The comparison demonstrates that ICP-MS provides more reliable results for the determination of heavy metals and other elements such as arsenic, in flame-resistant materials.

Table 5. EDXRF Wavelengths for Quantitative Analysis and Interference Identification

Elements	Spectrum	keV
Pb	$L_{\alpha 1}$	10.552
	$L_{\beta 1}$	12.614
	$L_{\beta 2}$	12.623
As	K_{α}	10.532
	$K_{\beta 1}$	11.727
Br	K_{α}	11.909
	$K_{\beta 1}$	13.292

Advantages of ICP-MS

A major advantage of ICP-MS for RoHS applications is its multi-element capability which enables it to determine a full suite of elements including mercury. This eliminates the need for a peripheral technique such as cold vapor atomic absorption (CVAA) for ICP-optical emission spectroscopy (OES). Antimony (Sb) and arsenic (As) are not currently listed in RoHS/ELV, but these elements are listed along with beryllium (Be) and selenium (Se) in the Green Procurement Guidelines issued by JIG (Joint Industry Guideline) [4] prepared jointly by the industry groups in Japan, the United States and the EU. ICP-MS allows the determination and quantification of all elements specified in current directives and guidelines as well as impurity elements which provide valuable information on the content of the sample.

Another advantage of the technique is its sensitivity. The RoHS/ELV maximum allowable concentration is 100 ppm (Cd) and 1000 ppm (Pb, Cr, Hg). Some manufacturers set specific requirements at, for example, 1/100 or 1/1000 of the RoHS/WEE

threshold which requires determination at lower than the 1–10 ppm level. Because ICP-MS is significantly more sensitive than ICP-OES or AAS, only 1/10–1/100 of the sample amount is required for ICP-MS. This reduces the time required for sample preparation and allows small sample volumes to be analyzed. This is an advantage if the sample itself is very small or the sample is a high value part, such as a noble metal. Further benefits of the simplified sample preparation procedure arise from the reduced volume of acid that is required to digest the sample and that needs to be disposed of at the end of the analysis.

ICP-MS also provides the possibility of employing isotope dilution mass spectrometry (IDMS) as a high caliber reference calibration technique for more accurate quantitative analysis. IDMS involves spiking samples before the dissolution process, which allows accurate calculation of sample preparation recovery.

Conclusions

The ICP-MS method developed at Nihon Environmental Services Co., Ltd. using the 7500c ORS is capable of measuring the four metals regulated by the RoHS/ELV directives efficiently, as well as the 10 heavy metals specified in the guidelines currently prepared jointly by the industries concerned in Japan, the United States and the EU.

To assure the quality of the data acquired according to the RoHS/ELV directives, it is desirable to have reliable third parties perform the same measurements to ensure that the results will be commercially acceptable worldwide. Nihon Environmental Services is ISO9001 accredited and conducts method development according to ISO management. The company also obtained laboratory accreditation (ISO/IEC17025) from the Japan Accreditation Board for Conformity Assessment (JAB) for the measurement of cadmium according to the EN1122 method, which employs ICP-MS as the determination method. IEC TC111 will also include ICP-MS. This experience provides further confidence in the ICP-MS method as applied to the RoHS/ELV directives.

References

1. BSEN1122:2001 “Plastics - Determination of cadmium - Wet decomposition method” (Japanese Standards Association)
2. US EPA SW-846 Method 3052,
<http://www.epa.gov/SW-846/pdfs/3052.pdf>
3. Results Proficiency Test Cadmium and Lead in Plastics October 2004. For more information contact: masahiko_endo@agilent.com
4. Guideline for Standardization of Material Declaration by Japan Electronics and Information Technology Association (JEITA JGPSSI),
<http://home.jeita.or.jp/eps/green2.htm>

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem/icpms.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


© Agilent Technologies, Inc. 2006

Printed in the USA
January 30, 2006
5989-3574EN



Agilent Technologies

Precise Time-Scaling of Gas Chromatographic Methods Using Method Translation and Retention Time Locking



Application

Gas Chromatography
May 1998

Authors

B. D. Quimby, L. M. Blumberg,
M. S. Klee, and P. L. Wylie
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

Complete development of a gas chromatographic method often involves a significant amount of effort. Once a method is completed, retention time locking (RTL) can be used to implement the method and to obtain the same retention times on multiple systems. This application note describes how to use method translation combined with RTL to implement precise time-scaled versions of a method on multiple instrument types. This allows the original method to be re-used with minimal effort, while optimizing the method for a given sample type or instrument setup. In this way, the utility of the original method is extended greatly, increasing the payback on the investment in its development and optimizing its use for specific analyses. In this note, the Agilent RTL Pesticide Library method is used as an example. The steps involved in precise time-scaling of the method to different speeds, detectors, and columns are presented.

Key Words

Pesticides, GC, GC-AED, retention time locking, RTL, method translation, scalable RT libraries

Introduction

Interest in the analysis of pesticide residues has been increasing recently, in part due to the discovery that some of these compounds act as endocrine disrupters. Agilent Technologies has responded to the need for rapid, accurate, and comprehensive screening analysis for pesticides by developing a method to screen for 567 pesticides and suspected endocrine disrupters. The method uses element-selective detection and a retention time locked library of retention times to find and identify pesticides in a sample.¹

In the method, sample extracts are run with element-selective detection using a prescribed set of chromatographic conditions and with the column retention time locked to the retention times in a table. If any peaks containing heteroatoms are observed, the section of the table corresponding to a small time window around the observed peak is searched. The time search results are further sorted using

the observed element content of the peak. The combination of time and element content narrows rapidly the possible compounds that could have produced the heteroatom response to a few pesticides.

The element-selective detection is done with either gas chromatography-atomic emission detection (GC-AED), which can screen for all the individual elements found in pesticides, or with a combination of other selective detectors like the electron capture detector (ECD), the nitrogen-phosphorus detector (NPD), the flame photometric detector (FPD), or the electrolytic conductivity detector (ELCD).

The GC-AED technique can also be used to calculate element ratios and to quantitate unknown peaks that are detected because of its equimolar element response factors. The measured element ratios can be used to further distinguish between possible identities of detected heteroatomic compounds, often resulting in a single entry as the likely identity of a given peak. With compound-independent calibration, the amount of the unknown can be calculated using element response factors generated with a different standard compound.



Agilent Technologies
Innovating the HP Way

Once the element-selective screen is completed, samples that contain any suspect compounds are run on a GC with mass spectral detection (GC-MS) system that is retention time locked to the pesticide method, thus having the same retention times as the element-selective detectors. Using the possible identities generated from the element screen, the GC-MS data is evaluated to decide which (if any) of the possible identities for suspect peaks is correct. The confirmation process is simplified greatly because the element screen usually yields only a few possibilities and because the retention time in the GC-MS run is accurately known. In practice, extracted ion chromatograms for characteristic ions of each possible compound are used to determine the identity of suspect compounds.

This screening method minimizes false negatives, even in dirty samples, by using element-selectivity and time in the initial screen. With element-selective detection, all compounds containing chlorine, phosphorus, nitrogen, etc. are detected. Even if a detected heteroatomic compound is not in the table, its presence is known, and it can be marked for further GC-MS evaluation. By using GC-MS for confirmation, false positives are also minimized.

The RTL Pesticide Library method is a good example of a method in which a substantial investment of time and material has been made. As with many methods intended for use in multiple laboratories, it would be desirable to be able to scale the method for use in different situations of sample type and instrument setup. Because the method relies on the measured retention times of 567 compounds, it would be impractical to re-measure all the retention times

whenever the method is modified, for example, to increase its speed.

Method translation²⁻⁴ is a calculation technique developed at Agilent Technologies that allows a capillary column GC method to be translated to different chromatographic conditions. The technique calculates the required changes in inlet pressure and oven temperature ramp rates and hold times required to maintain peak elution order identical to that of a reference method. In this way, the speed of an analysis can be scaled predictably to accommodate the needs of a specific sample or instrument type.

The inlet pressure calculated for the new version of a method by the method translation software is based on the assumed or nominal dimensions of the column. As such, the calculated inlet pressure will provide a close, but not exact, match to the desired scaled retention times. To match precisely the retention times of the scaled method to the desired scale factor, the new method must be retention time locked. Retention time locking³ (RTL) is a technique developed by Agilent Technologies whereby the inlet pressure required to match retention times precisely is calculated from a calibration curve of inlet pressure versus retention time.

Using method translation followed by RTL allows a method to be scaled by a precisely known factor. Once the chromatography has been scaled, a retention time table, such as the RTL Pesticide Library, can then be scaled by the same factor, resulting in a new library whose retention times match those of the scaled method precisely.

The steps required to scale the method are:

1. Determine the desired scale factor for the new method.

2. Use the method translation software⁴ to calculate the inlet pressure and oven temperature adjustments to obtain the desired scaling of the method. The scale factor is the "speed gain" value reported in the method translation software. Make sure that the new method parameters are consistent with the hardware capabilities of where the new method will be used.
3. Perform the RTL calibration runs for the new method. Alternatively, the method translation software can be used to calculate the RTL calibration points for the new method using those from the original method.
4. Retention time lock the new method using the locking reference standard from the original method. The new method should be locked to the original reference standard retention time divided by the scale factor.
5. Export the retention time table as a text file using the EXPORT function in the RTL SEARCH menu of the RTL ChemStation software.
6. Divide the retention times in the table by the scale factor in a spreadsheet program like Microsoft® Excel™.
7. Re-import the new, scaled table.
8. Run a representative test mixture to validate the scaled method.

Several examples of scaling the HP RTL Pesticide Library are presented below.

Experimental

All data were collected on Agilent 6890 Series GC systems. All systems were equipped with:

- Electronic pneumatics control (EPC)

- Split/splitless inlet
- Automatic liquid sampler

The GC-AED system also included an Agilent G2350A atomic emission detector with GC-AED ChemStation software (rev B.00.00) for Microsoft® Windows NT®.

The GC-micro-ECD system was controlled by Agilent GC ChemStation software (rev A.05.04). Both the GC-AED and the GC-micro-ECD ChemStations contained RTL software for GC ChemStation (G2080AA) and the Retention Time Locking Pesticide Library for GC ChemStation (G2081AA).

The GC-MS system (G1723A) used consisted of an 6890 Series GC equipped with an Agilent 5973 mass selective detector (MSD). The process for retention time locking the GC-MS system is described in reference 2.

All systems except the micro-ECD instrument used 30 m × 0.25 mm id × 0.25 µm HP-5MS columns (part no. 19091S-433). The Agilent micro-ECD instrument used 10 m × 0.1 mm id × 0.1 µm HP-5 column (part no. 19091J-141).

RTL measurements were made with a solution of dichlorvos, methyl chlorpyrifos, and mirex, each at 10-ppm concentration in acetone. All injections were 1-µL splitless, except for the micro-ECD experiments, which were 1-µL split 100:1. In all methods, inlets were operated at 250 °C and detectors at 300 °C.

Method translation requires inlets to be run in constant pressure mode to obtain precise scaling of retention times. Thus, all methods discussed in the note were run in this mode.

Results and Discussion

Locking GC-MS with Other GC Detectors

When using selective GC detectors in conjunction with GC-MS, one problem that is encountered is knowing the relationship between retention times on the selective detector and that of the GC-MS. In GC-MS, the outlet pressure of the column is vacuum, while with most other GC detectors, the outlet pressure of the column is at or near atmospheric pressure. This difference in outlet pressures results in large differences in retention time between GC with MS detection and GC with other detectors. Comparison of GC-FID, a general detector, with GC-MS is reasonably straightforward, because the total ion chromatogram (TIC) of the GC-MS system has similar response to the FID. Retention times on the GC-MS system corresponding to those on the GC-FID can be determined by looking for similar patterns of response. With selective detectors, this is much more difficult because the response patterns from selective detectors usually do not resemble the TIC. For this reason, matching the retention times of selective detectors precisely with the GC-MS system simplifies data analysis greatly.

In this first example of scaling the RTL Pesticide Library, the method will be scaled from the GC-AED method to the GC-MS method. In this case, the desired scale factor is exactly 1, that is, the GC-MS retention times are desired to be exactly the same as those of the GC-AED. The first step is to use the method translation software to determine the GC conditions to use for GC-MS.

Figure 1 shows the method translation software. The original method conditions for the GC-AED pesticide method are entered in the column labeled "Original Method." The column dimensions, carrier gas type, inlet pressure, outlet pressure, ambient pressure, and oven temperature program are entered here. Note that the inlet pressure is in psi (gauge), while the outlet pressure and ambient pressure are psi (absolute). The original method here is being used on a GC-AED system, so the outlet pressure is entered as atmospheric pressure plus 1.5 psi, the operating pressure of the GC-AED.

The "Criterion" parameter is set to "None," which allows the user to select a specific value of "speed gain" by adjusting the value of hold-up time for the translated method (see figure 1). In the column labeled "Translated Method," the parameters of column dimensions, carrier gas type, outlet pressure, and ambient pressure for the GC-MS method are entered. Note that the inlet pressure and oven program are not entered; they are calculated by the program. To set the speed gain to a desired value, take the calculated value of hold-up time in the first column (0.996060 minute) and divide it by the scale factor. Because in this case the desired scale factor ("speed gain") is 1, the same hold-up time for both the GC-AED and the GC-MS methods is required. Clicking the radio button next to the hold-up time in the "Translated Method" column will do this automatically.

The method translation indicates that to obtain the same retention times on the GC-MS system as on the GC-AED, use all the same method parameters

The RTL calibration file is constructed by running five calibration runs of the target compound, in this case methyl chlorpyrifos, at five different inlet pressures. The runs are made at conditions identical to the nominal method except that four of the runs are made at different pressures. The pressures used are typically:

- Target pressure – 20%
- Target pressure – 10%
- Target pressure (nominal method pressure)
- Target pressure + 10%
- Target pressure + 20%

The retention time of the target compound is determined for each run. The resulting set of five pressures and corresponding retention times is then entered in the RTL calibration dialog box for the method and saved with the method.

To lock the method on the GC-MS setup, the target compound is run at

GC Method Translation									
Criterion: ☐ Translate Only ☐ Best Efficiency ☐ Fast Analysis ☒ None				Speed gain: 1.00000					
				Original Method			Translated Method		
Column									
Length,		m		30			☒ 30		
Internal Diameter,		µm		250.0			☒ 250.0		
Film							☐ Unlock		
Thickness,		µm		.25			☐ 0.250		
Phase Ratio				250.0			☒ 250.0		
Carrier Gas				Helium			☒ Helium		
Enter one Setpoint							☐ Unlock		
Head Pressure,		psi		27.6			☐ 17.934		
Flow Rate,		mLn/min		2.7153			☐ 1.8938		
Outlet Velocity,		cm/sec		96.64			☐ 50.20		
Average Velocity,		cm/sec		50.20			☒ 0.996060		
Hold-up Time,		min		0.996060					
Outlet Pressure (absolute),		psi		16.2			☐ 0		
Ambient Pressure (absolute),		psi		14.696			☐ 14.696		
Oven Temperature				3-ramp Program					
		Initial		Ramp Rate		Final Temp.		Final Time	
				°C/min		°C		min	
		Ramp 1		25		150		0	
		Ramp 2		3		200		0	
		Ramp 3		8		280		10	
				°C/min		°C		min	
				25.000		150		0.000	
				3.000		200		0.000	
				8.000		280		10.000	
Sample Information				None					

Figure 1. Method translation software showing scaling HP RTL Pesticide Method from GC-AED conditions to GC-MS with a scale factor of 1.

the nominal method pressure, and the retention time is observed. The pressure and resulting retention time are then entered into the “(Re)Lock New Column” menu item of the RTL software to calculate the correct pressure for obtaining locked retention times.

Normally, the RTL calibration for a new method is determined by actually making the five calibration runs. In the current example, methyl chlorpyrifos would be run at:

- 17.93 psi – 20% = 14.34 psi
- 17.93 psi – 10% = 16.14 psi
- 17.93 psi (nominal method pressure)
- 17.93 psi + 10% = 19.72 psi
- 17.93 psi + 20% = 21.56 psi

However, because the new GC-MS method is scaled from an existing GC-AED method that already has RTL

calibration data, method translation can be used to calculate the new RTL calibration points. This is useful when you want to try a scaled method rapidly and save the time required in making the five runs. (Note: For methods that will be used extensively, the five-runs approach may provide a somewhat better calibration. It is recommended that for these methods, the standard calibration be performed.)

To calculate the five RTL calibration pairs of pressure and retention time for the GC-MS method from those of the GC-AED method:

- Take the inlet pressure used for each original GC-AED RTL calibration run, and enter it into the method translation software for the inlet pressure of the original method. Make sure the hold-up times are locked, giving a “speed gain” of 1.

- The inlet pressure calculated in the “Translated Method” column will now change to a new value, corresponding to the pressure that would be obtained if the calibration run were made on a GC-MS system. This pressure is used with the retention time obtained for the corresponding GC-AED calibration run as a calibration point for the GC-MS method.

When all five points have been calculated in this way, they are entered into the RTL calibration dialog box for the GC-MS method and saved with the method. Table 1 lists the original RTL calibration pressures and times with the calculated pressures and times for the GC-MS method.

To test the accuracy of using a predicted RTL calibration file for GC-MS, a real calibration set was measured on the GC-MS system. The data is shown in the first two columns of table 2. (Note: The calibration points are spaced ~ 5% apart in pressure instead of the typical 10%.) A GC-MS RTL calibration file was constructed with these measured points. For each point, the locking pressure required to lock the method was calculated and is shown in column 3 of table 2.

The locking pressure is the pressure determined by the RTL software that would make methyl chlorpyrifos have a retention time of 16.596 minutes. This is determined by entering the pressure and retention time for each point into the “(Re)Lock New Column” menu item of the RTL software. If the calibration is done correctly, the locking pressures determined from each point should be very similar, as they are in column 3 of table 2.

Column 4 of table 2 shows the locking pressures for the same set of runs but determined using the GC-MS RTL calibration points calculated using method translation. The calculated data provide locking pressures that agree well with those based on measured data. The range in locking pressures pressure is only from 17.72 to 17.75 psi. This range of 0.03 psi corresponds to only about a 0.006-minute range in the retention time of methyl chlorpyrifos.

Figure 2 shows the locked chromatograms from a three-component mixture run on GC-AED and GC-MS systems. As can be seen, the retention times are well matched between the two methods.

The RTL Pesticide Library contains the retention times of the 567 pesticides measured with GC-FID. The values measured with the FID would be the same observed with any detector that is operated at or near atmospheric pressure. Because retention time matching is critical in this application, the retention times for all the compounds in the table were also measured on the GC-MS system after scaling as described here. Figure 3 is a plot of the difference between the retention times measured on the GC-FID and the GC-MS systems. The plot shows the retention times match well within ± 0.1 minute out to 30 minutes. A few compounds at the end deviate outside this window, with one compound 0.2-minute different. The

Table 1. RTL Calibration Points from Original GC-AED Method and Calculated Points for GC-MS

GC-AED RTL Calibration		GC-MS RTL Calibration	
Pressure (psi)	Ret Time (min)	Calculated Pressure (psi)	Calculated Ret Time (min)
33.1	15.346	24.27	15.346
30.4	15.919	21.18	15.919
27.6	16.578	17.934	16.578
24.8	17.338	14.654	17.338
22.1	18.242	11.449	18.242

Table 2. Comparison of Locking Pressures Calculated Using Measured and Predicted GC-MS RTL Calibration Data

GC-MS Locking Runs		Locking Pressures	
Measured GC-MS RTL Cal Points		Using Measured RTL Cal Points	Using Calculated RTL Cal Points
Pressure (psi)	Ret Time (min)	Pressure (psi)	Pressure (psi)
20	16.127	17.73	17.75
19	16.326	17.72	17.73
18	16.536	17.72	17.72
17	16.760	17.74	17.74
16	16.988	17.72	17.74

deviation is clearly largest in the isothermal hold region, which starts at 31.87 minutes. This effect is seen with GC-MS, but not with scaling to other atmospheric pressure detectors. While the cause is not yet clearly understood, it appears related to the vacuum outlet pressure of the GC-MS column. Although this level of matching is very good, the table includes both the GC-FID and GC-MS retention times so that smaller time windows can be used in searching unknowns.

Locking GC-AED with Other GC Detectors

When the method translation step is done to scale the GC-AED method to other atmospheric pressure detectors, the only different parameter to enter is the outlet pressure. The outlet pressure for the GC-AED method is 16.2 psi and that for the others is 14.696 psi. The method translation calculates that the nominal GC-AED inlet pressure of 27.6 psi would be changed to 26.29 psi for the other atmospheric detectors. This difference (<5%) is so small that it can be neglected, because corrections in this range are compensated easily by the retention time locking step. Thus, the method conditions and RTL calibration points used with GC-AED are interchangeable with FID, NPD, ECD, FPD, and other atmospheric detector methods.

Note that this would not always be the case. If for example, a method is being scaled that uses a very low inlet pressure, the 1.5-psi difference in outlet pressure could become significant. It is best to check the method with method translation and see if the inlet pressure will change by >10%. If it does, it would be advisable to collect (or translate) a new RTL calibration centered around the translated nominal inlet pressure.

Gaining Speed in the Same Instrument Setup

In the analysis of pesticide residues in food, there are usually only a few compounds encountered in any one sample. Because the screening method uses selective detectors, it makes sense to consider trading speed for chromatographic resolution. Selective detectors respond to only those compounds containing a specific heteroatom(s), and the chromatography only needs to resolve those compounds from each other, not from every other compound in

the matrix. This approach can save a significant amount of analysis time.

In this example of scaling the RTL Pesticide Library, the method will be increased in speed at the expense of chromatographic resolution. The first consideration is by what factor to increase the speed. The method translation software is useful for determining this. A candidate speed gain, in this example threefold, is entered into the method translation software. The resulting inlet pressure and oven temperature ramp rates are then inspected to see if the instrument on




Figure 2. GC-AED chlorine and GC-MS TIC chromatograms of three-component locking mixture. Peak identifications: 1. dichlorvos, 2. methyl chlorpyrifos, 3. mirex.




Figure 3. Difference plot of GC-MS and GC-FID retention times in RTL Pesticide Library.

which the new method will be run is compatible with those parameters.

Figure 4 shows the method translation software with the data entered for a speed gain of 3. Note that columns for “Original Method” and “Translated Method” are set up as in the previous example with two exceptions. Because the scaling is from GC-AED to GC-AED, the outlet pressure in both columns is entered as 16.2 psi. The second and most significant difference is the holdup time. The desired “speed gain” is 3.

To set the speed gain, the calculated value of hold-up time in the first column (0.996060 minute) is divided by exactly 3. This value (0.33202 minute) is entered for the hold-up time in the second column. This will force the speed gain to exactly 3.

The inlet pressure and oven temperature ramp for the new threefold speed method are now calculated. The calculated inlet pressure is 87.862 psi, which is compatible with the EPC module on the current system (maximum 100 psi). Note that the helium source supplying the GC must be capable of reaching 100 psi of helium. An optional 150-psi EPC module is available for the HP 6890 GC to provide additional inlet pressure, if necessary.

The oven temperature program calculated for the new method has the first ramp listed as 75 °C/min. This ramp rate is compatible with the 240-V oven option on the current instrument but would not work with a 120-V oven, which is limited to about 50 °C/min in this temperature range. With a 120-V oven, the speed gain would be limited to about 2.

The next step is to calculate the RTL calibration points from the original

GC-AED method. This is done by the same process as shown in the GC-MS scaling above. In this case, when one of the original method RTL calibration pressures is entered, the resulting holdup time must be divided by 3 and entered for the holdup time in the “Translated Method” column. This will force the “speed gain” back to 3. The resulting inlet pressure is then paired with the retention time of the corresponding original GC-AED calibration run, but divided by 3 as a calibration point for the new method.

Table 3 shows the RTL calibration points from the original GC-AED method and calculated points for the threefold speed gain (3 $\times$) method.

When the calibration data is entered into the RTL calibration dialog box, the target time for methyl chlorpyrifos is entered as 5.532 minutes, which is 16.596 minutes divided by 3.

Table 4 compares the locking pressures determined with measured and with calculated RTL calibration points. As in the above GC-MS example, the range of the locking pressures from the calculated data is only 0.11 psi (87.88 to 87.99), which corresponds to ~ 0.003 minute.

Figure 5 compares the chromatograms of the RTL locking mixture from both the original and the 3 $\times$ scaled methods. Note that while the chromatographic resolution is reduced, the speed is increased by a factor of 3.

Figure 6 shows a plot of the difference between the RTL Pesticide Library retention times, divided by 3, and those of the 3 $\times$ method. The data were taken with a 36-component subset of the library. The plot shows the retention times match well within ± 0.05 minute for all compounds, even

Figure 4. Method translation software showing scaling RTL Pesticide method scaled to threefold faster method.

those in the 3.3-minute hold time at the end of the run.

Gaining Speed with a Small-Bore Column

In the previous example, speed was gained at the expense of resolution. In this example, speed will be gained while maintaining most of the resolution but sacrificing capacity. This is done by scaling the original method to a 0.1-mm id column.

In scaling to columns of a different diameter, there are two important considerations that must be obeyed to obtain precise matching to a library or reference method. The first is that the stationary phase composition must be the same as that used in the original method. The second is that the phase ratio of the column being scaled to must be the same as that of the reference method.

Columns of the same phase ratio have the same ratio of inner diameter to film thickness. Because the reference method was developed on a column with 0.25 mm id $\times$ 0.25 μ m film thickness, scaling to a 0.1-mm id column will require a 0.1- μ m film thickness. A 10-m column of these dimensions was chosen for this example.

The micro-ECD for the 6890 GC is extremely sensitive, with detection limits in the low femtogram range for polyhalogenated pesticides. These detection limits are so low that it is reasonable to consider using split mode for a rapid screening method. Using split mode with a split ratio of 100 still gives a detection limits in the range of a few picograms. The split is also more compatible with the relatively low capacity of the column.

Table 3. RTL Calibration Points from Original GC-AED Method and Calculated Points for Threefold Speed Gain (3 $\times$) Method

GC-AED RTL Calibration		3 $\times$ GC-AED RTL Calibration	
Pressure (psi)	Ret Time (min)	Calculated Pressure (psi)	Calculated Ret Time (min)
33.1	15.346	106.21	5.115
30.4	15.919	97.23	5.306
27.6	16.578	87.86	5.526
24.8	17.338	78.44	5.779
22.1	18.242	69.31	6.081

Table 4. Comparison of Locking Pressures Calculated Using Measured and Predicted 3 $\times$ GC-AED RTL Calibration Data

3 $\times$ GC-AED Locking Runs		Locking Pressures	
Measured 3 $\times$ GC-AED RTL Cal Points		Using Measured RTL Cal Points	Using Calculated RTL Cal Points
Pressure (psi)	Ret Time (min)	Pressure (psi)	Pressure (psi)
97	5.319	87.99	87.99
92	5.433	87.94	87.95
87	5.557	87.99	87.99
82	5.689	87.99	87.96
77	5.832	87.97	87.88




Figure 5. Chlorine chromatograms from original and 3 $\times$ GC-AED methods of three-component locking mixture. Peak identifications: 1. dichlorvos, 2. methyl chlorpyrifos, 3. mirex.

Figure 7 shows the method translation from the GC-AED method to the 0.1-mm id column with a scale factor of 3. A speed gain of 3 was again chosen based on oven and inlet limitations as described above. The same scaling process as used above is followed.

The RTL calibration points for the new 3× 0.1-mm micro-ECD method were both calculated with method translation and measured. Table 5 shows the calculated values.

When the locking pressures from the measured and calculated values were examined, the calculated values provided much poorer predictions of locking pressure than expected. The pressure required to actually lock the column was confirmed to be 65.95 psi, as predicted by the measured RTL calibration data. Method translation had predicted the inlet pressure would be 58.514 psi for an assumed 10-m column length. Because the actual locking pressure was noticeably higher, this suggests that the actual column length was longer and/or the column diameter was smaller and/or the film thickness larger than the assumed values.

As an experiment, it was assumed that the problem was in the assumed length of the column used in calculating the RTL calibration points. The column length entry for the 0.1-mm column was iteratively adjusted until the calculated inlet pressure matched the actual locking pressure, 65.95 psi. This resulted in a calculated column length of 10.5622 m. A new set of calculated RTL calibration points were calculated using 10.5622 m as the length of the 0.1-mm column. The results are shown in table 6.




Figure 6. Difference plot of RTL Pesticide Library (GC-FID) retention times divided by 3 minus 3× GC-AED retention times for 36-compound subset of the library.

GC Method Translation																																							
Criterion: ☐ Translate Only ☐ Best Efficiency ☐ Fast Analysis ☒ None Speed gain: 3.00000																																							
Column Length, m: 30 Internal Diameter, µm: 250.0 Film Thickness, µm: .25 Phase Ratio: 250.0					Translated Method ☐ 10 ☐ 100.0 ☐ Unlock ☐ 0.100 ☒ 250.0																																		
Carrier Gas Enter one Setpoint Head Pressure, psi: 27.6 Flow Rate, mL/min: 2.7153 Outlet Velocity, cm/sec: 96.64 Average Velocity, cm/sec: 50.20 Hold-up Time, min: 0.996060 Outlet Pressure (absolute), psi: 16.2 Ambient Pressure (absolute), psi: 14.696					☒ Helium ☒ Unlock ☐ 58.514 ☐ 0.7027 ☐ 172.31 ☐ 50.20 ☐ 0.332020 ☐ 14.696 ☐ 14.696																																		
Oven Temperature 3-ramp Program <table border="1"> <thead> <tr> <th></th> <th>Initial</th> <th>Ramp 1</th> <th>Ramp 2</th> <th>Ramp 3</th> </tr> </thead> <tbody> <tr> <td>Temp (°C)</td> <td>70</td> <td>150</td> <td>200</td> <td>280</td> </tr> <tr> <td>Time (min)</td> <td>2</td> <td>0</td> <td>0</td> <td>10</td> </tr> </tbody> </table>						Initial	Ramp 1	Ramp 2	Ramp 3	Temp (°C)	70	150	200	280	Time (min)	2	0	0	10	<table border="1"> <thead> <tr> <th>Ramp Rate</th> <th>Final Temp.</th> <th>Final Time</th> </tr> </thead> <tbody> <tr> <td>°C/min</td> <td>70</td> <td>2</td> </tr> <tr> <td>°C/min</td> <td>150</td> <td>0.667</td> </tr> <tr> <td>°C/min</td> <td>200</td> <td>0.000</td> </tr> <tr> <td>°C/min</td> <td>280</td> <td>3.333</td> </tr> </tbody> </table>					Ramp Rate	Final Temp.	Final Time	°C/min	70	2	°C/min	150	0.667	°C/min	200	0.000	°C/min	280	3.333
	Initial	Ramp 1	Ramp 2	Ramp 3																																			
Temp (°C)	70	150	200	280																																			
Time (min)	2	0	0	10																																			
Ramp Rate	Final Temp.	Final Time																																					
°C/min	70	2																																					
°C/min	150	0.667																																					
°C/min	200	0.000																																					
°C/min	280	3.333																																					
Sample Information: None																																							

Figure 7. Method translation software showing scaling RTL pesticide method scaled to a threefold faster method on a 10-m × 0.1-mm id column.

Table 7 shows a comparison of locking pressures calculated using measured and predicted 3× 0.1-mm id micro-ECD calibration data. The range of locking pressures from the measured data (66.03 to 65.93) only corresponds to a spread in retention times of about 0.004 minute. However, with the data calculated based on a 10-m assumed length, the spread (66.38 to 63.18) is much larger and would correspond to a time range of 0.14 minute. The locking pressures calculated using the 10.5622 value are much more consistent with the measured values. The range in retention times would be ~ 0.03 minute if all the calculated points are used, and if the first value in column 5 is ignored, the range drops to ~ 0.005 minute.

The fact that the agreement in locking pressures is much improved by using 10.56 m instead of 10 m suggests that length is probably the largest contributor to the discrepancy. These results should reinforce the recommendation that if a method is to be used extensively, it is prudent to obtain measured RTL calibration data. It should be noted, however, that even with the RTL calibration from the 10-m assumed length, the worst consequence would be that the RT locking step would need to be repeated an extra time to get a more precise match.

Figure 8 compares the chromatograms of the RTL locking mixture from both the original and the 3 × 0.1-mm id micro-ECD methods.

Table 5. RTL Calibration Points from Original GC-AED Method and Calculated Points for 3× 0.1-mm id Micro-ECD Method Assuming 10-m Column Length

GC-AED RTL Calibration		3x Micro-ECD RTL Calibration	
Pressure (psi)	Ret Time (min)	Calculated Pressure (psi)	Calculated Ret Time (min)
33.1	15.346	71.03	5.115
30.4	15.919	64.90	5.306
27.6	16.578	58.51	5.526
24.8	17.338	52.11	5.779
22.1	18.242	45.91	6.081

Table 6. RTL Calibration Points from Original GC-AED Method and Calculated Points for 3× 0.1-mm id Micro-ECD Method Assuming 10.5622-m Column Length

GC-AED RTL Calibration		3x Micro-ECD RTL Calibration	
Pressure (psi)	Ret Time (min)	Calculated Pressure (psi)	Calculated Ret Time (min)
33.1	15.346	80.03	5.115
30.4	15.919	73.13	5.306
27.6	16.578	65.95	5.526
24.8	17.338	58.74	5.779
22.1	18.242	51.75	6.081

Table 7. Comparison of Locking Pressures Calculated Using Measured and Predicted 3× 0.1-mm id Micro-ECD Calibration Data

3x Micro-ECD Locking Runs		Locking Pressures		
Measured 3x Micro-ECD RTL Cal Points		Using Measured RTL Cal Points	Using 10-m Calculated RTL Cal Points	Using 10.56-m Calculated RTL Cal Points
Pressure (psi)	Ret Time (min)	Pressure (psi)	Pressure (psi)	Pressure (psi)
48.81	6.323	65.95	66.38	65.30
52.66	6.041	66.03	65.77	65.85
58.51	5.797	65.95	65.12	65.96
64.36	5.585	65.93	64.36	65.95
70.22	5.396	66.00	63.18	65.90

Note that while the most of the chromatographic resolution is preserved, the speed is increased by a factor of 3.

After being locked, the three peaks in the 3× micro-ECD method had retention times of 1.924, 5.533, and 9.963 minutes, respectively. These values are very close to the RTL Pesticide Library retention times for the three compounds divided by 3: 1.932, 5.532, and 9.949. The fact that the largest difference between the scaled table and the 3× micro-ECD method is only 0.014 minute again demonstrates the precision of retention time matching achievable with the scaling technique described here.

Conclusions

Using method translation combined with retention time locking provides a means of extending the usefulness of existing capillary GC methods. The ability to precisely scale a method to meet the needs of different samples and instrument types greatly reduces the effort required to re-use methods, thus saving time and money.

References

1. P. L. Wylie and B. D. Quimby, "A Method Used to Screen for 567 Pesticides and Suspected Endocrine Disrupters," Hewlett-Packard Company, Application Note 228-402, Publication 5967-5860E, April 1998.
2. M. Klee and V. Giarrocco, "Predictable Translation of Capillary GC Methods for Fast GC," Hewlett-Packard Company, Application Note 228-373, Publication 5965-7673E, March 1997.
3. V. Giarrocco, B. D. Quimby, and M. S. Klee, "Retention Time Locking: Concepts and Applications," Hewlett-Packard Company, Application Note 228-392, Publication 5966-2469E, December 1997.
4. Capillary Column Method Translator, user contributed software, free download from: www.hp.com/go/mts.




Figure 8. Chlorine chromatogram from 1× GC-AED method (top) and 3× micro-ECD method (bottom) of three-component locking mixture. Peak identifications: 1. dichlorvos, 2. methyl chlorpyrifos, 3. mirex.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.


Microsoft® and Windows NT® are U.S. registered trademarks.

Copyright © 2006
Agilent Technologies, Inc.

Printed in the USA 1/2006
5967-5820E



Agilent Technologies
Innovating the HP Way



Performance Characteristics of the Agilent 7500ce - The ORS Advantage for High Matrix Analysis

Part 1 of a 3 part series on Environmental Analysis

Application

Environmental Analysis

Authors

Steve Wilbur and Emmett Soffey
Agilent Technologies, Inc.
3380 146th Pl SE Suite 300
Bellevue, WA 98007
USA

Ed McCurdy
Agilent Technologies
Lakeside, Cheadle Royal Business Park,
Stockport, Cheshire, SK8 3GR
UK

Abstract

The Agilent 7500ce ICP-MS was specifically designed and optimized for the analysis of trace metals in high matrix samples including environmental, clinical, geological, and others. The 7500ce uses enhanced Octopole Reaction System (ORS) technology for improved sensitivity and robustness over previous generation inductively coupled plasma mass spectrometry (ICP-MS) instruments. This application note outlines the theory of interference removal using the ORS, the design enhancements employed, and the typical performance of the Agilent 7500ce.

Introduction

This application note is Part One of a three part series on environmental analysis using the Agilent 7500ce ICP-MS system. Part Two is an application note demonstrating the ability of the Agilent 7500ce ICP-MS system to measure trace elements in drinking water, at substantially below regulated levels, under challenging real-world conditions [1].

Part Three is an application note covering the analysis of various high matrix environmental samples using the Agilent 7500ce ICP-MS [2].

This application note details the advances in ion optics and octopole reaction system (ORS) design that were incorporated into the 7500ce. These advances came about as a result of extensive testing and development of its predecessor (Agilent 7500c) with difficult, high-matrix samples. The design goals of the 7500ce were:

- Develop an ICP-MS system specifically to meet the needs of analytical laboratories to analyze unknown, variable, high-matrix samples, which are currently depending on inductively coupled plasma-optical emission spectroscopy (ICP-OES), graphite furnace atomic absorption (GFAA), and hydride and cold vapor techniques, in addition to ICP-MS.
- Maintain the simple, effective interference removal characteristics of the ORS - successfully introduced in the 7500c.
- Improve the overall sensitivity to allow ultra-trace analysis of mercury (Hg) and other low level elements, which were previously difficult in some very high matrix sample types.

These goals were achieved through enhancements in the sample introduction system, interface, ion optic, and ORS regions of the instrument. In common with all the other models in the 7500 Series, the 7500ce uses highly efficient 27 MHz plasma coupled to a low-flow nebulizer and cooled-spray chamber to minimize plasma and interface matrix effects. This approach has been



Agilent Technologies

successfully used in all Agilent ICP-MS instruments since the 4500 Series in 1994, but recent enhancements with the development of a new digitally driven, all solid-state RF generator have further increased plasma robustness. This serves to reduce metal oxide interferences, as evidenced by a very low CeO^+/Ce^+ ratio of <1.5% (<0.8% in He cell gas mode). Following the successful strategy of the 7500c, all ion lenses with the exception of the octopole are outside the high vacuum region and can be serviced without venting the mass analyzer. This design greatly reduces downtime for routine system maintenance. The 7500ce maintains a linear, axial flow of ions from the sampler and skimmer cones through a pair of on-axis extraction lenses, enhancing ion transmission and reducing the effects of matrix accumulation on the extraction lenses. Borrowed from the successful 4500 and 7500a systems, the 7500ce uses a simplified Omega lens to eliminate photons and neutrals from the ion beam before entering the octopole. Unlike older photon stop designs, the Omega lens eliminates photons and neutrals while maintaining high ion transmission, particularly at low masses. After the Omega lens, ions enter the octopole

reaction cell, which is now located on-axis to the quadrupole and detector, further enhancing ion transmission. The redesigned ion lens and ORS provide improved ion transmission without compromising the tight control of ion energy, which is essential for efficient interference removal by energy discrimination (ED).

Figure 1 compares the 7500c and 7500ce configurations, highlighting the simplification in the ion trajectory that has led to the improved performance specifications of the 7500ce. Enhancements in software designed specifically for routine high matrix analyses add additional capability and ease of use. These include the introduction of “Virtual Internal Standardization” (VIS) which allows the user to interpolate between internal standard (ISTD) response factors to create a VIS at a mass where no appropriate ISTD exists. Intelligent calibration resloping can automatically fine-tune a calibration curve, if needed, during a long sequence of high matrix samples, without the time consuming recalibration. This can be accomplished in the same process as monitoring a required continuing calibration verification (CCV).




Figure 1. A comparison of the ion optic and octopole configurations between the Agilent 7500c and 7500ce ICP-MS systems.

Enhanced ORS

Like its predecessor the 7500c, the 7500ce uses collision/reaction cell (CRC) technology in the form of the ORS to remove polyatomic interferences. The use of CRC technology to reduce interferences in ICP-MS is well-documented [3]. However, until now, there have been compromises associated with the use of some designs of CRC ICP-MS for trace level, multi-element analysis in unknown or variable matrices. These compromises included poor sensitivity for low-mass analytes, poor stability, and the necessity for matrix matching of samples and standards to avoid unexpected new interferences caused by complex, sequential reaction chemistry in the cell. As a result, some CRC systems allow only the analysis of a small number of analytes under a specific set of conditions for a single sample matrix.

Numerous publications [3, 4, 5] have discussed the mechanisms for polyatomic interference removal using CRC technology including:

- Collisionally induced dissociation (CID)
- Chemical reaction
 - Charge transfer
 - Atom transfer
- Kinetic energy discrimination (KED)

Mechanism 1, CID, does not occur to any great degree with the relatively light gases typically used in the collision cell because the combined kinetic energy of the collision does not generally exceed the bond energy of the polyatomic species. In most CRC ICP-MS systems, chemical reaction mechanisms including charge transfer and atom transfer

are the predominant mechanisms [4, 5]. However, in order to provide sufficient reduction of interferences, the reaction must be highly favored, which can require the use of very reactive gases for many interferences. Such gases can also react with analyte ions, so reducing sensitivity and compromising multi-element analysis, or form reaction by-products that can interfere with other analytes [4]. In this case, reaction cell conditions must be matched to a specific analyte/matrix combination and cannot be used simultaneously for multiple analytes in variable matrices. Mechanism 3, KED, relies on the fact that at the exit of the collision cell polyatomic species will possess lower kinetic energy than atomic ions at the same mass-to-charge ratio [3, 4]. This is due to the fact that collision cross sections of polyatomic ions are larger than for atomic ions, so that polyatomic species suffer more collisions with the cell gas, thus losing more of their initial energy. A bias voltage at the cell exit is then used to reject the low-energy polyatomic species, while allowing the high-energy atomic ions to enter the quadrupole for analysis and detection

Three Modes of Operation - One Set of Conditions

Table 1 lists the typical instrument conditions used for high-matrix analysis for the 7500ce. Instrument parameters are essentially the same for all three modes of operation¹. This is because no complex procedures are required to remove newly created interferences or to avoid the reactive loss of analyte in any ORS mode.

¹Slightly higher bias voltages are required in the octopole and quadrupole to maintain ion velocity in a pressurized collision cell compared with a nonpressurized cell. Other parameters, with the exception of the cell gas flow, are identical in all modes of operation.


Table 1. Instrument Parameters for Robust Plasma Conditions Used with the 7500ce

Instrument parameter	Normal mode	Hydrogen mode	Helium mode
RF Power	1500 W	<Same	<Same
Sample depth	8 mm	<Same	<Same
Carrier gas	0.85 L/min	<Same	<Same
Makeup gas	0.2 L/min	<Same	<Same
Spray chamber temp	2 °C	<Same	<Same
Extract 1	0 V	<Same	<Same
Extract 2	-160 V	<Same	<Same
Omega bias	-24 V	<Same	<Same
Omega lens	-0.6 V	<Same	<Same
Cell entrance	-30 V	<Same	<Same
QP focus	3 V	-11 V	<Same as H ₂
Cell exit	-30 V	-44 V	<Same as H ₂
Octopole bias	-7 V	-18 V	<Same as H ₂
QP bias	-3.5 V	-14.5 V	<Same as H ₂
Cell gas flow	0	3.0 mL/min H ₂	4.5 mL/min He


The Hydrogen Reaction Mode

In hydrogen reaction mode, the ORS is pressurized using a small flow of pure hydrogen at 1–5 mL min⁻¹. Simple reactions with hydrogen remove argon-based polyatomics according to the following examples.


Charge (e⁻) transfer:






Proton transfer:



Atom transfer:



In all cases the Ar interference is removed from mass 40, 56, 78, and 80. Since Ca, Fe, and Se do not react with H₂, there is no loss of analyte signal.



Note that some of these reaction processes lead to new polyatomic ion species, principally hydrides of the original interference. However, these new, cell-formed species all have low energy and are removed from the ion beam using the same bias voltage, as was discussed above, under interference removal by KED.

Reaction mechanisms can be highly efficient, as evidenced by the calibration curves in Figure 2 for ⁷⁸Se, ⁴⁰Ca and ⁵⁶Fe, which show that all the “normal” background species are reduced significantly under a single set of cell conditions.

Figure 3 illustrates the reduction in background from Ar⁺ at *m/z* = 40 as hydrogen flow in the cell is increased, yielding a 10⁹ reduction in background. Since the reaction chemistry is specific to argon polyatomics, no signal is lost due to reaction of the analyte with hydrogen, as could occur with other more reactive gases. However, due to the specificity of reaction mode, there are numerous examples where it is not useful. For example, in samples where the matrix composition is unknown, or there are multiple polyatomic interferences at a single *m/z*, it is not possible to use reaction mode effectively. In this case, a more generic method of interference removal is needed.




Figure 2. Calibration plots for ⁷⁸Se, ⁴⁰Ca, and ⁵⁶Fe under hydrogen reaction conditions.




Figure 3. Reduction in background on mass 40 for calcium using hydrogen reaction mode. In this case, as the hydrogen flow is increased to about 5 mL/min, the background at mass 40 decreased from approximately 2.5 billion cps to about 1 cps, a $>10^9$ reduction.

The Helium Collision Mode

Helium collision mode can reduce or eliminate polyatomic interferences by one of two mechanisms; either CID or KED. Both are nonreactive mechanisms and so they do not form any new polyatomic ionic species that must be managed. CID can occur when the collision energy between the polyatomic ion and the collision gas (typically He) is sufficient to break the polyatomic bond. The result is two (usually atomic) fragments at lower mass, one of which will retain the charge of the original ion. A few common polyatomic

interferences are bound weakly enough for this to occur. They include NaAr^+ , which can interfere with the measurement of ^{63}Cu in high sodium samples and ArO^+ which interferes with iron. However, when ion energies are properly controlled, KED is the more useful of the two techniques. Kinetic energy discrimination depends on the fact that polyatomic ions are always larger in collisional cross section than monatomic ions (Figure 4), and as a result undergo more collisions and so lose more energy when traversing a pressurized collision cell. Figures 5 and 6 depict the KED process.




Figure 4. Comparison of approximate ionic radii (in picometers) for copper and several polyatomic species.

Figure 5 shows the greater loss of energy of the polyatomic ion relative to the atomic ion, in this case ArCl^+ relative to As^+ . However, for KED to be effective, it must remove the polyatomic ion effectively while not significantly reducing the response of the atomic ion. This means there must be minimal overlap in ion kinetic energies between the polyatomic and atomic ions at the exit of the octopole. For this to be the case, the energy spread of incoming ions must be less than the energy difference between analyte and polyatomic interference at the octopole exit.




Figure 5. KED. Polyatomic species have a larger collision cross section, and so experience more energy dissipating collisions and exit the cell with lower kinetic energy. A small stopping potential between the exit of the octopole and the entrance of the quadrupole keeps the polyatomic ions from entering the quadrupole and being detected.

Only the Agilent ORS can accomplish this, as a result of the use of the ShieldTorch system, which minimizes plasma potential and eliminates secondary ionization in the interface, which would otherwise cause broadening of the ion energy spread. It is also essential to avoid band-broadening collisions induced by high extraction voltages in the high-pressure region immediately behind the skimmer cone. On the 7500ce, this is accomplished by using soft-extraction, (extract 1 operates at 0 to +5 V), as a result of which, the mean ion energy is maintained at less than 2 eV with an ion energy spread of about 0.5 eV, ideal for the KED of plasma-source polyatomic interferences.

A simplified schematic representation of ion kinetic energy and energy distribution for a typical ICP-MS system and from an Agilent 7500 ORS ICP-MS is shown in Figure 6.




Figure 6. Simplified schematic representation of ion kinetic energy and energy distribution of a typical ICP-MS system (upper), and from an Agilent 7500 ORS ICP-MS (lower).

After multiple collisions in the CRC, in both cases the average kinetic energy of the larger polyatomic ions is decreased relative to the smaller atomic ions by b eV. If a kinetic energy barrier is applied to the ion beam at the exit to the collision cell that is equivalent to the kinetic energy difference, b , (indicated by dashed line), then any ions whose kinetic energy is lower than the barrier will be blocked. If the energy distribution of ions is larger than the difference in average energies of the ions, only partial rejection of polyatomic ions occurs accompanied by a loss of atomic ions.

While ED was described on other designs of ICP-MS systems, these systems do not have the tight control of ion energy provided by the ShieldTorch System and so the ED is only effective for reducing the very low energy polyatomics formed within the cell, typically as a result of sequential reaction chemistry, which is characteristic of the use of a highly reactive cell gas, such as NH_3 . Table 2 shows the reactants and products for a number of polyatomic interferences using both hydrogen and ammonia reaction mode. As can be seen, in the presence of common matrix components such as carbon and sulfur, the use of NH_3 can create multiple new interferences, which must be removed. Avoiding the use of NH_3 eliminates the possibility of creating new, cell-formed, polyatomic cluster ions in the first place.

Reaction of hydrogen with plasma-based polyatomics such as Ar^+ is highly favored and results in elimination of the interferent. Neither hydrogen nor NH_3 are effective at removing the interference from ClO^+ on vanadium. Additionally, the use of ammonia can lead to reaction with other common matrix elements such as carbon and sulfur, creating new interferences such as HCN^+ on aluminum and NHSH^+ on titanium. Using the Agilent system with an inert cell gas and KED would eliminate the interference from ClO^+ on vanadium AND, for example, ArC^+ on Cr, without producing any new interferences.

An excellent test of the efficiency of interference removal can be seen in low-level calibration plots. When interferences are present, the response curve will be offset in the y direction by the magnitude of the interference, increasing the background equivalent concentration (BEC) and the detection limit (DL). When the interference is removed, the calibration curve intersects the y-axis at a point much nearer to zero with a correspondingly lower BEC and DL. Figure 7 depicts sub-ppb calibration curves for chromium and vanadium in 1% each methanol, HCl, and HNO_3 , with and without the use of helium collision mode. Since KED does not depend on chemical reaction, it is independent of matrix concentration as well as composition.

Table 2. Comparison of Reaction Products for Several Possible Reactants Involving Hydrogen and Ammonia

Reactants		Interfered analytes	Products	
Ar^+	H_2	Ca^+	H_2^+	Ar
Ar_2^+	H_2	Se^+	ArH^+	Ar, H
ArO^+	H_2	Fe^+	H_2O^+ , ArOH^+	
ClO^+	H_2	V^+	None	None
ClO^+	NH_3	V^+	None	None
HCN^+	H_2	Al^+	HCNH^+ (28)	H
C^+	NH_3		NH_3^+ (17)	C
			HCN^+ (27)	H_2
			HCNH^+ (28)	H
S^+	NH_3		NHSH^+ (48)	




Figure 7. Calibration plots of ^{52}Cr and ^{51}V in 1% nitric, 1% hydrochloric, 1% methanol showing the contribution of interferences from ArC^+ and ClO^+ in normal mode on the left and after removal of interferences by the ORS using He on the right.

Figure 8 depicts the effect of increasing HCl on the measured concentration of a 5-ppb solution of vanadium in both helium and normal (no gas) mode. Increasing the HCl from 0% to 1% causes an 80% increase in measured vanadium concentration in the no-gas mode. There is no increase in the V concentration reported for the variable sample matrix, when measured in He mode.




Figure 8. Effects of increasing HCl concentration on vanadium response in both normal and helium modes.

The Normal Mode

Normal mode uses the octopole as an ion guide only with no additional gas added. In this mode, the Agilent 7500ce ICP-MS operates as a conventional (non-collision cell) instrument. Because an octopole is a highly efficient ion guide as compared with a lower-order multipole, such as a hexapole or quadrupole, there are no compromises in ion transmission efficiency and the addition of a collision gas to promote collisional focusing in normal mode is not required. Because of this, the Agilent

7500ce exhibits exceptional sensitivity for uninterfered low mass elements, such as lithium, beryllium, and boron. Typically, normal mode is used only for these elements, though it is also acceptable for other elements that do not require interference removal such as lead, mercury, thallium, and uranium. Examination of Table 3 will show that the DLs for the interference-free heavy metals are essentially the same in all three modes, giving the user the flexibility to select as appropriate.

Table 3. Three Sigma Detection Limits (ppt). All Isotopes 1 s Total Integration Time Except Ca and Hg Which Were 3 s Total Integration Time

Mass	Element	STD Mode (No gas)		H ₂ Mode (5 mL/min)		He Mode (4 mL/min)	
		DL (3-Sigma)	BEC	DL (3-Sigma)	BEC	DL (3-Sigma)	BEC
6	Li	4.99	17.09	161.491	95.83	331.32	142.58
7	Li	1.67	14.36	23.755	26.31	9.38	20.55
9	Be	0.19	0.11	6.932	2.62	7.812	2.61
11	B	5.88	47.26	83.182	128.03	48.21	107.28
23	Na	3.36	148.40	62.682	313.64	37.65	299.38
24	Mg	0.27	0.72	2.570	1.75	3.37	1.41
27	Al	3.05	50.70	8.079	5.51	37.56	53.52
31	P	418.27	12521.95	—	—	1903.62	3800.52
39	K	1347.50	47564.25	29.532	118.74	2838.73	27943.17
40	Ca	—	—	2.936	7.13	—	—
43	Ca	460.04	8520.74	129.640	121.68	191.85	742.92
44	Ca	2932.48	50407.443	102.104	121.94	48.01	352.38
45	Sc	7.95	183.06	6.446	19.41	1.34	6.46
47	Ti	4.07	40.86	32.197	19.88	4.98	3.52
49	Ti	11.49	57.33	17.535	10.46	5.69	1.70
51	V	0.40	2.52	1.309	0.73	0.42	0.19
52	Cr	5.53	212.670	19.919	68.63	3.10	22.70
53	Cr	7.98	52.87	28.504	82.65	8.70	21.60
55	Mn	1.69	25.24	1.362	4.10	4.25	12.23
56	Fe	1443.70	55093.34	5.034	20.21	53.99	451.26
57	Fe	444.36	23132.21	66.614	261.56	71.06	215.90
59	Co	0.21	2.15	0.816	0.26	0.38	0.30
60	Ni	26.523	672.20	71.224	742.27	41.70	491.67
63	Cu	1.32	37.48	20.271	20.14	6.37	68.35
65	Cu	2.70	47.46	27.845	27.76	7.52	59.76
66	Zn	2.85	9.01	1.612	1.83	1.84	2.18
69	Ga	0.30	3.03	0.273	0.19	0.82	1.04
71	Ga	1.22	7.40	0.125	0.15	1.80	2.22
72	Ge	2.60	53.69	1.448	1.14	3.32	7.55
73	Ge	3.72	32.74	5.556	2.74	7.30	6.04
75	As	23.24	660.78	14.130	14.00	10.72	65.72
78	Se	48.10	6351.29	2.396	2.556	48.93	195.45
82	Se	26.92	251.29	15.225	56.51	20.63	116.01
85	Rb	0.27	1.06	0.349	0.57	0.72	0.34
88	Sr	0.19	0.84	0.072	0.04	0.38	0.13
89	Y	0.10	0.26	0.054	0.04	0.16	0.04
90	Zr	0.07	0.09	0.709	0.18	0.15	0.06

Table 3. Three Sigma Detection Limits (ppt). All Isotopes 1 s Total Integration Time, Except Ca and Hg Which Were 3 s Total Integration Time (Continued)

Mass	Element	STD Mode (No gas)		H ₂ Mode (5 mL/min)		He Mode (4 mL/min)	
		DL (3-Sigma)	BEC	DL (3-Sigma)	BEC	DL (3-Sigma)	BEC
93	Nb	0.12	0.20	0.68	0.53	0.15	0.05
95	Mo	0.32	0.67	14.53	4.33	0.31	0.1
101	Ru	0.60	1.40	19.27	5.74	0.28	0.09
103	Rh	0.08	0.11	4.24	1.75	0.05	0.0
105	Pd	0.30	0.27	10.11	6.39	0.33	0.15
107	Ag	0.23	0.33	1.42	1.61	0.28	0.4
111	Cd	0.56	0.83	0.32	0.20	0.86	0.54
115	In	0.07	0.11	0.05	0.03	0.08	0.05
116	Cd	0.33	0.41	0.40	0.47	0.34	0.23
118	Sn	0.24	0.43	0.55	0.54	0.91	0.73
121	Sb	0.11	0.08	0.21	0.010	0.46	0.25
125	Te	1.96	0.94	2.05	1.29	9.57	4.12
126	Te	1.12	1.64	2.08	1.67	7.33	4.27
127	I	2.02	21.73	3.57	22.30	7.71	20.41
133	Cs	0.09	0.04	0.06	0.04	0.15	0.06
137	Ba	0.22	0.20	0.38	0.16	0.9	0.38
139	La	0.17	1.94	2.49	2.46	0.66	2.14
140	Ce	0.223	2.65	2.18	3.21	0.47	2.88
141	Pr	0.11	0.25	0.12	0.28	0.12	0.31
146	Nd	0.39	0.44	0.43	0.50	0.70	0.73
147	Sm	0.22	0.17	0.11	0.04	0.58	0.24
153	Eu	0.02	0.03	0.04	0.02	0.11	0.03
157	Gd	0.17	0.14	0.15	0.05	0.35	0.22
159	Tb	0.03	0.02	0.01	0.01	0.055	0.03
161	Dy	0.18	0.15	0.05	0.05	0.23	0.17
163	Dy	0.15	0.08	0.08	0.04	0.23	0.16
165	Ho	0.04	0.00	0.02	0.01	0.05	0.02
166	Er	0.15	0.06	0.05	0.02	0.17	0.09
169	Tm	0.02	0.02	0.02	0.01	0.03	0.03
172	Yb	0.11	0.09	0.07	0.02	0.30	0.18
175	Lu	0.04	0.020	0.02	0.01	0.06	0.03
178	Hf	0.13	0.08	0.06	0.06	0.32	0.15
181	Ta	0.04	0.06	0.06	0.049	0.11	0.08
182	W	0.32	0.35	1.39	0.5	0.56	0.33
183	W	5.07	1.07	0.87	0.42	0.43	0.47
185	Re	0.12	0.07	0.07	0.05	0.12	0.08
193	Ir	0.09	0.10	0.25	0.08	0.33	0.15
195	Pt	0.14	0.17	1.94	0.52	0.22	0.18
197	Au	0.22	0.11	1.76	0.43	0.18	0.07
200	Hg	0.82	2.00	1.04	1.78	1.15	2.18
201	Hg	1.11	2.54	2.07	2.29	1.56	2.58
202	Hg	0.86	1.84	0.75	1.77	0.59	1.91
205	Tl	0.20	0.24	0.13	0.22	0.35	0.30
206	Pb	0.33	0.84	0.28	0.64	0.34	0.73
207	Pb	0.51	0.94	0.25	0.69	0.95	1.05
208	Pb	0.47	0.712	0.40	0.55	0.53	0.755
209	Bi	0.05	0.04	0.03	0.02	0.06	0.05
232	Th	0.04	0.04	0.03	0.01	0.06	0.05
238	U	0.05	0.04	0.04	0.01	0.05	0.044

Conclusions

The Agilent 7500ce ICP-MS has achieved its design goals of providing sensitive, robust, interference-free analysis of difficult, high-matrix samples. With five times the sensitivity of its predecessor, nine operating orders of dynamic range and increased matrix tolerance, it is capable of replacing both GFAA and ICP-OES instruments in addition to older generation ICP-MS systems. The 7500ce is unique in offering a single solution for multi-elemental analysis of complex and variable, high matrix samples, while allowing the operator the freedom to use simple and consistent sets of instrument conditions for almost all elements in almost any matrix.

References

1. "Real World Analysis of Trace Metals in Drinking Water using the Agilent 7500ce ICP-MS with Enhanced ORS Technology" Agilent Technologies publication 5989-0870EN
www.agilent.com/chem
2. "Analysis of High Matrix Environmental Samples with the Agilent 7500ce ICP-MS with Enhanced ORS Technology" Agilent Technologies publication 5989-0915EN
www.agilent.com/chem
3. E. McCurdy and G. Woods, The Application of collision/reaction cell inductively coupled plasma mass spectrometry to multi-element analysis in variable sample matrices, using He as a non-reactive cell gas (2004) *JAAS* **19**, (3).
4. S. D. Tanner, V. I. Baranov, and D. R. Bandura, (2002) *Spectrochimica Acta Part B*, **57**, 1361.
5. Using automated collision cell ICP-MS with rapid in-sample switching to achieve ultimate performance in environmental analysis Thermo Electron Corporation Application Note AN_E0640, (2003).

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.


Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
October 8, 2004
5989-1041EN





Interference-Free Semiquantitative Analysis Using the Agilent 7500ce ICP-MS Application

Elemental Analysis

Authors

Glenn Woods, Ed McCurdy
Agilent Technologies
Lakeside, Cheadle Royal Business Park
Stockport, Cheshire, SK83GR, UK

Steve Wilbur
Agilent Technologies, Inc.
3380 146th PI SE Suite 300
Bellevue, WA 98007 USA

Abstract

Rapid and accurate semiquantitative elemental screening of a wide range of sample types is shown to be possible using the Agilent 7500 ORS Series ICP-MS, in the helium-only collision mode. Polyatomic interferences are eliminated in the helium pressurized Octopole Reaction System cell, enabling greater accuracy and data integrity in complex sample matrices.

Introduction

One of the benefits of inductively coupled plasma mass spectrometry (ICP-MS) is the simplicity of the spectra. These are easy to interpret and are frequently used to “fingerprint” unknown samples, using the relative intensities of the various observed isotopes. This data can also provide a means of generating approximate concentrations for uncalibrated elements in a sample - referred to

as semiquantitative (or semiquant) analysis. Quantification is done by comparing the target elements to an internal standard element (or elements) of known concentration.

Semiquant analysis is useful in situations where semiquant calibration standards are unavailable, as is often the case, for example, with solids analysis by laser ablation, and also as a very powerful screening technique. While recent advances in collision/reaction cell (CRC) technology have all but eliminated interferences from quantitative ICP-MS, little is published on their applicability for semiquantitative analysis.

Semiquant elemental analysis by ICP-MS operates on the principle that the relative response (counts per unit concentration) of each element follows a consistent pattern, so the concentration for each element can be calculated from the measured response of any other element. This is because when acquired under consistent operating conditions, the relative elemental response is independent of the species of the element and relatively free from the effects of matrix. Furthermore, the relative response for a given isotope can be predicted with a reasonable degree of accuracy, based on the relative isotopic abundance of the measured isotope and the ionization potential (degree of ionization) of the element.

The Agilent ICP-MS ChemStation contains a database of relative response factors (RFs) for all of the naturally occurring elements that can be



Agilent Technologies

measured by ICP-MS. This database can be updated and resloped by analyzing a semiquant calibration standard or certified reference material and/or including one or more reference elements at known concentration (effectively internal standards - ISTDs) in the sample to be measured.

In common with fully quantitative analysis by conventional ICP-MS, there are several elements or isotopes that do not give accurate results using semiquant analysis because of either isobaric or polyatomic interferences. These of course include the isotopes that have overlaps from ionized argon species, including ^{40}Ca , ^{56}Fe , ^{78}Se , and ^{80}Se . Depending on the sample matrix being analyzed, other common polyatomic interferences from N, C, Cl, S, etc. can also give increased backgrounds and poorer accuracy in the determination of ^{54}Fe , ^{52}Cr , ^{51}V , ^{75}As , ^{77}Se , and many others.

CRC ICP-MS and Semiquant

Recent advances in CRC technology have all but eliminated interferences from quantitative ICP-MS for most matrix types. However, while highly reactive gases may be used for the removal of many interfering species, they have two important limitations: namely, they may cause the loss of some analytes by reaction, and they will cause some new interferences as a result of secondary reaction chemistry. As a result, these gases can be used effectively only when the analyst has some detailed knowledge of the interference that is being targeted, so that the thermodynamics of the reaction pathways can be predicted and a suitable cell gas and set of conditions can be selected for each target interference.

Even reaction gases that are effective at removing several different interferences (the so-called universal reaction gases) must rely on reaction chemistry to remove the interferences, and so they will not be effective against interfering ions that are unreactive with that particular gas. As a result, errors will be introduced if any highly reactive cell gas is used for the analysis of unknown or variable high matrix samples where, typically, the interferences are not known in advance.

For the most accurate semiquantification results to be achieved, it is essential that all elements are

acquired under the same conditions, so the consistent relationship between the response of adjacent elements is maintained. As a result, it is not possible to use CRC technology in reaction mode to reduce interferences in semiquant in the same way as in full quantification.

However, the unique ability of the Agilent 7500 ORS (Octopole Reaction System) to eliminate polyatomic interferences using carefully controlled kinetic energy discrimination (KED) in helium collision mode allows accurate semiquantification in complex, unknown sample matrices. Since helium is a nonreactive gas, no new interferences are formed in the cell, no analytes are lost by reaction, and the plasma-formed and matrix-formed polyatomic interferences are eliminated through a physical “molecular filtering” process, as a function of their larger ionic radii (Figure 1).




Figure 1. Graphic representation of the relative diameter of an atomic ion (Cu) compared with the polyatomic (molecular) ions that can interfere with the Cu at mass 65 [1, 2]. Most elemental ions are smaller than 150-picometer radius, while most polyatomic ions are larger.*

*Actual ion radii may vary according to conditions, but the relative relationships are constant.

Since only a single set of ORS cell parameters is used, consistent RFs are maintained, regardless of sample matrix. Since helium collision mode eliminates only polyatomic interferences, interference-free isotopes of elements suffering from isobaric interferences must still be used. For the most part,

the only significantly affected isotope is ^{40}Ca . In this case, ^{44}Ca can be used. KED eliminates the transmission of the larger polyatomic ions to the quadrupole by placing an energy barrier between the octopole and quadrupole (Figure 2).




Figure 2. Diagrammatic representation of KED after energy-depleting collisions within the ORS cell.

Since the larger polyatomic ions undergo more energy-depleting collisions with He in the cell than do the smaller atomic ions, they lack sufficient energy to cross the barrier. Figure 3 depicts the effects of KED on ion energy. Only the high-energy atomic ions exceed the stopping potential and are transmitted.




Figure 3. Effects of KED on the larger diameter polyatomic ions relative to the smaller atomic ions.

Figures 4–7 illustrate the effective removal of multiple polyatomic interferences on several interference-prone elements. In this case, a standard containing 5 ppb of the elements of interest was measured in a matrix containing increasing concentrations of sulfuric acid, hydrochloric acid, and butanol. This matrix was designed to create sulfur, carbon, chlorine, and oxygen based interferences. Measurements were taken in the “normal” mode (no gas in the collision cell), and in helium collision mode. Instrument conditions are listed in Table 1.

Since polyatomic interferences are removed simply due to their size and not their reactivity, He collision mode works effectively with all matrices. And

since only a single set of ORS cell parameters is used, consistent RFs are maintained, regardless of sample matrix.

Table 1. Experimental Conditions Used for Acquisitions Depicted in Figures 4–7

Instrument	Agilent 7500ce
Mode of operation	He cell gas (5 mL/min)
Cell gas flow variation	None
Cell voltage variation	None
Calibration matrix	1% HNO ₃
Sample matrix components	H ₂ SO ₄ + HCl + BuOH
Sample matrix levels (each)	0%, 0.1%, 0.5%, 1.0%
Analyte spike level	5 ppb
Internal standard	⁷² Ge
Interference correction equations used	None




Figure 4. Measurement of vanadium ($m/z = 51$) and ClO^+ ($m/z = 51$) in a matrix of increasing concentrations of sulfuric acid, hydrochloric acid, and butanol with and without the use of interference removal by KED in He collision mode.




Figure 5. Potential interferences at mass 52 in this matrix include $^{34}\text{S}^{18}\text{O}$, $^{35}\text{Cl}^{16}\text{O}^1\text{H}$, and $^{40}\text{Ar}^{12}\text{C}$. All are removed, regardless of reactivity, under a single set of conditions, allowing accurate quantification of Cr at the major isotope.




Figure 6. Potential interferences at mass 66 in this matrix include $^{34}\text{S}^{16}\text{O}_2$, $^{32}\text{S}^{34}\text{S}$, and $^{40}\text{Ar}^{12}\text{C}^{14}\text{N}$. All are removed, regardless of reactivity, under a single set of conditions, allowing accurate quantification of Zn at the preferred isotope.




Figure 7. Potential interferences at mass 65 in this matrix include $^{33}\text{S}^{16}\text{O}_2$, $^{32}\text{S}^{33}\text{S}$, and $^{40}\text{Ar}^{12}\text{C}_2^1\text{H}$ [3]. All are removed, regardless of reactivity, under a single set of conditions, allowing accurate quantification of Cu at this isotope.

Reproduced by permission of The Royal Society of Chemistry (2004) *J. Anal. At. Spectrom.*, **19**, 607–615.

Semiquant Analysis - Method

The instrument was tuned for typical robust plasma conditions, as indicated in Table 2.

Table 2. Typical Instrumental Conditions Used for Semiquant Analysis in He Collision Mode

RF power	1550 W
Carrier gas flow rate	0.85 L/min
Makeup gas flow rate	0.2 L/min
Sampling depth	8 mm
Peristaltic pump speed	0.05 rps
Spray chamber temperature	2 °C
Helium flow	3–5 mL/min

The following acquisition parameters were used (Figure 8).

Integration time:	0.1 s
Mass range:	5–240*
Replicates	1
Peak pattern	Peak hopping, single point per mass

* The “empty masses,” for example between 210–230 and masses for elements including C, O, N, F, and the noble gases, were skipped to reduce total acquisition time. Total acquisition time is less than 60 s for one replicate.




Figure 8. Semiquant acquisition parameter dialog box.

A single calibration standard at 100 ppb, made up in 1% HNO₃/0.5% HCl, was used to update the semiquant RF database for a range of elements across the mass range. Noncalibrated elements are updated by interpolating between calibrated isotopes, which the ICP-MS ChemStation software does automatically. Any number of calibration elements may be used, but increasing the number of calibration elements will reduce the mass range over which the factors are interpolated between measured reference elements and, therefore, improve semiquantitative accuracy. Internal standardization was applied using a typical suite of ISTD elements distributed across the mass range.

Results

Prior to the analysis of some reference materials to test the accuracy of semiquant analysis using the ORS, a further study was made to confirm matrix interference removal.

A very challenging test matrix consisting of 1% HNO₃, 1% HCl, 1% H₂SO₄, 1% Butanol, and 100 ppm each of Ca and Na was prepared, and spectra obtained in both non-gas and He modes. Figure 9 is the spectrum obtained when the matrix is analyzed with the ORS operating without any gas. In this mode, the instrument behaves like a standard non-CRC ICP-MS and peaks from polyatomic species such as ¹⁶O³⁵Cl (at 51), ⁴⁰Ar¹²C (at 52), ⁴⁰Ar¹⁶O/⁴⁰Ca¹⁶O (at 56), ³²S¹⁶O₂ (at mass 64), ⁴⁰Ar³²S (at mass 72), ⁴⁰Ar³⁵Cl (at 75), and ⁴⁰Ar⁴⁰Ar (at 80), etc. can be seen. In this matrix, analysis of many transition elements would be severely compromised.




Figure 9. Blank containing 1% each of HNO_3 , HCl , H_2SO_4 and BuOH , plus 100-ppm Ca and Na acquired on a 7500ce in non-gas mode. Note polyatomic peaks.

Figure 10 shows the spectra obtained from the same matrix, under the same operating conditions, except with He in the cell. Note the elimination of most of the polyatomic species to sub-ppb levels (the He mode spectrum is on an intensity scale 400 times lower than the non-gas mode spectrum). The analyte peaks are due to trace contamination in the matrix. The lower spectrum demonstrates

the interference removal power of the ORS in He mode. In this very challenging matrix, the ORS simultaneously removes all polyatomic interferences. At the same time, no new, cell-formed interferences are generated. The ORS offers greater data integrity in high matrix samples, in both semiquantitative and quantitative modes.




Figure 10. Blank containing 1% each of HNO_3 , HCl , H_2SO_4 , and BuOH , plus 100-ppm Ca and Na acquired on a 7500ce in He mode. Note polyatomic peaks were eliminated and the residual metal peaks arising from impurities in the matrix, Fe approx. 1.5 ppb, Zn approx. 5 ppb, Cu approx. 0.2 ppb. The isotopic fingerprint is overlaid to illustrate this point. Peak at m/z 75 is due to As and not ArCl , since there is no ArCl peak at m/z 77.

Tables 3 and 4 show the results of a semiquant measurement of two standard reference materials, NIST 1640 water and LGC 6177 landfill leachate. No attempt was made to matrix-match and the plasma conditions shown in Table 2 were used with the same He collision mode for all elements in all matrices. In all cases, for every certified element, the measured response was very close to the certified concentration from as low as 2 ppb for Rb in NIST 1640 to over 1700 ppm for Na in the LGC 6177 landfill leachate.

Table 3. Results for NIST 1640 Standard Reference Water Using He Semiquant Mode, in ppb

Element mass	SQ conc.	Ref	Element mass	SQ conc.	Ref	Element mass	SQ conc.	Ref
Li 7	IS Element	50.7	Se 78	21	21.96	Sm 147	0.072	N/A
Be 9	35	34.94	Br 79	<0.1600	N/A	Eu 153	0.0098	N/A
B 10	280	301.1	Rb 85	1.8	2	Gd 157	0.065	N/A
Na 23	30,000	29,350	Sr 88	120	124.2	Tb 159	0.0017	N/A
Mg 24	5,700	5,819	Y 89	0.051	N/A	Dy 163	0.021	N/A
Al 27	54	52	Zr 90	0.091	N/A	Ho 165	0.006	N/A
Si 28	4,800	4,730	Nb 93	0.0035	N/A	Er 166	0.016	N/A
P 31	35	N/A	Mo 95	46	46.75	Tm 169	<3.600E-4	N/A
S 34	110	N/A	Ru 101	<3.400E-3	N/A	Yb 172	0.0082	N/A
K 39	1,000	994	Rh 103	IS Element	N/A	Lu 175	6.50E-04	N/A
Ca 44	9,300	7,045	Pd 105	<2.900E-3	N/A	Hf 178	<1.400E-3	N/A
Sc 45	<5.800E-3	N/A	Ag 107	7.7	7.62	Ta 181	3.10E-04	N/A
Ti 49	0.089	N/A	Cd 114	22	22.79	W 182	0.017	N/A
V 51	13	12.99	In 115	0.0046	N/A	Re 185	0.0067	N/A
Cr 52	37	38.6	Sn 118	2.1	N/A	Os 189	<1.600E-3	N/A
Mn 55	120	121.5	Sb 121	15	13.79	Ir 193	IS Element	N/A
Fe 56	29	34.3	Te 125	<0.1200	N/A	Pt 195	<1.300E-3	N/A
Co 59	19	20.28	I 127	0.17	N/A	Au 197	0.0065	N/A
Ni 60	26	27.4	Cs 133	0.078	N/A	Hg 202	0.012	N/A
Cu 63	87	85.2	Ba 137	140	148	Tl 205	0.035	N/A
Zn 66	55	53.2	La 139	0.42	N/A	Pb 208	27	27.89
Ga 69	32	N/A	Ce 140	0.52	N/A	Bi 209	0.0015	N/A
Ge 72	IS Element	N/A	Pr 141	0.076	N/A	Th 232	0.16	N/A
As 75	24	26.67	Nd 146	0.35	N/A	U 238	0.85	N/A

Table 4. Results for LGC 6177 Standard Reference Landfill Leachate Using He Semiquant Mode, in ppb

Element mass	SQ conc.	Ref	Element mass	SQ conc.	Ref	Element mass	SQ conc.	Ref
Li 7	IS Element	N/A	Se 78	<16.00	N/A	Sm 147	<0.05000	N/A
Be 9	<2.400	N/A	Br 79	6,900	N/A	Eu 153	0.036	N/A
B 10	6,700	9,800	Rb 85	400	N/A	Gd 157	0.036	N/A
Na 23	1,500,000	1,750,000	Sr 88	980	N/A	Tb 159	0.0098	N/A
Mg 24	62,000	73,500	Y 89	0.28	N/A	Dy 163	0.14	N/A
Al 27	110	N/A	Zr 90	49	N/A	Ho 165	0.061	N/A
Si 28	22,000	N/A	Nb 93	1.4	N/A	Er 166	0.052	N/A
P 31	12,000	11,500	Mo 95	6.6	N/A	Tm 169	0.011	N/A
S 34	1,600	N/A	Ru 101	<0.04200	N/A	Yb 172	0.044	N/A
K 39	810,000	780,000	Rh 103	IS Element	N/A	Lu 175	0.01	N/A
Ca 44	77,000	74,800	Pd 105	<0.03500	N/A	Hf 178	0.44	N/A
Sc 45	0.21	N/A	Ag 107	1.8	N/A	Ta 181	0.0066	N/A
Ti 49	18	N/A	Cd 114	0.94	N/A	W 182	58	N/A
V 51	63	N/A	In 115	0.18	N/A	Re 185	0.061	N/A
Cr 52	160	180	Sn 118	48	N/A	Os 189	<0.01700	N/A
Mn 55	130	140	Sb 121	5	N/A	Ir 193	IS Element	N/A
Fe 56	3,300	3,800	Te 125	3	N/A	Pt 195	<0.01300	N/A
Co 59	40	N/A	I 127	1,200	N/A	Au 197	5.4	N/A
Ni 60	170	210	Cs 133	3.5	N/A	Hg 202	0.28	N/A
Cu 63	41	N/A	Ba 137	770	N/A	Tl 205	<7.600E-3	N/A
Zn 66	250	260	La 139	0.24	N/A	Pb 208	17	N/A
Ga 69	130	N/A	Ce 140	0.7	N/A	Bi 209	2.4	N/A
Ge 72	IS Element	N/A	Pr 141	<1.000E-2	N/A	Th 232	0.1	N/A
As 75	86	N/A	Nd 146	0.2	N/A	U 238	0.35	N/A

Conclusions

Semiquant has always been a powerful tool available to the ICP-MS analyst for quickly reporting the concentration of unknown, uncalibrated elements in a variety of simple matrices. However, in complex matrices, polyatomic interferences could introduce inaccuracies in the reported results for several elements. CRC technology which requires specific conditions for different elements or different sample matrices (for example, specific reaction processes to remove pre-identified interferences), cannot be used since this would result in deviation from the standard relative response tables upon which semiquant is based. Helium collision mode coupled with kinetic energy discrimination in the Agilent 7500 ORS Series instruments can overcome these limitations. By effectively removing all polyatomic interferences regardless of source and reactivity, rapid, accurate semiquantitative screening of a wide range of sample types for most possible analyte elements is possible.

CRC-ICP-MS systems that rely on the use of reaction gases such as CH₄ and NH₃ have limited applicability in unknown complex matrix samples

due to the risk of interference from new polyatomic species generated by reaction with the cell gas. Typically in environmental analysis, reaction mode can only be used for 4–5 analytes. Since He collision mode is nonreactive and produces no new interferences, it can be used for all analytes and in any matrix. He collision mode applies equally well in quantitative analysis, enabling the 7500ce to quantitate previously difficult-to-measure analytes at trace levels in complex, unknown sample matrices.

References

1. Inorganic Chemistry: Principles of Structure and Reactivity (4th Edition) James E. Huheey, Ellen A. Keiter, Richard L. Keiter, 1997 p. 292.
2. "Structural Inorganic Chemistry," (5th Edition) A.F. Wells, Clarendon Press, Oxford, 1984, p. 1288.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.


Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2004

Printed in the USA
September 20, 2004
5989-1492EN



Agilent Technologies



Extending the Dynamic Range of Environmental ICP-MS Using the Integrated Sample Introduction System and Octopole Reaction System

Replacing Graphite Furnace AA and Optical ICP Application

Environmental

Author

Steven M. Wilbur
Agilent Technologies, Inc.
2850 Centerville Road
Wilmington, DE 19808-1610
USA

Abstract

The Octopole Reaction System in the Agilent 7500c inductively coupled plasma mass spectrometer (ICP-MS) can be used to reduce the interferences on critical trace elements, such as arsenic and selenium in environmental samples. It can also be used to reduce the response of certain high concentration matrix elements, such as Na, K, Ca and Mg. As such, it can extend the dynamic range of ICP-MS over a range of elements to exceed that of the traditional combination of graphite furnace atomic absorption plus ICP optical emission spectroscopy (ICP-OES). When used in conjunction with the Integrated Sample Introduction System, dynamic range and productivity are further enhanced.

Introduction

While ICP-MS has become the predominant technique for environmental metals analysis, until recently, limitations in practical dynamic range have still necessitated the use of ancillary techniques such as graphite furnace atomic absorption (GFAA) and ICP-OES for measurements at extremely high or low concentrations. This has been especially

true for very high-concentration analytes or very high-matrix concentrations, which typically required dilution before analysis. To meet the dynamic range needs of environmental laboratories using a combination of GFAA and ICP-OES for each sample, the ICP-MS must be able to tolerate typical matrix concentrations with little or no dilution, measure high-concentration elements at ICP-OES levels (~100 ppm), and measure trace elements at GFAA limits of detection.

Dynamic Range in ICP-MS

Dynamic range as it pertains to ICP-MS can have many meanings depending on the context or application. It can mean the range of concentrations for a given analyte in a given matrix for which the instrument response is linear. It is also commonly defined by the linear range of the detector because this is well defined and independent of sample, plasma and other instrument conditions. However, in the analysis of environmental samples, neither of these definitions actually defines the actual useful dynamic range of the ICP-MS system. Environmental samples vary significantly in their composition and concentration, both of matrix and analyte. It is generally desirable to be able to measure certain elements at trace (ppb) or ultratrace (ppt) levels while measuring other elements in the same sample at much higher concentrations. As a result, the practical linear dynamic range of ICP-MS in environmental applications is limited by the interaction of many system processes and components.



Agilent Technologies

Limitations to Linear Dynamic Range

The detector ultimately limits the range of analysis for a given element in a given matrix. Employing both pulse and analog counting techniques, the linear range of modern ICP-MS detectors is $\sim 10^9$. Depending on the response of the element, this may be a concentration range from less than a ppt to hundreds of ppm. Element response is, in turn, dependent on many factors including relative isotopic abundance, ionization potential, the composition of the matrix, and various instrument design and tune parameters that affect ion transmission efficiency.

In practice, however, the dynamic range is limited to much narrower ranges of concentration by other factors. These factors include the effects of matrix, both on the plasma and on the transmission of ions from the plasma to the detector. A matrix high in easily ionized elements, such as sodium or potassium, can suppress the ionization of more difficult to ionize elements, such as Hg or Se. Also, high concentrations of heavy ions can suppress the response of lower mass ions through space charge effects in the ion optic region of the ICP-MS. Memory effects or carryover can also significantly limit the practical dynamic range. Typical washout after introducing a high-concentration sample is 2–4 orders of magnitude reduction in measured concentration per minute of rinse depending on the element and instrument configuration. Where analysis time is important, these memory effects limit the dynamic range per element significantly. Other limitations include the effects of deposition of matrix on the interface and lens components. Due to the extremely high sensitivity of ICP-MS, linear range is also limited by the availability of suitably clean blanks. It is very difficult in the production environmental laboratory to maintain blanks at the actual instrument background. For example, sensitivities of 100 million counts per second per ppm (100 MCPS/ppm) with instrument backgrounds of 1 to a 5 CPS are now quite possible. Such signal to noise yields an instrument background equivalent concentration (BEC) of 10–50 ppq. In this case, a typical environmental laboratory, whose blanks may contain a single-to double-digit ppt levels or higher of some elements, is sacrificing three or more orders of magnitude of its instruments maximum dynamic range.

From a practical standpoint, the single element dynamic range required by most environmental labs is only about three to at most four orders of magnitude. This is based on current required detection limits and concentration ranges typically found in environmental samples as well as limitations due to memory effects. However, the element-to-element dynamic range is much higher. For example, it is desirable to have very low limits of detection for highly toxic elements, such as mercury, and at the same time in the same sample, very high linear range for common matrix elements, such as calcium or sodium. In this case, the interelement dynamic range could be from 1–5 ppt for Hg to upwards of 1000 ppm for Na or Ca, or about 10^9 , while the single element range is still only 3–4 orders of magnitude. If we factor in the loss of range at the low end due to interferences or blank contamination, we have exceeded the range of the detector. To reduce this limitation, it is necessary to reduce both the background for certain elements and the count rates for others. It is also necessary to minimize the effects of sample matrix on the plasma and interface components.

Maximizing Dynamic Range

The combined application of several techniques is necessary to achieve the desired dynamic range. These techniques work together to:

1. Minimize memory effects
2. Minimize blank background
3. Minimize matrix-based spectroscopic interferences
4. Minimize matrix-based nonspectroscopic interferences
5. Minimize count rates for high-response, high-concentration analytes while maintaining maximum response for trace analytes
6. Minimize matrix accumulation on sample introduction and interface components

Most of these effects can be achieved through the implementation of two features of the Agilent 7500 series ICP-MS. One is the Integrated Sample Introduction System (ISIS). The other is the Octopole Reaction System (ORS), which defines the Agilent 7500c ORS system. Together, they comprise the Agilent 7500ci Environmental Analysis System.

ISIS

Two features of ISIS (see Figure 1) serve to minimize the effects of matrix on dynamic range and instrument performance. They are constant flow nebulization and rapid sample uptake. Constant flow nebulization takes advantage of very close coupling of the nebulizer peripump to the nebulizer. By minimizing the associated swept volume, it is not necessary to use high nebulizer flow during sample uptake and rinseout. At the same time, sample is delivered to the nebulizer peripump at very high flows via an open-split interface at the nebulizer peripump.

By uncoupling the sample uptake and rinse flow from the nebulizer flow, it is possible to have very rapid sample uptake and rinseout without overloading the sample introduction system (nebulizer,

spray chamber, and torch), and interface (interface cones and ion lenses). As a result, the total matrix loading on the ICP-MS is significantly reduced while uptake speeds and rinseout are improved. Furthermore, because all Agilent ICP-MS systems are designed for optimum performance using low-flow nebulizers, performance is never compromised to reduce matrix.

ISIS also has the ability to autodilute high-concentration samples, as needed, to further reduce matrix effects. Thus, the use of ISIS with an efficient low-flow nebulizer can address items 1, 4 and 6 above. Additional design features of all Agilent ICP-MS systems, which permit the analysis of high-matrix samples with minimum detrimental effects, are discussed in an Agilent ICP-MS Technical Note, publication 5968-1897E .




Figure 1: ISIS depicting large sample uptake and diluent pumps is at the upper left, and the small three-channel nebulizer pump is at the lower right.

ORS

Spectroscopic interferences from the plasma or sample matrix and excessive count rates for high-concentration analytes can be addressed through the use of the ORS. See Figure 2.

The ORS is a static, radio frequency (RF) only multipole composed of eight parallel stainless steel rods arranged in a linear octagon. The octopole is contained in a vessel that can be pressurized relative to the surrounding vacuum with a reaction gas, normally either helium or hydrogen. The octopole functions both as an ion guide, replacing many of the ion-focusing lenses on the non-octopole system, and as a collision/reaction cell.

When used in the pressurized collision/reaction mode, the ORS has the ability to significantly reduce or remove spectroscopic interferences from ionized argon and plasma or matrix-based polyatomic ions. By reducing the background, the signal to noise of the analyte is improved. Eliminating certain interferences also allows the measurement of alternate, more abundant analyte isotopes. For example, reduction of the argon-based interferences at m/z 40 and 80 allows the measurement of the major isotopes of Ca and Se, which is not possible without the use of the ORS in most environmental matrices. Use of the ORS to remove NaAr^+ allows the measurement of the most abundant copper isotope at m/z = 63.




Figure 2. Agilent 7500c ion optic region with octopole collision/reaction cell. Ion path is depicted by dark squares.

Experimental

Six-level external calibration plots were generated for Na-23, Mg-25, K-39, Ca-40, Fe-56, and Se-78. They are shown in Figures 3 through 8, with linear and logarithmic curve fits.




Figure 3. Calibration plot for sodium from 10 ppb to 100 ppm, hydrogen mode.




Figure 4. Calibration plot for magnesium from 10 ppb to 100 ppm, hydrogen mode.




Figure 5. Calibration plot for potassium from 10 ppb to 100 ppm, hydrogen mode.




Figure 6. Calibration plot for calcium from 10 ppb to 100 ppm, hydrogen mode.




Figure 7. Calibration plot for iron from 10 ppb to 100 ppm, hydrogen mode.




Figure 8. Calibration plot for selenium from 0.1 ppb to 100 ppm, hydrogen mode.

A response plot for the scandium internal standard at six different calibration levels is shown in Figure 9.




Figure 9. Response plot for scandium internal standard at six calibration levels.

Extending the Dynamic Range

We take advantage of two properties of the ORS to extend the practical dynamic range of the ICP-MS instrument in both directions. By using the ORS in hydrogen mode:

- We eliminate the argon based interference on Se 78 (or 80). This permits the measurement of a more abundant isotope, which is normally free of other matrix-based interferences. The other commonly measured isotopes of Se, m/z 77 and 82, in addition to being less abundant than 78 and 80, suffer from interferences from ArCl at 77 and Kr or HBr at 82, respectively. As a result, measurement of selenium in typical environmental samples at ppt levels is easily accomplished.

- We take advantage of the low-mass signal attenuation due to collisions with hydrogen gas within the cell. In this way, elements, which normally have very high response and can have high concentrations in environmental samples such as sodium and calcium, can be attenuated before the signal reaches the quadrupole and detector. This can be used to increase the linear range upward by a factor of 10. By reducing the ion current for these common elements, detector wear and tear is reduced as well.

In summary, use of the ORS in hydrogen mode for the 'mineral elements', Na, K, Ca, Mg, and Fe, and trace elements such as selenium, can, under a single set of conditions, extend the practical dynamic range of the ICP-MS by a factor of 10 or more downward for selenium and a factor of 10 upward for the minerals. The majority of the other analyte elements can be run in 'normal' mode, for example, no gas in the cell.

In special cases where matrix-based interferences prohibit the measurement of other analytes at sufficiently low levels, helium collision mode can be used as well. Examples include the measurement of ^{63}Cu in the presence of high concentrations of Na or As when Germanium is used as an internal standard. ^{74}GeH as well as ArCl can interfere with the measurement of As in some samples.

Figure 10 shows the acquisition parameter setup and Table 1 shows the results of analysis of a standard reference water sample, NIST 1640. Normally,

this sample would require two analyses to bracket both the trace elements, such as silver, and the matrix elements, such as sodium, within the calibration range. Also, minimizing the interference from CaO and ArO on iron is difficult at this level. In this example, the sample was analyzed only once, undiluted, and without the use of interference equations. The dynamic range was sufficient to measure sodium directly at ~ 30 ppm and the trace elements at ppb levels. Interferences on As, Fe, Se, Cu, and V were eliminated.




Figure 10. Acquisition parameters setup panel showing multi tune setup. Tune step 1 is hydrogen reaction mode, step 2 is helium collision mode, and step 3 is "normal mode", for example, the ORS is unpressurized.

Table 1. Analysis of NIST 1640: Trace Metals in Water without Dilution Using Multi Tune Acquisition

Sample:	NIST 1640		
Date/Time:	2/12/2002 17:05		
Method:	ENV7500C.M		
Element	Measured value	Certified value	% Recovery
Be 9	35.49	34.94	101.6
Na 23	29250	29350	99.7
Mg 24	5679	5819	97.6
Mg 25	5686	5819	97.7
Al 27	52.49	52	100.9
K 39	966.6	994	97.2
Ca 40	6938	7045	98.5
V 51	12.81	12.99	98.6
Cr 52	36.07	38.6	93.4
Mn 55	113.5	121.5	93.4
Fe 56	31.18	34.3	90.9
Co 59	21.41	20.28	105.6
Ni 60	26.9	27.4	98.2
Cu 63	84.64	85.2	99.3
Zn 66	59.69	53.2	112.2
As 75	28.98	26.67	108.7
Se 78	22.13	21.96	100.8
Mo 95	44.89	46.75	96.0
Mo 98	47.07	46.75	100.7
Ag 107	7.954	7.62	104.4
Cd 111	22.41	22.79	98.3
Cd 114	22.7	22.79	99.6
Sb 121	13.8	13.79	100.1
Ba 135	147.2	148	99.5
Ba 137	145.7	148	98.4
Pb 208	29.14	27.89	104.5

Figure 11 shows the Tuning Panels for both a water blank (A) and a mixed sodium (1000 ppm)/selenium (10 ppb) sample (B), under hydrogen collision conditions.





Figure 11. Tune Panel showing (A) blank water and (B) 1000 ppm sodium plus 10 ppb selenium simultaneously under hydrogen collision conditions.

Figure 12 displays the reaction gas autotuning panel for three elements, Fe-56, Se-78, and Pb-208. The hydrogen gas flow rate, which yields the lowest BEC, is calculated automatically.




Figure 12. Reaction gas autotuning panel.

Figure 13 compares the practical dynamic range of various elemental techniques.




Figure 13. Practical dynamic range in environmental samples comparing GFAA, ICP-OES, conventional ICP-MS and Agilent 7500C ORS ICP-MS.

Conclusions

Using the Agilent 7500c ICP-MS, it is now possible not only to meet, but to exceed the combined dynamic range of GFAA and ICP-OES for the analysis of typical environmental samples in a production laboratory environment. By taking advantage of the inherent matrix tolerance of the doubly off-axis octopole reaction system, hardware optimized for low sample flows, and ISIS, the 7500c can tolerate matrix levels previously restricted to optical ICP. Accurate quantitation of mineral

elements at 100s or even 1000s of ppm is possible. At the same time, the high sensitivity, low background, and ability to eliminate or reduce spectral interferences by the Agilent 7500c allow the simultaneous measurement of ultratrace levels of previously difficult elements, such as arsenic, selenium, or mercury.

For More Information

For more information on our products and services, visit our Web site at www.agilent.com/chem.

Agilent shall not be liable for errors contained herein or for incidental or consequential damages in connection with the furnishing, performance, or use of this material.

Information, descriptions, and specifications in this publication are subject to change without notice.

© Agilent Technologies, Inc. 2002

Printed in the USA
January 6, 2003
5988-6628EN



Agilent Technologies

Emerging Contaminants

Emerging Contaminants: PPCPs

Determination of Pharmaceuticals in Water by SPE and LC/MS/MS in Both Positive and Negative Ion Modes

The Use of Accurate Mass, Isotope Ratios, and MS/MS for the PPCPs in Water

EPA Method 1694: Agilent's 6410A LC/MS/MS Solution for Pharmaceuticals and Personal Care Products in Water, Soil, Sediment ...

Emerging Contaminants: PFOA/PFOS

Quantitative Analysis of Perfluorooctanoic Acid by LC/MSMS

Addressing the Challenges of Analyzing Trace Perfluorooctanoic Acid (PFOA) and Perfluorooctane Sulfonate (PFOS) Using LC/QQQ

Analyzing Compounds of Environmental Interest Using an LC/Q-TOF Part 2: Fluorotelomer Unsaturated Acids

Emerging Contaminants: PBDEs

GC Analysis of Polybrominated Flame Retardants

Determination of Polybrominated Diphenylethers (PBDE) in Sediment and Sewage Sludge

Determination of polybrominated diphenyl ethers in polymeric materials using the 6890 GC / 5973N-inert MSD with electron impact ...

Applying the 5975 inert MSD to the Higher Molecular Weight Polybrominated Diphenyl Ethers (PBDEs)

Polybrominated Diphenyl Ether (PBDE) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column

Emerging Contaminants: Other

Analyzing Compounds of Environmental Interest Using an LC/Q-TOF Part 3: Imidacloprid and Manool

Analyzing Compounds of Environmental Interest Using an LC/Q-TOF Part 1: Dyes and Pigments

Water Applications

Water: Volatiles

Ultra-Fast Total Petroleum Hydrocarbons (TPH) Analysis with Agilent Low Thermal Mass (LTM) GC and Simultaneous Dual-Tower Injection

Chlorinated Solvents and Disinfection By-Product Analysis Using Agilent J&W HP-1ms Ultra Inert and DB-1301 Capillary GC Columns

Analysis of VOCs by Purge-and-Trap GC/MS

Stir Bar Sorptive Extraction: Off-Flavor Compounds

Low Concentration Oxygenates Using Purge-and-Trap GC/MS

Gas Phase Sample Extraction System – Trace Analysis of Organic Components

BFB Tuning for Environmental Analysis

Analysis of VOCs by Purge-and-Trap GC/MS

Using the 6890 GC and 5973 MS for EPA Method 524.2

Gasoline (BTEX) in Water and Soil Using GC/FID

Ambient Headspace GC and GC-MSD for Nonpolar Volatiles

Analysis of EDB and DBCP with the 6890 GC and EPA Method 504

Analysis of Formaldehyde and Acetaldehyde

Water: Semi-volatiles

Addressing the Challenges of Analyzing Trace Perfluorooctanoic Acid (PFOA) and Perfluorooctane Sulfonate (PFOS) Using LC/QQQ

Fast USEPA 8270 Semivolatiles Analysis Using the 6890/5973 inert GC/MSD with Performance Electronics

Robustness of Eclipse PAH Columns for HPLC Analysis of Polycyclic Aromatic Hydrocarbons

Semivolatiles Retention Time Locked (RTL) Deconvolution Databases for Agilent GC/MSD Systems

Femtogram GC/MSD Detection Limits for Environmental Semivolatiles Using a Triple-Axis Detector

Index

Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column
EPA Method 1694: Agilent's 6410A LC/MS/MS Solution for Pharmaceuticals and Personal Care Products in Water, Soil, Sediment ...
Semivolatile Organics Analysis Using an Agilent J&W HP-5ms Ultra Inert Capillary GC Column
Sub-ppb Levels of Phthalates by Auto-SPME and GC-MS
Analysis Using High-Efficiency Capillary GC Columns
Separation of Explosives in EPA 8330
Parts-per-Trillion Level Calibration Using LVI-PTV-GC/MSD
Cycle Time Reduction Using the 7890A/5975 GC/MSD for EPA Method 8270
Drinking Water Analysis Using the 6890N/5975B inert GC/MSD
Synchronous SIM/Scan Low-Level PAH Analysis Using the 6890/5975 inert GC/MSD
Applying the 5975 inert MSD to the Higher Molecular Weight PBDEs
Fast USEPA 8270 Analysis Using the 6890N/5975 inert GC/MSD
Determination of PBDE in Polymeric Materials
Effect of Sample Matrix on Suppression of Ionization Using LC-ESI-MS
Full-Scan Low-Level PAH Analysis
Fast Analysis Using the 6890/5973 inert GC/MSD
Solid-Phase Extraction and RTL GC/MS Analysis of Selected PAHs
Solid-Phase Extraction and GC/MS Analysis of Selected Phenols
6890/5973 GC/MSD Improvements
A New Approach to the Analysis of Phthalate Esters by GC/MS
Analysis of Nitroaromatics and Nitro-PAH by Capillary GC-Micro-ECD
LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl) hydrazones
PAH by HPLC Hydrocarbon Index According to ISO 9377-4 (DIN H53)
Determination of N-Nitrosodimethylamine at Part-Per-Quadrillion Levels
Improved Data Quality in the Automated HPLC Analysis of PNAs (PAHs)

Water: Pesticides and Residues

Contract Laboratory Program (CLP) Pesticide Analysis with 0.18 mm ID High-Efficiency GC Columns Utilizing Helium Carrier Gas
A Direct Column-Performance Comparison for Rapid Contract Laboratory Program (CLP) Pesticide Analysis
Analysis of Atrazine in Drinking Water at the ppb Level Using New Agilent Reversed Phase LC Columns
Determination of Estrone-3-Sulfate in Water at Sub-ppt Level by LC-(ESI)- MS/MS
Analysis of Carbaryl and Carbofuran in Drinking Water with Post-Column Derivatization Using Agilent's New LC Column and SampliQ ...
Organophosphorus Pesticides Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column
A Rapid Method for Trace Analysis of Organophosphorus Pesticides in Drinking Water
Analysis of Organochlorine Pesticides in Drinking Water by Agilent 7820 Gas Chromatograph/Micro-Electron Capture Detector
Achieving the Desired Prescribed Sensitivities of Selected Herbicides by direct On-Column Aqueous Injection of Potable and ...
Use of Mass, Isotopy Ratios and MS/MS for PPCPs
Analysis of Herbicides by RRLC with Online Trace Enrichment
Determination of Pesticides by SPE and LC/MS/MS
Determination of Pharmaceuticals by SPE and LC/MS/MS in Pos and Neg Ion Modes
Screening for 926 Pesticides and Endocrine Disruptors by GC/MS
Identifying Pesticides with Full Scan, SIM, μ ECD, and FPD from a Single Injection
Pesticide Screening by GC/MSD Using DRS

Index

Determination of Phenyl Urea and Triazine Herbicides by LC/MS
Identification of Steroids by Ion Trap/LC/MS/MS
Analysis of Paraquat and Diquat by LC/MSD
Analyzing Phenyl Urea and Carbamate Pesticides Using ESI-, APPI-, and APCI-LC/MSD
Analysis of the Active Compound in Fungicide Formulation by LC
High-Resolution Separation of Sulfonylurea Pesticides
Analysis of Pesticides in Drinking Water
Analysis of Components, Contaminants, and Impurities in Fungicide Formulations
Determination of Acidic Herbicides by LC/MSD
Analysis of Glyphosate and Aminomethyl Phosphonic Acid by LC/MS
Identification and Quantitation of Pesticides in Parts-per-Trillion Range Using RTL and GC/MS
Analysis of Simazine, Thiobencarb, and Thiuram by LC/MS
The Analysis of Organophosphate Pesticides by LC/MS
Online Solid-Phase Extraction Ion Trap MS in Environmental Matrices
The Analysis of Dioxin Using a Benchtop MS
Fast Screening of PCB Congeners Using the 6890/5973N GC/MSD System
Fast Screening of Pesticides & Endocrine Disrupters Using the 6890/5973N GC/MSD System, II
Fast Dual-Column GC/ECD Analysis of Chlorinated Pesticides
Validation Analysis of EPA CLP Target Organochlorine Pesticides
Trace Level Pesticide Analysis by GC/MS Using LVI
The Analysis of Chlorinated Pesticides and PCBs
Analysis of Organochlorine Pesticides and PCB Congeners with the 6890 Micro-ECD
Analysis of S and P Compounds with an FPD on the 6890 GC
Screening for 567 Pesticides and Suspected Endocrine Disrupters
Analysis of EDB and DBCP with the 6890 Series GC-Micro-ECD
Fast Screening of Pesticides & Endocrine Disrupters Using the 6890/5973N GC/MSD System, I
Analysis of Bendiocarb and Metabolite by HPLC
Analysis of Paraquat and Diquat by HPLC
Gradient LC Analysis of Herbicides and Polyaromatic Hydrocarbons
A Comparison of Pre- and Post-Column Sample Treatment for the Analysis of Glyphosate

Water: Inorganics

Quantitative Analysis of Perchlorate by Ion Chromatography MS/MS
High-Speed Environmental Analysis Using the Agilent 7500cx with Integrated Sample Introduction System – Discrete Sampling (ISIS–DS)
Analysis of High-Matrix Environmental Samples Using the 7500cx ICP-MS
Determination of Se Species Using HPLC-ICP-MS
Determination of Butyltin Compounds by Isotope Dilution GC-MS
Performance Characteristics of the 7500cx – Evaluating Helium Collision Mode
Semiquantitative Analysis Using the 7500cx ICP-MS
Achieving Optimum Throughput in ICP-MS Analysis of Samples with the 7500ce ICP-MS
Ultra-Trace Analysis of Be in Samples by ICP-MS
Spectral Interference Removal in ICP-MS Using the ORS with Helium Collision Mode
Determination of Methyl Mercury by HPLC-ICP-MS
Ion Chromatography ICP-MS for Cr Speciation in Natural Samples

Index

Comparison of Traditional Metals Analysis vs ICP-MS
Determination of Arsenobetaine (AsB) in Fish Tissues Using HPLC-ICP-MS
Speciation of Organotin Compounds, Using an Experimental GC-ICP-MS Interface
Meeting Regulatory Requirements for Analysis of Trace Metals in Drinking Water Using 7500c ICP-MS
Comparison of GC-ICP-MS and HPLC-ICP-MS for the Analysis of Organotin Compounds
Measuring Elemental Ratios in Corals by LA-ICP-MS
Determination of Br in Drinking Water Using LC-ICP-MS and EPA Method 321.8
Determination of Hg by ICP-MS Using EPA Method 200.8
Determination of As in Samples Containing High Concentrations of Chloride by ICP-MS
Determination of Se by ICP-MS, Using the ShieldTorch
Determination of Trace Elements in Soils and Sediments by ICP-MS
Determination of Bromate and Iodate in Ozonized Water by Ion Chromatography
Meeting UK Drinking Water Requirements for Trace Metals Analysis Using the 4500 ICP-MS
ASTM Approved Method for Water Analysis by Capillary Electrophoresis
Analysis of As, Se and Sb in Seawater
Determination of Fluoride Traces by Ion Chromatography and ICP-MS Detection

Water: Other

Time-of-Flight LC/MS Identification and Confirmation of a Kairomone in *Daphnia magna* Cultured Medium
Analysis of Ionic Tenside Surfactants in Wastewater by HPLC

Soil & Sediment Applications

Soil & Sediment: Volatiles

Fast Analysis of Landfill Gas by Agilent Micro 3000 GC with Performance-Enhanced System
Ultra-Fast Total Petroleum Hydrocarbons (TPH) Analysis with Agilent Low Thermal Mass (LTM) GC and Simultaneous Dual-Tower Injection
Improving GC-MS Method Robustness and Cycle Times Using Capillary Flow Technology and Backflushing
Evaluation of Petroleum Hydrocarbon in Soil Using LC and GC/MS
Analysis of VOCs in Water Using Purge-and-Trap/GC/MS
Analysis of Gasoline (BTEX) Using GC/FID with Purge and Trap

Soil & Sediment: Semi-volatiles

GC Analysis of Polybrominated Flame Retardants
Determination of Polybrominated Diphenylethers (PBDE) in Sediment and Sewage Sludge
Fast USEPA 8270 Semivolatiles Analysis Using the 6890/5973 inert GC/MSD with Performance Electronics
Addressing the Challenges of Analyzing Trace Perfluorooctanoic Acid (PFOA) and Perfluorooctane Sulfonate (PFOS) Using LC/QQQ
Femtogram GC/MSD Detection Limits for Environmental Semivolatiles Using a Triple-Axis Detector
Semivolatile Analysis Using an Inertness Performance Tested Agilent J&W Ultra Inert DB-5ms Column
Polybrominated Diphenyl Ether (PBDE) Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column
EPA Method 1694: Agilent's 6410A LC/MS/MS Solution for Pharmaceuticals and Personal Care Products in Water, Soil, Sediment...
Improving GC-MS Method Robustness and Cycle Times Using Capillary Flow Technology and Backflushing
Semivolatile Organics Analysis Using an Agilent J&W HP-5ms Ultra Inert Capillary GC Column

Index

Fast Analysis of Polynuclear Aromatic Hydrocarbons Using Agilent Low Thermal Mass (LTM) GC/MS and Capillary Flow Technology...

Analysis of Semivolatiles Using High-Efficiency Capillary GC Columns

Separation of Explosives in EPA 8330

Synchronous SIM/Scan Low-Level PAH Analysis Using the 6890/5975 inert GC/MSD

Applying the 5975 inert MSD to the Higher Molecular Weight PBDEs

Determination of PBDE in Polymeric Materials Using the 6890 GC/5973N-inert MSD

Full-Scan Low-Level PAH Analysis

Fast Analysis Using the 6890/5973 inert GC/MSD

Separation of Carbezol and Various Metabolites

Retention Time Locked GC-MS Analysis of Phenols

Solid-Phase Extraction and GC/MS Analysis of Selected Phenols

Improvements in the 6890/5973 GC/MSD

Analysis of Dioxin Using a Benchtop MS

Analysis of Phthalate Esters by GC/MS

Analysis of Nitroaromatics and Nitro-PAH by Capillary GC with the 6890 Micro-ECD

Determination of N-Nitrosodimethylamine at Part-Per-Quadrillion Levels

Soil & Sediment: Pesticides and Residues

Contract Laboratory Program (CLP) Pesticide Analysis with 0.18 mm ID High-Efficiency GC Columns Utilizing Helium Carrier Gas

A Direct Column-Performance Comparison for Rapid Contract Laboratory Program (CLP) Pesticide Analysis

Organophosphorus Pesticides Analysis Using an Agilent J&W DB-5ms Ultra Inert Capillary GC Column

Column-Performance Comparison for Rapid CLP Pesticide Analysis

CLP Pesticide Analysis with 0.18 mm ID High-Efficiency GC Columns

Determination of Chlorinated Acid Herbicides in Soil by LC/MS/MS

Screening for 926 Pesticides and Endocrine Disruptors by GC/MS with DRS

Identifying Pesticides with Full Scan, SIM, μ ECD, and FPD from a Single Injection

Pesticide Screening by GC/MSD Using DRS

Effect of Column Temperature on Separation of Herbicides

Analysis of CLP Pesticides Using High-Temp DB-35ms and DB-XLB Columns

Solution for Chlorinated Pesticides and Herbicides Using DB-35ms and DB-XLB Columns

Identification and Quantitation of Pesticides in Parts-per-Trillion Using RTL and GC/MS

Analysis of Simazine, Thiobencarb, and Thiuram by LC/MS

Analysis of Organophosphate Pesticides by LC/MS

Fast Screening of Pesticide & Endocrine Disruptors Using the 6890/5973N GC/MSD System, II

Fast Screening of PCB Congeners Using the 6890/5973N GC/MSD System

Analysis of EPA CLP Target Organochlorine Pesticides with the 6890 Series GC and Micro-ECD

Dual-Column GC/ECD Analysis of Chlorinated Pesticides – EPA Methods 606/8080

Trace Level Pesticide Analysis by GC/MS Using Large-Volume Injection

Index

Screening for 567 Pesticides and Suspected Endocrine Disruptors
Analysis of S and P Compounds with an FPD on the 6890 Series GC
Analysis of Organochlorine Pesticides and PCB Congeners with the 6890 Micro-ECD
Fast Screening of Pesticides & Endocrine Disrupters Using the 6890/5973N GC/MSD System, 1
LC/DAD/MS Analysis of Carbonyl (2,4-Dinitrophenyl) hydrazones
Analysis of Bendiocarb and Metabolite by HPLC
Analysis of Paraquat and Diquat by HPLC

Soil & Sediment: Inorganics

Direct Analysis of Undiluted Soil Digests Using the Agilent High Matrix Introduction Accessory with the 7500cx ICP-MS
High-Speed Environmental Analysis Using the Agilent 7500cx with Integrated Sample Introduction System – Discrete Sampling (ISIS–DS)
Analysis of Undiluted Soil Digests Using the HMI with the 7500cx ICP-MS
Analysis of High-Matrix Environmental Samples Using the 7500cx ICP-MS
Semiquantitative Analysis Using the 7500cx ICP-MS
Spectral Interference Removal in ICP-MS Using the ORS with Helium Collision Mode
Comparison of Traditional Metals Analysis vs ICP-MS in High Throughput Commercial Labs
Speciation of Organotin Compounds, Using an Experimental GC-ICP-MS Interface
Separation and Analysis of Toxic As Species Using LC-ICP-MS
Improving the Analysis of Organotin Compounds Using RTL Methods and Databases
Meeting Regulatory Requirements for Analysis of Trace Metals in Drinking Water Using 7500c ICP-MS
Comparison of GC-ICP-MS and HPLC-ICP-MS for the Analysis of Organotin Compounds
Analysis of Rare Earth Elements by LA-ICP-MS
Determination of Bromate in Drinking Water Using LC-ICP-MS and EPA Method 321.8
Determination of As in Samples Containing High Concentrations of Chloride by ICP-MS
Determination of Hg in Drinking Water by ICP-MS Using EPA Method 200.8
Meeting UK Drinking Water Requirements for Trace Metals Analysis Using the 4500 ICP-MS
Determination of Se by ICP-MS, Using the ShieldTorch
Determination of Bromate and Iodate in Ozonized Water by Ion Chromatography
Determination of Trace Elements in Soils and Sediments by ICP-MS
Analysis of As, Se and Sb in Seawater
ASTM Approved Method for Water Analysis by Capillary Electrophoresis
Determination of Fluoride in Natural Waters by Ion Chromatography and ICP-MS Detection

Soil & Sediment: Other

Reversed-Phase Separation – 15 Explosives from Soil Extract
Analysis of Explosives and Related Compounds Using Polar and Non-Polar HPLC Columns
Analysis of Ionic Tenside Surfactants in Wastewater by HPLC
HPLC Analysis of Explosive Constituents in Soil Samples

Air Applications

Rapid Separation and Identification of Carbonyl Compounds by HPLC
High-Throughput Screening of Ambient Air Samples by ORS-ICP-MS and ISIS
Screening for 171 Air Pollutants Using GC/MS with DRS and a New Indoor Air Toxics Library
Monitoring of Hydrocarbons in Ambient Air Using Thermal Desorption-GC
SecureTD™ for Re-collection and Repeat Analysis of Desorbed Samples
Optimizing Performance and Extending the Application Range of Thermal Desorption
Benefits of Setting Up a UNITYe-Based Thermal Desorber Using an 6890 GC's EPC
HPLC Analysis of Formaldehyde in Indoor Air
Analysis of Formaldehyde and Acetaldehyde

Material Analysis Applications

Use of the Agilent 7020 ZetaProbe to control suspension stability
Basics of Zeta Potential
Control of Titania Coatings with the 7020 ZetaProbe
Using the 7500cx ICP-MS with High Matrix for Analysis of Metals in High Tech Manufacturing
RoHS/ELV Directives – Measurement of Heavy Metals Using ICP-MS
Analysis of Electroceramics Using Laser Ablation ICP-MS

Productivity Tools Applications

Integrated Second Peristaltic Pump for Improved Sample Throughput and Reduced Matrix Effects
Eliminate the Dilution Step from ICP-MS Sample Prep with the Agilent High Matrix Introduction System
Retention Time Locking with the MSD Productivity ChemStation
Case Study for Agilent Lab Monitor and Diagnostic Software
Capillary Flow Technology for GC/MS: a simple Tee configuration for analysis at trace concentrations with rapid backflushing for ...
Transfer of Existing 6890/5973 GC/MSD Methods to the New 7890/5975 GC/MSD
Injection of Fish Oil for the GC-ECD Analysis of PCBs: Using a Deans Switch With Backflush
Improving Productivity and Extending Column Life with Backflush
Using RTL and 3-Way Splitter to Identify Unknown in Strawberry Extract
Using the 1200 Series RRLC System Compared to a Conventional 1100 Series LC System
Improving the Effectiveness of Method Translation for Fast and High Resolution Separations
1200 Series RRLC System and the 6210 TOF MS
Achieving Fastest Analyses with the 1200 Series RRLC System and 2.1-mm Id Columns
Screening for Hazardous Chemicals Using a GC/MS/ECD/FPD with a 731 Compound DRS Database
RoHS/ELV Directives – Measurement of Heavy Metals Using ICP-MS
Precise Time-Scaling of GC Methods Using Method Translation and RTL
Performance Characteristics of the 7500ce – The ORS Advantage for High Matrix Analysis
Interference-Free Analysis Using the 7500ce ICP-MS
Extending the Dynamic Range of Environmental ICP-MS Using the ISIS and ORS